## ATTACHMENT 5.5-A: CULTURAL RESOURCES TECHNICAL REPORT



# Cultural Resource Assessment Report for the Collinsville 500/230kV Substation Project Contra Costa, Solano, and Sacramento Counties, California

Max van Rensselaer, MPS, RPA Allen Estes, Ph.D., RPA Rachael Irwin, B.A. Ashley Garrett, B.A. Joshua Noyer, B.A. Tara Kloess, B.A.

July 26, 2024

Chronicle Heritage Report Number: 23-567

# Cultural Resource Assessment Report for the Collinsville 500/230KV Substation Project Contra Costa, Solano, and Sacramento Counties, California

This report has been revised for public use by removal of site location information.

#### Prepared by:

Max van Rensselaer, MPS, RPA Allen Estes, Ph.D., RPA Rachael Irwin, B.A. Ashley Garrett, B.A. Joshua Noyer, B.A. Tara Kloess, B.A.

### **Prepared for:**

Insignia Environmental 545 Middlefield Road, Suite 210 Menlo Park, California 94025

**Technical Report No.: 23-567** 

Chronicle Heritage, LLC

1870 Olympic Blvd Walnut Creek, California 94596

July 26, 2024

# **Abstract**

PaleoWest LLC, dba Chronicle Heritage (Chronicle Heritage), completed a Cultural Resource Assessment supporting the proposed Collinsville 500/230kV Substation Project (Proposed Project) in the Sacramento River Delta region of Contra Costa, Solano, and Sacramento Counties in California. LS Power Grid California, LLC (LSPGC) proposes constructing a new electrical substation, 500 kilovolt (kV) transmission line, and 230 kV transmission line to increase reliability and renewable generation. The proposed transmission lines extend from Collinsville, California, to Pittsburg, California, and include aboveground and underwater components.

The Proposed Project is subject to Section 106 of the National Historic Preservation Act (NHPA) of 1966, as amended, the Abandoned Shipwreck Act of 1987 (National Park Service [NPS] 1990), and the California Environmental Quality Act (CEQA). The U.S. Army Corps of Engineers (USACE) is the lead federal agency, and the California Public Utilities Commission (CPUC) is the lead CEQA agency. Chronicle Heritage completed this work under contract to Insignia Environmental.

The proposed Area of Potential Impacts/Effects (API/APE) includes an approximately 4-mile (mi)-long stretch of submerged transmission cable under the Sacramento River, in addition to approximately 1 mi of overhead 230 kV transmission line, and two approximately 1.5-mi-long, single-circuit, 500 kV transmission line segments. The aboveground portion of the Proposed API/APE includes a 150-foot right-of-way corridor and approximately 20 acres for the proposed Collinsville Substation on Stratton Lane in Suisun City, about 1 mi north of the Sacramento River Delta.

For the aboveground portion of the Proposed Project, Chronicle Heritage completed a records search and archival research, informal Native American outreach, and an intensive pedestrian survey.

The pedestrian survey resulted in the identification of six new resources within the Proposed API/APE. Ten previously recorded cultural resources were revisited during the pedestrian survey, including eight resources within the Proposed API/APE and one National Register of Historic Places (NRHP)-nominated historic property adjacent to the Proposed API/APE and one other historic road that runs adjacent to the Proposed API/APE. One of the previously recorded resources, a historic transmission line that is within the Proposed API/APE is recommended eligible for listing in the NRHP or California Register of Historical Resources (CRHR). The six new resources that were recorded are not being recommended as eligible for listing in the NRHP or CRHR. The Proposed Project will not result in direct or indirect effects to the NRHP-nominated resource or to the transmission line that is recommended as eligible for NRHP/CRHR.

For the submerged portion of the Proposed Project, Chronicle Heritage's Maritime Division analyzed data from an intensive submerged cultural resources remote sensing survey; coordinated with the State of California's Underwater Archaeologist; performed a literature review and archival research; and performed an analysis of magnetometer, side-scan sonar, and subbottom profiler data collected during the survey. Results of the submerged cultural resources records search, archival research, survey, and analysis will be presented in Attachment A.

Cultural Resource Assessment Report for The Collinsville 500/230KV Substation Project
This page intentionally left blank.

# **Contents**

1	INTRODUC			
	1.1		ESCRIPTION	
	1.2	AREA OF PO	TENTIAL IMPACTS/AREA OF POTENTIAL EFFECTS	4
2	REGULATO	RY CONTEXT		33
	2.1			
			onal Historic Preservation Act	
			ndoned Shipwreck Act of 1987	
			ve American Graves Protection and Repatriation Act (NAGPRA)	
			ornia Public Resources Code 5097.9	
			ornia Environmental Quality Act	
			ornia Register of Historical Resources	
			embly Bill 52 (AB 52)	
	2.2			
			no County	
			tra Costa County	
_			amento County	
3			-NITAL OFTTINO	
	3.1		ENTAL SETTING	
			ate	
			ogy	
			setation and Associated Wildlife	
	3.2	-	etation and Associated Wildlife CT SETTING	
	5.2		er Archaic Period	
			lle Archaic Period	
			er Archaic Period	
			er Archaic/ Erioder Archaic/Emergent Period Transition	
			rgent Period	
	3.3		PHIC SETTING	
	0.0		Patwin People	
			Miwok People	
	3.4		VERVIEW	
			nish Era (1769–1821)	
		•	can Era (1822-1848)	
			orical Era (1848-present)	
4	RESEARCH	DESIGN	······································	67
	4.1		OT RESEARCH THEMES	67
	4.2	HISTORIC PI	ERIOD RESEARCH THEMES	68
5	TERRESTR	AL CULTURA	AL RESOURCE INVENTORY	69
-	5.1		AL RECORDS SEARCH RESULTS	
			ural Resources	
	5.2		RESEARCH RESULTS	
	5.3	NATIVE AME	ERICAN HERITAGE COMMISSION OUTREACH	91
	5.4	ARCHAEOLO	DGICAL SENSITIVITY	91
6	TERRESTR	AL SURVEY .		92

	6.1	PEDESTRIAN ARCHAEOLOGICAL SURVEY METHODS	
	6.2	PEDESTRIAN SURVEY OF NORTHERN PORTION OF TERRESTRIAL API/APE	93
	6.3	PEDESTRIAN SURVEY OF SOUTHERN PORTION OF TERRESTRIAL API/APE	95
7	CULTURAL	RESOURCE EVALUATIONS	96
	7.1	P-48-000041	
		7.1.1 Effects Analysis	
		7.1.2 Conclusion	
	7.2	P-48-000124	
		7.2.1 Significance Evaluation	100
		7.2.2 Conclusion	101
	7.3	P-48-000125	101
		7.3.1 Significance Evaluation	103
		7.3.2 Conclusion	104
	7.4	P-48-000128	104
		7.4.1 Significance Evaluation	105
		7.4.2 Conclusion	106
	7.5	P-48-000139	
		7.5.1 Significance Evaluation	
		7.5.2 Conclusion	
	7.6	P-48-000140	
		7.6.1 Significance Evaluation	
		7.6.2 Conclusion	
	7.7	P-48-000416	
		7.7.1 Significance Evaluation	
	7.0	7.7.2 Conclusion	
	7.8	P-48-000521	
		7.8.1 Significance Evaluation	
	7.9	P-48-000981	
	7.5	7.9.1 Significance Evaluation	
		7.9.2 Conclusion	
	7.10	P-07-002956	
	7.10	7.10.1 Significance Evaluation	
		7.10.2 Conclusion	
	7.11	AG-001	
		7.11.1 Significance Evaluation	
		7.11.2 Conclusion	
	7.12	AG-02	123
		7.12.1 Significance Evaluation	125
		7.12.2 Conclusion	126
	7.13	JN-01	
		7.13.1 Significance Evaluation	127
		7.13.2 Conclusion	
	7.14		
		7.14.1 Significance Evaluation	
		7.14.2 Conclusion	
	7.15	JN-04	
		7.15.1 Significance Evaluation	134

	7.15.2 Conclusion	135
8	SCUSSION AND INTERPRETATION	135
	8.1 PRECONTACT ARCHAEOLOGY IN THE API/APE	
	8.2 HISTORIC-ERA ARCHAEOLOGY IN THE API/APE	
9	JMMARY AND RECOMMENDATIONS	
5	9.1 INADVERTENT DISCOVERIES	
	9.2 INADVERTENT DISCOVERY OF HUMAN REMAINS	
10	REPARER QUALIFICATIONS	
	-	
11	EFERENCES	140
Fig	es	
_		_
	e 1-1. Project vicinity map.	
	e 1-2. Project location map.	
	e 1-3. Horizontal Proposed API/APE detail map (1 of 12).	
Fig	e 4-1. 1876 map showing land ownership (E. T. Upham, C. H. Rice, and Charles Dadami) withe Proposed API/APE (Thompson and West 1876).	
Fia	e 4-2. 1890 map showing land ownership (M. Dawson and J.W. Briggs) within the Propos	
,	API/APE (E. N. Eager 1890).	
Fig	e 4-3. Historic Topo map of the Proposed API/APE (Honker Bay, CA 1918; Collinsville, CA	4 1918).
Fig	e 4-4. Historic Topo map of the Proposed API/APE (Honker Bay, CA 1918; Collinsville, CA	4 1918).
Fig	e 4-5. Topographic map from 1978 depicting the northern portion of the Proposed API/ (USGS 1978)	APE
Fia	e 4-6. Historic aerial imagery of the northern extent of the Proposed API/APE (UCSB 19	
	e 4-7. Historic aerial imagery of the northern extent of the Proposed API/APE (UCSB 19	
	e 4-8. Aerial image showing limited development within the Proposed API/APE (in blue	
1 19	the vicinity (UCSB 1970)	
Fia	e 6-1 . Project overview, facing southwest.	
	e 6-2. Project overview, facing southwest:	
_	e 6-3. Project overview, facing northe 6-3. Project overview, facing southeast	
-	e 7-1. Site overview, facing south	
_	e 7-1. Site overview, facing southe 7-2. Site overview, facing north	
-		
	e 7-3. Site overview, facing north	
_	e 7-4. Site overview, facing south.	
-	27-5. Site overview, facing south.	
-	e 7-6. Site overview, facing north	
-	e 7-7. Site overview, facing north	
_	e 7-8. Site overview, facing east.	
	e 7-10. Site overview, facing north.	
-	e 7-11. Site overview, facing south	
	e 7-12. Site overview, facing southwest.	
	e 7-13. Site overview, facing north.	
	e 7-14. Site overview, facing east (Google Maps 2023)	
-	e 7-17. Site overview, facing northeast	
-	e 7-18. Site overview, facing northwest	
Fig	e 7-22. Site overview, facing east (Google Maps 2023)	129

# Cultural Resource Assessment Report for The Collinsville 500/230KV Substation Project

Figure 7-23. Overview of Stratton Lane, segment 1, view east	
Tables	
Table 4-1. Previously Recorded Cultural Resources within the API/APE	72
Table 4-2. Previously Recorded Cultural Resources in the 0.5-mi Buffer	73
Table 4-3. Previous Cultural Resource Investigations within the API/APE	75
Table 4-4. Previous Cultural Resource Investigations in 0.5-mi Buffer Around API/APE	78

# **Appendices**

Attachment A. Maritime Cultural Resources Assessment Report Attachment C. NAHC Correspondence

# Introduction

The LS Power Grid California, LLC (LSPGC) Collinsville 500/230 Kilovolt (kV) Substation Project (Project) is being constructed due to increasing demands on the California electric grid. The Project is subject to compliance with California Environmental Quality Act (CEQA) statutes and guidelines, and it requires approval from California Public Utilities Commission (CPUC), the lead agency under CEQA, of the assessment of the undertaking's impact on cultural resources. Since the Project construction crosses a waterway it must comply with authorization from the Secretary of the Army, acting through the Corps of Engineers (COE), for the discharge of dredged or fill material into all waters of the United States as stipulated in Section 404 of the Clean Water Act. The environmental review of the Project, therefore, also falls under the jurisdiction of the National Environmental Policy Act (NEPA) and the Section 106 review as set out by National Historic Preservation Act (NHPA). The COE is the approval agency for the Section 106 review for this Project.

Chronicle Heritage completed a records search, literature review, Native American outreach, terrestrial archaeological survey, resource evaluations, and maritime submerged survey in support of the Collinsville 500/230 kilovolt (kV) Substation Project (Project) in Contra Costa, Solano, and Sacramento Counties, California (Figure 1-1). This report presents the results of the records search, a review of historical maps and aerial photographs, terrestrial cultural resources survey results, and evaluations of sixteen properties identified within or immediately adjacent to the proposed Area of Potential Impacts (API)/Area of Potential Effects (APE). The cultural resources assessment for the underwater portion of the Proposed Project is presented in Attachment A. The purpose of this investigation is to determine the potential for the Project to adversely affect historic properties as defined by NHPA or historical resources as defined by CEQA.

# **Project Description**

The Project is in in the Sacramento River Delta region of Contra Costa, Solano, and Sacramento Counties in California (Figures 1-1 and 1-2). It is found in sections 22-24 and 26-27 of Township 3 North, Range 1 East in the Antioch North, California (USGS 1979) and Honker Bay, California (USGS 1981) U.S. Geological System (USGS) 7.5-minute quadrangles (Figure 1-3 through Figure 1-26). 1 The LSPGC Collinsville 500/230 Kilovolt (kV) Substation Project (Project) is designed to address multiple overloads on the 230 kV corridor between PG&E's existing Contra Costa and Newark substations. The Project would also provide additional supply from the 500 kV Vaca-Dixon Transmission System. into the northern Greater Bay Area to increase the reliability of the electric grid in the area, as well as advance additional renewable energy generation in the northern Greater Bay Area. This needed upgrade to the California electric grid was identified in the California Independent System Operators (CAISO) 2021-2022 Transmission Plan. The objective of the Transmission Plan was to fulfill the requirement to add approximately 1,000 megawatts of new resources per year in the state over the 10-year planning period. CAISO's Policy-Driven Need Assessment identified the Project as necessary to ensure deliverability of resources to meet policy goals and the resource adequacy needs of the state. The Policy-Driven Need Assessment is an iterative process, encompassing three studies: a reliability assessment, an on-peak deliverability assessment, and an off-peak deliverability assessment. The key objectives of the Policy-Driven Need Assessment are to assess

-

<sup>&</sup>lt;sup>1</sup> The latest Antioch North USGS 7,5-minute quadrangle that is available is dated 1995 and the latest Honker Bay USGS 7.5 minute quadrangle is dated 1985.

the transmission impacts of portfolio resources, identify necessary upgrades to ensure reliability and minimize excessive curtailment, and inform future portfolio development. The Project would address transmission constraints in the base portfolio (i.e., Cayetano-North Dublin 230 kV Transmission Line, Lone Tree-USWP-JRW-Cayetano 230 kV Transmission Line, and Las Positas-Newark 230 kV Transmission Line) identified by the assessment.

The main component of the Project, the LSPGC Collinsville Substation, is located near the unincorporated community of Collinsville, which is in southeastern Solano County. Other components of the Project would cross Solano, Sacramento, and Contra Costa counties in California: two single-circuit 500 kV transmission lines would be extended to interconnect PG&E's existing Vaca Dixon-Tesla 500 kV Transmission Line to the LSPGC Collinsville Substation, a new double-circuit 230 kV transmission line (the LSPGC 230 kV Transmission Line) would travel from the LSPGC Collinsville Substation, travel under the Delta waterways, and continue in an underground configuration before connecting to PG&E's existing Pittsburg Substation in the City of Pittsburg in northern Contra Costa County. The Project is in Sections 22–24 and 26–27 of Township 3 North, Range 1 East in the Antioch North, California (USGS 1978) and Honker Bay, California (USGS 1981) U.S. Geological System (USGS) 7.5-minute quadrangles (Figure 1-2, Figure 1-3, Figure 1-4).

The main components of the Proposed Project include the following:

- Constructing a new 500/230 kV substation, the LSPGC Collinsville Substation. The approximate size of the substation is 11 acres.
- Constructing two new approximately 1.5-mile-long, single-circuit 500 kV transmission line segments extending to interconnect (or "loop") PG&E's existing Vaca Dixon-Tesla 500 kV Transmission Line into the LSPGC Collinsville Substation. Each lattice steel tower (LST) would be installed on up to four pier foundations. Each pier foundation would be constructed 3-6 feet in diameter and 30 feet in depth.
- Constructing a new approximately 5.6-mile-long, double-circuit 230 kV transmission line to connect the LSPGC Collinsville Substation to PG&E's existing Pittsburg Substation. Six new tubular steel poles (TSP) with be installed, four direct bury with 6-foot diameter and a depth of 15-25 feet and two pier foundation with 12-foot diameter and depth of 20-50 feet. A six-poled guy structure will be built 12 feet in diameter and 15-25 feet in depth. An in-river structure will be constructed by driven piles and pile cap, with each pile 2.5 feet in diameter and 30-80 feet in depth.
  - Overhead segment: 1-mile-long double-circuit line connecting the LSPGC Collinsville Substation to the submarine segment.
  - Submarine segment: beginning at the in-river transition structure, up to six approximately 4.5-mile-long submarine cables would be installed between 6 and 15 feet below the river's sediment surface. The submarine cables would terminate at an onshore underground utility vault in the City of Pittsburg.
  - Underground segment: beginning at the onshore underground utility vault the submarine cables would transition to underground transmission cables, which would travel through two duct banks, one approximately 1,070-foot and a

second approximately 2,000-foot in length, that would terminate at two new riser structures prior to entering the existing PG&E's Pittsburg Substation.

- Extending and connecting an existing PG&E 12 kV distribution line to the LSPGC Collinsville Substation. Approximately 3 miles in length. Twenty-one wood poles will be installed to carry the line. Pole installation will cause a disturbance measuring 3 feet in diameter and 8 feet in depth.
- Constructing two new telecommunications paths to the LSPGC Collinsville Substation—a new microwave tower would be constructed at the substation and a new fiber optic line would be installed between existing fiber in the City of Pittsburg and the substation. 2 These two lines will be installed by their owners (e.g., AT&T, Comcast) generally within existing streets using the horizontal directional drilling (HDD) method of construction from a residential neighborhood located east of PG&E's existing Pittsburg Substation to a new fiber hub installed adjacent to PG&E's existing Pittsburg Substation and the new onshore underground utility vault associated with the LSPGC 230 kV Underground Segment. Trenching would be used to install the duct banks. The trenches would be 3 to 6 feet deep and 7 to 10 feet wide depending on the duct bank configurations.

In addition to the ground disturbances resulting from the construction of the Project components, other disturbances will be from the following construction related features:

- Construction of temporary and permanent access roads: approximately 24-foot-wide temporary access roads would be established during construction to access construction areas. Prior to use, vegetation would be removed, and the area would be bladed to establish a safe path for construction equipment and vehicles. Extensive grading and/or road base placement would not be anticipated along temporary access roads. Two new permanent access routes would be constructed to connect the primary entrance of the LSPGC Collinsville Substation to Stratton Lane and connect to PG&E's equipment within the substation perimeter.
- Staging areas: It is anticipated that five staging areas would be used to support
  construction. Three staging areas would be in the Collinsville area and used for longer-term
  construction staging needs for work on the LSPGC Collinsville Substation, LSPGC 230 kV
  Overhead Segment, LSPGC 230 kV Submarine Segment, PG&E 500 kV Interconnection, and
  PG&E 12 kV Distribution Line. Two staging areas would be located adjacent to PG&E's
  existing Pittsburg Substation in the City of Pittsburg and would be used for longer term
  construction staging needs for work on the LSPGC 230 kV Submarine Segment, LSPGC 230
  kV Underground Segment, LSPGC Telecommunications Line, and PG&E's modifications to
  its existing Pittsburg Substation. Staging area preparation would typically involve clearing,
  topsoil salvage, grubbing, and limited grading.
- Work areas and pulling sites: various work areas and pull sites will be prepared as needed to complete construction. It is estimated that 13.6 acres of disturbance will result from the creation of 46 work areas, and 13.5 acres of disturbance from 18 pull site preparation. Work area preparation would typically involve clearing, topsoil salvage, grubbing, and grading.

\_

<sup>&</sup>lt;sup>2</sup> The microwave tower would be constructed, operated, and maintained by PG&E.

# Area of Potential Impacts/Area of Potential Effects

A proposed Area of Potential Impacts/Area of Potential Effects (API/APE) was established for the Project. The Proposed API/APE included all of the Project components and the rights-of-way (ROWs) especially work areas, pull areas, and staging areas. The horizontal Proposed API/APE map is presented in Figures 1-3 to 1-14; the vertical Proposed API/APE map is presented in Figures 1-15 to 1-26.

The location for the LSPGC Collinsville Substation is off Stratton Lane just northeast of Collinsville, Solano County, California (Figures 1-8 and 1-20). The site is currently undeveloped and is part of the Shiloh I Wind Power Plant area. The Sacramento River flows east to west, bisecting the northern and southern portions of the Proposed API/APE.

The 500/230 kV overhead transmission lines are proposed to be approximately 1.5 mi long between the LSPGC Collinsville Substation and the existing Pittsburg Substation Figures 1-9 to 1-12; 1-21 to 1-24). Structures are proposed to range in height from approximately 100–120 ft and support - structures will reach depths of up to 30 feet. The overhead transmission line ROW is planned to be approximately 150 ft wide. From the last onshore structures to the single proposed in-river transition structure, the planned ROW width increases to approximately 325 ft.

As mentioned above, the submarine cable route is proposed to be approximately 4.5 mi long, running northeast-to-southwest across the Sacramento River Delta (Figure 1-11 to 1-13; 1-23 to 1-25). The submarine cable is proposed to be installed beneath the bay and riverbed to a depth of approximately 6 and 15 feet using jetting technology. Near the southern edge of the river just outside of the existing Pittsburg Substation, an onshore underground utility vault will receive the submarine cables. From that point, two underground transmission cables, which would travel through two duct banks, one approximately 1,070-foot and a second approximately 2,000-foot in length, that would terminate at two new riser structures prior to entering the existing PG&E's Pittsburg Substation. Trenching for the duct banks will reach a depth of 6 feet.




Figure 1-1. Project vicinity map.

This page intentionally left blank.							




Figure 1-2. Project location map.




Figure 1-3. Horizontal Proposed API/APE detail map (1 of 12).




Figure 1-4. Horizontal Proposed API/APE detail map (2 of 12).



Figure 1-5. Horizontal Proposed API/APE detail map (3 of 12).




Figure 1-6. Horizontal Proposed API/APE detail map (4 of 12).




Figure 1-7. Horizontal Proposed API/APE detail map (5 of 12).




Figure 1-8. Horizontal Proposed API/APE detail map (6 of 12).




Figure 1-9. Horizontal Proposed API/APE detail map (7 of 12).




Figure 1-10. Horizontal Proposed API/APE detail map (8 of 12).




Figure 1-11. Horizontal Proposed API/APE detail map (9 of 12).




Figure 1-12. Horizontal Proposed API/APE detail map (10 of 12).




Figure 1-13. Horizontal Proposed API/APE detail map (11 of 12).




Figure 1-14. Horizontal Proposed API/APE detail map (12 of 12).



Figure 1-15. Vertical Proposed API/APE detail map (1 of 12).




Figure 1-16. Vertical Proposed API/APE detail map (2 of 12).




Figure 1-17. Vertical Proposed API/APE detail map (3 of 12).




Figure 1-18. Vertical Proposed API/APE detail map (4 of 12).




Figure 1-19. Vertical Proposed API/APE detail map (5 of 12).




Figure 1-20. Vertical Proposed API/APE detail map (6 of 12).




Figure 1-21. Vertical Proposed API/APE detail map (7 of 12).




Figure 1-22. Vertical Proposed API/APE detail map (8 of 12).




Figure 1-23. Vertical Proposed API/APE detail map (9 of 12).



Figure 1-24. Vertical Proposed API/APE detail map (10 of 12).




Figure 1-25. Vertical Proposed API/APE detail map (11 of 12).




Figure 1-26. Vertical Proposed API/APE detail map (12 of 12).

This page intentionally left blank.

# **Regulatory Context**

The Project is subject to compliance with CEQA statutes and guidelines, and it requires approval from CPUC, as the responsible agent for making and enforcing regulation of the state's public utilities and the lead agency for this Project under CEQA, of the assessment of the undertaking's impact on cultural resources. Since the Project construction crosses a waterway it must comply with authorization from the Secretary of the Army, acting through the COE, for the discharge of dredged or fill material into all waters of the United States as stipulated in Section 404 of the Clean Water Act. The environmental review of the Project, therefore, also falls under the jurisdiction of the NEPA and the Section 106 review as set out by NHPA. The COE is the approval agency for the Section 106 review for this Project.

### **Federal**

### Section 404 of the Clean Water Act

- (a) The Secretary may issue permits, after notice and opportunity for public hearings for the discharge of dredged or fill material into the navigable waters at specified disposal sites. Not later than the fifteenth day after the date an applicant submits all the information required to complete an application for a permit under this subsection, the Secretary shall publish the notice required by this subsection.
- **(b)** Subject to subsection (c) of this section, each such disposal site shall be specified for each such permit by the Secretary:
- (1) through the application of guidelines developed by the Administrator, in conjunction with the Secretary, which guidelines shall be based upon criteria comparable to the criteria applicable to the territorial seas, the contiguous zone, and the ocean under section 403(c), and
- (2) in any case where such guidelines under clause (1) alone would prohibit the specification of a site, through the application additionally of the economic impact of the site on navigation and anchorage.
- (c) The Administrator is authorized to prohibit the specification (including the withdrawal of specification) of any defined area as a disposal site, and he is authorized to deny or restrict the use of any defined area for specification (including the withdrawal of specification) as a disposal site, whenever he determines, after notice and opportunity for public hearings, that the discharge of such materials into such area will have an unacceptable adverse effect on municipal water supplies, shellfish beds and fishery areas (including spawning and breeding areas), wildlife, or recreational areas. Before making such determination, the Administrator shall consult with the Secretary. The Administrator shall set forth in writing and make public his findings and his reasons for making any determination under this subsection.
- **(d)** The term "Secretary" as used in this section means the Secretary of the Army, acting through the Chief of Engineers.

(e)

- (1) In carrying out his functions relating to the discharge of dredged or fill material under this section, the Secretary may, after notice of opportunity for public hearing, issue general permits on a State, regional, or nationwide basis for any category of activities involving discharges of dredged or fill material if the Secretary determines that the activities in such category are similar in nature, will cause only minimal adverse environmental effects when performed separately, and will have only minimal cumulative adverse effects on the environment. Any general permit issued under this subsection shall
  - (A) be based on the guidelines described in subsection (b)(1) of this section, and
- **(B)** set forth the requirements and standards which shall apply to any activity authorized by such general permit.
- (2) No general permit issued under this subsection shall be for a period of more than five years after the date of its issuance and such general permit may be revoked or modified by the Secretary if, after opportunity for public hearing, the Secretary determines that the activities authorized by such general permit have an adverse impact on the environment or such activities are more appropriately authorized by individual permits.

#### (f)

- (1) Except as provided in paragraph (2) of this subsection, the discharge of dredge or fill material -
- (A) from normal farming, silviculture, and ranching activities such as plowing, seeding, cultivating, minor drainage, harvesting for the production of food, fiber, and forest products, or upland soil and water conservation practices;
- **(B)** for the purpose of maintenance, including emergency reconstruction of recently damaged parts, of currently serviceable structures such as dikes, dams, levees, groins, riprap, breakwaters, causeways, and bridge abutments or approaches, and transportation structures;
- **(C)** for the purpose of construction or maintenance of farm or stock ponds or irrigation ditches, or the maintenance of drainage ditches;
- **(D)** for the purpose of construction of temporary sedimentation basins on a construction site which does not include placement of fill material into the navigable waters;
- **(E)** for the purpose of construction or maintenance or farm roads or forest roads, or temporary roads for moving mining equipment, where such roads are constructed and maintained, in accordance with best management practices, to assure that flow and circulation patterns and chemical and biological characteristics of the navigable waters are not impaired, that the reach of the navigable waters is not reduced, and that any adverse effect on the aquatic environment will be otherwise minimized;
- **(F)** resulting from any activity with respect to which a State has an approved program under section 1288(b)(4) of this title which meets the requirements of subparagraphs (B) and (C) of such section, is not prohibited by or otherwise subject to regulation under this section or section 1311(a) or 1342 of this title (except for effluent standards or prohibitions under section 1317 of this title).

(2) Any discharge of dredged or fill material into the navigable waters incidental to any activity having as its purpose bringing an area of the navigable waters into a use to which it was not previously subject, where the flow or circulation of navigable waters may be impaired or the reach of such waters be reduced, shall be required to have a permit under this section.

#### (g)

- (1) The Governor of any State desiring to administer its own individual and general permit program for the discharge of dredged or fill material into the navigable waters (other than those waters which are presently used, or are susceptible to use in their natural condition or by reasonable improvement as a means to transport interstate or foreign commerce shoreward to their ordinary high water mark, including all waters which are subject to the ebb and flow of the tide shoreward to their mean high water mark, or mean higher high water mark on the west coast, including wetlands adjacent thereto), within its jurisdiction may submit to the Administrator a full and complete description of the program it proposes to establish and administer under State law or under an interstate compact. In addition, such State shall submit a statement from the attorney general (or the attorney for those State agencies which have independent legal counsel), or from the chief legal officer in the case of an interstate agency, that the laws of such State, or the interstate compact, as the case may be, provide adequate authority to carry out the described program.
- (2) Not later than the tenth day after the date of the receipt of the program and statement submitted by any State under paragraph (1) of this subsection, the Administrator shall provide copies of such program and statement to the Secretary and the Secretary of the Interior, acting through the Director of the United States Fish and Wildlife Service.
- (3) No later than the ninetieth day after the date of the receipt by the Administrator of the program and statement submitted by any State, under paragraph (1) of this subsection, the Secretary and the Secretary of the Interior, acting through the Director of the United States Fish and Wildlife Service, shall submit any comments with respect to such program and statement to the Administrator in writing.

#### (h)

- (1) Not later than the one-hundred-twentieth day after the date of the receipt by the Administrator of a program and statement submitted by any State under paragraph (1) of this subsection, the Administrator shall determine, taking into account any comments submitted by the Secretary and the Secretary of the Interior, acting through the Director of the United States Fish and Wildlife Service, pursuant to subsection (g) of this section, whether such State has the following authority with respect to the issuance of permits pursuant to such program:
  - (A) To issue permits which -
- (i) apply, and assure compliance with, any applicable requirements of this section, including, but not limited to, the guidelines established under subsection (b)(1) of this section, and sections 307 and 403 of this Act;
  - (ii) are for fixed terms not exceeding five years; and
  - (iii) can be terminated or modified for cause including, but not limited to, the following:

- (I) violation of any condition of the permit;
- (II) obtaining a permit by misrepresentation, or failure to disclose fully all relevant facts;
- (III) change in any condition that requires either a temporary or permanent reduction or elimination of the permitted discharge.
- **(B)** To issue permits which apply, and assure compliance with, all applicable requirements of section 308 of this Act, or to inspect, monitor, enter, and require reports to at least the same extent as required in section 308 of this Act.
- **(C)** To assure that the public, and any other State the waters of which may be affected, receive notice of each application for a permit and to provide an opportunity for public hearing before a ruling on each such application.
- **(D)** To assure that the Administrator receives notice of each application (including a copy thereof) for a permit.
- **(E)** To assure that any State (other than the permitting State), whose waters may be affected by the issuance of a permit may submit written recommendation to the permitting State (and the Administrator) with respect to any permit application and, if any part of such written recommendations are not accepted by the permitting State, that the permitting State will notify such affected State (and the Administrator) in writing of its failure to so accept such recommendations together with its reasons for so doing.
- **(F)** To assure that no permit will be issued if, in the judgement of the Secretary, after consultation with the Secretary of the department in which the Coast Guard is operating, anchorage and navigation of any of the navigable waters would be substantially impaired thereby.
- **(G)** To abate violations of the permit or the permit program, including civil and criminal penalties and other ways and means of enforcement.
- **(H)** To assure continued coordination with Federal and Federal-State water-related planning and review processes.
- (2) If, with respect to a State program submitted under subsection (g)(I) of this section, the Administrator determines that such State -
- (A) has the authority set forth in paragraph (1) of this subsection, the Administrator shall approve the program and so notify (i) such State, and (ii) the Secretary, who upon subsequent notification from such State that it is administering such program, shall suspend the issuance of permits under subsections (a) and (e) of this section for activities with respect to which a permit may be issued pursuant to such State program; or
- **(B)** does not have the authority set forth in paragraph (1) of this subsection, the Administrator shall so notify such State, which notification shall also describe the revisions or modifications necessary so that such State may resubmit such program for a determination by the Administrator under this subsection.

- (3) If the Administrator fails to make a determination with respect to any program submitted by a State under subsection (g)(I) of this section within one-hundred-twenty days after the date of the receipt of such program, such program shall be deemed approved pursuant to paragraph (2)(A) of this subsection and the Administrator shall so notify such State and the Secretary who, upon subsequent notification from such State that it is administering such program, shall suspend the issuance of permits under subsection (a) and (e) of this section for activities with respect to which a permit may be issued by such State.
- (4) After the Secretary receives notification from the Administrator under paragraph (2) or (3) of this subsection that a State permit program has been approved, the Secretary shall transfer any applications for permits pending before the Secretary for activities with respect to which a permit may be issued pursuant to such State program to such State for appropriate action.
- (5) Upon notification from a State with a permit program approved under this subsection that such State intends to administer and enforce the terms and conditions of a general permit issued by the Secretary under subsection (e) of this section with respect to activities in such State to which such general permit applies, the Secretary shall suspend the administration and enforcement of such general permit with respect to such activities.
- (i) Whenever the Administrator determines after public hearing that a State is not administering a program approved under section (h)(2)(A) of this section, in accordance with this section, including, but not limited to, the guidelines established under subsection (b)(1) of this section, the Administrator shall so notify the State, and, if appropriate corrective action is not taken within a reasonable time, not to exceed ninety days after the date of the receipt of such notification, the Administrator shall:
- (1) withdraw approval of such program until the Administrator determines such corrective action has been taken, and
- (2) notify the Secretary that the Secretary shall resume the programs for the issuance of permits under subsection (a) and (e) of this section for activities with respect to which the State was issuing permits and that such authority of the Secretary shall continue in effect until such time as the Administrator makes the determination described in clause (1) of this subsection and such State again has an approved program.
- (j) Each State which is administering a permit program pursuant to this section shall transmit to the Administrator
- (1) a copy of each permit application received by such State and provide notice to the Administrator of every action related to the consideration of such permit application, including each permit proposed to be issued by such State, and
- (2) a copy of each proposed general permit which such State intends to issue. Not later than the tenth day after the date of the receipt of such permit application or such proposed general permit, the Administrator shall provide copies of such permit application or such proposed general permit to the Secretary and the Secretary of the Interior, acting through the Director of the United States Fish and Wildlife Service. If the Administrator intends to provide written comments to such State with respect to such permit application or such proposed general permit, he shall so notify such

State not later than the thirtieth day after the date of the receipt of such application or such proposed general permit and provide such written comments to such State, after consideration of any comments made in writing with respect to such application or such proposed general permit by the Secretary and the Secretary of the Interior, acting through the Director of the United States Fish and Wildlife Service, not later than the ninetieth day after the date of such receipt. If such State is so notified by the Administrator, it shall not issue the proposed permit until after the receipt of such comments from the Administrator, or after such ninetieth day, whichever first occurs. Such State shall not issue such proposed permit after such ninetieth day if it has received such written comments in which the Administrator objects

- (A) to the issuance of such proposed permit and such proposed permit is one that has been submitted to the Administrator pursuant to subsection (h)(I)(E), or
- (B) to the issuance of such proposed permit as being outside the requirements of this section, including, but not limited to, the guidelines developed under subsection (b)(1) of this section unless it modified such proposed permit in accordance with such comments. Whenever the Administrator objects to the issuance of a permit under the preceding sentence such written objection shall contain a statement of the reasons for such objection and the conditions which such permit would include if it were issued by the Administrator. In any case where the Administrator objects to the issuance of a permit, on request of the State, a public hearing shall be held by the Administrator on such objection. If the State does not resubmit such permit revised to meet such objection within 30 days after completion of the hearing or, if no hearing is requested within 90 days after the date of such objection, the Secretary may issue the permit pursuant to subsection (a) or (e) of this section, as the cause may be, for such source in accordance with the guidelines and requirements of this Act.
- (k) In accordance with guidelines promulgated pursuant to subsection (i)(2) of section 304 of this Act, the Administrator is authorized to waive the requirements of subsection (j) of this section at the time of the approval of a program pursuant to subsection (h)(2)(A) of this section or any category (including any class, type, or size within such category) of discharge within the State submitting such program.
- (I) The Administrator shall promulgate regulations establishing categories of discharges which he determines shall not be subject to the requirements of subsection (j) of this section in any State with a program approved pursuant to subsection (h)(2)(A) of this section. The Administrator may distinguish among classes, types, and sizes within any category of discharges.
- (m) Not later than the ninetieth day after the date on which the Secretary notifies the Secretary of the Interior, acting through the Director of the United States Fish and Wildlife Service that
- (1) an application for a permit under subsection (a) of this section has been received by the Secretary, or
- (2) the Secretary proposes to issue a general permit under subsection (e) of this section, the Secretary of the Interior, acting through the Director of the United States Fish and Wildlife Service, shall submit any comments with respect to such application or such proposed general permit in writing to the Secretary.

- (n) Nothing in this section shall be construed to limit the authority of the Administrator to take action pursuant to section 309 of this Act.
- **(o)** A copy of each permit application and each permit issued under this section shall be available to the public. Such permit application or portion thereof, shall further be available on request for the purpose of reproduction.
- **(p)** Compliance with a permit issued pursuant to this section, including any activity carried out pursuant to a general permit issued under this section, shall be deemed compliance, for purposes of sections 309 and 505, with sections 301, 307, and 403.
- (q) Not later than the one-hundred-eightieth day after the date of enactment of this subsection, the Secretary shall enter into agreements with the Administrator, the Secretaries of the Departments of Agriculture, Commerce, Interior, and Transportation, and the heads of other appropriate Federal agencies to minimize, to the maximum extent practicable, duplication, needless paperwork, and delays in the issuance of permits under this section. Such agreements shall be developed to assure that, to the maximum extent practicable, a decision with respect to an application for a permit under subsection (a) of this section will be made not later than the ninetieth day after the date the notice of such application is published under subsection (a) of this section.
- (r) The discharge of dredged or fill material as part of the construction of a Federal project specifically authorized by Congress, whether prior to or on or after the date of enactment of this subsection, is not prohibited by or otherwise subject to regulation under this section, or a State program approved under this section, or section 301(a) or 402 of the Act (except for effluent standards or prohibitions under section 307), if information on the effects of such discharge, including consideration of the guidelines developed under subsection (b)(1) of this section, is included in an environmental impact statement for such project pursuant to the National Environmental Policy Act of 1969 and such environmental impact statement has been submitted to Congress before the actual discharge of dredged or fill material in connection with the construction of such project and prior to either authorization of such project or an appropriation of funds for such construction.

### (s)

- (1) Whenever on the basis of any information available to him the Secretary finds that any person is in violation of any condition or limitation set forth in a permit issued by the Secretary under this section, the Secretary shall issue an order requiring such persons to comply with such condition or limitation, or the Secretary shall bring a civil action in accordance with paragraph (3) of this subsection.
- (2) A copy of any order issued under this subsection shall be sent immediately by the Secretary to the State in which the violation occurs and other affected States. Any order issued under this subsection shall be by personal service and shall state with reasonable specificity the nature of the violation, specify a time for compliance, not to exceed thirty days, which the Secretary determines is reasonable, taking into account the seriousness of the violation and any good faith efforts to comply with applicable requirements. In any case in which an order under this subsection is issued to a corporation, a copy of such order shall be served on any appropriate corporate officers.

(3) The Secretary is authorized to commence a civil action for appropriate relief, including a permanent or temporary injunction for any violation for which he is authorized to issue a compliance order under paragraph (1) of this subsection. Any action under this paragraph may be brought in the district court of the United States for the district in which the defendant is located or resides or is doing business, and such court shall have jurisdiction to restrain such violation and to require compliance. Notice of the commencement of such action shall be given immediately to the appropriate State.

#### (4)

- (A) Any person who willfully or negligently violates any condition or limitation in a permit issued by the Secretary under this section shall be punished by a fine of not less than \$2,500 nor more than \$25,000 per day of violation, or by imprisonment for not more than one year, or by both. If the conviction is for a violation committed after a first conviction of such person under this paragraph, punishment shall be by fine of not more than \$50,000 per day of violation, or by imprisonment for not more than two years, or by both.
- **(B)** For the purposes of this paragraph, the term "person" shall mean, in addition to the definition contained in section 502(5) of this Act, any responsible corporate officer.
- **(5)** Any person who violates any condition or limitation in a permit issued by the Secretary under this section, and any person who violates any order issued by the Secretary under paragraph (1) of this subsection, shall he subject to a civil penalty not to exceed \$10,000 per day of such violation.
- (t) Nothing in this section shall preclude or deny the right of any State or interstate agency to control the discharge of dredged or fill material in any portion of the navigable waters within the jurisdiction of such State, including any activity of any Federal agency, and each such agency shall comply with such State or interstate requirements both substantive and procedural to control the discharge of dredged or fill material to the same extent that any person is subject to such requirements. This section shall not be construed as affecting or impairing the authority of the Secretary to maintain navigation.

#### **National Historic Preservation Act**

Authorized by the National Historic Preservation Act of 1966, as amended (NHPA) and administrated by the National Park Service (NPS), the National Register of Historic Places (NRHP) is the official list of the nation's historic places deemed worthy of preservation, and includes districts, sites, buildings, structures, and objects that are significant in American history, prehistory, architecture, archaeology, engineering, and culture. To be eligible for listing in the NRHP, a property must retain sufficient integrity to convey its significance and meet at least one of the following evaluation criteria:

- A. Is associated with events that have made a significant contribution to the broad patterns of our history; or
- B. Is associated with the lives of significant persons in our past; or
- C. Embodies the distinctive characteristics of a type, period, or method of construction, or represents the work of a master, or possesses high artistic values, or that represents a significant and distinguishable entity whose components may lack individual distinction; or

D. Has yielded, or may be likely to yield, information important in history or prehistory.

Should a cultural resource be determined eligible for NRHP listing, it is considered a "historic property" under 36 CFR 60.4. Properties listed or formally determined eligible for listing in the NRHP are automatically listed in the California Register of Historical Resources (CRHR) (Public Resources Code [PRC] Section 5024.1(d)(1)).

The NPS publication, How to Apply the National Register Criteria for Evaluation, National Register Bulletin 15, establishes how to evaluate the integrity of a historic property and defines integrity as "the ability of a property to convey its significance" (NPS 1997). The evaluation of integrity must be grounded in an understanding of a historic property's physical features and how they relate to the aspects of integrity. Determining which of these aspects are most important to a property requires knowing why and at what level (local, state, or national) it is significant and its period of significance. Although "rarity" of property type is not an aspect of significance, it is considered when assessing integrity.

To retain historic integrity, a property must possess several, and usually most, aspects of integrity: location, design, setting, materials, workmanship, feeling, and association. These seven aspects of integrity are defined as follows:

- 1. Location is the place where the historic property was constructed or the place where the historic event occurred.
- 2. Design is the combination of elements that create the form, plan, space, structure, and style of a property.
- 3. Setting is the physical environment of a historic property and refers to the character of the site and the relationship to surrounding features and open space. Setting often refers to the basic physical conditions under which a property was built and the functions it was intended to serve. These features can be either natural or manmade, including vegetation, paths, fences, and relationships between other features or open space.
- 4. Materials are the physical elements that were combined or deposited during a particular period or time and in a particular pattern or configuration to form a historic property.
- 5. Workmanship is the physical evidence of crafts of a particular culture or people during any given period of history or prehistory and can be applied to the property as a whole or to individual components.
- 6. Feeling is a property's expression of the aesthetic or historic sense of a particular period. It results from the presence of physical features that, when taken together, convey the property's historic character.
- 7. Association is the direct link between the important historic event or person and a historic property.

# **Abandoned Shipwreck Act of 1987**

The Abandoned Shipwreck Act (ASA) was signed into law on April 28, 1988. The purpose of the ASA is to protect historic shipwrecks in United States from treasure hunters and unauthorized salvagers. The ASA is found in public law at P. L. 100–298, §2, Apr. 28, 1988, 102 Stat. and in the U.S. Code at 43 U.S.C. §§ 2101–2106, et seq.

The ASA establishes Federal government ownership over most abandoned shipwrecks in the nation's rivers and lakes, and in the ocean to a distance of three miles offshore (NPS 2023). Under the Act, the U.S. Government asserted title to three categories of abandoned shipwrecks:

- abandoned shipwrecks embedded in a state's submerged lands;
- abandoned shipwrecks embedded in coralline formations protected by a state on its submerged lands; and
- abandoned shipwrecks located on a state's submerged lands and included in or determined eligible for inclusion in the National Register of Historic Places.

Upon asserting title, the Federal government transferred its title to the government entity that owned the submerged lands containing the shipwrecks. As a result, state governments have title to shipwrecks located on state lands, the Federal government has title to shipwrecks located on Federal lands, and Indian tribes have title to shipwrecks located on Indian lands. The Federal government, however, continues to hold title to sunken U.S. warships and other shipwrecks entitled to Sovereign Immunity, no matter where the vessels are located. Such vessels are not affected by the statute (NPS 2023).

The ASA stipulates that the laws of salvage and finds do not apply to abandoned shipwrecks claimed by the government under the Act. It removes those shipwrecks from the jurisdiction of Federal Admiralty Court, such that the wrecks, their cargo, and content are no longer treated as commodities lost at sea and in need of salvage. For archaeology, it means that shipwrecks are treated as historically and scientifically valuable (NPS 2023).

# Native American Graves Protection and Repatriation Act (NAGPRA)

NAGPRA requires Federal agencies and institutions that receive Federal funds (including museums, universities, state agencies, and local governments) to repatriate or transfer Native American human remains and other cultural items to the appropriate parties by—

- Consulting with lineal descendants, Indian Tribes, and Native Hawaiian organizations on Native American human remains and other cultural items;
- Protecting and planning for Native American human remains and other cultural items that may be removed from Federal or tribal lands;
- Identifying and reporting all Native American human remains and other cultural items in inventories and summaries of holdings or collections; and
- Giving notice prior to repatriating or transferring human remains and other cultural items.

The Act recognizes the rights of lineal descendants, Indian Tribes, and Native Hawaiian organizations (NHOs) in Native American human remains, funerary objects, sacred objects, and objects of cultural patrimony. The Secretary of the Interior is responsible for promulgating regulations to carry out the provisions of the Act and delegated this authority to the Assistant Secretary. Since 1993, the Department of the Interior (Department) has published rules under the title "Native American Graves Protection and Repatriation Act Regulations" including:

RIN 1024-AC07, 1993 Proposed Rule (58 FR 31122, May 28, 1993) and 1995 Final Rule (60 FR 62134, December 4, 1995);

- RIN 1024-AC84, Civil Penalties Final Rule (68 FR 16354, April 3, 2003) and Future Applicability Final Rule (72 FR 13184, March 21, 2007);
- RIN 1024-AD68, 2007 Proposed Rule Disposition of Culturally Unidentifiable Human Remains (72 FR 58582, October 16, 2007) and 2010 Final Rule Disposition of Culturally Unidentifiable Human Remains (75 FR 12378, March 15, 2010); and
- RIN 1024-AE00, Disposition of Unclaimed Cultural Items Final Rule (80 FR 68465, November 5, 2015).
- RIN 1024-AE19. to clarify and improve upon the systematic processes for disposition or repatriation of Native American human remains and cultural items (87 FR 63202, hereafter 2022 Proposed Rule).

This final rule revises and replaces definitions and procedures for lineal descendants, Indian Tribes, Native Hawaiian organizations, museums, and Federal agencies to implement the Native American Graves Protection and Repatriation Act of 1990. These regulations clarify and improve upon the systematic processes for the disposition or repatriation of Native American human remains, funerary objects, sacred objects, or objects of cultural patrimony. These regulations provide a step-by-step roadmap with specific timelines for museums and Federal agencies to facilitate disposition or repatriation. Throughout these systematic processes, museums and Federal agencies must defer to the Native American traditional knowledge of lineal descendants, Indian Tribes, and Native Hawaiian organizations. This rule is effective January 12, 2024. State

#### California Public Resources Code 5097.9

§ 5097.9 – Interference with Native American religion or damage to cemeteries or places of worship, etc., prohibited, construction and exemptions from law.

No public agency, and no private party using or occupying public property, or operating on public property, under a public license, permit, grant, lease, or contract made on or after July 1, 1977, shall in any manner whatsoever interfere with the free expression or exercise of Native American religion as provided in the United States Constitution and the California Constitution; nor shall any such agency or party cause severe or irreparable damage to any Native American sanctified cemetery, place of worship, religious or ceremonial site, or sacred shrine located on public property, except on a clear and convincing showing that the public interest and necessity so require.

#### § 5097.91 - Native American Heritage Commission

There is in state government a Native American Heritage Commission (NAHC), consisting of nine members appointed by the Governor with the advice and consent of the Senate.

### § 5097.94 - Powers and duties

This section discusses the powers and duties of the NAHC. These powers and duties include:

- To Identify and catalog places of special religious or social significance to Native Americans and known graves and cemeteries of Native American on private lands, notifying landowners whose property contains Native American graves and cemeteries and identifying the most likely descendant.
- To make recommendations relative to Native American sacred places that are located on private lands, are inaccessible to Native Americans, and have cultural significance

- to Native Americans for acquisition by the state or other public agencies for the purpose of facilitating or assuring access thereto by Native Americans.
- To make recommendations to the Legislature relative to procedures which will voluntarily encourage private property owners to preserve and protect sacred places in a natural state and to allow appropriate access to Native American religionists for ceremonial or spiritual activities.
- To make recommendations to the Director of Parks and Recreation and the California Arts Council relative to the California State Indian Museum and other Indian matters touched upon by department programs.
- To assist Native Americans in obtaining appropriate access to sacred places that are located on public lands for ceremonial or spiritual activities.
- To assist state agencies in any negotiations with agencies of the federal government for the protection of Native American sacred places that are located on federal lands.

# § 5097.98 - Notification of discovery of Native American human remains, descendants; disposition of human remains and associated grave goods.

This section discusses the procedures that need to be followed upon the discovery of Native American human remains. The NAHC, upon notification of the discovery of human remains, is required to contact the County Coroner pursuant to subdivision (c) of Section 7050.5 of the Health and Safety Code and shall immediately notify those persons it believes to be most likely descended from the deceased Native American.

Upon the discovery of the Native American remains, the landowner shall ensure that the immediate vicinity, according to generally accepted cultural or archaeological standards or practices, where the Native American human remains are located, is not damaged or disturbed by further development activity until the landowner has discussed and conferred, as prescribed in this section, with the most likely descendants regarding their recommendations, if applicable, taking into account the possibility of multiple human remains.

The landowner shall discuss and confer with the descendants all reasonable options regarding the descendants' preferences for treatment. The descendants' preferences for treatment may include the following:

- A. The nondestructive removal and analysis of human remains and items associated with Native American human remains.
- B. Preservation of Native American human remains and associated items in place.
- C. Relinquishment of Native American human remains and associated items to the descendants for treatment.
- D. Other culturally appropriate treatment.

The parties may also mutually agree to extend discussions, taking into account the possibility that additional or multiple Native American human remains, as defined in this section, are located in the Proposed API/APE, providing a basis for additional treatment measures.

The descendants may, with the permission of the owner of the land, or his or her authorized representative, inspect the site of the discovery of the Native American remains and may recommend to the owner or the person responsible for the excavation work means for treating or disposing, with appropriate dignity, the human remains and any associated grave goods.

The descendants shall complete their inspection and make their recommendation within 48 hours of their notification by the Native American Heritage Commission. The recommendation may include the scientific removal and nondestructive analysis of human remains and items associated with Native American burials.

Human remains of a Native American may be an inhumation or cremation and in any state of decomposition or skeletal completeness. Any items associated with human remains that are placed or buried with Native American human remains are to be treated in the same manner as the remains but do not by themselves constitute human remains.

Whenever the commission is unable to identify a descendant, or the descendants identified fail to make a recommendation, or the landowner or his or her authorized representative rejects the recommendation of the descendants and the mediation provided for in subdivision (k) of section 5097.94. if invoked, fails to provide measures acceptable to the landowner, the landowner or his or her authorized representative shall inter the human remains and items associated with Native American human remains with appropriate dignity on the property in a location not subject to further and future subsurface disturbance. To protect these sites, that landowner shall do one or more of the following:

- A. Record the site with the commission or the appropriate Information Center.
- B. Utilize an open-space or conservation zoning designation or easement.
- C. Record a document with the county in which the property is located.

Upon the discovery of multiple Native American human remains during a ground-disturbing land development activity, the landowner may agree that additional conferral with descendants is necessary to consider culturally appropriate treatment of multiple Native American human remains.

§ 5097.99. Obtaining or possessing Native American artifacts or human remains taken from grave or cairn on or after January 1, 1984; prohibition

This section discusses the prohibitions and felony charges for obtaining or possessing Native American artifacts or human remain from a grave or cairn.

§ 5097.991 Policy of the State that Native American Remains and Associated Grave Artifacts Shall be Repatriated

It is the policy of the state that Native American remains and associated grave artifacts shall be repatriated.

# California Environmental Quality Act

The Project is subject to compliance with CEQA statutes and guidelines, which require both public and private projects with financing or approval from a public agency to assess the undertaking's impact on cultural resources (PRC Section 21082, 21083.2 and 21084 and California Code of Regulations 10564.5). Specifically, under PRC Section 201084.1, a "project that may cause a substantial adverse change in the significance of an historical resource is a project that may have a significant effect on the environment." The first step in the CEQA compliance process in terms of historical resources is to identify any that may be affected by the project.

Cultural resources are buildings, sites, human-modified landscaped areas, traditional cultural properties, structures, or objects that may have historical, architectural, cultural, or scientific

importance based on established criteria. CEQA states that if a project will have a significant impact on important cultural resources, deemed "historically significant," then project alternatives and mitigation measures must be considered.

"Historical resource" is a term with a defined statutory meaning (PRC Section 21084.1). The determination of significant impacts on historical and archaeological resources is described in Sections 15064.5(a) and 15064.5(b) of the CEQA Guidelines. Section 15064.5(a) states that historical resources include the following:

- A resource listed or determined to be eligible by the State Historical Resources Commission for listing, in the CRHR (PRC Section 5024.1).
- A resource included in a local register of historical resources, as defined in Section 5020.1(k) of the PRC, or identified as significant in a historical resource survey meeting the requirements of Section 5024.1(g) of the PRC, will be presumed to be historically or culturally significant. Public agencies must treat any such resource as significant unless the preponderance of evidence demonstrates that it is not historically or culturally significant.
- Any object, building, structure, site, area, place, record, or manuscript that a lead agency determines to be historically significant or significant in the architectural, engineering, scientific, economic, agricultural, educational, social, political, military, or cultural annals of California may be considered a historical resource, provided the lead agency's determination is supported by substantial evidence in light of the whole record. Generally, a resource will be considered by the lead agency to be historically significant if the resource meets the criteria for listing in the [CRHR] (PRC Section 5024.1).
- The fact that a resource is not listed in or determined to be eligible for listing in the CRHR, not included in a local register of historical resources (pursuant to PRC Section 5020.1[k]) or identified in a historical resources survey (meeting the criteria in PRC Section 5024.1[g]) does not preclude a lead agency from determining that the resource may be an historical resource as defined in PRC Section 5020.1(j) or 5024.1.

# 1.1.1 California Register of Historical Resources

The CRHR program encourages public recognition and protection of resources of architectural, historical, archaeological, and cultural significance; identifies historical resources for state and local planning purposes; determines eligibility for state historic preservation grant funding; and affords certain protections under CEQA. The criteria established for eligibility for the CRHR are directly comparable to the national criteria established for the NRHP.

To be eligible for listing in the CRHR, a property must meet at least one of the following four criteria:

- It is associated with events that have made a significant contribution to the broad patterns of local or regional history, or the cultural heritage of California or the United States; or
- 2. It is associated with the lives of persons important to local, Californian, or national history; or
- 3. It embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values; or

4. It has yielded, or is likely to yield, information important to the prehistory or history of the local area, California, or the nation.

For a property to qualify under the CRHR's Criteria for Evaluation, it must also retain enough of its historic character or appearance (integrity) to be recognizable as a historical resource and to convey the reasons for its significance. For the purposes of eligibility for the CRHR, integrity is defined as, "the authenticity of a historical resource's physical identity evidenced by the survival of characteristics that existed during the resource's period of significance" (California Office of Historic Preservation 2001). To determine if a property retains the physical characteristics corresponding to its historic context, the NRHP has identified seven aspects of integrity, which the CRHR closely follows.

- 1. Location is the place where the historic property was constructed or the place where the historic event occurred.
- 2. Design is the combination of elements that create the form, plan, space, structure, and style of a property.
- 3. Setting is the physical environment of a historic property.
- 4. Materials are the physical elements that were combined or deposited during a particular period and in a particular pattern or configuration to form a historic property.
- 5. Workmanship is the physical evidence of the crafts of a particular culture or people during any given period in history or prehistory.
- 6. Feeling is the property's expression of the aesthetic or historic sense of a particular period.
- 7. Association is the direct link between an important historic event or person and a historic property.

Because integrity is based on a property's significance in a specific historic context, evaluations of integrity can only be completed after historic significance has been established.

# Assembly Bill 52 (AB 52)

Signed into law in September 2014, AB 52 created a new class of resources—tribal cultural resources—for consideration under CEQA. Tribal cultural resources may include sites, features, places, cultural landscapes, sacred places, or objects with cultural value to a California Native American tribe that are listed or determined to be eligible for listing in the California Register of Historic Resources (CRHR), included in a local register of historical resources, or a resource determined by the lead CEQA agency, in its discretion and supported by substantial evidence, to be significant and eligible for listing on the CRHR. AB 52 requires that the lead CEQA agency consult with California Native American tribes that have requested consultation for projects that may affect tribal cultural resources. The lead CEQA agency shall begin consultation with participating Native American tribes prior to the release of a negative declaration, mitigated negative declaration, or environmental impact report. Under AB 52, a project that has potential to cause a substantial adverse change to a tribal cultural resource constitutes a significant effect on the environment unless mitigation reduces such effects to a less than significant level.

### Local

# **Solano County**

The Solano County General Plan (Solano County 2008) offers goals, policies, and implementation programs to guide the preservation of precontact and historic archaeological sites in Solano County. The county's stated cultural resource goals include (1) collaboration with Native American groups to protect traditional cultural places and sacred spaces in the context of land use decisions and (2) leveraging the county's historic capital to drive economic development, especially tourism.

The policies related to cultural resources outlined by the Solano County General Plan include the following:

- RS.P-38. Identify and preserve important prehistoric and historic structures, features, and communities.
- RS.P-39. Tie historic preservation efforts to the County's economic development pursuits, particularly those relating to tourism.
- RS.P-40. Consult with Native American governments to identify and consider Native American cultural places in land use planning.

In pursuit of its cultural resource goals, Solano County designed an implementation program and possible mitigation measures in areas with medium to high potential for archaeological or cultural resources:

- RS.I-25. Require cultural resources inventories of all new development projects in areas identified with medium or high potential for archeological or cultural resources. Where a preliminary site survey finds medium to high potential for substantial archaeological remains, the County shall require a mitigation plan to protect the resource before issuance of permits. Mitigation may include:
  - Having a qualified archaeologist present during initial grading or trenching (monitoring);
  - Redesign of the project to avoid archaeological resources (this is considered the strongest tool for preserving archaeological resources);
  - o Capping the site with a layer of fill; and/or
  - Excavation and removal of the archaeological resources and curation in an appropriate facility under the direction of a qualified archaeologist.
  - Alert applicants for permits within early settlement areas to the potential sensitivity. If significant archaeological resources are discovered during construction or grading activities, such activities shall cease in the immediate area of the find until a qualified archaeologist can determine the significance of the resource and recommend alternative mitigation.

# **Contra Costa County**

The Contra Costa County General Plan (Contra Costa County 2010) details policies and implementation measures related to the stated goal of the identification and preservation of historic and cultural resources in Contra Costa County.

Contra Costa County's historic and cultural resource policies include:

- 9-28. Areas which have identifiable and important archaeological or historic significance shall be preserved for such uses, preferably in public ownership.
- 9-29. Buildings or structures that have visual merit and historic value shall be protected.
- 9-30. Development surrounding areas of historic significance shall have compatible and high-quality design in order to protect and enhance the historic quality of the area.
- 9-31. Within the Southeast County area, applicants for subdivision or land use permits to allow non-residential uses shall provide information to the County on the nature and extent of the archeological resources that exist in the area. The County Planning Agency shall be responsible for determining the balance between multiple use of the land and protection of resources (Contra Costa General Plan).

Contra Costa County's historic and cultural resource implantation measures include those related to the development review process, ordinance revisions, and other programs:

#### **Development Review Process**

- 9-i. Develop an archaeological sensitivity map to be used by staff in the environmental review process for discretionary permits to determine potential impacts upon cultural resources.
- 9-j. As a condition of approval of discretionary permits, include a procedure to be followed in the event that archaeological resources are encountered during development or construction.

#### **Ordinance Revisions**

- 9-k. Review existing County ordinances and guidelines and make amendments as necessary to ensure that they provide adequate safeguards for archaeological and historic resources.
- 9-I. Develop design guidelines for areas adjacent to or within scenic corridors or historic sites.

#### Other Programs

- 9-m. Promote the use of the State of California Historic Building Code to protect historic sites in the county.
- 9-n. Encourage owners of eligible historic properties to apply for State and federal registration of these sites and to participate in tax incentive programs for historic restoration.
- 9-o. Seek coordination and cooperation with federal, State, and local governments, and with private and non-profit organizations, to establish funding sources to preserve, restore, and enhance unique historic sites. Such funding sources may be used to acquire and preserve sites or to acquire easements over sites and building facades.
- 9-p. Identify funding mechanisms, including funding from the County to the extent possible, to support programs to preserve, restore, and enhance unique historic sites.

# **Sacramento County**

The Sacramento County General Plan (Sacramento County 2017) provides an overarching goal related to the protection and preservation of cultural resources:

Promote the inventory, protection and interpretation of the cultural heritage of Sacramento County, including historical and archaeological settings, sites, buildings, features, artifacts and/or areas of ethnic historical, religious or socioeconomical importance.

In pursuance of that goal, the Sacramento County General Plan identifies six objectives, and policies and implementation programs to accomplish those objectives.

**Objective 1:** Comprehensive knowledge of archeological and historic site locations.

#### <u>Implementation Measures:</u>

- A. In cooperation with the North Central Information Center (NCIC) and cultural resources professionals, conduct:
  - A comprehensive survey to record location of prehistoric, ethnohistoric and historic sites.
  - A comprehensive survey to identify historically and architecturally important structures.

<u>Objective 2:</u> Attention and care during project review and construction to ensure that cultural resource sites, either previously known or discovered on the project site, are properly protected with sensitivity to Native American values.

#### Policies:

- CO-150. Utilize local, state and national resources, such as the NCIC, to assist in determining the need for a cultural resources survey during project review.
- CO-151. Projects involving an adoption or amendment of a General Plan or Specific Plan or the designation of open space shall be noticed to all appropriate Native American tribes in order to aid in the protection of traditional tribal cultural places.
- CO-152. Consultations with Native American tribes shall be handled with confidentiality and respect regarding sensitive cultural resources on traditional tribal lands.
- CO-153. Refer projects with identified archeological and cultural resources to the Cultural Resources Committee to determine significance of resource and recommend appropriate means of protection and mitigation. The Committee shall coordinate with the Native American Heritage Commission in developing recommendations.
- CO-154. Protection of significant prehistoric, ethnohistoric and historic sites within open space easements to ensure that these resources are preserved in situ for perpetuity.
- CO-155. Native American burial sites encountered during preapproved survey or during construction shall, whenever possible, remain in situ. Excavation and reburial shall occur when in situ preservation is not possible or when the archeological significance of the site merits excavation and recording procedure. On-site reinterment shall have priority. The project developer shall provide the burden of proof that off-site reinterment is the only feasible alternative. Reinterment shall be the responsibility of local tribal representatives.

- CO-156. The cost of all excavation conducted prior to completion of the project shall be the responsibility of the project developer.
- CO-157. Monitor projects during construction to ensure crews follow proper reporting, safeguards, and procedures.
- CO-158. As a condition of approval of discretionary permits, a procedure shall be included to cover the potential discovery of archaeological resources during development or construction.

#### <u>Implementation Measures:</u>

- A. Develop a Cultural Resources Committee (appointed by the Board of Supervisors) to establish procedures and criteria for preservation and mitigation for cultural resources by utilizing information available from the Sacramento Archives and Museum Collection Center (SAMCC) and the North Central Information Center (NCIC).
- B. At the beginning of projects involving an adoption or amendment of a General Plan or Specific Plan or the designation of open space, notify the California Native American Heritage Commission and the appropriate Native American tribes regarding the project and, if requested by the tribes, set up consultation regarding the protection of traditional tribal cultural places. This notification and consultation process shall be carried out in accordance with Government Code Sections 65040.2, 65092, 65351, 65352, 65352.3, 65352.4, 65560, 65562.5; Public Resources Code Sections 5097.9, 5097.993; and Civil Code Section 815.3 and shall prevent public exposure of sensitive cultural resources.

#### C. Establish procedures to:

- Conduct periodic training programs for County Public Works and Infrastructure
  Agency and County Airports construction and maintenance personnel to facilitate
  their awareness of archeological site indicators and proper procedures.
- Utilize mitigation monitoring and reporting programs to provide for on-site monitoring during construction adjacent to known sites.
- Write letters during the environmental review process, to peoples of Native American descent based on a contact list provided by the Native American Heritage Commission, to request a Native American statement regarding a proposed project when that project is located on a site with known cultural resources.
- D. Pursue becoming a certified local government and establish a local County registry to document and protect cultural resources that are significant to the County of Sacramento. This registry should be administered through the Cultural Resources Committee (please refer to Implementation Measure A under Archeological Site Protection During Development).

**Objective 3:** Structures with architectural or historical importance preserved to maintain contributing design elements.

#### Policies:

CO-164. Structures having historical and architectural importance shall be preserved and protected.

- CO-165. Refer projects involving structures or within districts having historical or architectural importance to the Cultural Resources Committee to recommend appropriate means of protection and mitigation.
- CO-166. Development surrounding areas of historic significance shall have compatible design in order to protect and enhance the historic quality of the areas.
- CO-167. When conducting planning studies, County Planning and Environmental Review staff, shall encourage the adaptive reuse of historic resources when the original use is no longer feasible or allowed under proposed area planning efforts.
- CO-168. County-owned historic and cultural resources shall be preserved and maintained, such that modifications, alterations, and rehabilitations are conducted in a manner that is consistent with the U.S. Secretary of the Interiors Standards for the Treatment of Historic Properties.

#### <u>Implementation Measures:</u>

- A. In cooperation with the North Central Information Center (NCIC) and cultural resources professionals, conduct:
  - A comprehensive survey to record location of prehistoric, ethnohistoric and historic sites.
  - A comprehensive survey to identify historically and architecturally important structures.

**Objective 4:** Known cultural resources protected from vandalism unauthorized excavation, or accidental destruction.

#### Policies:

- CO-169. Restrict the circulation of cultural resource location information to prevent potential site vandalism. This information is exempt from the "Freedom of Information Act".
- CO-170. Cooperate with other agencies to enforce laws and aggressively prosecute illegal collection of artifacts.
- CO-171. Design and implement interpretive programs about known archeological or historical sites on public lands or in public facilities. Interpretation near or upon known sites should be undertaken only when adequate security is available to protect the site and its resources.

#### <u>Implementation Measures:</u>

- A. Develop a plan in conjunction with Archeological Conservancy to secure easements, agreements, or other appropriate mechanisms to protect known cultural sites from disturbance or erosion.
- B. Periodic patrol of County owned and managed archeological sites by park rangers.
- C. Implement a program within County departments which manage or patrol properties with known cultural resources to facilitate their awareness of archaeological site indicators and proper procedures in handling cultural resources.

**Objective 5:** Properly stored and classified artifacts for ongoing study.

#### Implementation Measures:

- A. Initiate discussions regarding the preparation of a comprehensive regional study design for the excavation, cataloging and analysis of cultural resource artifacts and the synthesis of available information.
- B. Identify a repository for cataloging and storage of excavated cultural artifacts.

**Objective 6:** Public awareness and appreciation of both visible and intangible historic and cultural resources.

#### Policies:

- CO-172. Provide historic and cultural interpretive displays, trails, programs, living history presentations, and public access to the preserved artifacts recovered from excavations.
- CO-173. Interpretive elements involving Native American cultural resources shall be located at village sites (provided any unexcavated resources are properly protected) representative of different physical environments found in the County.
- CO-174. Promote and support the California Indian Heritage Center.
- CO-175. The County shall support efforts to develop Cultural Resources Tourism program within the County as a tool to preserve important cultural resources and in order to encourage economic development of resources within the County.

#### **Implementation Measures:**

- A. In cooperation with local cultural resources experts:
  - o Present educational programs to school age children.
  - o Design educational criteria guidelines and study units for incorporation in county school curricula.

# Setting

# **Environmental Setting**

The Project is at the confluence of the Sacramento and San Joaquin Rivers at the eastern end of Suisun Bay and the western edge of the Sacramento–San Joaquin River Delta. It extends northward into the low-lying Montezuma Hills, and its southern point in Pittsburg is approximately 3 mi north of the California Coast Range foothills in Contra Costa County. The deep water and lack of tributaries within the Proposed API/APE is somewhat unusual, given its location at the distal edge of a major river delta. While most deltas expand outward in broad fans, the Sacramento–San Joaquin River Delta is an inverted delta that contracts with proximity to its outlet in the San Francisco Bay. The unique setting of the Proposed API/APE is a result of the region's geologic history.

Before the San Francisco Bay began to form at the start of the Holocene 12,000 years ago, the coastline was approximately 30 miles west of its current position near the Farallon Islands due to lower sea levels during the Pleistocene. The Sacramento and San Joaquin Rivers faced a steeper gradient and cut deep and narrow channels through the Proposed API/APE as water flowed steadily toward the Pacific Ocean. Gravels found in Pleistocene deposits of the Montezuma Hills at the northern end of the Proposed API/APE and Pleistocene alluvial fans at the southern edge of the proposed APE suggest a high-energy depositional environment during this time (Atwater 1982;

Helley and Graymer 1998). However, once the sea level started to rise in the Holocene and the San Francisco Bay flooded, the river's gradient and energy decreased, causing it to dump its sediment load away from the ocean in what is now the Sacramento-San Joaquin River Delta. This clay-rich material is evident in the muddy marsh deposits along the bank of the Sacramento River within the Proposed API/APE (Helley and Graymer 1998). Alternating sequences of fine to coarse-grained sediments represent cycles of marine transgression and regression throughout the Pleistocene, but the most recent iteration is best represented due to the erosion, burial, or uplift of ancient low depositional energy environments (Atwater 1982).

#### Climate

The Project area has a Mediterranean climate that consists of mild to moderately cold, wet winters, and hot, dry summers. High winds blow through the hill country within this area and are strongest during the winter. Approximately 90 percent of the annual precipitation occurs from November through April. Seasonal averages range from 23 inches (Best Places 2024). This relative aridity has influenced the history of land use and occupation of the southern Solano County. Pasture grasses are scarce, and forage is meager during the summer and fall. Dry-farming could be practiced in certain areas, though large-scale irrigation farming was only economically viable along the Sacramento River (Solano County 2024).

# Geology

This section is reproduced from the paleontological report prepared for this Project (Clifford 2024). The Project area is near the border of the Great Valley geomorphic province and the Coast Ranges geomorphic province. A geomorphic province is a region of unique topography and geology distinguished from other regions based on its landforms and tectonic history.

The Coast Ranges include north-northwest trending mountain ranges and valleys formed due to uplift along the active Pacific Plate-North American plate boundary system. The basement rocks in the Coast Ranges consist of the Franciscan Complex and the Salinian Block plutonic igneous basement rocks. The metamorphic and marine rocks of the Franciscan Complex were primarily derived from erosion of a volcanic arc, subsequent deposition in a deep marine environment, and later accretion onto the continental margin of North America during the subduction of the Farallon Plate (Schemmann et al. 2008). Later, the topography and geology of the region were highly influenced by the development of the San Andreas Fault Zone on the Pacific plate-North American plate boundary beginning at least 30 million years ago [Ma](Dickinson 1981).

The Great Valley is a 50 mile wide by 400 mile long alluvial plain in the central part of California that has accumulated sediment since the Jurassic Period (201–145 Ma) (California Geological Survey [CGS] 2002). The Great Valley is influenced by two rivers, with the northern portion of the valley, the Sacramento Valley, being drained by the Sacramento River and the southern portion of the valley, the San Joaquin Valley, drained by the San Joaquin River (CGS, 2002). The depth of the sedimentary deposits, combined with associated regional tectonic forces, have produced extensive oil fields particularly in the southernmost San Joaquin Valley and along anticlinal uplifts on its southwestern margin (CGS, 2002).

Locally, the Project area crosses the Suisun Bay, an estuarine embayment at the intersection of the San Francisco Bay and Sacramento River Delta. Estuaries often act as sediment "traps" (McLusky 1981), in this case resulting in accumulation of sediment in and near the river during the Pleistocene Epoch (2.58 Ma to 1y1,700 years ago) and Holocene Epoch (11,700 years ago to present). The northern portion of the Project area near the proposed Collinsville Substation is in the

southern edge of the Montezuma Hills, which is the surficial result of a local deep, asymmetric, south-plunging graben of underlying sediment from the Paleogene Period (66–23 Ma) (Krug et al. 1992).

### Soils

This section is reproduced with some revision from the paleontological report prepared for this Project (Clifford 2024). The geology of the Project area is mapped by Graymer et al. (2002) at a scale of 1:100,000 (Figure 3, Figure 4, and Figure 5). The Project area is underlain by the following geologic units: Montezuma Formation (Qmz), alluvial fan deposits (Qpf), delta mud deposits (Qhdm), bay mud deposits (Qhbm), alluvial fan deposits (Qhf), artificial fill (af), and unmapped sedimentary deposits of the Suisun Bay and the Sacramento River Delta.

The Montezuma Formation (Qmz) and alluvial fan deposits (Qpf) are too old to have any potential for human generated remains. The other soils are Holocene and, therefore, young enough to potentially contain archaeological deposits.

- Delta mud deposits (Qhdm) are composed of mud and peat with minor silt and sand deposited at or near sea level (Graymer et al. 2002). This unit underlies the lower-elevation, near-shore areas in the northern portion of the Project area. These areas may have been to wet to support human activity of any extent and probably have low sensitivity for archaeological deposits.
- Bay mud deposits from the Holocene (Qhbm) are composed of gray, green, blue, and black clay and silty clay underlying marshlands and tidal mud flats with lenses of well-sorted, fine sand and silt, shell, and peat (Graymer et al. 2002). This unit is mapped in the western edge of the northern portion of the Project area and the southwest corner of the southern portion of the Project area and may underlie more of the southern portion below the artificial fill (af, discussed below). Like the previous sediments, these were likely to wet when they were deposited for any extensive human activity.
- Alluvial fan deposits from the Holocene Epoch (Qhf) are composed of moderately to poorly sorted, moderately to poorly bedded sand, gravel, silt, and clay deposited where streams emanate from upland regions onto more gently sloping valley floors or plains (Graymer et al., 2002). This unit may underlie the southern portion of the Project area below the artificial fill (af, discussed below). These soils have probably moderate sensitivity for archaeological deposits, especially close to water sources. Archaeological deposits would likely lie on old land surfaces (paleosols) if they are present.
- Artificial fill (af) is composed of undifferentiated, man-made deposit of various materials and ages including dredge spoils, levee fill, road embankments, earthen dams, and railroad grades (Graymer at al. 2002). This unit underlies PG&E's existing Pittsburg Substation in the southern portion of the Project area. Because of its man-made origin and recent age, artificial fill has very low archaeological sensitivity.
- The geologic units in the Project area underlying Suisun Bay and the Sacramento River Delta are not mapped by Graymer et al. (2002). Previous sampling of submarine bay and delta sediment showed clay, silt, and coarse sand of intertidal to subtidal environments were deposited on thick estuarine mud from the middle Holocene (Chin et al., 2002; Luoma et al., 1984). These sediments are similar to the bay mud deposits (Qhbm) and delta mud deposits (Qhdm), though there is likely also significant contamination in the surficial sediment by debris from the nineteenth and twentieth century, including from mining and

agriculture (Capiella et al. 1999). Therefore, they have low sensitivity for archaeological deposits.

# Vegetation and Associated Wildlife

The Project area is partially within the low-elevation Suisun Terraces and Low Hills ecoregion that occurs on mostly Quaternary alluvium, surrounding Suisun Bay, upland from the lower part of the Delta. A few low hills occur, such as the Portrero Hills and Montezuma Hills. This region is mostly an urban or urbanizing region, and includes the cities of Fairfield, Concord, Pittsburg, and Antioch. The Montezuma Hills are mostly non-native grasslands, used for grazing and wind farms (USEPA 2016).

It also shares in the Delta ecoregion, which is a low elevation area, near sea level, at the confluence of major rivers. It is characterized by numerous sloughs and channels formed where the Sacramento, San Joaquin, Cosumnes, Mokelumne, and Calaveras Rivers enter the ecoregion. Water from these rivers commingles in the Delta and is influenced by tidal action, streamflow, and water diversion as it flows toward San Francisco Bay. Brackish tidal water enters the area when river flow is low during the summer and autumn. In the main part of the region, former wetland islands have been reclaimed for intensive agriculture with a network of levees. Corn, alfalfa, hay, and wheat are the most extensive crops on these organic soils, although various crops were grown historically. Soil temperature regimes are thermic and soil moisture regimes are mostly aguic, with some xeric on levees. Land subsidence and salinity intrusion are two of many important resource issues here. The western part of the ecoregion includes large areas of brackish and seasonal freshwater marshes and wetlands that surround Grizzly Bay and Suisun Bay. The native vegetation historically consisted of aquatic plants such as tules, cattails, and rushes. Saltgrass was dominant in many areas. Many of the diked wetlands are managed for waterfowl hunting. The Delta plays a central role in the distribution of water from the State's wetter northern regions to its southern, arid, and populous cities and agricultural areas. These water diversions can have adverse effects on species such as delta smelt, Chinook salmon, Central Valley steelhead, and green sturgeon (USEPA 2016).

# **Precontact Setting**

The most recently updated prehistory of the San Francisco Bay Area is presented by Milliken and others (2007), Also applicable to the Project vicinity is evidence gathered from recent archaeological investigations conducted in the Upper Los Vaqueros Watershed which is approximately 15 miles south of the Project, These studies have revealed nearly 10,000 years of occupation, one of the longest sequences of human presence yet documented in a single locality in the broader San Francisco Bay Area (Meyer and Rosenthal 1997; Price et al. 2008). The prehistory presented in Meyer and Rosenthal (1997), is summarized below to provide a context within which to evaluate cultural resources and develop potential research questions to guide recommendations for mitigation. The interested reader is referred to Milliken et al. (2007) for an updated prehistory of the broader San Francisco Bay Area.

Meyer and Rosenthal (1997) organized the prehistory of the Los Vaqueros region into five periods including:

- Lower Archaic period 10,000 to 6,000 B.P (8050 to 4050 B.C.)<sup>3</sup>
- Middle Archaic period 6,000 to 2,500 B.P. (4050 to 50 B.C.)
- Upper Archaic period 2,500 to 1,500 B.P. (50 B.C. to A.D. 450)
- Upper Archaic/Emergent period transition 1,500 to 700 B.P. (A.D. 450 to 1250)
- Emergent period 1,000 to 200 B.P. (A.D. 1250 to ca. 1750)

Two different chrono-cultural frameworks are commonly used to organize the archaeological record in the San Francisco Bay Area. One system comprises the Early-Middle-Late period divisions established by Beardsley (1954), commonly referred to as the Central California Taxonomic System (CCTS) (Gerow with Force 1968). The other system is based on the Archaic-Emergent period chronology established by Fredrickson (1973, 1994). The CCTS system divisions are primarily based on changes in material culture, including stylistic changes in artifacts such as shell beads, and the presence or absence of various artifact types or classes. Some temporal subdivisions have been refined to 200-300-year intervals on the basis of shell bead horizons that have recently been recalibrated using the radiocarbon dating technique (e.g., Groza 2002). The Archaic-Emergent period chronology represents changes in subsistence and settlement patterns, economic strategies, as well as stylistic elements of the material culture. Choice of chronocultural framework depends upon the research questions and the nature of the archaeological record being studied. It is interesting to note that Milliken et al. (2007) use a hybrid system for their recent reevaluation of the prehistory of the San Francisco Bay Area, applying a combination of the temporal sequence of the CCTS, and the cultural sequence of the Archaic-Emergent framework.

As Meyer and Rosenthal (1997) point out, the archaeological record of the Los Vagueros watershed area was not well-known when the CCTS was developed, with the earliest period beginning after people had been living in the Los Vagueros area for thousands of years. A general scarcity of temporally diagnostic artifact types, such as shell beads, from this area made the temporal divisions of the CCTS, which were based largely on changes in temporally diagnostic artifact types, not effective for linking discrete deposits from the Los Vagueros area to time-specific subperiods of the CCTS (Price et al. 2008). For these reasons, Meyer and Rosenthal framed their analysis with the Archaic-Emergent scheme, which allows for greater time depth. This framework also places the interpretive focus on behavioral changes, such as shifts in economic strategies and mobility patterns, though these are identified in part by temporally diagnostic artifacts, such as millingslabs or mortars. Nonetheless, with the accumulation of evidence in the 1990s from the archaeological excavations undertaken as part of the mitigation for the Los Vaqueros Reservoir, Meyer created a chrono-cultural sequence largely based on artifact types for the Los Vaqueros area (Milliken et al. 2007). This sequence presents the updated Los Vaqueros scheme in relation to both the Archaic-Emergent scheme (e.g., Fredrickson 1974) and the Early-Middle-Late scheme (e.g., Bennyhoff and Hughes 1987).

Notable developments and refinements of the chrono-cultural framework for the Los Vaqueros area directly resulted from the cultural resources mitigation measures stemming from compliance with both CEQA and NHPA (Price et al. 2008). These include:

57

<sup>&</sup>lt;sup>3</sup> When dates are presented in B.P., the corresponding B.C./A.D. dates are provided in parentheses as a conceptual aid.

- Extending the Lower Archaic 2000 years deeper in time to at least 10,000 B.P. (8050 B.C.), formerly the province of the PaleoIndian period according to Fredrickson (1974); and a time not covered by the CCTS (e.g., Bennyhoff and Hughes 1987).
- Extending the beginning of the Middle Archaic 1000 years back in time to around 6000 B.P. (4050 B.C.), whereas the Fredrickson Middle Archaic originates around 5000 B.P. (3050 B.C.) (1974).
- Dividing the Upper Archaic to include an Upper Archaic/Emergent transition period.
- Dividing the Emergent period into a Lower and an Upper Emergent period.

Precontact components from sites investigated in the project area include one from the Lower Archaic, four from the Middle Archaic, six from the Upper Archaic, seven from the Upper Archaic/Emergent transition, and six from the Emergent.

#### Lower Archaic Period

The earliest occupations during the Lower Archaic period are characterized by high residential mobility evidenced by short-term occupation of sites. Milliken et al. (2007) refer to this as a generalized mobile forager pattern. Artifacts characteristic of this period include millingslabs and handstones for processing plant resources such as seeds and nuts, and wide-stemmed projectile points. The radiocarbon date of 7920 cal B.C. represents the earliest date for cultural deposits from this period in the Kellogg Creek valley, obtained from a discrete charcoal concentration beneath an inverted millingslab at CA-CCO-696. The deposit lies at a depth of between 390 and 415 cm (Price et al, 2008).

Other characteristics of the Lower Archaic period include the importation of obsidian from the North Coast Ranges and the preference for a tightly flexed burial position. CA-CCO-696 yielded a tightly flexed burial at a depth of 325 cm, radiocarbon-dated to 5490 cal B.C. A few hundred meters from CA-CCO-696, the oldest documented grave in the Kellogg Creek valley was recovered from CA-CCO-637, radiocarbon-dated to 6570 cal B.C. (Meyer and Rosenthal 1998).

#### Middle Archaic Period

During the Middle Archaic period residential mobility had decreased and base camps were established. Groundstone mortars and pestles replaced handstones and millingslabs by 4000 cal B.C. (Milliken et al. 2007). A wooden mortar was recovered with a groundstone pestle at CA-CCO-637, radiocarbon-dated to 3800 cal B.C. (Meyer and Rosenthal 1997). A groundstone mortar was recovered in association with deposits containing the remains of acorns and wild cucumber, dating to at least 5,700 years ago, at CA-CCO-696 (Rosenthal and Meyer 2004; Wohlgemuth 2004). In addition to acorns, camp residents ground manzanita seeds and grey pine nuts. Despite the shift in plant resource processing tools, there is no documented change in associated floral assemblages throughout the Archaic period (Meyer and Rosenthal 1997). During the Middle Archaic period burial positions became more variable, ranging from flexed to extended positions. The first cut shell beads are found in mortuary contexts. Obsidian was obtained from distant sources (Price et al. 2008).

# **Upper Archaic Period**

During the Upper Archaic period residential mobility decreased and fixed villages were established. Plant resources from both the uplands and grassland-savanna were gathered, with an increased use of small seeds, but a continued preference for acorns. Bedrock milling stations, characterized by mortar cups ground into boulders and bedrock outcrops, first appeared between 1600 and 1300 B.P. (A.D. 350 to 650), based on stratigraphic evidence (Meyer and Rosenthal 1997). Bedrock milling stations are difficult to date because the mortars in the bedrock outcrops are only rarely found in stratigraphic association with intact midden containing datable evidence.

The Upper Archaic period burial customs once again show a preference for flexed burials. A difference in social status has been inferred from the differential distribution of uniformly made shell beads and ornaments in mortuary contexts. The shell also indicates the continuing importance of trade and exchange (Price et al. 2008).

# **Upper Archaic/Emergent Period Transition**

During the Upper Archaic/Emergent period transition there was a shift in burial practices and land-use patterns. Bedrock milling stations offer tangible evidence that more locations in the valley were utilized, but in contrast to the preceding period, occupations were brief and were probably associated with resource acquisition and processing. Occupation of the valley was more varied, including shorter-term use of both the lowland and the upland, where bedrock milling stations were often located. Burial customs shifted once again, to a preference for extended positions (Meyer and Rosenthal 1997). Obsidian use increased from earlier periods, but other exchange items were absent.

# **Emergent Period**

By the Emergent period fixed villages were once again established in the lowlands and bedrock milling stations continued to be used for bulk processing of grassland-savanna small seed resources and upland nut and berry crops. Obsidian use increased, inferred by the importation of obsidian cobbles and minimally modified flake blanks, exclusively from Napa Valley sources (Meyer and Rosenthal 1997). Milliken et al. (2007) note the introduction of the bow and arrow at the beginning of this period. The people, traditions and culture of the Emergent Period were most likely those encountered by the earliest European visitors to the area in the second half of the 18th century (Price et al. 2008).

# **Ethnographic Setting**

At the time of European contact, the Proposed API/APE was within the territory of the Patwin, a southern Wintun linguistic group (Kroeber 1925, 1930; Barrette 1908), and the Ompin, Bay Miwok, a western Utian linguistic group. Two analytical zones immediately surround Suisun Marsh—the Bay Area (Bay Miwok and Ohlone) and Middle Sacramento Valley (Patwin). Pre-mission populations in these regions were estimated as 2.1–4.0 persons per square mile in lands southeast of the marsh (Bay Miwok), increasing to 4.1–8.0 to the west and north (Meyer et al. 2013).

Modern representatives of the Bay Miwok, Ohlone, and Patwin heritages are still present in the area and are active in archaeological work. For a list of contacts from these tribes see Appendix C.

### The Patwin People

The Patwin comprise the southern branch of the Wintun people in Northern California who were native inhabitants of California since approximately A.D. 500 (Golla 2011), The extent of the territory they occupied included the southwest portion of the Sacramento Valley, from the lower hills of the eastern North Coast Ranges to the Sacramento River, from Princeton south to San Pablo and Suisun Bays and into Napa Valley as far north as Calistoga. Kroeber (1970) puts the 1770 population of the Wintun, including the Patwin, Nomlaki, and Wintu proper, at 12,000 individuals. Kroeber noted that there were permanent habitation sites of the Patwin along both banks of the Sacramento River, where small knolls were sufficient to protect the inhabitants from severe winters. Patwin were also commonly found along seasonal streams and springs in the foothill regions fronting the western margin of the Sacramento Valley. Many of these have been documented for the area between Knights Landing and Colusa far north of the Project area (Heizer and Hester 1970). One important Patwin village was Yulyul, the main village of the Suisun Patwin people of the Suisun Bay region is believed to be where Rockville is located today northwest of the Project area (Milliken 1995). In the late 1790s, when Patwin were first taken as converts to Mission Dolores in San Francisco and Mission San Jose. Sam Yeto, later baptized as Chief Solano, is described as the principal Suisun Patwin chief whose authority extended over an extensive area reaching from Petaluma Creek to the Sacramento River. Chief Solano lived at a Patwin village just south of Rockville. In the 1840s, he received the Suisun land grant, extending east from Rockville to Fairfield, from the Mexican government (Solano County 2023). Another village site, Tolenas, was identified by Kroeber about 15 miles northwest of the Project site (Johnson 1978).

The Patwin were organized into a principal village and a few satellite settlements. These groups were small, autonomous, and sometimes bounded by the limits of a small drainage. Each group had a head chief, and each village had a chief who administered its economic and ceremonial activities. The position of chief was usually inherited through the male line, but village elders occasionally chose some chiefs. McKern (1922) presented Patwin social structure in terms of three systems: the patrilineal family, the family social group, and the household unit.

The patrilineal family and descent were important features of Patwin social life, and the authority bestowed on the headman of each patriarchal family was undisputed, except in matters of tribal authority. The family social group is a larger unit that includes the husbands of female patrilineal family members and is unified by the authority of the family headman. Matrilocal residence was customary among the Patwin, and husbands routinely remained with their wife's families at least until they acquired enough wealth to establish an independent household (Kroeber 1932, 1970; McKern 1922, 1923).

Patwin subsistence relied on hunting, fishing, and gathering a wide variety of plant resources that were within their territory. Acorns were a major part of their diet and were obtained from hill and mountain oaks communally owned by the tribelet. Other easily gathered resources included blackberries, elderberries, wild grapes, new tule shoots, roots and bulbs, honey, salt (acquired from burning salt grass), and tobacco (Kroeber 1970). Kroeber's informants, however, did not report familiarity with many plants (e.g., buckeye, hazelnut, manzanita, etc.) that are dietary staples among other Native American groups.

Ethnographic records indicate that large game (e.g., deer, tule elk, antelope) were captured using nets or were shot using bows and arrows. Kroeber reports that two men would hold a wide meshed net while other hunters would drive deer into it, and waterfowl (ducks, geese, mudhens, quail, etc.) were also captured using nets. Fish were also a prime resource, and certain fishing sites were

privately owned. Fish (such as salmon, sturgeon, perch, chub, sucker, hardhead, pike, and trout) and other riverine resources (such as turtles and mussels) were caught with bone fishhooks, nets, seines, and weirs. Food resources were generally stored in bins and granaries, which were made of sticks set into the ground and were roofed with tules.

The Patwin manufactured a variety of utilitarian and ceremonial/luxury items, including baskets, stone tools, mortars and pestles, shell beads, and clothing. Coiled and twined baskets of willow and split tule were used for various purposes, including food collection, preparation, serving and storage; use as baby carriers; and for use as grave goods that were interred with the dead. A variety of tools (i.e., projectile points, bifaces, drills, scrapers, and knives) were manufactured from obsidian, chert, and basalt for both utilitarian (skinning, butchering, etc.) and ceremonial (such as burial accompaniment) purposes. Pestles and mortars made of oak and stone were used to process both plant and animal resources. Shell beads were also manufactured for personal adornment and as a medium of exchange. Clothing was generally minimal, and "men went without any covering, women wore skirts or aprons of tule or shredded bark" (Kroeber 1925).

The Patwin traded for various commodities and subsistence resources using clamshell disc beads as a medium of exchange. Kroeber referred to Patwin territory as a center for several religious sects among groups of central California Native Americans. These sects were generally based on the organization of male secret societies and are characterized by Kuksu or "bighead" dances. Kuksu emphasized curing and shamanistic functions, and its ceremonies generally consisted of impersonating spirits who journeyed from their home to a village, blessed the village, and then returned home (Kroeber 1925).

## The Miwok People

The Ompin group of Bay Miwok are associated with the eastern and southeastern Suisan Marsh edges, where the San Joaquin and Sacramento rivers enter the Suisun Bay (Meyer et al. 2013). Within the Bay Miwok grouping were the Saklan, Chupan, Wolwun, Julpun, and Ompin (Beeler 1955; Bennyhoff 1961). Archaeological and linguistic data support the assertion that the Miwok had arrived in the Diablo and Delta area before A.D. 1, displacing the earlier Hokan-speaking people that lived in the region (Wiberg 2010).

The Bay Miwok were hunter-gatherers, taking advantage of the abundant natural resources in the Delta and alluvial plains (Levy 1978). This lush environment was able to sustain a relatively dense population despite the lack of agriculture. The Delta marshland was very productive as were the Central Valley grasslands. Less productive portions of the regions included the uplands, which were able to support a mixture of oak and conifer trees (Wiberg 2010).

Like many other California groups, acorns were a staple carbohydrate of Bay Miwok foodways. In addition to this, however, a variety of flora and fauna were available for foraging and hunting. These included "several types of berries, clover, wild onions, and carrots, mammals, fish, reptiles, shellfish, and insects" (Wiberg 2011: 14). Vegetal resources also provided the material for cordage and weaving baskets. Baskets were used for cooking, as utensils, storage containers, water jugs, and as trays for leaching and drying acorn meal (Kroeber 1925:467).

Importantly, the Bay Miwok were not passively acquiring their subsistence from the environment. They were, in fact, very active in managing and improving their environment through fire. By burning grass and brush annually, they were able to be in better control of their natural resources. Their foraging for deer and rabbits was improved by eliminating much of the area in which they would hide. Periodic burning also kept them safe from predators and neighbors and improved the land's productivity (Wiberg 2010).

The Bay Miwok were organized into "tribelets," which were, "small independent group[s] of usually related intermarried families occupying a specific territory and speaking the same language or dialect" (Wiberg 2010: 22). Notably, a great diversity of languages was present in contact-period California, with some dialects only spoken by very small groups. These groups were not isolated; however, as trade and marriage enabled tribelets to access resources they otherwise would not have accessed. Other aspects of social life that would bring people together include regional festivals and religious dances. The division of labor within California tribelets usually distinguished between women's work in food harvesting, preparation, weaving, and childrearing, and men's work in hunting, fishing, trade, warfare, and the training of older sons.

When the Spanish arrived, trade patterns that were thousands of years old were in place. Archaeological evidence suggests that these trade patterns brought goods from as far as a few hundred miles away based on the sourcing of obsidian artifacts. Mollusk shell beads and ornaments, "evolved through many different and definable types through the millennia," which allows archaeologists to both estimate a relative date for a site and the social and cultural position of the people who once lived there (Wiberg 2011: 15).

The territory of the Saklan was, "the interior valleys from Lafayette to Walnut Creek and Danville" (Cook 1957: 147). Although the central village may have been near modern Walnut Creek, "at least two smaller, subsidiary Saklan settlements were known to exist" at the time of Spanish colonization (Fredrickson 1968). The location of these settlements is currently unknown. Although Spanish observations suggest that total Saklan population in the early nineteenth century was between 100–300 people (Fredrickson 1968), this number may have been much higher. Based on the group's absorption of 40 people lost to missionization between 1794–1798, as well as the conversion of others and attrition due to disease and food supply inconsistencies, Cook (1957: 143, 147) suggests that the preconquest population must have reached, "at least 300 and very likely was much greater."

More comprehensive ethnographic and archaeological summaries of the Saklan and their neighbors in what is today Contra Costa County may be found in *The Handbook of North American Indians*, *Volume 8: California* (Levy 1978:398-413), *Handbook of California Indians* (Kroeber 1925: 442-461), and *California Archaeology* (Moratto 1984).

#### **Historic Overview**

The history of northern California, Solano County, and the Proposed API/APE, in particular, can be divided into several periods of influence to establish a historic context to assess the potential significance of historic sites in the Proposed API/APE. Due to its location 40 mi (65 kilometers) east/northeast of San Francisco, the Proposed API/APE was largely isolated from the Spanish and Mexican periods of California. Therefore, events associated with the Spanish and Mexican periods, and cultural remains from those periods, are not expected to be reflected in the Proposed API/APE but are discussed briefly as a point of reference.

# Spanish Era (1769–1821)

The earliest historical accounts of the area come from the Spanish explorers who ventured into the area east of the Bay Area in the late eighteenth century. In 1775, when Captain Juan Manuel Ayala's expedition explored the San Francisco Bay, some of his men may have ventured up the Sacramento and San Joaquin rivers during three explorations of the Bay that yielded the first accurate maps of San Francisco Bay (Kamiya 2014). In 1776, the Anza-Font expedition traveled along the southern shore of Suisun Bay until reaching Antioch, where they noticed numerous

campsites before turning southeast in an attempt to cross the tule swamps (Cook 1957). There is no evidence that the Spanish explored north of the river at the site of the Project during this period, but they must have passed within a few miles of it on the southern side of the river (Farris et al. 1988). There are no documented Spanish settlements or structures in the Project area.

At the time of the Spanish arrival, Solano County was home to the Patwin Indians. Some of their village places have survived phonetically in such modern places as Suisun, Soscol, Ulatis, and Putah (Solano County 2023).

### Mexican Era (1822-1848)

Under the Spanish, the missions controlled the land. After Mexico seceded from Spain in 1821, land was granted to private citizens, a practice that increased significantly after the 1833 act of the Mexican legislature that established the secularization of the missions (JAH 2005). By 1845, the last of the mission land holdings were relinquished, opening the way for the large ranchos common to California in the mid-1800s. Predominant land use on the ranchos was the raising of livestock and ranching. The Proposed API/APE straddles two Mexican-era land grants, or ranchos, within Solano County and Contra Costa County.

The northern of these was the Rancho Ulpinos. It included 17,726 acres in southern Solano County, including what would become the cities of Collinsville, Rio Vista, Newtown, Birds Landing, and Montezuma. This Rancho includes two watercourses: the Sacramento River and the Estero Ulpinos. This Rancho was given to John Bidwell in 1852 by Governor Manuel Micheltorena (Perez 1982; U.S. District Court [USDC] 1857).

The 1848 Treaty of Guadalupe Hidalgo that ceded California to the U. S. provided that the land grants would be honored. As required by the Land Act of 1851, a claim for Rancho Los Ulpinos was filed with the Public Land Commission in 1852 and the grant was patented to John Bidwell in 1866 (USDC 1857).

The other rancho in the Proposed API/APE of the Project is the Rancho Los Medanos, immediately south of the Rancho Los Ulpinos. It is composed of 8,853 acres, including the watercourses of the San Joaquin River and the Suisan Bay, and covers the modern-day cities of Pittsburg and Antioch (Perez 1982).

The ranch was granted in 1835 to Jose Antonio Mesa and Jose Miquel Garcia. Mesa and Garcia sold the southern half of their rancho to Colonel Jonathan D. Stevenson in 1849 and the northern half to James Walsh, Michael Murray, and Ellen Fallon in 1850. There was confusion about the orientation of the grant, and in 1851, Stevenson arranged an exchange of deeds, whereby he received the western half of the rancho and Walsh, Murray, and Fallon received the eastern half (Supreme Court of California 1904).

As required by the Land Act of 1851, a claim for Rancho Los Medanos was filed with the Public Land Commission in 1852, and the grant was patented to Jonathan D. Stevenson and others by 1862 (Hoffman 1862). There are no documented Mexican structures associated with these rancheros documented in or near the Project area.

# Historical Era (1848-present)

Prior to the 20<sup>th</sup> century, the history of both Contra Costa and Solano Counties was overwhelmingly ranching and farming in character (EDAW 2008). During Mexican occupation, and for some years after that, cattle raising was the principal industry (EDAW 2008).

In the late 1840s and 1850s, former gold seekers and pioneers began settling Contra Costa and Solano counties, where they raised livestock and cultivated fruit orchards, vineyards, wheat, barley, and oats (EDAW 2008). Produce and livestock were transported overland by wagons to the many sloughs along the river, and then shipped by water to waiting markets. In the late 19th century, the development of the railroads spurred the economy by allowing the shipment of local goods to East Coast markets, significantly bolstering economic development, agricultural production, and population growth (EDAW 2008)

Twelve townships were established in Solano County between 1850 and 1871. Although the largest towns were adjacent to San Pablo and Suisun Bays, most towns were situated at the ends of sloughs or channels that primarily ran through the eastern portion of the county including the small town that became Collinsville. These earliest communities in Contra Costa Counties, such as Antioch, Pittsburg, and Walnut Creek, have grown into thriving cities and towns (McCullough 2022).

#### **History of Pittsburg**

Its earliest recorded history of the Pittsburg area dates to 1839 when the Mexican government granted nearly 9,000 acres of the Rancho Los Medanos to brothers Jose Antonio Mesa and Miguel Jose Mesa Garcia. In 1849 the land was purchased by Col. Jonathon Drake Stevenson and Dr. William C. Parker. The first streets were laid out by future U.S. Army Gen. William Tecumseh Sherman (City of Pittsburg 2022).

The area soon became known as New York Landing, and by 1855 was a fishing village of approximately 500 residents. By the 1870s the community thrived on fishing and canning industries, which would last for over 100 years.

Coal was discovered in the Mt. Diablo foothills of Contra Costa County and became one of the biggest industries in the county from the 1860s until the early 1900s (McCullough 2022). With the discovery of coal, the town of New York Landing became known as Black Diamond and shown on local maps for the first time in 1868 due to the influence of the Black Diamond Coal Company. Steam powered engines moved coal cars down the tracks along present day Railroad Avenue to the waterfront docks terminating at the waterfront coaling station and offloaded to awaiting ships on the way to market. The boom ended in 1885, and the company moved to Washington state to work a new claim (City of Pittsburg 2022)

During the 1870s, commercial fishing became a lucrative endeavor. The Black Diamond Cannery opened at the foot of Los Medanos St. By 1882, a network of 10 canneries formed along the Sacramento Delta. An industry was born with fishermen, packing plants, boat builders and the like dominating the local waterfront for the next 80 years. The town boasted the largest Delta fishing community in the state, made up primarily of Sicilian immigrants, the families of which have remained in the area for generations (City of Pittsburg 2022).

Charles Appleton Hooper, who became the local father of industry, was a wealthy lumber baron who purchased the Rancho Medanos land grant in `1900. He encouraged the city government to supply electricity to the town and in 1903 the town incorporated as Black Diamond. A rubber works and a steel company were started along with a large foundry. Pittsburgh industry and manufacturing created thousands of living wage jobs. In 1911, the city changed its name to Pittsburg because of the newly founded steel industry (City of Pittsburg 2022).

In 1942 Camp Stoneman was built as the main point of embarkation on the west coast during WWII. It closed in 1954 and its property became the city of Pittsburg's and was used for a school, commercial and residential development (Pittsburg Historical Museum 2024).

#### **History of Collinsville**

Early in 1846, Lansford W. Hastings acting as an agent responsible for finding a site for a Mormon colony chose an area in today's southeastern Solano County on the Sacramento River near present day Collinsville (Kyle 1990), The Mormon movement to California was part of a general exodus from the East and Midwest. The Mormons had been forced to leave their homes in Illinois and headed some place "beyond the Rocky Mountains". At the same time, those members of the Church in the eastern states were directed to proceed by ship to a spot on the Pacific Coast (Baldridge 1956).

In 1846, 238 Mormon immigrants landed in San Francisco on a ship from New York as an initial attempt to establish a Mormon colony in Northern California (McPhate 2019). Within a year, they built 100 permanent structures in San Francisco, including the first bank, library, and English-speaking school. The group's leader, Sam Brannan, started the city's first newspaper, the California Star, and became its first millionaire. Other Mormons founded towns, pioneered farming, and became among the first gold miners (McPhate 2019). It was around this time that Hastings built a four-room adobe in anticipation of a large land grant from the Mexican government to accommodate the Mormon arrivals (Bowen 2000),

The event known as the Bear Flag Revolt changed Hastings plans. In June 1846, 33 American immigrants rebelled against the Mexican government in the town of Sonoma because that they had not been allowed to buy or rent land and had been threatened with expulsion. This short-lived rebellion added to the tension of the recent outbreak of the Mexican-American War (NPS 2022). In the wake of these hostilities, Hastings abandoned the adobe house, which remained unoccupied until 1852. After that a series of owners lived in it until PG&E bought the land in 1964. The old, abandoned adobe still stands, but is rapidly deteriorating because of a lack of maintenance and a badly leaking roof (Bowen 2000).

The first permanent settler in Montezuma Township, as Collinsville was then called, was L.P. Marshall. He moved into the Hastings adobe, named it the "Montezuma House," and lived there for the next quarter of a century (Bowen 2000). In 1859, Mr. C.J. Collins settled on government land where Collinsville now stands. He surveyed the town plat and built a wharf and store (Bowen 2000).

By 1861, the Collinsville wharf was built, and the town applied for an official post office, allowing for better business and trade in the area (Supreme Court of California 1882). In 1861, George W. Miller was appointed the first postmaster. Collinsville soon became an important shipping port for hides and tallow (Bowen 2000).

The small fishing village was approved for a steam ferry in 1868 to travel between Collinsville, New York Landing, and Antioch. It soon became a major ferry stop for hides and tallow crossing the Carquinez Strait while traveling to the cities farther south. In 1867, the town was purchased by S. C. Bradshaw, who renamed the town Newport and began selling some 29,000 lots, many of which were submerged at high tide. His scam failed, and the sheriff seized the town. The land was later sold to E. I. Upham who returned the name Collinsville to the town in 1872 (Bowen 2000).

At one point, before the bridges were built, one of the passenger railroad lines between Sacramento and San Francisco passed through Collinsville. The train would unbuckle at Collinsville and be pulled across the Delta by barge (requiring several trips), and then be rebuckled on the other side at the foot of Railroad Avenue in Pittsburg and resumed its trip to San Francisco.

By the 1870s, Collinsville had a large salmon cannery and hotels and stores that serviced its workers. F. E. Booth built the salmon cannery in 1873 and employed many Italian fishermen, who lived on stilted houses in the marsh areas, an area dubbed "Little Venice" (Kyle 1990). When the cannery closed, Collinsville began declining; the population fell to just eight people and some 20

homes. Although the population has increased slightly since then, a fire in 2014 destroyed half of the town.

#### **History of Railroads**

In the late 1840s and 1850s, produce and livestock were transported overland by wagons to the many sloughs throughout the county, and then shipped by water to waiting markets. In 1868, with the completion of the California Pacific Railroad through Solano County, the shipment of goods to East Coast markets was accelerated and expanded (EDAW 2008)

In 1913, the Oakland, Antioch, and Eastern Railway, a high-speed electric interurban railway, opened its 93-mi route from San Francisco to Sacramento through largely unpopulated parts of southern Solano County (Boehle 2013). In 1928, the Sacramento Northern Railway purchased the railway, but the Depression and the popularity of the automobile contributed to the end of passenger service in 1940; by 1987, the railway had been abandoned (EDAW 2008).

The coming of the railroads in the latter part of the 1800s and the early 1900s to Contra Costa County made the industrial development that was occurring in Pittsburg even more attractive (McCullough 2022). The Central Pacific Railroad (CP) was chartered in 1862 by Congress to build a railroad eastward from Sacramento to complete the western part of the first Transcontinental Railroad in North America. The CP was the first transcontinental railroad to pass through present-day Pittsburg when the tracks were built in 1878 (Pittsburg Historical Museum 2024).

The Cornwall railroad station served passengers as well as freight. Cornwall was a small enclave separate from the village of Black Diamond but would eventually be annexed into Pittsburg in 1911. Black Diamond was a commercial fishing port situated on the Suisun Bay and the railroad made possible rail shipping of fish which up to that point had been shipped to market (Pittsburg Historical Museum 2024).

The Black Diamond Railroad (BD) was active at this time which was a short rail line shuttling coal from the local mines in the foothills to the waterfront Black Diamond coaling station. Where the CP crossed the BD railroad a train trestle and large earthen embankment was built to span the CP line and allow for uninterrupted service by both railroad lines (Pittsburg Historical Museum 2024).

In 1888 the Southern Pacific (SP) bought out the CP. In turn the Union Pacific (UP) merged with the SP in 1996 assuming the Union Pacific name. Today, manufactured goods from local and area industry are what can be seen along the local rails and switchyards. The UP mainline is known as the Mococo Line and is under the UP Tracy Subdivision of their railroad network (Pittsburg Historical Museum 2024).

#### History of the Transmission Lines.

The Pacific Gas & Electric (PG&E) Company was formed in 1905 by the merger of the San Francisco Gas Company and the California Electric Company. The need for transmission lines in northern California began during the 1920s, when the demand for electricity grew in relationship to commercial and residential development. Towers that predate World War II still exist in the major cross-tie electrical grids linking various power plants and substations. These early major electrical transmission lines remain critical to providing a reliable form of electrical power to much of California. The post-World War II period of electrical transmission generation and development was spurred on by rapid population growth and increasing demand from commercial and residential customers (Coleman 1952).

PG&E's 230kV Pittsburg-Tesla transmission were not the first electrical high-lead tie line built in the state nor in Contra Costa County or the East Bay Area, which witnessed electrical transmission tower development dating to the 1920s (Supernowicz 2017). PG&E's 230kV Pittsburg-Tesla transmission line that runs a distance of approximately 31 miles from City of Pittsburg through unincorporated portions of Contra Costa and Alameda counties was constructed as part of this expansion. The Pittsburg-Tesla line (running from the Pittsburg substation to the Tesla substation) was constructed in 1959-1960 and consists of 147 towers. It is considered by PG&E as a critical supply line for Contra Costa and Alameda counties (Lang 2008). The transmission towers of the 1960s were made of steel, riveted together with lattice and bents for support. They had not changed much since the 1920s. Most of the existing steel high-lead electrical transmission towers in California date to after World War II. Transmission lines were attached to the top of the tower along a slightly arched or V-shaped riveted steel lattice brace. In an electrical power grid or transmission system, the electricity first went to a transformer at the power plant that boosted the voltage. The long thick cables of transmission lines were made of copper or aluminum because they have a low resistance (Supernowicz 2017).

# Research Design

The following research themes identify important questions that may be addressed by the types of resources and data the Proposed API/APE has the potential to contain. The research themes discussed below cannot be addressed using data from other sources, such as archival records, but can only be addressed using the archaeological record (although in conjunction with the documentary record). Research themes outline the questions that can be asked of the archaeological record and the types of data required to answer them. The purpose of identifying relevant research themes here is to guide the evaluation of archaeological discoveries. If archaeological remains are encountered during Project ground disturbance, determining their ability to address the following research themes is critical to evaluating the significance of the deposits.

Research-driven archaeological investigation typically focuses on broad research themes of local relevance. Themes must be broadly defined since the nature of the specific data used to address them is generally not known in advance, and it is, therefore, not possible or practical to address all questions that may be relevant. This will ensure that fewer restrictions will be placed on interpreting data recovered from a site. These broad thematic questions concern such issues as chronology, subsistence, settlement, and trade or exchange. Precontact research themes are summarized in Table 4-1, and historical research themes in Table 4-2.

## **Precontact Research Themes**

Although no Precontact archaeological deposits have been discovered in the Proposed API/APE, P-48-000041 is a multicomponent site that includes the Hasting's adobe. It is near the Proposed API/APE and the Precontact component was observed on a small knoll near the adobe. The site appears to have been a small campsite (Elsasser 1956), Unfortunately, this Precontact deposit was never investigated so no data has been collected from it.

Table 4-1. Native American Research Questions and Data Requirement

**Culture Chronology** 

Potential Research Questions	1.	How can the materials present be used to refine the cultural chronology of the San Jose area?
	2.	What archaeological cross-dating determinations can be made using diagnostic artifacts independent of other chronometric evidence?
	3.	Can radiometrically datable materials be used to place stylistically temporally diagnostic artifacts into particular periods or phases?
Data Requirements	Temporally	diagnostic artifacts associated with datable materials.
	Features ar	nd stratified deposits with datable materials.
Subsistence		
Potential Research Questions	1.	What are the subsistence patterns represented by the archaeological deposits (e.g., terrestrial versus aquatic resources)?
	2.	Can changes in diet be observed in floral, faunal, and human remains? What do these reflect in terms of resource intensification and depression?
Data Requirements		gical resources with functionally and temporally diagnostic artifacts and features, including aunal remains.
Settlement		
Potential Research Questions	1.	What is the nature of the evidence for seasonal or permanent or semi-permanent residential features that would suggest villages (e.g., structures, storage features, midden deposits, etc.)?
	2.	What items represent settlement practices? Are changes in the settlement practices observable in the archaeological record?
	3.	What resources were locally available for exploitation? Was the area suitable for long term habitation or short-term resource exploitation use?
Data Requirements	_	gical resources with functionally and chronologically diagnostic artifacts and features, oral and faunal remains.
Trade and Exchar	nge	
Potential Research Questions	1.	Are exotic raw materials, especially obsidian, tools/items, or trade goods represented in the archaeological resource? What is the origin of these items?
Data Requirements	_	jical resources with functionally and chronologically diagnostic artifacts and features, ersonal, ceremonial, and trade items.

## **Historic Period Research Themes**

Buried and surface historic archaeological deposits have been recorded in the Proposed API/APE. These include included six previously recorded sites: P-07-002956 (two 230 kV PG&E transmission lines that are part of the Pittsburg-Tesla Transmission Line). P-48-000981 (three historical roads established in 1891, i.e., Grizzly Island Road, Collinsville Road, and Chadbourne Road), and four farmstead sites (P-48-000124, a barn with a small orchard, domestic and structural refuse, a possible well, and agricultural equipment; P-48-000125 (CA-SOL-284H), remains of a water conveyance system consisting of a covered well hole and a water pipe; P-48-000128 (CA-SOL-287H), a possible homesite; and P-48-000140, a possible homesite location with pepper trees. In addition to these, another five historic sites were recorded in the 0.5 mi buffer around the Proposed API/APE. These include a rail line of the Sacramento Northern Railway (P-07-000489),

three homesite/ranch sites ( $P-48-000139\ [CA-SOL-298H]$ ,  $P-48-000416\ [CA-SOL-299H]$ , and P-48-000521, and the Hasting's adobe (P-48-000041).

Table 4-2. Historic Research Questions and Data Requirements

Consumer Goods						
Potential Research Questions	Did the quality of goods and supplies flowing into the Collinsville area from the U.S. and abroad change over time as the area became a more established part of California, or did they decline as more local industries were developed to serve these needs?					
Data Requirements	Archaeological concentrations from discrete contexts (hollow-filled features and sheet refuse) representing a sufficient quantity and variety of artifacts are needed. Features should contain well-stratified temporally diagnostic deposits to assist researchers in documenting and understanding change over time. Features should retain integrity and have identifiable associations.					
Cultural Pluralism	and Ethic Adaptation					
Potential Research Questions	To what extent were households of different ethnic backgrounds present? What aspects of traditional behavior were retained and why?					
	2. Does this resource possess material remains that could elucidate economic distinctions between the material culture of members of distinct ethnic and subcultural groups?					
Data Requirements	The presence of features or artifacts that can be identified with specific ethic groups (e.g., faunal or ceramic materials associated with particular cuisines, items manufactured in and imported from overseas, or items of personal adornment historically used by specific groups).					
Ranching, Farmin	g, and Industry					
Potential Research Questions	Does the archaeological record contribute evidence of any ranching, farming, or other local industrial use?					
	2. What types of water management were used in ranching? Where wells dug or was the river used as a source of water for, irrigation? Did ranchers and farmers rely on rainwater? Is there evidence livestock raising or crop agriculture required different water management?					
	3. Is there any discernible relationship of local businesses, ranches, or farms to the railroads and transmission lines present in the Project area?					
	4. Can roads be associated with ranching or rise of other industries in the area?					
	5. Are artifacts present that can be used to associate household members with ranching or other local industries?					
Data Requirements	Dateable and identifiable structures or features designed for ranching or other commercial use.  Artifactual waste from ranching or other industry.					

# **Terrestrial Cultural Resource Inventory**

# **Terrestrial Records Search Results**

On May 5, 2023, Chronicle Heritage staff requested a records search of the California Historical Resources Information System (CHRIS) at the Northwest Information Center (NWIC) on the campus of Sonoma State University in Rohnert Park. The NWIC is an affiliate of the State of California

Office of Historic Preservation (OHP) and the official state repository of cultural resource records and reports for Santa Clara County. The records search included the Proposed API/APE and a surrounding 0.5-mi buffer. The records search aims to identify previously recorded cultural resources within and in the vicinity of the data center portion of the Proposed API/APE.

The results from the NWIC, received on June 13, 2023, identified 12 previously recorded cultural resources within the search area (Table 4-1 and Table 4-2). Of the 12 previously recorded resources, one is precontact, ten are historic, and one is multicomponent. Six of the 12 previously recorded resources are within the Proposed API/APE. Of the six resources within the Proposed API/APE, all six are historic. Additionally, one multicomponent site (P-48-000041) is immediately adjacent to the Proposed API/APE. These resources are briefly described below. The historic sites within the Proposed API/APE to the north of the Sacramento River represent the early American settlement period and late nineteenth century agricultural and town development phases that are characteristic of this region (Tremaine 1991:4). The historic site within the Proposed API/APE to the south of the Sacramento River is a transmission line. The results from the NWIC identified 43 previous cultural resource investigations within the search area (Table 4-3 and Table 4-4). Of the 43 previous investigations, 27 have surveyed all or portions of the Proposed API/APE. Within the last 10 years, only one previous investigation (S-049865) has surveyed portions of the Proposed API/APE, resulting in 180.7 acres (8.3%) of recent survey coverage.

#### **Cultural Resources**

The records search determined that the following previously recorded cultural resources are within or immediately adjacent to the Proposed API/APE:

#### P-07-002956

P-07-002956, is the Contra Costa-Moraga/ Pittsburg-Tesla Transmission Line which consists of two 230 kV Pacific Gas & Electric transmission lines that traverse Contra Costa County from east to west. The line begins in Antioch, leaving the substation as two parallel transmission lines, before it separates southeast of Pittsburg into two lines of towers. The southernmost line is commonly referred to as the "Contra Costa-Moraga" electrical transmission line that connects the power plant at Antioch with the substation in Moraga, a distance of 27 miles. The line begins in Antioch as two parallel transmission lines and then splits in Section 29, southeast of Pittsburgh, with one line trending north, forming part of the Pittsburgh-Tesla transmission line, while the southern-most line heads southwest towards Moraga. The southern line appears to be oldest, perhaps built in the late-1920s, while the northern line, still relatively early, appears to have been built prior to 1943. Both lines include riveted steel towers with three horizontal arms or masts mounted to the upper half of the towers. The subject rectangular, truncated-shaped, lattice transmission tower rests on four concrete piers. A form of "X" bracing with radiating steel lattice braces is used on opposing sides of the tower for support. The three steel arms, also containing lattice bracing, connect to twisted or elongated insulators attached to high lead cables that transmit electricity from tower to tower. The towers are mounted on concrete piers. The line of towers cut through a large swath of light-agricultural, open-space land (Supernowicz 2017). The Pittsburg-Tesla 230 kilovolt (kV) transmission line (Pittsburg-Tesla line) spans the area between the Pittsburg Substation, in the City of Pittsburg, and Tesla Substation, in northern Alameda County. PG&E owns and operates the existing line. The line runs a distance of approximately 31 miles (24 miles in Contra Costa County) (Supernowicz 2017).

Dana Supernowicz of Historic Resources Associates assessed the transmission lines for NRHP eligibility in 2017 (Supernowicz 2017). Based on two NRHP criteria (A [their relationship to the development of PG&E and the state electrical grid] and C [the towers appear to have been a design innovation at the time of construction]) the transmission lines were recommended as significant both individually and as part of a linear district comprised of multiple steel transmission towers and electrical lines tied to substations and power generating plants (Supernowicz 2017). The transmission lines appear to retain good integrity of design, materials, setting, association, and feeling, having minimal or no apparent major alterations, with the exception of upgrades to the lines and insulators. Conversely, hundreds of similar transmission towers were built throughout California. The power lines were not the first electrical high-lead tie line built in the state nor in Contra Costa County or the East Bay Area, which witnessed electrical transmission tower development dating to the 1920s. The post-World War II period of electrical transmission generation and development was spurred on by rapid population growth and increasing demand from commercial and residential customers.

#### P-48-000041

P-48-000041 is a multicomponent site consisting of a precontact campsite and the Hastings Adobe. The Hastings Adobe was initially constructed in 1846 by Lansford W. Hastings, a representative of the Mormon Church, who was tasked with establishing a Mormon settlement on the West Coast. The building was initially constructed with sun-dried bricks made from native clay adobe and consisted of four rooms and an attic. Hastings abandoned the adobe shortly after the United States claimed the land, and the Mormon community lost interest in the settlement. In 1853, the adobe was unofficially claimed by L. P. Marshall and his two sons, who made repairs to the adobe by adding a wooden frame around the entirety of the structure. The Marshalls occupied the structure until 1908, when the S. O. Stratton family purchased it. Further repairs and maintenance were done to the structure by the Strattons until it was ultimately purchased by PG&E in 1963 (Young 1971). Mr. Stratton noted an adjacent precontact campsite where he, "used to pick up arrow points" (Elsasser 1956). However, by 1956, A. B. Young noted that the campsite had been covered by sterile sandy soil and had been disturbed by modern agricultural processes (Young 1971). The Hastings Adobe was evaluated for eligibility in 1971 and was nominated to the NRHP in 1972. The Hastings Adobe is approximately 145 ft outside of the Proposed API/APE.

#### P-48-000124

P-48-000124 consists of a barn, the remains of a water tower, three depressions (of which two may be privies and one a possible cellar), and a eucalyptus windbreak. Furthermore, "local informants indicated that a two-story house once stood over the largest of the depressions" (Crist et al. 1980). Associated materials include brick, ceramic, metal, and glass debris scattered throughout the site boundary, with denser concentrations near the pepper tree. This site appears to be frequented by grazing goats. This site has not been previously evaluated for NRHP/CRHR eligibility.

#### P-48-000125

P-48-000125 is a historic artifact scatter first recorded in 1980 by C. Peeler Crist and updated in 2010 by Far Western. The original site record described it as a scatter of ceramics, glass, brick, construction materials, and a possible septic tank. A site revisit conducted in 2010 did not locate the artifacts nor the septic tank but did identify a pipe and wood-covered hole, previously described. Disturbances noted in the 2010 revisit included overgrown vegetation, animal grazing,

and modern use of the area, reflected by the construction of a cement water well and pump. This site has not been previously evaluated for NRHP/CRHR eligibility.

#### P-48-000128

P-48-000128 is a historic homestead first recorded in 1980 by Maniery et al. based on ethnographic accounts. Archaeological evidence of the homestead consisted of three ceramic fragments, square nails, and burned wooden boards. The site was revisited by Adrian Whitaker in 2010, and no elements of the site were located. Disturbances consisted of recent soil disking associated with mechanical agricultural land management practices. This site has not been previously evaluated for NRHP/CRHR eligibility.

#### P-48-000140

P-48-000140 was initially recorded in 1980 as a homesite with several features, including a possible well, a pit area with wooden structural remains, and historic artifacts. The site was revisited by Far Western in 2010, and only the pepper trees documented in 1980 were able to be located. The 2010 revisit indicated that bulldozers and other excavation activities had heavily modified the site's surface to create a recreational off-road motorcycle course. This site has not been previously evaluated for NRHP/CRHR eligibility.

#### P-48-000981

P-48-000981 includes Grizzly Island Road, Collinsville Road, and Chadbourne Road. A portion of Collinsville Road passes through the western edge of the Proposed API/APE. The collection of roads supported the transportation of goods to permanent populations in the marshlands, made possible by reclamation projects during the early twentieth century. Collinsville Road is a regularly maintained county road. A 2013 evaluation by Cheryl Brookshear recommended that P-48-000981 was not eligible for inclusion in the NRHP, CRHR, or for local designation.

Table 4-1. Previously Recorded Cultural Resources within the Proposed API/APE

Site No.	Resource Name	Age	Description	Company/Agency	Year
P-07-002956	Pittsburg-Tesla Transmission Line	Historic	Two 230 kV PG&E transmission lines	Garcia & Associates Historic Research Associates	2008
				Historic Research Associates	2017
P-48-000124	1H	Historic	A barn with a small orchard, domestic and	M. Crist, J. Brady, R. Goode	1980
			structural refuse, possible well, and agricultural equipment.	Far Western Anthropological Research Group	2010
P-48-000125	CA-SOL-284H	Historic	Remains of water	M. Crist, C. Peeler	1980
			conveyance system consisting of a covered well hole and a water pipe	Far Western Anthropological Research Group	2010

Site No.	Resource Name	Age	Description	Company/Agency	Year
P-48-000128	CA-SOL-287H	Historic	Possible homesite, no artifactual evidence	G. Maniery, J. Brady, R. Goode	1980
			remains.	Far Western Anthropological Research Group	2010
P-48-000140	#65H	Historic	Possible homesite location with pepper	G. Maniery, K. Gebhardt, R. Ambro,	1980
			trees.	Far Western Anthropological Research Group	2010
P-48-000981	Grizzly Island Road, Collinsville Road, Chadbourne Road	Historic	Historical roads established in 1891.	JRP Historical Consulting	2013

Table 4-2. Previously Recorded Cultural Resources in the 0.5-mi Buffer

Site No.	Resource Name	Age	Description	Company/Agency	Year
P-07- 000489	Sacramento Northern	Historic	Historic railroad from Chico, CA to Oakland,	Woodward-Clyde Consultants	1994
	Railway		CA as well as a raised embankment for the Oakland, Antioch, &	Tremaine & Associates, Inc.	2010
			Eastern Railway.	Environmental Science Associates	2019
P-48-	Hastings	Multicomponent	Historic Hastings	A.B. Elsasser	1956
000041	Adobe		Adobe structure and nearby precontact temporary habitation site.	Solano County Historical Society	1972
P-48- 000139	CA-SOL- 298H	Historic	Historic domestic refuse scatter and	K. Gebhardt, C. Peeler, G. Maniery,	1980
			several pepper trees.	Far Western Anthropological Research Group	2010
P-48- 000416	CA-SOL- 299H	Historic	Possible homesite with a cellar hole, three depressions and a scattering of bricks.	M. Crist, R. Ambro, C. Peeler,	1980
P-48- 000521	HW-C1	Historic	Historical ranch complex with a structure, two barns, and a coral.	Jones & Stokes Associates	2001

Site No.	Resource Name	Age	Description	Company/Agency	Year
P-48- 000949	CW-1 Handstone Isolate	Precontact	Isolated handstone.	Far Western Anthropological Research Group	2010

 ${\bf Table~4-3.~Previous~Cultural~Resource~Investigations~within~the~Proposed~API/APE}$ 

Report No.	Authors	Year	Title	Company/Agency
S-000595	R.F. King	1974	A Report on the Status of Generally Available Data Regarding Archaeological, Ethnographic, and Historical Resources Within a Five Mile Wide Corridor Through Portions of Colusa, Yolo, Solano, and Contra Costa Counties, California	-
S-000848	David A. Fredrickson	1976	A Summary of Knowledge of the Central and Northern California Coastal Zone and Offshore Areas, Vol. III, Socioeconomic Conditions, Chapter 7: Historical & Archaeological Resources	The Anthropology Laboratory, Sonoma State College; Winzler & Kelly Consulting Engineers
S-001784	David Chavez	1979	Preliminary Cultural Resources Identification: San Francisco Bay Study for Corps of Engineers Projects	-
S-001978	Anthony V. Aiello	1960	The Islands of Contra Costa	-
S-002458	Neil Ramiller, Suzanne Ramiller, Roger Werner, and Suzanne Stewart	1981	Overview of Prehistoric Archaeology for the Northwest Region, California Archaeological Sites Survey: Del Norte, Humboldt, Mendocino, Lake, Sonoma, Napa, Marin, Contra Costa, Alameda	Northwest Regional Office, California Archaeological Sites Survey, Anthropological Studies Center, Sonoma State University
S-002458	Suzanne Ramiller	1982	Prehistoric Archaeology Overview Northwest Region; California Archaeological Inventory, Volume I: Humboldt and Del Norte Counties	Anthropological Studies Center, Sonoma State University
S-002458	Roger H. Werner	1982	Archaeological Overview of Mendocino and Lake Counties	Anthropological Studies Center, Sonoma State University
S-002458	Suzanne Stewart	1982	Prehistoric Archaeology Overview Northwest Region; California Archaeological Inventory, Volume 3: Napa and Sonoma Counties	Anthropological Studies Center, Sonoma State University
S-002458	Suzanne Stewart	1982	Archaeological Overview of Alameda, Contra Costa, and Marin Counties	Anthropological Studies Center, Sonoma State University

Report No.	Authors	Year	Title	Company/Agency
S-002458	Neil Ramiller	1982	Environmental Overview of the Northwest Region	Anthropological Studies Center, Sonoma State University
S-005208	Gregory Greenway and William E. Soule	1977	Sacramento-San Joaquin Delta Investigations: Cultural Resources Reconnaissance	-
S-009462	Teresa Ann Miller	1977	Identification and Recording of Prehistoric Petroglyphs in Marin and Related Bay Area Counties	San Francisco State University
S-009583	David W. Mayfield	1978	Ecology of the Pre-Spanish San Francisco Bay Area	San Francisco State University
S-009795	Thomas Lynn Jackson	1986	Late Prehistoric Obsidian Exchange in Central California	Stanford University
S-011766	Miley Paul Holman	1989	Archaeological Literature Review and Field Inspection of Areas 1 through 9, Montezuma Hills, Solano County, California (letter report)	Holman & Associates
S-011826	Dorothea J. Theodoratus, Mary Pyle Peters, Clinton M. Blount, Pamela J. McGuire, Richard D. Ambro, Michael Crist, Billy J. Peck, and Myrna Saxe	1980	Montezuma I and II Cultural Resources	Theodoratus Cultural Research; Archaeological and Environmental Services
S-012790	Kenneth N. Owens	1991	Sacramento-San Joaquin Delta, California: Historical Resources Overview	Public History Research Institute, California State University, Sacramento
S-013263	Kim J. Tremaine	1991	An Archaeological Inspection of the Proposed Collinsville Wind Turbine Generation Site and Transmission Line, Solano County, California	BioSystems Analysis, Inc.
S-015529	Robert L. Gearhart II, Clell L. Bond, Steven D. Hoyt, James H. Cleland, James Anderson, Pandora Snethcamp, Gary Wesson, Jack Neville, Kim	1993	California, Oregon, and Washington: Archaeological Resource Study	Espey, Huston & Associates, Inc.; Dames & Moore

Report No.	Authors	Year	Title	Company/Agency
	Marcus, Andrew York, and Jerry Wilson			
S-016660	Jeffrey B. Fentress	1992	Prehistoric Rock Art of Alameda and Contra Costa Counties, California	California State University, Hayward
S-017835	Judy Myers Suchey	1975	Biological Distance of Prehistoric Central California Populations Derived from Non-Metric Traits of the Cranium	University of California, Riverside
S-018217	Glenn Gmoser	1996	Cultural Resource Evaluations for the Caltrans District 04 Phase 2 Seismic Retrofit Program, Status Report	California Department of Transportation
S-020395	Donna L. Gillette	1998	PCNs of the Coast Ranges of California: Religious Expression or the Result of Quarrying?	California State University, Hayward
S-024015	Shahira Ashkar	2001	Cultural Resource Inventory Report for the Montezuma Enhancement Site, Southern Energy's Multispecies Habitat Conservation Plan for Pittsburg and Contra Costa Power Plants, Solano and Contra Costa Counties, California	Jones & Stokes
S-030204	Donna L. Gillette	2003	The Distribution and Antiquity of the California Pecked Curvilinear Nucleated (PCN) Rock Art Tradition.	University of California, Berkeley
S-032596	Randall Milliken, Jerome King, and Patricia Mikkelsen	2006	The Central California Ethnographic Community Distribution Model, Version 2.0, with Special Attention to the San Francisco Bay Area, Cultural Resources Inventory of Caltrans District 4 Rural Conventional Highways	Consulting in the Past; Far Western Anthropological Research Group, Inc.
S-033600	Jack Meyer and Jeff Rosenthal	2007	Geoarchaeological Overview of the Nine Bay Area Counties in Caltrans District 4	Far Western Anthropological Research Group, Inc.
S-035796	Barbra Siskin, Cassidy DeBaker, and Jennifer Lang	2009	Cultural Resources Investigation and Architectural Evaluation of the Pittsburg-Tesla Transmission Line, Contra Costa and Alameda Counties, California	Garcia and Associates
S-038991	Adrian R. Whitaker and Philip Kaijankoski	2010	Archaeological Survey and Geoarchaeological Sensitivity Report for the Proposed PG&E, Collinsville Wind Project, Solano County, California	Far Western Anthropological Research Group, Inc.

Report No.	Authors	Year	Title	Company/Agency
S-049780	Brian F. Byrd, Adrian R. Whitaker, Patricia J. Mikkelsen, and Jeffrey S. Rosenthal	2017	San Francisco Bay-Delta Regional Context and Research Design for Native American Archaeological Resources, Caltrans District 4	California Department of Transportation, District 4
S-049780	Julianne Polanco	2016	FHWA_2016_0615_001, Caltrans District 4 Archaeological Context	California Office of Historic Preservation
S-049865	Naomi Scher and Adrian R. Whitaker	2016	Archaeological Survey and Geoarchaeological Sensitivity Report for the Proposed Solano Phase 4 Wind Project, Solano County, California	Far Western Anthropological Research Group, Inc.
S-051501	Lucian Schrader III	2016	Cultural Resources Constraints Report, Pittsburg- Eastshore-San Mateo-Tassajara-San Ramon-Moraga 230 kV Transmission Line ROW Vegetation Management, PM Number: 8099163	Blue Rock Services, Inc

# Table 4-4. Previous Cultural Resource Investigations in 0.5-mi Buffer Around the Proposed API/APE

Report No.	Authors	Year	Title	Company/Agency
S-007647	-	1985	Cultural Resource Investigation of the Proposed Pittsburg Marina Expansion Project.	Woodward-Clyde Consultants
S-009095	-	1985	Historic Resources Testing Program at the Proposed Pittsburg Marina Expansion Project	Woodward-Clyde Consultants
S-010481	Miley Paul Holman	1987	Archaeological Field Inspection of the Montezuma Hills Proposed Wind Farm Area, Solano County, California (letter report)	Holman & Associates
S-016522	-	1993	Archaeological Survey Report, Montezuma Wetlands Project, Solano County, California	Williams Self Associates
S-016522	-	2001	Supplementary Archaeological Survey of the Montezuma Wetlands Project	Williams Self Associates

Report No.	Authors	Year	Title	Company/Agency
S-017893	David Chavez	1995	Archaeological Resources Investigation for the Pittsburg Conveyance System Improvements Project (87.9191), Contra Costa County, California	David Chavez & Associates
S-018352	-	1976	East/Central Contra Costa County Wastewater Management Plan, California: Cultural Resources Survey	Arthur D. Little, Inc.
S-018352	Adam Cvijanovic and Larry Aull	1976	Assessment of Historical and Architectural Resources	American Institute of Architects
S-018352	Colin I. Busby	1976	Assessment of Archaeological Resources: East/Central Contra Costa County Wastewater Management Plan	University of California, Berkeley, Department of Anthropology
S-018440	G. James West and Patrick Welch	1996	Class II Archaeological Survey of the Contra Costa Canal, Contra Costa County, California	U.S. Bureau of Reclamation, Mid-Pacific Region
S-024272	-	2001	Cultural Resources Inventory Report for High Winds, LLC's, Proposed Wind Turbine Project in the Montezuma Hills of Solano County, California	Jones & Stokes
S-024322	Sally Morgan and Bruce Bachand	1998	Pittsburg District Energy Facility, Cultural Resources Technical Report (Supplement to Appendix K)	Woodward-Clyde Consultants
S-024986	-	2000	Cultural Resources Assessment, PG&E Proposed Tri-Valley 2002 Electric Power Capacity Increase Project	Basin Research Associates, Inc.
S-030579	Colin I. Busby	2004	Cultural Resources Report, Delta Energy Center Site (DEC) and Associated Linears, Cities of Pittsburg and Antioch, Contra Costa County, California, California Energy Commission (CEC), Project 98-AFC-3C	Basin Research Associates, Inc.
S-031962	Christopher C. Corey and Nancy E. Sikes	2006	Cultural Resources Survey for the Proposed Van Sickle Island Levee Reinforcement Project, Solano County, California	SWCA Environmental Consultants
S-034161	Miley Paul Holman	2007	Cultural Resources Study of the 8th Street Flood Improvement Project, Pittsburg, Contra Costa County, California (letter report)	Holman & Associates

Report No.	Authors	Year	Title	Company/Agency
S-044229	Allen G. Pastron and Michelle Touton Staley	2013	Phase I Cultural Resources Evaluation for the Pittsburg Forcemain Improvements Project, Contra Costa County, California	Archeo-Tec
S-049478	Eileen Barrow	2017	Cultural Resources Study for the Delta Diablo Pump Station Facilities Repair Project, Project Numbers 17128, 17129, 17130, 17131, and 17132, Contra Costa County, California	Tom Origer & Associates
S-051692	Heather L. MacInnes	2009	Cultural Resources Assessment, Chipps Island Tidal Wetland Restoration Project	Parus Consulting, Inc.

# **Archival Research Results**

Historical maps of the Proposed API/APE were examined to identify the potential for historic period (45 years and older) cultural resources that may be impacted by Project activities.

The earliest maps of the Proposed API/APE come from the General Land Office (GLO) survey maps dating back to 1870 (GLO 1870). An 1870 BLM GLO map shows the southernmost extent of the Proposed API/APE falling within the Mexican Land Grant territory of Rancho Los Medanos. No buildings, structures, or other features that would lie within the Proposed API/APE are depicted on the map. A portion of the Proposed API/APE north of Suisun Bay is depicted only as a salt marsh.

The Proposed API/APE is depicted on the Historical Atlas Map of Solano County, 1878, by Thompson and West (Figure 4-1; Thompson and West 1878). This map shows several structures in the Proposed API/APE that were part of the small town of Collinsville (whose name was recently changed from Newport). The area between the river and the town appears to have been marshland with no development. Immediately west of the Proposed API/APE at the edge of the river is Collins Wharf, which appears to have been connected to the town by a road through the marsh. The area was sparsely populated during this period. This map depicts ten or more structures, while the northern end of town had what appears to be a couple of residences and a schoolhouse, bordering a tract owned by C. H. Rice. This expansion seems more in keeping with a working salmon cannery, hotels, and stores in the town. The Collinsville Road can be seen on this early map, which would later become a recognized historical site (P-48-000981) within the Proposed API/APE.

A map of Solano County published in 1890 by E. N. Eager (Figure 4-2; Eager 1890) shows that there had been numerous land ownership changes in the Proposed API/APE, as S. M. Marshall, C.K. Marshall, and John Kirge at this time owned most of the land within the Proposed API/APE, south from the Proposed API/APE's northern boundary to the water's edge in the salt marshes. L. P. Marshall, a landowner immediately to the east, and two sons occupied the abandoned Hastings Adobe in 1855 (P-48-000041; Young 1971). Lansford W. Hastings built the adobe house in 1844 at the junction of the Sacramento River, San Joaquin River, and Suisun Bay and planned a town that he named Montezuma City. After California was ceded to the United States in the aftermath of the Mexican American War, he abandoned the site. The Marshalls repaired and improved the dwelling with a frame structure around the adobe. The Marshall family lived here until 1908, when they sold the building to the S. O. Stratton family. The adobe was nominated to the NRPH in 1972. It may be one of these structures depicted on the map.

The Honker Bay and Collinsville USGS 7.5-minute topographic quadrangle map of 1918 (Figure 4-3 and Figure 4-4; USGS 1918) shows that the town of Collinsville, west of the Proposed API/APE, was scaled down during this period, with a few buildings depicted along either side of the main road and the river's edge to the east of the main road. In the Proposed API/APE appears what is designated as Montezuma Landing with a pier and a few structures. Northwest of the landing, within the Proposed API/APE, at least two structures are depicted, including one along the main road and one north of the road.

The Honker Bay and Antioch North USGS 7.5-minute topographic quadrangle map of 1953 (USGS 1953) shows the Proposed API/APE before W. Trimble Road was constructed. To the west of the Proposed API/APE, Collinsville had grown to include over 20 structures along the main road and the river's edge. There is still marshland immediately east of town, where radio towers have been installed. The Proposed API/APE is undeveloped with a finger of water jutting inland from the river. This is called Marshall's Cut. To the north of the cut, two structures are depicted as well as scattered

structures farther to the north. These appear in the exact location as structures on the 1918 topographic map discussed above.




Figure 4-1. 1876 map showing land ownership (E. T. Upham, C. H. Rice, and Charles Dadami) within the Proposed API/APE (Thompson and West 1876).



Figure 4-2. 1890 map showing land ownership (M. Dawson and J.W. Briggs) within the Proposed API/APE (E. N. Eager 1890).

The Honker Bay topo map from 1953 also depicts an offshoot of the Atchison, Topeka, & Santa Fe Railway (AT&SF), intersecting the southern portion of the Proposed API/APE to the west of the

Pittsburg Substation. This unnamed railroad offshoot originates from the AT&SF and heads north, intersecting the Sacramento Northern Railway (P-07-000489), and then continues north into the Pittsburg Substation, where it appears to end just before reaching the banks of the Sacramento River. The railway offshoot first appeared on topographic maps in 1953 (USGS 1953), can be seen again on USGS Topo maps from 1993 (USGS 1993), and disappears from maps by 2012 (USGS 2012).

Furthermore, it was also at this time in 1953 that the Contra Costa-Moraga/Pittsburg-Tesla PG&E Electrical Transmission Lines (P-07-002956) first appeared on archival maps (USGS 1953). This transmission line consists of two lines that span 31 mi, beginning in Antioch, CA and ending at the Pittsburg Substation. This transmission line played a crucial role in the creation of PG&E and the development of a reliable supply of electrical power throughout Contra Costa and Alameda counties during the early to mid-twentieth century (Supernowicz 2017).

The Antioch North USGS 7.5-minute topographic quadrangle map of 1978 (Figure 4-5; USGS 1978) shows that the overall Proposed API/APE was slightly more developed with new roads, such as Stratton Lane and Talbert Lane. To the west of the Proposed API/APE, Collinsville appears to have remained relatively unchanged, with structures along the main road (Collinsville Road) and the river's edge. The land around town appears to have been drained, and dryland was created around the town, especially to the east of town where radio towers still stand. To the north of Marshall's Cut, only a few structures remain, and only one remains farther to the north.

A review of historical aerial photographs dating from 1937–1980 was also completed as part of the literature review. The aerial photograph from 1937 (Figure 4-6; UCSB 1937) shows that the land between the Proposed API/APE and Collinsville to the west had mostly dried up. The radio towers do not appear to have been constructed by this time. A couple of structures just west of the Proposed API/APE are most likely related to agriculture, as most of the area in and around the Proposed API/APE appears to be agricultural fields and grazing lands with very little development. Marshall's Cut is a feature of the Proposed API/APE, and there appears to have been some development at its northern end. A couple of scattered structures appear to the north of this area.

The 1957 aerial photograph (Figure 4-7; UCSB 1957) shows that very little change had occurred in the intervening decades. The pad for the radio tower can now be seen to the west of the Proposed API/APE, just south of what will later become Stratton Road. A couple of new structures had been built between the radio tower and the Proposed API/APE on the northern side of this road. There appears to have been substantial construction north of Collinsville on the western side of the waterway. By 1957, the Proposed API/APE itself had undergone very little change since 1937. The same development at the northern end of Marshall's Cut and the two scattered structures to the north can be seen. It was also at this time that historic aerial images show the development of the Pittsburg Substation, intersecting the southern extent of the Proposed API/APE (NETR 2023).

The 1970 aerial photograph (Figure 4-8; UCSB 1970) again shows that little change had occurred in the intervening decades. Some new construction appears just west of the Proposed API/APE at the southern end of the small cut along the waterfront. The land within the Proposed API/APE itself remained the same. The same development at the northern end of Marshall's Cut and the two scattered structures to the north can be seen.

The study of historical maps and aerial photographs has shown that very little change to the area has occurred from its initial development in the mid-nineteenth century until very recently. The small town of Collinsville never expanded beyond a few dozen buildings. The entire area remained mainly agricultural or unused lands (Figure 4-8). The agrarian use does not appear to have been more than a few farms or ranches scattered about. There appears to be some connection to the river for either small-scale river transport or fishing. The southern extent of the Proposed API/APE was

undeveloped prior to the construction of the Pittsburg Substation. The Pittsburg Substation first appears on historic maps in 1953 (USGS 1953) and can be seen on aerial images dating back to 1957 (NETR 2023). The entirety of the Proposed API/APE remained unchanged for most of the twentieth century.




Figure 4-3. Historic Topo map of the Proposed API/APE (Honker Bay, CA 1918; Collinsville, CA 1918).




Figure 4-4. Historic Topo map of the Proposed API/APE (Honker Bay, CA 1918; Collinsville, CA 1918).




Figure 4-5. Topographic map from 1978 depicting the northern portion of the Proposed API/APE (USGS 1978).




Figure 4-6. Historic aerial imagery of the northern extent of the Proposed API/APE (UCSB 1937).




Figure 4-7. Historic aerial imagery of the northern extent of the Proposed API/APE (UCSB 1957).




Figure 4-8. Aerial image showing limited development within the Proposed API/APE (in blue) and the vicinity (UCSB 1970).

# **Native American Heritage Commission Outreach**

Chronicle Heritage contacted the Native American Heritage Commission (NAHC) on May 5, 2023, to request a search of the Proposed API/APE in the Sacred Lands File (SLF). The NAHC responded on June 1, 2023, indicating that SLF search results were negative, and provided a list of 23 contacts, representing eight tribes with traditional affiliations to the area to contact for any additional findings.

On June 26, 2023, Chronicle Heritage sent letters to 23 tribal contacts to notify representatives of Project plans and to request any information of known Native American cultural resources in the Proposed API/APE or the vicinity. Chronicle Heritage received two responses: from Yvonne Perkins, Tribal Historic Preservation Officer (THPO) and Cultural Resource Chairperson of the Yocha Dehe Wintun Nation, and from Irene Zwierlein, Chairperson of the Mutsun Tribal Band of Mission San Juan Bautista.

On August 1, 2023, THPO Yvonne Perkins responded to Chronicle Heritage's outreach stating that the Cultural Resources Department had reviewed the Proposed Project information and concluded that the Proposed API/APE is within the aboriginal territories of the Yocha Dehe Wintun Nation. Perkins maintained that the Wintun Nation has a cultural interest and authority in the Proposed API/APE and requested formal consultation between the lead agency of the Proposed Project and the Wintun Cultural Resources Department (Perkins 2023).

A response from Irene Zwierlein contained recommendations from the A.M.T.B Inc. and Amah Mutsun Tribal Band of San Juan Bautista if any cultural or historic sensitivity is encountered within 1 mi of the Proposed API/APE. In the event that any cultural sensitivity is encountered in the records search results, Zwierlein's recommendations include cultural sensitivity training for all individuals and personnel who will be moving any earth, that a qualified California-trained archaeological monitor be present during any earth movement, and that a qualified Native American monitor be present during any earth movement.

Native American outreach conducted for the Proposed Project is solely a request for information regarding cultural resources within and in the vicinity of the Proposed API/APE. Outreach letters, follow-up calls, and emails do not constitute formal consultation and are not meant to replace consultation by the Lead Agencies under Section 106 of the NHPA or Assembly Bill 52. Attachment C includes copies of all NAHC correspondence.

# **Archaeological Sensitivity**

Results of the records search and archival research suggest that portions of the Proposed API/APE may be archaeologically sensitive.

Chronicle Heritage estimated the subsurface cultural sensitivity of the Proposed API/APE by analyzing local sedimentological, stratigraphical, and geomorphological information contained in academic and regulatory reports in relation to the distribution of recorded cultural resources in the region. Additionally, geologic maps and soil reports provided the units to be expected at depth with the Proposed API/APE.

Geologically, surficial units in the southern end of the Proposed API/APE near Pittsburg are mapped as artificial fill and Pleistocene alluvial fan deposits (Helley and Graymer 1998). Surficial units on the northern bank of the Sacramento River near Collinsville are mapped as Holocene peaty muck deposits, and the low-lying hills at the northern edge of the Proposed API/APE are mapped as Quaternary undifferentiated gravels (Helley and Graymer 1998). Soils within the Proposed API/APE

are clays and clay loams in the floodplain at the southern edge of the Proposed Project, silt clay loams on the northern bank of the Sacramento River, and clays in the Montezuma Hills at the northern edge of the Proposed API/APE (USDA 2023). Although Montezuma Hills clays are somewhat shallow with a depth to bedrock of approximately 102 centimeters (cm) (USDA 2023), the remaining soils within the Proposed API/APE are deep, mapped with a depth to bedrock of at least 2 meters (m) (USDA 2023). The Montezuma Hills clays have an overall low likelihood to yield buried cultural materials because they are relatively shallow and are mostly situated on hillslopes. However, soils within small drainages of the Montezuma Hills at the northern end of the Proposed API/APE have a moderate potential to contain buried cultural resources due to their position in a flat depositional setting near an ephemeral water source. Surface exposures within the Montezuma Hills clays and gravels are likely to contain historic resources given the presence of several previously recorded historic sites in the vicinity of Collinsville (see Section 3.1).

Clay loams in marshland on the north bank of the Sacramento River have a high potential to yield buried cultural deposits due to their depth of at least 2 m, their flat setting next to a significant water body, and ethnographic (Kroeber 1932) and archaeological (Arnold and Walsh 2010) evidence for sustained indigenous occupation of Sacramento–San Joaquin River Delta marshlands. As with soils in the Montezuma Hills, marshland loams are likely to contain historic resources given their proximity to previously recorded historic sites in the vicinity of Collinsville. Artificial fill and Pleistocene alluvial fan deposits in the southernmost section of the Proposed API/APE are unlikely to contain buried precontact materials due to heavy landscape modification associated with the historic development of Pittsburg and Pleistocene-aged material that may predate human occupation of the area.

# **Terrestrial Survey**

# **Pedestrian Archaeological Survey Methods**

Chronicle Heritage conducted an intensive pedestrian archaeological survey of terrestrial portions of the Proposed API/APE under the direction of Chronicle Heritage Senior Archaeologist Max van Rensselaer, MPS, RPA. Max van Rensselaer and Chronicle Heritage Associate Archaeologist Ashley Garrett served as Field Directors during the field effort with a crew that included Evan Tudor Elliott, Thea De Armond, Rachael Irwin, Camille Weiskopf, and Gregg Harmon.

The entirety of the terrestrial Proposed API/APE was surveyed in pedestrian transects no more than 15 m apart, with the exception of the proposed LSPGC Telecommunications Line route. Because the proposed LSPGC Telecommunications Line is limited to the public right-of-way, and construction will be temporary in nature, the proposed LSPGC Telecommunications Line route was not surveyed for cultural resources. Digital photographs were taken for use in documentation and reporting. Photographs include general views of the Proposed API/APE and topography, vegetation density, and other relevant images. An ArcGIS Collector receiver with submeter accuracy (±50 cm) was used to conduct the archaeological survey within the bounds of the Proposed API/APE, to identify the extent of previously recorded cultural resources, and to document artifacts and features within archaeological sites.

The Proposed API/APE was examined for the presence of historic or precontact period archaeological site indicators. Historic period site indicators include foundations, fence lines, ditches, standing buildings, objects, or structures such as sheds or concentrations of materials at least 45 years old, such as domestic refuse (e.g., glass bottles, ceramics, toys, buttons, and leather shoes) or refuse from other pursuits such as agriculture (e.g., metal tanks, farm machinery parts, and horseshoes) or structural materials (e.g., nails, glass window panes, corrugated metal, wood

posts or planks, metal pipes and fittings, etc.). Precontact site indicators include areas of darker soil with concentrations of ash, charcoal, faunal bone fragments (burned or unburned), shell, flaked stone, ground stone, and human bone.

The pedestrian survey covered approximately 409 acres. Due to issues gaining access to the PG&E Pittsburg Substation and surrounding area, only the portion of the Proposed API/APE north of the Sacramento River was initially surveyed. The southern extent of the terrestrial Proposed API/APE, south of the Sacramento River, was surveyed on December 19, 2023, after access to that portion of the Proposed API/APE was granted.

# Pedestrian Survey of Northern Portion of Terrestrial Proposed API/APE

The pedestrian survey of the northern portion of the Proposed API/APE was conducted August 21 to August 22, 2023, October 16– October 18, 2023, and again on June 28, 2024. Extensive disturbances from road grading, construction activities, wind turbine maintenance, and agricultural activities (including both cattle ranching and hay cultivation) were observed throughout the Proposed API/APE north of the Sacramento River (Figure 6-1).



Figure 6-1. Project overview, facing southwest.

The northern extent of the Proposed API/APE consisted of high rolling hills with varying slopes that ranged from 10–20 percent (Figure 6-2). The southern extent of the surveyed area north of the Sacramento River had gradually sloping hills with slopes ranging from 5–9 percent (Figure 6-3). Ground surface visibility was poor throughout the Proposed API/APE with 10–20 percent visibility due to the presence of thick vegetation and tall grasses. Vegetation consisted of low to tall grasses and weeds, including star thistle, turkey mullein, pigweed, and blindweed. In some areas, star thistle bushes were dense to the point of being impassable, and tall dried shrubs reached over 6 ft in height.

In areas where the ground was visible, the surface's integrity was disturbed by deep imprints and crevices from extensive cattle trampling.

In areas where soil visibility was limited, the survey crew employed periodic boot scrapes to enhance ground visibility. Soils within the northern extent of the Proposed API/APE consisted of a light to dark brown clay loam known as the Diablo-Ayer complex, formed of well-drained residuum weathered from weakly consolidated sediments (CSRL 2023). Soils within the southernmost extent of the Proposed API/APE consisted of a tidally influenced silty loam known as the Valdez-Columbia complex, made of a poorly drained fine-silty alluvium derived from igneous, metamorphic, and sedimentary rock (CSRL 2023). Several recently graded roads intersected the Proposed API/APE, which revealed soils of a light brown silty loam with subangular rock inclusions.



Figure 6-2. Project overview, facing north.



Figure 6-3. Project overview, facing southeast.

Nine previously recorded resources within or immediately adjacent to the Proposed API/APE were revisited (P-48-00041, P-48-000124, P-48-000125, P-48-000128, P-48-000139, P-48-000140, P-48-000416, P-48-000521, and P-48-000981). Of the nine previously recorded resources, eight were relocated (P-48-000041, P-48-000124, P-48-000125, P-48-000139, P-48-000140, P-48-000416, P-48-000521, and P-48-000981). One resource (P-48-000128) could not be located, except for a single piece of window glass, due to disturbances associated with agricultural activity. Five new resources were identified (AG-001, JN-01, JN-02, Stratton Lane, and JN-04). The nine previously recorded resources were updated using Department of Parks and Recreation (DPR) 523 forms. The five newly identified resources were recorded on DPR 523 forms. All of the DPR 523 forms can be found in Attachment D. A confidential map of the survey results of the Northern Portion of the Terrestrial Proposed API/APE is Figure 1 in Attachment E.

# Pedestrian Survey of Southern Portion of Terrestrial Proposed API/APE

The southern extent of the Proposed API/APE, south of the Sacramento River, was surveyed on December 19, 2023, by Associate Archaeologists Ashley Garrett and Josh Noyer. The survey area was in a developed, industrial area of the Pittsburg Substation on the south bank of the Sacramento River. There were multiple outbuildings and various modern infrastructure features throughout the survey area. The northern portion of the survey area's ground surface was a mixture of paved asphalt and imported ballast gravel. The southern portion of the survey area was largely unpaved with sandy gravelly soils and weedy brush vegetation. Areas with unpaved exposed soils were examined for surface cultural material.

Multiple double lane asphalt access roads travel through the survey area. Two mostly parallel access roads branch to the north through the area off an east-west access road that forms the southern boundary. The northeast edge of the survey area is bound by an industrial facility and immediately south of this facility, the remaining eastern edge is bound by fencing for a power substation. The northern edge of the survey area is bound by a chain-link fence and the south bank of the Sacramento River. The western portion of the survey area is crossed by multiple north-south running chain-link fences that run along both margins of the western most access road.

Multiple power transmission lines connecting with the substation adjacent to the east, cross through the central and southern portions of the survey area traveling northeast to southwest. Two of these transmission lines and associated towers were previously recorded as a historic resource (P-07-002956), these were revisited and a DPR update was prepared.

A portion of the Burlington Northern Santa Fe Railway line travels through the middle of the survey area entering in the south and traveling north-northwest before turning towards the east-northeast continuing out of the survey area. The rail is largely intact but no longer in use with several sections covered by asphalt where it crosses access roads. The railway is of historic age and a draft DPR site record (AG-002) was prepared for the section of the railway within the current survey area.

No other cultural resources were identified or recorded during the current survey.

The site P-07-002956, the Contra Costa-Moraga/Pittsburg-Tesla PG&E Electrical Transmission Lines, and AG-002 were updated and recorded using DPR 523 forms. These can be found in Attachment D. A confidential map of the survey results of the Southern Portion of the Terrestrial Proposed API/APE is Figure 2 in Attachment E.

## **Cultural Resource Evaluations**

#### P-48-000041

P-48-000041 is a multicomponent site consisting of a precontact campsite and the Hastings Adobe. The adobe was originally constructed in 1846 by Lansford W. Hastings, a representative of the Mormon Church, who was tasked with establishing a Mormon settlement on the West Coast. The building was originally constructed with sun-dried bricks made from native clay adobe and consisted of four rooms and an attic. Hastings abandoned the adobe shortly after the United States claimed the land, and the Mormon community lost interest in the settlement. In 1853, the adobe was unofficially claimed by L.P. Marshall and his two sons, who made repairs to the adobe by adding a wooden frame around the entirety of the structure. The Marshalls occupied the structure until 1908, when the S.O. Stratton family purchased it. Further repairs and maintenance were done to the structure by the Strattons until it was ultimately purchased by PG&E in 1963 (Young 1971). Mr. Stratton noted a nearby precontact campsite where he, "used to pick up arrow points" (Elsasser 1956). However, by 1956, A.B. Young noted that the campsite had been covered by sterile sandy soil and had been disturbed by modern agricultural processes (Young 1971). During the field visit, archaeologists were unable to find the prehistoric component of the site. The adobe was evaluated for eligibility in 1971 and was nominated to the NRHP in 1972. The adobe is outside of the Proposed API/APE. The site will not be impacted directly by Project construction.

## **Effects Analysis**

The adobe was nominated to the NRHP in 1972 due to its local significance in representing the nineteenth-century settlement of California and an attempted establishment of a Mormon

community by Langsford W. Hastings in what he called Montezuma City, which later became Collinsville. Acquired in 1853 by the Marshall family, the adobe was altered by placing a frame structure around the exterior of the building. After suffering vandalism following the purchase of land surrounding the adobe by PG&E in 1963, a high padlocked fence was placed around the Hastings Adobe (Figure 7-1). The NRHP evaluation form completed by Wood Young in 1971 describes the Hastings Adobe's condition as "deteriorated" and indicates restoration of the building is needed for, "perpetuation as a historic monument" (Young 1971). Although the adobe is described as retaining its, "basic architectural form," the integrity is, "expressly noted in the interior," because the exterior framework and porch area were modern additions. Therefore, while significant as a local historic monument and retaining integrity of the interior architectural plan to communicate its significance, the integrity of the exterior of the adpbe has been altered and remains deteriorated.



Figure 7-1. Site overview, facing south.

#### Conclusion

P-48-000041 has been nominated to the NRHP based on its local historical significance. The exterior of the building remains in a state of deterioration, has seen multiple modern additions, and remains fenced off to prevent further vandalism. Because the building is outside the Proposed Project footprint, it will not be directly affected by Project activities. During the field visit, a viewshed analysis was conducted to identify if visual impacts would adversely affect the historic property, and if the setting would be altered. The addition of structures associated with the construction of a transmission line for the Project will not constitute significant changes to the visual landscape as it currently exists to adversely affect the setting or feeling of the historic property. Due to deterioration, vandalism, and the addition new materials, including the reinforced structure around the adobe and a porch area, the integrity of the building;s exterior design has been compromised, and the building's significance is

communicated through the integrity of the design, materials, and workmanship of adobe's interior. The Project will have no impact upon the feeling, setting, or location of the building nor its association. Additionally, the precontact component of the site could not be located due to its likely destruction associated with soil disturbances including agricultural activity and animal grazing. As such, it is recommended that the Project will result in no adverse effect to the historic property. An update to the DPR 523 site record can be found in Attachment D.




Figure 7-2. Site overview, facing north.

#### P-48-000124

P-48-000124 was last recorded in 2010 and was described as a barn, the remains of a water tower, three depressions (of which two may be privies and one a possible cellar), and a eucalyptus windbreak. The artifact scatter was recorded as consisting of bricks, ceramics, metal, and glass debris dispersed throughout the recorded site boundary. During the revisit for this Project, the barn was no longer extant, and neither the water tower nor the three depressions could be located. The stump of a eucalyptus tree was noted within the site boundary. A small makeshift corral has been constructed 200 feet west of where the barn once stood and 50 feet east of Stratton Lane. The corral is constructed from a mixture of more modern materials and historic debris possibly taken from the destroyed barn. The corral is a rectangular shape divided into sections and measures approximately 50 feet (north-south) by 100 feet (east-west). The corral includes a wooden loading ramp on its south edge, based on the size of the ramp it was likely used for sheep. A mixture of round wooden and metal "T" posts supports wire fencing welded to rectangular metal plates. Based on historic aerials, the coral in its current form was constructed sometime after 2014, after destruction of the barn.

A historic artifact scatter remains, consisting of glass, ceramic, and wood fragments was identified. Approximately 30 glass shards were observed, including milk glass, blue, green, clear, and aqua glass. Two ceramic white ware sherds were observed. Additionally, one piece of milled lumber was observed, but due to dense vegetation was unable to be further inspected. Observed artifacts were generally fragmented and broken. Due to the lack of integrity of the site, site boundaries were not updated. A modern stock tank was observed within the site boundary, and heavy construction machinery was staged west of P-48-000124. Overall, the site was in poor condition, and previously described structures and features appear to have been destroyed (Figure 7-3 and Figure 7-4).

The site is within the Proposed API/APE. It is not likely to be directly impacted by Project construction.



Figure 7-3. Site overview, facing north.



Figure 7-4. Site overview, facing south.

# Criterion A/1: Associated with events that have made a significant contribution to the broad patterns of our history.

Evaluation as eligible for NRHP listing under criterion A/1 requires the property to be associated with either (or both) of two types of events: (1) a specific event marking an important moment in American prehistory or history and (2) a pattern of events or a historic trend that made a significant contribution to the development of a community, a state, or the nation (NPS 1995). No evidence was found to suggest that the barn was associated with a specific event of importance in American history or that it was associated with a pattern of events making a significant contribution in the development of Solano County or California. As such, P-48-000124 does not meet the threshold for historical significance under NRHP Criterion A or CRHR Criterion 1.

#### Criterion B/2: Associated with the lives of persons significant in our past.

Historic maps indicate the barn was constructed prior to 1877 on land owned by Knox Marshall (Thompson and West 1877). The Marshall family was involved in establishing Montezuma Township, later becoming Collinsville; owned land within and around the Proposed API/APE; and occupied the Hastings Adobe in the early twentieth century. Criterion B/2 applies to properties associated with individuals whose specific contributions to history can be identified and documented (NPS 1995). Although Marshall was an early settler in the area, it cannot be demonstrated from what we know about him that his contributions to the history of Solano County or California go beyond that. Therefore, the site is not historically significant under NRHP Criterion B or CRHR Criterion 2.

# Criterion C/3: Embody the distinctive characteristics of a type, period, or method of construction, or that represent the work of a master, or that possess high artistic values, or that represent a significant and distinguishable entity whose components may lack individual distinction.

This criterion applies to the physical design or construction of the property, including such elements as architecture, landscape architecture, engineering, and artwork (NPS 1995). This property does not embody distinctive characteristics of a type, period, or method of construction. It does not represent the work of a master. It does not possess high artistic value. The site has been extensively altered from its original appearance. Neither the barn nor the water tower is extant. As such, the building does not possess historical significance under NRHP Criterion C or CRHR Criterion 3.

#### Criterion D/4: Yielded, or may be likely to yield, information important in prehistory or history.

Under this criterion the property must have the potential to answer, in whole or in part, the questions posed in the research design (NPS 1995). Although the site is an example of early homesteading or farming, the site has been largely destroyed, and because of the limited artifact scatter still present at the site, the property is not likely to possess enough data to yield important or new information that could be used to answer research questions. Therefore, P-48-000124 does not appear to be significant under NRHP Criterion D or CRHR Criterion 4.

#### Integrity

Integrity is based on significance: why, where, and when a property is important. Only after significance is fully established can you proceed to the issue of integrity (NPS 1995). However, a brief statement regarding the integrity of the site can be made. The property is still in its original location, which retains much of its undeveloped and rural setting. Because the original structure no longer stands, it has lost all of its integrity of design, materials, workmanship, and historic feeling. Although some element of the property's association with the surrounding landscape persists, it is mostly lost because of the wreckage and removal of the original structures.

#### Conclusion

P-48-000124 does not possess historical significance under any of the evaluation criteria. Additionally, the site has been largely destroyed and no longer retains integrity. Chronicle Heritage recommends the site is not eligible for inclusion in the NRHP/CRHR. An update to the DPR 523 site record can be found in Attachment D.

#### P-48-000125

P-48-000125 was first recorded in 1980 by C. Peeler Crist and updated in 2010 by Far Western. The original site record described the site as a scatter of ceramics, glass, brick, construction materials, and a possible septic tank. The 2010 site revisit was unable to locate the artifacts or the septic tank but did identify a pipe and wood-covered hole that was previously described. Disturbances noted in the 2010 revisit include overgrown vegetation, animal grazing, and modern use of the area, reflected by the construction of a cement water well and pump. During the 2023 revisit for this Project, an artifact scatter consisting of domestic refuse was observed, including eight glass shards, two ceramic sherds, four bricks or brick fragments, a ferrous metal dowel, and an iron rod. Additionally, a well and modern water pump were noted. Disturbances included overgrown vegetation, animal grazing, and the construction of an adjacent road (Figure 7-5 and Figure 7-6).

The site is within the Proposed API/APE. It is not likely to be directly impacted by Project construction.



Figure 7-5. Site overview, facing south.



Figure 7-6. Site overview, facing north.

# Criterion A/1: Associated with events that have made a significant contribution to the broad patterns of our history.

Evaluation as eligible for NRHP listing under criterion A/1 requires the property to be associated with either (or both) of two types of events: (1) a specific event marking an important moment in American prehistory or history and (2) a pattern of events or a historic trend that made a significant contribution to the development of a community, a State, or the nation (NPS 1995). No evidence was found to suggest that P-48-000125 was associated with a specific event of importance in American history or that it was associated with a pattern of events making a significant contribution in the development of Solano County or California. As such, the property does not meet the threshold for historical significance under NRHP Criterion A or CRHR Criterion 1.

#### Criterion B/2: Associated with the lives of persons significant in our past.

Criterion B/2 applies to properties associated with individuals whose specific contributions to history can be identified and documented (NPS 1995). Research did not identify a specific individual or group that was associated with P-48-000125 that had any connection of importance to the history of California. An 1877 historic map indicates that the Collinsville District School stood in the vicinity of the site, but no further information regarding the school or land ownership at the site could be uncovered. The site is not historically significant under NRHP Criterion B or CRHR Criterion 2.

# Criterion C/3: Embody the distinctive characteristics of a type, period, or method of construction, or that represent the work of a master, or that possess high artistic values, or that represent a significant and distinguishable entity whose components may lack individual distinction.

This criterion applies to the physical design or construction of the property, including such elements as architecture, landscape architecture, engineering, and artwork (NPS 1995). This property does not embody distinctive characteristics of a type, period, or method of construction. It does not represent the work of a master. It does not possess high artistic value. P-48-000125 currently consists of a historic artifact scatter of non-diagnostic material including glass, ceramics, metal, and construction materials so any distinctive characteristics of a type, period, or method of construction have been lost. Overall, the site does not represent a significant or distinguishable entity. As such, the site does not possess historical significance under NRHP Criterion C or CRHR Criterion 3.

#### Criterion D/4: Yielded, or may be likely to yield, information important in prehistory or history.

Under this criterion the property must have the potential to answer, in whole or in part, the questions posed in the research design (NPS 1995). Although the site may be associated with early homesteading or farming, the site lacks an adequate archaeological component based on the limited number of artifacts and the non-diagnostic nature of the assemblage. Because of disturbances from agriculture and grazing, the site does not indicate the potential for significant subsurface deposits. This site is not likely to yield enough data or important or new information that could be used to answer research questions. Therefore, P-48-000125 is not significant under NRHP Criterion D or CRHR Criterion 4.

#### Integrity

Integrity is based on significance: why, where, and when a property is important. Only after significance is fully established can you proceed to the issue of integrity (NPS 1995). However, a brief statement regarding the integrity of the site can be made. The property is still in its original location, which retains some of its undeveloped and rural setting. Because the original structure no

longer stands, it has lost all of its integrity of design, materials, workmanship, and historic feeling. Although some element of the property's association with the surrounding landscape persists, it is mostly lost because of the wreckage and removal of the original structure.

#### Conclusion

P-48-000125 does not possess historical significance under any of the evaluation criteria. Chronicle Heritage recommends the site is not eligible for inclusion in the NRHP and CRHR. An update to the DPR 523 site record for the site can be found in Attachment D.

#### P-48-000128

P-48-000128 was first recorded in 1980 (Maniery et al. 1980) as a historic homestead site based on ethnographic accounts. Archaeological evidence for the homestead consisted of three ceramic fragments, square nails, and burned wooden boards. The site was revisited by Adrian Whitaker in 2010 (Whitaker 2010), but no elements of the site were located at that time. Disturbances consisted of recent soil disking associated with mechanical agricultural land management practices (Figure 77). During the revisit for this Project, Chronicle Heritage archaeologists identified a single fragment of window glass and observed disturbances consistent with agricultural mowing.

The site is within the Proposed API/APE. It is not likely to be directly impacted by Project construction.



Figure 7-7. Site overview, facing north.

# Criterion A/1: Associated with events that have made a significant contribution to the broad patterns of our history.

Evaluation as eligible for NRHP listing under criterion A/1 requires the property to be associated with either (or both) of two types of events: (1) a specific event marking an important moment in American prehistory or history and (2) a pattern of events or a historic trend that made a significant contribution to the development of a community, a State, or the nation (NPS 1995). P-48-000128 was initially recorded as a homestead site based on ethnographic accounts, but no evidence was found to link P-48-000128 with a specific event of importance in American history or with a pattern of events making a significant contribution in the development of Solano County or California. As such, the subject property does not meet the threshold for historical significance under NRHP Criterion A or CRHR Criterion 1.

#### Criterion B/2: Associated with the lives of persons significant in our past.

Criterion B/2 applies to properties associated with individuals whose specific contributions to history can be identified and documented (NPS 1995). An 1877 historic map indicates the site may have been within an area owned by C. Dadami (Thompson and West 1877). Archival research indicates Charles Dadami was born in 1848 in Switzerland and immigrated in 1867. Charles Dadami died in 1917 and is buried at the Collinsville Cemetery (FindAGrave 2023). Although Charles Dadami was an early Collinsville settler and was active in the community and the Catholic Church, archival research does not indicate that he contributed significantly to the history of Collinsville, Solano County, California, or the United States (Theodoratus Cultural Research 1980). Therefore, P-48-000128 does not appear to be significant under NRHP Criterion B or CRHR Criterion 2.

# Criterion C/3: Embody the distinctive characteristics of a type, period, or method of construction, or that represent the work of a master, or that possess high artistic values, or that represent a significant and distinguishable entity whose components may lack individual distinction.

This criterion applies to the physical design or construction of the property, including such elements 8as architecture, landscape architecture, engineering, and artwork (NPS 1995). This property does not embody distinctive characteristics of a type, period, or method of construction. It does not represent the work of a master. It does not possess high artistic value. The homestead reported at P-48-000128 has never been formally documented despite the location suggested by ethnographic reports. The existing artifact scatter is limited to a single non-diagnostic glass artifact, so any distinctive characteristics of a type, period, or method of construction have been lost. As such, P-48-000128 does not appear to be historically significant under NRHP Criterion C or CRHR Criterion 3.

#### Criterion D/4: Yielded, or may be likely to yield, information important in prehistory or history.

Under this criterion the property must have the potential to answer, in whole or in part, the questions posed in the research design (NPS 1995). Although the site may be associated with early homesteading or farming, the site lacks an adequate archaeological component since no significant archaeological component has been observed during the two most recent site visits. The property is not likely to yield enough data or important or new information that could be used to answer research questions. Therefore, P-48-000128 is not significant under NRHP Criterion D or CRHR Criterion 4.

#### Integrity

Integrity is based on significance: why, where, and when a property is important. Only after significance is fully established can you proceed to the issue of integrity (NPS 1995). However, a brief statement regarding the integrity of the site can be made. The property is still in its original

location, which retains some of its undeveloped and rural setting. Because the original structure no longer stands, it has lost all of its integrity of design, materials, workmanship, and historic feeling. Although some element of the property's association with the surrounding landscape persists, it is mostly lost because of the wreckage and removal of the original structure.

#### Conclusion

P-48-000128 does not possess historical significance under any of the evaluation criteria. Therefore, a formal discussion of historical integrity is not required. Chronicle Heritage recommends the line is not eligible for inclusion in the NRHP or CRHR. An update to the DPR 523 site record can be found in Attachment D.

#### P-48-000139

P-48-000139 was first recorded by Gebhardt and others (1980). Chronicle Heritage archaeologists revisited P-48-000139 on October 18, 2023 (Figure 7-8). The site boundary was consistent with the 1980 Sketch Map (Gebhardt et al. 1980) but was inconsistent with the GIS site boundary obtained from the Northwest Information Center. The historical domestic refuse scatter was successfully relocated and an obsidian biface isolated was found, technically making the site multi-component. In total, nine glass shards, three sherds of white improved earthenware, and one large indeterminate metal piece was found. Of the glass, eight were colorless and one was violet. There were no maker's marks or other diagnostic elements on any of the ceramic sherds.

Additionally, the previously observed fence line and much of the concrete structural remains from 2010 were no longer visible within the site. The fence line has since been removed entirely. Consistent with the original site records, several pepper and eucalyptus trees are still standing within the site. Other vegetation includes horehound, mustard, star thistle, turkey mullein, pigweed, and blindweed. The slope was variable with the center of the site being on a hill with a  $7^{\circ}$  southfacing slope.

Chronicle Heritage archaeologists updated the GIS site boundary to accurately depict the site's observed location.

The site is adjacent to the Proposed API/APE. It is not likely to be directly impacted by Project construction.



**Figure** 

7-8. Site overview, facing east.

### Significance Evaluation

# Criterion A/1: Associated with events that have made a significant contribution to the broad patterns of our history.

Evaluation as eligible for NRHP listing under criterion A/1 requires the property to be associated with either (or both) of two types of events: (1) a specific event marking an important moment in American prehistory or history and (2) a pattern of events or a historic trend that made a significant contribution to the development of a community, a State, or the nation (NPS 1995). P-48-000139 was initially recorded as a homestead site, but no evidence was found to link P-48-000139 with a specific event of importance in American history or with a pattern of events making a significant contribution in the development of Solano County or California. As such, the subject property does not meet the threshold for historical significance under NRHP Criterion A or CRHR Criterion 1.

#### Criterion B/2: Associated with the lives of persons significant in our past.

Criterion B/2 applies to properties associated with individuals whose specific contributions to history can be identified and documented (NPS 1995). Research did not identify a specific individual or group that was associated with P-48-000139 that had any connection of importance to the history of California. Therefore, P-48-000139 does not appear to be significant under NRHP Criterion B or CRHR Criterion 2.

# Criterion C/3: Embody the distinctive characteristics of a type, period, or method of construction, or that represent the work of a master, or that possess high artistic values, or that represent a significant and distinguishable entity whose components may lack individual distinction.

This criterion applies to the physical design or construction of the property, including such elements as architecture, landscape architecture, engineering, and artwork (NPS 1995). This property does not embody distinctive characteristics of a type, period, or method of construction. It does not represent the work of a master. It does not possess high artistic value. The existing artifact scatter is limited to non-diagnostic material, so any distinctive characteristics of a type, period, or method of construction, if it ever existed here, have been lost. As such, P-48-000139 does not appear to be historically significant under NRHP Criterion C or CRHR Criterion 3.

#### Criterion D/4: Yielded, or may be likely to yield, information important in prehistory or history.

Under this criterion the property must have the potential to answer, in whole or in part, the questions posed in the research design (NPS 1995). Although the site may be associated with early homesteading or farming, the site lacks an adequate archaeological component since no significant archaeological component has been observed during the two most recent site visits. The obsidian biface appears to be an isolate as no evidence of any other precontact deposits was observed on the site which has been heavily impacted by agricultural work. The property is not likely to yield enough data or important or new information that could be used to answer research questions. Therefore, P-48-000139 is not significant under NRHP Criterion D or CRHR Criterion 4.

#### Integrity

Integrity is based on significance: why, where, and when a property is important. Only after significance is fully established can you proceed to the issue of integrity (NPS 1995). However, a brief statement regarding the integrity of the site can be made. The property is still in its original location, which retains some of its undeveloped and rural setting. Because the original structure no longer stands, it has lost all of its integrity of design, materials, workmanship, and historic feeling. Although some element of the property's association with the surrounding landscape persists, it is mostly lost because of the wreckage and removal of the original structure.

#### Conclusion

P-48-000139 does not possess historical significance under any of the evaluation criteria. Therefore, a formal discussion of historical integrity is not required. Chronicle Heritage recommends the line is not eligible for inclusion in the NRHP or CRHR. An update to the DPR 523 site record can be found in Attachment D.

### P-48-000140

P-48-000140 was initially recorded in 1980 as a homesite with several features, including a possible well, a pit area with wooden structural remains, and historic artifacts. The site was revisited by Far Western in 2010, and only the pepper trees documented in 1980 were relocated. The 2010 revisit indicated bulldozers and other excavation activities had heavily modified the site's surface to create a recreational off-road motorcycle course (Figure 7-10). Chronicle Heritage revisited the site for this Project and identified five shards of non-diagnostic glass, a rusted and fragmented jerry can, a small pile of wood planks, and the previously documented pepper trees. Additionally, a modern rubber and concrete stock pond was noted in the northern portion of the site (Figure 7-11). Disturbances include evidence of earthmoving activities previously described in the 2010 update, modern refuse such as

plastics and rebar, and evidence of target shooting, including shotgun shells and small caliber ammunition casings throughout the site.

The site is within the Proposed API/APE. It is not likely to be directly impacted by Project construction.



Figure 7-10. Site overview, facing north.



Figure 7-11. Site overview, facing south.

# Criterion A/1: Associated with events that have made a significant contribution to the broad patterns of our history.

Evaluation as eligible for NRHP listing under criterion A/1 requires the property to be associated with either (or both) of two types of events: (1) a specific event marking an important moment in American prehistory or history and (2) a pattern of events or a historic trend that made a significant contribution to the development of a community, a State, or the nation (NPS 1995). P-48-000140 was first recorded in 1980 as a homesite with several domestic features, including a well, structural remains of a pit, and a historic artifact scatter. No evidence was found to link P-48-000140 with a specific event of importance in American history or with a pattern of events making a significant contribution in the development in Solano County, California, or the United States. As such, the subject property does not meet the threshold for historical significance under NRHP Criterion A or CRHR Criterion 1.

#### Criterion B/2: Associated with the lives of persons significant in our past.

Criterion B/2 applies to properties associated with individuals whose specific contributions to history can be identified and documented (NPS 1995). Research did not identify a specific individual or group that was associated with P-48-000140 that had any connection of importance to the history of California. Therefore, P-48-000140 is not historically significant under NRHP Criterion B or CRHR Criterion 2.

# Criterion C/3: Embody the distinctive characteristics of a type, period, or method of construction, or that represent the work of a master, or that possess high artistic values, or that represent a significant and distinguishable entity whose components may lack individual distinction.

This criterion applies to the physical design or construction of the property, including such elements as architecture, landscape architecture, engineering, and artwork (NPS 1995). This property does not embody distinctive characteristics of a type, period, or method of construction. It does not represent the work of a master. It does not possess high artistic value. P-48-000140 has been extensively altered from its original appearance as a result of agricultural activity and earthmoving associated with recreational vehicle trail construction, and the site is largely destroyed. None of the originally documented features remain, so any distinctive characteristics of a type, period, or method of construction have been lost. As such, the site does not possess historical significance under NRHP Criterion C or CRHR Criterion 3.

#### Criterion D/4: Yielded, or may be likely to yield, information important in prehistory or history.

Under this criterion the property must have the potential to answer, in whole or in part, the questions posed in the research design (NPS 1995). Although the site may be associated with early homesteading or farming, the site lacks an adequate archaeological component since the site does not retain any of the features for which it was originally documented. The associated artifact scatter is limited in size, and artifacts were observed to be fragmented, broken, and non-diagnostic. It is unlikely a significant or intact subsurface archaeological deposit exists, and the area has been subject to significant disturbances, including large-scale earth movement. The property is not likely to yield enough data or important or new information that could be used to answer research questions. Therefore, P-48-000140 is not significant under NRHP Criterion D or CRHR Criterion 4.

#### Integrity

Integrity is based on significance: why, where, and when a property is important. Only after significance is fully established can you proceed to the issue of integrity (NPS 1995). However, a brief statement regarding the integrity of the site can be made. The property is still in its original location, which retains some of its undeveloped and rural setting. Because the original structure no longer stands, it has lost all of its integrity of design, materials, workmanship, and historic feeling. Although some element of the property's association with the surrounding landscape persists, it is mostly lost because of the wreckage and removal of the original structure.

#### Conclusion

P-48-000140 does not possess historical significance under any of the evaluation criteria. The site has been significantly disturbed and little of the elements described in the original site recording exist. Chronicle Heritage recommends the line is not eligible for inclusion in the NRHP or CRHR. An update to the DPR 523 site record can be found in Attachment D.

#### P-48-000416

P-48-000140 was initially recorded in 1980 as a homesite with several features, including a cellar hole, three depressions, and a scatter of bricks (Crist et al. 1980). Chronicle Heritage revisited the site for this Project and identified the scatter of red bricks and one depression (Figure 7-12). However, the pepper tree, cellar, and wood pile described in the original records were not located. One historic glass bottle was identified with an "Owens" maker's mark. Ground visibility was poor and ranged from 10 to 20 percent throughout the site, with some areas of exposed soil and larger areas of dense vegetation. Vegetation consisted of low to tall grasses and weeds, including star thistle,

turkey mullein, pigweed, and blindweed. There was no slope within the site with conditions being relatively flat. Disturbances included modern activity evident by the presence of modern PVC pipe, clay pigeons, and modern shot gun shells.

The site is just outside the Proposed API/APE. It is not likely to be directly impacted by Project construction.



Figure 7-12. Site overview, facing southwest.

### **Significance Evaluation**

# Criterion A/1: Associated with events that have made a significant contribution to the broad patterns of our history.

Evaluation as eligible for NRHP listing under criterion A/1 requires the property to be associated with either (or both) of two types of events: (1) a specific event marking an important moment in American prehistory or history and (2) a pattern of events or a historic trend that made a significant contribution to the development of a community, a State, or the nation (NPS 1995). P-48-000416 was first recorded in 1980 as a homesite with several domestic features, including a cellar hole, three depressions, and a brick scatter. No evidence was found to link P-48-000416 with a specific event of importance in American history or with a pattern of events making a significant contribution in the development in Solano County, California, or the United States. As such, the subject property does not meet the threshold for historical significance under NRHP Criterion A or CRHR Criterion 1.

#### Criterion B/2: Associated with the lives of persons significant in our past.

Criterion B/2 applies to properties associated with individuals whose specific contributions to history can be identified and documented (NPS 1995). Research did not identify a specific individual or group that was associated with P-48-000416 that had any connection of importance to the history of California. Therefore, P-48-000416 is not historically significant under NRHP Criterion B or CRHR Criterion 2.

Criterion C/3: Embody the distinctive characteristics of a type, period, or method of construction, or that represent the work of a master, or that possess high artistic values, or that represent a significant and distinguishable entity whose components may lack individual distinction.

This criterion applies to the physical design or construction of the property, including such elements as architecture, landscape architecture, engineering, and artwork (NPS 1995). This property does not embody distinctive characteristics of a type, period, or method of construction. It does not represent the work of a master. It does not possess high artistic value. P-48-000416 has been extensively altered from its original appearance as a result of agricultural activity, and the site is largely destroyed. Only a couple of the originally documented features remain, so any distinctive characteristics of a type, period, or method of construction have been lost. As such, the site does not possess historical significance under NRHP Criterion C or CRHR Criterion 3.

#### Criterion D/4: Yielded, or may be likely to yield, information important in prehistory or history.

Under this criterion the property must have the potential to answer, in whole or in part, the questions posed in the research design (NPS 1995). Although the site may be associated with early homesteading or farming, the site lacks an adequate archaeological component since the site retains few of the features for which it was originally documented. The associated artifact scatter is limited in size, and artifacts were observed to be modern and not associated with the original site. It is unlikely a significant or intact subsurface archaeological deposit exists, and the area has been subject to significant disturbances, including extensive ground disturbance. The property is not likely to yield enough data or important or new information that could be used to answer research questions. Therefore, P-48-000416 is not significant under NRHP Criterion D or CRHR Criterion 4.

#### Integrity

Integrity is based on significance: why, where, and when a property is important. Only after significance is fully established can you proceed to the issue of integrity (NPS 1995). However, a brief statement regarding the integrity of the site can be made. The property is still in its original location, which retains some of its undeveloped and rural setting. Because the original structure no longer stands, it has lost all of its integrity of design, materials, workmanship, and historic feeling. Although some element of the property's association with the surrounding landscape persists, it is mostly lost because of the wreckage and removal of the original structure.

#### Conclusion

P-48-000416 does not possess historical significance under any of the evaluation criteria. The site has been significantly disturbed and little of the elements described in the original site recording exist. Chronicle Heritage recommends the line is not eligible for inclusion in the NRHP or CRHR. An update to the DPR 523 site record can be found in Attachment D.

#### P-48-000521

P-48-000 was initially recorded in 1980 as a ranch complex with several features, a collapsed structure, two barns, and a corral (Roark and Avina 2001). Chronicle Heritage revisited the site for

this Project and identified the corral, water basins for cattle, and an assortment of steel t-posts and barbed wire fencing (Figure 7-13). The property is currently being used as a cattle corral, which has been upgraded with new fencing and wire. The barn structures and concrete pad are no longer present on site. The site was not entered as the boundary was occupied by a small herd of roughly 20 cattle behind a barbed wire fence with no trespassing signs posted. Vegetation consisted of low grasses and thistles matted down by livestock activities. Several trees were identified within the site boundary including eucalyptus, pepper trees, and live oak. The slope within the site was relatively flat with a gentle northeastern slope. Ground visibility was fair with roughly 20 percent visibility. Extensive disturbance from cattle trampling over the whole area was evident.

The site is outside the Proposed API/APE. It is not likely to be directly impacted by Project construction.



Figure 7-13. Site overview, facing north.

## **Significance Evaluation**

# Criterion A/1: Associated with events that have made a significant contribution to the broad patterns of our history.

Evaluation as eligible for NRHP listing under criterion A/1 requires the property to be associated with either (or both) of two types of events: (1) a specific event marking an important moment in American prehistory or history and (2) a pattern of events or a historic trend that made a significant contribution to the development of a community, a State, or the nation (NPS 1995). P-48-000521 was first recorded

in 2001 as a ranch site with several associated features, including a collapsed structure, two barns, and a corral. No evidence was found to link P-48-000521 with a specific event of importance in American history or with a pattern of events making a significant contribution in the development in Solano County, California, or the United States. As such, the subject property does not meet the threshold for historical significance under NRHP Criterion A or CRHR Criterion 1.

#### Criterion B/2: Associated with the lives of persons significant in our past.

Criterion B/2 applies to properties associated with individuals whose specific contributions to history can be identified and documented (NPS 1995). Research did not identify a specific individual or group that was associated with P-48-000521 that had any connection of importance to the history of California. Therefore, P-48-000521 is not historically significant under NRHP Criterion B or CRHR Criterion 2.

Criterion C/3: Embody the distinctive characteristics of a type, period, or method of construction, or that represent the work of a master, or that possess high artistic values, or that represent a significant and distinguishable entity whose components may lack individual distinction.

This criterion applies to the physical design or construction of the property, including such elements as architecture, landscape architecture, engineering, and artwork (NPS 1995). This property does not embody distinctive characteristics of a type, period, or method of construction. It does not represent the work of a master. It does not possess high artistic value. P-48-000521 has been extensively altered from its original appearance as a result of agricultural activity, and the site is largely destroyed. Only the corral of the originally documented features remains, and it has been upgraded with new fencing and barbed wire, so any distinctive characteristics of a type, period, or method of construction have been lost. As such, the site does not possess historical significance under NRHP Criterion C or CRHR Criterion 3.

### Criterion D/4: Yielded, or may be likely to yield, information important in prehistory or history.

Under this criterion the property must have the potential to answer, in whole or in part, the questions posed in the research design (NPS 1995). Although the site may be associated with early homesteading or farming, the site lacks an adequate archaeological component. No associated artifacts were observed. It is unlikely a significant or intact subsurface archaeological deposit exists, and the area has been subject to significant disturbances, including extensive ground disturbance from cattle trampling the area. The property is not likely to yield enough data or important or new information that could be used to answer research questions. Therefore, P-48-000521 is not significant under NRHP Criterion D or CRHR Criterion 4.

#### Integrity

Integrity is based on significance: why, where, and when a property is important. Only after significance is fully established can you proceed to the issue of integrity (NPS 1995). However, a brief statement regarding the integrity of the site can be made. The property is still in its original location, which retains some of its undeveloped and rural setting. Because the original structures no longer stand, it has lost all of its integrity of design, materials, workmanship, and historic feeling. Although some element of the property's association with the surrounding landscape persists, it is mostly lost because of the removal of the original structure.

#### Conclusion

P-48-000416 does not possess historical significance under any of the evaluation criteria. The site has been significantly disturbed and little of the elements described in the original site recording exist.

Chronicle Heritage recommends the line is not eligible for inclusion in the NRHP or CRHR. An update to the DPR 523 site record can be found in Attachment D.

#### P-48-000981

P-48-000981 includes three area roadways. The collection of roads supported the transportation of goods to permanent populations in the marshlands made possible by reclamation projects during the early twentieth century. Cheryl Brookshear (2013) evaluated P-48-000981 for eligibility for listing in the NRHP and CRHR and found that P-48-000981 was not significant under any of the eligibility criteria, and was found to be ineligible for the NRHP, CRHR, or local designation through survey evaluation. An approximately 130-ft-long segment is a regularly maintained county road that passes through the Proposed API/APE. This portion of the road was revisited during the field survey for this Project (Figure 7-14). No historic or precontact artifacts were identified along the portion of Collinsville Road that intersects the Proposed API/APE. Additionally, the overall character and components of the road were consistent with the descriptions provided in Brookshear's 2013 evaluation.

The site is adjacent to the Proposed API/APE. It is not likely to be directly impacted by Project construction.



Figure 7-14. Site overview, facing east (Google Maps 2023).

## **Significance Evaluation**

Criterion A/1: Associated with events that have made a significant contribution to the broad patterns of our history.

Evaluation as eligible for NRHP listing under criterion A/1 requires the property to be associated with either (or both) of two types of events: (1) a specific event marking an important moment in American prehistory or history and (2) a pattern of events or a historic trend that made a significant contribution to the development of a community, a State, or the nation (NPS 1995). Although the roads may have been serviceable pathways for local residents, no evidence was found to link P-48-000981 to a specific event of importance in American history or to a pattern of events making a significant contribution in the development of Solano County or California. As such, the roads do not meet the threshold for historical significance under NRHP Criterion A or CRHR Criterion 1.

#### Criterion B/2: Associated with the lives of persons significant in our past.

Criterion B/2 applies to properties associated with individuals whose specific contributions to history can be identified and documented (NPS 1995). Brookshear's 2013 evaluation found the road is maintained by Solano County and is not associated with any single individual. The field identification effort for this Project did not identify associations with the portion of the road that intersects the Proposed API/APE. The road is, therefore, not found to be historically significant under NRHP Criterion B or CRHR Criterion 2.

# Criterion C/3: Embody the distinctive characteristics of a type, period, or method of construction, or that represent the work of a master, or that possess high artistic values, or that represent a significant and distinguishable entity whose components may lack individual distinction.

This criterion applies to the physical design or construction of the property, including such elements as architecture, landscape architecture, engineering, and artwork (NPS 1995). This property does not embody distinctive characteristics of a type, period, or method of construction. It does not represent the work of a master. It does not possess high artistic value. Brookshear's evaluation found that P-48-000981 exhibits common features of roads found throughout rural and urban areas and does not exhibit significance in relation to road construction (Brookshear 2013). P-48-000981 consists of a paved road that was constructed with standard materials, methods, and techniques (Brookshear 2013). No evidence demonstrating significance related to a type, period, or method of construction was observed during the field identification effort for this Project, As such, the road does not possess historical significance under NRHP Criterion C or CRHR Criterion 3.

#### Criterion D/4: Yielded, or may be likely to yield, information important in prehistory or history.

Under this criterion the property must have the potential to answer, in whole or in part, the questions posed in the research design (NPS 1995). Although the roads may be associated with early settlement, the site lacks an adequate archaeological component. The road is not likely to yield important, new information about design, construction methods, materials, or engineering that could not be ascertained through literature review or from other existing sources. No archaeological deposits were observed during the surface inspection, and any potential subsurface deposits have likely been impacted by road construction and agricultural activity. Therefore, the road is not significant under NRHP Criterion D or CRHR Criterion 4.

#### Integrity

Integrity is based on significance: why, where, and when a property is important. Only after significance is fully established can you proceed to the issue of integrity (NPS 1995). However, a brief statement regarding the integrity of the site can be made. The property is still in its original location, which retains some of its undeveloped and rural setting. Because it is not clear if the original surface of the roads exists because they have been continually maintained by the county, it has lost some of its integrity of design, materials, workmanship, and historic feeling. Some element

of the property's association with the surrounding landscape persists even though the structures fronting the roads have mostly changed through time.

#### Conclusion

The road intersecting the Proposed API/APE does not possess historical significance under any of the evaluation criteria. Therefore, a formal discussion of historical integrity is not required. Chronicle Heritage recommends the line is not eligible for inclusion in the NRHP or CRHR.

### P-07-002956

The subject property consists of two 230 kV Pacific Gas & Electric transmission lines that traverse a large swath of Contra Costa County from east to west. The site was originally recorded on December 6, 2017 by Dana E. Supernowicz, Architectural Historian, Historic Resource Associates. The site was revisited by Archaeologists Ashley Garrett and Josh Noyer of Chronicle Heritage on December 19, 2023 (Figures 7-15 and 7-16). The transmission lines appear to be unchanged since they were last recorded in 2017. The two lines were found running parallel to each other heading southeast to northwest. The two towers show signs of rusting on the support beams and "x" patterned lattice beams.

The site crosses above the Proposed API/APE It is not likely to be directly impacted by Project construction.



Figure 7-15. Overview of P-07-002956. View north.



Figure 7-16. Overview of P-074-002956. View east.

# Criterion A/1: Associated with events that have made a significant contribution to the broad patterns of our history.

Evaluation as eligible for NRHP listing under criterion A/1 requires the property to be associated with either (or both) of two types of events: (1) a specific event marking an important moment in American prehistory or history and (2) a pattern of events or a historic trend that made a significant contribution to the development of a community, a State, or the nation (NPS 1995). The Pittsburg-Tesla 230 kV Transmission Line and Contra Costa-Moraga 230kv Transmission Lines contribute to the significance of PG&E's development of electrical power and power transmission in northern California (specifically Alameda and Contra Costa Counties) in the 20th century. The need for the expansion of the electrical power supply in northern California was particularly acute during the 1920s, when the demand for electricity grew in relationship to commercial and residential development, and during the 1950s, when suburban developments sprang up in the East Bay Area after WWII (Supernowicz 2017). The transmission lines represent two important developments that connect cities in Alameda and Contra Costa County to electrical transmission grids organized around substations in Pittsburg, Tesla, and Moraga. This development and expansion of the electrical power grid was vital to the historic development in this area of California. As such, the subject property does appear to meet the threshold for historical significance under NRHP Criterion A or CRHR Criterion 1.

#### Criterion B/2: Associated with the lives of persons significant in our past.

Criterion B/2 applies to properties associated with individuals whose specific contributions to history can be identified and documented (NPS 1995). Research did not suggest that the subject property is

associated with a specific individual or group important to the history of California or beyond. The site is not historically significant under NRHP Criterion B or CRHR Criterion 2.

Criterion C/3: Embody the distinctive characteristics of a type, period, or method of construction, or that represent the work of a master, or that possess high artistic values, or that represent a significant and distinguishable entity whose components may lack individual distinction.

This criterion applies to the physical design or construction of the property, including such elements as architecture, landscape architecture, engineering, and artwork (NPS 1995). The transmission lines were designed as utilitarian electrical transmission lines, and, therefore, do not exhibit any distinctive or pioneering engineering features in the field of long electrical power transmission, or the development of electrical power in northern California (Lang 2008). However, the construction of these two lines used towers with lattice bracing and height consistent with tower design that was characteristic of the transmission tower from the 1920s through the 1940s. However, contra Supernowicz (2017), the towers do not appear to reach a level of historical significance required under NRHP Criterion C or CRHR Criterion 3.

#### Criterion D/4: Yielded, or may be likely to yield, information important in prehistory or history.

Under this criterion the property must have the potential to answer, in whole or in part, the questions posed in the research design (NPS 1995). The components used in the construction of the transmission line and its method of construction, although diagnostic for dating, are generic and are similar to components and methods used in the construction of modern transmission lines. The property is not likely to yield important, new information about design, construction methods, materials, or engineering that could not be ascertained through literature review or from other existing sources. Therefore, the site is not significant under NRHP Criterion D or CRHR Criterion 4.

#### Integrity:

For a property to be eligible for listing on the CRHR/NRHP it must retain sufficient integrity. The transmission lines appear to retain good integrity of design, materials, setting, association, and feeling, having minimal or no apparent major alterations, with the exception of upgrades to the lines and insulators (Supernowicz 2017). Therefore, the integrity of the transmission line supports the evaluation that P-07-002956 is eligible for listing in the NRHP and CRHP based on criterion A/1.

#### Conclusion

This resource is recommended eligible for inclusion in the NRHP and CRHP under criterion A/1. The historic context of the subject property is also rooted in the creation of Pacific Gas & Electric and the development of a reliable supply of electrical power throughout Contra Costa and Alameda counties during the early to mid-twentieth century. The Pacific Gas & Electric (PG&E) Company was formed in 1905 by the merger of the San Francisco Gas & Electric Company and the California Gas & Electric Company. The need for transmission lines in northern California was particularly acute during the 1920s, when the demand for electricity grew in relationship to commercial and residential development, and during the 1950s, when suburban developments sprang up in the East Bay Area (Coleman 1952; Pacific Gas & Electric Website 2017). The subject property represents two important high-lead electrical transmission grids that link cities in Contra Costa County to substations and communities to the west in western Contra Costa County. The transmission tie lines distribute power to businesses and residences throughout the region.

### **AG-001**

This newly recorded site is a historic-period artifact scatter consisting of assorted domestic materials, including kitchen appliances such as a refrigerator, oven, and water heater, construction materials such as concrete and brick fragments, and metal and glass. Generally, artifacts were observed fragmented, rusted, or broken. Two concrete postholes and pieces of two-by-four lumber were observed within the site. Historic aerial imagery (NETR 2023) does not indicate that a residence was previously constructed at the site's location. The site is approximately 67 ft north-south by 70 ft east-west (Figure 67-17 and Figure 7-18).

The site is within the Proposed API/APE. It is not likely to be directly impacted by Project construction.



Figure 7-17. Site overview, facing northeast.



Figure 7-18. Site overview, facing northwest.

# Criterion A/1: Associated with events that have made a significant contribution to the broad patterns of our history.

Evaluation as eligible for NRHP listing under criterion A/1 requires the property to be associated with either (or both) of two types of events: (1) a specific event marking an important moment in American prehistory or history and (2) a pattern of events or a historic trend that made a significant contribution to the development of a community, a State, or the nation (NPS 1995). This site is associated with a historic local occupation and likely represents a dumping episode in the mid-twentieth century. This site cannot be associated with significant events of that period. As such, the subject property does not meet the threshold for historical significance under NRHP Criterion A or CRHR Criterion 1.

#### Criterion B/2: Associated with the lives of persons significant in our past.

Criterion B/2 applies to properties associated with individuals whose specific contributions to history can be identified and documented (NPS 1995). Research did not suggest that the deposit is associated with a specific individual or group. Therefore, there is no evidence that it is linked to an individual who made an important contribution to the history of California or beyond. The site is composed of midtwentieth-century materials and is not associated with the early settlers of the nineteenth century. The site is not historically significant under NRHP Criterion B or CRHR Criterion 2.

# Criterion C/3: Embody the distinctive characteristics of a type, period, or method of construction, or that represent the work of a master, or that possess high artistic values, or that represent a significant and distinguishable entity whose components may lack individual distinction.

This criterion applies to the physical design or construction of the property, including such elements as architecture, landscape architecture, engineering, and artwork (NPS 1995). This property does not embody distinctive characteristics of a type, period, or method of construction. It does not represent the work of a master. It does not possess high artistic value. The site represents common

household items and construction materials of the mid-twentieth century that have been discarded in an open area. The deposit does not contain artifacts that embody the distinctive characteristics of a type, period, or method of construction. There are no architectural components associated with the site. As such, the building does not possess historical significance under NRHP Criterion C or CRHR Criterion 3.

#### Criterion D/4: Yielded, or may be likely to yield, information important in prehistory or history.

Under this criterion the property must have the potential to answer, in whole or in part, the questions posed in the research design (NPS 1995). Although the roads may be associated with early settlement, the site lacks an adequate archaeological component. The artifact scatter is limited in size, and artifacts were observed to be mostly discarded household appliances that cannot be associated with a particular household. It is unlikely a significant or intact subsurface archaeological deposit exists, and the area has been subject to significant disturbances. The property is not likely to yield enough data or important or new information that could be used to answer research questions. Therefore, the site is not significant under NRHP Criterion D or CRHR Criterion 4.

### Integrity

Integrity is based on significance: why, where, and when a property is important. Only after significance is fully established can you proceed to the issue of integrity (NPS 1995). However, a brief statement regarding the integrity of the site can be made. The property is still in its original location, which retains some of its undeveloped and rural setting. Because it is not associated with an original structure, it does not possess integrity of design, materials, workmanship, and historic feeling. Although some element of the property's association with the surrounding landscape persists, it lacks importance as a small discard area with no historic associations.

#### Conclusion

The site does not possess historical significance under any of the evaluation criteria. All observed artifacts were fragmented, rusted, or broken and in poor condition. Chronicle Heritage recommends the site not eligible for inclusion in the NRHP or CRHR.

#### AG-002

This resource consists of approximately 1,700 ft. of railroad segment from the Burlington Northern Santa Fe (BNSF) Railway line (Figures 7-19 and 7-20). The railway originates from the Sacramento Northern Railway and travels north-northeast with a turn to the east in the north portion of the Proposed API/APE. This segment of tracks has moderate integrity with its railroad ties and spikes still in place. The wooden railroad ties measure  $7.5 \times 7.5$  inches. The rail tracks are 4 ft. apart with an 8.5-inch gauge. This resource is largely intact. However, the rail ties are covered in sand and gravel sediment in some sections. Along the observed portion of the tracks there are three asphalt road crossings that have paved over the rail ties with the tracks still visible through the asphalt. Archival research dates this section of railroad to 1953 (USGS 1953).

The site crosses the Proposed API/APE It is not likely to be directly impacted by Project construction.



Figure 7-19. Overview of the Burlington Northern Santa Fe Railway line. View north-northeast.



Figure 7-20. Overview of the Burlington Northern Santa Fe Railway line. View south-southeast.

# Criterion 1: Associated with events that have made a significant contribution to the broad patterns of our history.

Evaluation as eligible for NRHP listing under criterion A/1 requires the property to be associated with either (or both) of two types of events: (1) a specific event marking an important moment in American prehistory or history and (2) a pattern of events or a historic trend that made a significant contribution to the development of a community, a State, or the nation (NPS 1995). The subject property is a railroad spur off of the main BNSF line that lies approximately 0.7 miles to the south. Although the main line has significance because of its connection to the development of the railroad and its impact on the history of the nation and the state, the spur line does not appear to contribute to the significance of the main line. As such, the subject property does not appear to meet the threshold for historical significance under NRHP Criterion A or CRHR Criterion 1.

#### Criterion 2: Associated with the lives of persons significant in our past.

Criterion B/2 applies to properties associated with individuals whose specific contributions to history can be identified and documented (NPS 1995). The spur first appears on the 1953 topographic maps and may be associated with the construction of the substation. This does not suggest that it is associated with a specific individual or group important to the history of California or beyond. The rail line is composed of mid-to-late twentieth-century materials and is not associated with the early settlers of the nineteenth century. The site is not historically significant under NRHP Criterion B or CRHR Criterion 2

# Criterion 3: Embody the distinctive characteristics of a type, period, or method of construction, or that represent the work of a master, or that possess high artistic values, or that represent a significant and distinguishable entity whose components may lack individual distinction.

This criterion applies to the physical design or construction of the property, including such elements as architecture, landscape architecture, engineering, and artwork (NPS 1995). This property does not embody distinctive characteristics of a type, period, or method of construction. It does not represent the work of a master. It does not possess high artistic value. The rail line appears to be constructed as a standard gauge rail, ties, and other hardware. There is nothing distinctive in the materials or methods of the construction of the rail line. As such, the building does not possess historical significance under NRHP Criterion C or CRHR Criterion 3.

#### Criterion D/4: Yielded, or may be likely to yield, information important in prehistory or history.

Under this criterion the property must have the potential to answer, in whole or in part, the questions posed in the research design (NPS 1995). The property is not likely to yield important, new information about design, construction methods, materials, or engineering that could not be ascertained through literature review or from other existing sources. Therefore, the site is not significant under NRHP Criterion D or CRHR Criterion 4.

#### Integrity

Integrity is based on significance: why, where, and when a property is important. Only after significance is fully established can you proceed to the issue of integrity (NPS 1995). However, a brief statement regarding the integrity of the spur line can be made. The property is still in its original location, which retains its industrial setting. Because it is a standard gauge spur line that is still in place, it does possess integrity of design, materials, workmanship, historic feeling, and its association with the surrounding environment persists, it lacks importance as a small spur line that may have been associated with construction of the substation. The line is no longer in use and has

not been for some time as it has been cut off from the main BNSF line and is covered over in places by sand and gravel.

#### Conclusion

In applying the National Register of Historic Places and the California Register of Historic Resources Criteria, this railway spur does not possess historical significance under any of the evaluation criteria. Chronicle Heritage recommends the line is not eligible for inclusion in the NRHP or CRHR.

#### JN-01

The site consists of a small historic domestic structure. a green, prefabricated domicile composed of metal siding, plywood, and wood framing with a tar paper roof. Windows were aluminum framed, single pane. The main structure is rectangular with dimensions of 35 feet long (positioned NE-SW) by 15 feet wide with a southeast facing wing with dimensions of 10 by 10 feet extending to the southeast of the main structure. Historic aerial imagery indicates this site was the location of a single-family property built sometime between 1957 and 1965. Ground visibility was variable, ranging from 5 to 10 percent visibility immediately around the structure to 90 percent in eroded areas east of the structure. A power pole that had been cut off at a height of about 3 ft was located east of the structure. Vegetation consisted of mostly of blackberry with low to tall grasses and weeds, including star thistle, turkey mullein, pigweed, and blindweed around the periphery. The structure is completely overgrown by blackberry bushes. The structure is positioned on a mostly flat area, on top of an embankment. The slope surrounding the structure was variable with a 5 percent slope on at the southern aspect and slopes ranging 15–30 percent towards the east. The western and northern portions were inaccessible due to blackberry overgrowth. Disturbances included possible squatting in the structure.

The site is within the Proposed API/APE. It is not likely to be directly impacted by Project construction.



Figure 7-21. Site overview, facing northeast.

# Criterion A/1: Associated with events that have made a significant contribution to the broad patterns of our history.

Evaluation as eligible for NRHP listing under criterion A/1 requires the property to be associated with either (or both) of two types of events: (1) a specific event marking an important moment in American prehistory or history and (2) a pattern of events or a historic trend that made a significant contribution to the development of a community, a State, or the nation (NPS 1995). The site is a domestic occupation structure important only to the original inhabitants. It is possibly associated with a dumping episode located to the south and recorded as AG-001 (see above). Collinsville had been well-established by the mid-twentieth century, and this site is not associated with any significant events of that period. As such, the site does not meet the threshold for historical significance under NRHP Criterion A or CRHR Criterion 1.

#### Criterion B/2: Associated with the lives of persons significant in our past.

Criterion B/2 applies to properties associated with individuals whose specific contributions to history can be identified and documented (NPS 1995). Research did not suggest that the subject property is associated with a specific individual or group important to the history of California or beyond. The site is comprised of mid-twentieth-century materials and is not associated with the early settlers of

the nineteenth century. The site is, therefore, not found to be historically significant under NRHP Criterion B or CRHR Criterion 2.

Criterion C/3: Embody the distinctive characteristics of a type, period, or method of construction, or that represent the work of a master, or that possess high artistic values, or that represent a significant and distinguishable entity whose components may lack individual distinction.

This criterion applies to the physical design or construction of the property, including such elements as architecture, landscape architecture, engineering, and artwork (NPS 1995). This property does not embody distinctive characteristics of a type, period, or method of construction. It does not represent the work of a master. It does not possess high artistic value. The site represents common household items and construction materials of the mid-20<sup>th</sup> century. The structure is a prefabricated home, and no significant architectural components are associated with the site. As such, the site does not possess historical significance under NRHP Criterion C or CRHR Criterion 3.

#### Criterion D/4: Yielded, or may be likely to yield, information important in prehistory or history.

Under this criterion the property must have the potential to answer, in whole or in part, the questions posed in the research design (NPS 1995). The site is associated with mid-20<sup>th</sup> century settlement, but the site lacks an adequate archaeological component. The site is not likely to yield important, new information about design, construction methods, materials, or engineering that could not be ascertained through literature review or from other existing sources. No archaeological deposits were observed during the surface inspection. Therefore, the site is not significant under NRHP Criterion D or CRHR Criterion 4.

#### Integrity

Integrity is based on significance: why, where, and when a property is important. Only after significance is fully established can you proceed to the issue of integrity (NPS 1995). However, a brief statement regarding the integrity of the site can be made. The property is still in its original location, which retains some of its undeveloped and rural setting. It still retains some of its integrity of design, materials, workmanship, and historic feeling. Some element of the property's association with the surrounding landscape persists.

#### Conclusion

The site does not possess historical significance under any of the evaluation criteria. Chronicle Heritage recommends the site is not eligible for inclusion in the NRHP and CRHR.

#### JN-02

The site consists of an unpaved, single-lane road that is partially graveled and travels for 1.1 miles and varies between 6-8 feet wide. The 2-track then travels southwest for approximately 100 ft and then crosses a culvert (Feature C1) that is composed of railroad ties that have been paved over with a rough aggregate concrete to create a culvert/bridge feature. The 2-track then travels towards the south along a raised (1-3 feet above the natural ground surface) track composed of fill soils that appear to be a mix of dredged soil and imported fill. Bricks and other cultural materials were observed within the fill soils of the raised portion of the track but are in a secondary context and were not recorded. The road has been poorly maintained, but frequently used with evidence of recent use and dumping at its southern terminus at site AG-001. Historic aerial imagery indicates the road was constructed sometime between 1937 and 1957. Ground visibility was variable, ranging from 5% to 10% visibility along the margins of the road corridor and up to 100% on the road surface.

Vegetation along the margins of the roadway consisted mostly of low to tall grasses and weeds, including star thistle, turkey mullein, pigweed, and blindweed. Disturbances included possible alterations to the original road alignment in sections.

The site is in the Proposed API/APE. It is not likely to be directly impacted by Project construction.



Figure 7-22. Site overview, facing east (Google Maps 2023).

## **Significance Evaluation**

# Criterion A/1: Associated with events that have made a significant contribution to the broad patterns of our history.

Evaluation as eligible for NRHP listing under criterion A/1 requires the property to be associated with either (or both) of two types of events: (1) a specific event marking an important moment in American prehistory or history and (2) a pattern of events or a historic trend that made a significant contribution to the development of a community, a State, or the nation (NPS 1995). Although the road may have been a serviceable pathway for local residents, no evidence was found to link it to a specific event of importance in American history or to a pattern of events making a significant contribution in the development of Solano County or California. As such, the road does not meet the threshold for historical significance under NRHP Criterion A or CRHR Criterion 1.

#### Criterion B/2: Associated with the lives of persons significant in our past.

Criterion B/2 applies to properties associated with individuals whose specific contributions to history can be identified and documented (NPS 1995). The road is not associated with any single individual.

The road is, therefore, not found to be historically significant under NRHP Criterion B or CRHR Criterion 2.

Criterion C/3: Embody the distinctive characteristics of a type, period, or method of construction, or that represent the work of a master, or that possess high artistic values, or that represent a significant and distinguishable entity whose components may lack individual distinction.

This criterion applies to the physical design or construction of the property, including such elements as architecture, landscape architecture, engineering, and artwork (NPS 1995). This property does not embody distinctive characteristics of a type, period, or method of construction. It does not represent the work of a master. It does not possess high artistic value. The road exhibits common features of unpaved roads found throughout rural areas and does not exhibit significance in relation to road construction. The road consists of an unpaved road that was not constructed with standard materials, methods, and techniques. No evidence demonstrating significance related to a type, period, or method of construction was observed during the field identification effort for this Project. As such, JN-02 does not possess historical significance under NRHP Criterion C or CRHR Criterion 3.

#### Criterion D/4: Yielded, or may be likely to yield, information important in prehistory or history.

Under this criterion the property must have the potential to answer, in whole or in part, the questions posed in the research design (NPS 1995). Although the roads may be associated with early settlement, the site lacks an adequate archaeological component. The road is not likely to yield important, new information about design, construction methods, materials, or engineering that could not be ascertained through literature review or from other existing sources. No archaeological deposits were observed during the surface inspection, and any potential subsurface deposits have likely been impacted by road construction and agricultural activity. Therefore, the JN-02 is not significant under NRHP Criterion D or CRHR Criterion 4.

#### Integrity

Integrity is based on significance: why, where, and when a property is important. Only after significance is fully established can you proceed to the issue of integrity (NPS 1995). However, a brief statement regarding the integrity of the site can be made. The property is still in its original location, which retains some of its undeveloped and rural setting. Because it is not clear if the original surface of the roads exists because they have been continually maintained by the county, it has lost some of its integrity of design, materials, workmanship, and historic feeling. Some element of the property's association with the surrounding landscape persists even though the structures fronting the roads have mostly changed through time.

#### Conclusion

JN-02 does not possess historical significance under any of the evaluation criteria. Chronicle Heritage recommends the site is not eligible for inclusion in the NRHP and CRHR.

#### Stratton Lane

The site consists of an unpaved, gravel road that travels for 6.4 miles and varies between 10-16 feet wide. Two segments were recorded totaling 1.4 miles. Much of the road corridor is bound on at least one side by barbed wire fencing with the road easement approximately 35-40 feet in width. The first segment (Segment 1) is a two-lane graveled road that travels east (Figure 7-23). The road segment

(Segment 1) then narrows to a single-lane and turns south for 0.4 miles gently curving towards the southeast. The second segment (Segment 2) of the original road alignment picks up 1000 feet to the southeast; then continues towards the east as a single-land dirt road. Only the western most 1000 feet of segment 2 was recorded. The road has been well maintained with evidence of periodic grading and re-gravelling; especially, in the north/western most portion. Ground visibility was variable, ranging from 5% to 10% visibility along the margins of the road corridor and up to 100% on the road surface. Vegetation along the margins of the roadway consisted mostly of low to tall grasses and weeds, including star thistle, turkey mullein, pigweed, and blindweed. Disturbances included possible alterations to the original road alignment in sections.

The site crosses much of the Proposed API/APE. Portions of it are likely to be directly impacted by Project construction of the LSPGC substation.



Figure 7-23. Overview of Stratton Lane, segment 1, view east.

## **Significance Evaluation**

# Criterion A/1: Associated with events that have made a significant contribution to the broad patterns of our history.

Evaluation as eligible for NRHP listing under criterion A/1 requires the property to be associated with either (or both) of two types of events: (1) a specific event marking an important moment in American prehistory or history and (2) a pattern of events or a historic trend that made a significant contribution

to the development of a community, a State, or the nation (NPS 1995). Although the road may have been a serviceable pathway for local residents, no evidence was found to link Stratton Lane to a specific event of importance in American history or to a pattern of events making a significant contribution in the development of Solano County or California. As such, the roads does not meet the threshold for historical significance under NRHP Criterion A or CRHR Criterion 1.

### Criterion B/2: Associated with the lives of persons significant in our past.

Criterion B/2 applies to properties associated with individuals whose specific contributions to history can be identified and documented (NPS 1995). Stratton Lane is maintained by Solano County and is not associated with any single individual. The field identification effort for this Project did not identify associations with the portion of Stratton Lane that intersects the Proposed API/APE. Stratton Lane is, therefore, not found to be historically significant under NRHP Criterion B or CRHR Criterion 2.

Criterion C/3: Embody the distinctive characteristics of a type, period, or method of construction, or that represent the work of a master, or that possess high artistic values, or that represent a significant and distinguishable entity whose components may lack individual distinction.

This criterion applies to the physical design or construction of the property, including such elements as architecture, landscape architecture, engineering, and artwork (NPS 1995). This property does not embody distinctive characteristics of a type, period, or method of construction. It does not represent the work of a master. It does not possess high artistic value. Stratton Lane exhibits common features of roads found throughout rural and urban areas and does not exhibit significance in relation to road construction (Brookshear 2013). Stratton Lane consists of an unpaved gravel road that was constructed with standard materials, methods, and techniques for basic utilitarian use. No evidence demonstrating significance related to a type, period, or method of construction was observed during the field identification effort for this Project. As such, Stratton Lane does not possess historical significance under NRHP Criterion C or CRHR Criterion 3.

### Criterion D/4: Yielded, or may be likely to yield, information important in prehistory or history.

Under this criterion the property must have the potential to answer, in whole or in part, the questions posed in the research design (NPS 1995). Although the roads may be associated with early settlement, the site lacks an adequate archaeological component. Stratton Lane is not likely to yield important, new information about design, construction methods, materials, or engineering that could not be ascertained through literature review or from other existing sources. No archaeological deposits were observed during the surface inspection, and any potential subsurface deposits have likely been impacted by road construction and agricultural activity. Therefore, Stratton Lane is not significant under NRHP Criterion D or CRHR Criterion 4.

### Integrity

Integrity is based on significance: why, where, and when a property is important. Only after significance is fully established can you proceed to the issue of integrity (NPS 1995). However, a brief statement regarding the integrity of the site can be made. The property is still in its original location, which retains some of its undeveloped and rural setting. Because it is not clear if the original surface of the roads exists because they have been continually maintained by the county, it has lost some of its integrity of design, materials, workmanship, and historic feeling. Some element of the property's association with the surrounding landscape persists even though the structures fronting the roads have mostly changed through time.

### Conclusion

Stratton Lane does not possess historical significance under any of the evaluation criteria. Chronicle Heritage recommends the site is not eligible for inclusion in the NRHP and CRHR.

### JN-04

The site consists of four (n=4) powerline poles (Features P1, P2, P3, and P4) (Figure 7-23). The southern termination of the recorded powerline is located at a cut power transmission pole (P1), which once provided power to a residential structure (site JN-001) dating to between 1957 and 1965. The power pole is approximately 24 inches in diameter at the cut and the cut is approximately 28-36 inches above the ground surface. A second power transmission pole (P2) was identified approximately 1500 ft to the north of P1. The pole is positioned south of where an east to west draining modern culvert 30 feet to the north of the pole. Pole P2 is largely complete and is approximately 20 feet tall and 18-24 inches in diameter with an intact, galvanized steel guy wire anchored 8 feet to the southwest of the pole. Power pole P3 is located approx. 500 feet to the north of P2. The main pole of P3 is largely intact but exhibits signs of burning/fire damage that possibly resulted from a lightning strike, surrounding fire, or electrical damage. Pole P3 is approx. 20 feet tall and varies in diameter from 18-24 inches. Whole and broken ceramic insulators, metal attachment hardware and 2 by 4 inch wood cross beams were identified approximately 5-10 feet northeast of P3. Power pole P4 is cut approximately 30-36 inches above the ground surface and is approximately 20-24 inches in diameter.

Ground visibility was variable, ranging from 5% to 10% visibility at poles P2, P3 and P4, with up to 100% at P1. Vegetation around the pole locations consisted mostly of low to tall grasses and weeds, including star thistle, turkey mullein, pigweed, and blindweed. Disturbances included possible fire alterations.

The site is in the Proposed API/APE along Stratton Lane just south of the 230 kV transmission line towers 1/2 and 1/3 (Figure 1 in Attachment 5; Figure 1-10). Portions of it are likely to be directly impacted by Project construction of the LSPGC substation.



Figure 7-23. View of Pole P2 with P3 to north, facing northwest.

### **Significance Evaluation**

# Criterion A/1: Associated with events that have made a significant contribution to the broad patterns of our history.

Evaluation as eligible for NRHP listing under criterion A/1 requires the property to be associated with either (or both) of two types of events: (1) a specific event marking an important moment in American prehistory or history and (2) a pattern of events or a historic trend that made a significant contribution to the development of a community, a State, or the nation (NPS 1995). Although the powerline may have been a necessary utility for the residents of house JN-01 (see above), no evidence was found to link this local powerline to a specific event of importance in American history or to a pattern of events making a significant contribution in the development of Solano County or California. As such, the powerline does not meet the threshold for historical significance under NRHP Criterion A or CRHR Criterion 1.

### Criterion B/2: Associated with the lives of persons significant in our past.

Criterion B applies to properties associated with individuals whose specific contributions to history can be identified and documented (NPS 1995). The powerline is not associated with any single individual. The field identification effort for this Project did not identify residents of the house JN-01 that appears to have been served by the powerline. The powerline is, therefore, not found to be historically significant under NRHP Criterion B or CRHR Criterion 2.

# Criterion C/3: Embody the distinctive characteristics of a type, period, or method of construction, or that represent the work of a master, or that possess high artistic values, or that represent a significant and distinguishable entity whose components may lack individual distinction.

This criterion applies to the physical design or construction of the property, including such elements as architecture, landscape architecture, engineering, and artwork (NPS 1995). This property does not embody distinctive characteristics of a type, period, or method of construction. It does not represent the work of a master. It does not possess high artistic value. The powerline consists of standard wooden poles that carry powerlines to residential locations. These are common features of residential structures in both rural and urban areas, and the features do not exhibit significance in relation to the development of power in the area. The powerline was constructed with standard materials, methods, and techniques for basic utilitarian use. No evidence demonstrating significance related to a type, period, or method of construction was observed during the field identification effort for this Project. As such, the powerline does not possess historical significance under NRHP Criterion C or CRHR Criterion 3.

### Criterion D/4: Yielded, or may be likely to yield, information important in prehistory or history.

Under this criterion the property must have the potential to answer, in whole or in part, the questions posed in the research design (NPS 1995). The powerline appears to be associated with a small mid-20<sup>th</sup> century residence. It lacks an adequate archaeological component. The powerline is not likely to yield important, new information about design, construction methods, materials, or engineering that could not be ascertained through literature review or from other existing sources. No archaeological deposits were observed during the surface inspection, and any potential subsurface deposits likely do not exist. Therefore, the powerline is not significant under NRHP Criterion D or CRHR Criterion 4.

### Integrity

Integrity is based on significance: why, where, and when a property is important. Only after significance is fully established can you proceed to the issue of integrity (NPS 1995). However, a brief statement regarding the integrity of the site can be made. The property is still in its original location, which retains some of its undeveloped and rural setting. Because the powerline has largely been dismantled, it has lost some of its integrity of design, materials, workmanship, and historic feeling. Some element of the property's association with the surrounding landscape persists.

### Conclusion

The site does not possess historical significance under any of the evaluation criteria. Chronicle Heritage recommends the site is not eligible for inclusion in the NRHP and CRHR.

# **Discussion and Interpretation**

# Precontact Archaeology in the Proposed API/APE

No intact Precontact archaeological deposits were discovered in the Project survey area or Proposed API/APE during the archaeological survey for the Project. However, there is some evidence that precontact activity did in fact occur with the Proposed API/APE. When the archaeological site P-48-000041 was originally recorded it was reported that there had been a precontact campsite near the Hastings' Adobe on a small knoll that contained some projectile points (Elsasser 1956). Even at that time the deposit had mostly been destroyed either through looting or erosion, and Elsasser reports the area had been covered with sand. It is unclear if any of this deposit

remains buried on site or not. The only other evidence of precontact use of the area was the discovery of an isolated obsidian biface as part of site P-48-000139.

These finds show that the area was used by precontact peoples. However, due to the meager finds very little can be learned about the precontact people of this area. It is not surprising that they were making use of the areas along the river where a lot of natural resources could be found, especially food sources such as fish, water plants, etc. that they could use to complement their diets as part of their subsistence. Unfortunately, no evidence of the specific resources was found during Project investigations. The presence of obsidian shows some contact with obsidian sources either through trade or travel to these areas such as those in Napa Valley or the eastern Sierras.

# Historic-era Archaeology in the Proposed API/APE

Historic-era sites identified during the archaeological survey include eleven associated with ranching and homesteading, two roads, a railroad spur, and transmission lines. Both the railroad spur (AG-002) that serviced the power substation and the transmission lines (P-7-002956) are part of the development of the electric grid that was expanded after WWII to service the growing urbanization of the wider Bay Area. Two sites (P-48-000981 and JN-02) are the roadways that were established in and around the Collinsville area as part of the development of ranching and other light industries (e.g., fishing and canning), and the sporadic residential development of the area. Eleven sites (P-48-000041, P-48-000124, P-48-000125, P-48-000128, P-48-000139, P-48-000140, P-48-000416, P-48-000521, AG-001, JN-01, and JN-04) are associated with ranching or homesteading. Of the sixteen sites only P-07-002956, the Contra Costa-Moraga/Pittsburg-Tesla PG&E Electrical Transmission Lines, is recommended as eligible for the CRHR because of its association with the development of the electric grid in California.

The archaeological record in the Proposed API/APE contributes evidence of primarily ranching. Even though the ranching and homesteading sites are not being recommended as eligible for the CRHR, they still offer some information for addressing research questions about the ranching and homesteading use of the Proposed API/APE. This is especially true of the Hasting's Adobe (P-48-00041) which was the first ranch house built in the area in the hopes of attracting Mormon settlers. Because of the Bear Flag Rebellion in 1846, the plan to settle Mormon immigrants on the Project Proposed API/APE was abandoned. The attempted establishment of a Mormon settlement here showed that the area was considered a good location for a settlement due to the proximity to the river and the abundant grasslands available for running cattle.

Most of the other historic ranching features in the Proposed API/APE have been destroyed by subsequent use of the area for agriculture and wind power. These features include foundations, fence lines, ditches, reservoirs, structures such as corrals, and associated refuse. They still are indications of the use of the Proposed API/APE for raising and herding livestock. The use of corrals indicates that livestock were round up and held to be managed in some way, such a branding, doctoring, or shipping to market.

The sites with evidence of water conveyance and storage, such as stock tanks, are directly related to providing water to herds. No substantial evidence of water management was discovered during the archaeological survey. This sort of activity is characterized by dams, spring boxes, large ditches fed by river water, or wells that were dug to the aquifer to provide water in concert with windmills. From the findings of the survey, only one water well was identified: a well was identified on P-48-000125, but it was outfitted with a modern water pump so the age of the well could not be determined, and it was unclear if the well was ever associated with a windmill. So, the research question regarding water maintenance in the area could not be addressed fully by the extant ranch features.

Regarding the research question about whether the roads are associated with ranching in the area there is no direct evidence that the roads were developed specifically as part of ranch operations. A segment of Stratton Lane (JN-02) that ended at the adobe house may mark a portion of and original track into the area. The other roads provide access into the Proposed API/APE and were probably used to access many of the home sites there and were not developed as part of the ranching industry.

There is no discernible relationship of the ranching features to the railroads and transmission lines present in the Proposed API/APE. The railroad spur (AG-002) and the transmission lines (P-7-002956) are both associated with the Pittsburg substation and date to the expansion of the electric grid after WWII.

All of the artifact scatters found at the various ranch or house sites were highly disturbed and contained almost no diagnostic elements. Those that did appear to be mid-20th century or later. They offer little information about the household members who lived in these residences and are not useful for addressing any of the questions presented in the research design. The most that can be said is that they appear to be typical domestic items such as tableware, ceramic, glassware, and other household items. In addition, none of the resources identified during the survey may warrant discussion of additional research topics not included in the research design.

# **Summary and Recommendations**

Chronicle Heritage completed a records search, literature review, Native American consultation, terrestrial archaeological survey, resource evaluations, and maritime submerged survey in support of the Collinsville 500/230 kilovolt (kV) Substation Project in Contra Costa, Solano, and Sacramento Counties, California. This cultural resource assessment resulted in the identification six new sites: AG-001, a historic-period artifact scatter; AG-002, a spur of the Burlington Northern Santa Fe Railway; JN-01, a small historic domestic structure; JN-02, an unpaved, single-lane road; Stratton Lane, of a partially paved and partially unpaved, gravel road; and JN-04, four powerline poles marking a historic powerline. Additionally, ten previously recorded resources were updated as part of the cultural resource assessment, including eight within the Proposed API/APE and two adjacent to the Proposed API/APE. Only P-07-002956 of the sixteen new or previously recorded cultural resources within or adjacent to the Proposed API/APE is recommended eligible for the NRHP or the CRHR. Chronicle Heritage recommends that the Proposed Project will not adversely affect the NRHP-nominated property (P-48-000041) adjacent to the Proposed API/APE.

### **Inadvertent Discoveries**

There is potential for the discovery of unanticipated archaeological materials during Project-related ground disturbance, such as clearing, grading, excavation, and/or general construction within the Proposed API/APE. Work at the location of the find will halt immediately within 50 ft of the find. If an archaeologist is not present at the time of the discovery, then the applicant shall contact an archaeologist for evaluation of the find to determine whether it qualifies as significant under CEQA.

If the find is determined not to be a unique archaeological resource (or significant under CEQA), construction can continue. The archaeologist will prepare a brief informal memorandum/letter that describes and assesses the significance of the resource, including a discussion of the methods used to determine the significance of the find.

- If the find appears to be significant and qualifies as a unique archaeological resource (or significant under CEQA), the archaeologist will determine if the resource can be avoided and will detail avoidance procedures in a formal memorandum/letter.
- If the resource cannot be avoided, the archaeologist shall develop an action plan to avoid or minimize impacts. The field crew shall not proceed until a Secretary of the Interior-qualified archaeologist approves the action plan. The action plan shall be in conformance with California PRC 21083.2.

# **Inadvertent Discovery of Human Remains**

Although unlikely, unanticipated human remains, including those interred outside formal cemeteries, may be encountered during Project ground disturbance in many locations throughout California. Section 7050.5(b) of the California Health and Safety Code will be implemented if human remains, or possible human remains, are located during Project-related construction excavation. Section 7050.5(b) states:

In the event of discovery or recognition of any human remains in any location other than a dedicated cemetery, there shall be no further excavation or disturbance of the site or any nearby area reasonably suspected to overlie adjacent remains until the coroner of the county in which the human remains are discovered has determined, in accordance with Chapter 10 (commencing with Section 27460) of Part 3 of Division 2 of Title 3 of the Government Code, that the remains are not subject to the provisions of Section 27492 of the Government Code or any other related provisions of law concerning investigation of the circumstances, manner and cause of death, and the recommendations concerning treatment and disposition of the human remains have been made to the person responsible for the excavation, or to their authorized representative, in the manner provided in PRC Section 5097.98.

Upon recognizing the remains as being of Native American origin, the Contra Costa, Solano, or Sacramento County Coroner(s) will contact the NAHC within 24 hours. Once NAHC identifies the most likely descendant/s, the descendants will make recommendations regarding proper burial, which will be implemented in accordance with Section 15064.5(e) of the CEQA Guidelines. All actions taken under this mitigation measure shall comply with Health and Human Safety Code § 7050.5(b).

# **Preparer Qualifications**

Chronicle Heritage Senior Archaeologist and Project Manager Maximilian van Rensselaer meets the Secretary of the Interior's professional qualification standards for Archaeology and has more than nine years of experience supervising and conducting cultural resource investigations, authoring and editing cultural resource reports, and managing field and office staff in multiple states. He is skilled in conducting cultural resource investigations for CEQA, Section 106 of the NHPA, and National Environmental Policy Act desktop analysis.

Chronicle Heritage Senior Archaeologist and Project Manager Allen Estes meets the Secretary of the Interior's professional qualification standards for Archaeology and has more than 25 years of experience supervising archaeological projects, including the management of surveys, excavation, construction monitoring, artifact analysis, curation, and technical reporting. He has guided clients through CEQA compliance for issues pertaining to cultural resources and has worked on projects

under the oversight of local and state agencies such as the City and County of San Francisco Planning Department, Caltrans, and San Francisco Public Utilities Commission.

Chronicle Heritage Associate Archaeologist and Lab Director Rachael Irwin earned a Bachelor of Arts in Anthropology from California State University, Chico, and has more than five years of experience conducting archaeological survey, excavation, and laboratory analysis. She is skilled in Native American consultation and coordination, identification of human remains, and macrobotanical analysis.

Chronicle Heritage Associate Archaeologist Ashley Garrett possesses a Bachelor of Arts in Anthropology and has eight years of experience conducting archaeological field studies, supervising field crews, and processing artifacts for curation across Northern California and Washington state. She also has two years of experience in conducting background research for cultural resource investigations and writing cultural resource reports for both the CEQA and Section 106 of the NHPA. She is skilled in team leadership, project coordination, and implementing cultural resource protection measures for CEQA and Section 106 projects.

# References

### Arnold, Jeanne E. and Michael R. Walsh

2010 California's Ancient Past: From Pacific to the Range of Light. University Press of Colorado.

### Atwater, Brian. F.

1982 Geologic maps of the Sacramento-San Joaquin Delta, California. No. 1401. U.S. Government Printing Office.

### Barrette, Samuel, A.

1908 The Ethno-Geography of the Pomo and Neighboring Indians. In *University of California Publications in American Archaeology and Ethnology*. Vol. 6, No. 1. University of California Press, Berkeley, California.

### Baldridge, Kenneth Wayne

A history of the Mormon settlement of central California with emphasis on New Hope and San Francisco, 1846-1847, and Modesto, 1920-1954. M. A. Thesis, University of Pacific. Electronic document: https://scholarlycommons.pacific.edu/uop\_etds/1326/. Accessed June 17, 2024.

### Beardsley, Richard K.

1954 Temporal and Areal Relationships in Central California Archaeology. *University of California Archaeological Survey Reports 24 and 25*. Reports of the University of California Archaeological Survey. Berkeley.

### Beeler, Madison S.

1955 Saclan. In International Journal of American Linguistics, Vol.21, No.3, pp. 201–209. University of Chicago Press, Chicago, Illinois.

### Bennyhoff, James

1961 Ethnogeography of the Plains Miwok. Unpublished Ph.D. Dissertation. University of California Berkeley.

### Bennyhoff, James A., and Richard E. Hughes

1987 Shell Bead Ornament Exchange Networks between California and the Western Great Basin. Anthropological Papers of the American Museum of Natural History 64 (2):79–175. Washington, DC.

### **Best Places**

2024 Solano CA Climate. Electronic document:

https://www.bestplaces.net/climate/county/california/solano. Accessed June 19, 2024.

### Boehle, Richard

2013 Interurban Electric Railways in Northern California and the Central Valley, Railwest.com. Web site copyright 2002-2013, DigitalNetExpress.com, Burbank, California

### Bowen, Jerry

Township began with Mormon colony site. *Historical Articles of Solano County, Online Database*. July 10, 2000, https://www.solanoarticles.com/history/index.php/weblog/more/township\_began\_with\_mormon\_colony\_site/, accessed October 2023.

### Brookshear, Cheryl and Herbert Rand

2013 Suisun Marsh Cultural Resources Contextual Report, Volume II. JRP Historical Consulting, LLC, Davis, California. Submitted to U.S. Bureau of Reclamation.

### California Geological Survey (CGS)

2002 California Geomorphic Provinces: Sacramento, California Geological Survey, California Department of Conservation, Note No. 36, 4 p.,

https://www.conservation.ca.gov/cgs/Documents/Publications/CGS-Notes/CGS-Note-36.pdf (accessed October 2023).

### California Soil Resources Lab (CSRL)

2023 California Soil Resources Lab Google Earth Layer. Electronic document, http://casoil resource.lawr.ucdavis.edu/soil\_web/ssurgo.php, accessed January 2023.

### Cappiella, K., C. Malzone, R. Smith, and B. Jaffe

1999 Sedimentation and bathymetry changes in Suisun Bay: 1867-1990. U.S. Geological Survey Open-File Report 99-563, https://pubs.usgs.gov/publication/ofr99563 (accessed October 2023).

### City of Pittsburg

Old Town Path of History. Electronic document: https://storymaps.arcgis.com/stories/432e3c43819a4a17bb5c3af540d2c42c. Accessed June 18, 2024.

### Clifford, Heather

2024 Paleontological Resource Technical Memorandum for the Collinsville 500/230 kV Substation Project, Sacramento River Delta Region in Contra Costa, Solano, and Sacramento Counties, California. Prepared for Insignia Environmental, Menlo Park, CA. Prepared by Chronicle Heritage, Sacramento, CA.

### Coleman, Charles M.

1952 P.G. and E. of California: The Centennial Story of Pacific Gas and Electric Company 1852-1952. New York: McGraw-Hill Book Company, Inc. 1952; Garcia & Associates.

### Contra Costa County

- 2010 [2005] Contra Costa County General Plan. Report digitally on file, https://www.contra costa.ca.gov/4732/General-Plan, accessed September 2023.
- 2022 Our County. Contra Costa County, California. Electronic resource, https://www.contracosta.ca.gov/31/Our-County#:~:text=The%20most%20notable%20landmark%20in, residents%20and%20visitors%20can%20enjoy, accessed November 2023.

### Cook, Sherburne F.

The Aboriginal Population of Alameda and Contra Costa Counties, California. In University of California Anthropological Records, Vol. 16, No.4, pp. 131-156. University of California Press, Berkeley and Los Angeles, California.

### Crist, M., J. Brady and R. Goode

1980 Site record for P-24-000124 (CA-SOL-283H). On file at the Northwest Information Center.

### Davis, Hon Win, J.

1890 An Illustrated History of Sacramento County, California. The Lewis Publishing Company, Chicago.

### Dickinson, W.R.

Plate tectonics and the continental margin of California, in Ernst, W.G. ed., The geotectonic development of California, Englewood Cliffs, New Jersey, Prentice-Hall, Rubey volume 1, p. 1–28.

### Eager, Edward N.

1890 Official Map of the County of Solano, California. Compiled by E. N. Eager, County, Surveyor.

### Eckbo, Dean, Austin and Williams (EDAW)

2008 Draft Environmental Impact Report, Solano County 2008 Draft General Plan. Prepared for County of Solano, Resource Management Department, April 18, 2008. Electronic document, https://www.solanocounty.com/civicax/filebank/blobdload.aspx?

BlobID=15179, accessed October 2023.

### Elsasser, A. B.

1956 Archaeological Site Survey Record. CA-SOL-33. Sacramento State College.

### Farris, Glen, Kathleen Davis, and John McAleer

1988 The John Marsh Stone House Project. Unpublished study available through California State Parks and Recreation, Sacramento, CA.

### FindAGrave

2023 Charles Dadami. Electronic resource, https://www.findagrave.com/memorial/113422032/charles-dadami, accessed November 2023.

### Fredrickson, David A.

- 1968 Archaeological Investigation at CCO-30, near Alamo, Contra Costa County, California. Center for Archaeological Research at Davis. Vol. 1. On file at the University of California, Davis.
- 1973 Early Cultures of the North Coast Ranges. Ph.D. Dissertation. Department of Anthropology. University of California, Davis.
- 1974 Cultural Diversity in Early Central California: A View from the North Coast Ranges. Journal of California Anthropology 1(1):41–53.
- 1994 Archaeological Taxonomy in Central California Reconsidered. In *Toward a New Taxonomic Framework for Central California Archaeology: Essays by James A. Bennyhoff and David A. Fredrickson*, Richard E. Hughes, editor, pp. 91-103. Contributions of the University of California Archaeology Research Facility 15. Berkeley.

### General Land Office (GLO)

Survey Plat Map for Township 2 North, Range 1 East, Mount Diablo Meridian. Electronic resource, https://www.google.com/maps/@38.0817541,-121.8531263,15.75z?entry=ttu, accessed October 2023.

### Golla, Victor

2011 California Indian Languages. University of California Press, Berkeley.

### Google Maps

2023 Intersection of Collinsville Road and Stratton Lane. Electronic resource, https://www.google.com/maps/@38.0817541,-121.8531263,15.75z?entry=ttu, accessed October 2023.

### Graymer, R.W., D.L. Jones, and E.E. Brabb,

2002 Geologic map and map database of northeastern San Francisco Bay region, California: Most of Solano County and parts of Napa, Marin, Contra Costa, San Joaquin, Sacramento, Yolo, and Sonoma Counties: Reston, Virginia, U.S. Geological Survey, Miscellaneous Field Studies Map No. 2403, doi:10.3133/mf2403.

### Groza, R.G.

2002 An AMS chronology for central California *Olivella* shell beads. Unpublished Master's thesis. Department of Anthropology, San Francisco State University, San Francisco, CA.

### Gudde, Erwin G.

1998 California Place Names: The Origin and Etymology of Current Geographical Names. Revised and enlarged by William Bright. 4<sup>th</sup> ed. University of California Press. Berkeley and Los Angeles, California.

### Heizer, Robert F., and Thomas R. Hester

1970 Names and Locations of Some Ethnographic Patwin and Maidu Indian Villages.
Contributions of the University of California Archaeological Research Facility 9: pp. 79118. Electronic document https://escholarship.org/uc/item/0tj64363. Accessed June
11, 2024.

### Helley, E. J. and R. W. Graymer

1998 Quaternary Geology of Contra Costa County, and Surrounding Parts of Alameda, Marin, Sonoma, Sacramento, and San Joaquin Counties, California: A Digital Database. U.S. Geological Survey, Open File Report.

### Historic Resource Associates

2017 P-07-002956, Department of Parks and Recreation Record, Contra Costa-Moraga/Pittsburg-Telsa PG&E Electrical Transmission Lines. Prepared by Historic Resource Associates. Submitted to the State of California – Resources Agency, Department of Parks and Recreation.

### Hoffman, Ogden

Reports of Land Cases Determined in the United States District Court, Northern District of California, Volume 1, Ogden Hoffman, District Judge. Report on file digitally at California State University, Monterey Bay, Digital Commons, Monterey, California.

### Kamiya, Gary

2014 Cursed ship San Carlos' luck turns: 1st to sail into S.F. Bay. *SF Gate*, August 15, 2014. Electronic document, https://www.sfgate.com/bayarea/article/Cursed-ship-San-Carlos-luck-turns-1st-to-sail-5692069.php, accessed October 2023.

### Kozakavich, Stacy C.

The Archaeology of Utopian and Intentional Communities, University Press of Florida, ISBN14: 9780813068978.

### Kroeber, Alfred L.

1925 Handbook of the Indians of California. Smithsonian Institution, Bureau of American Ethnology Bulletin 78. Washington Government Printing Office, Washington, D.C.

- 1932 The Patwin and their Neighbors. In *University of California Publications of American Archaeology and Ethnology*. Vol. 29, No. 4, pp. 253–423. University of California Press, Berkeley, California.
- 1970 Handbook of the Indians of California. California Book Company. Berkeley, California.

### Krug, E.H., V.B. Cherven, C.W. Hatten, and J.C. Roth

Subsurface structure in the Montezuma Hills, southwestern Sacramento basin, in Cherven, V.B., and Edmondson, W.F., eds., Structural Geology of the Sacramento Basin: Volume MP-41, Annual Meeting, Pacific Section, Society of Economic Paleontologists and Mineralogists, p. 41-60.

### Kyle, Douglas E.

1990 Historic Spots in California. 4th edition. Originally authored by Mildred Brooke Hoover, Hero Eugene Rensch, Ethel Grace Rensch and William N. Abeloe. Stanford University Press, Stanford, CA.

### Lang, Jennifer

2008 Site record for P-07-002956, On file at the Northwest Information Center.

### Levy, Richard

1978 Eastern Miwok. In *California*, edited by R.F. Heizer, pp. 398–413. Handbook of North American Indians Vol.8, William C. Sturtevant, general editor. Smithsonian Institution, Washington, D.C.

### Johnson, Patti J.

1978 Patwin. In *California*, edited by R.F. Heizer, pp. 350–360. Handbook of North American Indians Vol.8, William C. Sturtevant, general editor. Smithsonian Institution, Washington, D.C.

### Journal of American History (JAH)

2005 Mexican California. In California as I Saw It: First-Person Narratives of California's Early Years, 1849-1900. *Journal of American History* 92(1):324-325. Electrontic document, https://www.loc.gov/collections/california-first-person-narratives/articles-and-essays/early-california-history/mexican-california/, accessed October 2023.

### Lillard, Jeremiah B., Robert F. Heizer, and Franklin Fenenga

1939 An Introduction to the Archeology of Central California. Sacramento Junior College Department of Anthropology Bulletin 2. Sacramento, California.

### Lillard, Jeremiah B., and William K. Purves

1936 The Archaeology of The Deer-Creek-Consumnes Area. Sacramento Co., California. Sacramento Junior College Department of Anthropology. Bulletin 1.

### Maniery, G., R. Goode and J. Brady

1980 Site record for P-24-000128 (CA-SOL-287H). On file at the Northwest Information Center.

### McLusky, D.S.

The Estuarine Ecosystem: Ecology, Threats, and Management: Honiton, UK, Blackie, 224 p.

### McCullough, David

2022 Contra Costa County History. Conta Costa County Historical Society. Electronic document, https://www.cocohistory.org/contra-costa-county-history, accessed November 2023.

### McKern, W. C.

- 1922 Functional Families of the Patwin. In *University of California Publications of American Archaeology and Ethnology.* Vol 13, No.7, pp. 236–258. University of California Press, Berkeley, California.
- 1923 Patwin Houses. In University of California Publications of American Archaeology and Ethnology. Vol 20, pp. 159–171. University of California Press, Berkeley, California.

### McPhate, Mike

When San Francisco was a Mormon town. Electronic Document: https://www.californiasun.co/when-san-francisco-was-a-mormon-town/. Accessed June 17, 2024.

Meyer, Jack, Julia Costello, Patricia Mikkelsen, Melissa Johnson, and Naomi Scher

Volume I – Archaeological Resources; Suisun Marsh Habitat Management, Preservation, and Restoration Place Cultural Resources Contextual Report. Prepared by Far Western Anthropological Research Group, Inc. Submitted to Bureau of Reclamation, Mid Pacific Region December 2013. Report digitally available online.

### Meyer, Jack and Jeffrey S. Rosenthal

1997 Archaeological and Geoarchaeological Investigations at Eight Prehistoric Sites in the Los Vaqueros Reservoir Area, Contra Costa County, California. Anthropological Studies Center, Sonoma State University Academic Foundation, Rohnert Park, California. Submitted to the Contra Costa Water District, Concord, California. On file at the Northwest Information Center, Sonoma State University, Rohnert Park, CA (S-020072).

Milliken, Randall, Richard T. Fitzgerald, Mark G. Hylkema, Randy Groza, Tom Origer, David G. Bieling, Alan Leventhal, Randy S. Wiberg, Andrew Gottsfield, Donna Gillette, Viviana Bellifemine, Eric Strother, Robert Cartier and David A. Fredrickson

2007 Punctuated Culture Change in the San Francisco Bay Area. In *California Prehistory: Colonization, Culture, and Complexity*, Terry L. Jones and Kathryn A. Klar, editors, pp. 99-123. Altamira Press, Lanham, MD.

### Moratto, Michael J.

1984 California Archaeology. Academic Press, Orlando, Florida.

### Nationwide Environmental Title Research (NETR)

2023 Historic Aerials of APE. Electronic resource, http://historicaerials.com/viewer, accessed October 2023.

### National Park Service (NPS)

How to Apply the National Register Criteria for Evaluation. National Register Bulletin 15. Electronic document: chrome-extension://efaidnbmnnnibpcajpcglclefindmkaj/https://www.nps.gov/subjects/nationalregister/upload/NRB-15\_web508.pdf. Accessed June 20, 2024.

2022 Bear Flag Revolt, June 1846. Electronic document: https://www.nps.gov/goga/learn/historyculture/bear-flag-revolt.htm. Accessed June 17, 2024.

2023 Abandoned Shipwreck Act of 1987. Electronic document: https://www.nps.gov/subjects/archeology/abandoned-shipwreck-act.htm. Accessed June 24, 2024.

### Nelson, Nels C.

1909 Shellmounds of the San Francisco Bay Region. In *University of California Publications*American Archaeology and Ethnology, Vol.7, No.4, pp. 309–356. University of California Press, Berkeley, California.

### Pacific Gas & Electric

2017 Website. "History." www.pge.com, accessed December 2017.

### Perez, Cris

1982 Grants of Land in California Made by Spanish or Mexican Authorities. Prepared by Staff of the State Lands Commission. Report on file at California State University, Monterey Bay, Digital Commons. Monterey, California.

### Perkins, Yvonne

2023 Cultural Resources Department Review. Received by Katherine Sinsky, August 21, 2023.

### Pittsburg Historical Museum

The Railroads. Electronic document: https://pittsburgmuseum.org/history/f/railroads. Accessed June 18, 2024.

### Price, Heather, Angela Cook, Drew Bailey, and Thomas Young

2008 Cultural Resource Assessment of the Los Vaqueros Reservoir Expansion Project,
Alameda and Contra Costa Counties, California. Prepared for Environmental Science
Associates, San Francisco, CA.

### Ragir, Sonia

1972 The Early Horizon in Central California Prehistory. In Contributions of the University of California Archaeological Research Facility. University of California Department of Anthropology Berkeley, Berkeley, California.

### Sacramento County

- 2017 Sacramento County General Plan Conservation. Electronic document, https://planning.saccounty.gov/PlansandProjectsIn-Progress/Pages/General Plan.aspx, accessed November 2023.
- 2023 County History. Electronic document, https://www.saccounty.gov/Government/Pages/CountyHistory.aspx#:~:text=%E2%80%8BCounty%20History&text=With%20the%20discovery%20of%20gold,needs%20of%20a%20growing%20population,accessed November 2023.

### Schemmann, K., J.R. Unruh, and E.M. Moores

2008 Kinematics of Franciscan Complex exhumation: New insights from the geology of Mount Diablo, California: GSA Bulletin, v. 120, p. 543–555, doi:10.1130/B26056.1.

### Schenck, W. E. and E. J. Dawson

1929 Archaeology of the Northern San Joaquin Valley, University of California Press. Berkeley, California.

### Solano County

- 2008 Solano County General Plan. Electronic document, https://www.solanocounty.com/depts/rm/planning/general\_plan.asp, accessed November 2023.
- Solano County History. Electronic document, https://www.solanocounty.com/about/history.asp#:~:text=The%20area%20that%20became%20Solano,of%20the%20origin al%2027%20counties, accessed October 2023.
- 2024 Agriculture. Electronic document: https://www.solanocounty.com/depts/agriculture/department\_overview.asp. Accessed June 19, 2024.

### Supreme Court of California

- 1882 *Upham v. Hosking, 62 Cal. 250.* Prepared by the Supreme Court of California. On file digitally, https://casetext.com/case/upham-v-hosking.
- 1904 *Walsh v. Abbott, 145 Cal. 285, 78 P. 715.* Prepared by the Supreme Court of California. On file digitally, https://casetext.com/case/walsh-v-abbott.

### Supernowicz, Dana E.

2017 Contra Costa-Moraga/Pittsburg-Tesla PG&E Electrical Transmission Lines. The Resources Agency Department of Parks and Recreation Primary Record. Prepared by Historic Resource Associates, 2001 Sheffield Drive, El Dorado Hills, California 95762. December 2017.

### Theodoratus Cultural Research

1980 Montezuma I & II Cultural Resources. Prepared for Pacific Gas and Electric Company. Electronic document, https://coveredactions.deltacouncil.ca.gov/services/download.ashx?u=1927529f-f32b-4a1e-abd9-060e2a512d9d, accessed October 2023.

### Thompson and West

1878 Historical atlas map of Solano County, California. Compiled, drawn, and published from personal examinations and surveys by Thompson & West, No.6. Atlases of the United States. Thompson & West Publication, Oakland, California.

### Tremaine, Kim J.

1991 Archaeological Inspection of the Proposed Collinsville Wind Turbine Generation Site and Transmission Line, Solano County, California. Report prepared by BioSystems Analysis, Inc. for PG&E. Report no. S-013263 on file at the NWIC, Sonoma State University, Rohnert Park, California.

### University of California Santa Barbara (UCSB) Aerial Photography Collection

1937 Flight ABO-1938, Frame 56-37. Scale 1:20,000. August 25, 1937.

1957 Flight ABO-1957, Frame 17t-109. Scale 1:20,000. June 3, 1957.

1970 Flight CAS-3069, Frames 8-9. Scale 1:12,000.

### U.S. Department of Agriculture (USDA)

2023 Web Soil Survey. Natural Resources Conservation Service. https://websoilsurvey.nrcs.usda.gov/app/. Accessed August 2023.

### U.S. District Court (USDC)

2016

Case No.86 Northern District, Los Ulpinos Grant, John Bidwell. Transcripts of the Proceedings in Case No.319, John Bidwell Claimant vs. The United States, Defendant, For the Place Named "Los Ulpinos." Prepared by the United States District Court of Northern California. Transcript on file digitally, https://digicoll.lib.berkeley.edu/record/265448? In=en.

### U. S. Environmental Protection Agency (USEPA)

Ecoregion Download Files by State - Region 9 | US EPA. CA\_eco\_PosterText\_Final\_Feb2016.docx (live.com). Electronic document: https://www.epa.gov/eco-research/ecoregion-download-files-state-region-9#pane-04. Accessed June 19, 2024.

### U.S. Geological Survey (USGS)

1907 Antioch, CA topographic quadrangle map, Scale 1:62,500.

1918 Antioch, CA topographic guadrangle map, Scale 1:62,500.

1918 Collinsville, CA topographic quadrangle map, Scale 1:62,500.

1953 Collinsville, CA topographic quadrangle map, Scale 1:62,500.

1953 Honker Bay, CA topographic quadrangle map, Scale 1:62,500.

1978 Antioch, CA topographic quadrangle map, Scale 1:62,500

1981 Honker Bay, CA topographic quadrangle map, Scale 1:62,500

1993 Lodi, CA topographic quadrangle map, Scale 1:100000

- 2012 Honker Bay, CA topographic quadrangle map, Scale 1:24000
- 2018 Honker Bay, CA topographic quadrangle map, Scale 1:62,500

### Whitaker, Adrian

2010 Site record for P-24-000128 (CA-SOL-287H). On file at the Northwest Information Center.

### Wiberg, Randy

- 2010 Archaeological Investigations at CA-CCO-18/548: Final Report for the Vineyards at Marsh Creek Project, Contra Costa County, California. Holman & Associates, Archaeological Consultants.
- 2011 Magee Ranch Archaeological Survey and Subsurface Testing Report, Contra Costa County, California. Holman and Associates, Archaeological Consultants.

### Wohlgemuth, Eric

2004 The Course of Plant Food Intensification in Native Central California. Doctoral dissertation, Department of Anthropology, University of California, Davis.

### Young, Wood

1971 Hastings Adobe, Solano County, California. National Register of Historic Places Inventory/Nomination Form. Solano County Historical Society, October 14, 1971.



# Attachment A. Maritime Cultural Resources Assessment Report



Submerged Cultural Resources Assessment Survey, Collinsville 500/230 kV Substation Project, Solano, Sacramento, and Contra Costa Counties, California

Rikki Oeters Milewski, M.A., RPA Justin Milewski, B.A. July 26, 2024



# Submerged Cultural Resources Assessment Survey for the 500/230kV Substation Project, Solano, Sacramento, and Contra Costa Counties, California

This report has been revised for public use by removal of site location information.

### Prepared by:

Rikki Oeters Milewski, M.A., RPA Justin Milewski, B.A.

### **Prepared for:**

Insignia Environmental 545 Middlefield Road, Suite 210 Menlo Park, California 94025

**Technical Report No. 23-650** 

PaleoWest, LLC dba Chronicle Heritage

1406 West Government Street Pensacola, Florida 32502 901-229-4200

July 26, 2024

# **Abstract**

Conducted under contract to Insignia Environmental, PaleoWest, LLC dba Chronicle Heritage completed a Cultural Resource Assessment supporting the Proposed Collinsville 500/230kV Substation Project (Proposed Project) in the Sacramento River Delta region of Contra Costa, Solano, and Sacramento Counties in California. LS Power Grid California, LLC (LSPGC) proposes constructing a new electrical substation, 500 kilovolt (kV) transmission line, and 230 kV transmission line to increase reliability and renewable generation. The proposed transmission lines extend from Collinsville, California to Pittsburg, California and include aboveground and underwater components.

Required to meet stipulations of Section 404 of the Clean Water Act, the Proposed Project is subject to Section 106 of the National Historic Preservation Act (NHPA) of 1966, as amended, the Abandoned Shipwreck Act of 1987 (National Park Service [NPS] 1990), and the California Environmental Quality Act (CEQA), and the Abandoned Shipwreck Act of 1987. The U.S. Army Corps of Engineers (USACE) is the lead federal agency, and the California Public Utilities Commission (CPUC) is the lead CEQA agency.

The Proposed Area of Potential Impact (API) or Area of Potential Effect (APE) includes an approximately 4-mile (mi)-long stretch of submerged transmission cable under the Sacramento River, in addition to approximately 1 mi of overhead 230 kV transmission line, and two approximately 1.5-mi-long, single-circuit, 500 kV transmission line segments. For the submerged portion of the Proposed Project, Chronicle Heritage's Maritime Division analyzed data from an intensive submerged geophysical remote sensing survey; coordinated with the State of California's Underwater Archaeologist; performed a literature review and archival research; and performed an analysis of magnetometer, side-scan sonar, and subbottom profiler data collected during the survey.

Fieldwork was conducted by eTrac from September 17 to October 26, 2023, and was conducted under California State Lands Commission (CSLC) Low Energy Geophysical Survey Permit No. 9235. Analysis of the data indicated the presence of three potentially significant targets. Target 1 and Target 2 contained vessel-like structural components, and Target 3 is believed to represent the remains of a wooden barge-like watercraft. All Targets will be avoided by project activities which will preclude and mitigate any potential adverse effect.

In addition, one paleolandform was identified within the Proposed API/APE. While this feature was initially thought to cross 7 survey transects through and into the Proposed API/APE, upon closer analysis each cross section differed markedly from the other, indicating a noncontinuous landform but rather separate and independent features. This argues that what is represented by the subbottom record is a braided network of constantly changing and shifting river channels. Subsequently, the dynamic nature of this area also argues for a low probability of the potential for intact cultural material deposits.

Submerged Cultural Resources Assessment Survey for the Collinsville 500/230kV Substation Project, Solano, Sacramento, and Contra Costa Counties, California

- <b>j</b> , ,		
This page intentionally left blank.		

# **Contents**

1	INTRODUC	TION		
	1.1	PROJI	ECT DESCRIPTION	1
	1.2	AREA	OF POTENTIAL IMPACTS	2
2	REGULATO	RY CON	NTEXT	7
	2.1		RAL	
		2.1.1	National Historic Preservation Act	7
		2.1.2	Abandoned Shipwreck Act	7
	2.2	STATE	<u> </u>	
		2.2.1	California Public Resources Code 5097.9	
		2.2.2	California Environmental Quality Act	
	2.3		L	
		2.3.1	Solano County	
		2.3.2	Contra Costa County	
		2.3.3	Sacramento County	
3	SETTING			
	3.1		RONMENTAL SETTING	
	3.2		ONTACT SETTING	
	3.3		OGRAPHIC SETTING	
		3.3.1	The Patwin People	
		3.3.2	The Miwok People	
	3.4		IRIC OVERVIEW	
		3.4.1	Spanish Era (1769–1821)	
		3.4.2	Mexican Era (1822–1848)	
_		3.4.3	Historical Era (1848-present)	
4			(GROUND	
	4.1		PRIC CONTEXT	
		4.1.1	Maritime History of the Sacramento River Delta	
		4.1.2	California State Lands Commission Shipwreck Database	
_	4.2		OGRAPHIC REVIEW	
5				
	5.1		ERGED REMOTE SENSING SURVEY	
		5.1.1	Personnel	
		5.1.2	Remote Sensing Survey Equipment	
	г о	5.1.3		
	5.2		ANALYSIS CRITERIA, THEORY, AND COMMENTARY	
	F 7	5.2.1	Subbottom Profiler AnalysisOD AND THEORY FOR RECOGNITION OF A SUBMERGED PRECONTAC	
	5.3	HLDIN	UD AND THEURY FUR RECUGNITION OF A SUBMERGED PRECUNTAL	
		5.3.1	Magnetometer	
		5.3.2	Side-Scan Sonar	
	5.4		ANALYSIS	
	J. <del>4</del>	5.4.1	Data Processing	
		5.4.2	Magnetic Data Collection and Processing	
		5.4.3	Side-scan Sonar Data Collection and Processing	
		5.4.4	Subbottom Profiler Data Processing and Analysis	
		J. 1. 1	Cassottomin Tomor Batan roocooming and Analysis	/ 0

			5.4.5 Geographic Information System Analysis	
		5.5	INVESTIGATIVE FINDINGS	
		5.6	MAGNETOMETER RESULTS	
		5.7	SIDE-SCAN SONAR RESULTS	
		5.8	SUBBOTTOM PROFILER RESULTS	
		5.9	POTENTIALLY SIGNIFICANT TARGETS	
			5.9.1 Target 1	
			5.9.2 Target 2	
			5.9.3 Target 3	
6	CONCL	.USIO	DNS AND RECOMMENDATIONS	89
		6.1	PROCEDURES TO DEAL WITH UNEXPECTED SUBMERGED CULTURAL DISCOVERIES	90
7	REFER	ENC	ES	92
Fi	gures			
Fi	aure 1-1.	Subn	merged and terrestrial Project vicinity map	3
			posed submerged API/APE with centerline cable corridors and proposed subsea	
			ables	
Fi	gure 1-3.		posed submerged API/APE with centerline cable corridors and proposed subsea	
		ca	ables detailed map	6
Fi	gure 3-1.	View	v east of Collinsville from within the Proposed API/APE, facing north	16
Fi	gure 3-2.	Viev	w from within the Proposed API/APE, facing south	17
Fi	gure 4-1.		st's conception of the Embarcadero prior to the gold rush (courtesy of the	
		Sa	acramento Pioneer's Association Collection, City of Sacramento, Museum & Hist	ory
			ivision)	
Fi	gure 4-2.	. Lith	nograph of Sacramento in 1849 (courtesy of California State Library)	27
Fi	gure 4-3.	. Sacı	ramento waterfront in 1851, showing converted store ships (courtesy of the	
			alifornia Department of Parks & Recreation Collection, City of Sacramento, Muse	
			History Division).	
Fi	gure 4-4.		amer Dutchess, operated by Laurentzen Transportation Company between 1908	
			118 (photo courtesy of Rio Vista Museum)	30
Fi	gure 4-5.		4 Sacramento River News advertisement for passenger and freight service by	
			eamer Belvedere (Sacramento River News 1894)	
			thern Pacific steamer Apache (photo courtesy of Rio Vista Museum)	32
Fi	gure 4-7.		thern Pacific steamer <i>Navajo</i> , landlocked on Mandeville Island circa 1970 (as	
			resented in Schell 1995)	33
Fi	gure 4-8.		fornia Transportation Company steamer Capital City (courtesy of Rio Vista	
			useum).	
Fi	gure 4-9.		fornia Transportation Company sternwheelers Delta King and Delta Queen in 1930	
	,		s presented in Schell 1995)	
Fi	gure 4-10		eamer Red Bluff and barge Nebraska loading grain (photo courtesy of Yolo Count	
	,		ublic Library, Clarksburg Branch)	
ΗI	gure 4-11		pical scow-built Sacramento River freight schooner, also known as a "Hay Scow"	
۲.	a / 10		hoto courtesy of Yolo County Public Library, Clarksburg Branch).	5/
ΗI	gure 4-12		rzie Theresa hay scow schooner loading bales on a canal (photo courtesy of Yolo	7-7
		UC	ounty Public Library, Clarksburg Branch)	ა/

	38
Figure 4-14. Bier's 1901 map, as modified by Thompson (1980), showing locations of ferry landings since 1850 (as presented in Thomson 1980)	
Figure 4-15. Small ferry boats of Laurentzen Transportation Company (as presented in Schell 1995	5).
Figure 4-18. 1828 chart excerpt showing the Proposed API/APE (Chart No. 591-00-1828 from NOAA Historical Map and Chart Collection).	\'s
Figure 4-19. 1850 chart excerpt showing the Proposed API/APE (Chart No. 1706-00-1876 from NOAA's Historical Map and Chart Collection).	45
Figure 4-20. 1867 chart excerpt showing the Proposed API/APE (Chart No. 626-01-1867 from NOAA's Historical Map and Chart Collection).	46
Figure 4-21. 1883 chart excerpt showing the Proposed API/APE (Chart No. 5526-1758c-1883 from NOAA's Historical Chart Collection)	
Figure 4-22. 1910 chart excerpt showing the Proposed API/APE (Chart No. 5534-3609C-1916 from NOAA's Historical Map and Chart Collection).	
Figure 4-23. 1948 chart excerpt showing the Proposed API/APE (Chart No. 5534-9-1948 from NOAA's Historical Map and Chart Collection).	
Figure 4-24. 1958 chart showing the Proposed API/APE (Chart No. 5534-25-1958 from NOAA's Historical Map and Chart Collection).	
Figure 4-25. 1967 chart excerpt showing the Proposed API/APE (Chart No. 5534-29-1967 from NOAA's Historical Map and Chart Collection).	
Figure 4-26. 1979 chart excerpt showing the Proposed API/APE (Chart No. 18656-41-1979 from NOAA's Historical Map and Chart Collection).	
Figure 4-27. 1983 chart excerpt showing the Proposed API/APE (Chart No. 18656-45-1983 from NOAA's Historical Map and Chart Collection).	
Figure 4-28. 1990 chart excerpt showing the Proposed API/APE (Chart No. 18659-7-1990 from NOAA's Historical Map and Chart Collection).	
Figure 4-29. 1996 chart excerpt showing the Proposed API/APE (Chart No. 18659-16-2022 from NOAA's Historical Map and Chart Collection).	
Figure 4-30. 2022 chart excerpt showing the Proposed API/APE (Chart No. 18659-12-1996 from NOAA's Historical Map and Chart Collection).	
Figure 5-2. Applanix POS MV OceanMaster V5 navigation and inertial compensator used during the investigation	е
Figure 5-3. Survey instruments employed during the investigation included the magnetometer (to left), side-scan sonar (bottom left), and the subbottom profiler (right).	р
Figure 5-4. eTrac, Inc. survey vessel, R/V Rapid. Figure 5-5. eTrac, Inc., survey vessel, R/V Taku.	
Figure 5-6. Magnetometer and Subbottom 30 meter spaced Planned survey lines	
Figure 5-8. Magnetic contour maps of six wreck sites documented during recent Chronicle Heritage Projects. Black arrows indicate the declination of the magnetic anomaly's field. Note that the declination of all fields tends to orient within 20 degrees of magnetic north. See Tables 3-1 and 3-2 for additional information regarding these	
shipwrecks	e p
Figure 5-10. SonarWiz 7 software with mosaic example in the background, and a target selection zoom image to the left. Magnetic anomaly locations are overlaid	70

# Submerged Cultural Resources Assessment Survey for the Collinsville 500/230 kV Substation Project, Solano, Sacramento, and Contra Costa Counties, California

Figure 5-11. SonarWiz 7 sonar contact tabular format, automatically generated	dow. ch at
the time of the image was directly over the peak of the positive relief feature sho This image is from a past survey conducted in Tampa Bay (see Faught and James	
2009)	
Figure 5-13. GIS database example showing magnetic anomalies, side-scan sonar contacts,	
magnetic contours, tracklines, and raster chart data showing environmental con	
(data taken from a previous investigation)	
Figure 5-14. Magnetic contours map key.	
Figure 5-15. Magnetic contours map (1 of 4)	
Figure 5-16. Magnetic contours map (2 of 4).	
Figure 5-17. Magnetic contours map (3 of 4).	
Figure 5-18. Magnetic contours map (4 of 4).	
Figure 5-19. Side-scan sonar mosaic illustrating coverage of the maritime Survey area	
Figure 5-20. Example of Subbottom Feature 007 (F7) from the maritime survey area. This profi	
provided in both unannotated (above) and annotated (below) formats Figure 5-21. Subbottom profiler features identified within the Proposed API/APE, Feature 7 ca	
seen outlined in blue, crossing the cable corridor boundary	
Tables	
Table 5-1. Compilation of Magnetic Data from Various Sources	62
Table 5-2. Magnetic Anomaly Data	
Table 5-3. Side-Scan Sonar Contact Data	80
Table 5-4. Sonar Report	82

## **Appendices**

Appendix A. Qualifications

Appendix C. SCRAS Research Design

Submerged Cultural Resources Assessment Survey for the Collinsville 500/230 kV Substation Project, Solano, Sacramento, and Contra Costa Counties, California

This page intentionally left blank.
This page intentionally left blank.

# 1 Introduction

PaleoWest, LLC dba Chronicle Heritage completed a records search, literature review, Native American outreach, terrestrial archaeological survey, resource evaluations, and maritime submerged survey in support of the Collinsville 500/230 kilovolt (kV) Substation Project (Project) in Contra Costa, Solano, and Sacramento Counties, California (Figure 1-1). This report presents the results of the records search, a review of historical maps and aerial photographs, and maritime submerged cultural resources survey results. Required to meet stipulations of Section 404 of the Clean Water Act, the Proposed Project is subject to compliance with the National Historic Preservation Act (NHPA) and the California Environmental Quality Act (CEQA). The U.S. Army Corps of Engineers is the lead federal agency, and the California Public Utilities Commission (CPUC) is the lead CEQA agency. The purpose of this investigation is to determine the potential for the Proposed Project to adversely affect historical resources under the NHPA and CEQA.

# 1.1 Project Description

The Area of Potential Impact is in Sections 22–24 and 26–27 of Township 3 North, Range 1 East in the Antioch North, California (USGS 1978) and Honker Bay, California (USGS 1981) U.S. Geological System (USGS) 7.5-minute quadrangles (Figure 1-2, Figure 1-3, Figure 1-4). The Proposed Collinsville Substation will provide an additional supply from the 500 kV system into the northern Greater Bay Area, which will increase reliability and advance additional renewable generation. The Proposed Project has an in-service date requirement of June 1, 2028, per the California Independent System Operator (CAISO) functional specification.

The Proposed Project involves four major components:

- The construction of the proposed 500/230 kV Collinsville Substation, including:
  - o 500 kV gas-insulated, four position, breaker-and-a-half switchyard
  - o 500 kV series capacitor
  - Two 500/230 kV transformers
  - o 230 kV gas-insulated, four position, breaker-and-a-half switchyard
- The installation of the new double-circuit 230 kV line from the Proposed Collinsville Substation to the Pacific Gas and Electric (PG&E) existing Pittsburg Substation
- The construction of a new 500 kV interconnection between the existing Vaca Dixon-Tesla 500 kV line and the Proposed Collinsville Substation with possible adjustment to existing series capacitors at the Vaca Dixon Substation (PG&E scope)
- Reconfiguration of PG&E's existing Pittsburg Substation

The Proposed Collinsville Substation will be on property adjacent to PG&E's Vaca Dixon-Tesla 500 kV line. The Proposed Collinsville Substation site is approximately 20 acres and is off Talbert Lane in Suisun City, approximately 1 mile (mi) north of the Sacramento River Delta. The Proposed Collinsville Substation is designed to be expandable to accommodate a total of eight 500 kV positions in four bays and ten 230 kV positions in five bays, based on the CAISO's functional specification. The Proposed Project will establish a new access road to the Proposed Collinsville

Substation site and will also have adequate space to accommodate parking for operation and maintenance personnel vehicles.

The new Collinsville to Pittsburg double-circuit 230 kV transmission line will be a combination of overhead and submarine components. The overhead transmission line is proposed to be approximately 1–2 mi long between the Proposed Collinsville Substation and the northern edge of the Sacramento River. The overhead transmission line structures will be predominantly self-supporting, double-circuit tubular steel monopoles with a vertical conductor configuration and two optical ground wires. Structures are proposed to be approximately 100–120 feet (ft) tall. The overhead transmission line right-of-way (ROW) is planned to be approximately 150 ft wide. From the last onshore structures to the single proposed in-river transition structure, the planned ROW width increases to approximately 325 ft.

The submarine cable route is proposed to be approximately 4 mi long, running northeast-southwest across the Sacramento River Delta. Subject to detailed engineering, the submarine cable conductor is proposed to consist of approximately six 230 kV tri-core cables, each spaced approximately 70 ft apart. The submarine cable is proposed to be installed beneath the bay and riverbed to a depth of approximately 6 and 25 ft using jetting technology. Jet sled installation has short-term, localized impacts within the river and will cause minimal disturbance to the environment and navigation. Near the southern edge of the river, just outside of PG&E's existing Pittsburg Substation, four to six transition vaults will receive the submarine cables. From that point, the lines will continue underground until terminating at two new riser poles adjacent to PG&E's existing Pittsburg Substation.

LSPGC's scope for the new 230 kV lines is proposed to stop at dead-end structures near PG&E's existing Pittsburg Substation property line. PG&E will be responsible for bringing the new circuits from that point to the terminations within the Pittsburg Substation, the final configuration of which will be determined and established in the Transmission Interconnection Agreement with PG&E. At the opposite end of the Proposed Project, PG&E will also be responsible for interconnecting the Vaca Dixon-Tesla 500 kV line to terminate at new dead-end structures near the Proposed Collinsville Substation and to provide any required modifications to the existing series capacitors at Vaca Dixon.

Construction of the Proposed Project is planned to begin in early 2026 after necessary permits, agreements, and land rights are received. The construction phase of the Proposed Project is anticipated to be approximately 24–30 months, concluding with the energization of the new Project facilities.

# 1.2 Area of Potential Impacts

As mentioned above, the submarine cable route is proposed to be approximately 4 mi long, running northeast-to-southwest across the Sacramento River Delta. The submarine cable corridor, which is the actual Area of Potential Impact (API) or Area of Potential Effect (APE), is proposed to be installed beneath the bay and riverbed to a depth of approximately 6 and 25 ft using jetting technology. Near the southern edge of the river just outside of the existing Pittsburg Substation, four to six transition vaults will receive the submarine cables. From that point, the lines will continue underground until terminating at two new riser poles adjacent to PG&E's existing Pittsburg Substation.



Figure 1-1. Submerged and terrestrial Project vicinity map.

Submerged Cultural Resources Assessment Survey for the Collinsville 500/230 kV Substation Project, Solano, Sacramento, and Contra Costa Counties, California

1 Toject, Solano, Sacramento, and Contra Costa Counties, Camornia
This page intentionally left blank.




Figure 1-2. Proposed submerged API/APE with centerline cable corridors and proposed subsea cables.




Figure 1-3. Proposed submerged API/APE with centerline cable corridors and proposed subsea cables detailed map.

### 2 Regulatory Context

#### 2.1 Federal

#### 2.1.1 National Historic Preservation Act

The NHPA of 1966, as amended (54 United States Code [USC] 300101 et seq.), sets forth the responsibilities that federal agencies must meet regarding cultural resources, especially Section 106 and its implementing regulations in 36 CFR Part 800. Federal agencies must conduct the necessary studies and consultations to identify cultural resources that may be affected by an undertaking and evaluate cultural resources that may be affected to determine if they are eligible for the National Register of Historic Places (NRHP) (that is, whether identified resources constitute historic properties), and assess the potential for effects (adverse or not) to historic properties associated with the proposed undertaking. Historic properties are resources that are listed on or eligible for listing in the NRHP (36 CFR 800.16[1][1]). A property may be listed in the NRHP if it meets the criteria provided in the NRHP regulations (36 CFR 60.4). Typically, such properties must also be 50 years or older (36 CFR 60.4[d]).

The quality of significance in American history, architecture, archaeology, engineering, and culture is present in districts, sites, buildings, structures, and objects that possess integrity of location, design, setting, materials, workmanship, feeling, and association and meet at least one of the four following Criteria:

- That are associated with events that have made a significant contribution to the broad patterns of our history (Criterion A)
- That are associated with the lives of persons significant in our past (Criterion B)
- That embody the distinctive characteristics of a type, period, or method of construction, or that represent the work of a master, or that possess artistic value, or that represent a significant and distinguishable entity whose components may lack individual distinction (Criterion C)
- That have yielded, or may be likely to yield, information important in prehistory or history (Criterion D)

Section 106 defines an adverse effect as an effect that alters, directly or indirectly, the qualities that make a resource eligible for listing in the NRHP (36 CFR 800.5[a][1]). Consideration must be given to the property's location, design, setting, materials, workmanship, feeling, and association to the extent that these qualities contribute to the integrity and significance of the resource. Adverse effects may be direct and reasonably foreseeable or may be more remote in time or distance (36 CFR 8010.5[a][1]).

#### 2.1.2 Abandoned Shipwreck Act

Signed into law in 1988, the Abandoned Shipwreck Act of 1987 (Act; 43 U.S.C. §§ 2101 through 2106) provides that any abandoned shipwreck embedded in a state's submerged lands, or that is located on a state's submerged lands and is included in or determined eligible for inclusion in the National Register, is the property of that state and subject to that state's jurisdiction. Under California Public Resources Code section 6313(a), abandoned shipwrecks are under the jurisdiction of the California State Lands Commission

#### 2.2 State

#### 2.2.1 California Public Resources Code 5097.9

# § 5097.9 – Interference with Native American religion or damage to cemeteries or places of worship, etc., prohibited, construction and exemptions from law.

No public agency, and no private party using or occupying public property, or operating on public property, under a public license, permit, grant, lease, or contract made on or after July 1, 1977, shall in any manner whatsoever interfere with the free expression or exercise of Native American religion as provided in the United States Constitution and the California Constitution; nor shall any such agency or party cause severe or irreparable damage to any Native American sanctified cemetery, place of worship, religious or ceremonial site, or sacred shrine located on public property, except on a clear and convincing showing that the public interest and necessity so require.

#### § 5097.91 - Native American Heritage Commission

There is in state government a Native American Heritage Commission (NAHC), consisting of nine members appointed by the Governor with the advice and consent of the Senate.

#### § 5097.94 - Powers and duties

This section discusses the powers and duties of the NAHC. These powers and duties include:

- (a) To Identify and catalog places of special religious or social significance to Native Americans and known graves and cemeteries of Native American on private lands, notifying landowners whose property contains Native American graves and cemeteries and identifying the most likely descendant.
- (b) To make recommendations relative to Native American sacred places that are located on private lands, are inaccessible to Native Americans, and have cultural significance to Native Americans for acquisition by the state or other public agencies for the purpose of facilitating or assuring access thereto by Native Americans.
- (c) To make recommendations to the Legislature relative to procedures which will voluntarily encourage private property owners to preserve and protect sacred places in a natural state and to allow appropriate access to Native American religionists for ceremonial or spiritual activities.
- (d) To make recommendations to the Director of Parks and Recreation and the California Arts Council relative to the California State Indian Museum and other Indian matters touched upon by department programs.
- (e) To assist Native Americans in obtaining appropriate access to sacred places that are located on public lands for ceremonial or spiritual activities.
- (f) To assist state agencies in any negotiations with agencies of the federal government for the protection of Native American sacred places that are located on federal lands.

# § 5097.98 – Notification of discovery of Native American human remains, descendants; disposition of human remains and associated grave goods.

This section discusses the procedures that need to be followed upon the discovery of Native American human remains. The NAHC, upon notification of the discovery of human remains, is required to contact the County Coroner pursuant to subdivision (c) of Section 7050.5 of the Health and Safety Code and shall immediately notify those persons it believes to be most likely descended from the deceased Native American.

Upon the discovery of the Native American remains, the landowner shall ensure that the immediate vicinity, according to generally accepted cultural or archaeological standards or practices, where the Native American human remains are located, is not damaged or disturbed by further development activity until the landowner has discussed.

#### 2.2.2 California Environmental Quality Act

The Proposed Project is subject to compliance with CEQA, as amended. Compliance with CEQA statutes and guidelines requires both public and private projects with financing or approval from a public agency to assess the undertaking's impact on cultural resources (Public Resources Code [PRC] Section 21082, 21083.2 and 21084 and California Code of Regulations 10564.5). Specifically, under PRC Section 201084.1, a, "project that may cause a substantial adverse change in the significance of an historical resources is a project that may have a significant effect on the environment." The first step in the CEQA compliance process in terms of historical resources is to identify any that may be impacted by the Proposed Project.

Cultural resources are buildings, sites, human-modified landscaped areas, traditional cultural properties, structures, or objects that may have historical, architectural, cultural, or scientific importance based on established criteria. CEQA states that if a project will have a significant impact on important cultural resources deemed "historically significant," then project alternatives and mitigation measures must be considered.

"Historical resource" is a term with a defined statutory meaning (PRC Section 21084.1). The determination of significant impacts on historical and archaeological resources is described in Sections 15064.5(a) and 15064.5(b) of the State CEQA Guidelines. Section 15064.5(a) states that historical resources include the following:

- A resource listed or determined to be eligible by the State Historical Resources Commission for listing, in the California Register of Historical Resources (CRHR) (PRC Section 5024.1).
- A resource included in a local register of historical resources, as defined in Section 5020.1(k) of the PRC or identified as significant in a historical resource survey meeting the requirements of Section 5024.1(g) of the PRC, will be presumed to be historically or culturally significant. Public agencies must treat any such resource as significant unless the preponderance of evidence demonstrates that it is not historically or culturally significant.
- Any object, building, structure, site, area, place, record, or manuscript which a lead agency determines to be historically significant or significant in the architectural, engineering, scientific, economic, agricultural, educational, social, political, military, or cultural annals of California may be considered a historical resource, provided the lead agency's determination is supported by substantial evidence in light of the whole record. Generally, a resource will be considered by the lead agency to be historically

significant if the resource meets the criteria for listing in the [CRHR] (PRC Section 5024.1).

The fact that a resource is not listed in or determined to be eligible for listing in the CRHR, not included in a local register of historical resources (pursuant to PRC Section 5020.1[k]) or identified in a historical resources survey (meeting the criteria in PRC Section 5024.1[g]) does not preclude a lead agency from determining that the resource may be an historical resource as defined in PRC Section 5020.1(j) or 5024.1.

#### 2.3 Local

#### 2.3.1 Solano County

The Solano County General Plan (Solano County 2008) offers goals, policies, and implementation programs to guide the preservation of prehistoric and historic archaeological sites in Solano County. The county's stated cultural resource goals include (1) collaboration with Native American groups to protect traditional cultural places and sacred spaces in the context of land use decisions and (2) leveraging the county's historic capital to drive economic development, especially tourism.

The policies related to cultural resources outlined by the Solano County General Plan include the following:

- RS.P-38. Identify and preserve important prehistoric and historic structures, features, and communities.
- RS.P-39. Tie historic preservation efforts to the County's economic development pursuits, particularly those relating to tourism.
- RS.P-40. Consult with Native American governments to identify and consider Native American cultural places in land use planning.

In pursuit of its cultural resource goals, Solano County designed an implementation program and possible mitigation measures in areas with medium to high potential for archaeological or cultural resources:

- RS.I-25. Require cultural resources inventories of all new development projects in areas identified with medium or high potential for archeological or cultural resources. Where a preliminary site survey finds medium to high potential for substantial archaeological remains, the County shall require a mitigation plan to protect the resource before issuance of permits. Mitigation may include:
  - Having a qualified archaeologist present during initial grading or trenching (monitoring);
  - Redesign of the project to avoid archaeological resources (this is considered the strongest tool for preserving archaeological resources);
  - o Capping the site with a layer of fill; and/or
  - Excavation and removal of the archaeological resources and curation in an appropriate facility under the direction of a qualified archaeologist.
  - Alert applicants for permits within early settlement areas to the potential sensitivity. If significant archaeological resources are discovered during construction or grading activities, such activities shall cease in the immediate area

of the find until a qualified archaeologist can determine the significance of the resource and recommend alternative mitigation.

#### 2.3.2 Contra Costa County

The Contra Costa County General Plan (Contra Costa County 2010) details policies and implementation measures related to the stated goal of the identification and preservation of historic and cultural resources in Contra Costa County.

Contra Costa County's historic and cultural resource policies include:

- 9-28. Areas which have identifiable and important archaeological or historic significance shall be preserved for such uses, preferably in public ownership.
- 9-29. Buildings or structures that have visual merit and historic value shall be protected.
- 9-30. Development surrounding areas of historic significance shall have compatible and high-quality design in order to protect and enhance the historic quality of the area.
- 9-31. Within the Southeast County area, applicants for subdivision or land use permits to allow non-residential uses shall provide information to the County on the nature and extent of the archeological resources that exist in the area. The County Planning Agency shall be responsible for determining the balance between multiple use of the land and protection of resources (Contra Costa General Plan).

Contra Costa County's historic and cultural resource implantation measures include those related to the development review process, ordinance revisions, and other programs:

- Development Review Process
  - 9-i. Develop an archaeological sensitivity map to be used by staff in the environmental review process for discretionary permits to determine potential impacts upon cultural resources.
  - 9-j. As a condition of approval of discretionary permits, include a procedure to be followed in the event that archaeological resources are encountered during development or construction.

#### 2.3.3 Sacramento County

The Sacramento County General Plan (Sacramento County 2017) provides an overarching goal related to the protection and preservation of cultural resources:

Goal: Promote the inventory, protection and interpretation of the cultural heritage of Sacramento County, including historical and archaeological settings, sites, buildings, features, artifacts and/or areas of ethnic historical, religious or socioeconomical importance.

In pursuance of that goal, the Sacramento County General Plan identifies six objectives and policies and implementation programs to accomplish those objectives.

Objective 1: Comprehensive knowledge of archeological and historic site locations.

**Implementation Measures:** 

A. In cooperation with the North Central Information Center (NCIC) and cultural resources professionals, conduct:

- A comprehensive survey to record location of prehistoric, ethnohistoric and historic sites.
- A comprehensive survey to identify historically and architecturally important structures.

Objective 2: Attention and care during project review and construction to ensure that cultural resource sites, either previously known or discovered on the project site, are properly protected with sensitivity to Native American values.

#### Policies:

CO-150. Utilize local, state and national resources, such as the NCIC, to assist in determining the need for a cultural resources survey during project review.

CO-151. Projects involving an adoption or amendment of a General Plan or Specific Plan or the designation of open space shall be noticed to all appropriate Native American tribes in order to aid in the protection of traditional tribal cultural places.

CO-152. Consultations with Native American tribes shall be handled with confidentiality and respect regarding sensitive cultural resources on traditional tribal lands.

CO-153. Refer projects with identified archeological and cultural resources to the Cultural Resources Committee to determine significance of resource and recommend appropriate means of protection and mitigation. The Committee shall coordinate with the Native American Heritage Commission in developing recommendations.

CO-154. Protection of significant prehistoric, ethnohistoric and historic sites within open space easements to ensure that these resources are preserved in situ for perpetuity.

CO-155. Native American burial sites encountered during preapproved survey or during construction shall, whenever possible, remain in situ. Excavation and reburial shall

occur when in situ preservation is not possible or when the archeological significance of the site merits excavation and recording procedure. On-site reinterment shall have priority. The project developer shall provide the burden of proof that off-site reinterment is the only feasible alternative. Reinterment shall be the responsibility of local tribal representatives.

CO-156. The cost of all excavation conducted prior to completion of the project shall be the responsibility of the project developer.

CO-157. Monitor projects during construction to ensure crews follow proper reporting, safeguards, and procedures.

CO-158. As a condition of approval of discretionary permits, a procedure shall be included to cover the potential discovery of archaeological resources during development or construction.

#### **Implementation Measures:**

A. Develop a Cultural Resources Committee (appointed by the Board of Supervisors) to establish procedures and criteria for preservation and mitigation for cultural resources by

utilizing information available from the Sacramento Archives and Museum Collection Center (SAMCC) and the North Central Information Center (NCIC).

B. At the beginning of projects involving an adoption or amendment of a General Plan or Specific Plan or the designation of open space, notify the California Native American Heritage Commission and the appropriate Native American tribes regarding the project and, if requested by the tribes, set up consultation regarding the protection of traditional tribal cultural places. This notification and consultation process shall be carried out in accordance with Government Code Sections 65040.2, 65092, 65351, 65352, 65352.3, 65352.4, 65560, 65562.5; Public Resources Code Sections 5097.9, 5097.993; and Civil Code Section 815.3 and shall prevent public exposure of sensitive cultural resources.

#### C. Establish procedures to:

- Conduct periodic training programs for County Public Works and Infrastructure Agency and County Airports construction and maintenance personnel to facilitate their awareness of archeological site indicators and proper procedures.
- Utilize mitigation monitoring and reporting programs to provide for on-site monitoring during construction adjacent to known sites.
- Write letters during the environmental review process, to peoples of Native American descent based on a contact list provided by the Native American Heritage Commission, to request a Native American statement regarding a proposed project when that project is located on a site with known cultural resources.
- D. Pursue becoming a certified local government and establish a local County registry to document and protect cultural resources that are significant to the County of Sacramento. This registry should be administered through the Cultural Resources Committee (please refer to Implementation Measure A under Archeological Site Protection During Development).

# Objective 3: Preserve structures such as buildings, bridges, or other permanent structures with architectural or historical importance to maintain contributing design elements.

#### Policies:

CO-164. Structures having historical and architectural importance shall be preserved and protected.

CO-165. Refer projects involving structures or within districts having historical or architectural importance to the Cultural Resources Committee to recommend appropriate means of protection and mitigation.

CO-166. Development surrounding areas of historic significance shall have compatible design in order to protect and enhance the historic quality of the areas.

CO-167. When conducting planning studies, County Planning and Environmental Review staff, shall encourage the adaptive reuse of historic resources when the original use is no longer feasible or allowed under proposed area planning efforts.

CO-168. County-owned historic and cultural resources shall be preserved and maintained, such that modifications, alterations, and rehabilitations are conducted in a manner that is consistent with the U.S. Secretary of the Interiors Standards for the Treatment of Historic Properties.

#### **Implementation Measures:**

A. In cooperation with the North Central Information Center (NCIC) and cultural resources professionals, conduct:

- A comprehensive survey to record location of prehistoric, ethnohistoric and historic sites.
- A comprehensive survey to identify historically and architecturally important structures.

# Objective 4: Protect any known cultural resources protected from vandalism unauthorized excavation, or accidental destruction.

#### Policies:

CO-169. Restrict the circulation of cultural resource location information to prevent potential site vandalism. This information is exempt from the "Freedom of Information Act".

CO-170. Cooperate with other agencies to enforce laws and aggressively prosecute illegal collection of artifacts.

CO-171. Design and implement interpretive programs about known archeological or historical sites on public lands or in public facilities. Interpretation near or upon known sites should be undertaken only when adequate security is available to protect the site and its resources.

#### **Implementation Measures:**

- A. Develop a plan in conjunction with Archeological Conservancy to secure easements, agreements, or other appropriate mechanisms to protect known cultural sites from disturbance or erosion.
- B. Periodic patrol of County owned and managed archeological sites by park rangers.
- C. Implement a program within County departments which manage or patrol properties with known cultural resources to facilitate their awareness of archaeological site indicators and proper procedures in handling cultural resources.

#### Objective 5: Properly stored and classified artifacts for ongoing study.

#### **Implementation Measures:**

A. Initiate discussions regarding the preparation of a comprehensive regional study design for the excavation, cataloging and analysis of cultural resource artifacts and the synthesis of available information.

B. Identify a repository for cataloging and storage of excavated cultural artifacts.

Objective 6: Increase public education, awareness and appreciation of both visible and intangible cultural resources.

#### Policies:

CO-172. Provide historic and cultural interpretive displays, trails, programs, living history presentations, and public access to the preserved artifacts recovered from excavations.

CO-173. Interpretive elements involving Native American cultural resources shall be located at village sites (provided any unexcavated resources are properly protected) representative of different physical environments found in the County.

CO-174. Promote and support the California Indian Heritage Center.

CO-175. The County shall support efforts to develop Cultural Resources Tourism program within the County as a tool to preserve important cultural resources and in order to encourage economic development of resources within the County.

#### **Implementation Measures:**

A. In cooperation with local cultural resources experts:

- Present educational programs to school age children.
- Design educational criteria guidelines and study units for incorporation in county school curricula.

# 3 Setting

#### 3.1 Environmental Setting

The northern portion of the Proposed API/APE is within Township 3 North, Range 1 East, Sections 23, 24, 26, and 27, and the southern portion of the Proposed API/APE is within an unsectioned portion of Township 2 North Range 1 E as depicted on the USGS Antioch North 1979 and the USGS Honker Bay 2018 7.5′ minute quadrangle topographic maps (USGS 1979; USGS 2018). The Public Land Survey System titles the unsectioned southern portion as the Los Medanos Land Grant. This is where the Sacramento River meets the Suisun Bay, characterized by marshland that is subject to periodic flooding.

The Proposed API/APE is situated at the confluence of the Sacramento and San Joaquin Rivers at the eastern end of Suisun Bay and the western edge of the Sacramento–San Joaquin River Delta. The Proposed API/APE extends northward into the low-lying Montezuma Hills, opposite Collinsville (Figure 3–1) and its southern point in Pittsburg is approximately 3 mi north of the California Coast Range foothills in Contra Costa County (Figure 3–2). The deep water and lack of tributaries within the Proposed API/APE is somewhat unusual, given its location at the distal edge of a major river delta. While most deltas expand outward in broad fans, the Sacramento–San Joaquin River Delta is an inverted delta that contracts with proximity to its outlet in the San Francisco Bay. The unique setting of the Proposed API/APE is a result of the region's geologic history.

Before the San Francisco Bay began to form at the start of the Holocene 12,000 years ago, the coastline was approximately 30 mi west of its current position near the Farallon Islands due to lower sea levels during the Pleistocene. The Sacramento and San Joaquin Rivers faced a steeper gradient and cut deep and narrow channels through the Proposed API/APE as water flowed steadily toward the Pacific Ocean. Gravels found in Pleistocene deposits of the Montezuma Hills at the northern end of the Proposed API/APE and Pleistocene alluvial fans at the southern edge of the Proposed API/APE suggest a high-energy depositional environment during this time (Atwater 1982;

Helley and Graymer 1998). However, once the sea level started to rise in the Holocene and the San Francisco Bay flooded, the river's gradient and energy decreased, causing it to dump its sediment load away from the ocean in what is now the Sacramento–San Joaquin River Delta. This clay-rich material is evident in the muddy marsh deposits along the bank of the Sacramento River within the Proposed API/APE (Helley and Graymer 1998). Alternating sequences of fine to coarse–grained sediments represent cycles of marine transgression and regression throughout the Pleistocene, but the most recent iteration is best represented due to the erosion, burial, or uplift of ancient low depositional energy environments (Atwater 1982).



Figure 3-1. View east of Collinsville from within the Proposed API/APE, facing north.



Figure 3-2. View from within the Proposed API/APE, facing south.

#### 3.2 Precontact Setting

Research into local precontact cultures in northern California began with the work of N.C. Nelson of the University of California at Berkeley, who conducted the first intensive archaeological surveys of the San Francisco Bay region from 1906 to 1908. He maintained that the intensive use of shellfish—a subsistence strategy reflected in both coastal and bay shore middens—indicated a general economic unity in the region during precontact times (Moratto 1984:227). Nelson documented more than 100 shell mounds along the bay shore in Alameda and Contra Costa Counties when the area was still ringed by salt marshes 3–5 mi wide (Nelson 1909:322).

In 1911, Nelson supervised excavations at CA-SFR-7 (the Crocker Mound) near Hunter's Point, a site later dated to 3000–1500 years before present (B.P.). L.L. Loud identified archaeological components from this same period in Santa Clara County in 1911 while excavating at CA-SCL-1 (the Ponce, Mayfield, or Castro Mound site). R.J. Drake recognized them in San Mateo County in 1941–1942 at CA-SMA-23 (Mills Estate) in San Bruno (Moratto 1984:233). The work of Nelson and Loud in the Bay Area provided the impetus for investigation into the prehistory of central California, which began in earnest in the 1920s. Stockton-area amateur archaeologists J.A. Barr and E.J. Dawson excavated several sites and made substantial collections in the area from 1893 to the 1930s. Based on artifact comparisons, Barr identified what he felt were two distinct cultural traditions. Dawson later refined his work into a series of "Early," "Middle," and "Late" sites (Ragir 1972; Schenck and Dawson 1929).

Professional or academic-sponsored archaeological investigations began in the 1930s when J. Lillard and W. Purves of Sacramento Junior College formed a field school, which conducted excavations throughout the Sacramento Delta area. By means of artifact and burial data, they identified a three-phase sequence like Barr's and Dawson's, which they called "Early," "Intermediate," and "Recent" cultures (Lillard and Purves 1936). In 1954, Richard Beasley refined this system and extended it to include the region of San Francisco Bay. The result was referred to as

the Central California Taxonomic System (CCTS) (Lillard et al. 1939; Moratto 1984). Subsequently, the CCTS system was applied widely to site dating and taxonomy throughout central California.

Much of the subsequent archaeological investigation in the Bay Area and Central Valley focused on refining the CCTS through an analysis of environmental change, settlement and subsistence strategy, exchange, population movement, and related topics. These studies established subsequences for many regions of central California. The best received of these studies has been Fredrickson's (1973) concept of cultural "patterns" (Moratto 1984:201–214). His idea was that, despite local variations, widespread cultural patterns are identifiable. He described patterns as "adaptive modes," which extend across one or more regions and are, "characterized by particular technological skills and devices, particular economic modes, including participation in trade networks and practices surrounding wealth, and by particular mortuary and ceremonial practices" (Fredrickson 1973:7–8).

Fredrickson's chronological sequence for central California begins with the Windmiller Pattern, which possesses cultural elements belonging to both the Early and Middle Horizons. Sites from this period date from about 6950–3950 B.P. Although earlier occupations no doubt existed, sites from the Paleoindian Period (about 11,950–7950 B.P.) are thought to be buried beneath Holocene alluvial deposits and are not well documented in this part of California (Ragir 1972). Some scholars have suggested that Windmiller Pattern sites are associated with an influx of people from outside of California, who introduced subsistence patterns adapted for a riverine-wetlands environment (Moratto 1984:207).

Windmiller Pattern sites are often in riverine, marshland, or valley floor settings, as well as atop small knolls above prehistoric seasonal floodplains. Such an area provided a wide variety of plant and animal resources. Most Windmiller Pattern sites have contained burials with remains that are extended ventrally, oriented to the west, and that contain copious amounts of mortuary artifacts. These artifacts often include large projectile points and a variety of fishing paraphernalia: net weights, bone hooks, and spear points. The faunal remains indicate that the inhabitants hunted a range of large and small mammals. Stone mortars and grindstones for seed and nut processing are common finds. Other artifacts—such as charmstones, ochre, quartz crystals, and both Olivella and Haliotis shell beads—suggest a practice of ceremonialism and trade (Kozakavich 2017).

The subsequent Berkeley Pattern (previously included in the Middle Horizon culture) covers a period from about 3500–1500 B.P. in the San Francisco Bay region. This pattern shares some attributes with the Windmiller Pattern at the beginning of the sequence and with the Late Horizon Period at the end. Berkeley Pattern sites are much more common and well documented, and therefore better understood, than Windmiller Pattern sites. These sites are scattered in more diverse environmental settings, but riverine settings are prevalent.

Deeply stratified midden deposits, which developed over generations of occupation, are common to Berkeley Pattern sites. These middens contain numerous milling and grinding stones for food preparation (Kozakavich 2017). Projectile points in this pattern become progressively smaller and lighter over time, culminating in the introduction of the bow-and-arrow during the Late Horizon Period. Slate pendants, steatite beads, stone tubes, ear ornaments, and burial techniques that use variable directional orientation, flexed body positioning, and a general reduction of mortuary goods are unique to Berkeley Pattern sites (Fredrickson 1973:125–126; Moratto 1984:278–279).

The Late Prehistoric Period (formerly the Late Horizon) ranges in date from about 950–150 B.P. This period coincides with Fredrickson's Augustine Pattern, which is typified by intensive fishing, hunting, and gathering (especially acorns); a large population increase; expanded trade and exchange networks; increased ceremonial and social attributes; and the practice of cremation in

addition to flexed burials (Kozakavich 2017). Certain artifacts are also distinctive in this pattern: bone awl, bow-and-arrow use, occasional pottery, clay effigies, bone whistles, and stone pipes (Kozakavich 2017).

#### 3.3 Ethnographic Setting

At the time of European contact, the Proposed API/APE was within the territory of the Patwin, a southern Wintun linguistic group (Kroeber 1925, 1930; Barrette 1908), and the Ompin, Bay Miwok, a western Utian linguistic group. Two analytical zones immediately surround Suisun Marsh—the Bay Area (Bay Miwok and Ohlone) and Middle Sacramento Valley (Patwin). Pre-mission populations in these regions were estimated as 2.1–4.0 persons per square mile in lands southeast of the marsh (Bay Miwok), increasing to 4.1–8.0 to the west and north (Meyer et al. 2013).

#### 3.3.1 The Patwin People

Kroeber notes that by 1923, the southern half of the Patwin group was wholly extinct. The Patwin are members of California Penutian linguistic stock, and they occupied the southwest portion of the Sacramento Valley, from the lower hills of the eastern North Coast Ranges to the Sacramento River, from Princeton south to San Pablo and Suisun Bays and into Napa Valley as far north as Calistoga. Kroeber (1970) states that prior to contact, the Patwin totaled nearly 12,000 individuals. Kroeber noted that there were permanent habitation sites of the Patwin along both banks of the Sacramento River, where small knolls were sufficient to protect the inhabitants from severe winters. Patwin were also commonly found along seasonal streams and springs in the foothill regions fronting the western margin of the Sacramento Valley.

The Patwin were organized into a principal village and a few satellite settlements. These groups were small, autonomous, and sometimes bounded by the limits of a small drainage. Each group had a head chief, and each village had a chief who administered its economic and ceremonial activities. The position of chief was usually inherited through the male line, but village elders occasionally chose some chiefs. McKern (1922) presented Patwin social structure in terms of three systems: the patrilineal family, the family social group, and the household unit.

The patrilineal family and descent were important features of Patwin social life, and the authority bestowed on the headman of each patriarchal family was undisputed, except in matters of tribal authority. The family social group is a larger unit that includes the husbands of female patrilineal family members and is unified by the authority of the family headman. Matrilocal residence was customary among the Patwin, and husbands routinely remained with their wife's families at least until they acquired enough wealth to establish an independent household (Kroeber 1932, 1970; McKern 1922, 1923).

Patwin subsistence relied on hunting, fishing, and gathering a wide variety of plant resources that were within their territory. Acorns were a major part of their diet and were obtained from hill and mountain oaks communally owned by the tribelet. Other easily gathered resources included blackberries, elderberries, wild grapes, new tule shoots, roots and bulbs, honey, salt (acquired from burning salt grass), and tobacco (Kroeber 1970). Kroeber's informants, however, did not report familiarity with many plants (e.g., buckeye, hazelnut, manzanita, etc.) that are dietary staples among other Native American groups.

Ethnographic records indicate that large game (e.g., deer, tule elk, antelope) were captured using nets or were shot using bows and arrows. Kroeber reports that two men would hold a wide meshed net while other hunters would drive deer into it, and waterfowl (ducks, geese, mudhens, quail, etc.)

were also captured using nets. Fish were also a prime resource, and certain fishing sites were privately owned. Fish (such as salmon, sturgeon, perch, chub, sucker, hardhead, pike, and trout) and other riverine resources (such as turtles and mussels) were caught with bone fishhooks, nets, seines, and weirs. Food resources were generally stored in bins and granaries, which were made of sticks set into the ground and were roofed with tules.

The Patwin manufactured a variety of utilitarian and ceremonial/luxury items, including baskets, stone tools, mortars and pestles, shell beads, and clothing. Coiled and twined baskets of willow and split tule were used for various purposes, including food collection, preparation, serving and storage; use as baby carriers; and for use as grave goods that were interred with the dead. A variety of tools (i.e., projectile points, bifaces, drills, scrapers, and knives) were manufactured from obsidian, chert, and basalt for both utilitarian (skinning, butchering, etc.) and ceremonial (such as burial accompaniment) purposes. Pestles and mortars made of oak and stone were used to process both plant and animal resources. Shell beads were also manufactured for personal adornment and as a medium of exchange. Clothing was generally minimal, and "men went without any covering, women wore skirts or aprons of tule or shredded bark" (Kroeber 1925).

The Patwin traded for various commodities and subsistence resources using clamshell disc beads as a medium of exchange. Kroeber referred to Patwin territory as a center for several religious sects among groups of central California Native Americans. These sects were generally based on the organization of male secret societies and are characterized by Kuksu or "bighead" dances. Kuksu emphasized curing and shamanistic functions, and its ceremonies generally consisted of impersonating spirits who journeyed from their home to a village, blessed the village, and then returned home (Kroeber 1925).

#### 3.3.2 The Miwok People

The Ompin group of Bay Miwok are associated with the eastern and southeastern Suisan Marsh edges, where the San Joaquin and Sacramento rivers enter the Suisun Bay (Meyer et al. 2013). Within the Bay Miwok grouping were the Saklan, Chupan, Wolwun, Julpun, and Ompin (Beeler 1955; Bennyhoff 1961). Archaeological and linguistic data support the assertion that the Miwok had arrived in the Diablo and Delta area before A.D. 1, displacing the earlier Hokan-speaking people that lived in the region (Wiberg 2010).

The Bay Miwok were hunter-gatherers, taking advantage of the abundant natural resources in the Delta and alluvial plains (Levy 1978). This lush environment was able to sustain a relatively dense population despite the lack of agriculture. The Delta marshland was very productive as were the Central Valley grasslands. Less productive portions of the regions included the uplands, which were able to support a mixture of oak and conifer trees (Wiberg 2010).

Like many other California groups, acorns were a staple carbohydrate of Bay Miwok foodways. In addition to this, however, a variety of flora and fauna were available for foraging and hunting. These included "several types of berries, clover, wild onions, and carrots, mammals, fish, reptiles, shellfish, and insects" (Wiberg 2011: 14). Vegetal resources also provided the material for cordage and weaving baskets. Baskets were used for cooking, as utensils, storage containers, water jugs, and as trays for leaching and drying acorn meal (Kroeber 1925:467).

Importantly, the Bay Miwok were not passively acquiring their subsistence from the environment. They were, in fact, very active in managing and improving their environment through fire. By burning grass and brush annually, they were able to be in better control of their natural resources. Their foraging for deer and rabbits was improved by eliminating much of the area in which they

would hide. Periodic burning also kept them safe from predators and neighbors and improved the land's productivity (Wiberg 2010).

The Bay Miwok were organized into "tribelets," which were, "small independent group[s] of usually related intermarried families occupying a specific territory and speaking the same language or dialect" (Wiberg 2010: 22). Notably, a great diversity of languages was present in contact-period California, with some dialects only spoken by very small groups. These groups were not isolated, however, as trade and marriage enabled tribelets to access resources they otherwise would not have accessed. Other aspects of social life that would bring people together include regional festivals and religious dances. The division of labor within California tribelets usually distinguished between women's work in food harvesting, preparation, weaving, and childrearing, and men's work in hunting, fishing, trade, warfare, and the training of older sons.

When the Spanish arrived, trade patterns that were thousands of years old were in place. Archaeological evidence suggests that these trade patterns brought goods from as far as a few hundred miles away based on the sourcing of obsidian artifacts. Mollusk shell beads and ornaments, "evolved through many different and definable types through the millennia," which allows archaeologists to both estimate a relative date for a site and the social and cultural position of the people who once lived there (Wiberg 2011: 15).

The territory of the Saklan was, "the interior valleys from Lafayette to Walnut Creek and Danville" (Cook 1957: 147). Although the central village may have been near modern Walnut Creek, "at least two smaller, subsidiary Saklan settlements were known to exist" at the time of Spanish colonization (Fredrickson 1968). The location of these settlements is currently unknown. Although Spanish observations suggest that total Saklan population in the early nineteenth century was between 100–300 people (Fredrickson 1968), this number may have been much higher. Based on the group's absorption of 40 people lost to missionization between 1794–1798, as well as the conversion of others and attrition due to disease and food supply inconsistencies, Cook (1957: 143, 147) suggests that the preconquest population must have reached, "at least 300 and very likely was much greater."

More comprehensive ethnographic and archaeological summaries of the Saklan and their neighbors in what is today Contra Costa County may be found in The Handbook of North American Indians, Volume 8: California (Levy 1978:398-413), Handbook of California Indians (Kroeber 1925: 442-461), and California Archaeology (Moratto 1984).

#### 3.4 Historic Overview

The history of northern California, Solano County, and the Proposed API/APE, in particular, can be divided into several periods of influence to establish a historic context to assess the potential significance of historic sites in the Proposed API/APE. Due to its location 40 mi (65 kilometers) east/northeast of San Francisco, the Proposed API/APE was largely isolated from the Spanish and Mexican periods of California. Therefore, events associated with the Spanish and Mexican periods, and cultural remains from those periods, are not expected to be reflected in the Proposed API/APE but are discussed briefly as a point of reference.

#### 3.4.1 Spanish Era (1769-1821)

The earliest historical accounts of the area come from the Spanish explorers who ventured into the area east of the Bay Area in the late eighteenth century. In 1775, when Captain Juan Manuel Ayala's expedition explored the San Francisco Bay, some of his men may have ventured up the

Sacramento and San Joaquin rivers during three explorations of the Bay that yielded the first accurate maps of San Francisco Bay (Kamiya 2014). In 1776, the Anza-Font expedition traveled along the southern shore of Suisun Bay until reaching Antioch, where they noticed numerous campsites before turning southeast in an attempt to cross the tule swamps (Cook 1957). There is no evidence that the Spanish explored north of the river at the site of the Proposed Project during this period, but they must have passed within a few miles of it on the southern side of the river (Farris et al. 1988).

At the time of the Spanish arrival, Solano County was home to the Patwin Indians. Some of their village places have survived phonetically in such modern places as Suisun, Soscol, Ulatis, and Putah (Solano County 2023).

#### 3.4.2 Mexican Era (1822–1848)

Under the Spanish, the missions controlled the land. After Mexico seceded from Spain in 1821, land was granted to private citizens, a practice that increased significantly after the 1833 act of the Mexican legislature that established the secularization of the missions (JAH 2005). By 1845, the last of the mission land holdings were relinquished, opening the way for the large ranchos common to California in the mid-1800s. Predominant land use on the ranchos was the raising of livestock and ranching. The Proposed API/APE straddles two Mexican-era land grants, or ranchos, within Solano County and Contra Costa County.

The northern of these was the Rancho Ulpinos. It included 17,726 acres in southern Solano County, including what would become the cities of Collinsville, Rio Vista, Newtown, Birds Landing, and Montezuma. This Rancho includes two watercourses: the Sacramento River and the Estero Ulpinos. This Rancho was given to John Bidwell in 1852 by Governor Manuel Micheltorena (Perez 1982; U.S. District Court [USDC] 1857).

The 1848 Treaty of Guadalupe Hidalgo that ceded California to the U. S. provided that the land grants would be honored. As required by the Land Act of 1851, a claim for Rancho Los Ulpinos was filed with the Public Land Commission in 1852 and the grant was patented to John Bidwell in 1866 (USDC 1857).

The other rancho in the API/APE of the Proposed Project is the Rancho Los Medanos, immediately south of the Rancho Los Ulpinos. It is composed of 8,853 acres, including the watercourses of the San Joaquin River and the Suisan Bay, and covers the modern-day cities of Pittsburg and Antioch (Perez 1982).

The ranch was granted in 1835 to Jose Antonio Mesa and Jose Miquel Garcia. Mesa and Garcia sold the southern half of their rancho to Colonel Jonathan D. Stevenson in 1849 and the northern half to James Walsh, Michael Murray and Ellen Fallon in 1850. There was confusion about the orientation of the grant, and in 1851, Stevenson arranged an exchange of deeds, whereby he received the western half of the rancho and Walsh, Murray, and Fallon received the eastern half (Supreme Court of California 1904). As required by the Land Act of 1851, a claim for Rancho Los Medanos was filed with the Public Land Commission in 1852, and the grant was patented to Jonathan D. Stevenson et al. by 1862 (Hoffman 1862).

#### 3.4.3 Historical Era (1848-present)

#### **Contra Costa County**

Contra Costa County was one of the original 27 counties established in California, created by the legislature in 1850. The name refers to its position on the "opposite coast" directly across the bay from San Francisco (McCullough 2022).

The Spanish visited Contra Costa County in the 1770s during exploratory expeditions and named many of its geographic features and created some of the earliest maps. Later, Spain and ultimately Mexico granted great tracts of land called ranchos to settlers. Cattle ranching came first, followed by more varied farming (McCullough 2022).

One of the early responsibilities of the county was roads, which were important in the early days as connectors of the communities that spread across the county. These earliest communities, such as Antioch, Danville, Lafayette, and Walnut Creek, have grown into thriving cities and towns (McCullough 2022).

There are also several examples of towns that no longer exist. The great boom in coal mining in the eastern part of Contra Costa County created several thriving settlements, such as Stewartsville. Coal was one of the biggest industries in Contra Costa County from the 1860s until the early 1900s (McCullough 2022).

Agriculture was the latest economic activity in the nineteenth century, and through the years, there was a succession of crops grown, with wheat, grapes, and walnuts being the front runners. Industrial development eventually occurred with the Standard Oil refinery in Richmond, as well as other refineries later. Sugar refining, canning, explosives, and lumber also flourished in the late 1800s. The presence of deep water along the western shore and the Carquinez Strait made agricultural development in the region possible. Port Costa was an important spot from 1879 until 1930, serving as the point where the trains crossed the Carquinez Strait on an immense ferry, the largest in the world (McCullough 2022).

The coming of the Southern Pacific and Santa Fe Railroads in the latter part of the 1800s and the early 1900s made this industrial development even more attractive (McCullough 2022).

Today, Contra Costa County is home to more than one million residents with 19 cities and many established communities in the unincorporated area. It is now the ninth most populous county in the state (Contra Costa County 2022).

Solano County Throughout history, Solano County has been overwhelmingly agricultural in character (EDAW 2008). Different parts of the county had different soil and climate conditions, resulting in different kinds of agriculture predominating in different areas. Agriculture also changed over time as farmers experimented with different crops and discovered which ones were most productive. The arrival of the railroad and refrigerator cars stimulated further changes.

During Mexican occupation, and for some years after that, cattle raising was the principal industry of the county (EDAW 2008). The valleys were filled with oats, and one early county history repeated an oral account regarding the height they attained: a man seated on horseback could reach out with either hand, grab a fistful of oats, and tie a knot over his head. Grazing cattle could be seen only by the paths they had made.

In the late 1840s and 1850s, former gold seekers and pioneers began settling Solano County, where they raised livestock and cultivated fruit orchards, vineyards, wheat, barley, and oats (EDAW 2008). Produce and livestock were transported overland by wagons to the many sloughs throughout the

county, and then shipped by water to waiting markets. Twelve townships were established in Solano County between 1850 and 1871. Although the largest towns were adjacent to San Pablo and Suisun Bays, most towns were situated at the ends of sloughs or channels that primarily ran through the eastern portion of the county.

One of those towns was Collinsville, originally called Montezuma Township, named so after L. P. Marshall's Montezuma House nearby on the northern edge of Suisun Bay. The town was later sold to C. J. Collins in 1859 and was officially named Collinsville (Gudde 1998). By 1861, the Collinsville wharf was built, and the town applied for an official post office, allowing for better business and trade in the area (Supreme Court of California 1882). The small fishing village was approved for a steam ferry in 1868 to travel between Collinsville, New York Landing, and Antioch. It soon became a major ferry stop for hides and tallow crossing the Carquinez Strait while traveling to the cities farther south. In 1867, the town was purchased by S. C. Bradshaw, who renamed the town Newport and began selling some 29,000 lots, many of which were (literally) underwater (at high tide). The scam failed, and the sheriff seized the town and renamed it Collinsville. The land was later sold to E. I. Upham who returned the name Collinsville to the town in 1872 (Bowen 2000).

By the 1870s, Collinsville had a large salmon cannery and hotels and stores that serviced its workers. When the cannery closed, Collinsville began declining; the population fell to just eight people and some 20 homes. Although the population has increased slightly since then, a fire in 2014 destroyed half of the remaining sleepy town.

In 1868, the completion of the California Pacific Railroad through Solano County allowed the shipment of goods to East Coast markets, significantly bolstering economic development, agricultural production, and population growth (EDAW 2008)

In 1913, the Oakland, Antioch, and Eastern Railway, a high-speed electric interurban railway, opened its 93-mi route from San Francisco to Sacramento through largely unpopulated parts of southern Solano County (Boehle 2013). In 1928, the Sacramento Northern Railway purchased the railway, but the Depression and the popularity of the automobile contributed to the end of passenger service in 1940; by 1987, the railway had been abandoned (EDAW 2008).

Fruit agriculture dominated the early history of Solano County. One of the earliest fruits to prosper in Solano County was grapes. Grapes were plentiful from the 1850s to the 1870s, but in the latter decade, disease ruined much of the grape harvest. In the late 1870s, grape vines were largely replaced by orchards.

Currently, Solano County's most prevalent economic activities continue to be agriculture and livestock. A wide variety of vegetables, fruit, and nuts are grown, with walnuts being the most recent crop to gain popularity. The county is in the top five California producers of corn, lamb, sheep, and Sudan grass hay (EDAW 2008).

Increasingly, the county has become a bedroom community for Sacramento and the San Francisco Bay area, and major companies such as Anheuser-Busch, BIOSOURCE Technologies, Chiron, Costco, Genentech, and Pacific Bell are in Solano County (EDAW 2008). Even though a modern technological industry had moved into the northern county, Collinsville remains a small and isolated rural community.

#### **Sacramento County**

The first permanent settlement within the limits of what is now Sacramento County was established by Captain John A. Sutter, a European explorer known for his pioneering expeditions across the Americas. Sutter arrived in what would become the Sacramento region via the

Sacramento and Feather Rivers and established "Sutter's Fort" in 1839. Sutter's Fort quickly became a hub for fur trade and immigration into the remote region of Northern California. Year by year, parties of immigrants gradually increased, until after the discovery of gold, when they could be counted by thousands and tens of thousands (Davis 1890).

With the discovery of gold in California in 1848, the Sacramento region became a national and international focus of attention, drawing a mass migration of gold seekers, miners, and pioneers to the area (Davis 1890). During the Gold Rush era, Sacramento served as a center for commerce and agriculture as well as a major supply distribution point. The area was a terminus for wagon trains, riverboats, and stagecoaches. With the influx of migration to the area, Sacramento County was incorporated in 1850 in response to the needs of a growing population. The County is one of the original 27 counties of California and became the capital of the State of California in 1854.

Construction of the Central Pacific Railroad began in Sacramento and continued east to join the Union Pacific line in Utah in May 1869, forming the first transcontinental railroad and opening a major transportation route that linked the United States from the east and west (Davis 1890). Communications also opened up with the arrival of the Pony Express and the introduction of the telegraph. By the early 1900s, the use of automobiles was growing rapidly, and along with it came the construction of roads and bridges. Another major link between the east and west coasts, the Lincoln Highway, ran through Sacramento County.

In the early 1900s, Sacramento County was one of the large wheat growing counties, but as wheat growing became less profitable and the land became more valuable, the land gradually became utilized for vineyard and orchard production. The region's soils and climate were admirably adapted for these crops with its thermal belt in the foothills and higher plains regions. Sacramento became the chief shipping point for all kinds of fruits, especially citrus fruits (Davis 1890).

By the end of World War I, the area housed an airfield and a pilot training school and became a hub for the construction of bi-wing airplanes in the northern region of the county (Davis 1890). After the war, many of the planes were converted for civilian use. From that time on, aviation has grown to become a vital part of the region's development. Today, the County is home to the Sacramento County Airport System, which includes the Sacramento International Airport. Several military installations were in the region during the 1900s. Although the bases have closed, two former military locations, Mather and McClellan, have now become active business centers within the County.

Today, Sacramento is now home to seven cities and hosts a diverse employment sector. Government remains a major employer, with federal, state, and local offices in the region. The State Capitol houses the executive and legislative branches of the California government. Other large employment sectors include education, information technology, health services, leisure and hospitality, and transportation (Sacramento Country 2023).

# 4 Historical Background

#### 4.1 Historic Context

#### 4.1.1 Maritime History of the Sacramento River Delta

As a result of its role as a riverine navigational corridor between San Francisco Bay and the interior of California, the Sacramento River Delta experienced intensive navigation throughout the

nineteenth and twentieth centuries. Though earlier European exploration of the Sacramento River Delta widely employed boats, regular navigation of the Delta was only introduced in the 1830s.

In 1810, Mexico rebelled against the Spanish crown, ultimately gaining its independence from Spain in 1821. The Republic of Mexico issued land grants in the Sacramento area beginning in 1833, when John Rogers Cooper, a British sea captain who had married into a native California family, received one of the first grants in the area. The largest grant was issued to John Sutter, who in 1839 founded the town of New Helvetia near current-day Sacramento. The establishment of this town, the center point of several land grants, began the era of regular traffic on the river.

In 1841, Sutter purchased Fort Ross (renamed Sutter's Fort) for \$30,000, which also included a steam launch that he named the *Sacramento*. This vessel was the first to make regular round trips from the Sacramento area to San Francisco, taking two weeks for each trip. Soon after his purchase of the fort, Sutter constructed a road from the fort and a wharf at the mouth of Sutter's Slough, which became known as the Embarcadero (Figure 4-1).



Figure 4-1. Artist's conception of the Embarcadero prior to the gold rush (courtesy of the Sacramento Pioneer's Association Collection, City of Sacramento, Museum & History Division).

The area surrounding the Embarcadero, like most of the delta, was subject to frequent flooding, and, in Sutter's mind, was not a suitable location for a settlement. The Embarcadero was simply intended to be the port for his planned town of Suttersville, which he located to the south on higher ground. One of the earliest narratives on the Embarcadero is provided by William Grimshaw, who visited the area in November of 1848:

In about ten days-an average passing (traveling in a ship's longboat)-we arrived at Sutter's Embarcadero and made fast to some Sycamore trees, at the outlet of Sutter Slough and just above what is now the foot of I Street. Here was a spit of sand something like a small strip of beach.

The only vessel here was the barque *Providence*, dismantled and fitted up as a store by George McDougal and William (afterwards Judge) Blackburn. This vessel was moored to the river side and on the bank above was a broad shanty in which lived the firm above named, Wm. Nuttal, their clerk, and my old shipmate, Tom Newton, porter. Mrs. D. was living under the protection of McDougal as his mistress.

This shanty was at that time the only building where now stands the City of Sacramento. There was a rancheria of miserable Indians, who appeared to live by fishing, and a lot more were encamped across the outlet of the Slough. All the rest of the place was a complete wilderness. (Kantor 1964:11-12)

The Embarcadero was the main docking point for the area and would later become the jumping-off point for the thousands of people entering the area during the gold rush.

With the constant arrival of ships, passengers, crew, and cargo to the Embarcadero, the distance between it and the city of Suttersville became somewhat impractical. Sutter's son, John Sutter, Jr., helped, with the aid of Sam Brannan, to undercut John Sutter's plans to make Suttersville the area's main settlement by creating the town of Sacramento near the Embarcadero. The two cities briefly vied for control of the Sacramento River and the gold rush trade, ultimately resulting in Suttersville ceasing to exist as a viable center, leaving Sacramento as the dominant town in the area (Figure 4-2).




Figure 4-2. Lithograph of Sacramento in 1849 (courtesy of California State Library).

In 1847, the first steamboat to make regular runs on the Sacramento River was put into service. The *Sitka*, a small sidewheeler, barely 37 ft long, was purchased unassembled from the Russia America Company and assembled on Yerba Buena Island. Taking six days to make the run from Sutter's Fort to San Francisco, the vessel was generally slower than walking due to its weak engine. It was removed from service after a short time and converted to a sailing vessel, then sank in San Francisco Bay in 1848.

With the discovery of gold at Sutter's Mill in 1849, 100,000 gold-seekers descended on California, many of whom passed through Sacramento and the Embarcadero. With this mass influx of people

came great demand for goods and services, and a market eagerly filled by merchants and shippers from all over California. Among the first cargo vessels to arrive at Sacramento in 1849 were two ocean-going sailing vessels, the *Joven Guipuscoana*, owned by Sam Brennan, and the *Eliodora*. The *Whiton*, a bark, was among the first vessels to arrive from the east coast of the U.S. with a stated destination of Sacramento, reaching the Embarcadero on May 2, 1849.

As occurred in most ports during the height of the gold rush, as quickly as vessels arrived at the Embarcadero, their crews jumped ship to seek their fortunes in the gold fields. Abandoned vessels were turned into warehouses, hotels, store ships, and other uses (Figure 4-3). One abandoned vessel, *La Grange*, was used as the Sacramento jail from 1850 until it sank in 1859.




Figure 4-3. Sacramento waterfront in 1851, showing converted store ships (courtesy of the California Department of Parks & Recreation Collection, City of Sacramento, Museum & History Division).

Despite the rush of people to the gold fields and the abandonment of vessels by their crews and sometimes owners, some entrepreneurs recognized the money to be made in providing services to the gold rush participants. This included regular transportation service on the Sacramento River. Ocean-going sailing vessels were impractical, as they typically took a week or more to travel from San Francisco to Sacramento, and often had to be towed or kedged up the river. The answer, of course, was steam. In November of 1849, the steamer *Senator* arrived at Sacramento, and began regular service between that town and the coast. Carrying up to 300 passengers and 300 tons of freight per trip, the vessel made three round trips per week. Charging \$30 per passenger for a oneway trip from San Francisco to Sacramento, and \$30 per ton for freight, the *Senator* cleared monthly profits of \$60,000.

Such profits enticed other vessels, and by 1853, there were six vessels providing service between the two cities. Although such competition drove down the high rates, profits were still high as the

demand for transportation increased. In the summer of 1850, 203 vessels reached Sacramento, rising to 426 in 1851. Traffic reached a peak in 1852 and began to drop in 1853 due to the departure of many miners, who left after the easily accessible gold deposits had been extracted. Traffic would again increase in the area at the end of the decade with the discovery of the Comstock Lode in 1859.

In 1854, the California Steam Navigation Company was incorporated. This organization was essentially a cartel made up of the largest vessel operators on the river. Seven vessels, including Confidence, Colusa, Governor Dana, New World, Antelope, Helen Hensely, and Sam Soule, were able to leverage their domination of trade on the river by cutting prices, gaining control of wharves to shut out other operators, and other monopolistic behaviors. Operators that were not a part of the cartel either went bankrupt or agreed to charge prices fixed by the cartel.

With the expansion of agriculture along the Sacramento River after 1855, the river became the main route of travel for produce, linking the development of agriculture and the development of river navigation. Many farmers used small sloops, schooners, and other small vessels to bring their crops to market. These produce vessels soon evolved into a specialized type that was adapted to the needs of the river and the farmers. By 1864, regular service to San Francisco by these freight vessels was in place. Each vessel made two round-trip runs from San Francisco each week, dropping off empty shipping containers on the upstream trip and loading produce on the downstream trip.

Small steamboat companies evolved to serve the needs of the farmers. In 1867, the first produce steamer entered service on the river. The *Reform*, a 181-ton sternwheeler, offered a two-day round-trip service to San Francisco, carrying both cargo and passengers. Like the many sloops that preceded it, *Reform* called at many of the smaller landings on the river. The operation of this vessel evolved into the California Transportation Company, which was formed in 1875 and operated a small fleet of steamers until the end of the steam era (Thompson 1957:404).

In addition to organized vessel lines, several independent operators with one or perhaps two vessels, such as the *Dutchess* (Figure 4-4), provided service between smaller cities and the larger centers like Stockton and Sacramento. In the 1890s, J.C. Parker ran a small steam launch, *Belvedere*, between Rio Vista and Sacramento, making the round trip daily with stops at many small towns in between (Figure 4-5). In 1895, he incorporated the Parker Transportation Company, launching a larger vessel for the same run (Sacramento River News 1895) that could make one leg of the trip in four hours.




Figure 4-4. Steamer *Dutchess*, operated by Laurentzen Transportation Company between 1908 and 1918 (photo courtesy of Rio Vista Museum).

# STEAMER BELVEDERE LEAVES RIO VISTA DAILY AT Logical Research and Statements at 11:30 a. m.; Freeport, 9:45. Arrive at Sacraments at 11:30 a. m. Leaves Fish Market, between K and L. Sacraments, at 3 p. m.; Freeport, 4:15; Clarksburg, 4:45; Courtland, 5:30; Walnut Grove, 6:30; Ryde, 6:45; Isleton, 7:30. Arrive at Rio Vista at 8 p. m. Stops made at all landings. Fare, \$1, and 50 cents between landings.

Figure 4-5. 1894 Sacramento River News advertisement for passenger and freight service by steamer Belvedere (Sacramento River News 1894).

The small river vessels, both steamers and sailing vessels, independent and corporate, served a distinct need, as the larger river steamers stopped only at major towns along the river. Steamers such as the California Transportation Company's S.M. Whipple and the Chin-Du-Wan most likely stopped at all landings between Sacramento and San Francisco at one time or another. Historic maps depict many of these landings, which were constructed by, and belonged to, farmers and small towns along the river. There were likely many more landings that are not illustrated on maps.

Shipping on the Sacramento River increased throughout the second half of the nineteenth century and well into the twentieth century. At the beginning of the 1880s, an average of 202,000 tons per year were shipped on the river, increasing to 400,000 tons per year by the end of the century. Much of this traffic was wheat, accounting for 100,000 tons in 1900.

In the 1890s, river traffic began to consolidate under navigation companies, including the California Navigation and Improvement Company, Southern Pacific Railway, and the California Transportation Company. These companies, operating smaller steamers and serving the many small landings on the river, tended to drive the independent operators, who were not able to offer the regularity of schedule or match the prices of the larger operators, out of business. Of the 400,000 tons shipped in 1900, around 350,000 tons were shipped by three major carriers, including Southern Pacific (162,000 tons), the California Transportation Company (98,000 tons), and the Sacramento Transportation Company (88,000 tons) (McGowan 1961:214).

Freight rates varied according to the amount of competition on the river and the demand from shippers. Although the ultra-high rates of the gold rush era were an anomaly, rates, in general, were fairly consistent and reasonable. In 1877, sacked grain cost \$1 per ton to ship to San Francisco, potatoes \$1.50 per ton, and watermelons \$2 per hundred. A typical landing, or calling charge, was assessed for each stop except for landings in larger cities, which were often designated as free stops (Thompson 1957:407).

In the early twentieth century, a recession in freight traffic occurred, coinciding with a drop in wheat production along the Sacramento River. The total tonnage of freight shipped on the river declined from 400,000 tons in 1900 to 350,000 tons by the end of the recession in 1908 (McGowan 1961:214).

This recession was offset somewhat by an increase in passenger traffic. The total number of passengers on the river in 1901 was 8,673. By 1908, this had increased to over 150,000 per year (McGowan 1961:215). Increased affluence, lower fares, and the increasing popularity of excursions were likely behind this meteoric increase. The most visible river steamers during this period were the Southern Pacific sternwheelers *Apache* (Figure 4-6) and *Modoc*. With a capacity of 500 passengers, these boats were typical of river steamers, carrying cargo on the lowest deck and passengers on the upper two decks. Running from San Francisco to Sacramento with scheduled stops at Rio Vista, Isleton, and Clarksburg, these boats often made stops at smaller landings to pick up produce or passengers.




Figure 4-6. Southern Pacific steamer Apache (photo courtesy of Rio Vista Museum).

Typical of these trips was a voyage by the *Apache* on January 26 and 27, 1910. The vessel left San Francisco at 1:30 p.m. on January 26 with 26 passengers and stopped 25 times, including landings at Port Costa, Benicia, Collinsville, Emmaton, Rio Vista, Isleton, Ryde, Walnut Grove, Vorden, Courtland, and Clarksburg. Most stops were around two minutes, with the scheduled stops not often exceeding 25 minutes. The *Apache* arrived in Sacramento at 4:14 a.m., with a total upriver running time of 14:17 (McGowan 1961:215).

In the early 1910s, Southern Pacific added two more steamers to the San Francisco to Sacramento run, including the *Navaho* in 1910 and the *Seminole* in 1912. These two vessels operated as packets, making few or no stops, and ran in concert with the *Apache* and *Modoc*. The Navaho was described as a floating palace and was every bit as opulent as contemporary Mississippi River boats when she was launched in 1910. Making three trips per week with 10 stops on each run, she took eight or nine hours each way. The *Seminole* made no stops and typically took less than eight hours to make each leg of the trip. The *Navajo*, a fixture on the river for many years, was used along with two other vessels to block a levee breach on Mandeville Island in 1938; it was used as a bunkhouse and as storage for several years after (Figure 4-7). The *Navajo* was burned in 1973.

The California Transportation Company entered the passenger business for the first time in 1907 with the steamers *Pride of the River* and *Captain Weber*. This is mentioned in the Rio Vista *River News* of Friday, October 25, 1907, noting the new steamers and their run from Sacramento to San Francisco as first-class night boats carrying both freight and passengers. Meeting with success,

the company launched two luxurious vessels in 1913, the *Capital City* (Figure 4-8) and the *Fort Sutter*, each being 219 ft long with four decks and capable of carrying 500 passengers.




Figure 4-7. Southern Pacific steamer *Navajo*, landlocked on Mandeville Island circa 1970 (as presented in Schell 1995).




Figure 4-8. California Transportation Company steamer *Capital City* (courtesy of Rio Vista Museum).

The recession in freight on the Sacramento River began to reverse in 1910, when 500,000 tons of cargo were shipped. By 1914, this total had increased to 700,000 and then increased to 1,000,000 in 1918. At one point in 1913, eight large steamers were tied up to the Sacramento city wharf. By 1920,

Sacramento had 4,734 ft of linear dockage and 201,000 square ft of warehouse space (McGowan 1961:216). In response to the increased demand for freight capacity, the Sacramento Transportation Company launched the *Colusa* in 1911. The largest freighter on the river at the time of her launch, she was over 200 ft long but drew only 4 ft when fully loaded.

Passenger traffic peaked in 1913, with 212,000 passengers. Steamer lines struggled to keep up, with passengers often having to sleep on the deck or in passageways. Passenger traffic began to decline after 1920, however, due mainly to the introduction of the automobile and the improvement of the delta's road system. The three most popular boats—Fort Sutter, Capital City, and Captain Wheeler—carried 102,000 passengers in 1921, but by 1929 this dropped to 61,000. Still, this equated to just over 1,000 passengers per week (McGowan 1961:217).

Despite this drop in passengers on steam vessels, the 1920s witnessed the introduction of what many consider to be the finest boats to steam the Sacramento River. In 1927, the California Transportation Company launched the twin sternwheelers the *Delta King* and the *Delta Queen* (Figure 4-9). Built of iron and powered by compound steam engines, the vessels were constructed in Scotland, shipped in pieces, and then assembled in Stockton. The *Delta Queen* and the *Delta King* were each 250 ft in length, 58 ft in beam, and drew 11.5 ft of water, with a registered tonnage of 1,300. Like most steamboats, cargo was carried on the main deck, with the two upper decks reserved for passengers. The passenger cabins were finished with oak, teak, mahogany, and Oregon cedar. Each of the vessels cost the company \$875,000.

Passenger traffic continued to decline throughout the 1920s, dropping precipitously after 1929. In 1933, annual passenger traffic had dropped down to just 23,000 from the 61,000 passengers in 1929. By 1935, it had dropped to 17,000. By 1932, the existing steamboat companies consolidated as River Lines Incorporated (McGowan 1961:218). In the consolidation process, several of the long-standing river boats were removed from service, including *Isleton, Pride of the River, Flora, Dover, Red Bluff* (Figure 4-10), *Colusa, San Jose, Valletta, San Joaquin No. 1, San Joaquin No. 2, Sacramento,* and *Jacinto*.




Figure 4-9. California Transportation Company sternwheelers *Delta King* and *Delta Queen* in 1936 (as presented in Schell 1995).



Figure 4-10. Steamer *Red Bluff* and barge *Nebraska* loading grain (photo courtesy of Yolo County Public Library, Clarksburg Branch).

In addition to reduced passenger load, several labor strikes further crippled the river steamboat industry. Between May 1934 and February 1937, three strikes shut down river traffic. The first of these lasted for just two months, but the second strike lasted from July 1935 to April 1936. River Lines suspended river travel, which stayed suspended—permanently, as it turned out—on the San Joaquin River. The third strike lasted three months, until February of 1937, and cost the River Lines \$100,000 in addition to the loss of income from freight shipments (McGowan 1961:218).

As the Great Depression ended in the late 1930s, so did steamboat traffic on the Sacramento. In 1941, the *Delta King* and *Delta Queen* were leased to the U.S. Navy for use as troop transports on San Francisco Bay, effectively ending passenger steam navigation in any significant amount on the Sacramento River.

Steam navigation met its demise at the same time all over the United States. Mostly, the downfall was due to a general shift from boats to automobiles for passenger travel, and a shift to railroad transportation for freight travel. However, the delta was somewhat different.

The first serious competition to river travel by the railroad industry occurred during the 1870s, as railroad lines were being laid in the delta, and silting of the upper river due to hydraulic mining during the gold rush era restricted river travel in those areas. Rail service tended to be more reliable, and according to Thompson (1957:10), drew about 75 percent of the wheat crop from these areas. However, this was not indicative of the region as a whole. The introduction of the railroad provided an easy way for growers in the delta to gain access to a national market for their various crops. This, combined with the easy navigation of the lower Sacramento and San Joaquin rivers, which provided a direct route from Sacramento and Stockton to San Francisco, created more of a

symbiotic relationship between river travel and rail travel, rather than a competitive relationship. Rail companies took advantage of the river, building feeder lines to central loading centers in Sacramento, Stockton, Antioch, and Holt, where freighters could offload their cargo for direct shipment to anywhere throughout the country (Thompson 1957:411). Immediately downstream of the present investigation's Proposed API/APE, the Sacramento Northern Railway established a rail ferry between Mallard and Chipps Island to extend its rail connections. The ferry was served by the wooden railcar ferry *Bridgit*, which served only from 1912 until 1913, when it burned. It was subsequently replaced by the steel ferry *Ramon* (Graves 1994).

Freight shipment on the Sacramento followed a different path than passenger traffic. The decade of the 1920s, which saw a gradual reduction in passenger traffic, saw an increase in freight traffic. Freight traffic dropped off after World War I, but by 1925, Sacramento had become the second most important river port in the United States, behind only New Orleans. Between 1921 and the beginning of the Great Depression, yearly freight averaged 1,000,000 tons. Wharves sprung up all along the river in response to the increased demand. There were 22 warehouses between Chico and Colusa, 25 between Colusa and Sacramento, and 35 between Sacramento and Benecia, in addition to numerous small landings constructed by individual farmers.

By the middle of the 1920s, there were over 40 individuals and companies operating commercial vessels on the river. Many of these commercial vessels were steam sternwheelers or screw tugs, which towed barges in addition to carrying freight. Barges tended to be over 200 ft long and 40 ft wide. Steamers on the upper river above Sacramento were smaller in size than those on the lower, with the largest upper river steamers in the range of 150 ft long with a 3-ft draft, compared to the Delta King and Delta Queen, both at 250 ft overall.

Freight traffic on the Sacramento River dropped considerably after the start of the Great Depression. By 1931, total yearly tonnage had dropped below 1,000,000 for the first time since the early 1920s. Total yearly tonnage continued to decline year after year until 1938, when the total tonnage only reached 600,000. Several changes occurred within the industry during this period. Emphasis began to shift from dedicated passenger/cargo steamers to steam tugs towing unpowered barges. In 1920, steamers moved four times as much freight as tugs, but by 1937, this had been reduced to just double. Although still carrying a significant portion of the overall total, steamboats were in a state of decline. By 1943, tugs were carrying twice the freight of steamboats, and by 1947, tugs were shipping over 1,000,000 tons per year. By the 1950s, the total exceeded 2,000,000 tons per year. Eventually, gasoline or diesel-driven tugs replaced steam-power.

Although the gas and steam-powered vessels dominated river traffic on the Sacramento, as they did in other parts of the world, the characteristic Sacramento River freight schooner (also known as a "Hay Scow") continued to operate well into the 1920s (Figure 4-11) (Thompson 1957:409). Initially sharp bowed, like seagoing schooners, these economical bulk carriers gradually evolved into curious scow-built vessels of shallow draft, designed to simultaneously carry large loads of cargo and to navigate the difficult shoal waters and narrow canals of the delta (Figure 4-12). Sacramento River freight schooners were well suited for the carrying of bulk cargo such as hay and bagged grains.




Figure 4-11. Typical scow-built Sacramento River freight schooner, also known as a "Hay Scow" (photo courtesy of Yolo County Public Library, Clarksburg Branch).




Figure 4-12. *Lizzie Theresa* hay scow schooner loading bales on a canal (photo courtesy of Yolo County Public Library, Clarksburg Branch).

Assisting in the decline in steamboat and steam tug shipping lines were boats owned by large-scale farming operations, which discovered a cost saving by operating their own vessels, often in competition with the steam lines.

Although the *Delta King* and *Delta Queen* have survived to the present day, most vessels of the steamboat era have not. A large number were burned to the waterline in Sacramento in 1932 when one caught fire. The *Fort Sutter* was converted into a nightclub and then moved to an aquatic park in San Francisco. The *Port of Stockton* (ex-*Capital City*) sank in San Francisco in 1952. Several were used to repair levee breaks long the river, including the 252-ft sternwheeler *Navajo* (see above), which was stripped of its engines and used to block a breach on Mandeville Island, and *J.D. Peters*, which was positioned in such a way as to be able to use its paddlewheel to push water out of the breach. These vessels were used as bunkhouses and storage sheds until they had deteriorated to the point of becoming unusable. Others, like the *Mandeville* (Figure 4-13), were simply abandoned along the riverbank, and others were cut down and used as barges.



Figure 4-13. Steamer *Mandeville* lies abandoned on the shore of McDonald Island (as presented in Schell 1995).

Not all marine transportation on the Sacramento River Delta served to link San Francisco Bay with the upper reaches of the Sacramento River. Ferries developed to transport people and various goods over short distances across water obstacles that proliferated throughout the Delta as settlement increased.

Undoubtedly, one would think the first ferry appeared shortly after the desire of one or more people to cross a river in the delta. However, early ferry history emerges during the 1850s, after the area's population had grown, cites had been founded, and improvements were made to the landscape. Beginning in the 1850s, ferries were operated locally, by individuals, landowners, or

partnerships, and they were used both as commercial enterprises and for private use. Early ferries were located along major waterways, but as the population spread and delta areas were reclaimed, creating drainage channels and new waterways, ferries sprung up to provide links between the more remote areas and the mainland. They became an integral part of the area's transportation system.

Early ferry history is somewhat sparse. Some information does exist on early ferries, as Bier published a map in 1901 showing the locations of principal ferries in the lower Sacramento River area dating back to the 1850s. This map was updated by Thompson (1980) 80 years later to include ferries from the 1920s (Figure 4-14).




Figure 4-14. Bier's 1901 map, as modified by Thompson (1980), showing locations of ferry landings since 1850 (as presented in Thomson 1980).

As infrastructure developed and reclamation commenced and progressed, ferries became established at towns immediately adjacent to the levees. Ferries were run as commercial enterprises; initially private through the nineteenth century, later under local and county government control, and eventually as government-run free ferries. They formed an important link in the region's system of transportation, as the ferry system made it possible to travel across the Sacramento River Delta relatively unimpeded. According to Thompson (1980:62), the Old River/Newtown ferry between Brannan and Grand Islands, the ferry at Walnut Grove, and the ferry at New Hope Landing, made this travel possible at a time before many bridges had been constructed. Other ferries operated from smaller towns and villages to newly reclaimed areas. Wherever there was a significant need to cross a body of water in the area, a ferry existed.

Ferries varied in their mode of propulsion, but they can generally be assigned to one of three different categories: engine powered, cable, and current. Current ferries are attached to a cable running parallel to the current down the center of the channel. The ferry, attached to the downriver end of the cable, uses the attachment of the cable as leverage to rotate the vessel into the current at such an angle that it is propelled to the other bank. Cable ferries use a cable stretched bank to bank, either overhead or along the bottom, with machinery on board the ferry to pull the ferry along the cable. Engine-powered ferries can be either common river vessels simply used as ferries (Figure 4-15), or dedicated purpose-designed vessels. Propulsion can be through diesel or steam.

Ferries were gradually replaced by bridges as the network of roads expanded along with the popularity of the automobile. By the 1930s, most heavily used ferries had been replaced, including the ferries at Clarksburg, Courtland, and Freeport, which closed when the bridge over the Sacramento at Freeport opened in 1930. A handful of ferries continued to be in use well into the 1990s.

As the utilization of the Sacramento River Delta for passenger and freight shipping lines declined, commercial boats were replaced by a proliferation of recreational watercraft, particularly a budding powerboat presence. Although the Sacramento River Delta remains an important corridor for marine shipping, forming a corridor between the ports of Sacramento, Oakland, and San Francisco, the Delta is widely used by recreational watercraft.




Figure 4-15. Small ferry boats of Laurentzen Transportation Company (as presented in Schell 1995).

#### 4.1.2 California State Lands Commission Shipwreck Database

The CSLC maintains a comprehensive shipwreck database of nearly 1,500 shipwreck sites resting within California's state-administrated waters. Information within the inventory includes any available historical and/or descriptive details on any known shipwrecks in California waters. The CSLC Shipwreck Information, which may be accessed online (https://www.slc.ca.gov/wp-content/uploads/2018/12/ShipwreckInfo.pdf), allows researchers to search for wrecks by county in which the wrecks lie. It should be noted that, unless otherwise stated, the CSLC Shipwreck Information Database entries are the results of historical research rather than archaeological fieldwork, do not contain precise locational information pertaining to the listed wrecks, and represent an approximation of the shipwreck's location. Additionally, while the CSLC Shipwreck Information data table contains entries that include vessel name, vessel type, year built, year sunk, cause, owner, captain, propulsion type, and vessel dimensions; most of the vessels do not have a full associated dataset. Table 2-1 contains all of the available information for each vessel known to be lost in the vicinity of the Proposed API/APE.

A search of the CSLC Shipwreck Database returned many known shipwrecks within Contra Costa, Sacramento, and Solano Counties. The immense area of these counties necessitated further sorting of the information to reduce the number of known wrecks to only those relevant to the area of the present investigations.

The results indicate that nine historical shipwrecks are known to have occurred within or within the immediate vicinity of the Proposed API/APE. Automated Wreck and Obstructions System

The most comprehensive and up-to-date list of shipwrecks for the U.S. is the National Oceanic and Atmospheric Administration's (NOAA) Automated Wrecks and Obstructions Information System (AWOIS) and NOAA's Electronic Navigation Chart (ENC). These databases were consulted to identify known wreck sites or obstructions within or near the current survey corridor. The AWOIS database contains information on over 10,000 wreck sites and obstructions/hangs in the coastal waters of the United States. Information within the database includes the latitude and longitude of each feature, along with any known historical and/or descriptive details. The AWOIS website, which may be accessed at https://www.nauticalchart.noaa.gov/data/wrecks-and-obstructions.html, allows researchers to search for wrecks based on Latitude/Longitude coordinates. An Access Database file has been projected here into Google Earth to allow the researcher to view what wrecks or obstructions are within a given area.

For the purposes of this investigation, a review of the AWOIS and ENC Wrecks databases indicated 32 charted wrecks or obstructions within 1 mi of the Proposed API/APE. Many of these features are associated with one another and do not represent discrete wrecks. Other Shipwreck Sources

"Maritime and Underwater Archaeology of the Pacific Coast" by James Delgado (2002) provides a chronological-arranged overview of selected maritime archaeological sites, primarily focusing on shipwrecks, along the Pacific Coast of the United States. Relevant to the present investigation, is a section discussing sites dating between 1849 and 1855, which contains a discussion of archaeological investigations and historical backgrounds of shipwrecks within the Sacramento River, principally focusing on wrecks along the Sacramento waterfront. No vessel loss is listed in Delgado's work associated with the Proposed API/APE.

A more detailed publication, in reference to the Proposed API/APE, is A Map and Record Investigation of Historical Sites and Shipwrecks Along the Sacramento River Between Sacramento City and Sherman Island, published by the California State Lands Commission in 1988. This work provides a detailed historical overview of the Sacramento River Valley and the history of shipping

on the river, as well as a comprehensive list of sunken vessels within the Sacramento River between Sacramento and Sherman Island. Though this volume focuses primarily on shipwreck sites within the Sacramento River above the Proposed API/APE, it identifies no less than three historical shipwrecks that were lost within or immediately adjacent to the Proposed API/APE. Numerous shipwrecks are listed as having occurred within the Sacramento River with no specific locations provided. Without further information to determine their location relative to the Proposed API/APE, these shipwrecks have been omitted. As historical sources for the location of vessel losses are often imprecise, Table, presents an additional five vessels lost in the vicinity of the Proposed API/APE, but which, due to the vagueness of their locational descriptions, may or may not be pertinent to the Proposed API/APE of the present investigation.

# 4.2 Cartographic Review

Another excellent tool for identifying shipwrecks is a review of historic navigation maps and charts for the area. Often noting shipwrecks, obstructions, and other various hazards for the mariner, many of these charts can be accessed from NOAA's Office of Coast Survey's Historical Map and Chart Collection (www.historicalcharts.noaa.gov/historicals/search), and others are found in various repositories, publications, or websites. The NOAA website allows the researcher to specify the area or region of interest and then review all available maps for that area. Another valuable utility provided by this site is the virtual magnification feature, which allows the researcher to zoom in and out of specific areas. Multiple nautical charts were examined regarding the API/APE, and the charts which best represented the area or contained valuable information are presented below in chronological order.

The earliest navigational chart of the API/APE was published in 1828 (Chart No. 591-00), illustrated in Figure 4-18. Although the chart encompassed the entirety of San Francisco Bay, it provided toponyms for Suisun Bay, Knox Island (now Chipps Island), Jones Island (now Van Sickle Island), the Sacramento River, and the San Joaquin River. No cultural features (i.e., shipwrecks) were charted within the API/APE itself, but the "Projected Town of New York" is noted immediately south of the API/APE at the present site of the city of Pittsburg.

Chart No. 1706-00, published in 1850 (Figure 4-19) was the first chart of the API/APE in which the scale used, 1:75168, provided detailed bathymetric data for the upper reaches of Suisun Bay and the confluence of the Sacramento and San Joaquin Rivers. A large shoal, noted as Tongue Shoal, was demarcated on its northern side by a series of islets, named the Chain Islets, obstructing the mouth of the Sacramento River. Narrow channels of navigable water allowed passage along the west and north side of this shoal, or through a narrow, shallow channel east of the shoal. These shoals presented a significant enough hazard to navigation that the charts included two panoramic insets to assist mariners in aligning their vessels in the channel during passage through the shoals. The concentration of sounding measurements on the chart suggests that navigation followed the Sacramento River and along the southernmost branch of the San Joaquin River, later named the New York Slough, with the main branch of the San Joaquin being likewise navigable. In addition to those mentioned on previous charts, the chart displayed toponyms for Gwin Island (Browns Island), Ruckels Island (Winter Island), Sherman Island, and Burnett Island (Montezuma Island), as well as the Tongue and Fraser Shoals and numerous points within the area of the API/APE. No cultural features (i.e., shipwrecks or navigational aids) were represented within or adjacent to the API/APE.

Published in 1867, Chart No. 626-01(Figure 4-20) illustrated the beginnings of an ongoing morphological change to the eastern extent of Tongue shoal at the northern extent of the API/APE. The Chain Islets, once situated along the northern boundary of the shoal, were no longer charted,

but had instead aggregated to form Chain Island along the shoal's eastern boundary. The shallow channel to the east of Tongue Shoal had shifted westward. The waterways to the west and north of Tongue shoal remained navigable. The 1867 chart was the first to identify the southern branch of the San Joaquin River and the branch extending between Brown's Island and Winter Island as the New York and Middle Sloughs, respectively. Furthermore, toponyms within the vicinity of the API/APE changed to approximate their modern names, with Brown's Island replacing Gwin Island, Chipps Island relacing Knox Island, Van Sickle's Island replacing Jones Island, and Montezuma Island replacing Burnett Island. Although no cultural features were represented within or adjacent to the API/APE, the settlement of Collinsville appeared north of the API/APE. The village of New York appeared to the south, with the extension of a railway to a pier into the New York Slough; the settlement of Pittsburg Landing also had a similar railroad pier, appearing at the upper end of the New York Slough.

As illustrated in Chart No. 5526-1758C (Figure 4-21), published in 1883, the eastern channel through the Tongue Shoal filled in and the shoal again expanded, necessitating the use of the western channel to access the Sacramento River. By 1883, the first navigational aids had been placed in the vicinity of the API/APE, delimiting the eastern side of the channel within upper Suisun Bay as well as the placement of beacons at the head and foot of the Middle Ground within the mouth of the San Joaquin River.

Much of the increased shoaling at the mouth of the Sacramento River had reversed by 1910 as illustrated by Chart No. 5534-3609C (Figure 4-22). On this chart, a shallow eastern channel through Tongue Shoal had reopened, and increased shoaling to the west resulted in the expansion of Chain Island itself and the removal of Tongue Shoal from the chart. The 1918 chart indicated a substantial increase in settlement along the southern shore of the New York Slough, with numerous piers and docks appearing between Pittsburg, formerly New York, and Pittsburg Landing alongside increasing industrial structures. At the western extent of the survey area, on the southern shore of Chipp's Island and the opposite shore at Mallard Slough, a rail line extended to the shoreline with a ferry route and cable extending across the channel between the piers. No additional cultural features (i.e., shipwrecks) were charted within or near the API/APE.

Published in 1948, Chart No. 5534–9 (Figure 4–23), illustrated that, by that date, the shoaling at the mouth of the Sacramento River had further regressed, and a navigational channel passing to the east of Chain Island had deepened, with controlling depths of 10 ft within API/APE. A channel, dredged to a least depth of 30 ft, was cut through the New York Slough accessing the San Joaquin River. The main branch of the San Joaquin River remained navigable with a "Berthing Area" delimited west of the Fraser Shoal and an anchorage to the east within the river. The 1948 chart was the first to demarcate a "Cable Area" extending north to south across the river to the west of the API/APE, and to illustrate exposed wrecks within the API/APE. Three exposed wrecks are charted, north of New York Point within the API/APE, east of New York Point, and at Point Emmet at the foot of the New York Slough.

By 1958, the entrance to the Sacramento River had deepened, and the channel to the west of Chain Island had begun to shoal, as illustrated by Chart No. 5534-25 (Figure 4-24). At the southern end of the API/APE, a T-shaped pier was constructed on the north side of New York Point. The 1958 chart retained the exposed wreck west of New York Point, with the previously exposed wreck at Emmet Point being changed to a submerged wreck. The wreck charted east of New York Point in 1948 was not charted. Two new wrecks were first charted in 1958, an exposed wreck along the western shore of Winter Island, south of San Joaquin Point, and a new submerged wreck along the eastern shore of Van Sickle Island, both outside the API/APE.

Published in 1967, Chart No. 5534–29–1967 (Figure 4-25) first illustrated the Sacramento Ship Channel within the Sacramento River. On the San Joaquin River, the New York Slough channel remained the principal channel, with navigational aids and the demarcated "Berthing Area" in the main branch of the river being removed from charts. All charted wrecks appearing in the 1958 charts were retained in the 1967 chart. The railroad and ferry between Mallard Island and Chipps Island at the western end of the API/APE are illustrated as having been abandoned, with the piers being labeled as ruins extending into Suisun Bay. The cable area extending between the ruins was retained.

Chart No. 18656-41, published in 1979 (Figure 4-26) charted eight additional wrecks adjacent to the API/APE. These exposed wrecks included: one along the south shore of the New York Slough, one on the western shore of Winter Island, two on the eastern shore of Van Sickle Island, and three within the inlet at Collinsville opposite Montezuma Island. The submerged wreck at Point Emmet was no longer charted.

Chart No. 18656-45-1983 (Figure 4-27), published in 1983, illustrated many of the previously exposed wrecks as submerged wrecks. Three wrecks were charted for the first time: one exposed wreck near the northern limit of the API/APE, east of Montezuma Island; an exposed wreck on the east shore of Van Sickle Island, south of the previously charted wrecks; and a submerged wreck(s) along the south shore of Chipps Island. By 1990, all wrecks along Van Sickle Island and at Collinsville were charted as submerged wrecks (Chart No. 18659-7) (Figure 4-28).

By 1996 the wrecks within the New York Slough and the three westernmost wrecks east of Collinsville were no longer charted (Figure 4-29). Chart No. 18659-12, published in 1996, displayed four previously uncharted shipwrecks: an exposed wreck on the eastern shore of Van Sickle Island, south of the previously charted wrecks; an exposed wreck on the western bay of Winter Island; an exposed wreck on the northeastern shore of Winter Island; and a submerged wreck on the northeast corner of Fraser Shoal.

The most recent navigational chart of the API/APE was published in 2022 (Chart 18659-16) (Figure 4-30). The 2022 charts retained all charted wrecks that had appeared on the 1996 charts. Two wrecks are charted within the API/APE. Two obstructions were located within or near the southeastern boundary of the API/APE, along with several submerged pilings and pilings in shallow water off New York Point.




Figure 4-16. 1828 chart excerpt showing the Proposed API/APE (Chart No. 591-00-1828 from NOAA's Historical Map and Chart Collection).




Figure 4-17. 1850 chart excerpt showing the Proposed API/APE (Chart No. 1706-00-1876 from NOAA's Historical Map and Chart Collection).




Figure 4-18. 1867 chart excerpt showing the Proposed API/APE (Chart No. 626-01-1867 from NOAA's Historical Map and Chart Collection).




Figure 4-19. 1883 chart excerpt showing the Proposed API/APE (Chart No. 5526-1758c-1883 from NOAA's Historical Chart Collection).




Figure 4-20. 1910 chart excerpt showing the Proposed API/APE (Chart No. 5534-3609C-1916 from NOAA's Historical Map and Chart Collection).




Figure 4-21. 1948 chart excerpt showing the Proposed API/APE (Chart No. 5534-9-1948 from NOAA's Historical Map and Chart Collection).




Figure 4-22. 1958 chart showing the Proposed API/APE (Chart No. 5534-25-1958 from NOAA's Historical Map and Chart Collection).




Figure 4-23. 1967 chart excerpt showing the Proposed API/APE (Chart No. 5534-29-1967 from NOAA's Historical Map and Chart Collection).




Figure 4-24. 1979 chart excerpt showing the Proposed API/APE (Chart No. 18656-41-1979 from NOAA's Historical Map and Chart Collection).




Figure 4-25. 1983 chart excerpt showing the Proposed API/APE (Chart No. 18656-45-1983 from NOAA's Historical Map and Chart Collection).




Figure 4-26. 1990 chart excerpt showing the Proposed API/APE (Chart No. 18659-7-1990 from NOAA's Historical Map and Chart Collection).




Figure 4-27. 1996 chart excerpt showing the Proposed API/APE (Chart No. 18659-16-2022 from NOAA's Historical Map and Chart Collection).




Figure 4-28. 2022 chart excerpt showing the Proposed API/APE (Chart No. 18659-12-1996 from NOAA's Historical Map and Chart Collection).

# 5 Methods

# 5.1 Submerged Remote Sensing Survey

Remote sensing data employed in the assessment for the presence or absence of submerged cultural resources within the project corridor was collected by the California based hydrographic survey company, eTrac, Inc. Established in 2003 as a hydrographic and geophysical survey, vessel positioning, and instrumentation firm, eTrac has a fleet of over 20 survey vessels and is staffed with professionally licensed land surveyors and ACSM/THSOA (American Congress on Surveying and Mapping/The Hydrographic Society of America) certified hydrographers, and eTrac's projects are performed at the highest level of quality and detail that the industry demands.

Conducted from 17 September to 26 October under California State Lands Commission Low Energy Geophysical Survey Permit No. 9235, the geophysical survey included dual frequency side scan sonar, magnetometer, subbottom profiler, and a high resolution multibeam echosounder. Conducted to map the seafloor and sub-surface conditions, obstructions, and possible installation constraints of the cable route, the survey covered a 2,000-foot-wide corridor which encompassed the submarine cable route along its center line. Located in the center of the survey corridor, the power conductor consists of approximately six 230 kV tri-core cables, each spaced approximately 70 ft apart for a width of 420 feet (Survey of a 2,000-foot-wide area was required for repositioning of the centerline up or downstream in the event of any recorded hazards or possible constraints within the conductor corridor (i.e., boulder areas, etc.). The depth of the Proposed API/APE ranged from -.5 to -104 feet MLLW (Mean Lower Low Water) (Figure 5-1). The depths in the southern portion of the corridor, near the Pittsburg landing site, have the deepest depths within a 104 ft depression

located in the Stockton Deep water ship channel. The norther portions of the corridor, near Collinsville, has shallower depths. The submarine cable is proposed to be installed beneath the bay and riverbed to a depth of approximately 6 and 25 ft using jetting technology.




Figure 5-1. Depths within the Proposed API/APE, as presented in eTrac's 2023 Marine Geophysical Report.

A comprehensive study, the recorded survey data was assessed by Chronicle Heritage personnel for quality, and then subsequently processed and analyzed for the presence or absence of submerged cultural resources. In addition to the data, Chronicle Heritage also had access to eTrac's Survey Report. It should be stated that Chronicle Heritage often employs data from hydrographic "Hazard, Preconstruction" surveys to produce the associated submerged cultural resources report, as the equipment suites and data sets mirror those required for submerged cultural resources investigations, thereby negating the need for and attendant costs of duplicate surveys. Furthermore, the survey data acquired by the hydrographic company is often more robust and includes data not required for or obtained by the cultural survey such as multibeam data which is often far superior to side scan sonar in image resolution and position accuracy such as was conducted for this survey.

Chronicle Heritage personnel reviewed eTrac's survey methods to ensure that they met state and government specifications for cultural resources survey. Guiding Chronicle Heritage's assessment of eTrac's methods as well as subsequent in-house processing, analysis and presentation, Chronicle Heritage's maritime team developed a Research Design that identified survey methods and protocols which are based on survey requirements for numerous U.S. Army Corps Districts on the East and Gulf Coasts and inland Rivers and Lakes, and are employed for Section 404 Clean Water Act permit surveys (i.e., New York, Philadelphia, Wilmington, Charleston, Savannah, Jacksonville, Mobile, Tulsa, Galveston, St. Paul, etc. Appendix A).

#### 5.1.1 Personnel

All personnel involved with the remote sensing survey had the requisite experience to complete the project effectively and safely as proposed. The remote sensing survey was conducted by eTrac, Inc., a Woolpert Company, under California State Lands Commission Low Energy Geophysical Survey Permit No. 9235. Nicholas George, C.H. (Certified Hydrographer) served as project manager and oversaw the execution and completion of the remote sensing survey while acting as liaison between eTrac, Inc., and Chronicle Heritage Heritage. Steven James, M.A., RPA (Register of Professional Archaeologists) served as the Principal Investigator for the underwater survey. Regarding the analysis of data for potentially significant submerged cultural material, Rikki Oeters-Milewski, M.A., RPA served as a Qualified Maritime Archaeologist (QMA) and was assisted by

Justin Milewski, ABT for the duration of the project. Matthew Lowe, M.A., RPA served as co-author of the revised report.

#### 5.1.2 Remote Sensing Survey Equipment

The remote sensing equipment employed by eTrac for the submerged remote sensing survey were the magnetometer (to detect ferrous materials), side-scan sonar (to create images of the bottom), and the subbottom profiler (to reconstruct the structure of the underlying sediment beds). Locational control was conducted with Differential Global Positioning System (DGPS) technology and an Ultrashort Baseline (USBL). Data collection was performed in Hypack 2022 while analysis of the data was conducted with Hypack 2022, SonarWiz 7, and MagPick.

Due to the variable depths of the Proposed API/APE and the towed nature of the side-scan sonar and magnetometer, the height above bottom for both instruments was continually monitored and adjusted as necessary. Survey crews ensured the side-scan sonar was positioned at a depth of 10 to 20 percent the instrument range above the riverbed. The magnetometer was kept at a height of no more than 6 meters above the riverbed. In areas that were shallower than 6 meters, the height of the magnetometer was adjusted so that it would not contact the riverbed. The subbottom profiler was pole mounted on the stern of the vessel using a Universal Sonar Mount (USM), once deployed, the height of the instrument was not adjusted.

#### **Differential Global Positioning System**

A primary consideration in any remote sensing survey is positioning. Accurate positioning is essential during the running of survey tracklines and returning to recorded locations for refinement or diver analyses. Positioning was accomplished on this project using an Applanix POS MV Oceanmaster V5 navigation and inertial compensator with dual-antenna Global Navigation Satellite System (GNSS), with high-speed binary data streams supplied to the navigation computer (Figure 5-2).



Figure 5-2. Applanix POS MV OceanMaster V5 navigation and inertial compensator used during the investigation.

The Applanix POS MV Oceanmaster blends data with angular rate and acceleration data from its inertial motion unit (IMU) with heading from the GPS Azimuth Measurement System (GAMS) to produce a robust and accurate full six-degrees-of-freedom position and orientation solution. Thus, the unit can combine Global Navigation GNSS and inertial data and is perfect for conducting

marine remote sensing surveys, which rely on these data streams for accurate positioning and orientation of survey instruments. The unit achieves true heading by its dual antenna, eliminating magnetic calibration issues in areas with unreliable magnetic conditions. The Applanix POS MV Oceanmaster integrates real-time corrections from base stations (RTCM) and satellites (WAAS), allowing for sub-meter accuracy during the survey (Trimble 2019).

The project was planned in NAD83 California Zone 2, U.S. feet, using the 2011 adjustment and all side-scan, subbottom, and magnetometer target data were converted to this grid. The navigation data streams were in a geographic format, WGS84 (i.e., latitude, longitude). The raw data from the side-scan and subbottom devices are archived in this format, and the magnetic data are in the projected format. Navigation was conducted with Qinsy, Qinsy was written specifically for marine survey applications. Positional data for the towed side-scan sonar and magnetometer was provided by the USBL acoustic transducer, which was mounted on the starboard side of the stern USM mount pole mount. A cable counter measured the length of cable payout and was used to estimate the layback position behind the vessel for the towed instruments. The USBL was positioned on the fixed sonar mount and the beacon was positioned on the tethered cable of the towed equipment to track the position of the side-scan sonar and the magnetometer. A measurement was recorded from the acoustic center of the towed equipment to the tow point as well as the from the beacon to the tow point. These two measurements were entered into Qinsy and calibrations were run to determine angular offset values of the USBL. All positioning coordinates are based on the position of the DGPS antennae relative to the sensor location and the USBL. This layback information is critical for the accurate positioning of targets in the data analysis phase and for relocating any targets for additional investigations.

#### Magnetometer

Magnetometers measure the intensity of magnetic forces with a sensor that measures and records the ambient (background) magnetic strength and, if present, deviations from the ambient background (anomalies) caused by magnetic fields of ferrous objects and other sources, such as high voltage cables (Breiner 1973). These measurements are recorded in nanoteslas (nTs), the standard unit of magnetic intensity.

The success of the magnetometer in detecting anomalies in local magnetic fields has resulted in the instrument being a principal remote sensing tool of maritime archaeologists because anomalies can represent components of shipwrecks and other historical debris or objects hazardous to dredging or navigation. Although it is not possible to identify specific ferrous objects from the magnetic field contours, it is occasionally possible to approximate the shape, mass, and alignment characteristics of wrecks or other structures based on complex magnetic field patterns. In addition, other data (historic accounts, use patterns of the area, diver inspection), which overlap data from other remote sensing technologies, such as the side-scan sonar and prior knowledge of similar targets, can lead to accurate identification of potential targets.

There are three types of commercially available marine magnetometers: proton precession, cesium vapor, and Overhauser. Throughout the project, eTrac, Inc., employed a Geometrics 882 cesium vapor magnetometer (Figure 5-3). The magnetometer was towed at 30-meter interval spacing and at maximum 6 meters above the riverbed to ensure data quality. It must be noted that the magnetometer utilized during this survey had a sensitivity of .01 nT, a sampling rate of every .1 seconds, and background noise did not exceed 3nT throughout the duration of the survey. Data were stored in the navigation computer and archived. The Geometrics 882 is capable of subsecond recordation for precise location control, and data were collected at 10 hertz, providing a record of both the ambient field as well as the character and amplitude of the anomalies encountered.

Figure 5-3. Survey instruments employed during the investigation included the magnetometer (top left), side-scan sonar (bottom left), and the subbottom profiler (right).

#### Side-Scan Sonar

The remote sensing instrument used to search for physical features on or above the ocean floor was an EdgeTech 4125 side-scan sonar system (Figure 5-3). The side-scan sonar is an instrument that, through the transmission of dual fan-shaped pulses of sound and reception of reflected sound pulses, produces an acoustic image of the bottom. Under ideal circumstances, the side-scan sonar is capable of providing a near-photographic representation of the bottom on either side of the trackline of a survey vessel.

The EdgeTech 4125 has the internal capability for removal of the water column from the instrument's video printout as well as correction for slant range distortion. This side-scan sonar was used with the navigation system to provide manual positioning of fix or target points on the digital printout. Side-scan sonar data are useful in searching for the physical features indicative of submerged cultural resources. Specifically, the record is examined for features showing characteristics such as height above the bottom, linearity, and structural form. Additionally, potential acoustic targets are checked for any locational match with the data derived from the magnetometer and the subbottom profiler.

The 4125 side-scan sonar was linked to a towfish that simultaneously employed both 600- and 1600-kilohertz frequency settings and a variable side range of 40 m per channel (131.2 ft) on each of the survey lines. The 40-m-per-channel setting was chosen to provide detail and, at a minimum, 200 percent overlapping coverage with the 40-m line spacing and ensure full coverage of the survey area. The side-scan sonar was positioned at a height of 10 to 20 percent the instrument range in meters per channel above the riverbed to ensure data quality for the 40-meter line spacing. Employing both frequencies ensured that both maximum detail (using the 1600-kilohertz transducers) and greater penetration (via the lower 600-kilohertz transducers) could be acquired for review throughout the area surveyed.

#### **Subbottom Profiler**

Employed to determine the character of near-surface geologic features over the survey area, subbottom profilers generate low-frequency (0.5–30 kilohertz) sound pulses capable of penetrating the seabed and reflecting off sediment boundaries or larger objects below the surface. The data are then processed and reproduced as cross-sections based on two-way travel time (the time taken for the pulse to travel from the source to the reflector and back to the receiver). This travel time is then interpolated to depth in the sediment column by calculating at 1,500 meters per second (the average speed of sound in water).

Subbottom profilers have different ranges of sound wave frequency (sparkers, boomers, pingers, chirp, and parametric systems). Sparkers and boomers operate at low frequency (5 hertz to 2 kilohertz) and afford deep geologic penetration and low resolution, which is useful for deeper geologic time. Pingers (3.5 and 7 kilohertz) are more useful for penetrating late Pleistocene- and Holocene-aged deposits or paleolandscape features of interest to precontact archaeologists. CHIRP systems sweep multiple frequency ranges and are the most precise and accurate of the subbottom profiler systems, and they operate at 2–40 kilohertz. The resolution can be on the order of <1 to 10 centimeters (cm)(6 inches [in]) depending on sediment type and the quality of the acoustic return. The parametric systems represent the newest generation. They employ two separate sound pulses, which interact to generate a single, narrow sound beam. Thus, parametric systems suffer less from side lobes and reverberation than their linear contemporaries. eTrac, Inc., employed an Innomar SES-2000 Compact Parametric subbottom profiler system with a topside power unit, laptop processor, and fixed transducer (Figure 5-3). The device was run at 30-meter interval spacing and operated at a setting of 4–24 kilohertz for maximum penetration, resolution, and data quality.

Seismic cross-sections reconstruct the shapes and extents of reflectors such as facies in channel sediments, rock-sediment interfaces, marine sand bed cover, and so forth. In addition to subbottom profiling, and depending on the density of data points, the first bottom return data can be used for bathymetry. Shipwrecks can be studied with subbottom profilers once their location is known. Finding shipwrecks with a subbottom profiler survey is often unfruitful.

High- and low-amplitude reflectors distinguish differences in sediment characteristics such as particle size and consolidation (Stevenson et al. 2002). Facies contacts can be identified by discontinuities in the extent, slope angle, or shape of the reflector returns. This latter fact is important when identifying the sinusoidal shapes of drowned channel systems and other relict and buried fluvial system features (e.g., estuarine, tidal, lowland, and upland areas around drainage features). Parabolic-shaped reflectors indicate individual objects of sufficient size and hardness. The parabolic shape is the result of sound propagating outwardly from the item. Five types of signals may cause misinterpretation in the two-dimensional records: direct arrivals from the sound source, water surface reflection, side echoes, reflection multiples, and point source reflections. Judicious analysis is required to identify them.

Peats tend to reflect strongly, as do other fine grain or muddy sediments. Sand and shell deposits are less reflective and difficult to penetrate without lower seismic frequencies such as employed by the profiler system employed here.

#### Survey Vessels

eTrac, Inc., used two company-owned survey vessels throughout the execution of the submerged remote sensing survey; the R/V Rapid, a 28-ft, aluminum monohull powered by twin 250 hp outboard Suzuki engines (Figure 5-4); and the R/V Taku, a 33-ft, aluminum catamaran powered by twin 300 hp Suzuki outboard engines (Figure 5-5).

R/V Rapid is an aluminum monohull, hydrographic survey vessel which was utilized to collect the multibeam and sub-bottom data. Rapid is field proven having conducted numerous hydrographic and geophysical surveys throughout California with towed and mounted sensors. It is easily transported and can be mobilized for survey rapidly. A dual antenna GNSS positioning, and motion measurement system was installed on the vessel with a long antenna baseline allowing maximum heading accuracy. Rapid had all offsets on the vessel measured while on a trailer to ensure that measurements to the positioning equipment are accurate to less than 3-centimeters. The vessel is

equipped with two Universal Sonar Mounts (USM). The multibeam system was mounted on this specially engineered side mount. This mount positions the system with 100% repeatability and allows for surveying in shallow water due to a specifically designed break away block.

R/V *Taku* is a 2006/2007 built Armstrong Marine (currently Brix Marine), aluminum catamaran, hydrographic survey vessel which was utilized to collect the side-scan sonar and magnetometer data. The vessel is equipped with Optimus 360 Joystick controls, dynamic positioning, and an autopilot system. R/V *Taku* is a proven vessel for high quality data collection and high productivity in inclement weather. This survey vessel has proven its reliability for dozens of assignments throughout the continental US and Alaska.

Both vessels conformed to all U.S. Coast Guard specifications, according to class, and had a full complement of safety equipment. They carried all appropriate emergency supplies including but not limited to lifejackets, tool kit, first-aid supplies, flares, and air horns.



Figure 5-4. eTrac, Inc. survey vessel, R/V Rapid.



Figure 5-5. eTrac, Inc., survey vessel, R/V Taku.

#### 5.1.3 Remote Sensing Survey Procedures

The maritime survey area extended beyond the proposed cable placement to ensure full coverage of any areas with the potential to be affected by Proposed Project activities. Parallel survey lines were spaced at 30-m to 40-m intervals depending upon the capable coverage span of the geophysical instrument. The magnetometer and subottom profiler were run at 30-m interval spacing (Figure 5-6) while the side-scan sonar was run at 40-m interval spacing with vertical tie lines for data collection spaced at 425-m intervals (Figure 5-7). These planned survey lines were programmed into the navigation computer. The magnetometer, side-scan, and subbottom profiler were deployed for the entirety of the survey. Before initiating the survey, the instruments were mobilized, tested, and found operational. The helmsman viewed the navigational computer to accurately traverse the survey tracklines. The monitor displayed the preplotted trackline, the real-time position of the survey vessel, and the cross-track distance from the preplotted trackline. The speed of the survey vessel was maintained at approximately 4 knots for the uniform acquisition of data. The positioning points along the traveled line were recorded on the computer hard drive, and the magnetic data were also stored digitally.




Figure 5-6. Magnetometer and Subbottom 30 meter spaced Planned survey lines.




Figure 5-7. Side-scan sonar 40 meter spaced Planned survey lines.

# 5.2 Data Analysis Criteria, Theory, and Commentary

The remote sensing survey of the Proposed API/APE intended to locate and identify the presence or absence of potentially significant submerged cultural resources that, if present, might be adversely affected by proposed navigation improvement activities. However, the interpretation of remote sensing data obtained from both the magnetometer and side-scan sonar, as stated by Pearson et al. (1991), "relies on a combination of sound scientific knowledge and practical experience." The evaluation of remote sensing targets, with regard to a determination that the anomaly does or does not represent a significant resource, depends on a variety of factors. These include the detected characteristics of the individual targets (e.g., magnetic anomaly strength) associated with other side-scan or magnetic targets and relationships to observable target sources such as channel buoys or pipeline crossings.

### 5.2.1 Subbottom Profiler Analysis

Subbottom profilers generate low-frequency acoustic waves that penetrate the seabed and reflect off boundaries or objects located in the subsurface. The data are then processed and reproduced as a cross-section using two-way travel time to determine the depth (the time taken for the pulse to travel from the source to the reflector and back to the receiver by a constant). The shapes and extent of reflectors are used to identify bottom and subbottom profile characteristics.

In general, high- and low-amplitude linear reflectors (light and dark lines) distinguish between sediment beds; parabolic reflectors indicate point-source objects with sound propagating out from them, and erosional or nondepositional contacts can be identified by discontinuities in

extent, slope angle, and the shape of the reflector morphology. This latter fact is important when identifying drowned channel systems, other relicts, and buried fluvial system features (e.g., estuarine, tidal, lowland, and upland areas around drainage features).

Five types of spurious signals may cause confusion in the two-dimensional records that specialists recognize: direct arrival from the sound source, reflection multiples, water surface reflection, side echoes, and point-source reflections. A judicious analysis is required to identify these acoustic imagery phenomena. In all cases, precise inference of a sediment bed or other anomaly from the subbottom profiler data would necessitate coring.

In analysis, seismic impedance contrast returns indicating positive relief features, such as possible mounds and negative relief features as a probable paleochannel or other fluvial feature with margins and sediment beds, indicate high potential for precontact remains. Other features of interest are buried surface continuations.

Positive relief features on subbottom records are predictable phenomena given that piles of erosion-resistant material of differential character than the surrounding sediments should be perceivable with sound underwater imagery (e.g., subbottom profiler), and therefore, they have long drawn submerged precontact archaeologists as potentially identifiable features to find in places that have otherwise impossibly similar images to search (Stright 1990).

# 5.3 Method and Theory for Recognition of a Submerged Precontact Site

Chronicle Heritage's methodology for identifying submerged precontact sites entails developing criteria for the discovery of a "site" in any particular setting. The criteria are based on the geology and archaeology of the Proposed API/APE and models of site submergence. Models for the presence and preservation of submerged archaeological sites are discussed by several researchers including Waters (1992) in his chapter on coastal processes, Kraft et al. (1983), and others. Much of this has to do with the identification of landforms identifiable with remote sensing that have the potential for archaeological site presence. For instance, two models used in this project were horizontal surfaces near channel features and positive relief features considered potentially to represent midden features, i.e. shell middens. Causeways, fishing weirs, or other precontact infrastructure features are difficult to identify.

Publications are more limited that are specific to recognizing sedimentary signatures of the deposits that make up sites that have been transgressed by rising sea levels and then remained submerged, perhaps buried, until exposure. One study specifically focused on such information is Gagliano et al.'s (1982) Sedimentary Studies of Prehistoric Archaeological Sites: Criteria for the identification of submerged archaeological Sites of the Northern Gulf of Mexico Continental Shelf. This document has high value but limited distribution. Gagliano's group chose 15 terrestrial sites in Louisiana and Texas as analogs from 8 identifiable and mappable landforms commonly and consistently associated with archaeological sites on land, terrestrially. Their local geomorphic features included major natural levee, minor natural levee, Chenier and accretion ridges, barrier island, salt dome margin, estuarine margin, channel on Pleistocene terrace, and lake margins. They sampled sediments with excavations and box core sampling; recorded color, bedding, and contact descriptions; sorted the sediments to particle size; conducted point count and grain size analysis; and then geochemically analyzed the samples by levels. They showed that sites were recognized most frequently by shell content, fish bones, and charred wood. Some ceramic and lithic artifacts were identified, but they were rare and small.

Another aspect to realize about submerged precontact sites is that virtually all examples of inundated sites are partially, or wholly, reworked in ways somewhat analogous to deflation (Fischer 1995; Masters and Flemming 1983). This is caused by the fluidization of sediments at times of inundation and the removal of fine particles that are often redeposited with material by subsidence of the inundation or wave action. Faught (1996, 2002–2004) has shown sites with late-Pleistocene, early Holocene, and middle-Holocene artifacts to be reworked by sea level rise and submergence, but that artifact arrays remain cohesive as surface and near-surface remains.

Because of these factors, recognition that deposits are cultural is not always immediately apparent to the diver or at first glance of the collected materials. Artifacts are important but not always part of the site as Gagliano et al. (1982) have systematically determined. Expectations for midden deposits include the dominance of unarticulated specimens of mollusk species, faunal bone, and manuports (i.e., geologic items out of place). On the other hand, the discovery of any artifact would be important especially in any sediment bed below a marine bed.

#### 5.3.1 Magnetometer

Interpretation of data collected by the magnetometer, the tool of choice by the underwater archaeologist for locating buried shipwrecks, is perhaps the most problematic. Magnetic anomalies are evaluated and prioritized based on magnetic amplitude or deflection of nanotesla intensity from the ambient background in concert with duration or spatial extent (distance in feet along a trackline of an anomaly influence the ambient background). They are also correlated with side-scan contacts. Because the sonar record gives a visible indication of the target, identification or evaluation of potential significance is based on morphology, especially structural characteristics, as well as association with magnetic anomalies. Targets, such as isolated sections of pipe, can normally be immediately discarded as nonsignificant, while large areas of above-sediment wreckage are generally easy to identify.

The problems of differentiating between modern debris and shipwrecks, based on remote sensing data, have been discussed by several authors. This difficulty is particularly true in the case of magnetic data; therefore, it has received the most attention in the current body of literature dealing with the subject. Pearson and Saltus (1990:32) state, "even though a considerable body of magnetic signature data for shipwrecks is now available, it is impossible to positively associate any specific signature with a shipwreck or any other feature." There is no doubt that the only positive way to verify a magnetic source object is through physical examination. However, the size and complexity of a magnetic signature do provide a usable key for distinguishing modern debris and shipwreck remains (see also Garrison et al. 1989; Irion and Bond 1984; Pearson et al. 1993). Specifically, the magnetic signatures of most shipwrecks tend to be large in area and tend to display multiple magnetic peaks of differing amplitude.

In a study conducted for the Bureau of Ocean Energy Management for magnetic anomalies in the northern Gulf of Mexico, Garrison et al. (1989) indicate that a shipwreck signature will cover an area between 10,000 and 50,000 m². Using the Garrison et al. (1989) study, as well as years of "practical experience," in an effort to assess the potential significance of remote sensing targets, the Pearson et al. (1991) study developed general characteristics of magnetometer signatures most likely to represent shipwrecks. The report states that "the amplitude of magnetic anomalies associated with shipwrecks varies considerably, but, in general, the signature of large watercraft or portions of watercraft, range from moderate to high intensity (>50 nTs) when the sensor is at distances of 20 feet or so" (Pearson et al. 1991:70). Employing a table of magnetic data from various sources as baseline data, the report goes on to state that "data suggests that at a distance of 20 feet or less, watercraft of moderate size are likely to produce a magnetic anomaly (this would be a

complex signature [i.e., a cluster of dipoles and/or monopoles]) greater than 80 or 90 feet across the smallest dimension..." (Pearson et al. 1991:70).

While establishing baseline amounts of amplitude and duration reflective of the magnetic characteristics for a shipwreck site, the report "recognizes that a considerable amount of variability does occur" (Pearson et al. 1991:70). Generated in an effort to test the 50 nT per 80 ft criteria, and to determine the amount of variability, Table 5-1 lists numerous shipwrecks as well as single- and multiple-source objects located by magnetic survey and verified by divers. All shipwrecks met and surpassed the 50 nT per 80 ft criteria with one exception. Emanuel Point II's magnetic deviation falls below the cutoff, although the duration is above. Subsequent archaeological examinations have determined that Emanuel Point II contains very little iron (Greg Cook, personal communication, 2011). The majority of single-object readings fell below the criteria (with the exception of the pipeline, the two sections of pipe, and one of the seven rocket motors). However, the signature of the pipeline should appear as a linear feature on a magnetic contour map and should not be confused with a single-source object. The strengths of the two sections of pipe represent refinement readings that sought to produce the highest reading possible and should perhaps be discounted from the sample. Further, because of their association with the space program, rocket motors, which are single-source objects, must be considered potentially significant. While the shipwrecks and most single-source objects adhere to the 50 nT per 80 ft criteria, the multiple-source objects do not. If all targets listed on the table required prioritization of potential significance based on the 50 nT per 80 ft criteria, the two multiple-source object targets would be classified as potentially significant.

While the 50 nT per 80 ft criteria is a good general guide for most conditions, several recent studies have suggested that a 50 nT per 80 ft duration applied to remote sensing data as a baseline for all wreck sites is much too low. Allowing for a larger and more focused database on which to assess signature characteristics of specific vessel classes, the findings from these investigations argue for higher nanotesla and duration criteria for specific types of sites. Table 5-1 indicates the sizable magnetic deviation and duration of previously recorded and located steamboat wreck sites, the steamboat playing a critical role in the maritime commerce on the Sacramento River and the project area (see *Historical Background*). However, there is one exception, each of the known steamboat wrecks investigated has a magnetic deviation of at least 500 nT and a duration of no fewer than 110 ft, usually in the more than 200-ft range. As opposed to single objects, steamboat wrecks documented during previous investigations are generally much larger in magnetic strength (although not always), tend to have a longer duration, and typically have multicomponent signatures. It should be noted, however, that each steamboat wreck signature differs markedly due to environmental conditions, the amount of hull and machinery remaining, and the depth of water and overburden over the wreck site.

Table 5-1. Compilation of Magnetic Data from Various Sources

Vessel (Object)	Type and Size	Magnetic Deviation (nT)	Duration (ft)	Reference				
Shipwrecks								
J.D. Hinde	. Hinde 129-ft wooden sternwheeler		110	Gearhart and Hoyt 1990				
Mary	234-ft iron-hulled sidewheeler	1,180	200	Hoyt 1990				

Vessel (Object)	Type and Size	Magnetic Deviation (nT)	Duration (ft)	Reference	
Confederate Obstructions	Numerous vessels with machinery removed and filled with construction rubble	110	long duration	Irion and Bond 1984	
Utina	267-ft wooden freighter	690	150	James and Pearson 1991; Pearson and Simmons 1995	
Gen C.B. Comstock	177-ft wooden hopper dredge	200	200	James et al. 1991	
Egmont Shoal wreck	19th century Wooden-hulled copper clad sailing vessel	67	160	Krivor 2005	
USS Narcissus	Civil War wooden tug	582	176	Krivor 2005	
El Nuevo Constante	126-ft wooden collier	65	250	Pearson et al. 1991	
James Stockton	55-ft wooden schooner	80	130	Pearson et al. 1991	
modern shrimp boat	Segment 27 × 5 ft	350	90	Pearson et al. 1991	
Mary Somers	Iron-hulled sidewheeler	5,000	400	Pearson et al. 1993	
Homer	148-ft wooden side-wheeler	810	200	Pearson and Saltus 1990	
Shrimp Boat	Modern	162	110	Watts 2000	
Pappy's Lane Shipwreck	165-ft steel-hulled World War II landing craft	685	350	James et al. 2016	
USS Tecumseh	223 ft Civil War Cannonicus- class monitor	11,600	850	James et al. 2019	
8SJ4889 (Possibly Dixie Crystal)	125 ft late 19th/early 20th- century cargo freighter	1,960	250	Wilson et al. 2019	
P1S.0099	Possible 55-ft-long wreck	1,557	130	Wilson and Gates 2021	
Ben Franklin (SS Franklin)	264-ft steel-strapped wooden hull sidewheeler	4545	232	Derlikowski et al. 2022	
Undine	sternwheeler	193	200	James and Krivor 2000	
New Mattie	130-ft wooden sternwheeler	1,491	200	Buchner and Krivor 2001	
J.D. Hinde	129-ft sternwheeler	573	110	Gearhart and Hoyt 1990	
Choctaw	223-ton sternwheel towboat	797	250	Krivor et al. 2002	
Star of the West	172-ton ocean-going sidewheel	8,300	400	Krivor et al. 2002	
John Walsh	275-ft sidewheeler	1,602	280	James et al. 2002	
Mary Somers	Iron-hulled sidewheeler	5,000	325	Pearson et al. 1993	
	Single	Objects			
Pipeline	18-in diameter	1,570	200	Duff 1996	

Vessel (Object)	Type and Size	Magnetic Deviation (nT)	Duration (ft)	Reference
Pipe	3 in × 10 ft	55	352	Krivor 2005
Pipe/mast/davit	18 in × 26 ft	475	104	Lydecker 2007
Anchor	6-ft shaft	30	270	Pearson et al. 1991
Iron anvil	150 lbs.	598	26	Pearson et al. 1991
Engine block	ngine block modern gasoline			Rogers et al. 1990
Steel drum	55 gallons	191	35	Rogers et al. 1990
Pipe	8-ft long × 3 in diameter	121	40	Rogers et al. 1990
Railroad rail segment			40	Rogers et al. 1990
7 Rocket Motors	Rocket Motors 8-34 ft long		75–180	Watts 2000
	Multiple	Objects		
Cable and chain	able and chain 5 ft		50	Pearson et al. 1991
Scattered ferrous metal	14 × 3 ft	100	110	Pearson et al. 1991
Anchor/wire rope	nchor/wire rope 8-ft modern stockless/large coil		140	Rogers et al. 1990

Furthermore, it should be inferred that one of the biggest influences on a wreck site's magnetic signature is directly related to the distance from the magnetometer sensor to the wreck site. As stated in Pearson and Birchette:

For a typical iron object, the intensity of its magnetic signature [i.e., anomaly] is inversely proportional to the cube of the distance. One pound of iron, for example, would produce an anomaly of 100 nanoteslas at a distance of 2 feet. At a distance of 10 feet the same pound of iron would produce an anomaly of only 1 nanotesla. A 1,000-ton ship could produce a 700-nanotesla anomaly at 100 feet and a barely discernible 0.7-nanotesla anomaly at 1,000 feet (Pearson and Birchette 1999:4–13).

An example of a steamboat wreck that produces a magnetic signature of less than 500 nT involves the purported *Undine* site investigated by Panamerican in 1999 and 2000. During 1999, remote sensing operations located a magnetic anomaly with a magnetic deflection of 193 nT with a duration of 300 ft. During the 2000 field investigations, the anomaly was identified as the remnant of a charred steamboat about 38–40 ft below the river's surface and buried 8 ft below riverbed sediments. Historic records indicate the *Undine* was extensively salvaged after the scuttling incident, whereupon everything of value, including all iron plating, machinery, and cannon, were removed from the wreck, but the hull remained in place (James and Krivor 2000:16–17). While only a small portion of the wreck site was uncovered (due to the extensive amount of overburden), it was evident that little of the hull is extant, only just to the turn of the bilge.

It should also be stated that two of the wreck sites with either small areas of deviation or low nanotesla deflections, the *J.D. Hinde* and the purported *Undine*, represent either partial hull remains (*J.D. Hinde*) or were heavily burned and salvaged (*Undine*). Historic records indicate that the *J.D. Hinde* was also salvaged after the wrecking process. Retaining none of her steam

machinery or wheels, half of the vessel was no longer present, most likely as a result of dredging; both salvage and dredging the obvious reason for its small magnetic duration (James and Pearson 1993:22). Salvage efforts are often sought to remove any cargo as well as any machinery, cannon, anchors, or other goods of value. During the Civil War, the salvage of iron for reuse was often paramount. As stated by John B. Jones on August 11, 1863, "the iron was wanted more than anything else but men" (Black 1958:200). Therefore, it may be speculated that any wreck site that (1) has been salvaged in the past, (2) has been exposed to excessive environmental processes (i.e., current), or (3) has been affected by channelization efforts (i.e., dredging) will produce a lower nanotesla deflection (due to less ferrous metal on site) than a wreck not exposed to similar processes.

If the signatures of the entire steamboat wrecks listed in Table 5-1 are averaged, an average magnetic deviation of 2,627 nT with an average duration of 321 ft is obtained. Although the sensor distance, environmental factors, and the amount of ferrous metal remaining on any given steamboat site must be considered, previously identified wreck sites have tended to produce sizable >200-nT magnetic deviations with a minimum duration of 110 ft. While the 110-ft duration represents the lowest duration of any of the known steamboat wreck sites, it must be stated that in such cases, a portion of the wreck is no longer extant due to previous salvage and dredging or channelization efforts. However, until further surveys show that this short duration is an "anomaly," so to speak, it must be employed as the baseline duration. Similarly, with the exception of the *Undine* site, which, as stated previously, was heavily salvaged, all other surveyed steamboats have nanotesla deviations approaching 500 nT or above, but its 200-nT reading must be employed as the baseline amplitude.

While the data indicates the validity of employing specific nanotesla strength and duration criteria when assessing magnetic anomalies, other factors must be considered. Pearson and Hudson (1990) have argued that the past and recent use of a water body must be an important, and often the most important, consideration in the interpretation of remote sensing data. Unless the remote sensing data, the historical record, or the specific environment (i.e., harbor entrance channel) provides compelling or overriding evidence, it is otherwise believed that the history of use should be a primary consideration in the interpretation. The constitution of "compelling evidence" is, to some extent, left to the discretion of the researcher. However, in settings where modern commercial traffic and historic use have been intensive, the presence of a large quantity of modern debris must be anticipated. In harbor, bay, or riverine settings, where traffic is heavy, this debris will be scattered along the channel right-of-way, although it may be concentrated in areas where traffic would slow or halt, and it will appear on remote sensing survey records as discrete, small objects. These latter statements are certainly applicable to the current survey corridor with its built environment, shipping channels, and extensive maritime traffic.

In addition to anomaly strength and duration considerations, all anomalies were assessed for type (monopole [negative or positive influence], dipole [negative and positive influence], or complex) and association with other magnetic anomalies (i.e., clustering) and side-scan sonar targets. Concerning the analysis of these anomalies, relative to potential significance, many will be found to represent a small, single-source object (a localized deviation) and are generally identified and labeled as nonsignificant, especially in an area of high use. As seen on contour maps, the contour lines for this type of anomaly can be seen to approach or go to, but not beyond, the adjacent survey trackline on which it is located. This visual interpretation is corroborated during the analysis of the electronic magnetometer strip-chart data of each survey trackline. An examination of the strip chart will show that the target was recorded only on a single transect and that it was not recorded (i.e., did not influence the ambient magnetic background) on adjacent lines. This is an important

distinction when an anomaly's readings are large deviations but are recorded on only one line. This indicates the source for this target must be a small, discrete object, and the magnetometer sensor must have passed close by or directly over the object to generate the large readings on this survey line yet not be recorded or have had an influence on adjacent lines. Because these anomalies represent single-source objects, they are not considered representative of a potentially significant submerged cultural resource.

False positives can also be recorded as a result of geomagnetic storm activity (Carrier et al. 2016). These solar-originating magnetic field disturbances can confound magnetic records, generating deceptive signatures. Although more applicable to areas generally void of anomalous sources such as the Outer Continental Shelf (OCS), as opposed to heavily built and trafficked environments with hundreds of anomalous sources such as the current survey area, there are several ways to mitigate these disturbances. One possibility is through the use of a transverse gradiometer such as mandated by the Bureau of Ocean Energy Management (BOEM) for cultural resources surveys on the OCS. As gradiometers measure the change in the magnetic field between two nearby sensors, the wide-reaching disturbances are recorded equally between the sensors, nullifying the deviation. Another method used primarily by Chronicle Heritage is through the comparison of project magnetic strips to the nearest magnetic observatory (such as those listed on http://www.intermagnet.org/). However, as Carrier et al. (2016) observed, geomagnetic storms during periods of Kp-index of 5 or higher diminish the ability of the researcher to identify storm sudden onset signatures within a dataset. For this reason, NOAA's Geomagnetic Forecast (found at https://www.swpc.noaa.gov/products/3-day-geomagnetic-forecast) is consulted to ensure that data is not collected on days of Kp-index 5 or higher. The NOAA recorded Kp-index during the Collinsville magnetometer survey was well under 5 with just three hours on October 21 just approaching 5. The following is the Kp-index for each day: Oct. 19 < 4, Oct. 20 < 3, Oct. 21 < 5 (just at 5 for 3 hours), Oct 22 < 3, Oct. 23 < 1, Oct. 24 < 1, Oct. 25 < 2, Oct. 26 < 5 (https://www.spaceweatherlive.com/en/archive/2023/10/26/kp.html).

The majority of anomalies recorded during any survey are generated by debris and not shipwrecks. As stated by Gearhart (2011:91–92), "archaeologists have repeatedly struggled to characterize reliable differences between magnetic signatures of shipwrecks and debris," employing amplitude, duration (i.e., spatial extent), and complexity of the signature as vague defining criteria, along with judgmental experience, and further states that "present methods for marine magnetic data interpretation are uncertain at best and scientifically unfounded at worst." In Garrison et al.'s (1989) study to establish an interpretive framework that would help identify the nature of magnetic anomalies, it was predicted correctly that anomalies caused by debris might be differentiated from shipwreck anomalies based on the contrast between permanent and induced magnetism. The study states:

While it may not be analytically possible to contrast iron and steel by remnant magnetization one may be able to characterize anomalies as to their inductive magnetization...The argument here would rely on the structural complexity of a shipwreck having a large or detectable inductive magnetization. Anomalies without this component could be classified as exclusively ferromagnetic features and by local extension debris (Garrison et al. 1989:2:224).

In his article entitled Archaeological Interpretation of Marine Magnetic Data, Gearhart (2011) expands on Garrison et al.'s 1989 premise and convincingly shows that while "one cannot distinguish between the anomaly produced by a shipwreck, and one produced by a similarly complex concentration of magnetic debris...shipwreck anomalies can be characterized by their induced magnetic fields and are distinguishable from a significant proportion of simple-source anomalies."

He goes on to state, "the most important parameter to consider when interpreting anomalies based on magnetic induction is the direction of magnetic moment" (Gearhart 2011:106) and "deviation from the northerly magnetic moment direction, common to all induced anomalies, has proven to be the single most powerful discriminator between simple-source anomalies and complex-source anomalies, including shipwrecks" (Gearhart 2011:102).

In simplistic terms, the contour map of the magnetic moment of an induced anomaly will have its negative value to the north and its positive value to the south. Gearhart presents contours of numerous known wreck and debris anomalies and illustrates that magnetic moments of shipwrecks (in the earth's northern hemisphere) are oriented to the north (no more than a 26degree deviation), as are those of complex debris sites (i.e., large areas of wire rope), while those of simple-source debris anomalies are not. He concludes by suggesting ±20 degrees from magnetic north as an orientation that will allow the successful differentiation of simple-source debris anomalies from most complex-source anomalies and virtually all shipwrecks (Gearhart 2011). Several examples from recent Chronicle Heritage projects demonstrate the validity of this model (Figure 5-8). While not an exhaustive review, we found these same principles apply with no deviation from Gearhart's findings and leads us to also conclude that identifying and categorizing the magnetic moment of an induced anomaly does allow the researcher the ability to differentiate a large percentage of debris source anomalies from potentially significant resources during analysis. A case in point is the recent diver investigation of 13 magnetic anomalies in the Skyway Gulf Intracoastal Waterway (James et al. 2011). Employing the above criteria of declination of the magnetic moment of the 13 magnetic anomalies investigated, 7 anomalies had magnetic moments that did not meet the characteristics of complex-source anomalies, including shipwrecks, but rather had signatures representative of simple-source debris. Subsequent diver investigation clearly showed that these anomalies did indeed represent nonsignificant debris. Representing over half of the total anomalies, if the orientation of the magnetic moment had been a criterion, they would not have been recommended for subsequent investigation. The remaining six anomalies that had magnetic moment characteristics indicative of shipwrecks or complex debris sites were also found to represent debris (James et al. 2011). This, however, is not unexpected given that this method does not rule out complex-source debris anomalies or all simple-source debris anomalies, just a much larger percentage than would have been ruled out if the method had not been employed. The declination of magnetic moment characteristics as an indicator of potential significance will, we believe, be proven and accepted. The end result could well be the reduction of a significant number of anomalies currently recommended for subsequent investigation.

Such theoretical considerations as those mentioned above, are widely employed by both academic oriented and commercial maritime archaeologists. Maritime archaeologists base their interpretation on the model of magnetic induction which aligns with efficiently illustrating marine magnetic data resulting from archaeological surveys (Gearhart 2011:105). Using the above theoretical considerations, specifically the Gearhart model, data produced from the geophysical survey was analyzed. Magnetic anomalies that exhibited known shipwreck characteristics such as having multicomponent signatures or maintaining an induced magnetic field were considered potentially significant and are discussed further in *Investigative Findings*. As many single or simple source anomalies are distinguishable from anomalies produced by shipwrecks, many magnetic anomalies were considered non-significant and did not warrant further investigation.




Figure 5-8. Magnetic contour maps of six wreck sites documented during recent Chronicle Heritage Projects. Black arrows indicate the declination of the magnetic anomaly's field. Note that the declination of all fields tends to orient within 20 degrees of magnetic north. See Tables 3-1 and 3-2 for additional information regarding these shipwrecks.

#### 5.3.2 Side-Scan Sonar

In contrast to magnetic data, side-scan interpretation is less problematic, as objects are reconstructed as they look to the eye. Side-scan sonar contacts, such as tree falls, logs, or tires can be immediately discarded as nonsignificant, while large areas of above-sediment wreckage, as well as some exposed potential paleofeatures (i.e., rock outcrops), are generally apparent. The chief factors considered in analyzing side-scan data, with regard to the wreckage, include linearity, height off bottom, size, associated magnetics, and environmental context. Since historic resources in the form of shipwrecks usually contain large amounts of ferrous compounds, complex side-scan targets with complex magnetic anomalies are of the greatest importance. The usual outcome of targets with no associated magnetics are items such as rocks, trees, and other nonhistoric debris of limited interest to the archaeologist.

# 5.4 Data Analysis

### 5.4.1 Data Processing

Once collected, survey data were processed and analyzed using an array of software packages designed to display, edit, manipulate, map, and compare proximities of the raster, vector, and tabular data. These packages include SonarWiz 7 for mosaicking side-scan sonar and subbottom profiler data, mapping target extents and generating target reports, figure details, and Geographic Information System (GIS) layers; Hypack Magnetometer Editor, MagPick, and Hypack Export were

used for tabulating anomaly characteristics and contouring magnetic data and generating GIS data layers. ESRI ArcGIS was used to display the data on basemaps to conduct a "proximity analysis" for each of the three types of targets (e.g., see which magnetometer, side-scan, and subbottom profiler anomalies are near each other and may be associated) and to generate figures for this report.

#### 5.4.2 Magnetic Data Collection and Processing

Data from the magnetometer were collected using QINSY. The data were stored as \*.CSV files by time and day. Contour maps were produced of the magnetic data with MagPick using a Minimum Curvature gridding algorithm (Figure 5-9). The contour vector file is saved and exported into the combined GIS database. The contour maps allow a graphic illustration of anomaly locations, spatial extent, and association with other targets. Magnetic data are reviewed, and the location, strength, duration, altitude of the sensor, and type of anomaly are captured and exported to a data table, which is then converted to a GIS feature class. For potentially significant anomalies, the depth of burial is estimated using the half-width rule (Breiner 1999:31).




Figure 5-9. MagPick griding algorithm (pictured bottom left) magnetic data display of a survey line and anomaly locations (pictured top left), example of a magnetic profile (pictured top right), and anomaly data table (pictured bottom right).

### 5.4.3 Side-scan Sonar Data Collection and Processing

Post-processing of side-scan sonar is accomplished using SonarWiz 7, a product that enables the user to view the side-scan data in digitizer waterfall format, pick targets, and enter target parameters including length, width, height, material, and other characterizations into a database of contacts. In addition, SonarWiz 7 "mosaics" the side-scan data by associating each pixel (equivalent to about 10 cm) of the side-scan image with its geographic location determined from the real-time Hypack corrected position. SonarWiz 7 is the industry standard for mosaicking capability, and the results are exported as geo-referenced \*.TIFFs for importing to the project GIS (Figure 5-10 and Figure 5-11). SonarWiz 7 can generate target reports in \*.PDF, Word, or Excel format. Chronicle Heritage uses the Word format for reports.




Figure 5-10. SonarWiz 7 software with mosaic example in the background, and a target selection zoom image to the left. Magnetic anomaly locations are overlaid.




Figure 5-11. SonarWiz 7 sonar contact tabular format, automatically generated.

#### 5.4.4 Subbottom Profiler Data Processing and Analysis

Postprocessing of subbottom profiler data, like the side-scan data, is done with SonarWiz 7, which, in this case, enables the user to view the subbottom data in a planar, trackline format. The user may view the data in a digitizer window as a waterfall format, allowing the digitizing of subbottom features of interest, linear extent, depth, and type (Figure 5-12). SonarWiz 7 batch processes waterfall images to \*.JPG format for figure generation. Digitized reflectors and the contact databases are exported to the GIS as \*.SHP files. SonarWiz 7 also allows the user to calculate the amount of sonar coverage and illuminate gaps to ensure full coverage of the Proposed API/APE.




Figure 5-12. SonarWiz 7 subbottom waterfall image showing the seismic profile-digitizing window. The blue crosshairs in the background chart show the location of the cursor, which at the time of the image was directly over the peak of the positive relief feature shown. This image is from a past survey conducted in Tampa Bay (see Faught and James 2009).

#### 5.4.5 Geographic Information System Analysis

A project GIS database is constructed using geo-referenced images and layers generated during the magnetometer, side-scan, and subbottom data analyses. Other layers can be added such as orthographic aerial imagery or navigation charts (Figure 5-13). Several important things are accomplished by GIS compilation. First, the collected data are compared with one another and evaluated for accuracy and consistency of the positioning information. Second, magnetic, side-scan, and subbottom targets are compared for spatial relationships (proximity analysis).




Figure 5-13. GIS database example showing magnetic anomalies, side-scan sonar contacts, magnetic contours, tracklines, and raster chart data showing environmental context (data taken from a previous investigation).

## 5.5 Investigative Findings

The maritime remote sensing survey of the Proposed API/APE was conducted from September 18 through October 25, 2023. Analysis of the remote sensing data identified 74 magnetic anomalies, 15 side-scan sonar contacts, and 21 subbottom profile reflectors associated with 12 geomorphological features in the form of disparate relict channel landforms. Eleven of these subbottom profiler features were not indicative of intact relict landforms that contained the potential to possess cultural material. One paleolandform, however, was initially thought to cross 7 survey transects within the Proposed API/APE. Upon further analysis, it would seem this feature is indicative of a braided network of dynamic river channels. As such, there is a low probability for the potential for intact cultural material deposits. Still, the landform area is currently being evaluated through coring and soil analysis to determine the possibility for site potential and, if necessary, mitigation.

A total of three (n = 3) targets were determined to be potentially significant. Each of the potentially significant targets were comprised of a magnetic anomaly and a side-scan sonar contact. These targets are all recommended for avoidance by project activities and are discussed further in Section 6.4.

### 5.6 Magnetometer Results

Employing the previous discussions on target analysis, magnetic anomalies were assessed for potential significance based on magnetic deviation (above and/or below ambient background), duration (distance in feet along a trackline), type (monopole, dipole, or complex), declination (orientation of the field relative to magnetic north), and association with other magnetic anomalies (i.e., clustering) and side-scan sonar contacts. Analysis of the magnetometer data identified 74 magnetic anomalies with an intensity greater than 5 nT (Table 5-2). Of these anomalies, 15 were associated with side-scan sonar contacts, allowing for the identification of the anomalies source.

Of the magnetic anomalies associated with sonar contacts, five (n = 5) were identified as cables, five (n = 5) were identified as channel markers, two (n = 2) were identified as debris, one (n = 1) was identified as the remains of a barge, and two (n = 2) were identified as unknown structural objects. One of the unknown structural objects was located near infrastructure, and the other adjacent to a channel marker, which could have been responsible for the associated magnetic anomalies. Of the remaining 59 magnetic anomalies that were not associated with acoustic contacts, one (n = 1) was identified as infrastructure, four (n = 4) were found to be associated with a charted cable, two (n = 2) were determined to originate from unknown buried features located outside of the Proposed API/APE, and one (n = 1) was identified at the location of a previously charted obstruction; however, no evidence of the obstruction was identified on the acoustic record. The remaining 51 anomalies were classified as single-point sources (SPSs). Magnetic contour maps are displayed in Figure 5-14 through Figure 5-18.

Regarding the analysis of potential significance of the anomalies identified in this investigation, many were found to represent nonsignificant modern debris, meaning the anomaly occurred on a single survey line and did not meet the criteria established in the previous chapter for the existence of potentially significant resources. However, three (n=3) of the magnetic anomalies were considered potentially significant, each of which was associated with a side-scan sonar contact. M.057 was associated with contact S.0005; however, it cannot be determined if the sonar contact is the source of the anomaly or if the nearby infrastructure is the only generator of the magnetic signature. Similarly, M. 035 is associated with contact S.0015; however, due to the adjacent channel marker, it cannot be determined if the contact contains a magnetic signature. The final potentially significant anomaly, M.074, was found to be associated with the remains of a barge. The low intensity of the anomaly suggests that the barge was of wooden construction, lending to its potentially historic nature. Magnetic anomalies M.057, M.035, and M.074 are considered potentially significant. These anomalies are discussed in further detail in Section 6.4. The data class column in Table 5-2 indicates the data type used to assess each magnetic anomaly.

Table 5-2. Magnetic Anomaly Data

Name	X and Y Coordinates Removed	Duration (ft)	Intensity (nT)	Type <sup>2</sup>	Assoc.	Notes	Data Class	Potentially Significant
M.001		533.31	970.12	С	-	Infrastructure	Nav Chart	-
M.002		174.96	15.79	D	_	SPS	Mag	-
M.003		323.76	32.69	D	_	SPS	Mag	-
M.004		161.56	125.29	D	-	SPS	Mag	-
M.005		203.98	30.89	D	S.0008	Cable	Chart	-
M.006		243.42	65.84	D	_	Buried feature	Mag	-
M.007		287.84	22.8	D	_	SPS	Mag	-
M.008		194.51	137.57	D	_	SPS	Mag	-
M.009		54.37	78.73	M+	_	SPS	Mag	-
M.010		43.45	49.19	D	_	SPS	Mag	-
M.011		588.76	3498.87	С	S.0010	Channel marker	Nav Chart	-
M.012		363.1	1046.52	С	S.0006	Cable	Nav Chart	-
M.013		21.58	107.69	D	-	SPS	Mag	-
M.014		269	4428.53	С	S.0012	Channel marker	Nav Chart	-
M.015		206.22	87.93	M-	_	SPS	Mag	-
M.016		257.18	19.84	D	_	SPS	Mag	-
M.017		49.86	31.82	D	-	SPS	Mag	-
M.018		139.22	85.2	M-	_	SPS	Mag	-
M.019		284.7	25.66	M-	-	SPS	Mag	-
M.020		141.08	13.6	D	_	SPS	Mag	-
M.021		292.92	19.25	D	_	SPS	Mag	-

Submerged Cultural Resources Assessment Survey for the Collinsville 500/230 kV Substation Project, Solano, Sacramento, and Contra Costa Counties, California

Name	X and Y Coordinates Removed	Duration (ft)	Intensity (nT)	Type <sup>2</sup>	Assoc.	Notes	Data Class	Potentially Significant
M.022		82.59	81.35	D	-	SPS	Mag	-
M.023		105.33	11.92	M+	-	SPS	Mag	-
M.024		393.28	19.13	D	-	SPS	Mag	_
M.025		160.47	9.55	D	-	SPS	Mag	_
M.026		129.95	8.85	M+	-	SPS	Mag	-
M.027		392.68	6610.55	D	S.0014	Channel marker	Nav Chart	_
M.028		97.95	53.74	D	-	SPS	Mag	_
M.029		227.3	78.87	D	S.0014	Channel marker	Nav Chart	_
M.030		76.18	146.9	M-	-	SPS	Mag	_
M.031		155.54	37.22	D	-	SPS	Mag	_
M.032		104.3	69.64	D	-	SPS	Mag	_
M.033		332.91	37.37	M+	-	SPS	Mag	_
M.034		253.63	27.91	D	-	SPS	Mag	_
M.035		276.19	817.81	С	S.0015	Structural contact and channel marker	Side-scan and Nav Chart	Y
M.036		249.19	393.45	D	S.0016	Channel marker	Nav Chart	-
M.037		141.18	214.1	D	-	SPS	Mag	-
M.038		111.11	2403.97	С	-	SPS	Mag	-
M.039		90.02	10.77	D	S.0013	Debris	Side-scan	-
M.040		254.42	6.51	D	-	SPS	Mag	-
M.041		251.37	73.04	M+	-	SPS	Mag	-
M.042		230.24	16.91	M-	_	SPS	Mag	-
M.043		254.51	52.08	M-	-	SPS	Mag	_

Submerged Cultural Resources Assessment Survey for the Collinsville 500/230 kV Substation Project, Solano, Sacramento, and Contra Costa Counties, California

Name	X and Y Coordinates Removed	Duration (ft)	Intensity (nT)	Type <sup>2</sup>	Assoc.	Notes	Data Class	Potentially Significant
M.044		78.42	20.51	D	-	SPS	Mag	-
M.045		85.63	230.1	D	-	SPS	Mag	-
M.046		102.7	40.7	D	-	SPS	Mag	-
M.047		159.39	11.55	D	-	SPS	Mag	-
M.048		162.12	25.42	D	-	SPS	Mag	-
M.049		161.88	34.66	M+	_	SPS	Mag	-
M.050		147.05	27.62	D	-	SPS	Mag	-
M.051		112.18	152.46	M+	-	SPS	Mag	-
M.052		80.89	15.14	D	_	SPS	Mag	-
M.053		84.68	14.57	M-	-	SPS	Mag	-
M.054		314.49	1073.36	D	-	Charted cable	Nav Chart	-
M.055		233.26	18.03	M+	-	SPS	Mag	-
M.056		297.2	16.63	D	-	SPS	Mag	-
M.057		311.83	198.2	С	S.0005	Structural contact and infrastructure	Side-scan sonar and Nav Chart	Y
M.058		214.88	346.82	D	-	Charted cable	Nav Chart	-
M.059		226.1	496.7	D	-	Charted cable	Nav Chart	-
M.060		79.18	19.66	M-	-	SPS	Mag	-
M.061		124.93	41.64	D	_	SPS	Mag	-
M.062		99.36	73.95	D	S.0009	Cable	Nav Chart	-
M.063		105.83	14.64	D	-	SPS	Mag	-
M.064		481.21	18359.92	С	-	Charted cable	Nav Chart	-
M.065		102.6	3701.29	С	S.0002, S.0003	Charted cable	Nav Chart	-

### Submerged Cultural Resources Assessment Survey for the Collinsville 500/230 kV Substation Project, Solano, Sacramento, and Contra Costa Counties, California

Name	X and Y Coordinates Removed	Duration (ft)	Intensity (nT)	Type <sup>2</sup>	Assoc.	Notes	Data Class	Potentially Significant
M.066		222.87	113.27	M+	-	SPS	Mag	-
M.067		173.05	20.44	D	-	SPS	Mag	-
M.068		401.88	29.64	D	S.0001	Debris	Side-scan	-
M.069		150.21	82.09	D	_	SPS	Mag	-
M.070		137.96	8.66	M+	_	SPS	Mag	-
M.071		336.09	351.71	С	_	Unknown buried feature	Mag	-
M.072		204.22	2283.73	С	_	Unknown buried feature	Mag	-
M.073		159.23	23.58	D	S.0009	Cable	Nav Chart	-
M.074		207.3	15.45	D	S.011	Barge	Side-scan	Υ

<sup>2</sup> Type: M-, negative monopole; M+, positive monopole; D, dipole; C, multicomponent.

<sup>3</sup> Mag: Magnetometer

<sup>4</sup> Nav Chart: Navigation Chart




Figure 5-14. Magnetic contours map key.

### **Figure Removed**

Figure 5-15. Magnetic contours map (1 of 4).

**Figure Removed** 

Figure 5-16. Magnetic contours map (2 of 4).

**Figure Removed** 

Figure 5-17. Magnetic contours map (3 of 4).

**Figure Removed** 

Figure 5-18. Magnetic contours map (4 of 4).

### 5.7 Side-Scan Sonar Results

Side-scan sonar contacts, as visual images, were assessed for structure, linearity, height off bottom, size, associated magnetics, and environmental context. The side-scan sonar data revealed 15 contacts within the Proposed API/APE (Table 5-3 and Table 5-4), of which, 14 were associated with magnetic anomalies. Analysis of the contacts associated with anomalies

classified five (n = 5) as cable, four (n = 4) as channel markers, one (n = 1) as debris, one (n = 1) as the remains of a wooden barge, and two (n = 2) as structural. It must be noted that the two contacts classified as structural were located within the radius of magnetic anomalies that were associated with infrastructure and a channel marker; therefore, it cannot be determined if the contact contains a magnetic source that was washed out by the nearby structures or if the contacts do not contain and magnetics. The remaining contact without a magnetic association was classified as debris. The fact that the barge did not contain a magnetic signature indicates the vessel was constructed of wood. A side-scan sonar mosaic illustrating the survey coverage is presented in Figure 5-19 and contacts are displayed in the magnetic contour maps (see Figure 5-14 through Figure 5-18).

Regarding the analysis of the potential significance of the contacts identified in this investigation, three (n=3) were determined to potentially represent cultural material, each of which was associated with a magnetic anomaly. S.0005 and S.0015 contained structural components, and S.0011 was identified as the remains of a barge. These contacts are considered potentially significant. These contacts are discussed in further detail in Section 6.4. The data class column in Table 5-3 indicates the data type used to assess each magnetic anomaly.

Table 5-3. Side-Scan Sonar Contact Data

Contact	X and Y Coordinates Removed	Class	Height (m)	Length (m)	Width (m)	Shadow (m)	Description	Data Class	Assoc.	Potentially Significant
S.0001		Debris	1.3	35	11.4	6.6	Debris scatter of an unknown origin, likely modern	Side-scan	M.068	-
S.0002		Cable	2	15.6	1.7	11.8	Linear object associated with high intensity magnetic anomaly, likely cable	Side-scan, mag	M.065	-
S.0003		Cable	3.6	26.8	2	27	Linear object associated with high intensity magnetic anomaly, likely cable	Side-scan, mag	M.065	-
S.0005		Structural	1.3	55	25.5	4	Unknown object with structural components	Side-scan	M.057	Y
S.0006		Cable	2	42.6	1	17.3	Linear object associated with high intensity magnetic anomaly, likely cable	Side-scan, mag	M.012	-
S.0007		Debris	0.5	23.9	15.4	2.5	Series of objects protruding from sea floor, possibly debris	Side-scan	-	-
S.0008		Cable	0.6	14.9	0.6	8	Linear object associated with magnetic anomaly, likely cable	Side-scan, mag	M.005	-
S.0009		Cable	2.9	36.6	2.8	8.3	Linear object associated with magnetic anomalies, likely cable	Side-scan, mag	M.062 M.073	-
S.0010		Channel marker	12.1	25.8	24	81.7	Pilings associated with a channel marker	Nav chart, side-scan	M.011	-
S.0011		Wreck	3	39.4	14.2	25.3	Object with structural components, possibly the remains of a barge	Side-scan	M.074	Y
S.0012		Channel marker	15.3	42.3	35.3	81.2	Pilings associated with a channel marker	Nav chart, side-scan	M.014	-

### Submerged Cultural Resources Assessment Survey for the Collinsville 500/230 kV Substation Project, Solano, Sacramento, and Contra Costa Counties, California

S.0013	Debris	1	24.5	2.1	3.6	Unknown object, possibly modern debris	Side-scan	M.039	-
S.0014	Channel marker	15.2	8.6	3.5	81	Piling associated with a channel marker	Nav chart, side-scan	M.027 M.029	_
S.0015	Structural	1.1	64.7	9.4	7.2	Unknown object with structural components, associated with high intensity magnetic anomaly	Side-scan, mag	M.035	Y
S.0016	Channel marker	13.4	9.9	3.8	80.4	Pilings associated with a channel marker	Nav chart, side-scan	M.036	-

<sup>&</sup>lt;sup>2</sup> Mag: Magnetometer

<sup>&</sup>lt;sup>3</sup> Nav Chart: Navigation Chart

Table 5-4. Sonar Report

	Table 3-4. Solial Report	
Target Image	Target Info	User Entered Info
- 50 - 100 - 150	S.0001  • Sonar Time at Target: 10/4/2023 5:54:04 PM  • X and Y Coordinates Removed  • Map Projection: EPSG:6418  • Acoustic Source File: LSP_20231004_COLLINSVILLE _002.jsf	Dimensions and attributes  ■ Target Width: 11.44 US ft  ■ Target Height: 1.26 US ft  ■ Target Length: 35.01 US ft  ■ Target Shadow: 6.61 US ft  ■ Mag Anomaly: M.068  ■ Classification1: Debris Scatter  ■ Description: Debris scatter of an unknown origin, likely modern
- 100 - 150 US # 100	S.0002 • Sonar Time at Target: 10/4/2023 6:42:36 PM • X and Y Coordinates Removed • Map Projection: EPSG:6418 • Acoustic Source File: LSP_20231004_COLLINSVILLE _004.jsf	Dimensions and attributes  Target Width: 1.66 US ft Target Height: 2.00 US ft Target Length: 15.64 US ft Target Shadow: 11.84 US ft Mag Anomaly: M.065 Classification1: Cable Description: Linear object associated with high intensity magnetic anomaly, likely cable
- 50 - 100 - 150 Us s 100	S.0003  Sonar Time at Target: 10/4/2023 6:43:18 PM Xand Y Coordinates Removed Map Projection: EPSG:6418 Acoustic Source File: LSP_20231004_COLLINSVILLE _004.jsf	Dimensions and attributes  Target Width: 1.98 US ft Target Height: 3.57 US ft Target Length: 26.80 US ft Target Shadow: 26.99 US ft Mag Anomaly: M.065 Classification1: Cable Description: Linear object associated with high intensity magnetic anomaly, likely cable
- 50 - 100 - 150 Us h 100 150	S.0005  • Sonar Time at Target: 10/4/2023 8:39:27 PM  • X and Y Coordinates Removed  • Map Projection: EPSG:6418  • Acoustic Source File: LSP_20231004_COLLINSVILLE _014.jsf	Dimensions and attributes  ■ Target Width: 25.53 US ft  ■ Target Height: 1.32 US ft  ■ Target Length: 54.95 US ft  ■ Target Shadow: 4.14 US ft  ■ Mag Anomaly: M.057  ■ Classification1: Structural  ■ Description: Unknown object with structural components

Target Image	Target Info	User Entered Info
50 115 100	S.0006  • Sonar Time at Target: 10/16/2023 7:21:55 PM • X and Y Coordinates Removed • Map Projection: EPSG:6418 • Acoustic Source File: 20231016.002.jsf	Dimensions and attributes  Target Width: 0.99 US ft Target Height: 1.98 US ft Target Length: 42.60 US ft Target Shadow: 17.35 US ft Mag Anomaly: M.012 Classification1: Cable Description: Linear object associated with high intensity magnetic anomaly, likely cable
	S.0007  • Sonar Time at Target: 10/16/2023 7:54:20 PM • X and Y Coordinates Removed • Map Projection: EPSG:6418 • Acoustic Source File: 20231016.003.jsf	Dimensions and attributes  Target Width: 15.42 US ft Target Height: 0.50 US ft Target Length: 23.90 US ft Target Shadow: 2.48 US ft Mag Anomaly: Classification1: Debris Description: Series of objects protruding from sea floor
US ft 100	S.0008 Sonar Time at Target: 10/16/2023 8:28:11 PM X and Y Coordinates Removed Map Projection: EPSG:6418 Acoustic Source File: 20231016.007.jsf	Dimensions and attributes  Target Width: 0.55 US ft Target Height: 0.55 US ft Target Length: 14.90 US ft Target Shadow: 7.99 US ft Mag Anomaly: M.005 Classification1: Cable Description: Linear object associated with magnetic anomaly, likely cable or modern debris
50 US N	S.0009 • Sonar Time at Target: 10/16/2023 10:37:04 PM • X and Y Coordinates Removed • Map Projection: EPSG:6418 • Acoustic Source File: 20231016.012.jsf	Dimensions and attributes  Target Width: 2.81 US ft Target Height: 2.89 US ft Target Length: 36.56 US ft Target Shadow: 8.26 US ft Mag Anomaly: M.062, M.073 Classification1: Cable Description: Linear object associated with magnetic anomalies, likely cable

Target Image	Target Info	User Entered Info
- 100 - 150 US ft 100	S.0010 • Sonar Time at Target: 10/17/2023 7:25:47 PM • X and Y Coordinates Removed • Map Projection: EPSG:6418 • Acoustic Source File: 20231017.005.jsf	Dimensions and attributes  Target Width: 24.03 US ft Target Height: 12.12 US ft Target Length: 25.84 US ft Target Shadow: 81.65 US ft Mag Anomaly: M.011 Classification1: Channel Marker Description: Pilings associated with a channel marker
- 50 - 100 - 190 180 180	S.0011 • Sonar Time at Target: 10/17/2023 7:40:20 PM • X and Y Coordinates Removed • Map Projection: EPSG:6418 • Acoustic Source File: 20231017.005.jsf	Dimensions and attributes  Target Width: 14.15 US ft Target Height: 3.04 US ft Target Length: 39.36 US ft Target Shadow: 25.34 US ft Mag Anomaly: M.074 Classification1: Wreck Description: Object with structural components, possibly the remains of a barge
- 50 - 100 - 150	S.0012 • Sonar Time at Target: 10/18/2023 5:37:59 PM • X and Y Coordinates Removed • Map Projection: EPSG:6418 • Acoustic Source File: 20241018.001.jsf	Dimensions and attributes  Target Width: 35.30 US ft Target Height: 15.39 US ft Target Length: 42.25 US ft Target Shadow: 81.24 US ft Mag Anomaly: M.014 Classification1: Channel Marker Description: Pilings associated with a channel marker
- 100 - 100 - 150 US ft	S.0013  • Sonar Time at Target: 10/18/2023 6:37:36 PM • X and Y Coordinates Removed • Map Projection: EPSG:6418 • Acoustic Source File: 20241018.002.jsf	Dimensions and attributes  Target Width: 2.10 US ft Target Height: 1.02 US ft Target Length: 24.50 US ft Target Shadow: 3.58 US ft Mag Anomaly: M.039 Classification1: Debris Description: Unknown object, possibly modern debris

Target Image	Target Info	User Entered Info
50 US 100	S.0014  • Sonar Time at Target: 10/18/2023 7:03:13 PM • X and Y Coordinates Removed • Map Projection: EPSG:641 • Acoustic Source File: 20241018.003.jsf	Dimensions and attributes  Target Width: 3.55 US ft Target Height: 15.15 US ft Target Length: 8.56 US ft Target Shadow: 80.97 US ft Mag Anomaly: M.027, M.029 Classification1: Channel Marker Description: Piling associated with a channel marker
50 US 100	S.0015 • Sonar Time at Target: 10/18/2023 8:37:28 PM • X and Y Coordinates Removed • Map Projection: EPSG:641 • Acoustic Source File: 20241018.005.jsf	Dimensions and attributes
90 US n 190	S.0016 • Sonar Time at Target: 10/18/2023 9:38:55 PM • X and Y Coordinates Removed • Map Projection: EPSG:641 • Acoustic Source File: 20241018.008.jsf	Dimensions and attributes




Figure 5-19. Side-scan sonar mosaic illustrating coverage of the maritime Survey area.

### 5.8 Subbottom Profiler Results

The review of shallow seismic (subbottom profiler) data for this project included 19 gigabytes of data across the Proposed API/APE. These data were first bottom tracked to the first return then amplified using an Automatic Gain Control (AGC) algorithm. Penetration was typically 6–7 m (approximately 20–23 ft) below the mudline (BML) in the Proposed API/APE (Figure 5–20). It should be noted that no surface expressions of paleofeatures with the potential to contain preserved precontact sites, such as chert outcrops or exposed middens, were recorded on side-scan sonar records. Thus, these features were limited to interpretation from subbottom profiler data.


Analysis of the subbottom profiler record indicated the Proposed API/APE was composed of unconsolidated marine sediments (sand) to the depth of the instrument's capability, typically 5–6 m (16–19 ft). The shallow seismic records were dominated by high-amplitude reflectors (riverbed) underlaid with chaotic facies with rare defined reflectors. A total of 21 subbottom profiler reflectors associated with 12 geomorphological features in the form of relict channel landforms were identified within the Proposed API/APE (Figure 5–21). However, a majority of these paleochannels did not appear on adjacent lines, indicating that the channel, as a whole, is no longer intact due to the dynamic nature of such waterways.

Two sets of paleochannels, however, were identified across multiple survey lines. Feature 5 was identified across two adjacent lines, indicating the remnants of a relict paleochannel. However, the margins of this paleochannel, and the majority of other paleochannels identified in the dataset, were mostly truncated, as the channel intersected the extents of the current riverbed. Thus, the area in which cultural material could be located has been removed or dispersed by dynamic wave, and subsequently, sediment movement.

On a second review of the dataset, Feature 7 (Figure 5-20), another paleochannel with margins, was identified. The margins of this paleochannel were largely intact, and incline to form a terrace or levee on either side. These types of elevated landforms contain the potential for cultural material and indigenous archaeological sites. The terraced landform ranged from a depth of 4 to 8 feet below seafloor (BSF).

However, while this feature was initially thought to cross seven survey transects through and into the Proposed API/APE, upon closer analysis each cross section differed markedly from the others indicating a noncontinuous landform but rather separate and independent features. This argues that what is represented by the subbottom record is a braided network of constantly changing and shifting river channels. Subsequently, the dynamic nature of this area also argues for a low probability of the potential for intact cultural material deposits.

That said, the landform area is currently being evaluated through coring and soil analysis. While the probability is low for the presence of cultural material, if sediment analysis indicates the potential for prehistoric presence, a monitoring plan to mitigate impacts to the paleolandform will be developed, approved by the review agency, and implemented (e.g., archaeological monitoring via vacuum-water screening at the surface).






Figure 5-20. Example of Subbottom Feature 007 (F7) from the maritime survey area. This profile is provided in both unannotated (above) and annotated (below) formats.

### **Figure Removed**

Figure 5-21. Subbottom profiler features identified within the Proposed API/APE, Feature 7 can be seen outlined in blue, crossing the cable corridor boundary.

### 5.9 Potentially Significant Targets

Analysis of the remote sensing data identified three (n = 3) potentially significant targets within the Proposed API/APE. Each of these targets included a magnetic anomaly and a side-scan sonar contact. Target 1 was magnetic anomaly M.057 and sonar contact S.0005. Target 2 was magnetic anomaly M.035 and sonar contact S.0015. Target 3 was magnetic anomaly M.074 and sonar contact S.0011. Diver investigation column indicates if diver investigation on each target is recommended.

### 5.9.1 Target 1

Target 1 included magnetic anomaly M.057 and side-scan sonar contact S.0005. M.057 was identified as a complex magnetic anomaly with an intensity of 198.2 nT and a duration of 311.83 ft. Side-scan sonar contact S.0005 was classified as possible vessel like structural components, measuring 55 ft long, 25.5 ft wide, with a height of 1.3 ft. It must be noted that the location of Target 1 is adjacent to infrastructure, therefore, it cannot be determined if contact S.0005 contains a magnetic signature; meanwhile, it is highly probable that magnetics associated with S.0005 were absorbed into the overall magnetic signature of the nearby infrastructure. Nevertheless, due to the possible vessel like structural components of Target 1, the target must be considered to possibly represent a potentially significant cultural resource.

Because of the distance from the cable lay, avoidance of Target 1 can be accomplished, which will preclude and mitigate any potential adverse effect. Located approximately 187 feet from the actual cable lay, Target 1's proximity to the cable corridor renders the importance for positional accuracy throughout project activities. Prior to these activities (i.e., jetting, anchoring, etc.), all project personnel and vessels involved in Proposed Project construction activities will be made aware of the Target's location to ensure avoidance.

### 5.9.2 Target 2

Target 2 is comprised of magnetic anomaly M.035 and side-scan sonar contact S.0015. M.035 was identified as a complex magnetic anomaly with an intensity of 817.81 nT and a duration of 276.19 ft. Side-scan sonar contact S.0015 was classified as possible vessel like structural components, measuring 64.7 ft long, 9.4 ft wide, with a height of 1.1 ft. It must be noted that the location of Target 2 is adjacent to a channel marker; therefore, it cannot be determined if contact S.0015 contains a magnetic signature. Meanwhile, it is highly probable that magnetics associated with S.0015 were absorbed into the overall magnetic signature of the nearby channel marker. Nevertheless, due to the possible vessel like structural components of Target 2, the target must be considered to possibly represent a potentially significant cultural resource.

Because of the distance from the cable lay, avoidance of Target 2 can be accomplished, which will preclude and mitigate any potential adverse effect. Located approximately 175 feet from the actual cable lay, Target 2's close proximity to the cable corridor renders the importance for positional accuracy throughout project activities. Prior to these activities (i.e., jetting, anchoring, etc.), all project personnel and vessels involved in Proposed Project construction activities will be made aware of the Target's location to ensure avoidance.

### 5.9.3 Target 3

Target 3 includes magnetic anomaly M.074 and side-scan sonar contact S.0011. M.074 was identified as a dipole with an intensity of 15.45 nT and a duration of 207.3 ft. Contact S.0011 is rectangular in shape and measured 39.4 ft long, 14.2 ft wide, with a height of 3 ft. Its shape indicates a possible barge, the low intensity of the associated magnetic anomaly indicates that the possible watercraft is of wooden construction, lending to its likely historic nature relative to age. Structural components include transverse (side to side) and longitudinal frames. Because it is unknown if the barge is upside down or right side up, it is unknown if these represent floor futtocks and keelsons, or deck beams and stringers. Believed to represent the remains of a wooden bargelike watercraft, the target must be considered to represent a potentially significant cultural resource.

Because of the distance from the cable lay, avoidance of Target 3 can be accomplished, which will preclude and mitigate any potential adverse effect. Located approximately 235 feet from the actual cable lay, Target 3's somewhat close proximity to the cable corridor renders the importance for positional accuracy throughout project activities. Prior to these activities (i.e., jetting, anchoring, etc.), all project personnel and vessels involved in Proposed Project construction activities will be made aware of the Target's location to ensure avoidance.

### 6 Conclusions and Recommendations

eTrac, Inc., conducted a Phase 1 SCRAS on behalf of Chronicle Heritage. This investigation comprises a comprehensive geophysical investigation, including a magnetometer, side-scan sonar, and subbottom profiler, of the LSPGC 230 Kilovolt Submarine Cable Proposed API/APE. The Proposed API/APE is located on the lower Sacramento River and upper reaches of Suisun Bay within Contra Costa, Sacramento, and Solano counties, California.

The investigation revealed three potentially significant targets. Each target included a side-scan sonar contact and a magnetic anomaly. The acoustic contacts associated with Target 1 and Target 2 contained vessel-like structural components. Although their identity could not be determined, their structural characteristics indicate they may represent potentially significant cultural resources. Target 3 is believed to represent the remains of a wooden barge-like watercraft, and the target must be considered to represent a potentially significant cultural resource.

As stated in NRHP Bulletin 15, How to Apply the National Register Criteria for Evaluation (National Park Service n.d.) Properties found potentially eligible, eligible, or listed on the NRHP must be considered within the framework of the proposed action. If adverse impact to such property is possible, alternatives to the proposed action, i.e., avoidance, must be evaluated. Because of the distance from the cable lay, avoidance of targets can be accomplished, which will preclude and mitigate any potential adverse effect. Located over 150 feet from the actual cable lays, the proximity of Targets 1, 2, and 3 to the cable corridor renders the importance for positional accuracy throughout project activities. Prior to these activities (i.e., jetting, anchoring, etc.), all project personnel and vessels involved in Proposed Project construction activities will be made aware of the Target's location to ensure avoidance.

In addition, one paleolandform was identified within the Proposed API/APE. While this feature was initially thought to cross 7 survey transects and through and into the Proposed API/APE, upon closer analysis each cross section differed markedly from the other indicating a noncontinuous landform but rather separate and independent features. This argues that what is represented by

the subbottom record is a braided network of constantly changing and shifting river channels. Subsequently, the dynamic nature of this area also argues for a low probability of the potential for intact cultural material deposits.

That said, the landform area is currently being evaluated through coring and soil analysis. While the probability is low for the presence of cultural material, if sediment analysis indicates the potential for prehistoric presence, a monitoring plan to mitigate impacts to the paleolandform will be developed, approved by the review agency, and implemented (e.g., archaeological monitoring via vacuum-water screening at the surface).

### 6.1 Procedures to Deal with Unexpected Submerged Cultural Discoveries

Despite the intensive cultural resource survey and analysis investigations that have been performed in anticipation of this project, it is possible that cultural resource deposits, in the form of prehistoric or historic archaeological sites, may be discovered during construction. Details and procedures for the handling of these unanticipated discoveries will be outlined in an Unanticipated Discoveries Plan which will be developed and submitted for approval prior to construction. Based on the actual construction methods which are not known at this time, the Unanticipated Discoveries Plan will recommend mitigation measures to guide the identification of cultural material or resources (e.g., archaeological monitoring via vacuum-water screening at the surface in moderate to high sensitivity areas, or a Workers' Environmental Awareness Training program that educates the underwater construction team about what to look for (i.e., aboriginal pottery, precontact stone tools, bone, or shell tools, as well as historic shipwreck remains).

Submerged Cultural Resources Assessment Survey for the Collinsville 500/230 kV Substation Project, Solano, Sacramento, and Contra Costa Counties, California

This page intentionally left blank.

### 7 References

### Atwater, Brian. F.

1982 Geologic maps of the Sacramento-San Joaquin Delta, California. No. 1401. U.S. Government Printing Office.

### Barrette, Samuel, A.

1908 The Ethno-Geography of the Pomo and Neighboring Indians. In *University of California Publications in American Archaeology and Ethnology*. Vol. 6, No. 1. University of California Press, Berkeley, California.

### Beeler, Madison S.

1955 Saclan. In International Journal of American Linguistics, Vol.21, No.3, pp. 201–209. University of Chicago Press, Chicago, Illinois.

### Bennyhoff, James

1961 Ethnogeography of the Plains Miwok. Unpublished Ph.D. Dissertation. University of California Berkeley.

### Black, Frederick R.

1958 A History of Fort Wadsworth, New York Harbor. Cultural Resources Management Study #7. Submitted to the Division of Cultural Resources, North Atlantic Regional Office, National Park Service, U.S. Department of the Interior.

### Boehle, Richard

2013 Interurban Electric Railways in Northern California and the Central Valley, Railwest.com. Web site copyright 2002-2013, DigitalNetExpress.com, Burbank, California

### Bowen, Jerry

Township began with Mormon colony site. *Historical Articles of Solano County, Online Database*. July 10, 2000, https://www.solanoarticles.com/history/index.php/weblog/more/township\_began\_with\_mormon\_colony\_site/, accessed October 2023.

### Breiner, S.

1973 Applications Manual for Portable Magnetometers. Geometrics, Inc., Sunnyvale, California.

1999 Applications Manual for Portable Magnetometers. Geometrics, Inc., San Jose, California.

### Buchner, C. Andrew., and Michael Krivor

2001 Cultural Resources Reconnaissance Study of the White River Navigation Project. Prepared for the USACE, Memphis District, by Panamerican Consultants, Inc.

### California State Lands Commission

1988 A Map and Record Investigation of Historical Sites and Shipwrecks Along the Sacramento River Between Sacramento City and Sherman Island. California State Lands Commission, Sacramento.

### Carrier, Brandi M., Antti Pulkkinen, and Michael Heinz

2016 Recognizing Geomagnetic Storms in Marine Magnetometer Data: Toward Improved Archaeological Resource Identification Practices. *Science & Technology of Archaeological Research* 2(1):1–14.

### Contra Costa County

2010 Contra Costa County General Plan. https://www.contracosta.ca.gov/4732/General-Plan.

### Cook, Sherburne F.

1957 The Aboriginal Population of Alameda and Contra Costa Counties, California. In University of California Anthropological Records, Vol. 16, No.4, pp. 131-156. University of California Press, Berkeley and Los Angeles, California.

### Davis, Hon Win, J.

1890 An Illustrated History of Sacramento County, California. The Lewis Publishing Company, Chicago.

### Delgado, James P.

2002 Maritime and Underwater Archaeology on the Pacific Coast. In Ruppe, C.V. and J.F. Barstad, Eds. International Handbook of Underwater Archaeology, 221–246. Springer Science+Business Media, New York.

### Derlikowski, Andrew, Justin Milewski, and William Wilson

2022 Referendum to 2021 Submerged Cultural Resources Diver Identification of Targets in Moriches and Shinnecock Inlets in Connection with the Fire Island to Montauk Point Coastal Storm Risk management Project, Atlantic Coast of Long Island, New York. Commonwealth Heritage group, Inc., Pensacola, Florida, under subcontract to Taylor Engineering, Inc., Jacksonville, Florida. Submitted to the U.S. Army Corps of Engineers, New York District.

### Duff, James A.

1996 Underwater Archaeological Investigation and Documentation of Three Anomaly Clusters Within Three Segments of Proposed Preferred Corridor for Replacement of Bonner Bridge, Oregon Inlet, North Carolina. Panamerican Consultants, Inc., Memphis, Tennessee, under subcontract to Parsons, Brinckerhoff, Quade & Douglas, Inc., Morrisville, North Carolina. Submitted to the Federal Highway Administration and the North Carolina Department of Transportation.

### Eckbo, Dean, Austin and Williams (EDAW)

2008 Draft Environmental Impact Report, Solano County 2008 Draft General Plan. Prepared for County of Solano, Resource Management Department, April 18, 2008. Electronic document, https://www.solanocounty.com/civicax/filebank/blobdload.aspx? BlobID=15179, accessed October 2023.

### Farris, Glen, Kathleen Davis, and John McAleer

1988 The John Marsh Stone House Project. Unpublished study available through California State Parks and Recreation, Sacramento, CA.

### Faught, Michael K.

- 1996 Clovis Origins and Underwater Prehistoric Archaeology in Northwestern Florida. Ph.D. dissertation University of Arizona, Tucson.
- 2002–2004 Submerged Paleoindian and Archaic sites of the Big Bend, Florida. *Journal of Field Archaeology* 29(3-4):273–290.

### Faught, Michael K., and Stephen R. James, Jr.

2009 Addendum to the Remote Sensing Survey of the Tampa Bay harbor Survey along Cuts A & B Hillsborough & Pinellas Counties, Florida. Prepared for U.S. Army Corps of Engineers, Jacksonville District, by Panamerican Consultants, Inc., Memphis, Tennessee.

### Fischer, Anders

1995 Man & Sea in the Mesolithic: Coastal Settlement Above and Below Present Sea Level 53. Oxbow Monograph.

### Fredrickson, David A.

- 1968 Archaeological Investigation at CCO-30, near Alamo, Contra Costa County, California. Center for Archaeological Research at Davis. Vol. 1. On file at the University of California, Davis.
- 1973 Early Cultures of the North Coast Ranges. Ph.D. Dissertation. Department of Anthropology. University of California, Davis.

### Gagliano, Sherwood M., Charles E. Pearson, Richard A. Weinstein, Diane E. Wiseman and Cristopher M. McClendon

- 1982 Sedimentary Studies of Prehistoric Archaeological Sites: Criteria for the Identification of Submerged Archaeological. Sites of the Northern GOM Continental Shelf, Prepared for the U.S. Department of the Interior National Park Service, Division of State Plans and Grants, Contract No. C35003(79).
- Garrison, Ervan G., Charles P. Giammona, Frank J. Kelly, Anthony R. Trip, and Gary A. Wolff
  1989 Historic Shipwrecks and Magnetic Anomalies of the Northern Gulf of Mexico:
  Reevaluation of Archaeological Resource Management Zone 1. Volume II: Technical
  Narrative. OCS Study/MMS 89-0024. U.S. Department of the Interior, Minerals
  Management Service, Gulf of Mexico OCS Regional Office, New Orleans, Louisiana.

### Gearhart, Robert L.

2011 Archaeological Interpretation of Marine Magnetic Data, pp. 90–113. In *The Oxford Handbook of Maritime Archaeology*, edited by Alexis Catsambis, Ben Ford, and Donny L. Hamilton. Oxford University Press, New York.

### Gearhart, Robert L., and Steven A. Hoyt

1990 Channel to Liberty: Underwater Archaeological Investigations, Liberty County, Texas. Espey, Huston & Associates, Austin, Texas. Submitted to the U.S. Army Corps of Engineers, Galveston District.

### Graves, Roy

1994 Railroading on San Francisco Bay, The Western Railroader 17(175):1-11.

### Gudde, Erwin G.

1998 California Place Names: The Origin and Etymology of Current Geographical Names. Revised and enlarged by William Bright. 4<sup>th</sup> ed. University of California Press. Berkeley and Los Angeles, California.

### Helley, E. J. and R. W. Graymer

1998 Quaternary Geology of Contra Costa County, and Surrounding Parts of Alameda, Marin, Sonoma, Sacramento, and San Joaquin Counties, California: A Digital Database. U.S. Geological Survey, Open File Report.

### Hoffman, Ogden

1862 Reports of Land Cases Determined in the United States District Court, Northern District of California, Volume 1, Ogden Hoffman, District Judge. Report on file digitally at California State University, Monterey Bay, Digital Commons, Monterey, California.

### Hoyt, Steven D.

1990 National Register Assessment of the SS Mary, Port Aransas, Nueces County, Texas. Espey, Huston & Associates, Austin, Texas. Submitted to the U.S. Army Corps of Engineers, Galveston District.

### Irion, Jack B., and Clell L. Bond

1984 Identification and Evaluation of Submerged Anomalies, Mobile Harbor, Alabama. Espey, Huston & Associates, Austin, Texas. Submitted to the U.S. Army Corps of Engineers, Mobile District.

### James, Stephen R., Jr., Michael K. Faught, and Anderw D.W. Lydecker

2011 Diver Identification of Fourteen Target in the Gulf Intracoastal Waterway, Manatee, Pinellas, and Hillsborough Counties, Florida. Prepared for the U.S. Army Corps of Engineers, Jacksonville District. Prepared by Panamerican Consultants, Inc., Memphis, Tennessee.

### James, Stephen R., Jr., and Charles E. Pearson

- 1991 Magnetometer Survey and Ground Truthing Anomalies, Corpus Christi Ship Channel, Aransas and Nueces Counties, Texas. Coastal Environments, Inc., Baton Rouge, Louisiana. Submitted to the U.S. Army Corps of Engineers, Galveston District.
- Submerged Cultural Resources Investigations of the Steamboat J.D. Hinde (41LB85) Channel to Liberty, Liberty County Texas. Prepared for the U. S. Army Corps of Engineers, Galveston District by Panamerican Consultants, Inc., Tuscaloosa, Alabama and Coastal Environments, Inc.

### James, Stephen R., Jr., and Michael C. Krivor

2000 Submerged Cultural Resources Associated with the Battle of Johnsonville: The 2000 Season. Prepared for the Tennessee Historical Commission by Panamerican Consultants, Inc., Memphis, Tennessee.

### James, Stephen R., Jr., Jack C. Hudson, and Kay G. Hudson

1991 The 303 Hang: Archaeological Investigations of a Two Masted Schooner Wrecked Offshore Freeport, Brazoria County, Texas. Prepared for the U.S. Army Corps of Engineers, Galveston District, by Panamerican Consultants, Inc., Tuscaloosa, Alabama.

### James, Stephen R., William J. Wilson, and Erica K. Gifford

- 2016 Underwater Archaeological Assessment and Diver Assessment/Evaluation for Future Extension Concept/2014B Revised Bridge on New Location, Bonner Bridge Project, Dare County, North Carolina. Prepared for North Carolina Department of Transportation under contract to Parsons, Brinkerhoff, Inc., by Panamerican Consultants, Inc. Memphis, Tennessee.
- 2019 Submerged Cultural Resources Assessment for Priority Water Bottoms in the Mobile Bay Area, Mobile and Baldwin Counties, Alabama. Prepared for Mobile Bay Estuary Program, by Panamerican Consultants, Inc., Memphis, Tennessee.

### James, Stephen R., Andrew D.W. Lydecker, and Erica K. Gifford

2016 Remote Sensing Surveys and Underwater Inspections, Fire Island Inlet to Moriches Inlet, Storm Risk Reduction Project, Fire Island National Seashore, Suffolk County, New York. Prepared for the U.S. Army Corps of Engineers, New York District by Panamerican Consultants, Inc., Memphis, Tennessee.

James, Stephen R., Jr., Michael C. Krivor, Alan Whitehead, Kristin Zoelmer, and Michael C. Tuttle
2002 National Register of Historic Places Eligibility Evaluations of Targets 3B-2-2 and 3B-2-6
Located Within Item 3B-2 of the Upper Yazoo Projects and Limited Survey and National
Register of Historic Places Eligibility Evaluations of All Bridges, Structures, and Targets
4-6, 4-7, 4-11, 4-12, 4-15, and 4-16 Located Within Item 4B of the Upper Yazoo Projects,
Leflore County, Mississippi. Submitted to the USACE, Vicksburg District by
Panamerican Consultants, Inc., Memphis, Tennessee.

### Journal of American History (JAH)

2005 Mexican California. In California as I Saw It: First-Person Narratives of California's Early Years, 1849-1900. *Journal of American History* 92(1):324-325. Electrontic document, https://www.loc.gov/collections/california-first-person-narratives/articles-and-essays/early-california-history/mexican-california/, accessed October 2023.

### Kamiya, Gary

2014 Cursed ship San Carlos' luck turns: 1st to sail into S.F. Bay. *SF Gate*, August 15, 2014. Electronic document, https://www.sfgate.com/bayarea/article/Cursed-ship-San-Carlos-luck-turns-1st-to-sail-5692069.php, accessed October 2023.

### Kantor, J.R.K.

1964 Grimshaw's Narrative: Being the Story of Life and Events in California During Flush Times, Particularly the Years 1848–50, Including a Biographical Sketch. Sacramento Book Collectors Club, Sacramento, California.

### Kozakavich, Stacy C.

The Archaeology of Utopian and Intentional Communities, University Press of Florida, ISBN14: 9780813068978.

### Kraft, John C., Daniel F. Belknap, and Ilthan Kayan

1983 Potential of the Discovery of Human Occupation Sties on the Continental Shelves and Nearshore Coastal Zone. In *Quaternary Coastlines and Marine Archaeology*, edited by P. M. Master and N. C. Flemming, pp. 87-120. Academic Press, New York.

### Krivor, Michael C.

2005 Bonner Bridge Cultural Resources Survey and Diver Assessment of Submerged Targets, Dare County, North Carolina. Conducted for the North Carolina Department of Transportation under contract to Parson, Brinkerhoff, Quade & Douglas, Inc., by Panamerican Consultants, Inc., Memphis, Tennessee.

### Krivor, Michael C., Stephen R. James Jr., and Alan Whitehead

2002 National Register of Historic Places Eligibility Evaluations of 13 Potential Watercraft Targets within the Upper Yazoo Projects Items 5 through 9 Quitman, Tallahatchie and Leflore Counties, Mississippi. Prepared for the U.S. Army Corps of Engineers, Vicksburg District.

### Kroeber, Alfred L.

- Handbook of the Indians of California. Smithsonian Institution, Bureau of American Ethnology Bulletin 78. Washington Government Printing Office, Washington, D.C.
- 1932 The Patwin and their Neighbors. In *University of California Publications of American Archaeology and Ethnology*. Vol. 29, No. 4, pp. 253–423. University of California Press, Berkeley, California.
- 1970 Handbook of the Indians of California. California Book Company. Berkeley, California.

### Levy, Richard

1978 Eastern Miwok. In *California*, edited by R.F. Heizer, pp. 398–413. Handbook of North American Indians Vol.8, William C. Sturtevant, general editor. Smithsonian Institution, Washington, D.C.

### Lillard, Jeremiah B., and William K. Purves

1936 The Archaeology of The Deer-Creek-Consumnes Area. Sacramento Co., California. Sacramento Junior College Department of Anthropology. Bulletin 1.

### Lydecker, Andrew D.W.

2007 Historic Assessment and Diver Evaluations of Two Magnetic Anomalies Near Sand Key, Pinellas County, Florida. Prepared for the U.S. Army Corps of Engineers, Jacksonville District, under subcontract to the U.S. Army Corps of Engineers, Memphis District. Panamerican Consultants, Inc., Memphis, Tennessee.

### Masters, P.M., and N.C. Flemming

1983 Quaternary Coastlines. Academic Press, New York.

### McCullough, David

2022 Contra Costa County History. Conta Costa County Historical Society. Electronic document, https://www.cocohistory.org/contra-costa-county-history, accessed November 2023.

### McGowan, Joseph A.

1961 History of the Sacramento Valley. Lewis Historical Publishing Company, New York.

### McKern, W. C.

- Functional Families of the Patwin. In *University of California Publications of American Archaeology and Ethnology.* Vol 13, No. 7, pp. 236–258. University of California Press, Berkeley, California.
- 1923 Patwin Houses. In *University of California Publications of American Archaeology and Ethnology*. Vol 20, pp. 159–171. University of California Press, Berkeley, California.

### Meyer, Jack, Julia Costello, Patricia Mikkelsen, Melissa Johnson, and Naomi Scher

2013 Volume I – Archaeological Resources; Suisun Marsh Habitat Management, Preservation, and Restoration Place Cultural Resources Contextual Report. Prepared by Far Western Anthropological Research Group, Inc. Submitted to Bureau of Reclamation, Mid Pacific Region December 2013. Report digitally available online.

### Moratto, Michael J.

1984 California Archaeology. Academic Press, Orlando, Florida.

### National Park Service (NPS)

n.d. How to Apply the National Register of Criteria for Evaluation. National Register Bulletin 15. U.S. Department of the Interior, Interagency Resources Division, Washington, D.C.

### National Park Service (NPS)

Abandoned Shipwreck Act Guidelines. https://www.nps.gov/articles/abandoned-shipwreck-act-guidelines.htm#:~:text=Under%20the%20Act%2C%20the%20U.S.,a%20State's%20submerged%20lands%20and.

### Nelson, Nels C.

1909 Shellmounds of the San Francisco Bay Region. In *University of California Publications*American Archaeology and Ethnology, Vol.7, No.4, pp. 309–356. University of California Press, Berkeley, California.

### Pearson, Charles E., and Thomas Birchette

- 1995 Historical Assessment and Magnetometer and Terrestrial Surveys of the Gunboat USS Eastport and Steamboat Edward F. Dix, Red River Waterway, Grant Parish, Louisiana. Coastal Environments, Inc., Baton Rouge, Louisiana. Submitted to the USACE, Vicksburg District.
- 1999 The History and Archaeology of Two Civil War Steamboats: The Ironclad Gunboat USS Eastport and The Steamer Ed. F. Dix. Coastal Environments, Inc., Baton Rouge, Louisiana. Submitted to the U.S. Army Corps of Engineers, Vicksburg District.

### Pearson, Charles E., and Kay G. Hudson

1990 Magnetometer Survey of the Matagorda Ship Channel: Matagorda Peninsula to Point Comfort, Calhoun and Matagorda Counties, Texas. Submitted to the U.S. Army Corps of Engineers, Galveston District by Coastal Environments, Inc., Baton Rouge, Louisiana.

### Pearson, Charles E., and Allen R. Saltus, Jr.

1990 Cultural Resources Investigation at Island 86, Mississippi River, Arkansas-Mississippi.
Coastal Environments, Inc., Baton Rouge, Louisiana. Submitted to the U.S. Army Corps of Engineers, Vicksburg District.

1993 Underwater Archaeology on the Ouachita River, Arkansas: The Search for the Chieftain, Haydee, and Homer. Coastal Environments, Inc., Baton Rouge, Louisiana. Prepared for the U.S. Army Corps of Engineers, Vicksburg District.

Pearson, Charles E., Stephen R. James, Jr., Kay G. Hudson, and James Duff

1993 Underwater Archaeology Along the Lower Navidad and Lavaca Rivers, Jackson County, Texas. Coastal Environments, Inc., Baton Rouge, Louisiana. Submitted to the U.S. Army Corps of Engineers, Galveston District.

Pearson, Charles E., Bryan L. Guevin, and Allen R. Saltus, Jr.

1991 Remote-Sensing Survey of the Lower Pearl and West Pearl Rivers, Louisiana and Mississippi. Coastal Environments, Inc., Baton Rouge, Louisiana. Prepared for the U.S. Army Corps of Engineers, Vicksburg District.

Pearson, Charles E., and Joseph J. Simmons III

1995 Underwater Archaeology of the Wreck of the Steamship Mary (41NU252) and Assessment of Seven Anomalies, Corpus Christi Entrance Channel, Nueces County, Texas. Submitted to U.S. Army Corps of Engineers, Galveston District by Coastal Environments, Inc., Baton Rouge, Louisiana.

### Perez, Cris

1982 Grants of Land in California Made by Spanish or Mexican Authorities. Prepared by Staff of the State Lands Commission. Report on file at California State University, Monterey Bay, Digital Commons. Monterey, California.

### Ragir, Sonia

1972 The Early Horizon in Central California Prehistory. In Contributions of the University of California Archaeological Research Facility. University of California Department of Anthropology Berkeley, Berkeley, California.

Rogers, Robert, Steven D. Hoyt, Clell L. Bond, Leonard Voellinger, and Stephen R. James, Jr.
1990 Cultural Resources Investigations, Virginia Point, Galveston County, Texas. Espey,
Huston and Associates, Inc., Austin, Texas. Submitted to the U.S. Army Corps of
Engineers, Galveston District.

### Sacramento County

2017 Sacramento County General Plan Conservation Element. As amended September 26, 2017. https://planning.saccounty.gov/LandUseRegulationDocuments/Documents/General-Plan/Conservation%20Element%20-%20Amended%2009-26-17.pdf.

### Sacramento River News (Rio Vista, California)

1894 Advertisement for "Steamer Belvedere." November 23,1894. Rio Vista, California.

1895 New River Steamer. March 22, 1895. Rio Vista, California.

### Schenck, W. E. and E. J. Dawson

1929 Archaeology of the Northern San Joaquin Valley, University of California Press. Berkeley, California.

### Schell, Hal

Hal Schell's Guide to Cruising California's Delta: The Delta Dawdler's Dream Tour of this Fabulous 1,000 Mile Waterway. Schell Books, Stockton, California.

### Solano County

Solano County General Plan. Solano County Board of Supervisors. As amended August 5, 2008. https://www.solanocounty.com/depts/rm/planning/general\_plan.asp.

### Stevenson, I.R., Chloe McCann, and P.B. Runciman

2002 An attenuation-based sediment classification technique using Chirp sub-bottom profiler data and laboratory acoustic analysis. *Marine Geophysical Research* 23(4):277–298.

### Stright, Melanie J.

1990 Archaeological Sites on the North American Continental Shelf. In *Geological Society of America Centennial Special Volume* 4, pp. 439–465, Boulder, Colorado

### Supreme Court of California

- 1882 *Upham v. Hosking, 62 Cal. 250.* Prepared by the Supreme Court of California. On file digitally, https://casetext.com/case/upham-v-hosking.
- 1904 Walsh v. Abbott, 145 Cal. 285, 78 P. 715. Prepared by the Supreme Court of California. On file digitally, https://casetext.com/case/walsh-v-abbott.

### Thompson, John

- 1957 The Settlement Geography of the Sacramento-San Joaquin Delta, California. Ph.D. dissertation, Stanford University.
- 1980 From Waterways to Roadways in the Sacramento Delta. *California History*, 59(2):144–169.

### Trimble, Inc. North America

2019 Applanix POS MV Oceanmaster Datasheet. Trimble, Inc. North America, Houston, Texas.

### U.S. District Court (USDC)

1857 Case No.86 Northern District, Los Ulpinos Grant, John Bidwell. Transcripts of the Proceedings in Case No.319, John Bidwell Claimant vs. The United States, Defendant, For the Place Named "Los Ulpinos." Prepared by the United States District Court of Northern California. Transcript on file digitally, https://digicoll.lib.berkeley.edu/record/265448? In=en.

### U.S. Geological Survey (USGS)

- 1978 Antioch, California, 7.5-minute topographic quadrangle map, scale 1:62,500.
- 1981 Honker Bay, California, 7.5-minute topographic quadrangle map, scale 1:62,500.
- 1979 Antioch North, California, 7.5-minute topographic quadrangle map, scale 1:62,500.
- 2018 Honker Bay, California, 7.5-minute topographic quadrangle map, scale 1:62,500.

### Waters, Michael R.

1992 Principles of Geoarchaeology. University of Arizona Press, Tucson.

### Watts, Gordon P., Jr.

2000 Phase I Archaeological Remote Survey of the Virginia Beach and Fort Story Hurricane Protection Borrow Areas, Virginia. Prepared for the U.S. Army Corps of Engineers, Wilmington District by Tidewater Atlantic Research, Washington, North Carolina.

### Wiberg, Randy

- 2010 Archaeological Investigations at CA-CCO-18/548: Final Report for the Vineyards at Marsh Creek Project, Contra Costa County, California. Holman & Associates, Archaeological Consultants.
- 2011 Magee Ranch Archaeological Survey and Subsurface Testing Report, Contra Costa County, California. Holman and Associates, Archaeological Consultants.

### Wilson, William J., and P.W. Gates

2021 Phase I Cultural Resources Assessment of the 2021 Lower New York Bay Lateral Survey Program, Raritan Bay and Lower New York Bay New Jersey and New York. Panamerican Consultants, Inc., Memphis, Tennessee, under subcontract to WSP USA, Inc., Buffalo, New York. Submitted to Williams Partners LP, Houston, Texas.

### Wilson, William J., Stephen R. James, and Erica K. Gifford

2019 Archaeological Diver Investigations of Remote Sensing Anomalies in the St. Augustine Flood Shoal and Intracoastal Waterway Project, St. Johns County, Florida. Prepared for the U.S. Army Corps of Engineers, Jacksonville District by Panamerican Consultants, Inc., Memphis, Tennessee.

### Appendix A. Qualifications



This attests that

# Nicholas George

the National Society of Professional Surveyors has met the requirements established by Hydrographer Certification Board for certification as

## Hydrographer

by Authority of the Board of Directors

Chairman, Certification Board

letish duma Executive Director

Certificate Number \_\_341\_\_\_

Date\_3/5/2021



### Stephen R. James, M.A., RPA, Director of Maritime Division/Maritime Archaeologist

### **Experience Profile**

Director of PaleoWest's Maritime Division, Mr. James has over 30-years-experience as a maritime archaeologist. Mr. James has directed and managed submerged cultural resource projects of all types throughout the United States, the Caribbean, South Pacific, and Southeast Asia. He has acted as Project Manager and/or Principal Investigator on IDIQs for the U.S. Army Corps of Engineers Minneapolis/St. Paul, Detroit, Sacramento, Jacksonville, New York, Mobile, Philadelphia, Savannah, and Wilmington Districts. His experience includes extensive experience for other federal and state agencies, corporations, and non-profit organizations. Mr. James is thoroughly familiar with federal preservation laws and regulations, preservation compliance, site evaluation, the National Register process, and formulation and implementation of predictive modeling. He is responsible for developing Paleowest's remote sensing survey capabilities which include satellite positioning and navigation systems, terrestrial and marine magnetometers, sidescan sonar systems and subbottom profilers. He is also responsible for developing Paleowest's diving capabilities including development of Dive Operations and Safety Plans, all geared predominantly to Surface Supplied systems for their inherent safety factor. Certified by the Register of Professional Archaeologists since 1985, Mr. James is a graduate of the U.S. Army Corps of Engineers Dive Supervisor and Safety Course, Florida Keys Community College, Key West.

### **Representative Commonwealth Projects**

### 2023 (Selected)

Project Manager, Oregon Inlet Submerged Cultural Resources Survey, Dare County, North Carolina. Conducted for the USACE Jacksonville District.

Project Manager, Phase II NRHP Assessment and Archival Research of USSB WWI Emergency Fleet Hulks, Stony Point Cove, Delaware Bay, New Jersey. Conducted under subcontract to AKRF, New York.

Project Manager, Phase I Stony Point Submerged Cultural Resources Survey, Stony Point Cove, Delaware Bay, New Jersey. Conducted under subcontract to AKRF, New York.

Project Manager, Conservation and Archival Research on Revolutionary War Cannon Recovered from the Savannah River, Savannah, Georgia. USACE Jacksonville District.

### 2022 (Selected)

Project Manager, Submerged Cultural Resources Survey, Woodtick Peninsula, Lake Erie, Michigan – USACE Detroit and St. Louis Districts

Project Manager, Savannah Harbor Expansion Project Archaeological Monitoring, Savannah, Georgia, – Weeks Marine, Inc., and USACE Jacksonville District

Project Manager, Cultural Resources Survey for the Charleston to Port Royal channel Realignment, Beaufort and Charleston Counties, South Carolina. Underwater Remote Sensing Survey of the Atlantic Intracoastal Waterway conducted for the U.S. Army Corps of Engineers, Charleston District

### 2021 (Selected)

Project Manager/Principal Investigator, Fire Island to Montauk Diver Identification and GIS, Long Island, New York, 2021 – USACE New York District.

Project Manager/Principal Investigator, Submerged Cultural Resources Data Recovery of Site 38JA1178 and Artifact Recovery of Site 9CH1552, Savannah Harbor Expansion Project, Savannah, Georgia. Conducted for the USACE, Jacksonville District.

Project Manager/Principal Investigator, Submerged Cultural Resources Survey and Diver Identification, Savannah Harbor Expansion Project, Savannah, Georgia. Conducted for the USACE, Jacksonville District.



### **Education:**

M.A., Anthropology, Institute of Nautical Archaeology, Texas A&M, 1985

B.A., Anthropology, Memphis State University, 1979

### **Professional Affiliations:**

Society for Historical Archaeology

Register of Professional Archaeologists



### Stephen R. James, M.A., RPA, Director of Maritime Division/Maritime Archaeologist

Project Manager/Principal Investigator, Miami-Dade Submerged Cultural Resources Management Survey, Miami, Florida, 2021 – USACE Jacksonville District

### 2020 (Selected)

Project Manager, Submerged Cultural Resources Survey and Diver Investigation of Targets, Intracoastal Waterway Near the Jupiter Inlet, Palm Beach and Martin Counties, Florida. Conducted for the USACE, Jacksonville District.

Project Manager, American Intracoastal Waterway (AIWW), Nassau Sound (Sawpit Creek Vicinity), and Fernandina Harbor (Amelia River), Submerged Cultural Resources Survey, Nassau and Duval Counties, Florida. Conducted for the USACE, Jacksonville District.

Project Manager, Savannah River Below Augusta Training Wall Submerged Cultural Resources Survey and Diver Evaluations, Richmond County, Georgia and Aiken County, South Carolina. Conducted for the USACE, Jacksonville District.

Project Manager, Phase I Archaeological Marine Survey of 3670 Survey Line Miles for Proposed Artificial Reef Zones in Mobile Bay and Gulf of Mexico Offshore Alabama. Conducted for the Alabama Department of Conservation and Natural Resources.

Project Manager/Principal Investigator, Cultural Resources Remote Sensing Survey of the Gravesend Anchorage Area for the New York and New Jersey Harbor Anchorage Study, Kings County, New York. Conducted for the USACE, New York District.

### 2019 (Selected)

Project Manager, Davis Shores Shoal Investigations Associated with the Archaeological Diver Identification of Remote Sensing Anomalies in the St. Augustine Flood Shoal and Intercostal Waterway Project, St. Johns County, Florida. Conducted for the USACE, Jacksonville District.

Project Manager/Principal Investigator, Submerged Cultural Resources Survey and Terrestrial Archaeological and Magnetometer Survey for the Mid-Reach Sand Stockpile, Brevard County, Florida. USACE, Jacksonville District.

Project Manager/Principal Investigator, Submerged Cultural Resources Survey of St. Lucie River/Okeechobee Waterway Project, Martin County, Florida. USACE, Jacksonville District.

Project Manager/Principal Investigator, Anclote River Federal Navigation Project Submerged Cultural Resources Survey and Terrestrial Phase I Survey Pasco and Pinellas Counties, Florida. USACE, Jacksonville District.

### 2018 (Selected)

Project Manager/Principal Investigator, Canaveral Harbor Sand Bypass, Submerged Cultural Resources Survey and Archaeological Reconnaissance Survey, Brevard County, Florida. USACE, Jacksonville District.

Project Manager/Principal Investigator, Gulf Inland Waterway Federal Navigation Project Sarasota County, Florida Submerged And Terrestrial Cultural Resources Survey. USACE, Jacksonville District.

Project Manager/Principal Investigator, Submerged Cultural Resources Assessment Survey of Approximately 3,000 Line Miles for Priority Water Bottoms in the Mobile Bay Area, Mobile & Baldwin Counties, Alabama. Mobile Bay National Estuary Program.

### 2017 (Selected)

Project Manager/Principal Investigator, Phase III Data Recovery 2017 Field Season of the CSS Georgia. USACE, Savannah District under subcontract to DCA/GEC Joint Venture, LLC.

### 2016 (Selected)

Project Manager/Principal Investigator, Archaeological Data Recovery of the *Adriatic*, Sturgeon Bay, Wisconsin. Fincantieri Bay Shipbuilding Company.

Project Manager/Principal Investigator, Underwater Archaeological Survey and Diver Assessment/Evaluation for Future Extension Concept/2014B Revised Bridge Location, Bonner Bridge Project in Currituck and Dare Counties, North Carolina. STIP No. B-2500. Conducted for the NC Department of Transportation under subcontract to Parsons Brinkerhoff, Inc.



### RIKKI OETERS MILEWSKI, M.A., RPA

### Associate Maritime Archaeologist

### **EDUCATION**

M.A., University of West Florida, 2023 B.A., East Carolina University, 2017 YEARS OF PROFESSIONAL EXPERIENCE

3

### YEARS WITH FIRM

3

### **REGISTRATIONS / CERTIFICATIONS**

Register of Professional Archaeologists #5684

Surface-supplied Diving Supervisor (2023)

Surface-supplied Diver (2022)

Red Cross CPR & First Aid (bi-annual)

### PROFESSIONAL AFFILIATIONS

Society for Historical Archaeology

Rikki Oeters Milewski is a maritime archaeologist with over three years of experience in cultural resources management (CRM). She currently serves as an associate archaeologist for Chronicle Heritage's Maritime Division.

Rikki joined Chronicle Heritage in 2021 and completed her M.A. in Maritime Archaeology from the University of West Florida in 2023. She has participated in remote sensing/geophysical and diving investigations for Chronicle Heritage. She has served as GIS specialist, surface-supplied diver, surface-supplied diving supervisor, surface-supplied diver tender, remote sensing survey technician, and archival and historical background researcher on cultural resources investigations conducted for the USACE, Jacksonville, Mobile, New York, Philadelphia, Wilmington, and Savannah districts, the U.S. EPA Great Lakes National Program Office, and various other federal agencies, and private clients. She is skilled in the processing of collected data, the utilization of Sonar WizMap® side-scan mosaicking and subbottom profiler analysis software, the use of MagPick magnetometer processing software, various forms of GIS software platforms, archival and historical background research, and report authoring for submerged remote-sensing surveys and archaeological diver investigations.

### SELECT RECENT PROJECT EXPERIENCE

**Propel Energy Project, New York.** Associate Archaeologist (2024). A comprehensive remote-sensing survey was conducted to determine the presence of cultural material. Mrs. Milewski conducted archival research, processed and analyzed geophysical data, acted as GIS specialist, and authored the report. Client: WSP USA, Inc.

Intensive Cultural Resource Remote Sensing Survey for the Flagler County, FL Beach and Dune Restoration Project, Flagler County, FL. Associate Archaeologist (2024). A comprehensive remotesensing survey was conducted to determine the presence of cultural material. Mrs. Milewski conducted archival research, assisted with processing and analyzing geophysical data, acted as GIS specialist, and co-authored the report. Client: Olsen and Associates, Inc.

**Submerged Cultural Resources Assessment Survey Borrells Creek Bridge Replacement.** Associate Archaeologist (2024). A magnetometer survey with subsequent site plan recording of a previously identified archaeological site (9CM589) was conducted to determine the extents and exposure of the site. Mrs. Milewski processed and analyzed geophysical data, acted as GIS specialist, and authored the report. Client: Georgia Department of Transportation (GDOT)

Submerged Cultural Resources Assessment Survey Stillwell Road, Effingham County, GA. Associate Archaeologist (2024). A side-scan sonar survey was conducted to determine the presence of cultural material. Mrs. Milewski processed and analyzed geophysical data, acted as GIS specialist, and authored the report. Client: Atlas Technical Consultants.



**NEOM Heritage Project Phase 2, Gulf of Aqaba, Kingdom of Saudi Arabia.** Associate Archaeologist (2024). A comprehensive remote-sensing survey with subsequent diver investigations and diver survey was conducted to determine the presence of cultural material. Mrs. Milewski processed and analyzed geophysical data, acted as GIS specialist, served as an archaeological diver, and coauthored the report. Client: NEOM Heritage

Insignia Collinsville Substation, Submerged Cultural Resources Survey, Sacramento, CA. Associate Archaeologist (2023). A comprehensive remote-sensing survey was conducted to determine the presence of cultural resources. Mrs. Milewski conducted archival and historic background research, processed and analyzed geophysical data, acted as GIS specialist, and authored the report. Client: Collinsville Substation Energy

Brunswick Harbor Modifications, Submerged Cultural Resources Survey and Diver Identification, Glynn County, GA. Associate Archaeologist (2023). A comprehensive remote-sensing survey and a remote-sensing refinement survey with subsequent diver investigations was conducted to determine the cultural significance of identified targets deemed potentially significant. Rikki conducted archival and historic background research, acted as GIS specialist, and co-authored the report. Client: USACE, Jacksonville District

**Gulf Intracoastal Waterway, Longboat Pass Placement, Submerged Cultural Resources Survey and Archaeological Diver Investigations, Manatee County, FL.** Associate Archaeologist (2023). A comprehensive remote-sensing survey of a nearshore placement area was conducted to assess the presence of submerged cultural resources. A remote-sensing refinement survey with subsequent diver investigations was conducted to determine the cultural significance of previously identified targets deemed potentially significant. Rikki conducted archival and historic background research, served as field director and assistant dive supervisor, recorded diver investigation data, acted as GIS specialist, and co-authored the report. Client: USACE, Jacksonville District

Report on the Monitoring of Four Known Shipwrecks in Connection with the Sea Bright to Manasquan Inlet, Coastal Storm Risk Management and Erosion Control Project, Monmouth County, NJ. Associate Archaeologist (2023). A desktop monitoring report was conducted to synthesize previous investigations of four known shipwrecks. Rikki assisted with the completion of the report. Client: USACE, New York District

St. Nicholas Cemetery Geophysical Survey Report, Patuxent River Naval Air Station, St. Mary's County, MD. Associate Archaeologist (2023). A geophysical survey was conducted to determine the location of gravestones and marked and unmarked graves. Rikki assisted with the completion of the report. Client: Marstel-Day, LLC

**NEOM Submerged Cultural Resources Assessment Survey, Saudi Arabia.** Associate Archaeologist (2023). A comprehensive remote-sensing survey was conducted to assess the presence of submerged cultural resources. Rikki assisted with the completion of the report. Client: NEOM Heritage

Cultural Resources Remote Sensing Survey of the Proposed Stony Point Dredge Material Containment Dike, Stony Point Cove, Delaware River, Salem, NJ. Associate Archaeologist (2023). A comprehensive remote-sensing survey was conducted to determine the presence of submerged cultural resources and to record the Emergency Fleet Corporation Ship Breakwater. Rikki conducted archival and historic background research, acted as GIS specialist, and co-authored the report. Client: AKRF, Inc.



Submerged Cultural Resources Assessment Survey, Lakes Joel, Myrtle, and Preston, Osceola County, FL. Staff Archaeologist (2023). A comprehensive remote-sensing survey was conducted to assess the presence of submerged cultural resources. Rikki processed remote sensing data and coauthored the report. Client: Terracon Consultants, Inc.

Oregon Inlet Submerged Cultural Resources Survey, Dare County, NC. Staff Archaeologist (2023). A comprehensive remote-sensing survey was conducted to determine the presence of submerged cultural resources. Rikki conducted archival and historic background research, acted as GIS specialist, and co-authored the report. Client: USACE, Wilmington District

Submerged Cultural Resources Remote Sensing Survey and Diver Investigation of Proposed Peacock Bridge Replacement, Jackson County, FL. Staff Archaeologist (2023). A comprehensive remote-sensing survey with subsequent diver investigations was conducted to determine the presence of submerged cultural resources. Rikki acted as remote sensing technician, archaeological diver, GIS specialist, and authored the report. Client: Florida Department of Transportation

Submerged Archaeological Diver Investigations, Ponce de Leon Inlet, Volusia County, FL. Staff Archaeologist (2023). A remote-sensing refinement survey with subsequent diver investigations was conducted to determine the cultural significance of previously identified targets deemed potentially significant. Rikki conducted archival and historic background research, served as a member of the dive team as field director and diver, recorded diver investigation data, acted as GIS specialist, and co-authored the report. Client: USACE, Jacksonville District

Supplemental Geotechnical Investigation Dredged Material Management Facility, Milwaukee, MI. Staff Archaeologist (2023). A comprehensive remote-sensing survey with subsequent diver investigations was conducted to assess known submerged cultural resources. Rikki conducted archival and historic background research, acted as GIS specialist, and authored the report. Client: Milwaukee Metropolitan Sewerage District

Swan Creek Feasibility Study and Cultural Resources Survey, Lucas County, OH. Staff Archaeologist (2023). A remote sensing survey was conducted to assess the presence of submerged cultural resources. Rikki conducted archival and historic background research, acted as GIS specialist, and authored the report. Client: U.S. EPA, Great Lakes National Program Office

Lower Maumee River Cultural Resources Survey, Lucas County, OH. Staff Archaeologist (2023). A remote sensing survey was conducted to assess the presence of submerged cultural resources. Mrs. Milewski conducted archival and historic background research, acted as GIS specialist, and authored the report. Client: U.S. EPA, Great Lakes National Program Office

Submerged Cultural Resources Remote Sensing Survey Mobile River Barge Fleeting Area, Mobile County, AL. Staff Archaeologist (2022). A remote sensing survey was conducted to assess the presence of submerged cultural resources. Mrs. Milewski conducted archival and historic background research, acted as remote sensing survey technician and GIS specialist, and authored the report. Client: Parker Towing Company, Inc. and Thompson Engineering, Inc.

Remote Sensing Survey of CPF Area 7, 11, and 12, Contract 2 and Contract 3 Beachfill Area and Borrow Area 8D and 5D in Connections with the Fire Island to Montauk Point Coastal Storm Risk Management Project, Long Island, NY. Staff Archaeologist (2022). A remote sensing survey was conducted to assess the presence of submerged and terrestrial cultural resources. Mrs. Milewski conducted archival and historical background research, acted as GIS specialist, and assisted in the completion of the report. Client: USACE, New York District



**Underwater Remote Sensing Survey: Artificial Reef Program – Site Evaluations, Hernando Co., FL.** Staff Archaeologist (2022). Upon the proposal of potential artificial reef sites, a remote sensing survey was conducted to assess the presence of submerged cultural resources. Mrs. Milewski conducted archival and historic background research, acted as GIS specialist, and assisted with the completion of the report. Client: Morgan & Ecklund, Inc. and Water & Air Research, Inc.

Submerged Cultural Resources Survey of the Tampa Bay Channel for the Tampa Bay Navigational Improvement Study, Tamp, FL. Staff Archaeologist (2022). A remote sensing survey was conducted to assess the presence of submerged cultural resources. Mrs. Milewski conducted archival and background research, acted as GIS specialist, and assisted with the completion of the report. Client: USACE, Jacksonville District

Bay Raccourci Marsh Creation and Ridge Restoration Terrebonne Parish Cultural Resource Investigations, Houma, LA. Staff Archaeologist (2022). A remote sensing survey was conducted to assess the presence of submerged cultural resources. Mrs. Milewski acted as remote sensing survey technician. Client: Coastal Protection and Restoration Authority

Geographic Information System Mapping Product in Connection with the Fire Island to Montauk Point Coastal Storm Risk Management Project, Long Island, NY. Staff Archaeologist (2022). A cultural resource inventory and mapping product was created using data from previous investigations. Mrs. Milewski assisted with the compilation of data, historic background research, and the creation of GIS products. Client: USACE, New York District

Submerged Cultural Resources Data Recovery of Site 38JA1178 and Artifact Recovery of Site 9CH1552 Savannah Harbor Expansion Project, Savanah, GA. Staff Archaeologist (2021). In preparation for the expansion of the Savannah Harbor, artifacts were recovered and submerged cultural resources were recorded. Mrs. Milewski acted as surface-supplied diving tender. Client: USACE, Savannah District

Submerged Cultural Resource Diver Identification and Literature Review in Connection with the Fire Island to Montauk Point Coastal Storm Risk Management Project, Atlantic Coast of Long Island, NY. Staff Archaeologist (2021). A remote sensing refinement survey and diving assessment was conducted to investigate targets identified in previous investigations. Mrs. Milewski acted as remote sensing survey technician and surface-supplied diving tender. Client: USACE, New York District

Brigantine and Townsend Inlet to Hereford Nourishment Projects Expansion of Brigantine Inlet and Townsends Inlet Borrow Areas Submerged Cultural Resources Diver Identification and Evaluation, NJ. Staff Archaeologist (2021). A remote sensing refinement survey and diving assessment was conducted to investigate targets identified in previous investigations. Mrs. Milewski acted as remote sensing survey technician and surface-supplied diving tender. Client: USACE, Philadelphia District



### MATTHEW LOWE, M.A., RPA

### Staff Archaeologist

### **EDUCATION**

M.A., Maritime Studies, East Carolina University, Greenville, NC, 2022

B.A., History, University of Alabama, Tuscaloosa, AL, 2019

### YEARS OF PROFESSIONAL EXPERIENCE

3

### YEARS WITH FIRM

2

### REGISTRATIONS / CERTIFICATIONS

Register of Professional Archaeologists, #5297 Surface Supplied Diving CPR/First Aid

### PROFESSIONAL AFFILIATIONS

Society for Historical Archaeology

Since joining Chronicle Heritage in 2022 Matthew has served as a surface supplied diver for investigations conducted for the USCAE Jacksonville and Philadelphia Districts. He functioned as lead archaeological monitor for beach renourishment efforts at Egmont Key for the USACE Tampa district. His terrestrial work with Chronicle Heritage involved working on a Phase III excavation in Miami, Florida. He is also skilled in the processing of remote sensing data using Magpick and QGIS software. Matthew has previous experience as a Maritime Archaeologist with East Carolina University conducting remote sensing and an underwater investigation on sites in eastern North Carolina. During his time at ECU Matthew was well practiced in the use and operation of Hypack and SonarWiz remote sensing software. Matthew has previous experience with terrestrial Cultural Resource Management work as a Phase I field technician in the Southeastern United States.

### SELECT RECENT PROJECT EXPERIENCE

**Propel Energy Submerged Cultural Assessment, Long Island Sound, NY.** Associate Maritime Archaeologist (2024). A cultural resource assessment survey was carried out using side-scan sonar, magnetometer, and subbottom profiler on a cable placement area within Long Island Sound. Matthew acted as an Associate Maritime Archaeologist. He assisted in writing the report, most notably the methodology chapter. Client: WSP USA, Inc.

Hatteras Inlet Submerged Cultural Assessment, Hatteras Inlet, NC. Lead Geophysical Surveyor (2024). A cultural resource assessment survey was carried out using side-scan sonar, magnetometer, and subbottom profiler on multiple dredge sites within the Hatteras Inlet. Matthew acted as lead geophysical surveyor and directed the nearshore survey. He assisted in processing acquired side-scan, subbottom, and magnetometer data. Matthew also contributed to writing the historic background, methodology, Investigative findings, and conclusion report chapters. Client: USACE Wilmington District.

Flagler Beach Submerged Cultural Assessment, FL. Field Director/Remote Sensing Specialist (2024). A cultural resource assessment survey was carried out using side-scan sonar, magnetometer, and subbottom profiler on a nearshore placement area off Flagler Beach. Matthew acted as lead geophysical surveyor and directed the nearshore survey. He assisted in processing acquired side-scan, subbottom, and magnetometer data. Matthew also contributed to writing the historic background, methodology, Investigative findings, and conclusion report chapters. Client: Olsen and Associates.

**NEOM Maritime Phase II, Kingdom of Saudi Arabia.** Geophysical Technician/Archaeological Diver (2023-2024). An intensive cultural resource assessment was carried out using side-scan sonar, magnetometer, subbottom profiler, and archaeological diver surveys in the Gulf of Aqaba to ascertain the location of potentially significant cultural material for the NEOM project. Matthew



acted as a geophysical surveyor and an archaeological diver. Client: NEOM, Kingdom of Saudi Arabia.

Tampa Bay Harbor expansion Egmont Key Monitor, Tampa Bay, FL. Lead Archaeological Monitor (2023). Sand from the Tampa Bay maintenance dredging operation was used as beneficial renourishment for the beach and the cultural resources in the area associated with Fort Dade on Egmont Key. Matthew monitored the cultural resources on the beach throughout the dredging operations and ensured they were minimally impacted during the project. He interfaced with the client regarding previously mapped cultural materials. Client: Great Lakes Dock and Dredge Company.

**Longboat Pass Diver Investigations, Longboat Key, FL.** Archaeological Diver (2023). Cultural resource diving operations were carried out in the intercoastal waterway adjacent to Longboat Key prior to dredging operations. Matthew acted as a surface supplied diver on two distinct targets within the project area. He was also a standby diver and supported fieldwork operations. Client: USACE Jacksonville District.

Brunswick Harbor Submerged Resource Assessment, Brunswick River, GA. Geophysical Technician (2023). A submerged cultural resource assessment survey was carried out using sidescan sonar, magnetometer, and subbottom profiler on a nearshore dredge placement area adjacent to Brunswick Harbor and St. Simons Island within the Brunswick River. A diving target refinement survey was concurrently conducted on multiple targets selected for future cultural resource diver investigations. Matthew acted as geophysical technician and online surveyor for both the cultural resource assessment survey and refinement surveys. Client: USACE Jacksonville District.

Longboat Key Submerged Cultural Resource Assessment, Longboat Key, FL. Lead Geophysical Surveyor (2023). A cultural resource assessment survey was carried out using side-scan sonar, magnetometer, and subbottom profiler on a nearshore dredge placement area adjacent to Longboat Key. A diving target refinement survey was concurrently conducted on multiple targets selected for future cultural resource diver investigations. Matthew acted as lead geophysical surveyor and directed both the nearshore and refinement surveys. Client: USACE Jacksonville District.

Stony Point Submerged Cultural Resource Assessment, Stony Point, DE. Geophysical Technician (2023). A cultural resource assessment survey was carried out using side-scan sonar, magnetometer, and subbottom profiler on a breakwater consisting of Emergency Fleet Corporation (EFC) vessels. Matthew acted as geophysical technician and online surveyor for the duration of the project. Client: AKRF, Inc.

NEOM Maritime Phase I, NEOM, Kingdom of Saudi Arabia. Geophysical Technician and Archaeological Diver (2023). An intensive cultural resource assessment was carried out using sidescan sonar, magnetometer, subbottom profiler, and archaeological diver surveys in the northern Red Sea to ascertain the location of potentially significant cultural material for the NEOM project. Matthew acted as a geophysical surveyor, archaeological diver, and geophysical data analyst. Matthew also coordinated with hydrographic surveyor contractors to ensure the best possible quality of contractual data. Client: NEOM, Kingdom of Saudi Arabia.

Tampa Bay Harbor expansion Egmont Key Monitor, Tampa Bay, FL. Lead Archaeological Monitor (2022). Sand from the Tampa Bay maintenance dredging operation was used as beneficial renourishment for the beach and the cultural resources in the area associated with Fort Dade on Egmont Key. Matthew monitored the cultural resources on the beach throughout the dredging operations and ensured they were minimally impacted during the project. He interfaced with the



client regarding previously mapped cultural materials and is the author of the final archaeological monitoring report. Client: Great Lakes Dock and Dredge Company.

**Fire Island to Montauk Diver Investigation, Long Island, NY.** Staff Maritime Archeologist (2022). Cultural resource diving operations were carried out at the fire island inlet on submerged cultural resources in preparation for dredging operations. Matthew acted as a surface supplied diver on three distinct targets within the project area. He was also a standby diver and supported fieldwork operations. Client: USACE Philadelphia and Jacksonville Districts.

Tampa Bay Harbor Expansion Project, Tampa Bay, FL. Staff Maritime Archaeologist (2022). A cultural resource assessment survey using sidescan sonar, magnetometer, and sub-bottom profiler was carried out prior to maintenance dredging operations of the Tampa channel. Matthew analyzed and interpreted magnetometer data which was then used to create a GIS contour map of the anomalies. He contributed to writing the introduction, investigate findings and conclusion chapters of the report. Client: USACE Tampa District

Odom-Cooper-Flye Farm Archaeological Data Recovery of Six Sites, NC. Lab Technician (2022). Matthew organized and labelled cultural resources from the project into appropriate categories for proper storage.

(ECU) Visualizing Port History: An Historical and Archaeological Reconstruction of Washington, North Carolina's Historic Waterfront, Thesis, NC. Maritime Archaeological student (2019-2022). Matthew studied Maritime Archaeology at East Carolina University and completed his thesis in the spring of 2022. He used historic maps and economic data combined with Rhino 7 3D modelling software to create a diachronic analysis of the economic boom and bust of a regional American port at the turn of the 20th century. Graduated in May 2022.

(NOAA) Monitor National Marine Sanctuary Expansion Survey, NC. Maritime Archaeological student/remote sensing technician (2022). The NOAA Monitor National Marine Sanctuary underwent cultural heritage surveys for a proposed expansion in 2021. Matthew assisted in deploying, maintenance, and observation of sidescan sonar data for 12 wrecks in the proposed expansion area. He was a volunteer for NOAA during the survey.

(ECU) Copper Wreck Report of Investigations NCDCNR Permit # 660 PMR-TRR 2020, NC. Maritime Archaeological student (2020). The Copper Wreck, an early 20th century wreck at the historic port of Washington, NC was investigated as part of East Carolina University's 2020 fieldschool. Matthew took part in an underwater investigation of the Copper Wreck involving the measuring and detailed mapping of the site. He contributed to the writing of the final report.

# Appendix C. SCRAS Research Design

## RESEARCH PLAN

## SUBMERGED CULTURAL RESOURCES REMOTE SENSING SURVEY INSIGNIA COLLINSVILLE SUBSTATION CRA SACRAMENTO RIVER CONTRA COSTA, SOLANO AND SACRAMENTO COUNTIES, CALIFORNIA

### Introduction

PaleoWest's Maritime Division (PaleoWest) presents the following Research Plan to Insignia Environmental (Insignia) to conduct an intensive submerged cultural resources remote sensing survey for a proposed to support a new electrical substation and 230 kV transmission line in the Sacramento River Delta region, roughly midway between Sacramento and San Francisco. The project would require an approximately 4-mile-long stretch of submerged transmission cable under the Sacramento River (Figure 1). Specifically, the area of survey is a 2,000-foot wide 4-mile-long corridor that extends from Pittsburgh, California up the Sacramento River to landfall near Collinsville. Submitted to Insignia to fulfill the Permitee's obligations under Section 106 of the National Historic Preservation Act of 1966, as amended through 1992 (36 CFR Part 800, Protection of Historic Properties); and the Abandoned Shipwreck Act of 1987 (Abandoned Shipwreck Act Guidelines, National Park Service, Federal Register, Vol. 55, No. 3, December 4, 1990 pages 50116-50145), as well as to satisfy the requirements of the State of California, professional services to be provided include the following:

- Coordination with the State of California's State/Underwater Archaeologist.
- Archival Research, Literature review.
- Intensive magnetometer, sidescan sonar and subbottom profiler survey.
- Analysis of remote sensing data.
- Preparation and Submission of Report of Findings chapters.



Figure 1. Proposed survey corridor in blue.

## PaleoWest's Submerged Cultural Resources Overview:

PaleoWest is well qualified to perform the study as outlined. We are a full-service cultural resources management (CRM) firm with one of the largest professional underwater archaeological staffs in the United States. Comprised of what was the Panamerican Consultants Maritime Division (which was recently purchased by Commonwealth Heritage Group and then subsequently by PaleoWest), our capabilities encompass all levels and types of investigations, and each of our five fully-qualified maritime archaeologists is experienced with every phase of investigation, from archival research, remote sensing survey, data analysis, anomaly testing, data recovery, and fullscale mitigation. With the majority of our projects associated with navigation improvements, island restoration, beach renourishment and storm damage reduction, and flood control, these investigations have been conducted in offshore, coastal, estuarine, and riverine environments throughout the Atlantic, Gulf, and Pacific seaboards of the U.S., the Great Lakes, and the Caribbean, including many in the Sacramento River. This cumulative knowledge of the various submerged environments throughout the United States, and our understanding of and experience with applicable methodological approaches and appropriate technical support, as well as our awareness of the issues, theory, practice, legislation, and laws that guide cultural resource management (i.e., Section 106, Clean Water Act, the Abandoned Shipwreck Act, etc.), ensures our ability to provide succinct submerged cultural resources data for local, state and federal agencies to make informed resource management decisions.

From beach renourishment and storm protection projects on the East Coast, dredge disposal sites and island restoration projects in various bays, borrow investigations offshore the entire eastern seaboard, channel enlargement studies in various harbors (i.e., Mobile, Galveston, Tampa, New York), and flood control/Levee investigations on inland rivers including the Sacramento, PaleoWest (previously Panamerican) has conducted numerous submerged CRM investigations for various local, state and federal agencies including over a dozen U.S. Army Corps of Engineers Districts (i.e., Sacramento, Baltimore, New York, Wilmington, Savannah, New Orleans, Jacksonville, Mobile, Vicksburg, Memphis, Galveston and Tulsa), the Department of Defense

including the U.S. Navy (LANTDV and CHESDIV), the Bureau of Ocean Energy Management (Gulf of Mexico Region), and NOAA, as well as numerous state agencies, and private sector companies.

One of the largest and best equipped in the nation, PaleoWest's maritime archaeological unit has its own in-house remote sensing survey and diving equipment, including state-of-the-art-magnetometers, sidescan sonars, subbottom profilers, DGPS positioning and navigation systems, as well as a fleet of vessels. With experience in all types of site environments including rivers, harbors, bays, ship channels, high-impact surf zone, and offshore sites, we are acutely aware of the varying project area site dynamics. During years of successful examinations of underwater cultural resources, we have developed operating and investigative methods uniquely adapted to site conditions and the demands of cultural resources investigations. Furthermore, our in-house GIS capabilities allow all recorded data to be seemlessly and professionally presented. Our GIS deliverables are compatible with National Park Service and DNR GIS systems, which include georeferenced survey areas with pre and post-plot track lines, labeled magnetic contour maps and sidescan sonar data. Currently PaleoWest utilizes ArcView, HYPACK, or AutoGIS to transfer or digitally capture data into a dual PC and Mac platform. Cartographic and attribute data are fully transferable into Digital Line Graph (DLG) format. PaleoWest utilizes ArcGIS 9.2, PC Surfer, and HYPACK software packages, to perform in-house GIS applications.

PaleoWest has both the experience and the equipment to safely handle all types of remote sensing survey and diving tasks. From small assessments and environments requiring only SCUBA to difficult examinations (i.e., in black water or high-energy zones) requiring surface-supplied air equipment, paramount to any investigation of cultural resources is the question of personal safety. Commonwealth emphasizes the importance of safety in all field endeavors, especially in projects involving boat-handling and diving.

Illustrating PaleoWest's capabilities to perform the study as outlined, and underscoring our experience in the project area and our knowledge of the maritime history and submerged prehistoric issues which factor greatly in the Project Area, PaleoWest personnel have managed, directed, and conducted several surveys and diving investigations upriver from the current proposed project area, including:

- Underwater Investigations For Erosion Inventory Sites, Sacramento River Bank Protection Project, Sacramento, California. Prepared for the US. Army Corps of Engineers, Sacramento District by Panamerican Consultants, Inc., Memphis, Tennessee under contract to North State Resources, California (Lydecker and James 2009).
- Cultural Resources Remote Sensing Survey and Diver Investigation at Selected Target Locations, Sacramento River Bank Protection Project (SRBPP), Sacramento River and Tributaries. Prepared for the US. Army Corps of Engineers, Sacramento District Submitted by Panamerican Consultants, Inc., Memphis, Tennessee under contract to ICF International, Sacramento, California (Lydecker 2010).
- Data Recovery and Mitigation Measures for Adverse Effects to the Clarksburg Ferry (CA-YOL-223H), Sacramento River Bank Protection Project (SRBPP). Prepared for the US. Army Corps of Engineers, Sacramento District by Panamerican Consultants, Inc., Memphis, Tennessee under contract to North State Resources, California (James 2010).

## **Project Personnel**

The remote sensing survey team will consist of two positions: A Remote Sensing Specialist and a Remote Sensing Technician. All of team members are current in Red Cross training for First Aid and Cardio-Pulmonary Resuscitation (CPR), and Emergency Oxygen Administration. Vitae are presented in Appendix I for Key personnel.

Mr. Stephen R. James, Jr. will serve as Project Manager for the duration of this project and will oversee all aspects of the project. Mr. James holds a degree in anthropology from Memphis State University and a master's degree in nautical archaeology from the Institute of Nautical Archaeology, Texas A&M University. RPA (Register of Professional Archaeologists) certified since 1985, and with 25 years of experience in maritime archaeology, Head of Panamerican Consultants, Inc. Maritime Unit for 30 years and now Director of the Maritime Division at PaleoWEst/Commonwealth since the recent purchase of Panamerican, Mr. James has directed and managed submerged cultural resource projects of all types throughout the United States, the Caribbean and Pacific including extensive experience in California. Managing Panamerican's Memphis office since 1991, as well as all underwater projects, Mr. James has been Project Manager as Prime on numerous Corps District IDIQs including multiple Vicksburg and Memphis District IDIQs, the Wilmington District Submerged Cultural Resources IDIQ, the Savannah District IDIQ, as well as, our current Mississippi Valley District IDIQ and Jacksonville District BPA. As subcontractor, he has acted as Project Manager and/or Principal Investigator on IDIOs for the Sacramento, Jacksonville and New York District IDIQs, as well as, Mobile, Philadelphia, Savannah, and Wilmington District IDIQs. His experience includes extensive experience for other Districts including Baltimore, Fort Worth, Galveston, Los Angeles, New Orleans, and Seattle Districts, as well as for other federal and state agencies, corporations, and non-profit organizations. Mr. James is thoroughly familiar with federal preservation laws and regulations, preservation compliance, site evaluation, the National Register process, and formulation and implementation of predictive modeling. He is responsible for developing Panamerican's remote sensing survey capabilities which include satellite positioning and navigation systems, terrestrial and marine magnetometers, sidescan sonar systems and subbottom profilers. He is also responsible for developing Panamerican's diving capabilities including development of Dive Operations and Safety Plans, all geared predominantly to Surface Supplied systems for their inherent safety factor. Certified by the Register of Professional Archaeologists since 1985, Mr. James is a graduate of the U.S. Army Corps of Engineers Dive Supervisor and Safety Course, Florida Keys Community College, Key West.

As stated, Mr. James has extensive project experience in California and has directed or managed Phase I remote sensing surveys, Phase II Diver assessments, and Phase III Data recovery projects, many of them associated with California Gold Rush-Era shipwrecks. They include discovery of and investigation of the *Sterling, La Grange and Niantic*, all in Downtown Sacramento, as well as the remains of several unidentified Gold Rush-Era shipwreck remains. This experience gives him in-depth knowledge on the construction techniques and characteristics, as well as the materials found on these vessel types, some of which were built as whalers and or merchantmen. More recent projects conducted on shipwrecks in California include the Phase III Data Recovery of the Clarksburg Ferry in the Sacramento River below Sacramento. The investigation of the historic Clarksburg Ferry (CA-Yol-223H), a relatively intact example of a Sacramento River Delta ferry, a vessel type that played a significant role in the local and regional landscape well into the twentieth century, was conducted under subcontract to North State Resources, Inc., of Redding, California, and was undertaken to fulfill Section 106 requirements for adverse effects to this historic property from planned erosion repair work at RM 41.9R as part of the Sacramento District, U.S. Army Corps of Engineers' Sacramento River Bank Protection Program.

Mr. William Wilson, who will act as Principal Investigator and Remote Sensing Specialist for this project, has an M.A. in Maritime Archaeology from the University of West Florida, Pensacola, and is a Pensacola resident. RPA Certified and currently lead Maritime Archaeologist with Commonwealth, he recently acted as Principal Investigator/Remote Sensing Specialist on a large survey and diving investigation in the IWW at St. Augustine in which 7 targets were investigated by archaeological divers for a Jacksonville District Corps of Engineer project. Prior to this he directed the archaeological diving investigation of targets offshore New Smyrna Beach for the District as well. He has a wealth of remote sensing survey and diving project experience on the Savannah River for the Savannah District including the recent 2-year long Phase III Recovery of the CSS *Georgia*. He recently directed survey and diving investigations on the Savannah River near Augusta, as well as Jupiter AIWW, both conducted for the Jacksonville District. Closer to the project area, he was Principal Investigator and directed a large remote sensing survey off Fire Island, New York in 2022 for the New York District but through a Philadelphia District contract.

Mr. Justin Milewski will act as Remote Sensing Technician for the project. Currently working on his Master Thesis in Underwater Archaeology from the University of West Florida, since joining Commonwealth in 2021 Mr. Milewski has served as a Remote Sensing technician, as well as GIS technician on cultural resources investigations conducted for the USACE, Jacksonville, New York, Charleston, and Philadelphia Districts. He is skilled in the processing of collected data and in the utilization of our in-house state-of-the-art HYPACK MAX® software for remote sensing survey navigation and data acquisition, and Sonar WizMap® sidescan mosaicking software. Mr. Milewski has previous experience as a Maritime archaeologist with the University of West Florida conducting remote sensing surveys and underwater excavations on sites throughout the Pensacola, Florida area. Acting as Field Director and Remote Sensing Specialist he just completed a large remote sensing survey offshore South Carolina for the Charleston District. Acting in the same capacity, he is currently conducting a large remote sensing survey project in North Carolina for the Jacksonville District.

Rikki Oeters Milewski is a maritime archaeologist with over four years of experience in cultural resources management (CRM). She currently serves as an associate archaeologist for PaleoWest's Maritime Division. Mrs. Milewski joined PaleoWest in 2021 and completed her M.A. in Maritime Archaeology from the University of West Florida in 2023. She has participated in remote sensing/geophysical and diving investigations for PaleoWest. She has served as GIS specialist, surface-supplied diver, surface-supplied diving supervisor, surface-supplied diver tender, remote sensing survey technician, and archival and historical background researcher on cultural resources investigations conducted for the USACE, Jacksonville, Mobile, New York, Philadelphia, Wilmington, and Savannah districts, the U.S. EPA Great Lakes National Program Office, and various other federal agencies, and private clients. She is skilled in the processing of collected data, the utilization of Sonar WizMap® side-scan mosaicking and subbottom profiler analysis software, the use of MagPick magnetometer processing software, various forms of GIS software platforms, archival and historical background research, and report authoring for submerged remote-sensing surveys and archaeological diver investigations. She will act in this capacity for the project.

## **PROJECT PHASES**

#### **Task 1 - State Coordination**

As proper protocol dictates, and unless otherwise directed, the project will commence with coordination with the State of California's State/Underwater Archaeologist. The overall project will be discussed as will the proposed technical plan. The State's requirements for submerged cultural resources survey and report deliverables are as follows:

### Survey Specifications:

- Preplotted survey lines
- Maximum vessel speed no greater than 5 knots
- Survey line spacing equal or less than 30 meters (100 feet)
- Maximum 1.5 gammas background noise for magnetometer
- Minimum 100% coverage

#### Report Specifications:

- Discussion of survey methodology and survey events
- Map of the survey area
- Post Plot of survey track lines with annotated event marks
- Contour map of Magnetic anomalies
- Isometric maps of individual anomalies
- Sonar contact images
- Images of any Paleofeatures
- Recommendations for avoidance, assessment, etc. of potentially significant anomalies

## Task 2 - Archival and Literature Review

PaleoWest personnel will perform the necessary literature and records check of pertinent sources and collect information on the potential significance of any of the located submerged resources. Emphasis will be placed on the examination of historic documents that may aid in the identification of the submerged resources. A review of the State Master Site Files shall be made to gather data on nearby historic properties in relationship to maritime transportation and commerce, as well as prehistoric sites. Emphasis will be placed on the examination of historic and cartographic data relating to the locations of historic wrecks. Repositories may include, but are not limited to, the following: county records; university and private collections; photography collections; and regional and national archives. Emphasis shall also be placed on documentation related to exploration, colonization, development, agriculture, fishing, industry, trade, transportation, commerce, warfare, and shipbuilding. Appropriate information shall be collected that may provide a correlation between the targets and known shipwrecks.

Additional archival research will be conducted, as necessary, to identify, evaluate, and assess the significance of any recorded potentially significant targets. The contractor shall examine historic background data and build upon that data to further construct and refine a background history of the targets as they relate to the Project Area (i.e., place identifiable targets in appropriate historical context). These contexts can be used as the framework in which to apply the criteria for National Register of Historic Places (NRHP) evaluations.

Emphasis will also be placed on documentation related to the potential for submerged prehistoric sites including evaluating the submerged paleoenvironment, geology, sea level issues, etc. It should be mentioned that PaleoWest has extensive experience using sidescan sonar and subbottom profiling to identify potential paleolandscapes and issues of specifications for identification and avoidance of potential site locations (see Lydecker et al. 2011; Faught and James 2010, 2011).

It should be stated that two wreck symbols are within or adjacent to the proposed survey corridor as shown in Figure 2. At this time it is unknown what these wrecks represent. Archival research should illuminate their sinking time period and possibly type of wreck relative to significance or lack thereof.




Figure 2. Two wreck symbols are in or immediately adjacent to the survey area. One wreck symbol located at the southern end of the corridor just upriver (to the right) and immediately adjacent to the southern "Proposed Project Transition Structure." The second wreck symbol is on the extreme northern end just downriver (to the rleft) and immediately adjacent to the northern "Proposed Project Transition Structure." It may be in too shallow of water to survey.

## Task 3. Remote Sensing Survey, Equipment and Procedures

As in past surveys in California, the project area is to be surveyed with a transect interval that ensures 100% overlapping coverage of the Corridor or Area of Potential Effect (APE) and with transects spaced no more that 30-meters (100-feet) apart. As established by our navigation program this equates to approximately 177 statute survey line miles for the APE. Pre-planned tracklines, also stipulated by state regulations, are presented in Figure 3.




Figure 3. Pre-planned survey lines spaced at 15-meter intervals.

The remote sensing survey of the project areas will comprise a magnetometer, sidescan sonar and subbottom profiler investigation. The remote sensing will, through the use of these instruments and a DGPS navigation system, accurately locate and map potential shipwreck sites as well as locations thought to be conducive to prehistoric habitation (i.e., paleo landforms). Having conducted literally dozens these types of investigations, our methods comply with both Corps of Engineers and State of California survey stipulations. The equipment and methods are discussed below.

Onboard remote-sensing instrumentation will consist of a Marine Magnetics SeaSpy proton precession magnetometer, a Marine Sonic Technology Sea Scan PC side scan sonar system, an Edgetech 424 XSE-500 Shallow Tow X-Star Chirp Subbottom Profiler System, and a Trimble Navigation DSM212H, Integrated 12-channel Global Positioning System (DGPS). All instruments will be towed at a speed of not more than 5 knots. The magnetometer shall have a sensitivity of 1 gamma with 1-second repeatability. The sensor shall employ a depressor or other device capable of maintaining no greater than a six (6) meter tow height above the riverfloor or half the distance to the bottom, whichever is less.

The side-scan sonar shall have 600-1200 kHz capability and will be operated at a scale to assure 200% overlapping coverage from adjacent lanes. At individual targets, the field director may narrow the lane interval in order to define magnetic or sonar characteristics. All systems will be operationally compatible and instrumentation records will be electronically interfaced with an electronic navigation-positioning system offering repositioning accuracy of 1 meter or less. Positioning will be by corrected DGPS. All hard-copy analog or image records will be regularly

annotated with real time, absolute (e.g. state plane/UTM.), and relative position (transect number and distance), and event numbers. State Plane and UTM coordinates, water depth, and reproductions of magnetic targets, acoustic images, and subbottom features will be included in the draft and final reports.

A primary consideration in any remote sensing survey is positioning. Accurate positioning is essential during running of transect survey lines and accurate post processing of collected data. Positioning functions will be accomplished on this project through the use of a Trimble Navigation DSM212H, Integrated 12-channel Global Positioning System (GPS) and Dual-channel MSK Beacon receiver for differential (DGPS) capabilities with sub-meter accuracy or equivilant. Navigation, magnetic data acquisition, and post processing of data will be accomplish with Hypack Max®, computer software written and developed by Coastal Oceanographics, Inc. specifically for survey applications. Positioning information will be stored on magnetic disk in a Sony Vaio laptop computer employed for various survey software applications, data acquisition and storage. Also developed by Coastal Oceanographics, SonarWhiz.MAP®, a state-of-the-art program, will be employed for sonar and subbottom data acquisition. It allows real-time mosaicking, and advanced analysis tools such as target tabulation and related target and navigational information.

All work shall be conducted using the California State Plane Coordinate system survey feet and will be presented in NAD83 grid and UTM system coordinates.

#### SAFETY AND LOGISTICS

Safety will be the paramount concern during the remote sensing project. All PaleoWest personnel scheduled to participate in this research have been qualified in First Aid and CPR by the Red Cross or comparable agency. During the survey, there will be communication with shore in the event of an accident. All PaleoWest personnel are adequately covered by insurance for all activities required under this contract and a COI will be submitted upon award that names the client as coinsured.

Finally, as with all marine activities, a constant monitoring of the weather and environment will be taken to avoid any situation that would be a hazard to navigation or the safe and effective collection of remote sensing data or diving operations. Such contradictions to safe navigation and work could include, but are not limited to: shallows; breaking waves; severe weather; commercial or private craft; unidentified flotsam and jetsam obstructing the survey vessel path; bathers and other individuals in the water; and any other situation that can be considered a hazard to navigation.

## Task 4 - Data Analysis

Analysis of collected data will be conducted during and immediately upon completion of the remote sensing survey. When the survey of the Survey Area has been completed, the data for that area for all three instruments will be sent to our Pensacola Maritime office for analysis. In this manner, the schedule will be met.

Employing Hypack in the analysis, all magnetic data collected will be processed into both contour map and tabular format, which will include X/Y coordinates, nanotesla deviation, type, duration, and association with other anomalies or sidescan targets. All magnetic anomalies will be described and assessed as to potential significance by employing signal characteristics (e.g., spatial extent, structural features, etc.). Potentially significant targets are also presented as separate contour maps to allow enhanced visual representation. Magnetic data are presented in magnetic contour maps with trackline format. Sidescan sonar and subbottom targets are presented in tabular form with X/Y data, and located and presented on the contour maps. Images of the sidescan and subbottom targets are also presented.

The evaluation of the potential cultural significance of targets is then conducted, and is dependent on a variety of factors. These include the detected characteristics of the individual targets (e.g., magnetic anomaly strength and duration), association with other magnetic targets on the same or adjacent lines, relationships to observable target sources (i.e., modern debris, channel buoys, or pipeline crossings), as well as correlation to the historic record. Magnetic and sidescan anomalies are evaluated and prioritized based on amplitude or deflection intensity in concert with duration or spatial extent. Targets such as isolated sections of pipe can normally be immediately discarded as nonsignificant. The subbottom record is analyzed for submerged landforms that would be conducive to prehistoric habitation sites, or submerged/buried shell midden features, as well as buried anomalies that could represent shipwreck sites.

Targets that are likely to represent potential historic shipwrecks or other potential submerged resources (i.e., submerged relic landforms) will be identified, and recommendations will be made relative to the potential significance of the target identified. These recommendations will include a motivation as to the significance of the targets. Detailed maps will be produced for any anomaly/target that is recommended for further evaluation, and anomalies will be ranked as to priority for subsequent archaeological evaluation or avoidance.

It must be stated that Data Analysis generally takes place after the completion of the survey and is a somewhat lengthy process. During the survey, the workday is generally long with on-board personnel busy with minding data acquisition needs. Subsequently, analysis cannot be done during the survey. Data analysis is generally a one to one scenario with one day required for analysis of each instrument for each day of survey. Once processed and analyzed, the data must also be compared to the historic record.

## **Task 5 - REPORT REQUIREMENTS**

We will produce Methods, Results, Conclusions and Recommendations Chapters, as well as references. Additionally, we will give you our historical shipwreck research background (for the Sacto River Delta Area) to plug into the Historical Background Chapter produced by the California office.

### RESEARCH GUIDELINES

All field, laboratory, and office work to be carried out under this contract will be conducted in accordance with Florida Bureau Historic Preservation Survey Standards, as well as the Standards and Guidelines established in 36 CFR Part 66, Recovery of Scientific, Prehistoric, Historic, and Archaeological Data: Methods, Standards and Reporting Requirements (Federal Register, Vol. 42, No. 19 - Friday, January 18, 1977).

#### **References Cited**

- Faught, K. Michael, and Stephen R. James, Jr.
  - Diver Identification and Archaeological Testing of Ten Geomorphic Targets in Cuts A and B in Tampa Bay and Data Collection from Four Vibracores from Tampa Bay, Hillsborough County, Florida. Prepared for the U.S. Army Corps of Engineers, Jacksonville District and under contract to G.E.C., Inc., Baton Rouge, Louisiana by Panamerican Consultants, Inc., Memphis, Tennessee.
  - 2011 Diver Identification and Archaeological Testing: Addendum to Cultural Resources Remote Sensing Survey of Jacksonville Harbor Project GRR2, Duvall County, Florida. Prepared for the U.S. Army Corps of Engineers, Jacksonville District and under contract to G.E.C., Inc., Baton Rouge, Louisiana by Panamerican Consultants, Inc., Memphis, Tennessee.
- Lydecker, Andrew D.W., Michael K. Faught, Michael Murray, and Jelane Wallace
  - 2011 Sarasota Beach Erosion Control Cultural Resources Survey: Remote Sensing Survey of Four Offshore Borrow Areas, Nearshore and Shoreline Survey, Sarasota County, Florida. Prepared for the U.S. Army Corps of Engineers, Jacksonville District and under contract to G.E.C., Inc., Baton Rouge, Louisiana by Panamerican Consultants, Memphis, Tennessee.

## **APPENDIX I**

## VITAE OF PROJECT PERSONNEL



## For General Inquiries:

T: (886) 563-2536 T: (602) 254-6280 info@chronicleheritage.com



# Attachment C. NAHC Correspondence

## **Sacred Lands File & Native American Contacts List Request**

## NATIVE AMERICAN HERITAGE COMMISSION

1550 Harbor Blvd, Suite 100 West Sacramento, CA 95501 (916) 373-3710 (916) 373-5471 – Fax nahc@nahc.ca.gov

Information Below is Required for a Sacred Lands File Search

Project:			
Country			
USGS Quadrangle	e		
		Section(s):	
Company/Firm/A	gency:		
Contact Person:			
Street Address:			
City:			
	Extension		
Ear.			
Email:			
Project Description			
Project Locati	on Map is attached		

SLF&Contactsform: rev: 05/07/14



## NATIVE AMERICAN HERITAGE COMMISSION

June 1, 2023

Katherine Sinsky PaleoWest

ACTING CHAIRPERSON Reginald Pagaling Chumash

Via Email to: <a href="mailto:ksinsky@paleowest.com">ksinsky@paleowest.com</a>

SECRETARY

Sara Dutschke

Miwok

Re: Insignia Collinsville Substation Project, Contra Costa and Solano Counties

COMMISSIONER
Isaac Bojorquez
Ohlone-Costanoan

Dear Ms. Sinsky:

COMMISSIONER **Buffy McQuillen**Yokayo Pomo, Yuki,

Nomlaki

A record search of the Native American Heritage Commission (NAHC) Sacred Lands File (SLF) was completed for the information you have submitted for the above referenced project. The results were <u>negative</u>. However, the absence of specific site information in the SLF does not indicate the absence of cultural resources in any project area. Other sources of cultural resources should also be contacted for information regarding known and recorded sites.

COMMISSIONER
Wayne Nelson
Luiseño

Attached is a list of Native American tribes who may also have knowledge of cultural resources in the project area. This list should provide a starting place in locating areas of potential adverse impact within the proposed project area. I suggest you contact all of those indicated; if they cannot supply information, they might recommend others with specific knowledge. By contacting all those listed, your organization will be better able to respond to claims of failure to consult with the appropriate tribe. If a response has not been received within two weeks of notification, the Commission requests that you follow-up with a telephone call or email to ensure that the project information has been received.

COMMISSIONER **Stanley Rodriguez** *Kumeyaay* 

If you receive notification of change of addresses and phone numbers from tribes, please notify me. With your assistance, we can assure that our lists contain current information.

If you have any questions or need additional information, please contact me at my email address: <a href="mailto:Cody.Campagne@nahc.ca.gov">Cody.Campagne@nahc.ca.gov</a>.

COMMISSIONER Vacant

Sincerely,

COMMISSIONER Vacant

COMMISSIONER Vacant

EXECUTIVE SECRETARY Raymond C.

**Hitchcock** *Miwok, Nisenan* 

Cody Campagne Cultural Resources Analyst

Cody Campagne

Attachment

## NAHC HEADQUARTERS

1550 Harbor Boulevard Suite 100 West Sacramento, California 95691 (916) 373-3710 nahc@nahc.ca.gov NAHC.ca.gov

## **Native American Heritage Commission Native American Contact List** Solano, Contra Costa Counties 6/1/2023

Costanoan

Me-Wuk

Wintun

Wintun

Wintun

the Health and Safety Code, Section 5097.94 of the Public Resource Section 5097.98 of the Public Resources Code.

Amah MutsunTribal Band of Mission San Juan Bautista

Irene Zwierlein, Chairperson 3030 Soda Bay Road Lakeport, CA, 95453

Phone: (650) 851 - 7489 Fax: (650) 332-1526

amahmutsuntribal@gmail.com

Chicken Ranch Rancheria of Me-Wuk Indians

Lloyd Mathiesen, Chairperson P.O. Box 1159

Jamestown, CA, 95327 Phone: (209) 984 - 9066 Fax: (209) 984-9269 Imathiesen@crtribal.com

Cachil Dehe Band of Wintun Indians of the Colusa Indian Community

Clifford Mota, Tribal Preservation

Liaison

3730 Highway 45

Colusa, CA, 95932 Phone: (530) 458 - 8231 cmota@colusa-nsn.gov

Cachil Dehe Band of Wintun Indians of the Colusa Indian Community

Daniel Gomez, Chairman 3730 Highway 45

Colusa, CA, 95932 Phone: (530) 458 - 8231 dgomez@colusa-nsn.gov

Cortina Rancheria - Kletsel Dehe Band of Wintun Indians

Charlie Wright, Chairperson P.O. Box 1630

Williams, CA, 95987 Phone: (530) 473 - 3274 Fax: (530) 473-3301

Guidiville Indian Rancheria

Donald Duncan, Chairperson

P.O. Box 339

Talmage, CA, 95481 Phone: (707) 462 - 3682 Fax: (707) 462-9183 admin@guidiville.net

Indian Canyon Mutsun Band of Costanoan

Ann Marie Sayers, Chairperson

P.O. Box 28

Hollister, CA, 95024 Phone: (831) 637 - 4238 ams@indiancanyon.org

Indian Canyon Mutsun Band of Costanoan

Kanyon Sayers-Roods, MLD

Contact

1615 Pearson Court San Jose, CA, 95122

Phone: (408) 673 - 0626

kanyon@kanyonkonsulting.com

Muwekma Ohlone Indian Tribe of the SF Bay Area

Monica Arellano, Vice Chairwoman

20885 Redwood Road, Suite 232 Costanoan

Castro Valley, CA, 94546 Phone: (408) 205 - 9714 monicavarellano@gmail.com

Nashville Enterprise Miwok-Maidu-Nishinam Tribe

Cosme Valdez, Chairperson

P.O. Box 580986

Elk Grove, CA, 95758-0017 Phone: (916) 429 - 8047 Fax: (916) 429-8047

valdezcome@comcast.net

North Valley Yokuts Tribe

Timothy Perez,

P.O. Box 717 Costanoan Linden, CA, 95236 Northern Valley Phone: (209) 662 - 2788

huskanam@gmail.com

Yokut

Miwok

Pomo

Costanoan

Costanoan

This list is current only as of the date of this document. Distribution of this list does not relieve any person of statutory responsibility as defined in Section 7050.5 of

This list is only applicable for contacting local Native Americans with regard to cultural resources assessment for the proposed Insignia Collinsville Substation Project, Solano, Contra Costa Counties.

## **Native American Heritage Commission Native American Contact List** Solano, Contra Costa Counties 6/1/2023

North Valley Yokuts Tribe

Katherine Perez, Chairperson

P.O. Box 717 Linden, CA, 95236

Phone: (209) 887 - 3415

canutes@verizon.net

Wilton Rancheria

Steven Hutchason, THPO

9728 Kent Street Elk Grove, CA, 95624

Phone: (916) 683 - 6000 Fax: (916) 863-6015

shutchason@wiltonrancheria-

nsn.gov

The Ohlone Indian Tribe

Desiree Vigil, THPO

1775 Marco Polo Way, Apt. 21 Bay Miwok Ohlone Burlingame, CA, 94010 Phone: (650) 290 - 0245 Patwin Plains Miwok

dirwin0368@yahoo.com

Yocha Dehe Wintun Nation

Anthony Roberts, Chairperson P.O. Box 18

Brooks, CA, 95606 Phone: (530) 796 - 3400 thpo@vochadehe-nsn.gov Patwin

Miwok

Costanoan

Bay Miwok

Plains Miwok

Ohlone

Patwin

Maidu

Miwok

Miwok

Miwok

Yokut

Northern Valley

The Ohlone Indian Tribe

Andrew Galvan, Chairperson P.O. Box 3388

Fremont, CA, 94539 Phone: (510) 882 - 0527 Fax: (510) 687-9393

chochenyo@AOL.com

Yocha Dehe Wintun Nation

Yvonne Perkins, THPO, Cultural

Resources Chairman

P.O. Box 18 Patwin

Brooks, CA, 95606 Phone: (530) 796 - 3400 thpo@yochadehe-nsn.gov

United Auburn Indian Community of the Auburn Rancheria

Gene Whitehouse, Chairperson 10720 Indian Hill Road

Auburn, CA, 95603 Phone: (530) 883 - 2390 Fax: (530) 883-2380

bguth@auburnrancheria.com

Confederated Villages of Lisjan Nation

Corrina Gould, Chairperson 10926 Edes Avenue

Bay Miwok Oakland, CA, 94603 Ohlone Phone: (510) 575 - 8408 Delta Yokut

cvltribe@gmail.com

Wilton Rancheria

Jesus Tarango, Chairperson

9728 Kent Street

Elk Grove, CA, 95624 Phone: (916) 683 - 6000 Fax: (916) 683-6015

jtarango@wiltonrancheria-nsn.gov

Confederated Villages of Lisjan Nation

Deja Gould, Language Program

Manager

10926 Edes Ave Bay Miwok Oakland, CA, 94603 Ohlone Phone: (510) 575 - 8408 Delta Yokut

cvltribe@gmail.com

Confederated Villages of Lisjan Nation

Cheyenne Gould, Tribal Cultural

Resource Manager

10926 Edes Ave **Bay Miwok** Oakland, CA, 94603 Ohlone Phone: (510) 575 - 8408 Delta Yokut

cvltribe@gmail.com

Wilton Rancheria

Dahlton Brown, Director of

Administration 9728 Kent Street

Elk Grove, CA, 95624

Phone: (916) 683 - 6000 dbrown@wiltonrancheria-nsn.gov

This list is current only as of the date of this document. Distribution of this list does not relieve any person of statutory responsibility as defined in Section 7050.5 of the Health and Safety Code, Section 5097.94 of the Public Resource Section 5097.98 of the Public Resources Code.

This list is only applicable for contacting local Native Americans with regard to cultural resources assessment for the proposed Insignia Collinsville Substation Project, Solano, Contra Costa Counties.



BAY AREA, CALIFORNIA 1870 Olympic Blvd, Suite 100 Walnut Creek, CA 94596

June 26, 2023

Irene Zwierlein, Chairperson Amah Mutsun Tribal Band of Mission San Juan Bautista 3030 Soda Bay Road Lakeport, California, 95453

RE: Native American Outreach for the Insignia Collinsville Substation Project, Contra Costa and Solano Counties, California

Dear Chairperson Zwierlein,

PaleoWest, LLC (PaleoWest) is seeking any information you may have regarding Native American cultural resources in the vicinity of the 500/230 kV Collinsville Substation Project, which begins at the PG&E Pittsburg Substation in Contra Costa County, travels north for four miles across the Sacramento River, and ends at the proposed Collinsville substation site on the north bank of the river in Solano County. The project is depicted on the USGS *Honker Bay, CA* and *Antioch, CA,* topographic quadrangles, and on the enclosed maps. The project is subject to the California Environmental Quality Act (CEQA), with involvement from the U.S. Army Corps of Engineers (USACE) and California Public Utilities Commission (CPUC).

Terrestrial and marine archaeological surveys of the aboveground and submerged portions of the project area will be completed by qualified PaleoWest archaeologists later in the summer. Results of the records search indicate that five sites have been documented within the project area, and seven within a half-mile of the project area. Site types identified in the project area include two historic buildings, a historic structure, a historic site, and a precontact period isolated handstone. Results of the state shipwreck inventory search indicate that 37 wrecks have been documented in the underwater portion of the project area. A search of the Sacred Land File (SLF) by the Native American Heritage Commission (NAHC) was completed and the results were <u>negative</u>.

If you are aware of any Native American cultural resources or traditional cultural properties within or in the vicinity of the Project area shown on the enclosed maps, or if you have any concerns related to the overall Project, please contact me at 760-207-4242 or at my email address below. The information you provide will be used to assess areas of potential significant impact within the Project area, and any information provided will be confidential and not divulged to the public. We appreciate your time and assistance, and we greatly value any information you may provide.


Sincerely,


**PALEOWEST** 


Katherine Sinsky

Senior Archaeologist and Project Manager

760.207.4242







## The Amah Mutsun Tribal Band of San Juan Bautista & A.M.T.B. Inc.

## Letter of Response

## To whom it may concern:

It is our pride and privilege to be of service for any Native American Cultural Resource Monitoring, Consulting and/ or Sensitivity Training you may need or require. We take our Heritage and History seriously and are diligent about preserving as much of it as we can. Construction is a constant in the Bay Area and with that new discoveries are bound to happen. If you choose our services we will gladly guide all personnel through proper procedures to safely protect and preserve: Culture, Heritage, and History.

It is highly recommended, if not previously done, to search through Sacred Lands Files (SLF) and California Historical Resource Information Systems (CHRIS) as well as reaching out to the Native American Heritage Commission (NAHC) In order to determine whether you are working in a Cultural and/ or Historic sensitivity.

If you have received any positive cultural or historic sensitivity within 1 mile of the project area here is A.M.T.B Inc's and Amah Mutsun Tribal Band of San Juan Bautista's recommendations:

- All Crews, Individuals and Personnel who will be moving any earth be Cultural Sensitivity Trained.
- A Qualified California Trained Archaeological Monitor is present during any earth movement.
- A Qualified Native American Monitor is present during any earth movement.

If further Consultation, Monitoring or Sensitivity Training is needed please feel free to contact A.M.T.B. Inc. or Myself Directly.

Sincerely, Irenne Zwierlein

Arenne Zwierlein

3030 <mark>Soda</mark> Bay Road, Lakeport CA 95453 <u>amtbinc21@gmail.com</u> (650)851-7489

## Amah Mutsun Tribal Band of San Juan Bautista & AMTB Inc.

## 3030 Soda Bay Road Lakeport, CA 95453

Our rates for 2023

\$250.00 per hour.

4 hours minimum

Cancellations not 48 hours (about 2 days) prior will be charged a 4-hour minimum. There is a round trip mileage charge if canceled after they have traveled to site.

Anything over 8 hours a day is charged as time and a half.

Weekends are charged at time and a half.

Holidays are charged at double time.

For fiscal year (FY) 2023, standard per diem rate of \$329 (\$255 lodging, \$74 M&IE).

## M&IE Breakdown FY 2023

M&IE	Continental Breakfast/ Breakfast²	Lunch <sup>2</sup>	Diffici	Incidental Expenses	First & Last Day of Travel <sup>3</sup>
\$74.00	\$17.00	\$18.00	\$34.00	\$5.00	\$55.50

Beginning on July 1st, 2022, the standard mileage rates for the use of a car round trip (also vans, pickups or panel trucks) will be: \$62.50 cents per mile driven for business use or what the current federal standard is at the time.

Our Payment terms are 5 days from date on invoice.

Our Monitors are Members of the Amah Mutsun Tribal Band of Mission San Juan Bautista.

If you have any questions, please feel free to contact the A.M.T.B. Inc. at the below contact information.

Sincerely, Arenne Zwierlein

Irenne Zwierlein

3030 Soda Bay Rd, Lakeport

CA 95453
amtbinc21@gmail.com
(650)851-7489



## CERTIFICATE OF LIABILITY INSURANCE

7/25/2022

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

IMPORTANT: If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must have ADDITIONAL INSURED provisions or be endorsed. If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).

CONTACT

Allied Brokers				NAME: Brenda Aldaco					
				PHONE (A/C, No, Ext): (650) 328-1000 FAX (A/C, No): (650) 324-1142					
5911	Lytton Avenue			ADDRESS: Business	VIP@alliedbro	kers.com			
				IN:	SURER(S) AFFOI	RDING COVERAGE		NAIC #	
Palo	Alto		CA 94301	INSURER A: Scottsdale Insurance Company				41297	
INSUR	RED			INSURER B : United S	States Liability	Insurance Company		25895	
	Amah Mutsun Tribal Band			INSURER C:					
	3030 SODA BAY RD			INSURER D :					
				INSURER E :				1	
	LAKEPORT		CA 95453	INSURER F:					
cov	776 (A PACE OF C	TIEICATE	NUMBER:	INDUNERY.	- 8	REVISION NUMBER:			
THI INC	IS IS TO CERTIFY THAT THE POLICIES OF DICATED. NOTWITHSTANDING ANY REQU RTIFICATE MAY BE ISSUED OR MAY PER CLUSIONS AND CONDITIONS OF SUCH P	INSURANG UIREMENT, TAIN, THE	CE LISTED BELOW HAVE TERM OR CONDITION OF INSURANCE AFFORDED B	ANY CONTRACT OR O BY THE POLICIES DESC	NSURED NAM THER DOCUM RIBED HEREIN	ED ABOVE FOR THE POLIC ENT WITH RESPECT TO W	HICH TI	HIS	
NSR LTR	TYPE OF INSURANCE	INSD WVD	POLICY NUMBER	POLICY EFF (MM/DD/YYYY)	POLICY EXP (MM/DD/YYYY)	LIMIT	rs		
-	COMMERCIAL GENERAL LIABILITY		OCTORNO CONTROL	· · ·	1	EACH OCCURRENCE	5	1,000,000	
Ì	CLAIMS-MADE X OCCUR				3	DAMAGE TO RENTED PREMISES (Ea occurrence)	5	100,000	
ı	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1				3	MED EXP (Any one person)	5	5,000	
A			CPS7617452	07/09/2022	07/09/2023	PERSONAL & ADV INJURY	5	1,000,000	
	GENL AGGREGATE LIMIT APPLIES PER:		SEASON CONTRACT	3113712322	a management	GENERAL AGGREGATE	5	2,000,000	
-					5				
-						PRODUCTS - COMP/OP AGG	5	2,000,000	
-	OTHER: AUTOMOBILE LIABILITY	_				Deductible COMBINED SINGLE LIMIT	5	300	
						(Ea accident)	100		
-	ANY AUTO OWNED SCHEDULED				1 3	BODILY INJURY (Per person)	5		
	OWNED SCHEDULED AUTOS ONLY HIRED NON-OWNED				1	BODILY INJURY (Per accident) PROPERTY DAMAGE	\$		
	AUTOS ONLY AUTOS ONLY					(Per accident)	5		
	s 1 - 1000 pp - 3		2	- 8	8		5		
	UMBRELLA LIAB OCCUR					EACH OCCURRENCE	5		
	EXCESS LIAB CLAIMS-MADE					AGGREGATE	5		
	DED RETENTIONS					2000000 USAN DIAM	5		
	WORKERS COMPENSATION					PER OTH- STATUTE ER	77.00		
- 1	AND EMPLOYERS' LIABILITY  ANY PROPRIETOR/PARTNER/EXECUTIVE	11.00			8	E.L. EACH ACCIDENT	5		
k	OFFICER/MEMBER EXCLUDED? (Mandatory in NH)	N/A			-	E.L. DISEASE - EA EMPLOYEE	5		
	f yes, describe under DESCRIPTION OF OPERATIONS below				3	E.L. DISEASE - POLICY LIMIT	s		
	DESCRIPTION OF ELECTRONIC SCIENCE					Each Claim	7	\$1,000,000	
В	Professional Liability		SP 1573468B	06/21/2022	06/21/2023	Aggregate		\$1,000,000	
			31 13/34000	00/21/2022	00/21/2023	Deductible		\$2,500	
	RIPTION OF OPERATIONS / LOCATIONS / VEHIC OOF OF COVERAGE	LES (ACORI	D 101, Additional Remarka Sch	hedule, may be attached if n	ore space is req	uired)	id.		
CER	TIFICATE HOLDER			CANCELLATION					
For Your Information				SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS.					
				AUTHORIZED REPRESE	ENTATIVE				
				Dewender At	dance				



BAY AREA, CALIFORNIA 1870 Olympic Blvd, Suite 100 Walnut Creek, CA 94596

June 26, 2023

Lloyd Mathiesen, Chairperson Chicken Ranch Rancheria of Me-Wuk Indians P.O. Box 1159 Jamestown, California, 95327

RE: Native American Outreach for the Insignia Collinsville Substation Project, Contra Costa and Solano Counties, California

Dear Chairperson Mathiesen,

PaleoWest, LLC (PaleoWest) is seeking any information you may have regarding Native American cultural resources in the vicinity of the 500/230 kV Collinsville Substation Project, which begins at the PG&E Pittsburg Substation in Contra Costa County, travels north for four miles across the Sacramento River, and ends at the proposed Collinsville substation site on the north bank of the river in Solano County. The project is depicted on the USGS *Honker Bay, CA* and *Antioch, CA,* topographic quadrangles, and on the enclosed maps. The project is subject to the California Environmental Quality Act (CEQA), with involvement from the U.S. Army Corps of Engineers (USACE) and California Public Utilities Commission (CPUC).

Terrestrial and marine archaeological surveys of the aboveground and submerged portions of the project area will be completed by qualified PaleoWest archaeologists later in the summer. Results of the records search indicate that five sites have been documented within the project area, and seven within a half-mile of the project area. Site types identified in the project area include two historic buildings, a historic structure, a historic site, and a precontact period isolated handstone. Results of the state shipwreck inventory search indicate that 37 wrecks have been documented in the underwater portion of the project area. A search of the Sacred Land File (SLF) by the Native American Heritage Commission (NAHC) was completed and the results were <u>negative</u>.

If you are aware of any Native American cultural resources or traditional cultural properties within or in the vicinity of the Project area shown on the enclosed maps, or if you have any concerns related to the overall Project, please contact me at 760-207-4242 or at my email address below. The information you provide will be used to assess areas of potential significant impact within the Project area, and any information provided will be confidential and not divulged to the public. We appreciate your time and assistance, and we greatly value any information you may provide.

Sincerely,

**PALEOWEST** 

Katherine Sinsky

Senior Archaeologist and Project Manager

760.207.4242



BAY AREA, CALIFORNIA 1870 Olympic Blvd, Suite 100 Walnut Creek, CA 94596

June 26, 2023

Clifford Mota, Tribal Preservation Liaison, Cachil Dehe Band of Wintun Indians of the Colusa Indian Community 3730 Highway 45 Colusa, California, 95932

RE: Native American Outreach for the Insignia Collinsville Substation Project, Contra Costa and Solano Counties, California

Dear Tribal Leader Mota,

PaleoWest, LLC (PaleoWest) is seeking any information you may have regarding Native American cultural resources in the vicinity of the 500/230 kV Collinsville Substation Project, which begins at the PG&E Pittsburg Substation in Contra Costa County, travels north for four miles across the Sacramento River, and ends at the proposed Collinsville substation site on the north bank of the river in Solano County. The project is depicted on the USGS *Honker Bay, CA* and *Antioch, CA,* topographic quadrangles, and on the enclosed maps. The project is subject to the California Environmental Quality Act (CEQA), with involvement from the U.S. Army Corps of Engineers (USACE) and California Public Utilities Commission (CPUC).

Terrestrial and marine archaeological surveys of the aboveground and submerged portions of the project area will be completed by qualified PaleoWest archaeologists later in the summer. Results of the records search indicate that five sites have been documented within the project area, and seven within a half-mile of the project area. Site types identified in the project area include two historic buildings, a historic structure, a historic site, and a precontact period isolated handstone. Results of the state shipwreck inventory search indicate that 37 wrecks have been documented in the underwater portion of the project area. A search of the Sacred Land File (SLF) by the Native American Heritage Commission (NAHC) was completed and the results were <u>negative</u>.

If you are aware of any Native American cultural resources or traditional cultural properties within or in the vicinity of the Project area shown on the enclosed maps, or if you have any concerns related to the overall Project, please contact me at 760-207-4242 or at my email address below. The information you provide will be used to assess areas of potential significant impact within the Project area, and any information provided will be confidential and not divulged to the public. We appreciate your time and assistance, and we greatly value any information you may provide.

Sincerely,

**PALEOWEST** 

Katherine Sinsky

Senior Archaeologist and Project Manager

760.207.4242



BAY AREA, CALIFORNIA 1870 Olympic Blvd, Suite 100 Walnut Creek, CA 94596

June 26, 2023

Daniel Gomez, Chairman Cachil Dehe Band of Wintun Indians of the Colusa Indian Community 3730 Highway 45 Colusa, California, 95932

RE: Native American Outreach for the Insignia Collinsville Substation Project, Contra Costa and Solano Counties, California

Dear Chairman Gomez,

PaleoWest, LLC (PaleoWest) is seeking any information you may have regarding Native American cultural resources in the vicinity of the 500/230 kV Collinsville Substation Project, which begins at the PG&E Pittsburg Substation in Contra Costa County, travels north for four miles across the Sacramento River, and ends at the proposed Collinsville substation site on the north bank of the river in Solano County. The project is depicted on the USGS *Honker Bay, CA* and *Antioch, CA,* topographic quadrangles, and on the enclosed maps. The project is subject to the California Environmental Quality Act (CEQA), with involvement from the U.S. Army Corps of Engineers (USACE) and California Public Utilities Commission (CPUC).

Terrestrial and marine archaeological surveys of the aboveground and submerged portions of the project area will be completed by qualified PaleoWest archaeologists later in the summer. Results of the records search indicate that five sites have been documented within the project area, and seven within a half-mile of the project area. Site types identified in the project area include two historic buildings, a historic structure, a historic site, and a precontact period isolated handstone. Results of the state shipwreck inventory search indicate that 37 wrecks have been documented in the underwater portion of the project area. A search of the Sacred Land File (SLF) by the Native American Heritage Commission (NAHC) was completed and the results were negative.

If you are aware of any Native American cultural resources or traditional cultural properties within or in the vicinity of the Project area shown on the enclosed maps, or if you have any concerns related to the overall Project, please contact me at 760-207-4242 or at my email address below. The information you provide will be used to assess areas of potential significant impact within the Project area, and any information provided will be confidential and not divulged to the public. We appreciate your time and assistance, and we greatly value any information you may provide.

Sincerely,

**PALEOWEST** 

Katherine Sinsky

Senior Archaeologist and Project Manager

760.207.4242



BAY AREA, CALIFORNIA 1870 Olympic Blvd, Suite 100 Walnut Creek, CA 94596

June 26, 2023

Charlie Wright, Chairperson Cortina Rancheria-Kletsel Dehe Band of Wintun Indians P.O. Box 1630 Williams, California, 95987

RE: Native American Outreach for the Insignia Collinsville Substation Project, Contra Costa and Solano Counties, California

Dear Chairperson Wright,

PaleoWest, LLC (PaleoWest) is seeking any information you may have regarding Native American cultural resources in the vicinity of the 500/230 kV Collinsville Substation Project, which begins at the PG&E Pittsburg Substation in Contra Costa County, travels north for four miles across the Sacramento River, and ends at the proposed Collinsville substation site on the north bank of the river in Solano County. The project is depicted on the USGS *Honker Bay, CA* and *Antioch, CA,* topographic quadrangles, and on the enclosed maps. The project is subject to the California Environmental Quality Act (CEQA), with involvement from the U.S. Army Corps of Engineers (USACE) and California Public Utilities Commission (CPUC).

Terrestrial and marine archaeological surveys of the aboveground and submerged portions of the project area will be completed by qualified PaleoWest archaeologists later in the summer. Results of the records search indicate that five sites have been documented within the project area, and seven within a half-mile of the project area. Site types identified in the project area include two historic buildings, a historic structure, a historic site, and a precontact period isolated handstone. Results of the state shipwreck inventory search indicate that 37 wrecks have been documented in the underwater portion of the project area. A search of the Sacred Land File (SLF) by the Native American Heritage Commission (NAHC) was completed and the results were negative.

If you are aware of any Native American cultural resources or traditional cultural properties within or in the vicinity of the Project area shown on the enclosed maps, or if you have any concerns related to the overall Project, please contact me at 760-207-4242 or at my email address below. The information you provide will be used to assess areas of potential significant impact within the Project area, and any information provided will be confidential and not divulged to the public. We appreciate your time and assistance, and we greatly value any information you may provide.

Sincerely,

**PALEOWEST** 

Katherine Sinsky

Senior Archaeologist and Project Manager

760.207.4242



BAY AREA, CALIFORNIA 1870 Olympic Blvd, Suite 100 Walnut Creek, CA 94596

June 26, 2023

Donald Duncan, Chairperson Guidiville Indian Rancheria P.O. Box 339 Talmage, California, 95481

## RE: Native American Outreach for the Insignia Collinsville Substation Project, Contra Costa and Solano Counties, California

Dear Chairperson Duncan,

PaleoWest, LLC (PaleoWest) is seeking any information you may have regarding Native American cultural resources in the vicinity of the 500/230 kV Collinsville Substation Project, which begins at the PG&E Pittsburg Substation in Contra Costa County, travels north for four miles across the Sacramento River, and ends at the proposed Collinsville substation site on the north bank of the river in Solano County. The project is depicted on the USGS *Honker Bay, CA* and *Antioch, CA,* topographic quadrangles, and on the enclosed maps. The project is subject to the California Environmental Quality Act (CEQA), with involvement from the U.S. Army Corps of Engineers (USACE) and California Public Utilities Commission (CPUC).

Terrestrial and marine archaeological surveys of the aboveground and submerged portions of the project area will be completed by qualified PaleoWest archaeologists later in the summer. Results of the records search indicate that five sites have been documented within the project area, and seven within a half-mile of the project area. Site types identified in the project area include two historic buildings, a historic structure, a historic site, and a precontact period isolated handstone. Results of the state shipwreck inventory search indicate that 37 wrecks have been documented in the underwater portion of the project area. A search of the Sacred Land File (SLF) by the Native American Heritage Commission (NAHC) was completed and the results were negative.

If you are aware of any Native American cultural resources or traditional cultural properties within or in the vicinity of the Project area shown on the enclosed maps, or if you have any concerns related to the overall Project, please contact me at 760-207-4242 or at my email address below. The information you provide will be used to assess areas of potential significant impact within the Project area, and any information provided will be confidential and not divulged to the public. We appreciate your time and assistance, and we greatly value any information you may provide.

Sincerely,

**PALEOWEST** 

Katherine Sinsky

Senior Archaeologist and Project Manager

760.207.4242



BAY AREA, CALIFORNIA 1870 Olympic Blvd, Suite 100 Walnut Creek, CA 94596

June 26, 2023

Ann Marie Sayers, Chairperson Indian Canyon Mutsun Band of Costanoan P.O. Box 28 Hollister, California, 95024

RE: Native American Outreach for the Insignia Collinsville Substation Project, Contra Costa and Solano Counties, California

Dear Chairperson Savers,

PaleoWest, LLC (PaleoWest) is seeking any information you may have regarding Native American cultural resources in the vicinity of the 500/230 kV Collinsville Substation Project, which begins at the PG&E Pittsburg Substation in Contra Costa County, travels north for four miles across the Sacramento River, and ends at the proposed Collinsville substation site on the north bank of the river in Solano County. The project is depicted on the USGS *Honker Bay, CA* and *Antioch, CA,* topographic quadrangles, and on the enclosed maps. The project is subject to the California Environmental Quality Act (CEQA), with involvement from the U.S. Army Corps of Engineers (USACE) and California Public Utilities Commission (CPUC).

Terrestrial and marine archaeological surveys of the aboveground and submerged portions of the project area will be completed by qualified PaleoWest archaeologists later in the summer. Results of the records search indicate that five sites have been documented within the project area, and seven within a half-mile of the project area. Site types identified in the project area include two historic buildings, a historic structure, a historic site, and a precontact period isolated handstone. Results of the state shipwreck inventory search indicate that 37 wrecks have been documented in the underwater portion of the project area. A search of the Sacred Land File (SLF) by the Native American Heritage Commission (NAHC) was completed and the results were negative.

If you are aware of any Native American cultural resources or traditional cultural properties within or in the vicinity of the Project area shown on the enclosed maps, or if you have any concerns related to the overall Project, please contact me at 760-207-4242 or at my email address below. The information you provide will be used to assess areas of potential significant impact within the Project area, and any information provided will be confidential and not divulged to the public. We appreciate your time and assistance, and we greatly value any information you may provide.

Sincerely,

**PALEOWEST** 

Katherine Sinsky

Senior Archaeologist and Project Manager

760.207.4242



BAY AREA, CALIFORNIA 1870 Olympic Blvd, Suite 100 Walnut Creek, CA 94596

June 26, 2023

Kanyon Sayers-Roods, MLD Contact Indian Canyon Mutsun Band of Costanoan 1615 Pearson Court San Jose, California, 95122

RE: Native American Outreach for the Insignia Collinsville Substation Project, Contra Costa and Solano Counties, California

Dear Kanyon Sayers-Roods,

PaleoWest, LLC (PaleoWest) is seeking any information you may have regarding Native American cultural resources in the vicinity of the 500/230 kV Collinsville Substation Project, which begins at the PG&E Pittsburg Substation in Contra Costa County, travels north for four miles across the Sacramento River, and ends at the proposed Collinsville substation site on the north bank of the river in Solano County. The project is depicted on the USGS *Honker Bay, CA* and *Antioch, CA,* topographic quadrangles, and on the enclosed maps. The project is subject to the California Environmental Quality Act (CEQA), with involvement from the U.S. Army Corps of Engineers (USACE) and California Public Utilities Commission (CPUC).

Terrestrial and marine archaeological surveys of the aboveground and submerged portions of the project area will be completed by qualified PaleoWest archaeologists later in the summer. Results of the records search indicate that five sites have been documented within the project area, and seven within a half-mile of the project area. Site types identified in the project area include two historic buildings, a historic structure, a historic site, and a precontact period isolated handstone. Results of the state shipwreck inventory search indicate that 37 wrecks have been documented in the underwater portion of the project area. A search of the Sacred Land File (SLF) by the Native American Heritage Commission (NAHC) was completed and the results were negative.

If you are aware of any Native American cultural resources or traditional cultural properties within or in the vicinity of the Project area shown on the enclosed maps, or if you have any concerns related to the overall Project, please contact me at 760-207-4242 or at my email address below. The information you provide will be used to assess areas of potential significant impact within the Project area, and any information provided will be confidential and not divulged to the public. We appreciate your time and assistance, and we greatly value any information you may provide.

Sincerely,

**PALEOWEST** 

Katherine Sinsky

Senior Archaeologist and Project Manager

760.207.4242



BAY AREA, CALIFORNIA 1870 Olympic Blvd, Suite 100 Walnut Creek, CA 94596

June 26, 2023

Monica Arellano, Vice Chairperson Muwekma Ohlone Indian Tribe of the SF Bay Area 20885 Redwood Road, Suite 232 Castro Valley, California, 94546

RE: Native American Outreach for the Insignia Collinsville Substation Project, Contra Costa and Solano Counties, California

Dear Vice Chairperson Arellano,

PaleoWest, LLC (PaleoWest) is seeking any information you may have regarding Native American cultural resources in the vicinity of the 500/230 kV Collinsville Substation Project, which begins at the PG&E Pittsburg Substation in Contra Costa County, travels north for four miles across the Sacramento River, and ends at the proposed Collinsville substation site on the north bank of the river in Solano County. The project is depicted on the USGS *Honker Bay, CA* and *Antioch, CA,* topographic quadrangles, and on the enclosed maps. The project is subject to the California Environmental Quality Act (CEQA), with involvement from the U.S. Army Corps of Engineers (USACE) and California Public Utilities Commission (CPUC).

Terrestrial and marine archaeological surveys of the aboveground and submerged portions of the project area will be completed by qualified PaleoWest archaeologists later in the summer. Results of the records search indicate that five sites have been documented within the project area, and seven within a half-mile of the project area. Site types identified in the project area include two historic buildings, a historic structure, a historic site, and a precontact period isolated handstone. Results of the state shipwreck inventory search indicate that 37 wrecks have been documented in the underwater portion of the project area. A search of the Sacred Land File (SLF) by the Native American Heritage Commission (NAHC) was completed and the results were negative.

If you are aware of any Native American cultural resources or traditional cultural properties within or in the vicinity of the Project area shown on the enclosed maps, or if you have any concerns related to the overall Project, please contact me at 760-207-4242 or at my email address below. The information you provide will be used to assess areas of potential significant impact within the Project area, and any information provided will be confidential and not divulged to the public. We appreciate your time and assistance, and we greatly value any information you may provide.

Sincerely,

**PALEOWEST** 

Katherine Sinsky

Senior Archaeologist and Project Manager

760.207.4242



BAY AREA, CALIFORNIA 1870 Olympic Blvd, Suite 100 Walnut Creek, CA 94596

June 26, 2023

Cosme Valdez, Chairperson Nashville Enterprise Miwok Maidu-Nishinam Tribe P.O. Box 580986 Elk Grove, California, 95758-0017

RE: Native American Outreach for the Insignia Collinsville Substation Project, Contra Costa and Solano Counties, California

Dear Chairperson Valdez,

PaleoWest, LLC (PaleoWest) is seeking any information you may have regarding Native American cultural resources in the vicinity of the 500/230 kV Collinsville Substation Project, which begins at the PG&E Pittsburg Substation in Contra Costa County, travels north for four miles across the Sacramento River, and ends at the proposed Collinsville substation site on the north bank of the river in Solano County. The project is depicted on the USGS *Honker Bay, CA* and *Antioch, CA,* topographic quadrangles, and on the enclosed maps. The project is subject to the California Environmental Quality Act (CEQA), with involvement from the U.S. Army Corps of Engineers (USACE) and California Public Utilities Commission (CPUC).

Terrestrial and marine archaeological surveys of the aboveground and submerged portions of the project area will be completed by qualified PaleoWest archaeologists later in the summer. Results of the records search indicate that five sites have been documented within the project area, and seven within a half-mile of the project area. Site types identified in the project area include two historic buildings, a historic structure, a historic site, and a precontact period isolated handstone. Results of the state shipwreck inventory search indicate that 37 wrecks have been documented in the underwater portion of the project area. A search of the Sacred Land File (SLF) by the Native American Heritage Commission (NAHC) was completed and the results were <u>negative</u>.

If you are aware of any Native American cultural resources or traditional cultural properties within or in the vicinity of the Project area shown on the enclosed maps, or if you have any concerns related to the overall Project, please contact me at 760-207-4242 or at my email address below. The information you provide will be used to assess areas of potential significant impact within the Project area, and any information provided will be confidential and not divulged to the public. We appreciate your time and assistance, and we greatly value any information you may provide.

Sincerely,

**PALEOWEST** 

Katherine Sinsky

Senior Archaeologist and Project Manager

760.207.4242



BAY AREA, CALIFORNIA 1870 Olympic Blvd, Suite 100 Walnut Creek, CA 94596

June 26, 2023

Timothy Perez North Valley Yokuts Tribe P.O. Box 717 Linden, California, 95236

RE: Native American Outreach for the Insignia Collinsville Substation Project, Contra Costa and Solano Counties, California

Dear Timothy Perez,

PaleoWest, LLC (PaleoWest) is seeking any information you may have regarding Native American cultural resources in the vicinity of the 500/230 kV Collinsville Substation Project, which begins at the PG&E Pittsburg Substation in Contra Costa County, travels north for four miles across the Sacramento River, and ends at the proposed Collinsville substation site on the north bank of the river in Solano County. The project is depicted on the USGS *Honker Bay, CA* and *Antioch, CA,* topographic quadrangles, and on the enclosed maps. The project is subject to the California Environmental Quality Act (CEQA), with involvement from the U.S. Army Corps of Engineers (USACE) and California Public Utilities Commission (CPUC).

Terrestrial and marine archaeological surveys of the aboveground and submerged portions of the project area will be completed by qualified PaleoWest archaeologists later in the summer. Results of the records search indicate that five sites have been documented within the project area, and seven within a half-mile of the project area. Site types identified in the project area include two historic buildings, a historic structure, a historic site, and a precontact period isolated handstone. Results of the state shipwreck inventory search indicate that 37 wrecks have been documented in the underwater portion of the project area. A search of the Sacred Land File (SLF) by the Native American Heritage Commission (NAHC) was completed and the results were negative.

If you are aware of any Native American cultural resources or traditional cultural properties within or in the vicinity of the Project area shown on the enclosed maps, or if you have any concerns related to the overall Project, please contact me at 760-207-4242 or at my email address below. The information you provide will be used to assess areas of potential significant impact within the Project area, and any information provided will be confidential and not divulged to the public. We appreciate your time and assistance, and we greatly value any information you may provide.

Sincerely,

**PALEOWEST** 

Katherine Sinsky

Senior Archaeologist and Project Manager

760.207.4242



BAY AREA, CALIFORNIA 1870 Olympic Blvd, Suite 100 Walnut Creek, CA 94596

June 28, 2023

Katherine Perez, Chairperson North Valley Yokuts Tribe P.O. Box 717 Linden, California, 95236

RE: Native American Outreach for the Insignia Collinsville Substation Project, Contra Costa and Solano Counties, California

Dear Chairperson Perez,

PaleoWest, LLC (PaleoWest) is seeking any information you may have regarding Native American cultural resources in the vicinity of the 500/230 kV Collinsville Substation Project, which begins at the PG&E Pittsburg Substation in Contra Costa County, travels north for four miles across the Sacramento River, and ends at the proposed Collinsville substation site on the north bank of the river in Solano County. The project is depicted on the USGS *Honker Bay, CA* and *Antioch, CA,* topographic quadrangles, and on the enclosed maps. The project is subject to the California Environmental Quality Act (CEQA), with involvement from the U.S. Army Corps of Engineers (USACE) and California Public Utilities Commission (CPUC).

Terrestrial and marine archaeological surveys of the aboveground and submerged portions of the project area will be completed by qualified PaleoWest archaeologists later in the summer. Results of the records search indicate that five sites have been documented within the project area, and seven within a half-mile of the project area. Site types identified in the project area include two historic buildings, a historic structure, a historic site, and a precontact period isolated handstone. Results of the state shipwreck inventory search indicate that 37 wrecks have been documented in the underwater portion of the project area. A search of the Sacred Land File (SLF) by the Native American Heritage Commission (NAHC) was completed and the results were <u>negative</u>.

If you are aware of any Native American cultural resources or traditional cultural properties within or in the vicinity of the Project area shown on the enclosed maps, or if you have any concerns related to the overall Project, please contact me at 760-207-4242 or at my email address below. The information you provide will be used to assess areas of potential significant impact within the Project area, and any information provided will be confidential and not divulged to the public. We appreciate your time and assistance, and we greatly value any information you may provide.

Sincerely,

**PALEOWEST** 

Katherine Sinsky

Senior Archaeologist and Project Manager

760.207.4242



BAY AREA, CALIFORNIA 1870 Olympic Blvd, Suite 100 Walnut Creek, CA 94596

June 26, 2023

Desiree Vigil, THPO The Ohlone Indian Tribe 1775 Marco Polo Way, Apartment 21 Burlingame, California, 94010

RE: Native American Outreach for the Insignia Collinsville Substation Project, Contra Costa and Solano Counties, California

Dear Desiree Vigil,

PaleoWest, LLC (PaleoWest) is seeking any information you may have regarding Native American cultural resources in the vicinity of the 500/230 kV Collinsville Substation Project, which begins at the PG&E Pittsburg Substation in Contra Costa County, travels north for four miles across the Sacramento River, and ends at the proposed Collinsville substation site on the north bank of the river in Solano County. The project is depicted on the USGS *Honker Bay, CA* and *Antioch, CA,* topographic quadrangles, and on the enclosed maps. The project is subject to the California Environmental Quality Act (CEQA), with involvement from the U.S. Army Corps of Engineers (USACE) and California Public Utilities Commission (CPUC).

Terrestrial and marine archaeological surveys of the aboveground and submerged portions of the project area will be completed by qualified PaleoWest archaeologists later in the summer. Results of the records search indicate that five sites have been documented within the project area, and seven within a half-mile of the project area. Site types identified in the project area include two historic buildings, a historic structure, a historic site, and a precontact period isolated handstone. Results of the state shipwreck inventory search indicate that 37 wrecks have been documented in the underwater portion of the project area. A search of the Sacred Land File (SLF) by the Native American Heritage Commission (NAHC) was completed and the results were <u>negative</u>.

If you are aware of any Native American cultural resources or traditional cultural properties within or in the vicinity of the Project area shown on the enclosed maps, or if you have any concerns related to the overall Project, please contact me at 760-207-4242 or at my email address below. The information you provide will be used to assess areas of potential significant impact within the Project area, and any information provided will be confidential and not divulged to the public. We appreciate your time and assistance, and we greatly value any information you may provide.

Sincerely,

**PALEOWEST** 

Katherine Sinsky

Senior Archaeologist and Project Manager

760.207.4242



BAY AREA, CALIFORNIA 1870 Olympic Blvd, Suite 100 Walnut Creek, CA 94596

June 26, 2023

Andrew Galvan, Chairperson The Ohlone Indian Tribe P.O. Box 3388 Fremont, California, 94539

RE: Native American Outreach for the Insignia Collinsville Substation Project, Contra Costa and Solano Counties, California

Dear Chairperson Galvan,

PaleoWest, LLC (PaleoWest) is seeking any information you may have regarding Native American cultural resources in the vicinity of the 500/230 kV Collinsville Substation Project, which begins at the PG&E Pittsburg Substation in Contra Costa County, travels north for four miles across the Sacramento River, and ends at the proposed Collinsville substation site on the north bank of the river in Solano County. The project is depicted on the USGS *Honker Bay, CA* and *Antioch, CA,* topographic quadrangles, and on the enclosed maps. The project is subject to the California Environmental Quality Act (CEQA), with involvement from the U.S. Army Corps of Engineers (USACE) and California Public Utilities Commission (CPUC).

Terrestrial and marine archaeological surveys of the aboveground and submerged portions of the project area will be completed by qualified PaleoWest archaeologists later in the summer. Results of the records search indicate that five sites have been documented within the project area, and seven within a half-mile of the project area. Site types identified in the project area include two historic buildings, a historic structure, a historic site, and a precontact period isolated handstone. Results of the state shipwreck inventory search indicate that 37 wrecks have been documented in the underwater portion of the project area. A search of the Sacred Land File (SLF) by the Native American Heritage Commission (NAHC) was completed and the results were <u>negative</u>.

If you are aware of any Native American cultural resources or traditional cultural properties within or in the vicinity of the Project area shown on the enclosed maps, or if you have any concerns related to the overall Project, please contact me at 760-207-4242 or at my email address below. The information you provide will be used to assess areas of potential significant impact within the Project area, and any information provided will be confidential and not divulged to the public. We appreciate your time and assistance, and we greatly value any information you may provide.

Sincerely,

**PALEOWEST** 

Katherine Sinsky

Senior Archaeologist and Project Manager

760.207.4242



BAY AREA, CALIFORNIA 1870 Olympic Blvd, Suite 100 Walnut Creek, CA 94596

June 26, 2023

Gene Whitehouse, Chairperson United Auburn Indian Community of the Auburn Rancheria 10720 Indian Hill Road Auburn, California, 95603

RE: Native American Outreach for the Insignia Collinsville Substation Project, Contra Costa and Solano Counties, California

Dear Chairperson Whitehouse,

PaleoWest, LLC (PaleoWest) is seeking any information you may have regarding Native American cultural resources in the vicinity of the 500/230 kV Collinsville Substation Project, which begins at the PG&E Pittsburg Substation in Contra Costa County, travels north for four miles across the Sacramento River, and ends at the proposed Collinsville substation site on the north bank of the river in Solano County. The project is depicted on the USGS *Honker Bay, CA* and *Antioch, CA,* topographic quadrangles, and on the enclosed maps. The project is subject to the California Environmental Quality Act (CEQA), with involvement from the U.S. Army Corps of Engineers (USACE) and California Public Utilities Commission (CPUC).

Terrestrial and marine archaeological surveys of the aboveground and submerged portions of the project area will be completed by qualified PaleoWest archaeologists later in the summer. Results of the records search indicate that five sites have been documented within the project area, and seven within a half-mile of the project area. Site types identified in the project area include two historic buildings, a historic structure, a historic site, and a precontact period isolated handstone. Results of the state shipwreck inventory search indicate that 37 wrecks have been documented in the underwater portion of the project area. A search of the Sacred Land File (SLF) by the Native American Heritage Commission (NAHC) was completed and the results were negative.

If you are aware of any Native American cultural resources or traditional cultural properties within or in the vicinity of the Project area shown on the enclosed maps, or if you have any concerns related to the overall Project, please contact me at 760-207-4242 or at my email address below. The information you provide will be used to assess areas of potential significant impact within the Project area, and any information provided will be confidential and not divulged to the public. We appreciate your time and assistance, and we greatly value any information you may provide.

Sincerely,

**PALEOWEST** 

Katherine Sinsky

Senior Archaeologist and Project Manager

760.207.4242



BAY AREA, CALIFORNIA 1870 Olympic Blvd, Suite 100 Walnut Creek, CA 94596

June 26, 2023

Jesus Tarango, Chairperson Wilton Rancheria 9728 Kent Street Elk Grove, California, 95624

RE: Native American Outreach for the Insignia Collinsville Substation Project, Contra Costa and Solano Counties, California

Dear Chairperson Tarango,

PaleoWest, LLC (PaleoWest) is seeking any information you may have regarding Native American cultural resources in the vicinity of the 500/230 kV Collinsville Substation Project, which begins at the PG&E Pittsburg Substation in Contra Costa County, travels north for four miles across the Sacramento River, and ends at the proposed Collinsville substation site on the north bank of the river in Solano County. The project is depicted on the USGS *Honker Bay, CA* and *Antioch, CA,* topographic quadrangles, and on the enclosed maps. The project is subject to the California Environmental Quality Act (CEQA), with involvement from the U.S. Army Corps of Engineers (USACE) and California Public Utilities Commission (CPUC).

Terrestrial and marine archaeological surveys of the aboveground and submerged portions of the project area will be completed by qualified PaleoWest archaeologists later in the summer. Results of the records search indicate that five sites have been documented within the project area, and seven within a half-mile of the project area. Site types identified in the project area include two historic buildings, a historic structure, a historic site, and a precontact period isolated handstone. Results of the state shipwreck inventory search indicate that 37 wrecks have been documented in the underwater portion of the project area. A search of the Sacred Land File (SLF) by the Native American Heritage Commission (NAHC) was completed and the results were <u>negative</u>.

If you are aware of any Native American cultural resources or traditional cultural properties within or in the vicinity of the Project area shown on the enclosed maps, or if you have any concerns related to the overall Project, please contact me at 760-207-4242 or at my email address below. The information you provide will be used to assess areas of potential significant impact within the Project area, and any information provided will be confidential and not divulged to the public. We appreciate your time and assistance, and we greatly value any information you may provide.

Sincerely,

**PALEOWEST** 

Katherine Sinsky

Senior Archaeologist and Project Manager

760.207.4242



BAY AREA, CALIFORNIA 1870 Olympic Blvd, Suite 100 Walnut Creek, CA 94596

June 26, 2023

Dahlton Brown, Director of Administration Wilton Rancheria 9728 Kent Street, Elk Grove, California, 95624

RE: Native American Outreach for the Insignia Collinsville Substation Project, Contra Costa and Solano Counties, California

Dear Director Brown,

PaleoWest, LLC (PaleoWest) is seeking any information you may have regarding Native American cultural resources in the vicinity of the 500/230 kV Collinsville Substation Project, which begins at the PG&E Pittsburg Substation in Contra Costa County, travels north for four miles across the Sacramento River, and ends at the proposed Collinsville substation site on the north bank of the river in Solano County. The project is depicted on the USGS *Honker Bay, CA* and *Antioch, CA,* topographic quadrangles, and on the enclosed maps. The project is subject to the California Environmental Quality Act (CEQA), with involvement from the U.S. Army Corps of Engineers (USACE) and California Public Utilities Commission (CPUC).

Terrestrial and marine archaeological surveys of the aboveground and submerged portions of the project area will be completed by qualified PaleoWest archaeologists later in the summer. Results of the records search indicate that five sites have been documented within the project area, and seven within a half-mile of the project area. Site types identified in the project area include two historic buildings, a historic structure, a historic site, and a precontact period isolated handstone. Results of the state shipwreck inventory search indicate that 37 wrecks have been documented in the underwater portion of the project area. A search of the Sacred Land File (SLF) by the Native American Heritage Commission (NAHC) was completed and the results were <u>negative</u>.

If you are aware of any Native American cultural resources or traditional cultural properties within or in the vicinity of the Project area shown on the enclosed maps, or if you have any concerns related to the overall Project, please contact me at 760-207-4242 or at my email address below. The information you provide will be used to assess areas of potential significant impact within the Project area, and any information provided will be confidential and not divulged to the public. We appreciate your time and assistance, and we greatly value any information you may provide.

Sincerely,

**PALEOWEST** 

Katherine Sinsky

Senior Archaeologist and Project Manager

760.207.4242



BAY AREA, CALIFORNIA 1870 Olympic Blvd, Suite 100 Walnut Creek, CA 94596

June 26, 2023

Steve Hutchason, THPO Wilton Rancheria 9728 Kent Street Elk Grove, California, 95624

RE: Native American Outreach for the Insignia Collinsville Substation Project, Contra Costa and Solano Counties, California

Dear Steve Hutchason,

PaleoWest, LLC (PaleoWest) is seeking any information you may have regarding Native American cultural resources in the vicinity of the 500/230 kV Collinsville Substation Project, which begins at the PG&E Pittsburg Substation in Contra Costa County, travels north for four miles across the Sacramento River, and ends at the proposed Collinsville substation site on the north bank of the river in Solano County. The project is depicted on the USGS *Honker Bay, CA* and *Antioch, CA,* topographic quadrangles, and on the enclosed maps. The project is subject to the California Environmental Quality Act (CEQA), with involvement from the U.S. Army Corps of Engineers (USACE) and California Public Utilities Commission (CPUC).

Terrestrial and marine archaeological surveys of the aboveground and submerged portions of the project area will be completed by qualified PaleoWest archaeologists later in the summer. Results of the records search indicate that five sites have been documented within the project area, and seven within a half-mile of the project area. Site types identified in the project area include two historic buildings, a historic structure, a historic site, and a precontact period isolated handstone. Results of the state shipwreck inventory search indicate that 37 wrecks have been documented in the underwater portion of the project area. A search of the Sacred Land File (SLF) by the Native American Heritage Commission (NAHC) was completed and the results were negative.

If you are aware of any Native American cultural resources or traditional cultural properties within or in the vicinity of the Project area shown on the enclosed maps, or if you have any concerns related to the overall Project, please contact me at 760-207-4242 or at my email address below. The information you provide will be used to assess areas of potential significant impact within the Project area, and any information provided will be confidential and not divulged to the public. We appreciate your time and assistance, and we greatly value any information you may provide.

Sincerely,

**PALEOWEST** 

Katherine Sinsky

Senior Archaeologist and Project Manager

760.207.4242



BAY AREA, CALIFORNIA 1870 Olympic Blvd, Suite 100 Walnut Creek, CA 94596

June 26, 2023

Anthony Roberts, Chairperson Yocha Dehe Wintun Nation P.O. Box 18 Brooks, California, 95606

RE: Native American Outreach for the Insignia Collinsville Substation Project, Contra Costa and Solano Counties. California

Dear Chairperson Roberts,

PaleoWest, LLC (PaleoWest) is seeking any information you may have regarding Native American cultural resources in the vicinity of the 500/230 kV Collinsville Substation Project, which begins at the PG&E Pittsburg Substation in Contra Costa County, travels north for four miles across the Sacramento River, and ends at the proposed Collinsville substation site on the north bank of the river in Solano County. The project is depicted on the USGS *Honker Bay, CA* and *Antioch, CA,* topographic quadrangles, and on the enclosed maps. The project is subject to the California Environmental Quality Act (CEQA), with involvement from the U.S. Army Corps of Engineers (USACE) and California Public Utilities Commission (CPUC).

Terrestrial and marine archaeological surveys of the aboveground and submerged portions of the project area will be completed by qualified PaleoWest archaeologists later in the summer. Results of the records search indicate that five sites have been documented within the project area, and seven within a half-mile of the project area. Site types identified in the project area include two historic buildings, a historic structure, a historic site, and a precontact period isolated handstone. Results of the state shipwreck inventory search indicate that 37 wrecks have been documented in the underwater portion of the project area. A search of the Sacred Land File (SLF) by the Native American Heritage Commission (NAHC) was completed and the results were negative.

If you are aware of any Native American cultural resources or traditional cultural properties within or in the vicinity of the Project area shown on the enclosed maps, or if you have any concerns related to the overall Project, please contact me at 760-207-4242 or at my email address below. The information you provide will be used to assess areas of potential significant impact within the Project area, and any information provided will be confidential and not divulged to the public. We appreciate your time and assistance, and we greatly value any information you may provide.

Sincerely,

**PALEOWEST** 

Katherine Sinsky

Senior Archaeologist and Project Manager

760.207.4242



BAY AREA, CALIFORNIA 1870 Olympic Blvd, Suite 100 Walnut Creek, CA 94596

June 26, 2023

Yvonne Perkins, THPO, Cultural Resources Chairman Yocha Dehe Wintun Nation P.O. Box 18 Brooks, California, 95606

RE: Native American Outreach for the Insignia Collinsville Substation Project, Contra Costa and Solano Counties, California

Dear Chairman Perkins,

PaleoWest, LLC (PaleoWest) is seeking any information you may have regarding Native American cultural resources in the vicinity of the 500/230 kV Collinsville Substation Project, which begins at the PG&E Pittsburg Substation in Contra Costa County, travels north for four miles across the Sacramento River, and ends at the proposed Collinsville substation site on the north bank of the river in Solano County. The project is depicted on the USGS *Honker Bay, CA* and *Antioch, CA,* topographic quadrangles, and on the enclosed maps. The project is subject to the California Environmental Quality Act (CEQA), with involvement from the U.S. Army Corps of Engineers (USACE) and California Public Utilities Commission (CPUC).

Terrestrial and marine archaeological surveys of the aboveground and submerged portions of the project area will be completed by qualified PaleoWest archaeologists later in the summer. Results of the records search indicate that five sites have been documented within the project area, and seven within a half-mile of the project area. Site types identified in the project area include two historic buildings, a historic structure, a historic site, and a precontact period isolated handstone. Results of the state shipwreck inventory search indicate that 37 wrecks have been documented in the underwater portion of the project area. A search of the Sacred Land File (SLF) by the Native American Heritage Commission (NAHC) was completed and the results were <u>negative</u>.

If you are aware of any Native American cultural resources or traditional cultural properties within or in the vicinity of the Project area shown on the enclosed maps, or if you have any concerns related to the overall Project, please contact me at 760-207-4242 or at my email address below. The information you provide will be used to assess areas of potential significant impact within the Project area, and any information provided will be confidential and not divulged to the public. We appreciate your time and assistance, and we greatly value any information you may provide.

Sincerely,

**PALEOWEST** 

Katherine Sinsky

Senior Archaeologist and Project Manager

760.207.4242



August 21, 2023

Paleo West Attn: Katherine Sinsky, Senior Archaeologist 1870 Olympic Blvd, Suite 100 Walnut Creek, CA 94596

RE: Insignia Collinsville Substation Project YD-07132023-02

Dear Ms. Sinsky:

Thank you for the project notification dated June 26, 2023, regarding cultural information on or near the proposed Insignia Collinsville Substation Project. We appreciate your effort to contact us and wish to respond.

The Cultural Resources Department has reviewed the project and concluded that it is within the aboriginal territories of the Yocha Dehe Wintun Nation. Therefore, we have a cultural interest and authority in the proposed project area and would like to initiate a formal consultation with the lead agency. At the time of consultation, please provide our Cultural Resources Department with a project timeline, detailed project information and the latest cultural study for the proposed project.

To coordinate a date and time for the consultation meeting, please contact:

CRD Administrative Staff Yocha Dehe Wintun Nation

Office: (530) 796-3400

Email: THPO@yochadehe.gov

Please refer to identification number YD-07132023-02 in any correspondence concerning this project.

Thank you for providing us the opportunity to comment.

Sincerely,

DocuSigned by:

Guonne Perkins

Tribal Historic Preservation Officer



BAY AREA, CALIFORNIA 1870 Olympic Blvd, Suite 100 Walnut Creek, CA 94596

June 26, 2023

Corrina Gould, Chairperson Confederated Villages of Lisjan Nation 10926 Edes Avenue Oakland, California 94603

RE: Native American Outreach for the Insignia Collinsville Substation Project, Contra Costa and Solano Counties, California

Dear Chairperson Gould,

PaleoWest, LLC (PaleoWest) is seeking any information you may have regarding Native American cultural resources in the vicinity of the 500/230 kV Collinsville Substation Project, which begins at the PG&E Pittsburg Substation in Contra Costa County, travels north for four miles across the Sacramento River, and ends at the proposed Collinsville substation site on the north bank of the river in Solano County. The project is depicted on the USGS *Honker Bay, CA* and *Antioch, CA,* topographic quadrangles, and on the enclosed maps. The project is subject to the California Environmental Quality Act (CEQA), with involvement from the U.S. Army Corps of Engineers (USACE) and California Public Utilities Commission (CPUC).

Terrestrial and marine archaeological surveys of the aboveground and submerged portions of the project area will be completed by qualified PaleoWest archaeologists later in the summer. Results of the records search indicate that five sites have been documented within the project area, and seven within a half-mile of the project area. Site types identified in the project area include two historic buildings, a historic structure, a historic site, and a precontact period isolated handstone. Results of the state shipwreck inventory search indicate that 37 wrecks have been documented in the underwater portion of the project area. A search of the Sacred Land File (SLF) by the Native American Heritage Commission (NAHC) was completed and the results were <u>negative</u>.

If you are aware of any Native American cultural resources or traditional cultural properties within or in the vicinity of the Project area shown on the enclosed maps, or if you have any concerns related to the overall Project, please contact me at 760-207-4242 or at my email address below. The information you provide will be used to assess areas of potential significant impact within the Project area, and any information provided will be confidential and not divulged to the public. We appreciate your time and assistance, and we greatly value any information you may provide.

Sincerely,

**PALEOWEST** 

Katherine Sinsky

Senior Archaeologist and Project Manager

760.207.4242



BAY AREA, CALIFORNIA 1870 Olympic Blvd, Suite 100 Walnut Creek, CA 94596

June 26, 2023

Deja Gould, Language Program Manager Confederated Villages of Lisjan Nation 10926 Edes Avenue Oakland, California, 94603

RE: Native American Outreach for the Insignia Collinsville Substation Project, Contra Costa and Solano Counties, California

Dear Deja Gould,

PaleoWest, LLC (PaleoWest) is seeking any information you may have regarding Native American cultural resources in the vicinity of the 500/230 kV Collinsville Substation Project, which begins at the PG&E Pittsburg Substation in Contra Costa County, travels north for four miles across the Sacramento River, and ends at the proposed Collinsville substation site on the north bank of the river in Solano County. The project is depicted on the USGS *Honker Bay, CA* and *Antioch, CA,* topographic quadrangles, and on the enclosed maps. The project is subject to the California Environmental Quality Act (CEQA), with involvement from the U.S. Army Corps of Engineers (USACE) and California Public Utilities Commission (CPUC).

Terrestrial and marine archaeological surveys of the aboveground and submerged portions of the project area will be completed by qualified PaleoWest archaeologists later in the summer. Results of the records search indicate that five sites have been documented within the project area, and seven within a half-mile of the project area. Site types identified in the project area include two historic buildings, a historic structure, a historic site, and a precontact period isolated handstone. Results of the state shipwreck inventory search indicate that 37 wrecks have been documented in the underwater portion of the project area. A search of the Sacred Land File (SLF) by the Native American Heritage Commission (NAHC) was completed and the results were <u>negative</u>.

If you are aware of any Native American cultural resources or traditional cultural properties within or in the vicinity of the Project area shown on the enclosed maps, or if you have any concerns related to the overall Project, please contact me at 760-207-4242 or at my email address below. The information you provide will be used to assess areas of potential significant impact within the Project area, and any information provided will be confidential and not divulged to the public. We appreciate your time and assistance, and we greatly value any information you may provide.

Sincerely,

**PALEOWEST** 

Katherine Sinsky

Senior Archaeologist and Project Manager

760.207.4242