



United States  
Department of  
Agriculture

Forest  
Service

Cleveland National  
Forest

Descanso Ranger District  
3348 Alpine Blvd.  
Alpine, CA 91901-3923  
(619) 445-6235  
(619) 445-1753 FAX  
CRS 1-800-735-2922

---

File Code: 2720

Date: October 20, 2011

Gerry Akin  
Project Manager - Sunrise Overhead  
San Diego Gas & Electric Company  
8315 Century Park Court, CP21E  
San Diego, CA 92123

Dear Mr. Akin:

SDG&E's October 19, 2011 request to continue work until 1:00 PM (1300hours) on level Ev Project Activity Level (PAL) days has been reviewed by Forest Service staff assigned to the project.

You may work at the sites listed below until 1:00 PM on PAL Ev days under the following conditions: 1) Compliance with the Special Use Permit Fire Plan (Exhibit 9). 2) Compliance with all previous project variance permissions. 3) Adherence to fire mitigation measures previously proposed by SDG&E as approved by the Forest Service. A copy of this variance letter and the Fire Plan shall be at each worksite.

The following operations may proceed until 1:00 PM on PAL Ev days under the cumulative restrictions of PAL from A through Ev and use of the following staffed and operational fire equipment at each active work site: One 2000 to 4000 gallon water truck; a full time fire watch with a type 6 brush patrol carrying a minimum of 300 gallons of water or water trailer with a minimum of 300 gallons of water as described in Section 3 of the Fire Plan; appropriate fire tools kept within 25 feet of operations at all times. All fire equipment is to remain on site during operations and at least two hours past the end of the work day. A fire marshal shall patrol the area and monitor weather conditions. For mowing, mastication, and/or welding operations, an attended charged one inch or greater fire hose able to reach 100 feet beyond the work area will be utilized with wetting of the work area before, during, and after operations.

- 1) *Gate and barrier installation at CP69-3 and along La Posta Road:* **No variance for PAL level Ev.** Materials used for gates and barriers shall be installed as agreed upon by the Forest Service. Vegetation two inches in diameter or greater shall be cleared by hand with above ground stems 6-8 inches long and an intact root system left in place. All other vegetation shall be cleared in accordance with the Forest Service issued welding permit. The welding permit is required for welding, cutting or grinding, and is valid only on PAL days A-D. Operations must comply with Sections 3, 4 and Attachment 1 of the Fire Plan.

The following operations may proceed until 1:00 PM on PAL Ev days under the cumulative restrictions of PAL from A through Ev and use of the following staffed and operational fire equipment at each active work site: A fly box or fire box equipped with hand tools for all



workers as described in Section 3 of the Fire Plan; a designated fire patrol person to patrol all active work sites and two hours after the end of work.

- 2) *Hand clearing of vegetation (Non- Mechanized/ No Chainsaw) at TSAP's & Remote Tower Sites. **Approved project wide.***
- 3) *Hand clearing of vegetation (Non- Mechanized/ No Chain Saw) for egress routes at micro-pile sites. **Approved project wide.***
- 4) *Installation, maintenance and inspection of BMP's: **Approved project wide.***
- 5) *Mobilization/Removal of Equipment from Micro pile Sites: **Approved project wide.***
- 6) *Hydro mulching: **Approved project wide at vehicle accessible project areas where slope stabilization is necessary.***
- 7) *Rehabilitation and Transplanting work at all sites: **Approved project wide.***

The following operations may proceed until 1:00 PM on PAL Ev days under the cumulative restrictions of PAL from A through Ev, compliance with the Fire Plan, this variance notice, and use of the following staffed and operational fire equipment at each active work site.

For all sites the following applies: A fly box or fire box that includes tools as described in Section 3 of the Fire Plan for the number of personnel present; an onsite water tank, water truck, or trailer with a minimum of 300 gallons of water in reserve at all times for fire protection; a pump having a minimum rating of 23 gallons per minute at 175 psi pump pressure at sea level with a minimum one inch hose filled/ primed with water capable of reaching 100 feet past the work area. All activities shall comply with proper brush clearances as specified in the Fire Plan. For boulder breaking activities the work area will be cleared of flammable vegetation for a 10 foot radius and wet down for a 25 foot radius before, during, and after operations. A designated fire patrol person will be on site during work activities and two hours after the end of work. Notification will be made to the Forest Service 24 hours prior to start of work to allow opportunity for pre-inspection of equipment going to remote sites.

- 8) *Micro-pile foundation construction: Egress routes shall be established on the ground and clearly identifiable at all times. A map of the egress routes shall be provided to the Forest Service. Construction may occur on a site by site basis as follows:*
  - a) **HIGH FIRE DANGER AREAS;** La Posta Road Area limited to two (2) simultaneous sites per operational period or work day, this includes all sites between EP 107 and EP 141; the area between Lyon Valley Road and Japatul Road are limited to two (2) simultaneous sites per operational period or work day, this includes all sites between EP 11-3 and EP 24-1.....**AND**
  - b) **LOW TO MODERATE FIRE HAZARD AREAS;** All areas along the powerlink corridor located outside of the High Fire Danger Areas. These areas are limited to six (6) or less sites per operational period or work day.

**OR**


- c) La Posta Road Area work limited to four simultaneous micro-pile sites per operational period or work day. A minimum distance of .36 miles upslope from or adjacent to other work locations shall be maintained.

9) *Grading at TSAP's*: **No Ev variance.**

Also renewed are those work activities included in the Forest Service August 17<sup>th</sup> & 25<sup>th</sup>, September 1<sup>st</sup>, 8<sup>th</sup>, 15<sup>th</sup>, and 29<sup>th</sup>, October 6<sup>th</sup>, 13<sup>th</sup>, 2011 responses to SDG&E requests to continue work until 1:00 PM on PAL Ev days.

All SDG&E activities are subject to the PAL for Forest Service Area 685, the terms and conditions of the special use permit, project plans, and exhibits. Variances may be issued to SDG&E before the close of business every Thursday and are good for the next seven day period (October 21<sup>st</sup> thru October 27<sup>th</sup>). This variance may be rescinded at anytime by the Forest Service. If you have questions contact Brian Paul, Sunrise Project Manager at (619) 445-6235.

Sincerely,



JOHN TRUETT  
Acting District Ranger  
Sunrise Powerlink Project

Cc: SO Lands & Engineering