

Southern California Edison
MESA PTC A.15-03-003

DATA REQUEST SET A.15-03-003 ED-SCE-01

To: ENERGY DIVISION
Prepared by: Scott Lacy, P.E.
Title: Project Engineer
Dated: 05/22/2015

Question Q.34:

Cumulative Project--Mesa - Rush No. 3 Line Subtransmission

Provide additional details as to what the project entails, the project alignment, and when construction of the project is anticipated to start and end.

Response to Question Q.34:

The scope of work associated with reconductoring a portion of the existing Mesa-Rush #3 66 kV subtransmission line consists of installing approximately 0.5 miles of new underground ducts and vaults (including one new riser TSP) along Rush Street between San Gabriel Boulevard and Walnut Grove Avenue, followed by the installation and splicing of new cable.

Construction of this work is expected to begin in the 4th quarter of 2015 and be complete by the end of the 2nd quarter of 2016.