Draft Environmental Impact Report Appendices

SCE Ivanpah-Control Project

State Clearinghouse #2020080553




Prepared by

California Public
Utilities Commission

March 2026

Appendix 1

DETAILED PROJECT MAPS

This appendix contains the following information:

Segment 1 Strip Maps. 1-1
Segment 2 Strip Maps. 1-27
Segment 3N Strip Maps. 1-37
Segment 3S Strip Maps. 1-45



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed

- Milepost (1.0)
- Substation

Ivanpah-Control Proposed Project Segments
- Segment 1: Control-Haiwee-Inyokern

Roads
- Existing Access Road
- New Access Road

Segment 1 Strip Map

Sheet 1 of 26

Land Management/Ownership
- Bureau of Land Management
- LADWP and Local Government
- USDA Forest Service

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed

Milepost (1.0)

Ivanpah-Control Proposed Project Segments
- Segment 1: Control-Haiwee-Inyokern

Roads
- Existing Access Road
- New Access Road

Segment 1 Strip Map

Sheet 2 of 26

Land Management/Ownership
- Bureau of Land Management
- LADWP and Local Government
- USDA Forest Service

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Milepost (1.0)

Ivanpah-Control Proposed Project Segments

Segment 1: Control-Haiwee-Inyokern

Subtransmission Structures

Proposed New Structure

Structure to be Removed

Roads

Existing Access Road

New Access Road

Land Management/Ownership

Bureau of Land Management

LADWP and Local Government

USDA Forest Service

Segment 1 Strip Map

Sheet 3 of 26

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed

Milepost (1.0)

Ivanpah-Control Proposed Project Segments
- Segment 1: Control-Haiwee-Inyokern

Roads
- Existing Access Road
- New Access Road

Land Management/Ownership
- Bureau of Land Management
- LADWP and Local Government
- USDA Forest Service

Segment 1 Strip Map

Sheet 4 of 26

1:24,000

N 0 2,000 Feet



Segment 1 Strip Map

Sheet 5 of 26



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed

Milepost (1.0)

Ivanpah-Control Proposed Project Segments
- Segment 1: Control-Haiwee-Inyokern

Ivanpah-Control Project Alternatives
- Crater Mountain Realignment Alternative

Roads
- Existing Access Road
- New Access Road

Land Management/Ownership
- Bureau of Land Management
- LADWP and Local Government

Segment 1 Strip Map

Sheet 6 of 26

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed

Milepost (1.0)

Ivanpah-Control Proposed Project Segments
- Segment 1: Control-Haiwee-Inyokern

Ivanpah-Control Project Alternatives
- Crater Mountain Realignment Alternative

Roads
- Existing Access Road
- New Access Road

Land Management/Ownership
- Bureau of Land Management
- LADWP and Local Government

Segment 1 Strip Map

Sheet 7 of 26

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed

Milepost (1.0)

Ivanpah-Control Proposed Project Segments
- Segment 1: Control-Haiwee-Inyokern

Ivanpah-Control Project Alternatives
- Crater Mountain Realignment Alternative
- Manzanar Realignment Alternative

Roads
- Existing Access Road
- New Access Road

Land Management/Ownership
- Bureau of Land Management
- LADWP and Local Government
- USDA Forest Service

Segment 1 Strip Map

Sheet 8 of 26

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed

Milepost (1.0)

Ivanpah-Control Proposed Project Segments
- Segment 1: Control-Haiwee-Inyokern

Ivanpah-Control Project Alternatives
- Manzanar Realignment Alternative

Roads
- Existing Access Road
- New Access Road

Segment 1 Strip Map

Sheet 9 of 26

Land Management/Ownership
- Bureau of Land Management
- LADWP and Local Government
- USDA Forest Service

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed

- Milepost (1.0)
- Independence Telecommunications Tap
- Independence Telecommunications Tap: Alternative

Ivanpah-Control Proposed Project Segments
- Segment 1: Control-Haiwee-Inyokern

Ivanpah-Control Project Alternatives
- Manzanar Realignment Alternative

Roads
- Existing Access Road

Segment 1 Strip Map

Sheet 10 of 26

Land Management/Ownership
- Bureau of Land Management
- LADWP and Local Government

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed

Milepost (1.0)

Ivanpah-Control Proposed Project Segments
- Segment 1: Control-Haiwee-Inyokern

Ivanpah-Control Project Alternatives
- Manzanar Realignment Alternative

Roads
- Existing Access Road
- New Access Road

Segment 1 Strip Map

Sheet 11 of 26

Land Management/Ownership
- Bureau of Land Management
- LADWP and Local Government

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Milepost (1.0)

Subtransmission Structures

- Proposed New Structure
- Structure to be Removed

Ivanpah-Control Proposed Project Segments

- Segment 1: Control-Haiwee-Inyokern

Ivanpah-Control Project Alternatives

- Manzanar Realignment Alternative

Roads

- Existing Access Road
- New Access Road

Land Management/Ownership

- Bureau of Land Management
- LADWP and Local Government

Segment 1 Strip Map

Sheet 12 of 26

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Milepost (1.0)

Ivanpah-Control Proposed Project Segments

Segment 1: Control-Haiwee-Inyokern

Ivanpah-Control Project Alternatives

Manzanar Realignment Alternative

Roads

Existing Access Road

Subtransmission Structures

Proposed New Structure

Structure to be Removed

Land Management/Ownership

Bureau of Land Management

LADWP and Local Government

Segment 1 Strip Map

Sheet 13 of 26

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed

Milepost (1.0)

Ivanpah-Control Proposed Project Segments
- Segment 1: Control-Haiwee-Inyokern

Ivanpah-Control Project Alternatives
- Manzanar Realignment Alternative

Roads
- Existing Access Road
- New Access Road

Segment 1 Strip Map

Sheet 14 of 26

Land Management/Ownership
- Bureau of Land Management
- LADWP and Local Government
- State

1:24,000

N

0 2,000 Feet



Segment 1 Strip Map

Sheet 15 of 26



Segment 1 Strip Map

Sheet 16 of 26



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed

Milepost (1.0)

Ivanpah-Control Proposed Project Segments
- Segment 1: Control-Haiwee-Inyokern

Roads
- Existing Access Road
- New Access Road

Segment 1 Strip Map

Sheet 17 of 26

Land Management/Ownership
- Bureau of Land Management
- LADWP and Local Government
- State
- USDA Forest Service

N

1:24,000

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed

Milepost (1.0)

Ivanpah-Control Proposed Project Segments
- Segment 1: Control-Haiwee-Inyokern

Roads
- Existing Access Road
- New Access Road

Land Management/Ownership
- Bureau of Land Management
- LADWP and Local Government
- State

Segment 1 Strip Map

Sheet 18 of 26

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Segment 1 Strip Map

Sheet 19 of 26



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures

- Proposed New Structure
- Structure to be Removed

- Milepost (1.0)
- Substation

Ivanpah-Control Proposed Project Segments

- Segment 1: Control-Haiwee-Inyokern

Ivanpah-Control Project Alternatives

- Fossil Falls Realignment Alternative

Roads

- Existing Access Road
- New Access Road

Land Management/Ownership

- Bureau of Land Management
- LADWP and Local Government

Segment 1 Strip Map

Sheet 20 of 26

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed

- Milepost (1.0)
- Substation

Ivanpah-Control Proposed Project Segments
- Segment 1: Control-Haiwee-Inyokern

Ivanpah-Control Project Alternatives
- Fossil Falls Realignment Alternative

Roads
- Existing Access Road

Land Management/Ownership
- Bureau of Land Management

Segment 1 Strip Map

Sheet 21 of 26

1:24,000
N
0
2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed

Milepost (1.0)

Ivanpah-Control Proposed Project Segments
- Segment 1: Control-Haiwee-Inyokern

Ivanpah-Control Project Alternatives
- Fossil Falls Realignment Alternative

Roads
- Existing Access Road
- New Access Road

Segment 1 Strip Map

Sheet 22 of 26

Land Management/Ownership
- Bureau of Land Management
- Military

1:24,000
N
0
2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Segment 1 Strip Map

Sheet 23 of 26



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures

- Proposed New Structure
- Structure to be Removed

- Milepost (1.0)

Ivanpah-Control Proposed Project Segments

- Segment 1: Control-Haiwee-Inyokern

Roads

- Existing Access Road
- New Access Road

Land Management/Ownership

- Bureau of Land Management
- Military
- State

Segment 1 Strip Map

Sheet 24 of 26

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed

Milepost (1.0)

Ivanpah-Control Proposed Project Segments
- Segment 1: Control-Haiwee-Inyokern

Roads
- Existing Access Road

Land Management/Ownership
- Bureau of Land Management
- Military

Segment 1 Strip Map

Sheet 25 of 26

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed

- Milepost (1.0)
- Substation

Ivanpah-Control Proposed Project Segments
- Segment 1: Control-Haiwee-Inyokern
- Segment 2: Inyokern-Kramer

Roads
- Existing Access Road
- New Access Road

Land Management/Ownership
- Bureau of Land Management
- Military

Segment 1 Strip Map

Sheet 26 of 26

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Segment 2 Strip Map

Sheet 1 of 10

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed

- Milepost (1.0)
- Substation
- Segment 1: Control-Haiwee-Inyokern
- Segment 2: Inyokern-Kramer

Land Management/Ownership
- Bureau of Land Management
- Military
- State

Roads
- Existing Access Road

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Segment 2 Strip Map

Sheet 2 of 10

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed

- Milepost (1.0)
- Segment 2: Inyokern-Kramer

Land Management/Ownership
- Bureau of Land Management

Roads
- Existing Access Road

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Segment 2 Strip Map

Sheet 3 of 10

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed

- Milepost (1.0)
- Segment 2: Inyokern-Kramer

Land Management/Ownership
- Bureau of Land Management

Roads
- Existing Access Road
- New Access Road

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Segment 2 Strip Map

Sheet 4 of 10

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed

- Milepost (1.0)
- Segment 2: Inyokern-Kramer

Land Management/Ownership
- Bureau of Land Management

Roads
- Existing Access Road
- New Access Road
- Railroad

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Segment 2 Strip Map

Sheet 5 of 10

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed
- Milepost (1.0)
- Substation
- Segment 2: Inyokern-Kramer

Land Management/Ownership
- Bureau of Land Management

Roads
- Existing Access Road
- New Access Road

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Segment 2 Strip Map

Sheet 6 of 10

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed

- Milepost (1.0)
- Segment 2: Inyokern-Kramer

Land Management/Ownership
- Bureau of Land Management

Roads
- Existing Access Road

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Segment 2 Strip Map

Sheet 7 of 10

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed

- Milepost (1.0)
- Segment 2: Inyokern-Kramer

Land Management/Ownership
- Bureau of Land Management

Roads
- Existing Access Road
- New Access Road

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024;
ESRI, 2024; SCE, 2024.

Segment 2 Strip Map

Sheet 8 of 10

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed

- Milepost (1.0)
- Segment 2: Inyokern-Kramer

Land Management/Ownership
- Bureau of Land Management

Roads
- Existing Access Road
- New Access Road

1:24,000

N 0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Segment 2 Strip Map

Sheet 9 of 10

Subtransmission Structures
- Proposed New Structure
- Structure to be Removed

- Milepost (1.0)
- Segment 2: Inyokern-Kramer

Land Management/Ownership
- Bureau of Land Management
- Military

Roads
- Existing Access Road
- New Access Road

1:24,000

N

0 2,000 Feet


Segment 2
Map Extent
Inyokern
Substation
14
California City
58
Kramer
Substation
395
121346
121347
121348
121349
45
121350
121351
121352
121353
121354
121355
121356
121357
121358
121359
121360
46
121361
121362
121363
121364
121365
121366
121367
121368
47
121369
121370
121371
121372
121373
1
2
48
121374
121375
58
121376
1883326E
0
Kramer
Substation
0
395
1
Sources: Aspen, 2024; BLM, 2024;
ESRI, 2024; SCE, 2024.
Subtransmission Structures
Existing Structure
Proposed New Structure
Structure to be Removed
Milepost (1.0)
Substation
Segment 2: Inyokern-Kramer
Segment 3N: Kramer-Coolwater
Segment 3S: Kramer-Tortilla-Coolwater
Land Management/Ownership
Bureau of Land Management
Military
Roads
Existing Access Road
New Access Road
Railroad
Segment 2 Strip Map
Sheet 10 of 10
1:24,000
N
0
2,000
Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Existing Structure
- Proposed New Structure
- Structure to be Removed

- Milepost (1.0)
- Substation
- Segment 2: Inyokern-Kramer
- Segment 3N: Kramer-Coolwater
- Segment 3S: Kramer-Tortilla-Coolwater

Roads
- Existing Access Road
- New Access Road
- Railroad

Land Management/Ownership
- Bureau of Land Management
- Military

Segment 3N Strip Map

Sheet 1 of 8

1:24,000

N 0 2,000 Feet



6

7

8

9

10

11

Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures

- Existing Structure

- Milepost (1.0)
- Segment 3N: Kramer-Coolwater

Roads

- Existing Access Road

Land Management/Ownership

- Bureau of Land Management

Segment 3N Strip Map

Sheet 2 of 8

1:24,000

N 0 2,000 Feet



12

13

14

15

16

17

Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Existing Structure
- New-Remove-Existing

- Milepost (1.0)
- Segment 3N: Kramer-Coolwater

Roads
- Existing Access Road

Land Management/Ownership
- Bureau of Land Management
- Military

Segment 3N Strip Map

Sheet 3 of 8

1:24,000

N

0 2,000 Feet



18

19

20

21

22

23

Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Existing Structure
- New-Remove-Existing

- Milepost (1.0)
- Segment 3N: Kramer-Coolwater

Roads
- Existing Access Road

Land Management/Ownership
- Bureau of Land Management
- Military

Segment 3N Strip Map

Sheet 4 of 8

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Segment 3N Strip Map

Sheet 5 of 8

Subtransmission Structures
- Existing Structure
- New-Remove-Existing
- Structure to be Removed

- Milepost (1.0)
- Segment 3N: Kramer-Coolwater

Roads
- Existing Access Road

Land Management/Ownership
- Bureau of Land Management
- Military

1:24,000

N 0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Segment 3N Strip Map

Sheet 6 of 8

Subtransmission Structures
- Existing Structure
- New-Remove-Existing
- Structure to be Removed

- Milepost (1.0)
- Segment 3N: Kramer-Coolwater

Roads
- Existing Access Road

Land Management/Ownership
- Bureau of Land Management
- Military

1:24,000

N 0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Existing Structure
- New-Remove-Existing
- Structure to be Removed

- Milepost (1.0)
- Segment 3N: Kramer-Coolwater

Roads
- Existing Access Road
- Railroad

Land Management/Ownership
- Bureau of Land Management
- LADWP and Local Government
- Military
- State

Segment 3N Strip Map

Sheet 7 of 8

1:24,000

N 0 2,000 Feet

Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Existing Structure
- Proposed New Structure
- New-Remove-Existing
- Structure to be Removed

- Milepost (1.0)
- Substation
- Segment 3N: Kramer-Coolwater
- Segment 3S: Kramer-Tortilla-Coolwater

Roads
- Existing Access Road
- New Access Road
- Railroad

Land Management/Ownership
- Bureau of Land Management
- Military
- State

Segment 3N Strip Map

Sheet 8 of 8

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Existing Structure
- Proposed New Structure
- New-Remove-Existing
- Structure to be Removed

- Milepost (1.0)
- Substation
- Segment 2: Inyokern-Kramer
- Segment 3N: Kramer-Coolwater
- Segment 3S: Kramer-Tortilla-Coolwater

Roads
- Existing Access Road
- Railroad

Land Management/Ownership
- Bureau of Land Management
- Military

Segment 3S Strip Map

Sheet 1 of 8

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Segment 3S Strip Map

Sheet 2 of 8

Subtransmission Structures
- Existing Structure
- New-Remove-Existing

- Milepost (1.0)
- Segment 3S: Kramer-Tortilla-Coolwater

Roads
- Existing Access Road
- Railroad

Land Management/Ownership
- Bureau of Land Management

1:24,000

N 0 2,000 Feet



10

11

12

13

14

15

Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Existing Structure
- New-Remove-Existing

- Milepost (1.0)
- Segment 3S: Kramer-Tortilla-Coolwater

Roads
- Existing Access Road

Land Management/Ownership
- Bureau of Land Management

Segment 3S Strip Map

Sheet 3 of 8

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Existing Structure
- New-Remove-Existing
- Structure to be Removed

- Milepost (1.0)
- Segment 3S: Kramer-Tortilla-Coolwater

Roads
- Existing Access Road

Land Management/Ownership
- Bureau of Land Management
- Military

Segment 3S Strip Map

Sheet 4 of 8

1:24,000

N 0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Existing Structure
- New-Remove-Existing
- Structure to be Removed

- Milepost (1.0)
- Segment 3S: Kramer-Tortilla-Coolwater

Roads
- Existing Access Road
- New Access Road
- Railroad

Land Management/Ownership
- Bureau of Land Management
- Military
- State

Segment 3S Strip Map

Sheet 5 of 8

1:24,000

N

0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Existing Structure
- New-Remove-Existing
- Structure to be Removed

- Milepost (1.0)
- Substation
- Segment 3S: Kramer-Tortilla-Coolwater

Roads
- Existing Access Road
- New Access Road
- Railroad

Land Management/Ownership
- Bureau of Land Management
- LADWP and Local Government
- State

Segment 3S Strip Map

Sheet 6 of 8

1:24,000

N 0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Existing Structure
- New-Remove-Existing

- Milepost (1.0)
- Segment 3S: Kramer-Tortilla-Coolwater

Roads
- Existing Access Road
- Railroad

Land Management/Ownership
- Bureau of Land Management
- Military

Segment 3S Strip Map

Sheet 7 of 8

1:24,000

N 0 2,000 Feet



Sources: Aspen, 2024; BLM, 2024; ESRI, 2024; SCE, 2024.

Subtransmission Structures
- Existing Structure
- New-Remove-Existing
- Structure to be Removed

- Milepost (1.0)
- Substation
- Segment 3N: Kramer-Coolwater
- Segment 3S: Kramer-Tortilla-Coolwater

Roads
- Existing Access Road
- New Access Road
- Railroad

Land Management/Ownership
- Bureau of Land Management
- Military
- State

Segment 3S Strip Map

Sheet 8 of 8

1:24,000

N

0 2,000 Feet

Appendix 2

EMF FIELD MANAGEMENT PLAN

ARCADIS Design & Consultancy for natural and built assets

Mesa Associates, Inc.
Engineers and Consultants

Southern California Edison

EMF FIELD MANAGEMENT PLAN FOR THE SCE TLRR IVANPAH-CONTROL PROJECT

Appendix F - 4/13/2020
Issue 12 – 3/20/2020

Prepared for:

Kevin Garrity, PE
Southern California Edison
2 Innovation Way
Pomona, CA 91768

cc: Warnetta Logan
Phil Hung

Prepared by:
Mesa Associates
320 Commerce, Suite 200
Irvine, CA 92602
Tel: +1 714-508-2601

Our Ref.:
30002904 and 30002905

Date:
March 20, 2020

[Signature 1 Name]
[Title]

[Signature 2 Name]
[Title]

[Signature 3 Name]
[Title]

This document is intended only for the use of the individual or entity for which it was prepared and may contain information that is privileged, confidential and exempt from disclosure under applicable law. Any dissemination, distribution or copying of this document is strictly prohibited.

VERSION CONTROL

Issue	Date Issued	Page No.	Description	Reviewed by
1	3/8/2019	All pages.	Initial release. Combined all IC segments into one report.	B. Wanex
2	3/21/2019	All graphs.	Updates per SCE requests. Changed from 4-hour emergency line rating amperages to 10-year projected line amperages.	B. Wanex
3	4/3/2019	15, 20, 40, 107, all graphs.	Changed color and line types on graphs, removed blank pages.	B. Wanex
4	4/11/2019	2, 3, 8	Fixed typos.	B. Wanex
5	4/29/2019	9, 10	Table 2 header edit. Structure number typos.	B. Wanex
6	7/10/2019	All pages.	Modified terminology to reflect that utilized in PEA document and PTC Application.	C. Mulligan
7	9/20/2019	All structure sketches	Added vertical and horizontal dimensions per CPUC request.	B. Wanex
8	12/9/2019	Pages related to Segments 3N, 3S, and 4.	Updated to incorporate PEA and PLS-CADD changes to segments 3N, 3S, and 4.	B. Wanex
9	3/11/2020	All EMF figures and tables.	Changed amperage values to 2008 CAISO values as furnished and requested by SCE.	B. Wanex
10	3/12/2020	Figs. 3, 5, 7, 9, and 11. Pg. 15 added paragraph.	Added notes regarding transposition. Added residential paragraph. Used 2008 CAISO and Derated amperages for calculations.	B. Wanex
11	3/19/2020	Pages 8, 13, 14, 15, 16, 42-112	Minor clarifications and additional notes to figures.	B. Wanex
12	3/20/2020	104	Changed arrow direction.	B. Wanex

CONTENTS

Acronyms and Abbreviations ..... **xi**
Executive Summary **1**
Segments and Sections ***1***
Codes and Standards ***2***
Magnetic Field Reduction Measures ***2***
"No-Cost" Magnetic Field Reduction Design Options 2
"Low-Cost" Magnetic Field Reduction Design Options 2
EMF Background and Public Research **3**
Application of CPUC EMF Policy **6**
Project Description **8**
Geographic Segments **9**
Summary of IC PROJECT Components by Segment **11**
IC Project Segment 1 Section 1, Control Substation – Str. 214 11
IC Project Segment 1 Section 2, Str. 214 – Str. 442 12
IC Project Segment 1 Section 3, Str. 442 – Str. 683 12
IC Project Segment 1 Section 4, Str. 683 – Str. 912 12
IC Project Segment 1 Section 5, Str. 912 – Inyokern Substation 12
IC Project Segment 2 Section 1, Kramer Substation – Str. 121255 12
IC Project Segment 2 Section 2, Str. 121255 – Randsburg Substation 12
IC Project Segment 2 Section 3, Randsburg Substation – Str. 121042 12
IC Project Segment 2 Section 4, Str. 121042 – Inyokern Substation 12
IC Project Segment 3N, Kramer Substation – Coolwater Substation 12
IC Project Segment 3S Section 1, Kramer Substation – Tortilla Substation 13
IC Project Segment 3S Section 2, Tortilla Substation – Coolwater Substation 13
IC Project Segment 4 Section 1, Coolwater Substation – Str. 128574 13
IC Project Segment 4 Section 2, Str. 128574 – Str. 128595 13
IC Project Segment 4 Section 3, Str. 128595 – Str. 128638 13
IC Project Segment 4 Section 4, Str. 128638– Str. 128660 13
IC Project Segment 4 Section 5, Str. 128660 – Str. 128699 13
IC Project Segment 4 Section 6, Str. 128699 – Str. 128716 13
IC Project Segment 4 Section 7, Str. 128716 – Dunn Siding Substation 13
IC Project Segment 4 Section 8, Dunn Siding Substation – Str. 128753 13
IC Project Segment 4 Section 9, Str. 128753 – Str. 128774 13
IC Project Segment 4 Section 10, Str. 128774 – Str. 128817 13

IC Project Segment 4 Section 11, Str. 128817– Str. 128840 13
IC Project Segment 4 Section 12, Str. 128840 – Str. 128882 13
IC Project Segment 4 Section 13, Str. 128882 – Str. 128904 13
IC Project Segment 4 Section 14, Str. 128904 – Baker Substation 14
IC Project Segment 4 Section 15, Baker Substation – Str. 128949 14
IC Project Segment 4 Section 16, Str. 128949 – Str. 128971 14
IC Project Segment 4 Section 17, Str. 128971 – Str. 1281015 14
IC Project Segment 4 Section 18, Str. 1281015 – Str. 1281039 14
IC Project Segment 4 Section 19, Str. 1281039 – Str. 1281082 14
IC Project Segment 4 Section 20, Str. 1281082 – Str. 1281104 14
IC Project Segment 4 Section 21, Str. 1281104 – Str. 1281146 14
IC Project Segment 4 Section 22, Str. 1281146 – Str. 1281167 14
IC Project Segment 4 Section 23, Str. 1281167 – Mt. Pass Substation 14
IC Project Segment 4 Section 24, Mt. Pass Substation – Str. 1281210 14
IC Project Segment 4 Section 25, Str. 1281210 – Ivanpah Substation 14
Evaluation of Magnetic Field Reduction Design Options 14
Ivanpah – Control Segment 1, Control - Inyokern 14
Ivanpah – Control Segment 2, Kramer - Randsburg - Inyokern 15
Ivanpah – Control Segment 3N, Kramer - Coolwater 15
Ivanpah – Control Segment 3S, Kramer - Tortilla - Coolwater 15
Ivanpah – Control Segment 4, Ivanpah - Mt. Pass - Baker - Dunn Siding - Coolwater 15
Residential Graphs 15
Magnetic Field Assumptions 16
FINAL RECOMMENDATIONS FOR MAGNETIC FIELD REDUCTION DESIGN 17
Reduction Measures 17
Segment Graphs 18
Segment 1 Section 1 18
Segment 1 Section 2 20
Segment 1 Section 3 22
Segment 1 Section 4 24
Segment 1 Section 5 26
Segment 2 Section 1 28
Segment 2 Section 2 30
Segment 2 Section 3 32
Segment 2 Section 4 34
Segment 3N 36
Segment 3S Section 1 38

Segment 3S Section 2 ..... *40*
Segment 4 Section 1 ..... *42*
Segment 4 Section 2 ..... *44*
Segment 4 Section 3 ..... *46*
Segment 4 Section 4 ..... *48*
Segment 4 Section 5 ..... *50*
Segment 4 Section 6 ..... *52*
Segment 4 Section 7 ..... *54*
Segment 4 Section 8 ..... *56*
Segment 4 Section 9 ..... *58*
Segment 4 Section 10 ..... *60*
Segment 4 Section 11 ..... *62*
Segment 4 Section 12 ..... *64*
Segment 4 Section 13 ..... *66*
Segment 4 Section 14 ..... *68*
Segment 4 Section 15 ..... *70*
Segment 4 Section 16 ..... *72*
Segment 4 Section 17 ..... *74*
Segment 4 Section 18 ..... *76*
Segment 4 Section 19 ..... *78*
Segment 4 Section 20 ..... *80*
Segment 4 Section 21 ..... *82*
Segment 4 Section 22 ..... *84*
Segment 4 Section 23 ..... *86*
Segment 4 Section 24 ..... *88*
Segment 4 Section 25 ..... *90*
Residential Graphs **92**
Segment 1 Section 1, Str. 36-37 ..... *92*
Segment 1 Section 1, Str. 55-56 ..... *94*
Segment 1 Section 1, Str. 137-138 ..... *96*
Segment 1 Section 4, Str. 707-708 ..... *98*
Segment 1 Section 5, Str. 1045-1046 ..... *100*
Segment 2 Section 1, Str. 121165 – 121166 ..... *102*
Segment 3N, 2272 (Str. 1547460E_1547459E) – 2274 (W1546397E_E1546398E) *104*
Segment 3S Section 1, 3192 (Str. NA560118AE_SA560118BE) – 3193 (NA560117AE_SA560117BE) *106*

Segment 3S Section 1, Str. 3217 (NA560194AE_SA560194BE) – 3218 (NA560193AE_SA560193BE) ***108***

Segment 4 Section 1, Str. 128571 – 128572 ..... ***110***

Segment 4 Section 2, Str. 128608 – 128609 ..... ***112***

List of Tables

Table 1 – "Low Cost and No Cost" Options Considered & Adopted for Project 2
Table 2 – IC Project Segment 1, 126.2 miles, Approximate Section Lengths 10
Table 3 – IC Project Segment 2, 48.3 miles, Approximate Section Lengths 10
Table 4 – IC Project Segments 3N & 3S, 44.4 & 43.5 miles, Approximate Section Lengths 10
Table 5 – IC Project Segment 4, 95.3 miles, Approximate Section Lengths 10
Table 6 – Segment 4 Non-Derated vs. Derated Amps 15
Table 7 – 2008 CAISO Normal Ratings 16
Table 8 – Comparison of Magnetic Fields at Edge of ROW for Segment 1 Section 1 Str. 169 - 170 18
Table 9 – Comparison of Magnetic Fields at Edge of ROW for Segment 1 Section 2 Str. 251 - 252 20
Table 10 – Comparison of Magnetic Fields at Edge of ROW for Segment 1 Section 3 Str. 544 - 545 22
Table 11 – Comparison of Magnetic Fields at Edge of ROW for Segment 1 Section 4 Str. 768 - 769 24
Table 12 – Comparison of Magnetic Fields at Edge of ROW for Segment 1 Section 5 Str. 957 - 959 26
Table 13 – Comparison of Magnetic Fields at Edge of ROW for Segment 2 Section 1 Str. 121257 - 121256 28
Table 14 – Comparison of Magnetic Fields at Edge of ROW for Segment 2 Section 2 Str. 121170 - 121169 30
Table 15 – Comparison of Magnetic Fields at Edge of ROW for Segment 2 Section 3 Str. 121124 - 121123 32
Table 16 – Comparison of Magnetic Fields at Edge of ROW for Segment 2 Section 4 Str. 120997 - 120996 34
Table 17 – Comparison of Magnetic Fields at Edge of ROW for Segment 3N Str. N1561186E_S1561185E- N4457229E_S4457230E 36
Table 18 – Comparison of Magnetic Fields at Edge of ROW for Segment 3S Section 1 Str. NA560144AE_SA560144BE - NA560143AE_SA560143BE 38
Table 19 – Comparison of Magnetic Fields at Edge of ROW for Segment 3S Section 2 Str. 3235 - 3236 40
Table 20 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 1 Str. 128568 - 128569 42
Table 21 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 2 Str. 128585 - 128586 44
Table 22 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 3 Str. 128614-128615 46
Table 23 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 4 Str. 128645 - 128646 48
Table 24 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 5 Str. 128684 - 128685 50
Table 25 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 6 Str. 128712 -128713 52
Table 26 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 7 Str. 128730 - 128731 54
Table 27 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 8 Str. 128745 - 128746 56
Table 28 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 9 Str. 128770 - 128771 58

Table 29 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 10 Str. 128804 - 128805 60
Table 30 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 11 Str. 128825 - 128826 62
Table 31 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 12 Str. 128867 - 128868 64
Table 32 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 13 Str. 128885 - 128886 66
Table 33 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 14 Str. 128917 - 128918 68
Table 34 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 15 Str. 128939 - 128940 70
Table 35 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 16 Str. 128966 - 128967 72
Table 36 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 17 Str. 128990 - 128991 74
Table 37 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 18 Str. 1281018 - 1281019 76
Table 38 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 19 Str. 1281067 - 1281068 78
Table 39 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 20 Str. 1281098 - 1281099 80
Table 40 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 21 Str. 1281145 - 1281146 82
Table 41 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 22 Str. 1281154 – 1281155 84
Table 42 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 23 Str. 1281170 - 1281171 86
Table 43 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 24 Str. 1281202 - 1281203 88
Table 44 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 25 Str. 1281212- 1281213 90
Table 45 – Comparison of Magnetic Fields at Edge of ROW for Segment 1 Section 1 Str. 36-37 92
Table 46 – Comparison of Magnetic Fields at Edge of ROW for Segment 1 Section 1 Str. 55-56 94
Table 47 – Comparison of Magnetic Fields at Edge of ROW for Segment 1 Str. 137-138 96
Table 48 – Comparison of Magnetic Fields at Edge of ROW for Segment 3 Str. 707-708 98
Table 49 – Comparison of Magnetic Fields at Edge of ROW for Segment 5 Str. 1045-1046 100
Table 50 – Comparison of Magnetic Fields at Edge of ROW for Segment 2 Section 1 Str. 121165 – 121166 102
Table 51 – Comparison of Magnetic Fields at Edge of ROW for Segment 3N, Str. 1547460E_1547459E – 1546399E_1546400E 104
Table 52 – Comparison of Magnetic Fields at Edge of ROW for Segment 3S Section 1 Str. NA560118AE_SA560118BE – NA560117AE_SA560117BE 106
Table 53 – Comparison of Magnetic Fields at Edge of ROW for Segment 3S Section 1 Str. NA560194AE_SA560194BE– NA560193AE_SA560193BE 108
Table 54 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 1, Str. 128571 – 128572 110
Table 55 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 2, Str. 128608 – 128609 112

List of Figures

Figure 1 – IC Project Subtransmission Line Route Segments 9
Figure 2 - Typical Magnetic Field Levels for Segment 1 Section 1 Control – Structure 214, Str. 169 - 170 at 415 Amps 18
Figure 3 – Tower and Insulator Dimensions and Phasing 19
Figure 4 - Typical Magnetic Field Levels for Segment 1 Section 2 Structure 214 – Structure 442, Str. 251 - 252 at 415 Amps 20
Figure 5 – Tower and Insulator Dimensions and Phasing 21
Figure 6 - Typical Magnetic Field Levels for Segment 1 Section 3 Structure 442 – Structure 683, Str. 544 - 545 at 415 Amps 22
Figure 7 – Tower and Insulator Dimensions and Phasing 23
Figure 8 - Typical Magnetic Field Levels for Segment 1 Section 4 Structure 683 – Structure 912, Str. 768 - 769 at 415 Amps 24
Figure 9 – Tower and Insulator Dimensions and Phasing 25
Figure 10 - Typical Magnetic Field Levels for Segment 1 Section 5 Structure 912 – Inyokern Substation, Str. 957 - 958 at 415 Amps 26
Figure 11 – Tower and Insulator Dimensions and Phasing 27
Figure 12 - Typical Magnetic Field Levels for Segment 2 Section 1 Kramer Substation – Structure 121255, Str. 121257 - 121256 at 830 Amps 28
Figure 13 – Tower and Insulator Dimensions and Phasing 29
Figure 14 - Typical Magnetic Field Levels for Segment 2 Section 2 Structure 121255 – Randsburg Substation, Str. 121170 - 121169 at 830 Amps 30
Figure 15 – Tower and Insulator Dimensions and Phasing 31
Figure 16 - Typical Magnetic Field Levels for Segment 2 Section 3 Randsburg Substation – Structure 121042, Str. 121124 - 121123 at 830 Amps 32
Figure 17 – Tower and Insulator Dimensions and Phasing 33
Figure 18 - Typical Magnetic Field Levels for Segment 2 Section 4 Structure 121042 – Inyokern Substation, Str. 120997 - 120996 at 830 Amps 34
Figure 19 – Tower and Insulator Dimensions and Phasing 35
Figure 20 - Typical Magnetic Field Levels for Segment 3N Kramer Substation – Coolwater Substation, Str. 2012 (N1561186E_S1561185E) - 2013 (N4457229E_S4457230E) at 950 Amps 36
Figure 21 – Tower and Insulator Dimensions and Phasing 37
Figure 22 - Typical Magnetic Field Levels for Segment 3S Section 1 Kramer Substation – Tortilla Substation, Str. 3166 (NA560144AE_SA560144BE) - 3167 (NA560143AE_SA560143BE) at 975 Amps 38
Figure 23 – Tower and Insulator Dimensions and Phasing 39
Figure 24 - Typical Magnetic Field Levels for Segment 3S Section 2 Tortilla Substation – Coolwater Substation, Str 3236 - 3237 (1811388E - 1811383E) at 975 Amps 40
Figure 25 – Tower and Insulator Dimensions and Phasing 41
Figure 26 - Typical Magnetic Field Levels for Segment 4 Section 1 Coolwater Substation – Structure 128574, Str. 128568 - 128569 at 165 Amps 42
Figure 27 – Tower and Insulator Dimensions and Phasing 43
Figure 28 - Typical Magnetic Field Levels for Segment 4 Section 2 Structure 128574 – Structure 128595, Str. 128585 - 128586 at 165 Amps 44
Figure 29 – Tower and Insulator Dimensions and Phasing 45
Figure 30 - Typical Magnetic Field Levels for Segment 4 Section 3 Structure 128595 – Structure 128638, Str. 128614-128615 at 165 Amps 46
Figure 31 – Tower and Insulator Dimensions and Phasing 47
Figure 32 - Typical Magnetic Field Levels for Segment 4 Section 4 Structure 128638 – Structure 128660, Str. 128645 - 128646 at 165 Amps 48
Figure 33 – Tower and Insulator Dimensions and Phasing 49

Figure 34 - Typical Magnetic Field Levels for Segment 4 Section 5 Structure 128660 – Structure 128699, Str. 128684 - 128685 at 165 Amps 50
Figure 35 – Tower and Insulator Dimensions and Phasing 51
Figure 36 - Typical Magnetic Field Levels for Segment 4 Section 6 Structure 128699 – Structure 128716, Str. 128712 -128713 at 165 Amps 52
Figure 37 – Tower and Insulator Dimensions and Phasing 53
Figure 38 - Typical Magnetic Field Levels for Segment 4 Section 7 Structure 128716 – Dunn Siding Substation, Str. 128730 - 128731 at 165 Amps 54
Figure 39 – Tower and Insulator Dimensions and Phasing 55
Figure 40 - Typical Magnetic Field Levels for Segment 4 Section 8 Dunn Siding Substation – Structure 128753, Str. 128745 - 128746 at 150 Amps 56
Figure 41 – Tower and Insulator Dimensions and Phasing 57
Figure 42 - Typical Magnetic Field Levels for Segment 4 Section 9 Structure 128753 – Structure 128774, Str. 128770 - 128771 at 150 Amps 58
Figure 43 – Tower and Insulator Dimensions and Phasing 59
Figure 44 - Typical Magnetic Field Levels for Segment 4 Section 10 Structure 128774 – Structure 128817, Str. 128804 - 128805 at 150 Amps 60
Figure 45 – Tower and Insulator Dimensions and Phasing 61
Figure 46 - Typical Magnetic Field Levels for Segment 4 Section 11 Structure 128817 – Structure 128840, Str. 128825 - 128826 at 150 Amps 62
Figure 47 – Tower and Insulator Dimensions and Phasing 63
Figure 48 - Typical Magnetic Field Levels for Segment 4 Section 12 Structure 128840 – Structure 128882, Str. 128867 - 128868 at 150 Amps 64
Figure 49 – Tower and Insulator Dimensions and Phasing 65
Figure 50 - Typical Magnetic Field Levels for Segment 4 Section 13 Structure 128882 – Structure 128904, Str. 128885 - 128886 at 150 Amps 66
Figure 51 – Tower and Insulator Dimensions and Phasing 67
Figure 52 - Typical Magnetic Field Levels for Segment 4 Section 14 Structure 128904 – Baker Substation, Str. 128917 - 128918 at 150 Amps 68
Figure 53 – Tower and Insulator Dimensions and Phasing 69
Figure 54 - Typical Magnetic Field Levels for Segment 4 Section 15 Baker Substation – Structure 128949, Str. 128939 - 128940 at 215 Amps 70
Figure 55 – Tower and Insulator Dimensions and Phasing 71
Figure 56 - Typical Magnetic Field Levels for Segment 4 Section 16 Structure 128949 – Structure 128971, Str. 128966 - 128967 at 215 Amps 72
Figure 57 – Tower and Insulator Dimensions and Phasing 73
Figure 58 - Typical Magnetic Field Levels for Segment 4 Section 17 Structure 128971 – Structure 1281015, Str. 128990 - 128991 at 215 Amps 74
Figure 59 – Tower and Insulator Dimensions and Phasing 75
Figure 60 - Typical Magnetic Field Levels for Segment 4 Section 18 Structure 1281015 – Structure 1281039, Str. 1281018 - 1281019 at 215 Amps 76
Figure 61 – Tower and Insulator Dimensions and Phasing 77
Figure 62 - Typical Magnetic Field Levels for Segment 4 Section 19 Structure 1281039 – Structure 1281082, Str. 1281067 - 1281068 at 215 Amps 78
Figure 63 – Tower and Insulator Dimensions and Phasing 79
Figure 64 - Typical Magnetic Field Levels for Segment 4 Section 20 Structure 1281082 – Structure 1281104, Str. 1281098 - 1281099 at 215 Amps 80
Figure 65 – Tower and Insulator Dimensions and Phasing 81
Figure 66 - Typical Magnetic Field Levels for Segment 4 Section 21 Structure 1281104 – Structure 1281146, Str. 1281145 - 1281146 at 215 Amps 82
Figure 67 – Tower and Insulator Dimensions and Phasing 83

Figure 68 - Typical Magnetic Field Levels for Segment 4 Section 22 Structure 1281146 – Structure 1281167, Str. 1281154 – 1281155 at 215 Amps 84
Figure 69 – Tower and Insulator Dimensions and Phasing 85
Figure 70 - Typical Magnetic Field Levels for Segment 4 Section 23 Structure 1281167 – Mountain Pass Substation, Str. 1281170 - 1281171 at 215 Amps 86
Figure 71 – Tower and Insulator Dimensions and Phasing 87
Figure 72 - Typical Magnetic Field Levels for Segment 4 Section 24 Mountain Pass Substation – Structure 1281210, Str. 1281202 - 1281203 at 240 Amps 88
Figure 73 – Tower and Insulator Dimensions and Phasing 89
Figure 74 - Typical Magnetic Field Levels for Segment 4 Section 25 Structure 1281210 - Ivanpah Substation, Str. 1281212- 1281213 at 240 Amps 90
Figure 75 – Tower and Insulator Dimensions and Phasing 91
Figure 76 - Typical Magnetic Field Levels for Segment 1 Section 1 Control – Structure 214, Str. 36-37 at 415 Amps 92
Figure 77 – Tower and Insulator Dimensions and Phasing 93
Figure 78 – Typical Magnetic Field Levels for Segment 1 Section 1 Control – Structure 214, Str. 55-56 at 415 Amps 94
Figure 79 – Tower and Insulator Dimensions and Phasing 95
Figure 80 - Typical Magnetic Field Levels for Segment 1 Section 1 Control – Structure 214, Str. 137-138 at 415 Amps 96
Figure 81 – Tower and Insulator Dimensions and Phasing 97
Figure 82 – Typical Magnetic Field Levels for Segment 1 Section 4 Structure 683 – Structure 912, Str. 707-708 at 415 Amps 98
Figure 83 – Tower and Insulator Dimensions and Phasing 99
Figure 84 – Typical Magnetic Field Levels for Segment 1 Section 5 Structure 912 – Inyokern Substation, Str. 1045-1046 at 415 Amps 100
Figure 85 – Tower and Insulator Dimensions and Phasing 101
Figure 86 – Typical Magnetic Field Levels for Segment 2 Section 1 Kramer Substation – Structure 121255, Str. 121165 – 121166 at 830 Amps 102
Figure 87 – Tower and Insulator Dimensions and Phasing 103
Figure 88 – Typical Magnetic Field Levels for Segment 3N Kramer Substation – Coolwater Substation, Str. 1547460E_1547459E – 1546399E_1546400E at 950 Amps 104
Figure 89 – Tower and Insulator Dimensions and Phasing 105
Figure 90 – Typical Magnetic Field Levels for Segment 3S Section 1 Kramer Substation – Tortilla Substation, Str. NA560118AE_SA560118BE – NA560117AE_SA560117BE at 975 Amps 106
Figure 91 – Tower and Insulator Dimensions and Phasing 107
Figure 92 – Typical Magnetic Field Levels for Segment 3S Section 1 Kramer Substation – Tortilla Substation, Str. NA560194AE_SA560194BE – NA560193AE_SA560193BE at 975 Amps 108
Figure 93 – Tower and Insulator Dimensions and Phasing 109
Figure 94 – Typical Magnetic Field Levels for Segment 4 Section 1 Coolwater Substation – Structure 128574, Str. 128571 – 128572 at 165 Amps 110
Figure 95 – Tower and Insulator Dimensions and Phasing 111
Figure 96 – Typical Magnetic Field Levels for Segment 4 Section 2 Structure 128595 – Structure 128638, Str. 128608 – 128609 at 165 Amps 112
Figure 97 – Tower and Insulator Dimensions and Phasing 113

ACRONYMS AND ABBREVIATIONS

A, Amps	Amperes, a unit of measure for electrical current
AC	Alternating current
AAC	All aluminum conductor, a type of overhead power line conductor
ACCC	Aluminum conductor composite core, a type of "high-temperature low-sag" overhead power line conductor
ACSR	Aluminum conductor steel reinforced, a type of overhead power line conductor
CAISO	California Independent System Operator
CDHS	California Department of Health Services
CPCN	Certificate of Public Convenience and Necessity
CPUC	California Public Utilities Commission
DI	Ductile Iron, a type of transmission structure
ELF	Extremely low frequency
EMF	Electric and magnetic fields
EPRI	Electric Power Research Institute
FMP	Field Management Plan
Ft	Feet, a unit of measure for distance
GO	General Order
HTLS	High-temperature low-sag, a type of overhead conductor
Hz	Hertz, a unit of measure for electrical frequency
IARC	International Agency for Research on Cancer
IEEE	Institute of Electrical and Electronics Engineers
IEC	International Electrotechnical Commission
IC	Ivanpah – Control transmission line
kcmil	Kilo (thousand) circular mils, a unit of conductor size and measurement
kV	Kilovolt, a unit of measure for electrical potential
LWS	Light weight steel, a type of transmission structure
mG	milliGauss, a unit of measure for magnetic fields
NIEHS	National Institute of Environmental Health Sciences (USA)
NRBB	National Radiological Protection Board (UK)
°	Degrees, a unit of measure for electric phasors
OHGW	Overhead ground wire
OPGW	Optical ground wire
PEA	Proponent's Environmental Assessment

PTC	Permit to Construct
PLS-CADD	A software program for transmission line design
ROW	Right of way
SCE	Southern California Edison
Str	Structure
TLRR	Transmission Line Rating and Remediation
T/L	Transmission Line
TSP	Tubular steel pole, a type of transmission structure
µT	Microtesla, a unit of measure for magnetic fields
WHO	World Health Organization

EXECUTIVE SUMMARY

The Field Management Plan (FMP) presented in this report describes the magnetic field reduction design options incorporated into the design of the Southern California Edison Company's (SCE) Ivanpah – Control (IC) Project, which consists of modifications to the following existing 115 kilovolt (kV) subtransmission circuits:

- Control-Haiwee-Inyokern 115 kV subtransmission circuit
- Control-Haiwee-Coso-Inyokern 115 kV subtransmission circuit
- Kramer-Randsburg-Inyokern 115 kV subtransmission circuit
- Kramer-Coolwater 115 kV subtransmission circuit
- Kramer-Tortilla 115 kV subtransmission circuit
- Coolwater-Tortilla 115 kV subtransmission circuit
- Ivanpah-Mountain Pass-Baker-Dunn Siding-Coolwater 115 kV subtransmission circuit

Segments and Sections

These circuits are divided into separate segments and are further sub-categorized into multiple sections. The purpose of the IC Project is to ensure compliance with the California Public Utilities Commission's (CPUC) General Order 95 (GO 95) and North American Electric Reliability Corporation (NERC) Facility Ratings through remediating physical clearance discrepancies identified on existing 115 kV subtransmission lines.

As discussed in greater detail in the Proponent's Environmental Assessment (PEA), SCE has identified a variety of ways to accomplish the IC Project. For purposes of a conservative and complete analysis of all potential environmental impacts associated with the IC Project, the remediation scope of work includes a combination of complete rebuild of existing SCE facilities (including replacing existing structures and utilizing a new conductor), reconductoring only, and circuit derating. These five segments are denoted for purposes of the IC Project as Segment 1, Segment 2, Segment 3 North or "3N", Segment 3 South or "3S", and Segment 4. Details pertaining to the 115 kV subtransmission line infrastructure are provided in the PEA; a summary of the scope of work in each Segment is as follows:

- Segment 1: SCE has identified that a full rebuild of the subtransmission lines in Segment 1 is the most feasible approach to remediate these discrepancies.

- Segment 2: SCE has identified that a full rebuild of the subtransmission line in Segment 2 is the most feasible approach to remediate these discrepancies.

- Segment 3N (3 North): SCE has identified that reconductoring of the subtransmission line, in combination with replacement of a small number of structures, can be utilized to remediate the identified discrepancies.

- Segment 3S (3 South): SCE has identified that reconductoring and derating of the subtransmission line, in combination with replacement of a small number of structures, can be utilized to remediate the identified discrepancies.

- Segment 4: SCE has identified that derating the subtransmission circuit in Segment 4, in combination with the replacement of some existing structures and the construction of a ring bus at the existing Baker Substation, can be utilized to remediate the identified discrepancies.

Codes and Standards

The FMP for the IC Project of the IC Project has been prepared in accordance with the CPUC Interim EMF Decision No. 06-01-042 ("2006 CPUC Decision") and general recommendations supported by the U.S. National Institute of Environmental Health Sciences and also satisfies the CPUC approved EMF Design Guidelines as well as all national and state safety standards for reconductoring and new electric facilities.

Magnetic Field Reduction Measures

SCE provides this FMP to inform all interested parties of the evaluation of "no-cost and low-cost" magnetic field reduction design options being considered and the proposed application of these design options in the IC Project. The FMP also provides a summary of background information regarding current scientific research related to possible health effects of EMF and the CPUC EMF Policy.

"No-Cost" Magnetic Field Reduction Design Options

The "no-cost" magnetic field reduction design options that are incorporated into the design of the IC Project include the following utilization of structure types and characteristics which reduce and minimize the electrical and magnetic field (EMF): Vertical and delta conductor configurations, double-circuit monopole structure configurations, and taller structure heights are used in areas with potential overhead clearance discrepancies, thus increasing ground clearance and minimizing EMF in locations outside the right-of-way (ROW).

"Low-Cost" Magnetic Field Reduction Design Options

The only "low-cost" magnetic field reduction measure incorporated into the design of the IC Project is the utilization of post-construction phasing arrangement to minimize EMF.

The "no-cost and low-cost" magnetic field reduction design options implemented in the IC Project are described in Table 1. Several portions of the IC Project alignment which are of specific interest for the EMF study are noted in the table and further addressed in the EMF study for safety concerns. The most significant EMF conditions in each residential area will be modeled and graphed to address previous science studies.

Table 1 – "Low Cost and No Cost" Options Considered & Adopted for Project

Segment & Section	Start Structure	End Structure	EMF Reduction Design Options	Estimated Cost	Structures in Residential Area
IC Segment 1 Section 1	Control Substation	Structure 214	Conductor Arrangement Double Circuit Construction Structure Heights Phasing Circuits	No cost No cost No cost Low cost	35-37, 53-56, 137-138
IC Segment 1 Section 2 - 3	Structure 214	Structure 683	Conductor Arrangement Double Circuit Construction Structure Heights Phasing Circuits	No cost No cost No cost Low cost	N/A
IC Segment 1 Section 4	Structure 683	Structure 912	Conductor Arrangement Double Circuit Construction Structure Heights Phasing Circuits	No cost No cost No cost Low cost	706-708

Segment & Section	Start Structure	End Structure	EMF Reduction Design Options	Estimated Cost	Structures in Residential Area
IC Segment 1 Section 5	Structure 912	Inyokern	Conductor Arrangement Double Circuit Construction Structure Heights Phasing Circuits	No cost No cost No cost Low cost	1042-1050
IC Segment 2 Section 1 - 2	Kramer Substation	Randsburg Substation	Conductor Arrangement Structure Heights	No cost No cost	121165-121166
IC Segment 2 Section 3 - 4	Randsburg Substation	Inyokern Substation	Conductor Arrangement Structure Heights	No cost No cost	N/A
IC Segment 3N	Kramer Substation	Coolwater Substation	Structure Heights	No cost	1546399E_ 1546400E - W1546395E_ E1546396E
IC Segment 3S Section 1	Kramer Substation	Tortilla Substation	Structure Heights	No cost	NA560118AE_ SA560118BE - NA560117AE_ SA560117BE, NA560194AE_ SA560194BE - NA560193AE_ SA560193BE
IC Segment 3S Section 2	Tortilla Substation	Coolwater Substation	Structure Heights	No cost	N/A
IC Segment 4 Sections 1 - 7	Coolwater Substation	Dunn Siding Substation	Conductor Arrangement Structure Heights	No cost No cost	128571-128572 & 128608-128609
IC Segment 4 Section 8 - 14	Dunn Siding Substation	Baker Substation	Conductor Arrangement Structure Heights	No cost No cost	N/A
IC Segment 4 Section 15 - 25	Baker Substation	Structure Ivanpah	Conductor Arrangement Structure Heights	No cost No cost	N/A

EMF BACKGROUND AND PUBLIC RESEARCH

There are many sources of power frequency[1] electric and magnetic fields, including internal household and building wiring, electrical appliances, and electric power transmission and distribution lines. There have been numerous scientific studies about the potential health effects of EMF. After many years of research, the scientific community has been unable to determine if exposures to EMF cause health

[1] In the U.S., the power frequency is 60 Hertz (Hz).

hazards. State and federal public health regulatory agencies have determined that setting numeric exposure limits is not appropriate.[2]

Magnetic fields use the units of microtesla (μT) and milligauss (mG). One μT is equal to 10 mG.

Many of the questions about possible connections between EMF exposures and specific diseases have been successfully resolved due to an aggressive international research program. However, potentially important public health questions remain about whether there is a link between EMF exposures and certain diseases, including childhood leukemia and a variety of adult diseases (e.g., adult cancers and miscarriages). As a result, some health authorities have identified magnetic field exposures as a possible human carcinogen. As summarized in greater detail below, these conclusions are consistent with the following published reports: the National Institute of Environmental Health Sciences (NIEHS) 1999[3], the National Radiation Protection Board (NRPB) 2001[4], the International Commission on non-Ionizing Radiation Protection (ICNIRP) 2001, the California Department of Health Services (CDHS) 2002[5], the International Agency for Research on Cancer (IARC) 2002[6] and the World Health Organization (WHO) 2007[7]. The federal government conducted EMF research as a part of a $45-million research program managed by the NIEHS. This program, known as the EMF RAPID (Research and Public Information Dissemination), submitted its final report to the U.S. Congress on June 15, 1999.

The report concluded that:

- "The scientific evidence suggesting that ELF-EMF exposures pose any health risk is weak."[8]
- "The NIEHS concludes that ELF-EMF exposure cannot be recognized as entirely safe because of weak scientific evidence that exposure may pose a leukemia hazard."[9]
- "The NIEHS suggests that the level and strength of evidence supporting ELF-EMF exposure as a human health hazard are insufficient to warrant aggressive regulatory actions; thus, we do not recommend actions such as stringent standards on electric appliances and a national program to bury all transmission and distribution lines. Instead, the evidence suggests passive measures such as a continued emphasis on educating both the public and the regulated community on means aimed at reducing exposures. NIEHS suggests that the power industry continue its current practice of siting power lines to reduce exposures and continue to explore ways to reduce the creation of magnetic fields around transmission and distribution lines without creating new hazards."[10]

In 2001, Britain's NRPB arrived at a similar conclusion:

> "After a wide-ranging and thorough review of scientific research, an independent Advisory Group to the Board of NRPB has concluded that the power frequency electromagnetic fields that exist in the vast majority of homes are not a cause of cancer in general. However, some epidemiological studies

[2] CPUC Decision 06-01-042, p. 6, footnote 10.
[3] National Institute of Environmental Health Sciences' Report on Health Effects from Exposures to Power-Line frequency Electric and Magnetic Fields, NIH Publication No. 99-4493, June 1999.
[4] National Radiological Protection Board, Electromagnetic Fields and the Risk of Cancer, Report of an Advisory Group on Non-ionizing Radiation, Chilton, U.K. 2001.
[5] California Department of Health Services, An Evaluation of the Possible Risks from Electric and Magnetic Fields from Power Lines, Internal Wiring, Electrical Occupations, and Appliances, June 2002.
[6] World Health Organization / International Agency for Research on Cancer, IARC Monographs on the evaluation of carcinogenic risks to humans (2002), Non-ionizing radiation, Part 1: Static and extremely low frequency (ELF) electric and magnetic fields, IARC Press, Lyon, France: International Agency for Research on Cancer, Monograph, vol. 80, p. 338, 2002.
[7] WHO, Environmental Health Criteria 238, EXTREMELY LOW FREQUENCY FIELDS, 2007.
[8] National Institute of Environmental Health Sciences, NIEHS Report on Health Effects from Exposures to Power-Frequency Electric and Magnetic Fields, p. ii, NIH Publication No. 99-4493, 1999.
[9] *Ibid.*, p. iii.
[10] *Ibid.*, p. 37 – 38

do indicate a possible small risk of childhood leukemia associated with exposures to unusually high levels of power frequency magnetic fields."[11]

In 2002, three scientists for CDHS concluded:

"To one degree or another, all three of the [CDHS] scientists are inclined to believe that EMFs can cause some degree of increased risk of childhood leukemia, adult brain cancer, Lou Gehrig's disease, and miscarriage. They [CDHS] strongly believe that EMFs do not increase the risk of birth defects, or low birth weight.

They [CDHS] strongly believe that EMFs are not universal carcinogens, since there are a number of cancer types that are not associated with EMF exposure. To one degree or another they [CDHS] are inclined to believe that EMFs do not cause an increased risk of breast cancer, heart disease, Alzheimer's disease, depression, or symptoms attributed by some to a sensitivity to EMFs. However, all three scientists had judgments that were "close to the dividing line between believing and not believing" that EMFs cause some degree of increased risk of suicide. For adult leukemia, two of the scientists are 'close to the dividing line between believing or not believing' and one was 'prone to believe' that EMFs cause some degree of increased risk."[12]

Also, in 2002, the World Health Organization's (WHO) IARC concluded:

"EMF magnetic fields are possibly carcinogenic to humans"[13], based on consistent statistical associations of high-level residential magnetic fields with a doubling of risk of childhood leukemia...Children who are exposed to residential EMF magnetic fields less than 0.4 microTesla (4.0 milliGauss) have no increased risk for leukemia…. In contrast, "no consistent relationship has been seen in studies of childhood brain tumors or cancers at other sites and residential EMF electric and magnetic fields."[14]

In June of 2007, the WHO issued a report on their multi-year investigation of EMF and the possible health effects. After reviewing scientific data from numerous EMF and human health studies, they concluded:

- "Scientific evidence suggesting that everyday, chronic low-intensity (above 0.3- 0.4 μT [3-4 mG]) power-frequency magnetic field exposure poses a health risk is based on epidemiological studies demonstrating a consistent pattern of increased risk for childhood leukemia."[15] "In addition, virtually all of the laboratory evidence and the mechanistic evidence fail to support a relationship between low-level ELF magnetic fields and changes in biological function or disease status. Thus, on balance, the evidence is not strong enough to be considered causal, but sufficiently strong to remain a concern."[16]
- "A number of other diseases have been investigated for possible association with ELF magnetic field exposure. These include cancers in both children and adults, depression, suicide, reproductive dysfunction, developmental disorders, immunological modifications and neurological disease. The scientific evidence supporting a linkage between ELF magnetic fields and any of these diseases is much weaker than for childhood leukemia and in some cases (for example, for cardiovascular disease or breast cancer) the evidence is sufficient to give confidence that magnetic fields do not cause the disease"[17]

[11] NRPB, NRPB Advisory Group on Non-ionizing Radiation Power Frequency Electromagnetic Fields and the Risk of Cancer, NRPB Press Release May 2001.
[12] CDHS, An Evaluation of the Possible Risks From Electric and Magnetic Fields (EMFs) From Power Lines, Internal Wiring, Electrical Occupations and Appliances, p. 3, 2002.
[13] IARC, Monographs, Part I, Vol. 80, p. 338.
[14] *Ibid*., p. 332 – 334.
[15] WHO, Environmental Health Criteria 238, EXTREMELY LOW FREQUENCY FIELDS, p. 11 - 13, 2007.
[16] *Ibid*., p. 12.
[17] *Ibid*., p. 12.

- "Furthermore, given both the weakness of the evidence for a link between exposure to ELF magnetic fields and childhood leukemia, and the limited impact on public health if there is a link, the benefits of exposure reduction on health are unclear. Thus, the costs of precautionary measures should be very low."[18]

APPLICATION OF CPUC EMF POLICY

Recognizing the scientific uncertainty over the connection between EMF exposures and health effects, the CPUC adopted a policy that addresses public concern over EMF with a combination of education, information, and precaution-based approaches. Specifically, Decision 93-11-013 established a precautionary based "no-cost and low-cost" EMF policy for California's regulated electric utilities based on recognition that scientific research had not demonstrated that exposures to EMF cause health hazards and that it was inappropriate to set numeric standards that would limit exposure.

In 2006, the CPUC completed its review and update of its EMF Policy in Decision 06-01-042. This decision reaffirmed the finding that state and federal public health regulatory agencies have not established a direct link between exposure to EMF and human health effects,[19] and the policy direction that (1) use of numeric exposure limits was not appropriate in setting utility design guidelines to address EMF,[20] and (2) existing "no-cost and low-cost" precautionary-based EMF policy should be continued for proposed electrical facilities. The decision also reaffirmed that EMF concerns brought up during Certificate of Public Convenience and Necessity (CPCN) and Permit to Construct (PTC) proceedings for electric and transmission and substation facilities should be limited to the utility's compliance with the CPUC's "no-cost and low-cost" policies.[21]

The decision directed regulated utilities to hold a workshop to develop standard approaches for EMF Design Guidelines and such a workshop was held on February 21, 2006. Consistent design guidelines have been developed that describe the routine magnetic field reduction measures that regulated California electric utilities consider for new and upgraded transmission line and transmission substation projects. SCE filed its revised EMF Design Guidelines with the CPUC on July 26, 2006.

"No-cost and low-cost" measures to reduce magnetic fields would be implemented for the IC Project in accordance with SCE's EMF Design Guidelines. In summary, the process of evaluating "no-cost and low-cost" magnetic field reduction measures and prioritizing within and between land usage classes considers the following:

1. SCE's priority in the design of any electrical facility is public and employee safety. Without exception, design and construction of an electric power system must comply with all applicable federal, state, and local regulations, applicable safety codes, and each electric utility's construction standards. Furthermore, transmission and Subtransmission lines and substations must be constructed so that they can operate reliably at their design capacity. Their design must be compatible with other facilities in the area and the cost to operate and maintain the facilities must be reasonable.

---

[18] *Ibid*., p. 13.
[19] CPUC Decision 06-01-042, Conclusion of Law No. 5, mimeo. p. 19 ("As discussed in the rulemaking, a direct link between exposure to EMF and human health effects has yet to be proven despite numerous studies including a study ordered by this Commission and conducted by DHS.")
[20] CPUC Decision 06-01-042, mimeo. p. 17 - 18 ("Furthermore, we do not request that utilities include nonroutine mitigation measures, or other mitigation measures that are based on numeric values of EMF exposure, in revised design guidelines or apply mitigation measures to reconfigurations or relocations of less than 2,000 feet, the distance under which exemptions apply under GO 131-D. Non-routine mitigation measures should only be considered under unique circumstances.").
[21] CPUC Decision 06-01-042, Conclusion of Law No. 2, ("EMF concerns in future CPCN and PTC proceedings for electric and transmission and substation facilities should be limited to the utility's compliance with the Commission's low-cost/no-cost policies.").

2. As a supplement to Step 1, SCE follows the CPUC's direction to undertake "no-cost and low-cost" magnetic field reduction measures for new and upgraded electrical facilities. Any proposed "no-cost and low-cost" magnetic field measures, must, however, meet the requirements described in Step 1 above. The CPUC defines "no-cost and low-cost" measures as follows:

    - Low-cost measures, in aggregate, should:
        - Cost in the range of 4 percent of the total project cost.
        - Result in magnetic field reductions of "15% or greater at the utility R-O-W [right-of-way]…"[22]

    The CPUC Decision stated:

    "We direct the utilities to use 4 percent as a benchmark in developing their EMF mitigation guidelines. We will not establish 4 percent as an absolute cap at this time because we do not want to arbitrarily eliminate a potential measure that might be available but costs more than the 4 percent figure. Conversely, the utilities are encouraged to use effective measures that cost less than 4 percent."[23]

3. The CPUC provided further policy direction in Decision 06-01-042, stating that, "although equal mitigation for an entire class is a desirable goal, we will not limit the spending of EMF mitigation to zero on the basis that not all class members can benefit."[24] While Decision 06-01-042 directs the utilities to favor schools, day-care facilities and hospitals over residential areas when applying low-cost magnetic field reduction measures, prioritization within a class can be difficult on a project case-by-case basis because schools, day-care facilities, and hospitals are often integrated into residential areas, and many licensed day-care facilities are housed in private homes, and can be easily moved from one location to another. Therefore, it may be practical for public schools, licensed day-care centers, hospitals, and residential land uses to be grouped together to receive highest prioritization for low-cost magnetic field reduction measures. Commercial and industrial areas may be grouped as a second priority group, followed by recreational and agricultural areas as the third group. Low-cost magnetic field reduction measures will not be considered for undeveloped land, such as open space, state and national parks, and Bureau of Land Management and U.S. Forest Service lands. When spending for low-cost measures would otherwise disallow equitable magnetic field reduction for all areas within a single land-use class, prioritization can be achieved by considering location and/or density of permanently occupied structures on lands adjacent to the projects, as appropriate.

This FMP contains descriptions of various magnetic field models and the calculated results of magnetic field levels based on those models. These calculated results are provided only for purposes of identifying the relative differences in magnetic field levels among various subtransmission line design alternatives under a specific set of modeling assumptions and determining whether particular design alternatives can achieve magnetic field level reductions of 15 percent or more at the edges of the ROW. The calculated results are not intended to be predictors of the actual magnetic field levels at any given time or at any specific location if and when the IC Project is constructed. This is because magnetic field levels depend upon a variety of variables, including load growth, customer electricity usage, and other factors beyond SCE's control. The CPUC affirmed this in D. 06-01-042 stating:

> "Our [CPUC] review of the modeling methodology provided in the utility [EMF] design guidelines indicates that it accomplishes its purpose, which is to measure the relative differences between alternative mitigation measures. Thus, the modeling indicates relative differences in magnetic field

[22] CPUC Decision 06-01-042, p. 10.
[23] CPUC Decision 93-11-013, § 3.3.2, p.10.
[24] CPUC Decision 06-01-042, p. 10.

reductions between different transmission line construction methods but does not measure actual environmental magnetic fields."[25]

PROJECT DESCRIPTION

The IC Project design seeks to resolve all clearance discrepancies present in the existing subtransmission lines and incorporate an overhead fiber optic static wire to improve the reliability of the line. The IC Project alignment starts at SCE's Ivanpah Substation and ends at SCE's Control Substation.

The IC Project alignment is approximately 358 miles long. The existing subtransmission lines associated with the IC Project are predominantly lattice towers, lattice H-frames, wood H-frames, and some single delta wood pole structures. The structures located between Control Substation and Inyokern Substation are configured with vertical double circuits with one shield wire above the conductors for lightning protection. The structures located between Inyokern Substation and Ivanpah Substation are configured with the three phases horizontally spaced with dual overhead shield wires above the conductors for lightning protection in limited areas.

The existing subtransmission lines are comprised of 4/0 "Penguin" Aluminum Conductor Steel Reinforced (ACSR), 795 kcmil All Aluminum Conductor (AAC) "Arbutus", and 336 kcmil "Oriole" ACSR sections with select spans of 954 kcmil 37/0 AAC and 653.9 kcmil 18/3 ACSR in the section between Kramer Substation and Inyokern Substation. The original subtransmission lines were constructed between 1912 and 1969, with some modifications implemented in the last decade.

The original IC Project, included in SCE's July 2019 Application, proposed a complete rebuild of each of the subtransmission lines included in the Project, including the removal of all existing structures and conductor and the installation of new structures and conductor. The currently-proposed IC Project, included in SCE's April 2020 Application, proposes a complete rebuild of two subtransmission lines, the reconductor of two other subtransmission lines, and the derating of one subtransmission line. The location of this work, and the scopes of work along each subtransmission line, are presented in the 'Geographic Segments' and 'Summary of IC Project Components by Segment' sections below.

[25] CPUC Decision 06-01-042, p. 11.

GEOGRAPHIC SEGMENTS

The construction activities proposed under the IC Project are described in detail for each geographic segment, including the planned structure and conductor removals and installations and approximate line length values. For visual reference, Figure 1 depicts the location of each segment along the IC Project alignment.

Figure 1 – IC Project Subtransmission Line Route Segments



The IC Project has been divided into the following phase arrangement segments in the PEA. The sections are further subdivisions of the lines based on the line design and phasing.

Table 2 – IC Project Segment 1, 126.2 miles, Approximate Section Lengths

Segment & Section	Start Structure	End Structure	Approx. Length
IC Segment 1 Section 1	Control Substation	Structure 214	25.6 miles
IC Segment 1 Section 2	Structure 214	Structure 442	27.7 miles
IC Segment 1 Section 3	Structure 442	Structure 683	25.4 miles
IC Segment 1 Section 4	Structure 683	Structure 912	27.2 miles
IC Segment 1 Section 5	Structure 912	Inyokern Substation	20.3 miles

Table 3 – IC Project Segment 2, 48.3 miles, Approximate Section Lengths

Segment & Section	Start Structure	End Structure	Approx. Length
IC Segment 2 Section 1	Kramer Substation	Structure 121255	15.5 miles
IC Segment 2 Section 2	Structure 121255	Randsburg Substation	11.0 miles
IC Segment 2 Section 3	Randsburg Substation	Structure 121042	15.6 miles
IC Segment 2 Section 4	Structure 121042	Inyokern Substation	6.2 miles

Table 4 – IC Project Segments 3N & 3S, 44.4 & 43.5 miles, Approximate Section Lengths

Segment & Section	Start Structure	End Structure	Approx. Length
IC Segment 3N	Kramer Substation	Coolwater Substation	44.4 miles
IC Segment 3S Section 1	Kramer Substation	Tortilla Substation	32.1 miles
IC Segment 3S Section 2	Tortilla Substation	Coolwater Substation	11.4 miles

Table 5 – IC Project Segment 4, 95.3 miles, Approximate Section Lengths

Segment & Section	Start Structure	End Structure	Approx. Length
IC Segment 4 Section 1	Coolwater Substation	Structure 128574	5.6 miles
IC Segment 4 Section 2	Structure 128574	Structure 128595	3.0 miles
IC Segment 4 Section 3	Structure 128595	Structure 128638	6.0 miles
IC Segment 4 Section 4	Structure 128638	Structure 128660	3.1 miles
IC Segment 4 Section 5	Structure 128660	Structure 128699	5.6 miles
IC Segment 4 Section 6	Structure 128699	Structure 128716	2.4 miles

Segment & Section	Start Structure	End Structure	Approx. Length
IC Segment 4 Section 7	Structure 128716	Dunn Siding Substation	2.7 miles
IC Segment 4 Section 8	Dunn Siding Substation	Structure 128753	2.6 miles
IC Segment 4 Section 9	Structure 128753	Structure 128774	2.9 miles
IC Segment 4 Section 10	Structure 128774	Structure 128817	5.9 miles
IC Segment 4 Section 11	Structure 128817	Structure 128840	3.0 miles
IC Segment 4 Section 12	Structure 128840	Structure 128882	5.9 miles
IC Segment 4 Section 13	Structure 128882	Structure 128904	3.0 miles
IC Segment 4 Section 14	Structure 128904	Baker Substation	4.3 miles
IC Segment 4 Section 15	Baker Substation	Structure 128949	2.0 miles
IC Segment 4 Section 16	Structure 128949	Structure 128971	3.1 miles
IC Segment 4 Section 17	Structure 128971	Structure 1281015	6.3 miles
IC Segment 4 Section 18	Structure 1281015	Structure 1281039	3.4 miles
IC Segment 4 Section 19	Structure 1281039	Structure 1281082	6.2 miles
IC Segment 4 Section 20	Structure 1281082	Structure 1281104	3.1 miles
IC Segment 4 Section 21	Structure 1281104	Structure 1281146	5.8 miles
IC Segment 4 Section 22	Structure 1281146	Structure 1281167	2.6 miles
IC Segment 4 Section 23	Structure 1281167	Mt. Pass Substation	0.9 miles
IC Segment 4 Section 24	Mt. Pass Substation	Structure 1281210	4.8 miles
IC Segment 4 Section 25	Structure 1281210	Ivanpah Substation	1.1 miles

SUMMARY OF IC PROJECT COMPONENTS BY SEGMENT

IC Project Segment 1 Section 1, Control Substation – Str. 214

- Remove all existing structures.
- Install approximately 119 TSP and 62 LWS Structures.
- Reconductor the subtransmission lines by removing all existing conductor and installing 714 kcmil Dove Aluminum Conductor Composite Core (ACCC) conductor along the 25.6 mile segment.

IC Project Segment 1 Section 2, Str. 214 – Str. 442
- Remove all existing structures.
- Install approximately 87 TSP and 95 LWS Structures.
- Reconductor the subtransmission lines by removing all existing conductor and installing 714 kcmil Dove ACCC conductor along the 27.7 mile segment.

IC Project Segment 1 Section 3, Str. 442 – Str. 683
- Remove all existing structures.
- Install approximately 90 TSP and 96 LWS Structures.
- Reconductor the subtransmission lines by removing all existing conductor and installing 714 kcmil Dove ACCC conductor along the 25.4 mile segment.

IC Project Segment 1 Section 4, Str. 683 – Str. 912
- Remove all existing structures.
- Install approximately 63 TSP and 134 LWS Structures.
- Reconductor the subtransmission lines by removing all existing conductor and installing 714 kcmil Dove ACCC conductor along the 27.2 mile segment.

IC Project Segment 1 Section 5, Str. 912 – Inyokern Substation
- Remove all existing structures.
- Install approximately 149 TSP and 10 LWS Structures.
- Reconductor the subtransmission lines by removing all existing conductor and installing 714 kcmil Dove ACCC conductor along the 20.3 mile segment.

IC Project Segment 2 Section 1, Kramer Substation – Str. 121255
- Remove all existing structures except Str 121134A.
- Install approximately 118 TSP and no LWS Structures.
- Reconductor the subtransmission line by removing all existing conductor and installing 714 kcmil Dove ACCC conductor along the 15.5 mile segment.

IC Project Segment 2 Section 2, Str. 121255 – Randsburg Substation
- Remove all existing structures.
- Install approximately 87 TSP and no LWS Structures.
- Reconductor the subtransmission line by removing all existing conductor and installing 714 kcmil Dove ACCC conductor along the 11.0 mile segment.

IC Project Segment 2 Section 3, Randsburg Substation – Str. 121042
- Remove all existing structures.
- Install approximately 108 TSP and no LWS Structures.
- Reconductor the subtransmission line by removing all existing conductor and installing 714 kcmil Dove ACCC conductor along the 15.6 mile segment.

IC Project Segment 2 Section 4, Str. 121042 – Inyokern Substation
- Remove all existing structures.
- Install approximately 30 TSP and no LWS Structures.
- Reconductor the subtransmission line by removing all existing conductor and installing 714 kcmil Dove ACCC conductor along the 6.2 mile segment.

IC Project Segment 3N, Kramer Substation – Coolwater Substation
- Install 11 structures of various types to match existing structures.
- Reconductor the subtransmission line by removing all existing conductor and installing 714 kcmil Dove ACCC conductor along the 44.4 mile segment.

IC Project Segment 3S Section 1, Kramer Substation – Tortilla Substation
- Install 11 structures of various types to match existing structures.
- Reconductor the subtransmission line by removing all existing conductor and installing 714 kcmil Dove ACCC conductor along the 32.1 mile segment.

IC Project Segment 3S Section 2, Tortilla Substation – Coolwater Substation
- Install 4 structures of various types to match existing structures.
- Reconductor the subtransmission line by removing all existing conductor and installing 714 kcmil Dove ACCC conductor along the 11.4 mile segment.

IC Project Segment 4 Section 1, Coolwater Substation – Str. 128574
- Install 4 structures of various types to match existing structures.
- The existing line will be derated to 165 Amps to minimize sag.

IC Project Segment 4 Section 2, Str. 128574 – Str. 128595
- The existing line will be derated to 165 Amps to minimize sag.

IC Project Segment 4 Section 3, Str. 128595 – Str. 128638
- Install 3 structures of various types to match existing structures.
- The existing line will be derated to 165 Amps to minimize sag.

IC Project Segment 4 Section 4, Str. 128638– Str. 128660
- Install 1 structures of various types to match existing structures.
- The existing line will be derated to 165 Amps to minimize sag.

IC Project Segment 4 Section 5, Str. 128660 – Str. 128699
- Install 3 structures of various types to match existing structures.
- The existing line will be derated to 165 Amps to minimize sag.

IC Project Segment 4 Section 6, Str. 128699 – Str. 128716
- The existing line will be derated to 165 Amps to minimize sag.

IC Project Segment 4 Section 7, Str. 128716 – Dunn Siding Substation
- Install 4 structures of various types to match existing structures.
- The existing line will be derated to 165 Amps to minimize sag.

IC Project Segment 4 Section 8, Dunn Siding Substation – Str. 128753
- Install 3 structures of various types to match existing structures.
- The existing line will be derated to 150 Amps to minimize sag.

IC Project Segment 4 Section 9, Str. 128753 – Str. 128774
- Install 1 structure to match existing structure.
- The existing line will be derated to 150 Amps to minimize sag.

IC Project Segment 4 Section 10, Str. 128774 – Str. 128817
- Install 5 structures of various types to match existing structures.
- The existing line will be derated to 150 Amps to minimize sag.

IC Project Segment 4 Section 11, Str. 128817– Str. 128840
- The existing line will be derated to 150 Amps to minimize sag.

IC Project Segment 4 Section 12, Str. 128840 – Str. 128882
- The existing line will be derated to 150 Amps to minimize sag.

IC Project Segment 4 Section 13, Str. 128882 – Str. 128904
- Install 1 structure to match existing structure.
- The existing line will be derated to 150 Amps to minimize sag.

IC Project Segment 4 Section 14, Str. 128904 – Baker Substation
- Install 2 structures of various types to match existing structures.
- The existing line will be derated to 150 Amps to minimize sag.

IC Project Segment 4 Section 15, Baker Substation – Str. 128949
- The existing line will be derated to 215 Amps to minimize sag.

IC Project Segment 4 Section 16, Str. 128949 – Str. 128971
- The existing line will be derated to 215 Amps to minimize sag.

IC Project Segment 4 Section 17, Str. 128971 – Str. 1281015
- Install 3 structures of various types to match existing structures.
- The existing line will be derated to 215 Amps to minimize sag.

IC Project Segment 4 Section 18, Str. 1281015 – Str. 1281039
- Install 5 structures of various types to match existing structures.
- The existing line will be derated to 215 Amps to minimize sag.

IC Project Segment 4 Section 19, Str. 1281039 – Str. 1281082
- Install 14 structures of various types to match existing structures.
- The existing line will be derated to 215 Amps to minimize sag.

IC Project Segment 4 Section 20, Str. 1281082 – Str. 1281104
- Install 5 structures of various types to match existing structures.
- The existing line will be derated to 215 Amps to minimize sag.

IC Project Segment 4 Section 21, Str. 1281104 – Str. 1281146
- Install 6 structures of various types to match existing structures.
- The existing line will be derated to 215 Amps to minimize sag.

IC Project Segment 4 Section 22, Str. 1281146 – Str. 1281167
- The existing line will be derated to 215 Amps to minimize sag.

IC Project Segment 4 Section 23, Str. 1281167 – Mt. Pass Substation
- The existing line will be derated to 215 Amps to minimize sag.

IC Project Segment 4 Section 24, Mt. Pass Substation – Str. 1281210
- Install 2 structures of various types to match existing structures.
- The existing line will be derated to 240 Amps to minimize sag.

IC Project Segment 4 Section 25, Str. 1281210 – Ivanpah Substation
- The existing line will be derated to 240 Amps to minimize sag.

EVALUATION OF MAGNETIC FIELD REDUCTION DESIGN OPTIONS

Ivanpah – Control Segment 1, Control - Inyokern

A series of EMF analyses was completed for the subtransmission lines included in the IC Project located in Segment 1, and a calculated typical EMF profile is shown for each segment as well as an existing conditions calculation. The calculated magnetic fields can be found in Figure 2 – Figure 11 and Table 8 – Table 12. The magnetic field calculations were obtained using the proposed line design's PLS-CADD model and the 2008 CAISO amperages of 415A per each of the double circuit lines. Values shown in this report are not meant to be predictive of any date or any time but are to be used for a comparison of structure arrangements.

Ivanpah – Control Segment 2, Kramer - Randsburg - Inyokern

A series of EMF analyses was completed on the subtransmission lines included in the IC Project located in Segment 2, and a calculated typical EMF profile is shown for each segment as well as an existing conditions calculation. The calculated magnetic fields can be found in Figure 12 – Figure 19 and Table 13 – Table 16. The magnetic field calculations were obtained using the proposed line design's PLS-CADD model and the 2008 CAISO amperage of 830A. Values shown in this report are not meant to be predictive of any date or any time but are to be used for a comparison of structure arrangements.

Ivanpah – Control Segment 3N, Kramer - Coolwater

A series of EMF analyses was completed on the subtransmission lines included in the IC Project located in Segment 3N, and a calculated typical EMF profile is shown for each segment as well as an existing conditions calculation. The calculated magnetic fields can be found in Figure 20 – Figure 21 and Table 17. The magnetic field calculations were obtained using the proposed line design's PLS-CADD model and the 2008 CAISO amperage of 950A. Values shown in this report are not meant to be predictive of any date or any time but are to be used for a comparison of structure arrangements.

Ivanpah – Control Segment 3S, Kramer - Tortilla - Coolwater

A series of EMF analyses was completed on the subtransmission lines included in the IC Project located in Segment 3S, and a calculated typical EMF profile is shown for each segment as well as an existing conditions calculation. The calculated magnetic fields can be found in Figure 22 – Figure 25 and Table 18 – Table 19. The magnetic field calculations were obtained using the proposed line design's PLS-CADD model and the 2008 CAISO amperage of 975A. Values shown in this report are not meant to be predictive of any date or any time but are to be used for a comparison of structure arrangements.

Ivanpah – Control Segment 4, Ivanpah - Mt. Pass - Baker - Dunn Siding - Coolwater

A series of EMF analyses was completed on the subtransmission lines included in the IC Project located in Segment 4 and a calculated typical EMF profile is shown for each segment as well as an existing conditions calculation. The calculated magnetic fields can be found in Figure 26 – Figure 75 and Table 20 – Table 44. The magnetic field calculations were obtained using the proposed line design's PLS-CADD model and the derated amperages as listed in Table 6 below. The derated amperages are based on the PLS-CADD model for clearance mitigations. Values shown in this report are not meant to be predictive of any date or any time but are to be used for a comparison of structure arrangements.

Table 6 – Segment 4 Non-Derated vs. Derated Amps

Segment	Section	To	From	2008 CAISO Normal Rating (Amps)	Derated (Amps)
4	1 - 7	Coolwater	Dunn Siding	415	165
4	8 - 14	Dunn Siding	Baker	415	150
4	15 - 23	Baker	Mountain Pass	415	215
4	24 - 25	Mountain Pass	Ivanpah	415	240

Residential Graphs

An additional series of EMF analyses were completed on the subtransmission lines in residential areas throughout the project. Calculated typical EMF profiles are shown for these locations as well as an existing conditions calculation. The calculated magnetic fields can be found in Figure 76 – Figure 97 and Table 45 – Table 55. The magnetic field calculations were obtained using the proposed line design's PLS-CADD model and the 2008 CAISO amperage in each area. Values shown in this report are not meant to be predictive of any date or any times.

MAGNETIC FIELD ASSUMPTIONS

- Magnetic field characteristics were modeled using PLS-CADD software.
- Magnetic field models and the calculated results of magnetic field levels present in this document are intended only for the purposes of identifying relative differences in the magnetic field levels for the purpose of comparison and discussion of design alternatives to determine if a 15% or more reduction of magnetic field levels at the edges of the right of way can be achieved. These calculated results are not intended to be applied as actual predictions of magnetic fields at any specific time or location during or following project construction.
- All lines were modeled with balanced line currents and standard phases. Variation of phasing did not matter as long as the opposite circuit was modeled appropriately.
- Amperages and phasing were supplied by SCE. The amperages used to calculate the EMF for the IC Project were furnished by SCE for the 2008 CAISO ratings.
- Where data did not exist for the non-SCE parallel lines, reasonable assumptions were made for phase arrangement, conductor sizes, and load amperages.
- Existing conductor heights were based on preliminary subtransmission line models.
- Wire height used is the height of the wire where the target point is projected upon it.
- Wire position is determined by the currently displayed weather case.
- The current conductor type, ACSR, sags much more than the proposed conductor type, ACCC, resulting in lower EMF values. This generally leads to lower EMF results for the ACCC conductors.
- Magnetic field strength was calculated at a height of 3 feet above the terrain surface.
- Calculations were made at mid span.
- All calculations based on the EPRI Red Book methods (2nd Edition, 1982 - infinite straight wire with flat earth approximation), assuming flat terrain.
- These approximations are only valid for low frequency (50-60 Hz) AC transmission lines.
- The effects of earth return currents (earth resistivity) are ignored when calculating the magnetic field.
- 2008 CAISO Normal Ratings (Amps) provided by SCE for Circuit without the Proposed Project:

Table 7 – 2008 CAISO Normal Ratings

Description	Segment	2008 CAISO Normal Rating (Amps)
Control-Haiwee-Inyokern; Control Tap	1	830 (415 per line)
Control-Coso-Haiwee-Inyokern; Control Tap	1	830 (415 per line)
Kramer-Inyokern-Randsburg No. 1	2	830
Kramer-Coolwater	3N	950
Kramer-Tortilla	3S	975
Coolwater Segs 2 - Tortilla	3S	975

Description	Segment	2008 CAISO Normal Rating (Amps)
Ivanpah-Baker-Coolwater-Dunn Siding-Mountain Pass; Mountain Pass to Baker	4	415

FINAL RECOMMENDATIONS FOR MAGNETIC FIELD REDUCTION DESIGN

The IC Project design can benefit from double circuit construction, and vertical and delta conductor arrangement. Implementing both low cost and no cost measures significantly reduces the magnetic field and potential exposure risk well below CPUC approved EMF Design Guidelines as well as all national and state safety standards for reconductoring or new electric facilities.

Reduction Measures

1. Arrange conductors in a vertical or delta configuration for magnetic field reduction. This is considered a no cost measure as the entire line maintains the recommended phase arrangement.

2. Utilize double-circuit construction that reduces spacing between circuits as compared with single-circuit construction.

3. Utilize structure heights that meet or exceed EMF preferred design criteria of SCE.

4. After construction, change the phase arrangement as the circuit enters the substation thereby changing the final phasing to further reduce the magnetic field.

SEGMENT GRAPHS

These graphs are based on calculations that occur on spans that are the lowest within each section. In each of the Typical Magnetic Field Levels graphs presented in this document, the term "Proposed Project" is synonymous with the "IC Project" as described in Chapter 3 of the IC Project PEA document.

Segment 1 Section 1

Figure 2 - Typical Magnetic Field Levels for Segment 1 Section 1 Control – Structure 214, Str. 169 - 170 at 415 Amps



Table 8 – Comparison of Magnetic Fields at Edge of ROW for Segment 1 Section 1 Str. 169 - 170

Design Options	Left Edge (mG)	% Change[26]	Right Edge (mG)	% Change[26]
Projected Peak Values without Proposed Project 115 kV T/L	27.766	N/A	27.744	N/A
Proposed Project Peak Values 115 kV T/L During Construction	18.896	32% Decrease	18.975	32% Decrease
Proposed Project Peak Values 115 kV T/L After Construction	4.915	82% Decrease	4.946	82% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 70 Ft. Length – 4.5 Ft.

Proposed Construction and Insulator Length
Height – 85 Ft. Length – 4 Ft.

[26] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 3 – Tower and Insulator Dimensions and Phasing



Proposed After Construction:
Double Circuit – Monopole
Figure not to Scale

Proposed During Construction:
Double Circuit – Monopole
Figure not to Scale



Existing:
Double circuit - Lattice Tower
Figure not to Scale

Note: The phasing shown is due to the transposition requirements for this section of the line.

Segment 1 Section 2

Figure 4 - Typical Magnetic Field Levels for Segment 1 Section 2 Structure 214 – Structure 442, Str. 251 - 252 at 415 Amps



Table 9 – Comparison of Magnetic Fields at Edge of ROW for Segment 1 Section 2 Str. 251 - 252

Design Options	Left Edge (mG)	% Change[27]	Right Edge (mG)	% Change[27]
Projected Peak Values without Proposed Project 115 kV T/L	44.226	N/A	40.615	N/A
Proposed Project Peak Values 115 kV T/L During Construction	25.722	42% Decrease	25.722	37% Decrease
Proposed Project Peak Values 115 kV T/L After Construction	7.674	83% Decrease	7.674	81% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 70 Ft. Length – 4.5 Ft.

Proposed Construction and Insulator Length
Height – 85 Ft. Length – 4 Ft.

[27] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 5 – Tower and Insulator Dimensions and Phasing



Proposed After Construction:
Double Circuit – Monopole
Figure not to Scale

Proposed During Construction:
Double Circuit – Monopole
Figure not to Scale



Existing:
Double circuit - Lattice Tower
Figure not to Scale

Note: The phasing shown is due to the transposition requirements for this section of the line.

Segment 1 Section 3

Figure 6 - Typical Magnetic Field Levels for Segment 1 Section 3 Structure 442 – Structure 683, Str. 544 - 545 at 415 Amps



Table 10 – Comparison of Magnetic Fields at Edge of ROW for Segment 1 Section 3 Str. 544 - 545

Design Options	Left Edge (mG)	% Change[28]	Right Edge (mG)	% Change[28]
Projected Peak Values without Proposed Project 115 kV T/L	28.439	N/A	29.318	N/A
Proposed Project Peak Values 115 kV T/L During Construction	21.294	25% Decrease	21.294	27% Decrease
Proposed Project Peak Values 115 kV T/L After Construction	6.307	78% Decrease	6.307	78% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 70 Ft. Length – 4.5 Ft.

Proposed Construction and Insulator Length
Height – 95 Ft. Length – 4 Ft.

[28] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 7 – Tower and Insulator Dimensions and Phasing



Proposed After Construction:
Double Circuit – Monopole
Figure not to Scale

Proposed During Construction:
Double Circuit – Monopole
Figure not to Scale



Existing:
Double circuit - Lattice Tower
Figure not to Scale

Note: The phasing shown is due to the transposition requirements for this section of the line.

Segment 1 Section 4

Figure 8 - Typical Magnetic Field Levels for Segment 1 Section 4 Structure 683 – Structure 912, Str. 768 - 769 at 415 Amps



Table 11 – Comparison of Magnetic Fields at Edge of ROW for Segment 1 Section 4 Str. 768 - 769

Design Options	Left Edge (mG)	% Change[29]	Right Edge (mG)	% Change[29]
Projected Peak Values without Proposed Project 115 kV T/L	19.376	N/A	24.466	N/A
Proposed Project Peak Values 115 kV T/L During Construction	25.273	30% Increase	25.273	3% Increase
Proposed Project Peak Values 115 kV T/L After Construction	7.404	62% Decrease	7.404	70% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 70 Ft. Length – 4.5 Ft.

Proposed Construction and Insulator Length
Height – 90 Ft. Length – 4 Ft.

[29] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 9 – Tower and Insulator Dimensions and Phasing



Proposed After Construction:
Double Circuit – Monopole
Figure not to Scale

Proposed During Construction:
Double Circuit – Monopole
Figure not to Scale



Existing:
Double circuit - Lattice Tower
Figure not to Scale

Note: The phasing shown is due to the transposition requirements for this section of the line.

Segment 1 Section 5

Figure 10 - Typical Magnetic Field Levels for Segment 1 Section 5 Structure 912 – Inyokern Substation, Str. 957 - 958 at 415 Amps



Table 12 – Comparison of Magnetic Fields at Edge of ROW for Segment 1 Section 5 Str. 957 - 959

Design Options	Left Edge (mG)	% Change[30]	Right Edge (mG)	% Change[30]
Projected Peak Values without Proposed Project 115 kV T/L	41.893	N/A	43.987	N/A
Proposed Project Peak Values 115 kV T/L During Construction	23.83	43% Decrease	23.83	46% Decrease
Proposed Project Peak Values 115 kV T/L After Construction	7.088	83% Decrease	7.088	84% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 85 Ft. Length – 4.5 Ft.

Proposed Construction and Insulator Length
Height – 110 Ft. Length – 4 Ft.

[30] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 11 – Tower and Insulator Dimensions and Phasing



Proposed After Construction:
Double Circuit – Monopole
Figure not to Scale

Proposed During Construction:
Double Circuit – Monopole
Figure not to Scale



Existing:
Double Circuit - Lattice Tower
Figure not to Scale

Note: The phasing shown is due to the transposition requirements for this section of the line.

Segment 2 Section 1

Figure 12 - Typical Magnetic Field Levels for Segment 2 Section 1 Kramer Substation – Structure 121255, Str. 121257 - 121256 at 830 Amps



Assuming Curlew ACSR conductor, Top-Bottom phasing 0°,120°,240°-0°,120°,240°, and 400 Amps for parallel line.
Graph is extended to show the influence of the parallel line.

Table 13 – Comparison of Magnetic Fields at Edge of ROW for Segment 2 Section 1 Str. 121257 - 121256

Design Options	Left Edge (mG)	% Change[31]	Right Edge (mG)	% Change[31]
Projected Peak Values without Proposed Project 115 kV T/L	66.195	N/A	43.518	N/A
Proposed Project Peak Values 115 kV T/L	32.969	50% Decrease	32.276	26% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 70 Ft. Length – 4.5 Ft.

Proposed Construction and Insulator Length
Height – 88 Ft. Length – 4 Ft.

[31] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 13 – Tower and Insulator Dimensions and Phasing



Proposed:
Single Circuit – Monopole
Figure not to Scale



Existing:
Double Circuit - Lattice Tower
Figure not to Scale

Segment 2 Section 2

Figure 14 - Typical Magnetic Field Levels for Segment 2 Section 2 Structure 121255 – Randsburg Substation, Str. 121170 - 121169 at 830 Amps



Table 14 – Comparison of Magnetic Fields at Edge of ROW for Segment 2 Section 2 Str. 121170 - 121169

Design Options	Left Edge (mG)	% Change[32]	Right Edge (mG)	% Change[32]
Projected Peak Values without Proposed Project 115 kV T/L	12.046	N/A	12.111	N/A
Proposed Project Peak Values 115 kV T/L	11.04	8% Decrease	9.732	20% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 71 Ft. Length – 4.5 Ft.

Proposed Construction and Insulator Length
Height – 82 Ft. Length – 4 Ft.

[32] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 15 – Tower and Insulator Dimensions and Phasing



Proposed:
Single Circuit – Monopole
Figure not to Scale



Existing:
Double Circuit - Lattice Tower
Figure not to Scale

Segment 2 Section 3

Figure 16 - Typical Magnetic Field Levels for Segment 2 Section 3 Randsburg Substation – Structure 121042, Str. 121124 - 121123 at 830 Amps



Assuming Curlew ACSR conductor, Top-Bottom phasing 0°,120°,240°-0°,120°,240°, and 400 Amps for parallel line.
Graph is extended to show the influence of the parallel line.

Table 15 – Comparison of Magnetic Fields at Edge of ROW for Segment 2 Section 3 Str. 121124 - 121123

Design Options	Left Edge (mG)	% Change[33]	Right Edge (mG)	% Change[33]
Projected Peak Values without Proposed Project 115 kV T/L	26.491	N/A	39.544	N/A
Proposed Project Peak Values 115 kV T/L	23.198	12% Decrease	24.135	39% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 69 Ft. Length – 4.5 Ft.

Proposed Construction and Insulator Length
Height – 84 Ft. Length – 4 Ft.

[33] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 17 – Tower and Insulator Dimensions and Phasing



Proposed:
Single Circuit – Monopole
Figure not to Scale



Existing:
Double Circuit - Lattice Tower
Figure not to Scale

Segment 2 Section 4

Figure 18 - Typical Magnetic Field Levels for Segment 2 Section 4 Structure 121042 – Inyokern Substation, Str. 120997 - 120996 at 830 Amps



Assuming Curlew ACSR conductor, Top-Bottom phasing 0°,120°,240°-0°,120°,240°, and 400 Amps for parallel line.
Graph is extended to show the influence of the parallel line.

Table 16 – Comparison of Magnetic Fields at Edge of ROW for Segment 2 Section 4 Str. 120997 - 120996

Design Options	Left Edge (mG)	% Change[34]	Right Edge (mG)	% Change[34]
Projected Peak Values without Proposed Project 115 kV T/L	20.457	N/A	57.275	N/A
Proposed Project Peak Values 115 kV T/L	31.256	53% Increase	31.491	45% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 70 Ft. Length – 4.5 Ft.

Proposed Construction and Insulator Length
Height – 84 Ft. Length – 4 Ft.

[34] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 19 – Tower and Insulator Dimensions and Phasing



Proposed:
Single Circuit – Monopole
Figure not to Scale



Existing:
Double Circuit - Lattice Tower
Figure not to Scale

Segment 3N

Figure 20 - Typical Magnetic Field Levels for Segment 3N Kramer Substation – Coolwater Substation, Str. 2012 (N1561186E_S1561185E) - 2013 (N4457229E_S4457230E) at 950 Amps

(Structure numbers are between brackets while the four digit numbers are the construction numbers)



Assuming Drake ACSR conductor, Top-Bottom phasing 0°,120°,240°-0°,120°,240°, and 400 Amps for the parallel line.
Graph is extended to show the influence of the parallel line.

Table 17 – Comparison of Magnetic Fields at Edge of ROW for Segment 3N Str. N1561186E_S1561185E- N4457229E_S4457230E

Design Options	Left Edge (mG)	% Change[35]	Right Edge (mG)	% Change[35]
Projected Peak Values without Proposed Project 115 kV T/L	37.534	N/A	23.066	N/A
Proposed Project Peak Values 115 kV T/L	12.017	68% Decrease	24.004	4% Increase

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 57 Ft. Length – 4.5 Ft.

[35] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 21 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 3S Section 1

Figure 22 - Typical Magnetic Field Levels for Segment 3S Section 1 Kramer Substation – Tortilla Substation, Str. 3166 (NA560144AE_SA560144BE) - 3167 (NA560143AE_SA560143BE) at 975 Amps

(Structure numbers are between brackets while the four digit numbers are the construction numbers)



Table 18 – Comparison of Magnetic Fields at Edge of ROW for Segment 3S Section 1 Str. NA560144AE_SA560144BE - NA560143AE_SA560143BE

Design Options	Left Edge (mG)	% Change[36]	Right Edge (mG)	% Change[36]
Projected Peak Values without Proposed Project 115 kV T/L	21.338	N/A	21.998	N/A
Proposed Project Peak Values 115 kV T/L	20.003	6% Decrease	20.457	7% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 58 Ft. Length – 4.5 Ft.

[36] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 23 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 3S Section 2

Figure 24 - Typical Magnetic Field Levels for Segment 3S Section 2 Tortilla Substation – Coolwater Substation, Str 3236 - 3237 (1811388E - 1811383E) at 975 Amps

(Structure numbers are between brackets while the four digit numbers are the construction numbers)



Table 19 – Comparison of Magnetic Fields at Edge of ROW for Segment 3S Section 2 Str. 3235 - 3236

Design Options	Left Edge (mG)	% Change[37]	Right Edge (mG)	% Change[37]
Projected Peak Values without Proposed Project 115 kV T/L	14.418	N/A	13.741	N/A
Proposed Project Peak Values 115 kV T/L	14.37	0% Decrease	13.655	1% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 67 Ft. Length – 3.5 Ft.

Note: Typical structures in this section are H-Frames, and monopoles are used near the Tortilla Substation. The span next to the substation has the lowest mid-span, therefore this span was used in EMF calculations.

[37] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 25 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit - Monopole
Figure not to Scale

Note: Typical structures in this section are H-Frames, and monopoles are used near the Tortilla Substation. The span next to the substation has the lowest mid-span, therefore this span was used in EMF calculations.

Segment 4 Section 1

Figure 26 - Typical Magnetic Field Levels for Segment 4 Section 1 Coolwater Substation – Structure 128574, Str. 128568 - 128569 at 165 Amps



Assuming Partridge ACSR conductor, Top-Bottom phasing 0°,120°,240° and 400 Amps for parallel line. Graph is extended to show the influence of the parallel line.

Table 20 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 1 Str. 128568 - 128569

Design Options	Left Edge (mG)	% Change[38]	Right Edge (mG)	% Change[38]
Projected Peak Values without Proposed Project 115 kV T/L	43.026	N/A	28.842	N/A
Proposed Project Peak Values 115 kV T/L	25.581	41% Decrease	10.244	64% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 52 Ft. Length – 4.5 Ft.

[38] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 27 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 2

Figure 28 - Typical Magnetic Field Levels for Segment 4 Section 2 Structure 128574 – Structure 128595, Str. 128585 - 128586 at 165 Amps



Table 21 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 2 Str. 128585 - 128586

Design Options	Left Edge (mG)	% Change[39]	Right Edge (mG)	% Change[39]
Projected Peak Values without Proposed Project 115 kV T/L	29.316	N/A	30.282	N/A
Proposed Project Peak Values 115 kV T/L	10.71	63% Decrease	10.838	64% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 52 Ft. Length – 4.5 Ft.

[39] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 29 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 3

Figure 30 - Typical Magnetic Field Levels for Segment 4 Section 3 Structure 128595 – Structure 128638, Str. 128614-128615 at 165 Amps



Table 22 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 3 Str. 128614-128615

Design Options	Left Edge (mG)	% Change[40]	Right Edge (mG)	% Change[40]
Projected Peak Values without Proposed Project 115 kV T/L	52.149	N/A	53.513	N/A
Proposed Project Peak Values 115 kV T/L	17.825	66% Decrease	18.188	66% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 53 Ft. Length – 4.5 Ft.

[40] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 31 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 4

Figure 32 - Typical Magnetic Field Levels for Segment 4 Section 4 Structure 128638 – Structure 128660, Str. 128645 - 128646 at 165 Amps



Table 23 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 4 Str. 128645 - 128646

Design Options	Left Edge (mG)	% Change[41]	Right Edge (mG)	% Change[41]
Projected Peak Values without Proposed Project 115 kV T/L	43.919	N/A	46.016	N/A
Proposed Project Peak Values 115 kV T/L	15.081	66% Decrease	15.571	66% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 52 Ft. Length – 4.5 Ft.

[41] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 33 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 5

Figure 34 - Typical Magnetic Field Levels for Segment 4 Section 5 Structure 128660 – Structure 128699, Str. 128684 - 128685 at 165 Amps



Table 24 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 5 Str. 128684 - 128685

Design Options	Left Edge (mG)	% Change[42]	Right Edge (mG)	% Change[42]
Projected Peak Values without Proposed Project 115 kV T/L	29.207	N/A	30.559	N/A
Proposed Project Peak Values 115 kV T/L	10.843	63% Decrease	11.301	63% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 64 Ft. Length – 4.5 Ft.

[42] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 35 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 6

Figure 36 - Typical Magnetic Field Levels for Segment 4 Section 6 Structure 128699 – Structure 128716, Str. 128712 -128713 at 165 Amps



Table 25 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 6 Str. 128712 -128713

Design Options	Left Edge (mG)	% Change[43]	Right Edge (mG)	% Change[43]
Projected Peak Values without Proposed Project 115 kV T/L	62.237	N/A	65.846	N/A
Proposed Project Peak Values 115 kV T/L	18.716	70% Decrease	19.642	70% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height –53 Ft. Length – 4.5 Ft.

[43] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 37 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 7

Figure 38 - Typical Magnetic Field Levels for Segment 4 Section 7 Structure 128716 – Dunn Siding Substation, Str. 128730 - 128731 at 165 Amps



Table 26 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 7 Str. 128730 - 128731

Design Options	Left Edge (mG)	% Change[44]	Right Edge (mG)	% Change[44]
Projected Peak Values without Proposed Project 115 kV T/L	64.45	N/A	71.411	N/A
Proposed Project Peak Values 115 kV T/L	21.864	66% Decrease	23.818	67% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 52 Ft. Length – 4.5 Ft.

*Projected Peak Values without Proposed Project use Non-Derated Amps Value 260 A.

[44] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 39 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 8

Figure 40 - Typical Magnetic Field Levels for Segment 4 Section 8 Dunn Siding Substation – Structure 128753, Str. 128745 - 128746 at 150 Amps



Table 27 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 8 Str. 128745 - 128746

Design Options	Left Edge (mG)	% Change[45]	Right Edge (mG)	% Change[45]
Projected Peak Values without Proposed Project 115 kV T/L	52.62	N/A	53.076	N/A
Proposed Project Peak Values 115 kV T/L	15.338	71% Decrease	15.787	70% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 56 Ft. Length – 4.5 Ft.

*Projected Peak Values without Proposed Project use Non-Derated Amps Value 270 A.

[45] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 41 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 9

Figure 42 - Typical Magnetic Field Levels for Segment 4 Section 9 Structure 128753 – Structure 128774, Str. 128770 - 128771 at 150 Amps



Table 28 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 9 Str. 128770 - 128771

Design Options	Left Edge (mG)	% Change[46]	Right Edge (mG)	% Change[46]
Projected Peak Values without Proposed Project 115 kV T/L	22.606	N/A	23.094	N/A
Proposed Project Peak Values 115 kV T/L	9.549	58% Decrease	9.801	58% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 51 Ft. Length – 4.5 Ft.

[46] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 43 – Tower and Insulator Dimensions and Phasing



Existing:
Single – H-Frame
Figure not to Scale

Segment 4 Section 10

Figure 44 - Typical Magnetic Field Levels for Segment 4 Section 10 Structure 128774 – Structure 128817, Str. 128804 - 128805 at 150 Amps



Table 29 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 10 Str. 128804 - 128805

Design Options	Left Edge (mG)	% Change[47]	Right Edge (mG)	% Change[47]
Projected Peak Values without Proposed Project 115 kV T/L	71.412	N/A	73.822	N/A
Proposed Project Peak Values 115 kV T/L	21.798	69% Decrease	22.091	70% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 49 Ft. Length – 4.5 Ft.

[47] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 45 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 11

Figure 46 - Typical Magnetic Field Levels for Segment 4 Section 11 Structure 128817 – Structure 128840, Str. 128825 - 128826 at 150 Amps



Table 30 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 11 Str. 128825 - 128826

Design Options	Left Edge (mG)	% Change[48]	Right Edge (mG)	% Change[48]
Projected Peak Values without Proposed Project 115 kV T/L	28.476	N/A	30.005	N/A
Proposed Project Peak Values 115 kV T/L	9.781	66% Decrease	10.223	66% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 52 Ft. Length – 4.5 Ft.

[48] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 47 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 12

Figure 48 - Typical Magnetic Field Levels for Segment 4 Section 12 Structure 128840 – Structure 128882, Str. 128867 - 128868 at 150 Amps



Table 31 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 12 Str. 128867 - 128868

Design Options	Left Edge (mG)	% Change[49]	Right Edge (mG)	% Change[49]
Projected Peak Values without Proposed Project 115 kV T/L	27.466	N/A	28.781	N/A
Proposed Project Peak Values 115 kV T/L	9.618	65% Decrease	9.946	65% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 52 Ft. Length – 4.5 Ft.

[49] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 49 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 13

Figure 50 - Typical Magnetic Field Levels for Segment 4 Section 13 Structure 128882 – Structure 128904, Str. 128885 - 128886 at 150 Amps



Table 32 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 13 Str. 128885 - 128886

Design Options	Left Edge (mG)	% Change[50]	Right Edge (mG)	% Change[50]
Projected Peak Values without Proposed Project 115 kV T/L	27.626	N/A	28.831	N/A
Proposed Project Peak Values 115 kV T/L	9.542	65% Decrease	9.96	65% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 51 Ft. Length – 4.5 Ft.

[50] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 51 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 14

Figure 52 - Typical Magnetic Field Levels for Segment 4 Section 14 Structure 128904 – Baker Substation, Str. 128917 - 128918 at 150 Amps



Table 33 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 14 Str. 128917 - 128918

Design Options	Left Edge (mG)	% Change[51]	Right Edge (mG)	% Change[51]
Projected Peak Values without Proposed Project 115 kV T/L	29.139	N/A	30.498	N/A
Proposed Project Peak Values 115 kV T/L	9.42	68% Decrease	9.822	68% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 52 Ft. Length – 4.5 Ft.

[51] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 53 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 15

Figure 54 - Typical Magnetic Field Levels for Segment 4 Section 15 Baker Substation – Structure 128949, Str. 128939 - 128940 at 215 Amps



Table 34 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 15 Str. 128939 - 128940

Design Options	Left Edge (mG)	% Change[52]	Right Edge (mG)	% Change[52]
Projected Peak Values without Proposed Project 115 kV T/L	27.224	N/A	27.904	N/A
Proposed Project Peak Values 115 kV T/L	13.124	52% Decrease	13.433	52% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 52 Ft. Length – 4.5 Ft.

[52] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 55 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 16

Figure 56 - Typical Magnetic Field Levels for Segment 4 Section 16 Structure 128949 – Structure 128971, Str. 128966 - 128967 at 215 Amps



Table 35 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 16 Str. 128966 - 128967

Design Options	Left Edge (mG)	% Change[53]	Right Edge (mG)	% Change[53]
Projected Peak Values without Proposed Project 115 kV T/L	21.282	N/A	22.126	N/A
Proposed Project Peak Values 115 kV T/L	14.13	34% Decrease	14.678	34% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 52 Ft. Length – 4.5 Ft.

[53] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 57 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 17

Figure 58 - Typical Magnetic Field Levels for Segment 4 Section 17 Structure 128971 – Structure 1281015, Str. 128990 - 128991 at 215 Amps



Table 36 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 17 Str. 128990 - 128991

Design Options	Left Edge (mG)	% Change[54]	Right Edge (mG)	% Change[54]
Projected Peak Values without Proposed Project 115 kV T/L	27.569	N/A	28.585	N/A
Proposed Project Peak Values 115 kV T/L	13.312	52% Decrease	13.768	52% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 55 Ft. Length – 4.5 Ft.

[54] All data in Percent Change column is compared to the Projected Peak Values without the IC Project



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 18

Figure 60 - Typical Magnetic Field Levels for Segment 4 Section 18 Structure 1281015 – Structure 1281039, Str. 1281018 - 1281019 at 215 Amps



Table 37 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 18 Str. 1281018 - 1281019

Design Options	Left Edge (mG)	% Change[55]	Right Edge (mG)	% Change[55]
Projected Peak Values without Proposed Project 115 kV T/L	27.61	N/A	28.403	N/A
Proposed Project Peak Values 115 kV T/L	13.599	51% Decrease	13.964	51% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 51 Ft. Length – 4.5 Ft.

[55] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 61 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 19

Figure 62 - Typical Magnetic Field Levels for Segment 4 Section 19 Structure 1281039 – Structure 1281082, Str. 1281067 - 1281068 at 215 Amps



Table 38 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 19 Str. 1281067 - 1281068

Design Options	Left Edge (mG)	% Change[56]	Right Edge (mG)	% Change[56]
Projected Peak Values without Proposed Project 115 kV T/L	28.123	N/A	28.982	N/A
Proposed Project Peak Values 115 kV T/L	13.551	52% Decrease	13.924	52% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 52 Ft. Length – 4.5 Ft.

[56] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 63 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 20

Figure 64 - Typical Magnetic Field Levels for Segment 4 Section 20 Structure 1281082 – Structure 1281104, Str. 1281098 - 1281099 at 215 Amps



Table 39 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 20 Str. 1281098 - 1281099

Design Options	Left Edge (mG)	% Change[57]	Right Edge (mG)	% Change[57]
Projected Peak Values without Proposed Project 115 kV T/L	29.998	N/A	31.04	N/A
Proposed Project Peak Values 115 kV T/L	14.576	51% Decrease	15.052	52% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 52 Ft. Length – 4.5 Ft.

[57] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 65 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 21

Figure 66 - Typical Magnetic Field Levels for Segment 4 Section 21 Structure 1281104 – Structure 1281146, Str. 1281145 - 1281146 at 215 Amps



Table 40 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 21 Str. 1281145 - 1281146

Design Options	Left Edge (mG)	% Change[58]	Right Edge (mG)	% Change[58]
Projected Peak Values without Proposed Project 115 kV T/L	20.268	N/A	20.966	N/A
Proposed Project Peak Values 115 kV T/L	9.969	51% Decrease	10.285	51% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 51 Ft. Length – 4.5 Ft.

[58] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 67 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 22

Figure 68 - Typical Magnetic Field Levels for Segment 4 Section 22 Structure 1281146 – Structure 1281167, Str. 1281154 – 1281155 at 215 Amps



Table 41 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 22 Str. 1281154 – 1281155

Design Options	Left Edge (mG)	% Change[59]	Right Edge (mG)	% Change[59]
Projected Peak Values without Proposed Project 115 kV T/L	27.091	N/A	28.089	N/A
Proposed Project Peak Values 115 kV T/L	13.211	51% Decrease	13.678	51% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 56 Ft. Length – 4.5 Ft.

[59] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 69 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 23

Figure 70 - Typical Magnetic Field Levels for Segment 4 Section 23 Structure 1281167 – Mountain Pass Substation, Str. 1281170 - 1281171 at 215 Amps



Table 42 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 23 Str. 1281170 - 1281171

Design Options	Left Edge (mG)	% Change[60]	Right Edge (mG)	% Change[60]
Projected Peak Values without Proposed Project 115 kV T/L	23.925	N/A	24.824	N/A
Proposed Project Peak Values 115 kV T/L	12.198	49% Decrease	12.645	49% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 53 Ft. Length – 4.5 Ft.

[60] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 71 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 24

Figure 72 - Typical Magnetic Field Levels for Segment 4 Section 24 Mountain Pass Substation – Structure 1281210, Str. 1281202 - 1281203 at 240 Amps



Table 43 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 24 Str. 1281202 - 1281203

Design Options	Left Edge (mG)	% Change[61]	Right Edge (mG)	% Change[61]
Projected Peak Values without Proposed Project 115 kV T/L	29.335	N/A	30.375	N/A
Proposed Project Peak Values 115 kV T/L	13.314	55% Decrease	13.557	55% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 57 Ft. Length – 4.5 Ft.

[61] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 73 – Tower and Insulator Dimensions and Phasing



Existing:

Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 25

Figure 74 - Typical Magnetic Field Levels for Segment 4 Section 25 Structure 1281210 - Ivanpah Substation, Str. 1281212- 1281213 at 240 Amps



Table 44 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 25 Str. 1281212- 1281213

Design Options	Left Edge (mG)	% Change[62]	Right Edge (mG)	% Change[62]
Projected Peak Values without Proposed Project 115 kV T/L	27.569	N/A	28.585	N/A
Proposed Project Peak Values 115 kV T/L	9.727	65% Decrease	9.963	65% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 53 Ft. Length – 4.5 Ft.

[62] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 75 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

RESIDENTIAL GRAPHS

These graphs are based on calculations that occur on spans that are the lowest near residential areas that are of concern. The magnetic field created by these spans are less in magnitude than the worst span in each segment, but these are more of a concern for the residents that live near the ROW.

Segment 1 Section 1, Str. 36-37

Figure 76 - Typical Magnetic Field Levels for Segment 1 Section 1 Control – Structure 214, Str. 36-37 at 415 Amps



Table 45 – Comparison of Magnetic Fields at Edge of ROW for Segment 1 Section 1 Str. 36-37

Design Options	Left Edge (mG)	% Change[63]	Right Edge (mG)	% Change[63]
Projected Peak Values without Proposed Project 115 kV T/L	51.553	N/A	55.029	N/A
Proposed 115 kV T/L During Construction	6.772	87% Decrease	6.785	88% Decrease
Proposed 115 kV T/L After Construction	1.199	98% Decrease	1.203	98% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 70 Ft. Length – 4.5 Ft.

Proposed Construction and Insulator Length
Height – 115 Ft. Length – 4 Ft.

The residential areas are on both sides as viewed in this graph.

[63] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 77 – Tower and Insulator Dimensions and Phasing



Proposed After Construction:
Double Circuit – Monopole
Figure not to Scale

Proposed During Construction:
Double Circuit – Monopole
Figure not to Scale



Existing:
Double circuit - Lattice Tower
Figure not to Scale

Segment 1 Section 1, Str. 55-56

Figure 78 – Typical Magnetic Field Levels for Segment 1 Section 1 Control – Structure 214, Str. 55-56 at 415 Amps



Table 46 – Comparison of Magnetic Fields at Edge of ROW for Segment 1 Section 1 Str. 55-56

Design Options	Left Edge (mG)	% Change[64]	Right Edge (mG)	% Change[64]
Projected Peak Values without Proposed Project 115 kV T/L	36.656	N/A	38.304	N/A
Proposed 115 kV T/L During Construction	14.643	60% Decrease	14.644	62% Decrease
Proposed 115 kV T/L After Construction	3.638	90% Decrease	3.638	91% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 75 Ft. Length – 4.5 Ft.

Proposed Construction and Insulator Length
Height – 115 Ft. Length – 4 Ft.

The residential area is to the right as viewed in this graph.

[64] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 79 – Tower and Insulator Dimensions and Phasing



Proposed After Construction:
Double Circuit – Monopole
Figure not to Scale

Proposed During Construction:
Double Circuit – Monopole
Figure not to Scale



Existing:
Double circuit - Lattice Tower
Figure not to Scale

Segment 1 Section 1, Str. 137-138

Figure 80 - Typical Magnetic Field Levels for Segment 1 Section 1 Control – Structure 214, Str. 137-138 at 415 Amps



Table 47 – Comparison of Magnetic Fields at Edge of ROW for Segment 1 Str. 137-138

Design Options	Left Edge (mG)	% Change[65]	Right Edge (mG)	% Change[65]
Projected Peak Values without Proposed Project 115 kV T/L	38.942	N/A	38.519	N/A
Proposed 115 kV T/L During Construction	16.803	57% Decrease	16.803	56% Decrease
Proposed 115 kV T/L After Construction	4.21	89% Decrease	4.21	89% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 70 Ft. Length – 4.5 Ft.

Proposed Construction and Insulator Length
Height – 90 Ft. Length – 4 Ft.

The residential area is to the left as viewed in this graph.

[65] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 81 – Tower and Insulator Dimensions and Phasing



Proposed After Construction:
Double Circuit – Monopole
Figure not to Scale

Proposed During Construction:
Double Circuit – Monopole
Figure not to Scale



Existing:
Double circuit - Lattice Tower
Figure not to Scale

Segment 1 Section 4, Str. 707-708

Figure 82 – Typical Magnetic Field Levels for Segment 1 Section 4 Structure 683 – Structure 912, Str. 707-708 at 415 Amps



Table 48 – Comparison of Magnetic Fields at Edge of ROW for Segment 3 Str. 707-708

Design Options	Left Edge (mG)	% Change[66]	Right Edge (mG)	% Change[66]
Projected Peak Values without Proposed Project 115 kV T/L	40.22	N/A	41.849	N/A
Proposed 115 kV T/L During Construction	21.844	46% Decrease	21.844	48% Decrease
Proposed 115 kV T/L After Construction	6.046	85% Decrease	6.046	86% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 70 Ft. Length – 4.5 Ft.

Proposed Construction and Insulator Length
Height – 100 Ft. Length – 4 Ft.

The residential area is to the right as viewed in this graph.

[66] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 83 – Tower and Insulator Dimensions and Phasing



Proposed After Construction:
Double Circuit – Monopole
Figure not to Scale

Proposed During Construction:
Double Circuit – Monopole
Figure not to Scale



Existing:
Double circuit - Lattice Tower
Figure not to Scale

Segment 1 Section 5, Str. 1045-1046

Figure 84 – Typical Magnetic Field Levels for Segment 1 Section 5 Structure 912 – Inyokern Substation, Str. 1045-1046 at 415 Amps



Table 49 – Comparison of Magnetic Fields at Edge of ROW for Segment 5 Str. 1045-1046

Design Options	Left Edge (mG)	% Change[67]	Right Edge (mG)	% Change[67]
Projected Peak Values without Proposed Project 115 kV T/L	44.968	N/A	51.628	N/A
Proposed 115 kV T/L During Construction	20.331	55% Decrease	20.331	61% Decrease
Proposed 115 kV T/L After Construction	5.926	87% Decrease	5.926	89% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 70 Ft. Length – 4.5 Ft.

Proposed Construction and Insulator Length
Height – 85 Ft. Length – 4 Ft.

The residential area is to the right as viewed in this graph.

[67] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 85 – Tower and Insulator Dimensions and Phasing



Proposed After Construction:
Double Circuit – Monopole
Figure not to Scale

Proposed During Construction:
Double Circuit – Monopole
Figure not to Scale



Existing:
Double circuit - Lattice Tower
Figure not to Scale

Segment 2 Section 1, Str. 121165 – 121166

Figure 86 – Typical Magnetic Field Levels for Segment 2 Section 1 Kramer Substation – Structure 121255, Str. 121165 – 121166 at 830 Amps



Table 50 – Comparison of Magnetic Fields at Edge of ROW for Segment 2 Section 1 Str. 121165 – 121166

Design Options	Left Edge (mG)	% Change[68]	Right Edge (mG)	% Change[68]
Projected Peak Values without Proposed Project 115 kV T/L	22.567	N/A	22.737	N/A
Proposed Project Peak Values 115 kV T/L	5.699	75% Decrease	6.591	71% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 68 Ft. Length – 4.5 Ft.

Proposed Construction and Insulator Length
Height – 76 Ft. Length – 4 Ft.

The residential area is to the right as viewed in this graph.

[68] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 87 – Tower and Insulator Dimensions and Phasing



Proposed:
Single Circuit – Monopole
Figure not to Scale



Existing:
Single Circuit – Lattice Tower
Figure not to Scale

Segment 3N, 2272 (Str. 1547460E_1547459E) – 2274 (W1546397E_E1546398E)

(Structure numbers are between brackets while the four digit numbers are the construction numbers)

Figure 88 – Typical Magnetic Field Levels for Segment 3N Kramer Substation – Coolwater Substation, Str. 1547460E_1547459E – 1546399E_1546400E at 950 Amps



Assuming Drake ACSR conductor, Top-Bottom phasing 0°,120°,240°-0°,120°,240°, and 400 Amps for parallel line.
Graph is extended to show the influence of the parallel line.

Table 51 – Comparison of Magnetic Fields at Edge of ROW for Segment 3N, Str. 1547460E_1547459E – 1546399E_1546400E

Design Options	Left Edge (mG)	% Change[69]	Right Edge (mG)	% Change[69]
Projected Peak Values without Proposed Project 115 kV T/L	59.417	N/A	47.67	N/A
Proposed Project Peak Values 115 kV T/L	29.053	51% Decrease	42.177	12% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 56 Ft. Length – 4.5 Ft.

The residential area is to the left as viewed in this graph.

[69] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 89 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 3S Section 1, 3192 (Str. NA560118AE_SA560118BE) – 3193 (NA560117AE_SA560117BE)

(Structure numbers are between brackets while the four digit numbers are the construction numbers)

Figure 90 – Typical Magnetic Field Levels for Segment 3S Section 1 Kramer Substation – Tortilla Substation, Str. NA560118AE_SA560118BE – NA560117AE_SA560117BE at 975 Amps



Table 52 – Comparison of Magnetic Fields at Edge of ROW for Segment 3S Section 1 Str. NA560118AE_SA560118BE – NA560117AE_SA560117BE

Design Options	Left Edge (mG)	% Change[70]	Right Edge (mG)	% Change[70]
Projected Peak Values without Proposed Project 115 kV T/L	21.063	N/A	21.989	N/A
Proposed Project Peak Values 115 kV T/L	19.907	5% Decrease	20.361	7% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 72 Ft. Length – 4.5 Ft.

The residential areas are on both sides as viewed in this graph.

[70] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 91 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 3S Section 1, Str. 3217 (NA560194AE_SA560194BE) – 3218 (NA560193AE_SA560193BE)

(Structure numbers are between brackets while the four digit numbers are the construction numbers)

Figure 92 – Typical Magnetic Field Levels for Segment 3S Section 1 Kramer Substation – Tortilla Substation, Str. NA560194AE_SA560194BE – NA560193AE_SA560193BE at 975 Amps



Table 53 – Comparison of Magnetic Fields at Edge of ROW for Segment 3S Section 1 Str. NA560194AE_SA560194BE– NA560193AE_SA560193BE

Design Options	Left Edge (mG)	% Change[71]	Right Edge (mG)	% Change[71]
Projected Peak Values without Proposed Project 115 kV T/L	20.409	N/A	20.56	N/A
Proposed Project Peak Values 115 kV T/L	18.866	8% Decrease	19.077	7% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 55 Ft. Length – 4.5 Ft.

The residential areas are on both sides as viewed in this graph.

[71] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 93 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 1, Str. 128571 – 128572

Figure 94 – Typical Magnetic Field Levels for Segment 4 Section 1 Coolwater Substation – Structure 128574, Str. 128571 – 128572 at 165 Amps



Assuming Partridge ACSR conductor, Top-Bottom phasing 0°,120°,240° and 400 Amps for parallel line. Graph is extended to show the influence of the parallel line.

Table 54 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 1, Str. 128571 – 128572

Design Options	Left Edge (mG)	% Change[72]	Right Edge (mG)	% Change[72]
Projected Peak Values without Proposed Project 115 kV T/L	39.457	N/A	25.233	N/A
Proposed Project Peak Values 115 kV T/L	23.098	41% Decrease	8.789	65% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 52 Ft. Length – 4.5 Ft.

The residential area is to the left as viewed in this graph.

[72] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 95 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Segment 4 Section 2, Str. 128608 – 128609

Figure 96 – Typical Magnetic Field Levels for Segment 4 Section 2 Structure 128595 – Structure 128638, Str. 128608 – 128609 at 165 Amps



Table 55 – Comparison of Magnetic Fields at Edge of ROW for Segment 4 Section 2, Str. 128608 – 128609

Design Options	Left Edge (mG)	% Change[73]	Right Edge (mG)	% Change[73]
Projected Peak Values without Proposed Project 115 kV T/L	29.556	N/A	30.778	N/A
Proposed Project Peak Values 115 kV T/L	10.442	65% Decrease	10.784	65% Decrease

All calculations were made at a height of 3 feet all across the ROW.

Tower Height and Insulator Length
Height – 52 Ft. Length – 4.5 Ft.

The residential area is to the left as viewed in this graph.

[73] All data in Percent Change column is compared to the Projected Peak Values without the IC Project

Figure 97 – Tower and Insulator Dimensions and Phasing



Existing:
Single Circuit – H-Frame
Figure not to Scale

Appendix 3

AIR QUALITY

This appendix contains the following information:

Attachment 1. Air Quality/Greenhouse Gas Emissions Summary
Attachment 2. Segment Specific CalEEMod Output Summaries

Attachment 1

AIR QUALITY AND GREENHOUSE GAS EMISSIONS SUMMARY

Air Pollutant Emissions

GREAT BASIN (Proposed)	Maximum Annual Rate (Tons/Year)					
	NOx	ROG	PM10 Total	PM2.5 Total	CO	SO2
Maximum Annual Rate	7.54	2.86	14.86	1.79	20.59	0.08
	Daily Average during Maximum Year (Pounds/Day)					
	NOx	ROG	PM10 Total	PM2.5 Total	CO	SO2
Daily Average Rate, in Max Year	**48.31**	**18.34**	**95.27**	**11.46**	**131.97**	**0.49**

KERN COUNTY	Maximum Annual Rate (Tons/Year)					
	NOx	ROG	PM10 Total	PM2.5 Total	CO	SO2
Maximum Annual Rate	1.85	0.71	4.36	0.49	5.52	0.02
	Daily Average during Maximum Year (Pounds/Day)					
	NOx	ROG	PM10 Total	PM2.5 Total	CO	SO2
Daily Average Rate, in Max Year	**11.87**	**4.57**	**27.93**	**3.14**	**35.36**	**0.10**

MOJAVE DESERT	Maximum Annual Rate (Tons/Year)					
	NOx	ROG	PM10 Total	PM2.5 Total	CO	SO2
Maximum Annual Rate	2.60	2.04	6.87	0.82	10.46	0.03
	Daily Average during Maximum Year (Pounds/Day)					
	NOx	ROG	PM10 Total	PM2.5 Total	CO	SO2
Daily Average Rate, in Max Year	**16.69**	**13.05**	**44.06**	**5.23**	**67.05**	**0.21**

GHG Emissions	MT CO2e
Total, Duration of Construction	18,287
30 year Amortized	610
Gallons of diesel fuel	1,792,843
Percent of daily CA diesel fuel usage	0.15

Total Maximum Annual Proposed Project Emissions by Air Basin

	NOx	ROG	PM10 Total	PM2.5 Total	CO	SO2
	tons/year					
Great Basin	7.54	2.86	14.9	1.79	21	0.077
Kern County	1.85	0.71	4.36	0.5	5.52	0.015
Mojave Desert	2.60	2.04	6.87	0.8	10.5	0.033

Attachment 2

SEGMENT SPECIFIC CALEEMOD OUTPUT SUMMARIES

Total Maximum Annual Proposed Project Emissions by Alignment Segment

		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total	CO2e
Segment	YEAR	tons/year						
1A	2025	0.58	1.70	5.41	0.02	3.84	0.45	1359
	2026	0.05	0.37	0.94	0.00	1.29	0.14	286
	2027	0.00	0.04	0.16	0.00	0.24	0.03	43
1B Proposed	2025	0.38	1.13	3.57	0.01	2.68	0.31	907
	2026	0.05	0.33	0.79	0.00	0.52	0.06	214
	2027	0.00	0.01	0.05	0.00	0.04	0.00	11
1B Crater	2025	0.51	1.21	4.06	0.01	2.96	0.35	1014
	2026	0.02	0.12	0.41	0.00	0.84	0.09	140
	2027	0.01	0.05	0.22	0.00	0.32	0.04	60
1C Proposed	2025	0.62	1.89	4.83	0.02	3.53	0.42	1302
	2026	0.07	0.55	2.33	0.01	1.41	0.16	529
	2027	0.00	0.01	0.08	0.00	0.06	0.01	15
1C Manzanar	2025	1.05	2.05	6.41	0.02	3.50	0.44	1575
	2026	0.04	0.34	1.90	0.00	1.31	0.14	404
	2027	0.00	0.01	0.05	0.00	0.04	0.00	11
1D	2025	0.74	1.57	3.71	0.02	2.05	0.27	1006
	2026	0.12	0.94	4.61	0.01	2.70	0.30	998
	2027	0.00	0.02	0.14	0.00	0.04	0.01	26
1E Proposed	2025	0.37	0.84	1.83	0.01	1.53	0.19	541
	2026	0.09	0.67	2.86	0.01	2.29	0.26	686
	2027	0.01	0.06	0.23	0.00	0.39	0.04	68
1E Fossil Falls	2025	0.53	0.96	2.36	0.01	1.74	0.22	658
	2026	0.07	0.51	2.54	0.01	2.12	0.24	595
	2027	0.01	0.07	0.29	0.00	0.44	0.05	82
1F	2025	0.17	1.02	1.92	0.01	1.77	0.21	607
	2026	0.40	0.78	3.15	0.01	3.11	0.36	809
	2027	0.03	0.24	1.07	0.00	1.24	0.13	264
2	2025	0.38	2.34	2.53	0.02	3.19	0.39	1044
	2026	0.89	0.88	4.27	0.01	2.76	0.34	1014
	2027	0.15	1.15	6.84	0.01	4.69	0.52	1472
3N	2025	0.04	0.27	0.74	0.00	0.99	0.11	221
	2026	0.80	0.73	3.46	0.01	2.24	0.27	832
	2027	0.04	0.28	1.21	0.00	1.39	0.15	314
3S	2025	0.05	0.28	0.84	0.00	0.91	0.10	234
	2026	0.81	0.77	3.77	0.01	2.42	0.29	897
	2027	0.03	0.23	1.22	0.00	1.37	0.15	309

Appendix 4

BIOLOGICAL RESOURCES

Contents

Proposed Project 4-1

Table 4-1. Special-status Species Potential for Occurrence 4-1
a. Plants 4-1
b. Wildlife 4-18

Table 4-2. Disturbance Acres: Vegetation Communities 4-29
Table 4-3. Western Joshua Tree in Survey Area 4-32
Table 4-4. Disturbance Acres: Critical Habitat and Conservation Areas 4-32
Table 4-5. Disturbance Acres: Jurisdictional Waters 4-32

Alternatives 4-33

Table 4-6. Disturbance Acres: Alternatives Vegetation Communities 4-33
a. Crater Mountain Realignment Alternative 4-33
b. Manzanar Realignment Alternative 4-35
c. Fossil Falls Realignment Alternative 4-37

Table 4-7. Disturbance Acres: Alternatives Conservation Areas 4-39
a. Fossil Falls Realignment Alternative 4-39

Table 4-8. Western Joshua Tree in Alternative Areas 4-39
a. Fossil Falls Realignment Alternative 4-39

Table 4-9. Disturbance Acres: Alternatives Jurisdictional Waters 4-39
a. Crater Mountain Realignment Alternative 4-39
b. Manzanar Realignment Alternative 4-39
c. Fossil Falls Realignment Alternative 4-40

PROPOSED PROJECT

Table 4-1. Special-status Species Potential for Occurrence

a. Plants

Species Name	Common Name	Regulatory Status	Potential to Occur[1] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
Sensitive Plants – Observed in Survey Area							
Aliciella triodon	coyote gilia	Fed: None State: None CRPR: 2B.2 SR: S2	Present	Not likely to occur	Not likely to occur	Not likely to occur	Two observations in 2017-2018 of 800 individuals found in the Owens Valley along the Project alignment Segment 1: one near the southern end of Owens Lake and the other between Independence and Lone Pine in Inyo County, California. 14 observations in 2023 of over 37,000 individuals in Segment 1 in five general locations: northwest of Klondike Lake and north of Big Pine; east of Twin Lakes; between Manzanar and Lone Pine; between Lubken Canyon road and the northern edge of Owens Lake; and south of Owens Lake near Highway 190. 1 observation of over 1,000 individuals in material yard 'CH SA 1-16 Hwy-190' near Segment 1 south of Owens Lake adjacent to Highway 190. 16 observations in 2023 of 1,353 individuals found in 2 locations in the Crater Mountain Realignment Alternative alignment: on the north and south sides of Tinemaha Creek south of Big Pine; and north of Blackrock in the vicinity of the Los Angeles aqueduct. A 1985 CCH/CNDDB record was recorded within five miles of the Project alignment near Independence. A 2008 CCH record is within five miles of Segment 1 along the Project alignment and Crater Mountain Realignment Alternative alignment northwest of Big Pine. A 2011 CCH/CNDDB record and 2017 CCH record are within one mile of the Manzanar Realignment Alternative alignment east of Independence. Occurs in greasewood scrub and other Great Basin scrub vegetation types and pinyon-juniper woodland communities, in soils that are sometimes sandy, at elevations ranging from 4,000 to 5,600 feet above mean sea level (amsl). Likely to occur in suitable habitat such as Greasewood Scrub along the Project alignment Segment 1, Crater Mountain Realignment Alternative and Manzanar Realignment Alternative alignments, between Independence and Lone Pine and near the southern end of Owens Lake.
Allium atrorubens var. *cristatum*	crested onion, Inyo onion	Fed: None State: None CRPR: 4.3 SR: S4	Present	Not likely to occur	Not likely to occur	Not likely to occur	Five observations in 2017-2018 of 190 individuals found southwest of Bishop and north of Big Pine. Two historic CCH/CNDDB records (1927, 1969) within three miles of Project alignment Segment 1: one on the west side of Bishop, the other west of Big Pine. One recent CCH record (2011) within three miles of Segment 1 north northwest of Lone Pine. The species occurs on rocky or sandy substrate within Great Basin scrub and pinyon-juniper woodland communities at elevations ranging from 4,000 to 7,000 feet (1,200 to 2,100 m) amsl. Likely to occur in suitable habitat along Project alignment Segment 1 between Bishop and Lone Pine.

[1] Potential to Occur:
Present: Species (or sign) was observed in the Survey Area during recent surveys, or a population has been acknowledged by CDFW, USFWS, or local experts
High: Habitat (including soils) for the species occurs in the Survey Area and a known occurrence occurs within five miles within the past 20 years; however, the species was not detected during recent surveys.
Moderate: Habitat (including soils) for the species occurs the Survey Area and a known regional record has been documented, but not within five miles of the Project site or within the past 20 years; or there is a documented occurrence within five miles of the Survey Area within the past 20 years and marginal or limited habitat occurs on site; or the species' range includes the geographic area and suitable habitat exists in the Survey Area.
Low: Limited habitat for the species occurs in the Survey Area and the species' range includes the geographic area, but there are no documented occurrences within five miles of the Survey Area within the past 20 years.
Not likely to occur: Species or signs not observed in the Survey Area, the Survey Area is outside of the species' known range, and conditions in the Survey Area are not suitable for occurrence.

Species Name	Common Name	Regulatory Status	Potential to Occur[1] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
Androstephium breviflorum	pink funnel lily	Fed: None State: None CRPR: 2B.2 SR: S2?	Low	Present	Low	Low	Observations in one location along Project alignment Segment 2 north of Kramer Junction in Creosote Bush Scrub and Creosote Bush – White Bursage Scrub. Other occurrences within 5 miles include a 2008 CCH/CNDDB record located near the I-15 Afton Road exit, and a 1998 CCH/CNDDB record located near the I-15 Basin Road exit. Occurs in creosote bush scrub communities, including within bajadas, typically in sandy soil within the Mojave and Sonoran deserts at elevations ranging from 330 to 5,300 feet (100 to 1,600 m) amsl. Likely to occur in lowland areas in well-drained soils (sandy or gravelly) in Creosote Bush Scrub or other Mojavean desert scrub in one small area north of Kramer Junction; in the Mojave Valley between the Cady Mountains to the west and the Soda Mountains to the east and. Low potential to occur in suitable habitat along Segments 1, 3N, and 3S.
Astragalus geyeri var. *geyeri*	Geyer's milk-vetch	Fed: None State: None CRPR: 2B.2 SR: S2	Present	Not likely to occur	Not likely to occur	Not likely to occur	Two observations in 2017-2018 of 11 individuals were found along Project alignment Segment 1 south of Big Pine and east of Twin Lakes. 62 individuals observed in 2023 in one general location in the Crater Mountain Realignment Alternative alignment south of Aberdeen and north of Twin Lakes in Inyo County; located outside of a 1973 CCH/CNDDB observation that overlaps the Crater Mountain Realignment Alternative and Manzanar Realignment Alternative alignments near Blackrock. Observed at a reference site in 2023 south of Aberdeen and north of Twin Lakes in Inyo County, and less than 0.5 miles northwest of the Manzanar Realignment Alternative alignment. Occurs on sandy soil in chenopod scrub and Great Basin scrub at elevations ranging from 3,900 feet to 6,500 feet amsl. Likely to occur along Segment 1, Crater Lake Alternative, and Manzanar Realignment Alternative alignments within Greasewood Scrub east of Twin Lakes and Shadscale Scrub east of the Alabama Hills and north of Lone Pine.
Calochortus excavatus	Inyo County star-tulip	Fed: None State: None CRPR: 1B.1 BLM: S SR: S2	Present	Not likely to occur	Not likely to occur	Not likely to occur	Two observations in 2017-2018 of 80 individuals found along Project alignment Segment 1 near Keough Hot Springs and near Manzanar between US Highway 395 and the Owens River. 5 observations in 2023 of approximately 691 individuals at reference sites near Segment 1 in the Owens Valley in two locations: northwest of Klondike Lake and southeast of Manzanar between US Highway 395 and the Owens River. Several recent CCH/CNDDB records (2003, 2005) overlap Segment 1 between the Owens River and US Highway 395 southeast of Manzanar. Multiple historic to recent CCH/CNDDB records (1897, 1993 and more recent) within 5 miles of Segment 1 throughout the Owens Valley. Occurs in alkaline and moist soils in meadows and seeps and in chenopod scrub at elevations ranging from 4,300 to 6,600 feet amsl. Likely to occur along the Project alignment only in discrete alkaline marshes and moist habitat between Keough Hot Springs and Lone Pine.
Chorizanthe spinosa	Mojave spineflower	Fed: None State: None CRPR: 4.2 SR: S4	Not likely to occur	Present	Present	Present	23 observations in 2017-2018 of 7,915 individuals observed between Barstow and Kramer Junction along Project alignment Segments 3N and 3S; and also along Segment 2 north of Kramer Junction to the junction of Rosewood Boulevard with Highway 395. Numerous CCH/unprocessed CNDDB records near the alignment are located between Barstow and Edwards Air Force Base. Occurs in creosote bush and chenopod scrub communities sometimes on alkaline soils at elevations ranging from sea level to 4,300 feet (1,300 m) amsl. Likely to occur in suitable habitat along Segments 2, 3N, and 3S.
Cymopterus deserticola	desert cymopterus	Fed: None State: None CRPR: 1B.2 BLM: S SR: S2	Not likely to occur	High	Present	Present	Seven observations in 2017-2018 each with one individual found along Project alignment Segment 3N west of Barstow. Three relatively recent CNDDB records (1991, 1998, 2006) overlap Segment 3N in the same area where survey observations were made. An historic 1987 CNDDB record is within 2 miles Segment 3S the Kramer Hills.

Species Name	Common Name	Regulatory Status	Potential to Occur[1] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
							Occurs in sandy places within Mojave desert scrub and Joshua tree woodland vegetation types at elevations ranging from 2,300 feet (700 m) to 5,200 feet (1,595 m) amsl. Likely to occur along Segments 3N and 3S in suitable sandy soils in shadscale scrub and creosote bush – white bursage scrub between Kramer Junction and Barstow. High potential for occurrence in suitable habitat along Segment 2 between Johannesburg and Kramer Junction.
Cymopterus ripleyi var. *saniculoides*	sanicle cymopterus	Fed: None State: None CRPR: 1B.2 BLM: S SR: S1	Present	Not likely to occur	Not likely to occur	Not likely to occur	Five observations in 2017-2018, each with one individual, concentrated along Project alignment Segment 1 southeast of Grant near Cactus Flats Road at the north end of the Haiwee Reservoir. 6 observations in 2023 of 13 individuals along Segment 1 southeast of Grant near Cactus Flats Road at the north end of the Haiwee Reservoir. One recent CNDDB (2006) record overlaps Segment 1 east of Grant. Several historic CCH/CNDDB (1974-1982) are located within two miles of the Project alignment near the southwestern end of Owens Lake southeast of Grant. Occurs in gravelly, sandy, and carbonate substrate in Joshua tree woodland and Mojavean desert scrub at elevations ranging from 3,300 to 5,300 feet amsl. Likely to occur along Segment 1 only in a 4-mile stretch in suitable gravelly and sandy habitat between Owens Lake and the Haiwee Reservoir.
Diplacus [*Mimulus*] *mohavensis*	Mojave monkeyflower	Fed: None State: None CRPR: 1B.2 BLM: S SR: S2	Not likely to occur	Not likely to occur	Moderate	Present	Five observations in 2017-2018 of 271 individuals along Project alignment Segment 3S just south of Barstow at the base of the northern slopes of Daggett Ridge in Creosote Bush - White Bursage Scrub. One CCH/CNDDB record (1994) overlaps Segment 3S along Barstow Road south of Barstow. Several historic CCH/CNDDB records (1952-1987) occur within 3 miles of Segment 3S. An historic CCH/CNDDB (1938) record is located within 5 miles of Segment 3N in Calico. Occurs on well-drained gravels and sandy substrates, often in or adjacent to washes, in Joshua tree woodland and Mojave desert scrub at elevations ranging from 1,970 to 4,000 feet (600 to 1,200 m) amsl. Likely to occur along Segment 3S between Barstow and Daggett on the lower slopes and drainages of the Mitchel Range, Waterman Hills, Calico Mountains, Daggett Ridge, and Ord Mountains. Moderate potential to occur in suitable habitat along Segment 3S near Yermo.
Eriastrum sparsiflorum	Great Basin eriastrum	Fed: None State: None CRPR: 4.3 SR: S4	Present	Not likely to occur	Not likely to occur	Not likely to occur	One observation in 2017-2018 with approximately one hundred individuals found along Project alignment Segment 1 east of the Owens River 2.5 miles northeast of Aberdeen. Numerous historic and recent CCH records within 5 miles of Segment 1, Crater Mountain Realignment Alternative, and Manzanar Realignment Alternative alignments within the Owens Valley. Occurs on sandy decomposed granite within openings in chaparral, cismontane woodland, Great Basin scrub, Joshua tree woodland, creosote bush scrub, and pinyon-juniper woodland at elevations below 6,000 feet (2,000 m) amsl. Likely to occur in suitable habitat along Segment 1 between Bishop and Haiwee.
Eriophyllum mohavense	Barstow woolly sunflower	Fed: None State: None CRPR: 1B.2 BLM: S SR: S2	Not likely to occur	High	Present	High	11 observations in 2017-2018 of 2,891 individuals, and one observation in 2023 of 500 individuals along Segment 3N, east of Kramer Junction. Nine historic to recent CCH and/or CNDDB observations (1988-2015) overlap Segment 3N in the same areas as survey observations. Additional historic to recent CCH/CNDDB occurrences (1937-2011) overlapping Segment 3N and 3S are located in the Waterman Hills, south of Hawes Auxiliary Airport, along Helendale Road, near Lenwood, and southeast of Barstow. Numerous historic to recent CCH and/or CNDDB records (1983-2016) are located within 5 miles of Segment 2 between Fremont and Kramer Junction. Occurs in open chenopod scrub, Mojave desert scrub, and playas at elevations ranging from 1,640 to 2,600 feet (500 to 800 m) amsl. Likely to occur in Shadscale Scrub and other desert scrub vegetation along Segment 2 from Fremont south to Kramer Junction; along Segment 3N from Kramer Junction east to the Waterman Hills; along Segment 3S from Kramer Junction east to Daggett, and near Yermo.

Species Name	Common Name	Regulatory Status	Potential to Occur[1] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
Eschscholzia minutiflora subsp. *twisselmannii*	Red Rock poppy	Fed: None State: None CRPR: 1B.2 BLM: S SR: S2	Not likely to occur	Present	Not likely to occur	Not likely to occur	10 observations in 2017-2018 at eight locations of over 300 individuals, 25 observations in 2023 of 4,698 individuals, along Project alignment Segment 2 in the El Paso and Rand Mountains (between Ridgecrest and Kramer Junction). An historic CNDDB (1991) record overlaps Segment 2 in the Rand Mountains. Recent CCH and/or CNDDB records (2010-2011) records are located within 2 miles of Segment 2 in the El Paso Mountains. Occurs on volcanic and granitic substrates in Mojave desert scrub at elevations ranging from 2,200 to 4,000 feet (680 to 1,230 m) amsl. Likely to occur along the Segment 2 in the El Paso and Rand Mountains on volcanic and granitic substrates.
Goodmania luteola	golden goodmania	Fed: None State: None CRPR: 4.2 SR: S3	Present	Not likely to occur	Low	Not likely to occur	One observation with 300 individuals found along Project alignment Segment 1 north of Big Pine in Inyo County, California. Several historic to recent CCH records (1973-2011) located within 2 miles east of Segment 1 near Klondike Lake north of Big Pine. Occurs in meadows and playas containing clay soils at elevations ranging from 330 feet (70 m) to 7,300 feet (2,200 m) amsl. Likely to occur in suitable habitat along Segment 1 between Keough Hot Springs and Big Pine. Low potential to occur along Segment 3N near Yermo.
Loeflingia squarrosa var. *artemisiarum*	sagebrush loeflingia	Fed: None State: None CRPR: 2B.2 BLM: S SR: S2	Present	Low	Low	Low	One observation in 2017-2018 with 500 individuals, and 3 observations in 2023 of 700 individuals, found along Project alignment Segment 1 south of Keough Hot Springs and northwest of Klondike Lake, east and northeast of Warren Lake. Also observed in 2017-2018 at a reference site on the east side of the Mojave River near Hesperia. Observed in 2023 a reference site in one general location west of Klondike Lake. Historic to recent CCH and/or CNDDB records located within 5 miles of Segment 1 west and southwest of Klondike Lake, including an occurrence from 1998 overlapping Segment 1. One 1977 CNDDB record indicates presence of this species southwest of Kramer Junction on Edwards Air Force Base further than 5 miles from the alignment. Occurs on sandy soils in desert dunes, Great Basin scrub, and Sonoran desert scrub communities at elevations ranging from 2,300 feet to 5,300 feet amsl. Likely to occur along Segment 1 only in suitable sandy, desert dune habitat between Keough Hot Springs and Klondike Lake. Low potential to occur in areas with suitable habitat along Segment 1 within the Owen's Valley, Manzanar Realignment Alternative alignment, and Segments 2, 3N, an 3S in proximity to Kramer Junction. Not likely to occur along the Crater Mountain Realignment Alternative alignment suitable sandy, desert dune habitat is absent.
Menodora spinescens var. *mohavensis*	Mojave menodora	Fed: None State: None CRPR: 1B.2 BLM: S SR: S2	Not likely to occur	Not likely to occur	Present	Present	Nine observations in 2017-2018 of 157 individuals along Project alignment Segment 3N just north of Barstow in the Waterman Hills in Creosote Bush Scrub and along the Segment 3S at the base of the northern slopes of Daggett Ridge in Creosote Bush - White Bursage Scrub; 3 observations in 2023 of 5 individuals in Segment 3S in one location at the base of the northern slopes of Daggett Ridge. Three recent CNDDB records (2011)/historic CCH records (1978) occur within a mile of the alignment, one near Segment 3S at the base of the northern slopes of Daggett Ridge, and two near Segment 3N in the Waterman Hills and along Irwin Road. Occurs on andesite gravel, rocky hillsides, and canyons within Mojave desert scrub at elevations ranging from 2,300 to 6,600 feet (690 to 2,000 m) amsl. Likely to occur along the Segments 3S and 3N in andesite gravels on rocky slopes of the Mitchel Range, Waterman Hills, and Daggett Ridge surrounding Barstow.
Mentzelia torreyi	Torrey's blazing star	Fed: None State: None CRPR: 2B.2 SR: S2	Present	Not likely to occur	Not likely to occur	Not likely to occur	10 observations in 2017-2018 of 213 individuals, and 213 individuals observed in 2023, found along the Crater Mountain Realignment Alternative alignment southeast of Aberdeen, east of Blackrock, and north of Twin Lakes. Observed in 2017-2018 at a reference site in an alkali playa northeast of Calvert Lake in the Owens Valley. Observed in 2023 at a reference site south of Aberdeen and north of Twin Lakes in Inyo County, and less than 0.25 miles northwest of the Manzanar Realignment Alternative alignment. Historic CCH and/or CNDDB observations exist within two miles of the Project alignment east and south of Aberdeen.

Species Name	Common Name	Regulatory Status	Potential to Occur[1] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
							Occurs in sandy, rocky, alkaline, and volcanic soils in Great Basin scrub, Mojavean desert scrub, and pinyon-juniper woodland at elevations ranging from 3,000 to 6,900 feet amsl. Likely to occur in suitable alkaline shrubland habitat along Segment 1, Crater Mountain Realignment Alternative, and Manzanar Realignment Alternative alignments east of Aberdeen and north of Independence.
Mentzelia tridentata	threetooth blazingstar	Fed: None State: None CRPR: 1B.3 SR: S3	High	Present	High	Present	Two observations in 2023: 1 observation of 1 individual in Segment 2 northeast of Rand in the Rand Mountains and 1 observation of 15 individuals in Segment 3S southwest of Barstow at the base of Daggett Ridge. An undated CNDDB record overlaps the southern end of the Fossil Falls Realignment Alternative alignment. One 2006 CNDDB observation recorded within two miles of the Project alignment south of South Haiwee Reservoir, and two older records recorded in the Rose Valley. Observed in 2017-2018 at reference sites near Barstow, Cronese Lake, and Lucerne Valley. Several historic to recent CCH and/or CNDDB records within 5 miles of Segments 3N, 3S in the Barstow to Yermo areas including the Calico Mountains, Newberry Mountains, and Coso Range. One overlapping historic CNDDB record (1946) is located along the Union Pacific Railroad line in Yermo. Occurs in well-drained soils in Mojave desert scrub at elevations ranging from 2,300 to 3,800 feet amsl. Likely to occur in suitable habitat along Segment 1 and Fossil Falls Realignment Alternative alignment south of South Haiwee Reservoir to the north end of Rose Valley, along Segment 3N between Cronese Basin and Calico Mountains area west to Harper Lake, along Segment 3S and between Coolwater and Iron Mountain.
Muilla coronata	crowned muilla	Fed: None State: None CRPR: 4.2 SR: S3	Present	High	High	High	One observation in 2017-2018 of one individual was found along Project alignment Segment 1 southwest of Bishop near Bishop Creek. Historic to recent CCH records located within 5 miles of Segment 1 and Manzanar Realignment Alternative alignment in the Owens Valley around Bishop and Independence and within 5 miles of Segment 2 in the El Paso Mountains. Two historic CCH records overlap or are adjacent to Segment 2 along US Highway 395 north of Kramer Junction between Farmington Road and Powerline Road. Two recent CCH records are within 5 miles of Segments 3N and 3S near Yermo and Daggett. Occurs in desert scrub, Joshua tree woodland, and pinyon-juniper woodland at elevations ranging from 3,300 feet (1,000 m) to 5,300 feet (1,600 m) amsl. Likely to occur in suitable habitat throughout the Project and alternative alignments.
Oryctes nevadensis	Nevada oryctes	Fed: None State: None CRPR: 2B.1 SR: S2	Present	Not likely to occur	Not likely to occur	Not likely to occur	Two observations in 2017-2018 of a total of three individuals, and four observations in 2023 of 18 individuals, found along Project alignment Segment 1 southeast of Blackrock on the alignment near Twin Lakes. 60 observations in 2023 of 1,171 individuals found in four general locations on the Manzanar Realignment Alternative alignment: between Twin Lakes and the Owens River east of Blackrock; south of Kearsarge and Manzanar Reward Road; east of Lone Pine; and southwest of the intersection of highway 136 Owens River crossing. Observed in 2023 at a reference site in the Owens Valley between Bishop and Laws along Highway 6 west of the Owens River. There are several historic CCH and/or CNDDB records (1940-1986) that overlap or are within 0.18 mile of Segment 1 and Crater Mountain Realignment Alternative alignment east of Blackrock north of Twin Lakes. Several historic CNDDB records (1985-1995) either overlap or are within 0.25 mile of Manzanar Realignment Alternative alignment east of Manzanar and Lone Pine. Occurs in sandy soils in chenopod scrub and Mojavean desert scrub at elevations ranging from 4,000 to 5,000 feet amsl. Likely to occur in suitable habitat along the Segment, Crater Mountain Realignment Alternative, and Manzanar Realignment Alternative alignment between the Aberdeen and Lone Pine areas.

Species Name	Common Name	Regulatory Status	Potential to Occur[1] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
Pediomelum castoreum	Beaver Dam breadroot, Indian breadroot	Fed: None State: None CRPR: 1B.2 BLM: S SR: S2	Not likely to occur	Not likely to occur	Present	Moderate	Four observations in 2017-2018 totaling five individuals, and one observation in 2023 of one individual, found along Project alignment Segment 3N between Harper Lake and the Waterman Hills; three of these observations were located in a broad alluvial fan west of the Waterman Hills in Creosote Bush Scrub and one was located further east near the southeast side of Harper Lake in Spinescale Scrub. An undated CNDDB record occurs in a general area east of the Waterman Hills that barely intersects the alignment. Several historic CCH and/or CNDDB records recorded in general areas on the west side of Barstow, Daggett, and Yermo overlap Segments 3N and 3S. Several undated, historic, or recent CCH and/or CNDDB records exist within 5 miles of Segments 3N, 3S between in the Kramer Hills, Waterman Hills, south of Barstow, and near Daggett and Yermo. Occurs in sandy washes and road cuts in Joshua tree woodland and Mojave desert scrub at elevations ranging from 2,000 to 5,000 feet (610 to 1,525 m) amsl. Moderate to high potential to occur along Segments 3N, 3S in sandy washes between Kramer Junction and Yermo.
Phacelia inyoensis	Inyo phacelia	Fed: None State: None CRPR: 1B.2 BLM: S SR: S2	Present	Not likely to occur	Not likely to occur	Not likely to occur	Observed in 2017-2018 at a reference site near the Project alignment Segment 1 adjacent to Klondike Lake north of Big Pine. 5 observations in 2023 of over 10,650 individuals along Segment 1 in one location west to northwest of Klondike Lake, north of Big Pine. Observed in 2023 at a reference site east of the Manzanar Realignment Alternative alignment east of Lone Pine in the Alabama Hills. One historic CNDDB overlaps Segment 1 between Warren and Klondike Lakes. Recent CNDDB observations and CCH records exist within a mile of the Project alignment north of Olancha. Recent CNDDB observations and CCH records exist in the Alabama Hills within 7 miles of the Manzanar Realignment Alternative alignment. Occurs in alkaline substrate in meadows and seeps at elevations ranging from 3,700 to 10,500 feet amsl. Likely to occur in suitable habitat along Segment 1, Crater Mountain Realignment Alternative, and Manzanar Realignment Alternative alignments between Keough Hot Springs and Olancha.
Plagiobothrys parishii	Parish's popcornflower	Fed: None State: None CRPR: 1B.1 BLM: S SR: S1	Present	Not likely to occur	Not likely to occur	Not likely to occur	18 observations in 2017-2018 of 3,169 individuals, and 10 observation in 2023 of 3,378 individuals, found along Project alignment Segment 1 between Keough Hot Springs and Big Pine; near Manzanar north of Lone Pine; and near the southern end of Owens Lake. Observed in 2017-2018 at reference sites southeast of Cartago and north of Big Pine in Inyo County. Several historic to recent CCH and/or CNDDB records located within 5 miles of Segment 1 near Warren and Klondike Lakes, Manzanar, east side of Alabama Hills, Lone Pine, and Cartago. Occurs in moist and alkaline marshes and associated shrublands in wet, alkaline seeps at elevations ranging from 2,500 to 4,500 feet amsl. Likely to occur along Segment 1 Crater Lake Alternative, and Manzanar Realignment Alternative alignments only in discrete alkaline marshes between Keough Hot Springs and Big Pine; near Manzanar, and the southern end of Owens Lake.
Sclerocactus polyancistrus	Mojave fishhook cactus	Fed: None State: None CRPR: 4.2 SR: S3	Not likely to occur	Present	High	Present	Mojave fishhook cactus was observed in one general location along the alignment in Segment 2 on the north-facing slope of the Rand Mountains (north of Garlock Road) in Creosote Bush Scrub. Two observations in 2017-2018 of four individuals found along Project alignment Segment 2 on the north-facing slope of the Rand Mountains located between Kramer Junction and Ridgecrest. 2 observations in 2023 of 2 individuals in material yard 'ICKI SA 3-21 Hinkley Rd' near Segment 3S adjacent to Hinkley Road south of Hinkley. Recent unprocessed CNDDB records within 5 miles of Segment 2 on the east side of the El Paso Mountains and within 5 miles of Segments 3N and 3S in the Kramer Hills and along State Highway 58 west of Hinkley. One historic and one recent CCH records are located within 5 miles of Segments 3N, 3S in the Hinkley and Calico areas. Occurs in Mojave desert scrub with well- drained soils, typically on rocky gravelly mesas, slopes and outcrops at elevations ranging from 2,100 to 7,600 feet (640 to 2,320 m) amsl. Likely to occur in suitable habitat along Segments 2, 3N, and 3S.

Species Name	Common Name	Regulatory Status	Potential to Occur[1] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
Sidalcea covillei	Owens Valley checkerbloom	Fed: None State: SE CRPR: 1B.1 BLM: S SR: S2	Present	Not likely to occur	Not likely to occur	Not likely to occur	One observation in 2017-2018 of 100 individuals, and one observation in 2023 of 250 individuals, found southeast of Independence between the Los Angeles Aqueduct and the Owens River. Two recent CNDDB records overlap Segment 1 east of Independence and Manzanar between the Owens River and Los Angeles Aqueduct. An historic CCH/CNDDB record generally overlaps Segment 1 north of Lone Pine. Several historic to recent CCH and/or CNDDB records within 3 miles of Segment 1 and/or Crater Mountain Realignment Alternative alignment roughly between Wilkerson and Keough Hot Springs, west of Big Pine, west of Fish Springs, north and southeast of Independence, and south of Cartogo at the southwestern end of Owens Lake. Occurs in alkaline marshes, including baltic and mexican rush marsh, and the edges of alkaline meadows and springs in soils that frequently have an alkaline crust at elevations ranging from 3,600 feet to 4,500 feet amsl. Likely to occur only in discrete alkaline marsh habitat in a few locations along Segment 1, Crater Mountain Realignment Alternative, and Manzanar Realignment Alternative alignments between Wilkerson and Lone Pine and at the southwestern end of Owens Lake.
Yucca brevifolia	western Joshua tree	Fed: None State: SCT CRPR: None SR: SNR	Present	High	High	High	3,284 individuals observed in 2023 in two general locations along Project alignment Segment 1: northeast of Coso Junction between Highway 395 and Fossil Falls recreational area; and between highway 395 and Haiwee Reservoir. 291 individuals observed in 2023 at one general location on the Fossil Falls Realignment Alternative alignment: from just north of the small cinder cone east of Red Hill Cinder Cone to approximately one mile to the south north of the Fossil Falls area and north of Little Lake. 2 observations in 2023 of 7 individuals in material yard 'CH SA 1-17 Lakeview Rd' near Segment 1 adjacent to Lakeview Road east of Haiwee Reservoir. Species was not specifically surveyed for prior to 2023 surveys. Occurs within Los Angeles, Kern, Riverside, San Bernardino, Inyo, and Mono Counties. Outside of California it occurs in southwestern Utah, western Arizona, southern Nevada. Primarily found on desert flats, gentle alluvial fans, ridges, and gentle to moderate slopes at elevations ranging from 2,400 to 6,000 feet amsl. Joshua tree woodland is the most widespread sensitive natural community present within the Project alignment, documented sparsely in Segment 1 in the vicinity of Haiwee Reservoir. Likely to occur within suitable along Segment 1 west of Haiwee Reservoir; along Fossil Hill Alternative alignment; and Segments 2, 3N, 3S.
Astragalus lentiginosus var. *borreganus*	Borrego milkvetch	Fed: None State: None CRPR: 4.3 SR: S4	Moderate	Low	Moderate	Moderate	Not observed along the Project or alternative alignments during Project surveys. One historic CCH record within 1 mile of Segment 1 along West Inyokern Road east of the Inyokern Substation. Two historic CCH records within 5 miles of Segments 3N and 3S in the Barstow area. Occurs in Mojave desert scrub on sandy flats and semi-stabilized dunes at elevations ranging from 100 to 1,000 feet (30 to 320 m) amsl. Moderate potential to occur in suitable habitat along Segment 1 south of Little Lake, Segments 3N, 3S; low potential to occur along Segment 2.
Astragalus serenoi var. *shockleyi*	naked milkvetch, Shockley's milk- vetch	Fed: None State: None CRPR: 2B.2 SR: S3	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments during Project surveys. Observed in 2017-2018 at a reference site in Silver Canyon in the White Mountains in Inyo County in the region of the northern end of Segment 1. A 1957 CCH/CNDDB record was reported 2 miles northwest of the Crater Mountain Realignment Alternative alignment near Monola Spring. A 2015 CNDDB record is based on a photograph taken 3.3 miles east of the northern terminus of the Crater Mountain Realignment Alternative alignment. One 1957 CCH/CNDDB record within 5 miles of the Manzanar Realignment Alternative alignment. Occurs on alkaline and granitic alluvium in Chenopod scrub, Great Basin scrub, and pinyon-juniper woodland at elevations ranging from 3,800 feet to 7,600 feet amsl. Low potential to occur along Segment 1 or the alternative alignments as all known locations occur east of the Owens River and east Project.

Species Name	Common Name	Regulatory Status	Potential to Occur[1] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
Canbya candida	white pygmy-poppy	Fed: None State: None CRPR: 4.2 SR: S3S4	high	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments during Project surveys. Observed in 2017-2018 at reference sites west and upslope of Owens Lake in the region of Segment 1. Several historic CCH and/or CNDDB records within 2 miles of Segment 1 and the Fossil Falls Realignment Alternative alignment near Dunmovin, Coso, and Pearsonville. Several historic CCH and/or CNDDB records are found near Segments 2, 3N, 3S around Kramer Junction, Kramer Hills, Lockhart, Hinkley, Barstow, Calico, and Yermo. A 1927 CCH record occurs along Segment 1 west of US Highway 395 north of Kramer Junction. Occurs in sandy places in Joshua tree woodland, Mojave scrub, and pinyon-juniper woodland at elevations ranging from 1,970 to 4,430 feet (600 to 1,350 m) amsl. Moderate potential to occur in suitable habitat along Segment 1 south of Haiwee, Segments 2, 3N, and 3S.
Dedeckera eurekensis	July gold	Fed: None State: Rare CRPR: 1B.3 SR: S3	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments during Project surveys. Observed in 2017-2018 at a reference site in the lower portion of Coldwater Canyon in the White Mountains northeast of Bishop in the region of the northern end of Segment 1. Recent CCH observations are located within six miles of the Project alignment east of Bishop. Occurs in carbonate soils in Mojavean desert scrub at elevations ranging from 4,000 to 7,300 feet amsl. Low potential to occur along Segment 1 or alternative alignments, nearest known locations are recorded in the Inyo and White Mountains at higher elevations east of the Project.
Elymus scribneri	Scribner's wheat grass	Fed: None State: None CRPR: 2B.3 SR: S3	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments during Project surveys. Observed in 2017-2018 at a reference site in the White Mountains along Silver Canyon Road at approximately 9,500 feet amsl in the region of the northern end of Segment 1. A 1966 CNDDB record (Occurrence #4) is located more than 9 miles west of the Crater Mountain Realignment Alternative alignment along the west-facing slope of Colosseum Mountain in Kings Canyon National Park at 11,250 feet amsl. Occurs in the subalpine to alpine zone above 10,000 feet amsl. No CCH or CNDDB records for this species within 5 miles of the Project. Low potential to occur near the Manzanar Realignment Alternative alignment, as subalpine to alpine habitat for this species is absent and the Project and alternative alignments are below the elevation range for this species.
Eremothera boothii subsp. *intermedia*	desert shredding primrose	Fed: None State: None CRPR: 2B.3 SR: S3	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments during Project surveys. Observed in 2017-2018 at reference sites in the region of Segment 1 near Bishop, at the southern end of Chalfant Valley, and in Fish Lake Valley. An undated CNDDB record generally mapped in the Fish Springs area overlaps Segment 1 and the Crater Mountain Realignment Alternative alignment. An historic CCH/CNDDB record is located between Segment 1 and the Crater Mountain Realignment Alternative, east of Aberdeen. One historic CCH is located within 5 miles of Segment 1 in the Inyo Mountains east of Charlies Butte. An historic CCH/CNDDB record north of Fort Independence is within 5 miles of Segment 1. Occurs in gravelly, sandy, and carbonate substrate in Joshua tree woodland and Mojavean desert scrub at elevations ranging from 3,400 to 7,050 feet amsl. Low potential to occur within suitable habitat along Segment 1, Crater Mountain Realignment Alternative, and Manzanar Realignment Alternative alignments.
Phacelia parishii	Parish's phacelia	Fed: None State: None CRPR: 1B.1 BLM: S SR: S1	Not likely to occur	Not likely to occur	Moderate	Moderate	Parish's phacelia was not observed during surveys, but it was observed in four locations at the south end of Lucerne Dry Lake; 462 individuals were observed near each other. An 1884 CNDDB record (Occurrence #1) is approximately 1 mile (1.6 kilometers) north of the alignment in Barstow in an area that is now developed. A 1992 record (Occurrence #5) is generally located less than 1,000 feet (305 meters) north of the alignment in Yermo. A 2017 record (Occurrence #4) is located approximately 3.5 miles (5.6 kilometers) northwest of the alignment and northeast of Yermo and southwest of Alvord Mountain (CNDDB 2018, CCH 2018).

Species Name	Common Name	Regulatory Status	Potential to Occur[1] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
							Occurs in Mojavean desert scrub and playas in clay or alkaline soils along dry lake margins. Moderate potential to occur in Segment 3N and 3S.
Sarcobatus baileyi	Bailey's greasewood	Fed: None State: None CRPR: 2B.3 SR: S1	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments during Project surveys. Observed in 2017-2018 and 2023 at a reference site northeast of Bishop and east of the southern terminus of Fish Slough in the region of Segment 1. No CCH or CNDDB records within 5 miles of the Project or alternative alignments. Occurs in chenopod scrub in alkaline substrate, dry lakes, washes, and roadsides at elevations ranging from 4,920-5,250 feet (1,500-1,600 meters). Not likely to occur along the Project or alternative alignments due to the Project being located below the species' elevation range.
Thelypodium integrifolium subsp. *complanatum*	foxtail thelypodium	Fed: None State: None CRPR: 2B.2 SR: S2	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments during Project surveys. Observed in 2023 in the region of Segment 1 at a reference site near Laws at a spring south of the mouth of Silver Canyon. One historic CCH record located near Blackrock within 5 miles of Segment 1 and Crater Mountain Realignment Alternative alignment. One historic CNDDB record mapped in a general area centered on the Owen's River northeast of Blackrock overlaps Segment 1, Crater Mountain Realignment Alternative, and Manzanar Realignment Alternative alignments. Occurs in moist alkaline or sub-alkaline soils in Great Basin scrub and in meadows and seeps at elevations ranging from 3,600 to 8,200 feet amsl in Inyo, Mono, and Lassen Counties. Low potential to occur in suitable habitat along Segment 1, Crater Mountain Realignment Alternative, and Manzanar Realignment Alternative alignments near Blackrock.
Trifolium dedeckerae	DeDecker's clover	Fed: None State: None CRPR: 1B.3 BLM: S SR: S2	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments during Project surveys. Observed in 2023 at reference sites in Wyman Canyon in the White Mountains well north of Segment 1. Several historic to recent CCH and/or CNDDB records located within 5 miles of Segment 1 along Horseshoe Meadow Road west of Bartlett. Occurs in granitic and rocky soil in lower montane coniferous forest, pinyon-juniper forest, subalpine coniferous forest, and upper montane coniferous forest at elevations ranging from 6,900 feet to 11,500 feet amsl. Low potential to occur along the Project, Manzanar Realignment Alternative alignments due to the Project being located well below the species' elevation range.
Aliciella ripleyi	Ripley's aliciella	Fed: None State: None CRPR: 2B.3 SR: S2	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. There is a CNDDB record close to the alignment near Little Lake from 1931 (Occurrence #18), but its exact collection location is not known and is more likely from the cliffs on the east side of Little Lake. A 1970 unverified CNDDB location (Occurrence #10), was reported approximately 2.8 miles east of the Manzanar Realignment Alternative alignment in the Inyo Mountains at the base of a cliff as well as a 2016 CNDDB location (Occurrence #40) also located east of the alignment in the Inyo Mountains. Occurs in carbonate soils in Mojavean desert scrub at elevations ranging from 200 to 4,600 feet amsl, mostly east of the CH alignment in the Inyo, Panamint, and Funeral Mountains, and adjacent mountain ranges. Low potential to occur along the Project or alternative alignments due to lack of suitable habitat; there are no cliffs or rocky crevices within the CH alignment.
Allium atrorubens var. *atrorubens*	Great Basin onion	Fed: None State: None CRPR: 2B.3 SR: S2	Moderate	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. There is a recent CCH/CNDDB location within the foothills of the eastern Sierra Nevada southwest of Big Pine within 5 miles of Segment 1 and Crater Mountain Realignment Alternative alignment.

Species Name	Common Name	Regulatory Status	Potential to Occur[1] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
							Occurs on rocky or sandy substrate within Great Basin scrub and pinyon juniper woodland communities at elevations ranging from 3,940 to 6,900 feet amsl. Moderate potential to occur along Segment 1 and Crater Mountain Realignment Alternative alignment.
Astragalus hornii var. *hornii*	Horn's milk-vetch	Fed: None State: None CRPR: 1B.1 BLM: S SR: S1	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. There is one 1919 CNDDB record reported less than approximately 1.75 mile west of the Manzanar Realignment Alternative alignment. No other observations of this species have been recorded in the Owens Valley. Occurs in alkaline soils such as lake margins, meadows, seeps, and playas at elevations ranging from 200 to 1,000 feet amsl on the coastal side of the Sierra Nevada in Kern County (San Joaquin Valley), the southern Mojave Desert in and near the Antelope Valley (historic records), and in the City of San Bernardino (historic records). Low potential to occur along the Project or alternative alignments, all confirmed records occur outside of the known range for this species.
Astragalus jaegerianus	Lane Mountain milkvetch	Fed: FE State: None CRPR: 1B.1 SR: S2	Not likely to occur	Not likely to occur	Low	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Only extant population occurs approximately 6 miles north of the Segment 3N, north of Barstow in the Mud Hills, on Lane Mountain and surrounding Tiefort Mountains, east to the Fort Irwin area. Designated Critical Habitat is within 5 miles of the alignment north of Barstow-Yermo area. Occurs in Joshua tree woodland and Mojavean desert scrub in granitic sands and gravels from 3,000 to 4,000 feet amsl in Mud Hills (Coolgardie Mesa), on Lane Mountain and surrounding Tiefort Mountains, east to the Fort Irwin area more than 10 miles north of Barstow. Low potential to occur along the Project or alternative alignments due to lack of the combined attributes of substrate and elevation. It has never been reported in any location within 1 mile (1.6 kilometers) of the alignment and habitat models also indicate a lack of habitat within the alignment (DRECP Data Basin 2018).
Astragalus platytropis	broad-keeled milk-vetch	Fed: None State: None CRPR: 2B.2 SR: S1	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. No CCH or CNDDB records within 5 miles of the Project or alternative alignments. Occurs on rocky substrates in alpine, subalpine, and pinyon-juniper habitats at elevations ranging from 7,700 - 11,650 feet. Low potential to occur along the Project and Crater Mountain Realignment Alternative alignment due to the Project being located below the species' elevation range.
Atriplex argentea var. *hillmanii*	Hillman's silverscale	Fed: None State: None CRPR: 2B.2 SR: S2	High	Not likely to occur	Moderate	Moderate	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One 1973 CCH/CNDDB record is located in the Owens Valley east of Twin Lakes and overlaps Segment 1, Crater Mountain Realignment Alternative, and Manzanar Realignment Alternative alignments. One 1985 CCH record occurs along the Manzanar Realignment Alternative alignment in the Kearsarge area east of Independence. One historic CCH record within 5 miles of Segment 3N near Lockhart, another between Segments 3N and 3S north of Barstow. Occurs on alkaline soils in chenopod scrub, Great Basin scrub, and pinyon-juniper woodland at elevations ranging from 2,900 to 5,600 feet amsl. Likely to occur in suitable habitat along Segment 1, Crater Mountain Realignment Alternative, and Manzanar Realignment Alternative alignments between Fish Springs and Owens Lake; and moderate potential to occur along Segments 3N and 3S near Barstow.
Atriplex gardneri var. *falcata*	falcate saltbush	Fed: None State: None CRPR: 2B.2 SR: S2S3	Moderate	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. The 1974 CNDDB record was documented approximately 4 miles (6.4 kilometers) east of Segment 1, east of Keough Hot Springs.

Species Name	Common Name	Regulatory Status	Potential to Occur[1] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
							Occurs in Chenopod scrub and Great Basin scrub, often in alkaline soils, at elevations ranging from 4,000 to 5,600 feet amsl on east side of Sierra Nevada in Lassen and Plumas Counties. Not likely to occur as the Project and alternative alignments are outside of the current species' range.
Azolla microphylla	Mexican mosquito fern	Fed: None State: None CRPR: 4.2 SR: S4	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One historic CCH record located along Segment 1 at Mazourka Canyon Road between Independence and the Los Angeles Aqueduct. Two historic CCH records located within 2 miles of Segment 1 and Manzanar Realignment Alternative alignment, near Kearsarge and east of Manzanar. One historic CCH record within 2 miles west of Segment 1 south of Manzanar. Occurs in ponds and slow water features at elevations under 1,200 meters amsl. Low potential to occur in suitable habitat along Segment 1 and Manzanar Realignment Alternative alignment.
Blepharidachne kingii	King's eyelash grass	Fed: None State: None CRPR: 2B.3 SR: S2	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One historic CCH/CNDDB record within 5 miles of Segment 1 near Monola. Occurs in granitic and gravelly soils in Joshua tree woodland and pinyon-juniper woodland at elevations ranging from 3,000 to 7,100 feet amsl in desert mountain ranges to the east of the Owens Valley. Low potential to occur along Segment 1 near Big Pine.
Boechera dispar	pinyon rockcress	Fed: None State: None CRPR: 2B.3 SR: S3	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One historic CCH/CNDDB record generally mapped near Bishop within 5 miles of Segment 1. One historic CCH/CNDDB record within 2 miles of Segment 1 west of Big Pine. Occurs in granitic and gravelly soils in Joshua tree woodland, creosote bush scrub, and pinyon-juniper woodland at elevations ranging from 4,000 to 8,200 feet amsl. The habitat for pinyon rockcress is exclusively on slopes of mountains and adjacent foothills generally where Mojavean scrub transitions to pinyon-juniper. Low potential to occur along the Project or alternative alignments due to lack of suitable habitat.
Camissonia kernensis subsp. *kernensis*	Kern County evening-primrose	Fed: None State: None CRPR: 4.3 SR: S3	Moderate	Moderate	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Two historic CCH records within 5 miles of Segment 2 located west of US Highway 395 near Bradys. One historic CCH record within 5 miles of Segment 2 in the El Paso Mountains. Occurs on sandy slopes and flats, generally in sagebrush scrub or Joshua-tree woodland at elevations ranging from 2,590-6,990 feet (790-2,130 meters) amsl. Low potential to occur in suitable habitat along Segment 1 south of Little Lake and Segment 2 in the El Paso Mountains.
Clarkia xantiana subsp. *parviflora*	Kern Canyon clarkia	Fed: None State: None CRPR: 4.2 SR: S3?	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Two historic CCH/CNDDB records located within 5 miles of Segment 1 along the foot of the eastern Sierra Nevada foothills southwest of Olancha. One historic CNDDB record within 3 miles of Segment 1 located along the foot of the eastern Sierra Nevada foothills west of Coso Junction. Occurs on dry slopes in chaparral, cismontane woodland, Great Basin scrub, and valley and foothill grassland at elevations ranging from 2,295-11,875 feet (700-3,620 meters) amsl. Low potential to occur in suitable habitat along Segment 1 between Olancha and Little Lake.
Cleomella brevipes	short-pedicelled cleomella	Fed: None State: None CRPR: 4.2 SR: S3	High	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Several historic to recent CCH records throughout the Owens Valley and within 5 miles of Segment 1, Crater Mountain Realignment Alternative between Keough Hot Springs and Grant.

Species Name	Common Name	Regulatory Status	Potential to Occur[1] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
							Occurs in alkaline marshes and wet, salt-encrusted soil around thermal springs at elevations ranging from 1,295-7,200 feet (395-2,195 meters) amsl. Likely to occur within suitable habitat along Segment 1, Crater Mountain Realignment Alternative, and Manzanar Realignment Alternative alignments.
Crepis runcinata	fiddleleaf hawksbeard	Fed: None State: None CRPR: 2B.2 SR: S3	Moderate	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Two historic CNDDB records within 5 miles of Segment 1 in Bishop and Wilkerson. Occurs in moist locations, in alkaline soils, and in Mojavean desert scrub and pinyon and juniper woodland at elevations ranging from 3,900 to 10,200 feet amsl, mostly to the north of Bishop and in Deep Springs Valley. Low potential to occur in suitable habitat along Segment 1 north of Big Pine.
Cryptantha clokeyi	Clokey's cryptantha	Fed: None State: None CRPR: 1B.2 SR: S3	Not likely to occur	High	Moderate	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One recent CNDDB record within 3 miles west of Segment 2 on the south side of the Rand Mountains. One historic CCH record within 3 miles of Segment 3N in the Waterman Hills north of Barstow. Occurs in Mojavean desert scrub habitat at elevations of 2,400 to 4,500 amsl in the Mojave Desert. Likely potential to occur in suitable habitat along Segment 2 and moderate potential to occur along Segment 3N.
Cryptantha glomeriflora	clustered-flower cryptantha	Fed: None State: None CRPR: 4.3 SR: S4	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One historic CCH record located in the eastern Sierra Nevada foothills within 4 miles of Segment 1 southwest of Bartlett. Occurs on gravelly slopes and in dry meadows and snowmelt creekbeds, in Great Basin scrub, subalpine and upper montane coniferous forest at elevations ranging from 5,905-12,305 feet (1,800-3,750 meters) amsl. Low potential to occur along the Project or alternative alignments due to the Project being located below the species' elevation range.
Deinandra mohavensis	Mojave tarplant	Fed: None State: SE CRPR: 1B.3 BLM: S SR: S2	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Several historic CCH and/or CNDDB records within 5 to 6 miles of Segment 1 located on the eastern Sierra Nevada foothills west of Bradys. Occurs in moist sites and openings in chaparral, coastal scrub, and riparian scrub at elevations ranging from 2,100-5,250 feet (640-1,600 meters) amsl. Low potential to occur in suitable habitat along Segment 1 south of Little Lake.
Diplacus parryi	Parry's monkeyflower	Fed: None State: None CRPR: 2B.3 SR: S3	Moderate	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One historic CCH/CNDDB record located within 3 miles of the Manzanar Realignment Alternative alignment in the Inyo Mountains foothills east of Kearsarge. Occurs on steep hillsides and along washes in Great Basin scrub at elevations ranging from 3,935-8,530 feet (1,200-2,600 meters) amsl in the Inyo and White Mountains. Not likely to occur as the Project and alternative alignments are outside the current geographic range of the species.
Enceliopsis nudicaulis var. *nudicaulis*	naked-stemmed daisy	Fed: None State: None CRPR: 4.3 SR: S3	Moderate	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One historic CCH record within 5 miles of Segment 1 in the Inyo Mountains southeast of Tinemana Reservoir. Occurs on carbonate or volcanic substrates in Great Basin scrub and Mojavean desert scrub at elevations ranging from 3,115-6,560 feet (950-2,000 meters) amsl. Moderate potential to occur in suitable habitat in Segment 1.
Eremothera boothii subsp. *alyssoides*	Pine Creek evening-primrose	Fed: None State: None CRPR: 4.3 SR: S4	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Several historic to recent CCH records are present within 5 miles, a few within 1 mile, but their locations and/or species identification has been unverified.

Species Name	Common Name	Regulatory Status	Potential to Occur[1] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
							Occurs on sandy slopes and flats in Great Basin scrub at elevations ranging from 1,970-5,580 feet (600-1,700 meters) amsl within the White and Inyo Mountains, Warner Mountains, and Modoc Plateau. Low potential to occur in suitable habitat along Segment 1, Crater Mountain Realignment Alternative, and Manzanar Realignment Alternative alignments within the Owens Valley.
Eremothera boothii subsp. *boothii*	Booth's evening-primrose	Fed: None State: None CRPR: 2B.3 SR: S3	High	High	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One historic CCH/CNDDB record generally mapped to the Dunmovin area overlaps Segment 1; a second historic record overlaps Segment 2 and is generally mapped to the Kramer Hills north of Kramer Junction. Historic to recent CCH and/or CNDDB records within 5 miles of Segment 1, Crater Mountain Realignment Alternative, Manzanar Realignment Alternative, and Fossil Falls Realignment Alternative alignments in the Inyo Mountains east of Charlie's Butte, between Blackrock and Independence, and the Coso Range. Often found in Joshua tree woodland and in pinyon-juniper woodland and desert scrub at elevations ranging 2,950 to 7,900 feet amsl. Moderate to high potential to occur in suitable habitat along Segment 1, Crater Mountain Realignment Alternative, and Manzanar Realignment Alternative alignments between Aberdeen and Twin Lakes, and between Haiwee and Inyokern; likely to occur along Segment 2 in the Kramer Hills area.
Ericameria albida	white-flowered rabbitbrush	Fed: None State: None CRPR: 4.2 SR: S3	High	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Several recent to historic CCH records within 5 miles of Segment 1 at Warren and Klondike Lakes. Occurs on saline or alkaline soils in chenopod scrub, meadows and seeps, and playas at elevations ranging from 985-6,400 feet (300-1,950 meters) amsl. Likely to occur in suitable habitat along Segment 1 between Keough Hot Springs and Big Pine.
Eriogonum baileyi var. *praebens*	Bailey's woolly buckwheat	Fed: None State: None CRPR: 4.3 SR: S4	High	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Several recent to historic CCH records located within 4 miles of Segment 1, Crater Mountain Realignment Alternative, and Manzanar Realignment Alternative at Bishop Creek and McGee's Meadows southwest of the Segment 1 northern terminus, west of Crater Mountain, west of Manzanar, and the west side of the Alabama Hills. Occurs on sandy substrates in Great Basin scrub, meadows and seeps, and pinyon-juniper woodland at elevations ranging from 4,265-9,515 feet (1,300-2,900 meters) amsl. Likely to occur in suitable habitat along Segment 1, Crater Mountain Realignment Alternative, and Manzanar Realignment Alternative alignments in the Bishop area south to Owens Lake.
Eriogonum mensicola	Pinyon Mesa buckwheat	Fed: None State: None CRPR: 1B.3 BLM: S SR: S3	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One recent CNDDB record occurs within 5 miles of Segment 1, Crater Mountain Realignment Alternative, and Manzanar Realignment Alternative alignments in the Inyo Mountains at the north end of Santa Rita Flat. Occurs in rock or gravelly substrate in pinyon-juniper woodland, Great Basin scrub, and upper montane coniferous forest at elevations ranging from 5,900 to 8,900 feet (1,800 to 2,700 m) amsl in the White and Inyo Mountains and Desert Mountains province. Low potential to occur in suitable habitat along Segment 1 and Manzanar Realignment Alternative alignment between Aberdeen and Lone Pine.
Eriogonum microthecum var. *lapidicola*	Inyo Mountains buckwheat	Fed: None State: None CRPR: 4.3 SR: S2S3	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Several historic CCH records exist 4.5 to 6 miles from Segment 1 in the Santa Rita Flat area of the Inyo Mountains. Occurs on carbonate gravel or rocks in pinyon-juniper woodland and subalpine coniferous forest at elevations ranging from 8,530-10,170 feet (2,600-3,100 meters) amsl in the White and Inyo Mountains. Low potential to occur as the Project and alternative alignments are outside the current elevation and geographic range of the species.

Species Name	Common Name	Regulatory Status	Potential to Occur[1] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
Eriogonum spergulinum var. *pratense*	Mountain meadow wild buckwheat	Fed: None State: None CRPR: 4.3 SR: S3	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Two historic CCH records within 5 miles of Segment 1 in the eastern Sierra Nevada west of Owens Lake. Occurs on sandy or gravelly substrates in creeks and meadows within alpine boulder and rock fields at elevations ranging from 6,005-11,305 feet (1,830-3,445 meters) amsl in the southern high Sierra Nevada. Low potential to occur as the Project and alternative alignments are outside the current elevation and geographic range of the species.
Erythranthe bergeri	Berger's monkeyflower	Fed: None State: None CRPR: 3 SR: S1	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Only known documented occurrences are recorded in several recent CCH records within 2 miles of Segment 1 near the base of the foothills west of Warren Lake. Occurs in vernally mesic places with rocky, granitic substrates in Great Basin Scrub at approximately 4,050 feet (1,235 meters) elevation amsl. Minimal potential to occur in suitable habitat along Segment 1 near Big Pine.
Erythranthe rhodopetra	Red Rock Canyon monkeyflower	Fed: None State: None CRPR: 1B.1 BLM: S SR: S1	Not likely to occur	Low	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One historic CNDDB record generally mapped to the north side of the Rand Mountains overlaps Segment 2. Occurs in sandy washes in Mojavean desert scrub. Moderate potential to occur along Segment 2 in near the El Paso and Rand Mountains.
Eschscholzia androuxii	Joshua Tree poppy	Fed: None State: None CRPR: 4.3 SR: S3	Not likely to occur	Not likely to occur	Not likely to occur	Moderate	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One historic CCH record within 5 miles of Segment 3S south of Barstow. Occurs in sandy, rocky, or gravelly desert washes and on flats and slopes in Joshua tree woodland and Mojavean desert scrub at elevations ranging from 1,920-5,530 feet (585-1,685 meters) amsl, mostly within the southern Mojave Desert and Sonoran Desert provinces. Moderate potential to occur in suitable habitat along Segment 3S between Hinkley and Daggett; low potential to occur along Segment 3N near Barstow.
Euphorbia vallis-mortae	Death Valley sandmat	Fed: None State: None CRPR: 4.2 SR: S3	High	High	Low	Low	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One historic CCH record located along Segment 1 alignment south of Pearsonville. Several historic to recent CCH records within 2 miles of Segment 1 west of Owens Lake and between Pearsonville and Indian Wells. CCH records present beyond 5 miles of Segment 2 near the west side of the El Paso Mountains and east of Laurel Mountain. Occurs in dry, sandy or gravelly places in Mojavean desert scrub at elevations ranging from 755-4,790 feet (230-1,460 meters) amsl. Likely to occur in suitable habitat along Segment 1 south of Lone Pine and along Segment 2; low potential to occur along Segments 3N, 3S.
Euphrosyne nevadensis	Nevada wormwood	Fed: None State: None CRPR: 4.3 SR: S3	High	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One recent CCH record within 1 mile of Segment 1 west of Warren Lake. Occurs in alkaline, sandy plains and washes in chenopod scrub, Great Basin scrub, and pinyon-juniper woodland at elevations ranging from 3,280-6,740 feet (1,000-2,055 meters) amsl. Likely to occur in suitable habitat between Keough Hot Springs and Big Pine.
Fimbristylis thermalis	hot springs fimbristylis	Fed: None State: None CRPR: 2B.2 SR: S1S2	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One 1964 CNDDB record is from Keough Hot Springs west of CH alignment. Occurs in meadows and seeps, especially in alkaline soils and near hot springs at elevations ranging from 400 to 4,400 feet amsl. Not likely to occur in the Project or alternative alignments due to lack of suitable habitat.

Species Name	Common Name	Regulatory Status	Potential to Occur[1] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
Hecastocleis shockleyi	prickle-leaf	Fed: None State: None CRPR: 3 SR: S4	Moderate	Low	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Two historic CCH records within 5 miles of Segment 1 and Manzanar Realignment Alternative alignment northeast of Kearsarge and in Independence. One unverified historic CCH record within 1 mile of Segment 2 west of Rand. Occurs on dry, rocky slopes and washes in chenopod scrub and Mojavean desert scrub, often on carbonate substrates, at elevations ranging from 3,935-7,220 feet (1,200-2,2200 meters) amsl. Moderate potential to occur in suitable habitat along Segment 1 and Manzanar Realignment Alternative alignment near Independence and Kearsarge; low potential to occur along Segment 2 near the El Paso and Rand Mountains.
Lomatium rigidum	stiff lomatium	Fed: None State: None CRPR: 4.3 SR: S3	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One historic CCH record along Segment 1 alignment southeast of Warren Lake. Several historic to recent CCH records within 5 miles of Segment 1 southwest of Bishop; of Crater Mountain Realignment Alternative alignment west of Crater Mountain; of Segment 1 and Manzanar Realignment Alternative alignment east of Blackrock; and of Segment 1 west of Bartlett and Haiwee. Occurs on rocky slopes near streams in Great Basin scrub and pinyon-juniper woodland at elevations ranging from 3,935-7,220 feet (1,200-2,200 meters) amsl. Low potential to occur in suitable habitat between Keough Hot Springs and Big Pine.
Lupinus magnificus var. *glarecola*	Coso Mountains lupine	Fed: None State: None CRPR: 4.3 SR: S4	Moderate	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Several historic CCH records within 5 miles of Segment 1, Crater Mountain Realignment Alternative, and Manzanar Realignment Alternative alignments within the Owens Valley west of Bishop, southwest of Crater Mountain, within and west of Lone Pine, and west of Bartlett. Occur on granitic substrates, often scree and talus, on desert slopes and within washes in Great Basin scrub, Joshua tree woodland, and Mojavean desert scrub at elevations ranging from 3,640-8,005 feet (1,110-2,440 meters) amsl. Moderate potential to occur in suitable habitat along Segment 1, Crater Mountain Realignment Alternative, and Manzanar Realignment Alternative alignments between Bishop and Olancha.
Lupinus magnificus var. *hesperius*	Mcgee Meadows lupine	Fed: None State: None CRPR: 1B.3 BLM: S SR: S1	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Several historic CCH and/or CNDDB records within 5 miles of the northern end of Segment 1 west of Bishop and Crater Mountain Realignment Alternative alignment southwest of Blackrock. Occurs on steep, sandy slopes in upper montane coniferous forests and Great Basin scrub at elevations ranging from 4,135 to 6,005 feet amsl. Low potential to occur in suitable habitat along Segment 1 and Crater Mountain Realignment Alternative alignment between Bishop and Lone Pine.
Lupinus pusillus var. *intermontanus*	intermontane lupine	Fed: None State: None CRPR: 2B.3 SR: S2	Moderate	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Few historic CCH and/or CNDDB records within 5 miles of Segment 1 southeast of Bishop and near Monola. Occurs in Greasewood Scrub and Great Basin scrub at elevations below 5,250 feet amsl, mostly north of the Owens Valley or east of the Owens Valley. Low to moderate potential to occur in suitable habitat along Segment 1 between Keough Hot Springs and Owens Lake.
Lycium torreyi	Torrey's box-thorn	Fed: None State: None CRPR: 4.2 SR: S3	Not likely to occur	Not likely to occur	Moderate	Moderate	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Several historic CCH records within 5 miles of Segments 3N, 3S, northeast of the Kramer Hills, southwest and within Barstow. Occurs on sandy or rocky substrates in washes and on streambanks in Mojavean desert scrub and Sonoran desert scrub at elevations ranging from 165 feet below mean sea level to 4,005 feet amsl (50 meters below to 1,220 meters above). Moderate potential to occur in suitable habitat along Segments 3N and 3Snear Yermo.

Species Name	Common Name	Regulatory Status	Potential to Occur[1] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
Mentzelia eremophila	solitary blazing star	Fed: None State: None CRPR: 4.2 SR: S3S4	Not likely to occur	High	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Multiple historic to recent CCH records within 5 miles of Segment 2 in and around the El Paso and Rand Mountains area. Occurs in canyons, on rocky slopes and washes, and roadsides in Mojavean desert scrub at elevations ranging from 2,295-4,005 feet (700-1,220 meters) amsl. Likely to occur in suitable habitat along Segment 2 in the El Paso and Rand Mountain areas.
Mentzelia tricuspis	spiny-hair blazing star	Fed: None State: None CRPR: 2B.2 SR: S2	Not likely to occur	Not likely to occur	High	High	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Several historic CCH records within 5 miles of Segments 3N, 3S, in the Barstow, Waterman Hills, Daggett, and Calico areas. Occurs on sandy, gravelly soils on slopes and washes in Mojavean desert scrub at elevations ranging from 500 to 4,200 feet amsl at scattered locations in the Mojave and Sonoran Deserts. Moderate potential to occur in suitable habitat along Segments 3N, 3S near Barstow, Daggett, and Yermo.
Monardella exilis	Mojave monardella	Fed: None State: None CRPR: 4.2 SR: S3	Moderate	Moderate	Moderate	Moderate	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Several historic CCH records within 5 miles of Segment 1 and Fossil Falls Realignment Alternative alignment south Haiwee, Segments 2, 3N, and 3S in the Kramer Hills and Barstow areas. Occurs in sandy areas and washes in chenopod scrub, desert dunes, Great Basin scrub, Joshua tree woodland, Mojavean desert scrub, pinyon-juniper woodland, and lower montane coniferous forest at elevations ranging from 1,970-6,725 feet (600-2,050 meters) amsl. Low to moderate potential to occur in suitable habitat along Segment 1 south of Haiwee, Fossil Falls Realignment Alternative alignment, Segments 2, 3N, and 3S.
Nemacladus gracilis	slender nemacladus	Fed: None State: None CRPR: 4.3 SR: S4	Not likely to occur	Not likely to occur	Not likely to occur	Low	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One historic CCH record with an unverified location is within 5 miles of Segment 3S south of Barstow. Occurs on rocky slopes and sandy washes in cismontane woodland and valley and foothill grassland at elevations ranging from 395-6,235 feet (120-1,900 meters) amsl in the southern Sierra Nevada foothills, San Joaquin Valley, and South Coast Ranges. Not likely to occur as the Project and alternative alignments are outside the current geographic range of the species, and lack of suitable habitat.
Phacelia nashiana	Charlotte's phacelia	Fed: None State: None CRPR: 1B.2 BLM: S SR: S3	Moderate	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Several historic CCH records within 5 miles of Segment 1 and Fossil Falls Realignment Alternative alignment in the Coso Mountains and eastern Sierra Nevada near Little Lake and Pearsonville. Occurs in granitic and sandy soil in Joshua tree woodland, Mojavean desert scrub, and pinyon-juniper woodland at elevations below 8,000 feet (2,400 m) amsl. Moderate potential to occur along Segment 1 and Fossil Falls Realignment Alternative alignment between Coso Junction and Pearsonville.
Populus angustifolia	Narrow leaved cottonwood	Fed: None State: None CRPR: 2B.2 SR: S2	Moderate	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One historic CCH record located at Division Creek within 5 miles of Crater Mountain Realignment Alternative alignment west of Blackrock. Occurs on streambanks in riparian forests in pinyon-juniper woodland with willows (*Salix* spp) and water birch (*Betula occidentalis*) at elevations from 4,000 to 6,000 feet amsl. There are riparian areas that intersect the Crater Mountain Realignment Alternative alignment at Taboose Creek and Tinemaha Creek, however those areas are dominated by Fremont cottonwood (*Populus fremontii*). Moderate potential to occur within suitable habitat along Segment 1, Crater Mountain Realignment Alternative, and Manzanar Realignment Alternative alignments.

Species Name	Common Name	Regulatory Status	Potential to Occur[1] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
Psorothamnus arborescens var. *arborescens*	Mojave indigo-bush	Fed: None State: None CRPR: 4.3 SR: S4	Moderate	High	High	High	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One historic CCH record located along Segment 3N south of Lockhart, two more within 1 mile. Several historic CCH records within 5 miles of Segments 1 and 2 in Inyokern, Segment 2 in the Rand Mountains, Segments 3N and 3S in the Kramer Hills, Hinkley, and Barstow areas. Occurs in Mojavean desert scrub and riparian scrub at elevations ranging from 1,310-3,890 feet (400-1,185 meters) amsl. Moderate potential to occur along Segment 1 south of Little Lake; likely to occur along Segments 2, 3N, and 3S.
Puccinellia simplex	California alkali grass	Fed: None State: None CRPR: 1B.2 BLM: S SR: S2	Not likely to occur	Not likely to occur	Low	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One undated CNDDB record located in the Mud Hills within 5 miles north of Segment 3N. Prefers alkaline, vernally mesic sinks, flats, and lake margins in yerba mansa meadows, annual grasslands, and vernal pools at elevations from sea level to 3,000 feet amsl; species has a broad range in restricted habitats in California. Low potential to occur as the Project and alternative alignments lacks suitable habitat.
Ranunculus hydrocharoides	frog's-bit buttercup	Fed: None State: None CRPR: 2B.1 SR: S1	Moderate	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Two historic CCH/CNDDB records located within 5 miles of Segment 1 in Bishop and northwest of Independence. Occurs in freshwater marshes at elevations ranging from 4,000 to 9,200 feet amsl. Moderate potential to occur in suitable habitat along Segment 1 between Bishop and Independence.
Saltugilia latimeri	Latimer's woodland-gilia	Fed: None State: None CRPR: 1B.3 BLM: S SR: S3	Moderate	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Several recent CCH/CNDDB records within 5 miles of Segment 1 west of Bradys. Occurs on coarse sand to rocky soils on dry desert slopes, sometimes washes, in chaparral, Mojavean desert scrub, and pinyon-juniper woodland at elevations ranging from 1,310-6,235 feet (400-1,900 meters) amsl. Moderate potential to occur along Segment 1 and Fossil Falls Realignment Alternative alignment near Little Lake.
Sibara deserti	desert winged-rockcress	Fed: None State: None CRPR: 4.3 SR: S4	Moderate	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Two historic CCH records with unverified locations are within 5 miles of Segment 1 and Manzanar Realignment Alternative alignment in a canyon south of Mazourka Peak. Occurs in washes and on steep hillsides, dry flats, scree, calcareous rubble, rocky bluffs, and exposed crevices in Mojavean desert scrub. Moderate potential to occur along Manzanar Realignment Alternative alignment near.
Spartina gracilis	alkali cord grass	Fed: None State: None CRPR: 4.2 SR: S3	Moderate	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Several historic CCH records within 5 miles of Segment 1 southwest of and in Bishop, east of Keough Hot Springs, in Olancha, at Little Lake. Occurs along alkaline lake shores, streambanks, meadows, and marshes in Great Basin scrub at elevations ranging from 3,280-6,890 feet (1,000-2,100 meters) amsl. Moderate potential to occur in suitable habitat along Segment 1.
Sphenopholis obtusata	prairie wedge grass	Fed: None State: None CRPR: 2B.2 SR: S2	Moderate	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One historic CCH/CNDDB record located along Taboose Creek is within 5 miles of Segment 1 and Crater Mountain Realignment Alternative alignment.

Species Name	Common Name	Regulatory Status	Potential to Occur[1] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
							Occurs in moist locations, such as meadows and seeps and woodlands at elevations ranging from 800 to 9,500 feet amsl in the Sierra Nevada, Great Valley, and White Mountains. Moderate potential to occur along Taboose Creek within the Crater Mountain Realignment Alternative alignment, but suitable habitat is absent elsewhere.
Suaeda occidentalis	western horned seablite	Fed: None State: None CRPR: 2B.3 SR: S2	Moderate	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One historic CNDDB record within 5 miles of Segment 1 at Klondike Lake north of Big Pine. Occurs in moist and alkaline locations in Great Basin scrub at elevations below 7,200 feet amsl in isolated alkaline habitats in Inyo, Mono, Lassen, and Siskiyou Counties. Moderate potential to occur in suitable habitat along Segment 1 north of Big Pine.

b. Wildlife

Species Name	Common Name	Regulatory Status	Potential to Occur[2] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
Observed							
Insects							
Bombus crotchii	Crotch bumble bee	Fed: None State: SC SR: S2	Present	Moderate	Moderate	Moderate	One individual observed near Segment 1 during 2024 spring field checks. There are historic CNDDB records within 5 miles of Segments 1, 2, 3N, and 3S near Bishop, Haiwee, Little Lake, and the Kramer Hills. No Bumble Bee Atlas sightings within 5 miles of the Project. Occurs primarily to the west of the Mojave Desert in open grassland and scrub habitats, but the historic range includes the Owens Valley. Nesting occurs underground. Food plants include *Asclepias*, *Chaenactis*, *Lupinus*, *Medicago*, *Eschscholzia*, *Eriogonum*, *Phacelia*, and *Salvia* species. Low to moderate potential to occur in suitable habitats along Segment 1 and Crater Mountain Realignment Alternative, Manzanar Realignment Alternative, Fossil Hill Alternative alignments, and Segments 2, 3S, and 3N.
Reptiles							
Gopherus agassizii	desert tortoise	Fed: FT State: ST SR: S2S3	Present (sign)	Present	High	High	221 observations of living individuals or sign in 2017-2018, with 25 living individuals and 196 sign found along portions the Project alignment. No observations of living desert tortoise were made along Segment 1 during the 2017 protocol surveys; however, sign was documented and an incidental observation of a single adult desert tortoise was made near the Inyokern Substation in Ridgecrest during surveys for Jurisdictional Waters. Desert tortoise sign were observed between Inyokern and Little Lake, including two potential desert tortoise burrows, one desert tortoise carcass, and one scat. USFWS-designated critical habitat present overlapping

[2] Potential to Occur:
Present: Species (or sign) was observed in the Survey Area during recent surveys, or a population has been acknowledged by CDFW, USFWS, or local experts
High: Habitat (including soils) for the species occurs in the Survey Area and a known occurrence occurs within five miles within the past 20 years; however, the species was not detected during recent surveys.
Moderate: Habitat (including soils) for the species occurs the Survey Area and a known regional record has been documented, but not within five miles of the Project site or within the past 20 years; or there is a documented occurrence within five miles of the Survey Area within the past 20 years and marginal or limited habitat occurs on site; or the species' range includes the geographic area and suitable habitat exists in the Survey Area.
Low: Limited habitat for the species occurs in the Survey Area and the species' range includes the geographic area, but there are no documented occurrences within five miles of the Survey Area within the past 20 years.
Not likely to occur: Species or signs not observed in the Survey Area, the Survey Area is outside of the species' known range, and conditions in the Survey Area are not suitable for occurrence.

Species Name	Common Name	Regulatory Status	Potential to Occur[2] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
							Segment 2 on both sides of the Rand Mountains, adjacent to Segment 2 between the Rand Mountains and Kramer Junction, overlapping Segments 3N and 3S between Kramer Junction and Hinkley, overlapping Segment 3N north of Barstow, adjacent to Segment 3S south of Barstow. Occurs in arid, sandy or gravelly locations along riverbanks, washes, sandy dunes, creosote scrub, and rocky hillsides. Likely to occur only in suitable habitat, especially in designated critical habitat, between Olancha to Inyokern, between Inyokern and Kramer Junction, and from Kramer Junction to Barstow.
Sceloporus graciosus graciosus	northern sagebrush lizard	Fed: None State: None BLM: S SR: S3	Present	Not likely to occur	Not likely to occur	Not likely to occur	Five individuals of northern sagebrush lizard were observed in 2017-2018 southwest of Bishop, near the Tinemaha reservoir (northeast and south), and near the Alabama Hills in scrub habitats along Project alignment Segment 1 within 1,500 feet of a stream or the Owens River. One recent CNDDB record within 0.5 miles of Segment 1 between Grant and Haiwee. Occurs in sagebrush scrub and other types of shrublands, mainly in the mountains and prefers open areas with scattered low brush and sunny areas for basking. Suitable habitat between Bishop and south of Lone Pine (east of Alabama Hills). Likely to occur along Segment 1, Crater Mountain Realignment Alternative, and Manzanar Realignment Alternative alignments between Bishop and Haiwee.
Birds							
Accipiter cooperii	Cooper's hawk	Fed: None State: None CDFW: WL SR: S4	Present	Moderate	Present	Moderate	2 observations of two individuals in 2017-2018. A Cooper's hawk flushed out of the trees south of the South Haiwee Reservoir. There was one observation of a Cooper's hawk flying over the alignment in Creosote Bush – White Bursage Scrub just north of Elephant Mountain on Segment 3N. Woodland and riparian woodlands and shrublands near Little Lake, North/South Haiwee Reservoir, the Owens River (north of Lone Pine, south of Tinemaha reservoir, and south of the Control substation) all provide suitable habitat. eBird observations within the past 10 years during the March through August breeding season are concentrated in Bishop, Big Pine, Lone Pine, along the Owens River and the eastern Sierra Nevada foothills, Kramer Junction, Barstow, Baker, and the Clark Mountains. This species forages in open woodlands or woodland margins as well as in some shrublands. Nests are built in the upper canopy of a dense stand of trees such as live oak or cottonwood in riparian areas, canyon bottoms, river flood-plains, and live oak woodlands and savannas. Breeding resident throughout most of the wooded portion of the state, under 9,000 feet amsl. Northern portion of the Owens Valley north of Tinemaha Reservoir is winter range with the remainder of the Project located within the species' yearlong range. Likely to nest in suitable habitat within riparian woodland along the Owens River south of Tinemaha Reservoir intersecting or adjacent to Segment 1 and Manzanar Realignment Alternative alignment, and stream riparian corridors intersecting or adjacent to Crater Mountain Realignment Alternative alignment. Moderate potential to nest in communities, towns, or cities with landscaped tree canopy cover.
Aquila chrysaetos	golden eagle	Fed: None State: None CDFW: FP BLM: S SR: S3	Present	Present	High	High	3 Observations of 3 individuals in 2017-2018. One golden eagle was observed along Segment 1 just south of Bishop in the foothills of the Tungsten Hills. An immature golden eagle was observed soaring above Creosote Bush Scrub vegetation in the El Paso Mountains near Segment 2There are 5 historic (1974 – 1996) and 1 recent (2009) CNDDB records of observed nesting activity or existing nests located within 5 miles of Segment 1 between Haiwee and Pearsonville: 2009 observation mapped to a 2/5-mile accuracy overlaps Segment 1 south of Haiwee; 1996 observation mapped to a 1-mile accuracy overlaps Segment 1 west of Little Lake; 3 historic (1974-1979) occurrences are mapped within 500 feet east of Segment 1 between Little Lake and Pearsonville. Two CNDDB records (1979, 2010) of nesting activity occur within 5 miles of Segment 2 on the south side of the El Paso Mountains, the 2010 occurrence mapped to a 1/10-mile accuracy overlaps Segment

Species Name	Common Name	Regulatory Status	Potential to Occur[2] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
							2 and notes the nest was on a transmission tower. Two historic to recent (1977, 2008) CNDDB records of nesting activity or existing nests near Daggett Ridge within 5 miles of Segment 3S, one historic (1971) CNDDB record of an existing nest ~0.3 miles west of Segment 3N on Elephant Mountain. Occurs in cliff-walled canyons that provide suitable nesting habitat and in large trees and open areas within foothills, mountain areas, sage-juniper flats, and deserts. High potential for nesting golden eagles to occur in suitable hilly-, cliff-, or mountain-type type nesting habitat within proximity of Segment 1 between Haiwee and Pearsonville, Segment 2 in the El Paso and Rand Mountains, Segment 3N in the Waterman Hills, Segments 3N in the Mitchel Range and Elephant Mountain.
Athene cunicularia	burrowing owl	Fed: None State: None CDFW: SC BLM: S USFWS: BCC SR: S2	Moderate	High	Present	High	No burrowing owls were observed along the proposed alignment, but two burrows were observed along Segment 3N: one burrow on the south side of Harper Lake and the other between the Calico Mountains and the Mitchel Range to the west. CNDDB records at Coso Junction in Segment 1. One historic (1891) CNDDB record located in the Zurich area within ~3 miles northeast of Segment 1 and Big Pine. CNDDB historic (1979) and recent (2007) occurrences for burrowing owl are located within 5 miles of Segment 1 and Fossil Falls Realignment Alternative alignment east of Coso Junction; 2007 occurrence overlaps a proposed materials yard location along Gill Station Coso Road. Several recent CNDDB records within 5 miles of Segments 1 and 2 near Inyokern, Segment 3N in the Lockhart area, and Segments 3N and 3S in Hinkley and Barstow. Occurs mainly in grassland and open scrub from the seashore to interior California and is strongly associated with ground squirrel burrows. Suitable nesting habitat was observed near Harper Lake and between Calico Mountains and the Mitchell Range. Moderate potential in Segment 1 south of Olancha. High potential to occur in suitable habitat along Segments 2, 3N, and 3S.
Buteo regalis	Ferruginous hawk	Fed: None State: None CDFW: WL SR: S3S4	Moderate (wintering)	Moderate (wintering)	Present	Present	A ferruginous hawk was observed flying over Creosote Bush – White Bursage Scrub near Segments 3N and 3S west of Yermo during the surveys. The ferruginous hawk is a winter resident of southern California, but does not breed in this region. No CNDDB records within 5 miles of the Project. During winter, the species generally occurs in open grasslands, sagebrush flats, desert scrub, low foothills and fringes of pinyon and juniper habitats. Suitable wintering habitat for the ferruginous hawk is found primarily where alfalfa fields and pastures occur in the vicinity of Daggett and Hinkley. Moderate potential for wintering (non-nesting) ferruginous hawk to occur in the Project area.
Buteo swainsoni	Swainson's hawk	Fed: None State: ST BLM: S SR: S4	Present	Not likely to occur	Not likely to occur	Not likely to occur	Seven non-nesting individuals observed foraging along or flying over Segment 1 and alternative alignments from Bishop to Ridgecrest. Eleven CNDDB records occur near the alignment from Bishop, Klondike Lake, Big Pine south to the Tinemaha Reservoir, north of Independence, near Manzanar, and near the Haiwee Reservoir – ten of the eleven observations were of active nests or nesting behavior. Occurs in grasslands with scattered trees, juniper-sage flats, riparian areas, savannahs, and agricultural or ranch lands with tree groves. Requires adjacent suitable foraging areas such as grasslands, alfalfa or grain fields that support rodent populations. Potentially suitable nesting habitat was observed along Segment 1 near Bishop, Klondike Lake, Big Pine, Independence, Manzanar, and Haiwee Reservoir; high potential to occur in suitable habitat along Segment 1 and Crater Mountain and Manzanar Realignment Alternative alignments.
Calypte costae	Costa's hummingbird	Fed: None State: None USFWS: BCC SR: S4	Present	Low	Low	Low	One individual was observed near Segment 1 north of Coso. Species not tracked by CNDDB; numerous eBird observations near the Project during the breeding season in the past 10 years, concentrated in towns and cities with managed landscaped habitats such as Bishop, Big Pine, and Inyokern. Species can occur in desert scrub in the Sonoran and Mojave deserts, and chaparral. During the non-breeding season they use similar dry habitats as well as parks, gardens, and higher elevation mountains. In the Mojave

Species Name	Common Name	Regulatory Status	Potential to Occur[2] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
							desert they frequent scrub and woodlands near springs and streams with cottonwoods, brittlebush, four-winged saltbush, Mojave desert scrub species.
Circus hudsonius	northern harrier	Fed: None State: None CDFW: SSC USFWS: BCC SR: S3	Present	Not likely to occur	Not likely to occur	Not likely to occur	One non-nesting observation of a foraging adult male was made near Segment 1 in 2017 in Olancha, on the Olancha Sand Dunes adjacent to desert scrub. This individual was likely migrating through the area. One historic (1996) CNDDB record of a nesting pair within 3 miles west of Segment 1 northwest of Lone Pine. Occurs in large, undisturbed tracts of wetlands and grasslands with low, thick vegetation. They breed in freshwater and brackish marshes, lightly grazed meadows, old fields, tundra, dry upland prairies, and drained marshlands. Potentially suitable nesting habitat was observed in wetland and freshwater marsh habitat north of Olancha; low to moderate potential to occur in suitable habitat along Segment 1.
Contopus cooperi	olive-sided flycatcher	Fed: None State: None CDFW: SSC USFWS: BCC SR: S3	Present (Crater Mountain)	Not likely to occur	Not likely to occur	Not likely to occur	One olive-sided flycatcher was observed in June 2023 along Wyman Creek in the White Mountains well outside of Segment 1. One observation of one non-nesting adult olive-sided flycatcher in May 2023 within 1 mile of the Crater Mountain Realignment Alternative alignment at the Tinemaha campground area in Water Birch Thickets. There are no CNDDB records on or near the Crater Mountain Realignment Alternative alignment. Suitable nesting habitat for the olive-sided flycatcher includes open mature forests with tall trees. The olive-sided flycatcher is unlikely to nest along Segment 1 or the Crater Mountain Realignment Alternative alignment due to the lack of suitable habitat and documented breeding records for this species in the Crater Mountain Realignment Alternative alignment area.
Falco mexicanus	prairie falcon	Fed: None State: None CDFW: WL SR: S4	Present	Present	Present	High	Prairie falcons were observed along Segment 1 in 2017-2018, a potential prairie falcon nest was observed in an old corvid nest on a tower, very uncommon but studies have shown this to occur on transmission lines in the western United States. A juvenile was seen adjacent to the nest before it was disturbed. An adult prairie falcon was observed near Segment 2 perched on a tower in Creosote Bush Scrub south of the El Paso Mountains and west of Atolia. A second adult prairie falcon was observed soaring over Creosote Bush Scrub within Segment 3N east of Harper Lake near Fossil Bed Road. CNDDB documents this species as occurring in several USGS quadrangles overlapping and near the Project and alternative alignments. Species is commonly found in annual grasslands to alpine meadows, but is associated primarily with perennial grasslands, savannahs, rangeland, some agricultural fields, and desert scrub areas. They will typically use sheltered cliff ledges for cover and nesting. High potential for nesting golden eagles to occur in suitable cliff-type nesting habitat within proximity of Segment 1 near Bishop and Inyokern, Segment 2 in the El Paso and Rand Mountains, Segment 3N in the Waterman Hills, and Segments 3N and 4 in the Mitchel Range and Elephant Mountain; low potential to occur along Segment 4 in the Cave Mountain, Clark Mountains, Mohawk Ridge, and Mescal Range areas.
Haliaeetus leucocephalus	bald eagle	Fed: FD State: SE CDFW: FP BLM: S SR: S3	Present	Not likely to occur	Not likely to occur	Not likely to occur	Two non-nesting observations occurred along Segment 1: one adult was perched on a power pole near a fish hatchery just west of the Owens River on Fish Springs Road, south of Bishop, and another was observed flying near the Project alignment near south Haiwee Reservoir. There is one 1990 CNDDB record near Segment 1 to the west of Tinemaha Reservoir that references an occupied but unsuccessful nest. Nests in large, old-growth live trees with open branches. Species is known to roost communally in winter. Prefers trees near large bodies of water such as lake margins and rivers for both nesting and wintering. Most nests are within 1 mile of water. Potentially suitable nesting habitat is present along Segment 1 near Tinemaha Reservoir, the fish hatchery on Fish Springs Road, as well as locations with mature cottonwood trees near Klondike Lake, South Haiwee Reservoir, Owens Lake, and Little Lake.

Species Name	Common Name	Regulatory Status	Potential to Occur[2] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
Lanius ludovicianus	loggerhead shrike	Fed: None State: None CDFW: SSC SR: S4	Present	Present	Present	Present	Twenty-two total individuals observed in 2017-2018 vocalizing and foraging near Segment 1, Crater Mountain Realignment Alternative, Manzanar Realignment Alternative and Fossil Falls Realignment Alternative alignments in 11 locations. Four observations with 1 individual each vocalizing and foraging in various locations along alignment near Kramer Junction. A 2006 CNDDB nesting record overlaps Segment 3N south of Harper Lake. One individual was observed nesting in a tower surrounded by creosote bush scrub in the Indian Wells Valley south of the Inyokern Substation. Non-nesting observations were located near the following: south of Tinemaha Reservoir, Manzanar, North Haiwee Reservoir, Little Lake, Pearsonville, and north of Inyokern. Five observations in 2023: in August 2023, a pair of adults perched on shrub along Mazourka Canyon Road and one adult perched on a shrub in greasewood scrub near Owens River, south of Twin Lakes; in May 2023, one adult roosting on shrub flushed from vegetation along between Owenyo and Lone Pine, and two observations southeast of Twin Lakes on the Manzanar Realignment Alternative Alignment of one single adult roosting in desert scrub and of a pair exhibiting nesting behavior. Occurs in open woodlands, savannah, pinyon-juniper woodland, Joshua tree woodland, riparian woodland, desert oases, scrub, and washes in conjunction with sufficient shrubs, trees, posts, fencelines, or other perches. Prefers open country for hunting, with perches for scanning, and fairly dense shrubs and brush for nesting. Suitable nesting habitat was observed in the Indian Wells Valley; potentially suitable habitat along Segment 1, Crater Mountain Realignment Alternative and Manzanar Realignment Alternative alignments occurs where dense shrubs and brush provide adequate cover, from south of the Tinemaha Reservoir to Inyokern. Moderate nesting potential south of Harper Lake. Non-breeding individuals of the loggerhead shrike are likely to occur in many natural areas where they make use of native shrubs, trees, posts, and other perches.
Pandion haliaetus	osprey	Fed: None State: None CDFW: WL SR: S4	Present	Present	Not likely to occur	Not likely to occur	One osprey was observed in 2017-2018 foraging near Segment 1 just west of the South Haiwee Reservoir. Suitable foraging and nesting habitat is present around the larger lakes and rivers along the alignment in the Owens Valley. Occurs along ocean shores, bays, fresh-water lakes, and larger streams with larger trees. One osprey was observed perched atop a pole approximately 8 miles south of Atolia within near Segment 2 in 2017. One observation in 2023 of one adult osprey flying over the Manzanar Realignment Alternative Alignment southeast of Twin Lakes northeast of Fort Independence. Ospreys are winter residents and migrants of southern California. During migration and winter, the species generally occurs along ocean shores, bays, fresh-water lakes, and larger streams with larger tall trees. The osprey is unlikely to nest along the ICKI alignment due to lack of present throughout the Project area. One CNDDB occurrences of the species nesting is present in the Project area at the Tinemaha Reservoir (CNDDB 2018). There is no suitable nesting habitat for the osprey within the alignment, and this species is unlikely to encountered nesting occur except as an occasional migrant. Potentially suitable nesting habitat is present along Segment 1 near Tinemaha Reservoir, the fish hatchery on Fish Springs Road, as well as locations with mature cottonwood trees near Klondike Lake, South Haiwee Reservoir, Owens Lake, and Little Lake.
Pelecanus erythrorhynchos	American white pelican	Fed: None State: None CDFW: SSC USFWS: BCC SR: S1S2	Present	Not likely to occur	Not likely to occur	Not likely to occur	One observation in 2023, a flock of over 50 individuals flying over Owens River above Mazourka Canyon Road near Segment 1 and the Manzanar Realignment Alternative alignment. The American white pelican does not nest in the Owens Valley. California's nesting pelicans found primarily in the Klamath Basin but the species is widely dispersed during migration.

Species Name	Common Name	Regulatory Status	Potential to Occur[2] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
Piranga rubra	summer tanager	Fed: None State: None CDFW: SSC SR: S4	Present	Not likely to occur	Not likely to occur	Not likely to occur	A single non-nesting individual was observed near the Control Substation at the northern terminus of Segment 1. A recent non-nesting CNDDB record is located west of the alignment at Baker Creek near Big Pine. Two non-nesting CNDDB records have been reported, one in Afton Canyon (1977) in the Cady Mountains and the other north of the alignment in the Clark Mountains (1970). Occurs in mature, desert riparian communities dominated by cottonwoods and willows, which provide foraging and nesting habitat. There is no suitable nesting habitat for the summer tanager along the Project or alternative alignments, since large stands of undisturbed, mature riparian forest are mostly lacking.
Plegadis chihi	white-faced ibis	Fed: None State: None CDFW: WL SR: S3S4	Present	Not likely to occur	Not likely to occur	Not likely to occur	Remains of one individual as a result of a line strike was observed in 2017-2018 along Segment 1 just north of Highway 136 near Lone Pine. One observation in 2023 of five adults observed roosting on grassy shore at the southern end of Owens Lake northeast of Olancha near Segment 1. No CNDDB records within 5 miles. Species requires dense tule thickets for nesting, interspersed with areas of shallow water for foraging. Generally found near shallow freshwater marshes. Moderate potential to nest in suitable habitat along Segment 1 between Lone Pine and Olancha.
Polioptila melanura	black-tailed gnatcatcher	Fed: None State: None CDFW: WL SR: S3S4	Present	Low	Present	Low	Two black-tailed gnatcatchers were observed in 2017-2018 along Segment 1 in a desert wash adjacent to Tamarisk woodland, south of Highway 136. Inhabits wooded desert wash habitats; also occurs in desert scrub. A single black-tailed gnatcatcher was observed vocalizing and foraging in Creosote Bush Scrub along Segment 3N near Irwin Road. Black-tailed gnatcatchers occur in wooded desert wash habitats; also in desert scrub habitat in winter. The black-tailed gnatcatcher is a year-round resident of southern California and does not migrate. In the Mojave Desert, black-tailed gnatcatchers nests in desert washes containing mesquite, paloverde, ironwood, and acacia. The black-tailed gnatcatcher has a low to moderate likelihood of nesting within the ICKI alignment. There is potentially suitable nesting habitat for the black- tailed gnatcatcher in desert washes supporting catclaw acacia and other desert scrub vegetation, primarily between Halloran Wash and the Ivanpah Substation. It is unlikely to nest west of Afton Canyon to the Inyokern Substation.
Riparia riparia	bank swallow	Fed: None State: ST BLM: S SR: S3	Present	Not likely to occur	Not likely to occur	Not likely to occur	Three observations in 2017-2018 near Segment 1along the Owens River south of the Tinemaha Reservoir, area 2 miles north of Lone Pine, and near the Haiwee Substation. One historic CNDDB record along the Owens River northeast of Big Pine, within ~3 miles of Segment 1. Occurs near vertical banks/cliffs with fine-textured/sandy soils near streams, rivers, and lakes for nesting. Colonial nester; nests primarily in riparian and other lowland habitats west of the desert. Suitable nesting habitat potentially present along the Owens River south of the Tinemaha Reservoir, north of Lone Pine, and near the Haiwee Substation. Potentially suitable habitat with earthen banks, bluffs, and cliffs may occur along other discrete portions of the Owens River.
Toxostoma lecontei	Le Conte's thrasher	Fed: None State: None CDFW: SSC BLM: S USFWS: BCC SR: S3	Present	High	High	High	Two observations in 2023 east of the Owens River over the Manzanar Realignment Alternative alignment. One single adult was observed flushed from desert scrub vegetation east of the Alabama Hills. A pair of LeConte's thrashers were observed vocalizing in desert scrub vegetation south of Manzanar Reward Road. A 1946 CNDDB egg collection record mapped to a 1-mile accuracy is reported from Inyokern and overlaps Segments 1 and 2. Several historic CNDDB records located along Little Dixie Wash within 5 miles of Segment 2. There are two 2017 eBird nesting records for Le Conte’s thrasher within approximately 1 mile of Segment 2 at Inyokern. Recent and historic CNDDB records are located in Barstow within 5 miles of Segments 3N and 3S. Occurs in desert washes, desert scrub, alkali desert scrub, and desert succulent shrub communities; it also occurs in Joshua tree woodland. This species nests in dense, spiny shrubs or densely branched cactus habitat in desert washes 2 to 8 feet above ground.

Species Name	Common Name	Regulatory Status	Potential to Occur[2] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
Xanthocephalus xanthocephalus	yellow-headed blackbird	Fed: None State: None CDFW: SSC SR: S3	Present	Not likely to occur	Not likely to occur	Not likely to occur	A flock was observed along Segment 1 in 2017 at the South Haiwee Reservoir; no nesting birds observed. One observation in 2023 of one male adult flying over Segment 1 at the southern end of Owens Lake near Highway 190 north of Olancha. No CNDDB records exist within 5 miles of the Project. Occurs only where large insects are abundant, and nesting is timed with maximum emergence of aquatic insects. Nests occur in freshwater emergent wetlands with dense vegetation and deep water, often along borders of lakes or ponds. There is a low potential for nesting yellow-headed blackbirds to be encountered along Segment 1, since little undisturbed cattail and marsh habitat occurs along the alignment.
Mammals							
Cervus canadensis nannodes	tule elk	Fed: None State: None SR: S3	Present	Not likely to occur	Not likely to occur	Not likely to occur	One observation of tule elk in 2023 near Segment 1 and Crater Mountain Realignment Alternative alignments, with three males and six females in Fremont's Smokebush - Nevada Smokebush Scrub on the east-facing flanks of Crater Mountain. Tule elk are endemic to California and often occupy open arid habitats. There are 5 distinct populations of tule elk in the Owens Valley, a species introduced to this location in the 1930s by CDFW, including one that occurs near where the 2023 observation was made. Tule elk are likely to occur along Segment 1 and the Crater Mountain Realignment Alternative alignment.
Vulpes macrotis	desert kit fox	Fur-bearing mammal, CCR § 460	Not likely to occur	High	Present	High	Observations were documented along Segment 3N; two east of Kramer Junction in creosote bush scrub, one in the Waterman Hills in creosote bush scrub. Occur in open shrubland habitat within prey animal (jackrabbits, desert cottontail, rodents) habitat. Require loose sandy and loamy soils for excavating dens during pup rearing. Likely to occur only in suitable open shrubby habitat between Kramer Junction and Yermo.

Not Observed with Potential to Occur

Invertebrates							
Bombus occidentalis	western bumble bee	Fed: None State: SC SR: S1	Not likely to occur	Not likely to occur	Not likely to occur	Low	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One 1978 CNDDB record is located in the Kramer Hills within one mile of Segment 3S. No Bumble Bee Atlas sightings within 5 miles of the Project. Project is outside of the current and historic species' range. Occurs in semi-arid areas near washes or intermittent streams, including valley-foothill and desert riparian, habitat with sandy banks, willows, cottonwoods, and sycamores, especially in the northern half of California. Prefers loose, gravelly areas of streams in drier parts of range from sea level to over 6,500 feet amsl. It typically nests underground in abandoned rodent burrows or other cavities. Required plant genera include *Cirsium*, *Cleome*, *Helianthus*, *Lupinus*, *Chrysothamnus*, and *Melilotus*. Not likely to occur along the Project or alternative alignments as they are outside the species' range and largely lacks suitable habitat.
Danaus plexippus plexippus	Monarch butterfly	Fed: FC State: None SR: S2	High	High	Not likely to occur	Moderate	Recent candidate for listing under ESA. Many iNaturalist observations documented along Segments 1 and 2 between Bishop and Ridgecrest. One iNaturalist observation in Barstow (2016). Three recent CNDDB records near Segment 1, east of Lone Pine on the east side of the Inyo Mountains at Saline Valley. Exhibit long-distance migration, western population primarily overwinters in groves along the coast of California and Baja California, roosting in eucalyptus, Monterey pines, and Monterey cypress trees. Feed on nectar from a variety of flowers; reproduction depends on presence of milkweed, which is the only food source for larvae. Breeding in open areas, fields, and roadside areas with suitable blooming nectar sources

Species Name	Common Name	Regulatory Status	Potential to Occur[2] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
							and milkweed. In western North America, nectar and milkweed resources often associated with riparian corridors. The Project site is outside the monarch's coastal overwintering range.
Plebulina emigdionis	San Emigdio blue butterfly	Fed: None State: None SR: S1S2	High	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Recent CNDDB record is located 0.5 miles west of Segment 1 between the south end of Owens Lake and the north end of Haiwee Reservoir. Occurs in shadscale scrub in desert canyons and near washes at the southern end of the Sierra Nevada, in the San Emigdio Mountains, near Victorville, and near the south end of Owens Lake. Suitable shadscale scrub habitat between the southwestern end of Owens Lake and the north end of Haiwee Reservoir.
Pyrgulopsis wongi	Wong's springsnail	Fed: None State: None SR: S2	High	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Several historic CNDDB records within 5 miles of Segment 1 and alternative alignments west of Big Pine, the Poverty Hills, and Independence, in the Alabama Hills west of Lone Pine, west of Haiwee and Dunmovin. Several occurrences overlap Segment 1, including the north end of the Alabama Hills, the north end of Owens Lake south of Lone Pine, the south end of Owens Lake, and south of Little Lake. Occurs in seeps, headsprings, and upper reaches of springs. The species generally occurs in freshwater springs with areas of watercress on small bits of travertine and stone. Potentially suitable seeps and springs located along Segment 1 near the Alabama Hills, the southwestern end of Owens Lake, and the southern end of Little Lake. High potential to occur in suitable habitat along Segment 1.
Fish							
Catostomus fumeiventris	Owens sucker	Fed: None State: None CDFW: SSC SR: S3	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Several historic to recent CNDDB records in several locations along the Owens River and in ditches in and near Bishop to the northeast of Segment 1; at the Fish Springs Hatchery southeast of Big Pine; and south of the Tinemaha Reservoir near Aberdeen. Endemic to the Owens River drainage and is most common in areas with long runs and few riffles. Adults can thrive in reservoirs but needs gravelly riffles in tributary streams for spawning. Owens sucker occupies backwaters and warmer, lower, and calmer water. Low potential to occur within streams, ditches, and the Owens River within the Owens Valley where Segment 1 and the Crater Mountain and Manzanar Realignment Alternative alignments cross.
Amphibians							
Lithobates pipiens	northern leopard frog	Fed: None State: None CDFW: SSC SR: S2	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Several historic CNDDB records within 5 miles of Segment 1 and Crater Mountain Realignment Alternative alignment, including west of Bishop in Pine Creek, in the Owens River northeast of Aberdeen, east of Bishop at Birch Creek, and in Baker Creek west of Big Pine. Occurs east of the Sierra Nevada-Cascade Crest and near permanent or semi-permanent water in a variety of habitats. Shoreline cover and submerged and emergent aquatic vegetation are important habitat characteristics. Low to occur along Segment 1 and the Manzanar Realignment Alternative alignment, limited potentially suitable habitat between Bishop and just south of the Tinemaha Reservoir.

Species Name	Common Name	Regulatory Status	Potential to Occur[2] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
Reptiles							
Uma scoparia	Mojave fringe-toed lizard	Fed: None State: None CDFW: SSC BLM: S SR: S3S4	Not likely to occur	Not likely to occur	High	High	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Several historic to recent CNDDB occurrences within 5 miles of Segments 3N, 3Sin Harper Valley, between Hinkley and Barstow. Occurs in desert dunes, desert washes and Mojavean desert scrub communities. Shrubs or annual plants may be necessary for the arthropods found in the lizard's diet. It lives in fine, loose, wind-blown sand in sand dunes, dry lakebeds, riverbanks, desert washes, sparse alkali scrub, and desert scrub.
Birds							
Charadrius nivosus nivosus	western snowy plover	Fed: FT State: None CDFW: SSC SR: S3	High	Not likely to occur	High	High	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Two CNDDB records of nesting located within 5 miles of Segment 1, Crater Mountain Realignment Alternative, and Manzanar Realignment Alternative alignments: one 1992 CNDDB record at Tinemaha Reservoir south of Big Pine and one 2004 CNDDB record for at Owens Lake. Known nests reported on the shores of Owens Lake. The Owens Lake occurrence polygon overlaps Segment 1. Nesting has been reported at Harper Lake in 1977 and 1978 and assumed nesting there in 1988. Potentially suitable nesting habitat located on the southern edge of Harper Dry Lake. Occurs in sandy, gravelly or friable soils for nesting and they occur on sandy beaches, salt pond levees, and shores of large alkali lakes. High potential to occur in suitable habitat along Segment 1 at Owens Lake, Segments 3N and 3S near Harper Lake.
Charadrius montanus	mountain plover	Fed: None State: None CDFW: SSC BLM: S USFWS: BCC SR: S3	High (migration)	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Two CNDDB records located within 5 miles of Segment 1, Crater Mountain Realignment Alternative, and Manzanar Realignment Alternative alignments: one 1992 CNDDB record at Tinemaha Reservoir south of Big Pine and one 2004 CNDDB record for at Owens Lake. Occurs in short grasslands, freshly plowed fields, newly sprouting grain fields, and occasionally in sod farms, landscaping, bare ground, and flat topography, where it prefers grazed areas and areas with burrowing rodents within chenopod scrub and valley and foothill grassland communities. High potential to occur in suitable habitat along Segment 1 during migration; the Project and alternative alignments are located outside the species' breeding and overwintering ranges.
Coccyzus americanus occidentalis	western yellow-billed cuckoo	Fed: FT State: SE BLM: S SR: S1	Low	Not likely to occur	Low	Low	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Several historic to recent CNDDB records within 5 miles of Segment 1, Crater Mountain Realignment Alternative, and Manzanar Realignment Alternative alignments: west of Big Pine, north of Tinemaha Reservoir, north of Independence. One historic CNDDB occurrence mapped to a 2/5-mile accuracy northeast of Aberdeen overlaps Segment 1. CNDDB records near Segments 3N and 3S southwest of Barstow. Occurs in riparian forest and will nest in riparian thickets of willow, often mixed with cottonwoods, with an understory of blackberry, nettle, and wild grape. Not likely to nest along the Project or alternative alignments, known nesting areas are north of Tinemaha Reservoir outside of the alignment. Suitable dense riparian forest nesting habitat absent along the alignment, existing riparian forest along alignment is fragmented and disturbed.
Ixobrychus exilis	least bittern	Fed: None State: None CDFW: SSC SR: S4	High	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Two historic to recent CNDDB records within 5 miles of Segment 1 and Manzanar Realignment Alternative alignment: one east of Independence and one on the west side of Owens Lake.

Species Name	Common Name	Regulatory Status	Potential to Occur[2] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
							Occurs in marshlands in colonies and along borders of ponds and reservoirs where ample cover is available. Nests are usually placed low in tule and over water. High potential to occur in suitable nesting habitat along Segment 1 and Manzanar Realignment Alternative alignment east of Independence and along the shores of Owens Lake.
Mammals							
Antrozous pallidus	pallid bat	Fed: None State: None CDFW: SSC BLM: S SR: S3	Moderate	Moderate	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Several historic to recent CNDDB records within 5 miles of Segment 1, Manzanar Realignment Alternative, Segment 2, north of Independence, overlapping in Independence, in the Alabama Hills, overlapping in Lone Pine, on the south side of Owens Lake, overlapping south of Randsburg. Occurs in desert, grassland, shrubland, woodland and forest communities with rocky areas for roosting. Roosts on walls and ceilings of caves and mines, also buildings, bridges, rock crevices, and hollow trees; roosting sites are limiting to success and presence. This species is very sensitive to disturbance of roosting sites. Moderate potential to roost in suitable habitat along Segment 1 and alternative alignments, Segment 2, and Segment 4.
Corynorhinus townsendii	Townsend's big-eared bat	Fed: None State: None CDFW: SSC BLM: S SR: S2	High	High	High	High	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Multiple historic to recent CNDDB records within 5 miles of Segment 1 and alternative alignments, Segments 2, 3N: in the Tungsten Hills west of Bishop, in the foothills south of Bishop, southeast of Bishop, north of Independence, in the Alabama Hills, overlapping in Lone Pine, near the Haiwee Reservoir, overlapping south of Little Lake, overlapping south of Randsburg, south side of the Calico Mountains. Roosts in mines or caves in the winter and limestone caves, lava tubes, and human-made structures in the summer. Maternity colonies form between March and June. Foraging occurs near roosting habitat in arid desert scrub and pine forests. High potential to roost in suitable habitat along Segment 1 and alternative alignments, Segment 2, Segment 3N.
Euderma maculatum	spotted bat	Fed: None State: None CDFW: SSC BLM: S SR: S3	Moderate	Moderate	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Several historic CNDDB records within 5 miles of Segment 1 and Manzanar Realignment Alternative alignment in the Bishop area, south of Lone Pine, west of Bartlett, and along the western shore of Owens Lake. Several occurrences overlap Segment 1, including in Lone Pine and Cartago. One CNDDB record from China Lake. Roosting habitat includes rock crevices in cliffs or caves. Forages over open water and along washes, mainly for moths. It occupies a wide variety of habitats from arid deserts and grasslands to mixed conifer forests. Low to moderate potential to roost in suitable habitat along Segment 1 and alternative alignments, Segment 2.
Lepus townsendii townsendii	western white-tailed jackrabbit	Fed: None State: None CDFW: SSC SR: S3?	Moderate	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One historic CNDDB record north of Bishop within 5 miles of Segment 1. Occurs in sagebrush, subalpine conifer, juniper, alpine dwarf shrub and perennial grassland. Habitat includes open areas with scattered shrubs and exposed flat-topped hills with open stands of trees, brush and herbaceous understory. Low to moderate potential to occur in suitable habitat along Segment 1 north of Tinemaha Reservoir.
Microtus californicus mohav	Mohave River vole	Fed: None State: None CDFW: SSC SR: S1	Not likely to occur	Not likely to occur	Moderate	Moderate	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One historic CNDDB record in Lockhart within 5 miles of Segment 3N. Occurs only in weedy herbaceous growth in wet areas along the Mojave River and may be found in some irrigated pastures. Burrows into soft soil and feeds on leafy parts of grasses, sedges and herbs. Low to moderate potential to occur in suitable habitat along Segments 3N and 3S, where adjacent to or crossing the Mojave River and connected washes.

Species Name	Common Name	Regulatory Status	Potential to Occur[2] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
Microtus californicus vallicola	Owens Valley vole	Fed: None State: None CDFW: SSC BLM: S SR: S3	High	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Historic CNDDB records occur near Segment 1, Manzanar Realignment Alternative, and Fossil Hill Alternative alignments in the Bishop area, near Independence, the west side of the Alabama Hills, and north of Haiwee. Occurrences mapped to a 1-mile accuracy overlap Segment 1 in Independence, Lone Pine, Cartago, Olancha, and Little Lake. Occurs in wetlands and lush grassy habitats in the Owens Valley with friable soil for burrowing. It forages on grasses, sedges, and herbs. Potentially suitable burrowing and foraging habitat along Segment 1 in moist places between the southwestern end of Owens Lake and the north end of the Haiwee Reservoir.
Myotis ciliolabrum	western small-footed myotis	Fed: None State: None BLM: S SR: S3	Moderate	Moderate	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Two CNDDB records (1997, 1999) for western small-footed myotis occur east of Segment 1 and alternative alignments in or at the base of the Inyo Mountains. Occurs in a wide range of habitats, but mostly in arid wooded and brushy uplands near water. It will roost in caves, buildings, mines, and rock crevices and prefers open stands in forests and woodland for foraging. Habitat requirements include fresh drinking water and a wide variety of small flying insects. The species' range includes the Owens Valley and northwester and eastern parts of the Mojave Desert. Low to moderate potential to roost in suitable habitat along Segment 1 and alternative alignments, Segment 2.
Myotis thysanodes	fringed myotis	Fed: None State: None BLM: S SR: S3	Moderate	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. One CNDDB 2003 record is located along the Mojave River in Afton Canyon within 5 miles of Segment 4. Roosting sites consist of primarily abandoned mines, but include tree snags, rock outcrops, and natural caves. Forages in desert-scrub to fir-pine vegetation communities. The species' range includes much of California, including the Owens Valley and parts of the Mojave National Preserve, but excluding most of California's deserts. Low to moderate potential to roost in suitable habitat along Segment 1 and alternative alignments.
Myotis yumanensis	Yuma myotis	Fed: None State: None BLM: S SR: S4	Moderate	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Two historic CNDDB records located on the north and south sides of Owens Lake, within 5 miles of Segment 1 and Manzanar Realignment Alternative alignment. This bat species is associated with permanent water, typically rivers and streams, but also scour pools in bedrock. Found in riparian, forests, and arid scrublands and deserts and roosts in bridges, buildings, cliff crevices, caves, mines, and trees. The species' range includes much of California, including the Owens Valley but excluding most of California's deserts. Low to moderate potential to roost in suitable habitat along Segment 1 and alternative alignments.
Ovis canadensis sierrae	Sierra Nevada bighorn sheep	Fed: FE State: SE CDFW: FP SR: S3	Low	Not likely to occur	Not likely to occur	Not likely to occur	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. CNDDB records for Sierra Nevada bighorn sheep all occur in the eastern Sierra Nevada at higher elevations than the Project or alternative alignments. Occurs only in the Sierra Nevada between Yosemite National Park south to Sequoia National Park. Habitat requirements include steep, open terrain free of competition from other grazing ungulates. USFWS designated critical habitat is located within 5 miles east of the Proposed alignment in Segment 1; however, Not likely to occur along the Project or alternative alignments as no suitable habitat is present and the Project is located outside the species' range.

Species Name	Common Name	Regulatory Status	Potential to Occur[2] Segment 1	Potential to Occur Segment 2	Potential to Occur Segment 3N	Potential to Occur Segment 3S	Observations, Habitat, and Distribution
Taxidea taxus	American badger	Fed: None State: None CDFW: SSC SR: S3	Not likely to occur	High	High	High	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Several historic to recent CNDDB records within 5 miles of Segments 2, 3N, 3S: south of Inyokern, south of the Rand Mountains, west of Hinkley. An historic CNDDB occurrence mapped to a 1-mile accuracy overlaps Segment 2 in Randsburg. This species is most abundant in open shrub, forest, and herbaceous communities with friable soils; it requires sufficient food, friable soils, and open, uncultivated ground. Potentially suitable habitat for the American badger in areas with friable soils located near Randsburg in the upper Fremont Valley and near Hinkley.
Xerospermophilus mohavensis	Mohave ground squirrel	Fed: None State: ST BLM: S SR: S2	High	High	High	High	Not observed along the Project or alternative alignments, or at reference sites, during Project surveys. Observations of Mohave ground squirrel reported by Leitner (2008, 2015) and CNDDB (1932-2016) mostly near southwestern Owens Lake south to the northern end of North Haiwee Reservoir; west of South Haiwee Reservoir; between Coso Junction and the Inyokern Substation; between the Inyokern Substation and the Coolwater Substation, excluding the higher rocky areas in the El Paso and Rand Mountains. Multiple CNDDB occurrences overlap the Project. Occurs in relatively flat open terrain in Mojave desert scrub, alkali scrub, and Joshua tree woodland between 1,000 feet to 5,000 feet in the Mojave Desert between Owens Lake and Barstow. Potentially suitable burrow and foraging habitat located in relatively flat open terrain along Segment 1, Fossil Hill Alternative alignment, and Segment 2 from the southwestern end of Owens Lake to Inyokern Substation. Potentially suitable burrow and foraging habitat located in relatively flat open terrain along Segments 3N and 3S from Kramer Junction (excluding rocky areas) and east to Barstow.

Table 4-2. Disturbance Acres: Vegetation Communities

Vegetation Community	Segment Acres of Disturbance 1	2	3N	3S	TOTAL	CDFW Sensitive[3]
Woodland Vegetation						
Fremont cottonwood forest (Populus fremontii Forest) Alliance[2]	2.28	0.00	0.00	0.00	2.28	S3.2
Joshua tree woodland (Yucca brevifolia) Woodland Alliance[1,4]	6.65	0.00	0.00	0.00	6.65	S3
Red willow thickets (Salix laevigata) Woodland Alliance[2]	0.13	0.00	0.00	0.00	0.13	S3
Shrubland Vegetation						
Allscale scrub (Atriplex polycarpa) Shrubland Alliance[4,6]	84.83	19.34	9.77	7.54	121.49	S4
Allscale scrub (Atriplex polycarpa) Shrubland Alliance, Atriplex polycarpa Association[4,6]	12.26	1.41	17.63	5.65	36.95	
Allscale scrub (Atriplex polycarpa) Shrubland Alliance, (Atriplex polycarpa) Sparse Playa Association[4,6]	1.28	0.00	0.00	0.00	1.28	S4
Big sagebrush (Artemisia tridentata) Shrubland Alliance[5]	19.14	0.00	0.00	0.00	19.14	
Bitter brush scrub (Purshia tridentata) Shrubland Alliance[5]	0.42	0.00	0.00	0.00	0.42	S3
Black brush scrub (Coleogyne ramosissima) Shrubland Alliance[4,7]	44.64	0.00	0.00	0.00	44.64	S4
Bush seepweed scrub (Suaeda moquinii) Shrubland Alliance	0.00	0.00	0.00	1.29	1.29	S3

Vegetation Community	Segment Acres of Disturbance 1	2	3N	3S	TOTAL	CDFW Sensitive[3]
California joint fir - longleaf joint-fir scrub (Ephedra californica - Ephedra trifurca) Shrubland Alliance, Ephedra californica Association[4,7]	0.00	0.00	0.00	0.86	0.86	S4
Cheesebush - sweetbush scrub (Ambrosia salsola - Bebbia juncea) Shrubland Alliance, (Ambrosia salsola) Association[4,7]	8.46	1.73	0.00	0.28	10.49	S4
Cheesebush - sweetbush scrub (Ambrosia salsola - Bebbia juncea) Shrubland Alliance, (Stephanomeria pauciflora) Provisional Association[4,7]	0.30	0.00	0.00	0.00	0.30	S4
Cheesebush - sweetbush scrub (Ambrosia salsola - Bebbia juncea) Shrubland Alliance, (Ambrosia salsola – Atriplex confertifolia) Association[4,7]	16.50	0.00	0.00	0.00	16.50	S4
Cooper's Goldenbush Scrub (Ericameria cooperi) Provisional Alliance	0.00	5.40	0.00	0.00	5.40	
Creosote bush scrub (Larrea tridentata) Shrubland Alliance[4,6]	2.06	207.30	37.17	28.90	275.44	S5
Creosote bush scrub (Larrea tridentata) Shrubland Alliance, (Larrea tridentata – Atriplex polycarpa) Association[4,6]	0.00	0.00	0.00	2.89	2.89	
Creosote bush - white bursage scrub (Larrea tridentata-Ambrosia dumosa) Shrubland Alliance[4,6]	86.04	43.10	14.11	64.86	208.12	
Creosote bush scrub (Larrea tridentata) Shrubland Alliance, Larrea tridentata - Senna armata Provisionial Association Association[4,6]	0.00	0.00	0.00	0.02	0.02	
Creosote bush scrub (Larrea tridentata-Ambrosia dumosa) Shrubland Alliance, (Larrea tridentata - Ambrosia dumosa - Psorothamnus (arborescens, fremontii)) Association[4,6]	4.46	0.00	0.00	0.00	4.46	S5
Creosote bush scrub (Larrea tridentata-Ambrosia dumosa) Shrubland Alliance, (Larrea tridentata - Ambrosia dumosa) Association[4,6]	0.00	9.12	0.00	5.10	14.22	S5
Creosote bush scrub (Larrea tridentata-Ambrosia dumosa) Shrubland Alliance, (Larrea tridentata – Ambrosia dumosa – Atriplex polycarpa) Association[4,6]	0.54	0.00	0.00	0.00	0.54	
Fourwing saltbush scrub (Atriplex canescens) Shrubland Alliance[4,6]	25.42	0.09	6.72	1.46	33.68	S4
Fourwing saltbush scrub (Atriplex canescens) Shrubland Alliance, Atriplex canescens / herbaceous Association[4,6]	0.00	0.00	0.00	0.10	0.10	S4
Greasewood scrub (Sarcobatus vermiculatus) Shrubland Alliance	23.34	0.00	0.00	0.00	23.34	S3S4
Greasewood scrub (Sarcobatus vermiculatus) Shrubland Alliance, (Sarcobatus vermiculatus / Sporobolus airoides) Association	4.54	0.00	0.00	0.00	4.54	S3S4
Greasewood scrub (Sarcobatus vermiculatus) Shrubland Alliance, (Sarcobatus vermiculatus) Sparse Playa Provisional Association	3.54	0.00	0.00	0.00	3.54	S3S4
Nevada joint fir - Anderson's boxthorn - spiny hop sage scrub (Ephedra nevadensis - Lycium andersonii - Grayia spinosa) Shrubland Alliance[4,7]	11.69	0.00	0.00	0.00	11.69	S3S4
Quailbush scrub (Atriplex lentiformis) Shrubland Alliance, (Atriplex torreyi) Association[5]	1.56	0.00	0.00	0.00	1.56	S4
Rubber rabbitbrush scrub (Ericameria nauseosa) Shrubland Alliance[5]	21.38	15.60	0.00	0.00	36.98	S5
Shadscale scrub (Atriplex confertifolia) Shrubland Alliance[4,6]	11.12	0.00	3.55	5.01	19.68	S4
Shadscale scrub (Atriplex confertifolia) Shrubland Alliance, (Atriplex confertifolia Sparse Playa) Association[4,6]	2.88	0.00	0.00	0.00	2.88	S4.2
Spinescale scrub (Atriplex spinifera) Shrubland Alliance[4,6]	0.00	68.51	25.19	10.62	104.32	S3
Sandbar willow thickets (Salix exigua) Shrubland Alliance[2]	0.81	0.00	0.00	0.00	0.81	S4.2
Smokebush desert wash scrub (Psorothamnus (fremontii, polydenius)) Provisional Shrubland Alliance[5]	3.46	0.00	0.00	0.00	3.46	S3
Spiny menodora scrub (Menodora spinescens) Shrubland Alliance[5]	0.66	0.00	0.00	0.00	0.66	S3
Tamarisk thickets (Tamarix spp. Semi-natural Shrubland Stands) Shrubland Alliance	0.00	0.00	1.07	0.58	1.65	
White bursage scrub (Ambrosia dumosa) Shrubland Alliance[4,6]	47.49	0.00	1.73	6.03	55.24	S5
Winterfat scrubland (Krascheninnikovia lanata) Shrubland Alliance[5]	0.00	0.83	0.00	0.00	0.83	S3
Herbaceous Vegetation						
Alkali sacaton grassland (Sporobolus airoides) Herbaceous Alliance	0.04	0.00	0.00	0.00	0.04	S2.2
Baltic and Mexican rush marshes (Juncus arcticus (var. balticus, mexicanus)) Herbaceous Alliance	12.70	0.00	0.00	0.00	12.70	S4

Vegetation Community	Segment Acres of Disturbance 1	2	3N	3S	TOTAL	CDFW Sensitive[3]
Big galleta shrub-steppe (Pleuraphis rigida) Herbaceous Alliance, Pleuraphis rigida/Atriplex canescens Association[4,6]	0.00	0.00	0.39	0.00	0.39	S2.2
Cheatgrass - medusahead grassland (Bromus tectorum - Taeniatherum caput-medusae Semi-natural Herbaceous Stands) Alliance, (Bromus tectorum) Association	10.09	0.00	0.00	0.00	10.09	
Salt grass flats (Distichlis spicata) Herbaceous Alliance	9.16	0.00	0.00	0.00	9.16	S4
Sparsely vegetated playa Herbaceous Alliance, Sparsely vegetated playa / herbaceous Association	0.00	0.00	0.00	0.01	0.01	
Red brome or Mediterranean grass grasslands (Bromus rubens-Schismus (arabicus, barbatus)) Semi-natural Herbaceous Stands Herbaceous Alliance[4,6]	0.00	0.00	0.00	0.68	0.68	
Wire Lettuce - Brittle Spineflower Lava Flows (Stephanomeria pauciflora - Chorizanthe brevicornu) Lava Fields Provisional Alliance	1.68	0.00	0.00	0.00	1.68	S4
Yerba mansa - Nutall's sunflower - Nevada goldenrod alkaline wet meadows (Anemopsis californica - Helianthus nuttallii - Solidago spectabilis) Herbaceous Alliance, (Anemopsis californica) Provisional Association	0.19	0.00	0.00	0.00	0.19	S2
SUB TOTAL VEGETATION	481.71	372.44	117.33	141.90	1,113.38	
Other Land Use or Cover						
Active Agriculture	4.57	0.00	0.00	0.00	4.57	
Barren[6]	0.00	0.49	0.53	2.46	3.48	
Disturbed[6]	3.88	11.56	0.34	1.21	17.00	
Developed	56.42	61.27	34.22	23.50	175.40	
Ornamental/Landscaped	3.15	0.00	0.00	0.00	3.15	
Unvegetated Wash or River Bottom	0.00	0.00	0.10	0.78	0.89	
TOTAL	549.73	445.76	152.52	169.85	1,317.86	

NOTES: For Mitigation Measure BIO-1d (Compensation for habitat loss)
1: Joshua Tree Woodland (6.65 acres)
2: Riparian Thickets and Forests (3.22 acres)
3: Sensitive Natural Communities (S1-S3) (163.77 acres)
4: Desert Scrub (suitable for desert tortoise) (973.48 acres)
5: Desert Scrub (marginal for desert tortoise) (63.05 acres)
6: Western burrowing owl (suitable) (902.84 acres)
7: Western burrowing owl (marginal) (84.46 acres)

Table 4-3. Western Joshua Tree in Survey Area

	Number of Joshua Trees				
Western Joshua Trees	**Segment 1**	**Segment 2**	**Segment 3N**	**Segment 3S**	**Total**
Total Survey Area	5,823	0	179	4	6,006
Dead					
Branched	34	0	89	0	123
Not Branched	143	0	36	0	179
Live					
Branched	964	0	30	4	998
Not Branched	4,682	0	24	0	4,706

Table 4-4. Disturbance Acres: Critical Habitat and Conservation Areas

	Segment Acres of Disturbance				
Species	**1**	**2**	**3N**	**3S**	**TOTAL**
USFWS Desert Tortoise Critical Habitat (CH)	0.00	100.63	79.55	70.62	250.80
BLM Mohave Ground Squirrel (MGS) Conservation Area	34.17	255.44	98.31	68.35	456.27

Table 4-5. Disturbance Acres: Jurisdictional Waters

	Segment Acres of Disturbance				
Jurisdictional Feature	**1[1]**	**2**	**3N[2]**	**3S[2]**	**TOTAL[3]**
USACE/RWQCB Jurisdiction					
Other Waters	1.12	1.66	0.95	2.70	6.43
Wetlands	21.74	0.00	0.00	0.00	21.74
CDFW Jurisdiction					
Other Waters	2.31	3.44	2.18	3.77	11.70
Wetlands	21.74	0.00	0.00	0.00	21.74

1: Wetland habitats that occur in Segment 1 include emergent freshwater wetlands, scrub-shrub wetlands, and forested/woodland wetlands.
2: Potentially jurisdictional waters in Segments 3N and 3S are classified as non-vegetated rivers, streams, and washes, consisting of ephemeral dry washes that carry water for short periods of time as the result of seasonal precipitation. There are no major surface waters in Segments 3N and 3S.
3: Total acres of jurisdiction subject to updated jurisdictional delineation

ALTERNATIVES

Table 4-6. Disturbance Acres: Alternatives Vegetation Communities

a. Crater Mountain Realignment Alternative

Vegetation Community	Acres of Disturbance		CDFW Sensitive
	Segment 1 (Proposed Structure 171 to 279C)	Crater Mountain Realignment Alternative	
Actons and Virgin River brittle brush - Net-veined goldeneye scrub (Encelia (actonii, virginensis) - Viguiera reticulata) Shrubland Alliance, Encelia actoni Association	0.00	0.0001	S3
Alkali sacaton grassland (Sporobolus airoides) Herbaceous Alliance	1.05	0.72	S2.2
Allscale scrub (Atriplex polycarpa) Shrubland Alliance	13.26	6.67	S4
Baltic and Mexican rush marshes (Juncus arcticus (var. balticus, mexicanus)) Herbaceous Alliance	0.36	0.36	S4
Barren	0.03	0.03	
Big sagebrush (Artemisia tridentata) Shrubland Alliance	1.48	1.34	
Big sagebrush (Artemisia tridentata) Shrubland Alliance, (Artemisia tridentata – Ericameria nauseosa) Association	0.00	13.94	
Big sagebrush (Artemisia tridentata) Shrubland Alliance, (Artemisia tridentata / Distichlis spicata) Association	0.00	4.10	S3
Big sagebrush (Artemisia tridentata) Shrubland Alliance, Ericameria nauseosa / Bromus tectorum) Association	3.31	3.31	
Black willow thickets (Salix gooddingii) Woodland Alliance	0.09	0.09	S3
California buckwheat - Parish's goldeneye scrub (Eriogonum fasciculatum - Viguiera parishii) Shrubland Alliance, (Eriogonum fasciculatum rock outcrop) Association	0.00	0.29	S4
California buckwheat scrub (Eriogonum fasciculatum) Shrubland Alliance	0.00	1.25	S5
Cheatgrass - medusahead grassland (Bromus tectorum - Taeniatherum caput-medusae Semi-natural Herbaceous Stands) Alliance, (Bromus tectorum) Association	3.23	1.54	
Cheesebush - sweetbush scrub (Ambrosia salsola - Bebbia juncea) Shrubland Alliance, (Ambrosia salsola) Association	0.95	4.37	S4
Cheesebush - sweetbush scrub (Ambrosia salsola - Bebbia juncea) Shrubland Alliance, (Stephanomeria pauciflora) Provisional Association	2.07	2.52	S4
Common reed marshes (Phragmites australis) Herbaceous Alliance	0.05	0.05	
Developed	8.99	9.04	
Disturbed	3.95	3.95	
Fourwing saltbush scrub (Atriplex canescens) Shrubland Alliance	4.82	13.98	S4
Fremont cottonwood forest and woodland (Populus fremontii – Fraxinus velutina – Salix gooddingii) Woodland Alliance, (Populus fremontii / Salix exigua) Association	0.00	0.004	S3
Fremont's smokebush – Nevada smokebush scrub (Psorothamnus fremontii - Psorothamnus polydenius) Shrubland Alliance, (Psorothamnus arborescens) Provisional Association	8.51	15.10	S3

Vegetation Community	Acres of Disturbance		CDFW Sensitive
	Segment 1 (Proposed Structure 171 to 279C)	Crater Mountain Realignment Alternative	
Fremont's smokebush – Nevada smokebush scrub (Psorothamnus fremontii - Psorothamnus polydenius) Shrubland Alliance, (Psorothamnus arborescens – Atriplex confertifolia – Tetradymia spp.) Association	0.00	0.24	S3
Fremont's smokebush – Nevada smokebush scrub (Psorothamnus fremontii - Psorothamnus polydenius) Shrubland Alliance, (Psorothamnus polydenius – (Psorothamnus arborescens)) Association	0.00	13.75	S3
Greasewood scrub (Sarcobatus vermiculatus) Shrubland Alliance	8.03	4.88	
Greasewood scrub (Sarcobatus vermiculatus) Shrubland Alliance, (Sarcobatus vermiculatus – Atriplex confertifolia – (Picrothamnus desertorum, Suaeda moquinii)) Association	0.00	4.55	S3S4
Greasewood scrub (Sarcobatus vermiculatus) Shrubland Alliance, (Sarcobatus vermiculatus / Sporobolus airoides) Association	0.00	1.56	S3S4
Greasewood scrub (Sarcobatus vermiculatus) Shrubland Alliance, (Sarcobatus vermiculatus) Sparse Playa Provisional Association	0.72	0.68	S3S4
Hardstem bulrush marsh (Schoenoplectus acutus) Herbaceous Alliance	0.01	0.01	S3
Needleleaf rabbitbrush scrub (Ericameria teretifolia) Shrubland Alliance, (Ericameria teretifolia) Association	0.47	0.47	
Nevada joint fir - Anderson's boxthorn - spiny hop sage scrub (Ephedra nevadensis - Lycium andersonii - Grayia spinosa) Shrubland Alliance	4.70	3.79	S3S4
Nevada joint fir - Anderson's boxthorn - spiny hop sage scrub (Ephedra nevadensis - Lycium andersonii - Grayia spinosa) Shrubland Alliance, (Ephedra nevadensis – Ericameria cooperi) Association	0.00	2.04	S3S4
Nevada joint fir - Anderson's boxthorn - spiny hop sage scrub (Ephedra nevadensis - Lycium andersonii - Grayia spinosa) Shrubland Alliance, (Ephedra nevadensis – Ericameria teretifolia) Association	3.40	3.07	S3S4
Open Water	0.02	0.02	
Quailbush scrub (Atriplex lentiformis) Shrubland Alliance, (Atriplex lentiformis/Sporobolus airoides) Provisional Association	0.42	0.42	S4
Quailbush scrub (Atriplex lentiformis) Shrubland Alliance, (Atriplex torreyi / Distichlis spicata – Sporobolus airoides) Provisional Association	0.00	0.53	S4
Quailbush scrub (Atriplex lentiformis) Shrubland Alliance, (Atriplex torreyi) Association	4.18	3.64	S4
Rigid spineflower - hairy desert sunflower (Chorizanthe rigida - Geraea canescens) Desert Pavement Sparsely Vegetated Alliance, (Chorizanthe brevicornu – Stephanomeria pauciflora) Provisional Association	0.71	3.93	S4
Rubber rabbitbrush scrub (Ericameria nauseosa) Shrubland Alliance	4.40	4.21	S5
Russianthistle - dyers woad - fivehook bassia fields (Salsola tragus - Isitis - Bassia sp.) Herbaceous Semi-Natural Alliance	1.04	1.04	
Salt grass flats (Distichlis spicata) Herbaceous Alliance	0.52	0.39	S4

Vegetation Community	Acres of Disturbance: Segment 1 (Proposed Structure 171 to 279C)	Acres of Disturbance: Crater Mountain Realignment Alternative	CDFW Sensitive
Salt grass flats (Distichlis spicata) Herbaceous Alliance, (Distichlis spicata - Sporobolus airoidesl) Provisional Association	0.35	0.24	S4
Sandbar willow thickets (Salix exigua) Shrubland Alliance	0.04	0.04	S4.2
Shadscale scrub (Atriplex confertifolia) Shrubland Alliance	15.08	13.23	S4.2
Smokebush desert wash scrub (Psorothamnus (fremontii, polydenius)) Provisional Shrubland Alliance	6.20	5.07	S3
Spinescale scrub (Atriplex spinifera) Shrubland Alliance	2.60	2.06	S4.2
Water birch thicket (Betula occidentalis) Shrubland Alliance	0.06	0.06	S3
Wire Lettuce - Brittle Spineflower Lava Flows (Stephanomeria pauciflora - Chorizanthe brevicornu) Lava Fields Provisional Alliance	1.22	1.20	S4
Yerba mansa - Nutall's sunflower - Nevada goldenrod alkaline wet meadows (Anemopsis californica - Helianthus nuttallii - Solidago spectabilis) Herbaceous Alliance, (Anemopsis californica) Provisional Association	0.01	0.01	S2
TOTAL	**106.30**	**153.76**	

b. Manzanar Realignment Alternative

Vegetation Community	Acres of Disturbance: Segment 1 (Proposed Structure 279C to 527)	Acres of Disturbance: Manzanar Realignment Alternative	CDFW Sensitive
Active Agriculture	0.67	0.67	
Alkali sacaton - scratchgrass - alkali cordgrass alkaline wet meadow (Sporobolus airoides – Muhlenbergia asperifolia – Spartina gracilis) Herbaceous Alliance, Sporobolus airoides – Distichlis spicata Association	0.00	1.89	S2
Alkali sacaton grassland (Sporobolus airoides) Herbaceous Alliance	9.64	6.58	S2.2
Allscale scrub (Atriplex polycarpa) Shrubland Alliance	3.93	2.48	S4
Allscale scrub (Atriplex polycarpa) Shrubland Alliance, (Atriplex polycarpa) Sparse Playa Association	0.00	1.02	
Allscale scrub (Atriplex polycarpa) Shrubland Alliance, Atriplex polycarpa Association	5.57	6.03	
Baltic and Mexican rush marshes (Juncus arcticus (var. balticus, mexicanus)) Herbaceous Alliance	11.46	7.37	S4
Barren	0.00	0.04	
Basket bush - river hawthorn - desert olive patches (Rhus trilobata - Crataegus rivularis - Forestiera pubescens) Shrubland Alliance, (Forestiera pubescens) Provisional Association	0.0001	0.0001	S1S2
Big sagebrush (Artemisia tridentata) Shrubland Alliance	2.59	1.84	
Big sagebrush (Artemisia tridentata) Shrubland Alliance, (Artemisia tridentata – Ericameria nauseosa) Association	0.00	0.93	
Black willow thickets (Salix gooddingii) Woodland Alliance	0.000003	0.000003	S3
Bush seepweed scrub (Suaeda moquinii) Shrubland Alliance	0.20	0.57	S3

Vegetation Community	Acres of Disturbance: Segment 1 (Proposed Structure 279C to 527)	Acres of Disturbance: Manzanar Realignment Alternative	CDFW Sensitive
Cattail marshes (Typha (angustifolia, domingensis, latifolia)) Herbaceous Alliance	0.15	0.15	
Common and giant reed marshes (Phragmites australis – Arundo donax) Herbaceous Semi-Natural Alliance, (Phragmites australis) Western Ruderal Association	0.00	0.04	
Developed	28.65	26.07	
Disturbed	1.56	1.56	
Fourwing saltbush scrub (Atriplex canescens) Shrubland Alliance	0.40	0.91	S4
Fremont's smokebush – Nevada smokebush scrub (Psorothamnus fremontii - Psorothamnus polydenius) Shrubland Alliance, (Psorothamnus arborescens – Atriplex confertifolia – Tetradymia spp.) Association	0.00	2.83	S3
Fremont's smokebush – Nevada smokebush scrub (Psorothamnus fremontii - Psorothamnus polydenius) Shrubland Alliance, (Psorothamnus arborescens) Provisional Association	0.78	0.59	S3
Goodding's willow – red willow riparian woodland and forest (Salix gooddingii - Salix laevigata) Woodland Alliance, (Salix gooddingii) Association	0.00	0.30	S3
Greasewood scrub (Sarcobatus vermiculatus) Shrubland Alliance	28.91	22.38	S3S4
Greasewood scrub (Sarcobatus vermiculatus) Shrubland Alliance, (Sarcobatus vermiculatus – Atriplex confertifolia – (Picrothamnus desertorum, Suaeda moquinii)) Association	1.11	9.75	S3S4
Greasewood scrub (Sarcobatus vermiculatus) Shrubland Alliance, (Sarcobatus vermiculatus – Suaeda moquinii) Association	0.00	47.52	S3S4
Greasewood scrub (Sarcobatus vermiculatus) Shrubland Alliance, (Sarcobatus vermiculatus / Distichlis spicata) Association	0.00	6.14	S3S4
Greasewood scrub (Sarcobatus vermiculatus) Shrubland Alliance, (Sarcobatus vermiculatus / Sporobolus airoides) Association	0.12	0.83	S3S4
Greasewood scrub (Sarcobatus vermiculatus) Shrubland Alliance, (Sarcobatus vermiculatus) Association	1.35	15.50	S3S4
Hardstem and California bulrush marshes (Schoenoplectus (acutus, californicus)) Herbaceous Alliance, (Schoenoplectus (acutus, californicus) – Typha (angustifolia, latifolia)) Association	0.00	0.03	S3S4
Iodine bush scrub (Allenrolfea occidentalis) Shrubland Alliance, (Allenrolfea occidentalis / Distichlis spicata) Association	0.00	0.09	S3
Mesquite thickets (Prosopis glandulosa - Prosopis velutina - Prosopis pubescens) Woodland Alliance, (Prosopis pubescens [glandulosa] / (Atriplex spp. – Suaeda moquinii)) Association	0.00	0.24	S3
Nevada joint fir - Anderson's boxthorn - spiny hop sage scrub (Ephedra nevadensis - Lycium andersonii - Grayia spinosa) Shrubland Alliance	0.90	0.67	S3S4
Open Water	1.25	1.25	

Vegetation Community	Acres of Disturbance: Segment 1 (Proposed Structure 279C to 527)	Acres of Disturbance: Manzanar Realignment Alternative	CDFW Sensitive
Ornamental/Landscaped	0.02	0.02	
Quailbush scrub (Atriplex lentiformis) Shrubland Alliance, (Atriplex torreyi / Distichlis spicata – Sporobolus airoides) Provisional Association	0.38	2.87	S4
Quailbush scrub (Atriplex lentiformis) Shrubland Alliance, (Atriplex torreyi) Association	28.20	22.46	S4
Rubber rabbitbrush scrub (Ericameria nauseosa) Shrubland Alliance	25.57	19.92	
Rubber rabbitbrush scrub (Ericameria nauseosa) Shrubland Alliance, (Ericameria nauseosa – Atriplex torreyi) Association	0.00	0.06	S5
Rubber rabbitbrush scrub (Ericameria nauseosa) Shrubland Alliance, (Ericameria nauseosa / Sporobolus airoides) Association	0.00	1.59	S5
Russianthistle - dyers woad - fivehook bassia fields (Salsola tragus - Isitis - Bassia sp.) Herbaceous Semi-Natural Alliance	2.67	2.67	
Salt grass flats (Distichlis spicata) Herbaceous Alliance	4.12	3.37	S4
Salt grass flats (Distichlis spicata) Herbaceous Alliance, (Sarcobatus vermiculatus) Association	0.00	1.28	S4
Sandbar willow thickets (Salix exigua) Shrubland Alliance	0.67	0.62	S2
Shadscale scrub (Atriplex confertifolia) Shrubland Alliance	36.67	37.37	S4
Smokebush desert wash scrub (Psorothamnus (fremontii, polydenius)) Provisional Shrubland Alliance	2.55	0.65	S3
Spinescale scrub (Atriplex spinifera) Shrubland Alliance	6.57	5.27	S4.2
Tamarisk thickets (Tamarix spp. Semi-natural Shrubland Stands) Shrubland Alliance	9.14	17.79	
White bursage scrub (Ambrosia dumosa) Shrubland Alliance	2.04	21.81	S5
TOTAL	**218.59**	**304.02**	

c. Fossil Falls Realignment Alternative

Vegetation Community	Acres of Disturbance: Segment 1 (Proposed Structure 815 to 936)	Acres of Disturbance: Fossil Falls Realignment Alternative	CDFW Sensitive
Actons and Virgin River brittle brush - Net-veined goldeneye scrub (Encelia (actonii, virginensis) - Viguiera reticulata) Shrubland Alliance, Encelia actoni Association	0.00	0.05	S3
Allscale scrub (Atriplex polycarpa) Shrubland Alliance	18.69	19.94	S4
Allscale scrub (Atriplex polycarpa) Shrubland Alliance, (Atriplex polycarpa- Ambrosia salsola) Association	3.06	2.37	S4
Allscale scrub (Atriplex polycarpa) Shrubland Alliance, (Atriplex polycarpa) Sparse Playa Association	10.08	6.65	S4
Allscale scrub (Atriplex polycarpa) Shrubland Alliance, Atriplex polycarpa Association	4.88	17.27	
Cattail marshes (Typha (angustifolia, domingensis, latifolia)) Herbaceous Alliance, (Typha angustifolia – Distichlis spicata) Association	0.48	0.48	

Vegetation Community	Acres of Disturbance		CDFW Sensitive
	Segment 1 (Proposed Structure 815 to 936)	Fossil Falls Realignment Alternative	
Cheesebush - sweetbush scrub (Ambrosia salsola - Bebbia juncea) Shrubland Alliance, (Ambrosia salsola – Atriplex confertifolia) Association	0.63	0.56	S4
Cheesebush - sweetbush scrub (Ambrosia salsola - Bebbia juncea) Shrubland Alliance, (Ambrosia salsola – Larrea tridentata) Association	0.00	0.36	
Cheesebush - sweetbush scrub (Ambrosia salsola - Bebbia juncea) Shrubland Alliance, (Ambrosia salsola) Association	0.17	0.15	S4
Creosote bush - white bursage scrub (Larrea tridentata-Ambrosia dumosa) Shrubland Alliance	25.31	18.90	
Creosote bush scrub (Larrea tridentata) Shrubland Alliance	1.40	1.35	
Creosote bush scrub (Larrea tridentata) Shrubland Alliance, (Larrea tridentata – Atriplex polycarpa) Association	3.56	3.03	
Creosote bush scrub (Larrea tridentata-Ambrosia dumosa) Shrubland Alliance, (Larrea tridentata – Ambrosia dumosa – Atriplex polycarpa) Association	1.50	32.92	
Creosote bush scrub (Larrea tridentata-Ambrosia dumosa) Shrubland Alliance, (Larrea tridentata – Ambrosia dumosa – Ericameria cooperi) Association	0.00	13.97	
Creosote bush scrub (Larrea tridentata-Ambrosia dumosa) Shrubland Alliance, (Larrea tridentata - Ambrosia dumosa - Psorothamnus (arborescens, fremontii)) Association	0.00	2.65	S5
Creosote bush scrub (Larrea tridentata-Ambrosia dumosa) Shrubland Alliance, (Larrea tridentata - Ambrosia dumosa) Association	0.00	8.03	S5
Developed	12.12	12.66	
Fiddleneck - Phacelia Fields (Amsinckia (menziesii, tessellata) - Phacelia spp.) Herbaceous Alliance, (Amsinckia tessellata – Erodium cicutarium) Association	0.00	3.89	S5
Fourwing saltbush scrub (Atriplex canescens) Shrubland Alliance	3.87	2.64	S4
Joshua tree woodland (Yucca brevifolia) Woodland Forest Woodland Alliance, Yucca brevifolia / Larrea tridentata - Ambrosia dumosa Association	0.00	2.97	S3
Joshua tree woodland (Yucca brevifolia) Woodland Alliance	1.68	1.00	S3
Open Water	0.11	0.11	
Quailbush scrub (Atriplex lentiformis) Shrubland Alliance, (Atriplex torreyi) Association	1.88	1.81	S4
Salt grass flats (Distichlis spicata) Herbaceous Alliance	0.77	0.58	S4
White bursage scrub (Ambrosia dumosa) Shrubland Alliance	14.62	29.66	S5
Yerba mansa - Nutall's sunflower - Nevada goldenrod alkaline wet meadows (Anemopsis californica - Helianthus nuttallii - Solidago spectabilis) Herbaceous Alliance, (Anemopsis californica) Provisional Association	0.30	0.25	S2
Yerba mansa - Nutall's sunflower - Nevada goldenrod alkaline wet meadows (Anemopsis californica - Helianthus nuttallii -Solidago spectabilis) Herbaceous Alliance, (Anemopsis californica –Juncus arcticus var. mexicanus) Association	0.20	0.20	S2
TOTAL	**105.31**	**184.44**	

Table 4-7. Disturbance Acres: Alternatives Conservation Areas

a. Fossil Falls Realignment Alternative

	Acres of Disturbance	
Species	**Segment 1 (Proposed Structure 815 to 936)**	**Fossil Falls Realignment Alternative**
BLM Mohave Ground Squirrel (MGS) Conservation Area	37.09	80.49

Table 4-8. Western Joshua Tree in Alternative Areas

a. Fossil Falls Realignment Alternative

Western Joshua Trees	**Total**
Total Survey Area	1,305
Dead	
Branched	15
Not Branched	33
Live	
Branched	230
Not Branched	1,027

Table 4-9. Disturbance Acres: Alternatives Jurisdictional Waters

a. Crater Mountain Realignment Alternative

	Acres of Disturbance	
Jurisdictional Feature	**Segment 1 (Proposed Structure 171 to 279C)**	**Crater Mountain Realignment Alternative**
USACE/RWQCB Jurisdiction		
Other Waters	0.34	1.69
Wetlands	9.60	8.25
CDFW Jurisdiction		
Other Waters	0.57	2.31
Wetlands	9.60	8.28

b. Manzanar Realignment Alternative

	Acres of Disturbance	
Jurisdictional Feature	**Segment 1 (Proposed Structure 279C to 527)**	**Manzanar Realignment Alternative**
USACE/RWQCB Jurisdiction		
Other Waters	0.84	8.20
Wetlands	26.61	23.92
CDFW Jurisdiction		
Other Waters	1.35	9.22
Wetlands	26.61	24.09

c. Fossil Falls Realignment Alternative

Jurisdictional Feature	Acres of Disturbance	
	Segment 1 (Proposed Structure 815 to 936)	Fossil Falls Realignment Alternative
USACE/RWQCB Jurisdiction		
Other Waters	0.32	0.77
Wetlands	2.80	2.06
CDFW Jurisdiction		
Other Waters	1.32	2.25
Wetlands	2.80	2.06

Appendix 5A

CULTURAL RESOURCES

List of Tables:

Table Ap.5-1. Proposed Project Cultural Resources: Segment 1 2
Table Ap.5-2. Proposed Project Cultural Resources: Segment 2 50
Table Ap.5-3. Proposed Project Cultural Resources: Segment 3N 61
Table Ap.5-4. Proposed Project Cultural Resources: Segment 3S 69
Table Ap.5-5. Built Environment Resources on Proposed Project – All Segments 74
Table Ap.5-6. Built Environment Resources on Proposed Project with Potential for Visual Impacts 124
Table Ap.5-7. Archaeological Resources on Proposed Project with Potential for Visual Impacts (All Segments) 127
Table Ap.5-8. Resources Within the Owens Valley Landscape 144
Table Ap.5-9. Archaeological Resources: Crater Mountain Realignment Alternative 145
Table Ap.5-10. Archaeological Resources: Manzanar Realignment Alternative 149
Table Ap.5-11. Archaeological Resources: Fossil Falls Realignment Alternative 158
Table Ap.5-12. Archaeological Resources on Alternative Segments with Potential for Visual Impacts 163
Table Ap.5-13. Built Environment Resources on Alternative Segments 169
Table Ap.5-14. Built Environment Resources on Alternatives with Potential for Visual Impacts 175

APPENDIX 5A: CULTURAL RESOURCES

The data presented in this appendix supports the analysis of cultural resources and tribal cultural resources in the EIR.

Cultural Resources Data for the Proposed Project

Tables Ap.5-1 through Ap.5-4 are referenced in EIR Section C.6, Cultural Resources. These tables present the details for all cultural resources identified in surveys and studies for the Proposed Project. For each of the four project segments, these tables present:

- The resource number
- Land ownership
- Resource age (precontact, historic, or Multi-component)
- Resource type (using types defined in Section 3.6)
- Site description
- CPUC eligibility determination for the California Register of Historic Resources.
- Impact description (explaining how the resource would be affected by SCE construction activities).

Tables Ap.5-5 through Ap.5-7 present data on built environment resources; each table contains information for all four project segments.

Tribal Cultural Resources Data: Owens Valley Landscape

Table Ap.5-8 presents the precontact resources within the Owens Valley Landscape, which is defined in EIR Section 3.7 (Tribal Cultural Resources).

Cultural Resources Data for the Alternatives

Tables Ap.5-9 through Ap.5-14 present resource data for the alternatives, in the format described above for the Proposed Project.

CULTURAL RESOURCES DATA FOR THE PROPOSED PROJECT

Table Ap.5-1 presents all of the cultural resources in Segment 1 (primarily Inyo County). All of the precontact resources in Segment 1 are within the Owens Valley Landscape. The precontact resources within the Owens Valley Landscape are also presented in Table Ap.5-7.

Table Ap.5-1. Proposed Project Cultural Resources: Segment 1

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-000004/CA-INY-4	LADWP	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structure and associated demolition site. Install 2 new TSP monopole structures and associated work areas (1 is located within site boundaries and 1 is within 5 m of the northwestern edge), 2 guard structures, and existing access road will be graded as needed and a segment of paved road (existing) is slated for medium improvements.
P-14-000010/CA-INY-10 (incl. P-14-000091/ CA-INY-91)	LADWP; Private	Multi-component with protohistoric artifacts	Precontact: Habitation area. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1, 2, 3 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Eligible under Criteria 1 and 2.	Remove and replace existing OH subtransmission and telecom lines. Remove 3 lattice steel structures and their associated demolition sites, 2 demolition pull sites, Install 3 new TSP multi-pole suspension structures and 1 new TSP monopole structure and associated work areas, 3 shunt removal sites, and 3 segments of existing unpaved access road to be graded and improved as needed.
P-14-000092/CA-INY-0092	LADWP	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 existing steel lattice structure and associated work area and Install 1 new TSP monopole structure to be installed 9 m south of the site.
P-14-000111/CA-INY-111	LADWP; BLM Bishop FO; Private	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1, 2, 3 and 4, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Eligible under Criteria 1 and 2.	Remove and replace existing OH subtransmission and telecom lines. Remove 3 lattice steel structures and their associated demolition sites, 2 demolition pull sites, Install 3 new TSP multi-pole suspension structures and 1 new TSP monopole structure and associated work areas, 3 shunt removal sites, and 3 segments of existing unpaved access road to be graded and improved as needed.
P-14-000182/CA-INY-182H	BLM Ridgecrest FO; Private	Multi-component with protohistoric artifacts	Precontact: Habitation Area. Historic: Refuse and discard.	Precontact: Listed. Eligible individually under Criteria 1, 3 and 4, eligible as contributor to Fossil Falls Archaeological District under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 2 lattice steel structures and their associated demolition sites. Install 2 new TSP monopole structures and associated work areas, 2 pull sites, and existing unpaved access road that will be graded and improved as needed.
P-14-000271/CA-INY-271	Private	Precontact	Precontact: Residential base.	Precontact: Eligible individually under Criteria 1, 3 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Install 1 new TSP monopole structure and associated work area. Existing unpaved access road segment that will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-000328/CA-INY-328	LADWP, BLM Bishop FO; Private	Multi-component	Precontact: Residential base. Historic: Homestead/ farm/ranch resource.	Precontact: Eligible individually under Criteria 1 and 4, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, and eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Remove and replace existing OH subtransmission and telecom lines. Remove 9 structures and associated work areas. Install 3 new TSP multi-pole structures, 3 new TSP monopole structures and associated work areas. 4 pull sites, 3 shunt removal sites, and existing access roads that will be graded and improved as needed.
P-14-000371/CA-INY-371H	BLM Bishop FO; CSLC; LADWP; Private	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1 and 4, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3, and 4, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, and eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Removal of five lattice steel structures with demolition sites, installation of one TSP multi-poles and two TSP monopoles, three structure work areas, six demolition sites, six shunt removal sites, and the unpaved access road will be graded and improved as needed.
P-14-001317/CA-INY-1317	BLM Bishop FO; CSLC; LADWP; Private	Multi-component with protohistoric artifacts	Precontact: Residential base. Historic: Homestead/ farm/ranch resource.	Precontact: Listed. Eligible individually under Criteria 1, 3 and 4, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Land-scape under Criterion 1. Historic: Ineligible individually, and eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Project components within the site boundary established by Far Western include removal of nine structures (seven of which are lattice steel) with associated demolition sites, installation of three TSP multi-poles, two TSP monopoles seven structure work areas, four pull sites, two demolition pull sites, two guard sites, two pull sites, 10 shunt removal sites, and the existing access road that is slated for heavy improvement.
P-14-001471/CA-INY-1471/ H	BLM Ridgecrest FO; Private	Multi-component	Precontact: Residential base. Historic: Mining resource, Refuse and discard.	Precontact: Eligible individually under Criteria 1 and 4, eligible as contributor to the expanded Fossil Falls Archaeological District under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components within the site boundary include removal of one lattice steel suspension structure with an associated demolition area, installation of one TSP monopole with an associated work area, two shunt removal sites, and the access road that will be graded and improved as needed.
P-14-001473/CA-INY-1473H	BLM Ridgecrest FO	Multi-component	Precontact: Bedrock milling station. Historic: Homestead/ farm/ranch resource.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	The existing subtransmission alignment line (Remove, OH), the proposed subtransmission alignment (New, OH), the proposed telecom alignment (New, OH), and an existing access road which skirts the northwestern site boundary. Although the access road may require grading or other improvements, the

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
					overhead subtransmission alignment and telecom alignment lines do not require ground disturbance within the site boundary, since there are no existing or proposed structures, or other work areas proposed in this location; the overhead project components would span the site.
P-14-001474	BLM Ridgecrest FO	Historic	Historic: Rock feature.	Historic: Ineligible.	Unpaved access road will be graded and improved as needed.
P-14-001496/CA-INY-1496	BLM Bishop FO; CSLC; Private	Precontact with historic isolate	Precontact: Temporary camp.	Precontact: Eligible individually under Criterion 4, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Existing access road intersects the site. This existing access road may require grading or other improvements.
P-14-001873/CA-INY-1873 (incl. P-14-009424, P-14-009425, P-14-009426, P-14-009427/CA-INY-7349, CA-INY-7350, CA-INY-7351, CA-INY-7352)	BLM Ridgecrest FO	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, eligible as contributor to the expanded Fossil Falls Archaeological District under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 5 existing lattice steel structures and associated demolition areas. Install 5 new LWS monopole and associated construction areas, 2 shunt removal sites, and existing access road will be graded and improved as needed.
P-14-002146	LADWP; Private	Multi-component	Precontact: Habitation area. Historic: Refuse and discard.	Precontact: Listed under Criterion 4, eligible individually under Criteria 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	No project components overlap the site boundary.
P-14-002766/CA-INY-2766 (incl. P-14-009413 (previously recorded isolated find), P-14-009506/ CA-INY-7408)	BLM Ridgecrest FO	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structure and its associated demolition site. Install 1new TSP monopole structure and associated work area, 1 shunt removal site, 2 guard structures, and existing unpaved access road will be graded and improved as needed. Proposed construction material yard is within site boundary.
P-14-003642/CA-INY-3642/ H	Private	Multi-component	Precontact: Residential Base. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1, 3 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove 1 lattice steel structure with 1 associated demolition site.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-003653	Private	Precontact	Precontact: Bedrock milling station.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Due to project redesign this site is no longer in the Direct APE/API.
P-14-003760/CA-INY-3760H	Caltrans	Multi-component	Precontact: Bedrock milling station. Historic: Homestead/ farm/ranch resource, water infrastructure resource.	Precontact: Eligible individually under Criterion 4, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Eligible individually under Criteria 1 and 4, and eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structure that is within 5 m of site boundary and associated work area. Install 1 new TSP monopole structure and associated work area, 1 pull site and one existing access road that will be graded and improved as needed.
P-14-003767/CA-INY-3767 (incl. P-14-003766/ CA-INY-3766)	LADWP; Private	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1 and 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, and eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Install 1 LWS monopole with 1 associated work area. Remove 1 lattice steel structure with 1 associated demolition site. Existing access road will be graded and improved as needed.
P-14-003772/CA-INY-3772	LADWP; Private	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, and eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Remove and replace existing OH subtransmission and telecom lines, 2 pull sites, an existing access road will be graded and improved as needed.
P-14-003775/CA-INY-3775	LADWP; Private	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard, Rock feature.	Precontact: Eligible individually under Criterion 4, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, and eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Remove and replace existing OH subtransmission and telecom lines. Remove 4 lattice steel structures and associated demolition sites. Install 1new TSP multipole structure, 1new TSP monopole structure, 1 new LWS monopole structure and associated installation work areas. 2 pull sites, 3 shunt removal sites, 1 guard structure, and existing access road will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-003777/CA-INY-3777H	LADWP; Private	Multi-component	Precontact: Temporary camp. Historic: Homestead/ farm/ranch resource.	Precontact: Eligible individually under Criterion 4, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, and eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structure and associated demolition site. Install 1 new TSP monopole structure, 2 pull sites, 1 guard structure, and existing access road will be graded and improved as needed.
P-14-003778/CA-INY-3778 (incl. P-14-009207)	LADWP	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Eligible individually under Criterion 4, and eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Remove and replace existing OH subtransmission and telecom lines. Remove two lattice steel structures with two associated demolition sites. Three structure work areas. Existing access road will be graded and improved as needed.
P-14-003826/C A-INY-3826	Private; Caltrans	Multi-component with protohistoric artifacts	Precontact: Habitation area. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 4 lattice steel structures and 1 H-frame structure and associated work areas. Install 2 new TSP monopole and 2 new TSP multipole structures and associated work areas. 5 pull sites, 6 shunt removal sites, and existing access roads that will be graded and improved as needed.
P-14-004773/CA-INY-4773H	BLM Bishop FO; Private; LADWP	Multi-component with protohistoric artifacts	Precontact: Residential base. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 structure and associated work area. Install 1 new TSP monopole structure and associated work area. Work areas for adjacent structures to be removed and replaced within site boundary, 1 pull site and existing access roads segments that will be graded and improved as needed.
P-14-004786/CA-INY-4786	BLM Bishop FO	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components within the site boundary include installation of one new TSP monopole with an associated work area, one pull site, and one demolition site, and the existing access road that will be graded and improved as needed. A second access road abuts the southwestern portion of the updated site boundary.
P-14-005023	LADWP; Private	Historic	Historic: Military resource.	Historic: Eligible individually under Criterion 1, 2, and 4	Structure work area and existing access road will be graded and improved as needed. A TSP multipole will be installed within 12 m of the site boundary.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-005649/CA-INY-5296H (incl. P-14-009229, P-14-009230, P-14-011686/ CA-INY-7215, CA-INY-7216, CA-INY-8999)	LADWP; SCE; Private	Multi-component	Precontact: Lithic concentration. Historic: Electrical infrastructure resource, exploration and transportation resource, homestead/ farm/ranch resource.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Eligible individually under Criterion 4.	Remove and replace existing OH subtransmission and telecom lines. Remove 11 lattice steel structures and 1 H-frame structures and associated work areas. Install 10 new structures (1 TSP multi-pole structure, 2 TSP monopole structures and 7 LWS monopole structures) and associated work areas, 6 pull sites, 1 splice site, 4 shunt removal sites, 3 guard structures, and 2 existing access roads that will be graded and improved as needed.
P-14-005703 (incl. P-14-000602, P-14-006021, P-14-007354, P-14-009309, P-14-009310/CA-INY-602, CA-INY-6021, CA-INY-6263, CA-INY-72, CA-INY-7263H)	CSLC; California Dept of Fish and Wildlife; Private	Multi-component	Precontact: Multi-class artifact concentration, Bedrock milling station. Historic: Exploration and transportation resource, Refuse and discard.	Precontact: Listed under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Listed under Criterion 4, and eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Project components within the site boundary include, removal of three lattice steel structures with associated work areas, installation of three new TSP structures with associated work areas, one shunt removal site, the existing access road that will be graded and improved as needed, and one overland access route.
P-14-006811/CA-INY-5815	LADWP	Precontact	Precontact: Residential base.	Precontact: Eligible individually under Criteria 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structure and associated demolition site. Install 1 new TSP monopole structure and associated work area. Existing access road will be graded and improved as needed.
P-14-006995	BLM Ridgecrest FO; Private	Historic	Historic: Refuse and discard.	Historic: Eligible under Criterion 1, 2, and 4.	Existing access road will be graded and improved as needed.
P-14-007356	Private	Multi-component	Precontact: Multi-class artifact concentration. Historic: Exploration and transportation resource, Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Eligible under Criterion 4.	Proposed construction material yard, CH SA 1-20 US-395, construction area encompasses entire site. Yard has been moved.
P-14-008282/CA-INY-6600H	BLM Bishop FO; CSLC, Lands Division; Private	Precontact with historic isolate	Precontact: Multi-class artifact concentration.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove 1 lattice steel structure and associated demolition site. Install 1 new LWS monopole and associated work area. Existing access road will be graded and improved, as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-008723/CA-INY-6842	LADWP	Multi-component	Precontact: Quarry. Historic: Refuse and discard, Rock feature.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 6 lattice steel structures and associated work areas; Install 6 new structures (5 LWS monopoles and 1 new TSP monopole 25 m southeast of the site) and associated construction areas; 4 pull sites, 1 splice site, 6 shunt removal sites, 2 guard structures, and existing access road will be graded and improved as needed.
P-14-008772	BLM Bishop FO; Private	Historic	Historic: Refuse and discard.	Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Removal of two lattice steel structures with associated work areas, installation of one TSP monopole with an associated work area, and existing access road will be graded and improved as needed.
P-14-008773	BLM Bishop FO; Private	Multi-component	Precontact: Lithic concentration. Historic: Electrical infrastructure resource.	Precontact: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Project components within the site boundary consist of the removal of two lattice steel structures with associated work areas, installation of one TSP monopole with an associated work area, and the existing access road that will be graded and improved as needed.
P-14-008819/CA-INY-6931	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	One demolition area for the removal of a lattice steel suspension structure, one structure work area for the installation of new TSP monopole suspension structure, an additional demolition area associated with the removal of two suspension structures 5 to 15 m northeast of the site, the existing subtransmission alignment (Remove, OH), the proposed subtransmission alignment (New, OH), the proposed telecommunications alignment (Overhead, New), one shunt removal site, and two existing access roads that will be graded and improved as needed.
P-14-008820/CA-INY-6932	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard, Rock feature.	Precontact: Ineligible individually, eligible as contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Removal of one lattice steel suspension structure and installation of one new TSP monopole suspension structure with associated work area, and portions of three existing access roads will be graded and improved as needed.
P-14-008821/CA-INY-6933	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Two work areas associated with structures outside of the site boundary (one removal and one installation) and the existing access road will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-008822/CA-INY-6934	BLM Ridgecrest FO	Multi-component	Precontact: Bedrock milling station. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components within the site boundary consist of work areas associated with the removal of one lattice steel structure and installation of one new TSP multipole located approximately 10m northeast of the site boundary, and the existing access roads that will be graded and improved as needed.
P-14-008824/CA-INY-6936	LADWP; Private	Multi-component	Precontact: Lithic concentration. Historic: Exploration and transportation resource, Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Eligible individually under Criterion 4.	Remove and replace existing OH subtransmission and telecom lines. Remove 4 existing lattice steel structures and work areas; Install 3 new LWS monopoles and associated work areas; 2 shunt removal sites and existing access roads that will be graded and improved as needed.
P-14-008826 (incl. P-14-009335)	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components within the site boundary include removal of one lattice steel structure and associated demolition area, installation of one new LWS monopole structure and its associated work area, two shunt removal sites, and an existing access road that will be graded and improved as needed.
P-14-008844	BLM Ridgecrest FO; Private; LADWP	Historic	Historic: Electrical infrastructure resource.	Historic: Eligible under Criterion 1.	No project components are proposed within the archaeological component.
P-14-008848 (incl. P-14-009362)	BLM Ridgecrest FO; LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Removal of one lattice steel structure with an associated work area, installation of one new LWS monopole (immediately southwest of the site boundary) with an associated work area, one new guard site, and existing access road will be graded and improved as needed.
P-14-009214/CA-INY-7210	LADWP; Private	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Project components within the site boundary consist of the removal of one lattice steel suspension structure with an associated work area, installation of one new TSP monopole suspension structure with an associated work area, and the existing unpaved access road that will be graded and improved as needed.
P-14-009216	LADWP	Precontact	Precontact: Residential base.	Precontact: Eligible individually under Criteria 1 and 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structure and associated work area; Install 1 new TSP multipole and associated work areas; 4 pull sites; 4 shunt removal sites; and existing access road will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-009217	BLM Ridgecrest FO	Precontact with historic isolate	Precontact: Bedrock milling station.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	The only project component within the site boundary is a work area associated with a new structure installation (the structure is located outside of the site boundary). .
P-14-009219/CA-INY-7211	LADWP	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, and eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3, and 4.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 steel lattice structure and associated work area; Install 1 new monopole TSP structure and work area, and an existing access road will be graded and improved as needed.
P-14-009227	Private; LADWP; SCE	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components within the site boundary consist of the removal of one lattice steel structure with an associated work area and installation of one new LWS monopole with an associated work area, both located in the northwestern quadrant of the site.
P-14-009228/CA-INY-7214	Private; SCE	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines, remove 1 lattice steel structure with work area, install 1 TSP monopole with work area, 1 shunt removal site, 1 guard site, and 2 pull sites.
P-14-009232	LADWP	Precontact with historic isolate	Precontact: Residential base.	Precontact: Eligible individually under Criteria 1 and 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Removal of 1 lattice steel structure and associated demolition area, an additional demolition area associated with H-frame structure to be removed 15-20 m west of the site. Install 1 new LWS multipole 25 m west of the site and associated work area within site boundary, and existing access roads that will be graded and improved as needed.
P-14-009235/CA-INY-7218	LADWP	Multi-component	Precontact: Residential base. Historic: Exploration and transportation resource.	Precontact: Eligible individually under Criteria 1 and 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, and eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Remove and replace existing OH subtransmission and telecom lines. Remove four existing structures and associated work areas. Install one new TSP monopole and associated construction area. Two pull sites, three shunt removal sites. Existing access roads will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-009236/CA-INY-7219	LADWP	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Project components within the site boundary consist of the removal of one lattice steel structure with an associated demolition area, the work area for one new LWS monopole to be installed 5 m southwest of the site, and the unpaved access road that will be graded and improved as needed.
P-14-009239/CA-INY-7221 (incl. P-14-009238/ CA-INY-7220)	LADWP	Precontact with historic isolate	Precontact: Multi-class artifact concentration.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 existing lattice steel structure and associated demolition site; Install 1 new LWS monopole on southern boundary of the site, associated work area within site boundary. Existing access road will be graded and improved as needed.
P-14-009240/CA-INY-7222	LADWP	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, and eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3, and 4.	Remove and replace existing OH subtransmission and telecom lines. Removal of 1 lattice steel structure adjacent to the southeastern site boundary and its associated demolition area, installation of 2 LWS monopoles (1 within the site; 1 located 15 m north of site) and associated work areas; 2 shunt removal sites; and existing access road will be graded and improved as needed.
P-14-009242/CA-INY-7223	LADWP	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard, Water infrastructure resource.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, and eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3, and 4.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structure and associated demolition site; Install 1 new LWS monopole and associated work area, and existing access road will be graded and improved as needed.
P-14-009243/CA-INY-7224	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission line, 1 work area for new TSP monopole outside site boundary, removal 1 lattice steel structure with work area, and existing access road will be graded an improved as needed.
P-14-009245/CA-INY-7226	LADWP	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 2 lattice steel structures and work areas; Install 2 new LWS monopole structures and work areas; 2 shunt removal areas, 2 guard structures, and existing access road will be improved.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
				Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	
P-14-009248/CA-INY-7229	LADWP	Precontact	Precontact: Quarry.	Precontact: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structure and associated demolition site; Install 1 new TSP multipole structure and associated structure work area; 2 pull sites, and existing access road will be improved.
P-14-009249/CA-INY-7230	LADWP	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard, Water infrastructure resource.	Precontact: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, and eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3, and 4.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structure and associated demolition site, 2 guard structures, 1 shunt removal site, 1 pull site, and existing access road will be graded and improved as needed.
P-14-009250/CA-INY-7231 (incl. P-14-009251/ CA-INY-7232)	BLM Bishop FO; LADWP	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1 and 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, and eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3, and 4.	Remove and replace existing OH subtransmission and telecom lines. Remove 2 lattice steel structures and associated work areas. Install 1 new TSP monopole structures and 1 LWS monopole and associated construction areas, 2 shunt removal sites, 1 demolition site associated with H-frame structure to be removed 5 m from the northern boundary, and existing access road will be graded and improved as needed.
P-14-009252/CA-INY-7233	BLM Bishop FO	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, and eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3, and 4.	Remove and replace existing OH subtransmission line, install 1 OH telecom line, remove 1 lattice steel structure with work area, install 1 new LWS monopole structure with work area, and existing access road will be graded and improved as needed.
P-14-009254/CA-INY-7235	CSLC	Precontact with historic isolate	Precontact: Multi-class artifact concentration.	Precontact: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Removal of 1 lattice steel structure within the site and installation of a 1 new TSP monopole 15 m southeast of the site. Associated demolition and construction areas within site boundary.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-009259/CA-INY-7237 (incl. P-14-009260/ CA-INY-7238)	BLM Bishop FO	Multi-component	Precontact: Bedrock milling station. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Removal of 2 lattice steel structure and associated work areas, and installation of 2 new LWP monopole. Associated demolition and construction areas within site boundary. Existing access road will be graded and improved as needed.
P-14-009272/CA-INY-7241	BLM Bishop FO	Historic with Precontact isolate	Historic: Refuse and discard.	Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Removal of one lattice steel structure with an associated work area, installation of one new LWS monopole with an associated work area, and existing access road will be graded and improved as needed.
P-14-009277/CA-INY-7243	BLM Bishop FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Project components within the site boundary include the removal of two lattice steel structures (and their associated demolition sites), installation of one TSP multipole, their work areas, four pull sites, three shunt removal sites, and access roads that will be graded and improved as needed; a third demolition site overlaps the southern site boundary, for two existing structures to be removed outside of the site boundary. These proposed project components would involve ground disturbance within the site boundary.
P-14-009278/CA-INY-7244	BLM Bishop FO	Unknown	Unknown: Rock feature.	If precontact: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. If historic: Ineligible individually, and eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	The site is within the Direct APE/API; however, the site has been avoided through project redesign, such that no project components intersect the site boundary.
P-14-009279	BLM Bishop FO	Historic	Historic: Refuse and discard.	Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Removal of a lattice steel suspension structure with an associated work area, installation of one new TSP monopole structure with an associated work area, and three existing access roads will be graded and improved as needed.
P-14-009282	BLM Bishop FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard, Rock feature.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components within the site boundary consist of the removal of one lattice steel structure with an associated work area, installation of one new LWS monopole with an associated work area, and one shunt removal site. Three existing access roads lie adjacent to the north, west, and south boundaries of the site, and will be graded and improved as needed.
P-14-009283/CA-INY-7249	BLM Bishop FO	Multi-component	Precontact: Bedrock milling station.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a	Project components and elements within the site boundary consist of two work areas associated with structures located outside of the site boundary, which are slated for removal.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
			Historic: Refuse and discard.	contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, and eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3, and 4.	
P-14-009288/CA-INY-7252 (incl. P-14-009289/ CA-INY-7253)	LADWP	Multi-component	Precontact: Lithic concentration. Historic: Exploration and transportation resource, Refuse and discard.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Remove and replace existing OH subtransmission and telecom lines. Two existing steel lattice structures for removal and associated demolition areas, one new structure (TSP monopole) and associated construction area, and four existing access roads that will be graded and improved as needed.
P-14-009294	BLM Bishop FO	Historic with Precontact isolate	Historic: Rock feature.	Historic: Ineligible.	Project components and elements within the site boundary consist of the removal of one lattice steel structure with an associated work area, the construction area for the installation of a TSP multipole adjacent to the site boundary, and two pull sites.
P-14-009298	BLM Bishop FO	Historic with Precontact isolate	Historic: Refuse and discard.	Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Removal of one existing lattice steel structure with an associated work area, installation of one new LWS Monopole with an associated work area, and two existing access roads will be graded and improved as needed.
P-14-009300	BLM Bishop FO	Historic with Precontact isolate	Historic: Mining resource, Refuse and discard.	Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Removal of one lattice steel tower with an associated demolition area, the work area for a new LWS monopole that is located 13 m southwest of the site boundary, one shunt removal site, one splice site, and existing access road will be graded and improved as needed.
P-14-009305/CA-INY-7259 (incl. P-14-009304, P-14-009306)	BLM Bishop FO; Private	Multi-component	Precontact: Residential base. Historic: Refuse and discard, Rock feature.	Precontact: Eligible individually under Criteria 1 and 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3, and 4.	Remove and replace existing OH subtransmission and telecom lines. Remove 3 lattice steel structures, install 2 new LWS monopole structures and associated work areas, 2 pull sites, 1 shunt site, and existing access road which will be graded and improved as needed.
P-14-009309	California Dept of Fish and Wildlife	Historic	Historic: Refuse and discard.	Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Removal of one steel suspension structure with an associated demolition area, the work area for installation of an LWS monopole 8 m east of the site

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
					boundary, one shunt removal site, and the existing access roads will be graded and improved as needed.
P-14-009310	California Dept of Fish and Wildlife; LADWP	Historic	Historic: Homestead/ farm/ranch resource.	Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Removal of one lattice steel structure and associated demolition area and installation of LWS monopole with associated work area. An existing access road will be graded and improved as needed lies 4 m to the south of the site.
P-14-009311/CA-INY-7264	Private	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Project components within the site boundary consist of removal of one lattice steel suspension structure with an associated demolition area, one structure work area for the installation of a new LWS monopole, and the existing unpaved access roads that will be graded and improved as needed.
P-14-009314	Private	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components within the site boundary consist of one demolition site associated with the removal of a lattice steel tower structure that is located 6 m southwest of the site boundary, and one work area associated with the installation of a new LWS monopole suspension structure 12 m southeast of the site.
P-14-009315/CA-IN-7267	Private; BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Project components within the site boundary consist of removal of one lattice steel structure with an associated demolition site, installation of a new LWS monopole suspension structure with an associated work area, one shunt removal site, and the existing unpaved access road that will be graded and improved as needed.
P-14-009317	Private; BLM Ridgecrest FO; LADWP	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements within the eastern portion of the site boundary consist of removal of one lattice steel suspension structure with an associated demolition site, installation of a new LWS monopole suspension structure with an associated work area, and the existing access road that will be graded and improved as needed.
P-14-009318	BLM Ridgecrest FO	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Removal of one wood pole and removal of one lattice steel suspension structure with associated demolition areas, installation of one new LWS monopole suspension structure with an associated work area, two shunt removal sites, and existing access roads will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-009319/CA-INY-7270 (incl. P-14-9320/ CA-INY-7271)	BLM Ridgecrest FO	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard, Rock feature.	Precontact: Eligible individually under Criterion 1, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, and eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3, and 4.	The western extent of the site is located within the Direct APE/API. Project components within the site boundary consist of removal of one lattice steel suspension structure with an associated demolition site, a demolition site associated with the removal of a lattice structure 10 m west of the site boundary, installation of two new monopole suspension structures (one LWS, one TSP) with associated work areas, one pull site, and the existing access road that will be graded and improved as needed.
P-14-009321	Private	Multi-component	Precontact: Multi-class artifact concentration. Historic: Homestead/ farm/ranch resource.	Precontact: Eligible individually under Criterion 1, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, and eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3, and 4.	Project components within the site boundary consist of removal of one lattice steel structure 11 m southwest of the site and an associated work area within the site boundary, the installation of one new TSP multi-pole suspension structure and work area, and two pull sites. Proposed project components would involve ground disturbance within the site boundary.
P-14-009323	Private	Historic	Historic: Homestead/ farm/ranch resource.	Historic: Ineligible.	Removal of one lattice steel suspension structure with an associated demolition site, installation of a new LWS monopole suspension structure with an associated work area, one shunt removal site, and existing unpaved access road will be graded and improved as needed.
P-14-009334/CA-INY-7279	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard, Rock feature.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements within the site boundary consist of demolition area for a lattice steel suspension structure located immediately adjacent to and outside of the southwestern site boundary, the work area for the installation of a new LWS monopole suspension structure 10 m southwest of the site, and two existing access roads that will be graded and improved as needed.
P-14-009337	BLM Ridgecrest FO; LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	The western extent of the site is located within the Direct APE/API. Overlying the extreme edge of the western site boundary: two pull sites.
P-14-009345/CA-INY-7287	LADWP	Precontact	Precontact: Temporary camp.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structure 10 m southwest of the site and install 1 new LWS monopole suspension structure 40 m south- southwest of the site. Associated work areas within site boundary. Existing access road will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-009351	LADWP	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Project components within the site boundary consist of the demolition area associated with the removal of a lattice steel suspension structure (the structure is located 4 m southwest of the resource boundary), one structure work area associated with the installation of a new TSP monopole suspension structure (the structure is located 10 m southwest of the site), two shunt removal sites, and the existing unpaved access road that will be graded and improved as needed. Proposed project components would involve ground disturbance within the site boundary.
P-14-009352/CA-INY-7291	LADWP	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components within the site boundary consist of one new LWS monopole suspension structure with associated work area, and one demolition site associated with the removal of a lattice steel suspension structure 10 m north of the site.
P-14-009357	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components within the site boundary consist of removal of one lattice steel suspension structure with an associated demolition site, installation of a new LWS monopole suspension structure with an associated work area, and the existing unpaved access road that will be graded and improved as needed.
P-14-009358/CA-INY-7295	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Homestead/ farm/ranch resource.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components within the site boundary consist of one shunt removal site, removal of a lattice steel structure with an associated demolition area, a new LWS monopole with an associated work area, and the existing access roads that will be graded and improved as needed.
P-14-009359/CA-INY-7296	BLM Ridgecrest FO	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	The western two-thirds of the site is located within the Direct APE/API. Project components within the site boundary consist of removal of one lattice steel suspension structure with an associated demolition site, the work area for the installation of a new LWS monopole suspension structure (the structure is located 6 m south of the site), and the existing access road that will be graded and improved as needed.
P-14-009366/CA-INY-7300	LADWP; BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components within the site boundary consist of removal of one lattice steel suspension structure with an associated demolition site, installation of one new LWS monopole suspension structure with an associated work area, and the existing unpaved access road that will graded and improved as needed.
P-14-009367	LADWP	Historic with Precontact isolate	Historic: Refuse and discard.	Historic: Ineligible.	Project components within the site boundary consist of the demolition site associated with the removal of a lattice steel suspension structure (the structure is located 7 m south of the site boundary), the structure work area

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
					for the installation of a new LWS monopole suspension structure (the structure is located 6 m southwest of the site boundary), and the existing unpaved access road that will be graded and improved as needed.
P-14-009368/CA-INY-7302	LADWP	Historic with Precontact isolate	Historic: Refuse and discard, water infrastructure resource.	Historic: Ineligible.	Project components within the Direct APE/API consist of the demolition area for removal of a lattice steel suspension structure 5 m southeast of the site, installation of a new LWS monopole suspension structure with an associated work area, one shunt removal site, and the existing unpaved access road that will be graded and improved as needed.
P-14-009369	LADWP	Historic	Historic: Mining resource.	Historic: Ineligible.	Removal of one wood pole and one lattice steel structure and associated demolition sites, installation of one new TSP monopole structure, two guard structures, three pull sites, and existing access road will be graded and improved as needed.
P-14-009370/CA-INY-7304	BLM Ridgecrest FO; LADWP	Multi-component	Precontact: Lithic concentration. Historic: Homestead/ farm/ranch resource.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove one lattice steel suspension structure and associated demolition site. Install one new TSP monopole suspension structure and associated work area. Remove one existing demo pull site, two new pull sites, three new guard site structures. Existing unpaved access road will be graded and improved as needed.
P-14-009371/CA-INY-7305 (incl. P-14-009372, P-14-009373/CA-INY-7306, CA-INY-7307)	BLM Ridgecrest FO; LADWP	Multi-component	Precontact: Residential base. Historic: Mining resource.	Precontact: Eligible individually under Criteria 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 2 lattice steel structures and associated demolition sites. Install 2 new TSP monopole structure, 1 new TSP multi- pole suspension structure and associated work areas, 3 pull sites, 2 shunt removal sites, and existing access roads that will be graded and improved as needed.
P-14-009374/CA-INY-7308	BLM Ridgecrest FO	Multi-component	Precontact: Bedrock milling station. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components within the site boundary consist of the demolition area associated with removal of a lattice steel suspension structure (the structure is located 12 m southeast of the site boundary), the work area associated with the installation of a new LWS monopole suspension structure (the structure is location 25 m south of the site), and an existing unpaved access road is adjacent to the southwestern corner of the site and will be graded and improved as needed.
P-14-009375/CA-INY-7309	Private	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components within the site boundary consist of the demolition area associated with the removal of one lattice steel suspension structure (structure is located 9 m southwest of the site), the work area associated with the installation of a new LWS monopole suspension structure (structure is located 19 m southwest of the site), and the existing unpaved access road that will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-009377	BLM Ridgecrest FO	Historic with Precontact isolate	Historic: Refuse and discard.	Historic: Ineligible.	Project components within site boundaries consist of removal of two lattice steel suspension structures with associated demolition areas, installation of two new LWS monopole suspension structures with associated work area, a shunt removal site, and the existing access road that will be graded and improved as needed.
P-14-009381/CA-INY-7314	BLM Ridgecrest FO	Multi-component	Precontact: Multi-class artifact concentration. Historic: Exploration and transportation resource, Water infrastructure resource.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components within the site boundary consist of removal of one lattice steel structure and associated demolition sites, installation of one new LWS monopole structure, one shunt removal site, and an existing access road that will be graded and improved as needed.
P-14-009383/CA-INY-7316	BLM Ridgecrest FO	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures and install 1 new LWS monopole and associated work areas. Existing access road will be graded and improved as needed.
P-14-009403/CA-INY-7335	BLM Ridgecrest FO	Precontact with historic isolate	Precontact: Bedrock milling station.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Project components located within the site boundary consist of the demolition area associated with removal of one lattice steel suspension structure (the structure is located 3 m northeast of the site boundary), and the installation of one new LWS monopole suspension structure with an associated work area.
P-14-009404/CA-INY-7336	BLM Ridgecrest FO	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Existing access road will be graded and improved as needed. Nearby construction, which should avoid the resource includes removal of one LS Suspension Structure and installation of 1 LWS monopole.
P-14-009407/CA-INY-7338 (incl. P-14-009408/ CA-INY-7339)	BLM Ridgecrest FO	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 2 lattice steel structures and associated demolition sites. Install 2 new LWS monopole structures and associated work areas, 1 install structure located 5 m south of site boundary; 2 shunt removal sites and existing access road will be graded and improved as needed.
P-14-009411/CA-INY-7341	BLM Ridgecrest FO	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structure 25 m south of site and install 1 new LWS monopole structure 26 m south of site, associated work areas within site boundary; 2 shunt removal sites, and existing access road that will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-009415	BLM Ridgecrest FO	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Removal of one lattice steel suspension structure with an associated demolition area, the structure work area for the installation of a new TSP multi-pole suspension structure, three shunt removal sites, and existing access road will be graded and improved as needed.
P-14-009416/CA-INY-7343	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, eligible as contributor to the expanded Fossil Falls Archaeological District under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures and install 1 new LWS monopole and associated work areas; 2 pull sites, 2 shunt removal sites, and existing access road that will be graded and improved as needed.
P-14-009421/CA-INY-7346 (incl. P-14-009422, P-14-009423/CA-INY-7347, CA-INY-7348)	BLM Ridgecrest FO	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard, Rock feature.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, and eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3, and 4.	Remove and replace existing OH subtransmission and telecom lines. Remove 3 lattice steel structures and install 3 new LWS monopole and associated work areas; 2 shunt removal sites, and existing access road will be graded and improved as needed.
P-14-009429/CA-INY-7353	BLM Ridgecrest FO; Private	Multi-component	Precontact: Lithic concentration. Historic: Mining resource, Refuse and discard.	Precontact: Eligible individually under Criterion 4, eligible as contributor to the expanded Fossil Falls Archaeological District under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 2 lattice steel structures and install 1 new LWS monopole and associated work areas. 3 shunt removal sites. Existing access road will be graded and improved as needed.
P-14-009431/CA-INY-7354	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible individually, eligible as contributor to expanded Fossil Falls Archaeological District under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Only the extreme western extent of the site (about 5-percent) is located within the Direct APE/API. Project components within the site boundaries consist of a work area associated with the installation of a new LWS monopole, and a demolition area for removal of a lattice steel suspension structure.
P-14-009432/CA-INY-7355 (incl. P-14-009433, P-14-009434/CA-INY-7356, CA-INY-7357)	BLM Ridgecrest FO	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components within the site boundary consist of removal of two lattice steel structures and installation of two new LWS monopoles and their associated work areas, and the existing access road that will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-009436	BLM Ridgecrest FO	Precontact with historic isolate	Precontact: Temporary camp.	Precontact: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	The central portion of the site is located within the Direct APE/API. Project components with the site boundary consist of removal of one lattice steel suspension structure with an associated demolition area, a work area for the installation of a new LWS monopole, and the existing access road that will be graded and improved as needed.
P-14-009438/CA-INY-7358	BLM Ridgecrest FO	Multi-component	Precontact: Habitation area. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1 and 4, eligible as contributor to the expanded Fossil Falls Archaeological District under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures and install 1 new LWS monopole and associated work areas. Existing access road will be graded and improved as needed.
P-14-009439/CA-INY-7359	BLM Ridgecrest FO	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Ineligible individually, eligible as contributor to expanded Fossil Falls Archaeological District under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Project components within the site boundary consist of one new LWS monopole with an associated work area and removal of one lattice steel suspension structure with an associated demolition area. The existing access road that will be graded and improved as needed is located just outside the eastern boundary of the site.
P-14-009440/CA-INY-7360	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, eligible as contributor to the expanded Fossil Falls Archaeological District under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures and associated work area, 1 shunt removal sites. Existing access road will be graded and improved as needed.
P-14-009441	BLM Ridgecrest FO	Historic with precontact isolate	Historic: Mining resource.	Historic: Ineligible.	One new TSP monopole with an associated work area, removal of one lattice steel suspension structure with an associated demolition area, and existing access road will be graded and improved as needed.
P-14-009442	BLM Ridgecrest FO; Private	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Work areas associated with the removal of a lattice steel tower and the proposed construction of a TSP monopole, and existing access road will be graded and improved as needed.
P-14-009443/CA-INY-7363	BLM Ridgecrest FO; Private	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, eligible as contributor to the expanded Fossil Falls Archaeological District under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 2 lattice steel structures and install 2 new TSP monopole and associated work areas. 3 shunt removal sites. Existing access road will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-009444/CA-INY-7364	BLM Ridgecrest FO	Multi-component	Precontact: Bedrock milling station. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components within the site boundary consist of installation of a new LWS monopole with an associated work area, the demolition area associated with the removal of a lattice steel suspension structure with an associated work area, and the existing access road that will be graded and improved as needed.
P-14-009445/CA-INY-7365 (incl. P-14-009446)/ CA-INY-7366)	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as contributor to the expanded Fossil Falls Archaeological District under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components within the site boundary consist of removal of two lattice steel suspension structures with an associated demolition area, installation of two new LWS monopole and associated work areas, and the existing access road that will be graded and improved as needed.
P-14-009447/CA-INY-7367	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components within the site boundary consist of removal of one lattice steel suspension structure, and the work area for installation of one LWS monopole (located 14 m west of the site boundary).
P-14-009449/CA-INY-7368	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components within the site boundary include removal of one lattice steel suspension structure with an associated demolition area, the work area for installation of a new LWS monopole (which is 14 m west of the site boundary), and the existing access road that will be graded and improved as needed.
P-14-009450/CA-INY-7369	Private	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Install 1 TSP monopole and work area. Remove 1 lattice-steel suspension structure and work area. 2 shunt removal sites. Existing access road will be graded and improved as needed.
P-14-009451/ CA-94INY-7370	Private	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines, install 1 TWP multipole with work area, remove 1 lattice steel structure with work area, 1 new demolition site, remove 2 existing demolition pull site, 2 shunt removal sites, and the existing access road that will be graded and improved as needed.
P-14-009454/CA-INY-7371 (incl. P-14-009455, P-14-009456)/CA-INY-7372, CA-INY-7373)	Private	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, eligible as contributor to the expanded Fossil Falls Archaeological District under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 3 lattice steel structures, install 3 new LWS monopole and associated work areas. 6 guard structures, 1 pull site. Existing access road will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-009457/CA-INY-7374	Private	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures, install 1 new LWS monopole and associated work areas. 2 pull sites. Existing access road will be graded and improved as needed.
P-14-009459/CA-INY-7376 (incl. P-14-009460/ CA-INY-7377)	Private	Multi-component	Precontact: Bedrock milling station. Historic: Refuse and discard, Rock feature.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 2 lattice steel structures, install 1 new TSP monopole and associated work areas, 2 pull sites, 3 shunt removal sites. Existing access road will be graded and improved as needed.
P-14-009461/CA-INY-7378	Private	Multi-component	Precontact: Trail. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1, 3 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures, install 1 new TSP monopole and associated work areas. New overland travel.
P-14-009468	BLM Ridgecrest FO	Historic with precontact isolate	Historic: Rock feature.	Historic: Ineligible.	Demolition area associated with the removal of a lattice steel suspension structure located (the structure is located 14 m west of the site boundary) and work area associated with the installation of a TSP monopole (the pole is proposed for 15 m outside the western site boundary).
P-14-009470/CA-INY-7381	BLM Ridgecrest FO	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components within the site boundary consist of removal of one lattice steel suspension structure with an associated demolition area, a work area for the installation of one new TSP monopole (the proposed structure will be 23 m southeast of the site), and the existing access road that will be graded and improved as needed is located on the extreme eastern border of the site.
P-14-009471/CA-INY-7382	BLM Ridgecrest FO	Precontact with historic isolate	Precontact: Bedrock milling station.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Project components within the site boundary consist of installation of one LWS monopole with an associated work area, removal of one lattice steel suspension structure with an associated demolition area, and the existing access road that will be graded and improved as needed.
P-14-009472/CA-INY-7383	BLM Ridgecrest FO	Multi-component	Precontact: Multi-Class Artifact Concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 3 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components within the site boundary consist of removal of one lattice steel structure with an associated demolition area, installation of one new LWS monopole with an associated work area, and the existing access road that will be graded and improved as needed.
P-14-009473/CA-INY-7384	BLM Ridgecrest FO	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1, 3 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures south of site boundary and associated work area in site boundary. Existing access road will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-009474/CA-INY-7385	BLM Ridgecrest FO	Multi-component	Precontact: Multi-class Artifact Concentration. Historic: Refuse and discard	Precontact: Eligible individually under Criteria 3 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures, install 1 new TSP monopole and associated work areas, 2 pull sites. Existing access road will be graded and improved as needed.
P-14-009475/CA-INY-7386	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components within the site boundary consist of removal of one lattice steel suspension structure with an associated demolition area, installation of one TSP monopole with an associated work area, four shunt removal sites, and the existing access road that will be graded and improved as needed.
P-14-009477	BLM Ridgecrest FO	Historic with precontact isolate	Historic: Refuse and discard.	Historic: Ineligible.	Demolition area associated with the removal of a lattice steel structure (the structure is located 9.5 m north of the site boundary), work area associated with the installation of a TSP multipole (the proposed structure would be 21.5 m southeast of the site boundary), and existing access road will be graded and improved as needed.
P-14-009478	BLM Ridgecrest FO	Historic with precontact isolate	Historic: Refuse and discard.	Historic: Ineligible.	One demolition pull site (the structure is located outside the site boundary). An existing unpaved access road is located outside the site boundaries and will not impact the site.
P-14-009479/CA-INY-7388	BLM Ridgecrest FO	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Project components within the site boundary consist of installation of one TSP monopole with an associated work area, removal of one lattice steel suspension structure with and associated demolition area, and the existing access road that will be graded and improved as needed.
P-14-009480/CA-INY-7389	DOD NAWS China Lake	Multi-component	Precontact: Multi-class Artifact Concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 3 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components within the site boundary consist of removal of one lattice steel structure with an associated demolition area, installation of one new TSP monopole with an associated work area, and the existing access road.
P-14-009481/CA-INY-7390	DOD NAWS China Lake	Precontact with historic isolate	Precontact: Bedrock milling station.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission lines, remove 1 lattice steel structure with work area, work area for structure install outside of site boundary, 2 shunt removal sites.
P-14-009483/CA-INY-7391	DOD NAWS China Lake	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures, install 1 new TSP monopole and associated work areas, and existing access road will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-009484/CA-INY-7392	DOD NAWS China Lake	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures, install 1 new TSP monopole and associated work areas, and existing access road will be graded and improved as needed.
P-14-009485/CA-INY-7393	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures, install 1 new TSP monopole and associated work areas, and existing access road will be graded and improved as needed.
P-14-009486/CA-INY-7394	BLM Ridgecrest FO; DOD NAWS China Lake	Multi-component	Precontact: Lithic concentration. H istoric: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Install 1 new TSP monopole and associated work areas, and existing access road will be graded and improved as needed.
P-14-009487/CA-INY-7395	BLM Ridgecrest FO	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 2 lattice steel structures just outside site boundary, install 1 new TSP monopole outside site boundary and associated work areas, remove four shunts, and existing access road will be graded and improved as needed.
P-14-009489/CA-INY-7397	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements within the site boundary consist of the removal of a lattice steel suspension structure with an associated demolition site, installation of a new TSP monopole with an associated work area, two demolition pull sites, and the existing access road that will be graded and improved as needed.
P-14-009490/CA-INY-7398	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements within the site boundary consist of the work area associated with the installation of a new TSP monopole, the demolition area associated with the removal of a lattice steel structure, and the existing access road that will be graded and improved as needed.
P-14-009491/CA-INY-7399	DOD NAWS China Lake; BLM Ridgecrest FO; DOD NAWS China Lake	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Install 1 new TSP monopole and associated work areas, and existing access road will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-009492/CA-INY-7400	DOD NAWS China Lake; DOD NAWS China Lake; BLM Ridgecrest FO	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures, install 1 new TSP monopole just south of site boundary. Associated work areas within site boundary. Existing access road is approximately 5 m east of and parallel to the eastern site boundary.
P-14-009493/CA-INY-7401	DOD NAWS China Lake	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Demolition site extends into the southernmost part of the site and1 shunt removal site. Existing access road will be graded and improved as needed.
P-14-009494/CA-INY-7402	DOD NAWS China Lake; DOD NAWS China Lake; BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures, install 1 new TSP monopole and associated work areas, and existing access road will be graded and improved as needed.
P-14-009495/CA-INY-7403 (incl. P-14-009496/ CA-INY-7404)	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 2 lattice steel structures, install 2 new TSP monopole and associated work areas, and existing access road will be graded and improved as needed.
P-14-009497/CA-INY-7405	BLM Ridgecrest FO; DOD NAWS China Lake	Multi-component	Precontact: Lithic concentration. Historic: Electrical infrastructure resource, Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove one lattice steel structure and associated work area. Install one new TSP monopole and associated work area. One snug/splice site. Existing access road will be graded and improved as needed.
P-14-010005/CA-INY-7217 (incl. P-14-009233)	Private	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines, remove 2 lattice steel structures with work areas, install 1 TSP monopole with work area, 1 pull site, and existing access road will be graded and improved as needed.
P-14-010961/CA-INY-8391	LADWP	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	The site is located within the Direct APE/API; however, through project redesign, the site will be avoided. No ground-disturbing project components overlap this site, and no work will be conducted within the site boundary.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-010962/CA-INY-8392	LADWP	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	The site is partially within the Direct APE/API and a work area for installation of a new LWS structure is 3 m from the southern edge of the site boundary. However, no project components overlap the site.
P-14-010964/CA-INY-8392H	Private	Historic with precontact isolate	Historic: Homestead/ farm/ranch resource.	Historic: Ineligible.	The site is located within the Direct APE/API. A new structure work area is 15 m to the southwest.
P-14-010965	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	It does not intersect any project components and will not be affected by the project.
P-14-011847	BLM Ridgecrest FO	Historic	Historic: Homestead/ farm/ranch resource.	Historic: Ineligible.	Project components and elements within the site boundary consist of one guard site.
P-14-012071/CA-INY-9262	BLM Bishop FO	Precontact	Precontact: Lithic concentration, Rock feature.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	It does not intersect any project components and will not be affected by the project.
P-14-012764	Private	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Two LWS monopoles with associated work areas.
P-14-012777/CA-INY-9677	SCE	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1, and eligible as a contributor to the Owens Valley Land-scape under Criterion 1. Historic: Ineligible.	Project components and elements within the site boundary consist of one pull site covering the majority of the site and then tiny slivers of the following in the extreme northern 2m of the site: another pull site, a guard site, installation of a TSP monopole work area, and a work area associated with a lattice tower removal.
P-14-012781	SCE	Historic with precontact isolate	Historic: Refuse and discard.	Historic: Ineligible.	Access road that will be graded and improved as needed.
P-14-012782	SCE	Historic with precontact isolate	Historic: Refuse and discard.	Historic: Ineligible.	No project components are within the site boundary but the access road is located along the southeastern edge of the site and will be graded and improved as needed.
P-14-012783	SCE	Historic	Historic: Homestead/ farm/ranch resource.	Historic: Ineligible.	Two segments of access road will be graded and improved as needed.
P-14-012785/CA-INY-9685	SCE	Historic with precontact isolate	Historic: Water infrastructure resource.	Historic: Ineligible individually, eligible as contributor to Bishop Creek Hydroelectric System Historic District under Criterion 1.	The site is located outside of the right-of-way but within the Direct APE/API. The site is directly adjacent to existing access roads that will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-014498/ SWCA-L030-6369	BLM Ridgecrest FO	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1 and 4, eligible as contributor to the expanded Fossil Falls Archaeological District under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 2 lattice steel structures, install 2 LWS monopoles Located north and south of site boundary. All associated work areas within site boundary. Existing access road will be graded and improved as needed.
P-14-014504/ SWCA-L030-6385	BLM Ridgecrest FO	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	New TSP monopole structure, associated work areas within site boundary. Removal and installation of additional structures just south of site boundary, associated work areas within site boundary. A pull site is located at northern end of site. Existing access road will be graded and improved as needed.
P-14-014505/ SWCA-L030-6387	BLM Ridgecrest FO	Precontact with historic isolate	Precontact: Temporary camp.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Installation of new subtransmission line and telecom line. Removal/ installation structure work areas located within northern edge of site.
P-14-014507/ SWCA-L030-6390	BLM Ridgecrest FO	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structure just north of site, install 1 LWS monopoles within site. All associated work areas within site boundary. Existing access road will be graded and improved as needed.
SCE-CWA-2020A (incl. SCE-CWA-2020B)	Private	Multi-component	Precontact: Bedrock milling station. Historic: Homestead/ farm/ranch resource.	Precontact: Eligible individually under Criteria 2 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Eligible under Criterion 2, and 4.	Project components and elements within the site boundary include removal of one lattice steel structure and installation of one new TSP monopole and associated work areas, and an existing access road that will be graded and improved as needed.
SWCA-L030-1001	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures and associated demolition area, install 1 new TSP monopole and associated work areas. Work areas of adjacent structures within site boundary, 1 pull site, and existing access road will be graded and improved as needed.
SWCA-L030-1007	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines, 2 demolition pull sites, 1 work area for structure removal outside of site boundary, and existing access road will be graded and improved as needed.
P-14-014238/ CA-INY-010670/ SWCA-L030-1010	LADWP	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace OH subtransmission and telecom lines. Existing access road will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-1017	LADWP	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 2 lattice steel structures, install 2 new LWS monopole and associated work areas. Existing access road will be graded and improved as needed.
SWCA-L030-1023	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 2 lattice steel structures, install 2 new TSP monopole and associated work areas. 2 pull sites. New access road will be graded and improved as needed.
SWCA-L030-1024	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures, install 1 new TSP monopole and associated work areas, and existing access road will be graded and improved as needed.
P-14-014243/ CA-INY-010674/ SWCA-L030-1025	LADWP	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1 and 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, and eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3, and 4.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel and H-frame structures, install 1 new TSP monopole adjacent to site boundary. All associated work areas within site boundary, and existing access road will be graded and improved as needed.
P-14-014244/ CA-INY-010675/ SWCA-L030-1028	LADWP	Precontact	Precontact: Temporary camp.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structure and install 1 new TSP monopole adjacent to site boundary. All associated work areas within site boundary, and existing access road will be graded and improved as needed.
P-14-014245/ CA-INY-010676/ SWCA-L030-1030	LADWP	Precontact	Precontact: Residential base.	Precontact: Eligible individually under Criteria 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 2 lattice steel structures and install 2 new TSP monopole in site boundary. Remove 2 lattice steel structures and install 2 new TSP monopole adjacent to site boundary. All associated work areas within site boundary, and existing access road will be graded and improved as needed.
P-14-014246/ CA-INY-010677/ SWCA-L030-1031	LADWP	Precontact	Precontact: Temporary camp.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures and install 1 new TSP monopole adjacent to site boundary. All associated work areas within site boundary, and existing access road will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-014247/ CA-INY-010678/ SWCA-L030-1032	LADWP	Precontact with historic isolate	Precontact: Temporary camp.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures, install 1 new TSP monopole and associated work areas, 2 pull sites, 1 splice site, and existing access road will be graded and improved as needed.
SWCA-L030-1034	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures and install 1 new TSP monopole adjacent to site boundary. All associated work areas within site boundary, and existing access road will be graded and improved as needed.
SWCA-L030-1035	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Existing access road will be graded and improved as needed. Proposed overland travel through site.
P-14-014271/ CA-INY-010681/ SWCA-L030-1038	LADWP	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures, install 1 new TSP monopole and associated work areas, and existing access road will be graded and improved as needed.
SWCA-L030-1041	LADWP	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures, install 1 new LWS monopole and associated work areas, adjacent tower removal and installation work areas within site boundary, 1 guard structure, and existing access road will be graded and improved as needed.
P-14-014273/ CA-INY-010683/ SWCA-L030-1043	LADWP	Precontact	Precontact: Temporary camp.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures and associated work area, and existing access road will be graded and improved as needed.
SWCA-L030-1044	LADWP	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	One small portion of the site is overlapped by an access road; no other project components are within the site boundary, and the site can be avoided by project avoidance measures.
SWCA-L030-1045	LADWP	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary include the removal of one lattice steel structure with demolitions site, a work area for installation of one new monopole (outside the site boundary), and an existing access road that will be graded and improved as needed. Proposed project components would involve ground disturbance within the site boundary.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-1046	LADWP	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of portions of a demolition area associated with the removal of one lattice steel structure outside of the site boundary, a work area associated with the installation of one new LWS monopole, a pull site, and the existing access road that will be graded and improved as needed
P-14-014277/ CA-INY-010687/ SWCA-L030-1047	LADWP	Precontact with historic isolate	Precontact: Temporary camp.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures, install 1 new TSP monopole and associated work areas, and existing access road will be graded and improved as needed.
P-14-014278/ CA-INY-010688/ SWCA-L030-1048	LADWP	Precontact with protohistoric artifacts	Precontact: Residential base.	Precontact: Eligible individually under Criteria 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures, install 1 new TSP monopole and associated work areas, and existing access road will be graded and improved as needed.
P-14-014279/ CA-INY-010689/ SWCA-L030-1049	LADWP	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of the removal of one lattice steel structure with an associated demolition area, installation of one TWP monopole with an associated work area, and the existing access road that will be graded and improved as needed.
P-14-014311/ CA-INY-010690/ SWCA-L030-1050	LADWP	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. No construction work areas in site boundary. Existing access road will be graded and improved as needed.
P-14-014312/ CA-INY-010691/ SWCA-L030-1056	LADWP	Precontact	Precontact: Burial area.	Precontact: Eligible individually under Criteria 1, 3 and 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures, install 1 new TSP monopole and associated work areas, and existing access road will be graded and improved as needed.
P-14-014313/ CA-INY-010692/ SWCA-L030-1056B	LADWP	Precontact	Precontact: Burial area.	Precontact: Eligible individually under Criteria 1, 3 and 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. No construction work areas in site boundary. Existing access road will be graded and improved as needed.
SWCA-L030-1058	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of a portion of one demolition area for steel lattice structure removal outside the site boundary and the existing access road that will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-1131	Private	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard, Rock feature.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements within the site boundary consist of a temporary yard.
P-15-021121/ SWCA-L030-1135	Private	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Demolition area and new Structure Work Area.
SWCA-L030-1136	Private; DOD NAWS China Lake	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Project components and elements involving ground disturbance within the site boundary consist of an existing access road running along the eastern end of the site that will be graded and improved as needed.
P-15-021119/ SWCA-L030-1141	Private	Historic with precontact isolate	Historic: Refuse and discard.	Historic: Ineligible.	Remove one lattice steel structure and associated demolition area. Install one new TSP monopole structure and associated work area. Existing access road will be graded and improved as needed.
P-15-021118/ SWCA-L030-1142	Private	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Demolition area and new Structure Work Area.
P-15-021117/ SWCA-L030-1144	Private	Historic	Historic: Homestead/ farm/ranch resource.	Historic: Ineligible.	Remove one lattice steel structure and associated demolition area. Install one new LWS monopole structure and associated work area. Existing access road will be graded and improved as needed.
P-15-021116/ SWCA-L030-1145	Private	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Remove one lattice steel structure and associated demolition area. Install one new TSP monopole structure and associated work area. Existing access road will be graded and improved as needed.
P-14-014531/ CA-INY-010840/ SWCA-L030-12035	BLM Ridgecrest FO	Precontact	Precontact: Rock art.	Precontact: Eligible individually under Criteria 1, 3 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Install 1 new TSP monopole 32 m north of site. Structure removal/installation work areas within site boundary.
SWCA-L030-1258	Private; LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Project components and elements involving ground disturbance within the site boundary consist of portions of a demolition area and new structure work area.
SWCA-L030-1267	LADWP	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard, Water infrastructure resource.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 H-frame structure and associated work areas, adjacent tower removal and installation work areas within site boundary, 2 pull sites, 3 shunt removals, and existing access road will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-1271	LADWP	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of a portion of a demolition site for removal of a structure north of the site boundary.
P-14-014318/ SWCA-L030-1275	Private; LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
P-14-014319/ SWCA-L030-1276	Private	Historic	Historic: Refuse and discard, Rock feature.	Historic: Ineligible.	Temporary laydown yard.
P-14-014320/ SWCA-L030-1278	Private	Historic	Historic: Homestead/ farm/ranch resource.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
P-14-014325/ CA-INY-010700/ SWCA-L030-1283	Private	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Remove and replace existing OH subtransmission and telecom lines, remove 1 lattice steel structure with work area, install 1 new TSP multipole with work area, 4 demolition pull sites, 2 shunt removal site, and existing access road will be graded and improved as needed.
P-14-014326/ CA-INY-010701/ SWCA-L030-1285	Private	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Remove and replace existing OH subtransmission and telecom lines, 1 guard site, 1 shunt removal site, and existing access road will be graded and improved as needed.
P-14-014328/ CA-INY-010703/ SWCA-L030-1292	LADWP	Historic	Historic: Refuse and discard, Rock feature.	Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Existing access road will be graded and improved as needed.
P-14-014329/ SWCA-L030-1294	LADWP; BLM Bishop FO	Historic	Historic: Mining resource.	Historic: Ineligible.	Remove one H-frame lattice steel tower with associated demolition area. Install one new TSP monopole with associated work area. Both outside site boundary.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-1295	Private	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of an existing access road that will be graded and improved as needed.
SWCA-L030-1297	LADWP	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1 Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines, remove 1 lattice steel structure with work area, install 1 TSP monopole with work area, and existing access road will be graded and improved as needed.
P-14-014333/ CA-INY-010708/ SWCA-L030-1307	Private	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Project components and elements involving ground disturbance within the site boundary consist of a demolition area associated with the removal of a lattice steel structure outside of the site boundary, and the existing access road that will be graded and improved as needed.
P-14-014334/ SWCA-L030-1400	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	A small portion of the site is within the Direct APE/API; however, no project components are within the site boundary. A new permanent yard is directly adjacent to the site boundary.
SWCA-L030-15000	SCE; LADWP	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible individually under Criteria 1, and eligible as a contributor to the Owens Valley Land-scape under Criterion 1.	Proposed Project components and elements involving ground disturbance within the site boundary consist of small portions of demolition/work areas associated with the removal/installation of structures northwest of the site boundary, and the existing access road that will be graded and improved as needed.
SWCA-L030-15026	LADWP; Private	Historic	Historic: Refuse and discard.	Historic: Ineligible.	No project components are within the site boundary.
P-14-014534/ CA-INY-010843/ SWCA-L030-15068	BLM Bishop FO	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. No work areas within site boundary.
P-14-014335/ CA-INY-010710/ SWCA-L030-1590	LADWP	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Proposed construction material yard is in the northern half of the site.
P-14-014336/ CA-INY-010711/ SWCA-L030-1594	BLM Bishop FO	Multi-component	Precontact: Lithic concentration.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1 Historic: Ineligible individually, eligible as a	Existing access road will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
			Historic: Mining resource.	contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	
P-14-014537/ SWCA-L030-16006	Private	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
P-14-014538/ SWCA-L030-16023	CSLC; DOD NAWS China Lake	Historic	Historic: Rock feature.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1	No project components are within the site boundary.
P-14-014539/ SWCA-L030-16026	CSLC; Private	Historic	Historic: Homestead/ farm/ranch resource.	Historic: Ineligible.	New access road that will be graded and improved as needed.
P-15-021098/ SWCA-L030-16027	Private	Historic	Historic: Homestead/ farm/ranch resource.	Historic: Ineligible.	Existing access road is slated for heavy improvements.
P-14-014337/ CA-INY-010712/ SWCA-L030-1673	BLM Bishop FO	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structure, install 1 new monopole and associated work areas, 1 shunt removal site and existing access road will be graded and improved as needed.
P-14-014338/ CA-INY-010713/ SWCA-L030-1676	BLM Bishop FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4. Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Remove one lattice steel structure and associated demolition area.
P-14-014339/ CA-INY-010714/ SWCA-L030-1677	BLM Bishop FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Remove and replace existing OH subtransmission and telecom lines, remove one lattice steel structure and two steel H-frame structures with associated work areas, install one new TSP monopole with work area. Existing access road will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-014401/ CA-INY-010715/ SWCA-L030-1681	BLM Bishop FO	Historic with precontact isolate	Historic: Refuse and discard.	Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Remove one lattice steel structure and associated demolition area. One shunt removal site. Existing access road will be graded and improved as needed.
P-14-014402/ CA-INY-010716/ SWCA-L030-1688	BLM Bishop FO	Historic	Historic: Refuse and discard.	Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Remove one lattice steel structure and associated demolition area. Install one TSP monopole with associated work area.
P-14-014403/ SWCA-L030-1689	BLM Bishop FO	Historic with precontact isolate	Historic: Refuse and discard.	Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Existing access road will be graded and improved as needed.
P-14-014404/ CA-INY-010718/ SWCA-L030-1692	BLM Bishop FO	Historic	Historic: Refuse and discard.	Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Existing access road will be graded and improved as needed.
P-14-014405/ CA-INY-010719/ SWCA-L030-1700	BLM Bishop FO	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structure, install 1 new TSP monopole outside of site boundary. Associated work areas within site boundary.
P-14-014406/ SWCA-L030-1701	BLM Bishop FO	Historic	Historic: Refuse and discard.	Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	No project components are within the site boundary; however, the access road that will be graded and improved as needed, is within 5 m of the site boundary.
P-14-014407/ SWCA-L030-1705	BLM Bishop FO	Historic with precontact isolate	Historic: Exploration and transportation resource.	Historic: Ineligible.	Remove one lattice steel structure and associated demolition area. Install one LWS monopole with associated work area.
P-14-014408/ SWCA-L030-1706	BLM Bishop FO	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Remove one lattice steel structure and associated demolition area. Existing access road will be graded and improved as needed.
SWCA-L030-1707	BLM Bishop FO	Multi-component	Precontact: Lithic concentration. Historic: Electrical infrastructure resource, Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of a demolition area associated with the removal of a lattice steel tower outside of the site boundary, the work area for installation of a new LWS monopole outside of the site boundary, and the existing access roads that will be graded and improved as needed. These project components will involve ground disturbance.
P-14-014410/ CA-INY-010724/ SWCA-L030-1710	BLM Bishop FO	Historic	Historic: Refuse and discard.	Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Remove one lattice steel structure and associated demolition area. Install one TSP monopole with associated work area. One shunt removal site. Existing access road will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-014411/ CA-INY-010725/ SWCA-L030-2658	LADWP	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 2 lattice steel structure, install 2 new TSP monopole and associated work areas, 1 splice site, 3 shunt removal site and existing access road will be graded and improved as needed.
P-14-014412/ CA-INY-010726/ SWCA-L030-3560	LADWP	Multi-component	Precontact: Multi-class artifact concentration. Historic: Exploration and transportation resource.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 2 lattice steel structure, install 2 new TSP monopole and associated work areas, 2 pull sites, and existing access road will be graded and improved as needed.
P-14-014415/ CA-INY-010729/ SWCA-L030-4370	LADWP	Multi-component	Precontact: Residential base. Historic: Homestead/ farm/ranch resource.	Precontact: Eligible individually under Criteria 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures, install 1 new TSP monopole and associated work areas. New overland travel.
P-14-014421/ SWCA-L030-4375	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Remove one lattice steel structure with associated demolition area. Install one new TSP monopole with associated work area. Existing access road will be graded and improved as needed.
P-14-014422/ CA-INY-010731/ SWCA-L030-4376	LADWP; County of Inyo	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Eligible individually under Criterion 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures and associated work areas. Existing access roads that will be graded and improved as needed.
P-14-014423/ CA-INY-010732/ SWCA-L030-4383	LADWP; Private	Multi-component	Precontact: Bedrock milling station. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 2 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Eligible under Criteria 1 and 2.	Remove and replace the existing OH subtransmission and telecom lines, install of one new LWS multipole with an associated work area, remove of one lattice steel structure with an associated demolition area, one new LADWP crossing pull site, on pull site, and one shunt removal site.
P-14-014424/ SWCA-L030-4384	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Remove one lattice steel structure with associated demolition area.
SWCA-L030-4385	LADWP	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of one new TSP multipole with an associated work area, two pull sites, and the existing access road that will be graded and improved as needed.
P-14-014427/ CA-INY-010736/ SWCA-L030-4391	LADWP	Multi-component	Precontact: Temporary camp. Historic: Homestead/ farm/ranch resource.	Precontact: Eligible individually under Criteria 2 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. New structure associated construction area (structure outside of site boundary), 1 pull site, and existing access road will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-014428/ SWCA-L030-4396	LADWP; BLM Bishop FO	Historic	Historic: Homestead/ farm/ranch resource.	Historic: Ineligible.	Remove one lattice steel structure with associated demolition area. Install one new TSP monopole with associated work area. One pull site. Existing access road will be graded and improved as needed.
P-14-014429/ CA-INY-010738/ SWCA-L030-4397	LADWP; BLM Bishop FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1, 2 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures outside of site boundary, install 1 new structure within site boundary, all associated work areas within site boundary, 1 guard structure. Existing access roads that will be graded and improved as needed.
P-14-014430/ SWCA-L030-4398	LADWP	Historic with precontact isolate	Historic: Refuse and discard.	Historic: Ineligible.	Remove one lattice steel structure with associated demolition area. Install one new TSP monopole with associated work area. Existing access road will be graded and improved as needed.
SWCA-L030-4399	LADWP	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of a small portion of a demolition work area associated with removal and replacement of one structure located outside of the site boundary. The access road, which will be graded and improved as needed, abuts portions of the site boundary.
P-14-014432/ SWCA-L030-4400	LADWP	Historic with precontact isolate	Historic: Refuse and discard.	Historic: Ineligible.	Remove two lattice steel structures with associated demolition areas. Install one new LWS monopole with associated work area. Existing access road will be graded and improved as needed.
P-14-014433/ CA-INY-010742/ SWCA-L030-4403	LADWP	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines, 2 shunt removal sites, 1 area associated with removal of structure outside site boundary, and existing access road will be graded and improved as needed.
SWCA-L030-4408	LADWP	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures, install 1 new TSP monopole structure and associated work areas, 1 pull site. Existing access roads that will be graded and improved as needed.
P-14-014435/ CA-INY-010744/ SWCA-L030-4414	LADWP	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines, install 1 new TSP monopole with work area, 1 demolition area associated with removal of one structure outside of site boundary, and existing access road will be graded and improved as needed.
P-14-014436/ CA-INY-010745/ SWCA-L030-4415	LADWP	Precontact with historic isolate	Precontact: Multi-class artifact concentration.	Precontact: Eligible individually under Criteria 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Structure work area for removal/installation on edge of site boundary. Existing access roads that will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-4416	LADWP	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 1, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of the removal of one lattice steel structure with an associated demolition area, installation of one LWS monopole with an associated work are, one shunt removal site, and the existing access road that will be graded and improved as needed.
P-14-014438/ SWCA-L030-4417	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	One shunt removal site, the demolition area associated with the removal of a lattice steel structure outside of the site boundary, one splice site, and the existing access road that will be graded and improved as needed.
P-14-014439/ SWCA-L030-4418	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Existing access road that will be graded and improved as needed.
P-14-014440/ SWCA-L030-4419	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	One demolition area associated with the removal of a lattice steel structure outside of the site area, and existing access road will be graded and improved as needed.
P-14-014441/ SWCA-L030-4420	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Remove one lattice steel structure and associated demolition area. Install one new LWS monopole structure and associated work area.
P-14-014442/ SWCA-L030-4422	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Remove one lattice steel structure and associated demolition area. Install one new LWS monopole structure and associated work area. Existing access roads will be graded and improved as needed.
P-14-014443/ SWCA-L030-4429	BLM Bishop FO	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Remove one lattice steel structure and associated demolition area. One splice site. Existing access roads will be graded and improved as needed.
P-14-014444/ SWCA-L030-4433	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
SWCA-L030-4436	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	A portion of the site boundary lies within the Direct APE/API and a demolition work area for removal of a lattice steel tower abuts the northeastern site boundary.
P-14-014446/ SWCA-L030-4438	LADWP	Historic with precontact isolate	Historic: Refuse and discard.	Historic: Ineligible.	Removal of one lattice steel structure with an associated demolition area, the work area for installation of a TSP monopole outside of the site boundary, and existing access road will be graded and improved as needed.
P-14-014447/ SWCA-L030-4439	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
P-14-014448/ SWCA-L030-4446	Private; LADWP; BLM Bishop FO	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Remove one lattice steel structure and associated demolition area. Install one new TSP monopole structure and associated work area. One pull site. One guard site.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-014449/ SWCA-L030-4447	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
P-14-014450/ SWCA-L030-4448	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
SWCA-L030-5476	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	No project components within site boundary.
P-14-014452/ CA-INY-010761/ SWCA-L030-5479	LADWP	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures, install 1 new TSP monopole and associated work areas, 1 shunt removal site.
P-14-014453/ SWCA-L030-5483	BLM Bishop FO	Historic	Historic: Homestead/ farm/ranch resource.	Historic: Ineligible.	Construction materials yard within site boundary.
SWCA-L030-5485	BLM Bishop FO	Historic with precontact isolate	Historic: Homestead/ farm/ranch resource.	Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of the removal and replacement of the existing OH subtransmission and telecom lines, removal of one H-frame structure with an associated demolition area, installation of one new TSP multipole with an associated work area, two pull sites, and the existing access road that will be graded and improved as needed.
P-14-014455/ CA-INY-010764/ SWCA-L030-5489	BLM Bishop FO	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of a demolition area for the removal of one lattice steel structure, installation of one new TSP monopole with an associated work area, and the existing access roads that will be graded and improved as needed.
P-14-014456/ CA-INY-010765/ SWCA-L030-5490	LADWP; BLM Bishop FO	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures, install 1 new LWS monopole and associated work areas. Existing access roads that will be graded and improved as needed.
SWCA-L030-5491	BLM Bishop FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of the installation of one TSP multipole with an associated work area, a demolition area associated with removal of a lattice steel structure outside of the site boundary, and the existing access road that will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-5495	BLM Bishop FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of a small portion of one shunt removal site and a small portion of the existing access road that will be graded and improved as needed.
SWCA-L030-5496	BLM Bishop FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of a small portion of one shunt removal site and a small portion of the existing access road that will be graded and improved as needed.
P-14-014460/ SWCA-L030-5497	BLM Bishop FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove one lattice steel structure and associated demolition area. Install one new LWS monopole structure and associated work area. Three shunt removal sites. Existing access roads will be graded and improved as needed.
SWCA-L030-5498	BLM Bishop FO	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Project components and elements involving ground disturbance within the site boundary consist of the removal of one lattice steel structure with an associated demolition area, installation of one LWS monopole with an associated work area, four shunt removal sites, and the existing access road that will be graded and improved as needed.
P-14-014462/ SWCA-L030-5502	BLM Bishop FO	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Project components and elements involving ground disturbance within the site boundary consist of one shunt removal site and the existing access road that will be graded and improved as needed.
P-14-014463/ SWCA-L030-5504	BLM Bishop FO	Precontact with historic isolate	Precontact: Residential base.	Precontact: Eligible individually under Criteria 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Removal/install work area within site boundary. New TSP multi-pole installation adjacent to the northwestern site boundary, remove 1 lattice steel structure 15 m west- northwest of site boundary. Existing access roads that will be graded and improved as needed.
P-14-014464/ SWCA-L030-5505	LADWP; BLM Bishop FO	Multi-component	Precontact: Multi-class artifact concentration. Historic: Homestead/ farm/ranch resource.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures, install 1 new TSP monopole and associated work areas. Existing access roads that will be graded and improved as needed.
P-14-014465/ SWCA-L030-5506	LADWP; BLM Bishop FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Associated structure work areas within 2 m of the southern site boundary.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-014466/ SWCA-L030-5509	LADWP	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Proposed project components and elements involving ground disturbance within the site boundary consist of the installation of one new TSP multipole with an associated work area, removal of one lattice steel structure with an associated demolition area, and the existing access road that will be graded and improved as needed.
P-14-014467/ SWCA-L030-5513	BLM Bishop FO	Precontact	Precontact: Habitation area.	Precontact: Eligible individually under Criteria 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Remove 1 lattice steel structures, install 1 new TSP monopole and associated work areas, 1 pull site, 3 shunt removal sites, and existing unpaved access roads that will be graded and improved as needed.
P-14-014468/ SWCA-L030-5516	BLM Bishop FO	Historic	Historic: Homestead/ farm/ranch resource.	Historic: Ineligible.	Remove one H-frame structure and associated demolition area. Install one new LWS monopole structure and associated work area. One shunt removal site. Existing access road will be graded and improved as needed.
P-14-014469/ CA-INY-010778/ SWCA-L030-5517	LADWP; BLM Bishop FO	Multi-component	Precontact: Multi-class artifact concentration. Historic: Homestead/ Farm/Ranch resource.	Precontact: Eligible individually under Criteria 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Eligible under Criteria 1 and 2.	Remove and replace existing OH subtransmission and telecom lines. Remove 4 lattice steel structures, install 1 TSP monopole and 1 TSP multi-pole and associated work areas, 2 pull sites, 2 guard structures, and 2 shunt removal sites. Multiple existing access roads that will be graded and improved as needed, as well as multiple proposed overland travel routes through site.
P-14-014471/ CA-INY-010780/ SWCA-L030-5519	LADWP	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove H-frame structure located 15 m north of site boundary. Associated work areas within site boundary. Existing unpaved access roads that will be graded and improved as needed.
P-14-014472/ CA-INY-010781/ SWCA-L030-5520	LADWP, County of Inyo	Multi-component	Precontact: Habitation area. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1, 2, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Eligible under Criteria 1 and 2.	Remove and replace existing OH subtransmission and telecom lines. Remove 2 lattice steel structures, install 2 new LWS monopole structures and associated work areas within site boundary. Removal/installation of another set of structures just northwest of site boundary, associated work areas within site boundary, 2 guard structures, and 3 shunt removal sites. Existing unpaved access roads that will be graded and improved as needed.
P-14-014473/ CA-INY-010782/ SWCA-L030-5522	LADWP	Multi-component with protohistoric artifacts	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1 and 2, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of new overland travel routes, which would involve ground disturbance.
P-14-014474/ SWCA-L030-5523	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	No project components involving ground disturbance overlap the site boundary.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-5524	LADWP; Private	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard, Rock feature.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of an existing access road in the eastern end of the site that will be graded and improved as needed.
P-14-014476/ SWCA-L030-5845	BLM Bishop FO	Historic	Historic: Refuse and discard.	Historic: Ineligible.	One pull site.
P-14-014477/ SWCA-L030-5846	Private; LADWP; BLM Bishop FO	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
P-14-014666/ CA-INY-010922/ SWCA-L030-6000	SCE	Precontact	Precontact: Residential base.	Precontact: Eligible individually under Criteria 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Existing access road will be graded and improved as needed.
SWCA-L030-6001	SCE	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 1, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Project components and elements involving ground disturbance within the site boundary consist of the existing access road that crosses the southeasternmost edge of the site and will be graded and improved as needed.
P-14-014481/ SWCA-L030-6004	BLM Bishop FO	Historic	Historic: Refuse and discard, water infrastructure resource.	Historic: Ineligible.	Removal of a lattice steel structure with an associated demolition site.
SWCA-L030-6074	LADWP; Private	Historic	Historic: Mining Resource.	Historic: Ineligible.	Portions of the site are located within the Direct APE/API. Existing unpaved access road will be graded and improved as needed.
P-14-014483/ SWCA-L030-6076	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	The northeastern edge of the site overlaps the existing access road that will be graded and improved as needed.
P-14-014484/ SWCA-L030-6077	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Remove one lattice steel structure and associated demolition area. Install one new TSP monopole structure and associated work area. Two shunt removal sites.
P-14-014485/ SWCA-L030-6078	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Remove one lattice steel structure and associated demolition area. Install one new TSP monopole structure and associated work area. Two pull sites. Existing unpaved access road that will be graded and improved as needed.
P-14-014486/ SWCA-L030-6079	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Remove one lattice and two H-frame steel structures and associated demolition areas. Install two new TSP monopole structure and associated work area. Existing unpaved access road that will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-014487/ SWCA-L030-6081	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Remove one lattice steel structure and associated demolition area. Install one new TSP monopole structure and associated work area. One pull site. Existing unpaved access road that will be graded and improved as needed.
P-14-014488/ SWCA-L030-6082	LADWP	Historic	Historic: Homestead/ farm/ranch resource.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
P-14-014489/ SWCA-L030-6083	Private	Historic	Historic: Refuse and discard, Rock feature.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
P-14-014490/ CA-INY-010799/ SWCA-L030-6350	DOD NAWS China Lake	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. Two work areas associated with removal/installation of structures to be outside site boundary. Existing access road will be graded and improved as needed.
P-14-014491/ CA-INY-010800/ SWCA-L030-6352	DOD NAWS China Lake	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines, 2 work areas associated with installation/removal of structures, 1 pull site, 1 shunt removal site, and the existing access road that will be graded and improved as needed.
P-14-014492/ CA-INY-010801/ SWCA-L030-6356	Private; DOD NAWS China Lake	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines, 2 work areas associated with installation/removal of structures, and the existing access road that will be graded and improved as needed.
P-14-014493/ CA-INY-010802/ SWCA-L030-6359	DOD NAWS China Lake	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines, install 1 TSP monopole, remove 1 lattice steel structure, 2 associated work areas, and the existing access road that will be graded and improved as needed.
P-15-021102/ SWCA-L030-6360	DOD NAWS China Lake	Historic	Historic: Refuse and discard.	Historic: Ineligible.	One pull site.
P-15-021101/ SWCA-L030-6361	SCE	Historic	Historic: Refuse and discard.	Historic: Ineligible.	construction materials yard.
P-14-014494/ CA-INY-010803/ SWCA-L030-6363	BLM Ridgecrest FO	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Remove 2 lattice steel structures (1 structure 6 m outside of site boundary), install 2 new TSP monopole structures and associated work areas, and existing access road will be graded and improved as needed.
P-14-014495/ CA-INY-010804/ SWCA-L030-6365	Private	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Removal 2 lattice steel structures (1 structure 30 m outside of site boundary), install 2 new TSP monopole structures (1 structure 20 m outside of site boundary). All associated work areas within existing site boundary, 1 pull site, and existing access road will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-014496/ CA-INY-010805/ SWCA-L030-6366	DOD NAWS China Lake	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	One pull site and existing access road that will be graded and improved as needed.
SWCA-L030-6367	Private; DOD NAWS China Lake	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Existing access road that will be graded and improved as needed.
P-15-021100/ SWCA-L030-6368	BLM Ridgecrest FO	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
P-14-014499/ CA-INY-010808/ SWCA-L030-6370	BLM Ridgecrest FO	Precontact	Precontact: Temporary camp.	Precontact: Eligible individually under Criterion 4, eligible as contributor to expanded Fossil Falls Archaeological District under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Remove and replace existing OH subtransmission and telecom lines. and existing access road will be graded and improved as needed.
SWCA-L030-6373	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of one shunt removal site and the existing access road that will be graded and improved as needed.
P-14-014501/ SWCA-L030-6379	BLM Ridgecrest FO	Historic with precontact isolate	Historic: Mining resource.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
P-14-014502/ SWCA-L030-6381	BLM Ridgecrest FO	Historic	Historic: Mining resource.	Historic: Ineligible.	Remove two lattice steel structures and associated demolition areas. Install one new LWS monopole structure and associated work area. One pull site.
P-14-014503/ SWCA-L030-6382	BLM Ridgecrest FO	Historic with precontact isolate	Historic: Refuse and discard.	Historic: Ineligible.	Two pull sites.
P-14-014506/ CA-INY-010815/ SWCA-L030-6389	BLM Ridgecrest FO	Precontact with historic isolate	Precontact: Bedrock milling station.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Project components and elements involving ground disturbance within the site boundary consist of the existing access road that will be graded and improved as needed.
SWCA-L030-6396	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements involving ground disturbance within the site consist of the existing access road that will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-014509/ CA-INY-010818/ SWCA-L030-6397	BLM Ridgecrest FO	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Located outside of ROW. Existing access road will be graded and improved as needed.
P-14-014510/ CA-INY-010819/ SWCA-L030-6399	BLM Ridgecrest FO	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Located outside of ROW. Existing access road will be graded and improved as needed and a proposed helicopter landing zone.
SWCA-L030-6400	BLM Ridgecrest FO	Historic with precontact isolate	Historic: Refuse and discard.	Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of a small portion of a demolition area associated with removal of a lattice steel tower outside of the site boundary, and the existing access road that will be graded and improved as needed.
P-14-014512/ CA-INY-010821/ SWCA-L030-6401	BLM Ridgecrest FO	Multi-component	Precontact: Bedrock milling station. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of the existing access road that will be graded and improved as needed.
P-14-014513/ CA-INY-010822/ SWCA-L030-6402	DOD NAWS China Lake; BLM Ridgecrest FO	Multi-component	Precontact: Bedrock milling station. Historic: Refuse and discard, Rock feature.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of an existing access road that will be graded and improved as needed abutting the western edge of the site boundary and the southeastern edge of the site.
SWCA-L030-6413	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of the removal of a lattice steel structure with an associated demolition area, installation of a TSP multipole with an associated work area, two new pull sites, and the existing access road that will be graded and improved as needed.
P-14-014516/ SWCA-L030-6415	BLM Ridgecrest FO	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
SWCA-L030-6416	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-6417	BLM Ridgecrest FO	Historic with precontact isolate	Historic: Refuse and discard.	Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of a demolition area associated with removal of a lattice steel structure adjacent to the western site boundary, and a work area associated with installation of a LWS monopole outside of the site boundary. The existing unpaved access road is within 5 m of the western site boundary.
SWCA-L030-6418	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of the existing access road that will be graded and improved as needed.
P-14-014520/ CA-INY-010829/ SWCA-L030-6419	BLM Ridgecrest FO	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Located outside of ROW. Existing access road will be graded and improved as needed.
P-14-014521/ SWCA-L030-6420	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Existing access road will be graded and improved as needed.
SWCA-L030-6421	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of the existing access road that will be graded and improved as needed.
P-14-014523/ SWCA-L030-6422	BLM Ridgecrest FO; LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Remove one lattice steel structure and associated demolition area. One shunt removal site. Existing unpaved access road that will be graded and improved as needed.
P-14-014525/ CA-INY-010834/ SWCA-L030-6428	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Demolition site for removal of lattice steel structure north of site boundary. Existing unpaved access road that will be graded and improved as needed.
P-14-014526/ CA-INY-010835/ SWCA-L030-6430	Private	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Project components and elements involving ground disturbance within the site boundary consist of a demolition area associated with the removal of a lattice steel tower adjacent to the eastern site boundary, a work area for installation of a TSP monopole east of the site boundary, and a new access road that will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-014527/ CA-INY-010836/ SWCA-L030-6432	Private	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Located outside of ROW. Existing access road will be graded and improved as needed.
P-15-021099/ SWCA-L030-7193	Private	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Remove one lattice steel structure and associated demolition area. Install one new TSP monopole structure and associated work area. Two pull sites. Existing access road that will be graded and improved as needed.
SWCA-L030-7591	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	No project components are located within the site boundary.
P-14-014529/ CA-INY-010838/ SWCA-L030-7677	BLM Bishop FO	Precontact with historic isolate	Precontact: Multi-class artifact concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	No project components overlap this site, and no work will be conducted within the site boundary.
SWCA-L030-7679	BLM Bishop FO	Multi-component	Precontact: Lithic concentration. Historic: Homestead/ farm/ranch resource, Mining resource.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Eligible under Criteria 1 and 4.	Project components and elements involving ground disturbance within the site boundary consist of the demolition area associated with the removal of one lattice steel structure within 5 m of the site boundary, installation of one new LWS monopole within the site boundary with an associated work area, two shunt removal sites, and the existing access road that will be graded and improved as needed.
SWCA-L030-7720	BLM Bishop FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible individually, eligible as a contributor to the Patsiata Historic District under Criteria 1, 2, 3 and 4.	Remove and replace existing OH subtransmission and telecom lines. Removal of 1 H-frame and associated work area, removal and installation of structures 25 m south of site boundary, associated work areas within site boundary. Existing access road will be graded and improved as needed.
SWCA-L030-7736	LADWP	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Project components and elements involving ground disturbance within the site boundary consist of a small portion of a demolition area at the north end of the site and the existing access road that will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-015412/ SWCA-L030-S-62800	BLM Ridgecrest FO	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Project components include construction materials yard and an existing access road that will be graded and improved as needed.
P-14-015413/ CA-INY-011519/ SWCA-L030-S-62813	LADWP	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Eligible individually under Criteria 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Planned project components and elements involving ground disturbance within the site boundary include one construction materials yard which has the potential to impact the eligibility of the site.
P-14-015414/ SWCA-L030-S-62816	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Project components include construction materials yard.
SWCA-L030-S-62819	LADWP	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criteria 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1. Historic: Ineligible.	Planned project components and elements involving ground disturbance within the site boundary include one new CMY (CH SA 1-4 Big Pine Dump Road Alt 3), which has the potential to impact the eligibility of the site.
P-14-015416/ SWCA-L030-S-62825	LADWP	Historic with precontact isolate	Historic: Refuse and discard.	Historic: Ineligible.	Project components include construction materials yard.
P-14-015417/CA-INY-011523/SWCA-TROW-S-003	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Installation of one new tubular steel pole monopole with associated work areas, a demolition site for removal of a lattice structure and, associated work area, and use of existing access roads that will be graded and improved as needed.
P-14-014081/CA-INY-010523/SWCA-L030-1591	LADWP	Precontact with historic isolate	Precontact: Multi-class artifact concentration.	Precontact: Eligible individually under Criteria 1 and 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Planned project components and elements involving ground disturbance within the site boundary include one construction materials yard which has the potential to impact the eligibility of the site.
P-14-014201/CA-INY-010636/SWCA-TROW-S-002/ SWCAL030-5480	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as a contributor to the Owens Valley Landscape under Criterion 1.	Project components and elements involving ground disturbance within the site boundary consist of an existing tower and associated demolition work area, as well as an existing access road that will be graded and improved as needed.

Table Ap.5-2. Proposed Project Cultural Resources: Segment 2

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-15-002500	BLM Ridgecrest FO; Private	Historic	Historic: Mining resource.	Historic: Ineligible individually, eligible as contributor to Rand Historic District under Criterion 1.	Remove two structures and their associated work areas, install two new TSP monopole suspension structures and their associated work areas, seven shunt removal areas, one splice site; and two access roads that will be graded and improved as needed. Proposed construction materials yard.
P-15-002501	BLM Ridgecrest FO; Private	Historic	Historic: Mining Resource.	Historic: Ineligible.	Remove four lattice steel structures and associated demolition areas. Install four TSP monopoles and associated work areas. Four guard structures. Two stunt removal sites. Existing unpaved access roads, which will be graded and improved as needed.
P-15-008676	BLM Ridgecrest FO; CSLC; Private	Precontact	Precontact: District.	Precontact: Listed under Criteria 1 and 4.	No contributing elements of the district are located within the Direct APE/API.
P-15-010890	Private; City of Ridgecrest	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	construction materials yard.
P-15-014492	BLM Ridgecrest FO	Historic with precontact isolate	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road that transects the eastern edges of the site and will be graded and improved as needed.
P-15-014497	BLM Ridgecrest FO	Historic	Historic: Mining resource.	Historic: Ineligible.	Remove one lattice steel structure and associated demolition area. Install one new LWS monopole structure and associated work area. Install a new access road that will be graded and improved as needed.
P-15-014499	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are within the site boundary.
P-15-021138/ SWCA-L030-5153	BLM Ridgecrest FO	Historic	Historic: Mining resource.	Historic: Ineligible individually, eligible as contributor to Rand Historic District under Criterion 1.	Demolition site and new structure work area for the removal of a steel lattice suspension structure and replacement with a TSP monopole is the northeastern portion of the site, along with an existing access road that transects the eastern edge of the site and will be graded and improved as needed.
P-15-021139/ SWCA-L030-5154	BLM Ridgecrest FO; Private	Historic	Historic: Mining resource.	Historic: Ineligible individually, eligible as contributor to Rand Historic District under Criterion 1.	Shunt removal site, a demolition site, and a new structure work area for the removal of a steel lattice suspension structure located just east of the site boundary, and replacement with a TSP monopole located in the eastern portion of the site, along with an existing access road that will be graded and improved as needed. Additionally, another shunt removal site is located roughly 6 m south of the site boundary.
P-15-021140/ SWCA-L030-5155	BLM Ridgecrest FO; Private	Historic	Historic: Mining resource.	Historic: Ineligible individually, eligible as contributor to Rand Historic District under Criterion 1.	Demolition site and new structure work area for the removal of a steel lattice suspension structure and replacement with a TSP monopole located just north of the site boundary, and an additional demolition site and new structure work area for the

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
					removal of another steel lattice suspension structure and replacement with a TSP monopole in the southern portion of the site. Additionally, an existing access road transects the site and will be graded and improved as needed.
P-15-021144/ SWCA-L030-5161	BLM Ridgecrest FO; Private	Historic	Historic: Refuse and discard, Rock feature.	Historic: Ineligible individually, eligible as contributor to Rand Historic District under Criterion 1.	Three pull sites, one guard site, and one demolition site and new structure work area for the removal of a steel lattice suspension structure and replacement with a TSP monopole immediately north of the site boundary, along with two existing access roads that will be graded and improved as needed.
P-36-023525	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Removal of two steel lattice suspension structures and replacement with two TSP monopoles along with their associated demolition sites and new structure work areas, one shunt removal site, and existing access road will be graded and improved as needed.
P-36-023542	BLM Barstow FO and Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Removal of three steel lattice suspension structures and replacement with three TSP monopoles along with the associated demolition sites and new structure work areas, three shunt removal sites, and existing access road will be graded and improved as needed.
P-36-023543	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	One demolition site and three structure work areas for the removal and replacement of structures outside of the site boundary and one LWS monopole in the northwestern corner of the site.
P-36-027091	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are located within the site boundary.
P-15-021115/ SWCA-L030-1146	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Remove three lattice steel structures and associated demolition areas. Install three new TSP monopole structures and associated work areas. Existing access road will be graded and improved as needed.
P-15-021114/ SWCA-L030-1150	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Remove two lattice steel structures and associated demolition areas. Install one new LWS monopole structure and associated work area. One shunt removal site. Existing access road will be graded and improved as needed.
P-15-021113/ SWCA-L030-1153	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Remove two lattice steel structures and associated demolition areas. Install one new TSP and one new LWS monopole structures and associated work areas. Two shunt removal sites. Existing access road will be graded and improved as needed.
P-15-021112/ SWCA-L030-1157	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Remove one lattice steel structure and associated demolition area. Install one new LWS monopole structure and associated work area. Two shunt removal sites. Existing access road will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-15-021111/ SWCA-L030-1160	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Remove one lattice steel structure and associated demolition area. Install one new TSP monopole structure and associated work area. Two pull sites. Existing access road will be graded and improved as needed.
P-15-021123/ SWCA-L030-1165	BLM Ridgecrest FO; Private	Historic	Historic: Mining resource.	Historic: Ineligible individually, eligible as contributor to Rand Historic District under Criterion 1.	Two demolition sites for the removal of two lattice steel structures, two new work areas for the installation of two TSP monopole structures, and two existing access roads that will be graded and improved as needed.
SWCA-L030-1168	Private	Historic	Historic: Mining resource.	Historic: Ineligible individually, eligible as contributor to Rand Historic District under Criterion 1.	Five shunt removal sites, two demolition sites for the removal of two lattice towers, and two new structure work areas for the installation of two TSP pole structures. Additionally, four existing access roads transect the site and will be graded and improved as needed.
SWCA-L030-1170	Private	Historic	Historic: Refuse and discard.	Historic: Ineligible individually, eligible as contributor to Rand Historic District under Criterion 1.	Three guard sites, two demolition sites for the removal of two lattice towers (one of which is located outside of the site boundary), two work areas for the installation of two new TSP monopole structures (one of which is located outside of the site boundary), and an existing access road that will be graded and improved as needed.
P-15-021124/ SWCA-L030-1171	Private	Historic	Historic: Mining resource.	Historic: Ineligible individually, eligible as contributor to Rand Historic District under Criterion 1.	Pull site is located roughly 4 m south of the site boundary, and a demolition site and new structure work area for the removal of a lattice tower and replacement with a TSP monopole are located roughly 7 m north of the site boundary.
P-15-021125/ SWCA-L030-1172	Private	Historic	Historic: Refuse and discard.	Historic: Ineligible individually, eligible as contributor to Rand Historic District under Criterion 1.	Two pull sites, two guard sites, and a demolition site and new structure work area for a pole replacement outside of the site boundary. Additionally, an existing access road transects the site and will be graded and improved as needed.
P-15-021126/ SWCA-L030-1173	Private	Historic	Historic: Mining resource.	Historic: Ineligible individually, eligible as contributor to Rand Historic District under Criterion 1.	Two new pull sites and three demolition pull sites for removal.
P-15-021127/ SWCA-L030-1174	Private	Historic	Historic: Exploration and transportation resource.	Historic: Ineligible individually, eligible as contributor to Rand Historic District under Criterion 1.	Two pull sites, a guard site, and an existing access road that will be graded and improved as needed.
SWCA-L030-1176	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Three pull sites that overlay the northern and northeastern portion of the site. Additionally, Butte Ave. is roughly 3-6 m west of the site boundary and an existing access road that will be graded and improved as needed is roughly 3 m east and north of the site boundary.
P-15-021129/ SWCA-L030-1177	Private	Historic	Historic: Homestead/ farm/ranch resource.	Historic: Ineligible individually, eligible as contributor to Rand Historic District under Criterion 1.	Structure removal/install work areas, guard sites, and pull sites within site boundary. Existing access road to be graded and improved as needed.
SWCA-L030-1179	Private	Historic	Historic: Mining Resource.	Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of a demolition site and new structure work area for the removal of a lattice steel structure and replacement with a new TSP monopole structure. One

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
					existing access road to be graded and improved as needed is roughly 4 m southwest of the site boundary.
SWCA-L030-1180	Private	Historic	Historic: Mining Resource.	Historic: Ineligible.	No project components and elements involving ground disturbance are located within the site boundary; though a demolition site and new structure work area for the removal and replacement of structures located outside the site boundary are roughly 6+ m north of the site boundary.
P-15-021132/ SWCA-L030-1181	Private	Historic	Historic: Mining resource.	Historic: Ineligible individually, eligible as contributor to Rand Historic District under Criterion 1.	No project components and elements involving ground disturbance are located within the site boundary; though a structure work area for pole removal and replacement is located roughly 5 m south of the site boundary, and an existing access road that will be graded and improved as needed is located roughly 3 m west of the site boundary.
SWCA-L030-1183	Private	Historic	Historic: Mining Resource.	Historic: Ineligible.	Guard site that overlays the southwestern extent of the site.
SWCA-L030-1184	Private	Historic	Historic: Refuse and discard.	Historic: Ineligible individually, eligible as contributor to Rand Historic District under Criterion 1.	Demolition site and new structure work area for the removal of a lattice tower located immediately adjacent to the northern site boundary and replacement with a TSP monopole to be located roughly 9 m north of the site boundary, and an existing access road that will be graded and improved as needed transects the northeastern portion of the site.
SWCA-L030-1185	Private	Historic	Historic: Mining resource.	Historic: Ineligible individually, eligible as contributor to Rand Historic District under Criterion 1.	Two existing access roads that will be graded and improved as needed. Additionally, a guard site is located roughly 8 m north of the site boundary and a demolition site and work area for pole removal and replacement is located roughly 2 m south of the site boundary.
SWCA-L030-20000	BLM Ridgecrest FO	Historic	Historic: Refuse and discard, Rock feature.	Historic: Ineligible.	Structure work and demolition areas. Multiple pull sites.
SWCA-L030-5079	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Remove one lattice steel structure and associated demolition area. Install one TSP monopole structure and associated work area. One guard site. Existing access roads will be graded and improved as needed.
SWCA-L030-5083	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Guard site, a demolition site and new structure work area for the removal of a lattice steel structure located 2-3 m east of the site boundary and replacement with a TSP monopole structure located along the eastern site boundary.
SWCA-L030-5084	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
SWCA-L030-5085	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Guard site, a demolition site and new structure work area for the removal of a steel lattice structure and replacement with a TSP monopole structure, and an existing access road that will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-5086	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
SWCA-L030-5087	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	One pull site that overlays most of the site, and two sets of demolition sites and new structure work areas for pole replacements that extend north and south of the site respectively, along with an existing access road that abuts the western site boundary and will be graded and improved as needed.
SWCA-L030-5088	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	One splice site, and a demolition site and new structure work area for the removal of a lattice steel structure located east of the site boundary and replacement with a LWS monopole structure in the southeastern corner of the site, along with an existing access road that bisects the site and will be graded and improved as needed.
SWCA-L030-5089	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	There are no planned project components and elements within the site boundary; however, an existing access road that will be graded and improved as needed is located roughly 4 m west of the site boundary, and a demolition site and structure work area for pole removal and replacement is located roughly 7 m south of the site boundary.
SWCA-L030-5090	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Guard site, and a demolition site and new structure work area for the removal of a lattice tower and replacement with a TSP monopole structure north of the site boundary, along with an existing access road that bisects the eastern extent of the site and will be graded and improved as needed.
SWCA-L030-5093	BLM Ridgecrest FO; Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Demolition site and new structure work area for the removal of a lattice tower located in the northern portion of the site and replacement with a TSP monopole structure located just north of the site boundary, along with an existing access road that transects the western extent of the site and will be graded and improved as needed.
SWCA-L030-5094	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Demolition site and new structure work area for the removal of a lattice tower located immediately adjacent to the northern site boundary and replacement with a TSP monopole structure located roughly 5 m northwest of the site boundary. Additionally, an existing access road abuts the western site boundary and will be graded and improved as needed.
SWCA-L030-5096	BLM Ridgecrest FO; Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Two pull sites, and two sets of demolition sites and new structure work areas for the removal of two lattice towers and replacement with TSP monopole structures, one of which is located in the northern portion of the site and one of which is located just outside the southern site boundary. Additionally, two existing access roads transect the site and will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-5101	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Two existing access roads that will be graded and improved as needed. Additionally, a pull site is located roughly 2 m south of the site boundary and a demolition site for the removal of a lattice tower is located roughly 4 m north of the site boundary.
SWCA-L030-5102	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Demolition site and new structure work area for the removal of a lattice tower and replacement with a TSP monopole structure north of the site boundary, along with an existing access road that will be graded and improved as needed.
SWCA-L030-5103	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Work area for the removal of a lattice tower and replacement with a LWS monopole structure located outside and north of the site boundary. Additionally, an existing access road that will be graded and improved as needed abuts the southwestern boundary of the site.
SWCA-L030-5104	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Demolition site and new structure work area for the removal of a lattice suspension structure and replacement with a TSP monopole structure, along with a new overland travel route in the northern portion of the site.
SWCA-L030-5106	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Demolition site and three structure work areas for the removal of a steel lattice suspension structure and replacement with a TSP monopole structure along with the installation of a temporary LWS monopole structure, and an overland travel route.
SWCA-L030-5110	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Demolition site and a new structure work area for the removal of a steel lattice suspension structure and replacement with a TSP monopole structure in the northern portion of the site.
SWCA-L030-5111	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Splice site that overlays the northern extent of the site, and a demolition site and new structure work area for the removal of a steel lattice suspension structure and replacement with a TSP monopole structure, along with an existing access road that will be graded and improved as needed.
SWCA-L030-5113	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Demolition site and structure work area for the removal a steel lattice suspension structure and replacement with a TSP monopole in the northern portion of the site. Additionally, another work area is located roughly 5 m south of the site boundary.
SWCA-L030-5116	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Two shunt removal sites that overlay the northern portion of the site, and a demolition site and structure work area for the removal of a steel lattice suspension structure and replacement with a TSP monopole roughly 12 and 8 m south of the site boundary respectively. Additionally, an existing access road transects the western extent of the site and will be graded and improved as needed.
SWCA-L030-5117	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Demolition site and structure work area for the removal of a steel lattice suspension structure and installation of a TSP monopole in the southern portion of the site. and the Additionally, an existing access road transects the western extent of the site and

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
					will be graded and improved as needed, and an overland travel route is planned in the southern portion of the site.
SWCA-L030-5121	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Demolition site for the removal of a steel lattice suspension structure that is located roughly 7 m southwest of the site boundary.
SWCA-L030-5122	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Demolition site and structure work area for the removal of a steel lattice suspension structure and replacement with a TSP monopole, along with a new overland travel route, all of which are located in the central portion of the site.
SWCA-L030-5123	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Four shunt removal sites, one splice site, one pull site, along with a demolition site and new structure work area for the removal of a steel lattice suspension structure and replacement with a TSP monopole in the northern portion of the site. Additionally, an existing access road abuts the western extent of the site and will be graded and improved as needed, and a new overland travel route is planned.
SWCA-L030-5124	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Guard site, demolition site, and new structure work area for the removal of a steel lattice suspension structure and replacement with a TSP monopole, along with an overland travel route in the northern portion of the site.
SWCA-L030-5126	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Demolition site and new structure work area for the removal of a steel lattice structure and replacement with a TSP monopole located north of the site boundary.
SWCA-L030-5127	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road that transects the eastern extent of the site and will be graded and improved as needed.
SWCA-L030-5128	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Demolition site and a new structure work area for the removal of a steel lattice suspension structure and replacement with a LWS monopole located north of the site boundary, along with an existing access road that transects the western edge of the site and will be graded and improved as needed.
SWCA-L030-5129	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Four structure work areas and a demolition site for the removal of a steel lattice suspension structure and replacement with a LWS monopole in the central portion of the site and additional removal and replacement of transmission structures to the north and south of the site boundary. Additionally, an existing access road bisects the southwestern extent of the site and will be graded and improved as needed.
SWCA-L030-5131	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Demolition site and new structure work area for the removal of a steel lattice suspension structure and replacement with a TSP monopole in the northern part of the site, along with an existing access road that bisects the site and will be graded and improved as needed.
SWCA-L030-5132	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Splice site that overlays the northern extent of the site, along with a demolition site and structure work area for the removal of a steel lattice suspension structure and replacement with a TSP monopole to be located just west of the site boundary.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
					Additionally, an existing access road transects the northwestern extent of the site and will be graded and improved as needed.
SWCA-L030-5133	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Splice site that overlays most of the site, and a demolition site for the removal of a steel lattice suspension structure that overlays the northern tip of the site, along with an existing access road that bisects the western extent of the site and will be graded and improved as needed.
SWCA-L030-5134	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Demolition site and new structure work area for the removal of a steel lattice suspension structure and replacement with a TSP monopole in the southern portion of the site, along with an existing access road that will be graded and improved as needed.
SWCA-L030-5135	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Three shunt removal sites, two guard sites, and two demolition sites and new structure work areas for the removal of steel lattice suspension structures and replacement with TSP monopoles, along with a new overland travel route and two existing access roads that will be graded and improved as needed.
SWCA-L030-5142	BLM Ridgecrest FO	Historic	Historic: Mining Resource.	Historic: Ineligible.	Demolition site and new structure work area for the removal of a steel lattice suspension structure and replacement with a TSP monopole just north of the site boundary, along with an existing access road that will be graded and improved as needed.
SWCA-L030-5143	BLM Ridgecrest FO	Multi-component	Precontact: Bedrock milling station. Historic: Refuse and Discard.	Precontact: Eligible under Criterion 4. Historic: Ineligible.	The proposed project will not adversely impact the resource.
SWCA-L030-5145	BLM Ridgecrest FO	Historic	Historic: Mining Resource.	Historic: Ineligible.	Four shunt removal sites and two demolition sites for the removal of an H-frame structure in the southern portion of the site and a steel lattice suspension structure located north of the site boundary, and an existing access road that bisects the center of the site and will be graded and improved as needed.
SWCA-L030-5146	BLM Ridgecrest FO	Historic	Historic: Mining Resource.	Historic: Ineligible.	Demolition site and structure work area for the removal of a steel lattice suspension structure and replacement with a TSP monopole located just south and west of the site boundary. Additionally, an existing access road is roughly 4 m west of the site boundary and will be graded and improved as needed.
SWCA-L030-5148	BLM Ridgecrest FO	Historic	Historic: Mining Resource.	Historic: Ineligible.	Existing access road that bisects the center of the site and will be graded and improved. Additionally, a shunt removal site is located roughly 6 m north of the site boundary and a demolition site is located roughly 8 m south of the site boundary.
SWCA-L030-5149	BLM Ridgecrest FO	Historic	Historic: Mining Resource.	Historic: Ineligible.	No project components overlay the site boundary.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-5150	BLM Ridgecrest FO	Historic	Historic: Mining resource.	Historic: Ineligible individually, eligible as contributor to Rand Historic District under Criterion 1.	Demolition site and structure work area that overlay the portion of the site for removal of a steel lattice tower and replacement with a TSP monopole located roughly 5 m and 12 m north of the site boundary respectively, along with an existing access road that will be graded and improved as needed.
SWCA-L030-5151	BLM Ridgecrest FO; Private	Historic	Historic: Exploration and transportation resource, Mining resource.	Historic: Ineligible individually, eligible as contributor to Rand Historic District under Criterion 1.	Three pull sites that overlay most of the site area, and an existing access road that transects the southeastern portion of the site and will be graded and improved as needed. An additional access road that will be graded and improved as needed abuts the eastern site boundary.
SWCA-L030-5152	Private	Historic	Historic: Mining resource.	Historic: Ineligible individually, eligible as contributor to Rand Historic District under Criterion 1.	Two unpaved access roads that will be graded and improved as needed.
SWCA-L030-5157	BLM Ridgecrest FO; Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road that transects the northernmost part of the site and will be graded and improved as needed. An additional access road abuts the western site boundary but is a paved road, so grading will not occur.
SWCA-L030-5159	BLM Ridgecrest FO; Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road that transects the northern portion of the site and will be graded and improved as needed.
P-15-021143/ SWCA-L030-5160	BLM Ridgecrest FO	Historic	Historic: Mining resource.	Historic: Ineligible individually, eligible as contributor to Rand Historic District under Criterion 1.	No project components involving ground disturbance within site boundary.
SWCA-L030-5162	BLM Ridgecrest FO	Historic	Historic: Mining Resource.	Historic: Ineligible.	Existing unpaved access road will be graded and improved as needed.
SWCA-L030-5164	BLM Ridgecrest FO; Private	Historic	Historic: Mining Resource.	Historic: Ineligible.	Two pull sites that overlay the entire site boundary.
SWCA-L030-5166	BLM Ridgecrest FO; Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are directly within the boundary of the site; however, the western site boundary is immediately adjacent to a demolition site and work area for the removal of a lattice steel structure and replacement with a TSP monopole, and a guard site is located roughly 5 m west of the site boundary.
SWCA-L030-5168	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Demolition site and new structure work area for the removal of a steel lattice suspension structure and replacement with a TSP monopole, along with an existing access road that will be graded and improved as needed.
SWCA-L030-5169	BLM Ridgecrest FO; Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Demolition site associated with the removal of a steel lattice suspension structure north of the site boundary.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-15-021110/ SWCA-L030-5171	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components and elements involving ground disturbance overlay the site boundary; though a demolition site and structure work area are located roughly 1 m south and 3 m east of the site boundary.
P-15-021109/ SWCA-L030-5172	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Shunt removal area, and a demolition site and structure work area for the removal of a steel lattice suspension structure and replacement with a TSP monopole just west of the site boundary.
P-15-021108/ SWCA-L030-5173	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components and elements involving round disturbance overlay the site, though an existing access road that will be graded and improved as needed abuts the southern boundary of the site.
P-15-021107/ SWCA-L030-5174	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are within the site boundary.
P-15-021106/ SWCA-L030-5181	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Work area associated with the installation of a TSP monopole roughly 20 m south of the site boundary.
P-15-021105/ SWCA-L030-5186	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are situated directly within the project boundary, though an existing access road that will be graded and improved as needed abuts the western site boundary.
P-15-021104/ SWCA-L030-5190	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Demolition site and structure work areas associated with the removal of a steel lattice suspension structure and replacement with a LWS monopole roughly 12 m northwest of the site boundary.
P-15-021103/ SWCA-L030-5196	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Demolition site and structure work area for the removal of a steel lattice suspension structure located immediately adjacent to the site boundary, and replacement with a LWS monopole located within the site boundary, along with an existing access road that transects the eastern edge of the site and will be graded and improved as needed.
SWCA-L030-5197	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access roads will be graded and improved as needed.
SWCA-L030-5394	BLM Ridgecrest FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components within site boundary.
SWCA-L030-9027	CSLC	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Demolition site and structure work area for the removal of a steel lattice suspension structure and replacement with a TSP monopole located just west of the site boundary.
SWCA-L030-9028	CSLC	Historic with precontact isolate	Historic: Refuse and Discard.	Historic: Ineligible.	Demolition site and structure work area for the removal of a steel lattice suspension structure and replacement with a TSP monopole, along with an existing access road that will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-9029	CSLC	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
SWCA-L030-9030	CSLC	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Shunt removal site in the southern part of the site, and a demolition site and structure work area for the removal of a steel lattice suspension structure and replacement with a TSP monopole in the northern portion of the site, along with an existing access road that will be graded and improved as needed.
SWCA-L030-9031	CSLC; Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Shunt removal site, and demolition site and structure work area for the removal of a steel lattice suspension structure and replacement with a TSP monopole located just north of the site boundary, along with an existing access road that will be graded and improved as needed.
SWCA-L030-9032	CSLC; Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Shunt removal site and an existing access road that will be graded and improved as needed.

Table Ap.5-3. Proposed Project Cultural Resources: Segment 3N

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-36-026218	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible. Historic: Ineligible.	Project components within the site boundary consist of removal of one lattice steel suspension structure with an associated demolition site, structure work areas for the installation of one LWS monopole suspension structures (3.5 m south), two shunt removal sites, and two segments of the existing access road that will be graded and improved as needed.
P-36-000403/ CA-SBR-403	BLM Barstow FO; SCPPA; LADWP; Private	Multi-component	Precontact: Residential base. Historic: Homestead/ farm/ranch resource.	Precontact: Eligible under Criteria 1 and 4. Historic: Eligible under Criteria 1 and 4.	Remove and replace existing OH subtransmission and telecom lines. Remove and replace 3 wood pole H-frame structures, 2 structures are within site boundary and 1 is outside of site boundary, and associated work areas within site boundary. Existing access road to be graded and improved as needed.
P-36-005066/ CA-SBR-5066	SCE, Private	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Ineligible.	Numerous project components and elements involving ground disturbance that intersect the original site boundary, including three H-frame structures and associated work areas for reconductoring, three steel lattice structures and associated work areas for reconductoring, two monopole structures and associated work areas for modification, one monopole structure and associated work area for removal, one H-frame structure and associated work area for removal and replacement, four guard sites, four pull sites, nine work areas, and both new overland travel routes and the existing access road, which will be graded and improved as needed.
P-36-006148	BLM Barstow FO; SCPPA; Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Construction maintenance yard and existing access road will be graded and improved as needed.
P-36-006572	CSLC; SCE; Private	Historic with precontact isolate	Historic: Refuse and Discard.	Historic: Ineligible.	Three existing H-frame wood structures with associated work areas for reconductoring, one new construction maintenance yard, and the existing access road that will be graded and improved as needed.
P-36-007421/ CA-SBR-7421H	BLM Barstow FO	Multi-component	Precontact: Ceramic concentration. Historic: Military resource.	Precontact: Eligible under Criterion 4. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of three reconductoring work areas with existing structures, and the existing access road that will be graded and improved as needed.
P-36-007425/ CA-SBR-7425	SCE, SCPPA	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	Remove and replace existing OH subtransmission and telecom lines. Access 1 structure adjacent to site to conduct OH work. Existing access road to be graded and improved as needed.
P-36-007432/ CA-SBR-7432	BLM Barstow FO	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	The site is located within the Direct APE/API and there are no project components planned within the site boundary.
P-36-023239	SCPPA; Private	Historic with precontact isolate	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road to be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-36-023333	BLM Barstow FO; Private	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Ineligible.	The site is located within the Direct APE/API and there are no project components planned within the site boundary.
P-36-024926/ CA-SBR-15955	BLM Barstow FO	Precontact	Precontact: Temporary camp.	Precontact: Eligible under Criterion 4.	No project components overlap this site, and no work will be conducted within the site boundary.
P-36-028216	SCE	Historic	Historic: Refuse and discard, Rock feature.	Historic: Ineligible.	Construction material yard and one pull site.
SWCA-L030-1102	SCE	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing wooden H-frame structure with an associated work area for reconductoring, and two existing access roads that will be graded and improved as needed.
SWCA-L030-1104	Private	Historic	Historic: Exploration and transportation resource, Refuse and Discard.	Historic: Ineligible.	No project components involving ground disturbance are within the site boundaries; though a new overland travel route and an access road that will be graded and improved as needed are located 5 to 20 m south of the site boundary.
SWCA-L030-1105	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components involving ground disturbance intersect the site boundary, though an access road that will be graded and improved as needed is located roughly 7 m west of the site boundary.
SWCA-L030-1106	BLM Barstow FO; Private	Historic	Historic: Mining resource.	Historic: Eligible under Criteria 1 and 4.	Existing H-frame structure with associated work area for reconductoring in the northeastern portion of the site, and an existing access road that will be graded and improved as needed. An additional work area is located roughly 4 m south of the site boundary
SWCA-L030-1107	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
SWCA-L030-1227	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road that bisects the center of the site will be graded and improved as needed. Additionally, a structure work area is located roughly 4 m west of the site boundary.
SWCA-L030-1233	SCPPA	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road that bisects the northernmost extent of the site will be graded and improved as needed.
SWCA-L030-1241	SCPPA	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Structure work area is located roughly 9 m west of the site boundary.
SWCA-L030-1255	PG&E	Historic with precontact isolate	Historic: Refuse and Discard.	Historic: Ineligible.	Construction materials yard overlays the northern and eastern portion of the site.
SWCA-L030-2361	SCPPA; Private	Historic with precontact isolate	Historic: Refuse and Discard.	Historic: Ineligible.	Access road that will be graded and improved as needed is located immediately south of the site boundary.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-2364	SCPPA; Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Work area associated with reconductoring at a wooden H-frame structure that is located roughly 6 m west of the site, and the existing access road that bisects the northern extent of the site and will be graded and improved as needed.
SWCA-L030-2365	SCPPA; Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Access road will be graded and improved as needed is located roughly 9 m north of the site boundary.
SWCA-L030-2369	SCPPA; Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Work area for reconductoring on an existing H-frame structure and access road will be graded and improved as needed are located roughly 8 m south of the site boundary.
SWCA-L030-2371	SCPPA; Private	Historic with precontact isolate	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road that bisects the center of the site will be graded and improved as needed.
SWCA-L030-2374	SCPPA; Private	Historic	Historic: Homestead/ farm/ranch resource.	Historic: Ineligible.	Small portion of a work area for the removal and replacement of a wooden H-frame structure will be located roughly 12 m outside of the site boundary.
SWCA-L030-4016	Dept of Defense; BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Work area associated with reconductoring work on an existing multi-pole structure, two pull sites, and the existing access and spur roads that will be graded and improved as needed.
SWCA-L030-4017	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed abuts the eastern boundary of the site.
SWCA-L030-4019	BLM Barstow FO	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	No project components involving ground disturbance overlay within the site boundary, though an existing access road that will be graded and improved as needed is located roughly 3 m north of the site boundary and a structure work area is located roughly 10 m east of the site boundary.
SWCA-L030-4021	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Work area associated with reconductoring at an existing H-frame structure that is located outside of the site boundary, and the existing access road that bisects the western extent of the site and will be graded and improved as needed.
SWCA-L030-4022	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	One wooden H-frame structure with an associated work area for reconductoring, and the existing access road that bisects the northwestern extent of the site and will be graded and improved as needed.
SWCA-L030-4025	BLM Barstow FO; Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road that bisects the southern extent of the site will be graded and improved as needed.
SWCA-L030-4472	CSLC	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road that bisects the center of the site will be graded and improved as needed.
SWCA-L030-4476	CSLC	Historic	Historic: Refuse and discard, Rock feature.	Historic: Ineligible.	Pull site that overlies the southern portion of the site, and the existing access road that bisects the western extent of the site will be graded and improved as needed. Additionally, a work area for reconductoring at an existing H-frame structure is located roughly 3 m northwest of the site boundary.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-4477	CSLC	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road that bisects the center of the site will be graded and improved as needed.
SWCA-L030-9025	SCPPA; CSLC	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing wooden H-frame structure with an associated work area for reconductoring in the southeastern corner of the site, and the existing access road that bisects the center of the site and will be graded and improved as needed.
SWCA-L030-9026	SCPPA; Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road that will be graded and improved as needed is located roughly 6 m north of the site boundary.
SWCA-L030-9033	Dept of Defense	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing unpaved access road that will be graded and improved as needed is located roughly 14 m north of the site boundary.
SWCA-L030-9036	Dept of Defense	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing wooden H-frame structure with an associated work area for reconductoring in the southern extent of the site, and the existing access road will be graded and improved as needed.
SWCA-L030-9037	BLM Barstow FO; CSLC; Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
P-36-000718	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	The site is partially encircled by and directly adjoins an existing access road that may be graded or otherwise improved for the project.
P-36-006757/ CA-SBR-6757, CA-SBR-4037H, CA-SBR-4055	BLM Barstow FO; Private	Precontact	Precontact: Quarry.	Precontact: Eligible under Criterion 4.	Remove and replace existing OH subtransmission and telecom lines. Access 3 structures within site to conduct OH work. Existing access road to be graded and improved as needed.
P-36-006764	BLM Barstow FO; Private	Historic	Historic: Homestead/ farm/ranch resource.	Historic: Ineligible.	Construction materials yard overlays the central portion of the site, and the existing access road which marks the southeast boundary of the site will be graded and improved as needed.
P-36-027888/ CA-SBR-17379	Private	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	No project components are within the site boundary, though an access road that will be graded and improved as needed is located roughly 9 m south of the site boundary.
P-36-028018/ CA-SBR-17474	BLM Barstow FO	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	No project components are located within the site boundary.
P-36-028019	Private	Historic	Historic: Homestead/ farm/ranch resource.	Historic: Ineligible.	No project components and elements involving ground disturbance extend within the site boundary, though an access road that will be graded and improved as needed is located roughly 3 m east of the site boundary.
P-36-028020	Private	Historic	Historic: Rock feature.	Historic: Ineligible.	No project components involving ground disturbance are located within the site boundary, though a pull site is located roughly 3 m to the east of the site boundary, and a new structure work area is located roughly 10 m west of the site boundary.
P-36-028022	BLM Barstow FO	Historic	Historic: Rock feature.	Historic: Ineligible.	Work area associated with the installation of a new structure outside of the site boundary and two pull sites.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-36-028063/ CA-SBR-17493	Private	Precontact	Precontact: Rock feature.	Precontact: Ineligible	No project components involving ground disturbance are located within the site boundary, although an access road that will be graded and improved as needed is located immediately south of the site boundary.
P-36-028064/ CA-SBR-17494	Private	Precontact	Precontact: Quarry.	Precontact: Ineligible	Project components and elements that may cause ground disturbance within the site boundary consist of the existing access road that bisects the southern extent of the site and will be graded and improved as needed.
SWCA-L030-1108	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
SWCA-L030-1111	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	One guard site.
SWCA-L030-1112	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Work area for reconductor work on an existing H-frame structure in the northeastern corner of the site, and a demolition site and work area in the northwestern corner of the site for the removal of an existing H-frame structure and replacement with a new LWS H-frame suspension structure to be located roughly 15 m west of the site boundary, along with the existing access road that transects the northern extent of the site and will be graded and improved as needed.
SWCA-L030-1113	Private	Multi-component	Precontact: Temporary camp. Historic: Refuse and Discard.	Precontact: Eligible under Criterion 4. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Access 1 structure within site to conduct OH work, 1 splice site, and existing access road to be graded and improved as needed.
SWCA-L030-1115	Private	Historic	Historic: Homestead/ farm/ranch resource.	Historic: Ineligible.	Work area for reconductoring on an existing H-frame structure in the southern portion of the site.
SWCA-L030-1116	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	One guard site in the northern portion of the site and an existing access road will be graded and improved as needed.
SWCA-L030-1119	Private	Historic with precontact isolate	Historic: Refuse and Discard.	Historic: Ineligible.	No project components located within the site boundary, though an existing access road that will be graded and improved as needed is located roughly 5 m north of the site boundary.
SWCA-L030-1120	Private	Precontact with historic isolate	Precontact: Temporary camp.	Precontact: Ineligible	Project components and elements that may involve ground disturbance within the site boundary consist of the existing access road that will be graded and improved as needed.
SWCA-L030-1188	Private; USAF	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Two construction yards, one guard site, one existing H-frame structure for reconductoring and an associated work area, and the existing access road that will be graded and improved as needed.
SWCA-L030-1189	Private	Historic with precontact isolate	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are located within the site boundary, though a work area for reconducting on an existing H-frame structure is immediately adjacent to the northern site boundary and an existing access road that will be graded and improved as needed abuts the northeastern boundary of the site.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-1192	Private	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Ineligible.	Project components and elements that may involve ground disturbance within the site boundary consist of the existing access road that will be graded as improved as needed.
SWCA-L030-1193	Private	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Ineligible.	No project components are located within the site boundary, though a work area for reconductoring on an existing H-frame structure and an access road that will be graded and improved as needed are located immediately northeast of the site boundary.
SWCA-L030-1194	Private	Multi-component	Precontact: Quarry. Historic: Refuse and discard.	Precontact: Eligible under Criterion 4. Historic: Ineligible.	Existing access road will be graded and improved as needed.
SWCA-L030-1195	Private	Historic with precontact isolate	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are located within the site boundary; though an access road is roughly 9 m south of the site boundary and a work area for reconducting on an existing H-frame structure is located roughly 5 m west of the site boundary.
SWCA-L030-1199	Private	Historic with precontact isolate	Historic: Refuse and Discard.	Historic: Ineligible.	Reconductor work area and the existing access road that will be graded and improved as needed.
SWCA-L030-1200	Private	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard, Rock feature.	Precontact: Ineligible. Historic: Ineligible.	Project components involving ground disturbance within the site boundary consist of a reconductor work area associated with an existing H-frame structure, and the existing access road that will be graded and improved as needed.
SWCA-L030-1201	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Work area for reconducting on an existing wooden H-frame structure, and the existing access road that will be graded and improved as needed.
SWCA-L030-1215	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are located within the site boundary.
SWCA-L030-1220	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
SWCA-L030-3208	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are located within the site boundary, though an access road that will be graded and improved as needed is located roughly 15 m southwest of the site.
SWCA-L030-4000	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Pull site and existing access road will be graded and improved as needed.
SWCA-L030-4002	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	One pull site. Additionally, an access road will be graded and improved as needed abutting the northern site boundary.
SWCA-L030-4003	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are located within the site boundary, though an unpaved access road that will be graded and improved as needed is located roughly 12 m south of the site boundary.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-4004	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing H-frame structure for reconductoring and the associated work area in the western extent of the site.
SWCA-L030-4005	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing H-frame suspension structure for reconductoring and the associated work area in the southwestern portion of the site.
SWCA-L030-4006	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Work area associated with reconductoring on an H-frame structure is located roughly 3 m south of the site boundary.
SWCA-L030-4007	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are located within the site boundary, though a reconductor work area is located roughly 3 m east of the site boundary.
SWCA-L030-4012	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing H-frame suspension structure for reconductoring with an associated work area located in the northern extent of the site, and existing access road will be graded and improved as needed.
SWCA-L030-4029	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
SWCA-L030-4031	BLM Barstow FO	Historic with precontact isolate	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed. Additionally, a new structure work area is located roughly 5 m southeast of the site boundary.
SWCA-L030-4032	BLM Barstow FO	Precontact	Precontact: Temporary camp.	Precontact: Eligible under Criterion 4.	Remove and replace existing OH subtransmission and telecom lines. Access 1 structure within site to conduct OH work, and existing access road to be graded and improved as needed.
SWCA-L030-4033	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Work area associated with the installation of a new H-frame suspension structure.
SWCA-L030-4036	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
SWCA-L030-4038	Private; BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	One construction yard.
SWCA-L030-4039	Private; BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components and elements are located within the site boundary, though an access road that will be graded and improved as needed is located roughly 10 m southeast of the site boundary.
SWCA-L030-4041	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are located within the site boundary, though an access road that will be graded and improved as needed is located roughly 2 m northeast of the site boundary, and a work area for reconductoring is located roughly 10 m northwest of the site boundary.
SWCA-L030-4043	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are located within the site boundary, though an access road that will be graded and improved as needed is located roughly 2 m northeast of the site boundary, and a work area for reconductoring is located roughly 10 m northwest of the site boundary.
SWCA-L030-4046	BLM Barstow FO	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	Project components and elements that may involve ground disturbance within the site boundary consist of the existing access road that will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-4049	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of one pull site.
SWCA-L030-6496	U.S. Marine Corps	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components involving ground disturbance are located within the site boundary, though an access road that will graded and improved as needed is located 3 m south of the site boundary.
SWCA-L030-7623	USAF Edwards Air Force Base	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are located within the site boundary, though an unpaved access road abuts the site boundary.
SWCA-L030-7624	USAF Edwards Air Force Base	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Work area for reconductoring on an existing H-frame suspension structure, and the existing access road will be graded and improved as needed.
SWCA-L030-7625	USAF Edwards Air Force Base	Historic with precontact isolate	Historic: Refuse and Discard.	Historic: Ineligible.	Work area associated with reconducting on an existing H-frame structure, and two existing access roads will be graded and improved as needed.
SWCA-L030-7627	USAF Edwards Air Force Base	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Access road that will be graded and improved as needed abuts the southwestern edge of the site.
SWCA-L030-7628	USAF Edwards Air Force Base	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components involving ground disturbance are located within the site boundary, however, an access road will be graded and improved as needed abuts the southern tip of the site.
SWCA-L030-7629	US Air Force Edwards AFB	Multi-component	Precontact: Lithic concentration. Historic: Refuse and Discard.	Precontact: Ineligible. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of the work area associated with reconductoring on an existing wooden H-frame suspension structure in the western extent of the site, and the existing access road that will be graded and improved as needed.
SWCA-L030-7639	USAF Edwards Air Force Base	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are located within the site boundary, though an access road that will be graded and improved as needed is located roughly 3 m north of the site boundary.
SWCA-L030-9020	Dept of Defense	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are located within the site boundary, though a work area is located roughly 3 m east of the site boundary.
SWCA-L030-9022	Dept of Defense	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Work area associated with reconductoring on an existing wooden H-frame suspension structure in the western extent of the site. Additionally, an existing access road that will be graded and improved as needed is located roughly 5 m south of the site boundary.
SWCA-L303-2300	Private	Historic	Historic: Homestead/ farm/ranch resource.	Historic: Ineligible.	Guard site and the work area associated with reconductoring on an existing H-frame structure that is roughly 5 m south of the site boundary.

Table Ap.5-4. Proposed Project Cultural Resources: Segment 3S

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-36-000718	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	The site is partially encircled by and directly adjoins an existing access road that may be graded or otherwise improved for the project.
P-36-006757/CA-SBR-6757, CA-SBR-4037H, CA-SBR-4055	BLM Barstow FO; Private	Precontact	Precontact: Quarry.	Precontact: Eligible under Criterion 4.	Remove and replace existing OH subtransmission and telecom lines. Access 3 structures within site to conduct OH work. Existing access road to be graded and improved as needed.
P-36-006764	BLM Barstow FO; Private	Historic	Historic: Homestead/farm/ ranch resource.	Historic: Ineligible.	Construction materials yard overlays the central portion of the site, and the existing access road which marks the southeast boundary of the site will be graded and improved as needed.
P-36-027888/CA-SBR-17379	Private	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	No project components are within the site boundary, though an access road that will be graded and improved as needed is located roughly 9 m south of the site boundary.
P-36-028018/CA-SBR-17474	BLM Barstow FO	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	No project components are located within the site boundary.
P-36-028019	Private	Historic	Historic: Homestead/farm/ ranch resource.	Historic: Ineligible.	No project components and elements involving ground disturbance extend within the site boundary, though an access road that will be graded and improved as needed is located roughly 3 m east of the site boundary.
P-36-028020	Private	Historic	Historic: Rock feature.	Historic: Ineligible.	No project components involving ground disturbance are located within the site boundary, though a pull site is located roughly 3 m to the east of the site boundary, and a new structure work area is located roughly 10 m west of the site boundary.
P-36-028022	BLM Barstow FO	Historic	Historic: Rock feature.	Historic: Ineligible.	Work area associated with the installation of a new structure outside of the site boundary and two pull sites.
P-36-028063/CA-SBR-17493	Private	Precontact	Precontact: Rock feature.	Precontact: Ineligible	No project components involving ground disturbance are located within the site boundary, although an access road that will be graded and improved as needed is located immediately south of the site boundary.
P-36-028064/CA-SBR-17494	Private	Precontact	Precontact: Quarry.	Precontact: Ineligible	Project components and elements that may cause ground disturbance within the site boundary consist of the existing access road that bisects the southern extent of the site and will be graded and improved as needed.
SWCA-L030-1108	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
SWCA-L030-1111	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	One guard site.
SWCA-L030-1112	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Work area for reconductor work on an existing H-frame structure in the northeastern corner of the site, and a demolition site and work area in the northwestern corner of the site for the removal of an existing H-frame structure and replacement with a new LWS H-frame suspension structure to be

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
					located roughly 15 m west of the site boundary, along with the existing access road that transects the northern extent of the site and will be graded and improved as needed.
SWCA-L030-1113	Private	Multi-component	Precontact: Temporary camp. Historic: Refuse and Discard.	Precontact: Eligible under Criterion 4. Historic: Ineligible.	Remove and replace existing OH subtransmission and telecom lines. Access 1 structure within site to conduct OH work, 1 splice site, and existing access road to be graded and improved as needed.
SWCA-L030-1115	Private	Historic	Historic: Homestead/farm/ ranch resource.	Historic: Ineligible.	Work area for reconductoring on an existing H-frame structure in the southern portion of the site.
SWCA-L030-1116	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	One guard site in the northern portion of the site and an existing access road will be graded and improved as needed.
SWCA-L030-1119	Private	Historic with precontact isolate	Historic: Refuse and Discard.	Historic: Ineligible.	No project components located within the site boundary, though an existing access road that will be graded and improved as needed is located roughly 5 m north of the site boundary.
SWCA-L030-1120	Private	Precontact with historic isolate	Precontact: Temporary camp.	Precontact: Ineligible	Project components and elements that may involve ground disturbance within the site boundary consist of the existing access road that will be graded and improved as needed.
SWCA-L030-1188	Private; USAF	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Two construction yards, one guard site, one existing H-frame structure for reconductoring and an associated work area, and the existing access road that will be graded and improved as needed.
SWCA-L030-1189	Private	Historic with precontact isolate	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are located within the site boundary, though a work area for reconducting on an existing H-frame structure is immediately adjacent to the northern site boundary and an existing access road that will be graded and improved as needed abuts the northeastern boundary of the site.
SWCA-L030-1192	Private	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Ineligible.	Project components and elements that may involve ground disturbance within the site boundary consist of the existing access road that will be graded as improved as needed.
SWCA-L030-1193	Private	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Ineligible.	No project components are located within the site boundary, though a work area for reconductoring on an existing H-frame structure and an access road that will be graded and improved as needed are located immediately northeast of the site boundary.
SWCA-L030-1194	Private	Multi-component	Precontact: Quarry. Historic: Refuse and discard.	Precontact: Eligible under Criterion 4. Historic: Ineligible.	Existing access road will be graded and improved as needed.
SWCA-L030-1195	Private	Historic with precontact isolate	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are located within the site boundary; though an access road is roughly 9 m south of the site boundary and a work area for reconducting on an existing H-frame structure is located roughly 5 m west of the site boundary.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-1199	Private	Historic with precontact isolate	Historic: Refuse and Discard.	Historic: Ineligible.	Reconductor work area and the existing access road that will be graded and improved as needed.
SWCA-L030-1200	Private	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard, Rock feature.	Precontact: Ineligible. Historic: Ineligible.	Project components involving ground disturbance within the site boundary consist of a reconductor work area associated with an existing H-frame structure, and the existing access road that will be graded and improved as needed.
SWCA-L030-1201	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Work area for reconducting on an existing wooden H-frame structure, and the existing access road that will be graded and improved as needed.
SWCA-L030-1215	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are located within the site boundary.
SWCA-L030-1220	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
SWCA-L030-3208	Private	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are located within the site boundary, though an access road that will be graded and improved as needed is located roughly 15 m southwest of the site.
SWCA-L030-4000	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Pull site and existing access road will be graded and improved as needed.
SWCA-L030-4002	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	One pull site. Additionally, an access road will be graded and improved as needed abutting the northern site boundary.
SWCA-L030-4003	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are located within the site boundary, though an unpaved access road that will graded and improved as needed is located roughly 12 m south of the site boundary.
SWCA-L030-4004	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing H-frame structure for reconductoring and the associated work area in the western extent of the site.
SWCA-L030-4005	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing H-frame suspension structure for reconductoring and the associated work area in the southwestern portion of the site.
SWCA-L030-4006	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Work area associated with reconductoring on an H-frame structure is located roughly 3 m south of the site boundary.
SWCA-L030-4007	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are located within the site boundary, though a reconductor work area is located roughly 3 m east of the site boundary.
SWCA-L030-4012	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing H-frame suspension structure for reconductoring with an associated work area located in the northern extent of the site, and existing access road will be graded and improved as needed.
SWCA-L030-4029	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-4031	BLM Barstow FO	Historic with precontact isolate	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed. Additionally, a new structure work area is located roughly 5 m southeast of the site boundary.
SWCA-L030-4032	BLM Barstow FO	Precontact	Precontact: Temporary camp.	Precontact: Eligible under Criterion 4.	Remove and replace existing OH subtransmission and telecom lines. Access 1 structure within site to conduct OH work, and existing access road to be graded and improved as needed.
SWCA-L030-4033	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Work area associated with the installation of a new H-frame suspension structure.
SWCA-L030-4036	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Existing access road will be graded and improved as needed.
SWCA-L030-4038	Private; BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	One construction yard.
SWCA-L030-4039	Private; BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components and elements are located within the site boundary, though an access road that will be graded and improved as needed is located roughly 10 m southeast of the site boundary.
SWCA-L030-4041	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are located within the site boundary, though an access road that will be graded and improved as needed is located roughly 2 m northeast of the site boundary, and a work area for reconductoring is located roughly 10 m northwest of the site boundary.
SWCA-L030-4043	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are located within the site boundary, though an access road that will be graded and improved as needed is located roughly 2 m northeast of the site boundary, and a work area for reconductoring is located roughly 10 m northwest of the site boundary.
SWCA-L030-4046	BLM Barstow FO	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	Project components and elements that may involve ground disturbance within the site boundary consist of the existing access road that will be graded and improved as needed.
SWCA-L030-4049	BLM Barstow FO	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of one pull site.
SWCA-L030-6496	U.S. Marine Corps	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components involving ground disturbance are located within the site boundary, though an access road that will graded and improved as needed is located 3 m south of the site boundary.
SWCA-L030-7623	USAF Edwards Air Force Base	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are located within the site boundary, though an unpaved access road abuts the site boundary.
SWCA-L030-7624	USAF Edwards Air Force Base	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Work area for reconductoring on an existing H-frame suspension structure, and the existing access road will be graded and improved as needed.
SWCA-L030-7625	USAF Edwards Air Force Base	Historic with precontact isolate	Historic: Refuse and Discard.	Historic: Ineligible.	Work area associated with reconducting on an existing H-frame structure, and two existing access roads will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-7627	USAF Edwards Air Force Base	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Access road that will be graded and improved as needed abuts the southwestern edge of the site.
SWCA-L030-7628	USAF Edwards Air Force Base	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components involving ground disturbance are located within the site boundary, however, an access road will be graded and improved as needed abuts the southern tip of the site.
SWCA-L030-7629	US Air Force Edwards AFB	Multi-component	Precontact: Lithic concentration. Historic: Refuse and Discard.	Precontact: Ineligible. Historic: Ineligible.	Project components and elements involving ground disturbance within the site boundary consist of the work area associated with reconductoring on an existing wooden H-frame suspension structure in the western extent of the site, and the existing access road that will be graded and improved as needed.
SWCA-L030-7639	USAF Edwards Air Force Base	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are located within the site boundary, though an access road that will be graded and improved as needed is located roughly 3 m north of the site boundary.
SWCA-L030-9020	Department of Defense	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	No project components are located within the site boundary, though a work area is located roughly 3 m east of the site boundary.
SWCA-L030-9022	Department of Defense	Historic	Historic: Refuse and Discard.	Historic: Ineligible.	Work area associated with reconductoring on an existing wooden H-frame suspension structure in the western extent of the site. Additionally, an existing access road that will be graded and improved as needed is located roughly 5 m south of the site boundary.
SWCA-L303-2300	Private	Historic	Historic: Homestead/farm/ ranch resource.	Historic: Ineligible.	Guard site and the work area associated with reconductoring on an existing H-frame structure that is roughly 5 m south of the site boundary.

Table Ap.5-5. Built Environment Resources on Proposed Project – All Segments

This table lists all built environment resources within the Direct API for all segments (eligible and noneligible).

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
1, 2	P-14-004825/P-14-005766/008	Private (SCE)	ca. 1908 (SCE Control Substation)	Other	Bishop Creek Hydroelectric System Historic District. The district includes substations, powerhouses, gauging stations, flowlines, intakes, penstocks, diversions, reservoirs, dams, worker housing and other associated support buildings, towers, and transmission lines. Several contributing elements (Powerhouse 5, Bishop Intake Number 6 Dam) and resources (SCE Control Substation Complex (P-14-005766), SCE Randsburg Substation Complex (P-15-015221), and Tower Line (P-36-010316)) are located within the API.	Listed in the CRHR. Eligible under Criterion 1.	See individual contributing resources for impacts.
1	009	Private (SCE)	1913-1987	Transmission/ Utility Line	SCE Casa Diablo-Control-Sherwin 115kV Transmission Line (35.50 miles long) is a 115kV electrical transmission line and conductors mounted on single and double wood/steel poles that intersects project APE in two locations. Second transmission line (SCE Casa Diablo-Control 115kV TL) recorded as a separate resource parallels this one.	Ineligible.	One guard site and pole removal and installation sites.
1	010	Private (SCE)	1908-1965	Transmission/ Utility Line	SCE Casa Diablo-Control 115kV Transmission Line (52.80 miles long) is a 115kV electrical transmission line and conductors mounted on single and double wood/steel poles that intersects project APE in two locations. Second transmission line (SCE Casa Diablo-Control-Sherwin 115kV TL) recorded as a separate resource parallels this one.	Ineligible.	Two 95-foot TSP monopole installation sites, one tower removal site, one guard site, and one underground fiber optic installation site.
1	011	Private (SCE)	1907	Local Road	Access Road to SCE Control-Inyo Transmission Line (Plant 5 Road), approximately 1.37 miles long, is a partially-paved, one-lane road (unknown width) that makes two loops (around and within) the SCE Control Substation intersecting with the project APE in multiple locations.	Ineligible.	One guard site, two pull sites, pole removal and installation sites. Existing unpaved access roads will be graded and improved as needed.
1, 2	P-36-010316/ CA-SBR-10316H/013	Private (SCE); US Air Force, Edwards Air Force Base; California DOT	1911-1913	Transmission/ Utility Line	SCE Bishop Creek to San Bernardino "Tower Line"; SCE Bishop Creek Tower Line. Tower Line is composed of five modern-day segments of 70-feet tall double-circuit steel lattice towers, and conductors mounted on steel/wood poles that operate at 12kV and 115kV. The 5 segments are the Control-Haiwee-Inyokern No. 1 and Control-Coso-Haiwee-Inyokern, Kramer-Inyokern-Randsburg No. 1, Kramer-Victor 115 kV and Kramer-Roadway-Victor, Victor-Aqueduct-Hesperia, and Victor Apple-Valley Hesperia, and Arrowhead-Devil Canyon-Mojave Siphon-Shandin and Victor Calectric No. 2.	Listed in CRHR. Eligible under Criteria 1 and 3, and eligible as contributor to SCE Bishop Creek Hydroelectric System Historic District	Components in project API are to be removed and replaced. The removal and replacement of the historic transmission towers and conductor will result in a complete loss of integrity such that the historic line would no longer convey its identified significance.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
1	015	Private (SCE)	1907	Local Road	Plant 5 Road (1.37 miles long) is a partially-paved, one-lane road (unknown width) that makes two loops (around and within) the SCE Control Substation intersecting with the project APE in multiple locations.	Ineligible.	One guard site, one pull site, associated work and construction areas within boundary. Remove one 55-foot lattice steel dead-end tower. Install two 95-foot TSP monopoles. Remove and replace existing overhead subtransmission and telecom lines. Existing unpaved access roads will be graded and improved as needed.
1	020	Private (SCE); CSLC; CSLC; Private (LADWP); US Air Force; DOD NAWS China Lake, NAWS, China Lake	1911-1913	Local Road	Access Road to SCE Bishop Creek to San Bernardino "Tower Line" (Southern Sierras Power Company Access Road) is a system of paved and unpaved access and spur roads averaging 15-feet wide, 238 miles long, that follows Tower Line, intersecting with project APE continuously.	Ineligible.	Multiple guard sites, multiple pull sites, associated work and construction areas within boundary. Remove and replace existing overhead subtransmission and telecom lines. Install new underground telecom alignment. Existing unpaved access roads will be graded and improved as needed.
1	021	Private (SCE)	pre-1947	Access Road	Unpaved, one-lane access road, 11-feet wide and 1.20 miles long lies entirely within project APE. Trends parallel to Coyote Valley Road in the north. Road continues into northeast but resource alignment ends within Visual APE.	Ineligible.	Demo and pull sites within boundary.
1	023	Private (unidentified); BLM Bishop FO	pre-1880	Local Road	Coyote Valley Road; Coyote Valley Road; Coyote Creek Trail; Coyote Flat Road. Built before 1880, this road is a partially paved, one-lane road, 22 feet wide and approximately 12.34 miles long.	Eligible under Criterion 1.	Approximately 235 feet of Coyote Valley Road intersect the API at a Demo and Installation Site, a Shunt Removal Site, an Overhead Removal and Installation Site, and Access Roads.
1	025	Private (LADWP); BLM, Bishop	pre-1913	Local Road	Bir Road is a partially-paved, one-lane road, 20-feet wide, 3.3 miles long, almost entirely within project APE. Trends parallel to Coyote Valley Road in the south.	Ineligible.	Associated work and construction areas within boundary. Existing unpaved access roads will be graded and improved as needed. 300-feet west of Bir Road: Remove one 70-foot lattice steel suspension tower. Remove and replace existing overhead subtransmission and telecom lines.
1	026	Private (LADWP)	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 7-feet wide and 0.15 miles long, that lies entirely within project APE, providing access to a prospect mine located 145-feet south of road.	Ineligible.	Directly east of a demo site and pole installation site.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
1	027	Private (LADWP)	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 11-feet wide and 1.20 miles long, that lies entirely within project APE, providing access to the Coyote Flats region.	Ineligible.	Adjacent to a shunt removal site.
1	029	Private (LADWP); BLM, Bishop	pre-1947	Access Road	Rossi Hill Road is an unpaved, one-lane road, 20-feet wide and 0.42 miles long, that lies almost entirely within the project's Direct APE, providing access to Joseph W. Rossi property and the Rossi Tungsten Mine (Mineral Dome Prospect).	Ineligible.	Multiple pull sites, demo sites, installation sites, and a construction work yard. Possible use as a project access road.
1	032	Private (Estate of Jeanne E. Brown); BLM, Bishop	1945	Residential Building	301 Rossi Hill Road (110 x 260 feet) is a land Parcel (013-050-14) comprised of a residential complex including at least 3 buildings, including a wood-frame duplex dwelling (700 square feet), 2-story large barn, and additional outbuildings.	Ineligible.	Multiple demo sites and pull sites. Adjacent to access road.
1	033	Private (unidentified)	pre-1913	Two Lane Paved Road	Sunland Lane (Sunland Drive) is a paved, two-lane road, 25-feet wide and 3.8 miles long, that parallels U.S. Highway 395, with two termini in the south and terminates at an access road at boundary of Direct APE.	Ineligible.	Possible use as a project access road.
1	034	Private (unidentified)	ca. 1930s	Water Conveyance and Control	Ditch line and concrete cobble-lined spillway, 9-feet wide and 100 feet long, partially within Direct APE that provided water to mining operations at Rossi Hill Tungsten Mine.	Ineligible.	Multiple access roads intersect eastern portion of the ditch. Existing unpaved access roads will be graded and improved as needed.
1	036	Private (unidentified)	pre-1947-1975	Access Road	The unnamed road is an unpaved, one-lane road, 11-feet wide and 3 miles long, that lies entirely within Direct APE.	Ineligible.	One pull site. Possible use as a project access road. Existing unpaved access roads will be graded and improved as needed.
1	037	Private (unidentified)	pre-1913	Two Lane Paved Road	Sunland Reservation Road. Built before 1913, this paved, two-lane road is 21 feet wide and approximately 0.55 miles long.	Eligible under Criterion 1.	Visual impacts only. The proposed project will not adversely impact the resource.
1	041	Private (unidentified)	pre-1913	Historic Route	The unnamed road is an unpaved, one-lane road, 15-feet wide and 1.54 miles long, that intersects Direct APE at its terminus.	Ineligible.	One demo site and one installation site.
1	042	Private (unidentified)	pre-1913	Two Lane Paved Road	Gerkin Road. Built before 1913, this paved, two-lane road is 27 feet wide and approximately 3.8 miles long. Associated with Henry Gerken (Hinrich Gerken).	Eligible under Criterion 1.	Approximately 555 feet of Gerkin Road intersect the API at an Access Road and two Demo and Installation Sites. The proposed project will not adversely impact the resource.
1	047	Private (LADWP); BLM Bishop FO	pre-1913	Local Road	Collins Road. Built before 1913, this partially paved, two-lane road is 24 feet wide and approximately 4 miles long. It was constructed as a main wagon road through the Owens Valley and accesses the Owens River.	Ineligible	Approximately 730 feet of Collins Road intersect the API at three locations at a Guard Site, a Contractor Materials Yard, and an Access Road. The proposed

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
							project will not adversely impact the resource.
1	048	Private (LADWP); BLM Bishop FO	1913-1947	Two Lane Paved Road	County Road is a continuation of Inyo County Wagon Road. Built between 1913 and 1947, this partially paved, two-lane road is 23 feet wide and at least 12 miles long. Inyo County Wagon Road changes name to County Road at the API boundary.	Ineligible	Approximately 1.33-miles of County Road intersect the API at two locations at a Contractor Materials Yard, a Guard Site, and it as a project Access Road for almost a mile. The proposed project will not adversely impact the resource.
1	049	Private (unidentified)	pre-1975	Access Road	The unnamed road is an unpaved, one-lane road, 11-feet wide and 1.25 miles long, that lies entirely within project APE and parallels a perennial stream. Terminates at County Road.	Ineligible.	One guard site, one demo site, removal and installation sites. Existing unpaved access roads will be graded and improved as needed.
1	051	Private (LADWP)	1919-1946	Two Lane Paved Road	Keough Hot Springs Road is a paved, two-lane road, 23-feet wide and 0.9 miles long, that lies entirely within project APE. Provides access to Keough Hot Springs.	Ineligible.	One guard site. Existing unpaved access roads will be graded and improved as needed.
1	053	Private (LADWP)	1886	Water Conveyance and Control	Approximately 1.33-miles of County Road intersect the API at two locations at a Contractor Materials Yard, a Guard Site, and it as a project Access Road for almost a mile. The proposed project will not adversely impact the resource.	Eligible under Criterion 1.	Approximately 525 feet of Rawson Canal intersect the API at three Demo and Installation Sites, and Access Roads. The proposed project will not adversely impact the resource.
1	055	Private (LADWP)	pre-1949	Local Road	Big Pine Canal Road is an unpaved, one-lane road, 20-feet wide and 10.5 miles long, that courses through project APE. Parallels Big Pine Canal. Abruptly changes name west of Warren Lake.	Ineligible.	Multiple demo and shunt removal sites.
1	057	Private (unidentified), BLM, Bishop	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 15-feet wide and 0.65 miles long, that lies entirely within project APE.	Ineligible.	Multiple guard sites, demo sites, and removal and installations sites.
1	059	Private (unidentified)	pre-1913	Two Lane Paved Road	Reynolds Road is a partially paved, two-lane road, 36-feet wide and 1.32 miles long, that lies entirely within project APE.	Ineligible.	One demo site and two access roads. Existing unpaved access roads will be graded and improved as needed.
1	061	Private (unidentified)	pre-1913	Two Lane Paved Road	Baker Creek Road is a partially paved, two-lane road, 30-feet wide and 2.18 miles long, that lies entirely in project APE.	Ineligible.	One access road. Existing unpaved access roads will be graded and improved as needed.
1	062	Private (unidentified)	pre-1913	Two Lane Paved Road	Glacier Lodge Road is a paved, two-lane road built before 1913, 35 feet wide, and approximately 11 miles long. The road follows a valley along the lip of a mountainside directly north of Big Pine Creek.	Eligible under Criterion 1.	Approximately 161 feet of the road intersect the API at a Guard Site and Demo and Installation Sites. The

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
							proposed project will not adversely impact the resource.
1	071	Private (unidentified)	pre-1947	Access Road	Nancy Lane is a partially-paved, one-lane semicircular road, 20-feet wide, approximately 0.10-miles long.	Ineligible.	Unknown.
1	072	Private (unidentified)	pre-1913	Local Road	West Street is a one-land road, approximately 0.78-miles long. The road is paved in the northeast for approximately 0.47-miles and unpaved in the southwest for 0.31-miles.	Ineligible.	Unknown.
1	073	Private (unidentified)	pre-1947	Local Road	Old Glacier Road is an unpaved, one-lane road, 13-feet wide, approximately 0.11-mile long.	Ineligible.	Unknown.
1	074	Private (unidentified)	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 20-feet wide, approximately 0.45-miles long.	Ineligible.	Unknown.
1	077	Private (unidentified); BLM, Bishop	pre-1947	Water Conveyance and Control	Big Pine Creek Water System is a water system located approximately 0.20-miles west of the Big Pine Reservation that lies entirely in project APE. The resource contains a waterwheel (ca. pre-1947), a cylindrical water tank (ca. 1975-1987), a concrete lined ditch (ca. pre-1947), and a concrete lined canal (ca. 1967-1975).	Ineligible.	Five guard sites, three shunt removal sites, two transition pull sites, and existing and new access roads. Associated work and construction areas within site boundary. Remove three 65-foot wood pole. Remove ten 70-foot lattice steel suspension towers. Install new 105-foot TSP monopole. Install new 93-foot LWS monopole. Install new 110-foot TSP monopole. Install new 115-foot TSP monopole. Install new 130-foot dead-end TSP multi-pole. Remove and replace existing overhead subtransmission and telecom lines. Existing unpaved access roads will be graded and improved as needed.
1	078	Private (unidentified); BLM, Bishop	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 13-feet wide, approximately 0.35-miles long.	Ineligible.	Unknown.
1	079	Private (unidentified); BLM, Bishop	pre-1975	Access Road	The unnamed road is an unpaved, one-lane road, 13-feet wide, approximately 0.30-miles long that terminates at an unnamed road approximately 120-feet east of a water wheel feature.	Ineligible.	Unknown.
1	083	Private (unidentified); BLM, Bishop	pre-1975	Local Road	Big Pine Dump Road is a partially-paved one-land road, 30-feet wide, approximately 0.60-miles long.	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
1	084	Private (unidentified)	pre-1947	Two Lane Paved Road	Gregg Road is a paved, two-lane road, 20-feet wide, approximately 0.25-miles long, that initiates in the south from Big Pine Dump Road and terminates at the historic Woodsmen of the World Cemetery.	Ineligible.	Unknown.
1	086	Private (unidentified)	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 11-feet wide, approximately 1-mile long, that terminates approximately 400-feet south of Fish Springs Hatchery.	Ineligible.	Unknown.
1	087	Private (unidentified)	pre-1913	Access Road	The unnamed road is an unpaved, one-lane road, 13-feet wide, approximately 2-miles long.	Ineligible.	Unknown.
1	088	Private (unidentified); BLM, Bishop	pre-1913	Two Lane Paved Road	Fish Springs Road is a paved, two-lane road, 25-feet wide and 3 miles long, that lies entirely within project APE.	Ineligible.	One contractor material yard and two segments of unpaved access roads will be graded and improved as needed.
1	089	Private (unidentified)	pre-1947	Freeway/U.S Highway/State Route	Tinemaha Road (Old U.S. Highway 395) is a partially-paved, one-land road initiating west at Fish Springs Road, with two separate segments (approximately 600-meters apart) that merge into a single road. Terminates at a dead-end approximately 2-miles south of Fort Independence Reservation.	Ineligible.	Unknown.
1	090	Private (unidentified); BLM, Bishop	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 19-feet wide, approximately 0.86-miles long that terminates at the banks of Tinemaha Creek.	Ineligible.	Unknown.
1, 2	P-36-007545/ CA-SBR-7545H/ 093	Private (unidentified); BLM Bishop FO	1909-1934	Freeway/U.S Highway/State Route	U.S. Highway 395. Paved, 4-lane divided major highway, approximately 176-miles long. Highway encompasses S Main St, U.S. Highway 395 Business Loop, China Lake Blvd, W Inyokern Blvd, CA State Route 178, and North Sierra Highway. Approximately 1.81-miles of U.S. Highway 395 intersect the API at more than fourteen locations.	Eligible under Criterion 1.	Approximately 1.81-miles of U.S. Highway 395 intersect the API at more than fourteen locations including thirteen Removal Sites, nine Installation Sites, seven Guard Sites, four Shunt Removal Sites, six Pull Sites, overhead Removal and Installation Sites, and at existing and new Access Roads. The proposed project will not adversely impact the resource.
1	094	Private (unidentified); BLM, Bishop	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 9-feet wide, approximately 0.17-mile long.	Ineligible.	Unknown.
1	095	Private (unidentified); BLM, Bishop	pre-1913-1947	Local Road	East Elna Road is an unpaved, one-lane road, 15-feet wide, approximately 1-mile long.	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
1	100	Private (unidentified); BLM, Bishop	pre-1967	Access Road	The unnamed road is an unpaved, one-lane road, 9-feet wide, approximately 0.20-miles long, that terminates at the banks of the Owens River.	Ineligible.	Unknown.
1	101	Private (unidentified); BLM, Bishop	1907-1947	Local Road	Aberdeen Station Road is a partially paved, two-lane road, 30-feet wide, approximately 3.28-miles long. The road is paved on both sides of U.S. Highway 395 for approximately 2-miles and continues as an unpaved road east of the Owens River.	Ineligible.	Unknown.
1	102	Private (unidentified)	1913-1967	Access Road	The unnamed road is an unpaved, one-lane road, 12-feet wide, approximately 3.30-miles long. The road follows the transmission lines.	Ineligible.	Unknown.
1	109	Private (unidentified)	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 15-feet wide, approximately 1.76-miles, that terminates at the Los Angeles Aqueduct.	Ineligible.	Unknown.
1	110	Private (unidentified)	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 15-feet wide, approximately 3.24-miles, that initiates 20-feet east of the LA Aqueduct and terminates at the eastern banks of the Owens River.	Ineligible.	Unknown.
1	111	Private (unidentified)	pre-1907	Historic Route	North Coloseum Road is a partly paved road, between 6- and 20-feet wide, that spans approximately 4.5 miles.	Ineligible.	One contractor material yard.
1	112	Private (unidentified)	pre-1907	Historic Route	Coloseum Road is an unpaved, former wagon one-lane road, 14-feet wide and 3.12 miles long, that courses through the project APE.	Ineligible.	One contractor material yard.
1	114	Private (unidentified)	1949-1967	Access Road	The unnamed road is an unpaved, one-lane road, 21-feet wide, approximately 0.84-miles long, that terminates at an alluvial fan.	Ineligible.	Unknown.
1	115	Private (unidentified)	1948-1967	Access Road	The unnamed road is an unpaved, one-lane road, 20-feet wide, approximately 0.76-miles long, that terminates 15-feet west of a transmission line tower.	Ineligible.	Unknown.
1	116	Private (unidentified)	1967-1976	Access Road	The unnamed road is an unpaved, one-lane road, 10-feet wide, approximately 0.55-miles long.	Ineligible.	Unknown.
1	117	Private (unidentified)	1967-1976	Access Road	The unnamed road is an unpaved, one-lane road, 8-feet wide, approximately 0.10-miles long, that initiates approximately 0.58-miles west of Stevens Canal and terminates at a heavy concentration of high desert vegetation.	Ineligible.	Unknown.
1	119	Private (unidentified)	pre-1873	Historic Route	Mazourka Canyon Road; Citrus Road. Built before 1873, this resource is a former wagon road, now a partially paved, two-lane road between 15 to 20 feet wide. The road is approximately 17.80 miles long and travels through the Owens Valley and the Inyo National Forest.	Eligible under Criterion 1.	Approximately 2.48 miles of Mazourka Canyon Road intersect the API at 63 Installation Sites, a Guard Site, a Shunt Removal Site, and Access Roads. The

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
							proposed project will not adversely impact the resource.
1	120	Private (unidentified)	pre-1947	Access Road	The unnamed road is an unpaved, two-lane road, 25-feet wide, approximately 2.67-miles long.	Ineligible.	Unknown.
1	123	Private (unidentified)	ca. 1920s-1942	Local Road	Manzanar Reward Road is a partially paved road approximately 6.70 miles long. The road is divided into two segments: a paved north-south segment located west of US Highway 395 parallel to the historic Manzanar War Relocation Camp and a west-east segment located east of US Highway 395. Manzanar Reward Road was built ca. 1910s and modified in 1942.	Eligible under Criterion 1.	Approximately 740 feet of Manzanar Reward Road intersect the API at a Demo and Installation Site, a Construction Materials Yard, and Access Roads.
1	129	Private (unidentified)	pre-1907	Access Road	The unnamed road is an unpaved, one-lane road, 15-feet wide, approximately 1.78-miles long, that terminates along the banks of the Owens River.	Ineligible.	Unknown.
1	133	Private (unidentified)	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 10-feet wide, approximately 0.35-miles long, that terminates at an unnamed creek.	Ineligible.	Unknown.
1	134	Private (unidentified)	pre-1913	Water Conveyance and Control	Los Angeles Aqueduct Ditch is a concrete ditch approximately 26-feet wide, 3-feet deep, and 0.23 miles long that lies entirely within project APE.	Ineligible.	One shunt removal site. Associated work and construction areas within boundary. Remove 70-foot dead-end lattice steel tower. Install 80-foot suspension TSP multi-pole. Remove and replace existing overhead subtransmission and telecom lines. Existing unpaved access roads will be graded and improved as needed.
1	141	Private (unidentified)	pre-1955	Two Lane Paved Road	The unnamed road is an unpaved, two-lane road, 22-feet wide, approximately 0.31-miles long.	Ineligible.	Unknown.
1	145	Private (unidentified)	1967-1975	Access Road	The unnamed road is an unpaved, one-lane road, 15-feet wide, approximately 0.18-miles long, that terminates at an unnamed road approximately 376-feet west of the Owens River.	Ineligible.	Unknown.
1	147	Private (unidentified)	pre-1907	Two Lane Paved Road	Lone Pine Narrow Gauge Road is a paved, two-lane road, 25-feet wide, approximately 3.36-miles long, that terminates east of the Owens River at Owenyo Lone Pine Road.	Ineligible.	Unknown.
1	149	Private (unidentified)	pre-1947	Local Road	The unnamed road is an unpaved, two-lane road, 20-feet wide, approximately 0.92-miles, that terminates at an unnamed road located approximately 500-feet west of the Owens River.	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
1	150	Private (unidentified)	1955-1975	Water Conveyance and Control	LADWP Agricultural Reservoir is an agricultural reservoir that measures approximately 0.20-miles by 0.36-miles, with a total surface area of approximately 1.11-miles. The resources includes the reservoir area, composed of five separate reservoirs: 2 are narrow rectangles, 2 are triangles, 1 is a wider rectangle, all with rounded corners. The reservoirs are located on a 350-acre Parcel, directly north of Sub Station Road, directly east of Esha Street, and directly west of Owens River.	Ineligible.	Unknown.
1	151	Private (unidentified)	pre-1907	Two Lane Paved Road	Sub-Station Road. Early main wagon road and former access route to transmission lines and the Owens River built before 1907. Now, this partially paved, two-lane road is 20 feet wide and approximately 1.46-miles long. Terminates at a gated property	Eligible under Criterion 1	Approximately 0.65 miles of Sub-Station Road intersect the API at a Guard Site, a Demo Site and two Installation Sites. Sub-Station Road abuts two Demo and Installation Sites and a Construction Materials Yard. The proposed project will not adversely impact the resource.
1, 2	P-15-015209/P-14-004607/P-15-003366/CA-INY-4607H/CA-KER-10470H/ FT2-BA-45H; 152	CSLC; Private (unidentified); DOD NAWS China Lake, NAWS, China Lake; BLM, Ridgecrest; BLM, Bishop	1905-1910; pre-1944	Railroad	Southern Pacific Railroad is a historic railroad including tracks, grade and other railroad features (n=296) with a series of branches/spur lines that once spanned into 15 states for 76 miles. Two of the Southern Pacific lines are located in the area under review commencing in Lone Pine and ending north of the Randsburg Mining District: the Southern Pacific Mojave-Owenyo Branch and the U.S. Government Railroad. This resource includes multiple concrete culverts, concrete bridges, stone retaining walls, wooden loading dock and historic debris scatter.	Ineligible.	Unknown.
1	156	Private (unidentified)	pre-1907; 1947	Freeway/U.S Highway/State Route	California State Route 136 (Route 190) is a paved, two-lane road, 23-feet wide, approximately 17.5-miles long.	Ineligible.	Unknown.
1	157	Private (unidentified)	pre-1947	Two Lane Paved Road	Aqueduct Access Road is an unpaved, two-lane road, 22-feet wide, approximately 0.39-miles long, that terminates at a road loop located 89-feet east of the Los Angeles Aqueduct.	Ineligible.	Unknown.
1	158	Private (unidentified); BLM, Bishop	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 10-feet wide, approximately 1.22-miles long. The road initiates east from an unnamed road, intersects the old Southern Pacific Railroad bed and terminates at a transmission line access road.	Ineligible.	Unknown.
1	160	Private (unidentified); BLM, Bishop	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 20-feet wide, approximately 2.76-miles long, that terminates at an unnamed road just north of the dry Owens Lake bed.	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
1	164	Private (unidentified); BLM, Bishop	pre-1947	Access Road	The unnamed road is an unpaved, two-lane road, 27-feet wide, approximately 0.31-miles long, that terminates at an unnamed road that parallels the Los Angeles Aqueduct.	Ineligible.	Unknown.
1	165	Private (unidentified); BLM, Bishop	pre-1947	Access Road	The unnamed road is a paved, one-lane road, 35-feet wide, approximately 0.37-miles long, that terminates at an unnamed road approximately 25-feet east of the Los Angeles Aqueduct.	Ineligible.	Unknown.
1	166	Private (unidentified); BLM, Bishop	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 11-feet wide, approximately 0.24-miles long, that terminates at a dead end approximately 700-feet from the Los Angeles Aqueduct.	Ineligible.	Unknown.
1	167	Private (unidentified); BLM, Bishop	1928-1947	Local Road	Carroll Creek Road is an unpaved, two-lane road, 25-feet wide, approximately 1-mile long that bisects the Los Angeles Aqueduct terminating at a private parcel.	Ineligible.	Unknown.
1	168	Private (unidentified); BLM, Bishop	ca. 1927 -1947	Local Road	Bartlett Road is an unpaved, one-lane road, 16-feet wide, approximately 1.15-miles long, that terminates along the northwestern shore of Owens Lake at the Clark Chemical Company evaporation ponds.	Ineligible.	Unknown.
1	169	BLM, Bishop	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 12-feet wide, approximately 0.11-miles long, that terminates at an unnamed road approximately 82-feet east of the Los Angeles Aqueduct.	Ineligible.	Unknown.
1	170	BLM, Bishop	pre-1947	Access Road	The unnamed road is an unpaved, two-lane road, 22-feet wide, approximately 0.23-miles long, that terminates at an unnamed road located approximately 75-feet east of the Los Angeles Aqueduct.	Ineligible.	Unknown.
1	171	BLM, Bishop	1947-1955	Access Road	The unnamed road is an unpaved, one-lane road, 15-feet wide, approximately 1.15-miles long.	Ineligible.	Unknown.
1	172	BLM, Bishop	pre-1947	Access Road	The unnamed road is an unpaved road, 24-feet wide, approximately 1.36-miles long, that terminates at an unnamed road approximately 600-feet east of the Los Angeles Aqueduct.	Ineligible.	Unknown.
1	173	BLM, Bishop	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 14-feet wide, approximately 0.22-miles long, that terminates at a Los Angeles Aqueduct bridge.	Ineligible.	Unknown.
1	175	BLM, Bishop	pre-1947	Two Lane Paved Road	The unnamed road is an unpaved, two-lane road, 40-feet wide, approximately 0.40-miles long, that terminates at Cottonwood Powerhouse Road.	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
1	176	BLM, Bishop	pre-1907	Two Lane Paved Road	Cottonwood Road is a partially paved, two-lane road, 26-feet wide, approximately 4.2-miles long. The road follows Cottonwood Creek through the canyon.	Ineligible.	Unknown.
1	177	BLM, Bishop	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 16-feet wide, approximately 0.39-miles long.	Ineligible.	Unknown.
1	178	Private (unidentified); BLM, Bishop	pre-1947	Local Road	Los Angeles Aqueduct Access Road is an unpaved road, 35-feet wide, approximately 0.87-miles long. The road crosses the Los Angeles Aqueduct and terminates at an unnamed Los Angeles Aqueduct facility.	Ineligible.	Unknown.
1	179	Private (unidentified); BLM, Bishop	pre-1947	Access Road	Unnamed Los Angeles Aqueduct Access Road is an unpaved, one-lane road, 13-feet wide, approximately 0.74-miles long, that terminates at an unnamed road approximately 230-feet east of the Los Angeles Aqueduct.	Ineligible.	Unknown.
1	180	Private (unidentified); BLM, Bishop	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 10-feet wide, approximately 0.51-miles long, that terminates at an unnamed road located approximately 0.41-miles east of the Los Angeles Aqueduct.	Ineligible.	Unknown.
1	183	Private (unidentified); BLM, Bishop	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 11-feet wide, approximately 0.21-miles long, that terminates at an unnamed road that parallels the Los Angeles Aqueduct.	Ineligible.	Unknown.
1	184	BLM, Bishop	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 9-feet wide approximately 0.14-miles long, that terminates at an unnamed road located beside the Los Angeles Aqueduct.	Ineligible.	Unknown.
1	185	BLM, Bishop	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 14-feet wide, approximately 0.27-miles long, that terminates at an unnamed road located alongside the Los Angeles Aqueduct.	Ineligible.	Unknown.
1	187	Private (unidentified); BLM, Bishop	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 11-feet wide, approximately 0.32-miles long. The road is a U-shaped route and terminates approximately 60-feet east of the old Southern Pacific Railroad grade.	Ineligible.	Unknown.
1	206	Private (A. Chang)	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 21-feet wide, approximately 1.62-miles long, that terminates at a wash located approximately 0.44-miles south of a California Alkali Company evaporation pool.	Ineligible.	Unknown.
1	207	Private (unidentified)	ca. 1873	Freeway/U.S Highway/State Route	California State Route 190; Death Valley Scenic Byway. Built before 1873, this historic trail was improved over time for wagon and automobile travel. Now, it is a paved two-lane road, 14-feet wide with	Eligible under Criterion 1	Approximately 432 feet of California State Route 190 intersect the API at a

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
					1-foot shoulder, approximately 187.6-miles long. This resource has a Scenic Byway designation. Portions of road follow the alignment of former immigrant trail and toll road.		Shunt Removal Site, a Demo Site, and at a Contractor Materials Yard.
1	208	Private (Crawford Law Office)	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 10-feet wide, approximately 2.07-miles long, that terminates approximately 240-feet southeast of a transmission line tower.	Ineligible.	Unknown.
1	211	Private (Georgine Zamorski); BLM, Ridgecrest	pre-1947	Two Lane Paved Road	Fall Road is a partially paved, two-lane road, 22-feet wide, approximately 7.14-miles long that runs along the Los Angeles Aqueduct. A small segment of the road (approximately 0.87-miles) is paved initiating from the Los Angeles Aqueduct to U.S. Highway 395.	Ineligible.	Unknown.
1	214	Private (unidentified); BLM, Ridgecrest	1967-1975	Access Road	The unnamed road is an unpaved, one-lane road, 16-feet wide, approximately 0.48-miles long, that terminates at access road to SCE Control-Haiwee-Inyokern 115kV Transmission Line (a modern-day segment of the SCE Bishop Creek to San Bernardino 89kV "Tower Line").	Ineligible.	Unknown.
1	215	Private (unidentified); BLM, Ridgecrest	pre-1947	Local Road	Walker Creek Road is an unpaved, one-lane road, 25-feet wide, approximately 5.5-miles long. The road intersects U.S. Highway 395 and the Los Angeles Aqueduct, terminating at the banks of Walker Creek in the Inyo National Forest.	Ineligible.	Unknown.
1	216	Private (Richard Thies); BLM, Ridgecrest	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 11-feet wide, approximately 0.39-miles long. The road initiates south from the access road to SCE Bishop Creek to San Bernardino "Tower Line" located approximately 55-feet west of a center pivot irrigation system.	Ineligible.	Unknown.
1	218	Private (Robert and Eursell Jett); BLM, Ridgecrest	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 12-feet wide, approximately 0.38-miles long. The road initiates east from Cactus Flats Road and terminates at a private Parcel (Parcel 033-110-12).	Ineligible.	Unknown.
1	219	Private (unidentified; BLM, Ridgecrest	pre-1947	Two Lane Paved Road	Cactus Flats Road is a partially-paved, two-lane road, 30-feet wide, approximately 10.4-miles long, that terminates at a roundabout located in Little Cactus Flats. Approximately 1.36-miles of the road is paved initiating from U.S. Highway 395 and the remaining segment is unpaved.	Ineligible.	Unknown.
1	221	Private (Peter & Eneida Salerno); BLM, Ridgecrest	1958	Residential Building	751 Cactus Flats Road consists of two residential structures, 1,404-square feet, located in Olancha. This single family dwelling constructed in the Minimal Traditional style features a gabled roof. The smaller wooden dwelling constructed in the Vernacular style is unoccupied and dilapidated.	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
1	222	Private (unidentified); BLM, Ridgecrest	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 13-feet wide, approximately 0.41-miles long.	Ineligible.	Unknown.
1	223	Private (unidentified); BLM, Ridgecrest	pre-1947	Two Lane Paved Road	The unnamed road is an unpaved, two-lane road, 20-feet wide, approximately 3.35-miles long. The road initiates from North Haiwee Reservoir Dam, parallels the Los Angeles Aqueduct and intersects U.S. Highway 395.	Ineligible.	Unknown.
1	224	Private (unidentified); BLM, Ridgecrest	pre-1947	Local Road	Los Angeles Aqueduct Road is an unpaved, one-lane road, 10-feet wide, approximately 2.92-miles long.	Ineligible.	Unknown.
1	225	Private (unidentified); BLM, Ridgecrest	pre-1947	Two Lane Paved Road	North Haiwee Road is an unpaved, two-lane road, 37-feet wide, approximately 0.85-miles long, that terminates at the Los Angeles Aqueduct.	Ineligible.	Unknown.
1	226	Private (unidentified); BLM, Ridgecrest	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 10-feeet wide, approximately 0.54-miles long, that terminates at the old Southern Pacific Railroad bed located approximately 0.30-miles east of U.S. Highway 395.	Ineligible.	Unknown.
1	227	Private (unidentified); BLM, Ridgecrest	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 10-feet wide, approximately 0.30-miles, that terminates at the access road to SCE Bishop Creek to San Bernardino "Tower Line" located approximately 60-feet east of an SCE Control-Haiwee-Inyokern 115kV Transmission Line tower.	Ineligible.	Unknown.
1	228	Private (unidentified); BLM, Ridgecrest	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 10-feet wide, approximately 0.38-miles long. The road terminates at an access road to SCE Bishop Creek to San Bernardino "Tower Line" located approximately 34-feet south of an SCE Control-Haiwee-Inyokern 115kV Transmission Line tower.	Ineligible.	Unknown.
1	229	Private (unidentified); BLM, Ridgecrest	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 10-feet wide, approximately 0.36-miles long. The road initiates from the access road to SCE Bishop Creek to San Bernardino "Tower Line" located approximately 139-feet north of an SCE Control-Haiwee-Inyokern 115kV Transmission Line tower.	Ineligible.	Unknown.
1	230	Private (unidentified); BLM, Ridgecrest	pre-1947	Access Road	Sage Flat Road is a partially paved two-lane road, width unknown, approximately 6.17-miles long, that terminates at the Olancha Pass Trailhead. The road is paved for approximately 3.25-miles between	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
					U.S. Highway 395 and the Sage Flats residential community. The remainder of the road is unpaved.		
1	233	Private (unidentified)	pre-1947	Local Road	Lakeview Road is an unpaved, two-lane road, 30-feet wide, approximately 1.5-miles long. Terminates at the southern end of North Haiwee Reservoir.	Ineligible.	Unknown.
1	235	Private (unidentified); BLM, Ridgecrest	1967-1978	Access Road	The unnamed road is an unpaved, one-lane road, 8-feet wide, approximately 0.72-miles long, that terminates approximately 141-feet west of the Los Angeles Aqueduct.	Ineligible.	Unknown.
1	236	Private (unidentified); BLM, Ridgecrest	pre-1947	Two Lane Paved Road	Haiwee Reservoir Road is a paved, two-lane road, 30-feet wide, approximately 3.3-miles long, that terminates approximately 2-miles south of South Haiwee Reservoir and continues as an unnamed road past the SCE Haiwee Substation Complex.	Ineligible.	Unknown.
1	237	Private (unidentified); BLM, Ridgecrest	pre-1947	Local Road	South Haiwee Loop Road is an unpaved, one-lane road, 15-feet wide, approximately 0.82-miles long, that terminates in the south at an unnamed road located approximately 250-feet west of the Los Angeles Aqueduct.	Ineligible.	Unknown.
1	239	Private (unidentified); BLM, Ridgecrest	1967-1975	Local Road	Second Los Angeles Aqueduct Road is an unpaved, one-lane road, 18-feet wide, that follows Second Los Angeles Aqueduct for approximately 6.8-miles. Initiates in the northwest where the Los Angeles Aqueduct branches off into its second aqueduct segment and terminates where the road changes name to the Los Angeles Aqueduct Road.	Ineligible.	Unknown.
1	245	Private (unidentified); BLM, Ridgecrest	pre-1947-1967	Local Road	Dunmovin Road is an unpaved, one-lane road, 15-feet wide, approximately 2.6-miles long. The road initiates west from the Second Los Angeles Aqueduct, travels over the Los Angeles Aqueduct, through the unincorporated town of Dunmovin. Road terminates at an open pit mine in the east.	Ineligible.	Unknown.
1	246	Private (unidentified); BLM, Ridgecrest	1947-1975	Access Road	The unnamed road is an unpaved road, 15-feet wide, approximately 1.1-miles. The road runs south of a building located north of the Terra-Gen Power Facility and shares 266-feet with the access road to SCE Bishop Creek to San Bernardino "Tower Line".	Ineligible.	Unknown.
1	248	BLM, Ridgecrest	pre-1947	Access Road	The unnamed road is an unpaved road, 15-feet wide, approximately 2.34-miles long, that terminates at a wash southwest of the Terra-Gen Power Facility.	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
1	249	BLM, Ridgecrest	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 17-feet wide, 1.35-miles long, that initiates east of the First Los Angeles Aqueduct. Terminates at the access road to SCE Bishop Creek to San Bernardino "Tower Line."	Ineligible.	Unknown.
1	250	BLM, Ridgecrest	pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 15-feet wide, approximately 1-mile long, that terminates at the access road to SCE Bishop Creek to San Bernardino "Tower Line."	Ineligible.	Unknown.
1	251	BLM, Ridgecrest	1939-1948	Two Lane Paved Road	Gill Station Coso Road is a partially paved, two-lane road, 20-feet wide, approximately 11-miles long, that initiates from U.S. Highway 395 and continues east as a paved road for approximately 5.55-miles. The road continues unpaved. Terminates at a fork east of Coso Hot Springs.	Ineligible.	Unknown.
1	253	BLM, Ridgecrest	pre-1948	Access Road	The unnamed road is an unpaved, one-lane road, 7-feet wide, approximately 4-miles long, that terminates at the First Los Angeles Aqueduct.	Ineligible.	Unknown.
1	254	BLM, Ridgecrest	pre-1948	Access Road	The unnamed road is an unpaved, one-lane road, between 12 and 15-feet wide, approximately 4.30-miles long. Road crosses both the First and Second Los Angeles Aqueducts.	Ineligible.	Unknown.
1	257	Private (unidentified); BLM, Ridgecrest	1948-1954	Local Road	Cinder Road is a partially-paved road, width unknown, approximately 9-miles long, that terminates at Fossil Falls Access Road within Twin Mountain Rock Venture.	Ineligible.	Unknown.
1	262	Private (Little Lake Ranch, Inc.)	1919	Water Conveyance and Control	Little Lake; Owens Little Lake. Natural body of water and location of former water conveyance structure. The natural lake was spring fed creating a tule marsh in the bed of the Owens River. It was dammed in 1919 to create a "real" lake as part of a hotel development project. Today, only the body of water exists.	Eligible under Criterion 1.	An area of approximately 1,000 feet by 160 feet of Little Lake intersects the API at three locations. In the east, it intersects Telecom Overhead installation. In the middle portion, it intersects with a Demo and Pull site. In the west, the bank of the lake runs along an Access Road. The proposed project will not adversely impact the resource.
1	276	Private (unidentified)	pre-1943	Local Road	Black Mountain Blvd is an unpaved road, 11-feet wide in the north and up to 30-feet wide in the south, approximately 2.3-miles long, that terminates in the SCE Transmission corridor.	Ineligible.	Unknown.
1	277	Private (unidentified); DOD NAWS China Lake,	pre-1943	Local Road	Agnew Avenue is an unpaved road, 10-feet wide, approximately 3-miles long, that terminates at the SCE transmission line corridor.	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
1	281	Private (unidentified); DOD NAWS China Lake	1943-1948	Local Road	Neal Ranch Road is an unpaved road, 20-feet wide, approximately 3.1-miles long.	Ineligible.	Unknown.
1	295	Private (unidentified); DOD NAWS China Lake	1948-1971	Access Road	The unnamed road is an unpaved road, 14-feet wide, approximately 3.2-miles long. This road merges into the access road to SCE Bishop Creek to San Bernardino 89kV "Tower Line".	Ineligible.	Unknown.
1	297	Private (unidentified); DOD NAWS China Lake	1915-1943	Two Lane Paved Road	Athel Avenue is a partially paved road, 20-feet wide, approximately 3.5-miles long. The road is paved between California State Route 14 and Brown Road. The remainder is unpaved.	Ineligible.	Unknown.
1	299	Private (unidentified); DOD NAWS China Lake	1948-1971	Local Road	3 Pines Canyon Road is an unpaved road, 35-feet wide, that is approximately 1.1-miles long, that terminates at the access road to SCE Bishop Creek to San Bernardino 89kV "Tower Line" intersection.	Ineligible.	Unknown.
1	310	Private (unidentified); DOD NAWS China Lake	1948-1967	Access Road	The unnamed road is an unpaved road, former railroad grade, 10-feet wide, approximately 4.4-miles long.	Ineligible.	Unknown.
1	311	Private (unidentified); DOD NAWS China Lake	pre-1952	Access Road	The unnamed road is an unpaved road, 18-feet wide, approximately 7.5-miles long.	Ineligible.	Unknown.
1	315	Private (unidentified)	1915-1943	Freeway/U.S Highway/State Route	California State Route 178; West Inyokern Road; East Inyokern Road. Built between 1915-1943, this resource is the eastern segment of the 166-mile three county state route. This portion spans approximately 38-miles through the Indian Wells and Searles Valley. It is paved, with four-lanes, a central median, and 40 feet wide.	Eligible under Criterion 1.	Approximately 1,003 feet of California State Route 178 intersect the API at two locations at a Guard Site, an Overhead Installation Site, and Access Roads. It also runs adjacent to two Contractor Materials Yards (at SCE Inyokern Substation Complex and at SCE Ridgecrest Service Center).
1	P-14-003802/ CA-INY-3802H/ 125	Private (unidentified)	1942	Other	**Manzanar National Historic Site.** Former Japanese internment camp (6,200 acres) established during World War II, located west of the Eastern Sierras in the Owens Valley. It was one of ten Military and National Defense-style camps established as a result of Executive	Listed in the NRHP. Listed in the CRHR.	Visual impacts only. The proposed project will not adversely impact the resource.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
					Order 9066, signed by President Franklin D. Roosevelt on February 19, 1942. From 1942 to 1945 the relocation camp was home to over 10,000 men, women and children. Components include a 500-acre housing section enclosed by barbed wire, eight guard towers, Military and National Defense police housing, a cemetery, an airport, a reservoir, a sewage treatment plant, and agricultural fields for subsistence living.		
1	P-14-004589/ CA-INY-4589H/ 132	Private (unidentified)	1887-1893	Water Conveyance and Control	Stevens Ditch (Stevens Canal) is an earthen irrigation system, historically 15-miles long, that lies entirely within project APE. No associated components.	Ineligible.	Five guard sites, one shunt removal site, two pull sites, . Associated work and construction areas within boundary. Remove ten 70-foot lattice steel suspension towers. Install two 93-foot suspension TSP monopoles. Install 97-foot suspension LWS monopole. Install 110-foot suspension TSP monopole. Install two 115-foot suspension TSP monopoles. Remove and replace existing overhead subtransmission and telecom lines. Existing unpaved access roads will be graded and improved as needed.
1	P-14-004590/ CA-INY-4590H/ 050	Private (LADWP)	1850-1910	Two Lane Paved Road	Inyo County Wagon Road. Built between 1850 and 1910, this unmaintained, partially paved, historic wagon road averages 20 feet wide and is approximately 70 miles long. Associated artifacts include 3 house sites, 5 trash dumps, and an associated roadway yielding domestic artifacts from 1880-1920. Today, discontinuous segments of the historic road remain alongside present U.S. Highway 395 and are used as a secondary access road. Two pairs of parallel linear depressions lie within the API.	Eligible under Criteria 1 and 4	Approximately 600 feet of the Inyo County Wagon Road intersect the API at three locations. In the north, it intersects a Pull Site, and a Demo and Installation Site. In the south, it intersects a Demo and Installation Site, and Access Roads. The proposed project will not adversely impact the resource.
1	P-14-004591/ CA-INY-4591H/ 097	Private (unidentified); BLM Ridgecrest FO	pre-1913	Water Conveyance and Control	The Los Angeles Aqueduct is an approximately 388-miles long water conveyance and power generation system built before 1913. It was extended north to Bishop in 1926 and to Mono Lake in 1944. Components include unlined channels, concrete-lined channels, flumes, conduit, siphons, tunnels, spillways, reservoirs, dams, and power plants.	Listed in the CRHR. Eligible under Criteria 1, 2, 3, and 4.	Approximately 0.67 miles of the Los Angeles Aqueduct intersect the API at eight locations including five Shunt Removal Sites, three Demo Sites, Installation Site, a Pull Site, two Guard Sites, and an Access Road. The proposed project will not adversely impact the resource.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
1	P-14-004677/ CA-INY-4677H/ 096	Private (unidentified); BLM, Bishop	pre-1923	Local Road	Tinemaha Dam Haul Road is a raised, unpaved, one-lane road, 15-feet wide, approximately 1.2-miles long that initiates from the southwestern end of the Tinemaha Dam, intersects the former Southern Pacific Railroad grade and the access road for the "Tower Line".	Ineligible.	Unknown.
1	P-14-004681/ CA-INY-4681H/ 082	Private (unidentified); BLM, Bishop	ca. 1880s	Water Conveyance and Control	Steward Ranch Canal is a water conveyance system with three features: a weir, a canal, and ancillary irrigation ditch system. The main canal, 10-feet wide, approximately 2.4-miles long initiating at Big Pine Creek and terminating at the Steward Ranch. The ditches measure 12-feet from berm to berm, 3-feet wide at the bottom, with a depth of 6 to 12-inches.	Ineligible.	Unknown.
1	P-14-004682/ 054	Private (LADWP)	1886-1893	Water Conveyance and Control	Big Pine Canal is an artificial water conveyance system, 20-feet wide and 14.4 miles long, that courses through the project APE, consisting of Big Pine Canal, irrigation ditch with five associated sub features, the old route of the canal from Big Pine to Fish Springs, and 5 sub-features including lateral ditches (and associated field ditches, wooden boxes and gates), berms (with an associated catch basin).	Ineligible.	Two guard sites and one shunt removal site. Associated work and construction areas within boundary. Remove 78-foot lattice steel suspension tower (85-feet north). Install new 115-foot TSP monopole (120 feet of east of canal). Remove and replace existing overhead subtransmission and telecom lines. Existing unpaved access roads will be graded and improved as needed.
1	P-14-004825/ 014	Private (SCE)	1913	Transmission/ Utility Line	Bishop Creek Hydroelectric System Plant 6-Control-Plant 5 55kV Sub-Transmission Line (1.63 miles long) is an electrical 55kV sub-transmission line extended and modified over time. Poles are spaced 100-meets apart. Components: 17 steel lattice poles (ca. 1913-1918), three wood poles (ca.2005), one steel lattice tower, switch towers at Plant 6, hydro building at Plant 5.	Ineligible.	One guard site and associated work and construction areas within boundary. Remove one 55-foot dead-end lattice steel tower. Install two 95-foot TSP monopoles, and associated construction areas. Remove and replace existing overhead subtransmission and telecom lines. Existing unpaved access roads will be graded and improved as needed.
1	P-14-005022/ CA-INY-4943H/ 124	Private (unidentified)	1942-1945	Other	Manzanar Federal Airport; Inyo County Airport. Built between 1942-1945, abandoned World War II era airport with 10 associated components. Components include a concrete powerhouse building, two concrete main hanger foundations, two concrete parking areas, potential dump and oil disposal pit, a windsock circle with concrete pillar, an asphalt airport taxiway, two 5,000-foot-long asphalt-paved runways.	Eligible under Criterion 1.	A Contractor Material Yard overlaps the Manzanar Federal Airport.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
1	P-14-005023/ CA-INY-4944H/ 127	Private (unidentified)	1942	Other	Manzanar Relocation Center Sewer System (48 x 315 feet) is a sewage treatment system with 17 associated components including foundations and structures entirely within project APE.	Ineligible.	One pull site. Associated work and construction areas within site boundary. Remove 70-foot dead-end lattice steel tower. Install 120-foot dead-end TSP multi-pole. Remove and replace existing overhead subtransmission and telecom lines. Existing unpaved access roads will be graded and improved as needed.
1	P-14-007130/P-14-007131/268	DOD NAWS China Lake, BLM, Ridgecrest	pre-1915, 1928, 1937	Freeway/U.S Highway/State Route	Highway 23 (Owens Valley Midland Trail) is a partially-paved road that parallels and crosses U.S. Highway 23, 18-feet wide, approximately 11-miles long. The route roughly follows the alignment of a former 1915 wagon route known as the Midland Trail, a stagecoach and freight road with at least 7 stage lines. Some dirt and rock alignments are still present. This resource includes a trail, rock-lined path and clearing, small concrete foundation (2001), and an associated 1930s-1960s refuse concentration with church-key opened cans, Model T tires (2014), horseshoe (2001), 2 historic isolates (2014): mother of pearl button, Dietz highway torch, as well as a prehistoric loci (2014) including sparse scatter of 18 obsidian and angular waste debitage.	Ineligible.	Unknown.
1	P-14-007648/ CA-INY-6396H/ 193	CSLC; CDFW, Cartago Wildlife Area; Private (unidentified); BLM, Bishop	1917	Railroad	California Alkali Plant Spur is a railroad spur grade, 12-feet wide, approximately 0.9-miles long. Alternates between a raised grade and minor cuts to create a level grade. The spur branches off the old Jawbone Southern Pacific line just north of Cartago and heads southeast to the ruins of the California Alkali Plant. This resources includes a railroad grade, box culvert, abutments. The rails and ties have been removed. At the crossing of one large seasonal drainage are the concrete abutments for a short bridge spanning 13-feet and 3-inches. The abutments are identical, measuring 14-feet wide, 7-feet high, and 28-inches thick. Running the length of the grade on the east side is an iron pipe.	Ineligible.	Unknown.
1	P-14-007649/ CA-INY-6397H; 186	Private (unidentified); BLM, Bishop	1880-1914	Water Conveyance and Control	Ditch #3 is a hand-dug earthen ditch, 2.08 miles long, that lies entirely in project APE. Top of ditch is between 3 and 6-feet wide. Bottom of ditch is between 1 and 3-feet wide. The height of the ditch is between 0.5 to 2.5-feet.	Ineligible.	Two shunt removal sites. Associated work and construction areas within site boundary. Remove two 70-foot dead-end lattice steel towers. Install two new 120-foot dead-end TSP multi-poles. Remove and replace existing overhead subtransmission and telecom lines.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
							Three access roads. Existing unpaved access roads will be graded and improved as needed.
1	P-14-008141/ 197	CSLC; CDFW, Cartago Wildlife Area; Private (Wendy Benbrooke); BLM, Bishop	1870s	Other	Cartago Townsite (Cartago) is a townsite that is the location of a former station on the Owenyo Branch of the Southern Pacific Railroad (SPRR) on the western shore of Owens Lake. The Cartago Townsite is the location of a company town constructed by the California Alkali Company in 1917. This resource includes several original 1917 buildings (including schoolhouse, 4 small employee houses, 9 large houses), remains of a brick oven, brick vault from the plant office, soda evaporating ponds on the lakebed, concrete foundations and substructures of the old manufactory, and the bed of the railroad spur that once served the plant.	Ineligible.	Unknown.
1	P-14-008745/ CA-INY-6862/ 099	Private (unidentified)	1932	Water Conveyance and Control	Abandoned LADWP earthen drain ditch, between 15-feet and 30-feet wide and between 6-feet and 10-feet deep, approximately 1,531-feet long. It was constructed to drain water from the Carson and Colorado Railroad track (in operation 1883-1960). Components in the Indirect API consist of ditch headgate (constructed of milled lumber and steel) and an adjacent stilling well set in concrete.	Eligible under Criterion 1.	Approximately 348 feet of ditch intersect the API at an Overhead Removal and Installation Site, and at an Access Road. The proposed project will not adversely impact the resource.
1	P-14-008844/ CA-INY-6956/ 242	Private (unidentified); BLM Ridgecrest FO	1927	Substation	SCE Haiwee Substation Complex; Haiwee Powerhouse. Built in 1927, this resource is a 5.4MW hydroelectric substation complex. Components within API include a cast concrete power plant, three fenced substations containing transformers, powerlines, wooden water tank, surge chamber, portion of buried penstock, open concrete-lined canal, buried aqueduct, residential structure, garage, shed, valve boxes, driveways and parking areas, portion of rock retaining wall, rain gauge, and associated artifacts.	Eligible under Criterion 1.	An area of approximately 205 feet by 270 feet of the SCE Haiwee Substation Complex intersects the API at a Pull Site, Installation Site, and Access Road. The proposed project will not adversely impact the resource.
1	P-14-009477/ CA-INY-7397 (for site)/269	DOD NAWS China Lake, NAWS, China Lake; BLM, Ridgecrest	ca.1912	Other	North-south oriented, linear retaining wall that lines the west drainage bank east of U.S. Highway 395 near the base of a basalt escarpment. The wall is approximately 45-meters long and 3 to 4-feet tall composed of large volcanic rocks stacked at least 4 tiers high that partially enclose the east side of a transmission line tower (T-856). Associated artifacts include 2 biface reduction obsidian flakes and 3 sanitary cans.	Ineligible.	Unknown.
1	P-14-012883/ 046	Private (LADWP); BLM, Bishop	1950-1952	Transmission/ Utility Line	LADWP Owens Gorge 230kV Transmission Line (248 miles long) is an electrical 230kV transmission line, towers/poles, conductors and associated wire that parallel project corridor, intersecting project area. Line meets with 500kV Pacific Intertie at Highway 395 in Direct APE.	Ineligible.	Two pull sites and one demo site. Associated work and construction areas within boundary. Remove and replace existing overhead subtransmission and

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
					This resource contains approximately 80-feet tall dead-end and suspension steel lattice towers, and conductors mounted on 80-feet steel/wood poles.		telecom lines. Existing unpaved access roads will be graded and improved as needed.
1	P-15-011274/ CA-KER-6624H/ CA-INY-6545H/ 282	Private (unidentified); DOD NAWS China Lake	1875	Historic Route	Nadeau Road; Darwin Road; Buckley and Kelly Stage Road; Remi Nadeau Freight Road System; Mt. Springs Canyon Road. Built in 1875, this resource is an unpaved road segment, 10 feet wide, approximately 1.17 miles long, within a system of dirt freight roads. Isolated and artifact concentrations and three large well shaft sites with associated domestic artifacts located adjacent to road.	Eligible under Criterion 1.	Approximately 210 feet of Nadeau Road intersect the API at an Overhead Installation Site and Access Road. The proposed project will not adversely impact the resource.
1	P-15-013796/ 312	Private (unidentified); DOD NAWS China Lake	1913	Substation	SCE Inyokern Substation Complex is a substation complex, 363 x 248 feet and 89 x 84 feet, that lies entirely within project APE. This resource includes oil circuit breakers, transformers, voltage regulators, a control house, and a small shed.	Ineligible.	One guard site, one pull site, one demo site, one contractor material yard. Associated work and construction areas within boundary. Install new 90-foot dead-end TSP multi-pole. Remove and replace existing overhead subtransmission and telecom lines. Existing unpaved access roads will be graded and improved as needed.
1	P-15-015802/ CA-KER-8684H/ 284	Private (unidentified); DOD NAWS China Lake	1925-1943	Local Road	Leliter Road is a partially-paved road, 20-feet wide, approximately 4.69-miles long. The road initiates as an unpaved road for 0.42-miles and resumes as a paved road at U.S. Highway 395 for approximately 2.85-miles and transitions into an unpaved road for the remainder of the road. This resource consists of two features: the bladed road segment (FI) and a hand-painted metal sign (F2) reading "DANGER/ Rocket Sled Test Track/Do not Enter", and an associated artifact scatter along the roadside of 14 cans, 45 glass fragments, and approximately 100 lumber fragments and miscellaneous metal cans.	Ineligible.	Unknown.
1	P-15-017441/ CA-KER-9602H/ 273	Private (unidentified)	ca. 1850s	Historic Route	Brown Road, ca. 1850s, this historic wagon road is now a partially paved road, 20 feet wide with shoulders between 10 and 20 feet, approximately 22 miles long. Components include multiple homestead fence alignments, well pump houses and ten associated artifact loci.	Eligible under Criterion 1.	Brown Road intersects API in a T-shape at two locations for approximately 0.68 miles. In the north, Brown Road intersects a Demo, a Guard Site, and Contractor Materials Yard. In the south, Brown Road intersects a Guard Site, two Shunt Removal Sites, and one Pull Site. Brown Road also serves as an access road. The proposed project will not adversely impact the resource.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
1	P-15-017445/ CA-KER-9606H/ 298	Private (unidentified); DOD NAWS China Lake	pre-1915	Local Road	The unnamed road is an unpaved single-track road, between 6 and 8-feet wide, in a northeast to southwest orientation for approximately 3.49-miles long. Loci occur along roadside (A-E), all historic refuse dumps (ca. 1914-1937) containing domestic and building materials (rebar, brick). Isolated cans occur in a thin scatter up to 100 feet north and south of alignment.	Ineligible.	Unknown.
2	317	Private (unidentified)	1937	Transmission/ Utility Line	SCE Inyokern-Kramer-Randsburg No. 3 115kV Transmission Line is a galvanized steel lattice towers and transmission line that spans approximately 50-miles initiating in the north at the SCE Inyokern Substation continuing 22-miles south to the SCE Randsburg Substation and 27-miles south to the SCE Kramer Substation.	Ineligible.	Unknown.
2	318	Private (unidentified)	1948-1967	Local Road	North Mercury Street is an unpaved road, 20-feet wide, approximately 0.25-miles long. The road provides access to transmission lines.	Ineligible.	Unknown.
2	320	Private (unidentified)	1967-1971	Local Road	Weiman Avenue is an unpaved road, 15-feet wide, approximately 0.28-miles long.	Ineligible.	Unknown.
2	321	Private (unidentified)	1948-1967	Local Road	Access Road to SCE Inyokern-McGen-Searless No.1 Transmission Line consists of unpaved and paved road segments, both named and unnamed, approximately 33-miles long.	Ineligible.	Unknown.
2	322	Private (unidentified)	1972-1994	Local Road	Sydnor Ave is an unpaved road, 15-feet wide, that spans in two discontinuous segments for approximately 0.9-miles long.	Ineligible.	Unknown.
2	323	Private (unidentified)	pre-1943	Local Road	Felspar Avenue is an unpaved road segment, 25-feet wide, that spans approximately 0.9-miles creating a right angle.	Ineligible.	Unknown.
2	329	Private (unidentified)	pre-1948	Local Road	Ridgecrest Blvd is a partially-paved discontinuous road segments, 17-feet wide, that spans 12.5-miles long. The road is unpaved between Avenida del Sol and Jacks Ranch Road.	Ineligible.	Unknown.
2	330	Private (unidentified)	1948-1972	Other	Kerr McGee Youth Sports Complex (Stauffer Park) is a multi-use recreation facility, 8.4 acres, that overlaps project area. Components: baseball and soccer fields, playground, indoor facilities (gymnasium, two racquetball courts, aerobics room, showers, lockers, preschool, banquet rooms, meeting rooms, kitchen).	Ineligible.	The north half of facility overlaps with contractor material yard at two baseball fields.
2	331	Private (unidentified)	1967	Substation	SCE Downs Substation Complex is an open-air distribution substation on a 4.64-acre lot located on the corner of South Downs Street and West Ridgecrest Boulevard. The substation is enclosed behind a grounded chain-link fence with barbed wire strands above the fence.	Ineligible.	Unknown.
2	332	Private (unidentified)	1915-1947	Two Lane Paved Road	South Downs Street is a paved four-lane road, 20-feet wide, approximately 3.46-miles long. The road transitions into an unpaved	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
					road at the South China Lake Blvd intersection. The road is presumed to have been constructed as an access road through Ridgecrest.		
2	333	Private (unidentified)	1970-1973	Two Lane Paved Road	East Upjohn Ave is a paved road, 56-feet wide, approximately 1.24-miles long.	Ineligible.	Unknown.
2	334	Private (unidentified)	1948-1972	Other	SCE Ridgecrest Service Center is a service center complex on 3.96-acres surrounded by a tall fence located directly east of South China Lake Blvd and directly south of East Upjohn Avenue. This resource includes 10 rectangular industrial structures, a helicopter pad, a security guard house, and several concrete parking structures. There also appears to be construction materials, several shipping containers, and large elongated pieces of metal.	Ineligible.	Unknown.
2	341	Private (unidentified); BLM, Ridgecrest	1967-1971	Access Road	The unnamed road is an unpaved road, 11-feet wide, approximately 0.12-miles long, that terminates in the SCE transmission corridor.	Ineligible.	Unknown.
2	345	Private (unidentified); BLM, Ridgecrest	1971-1975	Local Road	Clone Avenue (Elone Avenue) is an unpaved road, 10-feet wide, approximately 0.45-miles long, that terminates at an access road to a SCE transmission line.	Ineligible.	Unknown.
2	354	BLM, Ridgecrest	1967-1971	Access Road	The unnamed road is an unpaved road, 10-feet wide, approximately 0.85-miles long.	Ineligible.	Unknown.
2	356	BLM, Ridgecrest	1971	Access Road	The unnamed road is an unpaved road, 8-feet wide, approximately 0.7-miles long, that terminates at an access road to SCE transmission line.	Ineligible.	Unknown.
2	357	BLM, Ridgecrest	1954-1967	Access Road	The unnamed road is an unpaved, one-lane road, 15-feet wide, approximately 1-mile long, that terminates at an unnamed road approximately 20-feet from the old Southern Pacific Railroad grade.	Ineligible.	Unknown.
2	363	BLM, Ridgecrest	1967-1971	Access Road	The unnamed road is an unpaved road, 13-feet wide, approximately 1-mile long, that terminates at the SCE transmission line corridor.	Ineligible.	Unknown.
2	364	BLM, Ridgecrest	pre-1948	Access Road	The unnamed road is an unpaved road, 13-feet wide, approximately 1-mile long, that terminates at the SCE transmission line corridor.	Ineligible.	Unknown.
2	380	Private (unidentified); BLM Ridgecrest FO	pre-1903	Two Lane Paved Road	Garlock Road. Built before 1903, this paved two-lane road is 24 feet wide with a 5-foot shoulder on both sides, and approximately 8.30 miles long. The evaluated road was once part of a much longer route that was utilized by mule teams transporting borax from Searles Lake to the port of San Pedro during the 1870s.	Eligible under Criterion 1.	Approximately 0.24 miles of Garlock Road intersect the API at two locations, a Guard Site, Overhead Installation Site, and Access Roads. It also runs adjacent to Contractor Materials Yard. The proposed project will not adversely impact the resource.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
2	381	Private (unidentified); BLM, Ridgecrest	pre-1965	Access Road	The unnamed road is an unpaved road, 16-feet wide, approximately 0.07-miles long, that terminates at the Southern Pacific Railroad line.	Ineligible.	Unknown.
2	382	Private (unidentified); BLM, Ridgecrest	pre-1965; pre-2009	Access Road	The unnamed road is an unpaved road, 15-feet wide, approximately 0.2-miles long, that terminates at the SCE transmission corridor.	Ineligible.	Unknown.
2	385	Private (unidentified); BLM, Ridgecrest	1954-1965	Local Road	Road R122 is an unpaved road, 18-feet wide, approximately 4.3-miles long, that terminates at the Southern Pacific Railroad line.	Ineligible.	Unknown.
2	387	Private (unidentified); BLM, Ridgecrest	pre-1965	Access Road	The unnamed road is an unpaved road, 9-feet wide, approximately 0.17-miles long.	Ineligible.	Unknown.
2	388	Private (unidentified); BLM, Ridgecrest	1965-1967	Access Road	The unnamed road is an unpaved road, 12-feet wide, approximately 0.72-miles long, that travels in a semicircle, entering and exiting on Goler Road.	Ineligible.	Unknown.
2	389	Private (unidentified); BLM, Ridgecrest	pre-1954	Two Lane Paved Road	Goler Road is a paved road, 22-feet wide and 4.2 miles long, that courses through project APE.	Ineligible.	One guard site, one shunt removal site, and contractor material yard. Associated work and construction areas within boundary. Remove nine 70-foot lattice steel suspension towers. Remove 70-foot dead-end lattice steel tower. Remove 80-foot dead-end lattice steel tower. Install two new 92-foot TSP suspension monopoles. Install five new 87-foot TSP suspension monopoles. Install four new 82-foot TSP suspension monopoles. Remove and replace existing overhead subtransmission and telecom lines. Existing unpaved access roads will be graded and improved as needed.
2	390	Private (unidentified); BLM, Ridgecrest	1965-1973	Local Road	Unnamed Transmission Line Access Road is an unpaved road, 9-feet wide, approximately 3.2-miles long, that terminates at the Union Pacific Railroad line. The road runs through the SCE transmission line corridor.	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
2	397	Private (unidentified); BLM, Ridgecrest	pre-1965	Access Road	Unnamed Transmission Line Access Road is an unpaved road, 16-feet wide, approximately 0.7-miles long. This road runs through the SCE transmission line corridor.	Ineligible.	Unknown.
2	401	Private (unidentified); BLM, Ridgecrest	pre-1965	Access Road	The unnamed road is an unmaintained paved road, 15-feet wide, approximately 0.1-miles long.	Ineligible.	Unknown.
2	402	Private (unidentified); BLM, Ridgecrest	pre-1965	Access Road	The unnamed road is an unpaved road, 11-feet wide, approximately 0.25-miles long, that initiates from an unnamed road located approximately 530-feet north of Road R85 and loops back around terminating at the unnamed road.	Ineligible.	Unknown.
2	403	Private (unidentified); BLM, Ridgecrest	1954-1965	Access Road	The unnamed road is an unpaved route, 10-feet wide, approximately 0.35-miles long, that terminates at an unknown mining feature located approximately 300-feet north of Road R85 in the Stringer District.	Ineligible.	Unknown.
2	404	Private (unidentified); BLM, Ridgecrest	pre-1954	Local Road	Road R85 is an unpaved road, 15-feet wide, approximately 2.5-miles long.	Ineligible.	Unknown.
2	409	BLM, Ridgecrest	pre-1954; pre-2005	Access Road	The unnamed road is an unpaved road, 12-feet wide, approximately 1.72-miles long, that terminates at the SCE transmission corridor.	Ineligible.	Unknown.
2	410	BLM, Ridgecrest	pre-1915	Access Road	The unnamed road is an unpaved wagon road, 15-feet wide, approximately 1.52-miles long.	Ineligible.	Unknown.
2	411	Private (unidentified); BLM, Ridgecrest	pre-1954	Access Road	The unnamed road is an unpaved road, 15-feet wide, approximately 1.9-miles long.	Ineligible.	Unknown.
2	412	Private (unidentified); BLM, Ridgecrest	1965-2006	Access Road	The unnamed road is an unpaved road, 10-feet wide, approximately 1.3-miles long.	Ineligible.	Unknown.
2	413	Private (unidentified); BLM, Ridgecrest	1954-1965	Local Road	The unnamed road is an unpaved road, 9-feet wide, approximately 7.38-miles long.	Ineligible.	Unknown.
2	415	BLM Ridgecrest FO	pre-1903	Local Road	Cuddeback Road. Built before 1903, this unpaved wagon road is 13 feet wide and approximately 5.86 miles long. It appears to extend from the Twenty Mule Team Parkway in the east continuing in the same trajectory.	Eligible under Criterion 1	Approximately 75 feet of Cuddeback Road intersect the API at two Installation Sites and a Guard site. The proposed project will not adversely impact the resource.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
2	416	BLM, Ridgecrest	1972-1994	Access Road	The unnamed road is an unpaved road, 8-feet wide, approximately 1.55-miles long.	Ineligible.	Unknown.
2	418	BLM, Ridgecrest	1952-1972	Local Road	The unnamed road is an unpaved road, 7-feet wide, approximately 5.03-miles long.	Ineligible.	Unknown.
2	419	BLM, Ridgecrest	1915-1947	Local Road	Fremont Peak Road is an unpaved road, 10-feet wide, approximately 15.11-miles long that circumnavigates Fremont Peak.	Ineligible.	Unknown.
2	421	Private (unidentified); BLM, Ridgecrest	pre-1952	Local Road	The unnamed road is an unpaved road, 11-feet wide, approximately 5.81-miles long.	Ineligible.	Unknown.
2	422	Private (unidentified); BLM, Ridgecrest	pre-1952	Access Road	The unnamed road is a paved road, 16-feet wide, approximately 1.65-miles long.	Ineligible.	Unknown.
2	423	Private (unidentified); BLM, Ridgecrest	1952-1972	Local Road	The unnamed road is an unpaved road, 10-feet wide, approximately 11.17-miles long, that terminates at a fork in the road.	Ineligible.	Unknown.
2	424	Private (unidentified); BLM, Ridgecrest	1952-1973	Two Lane Paved Road	Rosewood Blvd is a paved road, 10-feet wide, approximately 10.76-miles long.	Ineligible.	Unknown.
2	425	CSLC; Private (unidentified); BLM, Ridgecrest	pre-1952	Local Road	Locust Road is a partially-paved road, ranging between 8- to 38-feet wide, approximately 2.65-miles long. Located in the former Boron Air Force Station. West of U.S. Highway 395, the road is a double-track paved road. East of the highway, the road is a single-track dirt road. This resource includes an existing FAA dome structure used for aircraft flight tracking.	Ineligible.	Unknown.
2	426	CSLC; Private (unidentified); BLM, Ridgecrest	1972-1994	Local Road	East Waseca Road is an unpaved road, 10-feet wide, approximately 0.40-miles long.	Ineligible.	Unknown.
2	429	Private (unidentified); BLM, Ridgecrest	1952-1972	Local Road	Balsamo Road is an unpaved road, 24-feet wide, approximately 2.13-miles long.	Ineligible.	Unknown.
2	430	Private (unidentified); BLM, Ridgecrest	1952-1972	Local Road	Marshall Street is an unpaved road, 13-feet wide, approximately 0.52-miles long.	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
2	431	Private (unidentified); BLM, Ridgecrest	1972-1994	Local Road	Cumberland Road is an unpaved road, 21-feet wide, approximately 2.38-miles long.	Ineligible.	Unknown.
2	432	Private (unidentified)	1952-1972	Local Road	The unnamed road is an unpaved road, 8-feet wide, approximately 0.78-miles long, that terminates at the SCE transmission line corridor.	Ineligible.	Unknown.
2	433	Private (unidentified)	1952-1972	Local Road	Farmington Road is an unpaved road, 15-feet wide, approximately 10.3-miles long, that terminates at the east side of the Rio Tinto Borax Mine.	Ineligible.	Unknown.
2	437	Private (unidentified); BLM, Ridgecrest; DOD (Edwards AFB)	1952-1972	Local Road	Pipeline Road is an unpaved road, 15-feet wide, approximately 4-miles long, that terminates at the access road to SCE Kramer-Coolwater Transmission Line.	Ineligible.	Unknown.
2	457	CSLC; Private (unidentified); DOD (Edwards AFB); California DOT	1962	Transmission/ Utility Line	SCE Kramer-Rocket Test 115kV Transmission Line is a 115kV electrical transmission line and wood H-frame towers with ceramic insulators that spans approximately 11.33-miles connecting the SCE Kramer Substation (built in 1958) and SCE Rocket Test Substation (built in 1962).	Ineligible.	Unknown.
2	458	CSLC; Private (unidentified); DOD (Edwards AFB); California DOT	1937 /1966-1989	Substation	SCE Kramer Substation Complex is a substation complex situated on 26.57-acres. Structures at the utilitarian complex consist of a Control House, a Communications Building, a Maintenance Shop, a Pump House, a Water Tank, and a Relay House. The Relay House dates to circa 1937 while the remaining buildings date to circa 1966 to 1989. The Control House contains modernistic features with concrete masonry unit walls painted a buff color, a flat roof, and general rectilinear plan. Additional structures include the Mechanical Electric Equipment Room (MEER) and the Battery Enclosure Building.	Ineligible.	Unknown.
2	459	CSLC; Private (unidentified); DOD (Edwards AFB); California DOT	1950	Transmission/ Utility Line	SCE Kramer-Roadway-Victor 115kV Transmission Line is a 115kV electrical transmission line and tubular steel poles approximately 34.7-miles long connecting SCE Kramer Substation and SCE Victor Substation. The transmission line passes through the SCE Roadway Substation in Adelanto.	Ineligible.	Unknown.
2	P-15-007069/ P-36-008315/ P-15-002221 CHL No. 938/ CA-SBR-8315H/ CA-KER-8430H/	Private (Yellow Aster Mining & Milling Company); Private (RMDG	1895	Other	Rand Historic District: Gold mining district, ca. 1895, the majority of which is sited within Kern County. The district includes 17 discontinuous locations covering approximately 56 square miles: Little Butte Mining Complex, Kenyon Mine, Butte Lode Mining Complex, Yellow Aster Mine, Kelly Mine, the town of Randsburg, the town of Johannesburg, the town of Atolia, the town of Red Mountain, Stringer	Listed in NRHP; Listed in CRHR; Eligible under Criteria 1 and 3.	The Little Butte Mining Complex intersects the API at a Demo Site, a Removal and Installation Site, a Guard Site, a Pull Site, an Overhead Installation Site, and Access Roads.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
	C.A-KER-2221H/398	LLC); Private (SCE)			Mining District, Redrock Randsburg Road, Joberg Road, Butte Avenue, Red Mountain Road, Randsburg-Mojave Road, Mountain Wells Avenue, and the SCE Randsburg Substation Complex. The town of Randsburg, a contributor to the district, is considered the best-preserved mining town in the Mojave Desert.		Kenyon Mine intersects the API at a Demo Site, a Removal and Installation Site, a Pull Site and Overhead Installation Site. SCE Randsburg Substation Complex overlaps the API almost entirely at a Demo Site, a Removal and Installation Sites, a Pull Site and an Overhead Installation Site. The Stringer Mining District intersects the API at five locations at a Demo Site, five Removal and Installation Sites, a Guard Site, two Shunt Removal Sites, one Pull Site, and five Overhead Installation Sites. Randsburg-Mojave Road intersects API between an Overhead Installation Site and Access Road.
2	P-15-012543/ CA-KER-7078H/ 326	Private (unidentified)	ca. 1870s	Historic Route	Freight Road to Panamint Mine (Felspar Road) is an unpaved, discontinuous segments of former wagon road, 6-feet wide and 36 miles long.	Ineligible.	One shunt removal site. Associated work and construction areas within site boundary. Remove 70-foot lattice steel suspension tower. Temporary 70-foot LWS monopole. Remove and replace existing overhead subtransmission and telecom lines. Existing unpaved access roads will be graded and improved as needed.
2	P-15-015028/ CA-KER-8372H/ 335	Private (unidentified)	pre-1943	Historic Route	Bowman Road; Midland Trail. Considered a prehistoric route later used by early 20th century settlers in the Indian Wells Valley. Now, it is a partially paved, two-lane road, 25 feet wide, approximately 22 miles long.	Eligible under Criterion 1	Approximately 165 feet of Bowman Road intersect the API at Demo Sites, Removal and Installation Sites, a Guard Site, a Construction Material Yard, a Shunt Removal Site, Overhead Removal and Installation Sites, and Access Roads. The proposed project will not adversely impact the resource.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
2	P-15-015221/ CA-KER-8430H/ 399	Private (unidentified); BLM Ridgecrest FO	1912	Substation	SCE Randsburg Substation Complex. Open-air substation complex with two concrete pads enclosed by tall barbed-metal fencing, several switching racks, poles, transformers, a relay building, two stone and mortar walls, and tailing piles. No structures.	Eligible under Criteria 1 and 3, and eligible as contri-butor to SCE Bishop Creek Hydroelectric System Historic District.	Almost the entire site overlaps the API at Demo Sites, Removal and Installation Sites, a Pull Site, and an Overhead Installation Site. The proposed project will not adversely impact the resource.
2	P-15-017294/ CA-KER-9484H/ 361	BLM, Ridgecrest	pre-1915	Historic Route	The unnamed road is an unpaved one-lane prehistoric transit route and historic wagon road, 10-feet wide and 7.14 miles long, that courses through the project APE. Cultural corridor extends more than 100-meters wide at some loci along route.	Ineligible.	Associated work and construction areas within boundary. Remove 70-foot lattice steel suspension tower. Install new 87-foot LPS suspension monopole. Remove and replace existing overhead subtrans-mission and telecom lines. Existing unpaved access roads will be graded and improved as needed.
2	P-36-005731/ CA-SBR-5731H/ 444	Private (unidentified)	1897	Railroad	Kramer-Randsburg Railroad; Atchison, Topeka & Santa Fe Railway. Severed, railroad grade, approximately 26 miles long. Associated artifacts include torch-cut railroad tie spikes and domestic refuse deposit (ca. 1902-1930). Railway line begins inside Rand Historic District at SCE Randsburg Substation Complex. It provides access to SCE Randsburg Substation Complex and Burlington Northern Santa Fe (BNSF) Railroad. Abandoned in 1933 due to the Great Depression.	Eligible under Criterion 1	Approximately 720 feet of this segment intersects API at Removal and Installa-tion Sites, two Pull Sites, and an Overhead Removal and Installation Site. The proposed project will not adversely impact the resource.
2	P-36-007431/ CA-SBR-7431H/ 417	BLM, Ridgecrest	1872	Historic Route	Kramer Station Road (Kramer to Point of Rocks (Helendale) Road) is an unpaved single-track wagon road, ranging from 8- to 19-feet wide, approximately 16.5-miles long. Today, only a portion of the northern segment initiating north from California State Route 58 to U.S. Highway 395 is maintained. The resource contains 40 features associated with this road including 22 military-related deposits such as trending fence lines, a bomb, and prospect pit.	Ineligible.	Unknown.
2	P-36-025237/ 456.02	Private (Owner of Parcel 049-213-101)	pre-1934	Local Road	The unnamed road is an unpaved two-lane road, 10-feet wide, approximately 2.39-miles long, that terminates at the access road to SCE Kramer-Tortilla Transmission Line.	Ineligible.	Unknown.
2	P-36-025591/ 443	CSLC; Private (Kramer Apart-ments Corp.); DOD (Edwards	1958	Other	Darr Motel consists of three one-story WWII barracks (probably acquired from Edwards AFB) converted to a motel in 1958.	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
		AFB); California DOT					
2	P-36-025592/ 450	CSLC; Private (Karen D. Caillier); DOD (Edwards AFB); California DOT	ca. 1940s	Residential Building	40475 U.S. Highway 395 is a single-story building constructed as a dwelling and later converted to commercial use sited on 16.79-acres. The building is rectilinear in plan with a moderately pitched side gable roof covered in composite tiles. Exterior walls are constructed of Concrete Masonry Units (CMU) with steel sash windows installed along the street-facing (front) elevation.	Ineligible.	Unknown.
2	P-36-025593/ 452	Private (Karen D. Caillier)	ca.1950s	Residential Building	6158 State Route 58 (Caillier Residence) is a single-story building constructed as a dwelling and later converted to commercial use sited on 16.79-acres. The dwelling is horizontal wood framed building, rectilinear in plan atop a concrete foundation, and is covered by a moderately pitched side gable standing seam roof. An arched stucco wall partitions the residence. The property is partially enclosed by a 4-foot tall metal chain-link fence.	Ineligible.	Unknown.
2	P-36-025595/ 442	CSLC; Private (Kramer Services Corp.); DOD (Edwards AFB); California DOT	1960-1965 1971	Other	Kramer Services Corporation (Kramer Junction Four Corners, Beecher's Corner) is a 22-acre property spanning three parcels with multiple buildings. Three of the main buildings were constructed in the 1940s.	Ineligible.	Unknown.
2	P-36-026450/ 439	Private (unidentified); DOD (Edwards AFB)	1952 - 1956	Other	Unnamed Pipeline Landing Strip Road is an unpaved, unnamed road, between 26- and 66-feet wide, approximately 3.55-miles long. It has been widened to double as an airstrip (depicted as such on the 1973 USGS map). The eastern mile and a quarter segment is composed of the airstrip, 70 to 90-feet wide, and has berms lined with tires. The western quarter-mile segment narrows to a 30-foot bladed dirt roadway.	Ineligible.	Unknown.
2, 3N	440	CSLC; Private (unidentified); DOD (Edwards AFB); California DOT	1958	Transmission/ Utility Line	SCE Kramer-Coolwater 115kV Transmission Line is a 115kV electrical transmission line, poles, conductors that span approximately 44.3-miles connecting SCE Kramer Substation and SCE Coolwater Substation. This resource includes approximately 125-foot Tubular Steel poles.	Ineligible.	Unknown.
2, 3N, 3S	462	CSLC; Private (unidentified); DOD (Edwards AFB); California DOT	1972	Transmission/ Utility Line	SCE Coolwater-Kramer # 2 Transmission Line is an electrical transmission line and steel angle towers that span approximately 44.19-miles from the Coolwater Substation in Daggett to the Kramer Substation in Kramer Junction paralleling SCE Coolwater-Kramer #1 Transmission Line.	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
2, 3N, 3S	463	CSLC; Private (unidentified); DOD (Edwards AFB); California DOT	1972	Transmission/ Utility Line	SCE Coolwater-Kramer # 1 Transmission Line is an electrical transmission line and steel angle towers that span approximately 44.19-miles from the Coolwater Substation in Daggett to the Kramer Substation in Kramer Junction paralleling SCE Coolwater-Kramer #2 Transmission Line.	Ineligible.	Unknown.
2, 3S	445	CSLC; Private (unidentified); DOD (Edwards AFB); California DOT	pre-1932	Freeway/U.S Highway/State Route	State Route 58 is a major 2- to 4-lane highway, between 25 and 30-feet wide, approximately 241-miles long.	Ineligible.	Unknown.
2, 3S	461	CSLC; Private (Robert A Callier and Esther L Trust); DOD (Edwards AFB); California DOT	1972-1977	Water Conveyance and Control	Five water retention basins located on a 16.8-acre parcel with agricultural ponds, the Callier Residential Complex and buildings operating businesses. There is one southern basin, two northern basins paralleling each other, a western basin, and an eastern basin.	Ineligible.	Unknown.
3N	708	CSLC; CSLC; Private (SCE); Private (unidentified); DOD (Edwards AFB); California DOT; BLM, Barstow	1958	Two Lane Paved Road	Access Road to SCE Kramer-Coolwater Transmission Line is an unpaved road, 15-feet wide, approximately 44-miles long connecting SCE Kramer Substation and SCE Coolwater Substation.	Ineligible.	Unknown.
3N	712	CSLC; Private (unidentified); DOD (Edwards AFB); California DOT	pre-1972	Access Road	The unnamed road is an unpaved one-lane road, 10-feet wide, approximately 3.66-miles long that terminates at the Atchison, Topeka, and Santa Fe Railroad.	Ineligible.	Unknown.
3N	713	Private (unidentified); California DOT; BLM, Barstow	1956-1973	Local Road	Unnamed Pipeline Road is an unpaved one-lane road, 14.35-feet wide, approximately 6.22-miles long.	Ineligible.	Unknown.
3N	714	Private (unidentified); California DOT; BLM, Barstow	1947-1956	Local Road	The unnamed road is an unpaved one-lane road, 9.35-feet wide, approximately 4.72-miles long.	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
3N	716	BLM, Barstow	pre-1932-1972	Local Road	The unnamed road is an unpaved one-lane road, 10.23-feet wide, approximately 8.53-miles long.	Ineligible.	Unknown.
3N	718	BLM, Barstow	1969-1972	Access Road	The unnamed road is an unpaved one-lane road, 10.05-feet wide, approximately 2.38-miles long, that terminates at the Atchison, Topeka, and Santa Fe Railroad.	Ineligible.	Unknown.
3N	721	Private (unidentified); BLM, Barstow	pre-1972	Access Road	The unnamed road is an unpaved one-lane road, 8.7-feet wide, approximately 0.15-miles long.	Ineligible.	Unknown.
3N	722	Private (unidentified); BLM, Barstow	pre-1915-1969	Local Road	Kramer Road is an unpaved one-lane road, 8.62-feeet wide, approximately 7.26-miles long.	Ineligible.	Unknown.
3N	723	Private (unidentified)	pre-1932	Access Road	The unnamed road is an unpaved one-lane road, 11.31-feet wide, approximately 1.61-miles long.	Ineligible.	Unknown.
3N	724	Private (unidentified)	pre-1972	Access Road	The unnamed road is an unpaved, one-lane road, 13.78-feet wide, approximately 1.91-miles long, that terminates at the Atchison, Topeka, and Santa Fe Railroad line. The road is not accessible by any other roads.	Ineligible.	Unknown.
3N	727	Private (unidentified); BLM, Barstow	pre-1952	Access Road	The unnamed road is an unpaved one-lane road, 12.39-feet wide, approximately 1.32-miles long.	Ineligible.	Unknown.
3N	728	Private (unidentified); BLM, Barstow	pre-1972	Access Road	The unnamed road is an unpaved one-lane road, 12.28-feet wide, approximately 245-feet long. The road is not accessible by any other roads.	Ineligible.	Unknown.
3N	730	Private (Richardson Consolidated Inc.); BLM, Barstow	pre-1932, 1967	Residential Building	40892 Harper Lake Road is a residential complex comprised of approximately 7 wooden structures sited on 0.5-miles by 0.18-mile land segment. The structures on the ranch are comprised in Minimal Traditional and Vernacular-frame style. It appears that all structures are constructed of wood.	Ineligible.	Unknown.
3N	732	Private (unidentified)	pre-1932	Local Road	Roy Road is an unpaved road, 15-feet wide, approximately 4-miles long.	Ineligible.	Unknown.
3N	733	Private (unidentified)	pre-1932	Access Road	The unnamed road is an unpaved one-lane road, 15-feet wide, approximately 2.19-miles long.	Ineligible.	Unknown.
3N	734	Private (unidentified); BLM, Barstow	pre-1932	Access Road	The unnamed road is an unpaved one-lane road, 13.40-feet wide, approximately 1.0-mile long, that terminates at an unidentified structure.	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
3N	735	Private (unidentified); BLM, Barstow	pre-1932	Access Road	The unnamed road is an unpaved one-lane road, 8.38-feet wide, approximately 1.29-miles long.	Ineligible.	Unknown.
3N	736	Private (unidentified)	pre-1932	Access Road	The unnamed road is an unpaved one-lane road, 10.86-feet wide, approximately 2.14-miles long. Today, the only remnants of the well and unidentified building are concrete slabs.	Ineligible.	Unknown.
3N	737	Private (unidentified)	pre-1952	Access Road	The unnamed road is an unpaved one-lane road, 12.21-feet wide, approximately 0.84-miles long.	Ineligible.	Unknown.
3N	738	Private (unidentified); BLM, Barstow	pre-1978	Access Road	The unnamed road is an unpaved one-lane road, 9.73-feet wide, approximately 0.47-miles long, that terminates in a loop to the north at an unidentified structure.	Ineligible.	Unknown.
3N	739	Private (unidentified); BLM, Barstow	pre-1932	Local Road	County Road 20776 is an unpaved one-lane road, 13.87-feet wide, approximately 7.81-miles long.	Ineligible.	Unknown.
3N	745	Private (unidentified); BLM, Barstow	pre-1970	Access Road	The unnamed road is an unpaved one-lane road, 13.27-feet wide, approximately 1.52-miles long. Road leads past Black's Ranch.	Ineligible.	Unknown.
3N	746	Private (unidentified); BLM, Barstow	pre-1932	Local Road	Blacks Ranch Road (Brook Canyon Road) is an unpaved one-lane road, 15.52-feet wide, approximately 3.22-miles long.	Ineligible.	Unknown.
3N	747	Private (unidentified); BLM, Barstow	pre-1952	Access Road	The unnamed road is an unpaved one-lane road, 10.82-feet wide, approximately 0.15-miles long.	Ineligible.	Unknown.
3N	750	Private (unidentified); BLM, Barstow; DOD	pre-1952	Local Road	Holstead Road is an unpaved two-lane road, 25.86-feet wide, approximately 2.14-miles long, that terminates at 20220 Holstead Road.	Ineligible.	Unknown.
3N	753	Private (unidentified); BLM, Barstow	pre-1970	Access Road	The unnamed road is an unpaved one-lane road, 12.94-feet wide, approximately 1.52-miles long.	Ineligible.	Unknown.
3N	757	Private (unidentified); BLM, Barstow	1948-1952	Local Road	Mountain General Road (Transmission Line Access Road) is an unpaved road, 13.62-feet wide, approximately 10.34-miles long. Runs in backwards "C" curve through the foothills of Mt. General. Terminates at a site comprised of three large paved features, trash scatter, and an extensive scatter of bomb fragments.	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
3N	758	Private (unidentified); BLM, Barstow	pre-1956	Local Road	Burnt Tree Road (Holstead Road) is an unpaved one-lane road, 12.28-feet wide, approximately 3.60-miles long.	Ineligible.	Unknown.
3N	759	BLM, Barstow; DOD	pre-1952	Local Road	The unnamed road is an unpaved one-lane road, 12.85-feet wide, approximately 2.37-miles long that connects two points along the backwards C-shaped Mountain General Road.	Ineligible.	Unknown.
3N	765	BLM, Barstow	pre-1952	Access Road	The unnamed road is an unpaved one-lane road, 16-feet wide, approximately 1.74-miles long.	Ineligible.	Unknown.
3N	770	BLM, Barstow	pre-1970	Access Road	The unnamed road is an unpaved one-lane road, 15.69-feet wide, approximately 0.85-miles long.	Ineligible.	Unknown.
3N	771	BLM, Barstow	pre-1954	Access Road	The unnamed road is an unpaved one-lane road, 11.20-feet wide, approximately 1.57-miles long.	Ineligible.	Unknown.
3N	773	CSLC; Private (unidentified); BLM, Barstow	pre-1954	Local Road	Meadow Grove Road (Fossil Bed Road) is an unpaved one-lane road, 15-feet wide, approximately 6.32-miles long.	Ineligible.	Unknown.
3N	775	CSLC	pre-1933	Two Lane Paved Road	Fort Irwin Road; Old Yermo Road; Camp Irwin Road. This resource is built before 1933 as a paved two-lane Defense Access Road (DAR), 25 to 40 feet wide with 8-foot shoulder on each side, approximately 30 miles long.	Eligible under Criterion 1.	Approximately 212 feet of road intersect the API at a Guard Site, an Overhead Reconductor Site, and Access Roads. The proposed project will not adversely impact the resource.
3N	776	Private (SCE); Private (Bill Edward Clark); Yermo CSD	1954-1970	Access Road	The unnamed road is an unpaved one-lane road, 16.54-feet wide, spans approximately 0.11-miles that initiates from Meadow Grove Road at the west and terminates at Elephant Mountain Road at the east. Likely constructed same time as single family dwelling on 36033 Meadow Grove Road (ca. 1966).	Ineligible.	Unknown.
3N	777	Private (SCE); Private (Bill Edward Clark); Yermo CSD	1954-1970	Access Road	The unnamed road is an unpaved one-lane road, 16.02-feet wide, approximately 0.12-miles long.	Ineligible.	Unknown.
3N	782	SCE; Private (unidentified); Yermo CSD	pre-1970	Local Road	Yermo Access Road is an unpaved one-lane road, 16.15-feet wide, approximately 2.15-miles long.	Ineligible.	Unknown.
3N	783	SCE; Private (unidentified); Yermo CSD	pre-1970	Access Road	The unnamed road is an unpaved one-lane road, 8.49-feet wide, approximately 1.47-miles long.	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
3N	787	Private (SCE); Private (unidentified); DOD MCLB	pre-1970	Access Road	The unnamed road is an unpaved one-lane road, 12.45-feet wide, approximately 0.81-miles long, that travels in a C-shape and terminates at an unknown structure at what appears to be a water tower.	Ineligible.	Unknown.
3N	793	Private (SCE); Private (unidentified); Daggett CSD; BLM, Barstow	pre-1952	Access Road	The unnamed road is an unpaved one-lane road, 14.52-feet wide, approximately 0.25-miles long, that provides access to an 87-acre agricultural field owned by SCE.	Ineligible.	Unknown.
3N	797	Private (unidentified); BLM, Barstow	1954-1974	Access Road	The unnamed road is an unpaved one-lane road, 15.43-feet wide, approximately 0.42-miles long, that terminates at Yermo Union Pacific Train Yard and provides access to the Yermo Union Pacific Train Yard.	Ineligible.	Unknown.
3N	P-36-001910/ CA-SBR-1910H/ 790	Private (SCE); Private (unidentified); Daggett CSD; BLM Barstow FO	1903-1905	Railroad	San Pedro-Los Angeles and Salt Lake Railroad; Union Pacific Railroad. Approximately 700-mile-long railroad grade segment built between 1903-1905. The segment is62.5-inches wide with a 10-foot-wide raised gravel berm.	Eligible under Criterion 1.	Approximately 200 feet of this segment intersect the API at a Pull Site, four Overhead Reconductor Sites (along portion of grade entering yard), and Access Roads. The proposed project will not adversely impact the resource.
3N	P-36-004525/ CA-SBR-4525H/ 766	Private (unidentified); BLM Barstow FO	pre-1905	Historic Route	Barstow-Silver Lake Wagon Road; Irwin Road; Goldstone Road. Former wagon road, now a paved two-lane road is 25 feet wide and approximately 10.23 miles long. This is the original trajectory of the Barstow-Silver Lake Road (wagon road) established prior to 1905. Portions of the wagon road have been paved over, but other portions including apparent ruts are visible on desert pavement and meandering off of the paved road.	Eligible under Criterion 1	Approximately 228 feet of the Barstow-Silver Lake Wagon Road intersect the API at a Guard Site and Access Roads. The proposed project will not adversely impact the resource.
3N	P-36-007883/ CA-SBR-7883H/ 794	Private (SCE); Private (unidentified); Daggett CSD; BLM Barstow FO	1894-1902	Water Conveyance and Control	Daggett Ditch; Daggett Canal. Water conveyance system with lateral ditch, approximately 4.42-miles long, built between 1894-1902. Components include ditch alignment, two earthen berms, water tank, remnant wood structure, vertical-rising sluice gates, the head gate connecting it to the main ditch/canal, and remnant Tamarisk trees (dying or cut down) planted on the west berm.	Listed in CRHR. Eligible under Criteria 1 and 3.	Approximately 667 feet of the Daggett Ditch intersect the API at two Overhead Reconductor Sites and Access Roads. The proposed project will not adversely impact the resource.
3N	P-36-021629/ 781	Private (SCE); Private (Unclassified); Yermo CSD	ca. 1910, 1960-1965	Two Lane Paved Road	Yermo Road (Old 91) is a paved two-lane road, 21.78-feet wide, approximately 20-miles long. Components recorded in 2008 include "C" markers and four irregularly-spaced vehicular bridges with wood and metal guardrails and date stamps from 1952, 1956, and 1959. A culvert (ca. 1930-1950s) for seasonal wash channel was recorded as a feature in 2012, described as double-W beam guardrails anchored by	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
					wooden posts and attached to concrete parapets. Wood retaining walls flank the opening of the wash underpass on either side while the bridge connecting the road is a wood deck covered in asphalt. There is an associated refuse scatter.		
3N	P-36-024930/P-36-010895/CA-SBR-15938H/ CA-SBR-10895H/756	Private (unidentified); BLM, Barstow	pre-1932	Local Road	Fossil Bed Road (Daggett-Paradise Springs Road, Daggett-Barstow-Ballarat Road, Yermo Cutoff) is a complex of three roads: 1) a one-lane dirt road, 17-feet wide, approximately 4.3-miles long; 2) a one-lane dirt road, 18-feet wide, approximately 10-miles long. This is the main route in Hinkley constructed between 1953-1955; 3) a one-lane dirt road, 18-feet wide, approximately 14-miles long.	Ineligible.	Unknown.
3N	P-36-024931/ CA-SBR-15959H/755	Private (unidentified); BLM, Barstow	pre-1952	Access Road	The unnamed road is an unpaved one-lane road, 11-feet wide, approximately 1.12-miles long, that terminates at a wash.	Ineligible.	Unknown.
3N	P-36-026445/ 731	Private (unidentified)	pre-1932	Two Lane Paved Road	Harper Lake Road is a paved two-lane road, 40-feet wide, approximately 7.79-miles long. Terminates at the Mojave Solar Farm Facility.	Ineligible.	Unknown.
3N	P-36-026461/ 788	Private (SCE); Private (unidentified); DOD MCLB	pre-1950	Access Road	Daggett-Yermo Road (Ghost Town Road, Calico Road) is a paved two-lane road, 25.62-feet wide, approximately 2.77-miles long, that provides access to the Marine Corps Supply Center (Yermo Area).	Ineligible.	Unknown.
3N, 3S	P-36-026538/ 511	Private (unidentified)	pre-1932	Two Lane Paved Road	Hinkley Road (Rainbow Ranch Road) is a paved two-lane road, 21.41-feet wide with 1-foot shoulders, approximately 17.6-miles that terminates at National Trails Highway.	Ineligible.	Unknown.
3S	456	CSLC; Private (SCE); Private (unidentified); DOD (Edwards AFB); DOD MCLB; California DOT; BLM, Barstow	pre-1970	Local Road	Access Road to SCE Kramer-Tortilla 115kV Transmission Line (Bonanza Road) is an unpaved one-lane dirt road, between 13- and 17-feet wide, approximately 3-miles long. The access road is part of a grouping of three access roads that accesses transmission lines.	Ineligible.	Unknown.
3S	460	CSLC; Private (unidentified); DOD (Edwards AFB); California DOT	1967	Transmission/ Utility Line	SCE Kramer-Tortilla 115kV Transmission Line is a 115kV electrical transmission line and towers (wood and light weight steel poles with ceramic insulators), approximately 31.91-miles long, connecting SCE Kramer Substation and SCE Tortilla Substation.	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
3S	466	CSLC; Private (unidentified); DOD (Edwards AFB); California DOT	1952-1972	Two Lane Paved Road	Unnamed Transmission Line Access Road is an unpaved road, 27-feet wide, approximately 10.22-miles long, that runs along the SCE transmission corridor.	Ineligible.	Unknown.
3S	468	CSLC; Private (unidentified); DOD (Edwards AFB); California DOT	pre-1932	Local Road	The unnamed road is an unpaved road, 7-feet wide, approximately 5.83-miles long. This road leads to the mining town of Kramer Hills.	Ineligible.	Unknown.
3S	471	Private (unidentified); DOD (Edwards AFB); BLM, Barstow	1966-1972	Local Road	Rosario Avenue is an unpaved road, 8-feet wide approximately 2.56-miles long. Rosario Avenue is part of a subdivision (never came to fruition) platted southeast of Kramer Junction.	Ineligible.	Unknown.
3S	472	Private (unidentified); DOD (Edwards AFB); BLM, Barstow	1966-1972	Local Road	Cuando Avenue is an unpaved road, 14-feet wide, spans approximately 1-mile long. Cuando Avenue is part of a subdivision (never came to fruition) platted southeast of Kramer Junction.	Ineligible.	Unknown.
3S	473	Private (unidentified); DOD (Edwards AFB); BLM, Barstow	1966-1972	Local Road	Juanro Avenue is an unpaved road, 14-feet wide, spans approximately 1-mile long. Juanro Avenue is part of a subdivision (never came to fruition) platted southeast of Kramer Junction.	Ineligible.	Unknown.
3S	474	Private (unidentified); DOD (Edwards AFB); BLM, Barstow	1966-1972	Local Road	Pecos Avenue is an unpaved road, 14-feet wide, spans approximately 0.81-miles long. Pecos Avenue is part of a subdivision (never came to fruition) platted southeast of Kramer Junction.	Ineligible.	Unknown.
3S	475	Private (unidentified); DOD (Edwards AFB); BLM, Barstow	1966-1972	Local Road	Del Largo Street is an unpaved road, 14-feet wide, spans approximately 0.6-miles long. Del Largo Street is part of a subdivision (never came to fruition) platted southeast of Kramer Junction.	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
3S	476	Private (unidentified); DOD (Edwards AFB); BLM, Barstow	1966-1972	Local Road	El Cajon Avenue is an unpaved road, 14-feet wide, approximately 1.05-miles long, that terminates in the SCE transmission line corridor. El Cajon Avenue is part of a subdivision (never came to fruition) platted southeast of Kramer Junction.	Ineligible.	Unknown.
3S	477	Private (unidentified); DOD (Edwards AFB); BLM, Barstow	1966-1972	Local Road	La Bonita Road is an unpaved road, 14-feet wide, spans approximately 1.05-miles long. La Bonita Street is part of a subdivision (never came to fruition) platted southeast of Kramer Junction.	Ineligible.	Unknown.
3S	479	BLM, Barstow	1966-1972	Local Road	The unnamed road is an unpaved road, 10-feet wide, approximately 1.8-miles long. This unnamed road is part of a subdivision (never came to fruition) platted southeast of Kramer Junction.	Ineligible.	Unknown.
3S	480	BLM, Barstow	1966-1972	Local Road	San Miguel Street is an unpaved road, 10-feet wide, approximately 1.1-miles long. San Miguel Street is part of a subdivision (never came to fruition) platted southeast of Kramer Junction.	Ineligible.	Unknown.
3S	481	BLM, Barstow	1952-1972	Local Road	The unnamed road is an unpaved road, 8-feet wide, approximately 7.76-miles long, that terminates inside the transmission line corridor.	Ineligible.	Unknown.
3S	482	BLM, Barstow	1952-1972	Access Road	The unnamed road is an unpaved road, 8-feet wide, approximately 0.84-miles long, that terminates inside the transmission line corridor.	Ineligible.	Unknown.
3S	483	BLM, Barstow	1972-1995	Access Road	The unnamed road is an unpaved road, 8-feet wide, approximately 0.4-miles long, that terminates inside the transmission line corridor.	Ineligible.	Unknown.
3S	486	BLM, Barstow	pre-1932	Access Road	The unnamed road is an unpaved road, 8-feet wide, approximately 1.2-miles long, that terminates in the transmission line corridor.	Ineligible.	Unknown.
3S	491	Private (unidentified); BLM, Barstow	ca. 1940-1952	Local Road	The unnamed road is an unpaved road between 14- and 25-feet wide, approximately 7.77-miles long, that provides access to the Hawes Auxiliary Airport.	Ineligible.	Unknown.
3S	492	Private (unidentified); BLM, Barstow	pre-1952	Local Road	The unnamed road is an unpaved road, 10-feet wide, approximately 26.26-miles long, up to the Los Angeles County line (it is only delineated up to County Line Road).	Ineligible.	Unknown.
3S	493	BLM, Barstow	pre-1932	Local Road	The unnamed road is an unpaved road, 17-feet wide, approximately 7.24-miles long that terminates at the Atchison, Topeka and Santa Fe Railroad line to the north and terminates at Helendale Radar Cross Section Facility to the south.	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
3S	494	BLM, Barstow	pre-1932	Access Road	The unnamed road is an unpaved road, 8-feet wide, approximately 1.87-miles long that terminates at the Iron Mountains.	Ineligible.	Unknown.
3S	499	Private (unidentified); DOD; BLM, Barstow	1970-1994	Access Road	The unnamed road is an unpaved road, 11-feet wide, approximately 0.53-miles long that follows along the SCE transmission line corridor.	Ineligible.	Unknown.
3S	501	Private (Owner of Parcel 048-805-101); DOD; BLM, Barstow	1952-1970	Access Road	The unnamed road is an unpaved road, 8-feet wide, approximately 0.26-miles long that terminates in SCE transmission line corridor.	Ineligible.	Unknown.
3S	502	Private (unidentified); DOD; BLM, Barstow	1952-1970	Access Road	The unnamed road is an unpaved road, 8-feet wide, approximately 0.37-miles long that terminates in SCE transmission line corridor.	Ineligible.	Unknown.
3S	503	Private (unidentified); DOD; BLM, Barstow	pre-1932	Local Road	Hillview Truck Trail is an unpaved road, 15-feet wide, approximately 6.63-miles long that terminates in SCE transmission line corridor.	Ineligible.	Unknown.
3S	504	Private (unidentified); DOD; BLM, Barstow	pre-1952	Local Road	Hillview Road is an unpaved road, 9-feet wide, approximately 2.04-miles long that terminates at Iron Mountain Road.	Ineligible.	Unknown.
3S	505	Private (unidentified); DOD	pre-1913	Local Road	Old Hinkley Road is an unpaved road, 12-feet wide, approximately 4.28-miles long.	Ineligible.	Unknown.
3S	510	Private (unidentified)	pre-1932	Local Road	Riverview Road is an unpaved road, 26-feet wide, approximately 3.97-miles long.	Ineligible.	Unknown.
3S	515	Private (unidentified)	1952-1971	Local Road	Tamarack Road is an unpaved road, 23-feet wide, approximately 1-mile long.	Ineligible.	Unknown.
3S	518	Private (unidentified)	pre-1932	Local Road	Mountain View Road is a partially-paved road, 25-feet wide, approximately 7.51-miles long that terminates at an unknown structure.	Ineligible.	Unknown.
3S	520	Private (unidentified)	pre-1952	Local Road	Hervey Road is an unpaved road, 25-feet wide, approximately 1-mile long.	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
3S	521	Private (unidentified)	1952-1970	Access Road	The unnamed road is an unpaved road, 12-feet wide, approximately 0.24-miles that terminates in the SCE transmission corridor.	Ineligible.	Unknown.
3S	523	Private (unidentified)	pre-1932	Local Road	Summerset Road is a partially paved road, 18-feet wide, approximately 3.52-miles long. Between Community Blvd and Riverview Road, Summerset Road is unpaved.	Ineligible.	Unknown.
3S	524	Private (unidentified); BLM, Barstow	1930; 1995-2003	Water Conveyance and Control	Mojave Water Agency Complex is a complex of evaporation ponds situated on 27.41-acre parcel northwest of Lenwood south of Dixie Road and Riverview Road. Components include well infrastructure and piping, a concrete slab foundation (presumably to original single family dwelling), 2 large concrete water storage basins (ca. 1995-2003), a modern single-wide prefab building (presumably an office for well operations). Ponds are currently dry.	Ineligible.	Unknown.
3S	525	Private (unidentified); BLM, Barstow	1970-1994	Local Road	The unnamed road (transmission line access road) is an unpaved road, 23-feet wide, approximately 2.5-miles long. Route follows along transmission line corridor.	Ineligible.	Unknown.
3S	535	Private (unidentified); BLM, Barstow	pre-1970	Local Road	Carmel Court is an unpaved one-lane gravel road, 21-feet wide, approximately 0.22-miles long that provides access to the dwellings that surround the road.	Ineligible.	Unknown.
3S	552	Private (unidentified); BLM, Barstow	1970-1994	Access Road	The unnamed road is an unpaved one-lane dirt road, 14.54-feet wide, approximately 0.91-miles long that provides access to the Mojave River.	Ineligible.	Unknown.
3S	554	Private (unidentified); BLM, Barstow	pre-1954	Two Lane Paved Road	Western Drive is a partially-paved two-lane road, 36.34-feet wide, approximately 0.13-miles long. Western Drive is not accessible by any other road. The segment of Western Drive under current review is located on the northern side of Agate Road.	Ineligible.	Unknown.
3S	555	Private (unidentified)	pre-1954	Access Road	The unnamed road is an unpaved one-lane dirt road, 22-feet wide, approximately 0.13-miles long.	Ineligible.	Unknown.
3S	559	Private (BNSF Railway Company)	pre-1954	Local Road	Evans Road is a partially-paved road, 28-feet wide, approximately 1.43-miles long that travels in a C-shape and terminates in the BNSF Railway Barstow Yard.	Ineligible.	Unknown.
3S	560	Private (Arturo Rangel)	1946; 2006-2009	Residential Building	26130 Agate Road is a residential complex on 1.86-acres. Main building, Minimal Traditional style with a detached double carport garage. The other 2 structures are modern.	Ineligible.	Unknown.
3S	567	Private (unidentified)	pre-1956	Local Road	Osborne Road is an unpaved two-lane road, 50-feet wide, approximately 0.37-miles long. Osborne Road was constructed prior to	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
					1956 to serve as the northeastern boundary of a subdivision that never came to fruition.		
3S	568	Private (unidentified); BLM, Barstow	pre-1954	Access Road	The unnamed road is an unpaved one-lane road, 19-feet wide, approximately 0.58-miles long. The road was altered slightly when Interstate 15 was constructed at the southernmost segment of the road.	Ineligible.	Unknown.
3S	569	Private (unidentified); BLM, Barstow	pre-1970	Access Road	The unnamed road is an unpaved one-lane road, 16.27-feet wide, approximately 0.73-miles long that provides access to the SCE Kramer-Tortilla Transmission Line. Today, it serves as an access road to OHV and off-roading trails.	Ineligible.	Unknown.
3S	570	Private (unidentified); BLM, Barstow	1970-1994	Access Road	The unnamed road is an unpaved one-lane road, 16-feet wide, approximately 0.2-miles long. Today, it serves as an access road to OHV and off-roading trails.	Ineligible.	Unknown.
3S	581	Private (Rose Ann Torres); BLM, Barstow	pre-1970	Other	Concrete foundation, approximately 19.23-feet by 26.05-feet in size directly south of the SCE Kramer-Tortilla 115kV Transmission Line. No structures appear to have been constructed on top of the foundation.	Ineligible.	Unknown.
3S	585	Private (unidentified); BLM, Barstow	1970-1994	Access Road	The unnamed road is an unpaved road, 9-feet wide, approximately 0.24-miles long. The road has low integrity.	Ineligible.	Unknown.
3S	586	Private (unidentified); BLM, Barstow	1974-1989	Access Road	The unnamed road is an unpaved one-lane road, 11.30-feet wide, approximately 0.1-miles long. The road first appears on the 1989 USGS Aerial Survey.	Ineligible.	Unknown.
3S	588	Private (unidentified); BLM, Barstow	1974-1989	Access Road	The unnamed road is an unpaved one-lane road, 11-feet wide, approximately 0.17-miles long. The road first appears on the 1989 USGS Aerial Survey.	Ineligible.	Unknown.
3S	590	Private (unidentified)	1952-1954	Local Road	P Street consists of two segments of a partially-paved road, 30-feet wide, approximately 1.11-miles long within the Barstow Heights neighborhood (Crestview Subdivision). The unpaved segment spans approximately 0.24-miles. The two-lane paved segment spans approximately 0.87-miles.	Ineligible.	Unknown.
3S	591	Private (unidentified)	1952-1954	Local Road	Bonanza Road is a paved two-lane road, 30-feet wide, approximately 1-mile long within the Barstow Heights neighborhood (Crestview Subdivision).	Ineligible.	Unknown.
3S	597	Private (unidentified)	1952-1953	Local Road	O Street is a paved two-lane road, 30-feet wide, approximately 1.31-miles long within the Barstow Heights neighborhood (Crestview Subdivision).	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
3S	604	Private (unidentified)	1952-1954	Local Road	N Street is a paved two-lane road, 30-feet wide, approximately 1.38-miles long within the Barstow Heights neighborhood (Crestview Subdivision).	Ineligible.	Unknown.
3S	610	Private (unidentified)	1952-1954	Local Road	M Street is a paved two-lane road, 30-feet wide, approximately 1.43-miles long within the Barstow Heights neighborhood (Crestview Subdivision).	Ineligible.	Unknown.
3S	614	Private (unidentified)	1952-1954	Local Road	L Street is a paved two-lane road, 30-feet wide, approximately 1.98-miles long within the Barstow Heights neighborhood (Crestview Subdivision).	Ineligible.	Unknown.
3S	620	Private (unidentified)	1952-1954	Local Road	K Street is a paved two-lane road, 30-feet wide, approximately 1.48-miles long within the Barstow Heights neighborhood (Crestview Subdivision).	Ineligible.	Unknown.
3S	625	Private (unidentified)	1952-1954	Local Road	J Street is a paved two-lane road, 30-feet wide, approximately 1.5-miles long within the Barstow Heights neighborhood (Crestview Subdivision).	Ineligible.	Unknown.
3S	626	Private (Glenn G Garen)	1963	Residential Building	27912 Bonanza Road is a single-family residential dwelling (two structures), low stone wall and fence situated on approximately 0.214-acres located within the Barstow Heights Community. The first structure is a garage located at the back of the Parcel with a front gable roof and board siding in the gable. The second structure is a Minimal Traditional single-family dwelling at the front of the property with a wide-hipped gable roof.	Ineligible.	Unknown.
3S	627	Private (James W Franks)	1964	Residential Building	27915 Bonanza Road is a single-family residential dwelling and chain link fence situated on approximately 0.294-acres located within the Barstow Heights Community. Dwelling is Minimal Traditional style with attached garage with front gable.	Ineligible.	Unknown.
3S	628	Private (Heather Lea Louise Adams)	1964	Residential Building	27932 Bonanza Road is a single-family residential dwelling, chain link fence, and masonry wall situated on approximately 0.227-acres located within the Barstow Heights Community. Dwelling is Minimal Traditional style with attached garage features a wide-hipped gable roof.	Ineligible.	Unknown.
3S	632	Private (unidentified)	1952-1954	Two Lane Paved Road	I Street is a paved two-lane road, 30-feet wide, approximately 1.5-miles long within the Barstow Heights neighborhood (Crestview Subdivision).	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
3S	637	Private (unidentified); BLM, Barstow	1952-1954	Two Lane Paved Road	H Street is a paved two-lane road, 28-feet wide, approximately 1.57-miles long within the Barstow Heights neighborhood (Crestview Subdivision).	Ineligible.	Unknown.
3S	649	Private (Pacific Summit-Rimrock Ranch LLC); BLM, Barstow	1967	Substation	SCE Tortilla Substation Complex is a substation Complex for SCE power company that spans 0.31-miles, containing a concrete foundation, approximately 349.45-feet by 461.90-feet and features switching racks, 2 rectangular buildings, and barbed-wire fence enclosure. Located east of Barstow Heights neighborhood (Crestview Subdivision).	Ineligible.	Unknown.
3S	652	Private (unidentified); BLM, Barstow	pre-1970	Access Road	The unnamed road is an unpaved one-lane road, 21.43-feet wide, approximately 1.81-miles long that appears to access the SCE Tortilla Substation Complex.	Ineligible.	Unknown.
3S	662	BLM, Barstow	pre-1971	Access Road	The unnamed road is an unpaved one-lane road, 13-feet wide, approximately 0.72-miles long.	Ineligible.	Unknown.
3S	663	Private (unidentified); BLM, Barstow	pre-1974	Access Road	The unnamed road is an unpaved one-lane road, 12-feet wide, approximately 1.34-miles long, one of several unnamed dirt roads that lead into the Nebo desert to presumably access OHV trails and public lands.	Ineligible.	Unknown.
3S	664	Private (unidentified); DOD MCLB; BLM, Barstow	pre-1974	Access Road	The unnamed road is an unpaved one-lane road, 12-feet wide, approximately 0.81-miles long, one of several unnamed dirt roads that lead into the Nebo desert to presumably access OHV trails and public lands.	Ineligible.	Unknown.
3S	665	Private (unidentified); DOD MCLB; BLM, Barstow	1974-1989	Access Road	The unnamed road is an unpaved one-lane road, 26-feet wide, approximately 0.23-miles long. Presumably, the road was constructed to access a portion of the USMC Nebo Supply Center and Firing Range, used for Military and National Defense purposes.	Ineligible.	Unknown.
3S	667	DOD MCLB	1974-1995	Access Road	The unnamed road is an unpaved one-lane road, 10-feet wide, approximately 0.72-mileslong that terminates in Nebo desert lands, owned by United States Marine Corps and used as a supply center and shooting range. Provides access to the USMC shooting range.	Ineligible.	Unknown.
3S	670	DOD MCLB	1952-1956	Local Road	Pipeline Road is an unpaved one-lane road, 23-feet wide, approximately 8-miles long.	Ineligible.	Unknown.
3S	671	DOD MCLB	pre-1974	Access Road	The unnamed road is an unpaved one-lane road, 15.58-feet wide, approximately 0.1-miles long that terminates at the Marine Corps Supply Center Firing Range.	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
3S	672	DOD MCLB	1952-1971	Access Road	The unnamed road is an unpaved one-lane road, 18.84-feet wide, approximately 1-mile line. This is an L-shaped route that terminates at the USMC Daggett-Yermo Supply Center Pistol Range. This road is only used to access the facilities within the pistol range.	Ineligible.	Unknown.
3S	673	Private (unidentified); DOD MCLB	1956-1971	Two Lane Paved Road	Pendleton Road is a paved two-lane road, 25-feet wide, approximately 3.82-miles long. The road serves as a boundary for the Marine Corps Firing Range and access route to the Firing Range and Interstate 40.	Ineligible.	Unknown.
3S	674	Private (unidentified); California DOT; BLM, Needles; BLM, Barstow	pre-1931	Two Lane Paved Road	Access Road to SCE Boulder Dam-San Bernardino Transmission Line (SCE Access Road) is a series of unpaved segments, averaging 15-feet wide, approximately 225-miles long from San Bernardino County to Nevada. The roads initiate at Calectric Substation and terminate at Hoover Dam. Each of the SCE access roads connect or facilitate access to transmission line towers.	Ineligible.	Unknown.
3S	683	Private (unidentified)	pre-1969	Local Road	The unnamed road is a wide-bladed one-lane road, averaging 170-feet wide, approximately 12-miles long. In some segments, the road is up to 231-feet wide.	Ineligible.	Unknown.
3S	688	Private (unidentified); BLM, Barstow	pre-1965	Local Road	The unnamed road is an unpaved one-lane road, 14-feet wide, approximately 10.9-miles long.	Ineligible.	Unknown.
3S	691	Private (SCE); Private (unidentified); BLM, Barstow	pre-1971	Access Road	This is an unnamed road. DPR not provided.	Ineligible.	Unknown.
3S	692	Private (SCE); Private (Juan Perez); BLM, Barstow	1958	Residential Building	36886 National Trails Hwy is a residential complex containing 3 dwellings (comprised of 7 buildings). Sited between National Trails Highway (Route 66) and the Atchison, Topeka, and Santa Fe Railroad. The three Minimal Traditional style dwellings parallel the street with a large setback on the Parcel. Each house has a side gable roofline, a central ridge chimney, and wood board siding.	Ineligible.	Unknown.
3S	695	Private (SCE); Private (unidentified); BLM, Barstow	pre-1970	Access Road	The unnamed road is an unpaved one-lane road, 9-feet wide, approximately 1-mile long. The road serves as an access road to the SCE Cool Water-Segs 2 Tortilla Transmission Line.	Ineligible.	Unknown.
3S	P-36-002910/ CA-SBR-2910H/ 566	Private (unidentified); BLM Barstow FO	1911-1914	Historic Route	U.S. Route 66; National Old Trails Highway; Old National Trails Highway. Built between 1911 and 1914, this highway is two to four lanes and approximately 2,448 miles long. This resource enters the	Listed in CRHR. Eligible under Criteria 1 and 3.	Approximately 431 feet of U.S. Route 66 intersect the API in at least two locations including two Removal Sites, one

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
					project APE in Daggett and leaves south of Barstow. Two segments fall within the project APE. One is a paved 4-lane road with modern signage. The other is 60 feet wide. Components include historic "C" blocks between 0.20 and 0.40 miles apart (located inside the API).		Installation Site, two Guard Sites, an Overhead Reconductor Site, and Access Roads. The proposed project will not adversely impact the resource.
3S	P-36-004411/P-36-009360/CHL No. 577/FS No. 05-12-53-012/ CA-SBR-9360H/ 666	BLM Barstow FO; Private (LADWP); Private (Wilmoth Trust 10-11-07); Private (Intermountain Power Agency); Private (Harvard Property Partnership)	1867	Historic Route	Stoddard Wells Road; Cape Glouster Avenue; The Mormon Trail; Salt Lake Road; Old Spanish Trail. Constructed by Mormon agriculturalist Lafayette Mecham in 1867 to transport 100 tons of hay to Camp Cady. This partially paved two-lane road, approximately 38.82 miles long, enters project API at terminus of eastern fork as a one-lane dirt road. Per the 2012 update, there is no evidence of the historic Mormon Trail (recorded in 1996, 2007) in this segment.	Eligible under Criterion 1.	Approximately 348 feet of Stoddard Wells Road intersect the API at an Overhead Reconductor Site and Access Roads. The proposed project will not adversely impact the resource.
3S	P-36-006693/ CA-SBR-6693H/ 558	CSLC; Private (BNSF Railway Company); DOD (Edwards AFB); California DOT	1883; 1970-1979	Railroad	BNSF Railroad. Railroad grade connects Los Angeles and San Bernardino with the Las Vegas area. This segment has a berm maximum height of approximately 12 feet, a partially intact track, and is comprised of wooden ties, spikes with brackets, rails lying close to their original location, and a red metal bumping post with manufacturer's plaque "Western-Cullen Division/Federal Signal Corporation".	Listed in CRHR. Eligible under Criteria 1.	Approximately 0.28 miles of BNSF Railroad intersect the API at three locations. At Kramer Junction, BSNF Railroad intersects the API in one location at a Removal and Installation Site, a Guard Site, and an Overhead Reconductor Site. In Daggett, BSNF Railroad intersects API in two locations at a Removal Site, a Pull Site, three Guard Sites, and two New Overland Access Roads. The proposed project will not adversely impact the resource.
3S	P-36-006793/ CA-SBR-6793H/ 561	Private (SCE); Private (BNSF Railway Company); BLM Barstow FO	1885; 1923	Railroad	Atchison, Topeka & Santa Fe Railroad. Original railroad grade built in 1885 with second track installed in 1923. Components include a two-track railroad, 62-inch-wide berm, and concrete bridge. Follows the Historic Cajon Pass Railroad Alignment.	Listed in CRHR. Eligible under Criteria 1.	Approximately 160 feet of Atchison, Topeka & Santa Fe Railroad intersect the API at a Guard Site, an Overhead Reconductor Site, and a New Overland Access Road. The proposed project will not adversely impact the resource.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
3S	P-36-007689/P-36-012658/CA-SBR-7689H/CA-SBR-12357H/584	Private (SCE); Private (unidentified); BLM Barstow FO; Yermo CSD	1917-1922; 1963	Historic Route	Interstate 15; Old Arrowhead Trail; Mojave Freeway. Built between 1917 and 1922, this paved four to six lane highway is separated by a dividing strip. It is between 60 and 100 feet wide and approximately 1,434 miles long. It roughly follows the alignment of the Arrowhead Trail Highway, as well as a former wagon road, and is very close to the Mojave Trail, possibly associated in segments. Multiple modification to the road over the years including in the 1920s (as Arrowhead Trail), the 1930s (as State Road 91/466) and the 1960s (an almost full relocation to Interstate 15).	Eligible under Criterion 1.	Approximately 160 feet of Interstate 15 intersect the API at three locations: three Guard Sites and an Overhead Reconductor Site. The proposed project will not adversely impact the resource.
3S	P-36-010315/CA-SBR-10315H/682	Private (SCE); Private (unidentified); BLM Needles FO; BLM Barstow FO	1930-1931 1950-1979	Transmission/ Utility Line	SCE Boulder Dam-San Bernardino 138-kV Transmission Line is a 138-kV electrical transmission line comprised of seven modern-day segments. The approximately 225-mile-long transmission line was built in 1930-1931 with additions between 1950-1974. Components include 52-feet tall lattice steel H frame towers, 55-feet tall A-frame dead end tower, 54-feet tall three-legged lattice steel tower (double H-frame), 60-feet tall "T" towers, six 54-feet tall “SW” towers, and 12,000-feet of cable. Segments are the Eldorado-Baker-Coolwater-Dunn Siding-Mountain Pass, Ivanpah-Baker-Cool Water Dunn Siding-Mountain Pass, Cool water-Gale, Gale-PS512, Victor-Black Mountain -Support-Southcap Southdown (portions), Victor-Aqueduct-Phelan, and Arrowhead-Calectric-Devil Canyon-Shandin (portions).	Listed in CRHR. Eligible under Criteria 1 and 3.	Approximately 5.69 miles of the transmission line intersect the API. Components in project API are to be removed. The removal and replacement of the historic transmission towers and conductor will result in a complete loss of integrity such that the historic line would no longer convey its identified significance. It is recommended that the SCE Boulder Dam-San Bernardino Transmission Line be documented according to HAER Level II standards prior to commencement of project construction. This recommendation is consistent with SCE’s Historic-Era Electrical Infrastructure Management Program.
3S	P-36-010318/CA-SBR-10318H/573	Private (unidentified); BLM, Barstow	1916	Other	Interstate Telegraph Company Right-of-Way Grant for Tel&Tel is a single wood pole telecommunication line approximately 42.6-miles long outer Victorville to Barstow. Today, the line continues as an active telephone line and is managed by General Telephone & Electronics Corporation.	Ineligible.	Unknown.
3S	P-36-024000/P-36-024000/684	Private (unidentified); BLM Barstow FO	ca. 1930	Historic Route	Camp Rock Road; Terry Road. This resource, ca. 1930, is comprised of a series of discontinuous, unpaved, and paved segments that extend throughout the Lucerne Valley, Ord, Rodman, Newberry, and Fry Mountains for approximately 50 miles. Camp Rock Road terminates at the API boundary.	Eligible under Criterion 1.	Camp Rock Road terminates at an Installation Site and Overhead Reconductor Site. The proposed project will not adversely impact the resource.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
3S	P-36-025238/ CA-SBR-16148H/484	Private (Owner of Parcel 049-213-105); BLM, Barstow	pre-1932	Local Road	The unnamed road is an unpaved road, 27-feet wide, approximately 3.06-miles long, that terminates in Kramer Hills.	Ineligible.	Unknown.
3S	P-36-025239/ CA-SBR-16149H/485	BLM, Barstow	pre-1932	Local Road	Unnamed Road/Kramer Road is an unpaved road, 8-feet wide, approximately 2.88-miles long.	Ineligible.	Unknown.
3S	P-36-026440/ 513	Private (unidentified)	1932-1971	Local Road	Serra Road (Payer Lane, Livingston Road) consists of three partially-paved road segments, between 10- and 18-feet wide, approximately 4.02-miles long. The northernmost segment is approximately 1.48-miles long. The center segment is approximately 0.48-miles long. The third segment is approximately 0.50-miles long.	Ineligible.	Unknown.
3S	P-36-026441/ 522	Private (unidentified)	pre-1932	Local Road	Fairview Road is a partially-paved road, approximately 2.01-miles long. Between Highcrest Road going south to Riverview Road, Fairview road is unpaved.	Ineligible.	Unknown.
3S	P-36-026445/ 490	BLM, Barstow	pre-1932-1952	Local Road	Helendale Road (Harper Lake Road) is an unpaved road, between 30 and 40-feet wide, with berms and new fence lines along the alignment, approximately 31-miles long, that terminates at Abengoa Mojave Solar Project in the north. Terminates at Southern California Logistics Airport on George Air Force Base, a United States Air Force flight training facility in the south. A section of Helendale Road north of State Route 58 is also known as Harper Lake Road.	Ineligible.	Unknown.
3S	P-36-026447/ 488	Private (unidentified); BLM, Barstow	pre-1932	Local Road	The unnamed road is an unpaved road, 9-feet wide, approximately 1.78-miles long. The 2013 DPR notes an unrecorded historic dense debris scatter associated with this resource.	Ineligible.	Unknown.
3S	P-36-026448/ 478	Private (unidentified); US Air Force, Edwards Air Force Base; BLM, Barstow	pre-1937; pre-1973	Local Road	Apache Avenue is an unpaved road, comprised of two segments. The northern segment (ca. pre-1937), 12.5-feet wide, spans approximately 2.34-miles while the southern segment (ca. pre-1973), 13-feet wide, spans approximately 1-mile. The road is potentially an access road for a removed transmission line.	Ineligible.	Unknown.
3S	P-36-026466/ CA-SBR-16904H/676	Private (unidentified); DOD MCLB; BLM, Barstow	c. 1878-1896	Local Road	Ord Mountain Road consists of three unpaved one-lane road segments, 12.78-feet wide, approximately 21.20-miles long.	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
3S	P-36-026467/ 669	DOD MCLB	pre-1975	Transmission/ Utility Line	Remnants of an abandoned utility line containing standing wood poles with and without attached electrical wire and glass insulators located behind a fence on the Marine Corps Logistic Base approximately 2.35-miles southeast of Nebo Center.	Ineligible.	Unknown.
3S	P-36-026508/ 694	Private (SCE); Private (unidentified); BLM, Barstow	pre-1956	Two Lane Paved Road	Santa Fe Street is a paved two-lane road, 22.51-feet wide, approximately 6.19-miles long. The road parallels the Atchison, Topeka, and Santa Fe Railroad.	Ineligible.	Unknown.
3S	P-36-026523/ 557	Private (unidentified)	pre-1954	Local Road	Jasper Road is a paved two-lane, poorly-maintained road, between 14 and 21-feet wide, approximately 2.36-miles long. The heavily degraded road exists north of an abandoned railroad grade (P-36-006793) up to the 300 A pipeline right-of-way. There is an associated historic refuse scatter composed of 50+ cans (beverage/food, tobacco), an aqua glass Coca-Cola bottle base, five aqua glass fragments, and four screw-top brown glass bottles.	Ineligible.	Unknown.
3S	P-36-026527/ 528	Private (unidentified); BLM, Barstow	pre-1958	Local Road	Lenwood Road is a paved road, 24-feet wide, with 9-foot-wide shoulders, approximately 9.35-miles long.	Ineligible.	Unknown.
3S	P-36-026530/ 615	Private (multiple owners)	1952-1954	Other	Barstow Heights Community (Crestview Subdivision) is a subdivision community nestled south of Interstate 15, the Mojave Freeway, and the Mojave Desert that spans approximately 5.85-miles from east to west. The community is comprised of 1,440-acres, 13 east-west and 9 north-south coursing residential streets, with most homestead tracts approximately 5-acres each. The community was established around 1957 with 125 residents.	Ineligible.	Unknown.
3S	P-36-026535/ 556	Private (unidentified)	1933-1954	Local Road	Agate Road is a paved, one-lane, poorly-maintained road, between 28- and 45-feet wide, approximately 2.29-miles long. Road has been widened to approximately 45-feet around Walnut and Maple Streets. The road is slightly crowned with no associated ditches.	Ineligible.	Unknown.
3S	P-36-026539/ 506	Private (unidentified)	pre-1932	Local Road	Valley Wells Road is an unpaved road, 22-feet wide, approximately 3.97-miles long.	Ineligible.	Unknown.
3S	P-36-027410/P-36-028005/CA-SBR-17465/658	BLM Barstow FO	ca. 1911	Historic Route	State Route 247; Barstow Road; Old Woman Springs Road. Built before 1911, this paved two-lane highway is crowned and ditched, 27 feet wide and approximately 78.34 miles long. Components include a wooden remnant sign frame and historic refuse. Highway was used as a main thoroughfare from the 1910s to the 1950s between the Mojave	Eligible under Criterion 1, and eligible as contributor to Mojave Historic	Approximately 165 feet of State Route 247 intersect the API at a Guard Site, an Overhead Reconductor Site, and Access Roads. The proposed project will not adversely impact the resource.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
					Desert Communities. Segments of the Highway identified as CSLC Scenic Highway.	Cultural Landscape under Criterion 1.	
3S	P-36-027750/ 704	Private (SCE); Private (unidentified); BLM, Barstow	1958 /1961-1979	Substation	SCE Coolwater Substation Complex (Coolwater Steam Plant and Switchyard) is an electricity-generating and coal gasification processing facility substation complex. The complex was initially developed with a Chlorinator building, a chemical storage building, a generator excitation building, a combination building, a C.T. switch gear motor continuation building, a control building, single-story rectilinear plan office building, and brick perimeter wall. The still-active facility has expanded over several campaigns while keeping the same configuration.	Ineligible.	Unknown.
3S	P-36-027751/ 650	Private (SCE); Private (Pacific Summit-Rimrock Ranch LLC); BLM, Barstow	1958	Transmission/ Utility Line	SCE Coolwater-Segs 2-Tortilla Transmission Line is an electrical transmission line and components that spans approximately 13-miles connecting SCE Coolwater Substation with SCE Tortilla Substation and terminating at the Segs 2 Substation. Resource contains conductors mounted on three singular wood poles, H Frame wooden poles (with steel cross bracing and steel cross arm).	Ineligible.	Unknown.
3S	P-36-027753/ 685	Private (unidentified); BLM Barstow FO	1947	Freeway/U.S Highway/State Route	Interstate 40; Needles Freeway. Built in 1947, this paved freeway has multiple lanes, wide median, shoulders on both sides and is approximately 2,559 miles long. Eligible for the State Scenic Highway System.	Eligible under Criterion 1.	Approximately 255 feet of each of the two divided lanes of Interstate 40 intersect the API at an Overhead Reconductor Site. The proposed project will not adversely impact the resource.
3S	P-36-028052/ CA-SBR-17484H/565	Private (unidentified); BLM, Barstow	pre-1963	Other	PG&E Natural Gas Pipeline is a natural gas underground pipeline containing 1- to 2-foot diameter pipe, two segments of an associated dirt access road, 2-foot high berm. A portion of the pipeline has been exposed by erosion. There is an associated secondary deposited debris scatter (Locus A) containing 17 cans, 10 metal debris fragments, and eight glass fragments, likely deposited between the 1940s and 1960s. The access road lies approximately 15-feet north of the northern edge of the pipeline berm and trends alongside the length of the pipeline.	Ineligible.	Unknown.
3S	P-36-028131/ CA-SBR-17540H/668	DOD MCLB	1950s	Transmission/ Utility Line	Distribution Pole Line is an electrical distribution line system located behind a fence on the Marine Corps Logistics Base. The resource contains 19 wooden poles, glass and 2 ceramic insulators, and associated wire. The distribution line, 20-feet wide, spans a total of 4,341-feet initiating in the west and trending in an L-shape to the south. The east-west oriented segment is 2,411-feet. The north-south oriented segment is 1,930 feet in length. The distribution line is	Ineligible.	Unknown.

Seg-ment	Res. #	Land Ownership	Date Range	Resource Type	Site Description	CRHR Eligibility Recommendation	Impact Description
					inactive, in poor condition, and affected by erosion and weathering. Most of the wire is lying along the ground and six of the poles have only partially intact hardware.		
3S	P-36-029490/ 706	Private (SCE); Private (unidentified); BLM, Barstow	1962	Transmission/ Utility Line	SCE Coolwater-Tiefort Transmission Line is an electrical transmission line, approximately 29.39-miles long from Coolwater Steam Plant to Fort Irwin Military Base. The resource contains 28 single wood poles (between 60 and 90-feet tall), and horizontal post insulators with or without steel wishbone crossarms, associated wire. This connects Coolwater Switchyard and Tiefort Substation.	Ineligible.	Unknown.
3S	P-36-029915/ 707	Private (SCE); Private (unidentified)	pre-1952	Water Conveyance and Control	Wooden water storage structure, approximately 15-feet tall, appears to have been constructed for water storage. This resource is on a raised platform supported by four short wood beams, topped by a rectangular wood tank. Diagonal wood boards prop up one side and a PVC pipe connected to a funnel below the tank extends to the ground to the south. Earth has been built up around the structure. A large spillway extends out the southwest.	Ineligible.	Unknown.

Table Ap.5-6. Built Environment Resources on Proposed Project with Potential for Visual Impacts

Segment #	Only in the Visual APE?	Res. #	Date Range	Resource Type	Poles Visible from Resource?	Characteristic Sensitive to Visible Impact
1	No	23	pre-1880	Local Road	Yes	Setting, Feeling, Association
1	No	37	pre-1913	Two Lane Paved Road	Yes	Setting, Feeling, Association
1	No	42	pre-1913	Two Lane Paved Road	Yes	Setting, Feeling, Association
1	No	P-14-004590/CA-INY-4590H/050	1850-1910	Two Lane Paved Road	Yes	Setting, Feeling, Association
1	No	53	1886	Water Conveyance and Control	Yes	Setting, Feeling, Association
1	No	62	pre-1913	Two Lane Paved Road	Yes	Setting, Feeling, Association
1	No	P-14-004591/CA-INY-4591H/097	pre-1913	Water Conveyance and Control	Yes	Setting, Feeling, Association
1	No	P-14-008745/CA-INY-6862/099	1932	Water Conveyance and Control	Yes	Setting, Feeling, Association
1	No	119	pre-1873	Historic Route	Yes	Setting, Feeling, Association
1	No	123	ca. 1920s-1942	Local Road	Yes	Setting, Feeling, Association
1	No	P-14-005022/CA-INY-4943H/124	1942-1945	Other*	Yes	Setting, Feeling, Association
1	No	151	pre-1907	Two Lane Paved Road	Yes	Setting, Feeling, Association
1	No	207	ca. 1873	Freeway/U.S Highway/State Route	Yes	Setting, Feeling, Association
1	No	P-14-008844/CA-INY-6956/242	1927	Substation	Yes	Setting, Feeling, Association
1	No	262	1919	Water Conveyance and Control	Yes	Setting, Feeling, Association
1	No	P-15-017441/CA-KER-9602H/273	ca. 1850s	Historic Route	Yes	Setting, Feeling, Association
1	No	P-15-011274/CA-KER-6624H/CA-INY-6545H/282	1875	Historic Route	Yes	Setting, Feeling, Association
1	No	315	1915-1943	Freeway/U.S Highway/State Route	Yes	Setting, Feeling, Association
1	Yes	P-14-004861/59.01	1915	Other*	Yes	Setting, Feeling, Association
1	Yes	P-14-004858/063	1911	Residences and Buildings	Yes	Setting, Feeling, Association
1	Yes	064/Inyo County HRI (1981)	1900	Residences and Buildings	Yes	Setting, Feeling, Association
1	Yes	P-14-004864/065	1897	Other*	Yes	Setting, Feeling, Association
1	Yes	P-14-004863/066	1897	Residences and Buildings	Yes	Setting, Feeling, Association
1	Yes	P-14-004853/067	1927	Residences and Buildings	Yes	Setting, Feeling, Association
1	Yes	P-14-004860/67.01	1900	Residences and Buildings	Yes	Setting, Feeling, Association
1	Yes	P-14-004854/068	1906	Other*	Yes	Setting, Feeling, Association
1	Yes	P-14-004855/69.01	1921	Other*	Yes	Setting, Feeling, Association
1	Yes	P-14-004859/075	1910	Other*	Yes	Setting, Feeling, Association
1	Yes	P-14-005194/90.01	ca. 1880s	Railroad	Yes	Setting, Feeling, Association
1	Yes	P-14-006863/103.01	1911-1913	Water Conveyance and Control	Yes	Setting, Feeling, Association

Segment #	Only in the Visual APE?	Res. #	Date Range	Resource Type	Poles Visible from Resource?	Characteristic Sensitive to Visible Impact
1	Yes	P-14-004827/117.01	1923	Other*	Yes	Setting, Feeling, Association
1	Yes	P-14-004828/117.02	1927	Residences and Buildings	Yes	Setting, Feeling, Association
1	Yes	P-14-004831/117.03	1927	Other*	Yes	Setting, Feeling, Association
1	Yes	P-14-005892/117.04	1911	Other*	Yes	Setting, Feeling, Association
1	Yes	P-14-004846/117.05	1886	Other*	Yes	Setting, Feeling, Association
1	Yes	P-14-004844/117.06	1931	Residences and Buildings	Yes	Setting, Feeling, Association
1	Yes	P-14-004843/117.07	1902	Residences and Buildings	Yes	Setting, Feeling, Association
1	Yes	P-14-004842/117.08	1920	Residences and Buildings	Yes	Setting, Feeling, Association
1	Yes	P-14-004834/117.09	1865	Residences and Buildings	Yes	Setting, Feeling, Association
1	Yes	P-14-004835/117.10	1888	Other*	Yes	Setting, Feeling, Association
1	Yes	P-14-004841/117.11	1900	Residences and Buildings	Yes	Setting, Feeling, Association
1	Yes	P-14-004838/117.12	1872	Residences and Buildings	Yes	Setting, Feeling, Association
1	Yes	P-14-004836/117.13	1930	Residences and Buildings	Yes	Setting, Feeling, Association
1	Yes	P-14-004847/117.14	1927	Residences and Buildings	Yes	Setting, Feeling, Association
1	Yes	P-14-005022/CA-INY-4943H/124	1942-1945	Other*	Yes	Setting, Feeling, Association
1	Yes	P-14-003802/CA-INY-3802H/125	1942	Other*	Yes	Setting, Feeling, Association
1	Yes	P-14-004872/135	1928	Water Conveyance and Control	Yes	Setting, Feeling, Association
1	Yes	P-14-004886/146	1932	Other*	Yes	Setting, Feeling, Association
1	Yes	P-14-004890/148.01	1905	Residential Building	Yes	Setting, Feeling, Association
1	Yes	P-14-004884/150.19	1922	Other*	Yes	Setting, Feeling, Association
1	Yes	P-14-004851/198.01	1911	Other*	Yes	Setting, Feeling, Association
2	No	P-15-015028/CA-KER-8372H/335	pre-1943	Historic Route	Yes	Setting, Feeling, Association
2	No	380	pre-1903	Two Lane Paved Road	Yes	Setting, Feeling, Association
2	No	P-15-007069/P-36-008315/P-15-002221CHL No. 938/CA-SBR-8315H/CA-KER-8430H/ C.A-KER-2221H/398	1895	Other*	Yes	Setting, Feeling, Association
2	No	P-15-015221/CA-KER-8430H/399	1912	Substation	Yes	Setting, Feeling, Association
2	No	415	pre-1903	Local Road	Yes	Setting, Feeling, Association
2	No	P-36-005731/CA-SBR-5731H/444	1897	Railroad	Yes	Setting, Feeling, Association
1, 2	No	P-14-004825/P-14-005766/008	ca. 1908 (SCE Control Substation)	Other*	Yes	Setting, Feeling, Association

Segment #	Only in the Visual APE?	Res. #	Date Range	Resource Type	Poles Visible from Resource?	Characteristic Sensitive to Visible Impact
1, 2	No	P-36-010316/CA-SBR-10316H/013	1911-1913	Transmission/Utility Line	Yes	Setting, Feeling, Association
1, 2	No	P-36-007545/CA-SBR-7545H/093	1909-1934	Freeway/U.S Highway/State Route	Yes	Setting, Feeling, Association
3N	No	P-36-004525/CA-SBR-4525H/766	pre-1905	Historic Route	Yes	Setting, Feeling, Association
3N	No	775	pre-1933	Two Lane Paved Road	Yes	Setting, Feeling, Association
3N	No	P-36-001910/CA-SBR-1910H/790	1903-1905	Railroad	Yes	Setting, Feeling, Association
3N	No	P-36-007883/CA-SBR-7883H/794	1894-1902	Water Conveyance and Control	Yes	Setting, Feeling, Association
3S	No	P-36-006693/CA-SBR-6693H/558	1883; 1970-1979	Railroad	Yes	Setting, Feeling, Association
3S	No	P-36-006793/CA-SBR-6793H/561	1885; 1923	Railroad	Yes	Setting, Feeling, Association
3S	No	P-36-002910/CA-SBR-2910H/566	1911-1914	Historic Route	Yes	Setting, Feeling, Association
3S	No	P-36-007689/P-36-012658/CA-SBR-7689H/ CA-SBR-12357H/584	1917-1922; 1963	Historic Route	Yes	Setting, Feeling, Association
3S	No	P-36-027410/P-36-028005/CA-SBR-17465/658	ca. 1911	Historic Route	Yes	Setting, Feeling, Association
3S	No	P-36-004411/P-36-009360/CHL No. 577/FS No. 05-12-53-012/CA-SBR-9360H/666	1867	Historic Route	Yes	Setting, Feeling, Association
3S	No	P-36-010315/CA-SBR-10315H/682	1930-1931 1950-1979	Transmission/Utility Line	Yes	Setting, Feeling, Association
3S	No	P-36-024000/P-36-024000/684	ca. 1930	Historic Route	Yes	Setting, Feeling, Association
3S	No	P-36-027753/685	1947	Freeway/U.S Highway/State Route	Yes	Setting, Feeling, Association
3S	Yes	P-36-023423/CA-SBR-14798H/698	ca. 1930-1931/1951	Other*	Yes	Setting, Feeling, Association

*Other resource types include historic districts, non-residential buildings, airport/airfields, relocation center, hotel/lodge, schools, dairy.

Table Ap.5-7. Archaeological Resources on Proposed Project with Potential for Visual Impacts (All Segments)

This table lists all resources within the Direct and Visual APE/I subject to Visual impacts (eligible under criteria 1, 2, 3 and therefore subject to impacts on setting, feeling, or association).

Segment #	Res. #	Age	Resource Type	Number of New Poles Visible from Site	Characteristics Sensitive to Visual Impact
1	P-14-000004/CA-INY-4	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Unknown	None
1	P-14-000010/CA-INY-10 (incl. P-14-000091/CA-INY-91)	Multi-component with protohistoric artifacts	Precontact: Habitation area. Historic: Refuse and discard.	Unknown	Petroglyphs
1	P-14-000028	Precontact	Precontact: Habitation area.	39	Petroglyphs
1	P-14-000030	Precontact	Precontact: Habitation area.	29	Petroglyphs
1	P-14-000092/CA-INY-0092	Precontact	Precontact: Multi-class artifact concentration.	Unknown	None
1	P-14-000111/CA-INY-111	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Unknown	Petroglyphs
1	P-14-000182/CA-INY-182H	Multi-component with protohistoric artifacts	Precontact: Habitation Area. Historic: Refuse and discard.	Unknown	Petroglyphs
1	P-14-000205	Precontact	Precontact: Temporary Camp.	3	Petroglyphs
1	P-14-000208	Precontact	Precontact: Habitation area.	20	Petroglyphs
1	P-14-000210	Precontact	Precontact: Rock Art.	28	Petroglyphs
1	P-14-000211	Precontact	Precontact: Temporary Camp.	23	Petroglyphs
1	P-14-000270	Precontact	Precontact: Rock Art.	13	Petroglyphs
1	P-14-000271/CA-INY-271	Precontact	Precontact: Residential base.	Unknown	Petroglyphs
1	P-14-000328/CA-INY-328	Multi-component	Precontact: Residential base. Historic: Homestead/farm/ranch resource.	Unknown	Setting, feeling, and association
1	P-14-000371/CA-INY-371H	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-000388	Precontact	Precontact: Rock Art.	20	Petroglyphs
1	P-14-000389	Precontact	Precontact: Rock Art.	17	Petroglyphs
1	P-14-000390	Precontact	Precontact: Rock Art.	16	Petroglyphs
1	P-14-001317/CA-INY-1317	Multi-component with protohistoric artifacts	Precontact: Residential base. Historic: Homestead/farm/ranch resource.	Unknown	Cupules
1	P-14-001471/CA-INY-1471/H	Multi-component	Precontact: Residential base. Historic: Mining resource.	Unknown	None
1	P-14-001473/CA-INY-1473H	Multi-component	Precontact: Bedrock milling station. Historic: Homestead/farm/ranch resource.	Unknown	None

Segment #	Res. #	Age	Resource Type	Number of New Poles Visible from Site	Characteristics Sensitive to Visual Impact
1	P-14-001496/CA-INY-1496	Precontact with historic isolate	Precontact: Temporary camp.	Unknown	Setting, feeling, and association
1	P-14-001650	Precontact	Precontact: Temporary Camp.	30	Petroglyphs
1	P-14-001873/CA-INY-1873 (incl. P-14-009424, P-14-009425, P-14-009426, P-14-009427/CA-INY-7349, CA-INY-7350, CA-INY-7351, CA-INY-7352)	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-002146	Multi-component	Precontact: Habitation area. Historic: Refuse and discard.	Unknown	None
1	P-14-002325	Multi-component	Precontact: Temporary Camp. Historic: Unknown.	7	Petroglyphs
1	P-14-002533	Precontact	Precontact: Rock Art.	29	Petroglyphs
1	P-14-002766/CA-INY-2766 (incl. P-14-009413 (previously recorded isolated find), P-14-009506/CA-INY-7408)	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-003440	Precontact	Precontact: Habitation area.	31	Petroglyphs
1	P-14-003454	Precontact	Precontact: Rock Art.	33	Petroglyphs
1	P-14-003642/CA-INY-3642/H	Multi-component	Precontact: Residential Base. Historic: Refuse and discard.	Unknown	Petroglyphs
1	P-14-003653	Precontact	Precontact: Bedrock milling station.	Unknown	None
1	P-14-003655	Precontact	Precontact: Rock Art.	31	Petroglyphs
1	P-14-003760/CA-INY-3760H	Multi-component	Precontact: Bedrock milling station. Historic: Homestead/farm/ranch resource, water infrastructure resource.	Unknown	None; eligible under Criterion 1 due to association with construction camp
1	P-14-003767/CA-INY-3767 (incl. P-14-003766/CA-INY-3766)	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-003772/CA-INY-3772	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-003775/CA-INY-3775	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard, Rock feature.	Unknown	Setting, feeling, and association
1	P-14-003777/CA-INY-3777H	Multi-component	Precontact: Temporary camp. Historic: Homestead/farm/ranch resource.	Unknown	Setting, feeling, and association
1	P-14-003778/CA-INY-3778 (incl. P-14-009207)	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Unknown	Setting, feeling, and association

Segment #	Res. #	Age	Resource Type	Number of New Poles Visible from Site	Characteristics Sensitive to Visual Impact
1	P-14-003826/CA-INY-3826	Multi-component with protohistoric artifacts	Precontact: Habitation area. Historic: Refuse and discard.	Unknown	Petroglyphs and ethnographic/ protohistoric village
1	P-14-004639	Precontact	Precontact: Temporary Camp.	22	Petroglyphs
1	P-14-004671	Precontact	Precontact: Rock Art.	1	Petroglyphs
1	P-14-004773/CA-INY-4773H	Multi-component with protohistoric artifacts	Precontact: Residential base. Historic: Refuse and discard.	Unknown	None
1	P-14-004786/CA-INY-4786	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-005023	Historic	Historic: Military resource.	Unknown	Setting and association with district
1	P-14-005649/CA-INY-5296H (incl. P-14-009229, P-14-009230, P-14-011686/ CA-INY-7215, CA-INY-7216, CA-INY-8999)	Multi-component	Precontact: Lithic concentration. Historic: Electrical infrastructure resource, exploration and transportation resource, homestead/ farm/ranch resource.	Unknown	None
1	P-14-005703 (incl. P-14-000602, P-14-006021, P-14-007354, P-14-009309, P-14-009310/ CA-INY-602, CA-INY-6021, CA-INY-6263, CA-INY-72, CA-INY-7263H)	Multi-component	Precontact: Multi-class artifact concentration. Historic: Exploration and transportation resource, Refuse and discard.	Unknown	None apparent
1	P-14-006028	Precontact	Precontact: District.	38	Petroglyphs and potentially other district-related characteristics
1	P-14-006033	Precontact	Precontact: Temporary Camp.	30	Petroglyphs
1	P-14-006811/CA-INY-5815	Precontact	Precontact: Residential base.	Unknown	None
1	P-14-006995	Historic	Historic: Refuse and discard.	Unknown	None; archaeological remains of homestead
1	P-14-007356	Multi-component	Precontact: Multi-class artifact concentration. Historic: Exploration and transportation resource, Refuse and discard.	Unknown	None
1	P-14-008282/CA-INY-6600H	Precontact with historic isolate	Precontact: Multi-class artifact concentration.	Unknown	Setting, feeling, and association
1	P-14-008723/CA-INY-6842	Multi-component	Precontact: Quarry. Historic: Refuse and discard, Rock feature.	Unknown	None
1	P-14-008772	Historic	Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-008773	Multi-component	Precontact: Lithic concentration. Historic: Electrical infrastructure resource.	Unknown	Setting, feeling, and association
1	P-14-008819/CA-INY-6931	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None

Segment #	Res. #	Age	Resource Type	Number of New Poles Visible from Site	Characteristics Sensitive to Visual Impact
1	P-14-008820/CA-INY-6932	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard, Rock feature.	Unknown	None
1	P-14-008821/CA-INY-6933	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-008822/CA-INY-6934	Multi-component	Precontact: Bedrock milling station. Historic: Refuse and discard.	Unknown	None
1	P-14-008824/CA-INY-6936	Multi-component	Precontact: Lithic concentration. Historic: Exploration and transportation resource, Refuse and discard.	Unknown	None
1	P-14-008826 (incl. P-14-009335)	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-008844	Historic	Historic: Electrical infrastructure resource.	Unknown	None; built elements determined not visually impacted (Urbana 2021)
1	P-14-009214/CA-INY-7210	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-009216	Precontact	Precontact: Residential base.	Unknown	Setting, feeling, and association
1	P-14-009217	Precontact with historic isolate	Precontact: Bedrock milling station.	Unknown	None
1	P-14-009219/CA-INY-7211	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-009227	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009228/CA-INY-7214	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Unknown	None
1	P-14-009232	Precontact with historic isolate	Precontact: Residential base.	Unknown	Setting, feeling, and association
1	P-14-009235/CA-INY-7218	Multi-component	Precontact: Residential base. Historic: Exploration and transportation resource.	Unknown	Setting, feeling, and association
1	P-14-009236/CA-INY-7219	Precontact with historic isolate	Precontact: Lithic concentration.	Unknown	Setting, feeling, and association
1	P-14-009239/CA-INY-7221 (incl. P-14-009238/CA-INY-7220)	Precontact with historic isolate	Precontact: Multi-class artifact concentration.	Unknown	Setting, feeling, and association
1	P-14-009240/CA-INY-7222	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-009242/CA-INY-7223	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard, Water infrastructure resource.	Unknown	Setting, feeling, and association

Segment #	Res. #	Age	Resource Type	Number of New Poles Visible from Site	Characteristics Sensitive to Visual Impact
1	P-14-009243/CA-INY-7224	Precontact	Precontact: Lithic concentration.	Unknown	Setting, feeling, and association
1	P-14-009245/CA-INY-7226	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-009248/CA-INY-7229	Precontact	Precontact: Quarry.	Unknown	Setting, feeling, and association
1	P-14-009249/CA-INY-7230	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard, Water infrastructure resource.	Unknown	Setting, feeling, and association
1	P-14-009250/CA-INY-7231 (incl. P-14-009251/CA-INY-7232)	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-009252/CA-INY-7233	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-009254/CA-INY-7235	Precontact with historic isolate	Precontact: Multi-class artifact concentration.	Unknown	Setting, feeling, and association
1	P-14-009259/CA-INY-7237 (incl. P-14-009260/CA-INY-7238)	Multi-component	Precontact: Bedrock milling station. Historic: Refuse and discard.	Unknown	None
1	P-14-009272/CA-INY-7241	Historic with Precontact isolate	Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-009277/CA-INY-7243	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-009278/CA-INY-7244	Unknown	Unknown: Rock feature.	Unknown	Setting, feeling, and association
1	P-14-009279	Historic	Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-009282	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard, Rock feature.	Unknown	None
1	P-14-009283/CA-INY-7249	Multi-component	Precontact: Bedrock milling station. Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-009288/CA-INY-7252 (incl. P-14-009289/CA-INY-7253)	Multi-component	Precontact: Lithic concentration. Historic: Exploration and transportation resource, Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-009298	Historic with Precontact isolate	Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-009300	Historic with Precontact isolate	Historic: Mining resource.	Unknown	Setting, feeling, and association
1	P-14-009305/CA-INY-7259 (incl. P-14-009304, P-14-009306)	Multi-component	Precontact: Residential base. Historic: Refuse and discard, Rock feature.	Unknown	Setting, feeling, and association
1	P-14-009309	Historic	Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-009310	Historic	Historic: Homestead/farm/ranch resource.	Unknown	Setting, feeling, and association
1	P-14-009311/CA-INY-7264	Precontact	Precontact: Lithic concentration.	Unknown	Setting, feeling, and association

Segment #	Res. #	Age	Resource Type	Number of New Poles Visible from Site	Characteristics Sensitive to Visual Impact
1	P-14-009314	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009315/CA-IN-7267	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-009317	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009319/CA-INY-7270 (incl. P-14-9320/CA-INY-7271)	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard, Rock feature.	Unknown	Setting, feeling, and association
1	P-14-009321	Multi-component	Precontact: Multi-class artifact concentration. Historic: Homestead/farm/ranch resource.	Unknown	Setting, feeling, and association
1	P-14-009334/CA-INY-7279	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard, Rock feature.	Unknown	None
1	P-14-009345/CA-INY-7287	Precontact	Precontact: Temporary camp.	Unknown	None
1	P-14-009351	Precontact	Precontact: Multi-class artifact concentration.	Unknown	None
1	P-14-009352/CA-INY-7291	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009357	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009358/CA-INY-7295	Multi-component	Precontact: Lithic concentration. Historic: Homestead/farm/ranch resource.	Unknown	None
1	P-14-009359/CA-INY-7296	Precontact with historic isolate	Precontact: Lithic concentration.	Unknown	None
1	P-14-009366/CA-INY-7300	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009370/CA-INY-7304	Multi-component	Precontact: Lithic concentration. Historic: Homestead/farm/ranch resource.	Unknown	None
1	P-14-009371/CA-INY-7305 (incl. P-14-009372, P-14-009373/CA-INY-7306, CA-INY-7307)	Multi-component	Precontact: Residential base. Historic: Mining resource.	Unknown	None
1	P-14-009374/CA-INY-7308	Multi-component	Precontact: Bedrock milling station. Historic: Refuse and discard.	Unknown	None
1	P-14-009375/CA-INY-7309	Precontact	Precontact: Lithic concentration.	Unknown	None
1	P-14-009381/CA-INY-7314	Multi-component	Precontact: Multi-class artifact concentration. Historic: Exploration and transportation resource, Water infrastructure resource.	Unknown	None

Segment #	Res. #	Age	Resource Type	Number of New Poles Visible from Site	Characteristics Sensitive to Visual Impact
1	P-14-009383/CA-INY-7316	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009403/CA-INY-7335	Precontact with historic isolate	Precontact: Bedrock milling station.	Unknown	None
1	P-14-009404/CA-INY-7336	Precontact with historic isolate	Precontact: Lithic concentration.	Unknown	None
1	P-14-009407/CA-INY-7338 (incl. P-14-009408/CA-INY-7339)	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009411/CA-INY-7341	Precontact with historic isolate	Precontact: Lithic concentration.	Unknown	None
1	P-14-009416/CA-INY-7343	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009421/CA-INY-7346 (incl. P-14-009422, P-14-009423/CA-INY-7347, CA-INY-7348)	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard, Rock feature.	Unknown	Setting, feeling, and association
1	P-14-009429/CA-INY-7353	Multi-component	Precontact: Lithic concentration. Historic: Mining resource.	Unknown	None
1	P-14-009431/CA-INY-7354	Precontact	Precontact: Lithic concentration.	Unknown	None
1	P-14-009432/CA-INY-7355 (incl. P-14-009433, P-14-009434/CA-INY-7356, CA-INY-7357)	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Unknown	None
1	P-14-009436	Precontact with historic isolate	Precontact: Temporary camp.	Unknown	Setting, feeling, and association
1	P-14-009438/CA-INY-7358	Multi-component	Precontact: Habitation area. Historic: Refuse and discard.	Unknown	None
1	P-14-009439/CA-INY-7359	Precontact with historic isolate	Precontact: Lithic concentration.	Unknown	None
1	P-14-009440/CA-INY-7360	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009443/CA-INY-7363	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Unknown	None
1	P-14-009444/CA-INY-7364	Multi-component	Precontact: Bedrock milling station. Historic: Refuse and discard.	Unknown	None
1	P-14-009445/CA-INY-7365 (incl. P-14-009446)/CA-INY-7366)	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009447/CA-INY-7367	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009449/CA-INY-7368	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None

Segment #	Res. #	Age	Resource Type	Number of New Poles Visible from Site	Characteristics Sensitive to Visual Impact
1	P-14-009450/CA-INY-7369	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009451/CA-94INY-7370	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009454/CA-INY-7371 (incl. P-14-009455, P-14-009456)/CA-INY-7372, CA-INY-7373)	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009457/CA-INY-7374	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009459/CA-INY-7376 (incl. P-14-009460/CA-INY-7377)	Multi-component	Precontact: Bedrock milling station. Historic: Refuse and discard, Rock feature.	Unknown	None
1	P-14-009461/CA-INY-7378	Multi-component	Precontact: Trail. Historic: Refuse and discard.	Unknown	Petroglyphs
1	P-14-009470/CA-INY-7381	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009471/CA-INY-7382	Precontact with historic isolate	Precontact: Bedrock milling station.	Unknown	None
1	P-14-009472/CA-INY-7383	Multi-component	Precontact: Multi-Class Artifact Concentration. Historic: Refuse and discard.	Unknown	Petroglyphs
1	P-14-009473/CA-INY-7384	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Unknown	Petroglyphs
1	P-14-009474/CA-INY-7385	Multi-component	Precontact: Multi-class Artifact Concentration. Historic: Refuse and discard	Unknown	Petroglyphs
1	P-14-009475/CA-INY-7386	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009479/CA-INY-7388	Precontact with historic isolate	Precontact: Lithic concentration.	Unknown	None
1	P-14-009480/CA-INY-7389	Multi-component	Precontact: Multi-class Artifact Concentration. Historic: Refuse and discard.	Unknown	Petroglyphs
1	P-14-009481/CA-INY-7390	Precontact with historic isolate	Precontact: Bedrock milling station.	Unknown	None
1	P-14-009483/CA-INY-7391	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009484/CA-INY-7392	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009485/CA-INY-7393	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None

Segment #	Res. #	Age	Resource Type	Number of New Poles Visible from Site	Characteristics Sensitive to Visual Impact
1	P-14-009486/CA-INY-7394	Multi-component	Precontact: Lithic concentration. H Historic: Refuse and discard.	Unknown	None
1	P-14-009487/CA-INY-7395	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009489/CA-INY-7397	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009490/CA-INY-7398	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009491/CA-INY-7399	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009492/CA-INY-7400	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-009493/CA-INY-7401	Precontact	Precontact: Lithic concentration.	Unknown	None
1	P-14-009494/CA-INY-7402	Precontact	Precontact: Lithic concentration.	Unknown	None
1	P-14-009495/CA-INY-7403 (incl. P-14-009496/CA-INY-7404)	Precontact	Precontact: Lithic concentration.	Unknown	None
1	P-14-009497/CA-INY-7405	Multi-component	Precontact: Lithic concentration. Historic: Electrical infrastructure resource, Refuse and discard.	Unknown	None
1	P-14-010005/CA-INY-7217 (incl. P-14-009233)	Precontact with historic isolate	Precontact: Lithic concentration.	Unknown	None
1	P-14-010012	Precontact	Precontact: Multi-class artifact concentration.	6	Petroglyphs
1	P-14-010015	Precontact	Precontact: Rock Art.	3	Petroglyphs
1	P-14-010018	Precontact	Precontact: Rock Art.	4	Petroglyphs
1	P-14-010025	Precontact	Precontact: Habitation area.	7	Petroglyphs
1	P-14-010036	Precontact	Precontact: Habitation area.	25	Petroglyphs
1	P-14-010037	Precontact	Precontact: Rock Art.	24	Petroglyphs
1	P-14-010038	Precontact	Precontact: Rock Art.	28	Petroglyphs
1	P-14-010039	Precontact	Precontact: Rock Art.	29	Petroglyphs
1	P-14-010049	Precontact	Precontact: Rock Art.	4	Petroglyphs
1	P-14-010961/CA-INY-8391	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	None

Segment #	Res. #	Age	Resource Type	Number of New Poles Visible from Site	Characteristics Sensitive to Visual Impact
1	P-14-010962/CA-INY-8392	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-011302	Precontact	Precontact: Rock Art.	40	Petroglyphs
1	P-14-011303	Precontact	Precontact: Rock Art.	40	Petroglyphs
1	P-14-011333	Precontact	Precontact: Rock Art.	33	Petroglyphs
1	P-14-011427	Precontact	Precontact: Rock Art.	14	Petroglyphs
1	P-14-012071/CA-INY-9262	Precontact	Precontact: Lithic concentration, Rock feature.	Unknown	Setting, feeling, and association
1	P-14-012777/CA-INY-9677	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-012785/CA-INY-9685	Historic with precontact isolate	Historic: Water infrastructure resource.	Unknown	None; element of mining district
1	P-14-012856	Precontact	Precontact: Rock Art.	22	Petroglyphs
1	P-14-014081/CA-INY-010523/SWCA-L030-1591	Precontact with historic isolate	Precontact: Multi-class artifact concentration.	Unknown	None
1	P-14-014201/CA-INY-010636/ SWCA-TROW-S-002/SWCAL030-5480	Precontact	Precontact: Lithic concentration.	Unknown	None
1	P-14-014238/CA-INY-010670/SWCA-L030-1010	Precontact with historic isolate	Precontact: Lithic concentration.	Unknown	Setting, feeling, and association
1	P-14-014243/CA-INY-010674/SWCA-L030-1025	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-014244/CA-INY-010675/SWCA-L030-1028	Precontact	Precontact: Temporary camp.	Unknown	None
1	P-14-014245/CA-INY-010676/SWCA-L030-1030	Precontact	Precontact: Residential base.	Unknown	None
1	P-14-014246/CA-INY-010677/SWCA-L030-1031	Precontact	Precontact: Temporary camp.	Unknown	Setting, feeling, and association
1	P-14-014247/CA-INY-010678/SWCA-L030-1032	Precontact with historic isolate	Precontact: Temporary camp.	Unknown	None
1	P-14-014271/CA-INY-010681/SWCA-L030-1038	Precontact	Precontact: Multi-class artifact concentration.	Unknown	None
1	P-14-014273/CA-INY-010683/SWCA-L030-1043	Precontact	Precontact: Temporary camp.	Unknown	None
1	P-14-014277/CA-INY-010687/SWCA-L030-1047	Precontact with historic isolate	Precontact: Temporary camp.	Unknown	None
1	P-14-014278/CA-INY-010688/SWCA-L030-1048	Precontact with protohistoric artifacts	Precontact: Residential base.	Unknown	None
1	P-14-014279/CA-INY-010689/SWCA-L030-1049	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-014311/CA-INY-010690/SWCA-L030-1050	Precontact	Precontact: Multi-class artifact concentration.	Unknown	None
1	P-14-014312/CA-INY-010691/SWCA-L030-1056	Precontact	Precontact: Burial area.	Unknown	Prehistoric mortuary complex
1	P-14-014313/CA-INY-010692/SWCA-L030-1056B	Precontact	Precontact: Burial area.	Unknown	Prehistoric mortuary complex

Segment #	Res. #	Age	Resource Type	Number of New Poles Visible from Site	Characteristics Sensitive to Visual Impact
1	P-14-014325/CA-INY-010700/SWCA-L030-1283	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-014326/CA-INY-010701/SWCA-L030-1285	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-014328/CA-INY-010703/SWCA-L030-1292	Historic	Historic: Refuse and discard, Rock feature.	Unknown	Setting, feeling, and association
1	P-14-014333/CA-INY-010708/SWCA-L030-1307	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-014335/CA-INY-010710/SWCA-L030-1590	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Unknown	None
1	P-14-014336/CA-INY-010711/SWCA-L030-1594	Multi-component	Precontact: Lithic concentration. Historic: Mining resource.	Unknown	Setting, feeling, and association
1	P-14-014337/CA-INY-010712/SWCA-L030-1673	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-014338/CA-INY-010713/SWCA-L030-1676	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-014339/CA-INY-010714/SWCA-L030-1677	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-014401/CA-INY-010715/SWCA-L030-1681	Historic with precontact isolate	Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-014402/CA-INY-010716/SWCA-L030-1688	Historic	Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-014403/SWCA-L030-1689	Historic with precontact isolate	Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-014404/CA-INY-010718/SWCA-L030-1692	Historic	Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-014405/CA-INY-010719/SWCA-L030-1700	Precontact	Precontact: Multi-class artifact concentration.	Unknown	Setting, feeling, and association
1	P-14-014406/SWCA-L030-1701	Historic	Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-014410/CA-INY-010724/SWCA-L030-1710	Historic	Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	P-14-014411/CA-INY-010725/SWCA-L030-2658	Precontact	Precontact: Multi-class artifact concentration.	Unknown	None
1	P-14-014412/CA-INY-010726/SWCA-L030-3560	Multi-component	Precontact: Multi-class artifact concentration. Historic: Exploration and transportation resource.	Unknown	None
1	P-14-014415/CA-INY-010729/SWCA-L030-4370	Multi-component	Precontact: Residential base. Historic: Homestead/farm/ranch resource.	Unknown	None
1	P-14-014422/CA-INY-010731/SWCA-L030-4376	Precontact	Precontact: Multi-class artifact concentration.	Unknown	None
1	P-14-014423/CA-INY-010732/SWCA-L030-4383	Multi-component	Precontact: Bedrock milling station. Historic: Refuse and discard.	Unknown	None

Segment #	Res. #	Age	Resource Type	Number of New Poles Visible from Site	Characteristics Sensitive to Visual Impact
1	P-14-014427/CA-INY-010736/SWCA-L030-4391	Multi-component	Precontact: Temporary camp. Historic: Homestead/farm/ranch resource.	Unknown	None
1	P-14-014429/CA-INY-010738/SWCA-L030-4397	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-014433/CA-INY-010742/SWCA-L030-4403	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-014435/CA-INY-010744/SWCA-L030-4414	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-014436/CA-INY-010745/SWCA-L030-4415	Precontact with historic isolate	Precontact: Multi-class artifact concentration.	Unknown	None
1	P-14-014452/CA-INY-010761/SWCA-L030-5479	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-014455/CA-INY-010764/SWCA-L030-5489	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-014456/CA-INY-010765/SWCA-L030-5490	Precontact	Precontact: Multi-class artifact concentration.	Unknown	None
1	P-14-014462/SWCA-L030-5502	Precontact	Precontact: Multi-class artifact concentration.	Unknown	None
1	P-14-014463/SWCA-L030-5504	Precontact with historic isolate	Precontact: Residential base.	Unknown	None
1	P-14-014464/SWCA-L030-5505	Multi-component	Precontact: Multi-class artifact concentration. Historic: Homestead/farm/ranch resource.	Unknown	None
1	P-14-014465/SWCA-L030-5506	Precontact	Precontact: Lithic concentration.	Unknown	None
1	P-14-014466/SWCA-L030-5509	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-014467/SWCA-L030-5513	Precontact	Precontact: Habitation area.	Unknown	None
1	P-14-014469/CA-INY-010778/SWCA-L030-5517	Multi-component	Precontact: Multi-class artifact concentration. Historic: Homestead/Farm/Ranch resource.	Unknown	Cupules
1	P-14-014471/CA-INY-010780/SWCA-L030-5519	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Unknown	None
1	P-14-014472/CA-INY-010781/SWCA-L030-5520	Multi-component	Precontact: Habitation area. Historic: Refuse and discard.	Unknown	None
1	P-14-014473/CA-INY-010782/SWCA-L030-5522	Multi-component with protohistoric artifacts	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-014490/CA-INY-010799/SWCA-L030-6350	Precontact	Precontact: Lithic concentration.	Unknown	None
1	P-14-014491/CA-INY-010800/SWCA-L030-6352	Precontact	Precontact: Lithic concentration.	Unknown	None
1	P-14-014492/CA-INY-010801/SWCA-L030-6356	Precontact with historic isolate	Precontact: Lithic concentration.	Unknown	None

Segment #	Res. #	Age	Resource Type	Number of New Poles Visible from Site	Characteristics Sensitive to Visual Impact
1	P-14-014493/CA-INY-010802/SWCA-L030-6359	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-014494/CA-INY-010803/SWCA-L030-6363	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Unknown	None
1	P-14-014495/CA-INY-010804/SWCA-L030-6365	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Unknown	None
1	P-14-014496/CA-INY-010805/SWCA-L030-6366	Precontact	Precontact: Lithic concentration.	Unknown	None
1	P-14-014498/SWCA-L030-6369	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Unknown	None
1	P-14-014499/CA-INY-010808/SWCA-L030-6370	Precontact	Precontact: Temporary camp.	Unknown	None
1	P-14-014504/SWCA-L030-6385	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Unknown	None
1	P-14-014505/SWCA-L030-6387	Precontact with historic isolate	Precontact: Temporary camp.	Unknown	None
1	P-14-014506/CA-INY-010815/SWCA-L030-6389	Precontact with historic isolate	Precontact: Bedrock milling station.	Unknown	None
1	P-14-014507/SWCA-L030-6390	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Unknown	None
1	P-14-014509/CA-INY-010818/SWCA-L030-6397	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-014510/CA-INY-010819/SWCA-L030-6399	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Unknown	None
1	P-14-014512/CA-INY-010821/SWCA-L030-6401	Multi-component	Precontact: Bedrock milling station. Historic: Refuse and discard.	Unknown	None
1	P-14-014513/CA-INY-010822/SWCA-L030-6402	Multi-component	Precontact: Bedrock milling station. Historic: Refuse and discard, Rock feature.	Unknown	None
1	P-14-014520/CA-INY-010829/SWCA-L030-6419	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-014525/CA-INY-010834/SWCA-L030-6428	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	P-14-014526/CA-INY-010835/SWCA-L030-6430	Precontact	Precontact: Lithic concentration.	Unknown	Setting, feeling, and association
1	P-14-014527/CA-INY-010836/SWCA-L030-6432	Precontact	Precontact: Lithic concentration.	Unknown	Setting, feeling, and association
1	P-14-014529/CA-INY-010838/SWCA-L030-7677	Precontact with historic isolate	Precontact: Multi-class artifact concentration.	Unknown	None
1	P-14-014531/CA-INY-010840/SWCA-L030-12035	Precontact	Precontact: Rock art.	Unknown	Petroglyphs
1	P-14-014534/CA-INY-010843/SWCA-L030-15068	Precontact	Precontact: Multi-class artifact concentration.	Unknown	Setting, feeling, and association

Segment #	Res. #	Age	Resource Type	Number of New Poles Visible from Site	Characteristics Sensitive to Visual Impact
1	P-14-014666/CA-INY-010922/SWCA-L030-6000	Precontact	Precontact: Residential base.	Unknown	None
1	P-14-015413/CA-INY-011519/ SWCA-L030-S-62813	Precontact	Precontact: Multi-class artifact concentration.	Unknown	None
1	P-14-015417/CA-INY-011523/SWCA-TROW-S-003	Precontact	Precontact: Lithic concentration.	Unknown	None
2	P-15-002500	Historic	Historic: Mining resource.	Unknown	Setting and association with district
2	P-15-008676	Precontact	Precontact: District.	Unknown	Petroglyphs and potentially other district-related characteristics
2	P-15-021123/SWCA-L030-1165	Historic	Historic: Mining resource.	Unknown	Setting and association with district
2	P-15-021124/SWCA-L030-1171	Historic	Historic: Mining resource.	Unknown	Setting and association with district
2	P-15-021125/SWCA-L030-1172	Historic	Historic: Refuse and discard.	Unknown	Setting and association with district
2	P-15-021126/SWCA-L030-1173	Historic	Historic: Mining resource.	Unknown	Setting and association with district
2	P-15-021127/SWCA-L030-1174	Historic	Historic: Exploration and transportation resource.	Unknown	Setting and association with district
2	P-15-021129/SWCA-L030-1177	Historic	Historic: Homestead/farm/ranch resource.	Unknown	Setting and association with district
2	P-15-021132/SWCA-L030-1181	Historic	Historic: Mining resource.	Unknown	Setting and association with district
2	P-15-021138/SWCA-L030-5153	Historic	Historic: Mining resource.	Unknown	Setting and association with district
2	P-15-021139/SWCA-L030-5154	Historic	Historic: Mining resource.	Unknown	Setting and association with district
2	P-15-021140/SWCA-L030-5155	Historic	Historic: Mining resource.	Unknown	Setting and association with district
2	P-15-021143/SWCA-L030-5160	Historic	Historic: Mining resource.	Unknown	Setting and association with district
2	P-15-021144/SWCA-L030-5161	Historic	Historic: Refuse and discard, Rock feature.	Unknown	Setting and association with district
3N	P-36-000035	Precontact	Precontact: Habitation area.	25	Petroglyphs
3N	P-36-000073	Precontact	Precontact: Habitation area.	19	Petroglyphs
3N	P-36-000208	Precontact	Precontact: Habitation area.	1	Petroglyphs
3N	P-36-000403/CA-SBR-403	Multi-component	Precontact: Residential base. Historic: Homestead/farm/ranch resource.	Unknown	None
1	SCE-CWA-2020A (incl. SCE-CWA-2020B)	Multi-component	Precontact: Bedrock milling station. Historic: Homestead/farm/ranch resource.	Unknown	None
1	SWCA-L030-1001	Precontact	Precontact: Lithic concentration.	Unknown	None
1	SWCA-L030-1007	Precontact	Precontact: Lithic concentration.	Unknown	None
1	SWCA-L030-1017	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	SWCA-L030-1023	Precontact	Precontact: Lithic concentration.	Unknown	None
1	SWCA-L030-1024	Precontact	Precontact: Lithic concentration.	Unknown	None

Segment #	Res. #	Age	Resource Type	Number of New Poles Visible from Site	Characteristics Sensitive to Visual Impact
1	SWCA-L030-1034	Precontact	Precontact: Lithic concentration.	Unknown	None
1	SWCA-L030-1035	Precontact	Precontact: Lithic concentration.	Unknown	None
1	SWCA-L030-1041	Precontact with historic isolate	Precontact: Lithic concentration.	Unknown	None
1	SWCA-L030-1044	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	SWCA-L030-1045	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	SWCA-L030-1046	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	SWCA-L030-1058	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
3N	SWCA-L030-1106	Historic	Historic: Mining resource.	Unknown	None; eligible under Criterion 1 due to association with historic mining
1	SWCA-L030-1131	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard, Rock feature.	Unknown	None
1	SWCA-L030-1136	Precontact	Precontact: Lithic concentration.	Unknown	None
2	SWCA-L030-1168	Historic	Historic: Mining resource.	Unknown	Setting and association with district
2	SWCA-L030-1170	Historic	Historic: Refuse and discard.	Unknown	None
2	SWCA-L030-1184	Historic	Historic: Refuse and discard.	Unknown	Setting and association with district
2	SWCA-L030-1185	Historic	Historic: Mining resource.	Unknown	Setting and association with district
1	SWCA-L030-1258	Precontact	Precontact: Lithic concentration.	Unknown	None
1	SWCA-L030-1267	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard, Water infrastructure resource.	Unknown	None
1	SWCA-L030-1271	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	SWCA-L030-1295	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	SWCA-L030-1305	Precontact	Precontact: Rock Art.	6	Petroglyphs
1	SWCA-L030-15000	Precontact with historic isolate	Precontact: Lithic concentration.	Unknown	None
1	SWCA-L030-1707	Multi-component	Precontact: Lithic concentration. Historic: Electrical infrastructure resource, Refuse and discard.	Unknown	None

Segment #	Res. #	Age	Resource Type	Number of New Poles Visible from Site	Characteristics Sensitive to Visual Impact
1	SWCA-L030-4385	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	SWCA-L030-4399	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	SWCA-L030-4408	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	SWCA-L030-4416	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	SWCA-L030-4436	Precontact	Precontact: Lithic concentration.	Unknown	None
2	SWCA-L030-5150	Historic	Historic: Mining resource.	Unknown	Setting and association with district
2	SWCA-L030-5151	Historic	Historic: Exploration and transportation resource, Mining resource.	Unknown	Setting and association with district
2	SWCA-L030-5152	Historic	Historic: Mining resource.	Unknown	Setting and association with district
1	SWCA-L030-5476	Precontact	Precontact: Lithic concentration.	Unknown	None
1	SWCA-L030-5491	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	SWCA-L030-5495	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	SWCA-L030-5496	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	SWCA-L030-5498	Precontact with historic isolate	Precontact: Lithic concentration.	Unknown	None
1	SWCA-L030-5524	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard, Rock feature.	Unknown	None
1	SWCA-L030-6001	Precontact with historic isolate	Precontact: Lithic concentration.	Unknown	None
1	SWCA-L030-6367	Precontact	Precontact: Lithic concentration.	Unknown	None
1	SWCA-L030-6373	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	SWCA-L030-6396	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	SWCA-L030-6413	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	SWCA-L030-6416	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None

Segment #	Res. #	Age	Resource Type	Number of New Poles Visible from Site	Characteristics Sensitive to Visual Impact
1	SWCA-L030-6418	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	SWCA-L030-6421	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	SWCA-L030-7591	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
1	SWCA-L030-7679	Multi-component	Precontact: Lithic concentration. Historic: Homestead/farm/ranch resource, Mining resource.	Unknown	None; mining site
1	SWCA-L030-7720	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	Setting, feeling, and association
1	SWCA-L030-7736	Precontact	Precontact: Multi-class artifact concentration.	Unknown	None
1	SWCA-L030-S-62819	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	None

TRIBAL CULTURAL RESOURCES – THE OWENS VALLEY LANDSCAPE

Table Ap.5-8. Resources Within the Owens Valley Landscape

Confidential Information

CULTURAL RESOURCES DATA FOR ALTERNATIVES

Table Ap.5-9. Archaeological Resources: Crater Mountain Realignment Alternative

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
170-99-23-S19	BLM Bishop FO, LADWP	Precontact with historic isolate	Precontact: Habitation area.	Precontact: Eligible under Criteria 1, 3 and 4.	Install one new LWS monopole, associated work area, and one new access road. Existing access road will be improved and graded as needed.
P-14-000392/ CA-INY-392	BLM Bishop FO, Private	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criteria 1 and 4.	Existing access road will be improved and graded as needed.
P-14-002789/ CA-INY-2789	BLM Bishop FO, LADWP	Multi-component	Precontact: Multi-class artifact concentration.	Precontact: Eligible under Criterion 4. Historic: Ineligible.	Existing access road will be improved and graded as needed.
P-14-005632/ CA-INY-5281	LADWP	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Precontact: Eligible under Criteria 1 and 4. Historic: Ineligible.	One structure work area is within eight feet of site boundary. One pull site. Additional pull site is within 25 feet of site boundary. Existing access road will be improved and graded as needed.
P-14-011817/ CA-INY-9092	BLM Bishop FO	Precontact	Precontact: Habitation area.	Precontact: Eligible under Criteria 1 and 4.	No project components are within site boundary.
P-14-011819/ CA-INY-9094 (including P-14-012856 and P-14-012857/ P-14-013134)	BLM Bishop FO	Precontact	Precontact: Habitation area.	Precontact: Eligible under Criteria 1, 3 and 4.	Install one new LWS monopole, associated work area, and one new access road. Existing access road will be improved and graded as needed within 10 feet of the site.
SWCA-L030-S-60019	Private, unknown, and BLM Bishop FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criteria 1 and 4.	One structure work area is within 25 feet of the site. No project components are within site boundary.
SWCA-L030-S-60021	Private, unknown and BLM Bishop FO	Multi-component	Precontact: Habitation area. Historic: Refuse and discard.	Precontact: Eligible under Criteria 1 and 4. Historic: Ineligible.	Install one new LWS monopole and associated work area. Existing access road will be improved and graded as needed.
SWCA-L030-S-60023	LADWP	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible under Criteria 1 and 4. Historic: Eligible under Criteria 1 and 4.	Existing access road will be improved and graded as needed within 6 feet of site boundary.
SWCA-L030-S-60039	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	No project components occur within the site boundary.
SWCA-L030-S-60040	LADWP	Precontact with protohistoric isolate	Precontact: Multi-class artifact concentration.	Precontact: Eligible under Criterion 4.	No project components occur within the site boundary.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-S-60055	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	No project components occur within the site boundary.
SWCA-L030-S-60059	LADWP	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Eligible under Criteria 1 and 4.	Pull site is within 25 feet of site boundary. No project components are within site boundary.
SWCA-L030-S-60065	LADWP	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible under Criteria 1 and 4.	One structure work area is within 30 feet of the site. No project components are within site boundary.
SWCA-L030-S-60069	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criteria 1 and 4.	No project components are within site boundary.
SWCA-L030-S-60071	LADWP	Multi-component	Precontact: Multi-class artifact concentration. Historic: Homestead/farm/ranch resource.	Precontact: Eligible under Criteria 1 and 4. Historic: Eligible under Criteria 1 and 4.	Install one new LWS monopole and associated work area. Additional work area is within 25 feet of site boundary. Two existing access roads will be improved and graded as needed.
SWCA-L030-S-60072	LADWP	Precontact	Precontact: Temporary camp.	Precontact: Eligible under Criteria 1 and 4.	Existing access road will be improved and graded as needed.
SWCA-L030-S-60088	LADWP	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Precontact: Eligible under Criteria 1 and 4. Historic: Ineligible.	One structure work area is within 25 feet of site boundary. No project components are within site boundary.
SWCA-L030-S-60101	BLM Bishop FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criteria 1.	Existing access road will be improved and graded as needed
SWCA-L030-S-60106	BLM Bishop FO	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	No project components occur within the site boundary.
SWCA-L030-S-60128	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 1.	No project components occur within the site boundary.
SWCA-L030-S-60130	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	No project components occur within the site boundary.
SWCA-L030-S-61010	BLM Bishop FO, LADWP	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Precontact: Eligible under Criteria 1 and 4. Historic: Ineligible.	Two existing access roads will be improved and graded as needed.
SWCA-L030-S-61013	BLM Bishop FO, LADWP	Precontact	Precontact: Residential base.	Precontact: Eligible under Criteria 1 and 4.	Two structure work areas are within 30 feet of site boundary. Existing access road will be improved and graded as needed.
SWCA-L030-S-61021	LADWP	Precontact	Precontact: Bedrock milling station.	Precontact: Eligible under Criteria 1 and 4.	One structure work area is within 25 feet of the site. No project components are within site boundary.
SWCA-L030-S-61022	LADWP	Precontact	Precontact: Bedrock milling station.	Precontact: Eligible under Criteria 1 and 4.	One structure work area is within 25 feet of the site. No project components are within site boundary.
SWCA-L030-S-61028	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	One structure work area is within 25 feet of site boundary. No project components are within site boundary.
SWCA-L030-S-61031	LADWP	Precontact with historic isolate	Precontact: Multi-class artifact concentration.	Precontact: Eligible under Criterion 4.	No project components are within site boundary.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-S-61033	LADWP	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Eligible under Criterion 4.	Existing access road will be improved and graded as needed.
SWCA-L030-S-61035	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Existing access road will be improved and graded as needed.
SWCA-L030-S-61036	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	No project components are within site boundary. Existing access road will be improved and graded as needed within seven feet of site boundary.
SWCA-L030-S-61040	LADWP	Precontact with protohistoric isolate	Precontact: Temporary camp.	Precontact: Eligible under Criterion 4.	No project components occur within the site boundary.
SWCA-L030-S-61055	LADWP	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible under Criteria 1 and 4. Historic: Eligible under Criteria 1 and 4.	Install one LWS monopole and associated work area. Existing access road will be improved and graded as needed. Additional access road is within 15 feet of site boundary.
SWCA-L030-S-61060	LADWP	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Eligible under Criterion 4.	Existing access road will be improved and graded as needed.
SWCA-L030-S-61063	LADWP	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible under Criteria 1 and 4. Historic: Ineligible.	One pull site, one guard site, and one structure work area. Existing access road will be improved and graded as needed.
SWCA-L030-S-61067	LADWP	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible under Criterion 4. Historic: Ineligible.	One guard site.
SWCA-L030-S-61070	LADWP	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Eligible under Criterion 4.	One structure work area is within 25 feet of site boundary. No project components are within site boundary.
SWCA-L030-S-61072	BLM Bishop FO	Precontact	Precontact: Temporary camp.	Precontact: Eligible under Criteria 1 and 4.	No project components occur within the site boundary.
SWCA-L030-S-62000	BLM Bishop FO	Precontact	Precontact: Rock feature.	Precontact: Eligible under Criteria 1 and 4.	No project components occur within the site boundary.
SWCA-L030-S-62003	BLM Bishop FO	Precontact	Precontact: Habitation area.	Precontact: Eligible under Criteria 1 and 4.	No project components occur within the site boundary.
SWCA-L030-S-62007	BLM Bishop FO	Precontact	Precontact: Residential base.	Precontact: Eligible under Criteria 1 and 4.	No project components occur within the site boundary.
SWCA-L030-S-62009	BLM Bishop FO	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Eligible under Criterion 1.	Existing access road will be improved and graded as needed.
SWCA-L030-S-62018	BLM Bishop FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	No project components are within site boundary.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-S-62025	BLM Bishop FO	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Eligible under Criterion 4.	One structure work area.
SWCA-L030-S-62029	BLM Bishop FO, LADWP	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	One structure work area is within 25 feet of site boundary. No project components are within site boundary.
SWCA-L030-S-62030	BLM Bishop FO, LADWP	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible under Criterion 4. Historic: Ineligible.	One structure work area is within 25 feet of site boundary. No project components are within site boundary.
SWCA-L030-S-62031	BLM Bishop FO	Precontact with historic isolate	Precontact: Multi-class artifact concentration.	Precontact: Eligible under Criterion 4.	One structure work area.
SWCA-L030-S-62034	BLM Bishop FO, LADWP	Multi-component	Precontact: Residential base. Historic: Water infrastructure resource.	Precontact: Eligible under Criteria 1 and 4. Historic: Ineligible.	Install one new LWS monopole, associated work area, and one new access road. Existing access road will be improved and graded as needed.
SWCA-L030-S-62038	LADWP	Precontact	Precontact: Residential base.	Precontact: Eligible under Criteria 1 and 4.	One structure work area is within 25 feet of the site. Existing access road will be improved and graded as needed.
SWCA-L030-S-62042	LADWP	Precontact with historic isolate	Precontact: Multi-class artifact concentration.	Precontact: Eligible under Criterion 4.	Install one new LWS monopole, associated work area, and one new access road.
SWCA-L030-S-62044	LADWP	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Precontact: Eligible under Criteria 1 and 4. Historic: Ineligible.	Install one new TSP monopole, associated work area, overhead subtransmission line and one new access road.

Table Ap.5-10. Archaeological Resources: Manzanar Realignment Alternative

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-000420/CA-INY-420	LADWP	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Precontact: Eligible under Criterion 4. Historic: Eligible under Criterion 4.	One structure work area is within 10 feet of the site boundary. An additional structure work area is within 30 feet of site boundary. No project components are located within site boundaries.
P-14-000422/CA-INY-422	LADWP	Precontact	Precontact: Lithic concentration	Precontact: Eligible under Criterion 4.	One structure work area and one new access road. Existing access road will be improved and graded as needed.
P-14-002787/CA-INY-2787	LADWP	Precontact with historic isolate	Precontact: Lithic concentration	Precontact: Eligible under Criterion 4.	One new access road will be constructed. Existing access road will be improved and graded as needed.
P-14-002788/CA-INY-2788	LADWP	Precontact	Precontact: Lithic concentration	Precontact: Eligible under Criterion 4.	One structure work area is within 25 feet of site boundary. Existing access road will be improved and graded as needed.
P-14-003383/CA-INY-3383	LADWP	Precontact	Precontact: Lithic concentration	Precontact: Eligible under Criterion 4.	Existing access road will be improved and graded as needed. An additional existing access road is within 30 feet of site boundary.
P-14-003404/CA-INY-3404	LADWP	Historic	Historic: Exploration and transportation resource, Refuse and discard	Historic: Ineligible.	Two structure work areas, construction of one new unpaved access road, and the use and maintenance of an existing access road.
P-14-004589/CA-INY-4589	LADWP	Multi-component	Precontact: Lithic concentration Historic: Water infrastructure resource.	Precontact: Eligible under Criterion 4. Historic: Eligible under Criterion 4.	Install one new LWS monopole and associated work area. Existing access road will be improved and graded as needed.
P-14-010966/CA-INY-8396	LADWP	Precontact with historic isolate	Precontact: Lithic concentration	Precontact: Eligible under Criterion 4.	One structure work area.
P-14-012341/CA-INY-9474	LADWP	Precontact with historic isolate	Precontact: Multi-class artifact concentration	Precontact: Eligible under Criterion 4.	No project components are within site boundary.
P-14-012346/CA-INY-9479	LADWP	Precontact	Precontact: Lithic concentration	Precontact: Ineligible.	No project components or elements are located within site boundaries.
P-14-012357/CA-INY-9490	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	No project components or elements are located within site boundaries.
P-14-012362/CA-INY-9495	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	No project components or elements are located within site boundaries.
P-14-012382/CA-INY-9515	LADWP	Precontact	Precontact: Temporary camp.	Precontact: Eligible under Criterion 4.	No project components are within site boundary.
P-14-012386/CA-INY-9519 (includes P-14-012387 and P-14-012391)	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	Install two new LWS monopoles, two associated work areas, and two new access roads. Existing access road will be improved and graded as needed.
P-14-012392/CA-INY-9525	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	No project components are within site boundary.
P-14-012398/CA-INY-9531	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	One pull site.
P-14-012399/CA-INY-9532	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	No project components are within site boundary.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-012438/CA-INY-9570	LADWP	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Ineligible.	One structure work area.
P-14-012637 (Includes P-14-012369 and P-14-012377)	LADWP	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	No project components are within site boundary.
P-14-013144/CA-INY-9891	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	Existing access road will be improved and graded as needed within 15 feet of site boundary.
P-14-014240/CA-INY-14240 (includes P-14-014241)	LADWP	Precontact with historic isolate	Precontact: Multi-class artifact concentration.	Precontact: Eligible under Criterion 4.	Two pull sites, install two new LWS monopoles, two associated work areas, and one new access road. Two existing access roads will be improved and graded as needed.
SRI 1090	LADWP	Precontact	Precontact: Temporary camp.	Precontact: Eligible under Criterion 4.	No project components are within site boundary.
SRI 1103	LADWP	Precontact with historic isolate	Precontact: Temporary camp.	Precontact: Eligible under Criterion 4.	Existing access road will be improved and graded as needed.
SRI 1163	LADWP	Precontact	Precontact: Temporary camp.	Precontact: Eligible under Criterion 4.	No project components or elements are located within site boundaries.
SRI 1193	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	No project components or elements are located within site boundaries.
SRI 1213	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	One structure work area is within 30 feet of site boundary. No project components are within site boundary.
SRI 1215	LADWP	Precontact	Precontact: Temporary camp.	Precontact: Eligible under Criterion 4.	Existing access road will be improved and graded as needed within 30 feet of site boundary. No project components are within site boundary.
SRI 3011	LADWP	Precontact	Precontact: Temporary camp.	Precontact: Eligible under Criterion 4.	One structure work area is within 30 feet of site boundary. No project components are within site boundary.
SRI 3026	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	Two pull sites, one structure work area, and one LWS monopole installation.
SRI 3115	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	One pull site.
SRI 3166	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	No project components or elements are located within site boundaries.
SRI 3273	LADWP	Precontact with historic isolate	Precontact: Multi-class artifact concentration.	Precontact: Eligible under Criterion 4.	Existing access road will be improved and graded as needed within 15 feet of site boundary.
SRI 3289	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	One structure work area is within 25 feet of site boundary.
SRI 3292	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	One structure work area is within 30 feet of site boundary. No project components are within site boundary.
SRI 4014	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	The use and maintenance of an existing unpaved access road.
SRI 4017	LADWP	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	One structure work area is within 25 feet of site boundary. No project components are within site boundary.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SRI 5036	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	Use of and maintenance of an unpaved access road.
SRI 5091	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	Two structure work areas within 25 feet of site boundary. Existing access road will be improved and graded as needed within 30 feet of site boundary. No project components are within site boundary.
SRI 6004	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	One structure work area.
SRI 6006	LADWP	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Ineligible.	No project components or elements are located within site boundaries.
SRI 7001	LADWP	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Precontact: Eligible under Criterion 4. Historic: Eligible under Criterion 4.	Two structure work areas within 30 feet of site boundary. No project components are within site boundary.
SRI 7018	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	No project components or elements are located within site boundaries.
SRI 7023	LADWP	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible under Criterion 4. Historic: Ineligible.	Two structure work areas are within 25 feet of site boundary.
SRI 7200	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	One structure work area within 30 feet of site boundary. Existing access road will be graded and improved as needed within 15 feet of site boundary.
SRI 8003	LADWP	Historic	Historic: Refuse and discard.	Historic: Ineligible.	One structure work area.
SRI 9104	LADWP	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	No project components are within site boundary.
SRI 9106	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	No project components or elements are located within site boundaries.
SRI 9108	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	One structure work area within 30 feet of site boundary. No project components are within site boundary.
SRI 9110	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	One pull site.
SRI 9114	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	No project components are within site boundary.
SRI 9116	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	One structure work area is within 30 feet of site boundary. No project components are within site boundary.
SRI 9118	LADWP	Precontact with historic isolate	Precontact: Temporary camp.	Precontact: Eligible under Criterion 4.	Install one new LWS monopole, associated work area, and one new access road. Existing access road will be improved and graded as needed.
SRI 9120	BLM Bishop FO and LADWP	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	No project components or elements are located within site boundaries.
SRI 9122	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	No project components or elements are located within site boundaries.
SRI 9124	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	Install one new LWS monopole and associated work area.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SRI 9128	LADWP	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Precontact: Eligible under Criterion 4. Historic: Eligible under Criterion 4.	One guard site. Existing access road will be improved and graded as needed. One structure work area is within 30 feet of site boundary.
SRI 9132	LADWP	Precontact	Precontact: Temporary camp.	Precontact: Eligible under Criterion 4.	Install one new LWS monopole, associated work area, and one new access road. Existing access road will be improved and graded as needed
SRI 9144	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	Existing access road will be improved and graded as needed.
SRI 9148	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	Install one new LWS monopole, associated work area, and one new access road. Existing access road will be improved and graded as needed.
SRI 9154	LADWP	Precontact with historic isolate	Precontact: Temporary camp.	Precontact: Eligible under Criterion 4.	One structure work area, one monopole installation and one existing access road will be improved and graded as needed within 30 feet of site boundary. No project components are within site boundary.
SRI 9156	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	One structure work area. Install one new LWS monopole within 15 feet of site boundary. Existing access road will be improved and graded as needed.
SRI 9160	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible	No project components or elements are located within site boundaries.
20231023-MER-001-S	LADWP	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	Install two new LWS monopoles, two associated work areas, and two new access roads. Existing access road will be improved and graded as needed.
20231031-AJD-001-S	LADWP	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	Work area for a subtransmission tower; One new access spur road; Existing access road will be graded and improved as needed
20231031-MER-001-S	LADWP	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	Work area for a subtransmission tower; One new access spur road; Existing access road will be graded and improved as needed
20230822-BTB-001-S	LADWP	Historic	Historic: Water infrastructure.	Historic: Ineligible.	There are no project components within the site boundary.
20230824-G_F-002-S	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	One structure work area is within 25 feet of site boundary.
BLM-DPR 175-4	LADWP	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4. Historic: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	One structure work area is within 30 feet of site boundary. Existing access road will be improved and graded as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
20230822-AJD-002-S	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	There are no project components within the site boundary.
20230822-MER-001-S	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	One structure work area is within 25 feet of site boundary. No project components are within site boundary.
20230822-MER-003-S	LADWP	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4.	There are no project components within the site boundary.
20230823-BTB-001-S	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4.	One structure work area is within 25 feet of site boundary. No project components are within site boundary.
20230823-MER-001-S	LADWP	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Eligible individually under Criterion 4.	Install one new LWS monopole and associated work area. One new access road within 1 foot of site boundary.
20230824-G_F-001-S	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4.	One structure work area is within 30 feet of site boundary. No project components are within site boundary.
20230824-MER-001-S	LADWP	Precontact	Precontact: Quarry.	Precontact: Eligible individually under Criterion 4.	Install one new LWS monopole, associated work area, and one new access road. Additional work area is within 25 feet of site boundary. Existing access road will be improved and graded as needed.
20230825-MER-002-S	LADWP	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible. Historic: Ineligible.	There are no project components within the site boundary.
20230825-MER-006-S	LADWP	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4.	Existing access road will be improved and graded as needed.
20230826-MER-001-S	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4.	Install one new LWS monopole and associated work area. Existing access road will be improved and graded as needed within 1 foot of site boundary.
20230827-MER-001-S	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	Install one new LWS monopole, associated work area, and one new access road.
20230828-AJD-001-S	LADWP	Precontact	Precontact: Temporary camp.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	There are no project components within the site boundary.
20230829-G_F-001-S	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	Install one new LWS monopole, associated work area, and one new access road. Existing access road will be improved and graded as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
20230829-MER-001-S	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	One structure work area is within 25 feet of site boundary. No project components are within site boundary.
20230831-MER-001-S	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	Two structure work areas are within 25 feet of site boundary. Existing access road will be improved and graded as needed.
20230919-AJD-001-S	LADWP	Historic	Historic: Homestead/farm/ranch resource.	Historic: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	One pull site.
20230919-AJD-002-S	LADWP	Historic	Historic: Homestead/farm/ranch resource.	Historic: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	Existing access road will be improved and graded as needed.
20230921-AJD-001-S	LADWP	Precontact with historic isolate	Precontact: Multi-class artifact concentration.	Precontact: Eligible individually under Criterion 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	One structure work area is within 25 feet of site boundary. Existing access road will be improved and graded as needed.
20230923-AJD-001-S	LADWP	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4. Historic: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	Install one new LWS monopole, associated work area, and one new access road. Existing access road will be improved and graded as needed.
20230925-AJD-001-S	LADWP	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4. Historic: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	Install two new LWS monopoles, two associated work areas, and one new access road. An additional work area is within 30 feet of site boundary. Two existing access roads will be improved and graded as needed.
20230926-AJD-003-S	LADWP	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4. Historic: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	Structure work area.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
20230927-AJD-001-S	LADWP	Historic with precontact isolate	Historic: Refuse and discard.	Historic: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	One structure work area is within 25 feet of site boundary.
20230927-MER-001-S	LADWP	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4. Historic: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	There are no project components within the site boundary.
20231029-AJD-001-S	LADWP	Historic with precontact isolate	Historic: Exploration and transportation resource, Refuse and discard.	Historic: Eligible under Criteria 1 and 4, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	Install one new LWS monopole and associated work area. Existing access roads will be improved and graded as needed.
20231029-MER-002-S	LADWP	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4. Historic: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	Existing access road will be improved and graded as needed.
20231031-MER-001-S	LADWP	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	Existing access road will be improved and graded as needed. One structure work area is within 25 feet of site boundary.
20231031-AJD-001-S	LADWP	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	Existing access road will be improved and graded as needed. One structure work area is within 25 feet of site boundary.
20231023-MER-001-S	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	Install two subtransmission towers with associated work areas; Two additional work areas for subtransmission towers; Three access spur roads; Existing access road will be graded and improved as needed
P-14-000035/CA-INY-35	LADWP	Precontact	Precontact: Habitation area.	Precontact: Eligible individually under Criterion 4.	Existing access road will be improved and graded as needed.
P-14-000081/CA-INY-81	LADWP	Multi-component	Precontact: Multi-class artifact concentration.	Precontact: Eligible individually under Criterion 4, and eligible as contributor to	Existing access road will be improved and graded as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
			Historic: Refuse and discard.	Patsiata Historic District under Criteria 1, 2, 3, and 4. Historic: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	
P-14-000085/CA-INY-85	LADWP	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4. Historic: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	One new access spur road; Existing access road will be graded and improved as needed
P-14-000311/CA-INY-311	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4.	Install one new LWS monopole, associated work area, and one new access road. Existing access road will be improved and graded as needed.
P-14-002783/CA-INY-2783	LADWP	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4. Historic: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	Existing access road will be improved and graded as needed.
P-14-002784/CA-INY-2784	LADWP	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	Existing access road will be improved and graded as needed within 10 feet of site boundary.
P-14-004607	LADWP	Multi-component	Precontact: Lithic concentration. Historic: Exploration and transportation resource.	Precontact: Ineligible. Historic: Ineligible.	No project components are within site boundary.
P-14-005654/CA-INY-5301	LADWP	Historic with precontact isolate	Historic: Refuse and discard.	Historic: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	Existing access road will be graded and improved as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-007831	LADWP	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible individually under Criterion 4, and eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	Install one new LWS monopole, associated work area, and one new access road. Existing access road will be improved and graded as needed.
P-14-007834	LADWP	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4. Historic: Ineligible.	One structure work area within 30 feet of site boundary. Existing access road will be improved and graded as needed.
P-14-008008; P-14-013589/ CA-INY-10191	LADWP	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4. Historic: Ineligible individually, eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	One structure work area. Existing access road will be improved and graded as needed.
P-14-009248; P-14-014226; P-14-014227; P-14-014228/ CA-INY-7229; CA-INY-10662; CA-INY-10663	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible individually under Criteria 1 and 4, and eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	Install one new TSP monopole, associated work area, three pull sites, and two guard sites. Existing access road will be improved and graded as needed.
P-14-013586/CA-INY-10188	LADWP	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Eligible individually under Criterion 4, and eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	Two structure work areas are within 30 feet of site boundary. Existing access road will be improved and graded as needed.
P-14-013587; P-14-013588/ CA-INY-10189; CA-INY-10190	LADWP	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Precontact: Eligible individually under Criterion 4, and eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4. Historic: Ineligible individually, and eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	Two structure work areas are within 30 feet of site boundary. Existing access road will be improved and graded as needed.
P-14-013814/CA-INY-10318	LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible individually, and eligible as contributor to Patsiata Historic District under Criteria 1, 2, 3, and 4.	Structure work areas.

Table Ap.5-11. Archaeological Resources: Fossil Falls Realignment Alternative

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-010021	BLM Ridgecrest FO	Precontact	Precontact: Bedrock milling station.	Precontact: Eligible under Criterion 4.	No project components are within site boundary.
P-14-010028	BLM Ridgecrest FO	Precontact with historic isolate	Precontact: Temporary camp.	Precontact: Ineligible.	No project components are within site boundary.
P-14-010030	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	Existing access road will be improved and graded as needed.
P-14-010034	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	No project components are within site boundary.
P-14-001636/ CA-INY-1636	BLM Ridgecrest FO	Precontact with historic isolate	Precontact: Multi-class artifact concentration.	Precontact: Listed as a contributor to the Fossil Falls Archaeological District under Criterion 4, and eligible under Criterion D.	Install two new LWS monopoles, associated work areas, and one new access road. Two existing access roads will be improved and graded as needed.
P-14-001796/ CA-INY-1796	BLM Ridgecrest FO	Precontact	Precontact: Quarry.	Precontact: Eligible under Criteria 1 and 4.	Install eleven new LWS monopoles and one new TSP monopole, twelve associated work areas, two pull sites, and eleven new access roads. Existing access road will be improved and graded as needed.
P-14-002780/ CA-INY-2780	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible under Criterion 4. Historic: Ineligible.	One structure work area. Existing access road will be improved and graded as needed.
P-14-002781/ CA-INY-2781	BLM Ridgecrest FO	Precontact with historic isolate	Precontact: Multi-class artifact concentration.	Precontact: Eligible under Criteria 1 and 4.	Install one new LWS monopole, one associated work area, and one additional structure work area. Existing access road will be improved and graded as needed.
P-14-003403/ CA-INY-3403	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criteria 1 and 4.	Existing access road will be improved and graded as needed.
P-14-003407/ CA-INY-3407H	BLM Ridgecrest FO; LADWP	Multi-component	Precontact: Lithic concentration. Historic: Homestead/farm/ranch resource.	Precontact: Eligible under Criterion 4. Historic: Eligible under Criterion 4.	Install one new LWS monopole, one associated work area, and an additional structure work area. Existing access road will be improved and graded as needed within 1 foot of site boundary.
P-14-004654/ CA-INY-4654	BLM Ridgecrest FO	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Eligible under Criteria 3 and 4.	Existing access road will be improved and graded as needed within 30 feet of site boundary. No project components occur within the site boundary.
P-14-009477/ CA-INY-7387	BLM Ridgecrest FO	Multi-component	Precontact: Bedrock milling station. Historic: Refuse and discard.	Precontact: Eligible under Criterion 4. Historic: Ineligible.	One pull site and one structure work area. Another pull site and access road is within 10 feet of site boundary.
P-14-014511	BLM Ridgecrest FO	Historic with precontact isolate	Historic: Refuse and discard.	Historic: Ineligible.	No project components are within site boundary.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
P-14-014514	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible. Historic: Ineligible.	No project components are within site boundary.
SWCA-L030-S-60224	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	No project components are within site boundary.
SWCA-L030-S-60229	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	One structure work area is within 30 feet of site boundary. No project components are within site boundary.
SWCA-L030-S-60239	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criteria 1 and 4.	One structure work area is within 30 feet of site boundary. No project components are within site boundary.
SWCA-L030-S-60243 (formerly SWCA-L030-S-60329)	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible under Criteria 1 and 4. Historic: Ineligible.	Two structure work areas are within 30 feet of site boundary. No project components are within site boundary.
SWCA-L030-S-60254	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	One structure work area is within 30 feet of site boundary. No project components are within site boundary.
SWCA-L030-S-60260	BLM Ridgecrest FO	Precontact with historic isolate	Precontact: Quarry.	Precontact: Eligible under Criteria 1 and 4.	One structure work area and one new access road. Existing access road will be improved and graded as needed
SWCA-L030-S-60262	BLM Ridgecrest FO	Precontact	Precontact: Quarry.	Precontact: Eligible under Criterion 4.	Two structure work areas and existing access road are within 30 feet of site boundary. No project components are within site boundary.
SWCA-L030-S-60271	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criteria 1 and 4.	One structure work area is within 30 feet of site boundary. No project components are within site boundary.
SWCA-L030-S-60275	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criteria 1 and 4.	One structure work area is within 30 feet of site boundary. No project components are within site boundary.
SWCA-L030-S-60287	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 1.	No project components are within site boundary.
SWCA-L030-S-60289	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 1.	No project components are within site boundary.
SWCA-L030-S-60302	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	Install one new LWS monopole, associated work area, and one new access road.
SWCA-L030-S-60303	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Homestead/farm/ranch resource.	Precontact: Eligible under Criterion 4. Historic: Ineligible.	Install one new LWS monopole and associated work area. Two existing access roads will be improved and graded as needed.
SWCA-L030-S-60308	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	Existing access road will be improved and graded as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-S-60310	BLM Ridgecrest FO	Historic with precontact isolate	Historic: Refuse and discard.	Historic: Ineligible.	No project components occur within the site boundary.
SWCA-L030-S-60313	BLM Ridgecrest FO	Precontact	Precontact: Temporary camp.	Precontact: Eligible under Criterion 4.	Install one new LWS monopole and associated work area. Two existing access roads will be improved and graded as needed.
SWCA-L030-S-60320	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	Existing access road will be improved and graded as needed.
SWCA-L030-S-61290	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	One structure work area is within 30 feet of site boundary. No project components are within site boundary.
SWCA-L030-S-61298	BLM Ridgecrest FO	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Eligible under Criterion 4.	One pull site and one structure work area. Install one new TSP monopole within 15 feet of the site boundary.
SWCA-L030-S-61346	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	No project components occur within the site boundary.
SWCA-L030-S-61356	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	Existing access road will be improved and graded as needed.
SWCA-L030-S-61364	BLM Ridgecrest FO	Precontact	Precontact: Bedrock milling station.	Precontact: Eligible under Criterion 4.	No project components occur within the site boundary.
SWCA-L030-S-61373	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	No project components occur within the site boundary.
SWCA-L030-S-61375	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criteria 3 and 4.	One structure work area is within 30 feet of site boundary. No project components are within site boundary.
SWCA-L030-S-61385	BLM Ridgecrest FO	Precontact	Precontact: Rock art.	Precontact: Eligible under Criteria 1, 3 and 4.	One structure work area is within 30 feet of site boundary. No project components are within site boundary.
SWCA-L030-S-61398	BLM Ridgecrest FO	Multi-component	Precontact: Bedrock milling station. Historic: Refuse and discard.	Precontact: Eligible under Criterion 4. Historic: Ineligible.	Install one new LWS monopole, associated work area, and one new access road. Existing access road will be improved and graded as needed.
SWCA-L030-S-62369	BLM Ridgecrest FO	Historic with precontact isolate	Historic: Refuse and discard.	Historic: Ineligible.	No project components occur within the site boundary.
SWCA-L030-S-62370	BLM Ridgecrest FO	Historic	Historic: Refuse and discard.	Historic: Ineligible.	No project components occur within the site boundary.
SWCA-L030-S-62381	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	One structure work area. Install one new LWS monopole within 25 feet of the site boundary.
SWCA-L030-S-62386	BLM Ridgecrest FO, LADWP	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criteria 1 and 4.	Existing access road will be improved and graded as needed.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-S-62387	LADWP	Historic with precontact isolate	Historic: Refuse and discard.	Precontact: Eligible under Criterion 1.	Existing access road will be improved and graded as needed.
SWCA-L030-S-62389	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criteria 1 and 4.	One structure work area is within 25 feet of site boundary. No project components are within site boundary
SWCA-L030-S-62391	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criteria 1 and 4.	No project components occur within the site boundary.
SWCA-L030-S-62401	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Eligible under Criterion 4. Historic: Ineligible.	Install one new LWS monopole and associated work area. Two existing access roads will be improved and graded as needed.
SWCA-L030-S-62403	BLM Ridgecrest FO	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	One structure work area and one existing access road are within 30 feet of site boundary. No project components are within site boundary.
SWCA-L030-S-62405	BLM Ridgecrest FO	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	Install one new TSP monopole, associated work site, and two pull sites.
SWCA-L030-S-62409	BLM Ridgecrest FO	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	No project components occur within the site boundary.
SWCA-L030-S-62412	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Exploration and transportation resource, Mining resource.	Precontact: Eligible under Criterion 4. Historic: Ineligible.	Install one new LSW monopole, associated work site, and one new access road. Another two work areas and two new access roads are within 30 feet of site boundary. Existing access road will be improved and graded as needed.
SWCA-L030-S-62414	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	Existing access road will be improved and graded as needed.
SWCA-L030-S-62416	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	One structure work area is within 30 feet of site boundary. No project components are within site boundary.
SWCA-L030-S-62417	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	One structure work area is within 30 feet of site boundary. No project components are within site boundary.
SWCA-L030-S-62418	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	Existing access road will be improved and graded as needed.
SWCA-L030-S-62419	BLM Ridgecrest FO	Precontact with historic isolate	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	No project components occur within the site boundary.
SWCA-L030-S-62420	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	One structure work area is within 30 feet of site boundary. Existing access road will be improved and graded as needed.
SWCA-L030-S-62422	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	One structure work area and one existing access road are within 25 feet of site boundary. No project components are within site boundary.

Res. #	Land Ownership	Age*	Resource Type	CPUC Eligibility Determination	Impact Description
SWCA-L030-S-62423	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	No project components are within site boundary.
SWCA-L030-S-62424	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	One structure work area is within 30 feet of site boundary. No project components are within site boundary.
SWCA-L030-S-62459	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criterion 4.	One structure work area is within 30 feet of site boundary. Existing access road will be improved and graded as needed.
SWCA-L030-S-62460	BLM Ridgecrest FO	Precontact with protohistoric and historic isolate	Precontact: Habitation area.	Precontact: Eligible under Criteria 1 and 4.	Two structure work areas are within 30 feet of site boundary. Existing access road will be improved and graded as needed.
SWCA-L030-S-62464	BLM Ridgecrest FO	Precontact with historic isolate	Precontact: Bedrock milling station.	Precontact: Eligible under Criterion 4.	One structure work area is within 30 feet of site boundary. Existing access road will be improved and graded as needed.
SWCA-L030-S-62466	BLM Bishop FO	Precontact	Precontact: Lithic concentration.	Precontact: Ineligible.	No project components are within site boundary.
SWCA-L030-S-62509	BLM Ridgecrest FO	Precontact	Precontact: Multi-class artifact concentration.	Precontact: Ineligible.	One structure work area is within 25 feet of resource boundary.
SWCA-L030-S-62564	BLM Ridgecrest FO	Historic	Historic: Refuse and discard.	Historic: Ineligible.	Existing access road will be improved and graded as needed.
SWCA-L030-S-62610	LADWP	Multi-component	Precontact: Bedrock milling station. Historic: Refuse and discard.	Precontact: Eligible under Criterion 4. Historic: Ineligible.	Existing access road will be improved and graded as needed.
SWCA-L030-S-62725	BLM Ridgecrest FO	Precontact	Precontact: Lithic concentration.	Precontact: Eligible under Criteria 1 and 4.	Existing access road will be improved and graded within 10 feet of site boundary.
SWCA-L030-S-62728	BLM Ridgecrest FO	Historic with precontact isolate	Historic: Refuse and discard.	Historic: Ineligible.	No project components or elements are located within site boundaries.
SWCA-L030-S-62731	BLM Ridgecrest FO	Precontact with historic isolate	Precontact: Multi-class artifact concentration.	Precontact: Eligible under Criteria 1 and 4.	One pull site. One structure work area is within 25 feet of site boundary.
SWCA-L030-S-62737	BLM Ridgecrest FO	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Precontact: Ineligible. Historic: Ineligible.	No project components or elements are located within site boundaries.

Table Ap.5-12. Archaeological Resources on Alternative Segments with Potential for Visual Impacts

Res. #	Age*	Resource Type	Number of Poles Visible within 1.5 miles (July 2024 VIA Report)	Characteristics Sensitive to Visible Impact
Crater Mountain Realignment Alternative				
170-99-23-S19	Precontact with historic isolate	Precontact: Habitation area.	25	Petroglyphs
P-14-000010 (including P-14-000091)	Multi-component	Precontact: Habitation area. Historic: Refuse and Discard	Unknown	Petroglyphs and cupules
P-14-000111	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and Discard	Unknown	Petroglyphs
P-14-000270	Precontact	Precontact: Habitation area.	Unknown	Petroglyphs
P-14-000390	Precontact	Precontact: Rock art.	Unknown	Petroglyphs
P-14-000392/CA-INY-392	Precontact	Precontact: Lithic concentration.	Unknown	
P-14-000393	Precontact	Precontact: Rock art.	Unknown	Petroglyphs
P-14-000394	Precontact	Precontact: Rock art.	Unknown	Petroglyphs
P-14-000397	Precontact	Precontact: Lithic concentration.	Unknown	Petroglyphs
P-14-005632/CA-INY-5281	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	20	None
P-14-011817/CA-INY-9092	Precontact	Precontact: Habitation area.	Unknown	None
P-14-011818	Precontact	Precontact: Habitation area.	Unknown	Petroglyphs
P-14-011819/CA-INY-9094 (including P-14-012856 and P-14-012857/P-14-013134.)	Precontact	Precontact: Habitation area.	22	None
P-14-012280	Precontact	Precontact: Lithic concentration.	Unknown	Petroglyphs
SWCA-L030-S-60019	Precontact	Precontact: Lithic concentration.	Unknown	None
SWCA-L030-S-60021	Multi-component	Precontact: Habitation area. Historic: Refuse and discard.	Unknown	None
SWCA-L030-S-60023	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	22	None
SWCA-L030-S-60059	Precontact	Precontact: Multi-class artifact concentration.	Unknown	None
SWCA-L030-S-60065	Precontact with historic isolate	Precontact: Lithic concentration.	Unknown	None
SWCA-L030-S-60069	Precontact	Precontact: Lithic concentration.	Unknown	None
SWCA-L030-S-60071	Multi-component	Precontact: Multi-class artifact concentration. Historic: Homestead/farm/ranch resource.	22	None
SWCA-L030-S-60072	Precontact	Precontact: Temporary camp.	21	None
SWCA-L030-S-60088	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	21	None
SWCA-L030-S-60101	Precontact	Precontact: Lithic concentration.	Unknown	None

Res. #	Age*	Resource Type	Number of Poles Visible within 1.5 miles (July 2024 VIA Report)	Characteristics Sensitive to Visible Impact
SWCA-L030-S-60128	Precontact	Precontact: Lithic concentration.	Unknown	None
SWCA-L030-S-61010	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	Unknown	None
SWCA-L030-S-61013	Precontact	Precontact: Residential base.	Unknown	None
SWCA-L030-S-61021	Precontact	Precontact: Bedrock milling station.	Unknown	None
SWCA-L030-S-61022	Precontact	Precontact: Bedrock milling station.	Unknown	None
SWCA-L030-S-61055	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	20	None
SWCA-L030-S-61063	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	20	None
SWCA-L030-S-61072	Precontact	Precontact: Temporary camp.	Unknown	None
SWCA-L030-S-61101	Precontact	Precontact: Rock art.	Unknown	Petroglyphs
SWCA-L030-S-62000	Precontact	Precontact: Rock feature.	Unknown	None
SWCA-L030-S-62003	Precontact	Precontact: Habitation area.	Unknown	None
SWCA-L030-S-62007	Precontact	Precontact: Residential base.	Unknown	None
SWCA-L030-S-62009	Precontact	Precontact: Multi-class artifact concentration.	Unknown	None
SWCA-L030-S-62034	Multi-component	Precontact: Residential base. Historic: Water infrastructure resource.	21	None
SWCA-L030-S-62038	Precontact	Precontact: Residential base.	21	None
SWCA-L030-S-62044	Multi-component	Precontact: Residential base. Historic: Refuse and discard.	21	None
Fossil Falls Realignment Alternative				
P-14-000182	Multi-component	Precontact: Habitation area. Historic: Refuse and discard.	24	Petroglyphs
P-14-000205	Precontact	Precontact: Rock art.	10	Petroglyphs
P-14-000208	Precontact	Precontact: Habitation area.	9	Petroglyphs
P-14-000210	Precontact	Precontact: Rock art.	19	Petroglyphs
P-14-000211	Precontact	Precontact: Rock art.	20	Petroglyphs
P-14-000271	Precontact	Precontact: Residential base.	24	Petroglyphs
P-14-000372	Precontact	Precontact: Habitation area.	9	None
P-14-000388	Precontact	Precontact: Rock art.	13	Petroglyphs
P-14-000389	Precontact	Precontact: Rock art.	25	Petroglyphs
P-14-001640	Precontact	Precontact: Habitation area.	23	Petroglyphs
P-14-001650	Precontact	Precontact: Rock art.	19	Petroglyphs

Res. #	Age*	Resource Type	Number of Poles Visible within 1.5 miles (July 2024 VIA Report)	Characteristics Sensitive to Visible Impact
P-14-001660	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and Discard	21	Petroglyphs
P-14-001796/CA-INY-1796	Precontact	Precontact: Quarry.	Unknown	None
P-14-002781/CA-INY-2781	Precontact with historic isolate	Precontact: Multi-class artifact concentration.	Unknown	None
P-14-003403/CA-INY-3403	Precontact	Precontact: Lithic concentration.	Unknown	None
P-14-003642	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and Discard	8	Petroglyphs
P-14-003647	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and Discard	9	Petroglyphs
P-14-003655	Precontact	Precontact: Rock art.	10	Petroglyphs
P-14-003826	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and Discard	29	Petroglyphs and historic-era Native American village
P-14-004639	Precontact	Precontact: Multi-class artifact concentration.	5	Petroglyphs
P-14-004642	Precontact	Precontact: Rock art.	4	Petroglyphs
P-14-004654/CA-INY-4654	Precontact	Precontact: Multi-class artifact concentration.	25	Petroglyphs
P-14-004655	Precontact	Precontact: Rock art.	25	Petroglyphs
P-14-004671	Precontact	Precontact: Rock art.	25	Petroglyphs
P-14-004672	Precontact	Precontact: Multi-class artifact concentration.	24	Petroglyphs
P-14-006028	Precontact	Archaeological District	42	Petroglyphs and potentially other district-related characteristics
P-14-008002	Multi-component	Precontact: Multi-class artifact concentration. Historic: Rock feature, Trail.	9	Petroglyphs
P-14-008844	Historic	Historic: Refuse and Discard	9	None
P-14-009461	Multi-component	Precontact: Lithic concentration, Trail. Historic: Refuse and Discard.	8	Petroglyphs
P-14-009472	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and Discard	5	Petroglyphs
P-14-009473	Precontact	Precontact: Rock art.	4	Petroglyphs
P-14-009474	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and Discard	2	Petroglyphs
P-14-009480	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and Discard	2	Petroglyphs
P-14-010012	Precontact	Precontact: Multi-class artifact concentration.	25	Petroglyphs
P-14-010015	Precontact	Precontact: Rock art.	24	Petroglyphs

Res. #	Age*	Resource Type	Number of Poles Visible within 1.5 miles (July 2024 VIA Report)	Characteristics Sensitive to Visible Impact
P-14-010018	Precontact	Precontact: Rock art.	23	Petroglyphs
P-14-010025	Precontact	Precontact: Habitation area.	24	Cupules
P-14-010031	Precontact	Precontact: Lithic concentration.	25	Petroglyphs
P-14-010032	Precontact	Precontact: Rock art.	25	Petroglyphs
P-14-010036	Precontact	Precontact: Habitation area.	0	Petroglyphs
P-14-010037	Precontact	Precontact: Rock art.	9	Petroglyphs
P-14-010038	Precontact	Precontact: Rock art.	11	Petroglyphs
P-14-010039	Precontact	Precontact: Rock art.	23	Petroglyphs
P-14-010049	Precontact	Precontact: Lithic concentration.	26	Petroglyphs
P-14-011427	Precontact	Precontact: Rock art.	8	Petroglyphs
P-14-011435	Precontact	Precontact: Temporary camp.	10	Petroglyphs
P-14-014332	Precontact	Precontact: Lithic concentration.	7	Petroglyphs
P-14-014531	Precontact	Precontact: Rock art.	2	Petroglyphs
SWCA-L030-S-60239	Precontact	Precontact: Lithic concentration.	Unknown	None
SWCA-L030-S-60243 (formerly SWCA-L030-S-60329)	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
SWCA-L030-S-60260	Precontact with historic isolate	Precontact: Quarry.	Unknown	None
SWCA-L030-S-60271	Precontact	Precontact: Lithic concentration.	Unknown	None
SWCA-L030-S-60275	Precontact	Precontact: Lithic concentration.	Unknown	None
SWCA-L030-S-60287	Precontact	Precontact: Lithic concentration.	Unknown	None
SWCA-L030-S-60289	Precontact	Precontact: Lithic concentration.	Unknown	None
SWCA-L030-S-61371	Precontact	Precontact: Multi-class artifact concentration.	25	Petroglyphs
SWCA-L030-S-61375	Precontact	Precontact: Lithic concentration.	25	Petroglyphs
SWCA-L030-S-61381	Precontact	Precontact: Rock art.	24	Petroglyphs
SWCA-L030-S-61385	Precontact	Precontact: Rock art.	25	Petroglyphs
SWCA-L030-S-61389	Precontact	Precontact: Rock art.	24	Petroglyphs
SWCA-L030-S-61395	Precontact	Precontact: Lithic concentration.	24	Petroglyphs
SWCA-L030-S-62386	Precontact	Precontact: Lithic concentration.	Unknown	None
SWCA-L030-S-62387	Historic with precontact isolate	Historic: Refuse and discard.	Unknown	None
SWCA-L030-S-62389	Precontact	Precontact: Lithic concentration.	Unknown	None
SWCA-L030-S-62391	Precontact	Precontact: Lithic concentration.	Unknown	None
SWCA-L030-S-62460	Precontact with protohistoric and historic isolate	Precontact: Habitation area.	Unknown	None

Res. #	Age*	Resource Type	Number of Poles Visible within 1.5 miles (July 2024 VIA Report)	Characteristics Sensitive to Visible Impact
SWCA-L030-S-62725	Precontact	Precontact: Lithic concentration.	Unknown	None
SWCA-L030-S-62731	Precontact with historic isolate	Precontact: Multi-class artifact concentration.	Unknown	None
Manzanar Realignment Alternative				
20231023-MER-001-S	Precontact with historic isolate	Precontact: Lithic concentration.	Unknown	None
20231031-AJD-001-S	Precontact with historic isolate	Precontact: Lithic concentration.	Unknown	None
20231031-MER-001-S	Precontact with historic isolate	Precontact: Lithic concentration.	Unknown	None
BLM-DPR 175-4	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
20230822-AJD-002-S	Precontact	Precontact: Lithic concentration.	Unknown	None
20230827-MER-001-S	Precontact	Precontact: Lithic concentration.	Unknown	None
20230828-AJD-001-S	Precontact	Precontact: Temporary camp.	Unknown	None
20230829-G_F-001-S	Precontact	Precontact: Lithic concentration.	Unknown	None
20230829-MER-001-S	Precontact	Precontact: Lithic concentration.	Unknown	None
20230831-MER-001-S	Precontact	Precontact: Lithic concentration.	Unknown	None
20230919-AJD-001-S	Historic	Historic: Homestead/farm/ranch resource.	Unknown	None
20230919-AJD-002-S	Historic	Historic: Homestead/farm/ranch resource.	Unknown	None
20230921-AJD-001-S	Precontact with historic isolate	Precontact: Multi-class artifact concentration.	Unknown	None
20230923-AJD-001-S	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
20230925-AJD-001-S	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	None
20230926-AJD-003-S	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
20230927-AJD-001-S	Historic with precontact isolate	Historic: Refuse and discard.	Unknown	None
20230927-MER-001-S	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
20231029-AJD-001-S	Historic with precontact isolate	Historic: Exploration and transportation resource, Refuse and discard.	19	None
20231029-MER-002-S	Multi-component	Precontact: Lithic concentration. Historic: Refuse and discard.	Unknown	None
20231031-MER-001-S	Precontact with historic isolate	Precontact: Lithic concentration.	Unknown	None
20231031-AJD-001-S	Precontact with historic isolate	Precontact: Lithic concentration.	Unknown	None
20231023-MER-001-S	Precontact	Precontact: Lithic concentration.	Unknown	None
P-14000030	Precontact	Precontact: Habitation area.	10	Petroglyphs

Res. #	Age*	Resource Type	Number of Poles Visible within 1.5 miles (July 2024 VIA Report)	Characteristics Sensitive to Visible Impact
P-14-000081/CA-INY-81	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	None
P-14-000085/CA-INY-85	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Unknown	None
P-14-002783/CA-INY-2783	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	Unknown	None
P-14-002784/CA-INY-2784	Precontact with historic isolate	Precontact: Lithic concentration.	Unknown	None
P-14-005654/CA-INY-5301	Historic with precontact isolate	Historic: Refuse and discard.	Unknown	None
P-14-007831	Precontact with historic isolate	Precontact: Lithic concentration.	Unknown	None
P-14-008008; P-14-013589/CA-INY-10191	Multi-component	Precontact: Temporary camp. Historic: Refuse and discard.	20	None
P-14-009248; P-14-014226; P-14-014227; P-14-014228/CA-INY-7229; CA-INY-10662; CA-INY-10663	Precontact	Precontact: Lithic concentration.	Unknown	None
P-14-009513	Multi-component	Precontact: Multi-class artifact concentration.	7	Setting may be a factor due to possible association with Indian Wars.
P-14-013586/CA-INY-10188	Precontact	Precontact: Multi-class artifact concentration.	Unknown	None
P-14-013587; P-14-013588/CA-INY-10189; CA-INY-10190	Multi-component	Precontact: Multi-class artifact concentration. Historic: Refuse and discard.	Unknown	None
P-14-013814/CA-INY-10318	Precontact	Precontact: Lithic concentration.	Unknown	None

Table Ap.5-13. Built Environment Resources on Alternative Segments

Alternative	Res. Number	Landowner	BLM Land?	Date Range	Resource Type	Alternatives Resource Description	CPUC Eligibility Determination	Impact Description
CM, M, FF	P-36-010316/ CA-SBR-10316H	SCE (SCE)	Yes	ca. 1911-1913	Transmission/ Utility Line	SCE Bishop Creek to San Bernardino "Tower Line": electrical 12kV and 115kV transmission line, towers, poles, and associated wire. "Tower Line" is comprised of 5 transmission line segments, composed of 70-ft tall double-circuit steel lattice towers and conductors mounted on steel/wooden poles. The line, in its entirety, has a length of 238 miles. One segment intersects the Crater Mountain Direct API in two areas for a total length of approximately 1,342 feet.	Listed under Criteria 1 and 3.	Pull sites, guard site, structure work area, access road
CM, M, FF	19	SCE (SCE)	Yes	ca. 1969-1975	Access Road	The access road to SCE Sylmar-Celilo Transmission Line, approximately 15-feet wide, is composed of a series of unpaved segments extending approximately 180-miles through Mono, Inyo, and Kern Counties to provide access for transmission line maintenance. The majority of the route retains integrity as an active in-use route.	Ineligible	Structure work area, new access road, road grading
CM, M, FF	P-15-014557	SCE (SCE)	Yes	ca. 1911-1913	Access Road	The access road to SCE Bishop Creek to San Bernardino "Tower Line", approximately 15-feet wide, is composed of a series of unpaved and paved segments extending the full-length of the 238-mile Tower Line through Inyo, Kern and San Bernardino Counties. The main road alignment was constructed simultaneous with the Tower Line construction.	Ineligible	Pull sites, access road, structure work areas
CM, M, FF	P-14-012883	Private (LADWP)	Yes	ca. 1950-1952	Transmission/ Utility Line	The LADWP Owens Gorge 230kV Transmission Line is composed of steel lattice towers and spans 248 miles from Mesa Camp, following Owens Gorge, to the Sylmar neighborhood in Los Angeles.	Ineligible	Unknown
CM (not DAPE)	P-14-004682	Private (LADWP)	No	ca. 1880s-1893	Water Conveyance and Control	Big Pine Canal is an artificial water conveyance system, approximately 20 ft wide. Components: Big Pine Canal, irrigation ditch with 5 associated features, old route of canal from Big Pine to Fish Springs. Subfeatures: 2A lateral ditch (2-6 ft wide) and 7 associated field ditches with 4 wooden boxes/gates, 2B lateral ditch (2-6 ft wide) with 4 field ditches and 2 wooden boxes/gates, 2C berm (4x6x12 ft) with catch basin, 2D berm, 2E lateral ditch (2-6 ft wide) with 8 gates, 6 wooden boxes, and 8-inch metal pipe. Total length is approximately 14.40 miles.	Eligible under Criterion 1.	No project components in resource.
CM	P-14-014295	County of Inyo	Yes	Pre-1913	Access Road	This unnamed road is an unpaved, single-lane road, approximately 13-feet wide, that spans approximately 2-miles. The road initiates west from Fish Springs Road and terminates south at Birch Creek Road and provides access to the SCE Control-Haiwee-Inyokern 115kV Transmission Line and the SCE Control-Coso-Haiwee-Inyokern 115kV Transmission Line (modern-day segments of the SCE Bishop Creek to San Bernardino 89kV "Tower Line"), Fish Springs Mining District, and Fish Springs Trout Hatchery.	Ineligible	Structure work area, new access roads

Alternative	Res. Number	Landowner	BLM Land?	Date Range	Resource Type	Alternatives Resource Description	CPUC Eligibility Determination	Impact Description
CM	P-14-014297	County of Inyo	Yes	Pre-1947	Local Road	Tinemaha Road is a partially paved single lane road that initiates west in two separate segments that stem from Fish Springs Road and merge into a single road approximately 0.48-miles in. The road is approximately 15 miles long and terminates at a dead-end approximately 2-miles south of Fort Independence Reservation. The road presumably provided access to adjacent agricultural lands, US Highway 395, recreational areas, mines, the SCE Control-Haiwee-Inyokern 115kV Transmission Line and the SCE Control-Coso-Haiwee-Inyokern 115kV Transmission Line (modern-day segments of the SCE Bishop Creek to San Bernardino 89kV "Tower Line") and the communities of Fish Springs, Aberdeen and Blackrock.	Ineligible	Pull sites, structure work area, access road improvements
CM (not DAPE)	P-14-005194	Private (unidentified)	Yes	ca. 1880s	Railroad	Abandoned LADWP earthen drain ditch, between 15-feet and 30-feet wide and between 6-feet and 10-feet deep, approximately 1,531-feet long. It was constructed to drain water from the Carson and Colorado Railroad track (in operation 1883-1960). Components in the Indirect API consist of ditch headgate (constructed of milled lumber and steel) and an adjacent stilling well set in concrete.	Eligible under Criterion 1.	No project components in resource.
CM, M & FF (not DAPE)	P-36-007545/ CA-SBR-7545H	Caltrans	Yes	ca. 1915-1947	Freeways, U.S Highways, State Routes	US Highway 395 is a paved, 4-lane divided major highway (between Warm Springs Road in Bishop and the SCE Kramer substation in Kramer Junction). This recorded section of the road has a length of approximately 176 miles.	Eligible under Criterion 1.	Guard sites
CM, M & FF (not DAPE)	P-14-004591/ CA-INY-4591H	Private (LADWP)	Yes	Pre-1913	Water Conveyance and Control	Los Angeles Aqueduct is a complex of water conveyance and power generation structures extending Lee Vining Intake (Mono County) to the Van Norman Reservoir Complex (San Fernando Valley), a length of 338 miles. This aqueduct is composed of unlined channels, concrete-lined channels, flumes, conduit, siphons, tunnels, spillways, reservoirs, dams, and power plants.	Listed under Criteria 1, 2, and 3.	Improvements to existing access roads, pull site
CM (not DAPE)	P-14-006863	Unknown	No	ca. 1911-1913	Water Conveyance and Control	Lower Owens River Intake. DPR not provided by Urbana.	Eligible under Criteria 1 and 3.	No project components in resource.
M	P-14-014304	Private (unidentified)	No	Pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 15-feet wide, approximately 1.76-miles. Terminates at the Los Angeles Aqueduct.	Ineligible	Guard site, improve existing access road
M	P-14-014305	Private (unidentified)	No	Pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 15-feet wide, approximately 3.24-miles. Initiates 20-feet east of the LA Aqueduct. Terminates at the eastern banks of the Owens River.	Ineligible	Guard site, new access road; improve existing access road
CM	P-14-014306	County of Inyo	No	Pre-1907	Local Road	North Coloseum Road (Black Rock Spring Road) is a partly paved road, between 6 and 20-feet wide, that spans approximately 4.5 miles. The evaluated route initiates north from U.S. Highway 395 and terminates at Goodale Road. The	Ineligible	Pull sites, structure work area, improve existing access road

Alternative	Res. Number	Landowner	BLM Land?	Date Range	Resource Type	Alternatives Resource Description	CPUC Eligibility Determination	Impact Description
						southern segment between U.S Highway 395 and Blackrock Springs is a paved double-lane road (one lane on each side). A portion of the road north of the Division Creek Ditch is unmaintained and barely discernable from aerial imagery. The road provides access to private parcels and land owned by the Los Angeles Department of Water and Power.		
M	P-14-014309	Private (unidentified)	No	ca. 1948-1967	Access Road	The unnamed road is an unpaved, one-lane road, 20-feet wide, approximately 0.76-miles long. Terminates 15-feet west of a transmission line tower.	Ineligible	Improve existing access road
M	P-14-014322	Private (unidentified)	Yes	Pre-1873	Historic Route	Mazourka Canyon Road (Citrus Road) is a partially paved two-lane former wagon road, approximately 25 ft wide. Extends for approximately 17.8 miles, starting east of US Hwy 395 in Independence and terminates approximately 1.25 miles southeast of Mazourka Peak. Approximately 4.53 miles are paved.	Eligible under Criterion 1.	46 structure work areas, guard structure, access road improvement
M	P-14-014324	Private (unidentified)	Yes	ca. 1920s-1942	Historic Route	Manzanar Reward Road (Francis Road is a partially paved road, unknown width. Extends for approximately 6.70 miles. North/south segment (paved) spans 1.20 miles, the entire length of the Manzanar War Relocation Camp. East/west segment (paved for 2.40 miles) spans 5.50 miles, intersecting the Manzanar Federal Airport and terminating at an unnamed road 540 ft east of Reward, California/Inyo Mountains.	Eligible under Criterion 1.	Structure work area, access road improvements and grading
M	P-14-004589	Private (unidentified)	No	ca. 1887-1893	Water Conveyance and Control	Stevens Ditch (Stevens Canal) is an earthen irrigation system, historically 15-miles long. No associated components.	Ineligible	Structure work area, install new steel structure, improve access road
M	P-14-014350	Private (unidentified)	No	Pre-1907	Two Lane Paved Road	Lone Pine Narrow Gauge Road is a paved, two-lane road, 25-feet wide, approximately 3.36-miles long. Terminates east of the Owens River at Owenyo Lone Pine Road.	Ineligible	Improve existing access road
M	P-15-015209	CSLC; Private (unidentified); DOD NAWS China Lake, NAWS, China Lake; BLM, Ridgecrest FO; BLM, Bishop FO	Yes	ca. 1905-1910	Railroad	Southern Pacific Railroad (Southern Pacific Owenyo Branch "The Jawbone") is an historic railroad including tracks, grade and other railroad features (n=296) with a series of branches/spur lines that once spanned into 15 states for 76 miles. Two of the Southern Pacific lines are located in the area under review commencing in Lone Pine and ending north of the Randsburg Mining District: the Southern Pacific Mojave-Owenyo Branch and the U.S. Government Railroad. Components: multiple concrete culverts, concrete bridges, stone retaining walls, wooden loading dock and historic debris scatter. The Mojave-Owenyo Branch once spanned 142-miles from Lone Pine into the Fremont Valley in Kern County. The U.S. Government Railroad (an offshoot of the Mojave-Owenyo Branch) spanned approximately 16-miles, initiating east from Inyokern and terminating within China Lake Naval Base in the Argus Range. The NAWS China Lake spur	Ineligible	Structure work area; improve existing access road

Alternative	Res. Number	Landowner	BLM Land?	Date Range	Resource Type	Alternatives Resource Description	CPUC Eligibility Determination	Impact Description
						(FT2-BA-45H) was constructed before 1944 has been removed after 1973 but is still visible to an extent retaining integrity of location and setting because it has not appreciably changed route or location since its construction.		
M	P-14-014348	Private (unidentified)	Yes	Pre-1907	Freeway/U.S Highway/ State Route	California State Route 136 is a paved, two-lane road, 23-feet wide, approximately 17.5-miles long.	Ineligible	Improve existing access road
M	P-14-014351	Private (unidentified); BLM, Bishop FO	Yes	Pre-1947	Access Road	The unnamed road is an unpaved, one-lane road, 10-feet wide, approximately 1.22-miles long. The road initiates east from an unnamed road, intersects the old Southern Pacific Railroad bed and terminates at a transmission line access road.	Ineligible	Improve existing access road
M	159	Unknown	Yes	Pre-1947	Historic Route	Lubkin/Lubken Canyon Road is a partially paved road, approximately 17-25 ft wide. Extends for a total length of 7.38 miles. Segments are interrupted by U.S. Route 395. Western segment is 25 ft wide and extends from U.S. Route 395 to Horse Meadows Road; eastern segment is 17 ft wide and extends from U.S. Route 39 to Inyo County Assessor's Parcel No. 026-210-09.	Eligible under Criterion 1.	Guard structure, structure work area adjacent, access road grading or improvement
M	P-14-014352	Private (unidentified); BLM, Bishop FO	Yes	Pre-1947	Local Road	The unnamed road is an unpaved, one-lane road, 20-feet wide, approximately 2.76-miles long. Terminates at an unnamed road just north of the dry Owens Lake bed.	Ineligible	Improve existing access road
FF (not DAPE)	P-14-008844	Private (unidentified); BLM Ridgecrest FO	Yes	1927	Substation	SCE Haiwee Substation Complex (Haiwee Powerhouse) is a 5.4MW hydroelectric substation complex. Components within API include a cast concrete power plant, three fenced substations containing transformers, powerlines, wooden water tank, surge chamber, portion of buried penstock, open concrete-lined canal, buried aqueduct, residential structure, garage, shed, valve boxes, driveways and parking areas, portion of rock retaining wall, rain gauge, and associated artifacts.	Eligible under Criterion 1.	No project components in resource.
FF	P-14-014397	Private (unidentified); BLM Ridgecrest FO	Yes	Pre-1947-1967	Local Road	Dunmovin Road is an unpaved, one-lane road, 15-feet wide, approximately 2.6-miles long. The road initiates west from the Second Los Angeles Aqueduct, travels over the Los Angeles Aqueduct, through the unincorporated town of Dunmovin. Road terminates at an open pit mine in the east.	Ineligible	One structure work area; improve existing access road
FF	P-14-014398	Private (unidentified); BLM Ridgecrest FO	Yes	ca. 1947-1975	Access Road	The unnamed road is an unpaved road, 15-feet wide, approximately 1.1-miles. The road runs south of a building located north of the Terra-Gen Power Facility and shares 266-feet with the access road to SCE Bishop Creek to San Bernardino “Tower Line”.	Ineligible	Pull site, new unpaved access road
FF	P-14-014399	BLM Ridgecrest FO	Yes	ca. 1913-1947	Access Road	The unnamed road is an unpaved road, 15-feet wide, approximately 2.34-miles long. Terminates at a wash southwest of the Terra-Gen Power Facility.	Ineligible	Structure work area, new unpaved access roads

Alternative	Res. Number	Landowner	BLM Land?	Date Range	Resource Type	Alternatives Resource Description	CPUC Eligibility Determination	Impact Description
FF	P-14-014417	BLM Ridgecrest FO	Yes	ca. 1939-1948	Two Lane Paved Road	Gill Station Coso Road is a partially paved, two-lane road, 20-feet wide, approximately 11-miles long. Initiates from U.S. Highway 395 and continues east as a paved road for approximately 5.55-miles. The road continues unpaved. Terminates at a fork east of Coso Hot Springs.	Ineligible	Improve existing access roads
FF	P-14-014418	BLM Ridgecrest FO	Yes	Pre-1948	Access Road	The unnamed road is an unpaved, one-lane road, 7-feet wide, approximately 4-miles long. Terminates at the First Los Angeles Aqueduct.	Ineligible	Adjacent to multiple new unpaved access roads.
FF	P-14-014420	Private (unidentified); BLM Ridgecrest FO	Yes	ca. 1948-1954	Local Road	Cinder Road is a partially-paved road, width unknown, approximately 9-miles long. Terminates at Fossil Falls Access Road within Twin Mountain Rock Venture.	Ineligible	Improve existing access roads
FF	P-14-007130	DOD NAWS China Lake, NAWS, China Lake; BLM, Ridgecrest FO	Yes	ca. 1912	Other	This north-south oriented, linear retaining wall lines the west drainage bank east of U.S. Highway 395 near the base of a basalt escarpment. The wall is approximately 45-meters long and 3 to 4-feet tall composed of large volcanic rocks stacked at least 4 tiers high that partially enclose the east side of a transmission line tower (T-856). Associated Artifacts include biface reduction obsidian flakes (n=2) and sanitary cans (n=3).	Ineligible	Pull site
CM	906	County of Inyo	Yes	Pre-1947	Local Road	Birch Creek Road is an unpaved route, approximately 15 feet wide, extending for approximately 1.72 miles along the northern banks of Birch Creek. Birch Creek Road provides access to a small handful of private residences and is one of several roads that provide access to mines located in the Fish Springs Mining District.	Ineligible	Guard site, structure work area
CM	918	County of Inyo	Yes	Pre-1947	Local Road	Fuller Road is a paved road, approximately 15 feet wide, extending for approximately 2.57 miles. The road spans between Inyo County Assessor's Parcel No. 018-240-04 and an unnamed road fork located on Parcel No. 018-350-08. A small portion of the road east of Tinehama Road is unmaintained and no longer in-use.	Ineligible	Improve existing access road
CM	920	County of Inyo	No	ca. 1947-1977	Access Road	Tinemaha Creek Road is an unimproved road, between approximately 7 to 10 feet wide, extending for approximately 0.55 miles. The road initiates west from an SCE transmission line road.	Ineligible	Improve existing access road
CM	921	County of Inyo	No	Pre-1947	Access Road	The unnamed road is an unimproved road, approximately 7 feet wide, extending for approximately 1.21 miles. The road initiates west from an SCE transmission line road and terminates towards the far west end of Inyo County Assessor's Parcel No. 018-240-06.	Ineligible	No project components in resource.
CM	922	County of Inyo	Yes	ca. 1947-1977	Access Road	The unnamed road is an unimproved route, approximately 7 feet wide, extending for approximately 3.48 miles. The road initiates west from SCE transmission line	Ineligible	No project components in resource.

Alternative	Res. Number	Landowner	BLM Land?	Date Range	Resource Type	Alternatives Resource Description	CPUC Eligibility Determination	Impact Description
						road and terminates towards the far west end of Inyo County Assessor's Parcel No. 018-350-14.		
CM	923	County of Inyo	Yes	Pre-1947	Historic Route	Taboose Creek Road is an unpaved road, approximately 7 - 15 ft wide. Two discontiguous segments located on the northern and southern sides of Taboose Creek. Segment 1, north of Taboose Creek, extends from Tinemaha Road/ Aberdeen Station Road and terminates at the Taboose Pass Trail Head; Segment 2, south of Taboose Creek, extends from Tinemaha Road and Old Hwy 395. The road, in its entirety, has a length of 5.1 miles.	Eligible under Criterion 1.	Improve existing access roads
CM	924	Unknown	No	ca. 1947-1977	Other	Taboose Creek Campground is a secluded, minimalist campground, located along the banks of Taboose Creek, south of Big Pine. The campground includes a total of 35 camping sites (along both sides of the creek) for tents and RV's, picnic tables, fire grills, and vaulted toilets.	Ineligible	No project components in resource.
CM	925	County of Inyo	Yes	Pre-1947	Historic Route	Old Highway 395 is a historic federal highway established developed based on old trails and existing stagecoach routes and eventually extended between the Canadian and Mexican borders. Portions of the historic route were realigned and replaced with more direct segments. Today, active segments of the historic route have been commemorated with the installation of “Historic Route” signs. The evaluated segment of Old Highway 395 is partially paved, approximately 20 feet wide, extending for approximately 2.42 miles. This segment is no longer maintained and no longer retains integrity.	Ineligible	New overhead conductors
CM	926	County of Inyo	Yes	Pre-1947	Two Lane Paved Road	Goodale Road is a paved two-lane route, approximately 20 feet wide, that spans for approximately 3.67 miles connecting the Los Angeles Aqueduct and an unnamed road. Goodale Road was named after Ezra M. Goodale, an early settler of the Owens Valley who acquired several acres of land through the Homestead Act.	Ineligible	Pull site, improve existing access road
CM	929	County of Inyo	Yes	Pre-1947	Local Road	Goodale Creek Road is an unpaved road, between approximately 15 to 20 feet wide, that spans for approximately 6.22 miles connecting unnamed road located on Inyo County Assessor's Parcel No. 021-060-05 and Goodale Creek.	Ineligible	Improve existing access road
CM	930	County of Inyo	No	ca. 1947-1977	Access Road	The unnamed road is an unpaved route, approximately 7 feet wide, that spans for approximately 1.87 miles connecting N. Coloseum Road and the headgates to the Los Angeles Aqueduct.	Ineligible	Improve existing access road
M	935	County of Inyo	No	ca. 1947-1977	Access Road	The unnamed road is an unpaved road, approximately 0.5 miles long connecting the Owens River and the Molvier Canal.	Ineligible	Structure work area
M	939	County of Inyo	No	Pre-1947	Water Conveyance and Control	The Eclipse Ditch is a non-operational 11 mile earthen ditch and dirt berm that spans along the east side of the Owens Valley, approximately 15 feet wide and an average of 8 feet deep. The ditch was constructed to convey water to the Eclipse	Ineligible	Structure work area; improve existing access roads;

Alternative	Res. Number	Landowner	BLM Land?	Date Range	Resource Type	Alternatives Resource Description	CPUC Eligibility Determination	Impact Description
						Mill and to ranches located on the east side of the Owens Valley. Named after the Eclipse Mine (later renamed the Brown Monster Mine) from the early 1860s.		construct new access road
M	942	County of Inyo	No	ca. 1947-1977	Access Road	The unnamed road is an unpaved four wheel drive road, approximately 14 feet wide, that spans approximately 2 miles connecting Owenyo Lone Pine Road and the Owens River.	Ineligible	Intersects multiple new access roads
M	P-14-013562	Private (LADWP); County of Inyo	No	ca. 1937-1947	Other	ESA-ORWT-Built-029H is the remains of a bridge structure located on the southwestern and northeastern side of the Owens River. The feature was constructed of concrete with gravel aggregate poured in 1 foot by 1 foot increments. The concrete structure is alongside a dirt road, and perpendicular to a contemporary-era steel pedestrian bridge. The bridge abutments are the only remaining feature of the original bridge structure.	Ineligible	Improve existing access roads
FF	958	County of Inyo	Yes	ca. 1947-1976	Access Road	The unnamed road is an unpaved road, approximately 10 feet wide, that spans approximately 2.79 miles connecting Cinder Road and LADWP Owens Gorge 230kV Transmission Line. The road once led to an open pit mine.	Ineligible	Improve existing access roads
FF	959	County of Inyo	Yes	Pre-1947	Access Road	The unnamed road is a narrow, unpaved road, approximately 9 feet wide, that spans approximately 1.26 miles connecting Cinder Road and a private parcel identified. The road passes through an area historically used for mining, and may have been used to access mining facilities.	Ineligible	Improve existing access roads
	960	County of Inyo	Yes	Pre-1947	Access Road	The unnamed road is a narrow, unpaved road, approximately 17 feet wide, that spans approximately 1.54 miles connecting the LADWP Owens Gorge 230kV Transmission Line and a non-extant mining drill site.	Ineligible	Structure work area; improve existing access roads
FF	966	County of Inyo	Yes	ca. 1947-1976	Local Road	The unnamed road is a narrow, unpaved road, approximately 22.5 feet wide, that spans approximately 2.3 miles connecting Cinder Road and an undeveloped parcel between Volcano Peak and Little Lake.	Ineligible	
	972	County of Inyo	Yes	ca. 1947-1976	Access Road	The unnamed road is a narrow, unpaved road, approximately 12.5 feet wide, that spans approximately 0.44 miles connecting the LADWP Owens Gorge 230kV Transmission Line and two non-extant, unnamed mines.	Ineligible	Structure work area; construct new unpaved access road; improve existing access roads
CM, M, FF	974	SCE (SCE)	Yes	1970	Transmission/ Utility Line	Pacific Direct Intertie (PDCI)/Celilo-Sylmar 500 kV power system: high voltage, direct current (HVDC) powerline linking power systems between the Pacific Northwest and Southern California region. Extends from Bonneville Power Administration Celilo Converter Station (Oregon via Nevada) to the SCE Sylmar Converter Station in northern Los Angeles County, a length of 846 miles.	Eligible under Criteria 1 and 3.	Pull sites, improve existing access roads

Table Ap.5-14. Built Environment Resources on Alternatives with Potential for Visual Impacts

Alternative	Only in the Visual APE?	Res. #	Date Range	Resource Type	Poles Visible from Resource?	Characteristic Sensitive to Visual Impact
Crater Mountain, Manzanar, Fossil Falls	No	P-36-010316/ CA-SBR-10316H	ca. 1911-1913	Transmission/Utility Line	Yes	Setting, Feeling, Association
Crater Mountain	Yes	P-14-004682	ca. 1880s-1893	Water Conveyance and Control	Yes	Setting, Feeling, Association
Crater Mountain, Manzanar	Yes for Crater Mountain and Manzanar	P-14-005194	ca. 1880s	Railroad	Yes	Setting, Feeling, Association
Crater Mountain, Manzanar, Fossil Falls	Yes for Manzanar and Fossil Falls	P-36-007545/ CA-SBR-7545H	ca. 1915-1947	Freeways, U.S Highways, State Routes	Yes	Setting, Feeling, Association
Crater Mountain, Manzanar, Fossil Falls	Yes for Fossil Falls only	P-14-004591/ CA-INY-4591H	Pre-1913	Water Conveyance and Control	Yes	Setting, Feeling, Association
Crater Mountain	No	P-14-006863	ca. 1911-1913	Water Conveyance and Control	Yes	Setting, Feeling, Association
Manzanar	No	P-14-014322	Pre-1873	Historic Route	Yes	Setting, Feeling, Association
Manzanar	No	P-14-014324	ca. 1920s-1942	Historic Route	Yes	Setting, Feeling, Association
Manzanar	No	159	Pre-1947	Historic Route	Yes	Setting, Feeling, Association
Fossil Falls	Yes	P-14-008844	1927	Substation	Yes	Setting, Feeling, Association
Crater Mountain	No	923	Pre-1947	Historic Route	Yes	Setting, Feeling, Association
Crater Mountain, Manzanar, Fossil Falls	No	974	1970	Transmission/Utility Line	Yes	Setting, Feeling, Association

Appendix 5B

NATIVE AMERICAN CONSULTATION

Appendix 5B contains the following information related to EIR Section 3.7, Tribal Cultural Resources:

- **Part 1**: Summary of Individual Consultation with each Tribe from December 2018 through March 2026 (at the time of publication of the Draft EIR)
- **Part 2**: Correspondence with the Native American Heritage Commission (November – December 2018)
- **Part 3**: Assembly Bill 52 Notification Letters

Part 1:

SUMMARY OF INDIVIDUAL CONSULTATION WITH EACH TRIBE FROM DECEMBER 2018 THROUGH 2026

PART 1: SUMMARY OF INDIVIDUAL CONSULTATION WITH EACH TRIBE FROM DECEMBER 2018 THROUGH 2025

Introduction

As described in EIR Section 3.7, Native American consultation for the Ivanpah-Control Project began in late 2018, when SCE submitted its draft Proponent's Environmental Assessment to the CPUC. SCE submitted its formal Permit to Construct (PTC) application for the Project to the CPUC on July 17, 2019. SCE subsequently submitted two amended applications (on April 13, 2020 and on October 31, 2024).

Formal consultation was initiated with the consulting tribes in 2020 and 2021. After that time, due to project revisions, development of alternatives, and the time required to complete cultural resources surveys and reports, the CEQA process has extended several more years. In addition, the CEQA process was extended due to SCE's change in the project alignment and to accommodate the time required for cultural resources surveys and investigations. During this time, there were periods of inactivity in the consultation process.

Based on requests from consulting tribes, site visits were made to portions of Segment 1 (Inyo County) within the Owens River Valley.

Consultation with individual tribes is detailed in the following sections, including project information provided before the initiation of formal consultation. The information provided by the consulting tribes was considered in the analysis of effects on tribal cultural resources (EIR Section 3.7) and in the development of the mitigation measures presented in EIR Section 3.6 (Cultural Resources) and EIR Section 3.7 (Tribal Cultural Resources). The consultation process will continue through and after the public review period for the Draft EIR, allowing additional time for comments on mitigation measures.

Summary of Consultation Activities with Each Tribe

5B.1 Big Pine Paiute Tribe of the Owens Valley

- December 14, 2018: The CPUC mailed the Tribe a notice requesting pre-filing input.
- March 12, 2020: The CPUC spoke with the Tribe about having a joint-tribe meeting (with other Owens Lake tribes) in Bishop.
- May 2020: An email regarding BLM data-sharing agreements was sent to the Tribe. Also on May 2020, the Tribe participated in a joint meeting with CPUC explaining SCE's proposed construction of the Ivanpah-Control and Control-Silver Peak Projects.
- **August 25, 2020: The CPUC initiated formal consultation** with a mailed formal AB 52 notification which included a brief description of the proposed project and its location, the lead agency contact information, and a notification that the Tribe had 30 days to request consultation.
- September 28, 2020: The Tribe requested formal consultation.
- October - November 2020: CPUC held two meetings and multiple email exchanges with the Tribe discussing an overview of the Project, AB 52 consultation process, and Google Earth data available for the Tribe to review.
- December 2021: CPUC sent the Tribe a project status update, a summary of the cultural studies information on the Class III cultural resources inventory report, and information about archeological testing that would occur in early 2022.
- December 26, 2023: CPUC emailed the Tribe a notice to schedule an in-person consultation meeting.
- September 25, 2024: CPUC called the Tribe to schedule a consultation meeting.

- October 2024: CPUC sent the Tribe a series of emails containing a request to schedule consultation meetings, a letter detailing a basic project description, geographic data (KMZ) files of all project components and ethnographic research, and an Excel file of a summary table of cultural resources along the proposed and alternative alignments. On October 14, 2024, the Tribe was informed that Segment 4 had been omitted from the Project.
- November 2024: CPUC sent the Tribe a series of emails containing references cited for ethnographic research, a request to schedule meetings, and requests to gauge interest and input for participation in site visits to Segments 1, 2, 3N, and 3S.
- December 2024: CPUC sent the Tribe a series of emails containing a map of the site visit route and two Excel files of summary tables for original and revised sites selected for Segment 1 site visit. CPUC and the Tribe held a series of calls to discuss alternatives and the CPUC requested input on mitigation measures.
- January – March 2025: CPUC and the Tribe exchanged a series of emails providing updates on alternatives, logistics for the Segment 1 site visit, and data sharing protocols.
- April 2025: CPUC and the Tribe conducted a site visit for Segment 1 from April 15-17. CPUC and the Tribe exchanged a series of emails prior to and after the site visit regarding details of the site visit. CPUC and the Tribe held a site visit debrief meeting on April 28 via Zoom.
- July – August 2025: CPUC and the Tribe exchanged a series of emails regarding mitigation measures, and GIS files related to the Project.
- July 29, 2025: CPUC and the Tribe held a virtual meeting.
  - Mitigation Request: The Tribe requested mitigation measures including community benefit program, language class, curation facility funding, tribal monitoring training, or vehicle for tribal monitors. The Tribe also indicated that they prefer reburial of tribal cultural resources in place in all feasible locations. In response to the Tribe's requests, the mitigation measures presented in the Draft EIR include MM CUL-1a (Develop Data Recovery Plans for Known Historical Archaeological Resources) which includes provision to rebury tribal cultural resources in place or near the project to the extent feasible and MM TCR-1b (Provide Funding to Tribes for Research, Education, and Interpretation).
- December 2025 – January 2026: On December 2, 2025, and January 2, 2026, the CPUC provided draft mitigation measures for Tribal cultural and cultural resources to the Tribe for review and comment. The CPUC requested the Tribe's comments and input by January 16, 2026. On December 3, 2025, and January 2, 2026, the Tribe responded that they had received the draft mitigation measures and that they would review them, but no comments were submitted to the CPUC.

5B.2 Bishop Paiute Tribe

- December 14, 2018: The CPUC mailed and emailed notice requesting pre-filing input and emailed a project fact sheet to the Tribe.
- October – November 2019: CPUC sent further pre-consultation notices via mail and email to the Tribe.
- January 23, 2020: The Tribe sent a request for formal consultation via email to the CPUC.
- March 12, 2020: The CPUC spoke with the Tribe about a potential joint-tribe (with other Owens Lake tribes) meeting in Bishop.
- May 2020: The CPUC sent the Tribe an email regarding BLM data-sharing agreements, and the Tribe participated in a joint meeting for the proposed Ivanpah-Control and Control-Silver Peak Projects[1].

[1] The Control-Silver Peak Project is a similar proposed transmission line by SCE currently under review by the CPUC. The Control-Silver Peak Project affects similar Tribes as the Ivanpah-Control Project.

- **August 25, 2020: The CPUC initiated formal consultation** with a mailed formal AB 52 notification, which included a brief description of the Proposed Project and its location, the lead agency contact information, and a notification that the Tribe had 30 days to request consultation.
- December 18, 2020: CPUC and Tribe held a zoom meeting regarding an overview of the Project, CPUC review process, and AB 52 consultation process.
- December 2021: CPUC sent the Tribe an email containing a project status update, a summary of the cultural studies, information on the Class III Inventory report, and information about archeological testing that would occur in early 2022.
- September 25, 2024: CPUC and the Tribe held a call to schedule a consultation meeting.
- October 2024: CPUC sent an email to the Tribe requesting to schedule meetings. Further email correspondence from CPUC to the Tribe also contained a letter detailing a basic project description, KMZ files of all project components, ethnographic research, and an Excel file of a summary table of cultural resources along the proposed and alternative alignments. On October 14, 2024, the Tribe was informed that Segment 4 had been omitted from the Project.
- November 2024: CPUC sent the Tribe a series of emails containing references cited for ethnographic research, a request to schedule meetings, a request to provide input on participation in a site visit to Segments 1, 2, 3N, and 3S.
- December 2024 – February 2025: CPUC sent the Tribe a series of emails containing a map of the site visit route and two XLSX files of summary tables for original and revised sites selected for Segment 1 site visit. CPUC requested input on mitigation measures and site visit details.
- March 2025: CPUC and the Tribe exchanged a series of emails and text messages regarding the confirmation of the April site visit and details of the site visit.
- April 2025: CPUC and the Tribe conducted a site visit for Segment 1 from April 15-17. CPUC sent the Tribe a series of emails prior to and after the site visit regarding details of the site visit. CPUC and the Tribe held a site visit debrief meeting on April 28 via Zoom.
- July – August 2025: CPUC and the Tribe exchanged a series of emails regarding mitigation measures related to the Project and requested project data.
  - Mitigation Request: The Tribe requested a mitigation measure for repatriation funds. The Draft EIR includes Mitigation Measure TCR-1b (Provide Funding to Tribes for Research, Education, and Interpretation), which would make funds available to tribes for efforts like this.
- December 2025 – January 2026: On December 2, 2025, and January 2, 2026, the CPUC provided draft mitigation measures for Tribal cultural and cultural resources to the Tribe for review and comment. The CPUC requested the Tribe's comments and input by January 16, 2026; no response was received.

5B.3 Cocopah Indian Tribe

- December 14, 2018: CPUC sent a notice to the Tribe requesting pre-filing input.
- October 22, 2019: CPUC sent a follow up pre filing request to the Tribe.
- November 15, 2019: The Tribe confirmed receipt of Pre-Consultation Notice.
- March 10, 2020: CPUC emailed the Tribe an updated fact sheet with project changes and a KMZ file.
- May 1, 2020: CPUC sent the Tribe an email regarding BLM data-sharing agreements.
- January 26, 2021: CPUC held a call with the Tribe and the Tribe indicated they were interested in consultation and requested more information about the Project. The CPUC provided pre-consultation notices and Google Earth data about the Project.
- January 27, 2021: The Tribe requested formal consultation via email.

- **February 1, 2021: CPUC initiated formal consultation with the Tribe** via a mailed formal AB 52 notification which included a brief description of the proposed project and its location, the lead agency contact information, and a notification that the Tribe had 30 days to request consultation.
- December 17, 2021: CPUC sent the Tribe a series of emails containing a project status update, a summary of the cultural studies, information on the Class III inventory report, information about archaeological testing that would occur in early 2022.
- December 26, 2023: CPUC emailed notice for in-person consultation meetings January 8 and 9, 2024, in Barstow and Ridgecrest. The Tribe responded and stated they would not be in attendance for the in-person meeting but requested current summaries of the Project and notes from the meeting.
- January 8, 2024: The CPUC provided the request materials and meeting notes.
- October 14, 2024: CPUC sent the Tribe an email requesting to schedule meetings and a letter detailing a basic project description. The Tribe was informed that Segment 4 had been omitted from the Project.
- November 2024: CPUC and the Tribe exchanged a series of emails containing KMZ files of all project components and ethnographic research, an Excel file of a summary table of cultural resources along the proposed and alternative alignments, references cited for ethnographic research, a request to schedule meetings and a request to gauge interest for participation in site visits to Segments 1, 2, 3N, and 3S.
- December 2025 – January 2026: On December 2, 2025, and January 2, 2026, the CPUC provided draft mitigation measures for Tribal cultural and cultural resources to the Tribe for review and comment. The CPUC requested the Tribe's comments and input by January 16, 2026; no response was received.

5B.4 Colorado River Indian Tribes

- December 14, 2018: CPUC mailed the Tribe a notice requesting pre-filing input.
- January 8, 2019: The Tribe responded with a request for consultation and forms of mitigation:
  - Mitigation Request: Tribe requests resource avoidance and mitigation, notification regarding tribal monitoring opportunities and pedestrian surveys. The Draft EIR includes Mitigation Measures CUL-1a (Develop Data Recovery Plans for Known Historical Archaeological Resources), CUL-1f (Tribal Monitoring), CUL-1g (Remove Structures by Helicopter in Culturally Sensitive Areas), CUL-1h (Leave All Foundations in Place for Structures Removed in Culturally Sensitive Areas), and CUL-1i (Avoid Disturbance Within Environmentally Sensitive Areas).
- October 22, 2019: CPUC sent a Pre-Consultation Notice to the Tribe.
- November 26, 2019: The Tribe confirmed receipt of the Pre-Consultation Notice.
- January 8, 2020: The Tribe request formal consultation via email.
- January 29, 2020: The Tribe mailed CPUC a letter requesting consultation and to schedule an informal meeting. CPUC sent a response to the Tribe to begin scheduling the meeting and provided an updated fact sheet with project changes and a KMZ file.
- May 1, 2020: CPUC sent the Tribe an email regarding BLM data-sharing agreements.
- May 26, 2020: The Tribe sent CPUC an email in response to the data sharing agreements and noted that the Tribe is "interested in the Project and we are concerned about the potential impact to cultural resources extending from the Coolwater Subdivision to Ivanpah Substation."
- June 7, 2020: The Tribe emailed BLM regarding the data sharing agreement and provided a copy to CPUC team members.
- **August 25, 2020: The CPUC initiated formal consultation with the Tribe** via mailed formal AB 52 notification, which included a brief description of the proposed project and its location, the lead agency contact information, and a notification that the Tribe had 30 days to request consultation.

- September 25, 2020: The Tribe requested an extension of the NOP comment period through October 9, 2020.
- September 29, 2020: CPUC granted the Tribe's requested extension.
- November 20, 2020: The Tribe requested consultation via a phone call with CPUC.
- November 30, 2020: CPUC emailed the Tribe with proposed dates for a consultation meeting.
- February 2, 2021: CPUC gave a 15-minute presentation on the project to the Tribe. The Tribe requested that no further meetings occur until the Tribe had the opportunity to review the final Archaeological Inventory Report (Class III Inventory Report).
- December 17, 2021: CPUC provided the Tribe with a project status update, a summary of the cultural studies, the Class III Inventory Report, and information about archeological testing that would occur in early 2022.
- December 26, 2023: CPUC invited the Tribe to attend in-person AB 52 consultation meeting on January 8th and 9th in Barstow and Ridgecrest. CPUC provided the Tribe with an updated fact and Project summary.
- January 8-9, 2024: The Tribe participated in the in-person consultation meetings, with a virtual attendance option. The meetings included a summary of the Project, surveys, AB 52 consultation, and a discussion.
- September 26, 2024: CPUC held a call with the Tribe to schedule a consultation meeting.
- October 14, 2024: CPUC emailed the Tribe a request to schedule meetings and a letter detailing a basic project description. The Tribe was also informed that Segment 4 had been omitted from the Project.
- November 2024: CPUC sent the Tribe a series of emails containing KMZ files of all project components and ethnographic research, an Excel file of a summary table of cultural resources along the proposed and alternative alignments, references cited for ethnographic research, and a request to schedule meetings via phone, and a request for input on site visits to Segments 1, 2, 3N, and 3S.
- December 2025 – January 2026: On December 2, 2025, and January 2, 2026, the CPUC provided draft mitigation measures for Tribal cultural and cultural resources to the Tribe for review and comment. The CPUC requested the Tribe's comments and input by January 16, 2026, In response to the Tribe's request in January 2019, the draft mitigation measures include Mitigation Measures CUL-1a (Develop Data Recovery Plans for Known Historical Archaeological Resources), CUL-1f (Tribal Monitoring), MM CUL-1g (Remove Structures by Helicopter in Culturally Sensitive Areas), CUL-1h (Leave All Foundations in Place for Structures Removed in Culturally Sensitive Areas), and CUL-1i (Avoid Disturbance Within Environmentally Sensitive Areas).

5B.5 Fernandeño Tataviam Band of Mission Indians

- **September 14, 2020: The CPUC initiated formal consultation** via mailed formal AB 52 notification which included a brief description of the proposed project and its location, the lead agency contact information, and a notification that the Tribe had 30 days to request consultation.
- September 24, 2020: The Tribe requested formal consultation via email.
- October 2, 2020: The CPUC mailed and emailed the formal AB 52 initiation letter to the Tribe.
- January 14, 2021: The Tribe informed the CPUC via phone call that they prefer to schedule a meeting after the Tribe reviews the final archaeological inventory report (Class III Inventory Report).
- December 17, 2021: CPUC emailed the Tribe a notice with a project status update, a summary of the cultural studies, the Class III inventory report, and information about archeological testing that would occur in early 2022.

- December 26, 2023: CPUC emailed a notice to the Tribe regarding an in-person consultation meeting with CPUC.
- **January 2, 2024: The Tribe responded that the Cultural Resources Management Division of the Tribe would not be requesting consultation pursuant to AB 52 for the Project.**
- October 14, 2024: CPUC emailed the Tribe a request to schedule meetings and a letter detailing a basic project description. The Tribe was also informed that Segment 4 had been omitted from the Project.
- November 2024: CPUC sent the Tribe a series of emails containing KMZ files of all project components and ethnographic research, an Excel file of a summary table of cultural resources along the proposed and alternative alignments, references cited for ethnographic research, a request to schedule meetings, and a request for input on participation in a site visit to Segments 1, 2, 3N, and 3S.
- December 2025 – January 2026: On December 2, 2025, and January 2, 2026, the CPUC provided draft mitigation measures for Tribal cultural and cultural resources to the Tribe for review and comment. The CPUC requested the Tribe's comments and input by January 16, 2026; no response has been received.

5B.6 Fort Independence Band of Paiute Indians

- December 14, 2018: CPUC mailed the Tribe notice requesting pre-filing input via mail.
- December 1, 2019: The Tribe requested that they be included in consultation on the Project.
- October 22, 2019: CPUC informed the Tribe that the application from SCE was deemed incomplete and that consultation would not occur until within 14 days of deeming the application complete. CPUC also provided an overview of the Project and Project map.
- January 29, 2020: CPUC emailed the Tribe an updated fact sheet with known project changes and a KMZ file.
- February 20, 2020: CPUC and the Tribe held a call and CPUC provided an overview of the Project, Section 106 and Ab 52 consultation process, and future meetings. The Tribe shared information on the Owens Lake Historic Shoreline and other recent projects the Tribe has participated in.
  - Mitigation Request: Mitigation measures including funding for tribal curation and preservation facilities. The Draft EIR includes Mitigation Measure TCR-1b (Provide Funding to Tribes for Research, Education, and Interpretation), which would make funds available to tribes for efforts like this.
- May 2020: CPUC sent the Tribe an email regarding BLM data-sharing agreements. The Tribe also participated in a joint meeting for Ivanpah-Control and Control-Silver Peak projects.
- **August 26, 2020: The CPUC initiated formal consultation** with the Tribe via mailed formal AB 52 notification, which included a brief description of the proposed project and its location, the lead agency contact information, and a notification that the Tribe had 30 days to request consultation.
- November 7, 2020: The Tribe formally requested consultation via email.
- November 10, 2020: A virtual meeting was held with the Tribe and the CPUC. CPUC and the Tribe discussed the consultation process, resource designation and nomination, and Google Earth data.
- December 17, 2021: CPUC emailed the Tribe with a project status update, a summary of the cultural studies, the Class III inventory report, and information about archeological testing that would occur in early 2022. The Tribe did not reply.
- October 2024: CPUC sent the Tribe a series of emails requesting to schedule meetings, a letter detailing a basic project description, KMZ files of all project components and ethnographic research, and an Excel file of a summary table of cultural resources along the proposed and alternative alignments. On October 14, 2024, the Tribe was informed that Segment 4 had been omitted from the Project.

- November 2024: CPUC sent the Tribe a series of emails containing references cited for ethnographic research, a request to schedule meetings, and a request for input on site visits to Segments 1, 2, 3N, and 3S. A meeting was held with the Tribe to discuss selected sites for the Segment 1 site visit and an Excel file of a summary table of selected sites was shared.
- December 2024: CPUC sent the Tribe a series of emails containing a PDF map of the site visit route and two XLSX files of summary tables for original and revised sites selected for Segment 1 site visit.
- March 2025: The Tribe requested a meeting with CPUC Commissioner Douglas, and a meeting was held to discuss the Tribe's concerns about the project.
- April 2025: A site visit for Segment 1 was held from April 15-17. CPUC sent the Tribe a series of emails prior to and after the site visit regarding details of the site visit. A virtual site visit debrief meeting was held on April 28.
- July 2025: CPUC and the Tribe exchanged a series of emails regarding mitigation measures related to the Project and requested project data.
- August 2025: Two virtual meetings were held with the Tribe and CPUC. On August 4 and 19, the Tribe provided the following requests:
  - Mitigation Request: Measures related to inadvertent discovery and a reburial plan. The Tribe also suggested mitigation measures related to a funded GIS program and use of cadaver dogs for archaeological investigations. In responses to the Tribe's request, the potential use of Historical Human Remains Detection (HHRD) dogs as a method to determine the potential presence of human remains, the concept was further investigated by the CPUC team and Mitigation Measure CUL-1d was revised to present an option for SCE to use HHRD dogs before the start of ground disturbance. In addition, Mitigation Measure CUL-1d (Prepare and implement a Cultural Resources Management Plan) currently requires SCE to pay fees associated with reburial or curation for artifacts."
- December 2025 – January 2026: On December 2, 2025, and January 2, 2026, the CPUC provided draft mitigation measures for Tribal cultural and cultural resources to the Tribe for review and comment. The CPUC requested the Tribe's comments and input by January 16, 2026. On January 13, 2026, a virtual meeting was held between the CPUC and the Tribe. The meeting included a discussion of the draft mitigation measures. The Tribe provided feedback regarding the mitigation measures related to Tribal monitoring and the funding program. On January 23, the Tribe sent an email expressing concerns about archaeological testing.
- February 2026: On February 3 and February 9, the CPUC held virtual meetings and with the Tribe to discuss potential testing of sites along alternative routes.

5B.7 Fort Mojave Indian Tribe

- December 14, 2018: The CPUC mailed the Tribe notice requesting pre-filing input.
- December 20, 2019: The Tribe requested formal consultation via email.
- May 1, 2020: CPUC sent an email to the Tribe regarding BLM data-sharing agreements.
- **August 25, 2020: The CPUC initiated formal consultation** with the Tribe via mailed formal AB 52 notification, which included a brief description of the proposed project and its location, the lead agency contact information, and a notification that the Tribe had 30 days to request consultation.
- November 24, 2020: CPUC mailed and emailed formal AB 52 consultation initiation notice to the Tribe.
- February 25, 2021: A virtual meeting was held between the CPUC and the Tribe. CPUC provided an overview of the Project and discussed AB 52 consultation with the Tribe.
- March 8, 2021: CPUC emailed the Tribe KMZ files of the Project alignment, direct and indirect APE/API, and a definition of the APE/API.

- December 26, 2023: CPUC invited the Tribe to attend in-person AB 52 consultation meeting on January 8th and 9th in Barstow and Ridgecrest. CPUC provided the Tribe with an updated fact and Project summary.
- January 8-9, 2024: The Tribe participated in the in-person consultation meetings, with a virtual attendance option. The meetings included a summary of the Project, surveys, AB 52 consultation, and a discussion.
- October 2024: CPUC sent a series of emails to the Tribe including a request to schedule meetings and a letter detailing a basic project description, a summary table of project tribal cultural resources, Google Earth data, and ethnographic information. On October 14, 2024, the Tribe was informed that Segment 4 had been omitted from the Project.
- November 2024: CPUC sent the Tribe a series of emails containing KMZ files of all project components and ethnographic research, an Excel file of a summary table of cultural resources along the proposed and alternative alignments, references cited for ethnographic research, a request to schedule meetings, and a request for input on participation in site visits to Segments 1, 2, 3N, and 3S.
- December 2024: CPUC sent the Tribe a series of emails providing a PPT file of project summary from a January 2024 meeting, an Excel file of a summary table of selected sites, a PDF map of the site visit route, and two XLSX files of summary tables for original and revised sites selected for the Segment 1 site visit.
- December 2025 – January 2026: On December 2, 2025, and January 2, 2026, the CPUC provided draft mitigation measures for Tribal cultural and cultural resources to the Tribe for review and comment. The CPUC requested the Tribe's comments and input by January 16, 2026; no response has been received.

5B.8 Kern Valley Indian Community

- December 14, 2018: CPUC mailed the Tribe a notice requesting pre-filing input.
- October 22, 2019: CPUC sent the Tribe a follow up pre-filing input notice.
- November 18, 2019: The Tribe requested another copy of the Pre-Consultation notice. CPUC sent the Tribe another copy.
- March 9, 2020: The Tribe requested formal consultation via phone and indicated they were interested in tribal monitoring and discussing project details. CPUC sent the Tribe an updated fact sheet with known project changes and a KMZ file.
- May 1, 2020: CPUC emailed the Tribe regarding BLM data-sharing agreements.
- **August 25, 2020: The CPUC initiated formal consultation** with the Tribe via mailed formal AB 52 notification, which included a brief description of the proposed project and its location, the lead agency contact information, and a notification that the Tribe had 30 days to request consultation.
- December 1, 2020: The Tribe confirmed that they would like to consult via phone call.
- December 4, 2020: CPUC mailed AB 52 initiation letter to the Tribe.
- January 26, 2021: A virtual meeting was held with the Tribe and the CPUC. CPUC provided an overview of the Project and discussed the AB 52 consultation process.
- December 17, 2021: CPUC emailed the Tribe a project status update, a summary of cultural studies, information on the Class III inventory report, and information about archeological testing that would occur early 2022 was sent to the Tribe via email.
- December 26, 2023: CPUC invited the Tribe to attend in-person AB 52 consultation meeting on January 8th and 9th in Barstow and Ridgecrest. CPUC provided the Tribe with an updated fact and Project summary.

- January 8-9, 2024: The Tribe participated in the in-person consultation meetings, with a virtual attendance option. The meetings included a summary of the Project, surveys, AB 52 consultation, and a discussion.
- January 16, 2024: A phone call was held with the Tribe.
  - Mitigation Request: The Tribe provided requests for Tribal monitoring of the Project, for reburial of artifacts, and to not excavate tower footings. These requests are incorporated into the mitigation measures presented in the Draft EIR in Mitigation Measures CUL-1d (Prepare and Implement a Cultural Resources Management Plan), CUL-f (Tribal Monitoring), and CUL-1h (Leave All Foundations in Place for Structures Removed in Culturally Sensitive Areas).
- October 14, 2024: CPUC emailed the Tribe a request to schedule meetings and a letter detailing a basic project description. The Tribe was also informed that Segment 4 had been omitted from the Project.
- November 2024: CPUC sent the Tribe a series of emails containing KMZ files of all project components and ethnographic research, an Excel file of a summary table of cultural resources along the proposed and alternative alignments, cited for ethnographic research, a request to schedule meetings, and a request for input on participation in site visits to Segments 1, 2, 3N, and 3N, a PPT file of project summary from a January 2024 meeting, an Excel file of a summary table of selected sites, and a PDF map of the site visit route.
  - Mitigation Request: The Tribe provided additional requests for avoidance, protection in place, and to leave concrete tower footings in place. These requests are incorporated into the mitigation measures presented in the Draft EIR.
- December 2025 – January 2026: On December 2, 2025, and January 2, 2026, the CPUC provided draft mitigation measures for Tribal cultural and cultural resources to the Tribe for review and comment. The CPUC requested the Tribe's comments and input by January 16, 2026; no response has been received.

5B.9 Lone Pine Paiute-Shoshone Tribe

- December 14, 2018: CPUC mailed notice requesting pre-filing input to the Tribe.
- November 18, 2019: The Tribe requested a copy of December 14, 2018, pre-consultation notice via phone. CPUC resent pre consultation notice.
- March 12, 2020: The CPUC spoke with the Tribe about having a joint Tribe meeting in Bishop.
- May 5, 2020: CPUC emailed the Tribe regarding BLM data-sharing agreements. The Tribe participated in a joint meeting for the Ivanpah-Control and Control-Silver Peak projects.
- **August 26, 2020: CPUC initiated formal consultation** with the Tribe via mailed formal AB 52 notification, which included a brief description of the proposed project and its location, the lead agency contact information, and a notification that the Tribe had 30 days to request consultation.
- February 18, 2021: A Zoom meeting was held with the Tribe and the CPUC. CPUC provided an overview of the Project and discussed the AB 52 consultation process, Tribal monitoring, and Google Earth data.
  - Mitigation Request: The Tribe requested that Tribal monitoring occur for all of construction.
- December 17, 2021: CPUC emailed the Tribe a project status update, a summary of the cultural studies, information on the Class III inventory report, and information about archeological testing that would occur in early 2022.
- December 26, 2023: CPUC invited the Tribe to attend in-person AB 52 consultation meeting on January 8th and 9th in Barstow and Ridgecrest. CPUC provided the Tribe with an updated fact and Project summary.

- January 8-9, 2024: The Tribe participated in the in-person consultation meetings, with a virtual attendance option. The meetings included a summary of the Project, surveys, AB 52 consultation, and a discussion.
- September 20, 2024: CPUC held a call with the Tribe and provided the Tribe a project update, and coordination recommendations with BLM. The Tribe informed the CPUC that the Manzanar and Fossil Falls alternatives may affect more resources than the Proposed Project. This information was incorporated into the alternatives analysis (see Chapter 4, Alternatives). The Tribe requested summary tables of all resources, eligibility recommendations, and preliminary mitigation, and Google Earth data.
- October 14, 2024: CPUC sent the Tribe a series of emails containing a request to schedule meetings, a letter detailing a basic project description, Google Earth data of all project components and ethnographic research, and an Excel file of a summary table of cultural resources along the proposed and alternative alignments. The Tribe was also informed that Segment 4 had been omitted from the Project.
- November 2024: CPUC sent the Tribe a series of emails containing references cited for ethnographic research, a request to schedule meetings, a request for input on participation in site visits to Segments 1, 2, 3N, and 3S, an improved PDF map of the site visit route, and two XLSX files of summary tables for original and revised sites selected for Segment 1 site visit.
- April 2025: CPUC and the Tribe conducted a site visit for Segment 1 from April 15-17. CPUC sent the Tribe a series of emails prior to and after the site visit regarding details of the site visit. CPUC and the Tribe held a site visit debrief meeting on April 28 via Zoom.
- July 8, 2025: CPUC sent the Tribe a series of emails regarding mitigation measures, and GIS files related to the Project.
  - Mitigation Request: The Tribe indicated they would be interested in mitigation in the form of compensatory funding of tribal projects or priorities. In response to the Tribe's requests, the mitigation measures included in the Draft EIR include TCR-1b (Provide Funding to Tribes for Research, Education, and Interpretation) and MM CUL-1f (Tribal Monitoring).
- December 2025 – January 2026: On December 2, 2025, and January 2, 2026, the CPUC provided draft mitigation measures for Tribal cultural and cultural resources to the Tribe for review and comment. The CPUC requested the Tribe's comments and input by January 16, 2026; no response was received.

5B.10 Mono Lake Kutzadika Tribe

- April 1, 2020: The CPUC sent a pre-consultation notice and a project fact sheet to the Tribe.
- **August 25, 2020: The CPUC initiated formal consultation** with the Tribe via mailed formal AB 52 notification, which included a brief description of the proposed project and its location, the lead agency contact information, and a notification that the Tribe had 30 days to request consultation.
- September 13, 2020: The Tribe formally requested consultation via email.
- October 15, 2020: A Zoom meeting was held with the Tribe and the CPUC.
- December 17, 2021: CPUC emailed the Tribe a project status update, a summary of the cultural studies, information on the Class III inventory report, and information about archeological testing that would occur in early 2022.
- October 14, 2024: CPUC emailed the Tribe a request to schedule meetings and a letter detailing a basic project description. The Tribe was also informed that Segment 4 had been omitted from the Project.
- November 2024: CPUC sent the Tribe a series of emails containing KMZ files of all project components and ethnographic research, an Excel file of a summary table of cultural resources along the proposed

and alternative alignments, references cited for ethnographic research, a request to schedule meetings, and a request for input on participation in site visits to Segment 1, 2, 3N, and 3S.

- December 2025 – January 2026: On December 2, 2025, and January 2, 2026, the CPUC provided draft mitigation measures for Tribal cultural and cultural resources to the Tribe for review and comment. The CPUC requested the Tribe's comments and input by January 16, 2026; no response has been received.

5B.11 Morongo Band of Mission Indians

- December 14, 2018: The CPUC mailed the Tribe notice requesting pre-filing input. The Tribe indicated that the Project is in the Tribe's area of interest and asked to be included on AB 52 notifications. Further consultation occurred via email on December 24, 2018.
- January 29, 2020: CPUC sent a request for a conference call, an updated fact sheet with known project changes, and a KMZ via email.
- February 26, 2020: A call occurred with the Tribe and the CPUC. CPUC provided an overview of the Project and the AB 52 consultation, status of cultural surveys and report, coordination with BLM, and the Tribe discussed their geographic area.
  - Mitigation Request: The tribe requested mitigation involving tribal monitoring. The Draft EIR includes Mitigation Measure CUL-1f, which requires SCE to employ tribal monitors during all ground disturbing activities.
- May 1, 2020: An email was sent to the Tribe regarding BLM data-sharing agreements.
- **August 26, 2020: CPUC initiated formal consultation** with the Tribe via mailed formal AB 52 notification, which included a brief description of the proposed project and its location, the lead agency contact information, and a notification that the Tribe had 30 days to request consultation.
- September 3, 2020: CPUC mailed a formal consultation notice to the Tribe.
- October 23, 2020: A virtual meeting was held with the Tribe and the CPUC. CPUC provided an overview of the Project and discussed the AB 52 consultation process with the Tribe.
- December 17, 2021: CPUC emailed the Tribe a project status update, a summary of the cultural studies, information on the Class III inventory report, and information about archaeological testing that would occur in early 2022.
- December 26, 2023: CPUC invited the Tribe to attend in-person AB 52 consultation meeting on January 8th and 9th in Barstow and Ridgecrest. CPUC provided the Tribe with an updated fact and Project summary.
- January 8-9, 2024: The Tribe participated in the in-person consultation meetings, with a virtual attendance option. The meetings included a summary of the Project, surveys, AB 52 consultation, and a discussion.
- October 14, 2024: Email correspondence was sent to the Tribe containing a request to schedule meetings and a letter detailing a basic project description. The Tribe was also informed that Segment 4 had been omitted from the Project.
- November 2024: CPUC sent the Tribe a series of emails containing KMZ files of all project components and ethnographic research, an Excel file of a summary table of cultural resources along the proposed and alternative alignments, references cited for ethnographic research, a request to schedule meetings, and a request for input on participation in site visits to Segments 1, 2, 3N, and 3S.
- December 4, 2024: CPUC held a Teams meeting with the Tribe to discuss interest in possible site visits to Segments 2, 3N, and 3S and to address general concerns about the Project.

- May-June 2025: CPUC and the Tribe exchanged a series of emails regarding the status of mitigation measures related to the Project and requested project data.
- December 2025 – January 2026: On December 2, 2025, and January 2, 2026, the CPUC provided draft mitigation measures for Tribal cultural and cultural resources to the Tribe for review and comment. The CPUC requested the Tribe's comments and input by January 16, 2026; no response has been received.

5B.12 Quechan Tribe of the Fort Yuma Reservation

- **September 14, 2020: The CPUC initiated formal consultation** with the Tribe via a mailed AB 52 notification, which included a brief description of the proposed project and its location, the lead agency contact information, and a notification that the Tribe had 30 days to request consultation.
- November 24, 2020: The Tribe formally requested consultation via email.
- February 23, 2021: A Zoom meeting was held with the Tribe and the CPUC. CPUC provided an overview of the Project and discussed the AB 52 consultation process.
- December 2021: CPUC emailed the Tribe a project status update, a summary of the cultural studies, information on the Class III inventory report, and information about archeological testing that would occur in early 2022. The Tribe responded that they were not interested in information about archaeology testing, providing monitoring, concerns about testing efforts, or a site visit.
- December 26, 2023: CPUC emailed the Tribe regarding an in-person consultation meeting. The Tribe did not attend either January 8 or 9 meeting.
- January 16, 2024: CPUC held a call with the Tribe and provided and discussed materials form the January 8 and 9 in-person and virtual AB 52 meetings.
- October 14, 2024: CPUC emailed the Tribe a request to schedule meetings and a letter detailing a basic project description. The Tribe was also informed that Segment 4 had been omitted from the Project.
- November 2024: CPUC sent the Tribe a series of emails containing KMZ files of all project components and ethnographic research, an Excel file of a summary table of cultural resources along the proposed and alternative alignments, references cited for ethnographic research, a request to schedule meetings, and a request for input on participation in site visits to Segments 1, 2, 3N, and 3S.
- December 2024: CPUC sent the Tribe a series of emails containing an Excel file of a summary table of selected sites, an improved PDF map of the site visit route, and two XLSX files of summary tables for original and revised sites selected for Segment 1 site visit.
- December 2025 – January 2026: On December 2, 2025, the CPUC provided draft mitigation measures for Tribal cultural and cultural resources to the Tribe for review and comment. The CPUC requested the Tribe's comments and input by January 16, 2026. On December 12, 2025, the Tribe responded that they had no comments on the draft mitigation measures.

5B.13 San Fernando Band of Mission Indians

- December 14, 2018: CPUC mailed a notice requesting pre-filing input to the Tribe.
- March 9, 2020: CPUC emailed the Tribe an updated fact sheet with known project changes and a KMZ file.
- May 1, 2020: CPUC emailed the Tribe BLM data sharing agreements.
- **September 4, 2020: The CPUC initiated formal consultation** with the Tribe via mailed AB 52 notification, which included a brief description of the proposed project and its location, the lead agency contact information, and a notification that the Tribe had 30 days to request consultation.

- September 23, 2020: The Tribe requested formal consultation specific to Segments 3N and 3S.
- January 22, 2021: A virtual meeting was held with the Tribe and the CPUC. CPUC provided an overview of the Project and discussed the consultation process, biology reports, cultural reports, and Google Earth data. The Tribe requested a copy of the biology report.
  - Mitigation Request: The Tribe indicated they were interested in mitigation measures related to tribal monitoring, avoidance, and minimization. In response to the Tribe's requests, the mitigation measures in the Draft EIR include CUL-1a (Develop Data Recovery Plans for Known Historical Archaeological Resources), CUL-1f (Tribal Monitoring), CUL-1g (Remove Structures by Helicopter in Culturally Sensitive Areas), CUL-2h (Leave All Foundations in Place for Structures Removed in Culturally Sensitive Areas), and CUL-1i (Avoid Disturbance Within Environmentally Sensitive Areas).
- February 8, 2021: CPUC mailed the Tribe thumb drives with a PDF of the biology report.
- December 17, 2021: CPUC emailed the Tribe a project status update, a summary of the cultural studies, information on the Class III inventory report, and information about archaeological testing that would occur in early 2022.
- December 26, 2023: CPUC invited the Tribe to attend in-person AB 52 consultation meeting on January 8 and 9, 2024, in Barstow and Ridgecrest. CPUC provided the Tribe with an updated fact and Project summary.
- January 8-9, 2024: The Tribe participated in the in-person consultation meetings, with a virtual attendance option. The meetings included a summary of the Project, surveys, AB 52 consultation, and a discussion.
- October 14, 2024: CPUC emailed the Tribe a request to schedule meetings and a letter detailing a basic project description. The Tribe was also informed that Segment 4 had been omitted from the Project.
- November 2024: CPUC sent the Tribe a series of emails containing KMZ files of all project components and ethnographic research, an Excel file of a summary table of cultural resources along the proposed and alternative alignments, references cited for ethnographic research, a request to schedule meetings, and a request for input on participation in site visits to Segments 1, 2, 3N, and 3S.
- December 2025 – January 2026: On December 2, 2025, and January 2, 2026, the CPUC provided draft mitigation measures for Tribal cultural and cultural resources to the Tribe for review and comment. The CPUC requested the Tribe's comments and input by January 16, 2026; no response has been received.

5B.14 San Manuel Band of Mission Indians

- December 14, 2018: CPUC mailed the Tribe a notice requesting pre-filing input.
- January 28, 2019: The Tribe requested formal consultation via email.
- January 29, 2020: CPUC emailed the Tribe an updated fact sheet with known project changes and a KMZ file.
- February 10, 2020: A conference call was held with the Tribe and the CPUC. CPUC provided an overview of the Project and discussed the Tribe's geographic area, tribal cultural resources in the Project area, and the AB 52 consultation process.
  - Mitigation Request: The Tribe requested that pole replacement occur within the same location as existing poles in the boundaries of sensitive resources. Mitigation Measure CUL-1d (Prepare and implement a Cultural Resources Management Plan) is included in the Draft EIR; this measure requires development of a detailed approach to avoidance of known resources and for treatment of unanticipated resources that are found during construction.
- May 1, 2020: CPUC emailed the Tribe regarding BLM data-sharing agreements.

- **August 25, 2020: The CPUC initiated formal consultation** with the Tribe via mailed AB 52 notification, which included a brief description of the proposed project and its location, the lead agency contact information, and a notification that the Tribe had 30 days to request consultation.
- September 8, 2020: The Tribe again formally requested consultation via email.
- November 8, 2020: The Tribe sent an email noting that they are waiting until the archology report (Class III Inventory Report) is complete before scheduling a consultation meeting, outlining the Tribe's concerns with the BLM data sharing procedures, and inquiring about project details.
- January 6, 2021: The Tribe stated that they would prefer to meet regarding consultation after receiving the final Class III Archaeological Inventory Report.
- December 17, 2021: CPUC emailed the Tribe a project status update, a summary of the cultural studies, the Class II inventory report, and information about archaeological testing that would occur in early 2022.
- February 2022: The Tribe requested more information about the resources where testing is planned and the proposed testing methods within Segments 2-4.
  - Mitigation Request: The Tribe also strongly recommended that artifacts not be collected during Phase I and II archeological assessments.
  - The tribe further requested that if any human remains are discovered within Serrano Ancestral Territory, the Tribe would like its CRM department be notified immediately during testing. Additionally, the Tribe did not request the presence of Tribal monitors or the accommodation of site-visits. The Tribe also stated they had no objections to the proposed testing locations and asked for confirmation on if and how previous concerns about the testing plan summary were addressed.
  - In response to the Tribe's requests, the mitigation measures presented I the Draft EIR include CUL-1a (Develop Data Recovery Plans for Known Historical Archaeological Resources), CUL-1d (Prepare and Implement a Cultural Resources Management Plan, which addresses assessment, treatment, and notification in the event that human remains are discovered), CUL-1f (Tribal Monitoring), CUL-1g (Remove Structures by Helicopter in Culturally Sensitive Areas), CUL-1h (Leave All Foundations in Place for Structures Removed in Culturally Sensitive Areas), and CUL-1i (Avoid Disturbance Within Environmentally Sensitive Areas).
- December 26, 2023: CPUC invited the Tribe to attend in-person AB 52 consultation meeting on January 8-9, 2024, in Barstow and Ridgecrest. CPUC provided the Tribe with an updated fact and Project summary. The Tribe responded that only a portion of the Project lies within the Tribe's ancestral territory and that they were interested in attending the meeting with the understanding that the meeting would focus on encroaching areas.
- January 8-9, 2024: The Tribe participated in the in-person consultation meetings, with a virtual attendance option. The meetings included a summary of the Project, surveys, AB 52 consultation, and a discussion.
- September 26, 2024: CPUC called the Tribe to schedule an AB 52 meeting.
- October 2024: CPUC sent the Tribe a series of emails containing a request to schedule meetings, a letter detailing a basic project description, KMZ files of all project components, ethnographic research, and an Excel file of a summary table of cultural resources along the proposed and alternative alignments. On October 14, 2024, the Tribe was informed that Segment 4 had been omitted from the Project.
- November 2024: CPUC sent the Tribe a series of emails requesting to schedule meetings and to request input on participation in site visits to Segments 1, 2, 3N, 3S.

- December 2024: Email correspondence was sent to the Tribe containing a PDF map of the site visit route. The Tribe responded with an area of interest and shared information on resources within the area of interest.
- January – March 2025: CPUC sent the Tribe a series of emails regarding site visits, alternatives, and project data sharing.
- December 2025 – January 2026: On December 2, 2025, and January 2, 2026, the CPUC provided draft mitigation measures for Tribal cultural and cultural resources to the Tribe for review and comment. The CPUC requested the Tribe's comments and input by January 16, 2026; no response has been received.

5B.15 Tejon Indian Tribe

- December 14, 2018: CPUC mailed the Tribe a notice requesting pre-filing input.
- October 2019: The Tribe requested formal consultation via email. The Tribe also requested zoomed-in maps. In addition, the Tribe provided information regarding ethnohistory via email. Also:
  - Mitigation Request: The Tribe requested that the survey crew include one or more qualified Tribal Cultural Specialists and/or Professional Archaeologists in the project survey crews in Kern County. In response to the Tribe's request, the Draft EIR includes mitigation measure MM CUL-1f (Tribal Monitoring).
- November 4, 2019: The CPUC emailed maps and KMZ files and forwarded the Tribe's requests to SCE.
- April 14, 2020: An initial conference call was held with the Tribe and the CPUC.
- May 1, 2020: CPUC emailed the Tribe BLM data-sharing agreements.
- **August 26, 2020: The CPUC initiated formal consultation** with the Tribe via mailed AB 52 notification, which included a brief description of the proposed project and its location, the lead agency contact information, and a notification that the Tribe had 30 days to request consultation.
- October 19, 2020: The Tribe again requested formal consultation via email.
- December 17, 2021: CPUC emailed the Tribe a project status update, a summary of the cultural studies, information on the Class III inventory report, and information about archaeological testing that would occur in early 2022.
- February 16, 2022: The Tribe emailed CPUC stating that they had been working to ensure that the proper Tribes are receiving monitoring work associated with archaeological testing for the Project. They arranged for 2 days of monitoring work to be transferred from Tejon to the Kern Valley Indian Community for the Project.
- December 26, 2023: CPUC invited the Tribe to attend in-person AB 52 consultation meeting on January 8th and 9th in Barstow and Ridgecrest. CPUC provided the Tribe with an updated fact and Project summary.
- January 8-9, 2024: The Tribe participated in the in-person consultation meetings, with a virtual attendance option. The meetings included a summary of the Project, surveys, AB 52 consultation, and a discussion.
- September 26, 2024: CPUC called the Tribe to schedule an AB 52 meeting.
- October 14, 2024: CPUC emailed the Tribe a request to schedule meetings and a letter detailing a basic project description. The Tribe was also informed that Segment 4 had been omitted from the Project.
- November 2024: CPUC sent the Tribe a series of emails containing KMZ files of all project components and ethnographic research, an Excel file of a summary table of cultural resources along the proposed

and alternative alignments, references cited for ethnographic research, a request to schedule meetings, and a request for input on participation in site visits to Segments 1, 2, 3N, and 3S.

- December 2024: CPUC sent the Tribe a series of emails containing an Excel file of a summary table of selected sites, a PDF map of the site visit route, and two XLSX files of summary tables for original and revised sites selected for the Segment 1 site visit.
- December 2025 – January 2026: On December 2, 2025, and January 2, 2026, the CPUC provided draft mitigation measures for Tribal cultural and cultural resources to the Tribe for review and comment. The CPUC requested the Tribe's comments and input by January 16, 2026; no response has been received.

5B.16 Timbisha Shoshone Tribe

- December 14, 2018: CPUC mailed the Tribe a notice requesting pre-filing input.
- January 7, 2019: The Tribe requested formal consultation via email. CPUC emailed the Tribe an updated fact sheet with known project changes and a KMZ file.
- May 1, 2020: BLM data sharing agreements were sent to the Tribe via email.
- **August 26, 2020: The CPUC initiated formal consultation** with the Tribe via mailed AB 52 notification, which included a brief description of the proposed project and its location, the lead agency contact information, and a notification that the Tribe had 30 days to request consultation.
- November 6, 2020: The Tribe requested formal consultation.
- November 18, 2020: CPUC held a virtual meeting with the Tribe. CPUC provided a Project overview and discussed consultation, BLM coordination, and resources of interest to the Tribe.
  - Mitigation Request: The Tribe requested mitigation related to tribal monitoring. In response to the Tribe's request, the Draft EIR includes mitigation measure MM CUL-1f (Tribal Monitoring).
- December 17, 2021: CPUC emailed the Tribe a project status update, a summary of the cultural studies, information on the Class III inventory report, and information about archeological testing that would occur in early 2022.
- December 26, 2023: CPUC invited the Tribe to attend in-person AB 52 consultation meeting on January 8th and 9th in Barstow and Ridgecrest. CPUC provided the Tribe with an updated fact and Project summary.
- January 8-9, 2024: The Tribe participated in the in-person consultation meetings, with a virtual attendance option. The meetings included a summary of the Project, surveys, AB 52 consultation, and a discussion.
- October 14, 2024: CPUC emailed the Tribe a request to schedule meetings and a letter detailing a basic project description. The Tribe was also informed that Segment 4 had been omitted from the Project.
- November 2024: CPUC sent the Tribe a series of emails containing KMZ files of all project components and ethnographic research, an Excel file of a summary table of cultural resources along the proposed and alternative alignments, references cited for ethnographic research, a request to schedule meeting, and a request for input on participation in site visits to Segments 1, 2, 3N, and 3S.
- December 2024: CPUC sent the Tribe a series of emails containing a PDF map of the site visit route and two XLSX files of summary tables for original and revised sites selected for the Segment 1 site visit.
- April 2025: CPUC and the Tribe conducted a site visit for Segment 1 from April 15-17. CPUC sent the Tribe a series of emails prior to and after the site visit regarding details of the site visit. CPUC and the Tribe held a site visit debrief meeting on April 28 via Zoom.

- July 2025: CPUC and the Tribe exchanged a series of emails regarding the status of mitigation measures related to the Project.
- December 2025 – January 2026: On December 2, 2025, and January 2, 2026, the CPUC provided draft mitigation measures for Tribal cultural and cultural resources to the Tribe for review and comment. The CPUC requested the Tribe's comments and input by January 16, 2026; no response has been received.

5B.17 Tubatulabals of Kern Valley

- October 19, 2022: CPUC the Tribe sent a pre-consultation notice.
- April 19, 2020: The Tribe requested formal consultation via email and stated the "project is within sensitive areas of cultural landscape of the Tubatulabal Tribe, especially within the area south of the Little Lake to Ridgecrest corridors."
- May 1, 2020: CPUC sent the Tribe an email regarding BLM data sharing agreements.
- **August 25, 2020: CPUC initiated formal consultation** with the Tribe via mailed AB 52 notification, which included a brief description of the proposed project and its location, the lead agency contact information, and a notification that the Tribe had 30 days to request consultation.
- December 1, 2020: The Tribe confirmed they were interested in consultation via phone call.
- December 15, 2020: A Zoom meeting was held with the Tribe and CPUC. CPUC provided an overview of the Project and discussed the consultation process, Google Earth data, and habitat reports. CPUC mailed the Tribe a thumb drive with the habitat assessment technical reports on December 22, 2020.
- December 17, 2021: CPUC emailed the Tribe a notice with a project status update, a summary of the cultural studies, information on the Class III inventory report, and information about archaeological testing that would occur in early 2022.
- December 26, 2023: CPUC invited the Tribe to attend in-person AB 52 consultation meeting on January 8-9, 2024, in Barstow and Ridgecrest. CPUC provided the Tribe with an updated fact and Project summary.
- January 8-9, 2024: The Tribe participated in the in-person consultation meetings, with a virtual attendance option. The meetings included a summary of the Project, surveys, AB 52 consultation, and a discussion.
- October 14, 2024: CPUC emailed the Tribe a request to schedule meetings and a letter detailing a basic project description. The Tribe was also informed that Segment 4 had been omitted from the Project.
- November 2024: CPUC sent the Tribe a series of emails containing KMZ files of all project components and ethnographic research, an Excel file of a summary table of cultural resources along the proposed and alternative alignments, references cited for ethnographic research, a request to schedule meetings, and a request for input on participation in site visits to Segments 1, 2, 3N, and 3S.
- December 2025 – January 2026: On December 2, 2025, and January 2, 2026, the CPUC provided draft mitigation measures for Tribal cultural and cultural resources to the Tribe for review and comment. The CPUC requested the Tribe's comments and input by January 16, 2026; no response has been received.

5B.18 Twenty-Nine Palms Band of Mission Indians

- December 14, 2018: The CPUC sent the Tribe notice initiating pre-filing consultation.
- November 22, 2019: The Twenty-Nine Palms Band of Mission Indians requested formal consultation via email.

- January 22, 2020: CPUC emailed the Tribe a request for a conference call, an updated fact sheet with known project changes, and a KMZ file.
- April 9, 2020: The Tribe responded and indicated they were interested in scheduling in a call.
- April 15, 2020: CPUC and the Tribe held an initial conference call. The CPUC and the Tribe provided an overview of the Project and discussed Cultural Resources Reports, data sharing, the Tribe's geographic area, and inter-tribal meetings and consultation.
- **August 26, 2020: CPUC initiated formal consultation** via mailed AB 52 notification, which included a brief description of the proposed project and its location, the lead agency contact information, and a notification that the Tribe had 30 days to request consultation.
- December 17, 2021: CPUC emailed the Tribe a project status update, a summary of the cultural studies, information on the Class III inventory report, and information about archaeological testing to be conducted in early 2022.
- December 26, 2023: CPUC invited the Tribe to attend in-person AB 52 consultation meeting on January 8-9, 2024, in Barstow and Ridgecrest. CPUC provided the Tribe with an updated fact and Project summary.
- January 8-9, 2024: The Tribe participated in the in-person consultation meetings, with a virtual attendance option. The meetings included a summary of the Project, surveys, AB 52 consultation, and a discussion.
- September 26, 2024: CPUC and the Tribe spoke on the phone to schedule an AB 52 meeting.
- October 14, 2024: CPUC emailed the Tribe a request to schedule meetings and a letter detailing a basic project description. The Tribe was also informed that Segment 4 had been omitted from the Project.
- November 2024: CPUC sent the Tribe a series of emails containing KMZ files of all project components and ethnographic research, an Excel file of a summary table of cultural resources along the proposed and alternative alignments, references cited for ethnographic research, a request to schedule meetings and to gauge interest for participation in site visits to Segments 1, 2, 3N, and 3S.
- December 4, 2024: The CPUC called the Tribe to confirm receipt of materials in November 2024 emails.
- December 2025 – January 2026: On December 2, 2025, and January 2, 2026, the CPUC provided draft mitigation measures for Tribal cultural and cultural resources to the Tribe for review and comment. The CPUC requested the Tribe's comments and input by January 16, 2026; no response has been received.

Part 2:

CORRESPONDENCE WITH THE NATIVE AMERICAN HERITAGE COMMISSION (NOVEMBER – DECEMBER 2018)

From: Blanchard, Billie C. <billie.blanchard@cpuc.ca.gov>
Sent: Thursday, November 8, 2018 3:12 PM
To: gayle.Totton@NAHC.ca.gov

Subject: FW: NAHC request for Ivanpah-Control
Attachments: Ivanpah-Control Pre-Filing Local Gov Tribal Cons List Req11-8-18.docx

Ms. Totton:
Please find attached a CPUC request for a Tribal Consultation Contact List and a Sacred Lands File Search for the Southern California Edison's Ivanpah – Control Project that will be filed at the CPUC.
Let us know if you have any questions regarding our request.
Regards
Billie

Billie Blanchard
Senior Analyst|Project Manager
Infrastructure, Planning, and Permitting Branch
Energy Division|California Public Utilities Commission
916-823-4799 | Billie.Blanchard@cpuc.ca.gov

Local Government Tribal Consultation List Request
Native American Heritage Commission

1550 Harbor Blvd, Suite 100
West Sacramento, CA 95691
916-373-3710
916-373-5471 – Fax
nahc@nahc.ca.gov

Type of List Requested

☒ **CEQA Tribal Consultation List (AB 52)** – ***Per Public Resources Code § 21080.3.1, subs. (b), (d), (e) and 21080.3.2***

☐ **General Plan (SB 18)** - ***Per Government Code § 65352.3.***

Local Action Type:
___ General Plan ___ General Plan Element ___ General Plan Amendment
___ Specific Plan ___ Specific Plan Amendment ___ Pre-planning Outreach Activity

Required Information
Project Title: *IVANPAH-CONTROL PROJECT*
Local Government/Lead Agency: *CALIFORNIA PUBLIC UTILITIES COMISSION*

Contact Person: *BILLIE BLANCHARD, CPUC PROJECT MANAGER*
Street Address: *300 Capitol Mall, 4th Floor*
City *SACRAMENTO* **Zip:** *95814*
Phone: *(510) 685-1634 (cell)*
Fax: *N/A*
Email: *billie.blanchard@cpuc.ca.gov*

Specific Area Subject to Proposed Action
County: *SAN BERNARDINO, KERN, INYO* **City/Community:** *VARIOUS*

Project Description: *Southern California Edison (SCE) is proposing to rebuild components of the existing 115 kilovolt (kV) transmission lines between the Ivanpah, Coolwater, and Kramer Substations in San Bernardino County, the Inyokern Substation in Kern County, and the Haiwee and Control Substations in Inyo County. The project is subject to review under the California Environmental Quality Act (CEQA). The transmission system included in the Ivanpah-Control Project extends over 350 miles, from eastern San Bernardino County, through the northeastern corner of Kern County, and into Inyo County. As shown in Figure 1, the route connects numerous substations, which would require updated interconnection to the new conductors. The major route segments are as follows and each is described below: Ivanpah-Coolwater (96 miles); Coolwater-Kramer (44 and 46 miles following two routes); Kramer-Inyokern (48 miles); and Inyokern-Control (126 miles).*

Additional Request

☒ **Sacred Lands File Search**
Required Information:

USGS Quadrangle Name(s): *Please see the table on the following page*

Township:_____ Range:_____ Section(s):_____

Please see the table on the following page for township, range, and section data.

USGS Quadrangles and Section Data for the SCE Ivanpah-Control Project

Transmission Segment Name	USGS CODE	QUAD NAME	Township, Range, Section
Kramer-Inyokern	35117C5	RED MOUNTAIN	Township 30S, Range 41E, Section 30
Kramer-Inyokern	35117C5	RED MOUNTAIN	Township 30S, Range 41E, Section 31
Kramer-Inyokern	35117C5	RED MOUNTAIN	Township 31S, Range 41E, Section 6
Kramer-Inyokern	35117C5	RED MOUNTAIN	Township 31S, Range 41E, Section 7
Kramer-Inyokern	35117C6	JOHANNESBURG	Township 29S, Range 40E, Section 36
Kramer-Inyokern	35117C6	JOHANNESBURG	Township 30S, Range 40E, Section 1
Kramer-Inyokern	35117C6	JOHANNESBURG	Township 30S, Range 40E, Section 12
Kramer-Inyokern	35117C6	JOHANNESBURG	Township 30S, Range 40E, Section 13
Kramer-Inyokern	35117C6	JOHANNESBURG	Township 30S, Range 40E, Section 24
Kramer-Inyokern	35117C6	JOHANNESBURG	Township 30S, Range 41E, Section 19
Kramer-Inyokern	35117C6	JOHANNESBURG	Township 30S, Range 41E, Section 30
Kramer-Inyokern	35117B5	BORON NE	Township 32S, Range 41E, Section 4
Kramer-Inyokern	35117B5	BORON NE	Township 32S, Range 41E, Section 5
Kramer-Inyokern	35117B5	BORON NE	Township 32S, Range 41E, Section 9
Kramer-Inyokern	35117B5	BORON NE	Township 32S, Range 41E, Section 16
Kramer-Inyokern	35117B5	BORON NE	Township 32S, Range 41E, Section 21
Kramer-Inyokern	35117B5	BORON NE	Township 32S, Range 41E, Section 28
Kramer-Inyokern	35117B5	BORON NE	Township 31S, Range 41E, Section 7
Kramer-Inyokern	35117B5	BORON NE	Township 31S, Range 41E, Section 8
Kramer-Inyokern	35117B5	BORON NE	Township 31S, Range 41E, Section 17
Kramer-Inyokern	35117B5	BORON NE	Township 31S, Range 41E, Section 20
Kramer-Inyokern	35117B5	BORON NE	Township 31S, Range 41E, Section 29
Kramer-Inyokern	35117B5	BORON NE	Township 31S, Range 41E, Section 32
Kramer-Inyokern	35117A5	SADDLEBACK MTN.	Township 11N, Range 6W, Section 7
Kramer-Inyokern	35117A5	SADDLEBACK MTN.	Township 11N, Range 6W, Section 18
Kramer-Inyokern	35117A5	SADDLEBACK MTN.	Township 11N, Range 6W, Section 19
Kramer-Inyokern	35117A5	SADDLEBACK MTN.	Township 11N, Range 6W, Section 30
Kramer-Inyokern	35117A5	SADDLEBACK MTN.	Township 11N, Range 6W, Section 31
Kramer-Inyokern	35117A5	SADDLEBACK MTN.	Township 11N, Range 6W, Section 32
Kramer-Inyokern	35117A5	SADDLEBACK MTN.	Township 11N, Range 7W, Section 1
Kramer-Inyokern	35117A5	SADDLEBACK MTN.	Township 11N, Range 7W, Section 12
Kramer-Inyokern	35117A5	SADDLEBACK MTN.	Township 12N, Range 7W, Section 36
Kramer-Inyokern	35117A5	SADDLEBACK MTN.	Township 32S, Range 41E, Section 27
Kramer-Inyokern	35117A5	SADDLEBACK MTN.	Township 32S, Range 41E, Section 28
Kramer-Inyokern	35117A5	SADDLEBACK MTN.	Township 32S, Range 41E, Section 34
Kramer-Inyokern	34117H5	KRAMER JUNCTION	Township 10N, Range 6W, Section 5
Kramer-Inyokern	34117H5	KRAMER JUNCTION	Township 10N, Range 6W, Section 6
Kramer-Inyokern	34117H5	KRAMER JUNCTION	Township 11N, Range 6W, Section 32
Coolwater-Tortilla-Kramer	34117H1	BARSTOW	Township 9N, Range 2W, Section 4
Coolwater-Tortilla-Kramer	34117H1	BARSTOW	Township 9N, Range 2W, Section 5
Coolwater-Tortilla-Kramer	34117H1	BARSTOW	Township 9N, Range 2W, Section 6

Transmission Segment Name	USGS CODE	QUAD NAME	Township, Range, Section
Coolwater-Tortilla-Kramer	34117H1	BARSTOW	Township 9N, Range 2W, Section 9
Coolwater-Tortilla-Kramer	34117H1	BARSTOW	Township 9N, Range 2W, Section 10
Coolwater-Tortilla-Kramer	34117H1	BARSTOW	Township 9N, Range 2W, Section 15
Coolwater-Tortilla-Kramer	34117H2	HINKLEY	Township 9N, Range 3W, Section 1
Coolwater-Tortilla-Kramer	34117H2	HINKLEY	Township 9N, Range 3W, Section 2
Coolwater-Tortilla-Kramer	34117H2	HINKLEY	Township 9N, Range 3W, Section 3
Coolwater-Tortilla-Kramer	34117H2	HINKLEY	Township 9N, Range 3W, Section 4
Coolwater-Tortilla-Kramer	34117H2	HINKLEY	Township 9N, Range 3W, Section 5
Coolwater-Tortilla-Kramer	34117H2	HINKLEY	Township 9N, Range 3W, Section 6
Coolwater-Tortilla-Kramer	34117H2	HINKLEY	Township 9N, Range 4W, Section 1
Coolwater-Tortilla-Kramer	34117H2	HINKLEY	Township 9N, Range 2W, Section 6
Coolwater-Tortilla-Kramer	34117H3	TWELVE GAUGE LAKE	Township 9N, Range 4W, Section 1
Coolwater-Tortilla-Kramer	34117H3	TWELVE GAUGE LAKE	Township 9N, Range 4W, Section 2
Coolwater-Tortilla-Kramer	34117H3	TWELVE GAUGE LAKE	Township 9N, Range 4W, Section 3
Coolwater-Tortilla-Kramer	34117H3	TWELVE GAUGE LAKE	Township 9N, Range 4W, Section 4
Coolwater-Tortilla-Kramer	34117H3	TWELVE GAUGE LAKE	Township 9N, Range 4W, Section 5
Coolwater-Tortilla-Kramer	34117H3	TWELVE GAUGE LAKE	Township 9N, Range 4W, Section 6
Coolwater-Tortilla-Kramer	34117H3	TWELVE GAUGE LAKE	Township 9N, Range 5W, Section 1
Coolwater-Tortilla-Kramer	34117H3	TWELVE GAUGE LAKE	Township 9N, Range 5W, Section 2
Coolwater-Tortilla-Kramer	34117H4	KRAMER HILLS	Township 10N, Range 6W, Section 14
Coolwater-Tortilla-Kramer	34117H4	KRAMER HILLS	Township 10N, Range 6W, Section 15
Coolwater-Tortilla-Kramer	34117H4	KRAMER HILLS	Township 10N, Range 6W, Section 23
Coolwater-Tortilla-Kramer	34117H4	KRAMER HILLS	Township 10N, Range 6W, Section 24
Coolwater-Tortilla-Kramer	34117H4	KRAMER HILLS	Township 10N, Range 6W, Section 25
Coolwater-Tortilla-Kramer	34117H4	KRAMER HILLS	Township 9N, Range 5W, Section 2
Coolwater-Tortilla-Kramer	34117H4	KRAMER HILLS	Township 9N, Range 5W, Section 3
Coolwater-Tortilla-Kramer	34117H4	KRAMER HILLS	Township 9N, Range 5W, Section 4
Coolwater-Tortilla-Kramer	34117H4	KRAMER HILLS	Township 10N, Range 5W, Section 29
Coolwater-Tortilla-Kramer	34117H4	KRAMER HILLS	Township 10N, Range 5W, Section 30
Coolwater-Tortilla-Kramer	34117H4	KRAMER HILLS	Township 10N, Range 5W, Section 32
Coolwater-Tortilla-Kramer	34117H4	KRAMER HILLS	Township 10N, Range 5W, Section 33
Coolwater-Tortilla-Kramer	34117H5	KRAMER JUNCTION	Township 10N, Range 6W, Section 5
Coolwater-Tortilla-Kramer	34117H5	KRAMER JUNCTION	Township 10N, Range 6W, Section 8
Coolwater-Tortilla-Kramer	34117H5	KRAMER JUNCTION	Township 10N, Range 6W, Section 9
Coolwater-Tortilla-Kramer	34117H5	KRAMER JUNCTION	Township 10N, Range 6W, Section 10
Coolwater-Tortilla-Kramer	34117H5	KRAMER JUNCTION	Township 10N, Range 6W, Section 15
Coolwater-Tortilla-Kramer	34116G7	MINNEOLA	Township 9N, Range 1E, Section 21
Coolwater-Tortilla-Kramer	34116G7	MINNEOLA	Township 9N, Range 1E, Section 22
Coolwater-Tortilla-Kramer	34116G7	MINNEOLA	Township 9N, Range 1E, Section 23
Coolwater-Tortilla-Kramer	34116G7	MINNEOLA	Township 9N, Range 1E, Section 27
Coolwater-Tortilla-Kramer	34116G8	DAGGETT	Township 9N, Range 1E, Section 19
Coolwater-Tortilla-Kramer	34116G8	DAGGETT	Township 9N, Range 1E, Section 20
Coolwater-Tortilla-Kramer	34116G8	DAGGETT	Township 9N, Range 1E, Section 21

Transmission Segment Name	USGS CODE	QUAD NAME	Township, Range, Section
Coolwater-Tortilla-Kramer	34116G8	DAGGETT	Township 9N, Range 1E, Section 28
Coolwater-Tortilla-Kramer	34116G8	DAGGETT	Township 9N, Range 1E, Section 29
Coolwater-Tortilla-Kramer	34116G8	DAGGETT	Township 9N, Range 1W, Section 20
Coolwater-Tortilla-Kramer	34116G8	DAGGETT	Township 9N, Range 1W, Section 21
Coolwater-Tortilla-Kramer	34116G8	DAGGETT	Township 9N, Range 1W, Section 22
Coolwater-Tortilla-Kramer	34116G8	DAGGETT	Township 9N, Range 1W, Section 23
Coolwater-Tortilla-Kramer	34116G8	DAGGETT	Township 9N, Range 1W, Section 24
Coolwater-Tortilla-Kramer	34117G1	BARSTOW SE	Township 9N, Range 1W, Section 19
Coolwater-Tortilla-Kramer	34117G1	BARSTOW SE	Township 9N, Range 1W, Section 20
Coolwater-Tortilla-Kramer	34117G1	BARSTOW SE	Township 9N, Range 2W, Section 13
Coolwater-Tortilla-Kramer	34117G1	BARSTOW SE	Township 9N, Range 2W, Section 14
Coolwater-Tortilla-Kramer	34117G1	BARSTOW SE	Township 9N, Range 2W, Section 15
Coolwater-Tortilla-Kramer	34117G1	BARSTOW SE	Township 9N, Range 2W, Section 24
Coolwater-Kramer	34116H8	NEBO	Township 9N, Range 1E, Section 5
Coolwater-Kramer	34116H8	NEBO	Township 9N, Range 1E, Section 8
Coolwater-Kramer	34116H8	NEBO	Township 9N, Range 1E, Section 9
Coolwater-Kramer	34116H8	NEBO	Township 9N, Range 1E, Section 16
Coolwater-Kramer	34116H8	NEBO	Township 10N, Range 1E, Section 30
Coolwater-Kramer	34116H8	NEBO	Township 10N, Range 1E, Section 31
Coolwater-Kramer	34116H8	NEBO	Township 10N, Range 1E, Section 32
Coolwater-Kramer	34116H8	NEBO	Township 10N, Range 1W, Section 8
Coolwater-Kramer	34116H8	NEBO	Township 10N, Range 1W, Section 9
Coolwater-Kramer	34116H8	NEBO	Township 10N, Range 1W, Section 10
Coolwater-Kramer	34116H8	NEBO	Township 10N, Range 1W, Section 14
Coolwater-Kramer	34116H8	NEBO	Township 10N, Range 1W, Section 15
Coolwater-Kramer	34116H8	NEBO	Township 10N, Range 1W, Section 23
Coolwater-Kramer	34116H8	NEBO	Township 10N, Range 1W, Section 24
Coolwater-Kramer	34116H8	NEBO	Township 10N, Range 1W, Section 25
Coolwater-Kramer	34117H1	BARSTOW	Township 10N, Range 2W, Section 4
Coolwater-Kramer	34117H1	BARSTOW	Township 10N, Range 2W, Section 5
Coolwater-Kramer	34117H1	BARSTOW	Township 10N, Range 2W, Section 6
Coolwater-Kramer	34117H1	BARSTOW	Township 10N, Range 2W, Section 9
Coolwater-Kramer	34117H1	BARSTOW	Township 10N, Range 2W, Section 10
Coolwater-Kramer	34117H1	BARSTOW	Township 10N, Range 2W, Section 11
Coolwater-Kramer	34117H1	BARSTOW	Township 10N, Range 2W, Section 12
Coolwater-Kramer	34117H1	BARSTOW	Township 10N, Range 1W, Section 7
Coolwater-Kramer	34117H1	BARSTOW	Township 10N, Range 1W, Section 8
Coolwater-Kramer	34117H2	HINKLEY	Township 10N, Range 2W, Section 6
Coolwater-Kramer	34117H2	HINKLEY	Township 10N, Range 3W, Section 1
Coolwater-Kramer	34117H2	HINKLEY	Township 10N, Range 3W, Section 2
Coolwater-Kramer	34117H2	HINKLEY	Township 10N, Range 3W, Section 3
Coolwater-Kramer	34117H2	HINKLEY	Township 10N, Range 3W, Section 4
Coolwater-Kramer	34117H2	HINKLEY	Township 10N, Range 3W, Section 5

Transmission Segment Name	USGS CODE	QUAD NAME	Township, Range, Section
Coolwater-Kramer	34117H2	HINKLEY	Township 10N, Range 3W, Section 6
Coolwater-Kramer	34117H2	HINKLEY	Township 10N, Range 4W, Section 1
Coolwater-Kramer	34117H3	TWELVE GAUGE LAKE	Township 10N, Range 5W, Section 1
Coolwater-Kramer	34117H3	TWELVE GAUGE LAKE	Township 10N, Range 5W, Section 2
Coolwater-Kramer	34117H3	TWELVE GAUGE LAKE	Township 10N, Range 4W, Section 1
Coolwater-Kramer	34117H3	TWELVE GAUGE LAKE	Township 10N, Range 4W, Section 2
Coolwater-Kramer	34117H3	TWELVE GAUGE LAKE	Township 10N, Range 4W, Section 3
Coolwater-Kramer	34117H3	TWELVE GAUGE LAKE	Township 10N, Range 4W, Section 4
Coolwater-Kramer	34117H3	TWELVE GAUGE LAKE	Township 10N, Range 4W, Section 5
Coolwater-Kramer	34117H3	TWELVE GAUGE LAKE	Township 10N, Range 4W, Section 6
Coolwater-Kramer	34117H4	KRAMER HILLS	Township 10N, Range 6W, Section 1
Coolwater-Kramer	34117H4	KRAMER HILLS	Township 10N, Range 6W, Section 2
Coolwater-Kramer	34117H4	KRAMER HILLS	Township 10N, Range 6W, Section 3
Coolwater-Kramer	34117H4	KRAMER HILLS	Township 10N, Range 5W, Section 2
Coolwater-Kramer	34117H4	KRAMER HILLS	Township 10N, Range 5W, Section 3
Coolwater-Kramer	34117H4	KRAMER HILLS	Township 10N, Range 5W, Section 4
Coolwater-Kramer	34117H4	KRAMER HILLS	Township 10N, Range 5W, Section 5
Coolwater-Kramer	34117H4	KRAMER HILLS	Township 10N, Range 5W, Section 6
Coolwater-Kramer	34117H5	KRAMER JUNCTION	Township 10N, Range 6W, Section 3
Coolwater-Kramer	34117H5	KRAMER JUNCTION	Township 10N, Range 6W, Section 4
Coolwater-Kramer	34117H5	KRAMER JUNCTION	Township 10N, Range 6W, Section 5
Coolwater-Kramer	34116G7	MINNEOLA	Township 9N, Range 1E, Section 14
Coolwater-Kramer	34116G7	MINNEOLA	Township 9N, Range 1E, Section 15
Coolwater-Kramer	34116G7	MINNEOLA	Township 9N, Range 1E, Section 16
Coolwater-Kramer	34116G7	MINNEOLA	Township 9N, Range 1E, Section 23
Coolwater-Kramer	34116G8	DAGGETT	Township 9N, Range 1E, Section 16
Baker-Dunn-Siding-Coolwater	35116C1	BAKER	Township 14N, Range 8E, Section 24
Baker-Dunn-Siding-Coolwater	35116C1	BAKER	Township 14N, Range 8E, Section 25
Baker-Dunn-Siding-Coolwater	35116C1	BAKER	Township 14N, Range 8E, Section 26
Baker-Dunn-Siding-Coolwater	35116C1	BAKER	Township 14N, Range 8E, Section 34
Baker-Dunn-Siding-Coolwater	35116C1	BAKER	Township 14N, Range 8E, Section 35
Baker-Dunn-Siding-Coolwater	35116C1	BAKER	Township 14N, Range 9E, Section 19
Baker-Dunn-Siding-Coolwater	35116B1	SODA LAKE NORTH	Township 13N, Range 8E, Section 3
Baker-Dunn-Siding-Coolwater	35116B1	SODA LAKE NORTH	Township 14N, Range 8E, Section 34
Baker-Dunn-Siding-Coolwater	35116B2	WEST OF SODA LAKE	Township 12N, Range 7E, Section 2
Baker-Dunn-Siding-Coolwater	35116B2	WEST OF SODA LAKE	Township 12N, Range 7E, Section 10
Baker-Dunn-Siding-Coolwater	35116B2	WEST OF SODA LAKE	Township 12N, Range 7E, Section 11
Baker-Dunn-Siding-Coolwater	35116B2	WEST OF SODA LAKE	Township 12N, Range 7E, Section 15
Baker-Dunn-Siding-Coolwater	35116B2	WEST OF SODA LAKE	Township 12N, Range 7E, Section 16
Baker-Dunn-Siding-Coolwater	35116B2	WEST OF SODA LAKE	Township 13N, Range 7E, Section 24
Baker-Dunn-Siding-Coolwater	35116B2	WEST OF SODA LAKE	Township 13N, Range 7E, Section 25
Baker-Dunn-Siding-Coolwater	35116B2	WEST OF SODA LAKE	Township 13N, Range 7E, Section 35
Baker-Dunn-Siding-Coolwater	35116B2	WEST OF SODA LAKE	Township 13N, Range 7E, Section 36

Transmission Segment Name	USGS CODE	QUAD NAME	Township, Range, Section
Baker-Dunn-Siding-Coolwater	35116B2	WEST OF SODA LAKE	Township 13N, Range 8E, Section 3
Baker-Dunn-Siding-Coolwater	35116B2	WEST OF SODA LAKE	Township 13N, Range 8E, Section 4
Baker-Dunn-Siding-Coolwater	35116B2	WEST OF SODA LAKE	Township 13N, Range 8E, Section 8
Baker-Dunn-Siding-Coolwater	35116B2	WEST OF SODA LAKE	Township 13N, Range 8E, Section 9
Baker-Dunn-Siding-Coolwater	35116B2	WEST OF SODA LAKE	Township 13N, Range 8E, Section 17
Baker-Dunn-Siding-Coolwater	35116B2	WEST OF SODA LAKE	Township 13N, Range 8E, Section 18
Baker-Dunn-Siding-Coolwater	35116B2	WEST OF SODA LAKE	Township 13N, Range 8E, Section 19
Baker-Dunn-Siding-Coolwater	35116A2	CRUCERO HILL	Township 12N, Range 7E, Section 16
Baker-Dunn-Siding-Coolwater	35116A3	CAVE MOUNTAIN	Township 11N, Range 6E, Section 4
Baker-Dunn-Siding-Coolwater	35116A3	CAVE MOUNTAIN	Township 11N, Range 6E, Section 5
Baker-Dunn-Siding-Coolwater	35116A3	CAVE MOUNTAIN	Township 11N, Range 6E, Section 8
Baker-Dunn-Siding-Coolwater	35116A3	CAVE MOUNTAIN	Township 12N, Range 6E, Section 24
Baker-Dunn-Siding-Coolwater	35116A3	CAVE MOUNTAIN	Township 12N, Range 6E, Section 25
Baker-Dunn-Siding-Coolwater	35116A3	CAVE MOUNTAIN	Township 12N, Range 6E, Section 26
Baker-Dunn-Siding-Coolwater	35116A3	CAVE MOUNTAIN	Township 12N, Range 6E, Section 33
Baker-Dunn-Siding-Coolwater	35116A3	CAVE MOUNTAIN	Township 12N, Range 6E, Section 34
Baker-Dunn-Siding-Coolwater	35116A3	CAVE MOUNTAIN	Township 12N, Range 6E, Section 35
Baker-Dunn-Siding-Coolwater	35116A3	CAVE MOUNTAIN	Township 12N, Range 7E, Section 16
Baker-Dunn-Siding-Coolwater	35116A3	CAVE MOUNTAIN	Township 12N, Range 7E, Section 17
Baker-Dunn-Siding-Coolwater	35116A3	CAVE MOUNTAIN	Township 12N, Range 7E, Section 19
Baker-Dunn-Siding-Coolwater	35116A3	CAVE MOUNTAIN	Township 12N, Range 7E, Section 20
Baker-Dunn-Siding-Coolwater	35116A4	DUNN	Township 11N, Range 5E, Section 10
Baker-Dunn-Siding-Coolwater	35116A4	DUNN	Township 11N, Range 5E, Section 11
Baker-Dunn-Siding-Coolwater	35116A4	DUNN	Township 11N, Range 5E, Section 12
Baker-Dunn-Siding-Coolwater	35116A4	DUNN	Township 11N, Range 5E, Section 15
Baker-Dunn-Siding-Coolwater	35116A4	DUNN	Township 11N, Range 5E, Section 16
Baker-Dunn-Siding-Coolwater	35116A4	DUNN	Township 11N, Range 5E, Section 19
Baker-Dunn-Siding-Coolwater	35116A4	DUNN	Township 11N, Range 5E, Section 20
Baker-Dunn-Siding-Coolwater	35116A4	DUNN	Township 11N, Range 5E, Section 21
Baker-Dunn-Siding-Coolwater	35116A4	DUNN	Township 11N, Range 6E, Section 7
Baker-Dunn-Siding-Coolwater	35116A4	DUNN	Township 11N, Range 6E, Section 8
Baker-Dunn-Siding-Coolwater	35116A5	ALVORD MTN. EAST	Township 11N, Range 4E, Section 24
Baker-Dunn-Siding-Coolwater	35116A5	ALVORD MTN. EAST	Township 11N, Range 4E, Section 25
Baker-Dunn-Siding-Coolwater	35116A5	ALVORD MTN. EAST	Township 11N, Range 4E, Section 26
Baker-Dunn-Siding-Coolwater	35116A5	ALVORD MTN. EAST	Township 11N, Range 4E, Section 27
Baker-Dunn-Siding-Coolwater	35116A5	ALVORD MTN. EAST	Township 11N, Range 4E, Section 34
Baker-Dunn-Siding-Coolwater	35116A5	ALVORD MTN. EAST	Township 11N, Range 5E, Section 19
Baker-Dunn-Siding-Coolwater	34116H5	MANIX	Township 10N, Range 3E, Section 13
Baker-Dunn-Siding-Coolwater	34116H5	MANIX	Township 10N, Range 4E, Section 3
Baker-Dunn-Siding-Coolwater	34116H5	MANIX	Township 10N, Range 4E, Section 4
Baker-Dunn-Siding-Coolwater	34116H5	MANIX	Township 10N, Range 4E, Section 7
Baker-Dunn-Siding-Coolwater	34116H5	MANIX	Township 10N, Range 4E, Section 8
Baker-Dunn-Siding-Coolwater	34116H5	MANIX	Township 10N, Range 4E, Section 9

Transmission Segment Name	USGS CODE	QUAD NAME	Township, Range, Section
Baker-Dunn-Siding-Coolwater	34116H5	MANIX	Township 10N, Range 4E, Section 18
Baker-Dunn-Siding-Coolwater	34116H5	MANIX	Township 11N, Range 4E, Section 34
Baker-Dunn-Siding-Coolwater	34116H6	HARVARD HILL	Township 10N, Range 2E, Section 34
Baker-Dunn-Siding-Coolwater	34116H6	HARVARD HILL	Township 10N, Range 2E, Section 35
Baker-Dunn-Siding-Coolwater	34116H6	HARVARD HILL	Township 10N, Range 2E, Section 36
Baker-Dunn-Siding-Coolwater	34116H6	HARVARD HILL	Township 10N, Range 3E, Section 13
Baker-Dunn-Siding-Coolwater	34116H6	HARVARD HILL	Township 10N, Range 3E, Section 14
Baker-Dunn-Siding-Coolwater	34116H6	HARVARD HILL	Township 10N, Range 3E, Section 22
Baker-Dunn-Siding-Coolwater	34116H6	HARVARD HILL	Township 10N, Range 3E, Section 23
Baker-Dunn-Siding-Coolwater	34116H6	HARVARD HILL	Township 10N, Range 3E, Section 27
Baker-Dunn-Siding-Coolwater	34116H6	HARVARD HILL	Township 10N, Range 3E, Section 28
Baker-Dunn-Siding-Coolwater	34116H6	HARVARD HILL	Township 10N, Range 3E, Section 29
Baker-Dunn-Siding-Coolwater	34116H6	HARVARD HILL	Township 10N, Range 3E, Section 30
Baker-Dunn-Siding-Coolwater	34116H6	HARVARD HILL	Township 10N, Range 3E, Section 31
Baker-Dunn-Siding-Coolwater	34116H7	YERMO	Township 9N, Range 1E, Section 10
Baker-Dunn-Siding-Coolwater	34116H7	YERMO	Township 9N, Range 1E, Section 11
Baker-Dunn-Siding-Coolwater	34116H7	YERMO	Township 9N, Range 1E, Section 12
Baker-Dunn-Siding-Coolwater	34116H7	YERMO	Township 9N, Range 1E, Section 15
Baker-Dunn-Siding-Coolwater	34116H7	YERMO	Township 9N, Range 2E, Section 3
Baker-Dunn-Siding-Coolwater	34116H7	YERMO	Township 9N, Range 2E, Section 4
Baker-Dunn-Siding-Coolwater	34116H7	YERMO	Township 9N, Range 2E, Section 5
Baker-Dunn-Siding-Coolwater	34116H7	YERMO	Township 9N, Range 2E, Section 6
Baker-Dunn-Siding-Coolwater	34116H7	YERMO	Township 9N, Range 2E, Section 7
Baker-Dunn-Siding-Coolwater	34116H7	YERMO	Township 10N, Range 2E, Section 34
Baker-Dunn-Siding-Coolwater	34116G7	MINNEOLA	Township 9N, Range 1E, Section 15
Baker-Dunn-Siding-Coolwater	34116G7	MINNEOLA	Township 9N, Range 1E, Section 22
Baker-Dunn-Siding-Coolwater	34116G7	MINNEOLA	Township 9N, Range 1E, Section 23
Ivanpah-Mtn Pass-Baker	351150000	IVANPAH LAKE	Township 16N, Range 14E, Section 4
Ivanpah-Mtn Pass-Baker	351150000	IVANPAH LAKE	Township 16N, Range 14E, Section 8
Ivanpah-Mtn Pass-Baker	351150000	IVANPAH LAKE	Township 16N, Range 14E, Section 9
Ivanpah-Mtn Pass-Baker	351150000	IVANPAH LAKE	Township 16N, Range 14E, Section 17
Ivanpah-Mtn Pass-Baker	3511500000	CLARK MTN.	Township 16N, Range 13E, Section 1
Ivanpah-Mtn Pass-Baker	3511500000	CLARK MTN.	Township 16N, Range 13E, Section 2
Ivanpah-Mtn Pass-Baker	3511500000	CLARK MTN.	Township 16N, Range 13E, Section 3
Ivanpah-Mtn Pass-Baker	3511500000	CLARK MTN.	Township 16N, Range 14E, Section 17
Ivanpah-Mtn Pass-Baker	3511500000	CLARK MTN.	Township 16N, Range 14E, Section 18
Ivanpah-Mtn Pass-Baker	35115D5	MESCAL RANGE	Township 16N, Range 13E, Section 3
Ivanpah-Mtn Pass-Baker	35115D5	MESCAL RANGE	Township 16N, Range 13E, Section 4
Ivanpah-Mtn Pass-Baker	35115D5	MESCAL RANGE	Township 16N, Range 13E, Section 7
Ivanpah-Mtn Pass-Baker	35115D5	MESCAL RANGE	Township 16N, Range 13E, Section 8
Ivanpah-Mtn Pass-Baker	35115D5	MESCAL RANGE	Township 16N, Range 13E, Section 9
Ivanpah-Mtn Pass-Baker	35115D5	MESCAL RANGE	Township 16N, Range 13E, Section 18
Ivanpah-Mtn Pass-Baker	35115D6	VALLEY WELLS	Township 16N, Range 12.5E, Section 13

Transmission Segment Name	USGS CODE	QUAD NAME	Township, Range, Section
Ivanpah-Mtn Pass-Baker	35115D6	VALLEY WELLS	Township 16N, Range 13E, Section 18
Ivanpah-Mtn Pass-Baker	35115D6	VALLEY WELLS	Township 16N, Range 11E, Section 36
Ivanpah-Mtn Pass-Baker	35115D6	VALLEY WELLS	Township 16N, Range 12E, Section 13
Ivanpah-Mtn Pass-Baker	35115D6	VALLEY WELLS	Township 16N, Range 12E, Section 22
Ivanpah-Mtn Pass-Baker	35115D6	VALLEY WELLS	Township 16N, Range 12E, Section 23
Ivanpah-Mtn Pass-Baker	35115D6	VALLEY WELLS	Township 16N, Range 12E, Section 24
Ivanpah-Mtn Pass-Baker	35115D6	VALLEY WELLS	Township 16N, Range 12E, Section 27
Ivanpah-Mtn Pass-Baker	35115D6	VALLEY WELLS	Township 16N, Range 12E, Section 28
Ivanpah-Mtn Pass-Baker	35115D6	VALLEY WELLS	Township 16N, Range 12E, Section 29
Ivanpah-Mtn Pass-Baker	35115D6	VALLEY WELLS	Township 16N, Range 12E, Section 31
Ivanpah-Mtn Pass-Baker	35115D6	VALLEY WELLS	Township 16N, Range 12E, Section 32
Ivanpah-Mtn Pass-Baker	35115D7	SOLOMONS KNOB	Township 15N, Range 11E, Section 1
Ivanpah-Mtn Pass-Baker	35115D7	SOLOMONS KNOB	Township 15N, Range 11E, Section 2
Ivanpah-Mtn Pass-Baker	35115D7	SOLOMONS KNOB	Township 15N, Range 11E, Section 3
Ivanpah-Mtn Pass-Baker	35115D7	SOLOMONS KNOB	Township 15N, Range 11E, Section 8
Ivanpah-Mtn Pass-Baker	35115D7	SOLOMONS KNOB	Township 15N, Range 11E, Section 9
Ivanpah-Mtn Pass-Baker	35115D7	SOLOMONS KNOB	Township 15N, Range 11E, Section 10
Ivanpah-Mtn Pass-Baker	35115D7	SOLOMONS KNOB	Township 15N, Range 11E, Section 17
Ivanpah-Mtn Pass-Baker	35115D7	SOLOMONS KNOB	Township 15N, Range 11E, Section 18
Ivanpah-Mtn Pass-Baker	35115D7	SOLOMONS KNOB	Township 16N, Range 11E, Section 36
Ivanpah-Mtn Pass-Baker	35115D7	SOLOMONS KNOB	Township 15N, Range 10E, Section 13
Ivanpah-Mtn Pass-Baker	35115D8	TURQUOISE MTN.	Township 15N, Range 10E, Section 13
Ivanpah-Mtn Pass-Baker	35115D8	TURQUOISE MTN.	Township 15N, Range 10E, Section 14
Ivanpah-Mtn Pass-Baker	35115D8	TURQUOISE MTN.	Township 15N, Range 10E, Section 22
Ivanpah-Mtn Pass-Baker	35115D8	TURQUOISE MTN.	Township 15N, Range 10E, Section 23
Ivanpah-Mtn Pass-Baker	35115C8	HALLORAN SPRINGS	Township 14N, Range 9E, Section 1
Ivanpah-Mtn Pass-Baker	35115C8	HALLORAN SPRINGS	Township 14N, Range 9E, Section 2
Ivanpah-Mtn Pass-Baker	35115C8	HALLORAN SPRINGS	Township 14N, Range 9E, Section 11
Ivanpah-Mtn Pass-Baker	35115C8	HALLORAN SPRINGS	Township 15N, Range 9E, Section 36
Ivanpah-Mtn Pass-Baker	35115C8	HALLORAN SPRINGS	Township 15N, Range 10E, Section 21
Ivanpah-Mtn Pass-Baker	35115C8	HALLORAN SPRINGS	Township 15N, Range 10E, Section 22
Ivanpah-Mtn Pass-Baker	35115C8	HALLORAN SPRINGS	Township 15N, Range 10E, Section 28
Ivanpah-Mtn Pass-Baker	35115C8	HALLORAN SPRINGS	Township 15N, Range 10E, Section 29
Ivanpah-Mtn Pass-Baker	35115C8	HALLORAN SPRINGS	Township 15N, Range 10E, Section 31
Ivanpah-Mtn Pass-Baker	35115C8	HALLORAN SPRINGS	Township 15N, Range 10E, Section 32
Ivanpah-Mtn Pass-Baker	35116C1	BAKER	Township 14N, Range 9E, Section 9
Ivanpah-Mtn Pass-Baker	35116C1	BAKER	Township 14N, Range 9E, Section 10
Ivanpah-Mtn Pass-Baker	35116C1	BAKER	Township 14N, Range 9E, Section 11
Ivanpah-Mtn Pass-Baker	35116C1	BAKER	Township 14N, Range 9E, Section 16
Ivanpah-Mtn Pass-Baker	35116C1	BAKER	Township 14N, Range 9E, Section 17
Ivanpah-Mtn Pass-Baker	35116C1	BAKER	Township 14N, Range 9E, Section 19
Ivanpah-Mtn Pass-Baker	35116C1	BAKER	Township 14N, Range 9E, Section 20
Control-Haiwee-Inyokern	37118C3	POLETA CANYON	Township 8S, Range 33E, Section 8

Transmission Segment Name	USGS CODE	QUAD NAME	Township, Range, Section
Control-Haiwee-Inyokern	37118C3	POLETA CANYON	Township 8S, Range 33E, Section 9
Control-Haiwee-Inyokern	37118C3	POLETA CANYON	Township 8S, Range 33E, Section 16
Control-Haiwee-Inyokern	37118C4	BISHOP	Township 7S, Range 32E, Section 16
Control-Haiwee-Inyokern	37118C4	BISHOP	Township 7S, Range 32E, Section 17
Control-Haiwee-Inyokern	37118C4	BISHOP	Township 7S, Range 32E, Section 21
Control-Haiwee-Inyokern	37118C4	BISHOP	Township 7S, Range 32E, Section 22
Control-Haiwee-Inyokern	37118C4	BISHOP	Township 7S, Range 32E, Section 23
Control-Haiwee-Inyokern	37118C4	BISHOP	Township 7S, Range 32E, Section 24
Control-Haiwee-Inyokern	37118C4	BISHOP	Township 7S, Range 32E, Section 25
Control-Haiwee-Inyokern	37118C4	BISHOP	Township 7S, Range 33E, Section 30
Control-Haiwee-Inyokern	37118C4	BISHOP	Township 7S, Range 33E, Section 31
Control-Haiwee-Inyokern	37118C4	BISHOP	Township 7S, Range 33E, Section 32
Control-Haiwee-Inyokern	37118C4	BISHOP	Township 8S, Range 33E, Section 5
Control-Haiwee-Inyokern	37118C4	BISHOP	Township 8S, Range 33E, Section 8
Control-Haiwee-Inyokern	37118B3	BIG PINE	Township 9S, Range 33E, Section 1
Control-Haiwee-Inyokern	37118B3	BIG PINE	Township 9S, Range 33E, Section 2
Control-Haiwee-Inyokern	37118B3	BIG PINE	Township 9S, Range 33E, Section 12
Control-Haiwee-Inyokern	37118B3	BIG PINE	Township 9S, Range 33E, Section 13
Control-Haiwee-Inyokern	37118B3	BIG PINE	Township 8S, Range 33E, Section 16
Control-Haiwee-Inyokern	37118B3	BIG PINE	Township 8S, Range 33E, Section 21
Control-Haiwee-Inyokern	37118B3	BIG PINE	Township 8S, Range 33E, Section 22
Control-Haiwee-Inyokern	37118B3	BIG PINE	Township 8S, Range 33E, Section 27
Control-Haiwee-Inyokern	37118B3	BIG PINE	Township 8S, Range 33E, Section 34
Control-Haiwee-Inyokern	37118B3	BIG PINE	Township 8S, Range 33E, Section 35
Control-Haiwee-Inyokern	37118B3	BIG PINE	Township 9S, Range 34E, Section 18
Control-Haiwee-Inyokern	37118B3	BIG PINE	Township 9S, Range 34E, Section 19
Control-Haiwee-Inyokern	37118B3	BIG PINE	Township 9S, Range 34E, Section 29
Control-Haiwee-Inyokern	37118B3	BIG PINE	Township 9S, Range 34E, Section 30
Control-Haiwee-Inyokern	37118B3	BIG PINE	Township 9S, Range 34E, Section 32
Control-Haiwee-Inyokern	37118A2	TINEMAHA RESERVOIR	Township 10S, Range 34E, Section 22
Control-Haiwee-Inyokern	37118A2	TINEMAHA RESERVOIR	Township 10S, Range 34E, Section 26
Control-Haiwee-Inyokern	37118A2	TINEMAHA RESERVOIR	Township 10S, Range 34E, Section 27
Control-Haiwee-Inyokern	37118A2	TINEMAHA RESERVOIR	Township 10S, Range 34E, Section 35
Control-Haiwee-Inyokern	37118A2	TINEMAHA RESERVOIR	Township 11S, Range 34E, Section 2
Control-Haiwee-Inyokern	37118A2	TINEMAHA RESERVOIR	Township 11S, Range 34E, Section 11
Control-Haiwee-Inyokern	37118A2	TINEMAHA RESERVOIR	Township 11S, Range 34E, Section 12
Control-Haiwee-Inyokern	37118A2	TINEMAHA RESERVOIR	Township 11S, Range 34E, Section 13
Control-Haiwee-Inyokern	37118A3	FISH SPRINGS	Township 10S, Range 34E, Section 4
Control-Haiwee-Inyokern	37118A3	FISH SPRINGS	Township 10S, Range 34E, Section 9
Control-Haiwee-Inyokern	37118A3	FISH SPRINGS	Township 10S, Range 34E, Section 15
Control-Haiwee-Inyokern	37118A3	FISH SPRINGS	Township 10S, Range 34E, Section 16
Control-Haiwee-Inyokern	37118A3	FISH SPRINGS	Township 10S, Range 34E, Section 22
Control-Haiwee-Inyokern	37118A3	FISH SPRINGS	Township 9S, Range 34E, Section 32

Transmission Segment Name	USGS CODE	QUAD NAME	Township, Range, Section
Control-Haiwee-Inyokern	37118A3	FISH SPRINGS	Township 9S, Range 34E, Section 33
Control-Haiwee-Inyokern	36118H2	BLACKROCK	Township 11S, Range 34E, Section 13
Control-Haiwee-Inyokern	36118H2	BLACKROCK	Township 11S, Range 34E, Section 24
Control-Haiwee-Inyokern	36118H2	BLACKROCK	Township 11S, Range 34E, Section 25
Control-Haiwee-Inyokern	36118H2	BLACKROCK	Township 11S, Range 34E, Section 36
Control-Haiwee-Inyokern	36118H2	BLACKROCK	Township 12S, Range 35E, Section 6
Control-Haiwee-Inyokern	36118H2	BLACKROCK	Township 12S, Range 35E, Section 7
Control-Haiwee-Inyokern	36118H2	BLACKROCK	Township 12S, Range 35E, Section 18
Control-Haiwee-Inyokern	36118H2	BLACKROCK	Township 12S, Range 35E, Section 19
Control-Haiwee-Inyokern	36118H2	BLACKROCK	Township 12S, Range 35E, Section 20
Control-Haiwee-Inyokern	36118H2	BLACKROCK	Township 12S, Range 35E, Section 29
Control-Haiwee-Inyokern	36118H2	BLACKROCK	Township 11S, Range 35E, Section 31
Control-Haiwee-Inyokern	36118G2	INDEPENDENCE	Township 14S, Range 35E, Section 2
Control-Haiwee-Inyokern	36118G2	INDEPENDENCE	Township 13S, Range 35E, Section 3
Control-Haiwee-Inyokern	36118G2	INDEPENDENCE	Township 13S, Range 35E, Section 4
Control-Haiwee-Inyokern	36118G2	INDEPENDENCE	Township 13S, Range 35E, Section 10
Control-Haiwee-Inyokern	36118G2	INDEPENDENCE	Township 13S, Range 35E, Section 15
Control-Haiwee-Inyokern	36118G2	INDEPENDENCE	Township 13S, Range 35E, Section 22
Control-Haiwee-Inyokern	36118G2	INDEPENDENCE	Township 13S, Range 35E, Section 23
Control-Haiwee-Inyokern	36118G2	INDEPENDENCE	Township 13S, Range 35E, Section 26
Control-Haiwee-Inyokern	36118G2	INDEPENDENCE	Township 13S, Range 35E, Section 35
Control-Haiwee-Inyokern	36118G2	INDEPENDENCE	Township 12S, Range 35E, Section 29
Control-Haiwee-Inyokern	36118G2	INDEPENDENCE	Township 12S, Range 35E, Section 32
Control-Haiwee-Inyokern	36118F1	UNION WASH	Township 14S, Range 35E, Section 13
Control-Haiwee-Inyokern	36118F1	UNION WASH	Township 14S, Range 35E, Section 24
Control-Haiwee-Inyokern	36118F1	UNION WASH	Township 14S, Range 36E, Section 19
Control-Haiwee-Inyokern	36118F1	UNION WASH	Township 14S, Range 36E, Section 30
Control-Haiwee-Inyokern	36118F1	UNION WASH	Township 14S, Range 36E, Section 31
Control-Haiwee-Inyokern	36118F1	UNION WASH	Township 15S, Range 36E, Section 5
Control-Haiwee-Inyokern	36118F1	UNION WASH	Township 15S, Range 36E, Section 6
Control-Haiwee-Inyokern	36118F1	UNION WASH	Township 15S, Range 36E, Section 8
Control-Haiwee-Inyokern	36118F1	UNION WASH	Township 15S, Range 36E, Section 16
Control-Haiwee-Inyokern	36118F1	UNION WASH	Township 15S, Range 36E, Section 17
Control-Haiwee-Inyokern	36118F2	MANZANAR	Township 14S, Range 35E, Section 2
Control-Haiwee-Inyokern	36118F2	MANZANAR	Township 14S, Range 35E, Section 11
Control-Haiwee-Inyokern	36118F2	MANZANAR	Township 14S, Range 35E, Section 12
Control-Haiwee-Inyokern	36118F2	MANZANAR	Township 14S, Range 35E, Section 13
Control-Haiwee-Inyokern	361180	LONE PINE	Township 16S, Range 36E, Section 2
Control-Haiwee-Inyokern	361180	LONE PINE	Township 16S, Range 36E, Section 11
Control-Haiwee-Inyokern	361180	LONE PINE	Township 16S, Range 36E, Section 14
Control-Haiwee-Inyokern	361180	LONE PINE	Township 16S, Range 36E, Section 23
Control-Haiwee-Inyokern	361180	LONE PINE	Township 16S, Range 36E, Section 26
Control-Haiwee-Inyokern	361180	LONE PINE	Township 16S, Range 36E, Section 35

Transmission Segment Name	USGS CODE	QUAD NAME	Township, Range, Section
Control-Haiwee-Inyokern	361180	LONE PINE	Township 15S, Range 36E, Section 15
Control-Haiwee-Inyokern	361180	LONE PINE	Township 15S, Range 36E, Section 16
Control-Haiwee-Inyokern	361180	LONE PINE	Township 15S, Range 36E, Section 22
Control-Haiwee-Inyokern	361180	LONE PINE	Township 15S, Range 36E, Section 27
Control-Haiwee-Inyokern	361180	LONE PINE	Township 15S, Range 36E, Section 34
Control-Haiwee-Inyokern	361180	LONE PINE	Township 15S, Range 36E, Section 35
Control-Haiwee-Inyokern	36118D1	BARTLETT	Township 18S, Range 36E, Section 1
Control-Haiwee-Inyokern	36118D1	BARTLETT	Township 18S, Range 36E, Section 12
Control-Haiwee-Inyokern	36118D1	BARTLETT	Township 18S, Range 36E, Section 13
Control-Haiwee-Inyokern	36118D1	BARTLETT	Township 16S, Range 36E, Section 35
Control-Haiwee-Inyokern	36118D1	BARTLETT	Township 17S, Range 36E, Section 1
Control-Haiwee-Inyokern	36118D1	BARTLETT	Township 17S, Range 36E, Section 11
Control-Haiwee-Inyokern	36118D1	BARTLETT	Township 17S, Range 36E, Section 12
Control-Haiwee-Inyokern	36118D1	BARTLETT	Township 17S, Range 36E, Section 13
Control-Haiwee-Inyokern	36118D1	BARTLETT	Township 17S, Range 36E, Section 14
Control-Haiwee-Inyokern	36118D1	BARTLETT	Township 17S, Range 36E, Section 24
Control-Haiwee-Inyokern	36118D1	BARTLETT	Township 17S, Range 36E, Section 25
Control-Haiwee-Inyokern	36118D1	BARTLETT	Township 17S, Range 36E, Section 36
Control-Haiwee-Inyokern	36117C8	VERMILLION CANYON	Township 19S, Range 37E, Section 8
Control-Haiwee-Inyokern	36117C8	VERMILLION CANYON	Township 19S, Range 37E, Section 17
Control-Haiwee-Inyokern	36117C8	VERMILLION CANYON	Township 19S, Range 37E, Section 20
Control-Haiwee-Inyokern	36117C8	VERMILLION CANYON	Township 19S, Range 37E, Section 28
Control-Haiwee-Inyokern	36117C8	VERMILLION CANYON	Township 19S, Range 37E, Section 29
Control-Haiwee-Inyokern	36118C1	OLANCHA	Township 18S, Range 36E, Section 13
Control-Haiwee-Inyokern	36118C1	OLANCHA	Township 18S, Range 36E, Section 24
Control-Haiwee-Inyokern	36118C1	OLANCHA	Township 18S, Range 36E, Section 25
Control-Haiwee-Inyokern	36118C1	OLANCHA	Township 18S, Range 36E, Section 36
Control-Haiwee-Inyokern	36118C1	OLANCHA	Township 19S, Range 37E, Section 7
Control-Haiwee-Inyokern	36118C1	OLANCHA	Township 19S, Range 37E, Section 8
Control-Haiwee-Inyokern	36117B8	HAIWEE RESERVOIRS	Township 19S, Range 37E, Section 28
Control-Haiwee-Inyokern	36117B8	HAIWEE RESERVOIRS	Township 19S, Range 37E, Section 33
Control-Haiwee-Inyokern	36117B8	HAIWEE RESERVOIRS	Township 20S, Range 37E, Section 4
Control-Haiwee-Inyokern	36117B8	HAIWEE RESERVOIRS	Township 20S, Range 37E, Section 9
Control-Haiwee-Inyokern	36117B8	HAIWEE RESERVOIRS	Township 20S, Range 37E, Section 16
Control-Haiwee-Inyokern	36117B8	HAIWEE RESERVOIRS	Township 20S, Range 37E, Section 21
Control-Haiwee-Inyokern	36117B8	HAIWEE RESERVOIRS	Township 20S, Range 37E, Section 22
Control-Haiwee-Inyokern	36117B8	HAIWEE RESERVOIRS	Township 20S, Range 37E, Section 27
Control-Haiwee-Inyokern	36117B8	HAIWEE RESERVOIRS	Township 20S, Range 37E, Section 34
Control-Haiwee-Inyokern	36117B8	HAIWEE RESERVOIRS	Township 21S, Range 37E, Section 2
Control-Haiwee-Inyokern	36117B8	HAIWEE RESERVOIRS	Township 21S, Range 37E, Section 11
Control-Haiwee-Inyokern	36117A8	COSO JUNCTION	Township 21S, Range 37E, Section 11
Control-Haiwee-Inyokern	36117A8	COSO JUNCTION	Township 21S, Range 37E, Section 14
Control-Haiwee-Inyokern	36117A8	COSO JUNCTION	Township 21S, Range 37E, Section 23

Transmission Segment Name	USGS CODE	QUAD NAME	Township, Range, Section
Control-Haiwee-Inyokern	36117A8	COSO JUNCTION	Township 21S, Range 37E, Section 26
Control-Haiwee-Inyokern	36117A8	COSO JUNCTION	Township 21S, Range 37E, Section 35
Control-Haiwee-Inyokern	36117A8	COSO JUNCTION	Township 21S, Range 37E, Section 36
Control-Haiwee-Inyokern	36117A8	COSO JUNCTION	Township 22S, Range 37E, Section 1
Control-Haiwee-Inyokern	36117A8	COSO JUNCTION	Township 22S, Range 37E, Section 12
Control-Haiwee-Inyokern	36117A8	COSO JUNCTION	Township 22S, Range 37E, Section 13
Control-Haiwee-Inyokern	36117A8	COSO JUNCTION	Township 22S, Range 37E, Section 24
Control-Haiwee-Inyokern	35117H8	LITTLE LAKE	Township 22S, Range 37E, Section 24
Control-Haiwee-Inyokern	35117H8	LITTLE LAKE	Township 22S, Range 37E, Section 25
Control-Haiwee-Inyokern	35117H8	LITTLE LAKE	Township 22S, Range 38E, Section 30
Control-Haiwee-Inyokern	35117H8	LITTLE LAKE	Township 22S, Range 38E, Section 31
Control-Haiwee-Inyokern	35117H8	LITTLE LAKE	Township 23S, Range 38E, Section 6
Control-Haiwee-Inyokern	35117H8	LITTLE LAKE	Township 23S, Range 38E, Section 7
Control-Haiwee-Inyokern	35117H8	LITTLE LAKE	Township 23S, Range 38E, Section 8
Control-Haiwee-Inyokern	35117H8	LITTLE LAKE	Township 23S, Range 38E, Section 17
Control-Haiwee-Inyokern	35117H8	LITTLE LAKE	Township 23S, Range 38E, Section 20
Control-Haiwee-Inyokern	35117H8	LITTLE LAKE	Township 23S, Range 38E, Section 29
Control-Haiwee-Inyokern	35117H8	LITTLE LAKE	Township 23S, Range 38E, Section 32
Control-Haiwee-Inyokern	35117H8	LITTLE LAKE	Township 23S, Range 38E, Section 33
Control-Haiwee-Inyokern	35117H8	LITTLE LAKE	Township 24S, Range 38E, Section 4
Control-Haiwee-Inyokern	35117G7	PEARSONVILLE	Township 25S, Range 38E, Section 1
Control-Haiwee-Inyokern	35117G7	PEARSONVILLE	Township 25S, Range 38E, Section 2
Control-Haiwee-Inyokern	35117G7	PEARSONVILLE	Township 25S, Range 38E, Section 12
Control-Haiwee-Inyokern	35117G7	PEARSONVILLE	Township 25S, Range 38E, Section 13
Control-Haiwee-Inyokern	35117G7	PEARSONVILLE	Township 25S, Range 38E, Section 24
Control-Haiwee-Inyokern	35117G7	PEARSONVILLE	Township 24S, Range 38E, Section 9
Control-Haiwee-Inyokern	35117G7	PEARSONVILLE	Township 24S, Range 38E, Section 15
Control-Haiwee-Inyokern	35117G7	PEARSONVILLE	Township 24S, Range 38E, Section 16
Control-Haiwee-Inyokern	35117G7	PEARSONVILLE	Township 24S, Range 38E, Section 22
Control-Haiwee-Inyokern	35117G7	PEARSONVILLE	Township 24S, Range 38E, Section 27
Control-Haiwee-Inyokern	35117G7	PEARSONVILLE	Township 24S, Range 38E, Section 34
Control-Haiwee-Inyokern	35117G7	PEARSONVILLE	Township 24S, Range 38E, Section 35
Control-Haiwee-Inyokern	35117G8	NINEMILE CANYON	Township 24S, Range 38E, Section 4
Control-Haiwee-Inyokern	35117G8	NINEMILE CANYON	Township 24S, Range 38E, Section 9
Control-Haiwee-Inyokern	35117F7	INYOKERN	Township 26S, Range 39E, Section 5
Control-Haiwee-Inyokern	35117F7	INYOKERN	Township 26S, Range 39E, Section 6
Control-Haiwee-Inyokern	35117F7	INYOKERN	Township 26S, Range 39E, Section 8
Control-Haiwee-Inyokern	35117F7	INYOKERN	Township 26S, Range 39E, Section 17
Control-Haiwee-Inyokern	35117F7	INYOKERN	Township 26S, Range 39E, Section 20
Control-Haiwee-Inyokern	35117F7	INYOKERN	Township 25S, Range 38E, Section 24
Control-Haiwee-Inyokern	35117F7	INYOKERN	Township 25S, Range 39E, Section 19
Control-Haiwee-Inyokern	35117F7	INYOKERN	Township 25S, Range 39E, Section 30
Control-Haiwee-Inyokern	35117F7	INYOKERN	Township 25S, Range 39E, Section 31

Transmission Segment Name	USGS CODE	QUAD NAME	Township, Range, Section
Randsburg-Inyokern	35117F7	INYOKERN	Township 26S, Range 39E, Section 20
Randsburg-Inyokern	35117F7	INYOKERN	Township 26S, Range 39E, Section 28
Randsburg-Inyokern	35117F7	INYOKERN	Township 26S, Range 39E, Section 29
Randsburg-Inyokern	35117F7	INYOKERN	Township 26S, Range 39E, Section 33
Randsburg-Inyokern	35117000000	RIDGECREST SOUTH	Township 28S, Range 39E, Section 2
Randsburg-Inyokern	35117000000	RIDGECREST SOUTH	Township 28S, Range 39E, Section 11
Randsburg-Inyokern	35117000000	RIDGECREST SOUTH	Township 28S, Range 39E, Section 13
Randsburg-Inyokern	35117000000	RIDGECREST SOUTH	Township 28S, Range 39E, Section 14
Randsburg-Inyokern	3.5117E+11	INYOKERN SE	Township 26S, Range 39E, Section 33
Randsburg-Inyokern	3.5117E+11	INYOKERN SE	Township 27S, Range 39E, Section 4
Randsburg-Inyokern	3.5117E+11	INYOKERN SE	Township 27S, Range 39E, Section 9
Randsburg-Inyokern	3.5117E+11	INYOKERN SE	Township 27S, Range 39E, Section 10
Randsburg-Inyokern	3.5117E+11	INYOKERN SE	Township 27S, Range 39E, Section 15
Randsburg-Inyokern	3.5117E+11	INYOKERN SE	Township 27S, Range 39E, Section 22
Randsburg-Inyokern	3.5117E+11	INYOKERN SE	Township 27S, Range 39E, Section 26
Randsburg-Inyokern	3.5117E+11	INYOKERN SE	Township 27S, Range 39E, Section 27
Randsburg-Inyokern	3.5117E+11	INYOKERN SE	Township 27S, Range 39E, Section 35
Randsburg-Inyokern	3.5117E+11	INYOKERN SE	Township 28S, Range 39E, Section 2
Randsburg-Inyokern	35117D6	EL PASO PEAKS	Township 28S, Range 39E, Section 13
Randsburg-Inyokern	35117D6	EL PASO PEAKS	Township 28S, Range 39E, Section 24
Randsburg-Inyokern	35117D6	EL PASO PEAKS	Township 28S, Range 39E, Section 25
Randsburg-Inyokern	35117D6	EL PASO PEAKS	Township 28S, Range 39E, Section 36
Randsburg-Inyokern	35117D6	EL PASO PEAKS	Township 28S, Range 40E, Section 31
Randsburg-Inyokern	35117D6	EL PASO PEAKS	Township 28.5S, Range 40E, Section 32
Randsburg-Inyokern	35117D6	EL PASO PEAKS	Township 29S, Range 40E, Section 5
Randsburg-Inyokern	35117D6	EL PASO PEAKS	Township 29S, Range 40E, Section 8
Randsburg-Inyokern	35117D6	EL PASO PEAKS	Township 29S, Range 40E, Section 9
Randsburg-Inyokern	35117D6	EL PASO PEAKS	Township 29S, Range 40E, Section 15
Randsburg-Inyokern	35117D6	EL PASO PEAKS	Township 29S, Range 40E, Section 16
Randsburg-Inyokern	35117D6	EL PASO PEAKS	Township 29S, Range 40E, Section 22
Randsburg-Inyokern	35117D6	EL PASO PEAKS	Township 29S, Range 40E, Section 26
Randsburg-Inyokern	35117D6	EL PASO PEAKS	Township 29S, Range 40E, Section 27
Randsburg-Inyokern	35117D6	EL PASO PEAKS	Township 29S, Range 40E, Section 35
Randsburg-Inyokern	35117C6	JOHANNESBURG	Township 29S, Range 40E, Section 35
Randsburg-Inyokern	35117C6	JOHANNESBURG	Township 29S, Range 40E, Section 36
Baker-Dunn-Siding-Coolwater	35116B2	WEST OF SODA LAKE	Township 13N, Range 7E, Section 2
Baker-Dunn-Siding-Coolwater	35116B2	WEST OF SODA LAKE	Township 13N, Range 7E, Section 35
Control-Haiwee-Inyokern	36117A8	COSO JUNCTION	Township 21S, Range 37E, Section 36
Control-Haiwee-Inyokern	36117A8	COSO JUNCTION	Township 21S, Range 37E, Section 1
Control-Haiwee-Inyokern	36117A8	COSO JUNCTION	Township 22S, Range 37E, Section 36
Control-Haiwee-Inyokern	36117A8	COSO JUNCTION	Township 22S, Range 37E, Section 1

NATIVE AMERICAN HERITAGE COMMISSION
Cultural and Environmental Department
1550 Harbor Blvd., Suite 100
West Sacramento, CA 95691 Phone: (916) 373-3710
Email: nahc@nahc.ca.gov
Website: http://www.nahc.ca.gov

December 3, 2018

Billie Blanchard
California Public Utilities Commission

VIA Email to: billie.blanchard@cpuc.ca.gov

RE: Native American Tribal Consultation, Pursuant to the Assembly Bill 52 (AB 52), Amendments to the California Environmental Quality Act (CEQA) (Chapter 532, Statutes of 2014), Public Resources
- Code Sections 5097.94 (m), 21073, 21074, 21080.3.1, 21080.3.2, 21082.3, 21083.09, 21084.2 and 21084.3, Ivanpah-Control Project, Kern, Inyo and San Bernardino Counties.

Dear Ms. Blanchard:

Pursuant to Public Resources Code section 21080.3.1 (c), attached is a consultation list of tribes that are traditionally and culturally affiliated with the geographic area of the above-listed project. Please note that the intent of the AB 52 amendments to CEQA is to avoid and/or mitigate impacts to tribal cultural resources, (Pub. Resources Code §21084.3 (a)) ("Public agencies shall, when feasible, avoid damaging effects to any tribal cultural resource.")

Public Resources Code sections 21080.3.1 and 21084.3(c) require CEQA lead agencies to consult with California Native American tribes that have requested notice from such agencies of proposed projects in the geographic area that are traditionally and culturally affiliated with the tribes on projects for which a Notice of Preparation or Notice of Negative Declaration or Mitigated Negative Declaration has been filed on or after July 1, 2015. Specifically, Public Resources Code section 21080.3.1 (d) provides:

> Within 14 days of determining that an application for a project is complete or a decision by a public agency to undertake a project, the lead agency shall provide formal notification to the designated contact of, or a tribal representative of, traditionally and culturally affiliated California Native American tribes that have requested notice, which shall be accomplished by means of at least one written notification that includes a brief description of the proposed project and its location, the lead agency contact information, and a notification that the California Native American tribe has 30 days to request consultation pursuant to this section. (Public Resources Code §21080.3.1(d))

The AB 52 amendments to CEQA law does not preclude initiating consultation with the tribes that are culturally and traditionally affiliated within your jurisdiction prior to receiving requests for notification of projects in the tribe's areas of traditional and cultural affiliation. The Native American Heritage Commission (NAHC) recommends, but does not require, early consultation as a best practice to ensure that lead agencies receive sufficient information about cultural resources in a project area to avoid damaging effects to tribal cultural resources.

In accordance with Public Resources Code section 21080.3.1 (d), formal notification must include a brief description of the proposed project and its location, the lead agency contact information, and a notification that the California Native American tribe has 30 days to request consultation. The NAHC also recommends, but does not require that agencies should also include with their notification letters,

information regarding any cultural resources assessment that has been completed on the Area of Potential Effect (APE), such as:

1. The results of any record search that may have been conducted at an Information Center of the California Historical Resources Information System (CHRIS), including, but not limited to:

   - A listing of any and all known cultural resources that have already been recorded or are adjacent to the APE, such as known archaeological sites;

   - Copies of any and all cultural resource records and study reports that may have been provided by the Information Center as part of the records search response;

   - Whether the records search indicates a low, moderate, or high probability that unrecorded cultural resources are located in the APE; and

   - If a survey is recommended by the Information Center to determine whether previously unrecorded cultural resources are present.

2. The results of any archaeological inventory survey that was conducted, including:

   - Any report that may contain site forms, site significance, and suggested mitigation measures.

     All information regarding site locations, Native American human remains, and associated funerary objects should be in a separate confidential addendum, and not be made available for public disclosure in accordance with Government Code section 6254.10.

3. The result of the Sacred Lands File (SLF) check conducted through the Native American Heritage Commission was positive. Please contact the Kern Valley Indian Community and the Lone Pine Paiute-Shoshone Tribe on the attached list for more information.

4. Any ethnographic studies conducted for any area including all or part of the potential APE; and

5. Any geotechnical reports regarding all or part of the potential APE.

Lead agencies should be aware that records maintained by the NAHC and CHRIS are not exhaustive or conclusive as to the presence of resources that may be tribal cultural resources. A negative response to these searches does not preclude the existence of a tribal cultural resource. A tribe may be the only source of information regarding the existence of a tribal cultural resource.

This information will aid tribes in determining whether to request formal consultation. In the event that they do, having the information beforehand will help to facilitate the consultation process.

If you receive notification of change of addresses and phone numbers from tribes, please notify the NAHC. With your assistance, we are able to assure that our consultation list remains current.

If you have any questions, please contact me at my email address: katy.sanchez@nahc.ca.gov.

Sincerely,

Katy Sanchez

KATY SANCHEZ
Associate Environmental Planner

Native American Heritage Commission
Tribal Consultation List
12/3//2018

Big Pine Paiute Tribe of the Owens Valley
Genevieve Jones, Chairperson
P.O. Box 700 — Paiute - Shoshone
Big Pine , CA 93513
j.paydon@bigpinepaiute.org
(760) 938-2003

Big Pine Paiute Tribe of Owens Valley
Sally Manning, Environmental Director
P.O. Box 700 — Paiute
Big Pine , CA 93513
s.manning@bigpinepaiute.org
(760) 938-2003

Big Pine Paiute Tribe of the Owens Valley
Danelle Gutierrez THPO
P.O. Box 700 — Paiute
Big Pine , CA 93513
d.gutierrez@bigpinepaiute.org
(760) 938-2003, ext. 228

Bishop Paiute Tribe
Bill Vega, Chairperson
50 Tu Su Lane — Paiute - Shoshone
Bishop , CA 93514
deston.rogers@bishoppaiute.o
(760) 873-3584

Bishop Paiute Tribe
Raymond Andrews, THPO
50 Tu Su Lane — Paiute - Shoshone
Bishop , CA 93514
(760) 920-0357 Cell
(760) 873-8435 ext 250

Death Valley Timbi-sha Shoshone Tribe
George Gholoson, Chairperson
P. O. Box 1779 / 1349 Rocking — Western Shoshone
Bishop , CA 93515/ 9
george@timbisha.com
(760) 872-3614

Fort Independence Indian Community of Paiutes
Norman Wilder, Chairman
P.O. Box 67 — Paiute
Independence , CA 93526
businesscommittee@fortindependence.c
(760) 878-5160
(760) 878-8065

Kern Valley Indian Community
Julie Turner, Secretary
P.O. Box 1010 — Kawaiisu
Lake Isabella , CA 93240 — Tubatulabal
(661) 340-0032 Cell

Kern Valley Indian Community
Robert Robinson, Chairperson
P.O. Box 1010 — Tubatulabal
Lake Isabella , CA 93283 — Kawaiisu
brobinson@iwvisp.com
(760) 378-2915 Cell

Lone Pine Paiute-Shoshone Tribe
Mary Wuester, Chairwoman
P.O. Box 747
Lone Pine , CA 93545 — Paiute
Shoshone
(760) 876-1034

This list is current only as of the date of this document and is based on the information available to the Commission on the date it was produced.

Distribution of this list does not relieve any person of statutory responsibility as defined in Section 7050.5 of the Health and Safety Code, Section 50 97.94 of the Public Resources Code and Section 5097.98 of the Public Resources Code.

This list is applicable only for consultation with Native American tribes under Public Resources Code Sections 21080.1, 21080.3.1, and 21080.3.2 for Ivanpah-Control Project, Inyo County.

Native American Heritage Commission
Tribal Consultation List
12/3//2018

Walker River Reservation
Melanie McFalls. Chairperson
P.O. Box 220
Schurz , NV 89427
(775) 773-2306

Northern Paiute

This list is current only as of the date of this document and is based on the information available to the Commission on the date it was produced.

Distribution of this list does not relieve any person of statutory responsibility as defined in Section 7050.5 of the Health and Safety Code, Section 50 97.94 of the Public Resources Code and Section 5097.98 of the Public Resources Code.

This list is applicable only for consultation with Native American tribes under Public Resources Code Sections 21080.1, 21080.3.1, and 21080.3.2 for Ivanpah-Control Project, Inyo County.

Native American Heritage Commission
Tribal Consultation List
12/3//2018

Big Pine Paiute Tribe of the Owens Valley
Genevieve Jones, Chairperson
P.O. Box 700 Paiute - Shoshone
Big Pine , CA 93513
j.paydon@bigpinepaiute.org
(760) 938-2003

Big Pine Paiute Tribe of Owens Valley
Sally Manning, Environmental Director
P.O. Box 700 Paiute
Big Pine , CA 93513
s.manning@bigpinepaiute.org
(760) 938-2003

Big Pine Paiute Tribe of the Owens Valley
Danelle Gutierrez THPO
P.O. Box 700 Paiute
Big Pine , CA 93513
d.gutierrez@bigpinepaiute.org
(760) 938-2003, ext. 228

Kern Valley Indian Community
Julie Turner, Secretary
P.O. Box 1010 Kawaiisu
Lake Isabella , CA 93240 Tubatulabal
(661) 340-0032 Cell

Kern Valley Indian Community
Robert Robinson, Chairperson
P.O. Box 1010 Tubatulabal
Lake Isabella , CA 93283 Kawaiisu
brobinson@iwvisp.com
(760) 378-2915 Cell

This list is current only as of the date of this document and is based on the information available to the Commission on the date it was produced.

Distribution of this list does not relieve any person of statutory responsibility as defined in Section 7050.5 of the Health and Safety Code, Section 50 97.94 of the Public Resources Code and Section 5097.98 of the Public Resources Code.

This list is applicable only for consultation with Native American tribes under Public Resources Code Sections 21080.1, 21080.3.1, and 21080.3.2 for Ivanpah-Control Project, Kern County.

Native American Heritage Commission
Tribal Consultation List
12/3//2018

Big Pine Paiute Tribe of the Owens Valley
Genevieve Jones, Chairperson
P.O. Box 700 Paiute - Shoshone
Big Pine , CA 93513
j.paydon@bigpinepaiute.org
(760) 938-2003

Big Pine Paiute Tribe of Owens Valley
Sally Manning, Environmental Director
P.O. Box 700 Paiute
Big Pine , CA 93513
s.manning@bigpinepaiute.org
(760) 938-2003

Big Pine Paiute Tribe of the Owens Valley
Danelle Gutierrez THPO
P.O. Box 700 Paiute
Big Pine , CA 93513
d.gutierrez@bigpinepaiute.org
(760) 938-2003, ext. 228

Kern Valley Indian Community
Robert Robinson, Chairperson
P.O. Box 1010 Tubatulabal
Lake Isabella , CA 93283 Kawaiisu
brobinson@iwvisp.com
(760) 378-2915 Cell

This list is current only as of the date of this document and is based on the information available to the Commission on the date it was produced.

Distribution of this list does not relieve any person of statutory responsibility as defined in Section 7050.5 of the Health and Safety Code, Section 50 97.94 of the Public Resources Code and Section 5097.98 of the Public Resources Code.

This list is applicable only for consultation with Native American tribes under Public Resources Code Sections 21080.1, 21080.3.1, and 21080.3.2 for Ivanpah-Control Project, San Bernardino County.

Part 3:

ASSEMBLY BILL 52 NOTIFICATION LETTERS

Appendix 5A presents data related to EIR Section 3.6, Cultural Resources. This appendix contains the following information related to EIR Section 3.7, Tribal Cultural Resources:

- Assembly Bill 52 Notification Letters
  - Request for Pre-Filing Input (2018)
  - Pre-Filing Outreach (2018)
  - AB 52 Pre-Consultation Notice (2019)
  - Formal Project Notification (2020)
  - Initiation of AB 52 Consultation (2020)
  - Invitation to Attend AB 52 Meeting (2023)
  - Project Status Update (2024)

The notices provided in this Appendix are examples of the notices provided to all tribes; the notices sent to the Big Pine Paiute Tribe of the Owens Valley are the same as those sent to the other tribes.

The following Tribes received only the Request for Pre-filing Input (2018) and did move forward with consultation:

- Agua Caliente Band of Cahuilla Indians
- Bridgeport Indian Colony
- Cabazon Band of Mission Indians
- Chemehuevi Tribe
- Gabrieleno Band of Mission Indians
- Mission Creek Band of Mission Indians
- Pala Band of Mission Indians
- Pechanga Band of Luiseno Indians
- Rincon band of Luiseno Indians
- Santa Ysabel Band of the Iipay Nation
- Serrano Nation of Mission Indians
- Susanville Indian Rancheria
- Tongva Ancestral Territorial Tribal Nation
- Torres Martinez Desert Cahuilla Indians
- Walker River Reservation

The following Tribes received all notices:

- Big Pine Paiute Tribe of the Owens Valley
- Bishop Paiute Tribe
- Cocopah Indian Tribe
- Colorado River Indian Tribes
- Fernandeño Tataviam Band of Mission Indians
- Fort Mojave Indian Tribe
- Fort Independence Band of Paiute Indians
- Kern Valley Indian Community
- Lone Pine Paiute-Shoshone Tribe
- Mono Lake Kutzadika Tribe
- Morongo Band of Mission Indians
- Quechan Tribe of the Fort Yuma Reservation
- San Fernando Band of Mission Indians
- San Manuel Band of Mission Indians
- Tejon Indian Tribe
- Timbisha Shoshone Tribe
- Tubatulabals of Kern Valley
- Twenty-Nine Palms Band of Mission Indians

PUBLIC UTILITIES COMMISSION
505 VAN NESS AVENUE
SAN FRANCISCO, CA 94102-3298

December 14, 2018

Genevieve Jones, Chairperson
Big Pine Paiute Tribe of the Owens Valley
PO Box 700
Big Pine, CA 93513

Re: Request for Pre-Filing Input for Proposed SCE Ivanpah-Control Project

Dear Ms. Jones,

I am Billie Blanchard, project manager for the proposed Southern California Edison (SCE) Ivanpah-Control (IC) Project that is under the jurisdiction of the California Public Utilities Commission (CPUC). The proposed project will be undergoing review under the California Environmental Quality Act (CEQA) in the spring of 2019, and we will initiate consultation under Assembly Bill (AB) 52 at that time.

SCE is proposing to rebuild portions of its 115-kilovolt electric transmission system in Inyo, San Bernardino, and Kern Counties in order to ensure reliable electric service. A map of the IC Project area is shown in Attachment A. The transmission system that would be affected in the Ivanpah-Control Project extends over 350 miles, from eastern San Bernardino County, through the northeastern corner of Kern County, and into Inyo County. A Fact Sheet describing the IC Project is also enclosed.

In advance of SCE's formal application filing with the CPUC, the CPUC is in a "pre-filing process," in which we review preliminary SCE project information and reach out to potentially interested parties, including Native American tribes. The CPUC, as the future lead agency under CEQA, is contacting Native American tribes traditionally and culturally affiliated with the proposed project's geographic area.

No cultural resources surveys have been completed to date, so there is currently no project resource data that we can share. The attached Fact Sheet provides a description of the project. More detailed maps can be made available upon request.

Request for Pre-Filing Comments

I am your main point of contact for this project. If you have any comments or concerns regarding potential impacts to tribal cultural resources (as defined in Public Resources Code § 21074) in relation to the proposed project, or would like to request any additional information, please contact me at Billie.Blanchard@cpuc.ca.gov or (916) 823-4799, copying also our consultant project manager, Susan Lee at SLee@AspenEG.com. You may also mail correspondence to me at the address below; however, emailing is the most expeditious method of communicating and provides an opportunity for me to respond immediately.

Future Consultation

Formal consultation regarding the IC Project will be initiated in the spring of 2019. At that time, the CPUC will contact all Native American tribes who have requested formal notification of projects pursuant to Public Resources Code (PRC) Section 21080.3.1(b) or are on the Native American Heritage Commission (NAHC) tribal contact list for formal Native American consultation from NAHC as requested by the CPUC for best practices compliance.

We note that from the NAHC list and the list provided to us by Inyo County, there are multiple names for the Big Pine Paiute Tribe of the Owens Valley: Jill Paydon (Tribal Administrator), Danielle Guiterrez (THP), and Sally Manning (Environmental Director). Please confirm whether we should continue to reach out to you, as well as to the other three named members listed above.

The Big Pine Paiute Tribe of the Owens Valley is on the NAHC list for the project area, so unless you inform us that you have no interest in this project, we will invite you to formal consultation in the spring of 2019. However, we note that, at this time, the Tribe has not submitted a request to the CPUC to be consulted under PRC Section 210803.1(b). If you are interested in getting on the CPUC's consultation list, please submit a request to the CPUC's Tribal Liaison.

Stephanie Green is the CPUC Tribal Liaison. Ms. Green is copied here and is available to you for this and all other CPUC tribal matters. Ms. Green can be reached at 415-703-5245 and Stephanie.Green@cpuc.ca.gov.

Sincerely,

Billie Blanchard

Billie Blanchard
CPUC Project Manager
California Public Utilities Commission
300 Capitol Mall, 4th Floor Room 4-21
Sacramento, CA 95814

cc: Stephanie Green, CPUC Tribal Liaison
Lonn Maier, CPUC Program and Project Supervisor
Susan Lee, Aspen Environmental Group
Beth Bagwell, Aspen Environmental Group

Attachments:

- Proposed Project Overview Map
- Fact Sheet



SCE Ivanpah-Control Project

From: Susan Lee
Sent: Sunday, December 16, 2018 12:12 PM
To: g.jones@bigpinepaiute.org; d.guiterrez@bigpinepaiute.org; j.paydon@bigpinepaiute.org; s.manning@bigpinepaiute.org
Cc: Blanchard, Billie C.; Beth Bagwell; Teresa O'Grady
Subject: CPUC Pre-Filing Outreach regarding proposed Southern California Edison Project
Attachments: Big Pine Paiute (Inyo) Jones.pdf; Big Pine Paiute (NAHC) Guiterrez.pdf; Big Pine Paiute (NAHC) Manning.pdf; Big Pine Paiute (NAHC) Paydon.pdf; Fact Sheet SCE Ivanpah-Control.pdf

Dear Ms. Jones, Mr. Guiterrez, Ms. Paydon, and Ms. Manning,

On behalf of Billie Blanchard of the California Public Utilities Commission, the Big Pine Paiute Tribe of the Owens Valley is invited to provide preliminary comments on an electric transmission upgrade project proposed by the Southern California Edison (SCE) company.

The SCE project is called the Ivanpah-Control Project, and it is described in the attached letter and Fact Sheet. These documents have also been sent to you via U.S. Mail. The CPUC is reviewing the project in a "pre-filing" process, and the formal application is expected in the spring of 2019. At that time, the CPUC will initiate formal consultation under AB 52. At this time, we would appreciate hearing about any preliminary comments or concerns that you have about the SCE Ivanpah-Control Project.

Thank you very much for your review of this information. If you have questions about the project or the CPUC's process, please feel free to contact me or CPUC Project Manager Billie Blanchard at Billie.Blanchard@cpuc.ca.gov.

Sincerely,
Susan V. Lee

Aspen environmental group

Susan V. Lee
Vice President
www.aspeneg.com

Aspen Environmental Group
235 Montgomery Street, Suite 935
San Francisco CA 94104
Office: (415) 696-5311
Cell: (415) 290-4984

PUBLIC UTILITIES COMMISSION

505 VAN NESS AVENUE
SAN FRANCISCO, CA 94102-3298

October 22, 2019

Ms. Genevieve Jones, Chairperson
Big Pine Paiute Tribe of the Owens Valley
PO Box 700
Big Pine, CA 93513

Subject: California Public Utilities Commission Southern California Edison Ivanpah-Control (I-C) Project Permit to Construct Application (A.19-07-015) and Second AB 52 Pre-Consultation Notice

Dear Ms. Jones:

The California Public Utilities Commission (CPUC) has received an application from Southern California Edison (SCE) for a Permit to Construct (PTC) the proposed Ivanpah – Control (I-C) Project (project) (CPUC Application A.19-07-015).

The CPUC has identified deficiencies in the application, including lack of cultural resource survey reports, and has not deemed the application complete. The CPUC will be the lead agency responsible for environmental review of the project in compliance with the California Environmental Quality Act (CEQA). The Bureau of Land Management (BLM) will be the lead agency under the National Environmental Policy Act (NEPA); the BLM will prepare a separate Environmental Impact Statement (EIS) and will comply with Section 106 of the National Historic Preservation Act.

The CPUC will formally initiate consultation with interested tribes under Assembly Bill (AB) 52 within 14 days of deeming the I-C application complete. The CPUC will not deem the application complete until the cultural resources surveys of project areas are completed, and SCE submits a cultural resources survey report(s) that meets CPUC's requirements. Evaluation of archaeological, historical, and tribal cultural resources may continue after the application is deemed complete.

In advance of deeming the I-C application complete and the CPUC's formal AB 52 consultation with interested tribes, the CPUC is reaching out to tribes identified on the Native American Heritage Commission (NAHC) list who may have knowledge of tribal cultural resources in or near the proposed project alignment. The CPUC previously sent a letter to you about the I-C project during the "pre-filing" process (December 2018). In the previous letter, the CPUC provided a Fact Sheet on the project and requested comments on the project.

This letter provides an overview of the proposed project location, requests information you can share about tribal cultural resources in the proposed project area, and provides information about how to participate in the CPUC's formal AB 52 tribal consultation process once the I-C application is deemed complete.

Project Location

SCE is proposing to rebuild segments of its existing 115-kilovolt electric transmission system in Inyo, San Bernardino, and Kern Counties in order to ensure reliable electric service within this portion of their service area. A map of the proposed project alignment is provided in Attachment A. Additional details on the project location, including SCE's proposed work areas, is available upon request. The transmission system that would be affected by the proposed project extends over 350 miles from eastern San Bernardino County, through the northeastern corner of Kern County, and into Inyo County.

Pre-Consultation During CPUC I-C Application Deficiency Review Period

Big Pine Paiute Tribe of the Owens Valley is on the NAHC list for the project area, indicating that members of your Tribe may have knowledge of tribal cultural resources within the project. The CPUC is interested in speaking with any representative of your Tribe that has knowledge of tribal cultural resources within the proposed project area so that the CPUC may define potential tribal cultural resources within the project area and begin evaluating impacts on those resources within the context of CEQA. There will be additional opportunity to share information and provide comments on tribal cultural resource impacts and mitigation during the formal AB 52 process; however, we would like to start the discussion in advance of formal AB 52 consultation to provide additional time for Tribes to comment and share information with the CPUC.

Formal Consultation

Unless you inform us that you have no interest in the project, we will invite you to participate in AB 52 formal consultation when we initiate consultation for this project. We note that Big Pine Paiute Tribe of the Owens Valley has not submitted a request to the CPUC to be considered under PRC Section 21080.3.1. If you would like to be included in the formal AB 52 tribal consultation efforts for I-C and possibly other CPUC projects, please submit a written request specifying the geographic area of tribal affiliation to the CPUC's Tribal Liaison, Stephanie Green and copy Billie Blanchard, using the contact information provided below:

Stephanie Green, CPUC Tribal Liaison
stephanie.green@cpuc.ca.gov
(415) 703-5245

Billie Blanchard, CPUC Senior Project Manager
billie.blanchard@cpuc.ca.gov
(916) 823-4799

Ms. Green is copied here and is available to you for this and all other CPUC tribal matters.

To provide information on tribal cultural resources within the project area, or request additional information about the project, please contact me at Billie.Blanchard@cpuc.ca.gov or (916) 823-4799.

Sincerely,

Billie Blanchard

Billie Blanchard
CPUC Senior Project Manager for the I-C Project

cc: Stephanie Green, CPUC Tribal Liaison
Lonn Maier, CPUC Program and Project Supervisor
Susan Lee, Aspen Environmental Group
Susanne Heim, Panorama Environmental
Jim Allan and Beth Bagwell, Aspen Environmental Group
Mark Giambastiani, G2 Archaeology
Mark Mackiewicz, BLM National Project Manager
Scott Whiteside, BLM National Project Manager
Tiffany Arend, BLM Archaeologist

Attachment: Project Location Map

Attachment 1: SCE Ivanpah – Control Project



This page is intentionally left blank.

STATE OF CALIFORNIA Gavin Newsom, Governor

PUBLIC UTILITIES COMMISSION
505 VAN NESS AVENUE
SAN FRANCISCO, CA 94102-3298

August 26, 2020

Danelle Gutierrez, THPO
Big Pine Paiute Tribe of the Owens Valley
P.O. Box 700
Big Pine, CA 93513

Re: ***California Environmental Quality Act Public Resources Code section 21080.3.1(b) pursuant to California Assembly Bill 52, Formal Notification of Proposed Southern California Edison Ivanpah-Control Project***

Dear Ms. Gutierrez,

I am John Forsythe, California Public Utilities Commission (CPUC) project manager for the proposed Southern California Edison (SCE) Ivanpah-Control (I-C) Project (project.) This project is under the jurisdiction of the CPUC, the lead agency responsible for environmental review of the project in compliance with the California Environmental Quality Act (CEQA). Pursuant to California Assembly Bill (AB) 52, the CPUC is providing you with formal notification of the project, located within Inyo, Kern, and San Bernardino County, California. As you may recall, the CPUC previously provided the Big Pine Paiute Tribe of the Owens Valley with a pre-consultation notice in late 2018, and in response you requested AB 52 consultation for the project. This notification formally starts the AB 52 process. The present notice includes:

- A description of the proposed project and location;
- A clear and definitive statement that the tribe has 60 days to make the previous request for consultation official (following California Executive Order N-54-20);
- The lead agency contact information; and
- A map of the project area.

The Bureau of Land Management (BLM) will be the lead agency under the National Environmental Policy Act (NEPA); the BLM will prepare a separate Environmental Impact Statement (EIS) and will be responsible for compliance with Section 106 of the National Historic Preservation Act.

Project Background and AB 52 Consultation Schedule

SCE filed an initial application with the CPUC on July 17, 2019 and an amended application on April 13, 2020 for a Permit to Construct (Application A.19-07-015) the project. The CPUC is currently reviewing the application and supporting materials provided by SCE, including the Proponent's Environmental Assessment (PEA) and has requested that SCE prepare additional application materials that are required before the CPUC can deem the application complete, including cultural resource reports. The CPUC anticipates that SCE's application will be deemed complete by early 2021; however, this schedule is subject to change.

Starting in late 2018, the CPUC issued multiple pre-consultation notices and held initial meetings with Native America tribes prior to and during the application review process in an effort to begin establishing communication with tribes that may be interested in formal AB 52 consulting, sharing information about the project, and requesting information about tribal concerns and cultural resources.

The CPUC has decided to initiate the formal AB 52 consultation process with interested tribes rather than waiting until the project application is deemed complete. The earlier start to AB 52 consultation is intended to accommodate tribal requests for early consultation, extend the formal consultation phase, and provide assurance that all information about tribal cultural resources shared between Native Americans and the CPUC will be treated confidentially under the scope of AB 52. All information obtained from Native Americans to date has been managed consistent with AB 52 requirements.

The CPUC will begin public scoping for the project in September 2020. Tribal representatives that receive this letter will also receive a copy of the Notice of Preparation (NOP) and are invited to participate in public scoping in addition to formal AB 52 consultation.

Project Description and Location

SCE is proposing to rebuild segments of its existing 115-kilovolt electric transmission system in Inyo, San Bernardino, and Kern Counties in order to ensure reliable electric service within this portion of their service area. The transmission system that would be affected by the proposed project extends over 350 miles. A map of the proposed project alignment is provided in **Attachment A**. The project corridor traverses residential, commercial, agricultural, recreation, and open space land uses.

The proposed project involves transmission system upgrades along five segments, summarized as follows:

- **Segment 1: Control Substation (Bishop) to Inyokern Substation.** The 126-mile project segment includes 111 miles located in Inyo County and 15 miles in Kern County. Approximately 1,161 electrical transmission structures (poles) would be removed and approximately 905 new structures would be installed.
- **Segment 2: Inyokern Substation to Kramer Junction.** The 48-mile project segment is in Kern and San Bernardino Counties; it includes removal of approximately 390 electrical transmission structures, and installation of approximately 342 electrical transmission structures.
- **Segments 3N and 3S: Kramer Junction-Coolwater Substation (East of Barstow).** Segment 3N is a 44-mile route segment that connects the two substations in a route that passes north of Barstow. Segment 3S connects the same two substations, but the line is located south of Barstow. Upgrades in these segments include removal and replacement of approximately 43 transmission structures in Segment 3N and approximately 42 structures in Segment 3S. As part of the SCE's deteriorated pole program, SCE will replace nearly 400 poles prior to the start of construction of the Ivanpah-Control Project.
- **Segment 4: Coolwater Substation (East of Barstow) to Ivanpah Substation (near Primm, Nevada).** This 96-mile project segment runs east from Barstow ending just west of the California-Nevada border. It includes removal of approximately 60 existing transmission structures, installation of approximately 62 transmission structures, and modification of approximately another 83 existing structures.

In all segments except Segment 4, the project would include removal of the existing conductor and installation of new high capacity conductor. In certain segments, this change would increase the capacity of the line allowing the line to carry or distribute more power. The project would also include installation of marker balls on overhead wires where determined to be appropriate, and the installation of fiber optic cable. Generally, replacement structures will not be placed in the same location as the removed structures.

Additional information about the project is available in SCE's application and supporting materials provided on the project website:
https://www.cpuc.ca.gov/Environment/info/aspen/ivanpah-control/ivanpah-control.htm

Consultation Request

I (John Forsythe) am the CPUC project manager for this project. Given the size of the project and the number of interested parties involved, the CPUC has enlisted the support of Elizabeth A. Bagwell, PhD, RPA, Senior Cultural Resources Specialist at Aspen Environmental Group (Aspen). Dr. Bagwell will be serving as the point of contact for AB 52 consultation and will be an official representative of the CPUC in these efforts. Dr. Bagwell is assisted in the AB 52 consultation process by her associates at PaleoWest, including Evan Tudor Elliott, James Potter, and Vanessa Mirro. Together, these cultural resources specialists will be officially representing the CPUC in the consultation with tribes.

The CPUC understands that the Big Pine Paiute Tribe of the Owens Valley has been engaged in informal consultation and has requested inclusion in the AB 52 consultation process. To formalize that request, please send an official request within 60 days of receipt of this notice, following the spirit of the AB 52 extension in Executive Order N-54-20. This formal request can be sent to john.forsythe@cpuc.ca.gov and/or bbagwell@aspeneg.com, or can be mailed to the CPUC address below.

If you have any comments or concerns regarding potential impacts to tribal cultural resources (as defined in Public Resources Code § 21074) in relation to the project, or would like to request any additional information, please contact Dr. Bagwell by email at bbagwell@aspeneg.com or at (916) 926-2736, and/or contact me by email at john.forsythe@cpuc.ca.gov or at (916) 217-5073. You may also mail correspondence to me at the address below, however emailing is the most expeditious method of communicating, and provides an opportunity for expeditious response.

Sincerely,

John Forsythe, CPUC Project Manager
California Public Utilities Commission
505 Van Ness Avenue
San Francisco, CA, 94102-3298

cc: Christine Root, CPUC Program and Project Supervisor
Beth Bagwell, Aspen Environmental Group
Susan Lee, Aspen Environmental Group
Susanne Heim, Panorama Environmental, Inc.

Attachments:

- Attachment A: Proposed Project Overview Map

Attachment A: Proposed Project Overview Map



PUBLIC UTILITIES COMMISSION
505 VAN NESS AVENUE
SAN FRANCISCO, CA 94102-3298

October 1, 2020

Danelle Gutierrez, THPO
Big Pine Paiute Tribe of the Owens Valley
P.O. Box 700
Big Pine, CA 93513

Dear THPO Gutierrez,

On September 28, 2020, the California Public Utilities Commission (CPUC) received a written request from you, stating that the Big Pine Paiute Tribe of the Owens Valley would like to consult with the CPUC regarding the identification of Tribal Cultural Resources and any potential impacts to those resources associated with Southern California Edison's (SCE) proposed Ivanpah-Control Project. The CPUC is interested in working with you to identify any places or resources that your tribe feels are significant, regardless of whether they were identified in an archaeological survey.

In accordance with Assembly Bill 52 (AB 52) and Section 21080.3.1(e) of the California Public Resources Code, we are hereby initiating consultation with Big Pine Paiute Tribe of the Owens Valley.

On March 5, 2020, you and CPUC representatives had a pre-consultation meeting to discuss the project and the CPUC's role as lead agency for the California Environmental Quality Act (CEQA) process. We would like to invite you to a second meeting to continue the discussion and provide you with updates about the project. Given the safety concerns associated with Covid-19 we propose this next meeting be conducted as a Zoom video/telephone conference, which the CPUC is happy to host. In the future, we are open to face-to-face meetings or site visits if all parties feel comfortable and are in agreement about appropriate safety precautions.

Summary of Cultural Resources ork and Documentation
SCE is proposing to rebuild and upgrade portions of a 358-mile transmission system in Inyo, San Bernardino, and Kern Counties. The upgrades will take place in the following segments:

- Segment 1: Control Substation (Bishop) to Inyokern Substation
- Segment 2: Inyokern Substation to Kramer Junction
- Segments 3N and 3S: Kramer Junction-Coolwater Substation (East of Barstow)
- Segment 4: Coolwater Substation (East of Barstow) to Ivanpah Substation (near Primm, Nevada)

A 9,455-acre study area for potential direct impacts on cultural resources and tribal cultural resources has been identified for the project. The study area is identical for the CPUC's CEQA

analysis and the Bureau of Land Management's (BLM) National Environmental Policy Act (NEPA)/Section 106 analysis. A series of reports to identify the resources that the project might impact are being prepared. These reports include a record search, a geoarchaeological study, an archaeological inventory, and a built-environment inventory. The record search has been finalized. Draft reports presenting the results of the fieldwork and the geoarchaeological study have been prepared and are currently undergoing agency review.

The preliminary results of the archaeological inventory indicate there are 824 archaeological resources that could be impacted by ground disturbing activities associated with the project. These results are presented by project segment in Table 1, below. Also, refer to the attached figure for the location of the segments noted below. The CPUC intends to avoid impacts to archaeological and tribal cultural resources as much as possible.

able 1: Archaeological Resources by Segment

Segment	Prehistoric	Historic-Era	Multi-Component	Total
Segment 1	74	95	182	351
Segment 2	1	104	3	108
Segment 3N	6	32	2	40
Segment 3S	10	132	5	147
Segment 4	36	111	31	178
Project Total	**127**	**474**	**223**	**824**

When the archeological and cultural resources reports are finalized, we will let you know. As these reports include cultural resources located on federal land as well as state owned and private land the confidentiality concerns of all parties needs to be addressed. Therefore we have established one point of contact for the distribution of these reports through BLM Archaeologist Adam Gutierrez by email apgutierrez@blm.gov or at (951) 697-5322. Reports that include California Department of Parks and Recreation Forms (DPR forms) and maps showing resource locations can be obtained after signing a project specific Data Sharing Agreement with BLM. Please contact Mr. Gutierrez if you have any questions or would like to request a BLM data sharing agreement.

As the CPUC project manager, I am the official AB 52 point of contact for this project. Given the size of the project and the number of interested parties involved, the CPUC has enlisted the support of Elizabeth A. Bagwell, PhD, RPA, Senior Cultural Resources Specialist at Aspen Environmental Group (Aspen). Dr. Bagwell will be serving as the primary point of contact for AB 52 consultation and will be an official representative of the CPUC in these efforts. Dr. Bagwell is assisted in the AB 52 consultation process by her associates at PaleoWest, including Evan Tudor Elliott, James Potter, and Vanessa Mirro. Together, these cultural resources specialists will be officially representing the CPUC in AB 52 consultation with tribes.

If you have any questions please contact Dr. Bagwell by email at bbagwell@aspeneg.com or at (916) 926-2736, and/or contact me by email at john.forsythe@cpuc.ca.gov or at (916) 217-5073. You may also mail correspondence to me at the address below, however emailing or calling are the best ways to reach us.

We look forward to scheduling a meeting, discussing an appropriate meeting agenda, and identifying appropriate participants.

Respectfully,

John Forsythe, CPUC Project Manager
California Public Utilities Commission
505 Van Ness Avenue
San Francisco, CA, 94102-3298

cc: Christine Root, CPUC Program and Project Supervisor
Beth Bagwell, Aspen Environmental Group
Susan Lee, Aspen Environmental Group
Susanne Heim, Panorama Environmental, Inc.

Attachments:

- Attachment A: Proposed Project Overview Map

Attachment A: Proposed Project Overview Map



Gmail

Sara Sloan <sara.sloan@panoramaenv.com>

SCE Ivanpah-Control Project – Invitation to Attend an In-Person AB 52 Meeting with CPUC on January 8th and 9th to Provide a Status Update and Discuss Resource Mitigation

Beth Bagwell <Bbagwell@aspeneg.com> Tue, Dec 26, 2023 at 10:20 AM
To: "d.gutierrez@bigpinepaiute.org" <d.gutierrez@bigpinepaiute.org>
Cc: Aaron Lui <Ivanpah-Control-AB52@panoramaenv.com>, "Forsythe, John" <John.Forsythe@cpuc.ca.gov>, Diana Dyste <ddyste@pinonheritage.com>

THPO Gutierrez,

The California Public Utilities Commission (CPUC) is reaching out to give you an update about the cultural resources studies for Southern California Edison's (SCE) Ivanpah-Control Transmission Line Rebuild Project (project), which is being reviewed under CEQA by the CPUC. SCE's proposed project is to rebuild and upgrade portions of a 358-mile transmission-line system between Bishop and Kramer Junction, then from Kramer Junction to Barstow to Ivanpah.

The CPUC is in the process of making *determinations of eligibility for the CRHR, identifying impacts, and considering possible mitigation (such as avoidance or monitoring).* We would really appreciate tribal input on all of these topics. The BLM is going through a similar process as part of Section 106.

We would like to invite you to an in-person AB 52 meeting with CPUC representatives Beth Bagwell and Diana Dyste in Barstow on January 8th or in Ridgecrest on January 9th to provide you with project updates and get any input you would like to share. Details are provided below. ***Lunch will be provided.***

MEETING DETAILS:

January 8, 2024 - Barstow, CA (12:30 pm to 2:30 pm)

(BLM meeting is in the morning at the BLM Field Office, see separate correspondence from BLM for more details).

CPUC Meeting from 12:30 pm to 2:30 pm

Barstow Community College – Room L-04 LRC Conference Room

2700 Barstow Rd, Barstow, CA 92311

Lunch will be provided- Bean Burritos, Sandwiches, Coffee/Tea, Soda, Water

January 9, 2024 - Ridgecrest, CA (Noon to 2 pm)

(BLM meeting is in the afternoon following the CPUC meeting, to be hosted at the BLM Field Office. See separate correspondence from BLM for more details).

CPUC meeting from Noon to 2 pm

Maturango Museum – Coso Room

100 E. Las Flores Avenue, Ridgecrest, CA 93555

Lunch will be provided- Bean Burritos, Sandwiches, Coffee/Tea, Soda, Water

Meeting Agenda

- Introductions/Opening
- Brief summary of project
- Brief summary of 3 alternatives in Owens Valley
- Resource types and numbers in project area
- CPUC resource summary table and discussion
- Interactive map of ethnographic literature, project area, and survey results
- Open discussion – site visits, monitoring, etc.
- Closing

Brief summary of the Project (see map on page 4)

- SCE proposes to rebuild and upgrade portions of a 358-mile transmission-line system
- Includes a 6,500-acre Area of Potential Effect (APE)/Area of Potential Impact (API) in Inyo, San Bernardino, and Kern Counties
- The project begins just west of Bishop and extends south along Hwy 395 to Kramer Junction, then east to Barstow, and northeast along Interstate 15 to the Nevada border
- There are 282 archaeological resources that may be of interest to tribes
- The Owens Valley along Hwy 395 has the highest density of sensitive resources and potential construction impacts
- The segment east of Kramer Junction and along the Interstate 15 corridor would have the least extensive construction and has fewer resources.

All of the cultural resources reports for the main project area are complete. The reports for the alternatives are still in progress.

We look forward to hearing from you.

Regards,

Beth Bagwell

Elizabeth A. Bagwell, PhD, RPA

Senior Cultural Resources Specialist and CPUC Designee for AB 52

bbagwell@aspeneg.com

Office/Cell: 916-926-2736

2 attachments

Fact Sheet Ivanpah-Control Project 2023 DecRev.pdf
763K

IC CPUC update Dec 2023.pdf
1242K

PUBLIC UTILITIES COMMISSION
505 VAN NESS AVENUE
SAN FRANCISCO, CA 94102-3298

October 14, 2024

Ms. Danelle Gutierrez, Tribal Historic Preservation Officer
Big Pine Paiute Tribe of the Owens Valley
P.O. Box 700
Big Pine, CA 93513

Re: SCE Ivanpah Control Project
Invitation to Attend In-person or Virtual AB 52 Meetings with the CPUC in October 2024 to Provide a Project Status Update and Discuss Resource Mitigation

Dear Ms. Danelle Gutierrez,

On behalf of the California Public Utilities Commission (CPUC), I am reaching out to give you an update about the cultural resources studies for Southern California Edison's (SCE) Ivanpah-Control Transmission Line Rebuild Project (project), which is being reviewed under CEQA by the CPUC.

Since we last met in January 2024 for a project status update, a few minor changes have occurred to project components. Also, Segment 4 has been removed from this project and may be evaluated as a separate project in the future. Figure 1 attached shows the route of the project as now proposed.

A summary of the project is included below:

- SCE proposes to rebuild and upgrade portions of a 262-mile transmission-line system.
- The study area includes an approximately 6,000-acre Area of Potential Effects (APE)/Area of Potential Impacts (API) in Inyo, San Bernardino, and Kern Counties.
- The project begins just west of Bishop and extends south along Hwy 395 to Kramer Junction, then east to the Coolwater Substation near Barstow.
- The Owens Valley along Hwy 395 has the highest density of sensitive resources and potential construction impacts.
- In the Owens Valley, three route alternatives have been proposed (Crater Mountain, Fossil Falls, and Manzanar). Each alternative would move a segment of the proposed route to another location, adjacent to existing transmission lines (See Figure 2 through Figure 4; Table 2).
- There are 268 archaeological resources along the proposed project corridor (Table 1) and 244 archaeological resources in the alternative corridors (Table 2) that may be of interest to tribes. There are 244 total resources along Segment 1 and 244 different resources that might be impacted if all 3 alternative segments are implemented.
- A comparison of alternatives is still in process.

All of the cultural resources reports for the proposed project are complete. The reports for the alternatives are complete and undergoing agency review.

The CPUC is in the process of *making determinations of eligibility for the CRHR, identifying impacts, and considering possible mitigation (such as avoidance or monitoring).* We would appreciate tribal input on these topics.

INVITATION TO MEETINGS, October 2024

During AB 52 meetings, the CPUC representative will provide a table listing all cultural resources with precontact components. The table presents the following information:

- All construction disturbance areas, including each of the existing or new towers proposed to be constructed or removed and all other work areas within the resource boundaries
- A brief description of each resource, the results of independent CPUC desktop ethnohistoric research focused on historic maps, preliminary eligibility findings based on archaeological information, and examples of potential mitigation measures that could apply

During the meeting, a visual aid—either a Google Earth image or a PDF—showing the resource boundaries and project components for the main route and alternative routes will be available for viewing with the CPUC. Requests for copies of project cultural resources reports must be submitted to the Bureau of Land Management. Confidential versions of the reports including DPR 523 resource record forms will be available after signing a data sharing agreement with BLM. However, the CPUC can provide copies of any DPR 523 resource record forms for resources located on private land or state-owned land, upon request.

Please contact me if you have any questions.

Sincerely,

Elizabeth A. Bagwell, PhD, RPA
CPUC Designee for AB 52
Senior Cultural Resources Specialist
Piñon Heritage Solutions
Email: bbagwell@pinonheritage.com
Cell/Office Phone: (916) 926-2736

CC: John Forsythe, Senior Project Manager at CPUC
Stephanie Green, CPUC Tribal Liaison
Susan Lee, Aspen Environmental Group

Aaron Lui, Panorama Environmental

Attachments: Summary tables, Project map, Alternatives maps

Table 1: Summary of Archaeological Survey Findings – Main Project

	1		1	105
Segment 3N	6	32	2	40
Segment 3S	10	45	5	60
Total	**94**	294	**174**	562

Table 2: Summary of Archaeological Survey Findings for Alternatives

Alternative Name	Acreage Surveyed	Precontact Site Quantity	Historic-Era Site Quantity	Multi-component Site Quantity
Crater Mountain	678	49	7	9
Manzanar	1,449	84	9	21
Fossil Falls	756	73	6	8
Total	2,883	**206**	22	**38**

Appendix 6

GEOLOGY, SOILS, AND PALEONTOLOGY

This appendix presents the following tables:

- Table Ap.6-1. Geologic Units Underlying the Proposed Project
- Table Ap.6-2. DWR Groundwater Basins and Subsidence Potential
- Table Ap.6-3. Significant Active and Potentially Active Faults in the Vicinity of the Proposed Project
- Table Ap.6-4. Significant Historic Earthquakes from 1900-2023 within 50 miles of the Proposed Project
- Table Ap.6-5. Select Characteristics of Soils Underlying Segment 1 of the Proposed Project
- Table Ap.6-6. Select Characteristics of Soils Underlying Segment 2 of the Proposed Project
- Table Ap.6-7. Select Characteristics of Soils Underlying Segment 3N of the Proposed Project
- Table Ap.6-8. Select Characteristics of Soils Underlying Segment 3S of the Proposed Project

Table Ap.6-1. Geologic Units Underlying the Proposed Project

Geologic Unit/ Formation	Age	Project Location	Description
Qw – wash deposits	Recent	Segments 3S and 3N	Alluvial deposits occurring in modern washes of rivers and streams, may include some older wash deposits.
Qs - dune sand	Recent	Segment 3S	Windblown sand, local dunes
Qal - alluvium	Recent-Holocene	Segments 1 and 2; Control, Haiwee, and Inyokern Substations	Segment 1, Control, Haiwee, and Inyokern Substations: Alluvium, alluvial fan deposits, and colluvium. Locally may include pumice tuff-breccia, playa and lakebed deposits, talus, slope wash, flood-plain deposits, and glacial outwash. May include dissected alluvium of Pleistocene age in some areas. Segment 2: Alluvial fan deposits; includes dissected alluvium of probable Pleistocene age in some areas. Segment 3, Kramer Substation: alluvium and alluvial fan deposits.
Q - alluvium	Holocene to Pleistocene	Segments 2, 3N, and 3S; Kramer, Tortilla, and Coolwater Substations	Unconsolidated, poorly sorted stream, fan, and basin deposits. Sediment ranges from clay to boulder size.
Ql - lake deposits	Quaternary	Segments 1 and 3N	Segment 1: Fine sand, silt, and clay of lacustrine and fluviatile deposits of Owens Valley/Owens Lake. Segment 3N: Clay, silt, and fine sand; minor evaporite lenses; in part interbedded with alluvium.
Qo – older alluvium	Pleistocene	Segments 3N and 3S	Older dissected alluvial deposits.
Qod – well dissected alluvial fans	Pleistocene	Segment 3S	Well to very well dissected alluvial fan deposits.
Qc – nonmarine sedimentary deposits	Pleistocene	Segments 1 and 2	Segment 1: Mapped as Friant Formation on Mariposa 250K sheet. Older alluvium locally includes gravel, sand, clay, volcanic ash, pumice fragments, dissected alluvium terraces and terrace gravels, and interbedded continental stream and lake deposits. May include lake deposits of ancient Waucobi Lake in Bishop area. Segment 2: Older dissected alluvium and terrace gravels.
Qpv^{b} – basaltic volcanic rocks	Pleistocene	Segment 1	Basalt and basaltic-andesite flows of the Coso Range, some basalt flows may be late Tertiary. Black Mountains Basalt. Unnamed basalts (some of which may be older or younger than Pleistocene).
QT- continental deposits	Plio-Pleistocene	Segment 3N	Unnamed fanglomerate deposits, includes sandstone, conglomeritic sandstone, and conglomerate.
Pv^{p} – pyroclastic volcanic rocks	Pliocene	Segment 1	Volcanic rocks of the Coso Formation – rhyolitic tuff, lapilli tuff, and tuff breccia, white to light brown, sometimes reddish, moderately well bedded, often slightly welded, limy, or ferruginous; age may range to Pleistocene.
Mt – nonmarine sedimentary rocks and volcanic rocks of the Tropico Group	Miocene	Segment 3S	Tropico Group – Conglomerate, arkosic sandstone, siltstone, tuff, basalt breccia, shale, limestone, and chert.
Mi^{a}/Mi^{d} – shallow intrusive rocks	Miocene	Segment 3N	Intrusive andesite, dacite, and rhyolite
JKgd - granodiorite	Cretaceous - Jurassic	Segment 3N	Unnamed biotite granodiorite and biotite granodiorite porphyry.
Jqd – quartz diorite	Jurassic	Segment 3S	Quartz diorite.

Geologic Unit/ Formation	Age	Project Location	Description
Mzv – metavolcanic rocks	Mesozoic (Jurassic)	Segment 3S	Porphyry complex and unnamed metavolcanic rocks.
gr – undifferentiated granitic rocks	Mesozoic	Segments 1 and 2	Undivided granitic rocks, but may include: granite, quartz diorite, quartz monzonite, granodiorite, hornblende diorite, pegmatite, aplite, granophyre, and gneissic granite.
wg – Waterman Gneiss	Mesozoic to Precambrian	Segment 3N	Cataclastically deformed rocks of uncertain age that occurs in the Barstow area
ms – metasedimentary rocks of uncertain age	Mesozoic to Precambrian	Segment 3S	Quartzite, phyllite, and schist.
Pz – Marine sedimentary and metasedimentary rocks	Paleozoic	Segment 2	Garlock series – tactite, marble, phyllite, schist, hornfels, chert, limestone and shale (Permian in part).
Mzv – metavolcanic rocks	Mesozoic (Jurassic)	Segment 3S	Porphyry complex and unnamed metavolcanic rocks.
gr – undifferentiated granitic rocks	Mesozoic	Segments 1 and 2	Undivided granitic rocks, but may include: granite, quartz diorite, quartz monzonite, granodiorite, hornblende diorite, pegmatite, aplite, granophyre, and gneissic granite.
wg – Waterman Gneiss	Mesozoic to Precambrian	Segment 3N	Cataclastically deformed rocks of uncertain age that occurs in the Barstow area
ms – metasedimentary rocks of uncertain age	Mesozoic to Precambrian	Segment 3S	Quartzite, phyllite, and schist.
Pz – Marine sedimentary and metasedimentary rocks	Paleozoic	Segment 2	Garlock series – tactite, marble, phyllite, schist, hornfels, chert, limestone and shale (Permian in part).
pЄs - metamorphic schist	Precambrian	Segment 2; Randsburg Substation	Rand Schist – mica-quartz-albite schist and actinolite schist

Table Ap.6-2. DWR Groundwater Basins and Subsidence Potential

Groundwater Basin	Project Segment	2014 Subsidence Potential	Vertical Surface Displacement, years 2015-2023 (feet)
Owens Valley	1	Low-Medium	-0.5 to 0.5
Rose Valley	1	Insufficient data	
Indian Wells Valley	1, 2	Low	-0.5 to 0.5
Fremont Valley	2	Medium to High	NA
Cuddeback Valley	2	Insufficient data	NA
Harper Valley	2, 3N, 3S	High	NA
Lower Mojave River Valley	3N, 3S	High	-0.5 to 0.5

Table Ap.6-3. Significant Active and Potentially Active Faults in the Vicinity of the Proposed Project

Fault Name	Nearest Project Component	Distance (miles)[1]	Maximum Estimated Earthquake Magnitude[2]	Fault Type and Dip Direction
Owens Valley fault zone	Segment 1	0 (crosses 23 times)	7.3	Right-lateral strike-slip, 90°
Little Lake fault zone	Segment 1	0	6.9	Right-lateral strike-slip
Southern Sierra Nevada fault zone - Haiwee Section	Segment 1	0	7.5	Normal, 50° E
Airport Lake fault zone	Segment 1	2.9	5.5-6.5[3]	Normal, right lateral
White Mountains fault zone	Segment 1	3.5	7.4	Right-lateral strike-slip, 90°
Independence fault (Southern Sierra Nevada fault zone)	Segment 1	3.7	7.5	Normal, 50°E
Fish Slough fault zone	Segment 1	4.3	6.8	Normal, 50° E
Round Valley fault	Control Substation	7.5	7.1	Normal, 50° E
Hunter Mountain Connected (Hunter Mountain-Saline Valley-Panamint Valley)	Segment 1	12.1	7.6	Right-lateral strike-slip, 90°
Hilton Creek fault	Control Substation	19.2	6.9	Normal, 50° E
Kern Canyon fault	Segment 1	20.3	6.5 to 7.5[4]	Normal, 60° E
Death Valley fault zone (Fish Lake Valley fault)	Segment 1	27.8	7.2	Right-lateral strike-slip, 90°
Panamint Valley	Segment 1	34.2	7.4	Right-lateral strike-slip, 90°
Hartley Springs fault zone	Control Substation	35.3	6.8	Normal, East
Death Valley fault zone (Northern)	Segment 1	39.3	7.3	Right-lateral strike-slip, 90°
Garlock Fault zone (various segment rupture combinations)	Segment 2	0	7.3 to 7.7	Left-lateral strike-slip, 90°
Lenwood-Lockhart-Old Woman Springs fault zone	Segments 2, 3N, and 3S	0	7.5	Right-lateral strike-slip, 90°
Helendale-South Lockhart fault zone	Segments 2, 3N, and 3S	0	7.4	Right-lateral strike-slip, 90°
Tank Canyon	Segment 2	29	6.4	Normal, 50° W
Gravel Hills- Harper Lake fault zone	Segment 3N	0	7.1	Right-lateral strike-slip, 90°
Blackwater fault zone	Segment 3N	1.8		Right-lateral strike-slip, 90°
Camp Rock-Emerson-Copper Mtn fault zone	Segment 3N, 3S, and Coolwater Substation	4.7	7.1	Right-lateral strike-slip, 90°
Johnson Valley fault zone	Segment 3N, 3S, and Coolwater Substation	23.5	6.9	Right-lateral strike-slip, 90°
North Frontal (West) fault	Segment 3S and Tortilla Substation	29.5	7.2	Reverse, 49° S
North Frontal (East) fault	Segment 3S	33.4	7.0	Thrust, 41° S
S. San Andreas fault zone (various segment rupture combinations)	Segment 3S	40	6.9 to 8.1	Right-lateral strike-slip, 90°
Cleghorn fault	Segment 3S	40.9	6.8	Right-lateral strike-slip, 90°
San Jacinto fault zone (various segment rupture combinations)	Segment 3S	46	7.1 to 7.8	Right-lateral strike-slip, 90°

Table Ap.6-4. Significant Historic Earthquakes from 1900-2023 within 50 miles of the Proposed Project

Date	Earthquake Magnitude	Earthquake Name or General Location	Fault Involved, if Known	Approximate Closest Distance to Proposed Project and Closest Project Component
July 5, 2019	7.1	Ridgecrest Earthquake Sequence	Little Lake and/or Airport Lake fault zones	12.9 miles east of Segment 1
July 4, 2019	6.4	Ridgecrest Earthquake Sequence	Little Lake and/or Airport Lake fault zones	16.8 miles east of Segments 1 and 2, and Inyokern Substation
May 17, 1993	6.1	Near Big Pine	Northern Death Valley fault zone	26.5 miles east of Segment 1
June 28, 1992	7.3	Landers Earthquake	Johnson Valley, Landers, Homestead Valley	54 miles south of Segment 3S and Coolwater Substation
June 28, 1992	6.3	Big Bear Earthquake (Landers Earthquake sequence)	Unnamed fault	46 miles south of Segment 3S and Coolwater Substation
July 21, 1986	6.4	Chalfant Valley Earthquake	White Mountains fault zone	14.1 miles north of Segment 1 and Control Substation
November 23, 1984	6.1	Round Valley Earthquake	Round Valley fault	11.0 miles northwest of Segment 1 and Control Substation
May 27, 1980	6.2	Mammoth Lakes Earthquake Sequence	Hilton Creek fault	21.3 miles northwest of Segment 1 and Control Substation
May 25, 1980	6.1	Mammoth Lakes Earthquake Sequence	Hilton Creek fault	26.0 miles northwest of Segment 1 and Control Substation
May 25, 1980	6.0	Mammoth Lakes Earthquake Sequence	Hilton Creek fault	32.9 miles northwest of Segment 1 and Control Substation
May 25, 1980	6.1	Mammoth Lakes Earthquake Sequence	Hilton Creek fault	23.4 miles northwest of Segment 1 and Control Substation
April 10, 1947	6.5	Manix Earthquake	Manix fault	20 miles east of Segment 3N and Coolwater Substation
March 15, 1946	6.3	Walker Pass Earthquake	Uncertain	14 miles northwest of Inyokern Substation
November 4, 1908	6.5	Panamint Range or Death Valley Region	Uncertain	49.7 miles northeast of Inyokern Substation
March 26, 1872	Estimated 7.4 to 7.9	Owens Valley Earthquake	Owens Valley fault zone	0 to 0.6 miles east of Segment 1

Table Ap.6-5. Select Characteristics of Soils Underlying Segment 1 of the Proposed Project

Unit ID	Name	Description	Total Length (miles)	Percentage of Segment 1 (%)	Susceptibility to Erosion		Expansion Potential	Corrosion Potential	
					Wind	Sheet & Rill		Steel	Concrete
SSURGO Soil Survey CA802									
110	Aquents-Aquic torripsamments association, 0 to 2 percent slopes	Present on stream terraces and river valleys; parent material consists of alluvium from mixed sources.	2.31	1.8	Moderate-High	Low-Moderate	Low	Moderate-High	Low-High
115	Arizo gravelly loamy sand, 5 to 9 percent slopes	Present on fan terraces, alluvial fans and fan piedmonts; parent material consists of alluvium derived from granite	1	0.78	High	Low	Low	Moderate	Low
116	Arizo gravelly loamy sand, 9 to 15 percent slopes	Present on fan piedmonts, fan terraces, and alluvial fans; parent material consists of alluvium derived from granite	0.88	0.69	High	Low	Low	Moderate	Low
118	Arizo-Yellowrock complex, 5 to 9 percent slopes	Present on alluvial fans and fan piedmonts; parent material consists of alluvium derived from granite	4.18	3.26	High	Low	Low	Moderate-High	Low-High
145	Cajon loamy sand, stratified substra-tum, 0 to 5 percent slopes	Present on inset fans and fan piedmonts; parent material consists of alluvium derived from granite	0.82	0.64	High	Low	Low	High	Moderate
146	Cajon gravelly loamy sand, 0 to 5 percent slopes	Present on fan piedmonts, fan terraces, and alluvial fans; parent material consists of alluvium derived from granite	4.01	3.13	High	Low	Low	Moderate	Moderate
148	Cajon-Mazourka-Eclipse complex, 0 to 2 percent slopes	Present on river valleys, lake terraces, lacustrine terraces, and stream terraces; parent material consists of alluvium derived from mixed sources	1.4	1.09	High	Low-Moderate	Low-Moderate	High	Moderate
149	Cajon-Typic Torriorthents complex, 0 to 5 percent slopes	Present on shoreline barrier bars, barrier bar on relict shorelines, and lake plains; parent material consists of alluvium derived from granite	0.66	0.51	Moderate-High	Low	Low	Moderate-High	Low-High
152	Cartago gravelly loamy coarse sand, 5 to 30 percent slopes	Present on alluvial fans and fan piedmonts; parent material consists of alluvium derived from granite	2.03	1.58	High	Low	Low	Low	Low
154	Cartago gravelly loamy sand, 0 to 2 percent slopes	Present on alluvial fans and fan piedmonts; parent material consists of alluvium derived from granite	2.07	1.62	High	Low-Moderate	Low	Low	Low

Unit ID	Name	Description	Total Length (miles)	Percentage of Segment 1 (%)	Susceptibility to Erosion		Expansion Potential	Corrosion Potential	
					Wind	Sheet & Rill		Steel	Concrete
155	Cartago gravelly loamy sand, 2 to 5 percent slopes	Present on alluvial fans and fan piedmonts; parent material consists of alluvium derived from granite	0.68	0.53	High	Low-Moderate	Low	Low	Low
187	Dehy sandy loam, loamy substratum, 0 to 2 percent slopes	Present on fan terraces and fan piedmonts; parent material consists of alluvium derived from mixed sources	0.53	0.42	Moderate-High	Low-Moderate	Low	Moderate	Moderate
191	Division-Numu complex, 0 to 2 percent slopes	Present on lacustrine lake terraces, stream terraces, and river valleys; parent material consists of alluvium derived from mixed sources and lacustrine deposits derived from mixed sources	1.83	1.42	Moderate-High	Low-High	Low-High	High	Moderate-High
196	Goodale loamy coarse sand, 5 to 15 percent slopes	Present on alluvial fans, fan terraces, and fan piedmonts; parent material consists of alluvium derived from granite	0.11	0.08	Moderate-High	Low	Low	High	Low
200	Goodale-Cartago complex, 5 to 15 percent slopes	Present on alluvial fans, fan terraces, and fan piedmonts; parent material consists of alluvium derived from granite	2.12	1.65	Moderate-High	Low	Low	Low	Low
201	Goodale-Cartago complex, moist, 2 to 5 percent slopes	Present on alluvial fans, fan terraces, and fan piedmonts; parent material consists of alluvium derived from granite	0.47	0.37	Moderate-High	Low	Low	Low	Low
202	Goodale-Cartago complex, moist, 5 to 15 percent slopes	Present on alluvial fans, fan terraces, and fan piedmonts; parent material consists of alluvium derived from granite	1.78	1.39	Moderate-High	Low	Low	Low-High	Low
207	Helendale-Cajon complex, 0 to 5 percent slopes	Present on fan terraces and fan piedmonts; parent material consists of alluvium derived from granite	2.29	1.79	High	Low	Low	Moderate-High	Low-Moderate
208	Helendale-Cajon complex, dry, 0 to 5 percent slopes	Present on fan terraces and fan piedmonts; parent material consists of alluvium derived from granite	1.1	0.85	High	Low	Low	Moderate-High	Low-Moderate
210	Hesperia-Cartago complex, 0 to 5 percent slopes	Present on fan piedmonts and alluvial fans; parent material consists of alluvium derived from granite	0.41	0.32	Moderate-High	Low	Low	Low	Low
221	Inyo sand, 0 to 9 percent slopes	Present on dunes on stream terraces and river valleys; parent material consists of alluvium derived from mixed sources	0.52	0.4	High	Low	Low	High	Low

Unit ID	Name	Description	Total Length (miles)	Percentage of Segment 1 (%)	Susceptibility to Erosion		Expansion Potential	Corrosion Potential	
					Wind	Sheet & Rill		Steel	Concrete
230	Lithic Torriorthents-Badland complex, 15 to 75 percent slopes	Present on hills and mountains; parent material consists of residuum weathered from metavolcanics and/or metasedimentary rock and/or granite	0.72	0.57	High	Low	Low	Moderate	Low
231	Lithic Torriorthents-Lithic Haplargids-Rock outcrop complex, 30 to 75 percent slopes	Present on hills and mountains; parent material consists of residuum weathered from metavolcanics and/or metasedimentary rock and/or granite	0.92	0.72	Low-High	Low	Low-Moderate	Moderate	Low
245	Lubkin-Tinemaha complex, moist, 5 to 15 percent slopes	Present on alluvial fans, fan terraces, and fan piedmonts; parent material consists of alluvium derived from granite	0.57	0.44	High	Low	Low	Low	Low
247	Lucerne gravelly loamy sand, 2 to 5 percent slopes	Present on alluvial fans and fan piedmonts; parent material consists of alluvium derived from granite	1.26	0.98	High	Low	Low	Low	Low
249	Manzanar silt loam, 0 to 2 percent slopes	Present on river valleys, and lake and stream terraces; parent material consists of alluvium and/or lacustrine deposits derived from mixed sources	5.35	4.17	Moderate	Low-Moderate	Low-Moderate	High	High
251	Manzanar-Westguard association, 0 to 2 percent slopes	Present on stream terraces and river valleys; parent material consists of alluvium derived from mixed sources	0.98	0.77	Moderate-High	Low-Moderate	Low-Moderate	High	Moderate-High
252	Manzanar-Winnedumah association, 0 to 2 percent slopes	Present on lake and stream terraces, lake beds (relict) and river valleys; parent material consists of alluvium and/or lacustrine deposits derived from mixed sources	1.63	1.27	Moderate	Low-Moderate	Low-Moderate	High	High
257	Mazourka-Eclipse complex, 0 to 2 percent slopes	Present on stream and lake terraces, and river valleys; parent material consists of alluvium derived from mixed sources	1.11	0.87	High	Low-Moderate	Low-Moderate	High	Moderate
259	Mazourka-Slickspots-Cajon complex, 0 to 2 percent slopes	Present on stream and lake terraces, lacustrine terraces, and river valleys; parent material consists of alluvium derived from mixed sources	0.76	0.6	High	Low-Moderate	Low	High	Moderate

Unit ID	Name	Description	Total Length (miles)	Percentage of Segment 1 (%)	Susceptibility to Erosion		Expansion Potential	Corrosion Potential	
					Wind	Sheet & Rill		Steel	Concrete
261	Mazourka hard substratum-Mazourka-Eclipse complex, 0 to 2 percent slopes	Present on stream terraces and river valleys; parent material consists of alluvium derived from mixed sources	4.52	3.52	High	Low-High	Low-Moderate	Moderate-High	Moderate
273	Neuralia-Timosea-Typic Argidurids complex, 2 to 15 percent slopes	Present on fan terraces, fan remnants, and fan piedmonts; parent material consists of alluvium derived from granite	5.25	4.09	Moderate-High	Low	Low-High	Moderate-High	Low-Moderate
290	Pokonahbe-Rindge family association, 0 to 5 percent slopes	Present on lake and stream terraces, springs along fault escarpments, and river valleys; parent material consists of organic material over alluvium derived from mixed sources	1.14	0.89	Moderate-High	Low-Moderate	Low-Moderate	High	Low-Moderate
293	Poleta-Mazourka-Eclipse complex, 0 to 2 percent slopes	Present on stream and lake terraces, and river valleys; parent material consists of alluvium derived from mixed sources	1.65	1.28	High	Low-Moderate	Low	High	Low-Moderate
294	Poleta-Mazourka-Slickspots complex, 0 to 2 percent slopes	Present on stream and lake terraces, and river valleys; parent material consists of alluvium derived from mixed sources	1.2	0.94	High	Low-Moderate	Low-Moderate	High	Low-Moderate
296	Rienhakel sand, 0 to 2 percent slopes	Present on valleys, and stream and lake terraces; parent material consists of alluvium derived from mixed sources	2.84	2.21	High	Low-Moderate	Low-Moderate	High	High
308	Seaman-Yellowrock complex, 2 to 5 percent slopes	Present on fan terraces, alluvial fans, and fan piedmonts; parent material consists of alluvium derived from mixed sources	1.13	0.88	High	Low-Moderate	Low	High	Moderate
311	Shabbell sandy loam, 0 to 2 percent slopes	Present on stream terraces, fan terraces, and fan piedmonts; parent material consists of alluvium derived from mixed sources	0.28	0.22	Moderate	Low	Low	Moderate	Low
318	Shondow-Hessica association, 0 to 2 percent slopes	Present on stream terraces and river valleys; parent material consists of alluvium derived from mixed sources	0.36	0.28	Moderate-High	Low-Moderate	Low-Moderate	Moderate-High	Moderate-High
324	Timosea-Neuralia complex, warm, 2 to 9 percent slopes	Present on fan terraces and fan piedmonts; parent material consists of alluvium derived from granite	2.15	1.68	Low-High	Low	Low-Moderate	Moderate-High	Low-Moderate

Unit ID	Name	Description	Total Length (miles)	Percentage of Segment 1 (%)	Susceptibility to Erosion		Expansion Potential	Corrosion Potential	
					Wind	Sheet & Rill		Steel	Concrete
327	Torrifluvents, 0 to 2 percent slopes	Present on stream terraces and river valleys; parent material consists of alluvium derived from mixed sources	0.05	0.04	Low-Moderate	Low-Moderate	Low-Moderate	High	High
328	Torrifluvents-Fluvaquentic Endoaquolls complex, 0 to 2 percent slopes	Present on stream terraces, depressions, and river valleys; parent material consists of volcanic ash and/or alluvium derived from mixed sources	0.9	0.7	Low-Moderate	Low-Moderate	Low-Moderate	High	High
332	Typic Psamma-quents, 0 to 2 percent slopes	Present on rims on playas and lake plains; parent material consists of alluvium derived from mixed sources and lacustrine deposits	1.79	1.4	High	Low-Moderate	Low	High	High
358	Westguard-Rienhakel association, 0 to 2 percent slopes	Present on lake terraces, stream terraces, and river valleys; parent material consists of alluvium derived from mixed sources	1.78	1.39	High	Low-High	Low-Moderate	Moderate-High	Moderate-High
359	Whitewolf-Toquerville families associ-ation, 15 to 50 percent slopes	Present on hills; parent material consists of colluvium derived from granite and/or residuum weathered from granite	0.84	0.66	High	Low	Low	Low	Low
360	Whitewolf-Toquerville families associa-tion, warm, 15 to 50 percent slopes	Present on hills; parent material consists of colluvium derived from granite and/or residuum weathered from granite	0.27	0.21	High	Low	Low	Low	Low
362	Winerton-Hessica complex, 0 to 2 percent slopes	Present on stream terraces and river valleys; parent material consists of alluvium derived from mixed sources	7.73	6.03	Moderate-High	Low-Moderate	Low-Moderate	Moderate-High	Moderate-High
363	Winnedumah silt loam, 0 to 2 percent slopes	Present on lake beds (relict), stream terraces, and river valleys; parent material consists of alluvium derived from mixed sources and/or lacustrine deposits	4.99	3.89	Moderate	Low-Moderate	Low-Moderate	High	High
364	Winnedumah fine sandy loam, 0 to 2 percent slopes	Present on lakebeds (relict), stream terraces, and river valleys; parent material consists of alluvium derived from mixed sources and/or lacustrine deposits	1.41	1.1	Moderate-High	Low-Moderate	Low-Moderate	High	High

Unit ID	Name	Description	Total Length (miles)	Percentage of Segment 1 (%)	Susceptibility to Erosion		Expansion Potential	Corrosion Potential	
					Wind	Sheet & Rill		Steel	Concrete
366	Xeric Argidurids, 2 to 9 percent slopes	Present on fan remnants and fan piedmonts; parent material consists of alluvium derived from granite	1.32	1.03	High	Low	Low-High	Moderate	Low
369	Xeric Haplodurids, 2 to 9 percent slopes	Present on alluvial fans and fan piedmonts; parent material consists of alluvium derived from mixed sources and/or alluvium derived from volcanic rock	1.63	1.27	High	Low	Low	Low	Low
372	Yellowrock sand, 0 to 5 percent slopes	Present on alluvial fans, fan terraces, and fan piedmonts; parent material consists of alluvium derived from mixed sources	0.54	0.42	High	Low	Low	High	High
374	Yellowrock-Seaman complex, 2 to 5 percent slopes	Present on alluvial fans, fan terraces, and fan piedmonts; parent material consists of alluvium derived from mixed sources	0.41	0.32	High	Low-Moderate	Low	High	High
378	Yermo stony-Yermo complex, 5 to 15 percent slopes	Present on fan piedmonts and fan terraces; parent material consists of alluvium derived from mixed sources	1.11	0.86	Low-Moderate	Low	Low	High	Moderate
379	Yermo stony-Yermo complex, cool, 5 to 15 percent slopes	Present on fan terraces and fan piedmonts; parent material consists of alluvium derived from metasedimentary rock	0.59	0.46	Low-Moderate	Low	Low	High	Moderate
STATSGO National Soil Survey - California									
S768	Rosamond variant-Rosamond-Playas-Gila-Cajon Variant-Cajon	Rosamond: present on lower margin of alluvial fans between the sloping fans and playas; parent material consists of alluvium derived from granitic rock; slopes are 0 to 2 percent. Gila: present on alluvial fans and flood plains; parent material consists of stratified alluvium; slopes are 0 to 5 percent. Cajon: present on alluvial fans and river terraces; parent material consists of alluvium derived from granitic rock; slopes are 0 to 15 percent.	1.27	1.01	Low-High	Low-Moderate	Low-Moderate	Low-High	Low-High
S1024	Wasco-Rosamond-Cajon	Wasco: present on alluvial fans and flood plains; parent material derived from igneous and/or sedimentary rock; slopes are 0 to 5 percent.	17.93	14.21	Moderate-High	Low-Moderate	Low-Moderate	Low-High	Low-High

Unit ID	Name	Description	Total Length (miles)	Percentage of Segment 1 (%)	Susceptibility to Erosion		Expansion Potential	Corrosion Potential	
					Wind	Sheet & Rill		Steel	Concrete
		Rosamond: present on lower margin of alluvial fans between the sloping fans and playas; parent material consists of alluvium derived from granitic rock; slopes are 0 to 2 percent. Cajon: present on alluvial fans and river terraces; parent material consists of alluvium derived from granitic rock; slopes are 0 to 15 percent.							
S1077	Rock outcrop-Mexispring	Present on hills and mountains; parent material consists of colluvium and residuum derived from granitic rocks; slopes are 15 to 85 percent.	0.38	0.31	Low	Low-Moderate	Low	High	Low
S1086	Yermo-Ulymeyer-Tinemana-Goodale-Cartago	Yermo: present alluvial fans or uplands; parent material consists of alluvium derived from mixed sources; slopes are 0 to 50 percent. Ulymeyer: present on alluvial fans and fan terraces; parent material consists of alluvium derived from granitic rock; slopes are 5 to 15 percent. Tinemana: present on alluvial fans and fan terraces; parent material consists of alluvium derived from granitic sources; slopes are 0 to 15 percent. Goodale: present on bouldery alluvial fans and fan terraces; parent material consists of alluvium derived from granitic rock; slopes are 0 to 15 percent. Cartago: present on alluvial fans, fan terraces, and edges of valley floors; parent material consists of alluvium derived from granitic rock; slopes are 0 to 30 percent.	10.43	8.26	Low-High	Low	Low	Low-High	Low-Moderate
S1127	Upspring-Sparkhule-Rock outcrop	Upspring: present on hills, mountains, and plateaus; parent material consists of alluvium derived from extrusive basic igneous rocks and some pyroclastic material; slopes are 8 to 75 percent.	4.27	3.39	Low-Moderate	Low-Moderate	Low-Moderate	Low-Moderate	Low

Unit ID	Name	Description	Total Length (miles)	Percentage of Segment 1 (%)	Susceptibility to Erosion		Expansion Potential	Corrosion Potential	
					Wind	Sheet & Rill		Steel	Concrete
		Sparkhule: present on rock pediments and hills; parent material consists of alluvium derived from volcanic or granitic rock; slopes are 5 to 50 percent.							

Table Ap.6-6. Select Characteristics of Soils Underlying Segment 2 of the Proposed Project

Unit ID	Name	Description	Total Length (miles)	Percentage of Segment 2 (%)	Susceptibility to Erosion		Expansion Potential	Corrosion Potential	
					Wind	Sheet & Rill		Steel	Concrete
STATSGO National Soil Survey - California									
S769	Neuralia-Garlock-Cajon-Alko	Neuralia: present on alluvial fans, fan terraces, and plains; parent material consists of alluvium derived from mixed sources; slopes are 0 to 15 percent. Garlock: present on old stream terraces and alluvial fans; parent material consists of alluvium derived from mixed sources; slopes are 2 to 9 percent. Cajon: present on alluvial fans, fan aprons, fan skirts, inset fans, and river terraces; parent material consists of alluvium derived from granitic rocks; slopes are 0 to 15 percent. Alko: present on fan piedmonts; parent material consists of alluvium derived from ignimbrite, granodiorite, and basalt; slopes are 0 to 15 percent.	6.44	13.31	Moderate-High	Low-Moderate	Low-Moderate	Low-High	Low-Moderate
S770	Randsburg-Muroc	Randsburg: present on hills and granitic rock pediments; parent material consists of residuum derived from granitic rock; slopes are 2 to 50 percent. Muroc: present on hills and granitic rock pediments; parent material consists of alluvium derived from granitic rock; slopes are 2 to 15.	9.43	19.5	Moderate-High	Moderate	Low	Moderate	Low

Unit ID	Name	Description	Total Length (miles)	Percentage of Segment 2 (%)	Susceptibility to Erosion		Expansion Potential	Corrosion Potential	
					Wind	Sheet & Rill		Steel	Concrete
S813	Trigger-Sparkhule-Rock outcrop	Trigger: present on uplands; parent material consists of alluvium derived from hard sedimentary rock; slopes are 5 to 50 percent. Sparkhule: present on rock pediments and hills; parent material consists of residuum derived from volcanic or granitic rocks; slopes are 5 to 50 percent.	2.86	5.91	Low-Moderate	Low-Moderate	Low-Moderate	Moderate	Low
S1024	Wasco-Rosamond-Cajon	Wasco: present on alluvial fans and flood plains; parent material derived from igneous and/or sedimentary rock; slopes are 0 to 5 percent. Rosamond is present on the lower margin of the alluvial fans between the sloping fans and the playas; parent material consists of alluvium derived from granitic rock; slopes are 0 to 2 percent. Cajon: present on alluvial fans, fan aprons, fan skirts, inset fans, and river terraces; parent material consists of alluvium derived from granitic rock; slopes are 0 to 15 percent.	24.56	50.77	Moderate-High	Low-Moderate	Low-Moderate	Low-High	Low-High
S1126	Tecopa-Rock outcrop-Lithic Torriorthents	Tecopa: present on low hills and low mountain side slopes; parent material consists of residuum and colluvium derived from quartzite, schists, and gneiss; slopes are 15 to 75 percent.	3.07	6.35	Low	Low	Low	Moderate	Moderate
S1142	Nickel-Bitter-Arizo	Nickel: present on fan remnants; parent material consists of alluvium derived from mixed sources; slopes are 0 to 35 percent. Bitter: present on dissected fan terraces; parent material consists of alluvium derived from granite, gneiss, schist, limestone, and quartzite; slopes are 2 to 20 percent. Arizo: present on recent alluvial fans, inset fans, fan apron, fan skirts, stream terraces, and floodplains of intermittent streams and channels; parent material is alluvium derived from mixed sources; slopes are 0 to 15 percent.	1.00	2.06	Moderate-High	Low	Low	Moderate-High	Low-Moderate

Unit ID	Name	Description	Total Length (miles)	Percentage of Segment 2 (%)	Susceptibility to Erosion		Expansion Potential	Corrosion Potential	
					Wind	Sheet & Rill		Steel	Concrete
S1143	Cajon-Arizo	Cajon: present on alluvial fans, fan aprons, fan skirts, inset fans, and river terraces; parent material consists of alluvium derived from granitic rocks; slopes are 0 to 15 percent. Arizo: present on recent alluvial fans, inset fans, fan apron, fan skirts, stream terraces, and floodplains of intermittent streams and channels; parent material is alluvium derived from mixed sources; slopes are 0 to 15 percent.	1.00	2.08	Moderate-High	Low-Moderate	Low-Moderate	Low-High	Low-Moderate

Table Ap.6-7. Select Characteristics of Soils Underlying Segment 3N of the Proposed Project

Unit ID	Name	Description	Total Length (miles)	Percentage of Segment 3N (%)	Susceptibility to Erosion		Expansion Potential	Corrosion Potential	
					Wind	Sheet & Rill		Steel	Concrete
SSURGO Soil Survey CA671									
112	Cajon Sand, 0 To 2 Percent Slopes	Present on alluvial fans; parent material consists of alluvium derived from granite sources	5.3	11.9	High	Low	Low	Low	Low
113	Cajon Sand, 2 To 9 Percent Slopes	Present on alluvial fans; parent material consists of alluvium derived from mixed sources	3.3	7.4	High	Low	Low	Low	Low
115	Cajon Gravelly Sand, 2 To 15 Percent Slopes	Present on alluvial fans; parent material consists of alluvium derived from granite sources	4.6	10.4	High	Low	Low	Low	Low
117	Cajon Loamy Sand, Loamy Substra-tum, 0 To 2 Percent Slopes	Present on alluvial fans; parent material consists of alluvium derived from granite sources	1.5	3.4	High	Low-Moderate	Low	High	Moderate
131	Helendale Loamy Sand, 0 To 2% Slopes	Present on fan remnants and inset fans; parent material consists of alluvium derived from granite sources	0.5	1.1	High	Moderate	Low	Moderate	Low
137	Kimberlina Loamy Fine Sand, Cool, 0 To 2 Percent Slopes	Found on fan skirts and fan aprons; parent material consists of alluvium derived from mixed sources	0.1	0.2	High	Moderate	Moderate	Moderate	Moderate

Unit ID	Name	Description	Total Length (miles)	Percentage of Segment 3N (%)	Susceptibility to Erosion		Expansion Potential	Corrosion Potential	
					Wind	Sheet & Rill		Steel	Concrete
151	Nebona-Cudde-back Complex, 2 To 9 Percent Slopes*	Present on fan remnants; parent material consists of alluvium derived from mixed sources	0.7	1.7	Moderate-High	Moderate	Low	High	High
152	Norob-Halloran Complex, 0 To 5 Percent Slopes*	Present on fan remnants; parent material consists of alluvium derived from granitic sources	4.7	10.7	High	Moderate	Low	High	High
159	Rosamond Loam, Saline-Alkali	Found on fan skirts; parent material consists of alluvium derived from granite	0.7	1.5	Moderate	Moderate-High	Moderate	High	High
170	Victorville Variant Sand	Present on flood plains; parent material consists of alluvium derived from granite	0.3	0.8	High	Moderate	Low	High	High
STATSGO National Soil Survey - California									
S1024	Wasco-Rosamond-Cajon	Wasco: present on alluvial fans and flood plains; parent material derived from igneous and/or sedimentary rock; slopes are 0 to 5 percent. Rosamond is present on the lower margin of the alluvial fans between the sloping fans and the playas; parent material consists of alluvium derived from granitic rock; slopes are 0 to 2 percent. Cajon: present on alluvial fans, fan aprons, fan skirts, inset fans, and river terraces; parent material consists of alluvium derived from granitic rock; slopes are 0 to 15 percent.	15.1	33.8	Moderate-High	Low-Moderate	Low-Moderate	Low-High	Low-High
S769	Neuralia-Garlock-Cajon-Alko	Neuralia: present on alluvial fans, fan terraces, and plains; parent material consists of alluvium derived from mixed sources; slopes are 0 to 15 percent. Garlock: present on old stream terraces and alluvial fans; parent material consists of alluvium derived from mixed sources; slopes are 2 to 9 percent. Cajon: present on alluvial fans, fan aprons, fan skirts, inset fans, and river terraces; parent material consists of alluvium	7.9	17.9	Moderate-High	Low-Moderate	Low-Moderate	Low-High	Low-Moderate

Unit ID	Name	Description	Total Length (miles)	Percentage of Segment 3N (%)	Susceptibility to Erosion		Expansion Potential	Corrosion Potential	
					Wind	Sheet & Rill		Steel	Concrete
		derived from granitic rocks; slopes are 0 to 15 percent. Alko: present on fan piedmonts; parent material consists of alluvium derived from ignimbrite, granodiorite, and basalt; slopes are 0 to 15 percent.							
S1134	Trigger-Rock Outcrop-Calvista	Trigger: present on uplands; parent material consists of alluvium derived from hard sedimentary rock; slopes are 5 to 50 percent.	1.4	3.1					
S1142	Nickel-Bitter-Arizo	Nickel: present on fan remnants; parent material consists of alluvium derived from mixed sources; slopes are 0 to 35 percent. Bitter: present on dissected fan terraces; parent material consists of alluvium derived from granite, gneiss, schist, limestone, and quartzite; slopes are 2 to 20 percent. Arizo: present on recent alluvial fans, inset fans, fan apron, fan skirts, stream terraces, and floodplains of intermittent streams and channels; parent material is alluvium derived from mixed sources; slopes are 0 to 15 percent.	3.8	8.5	Moderate-High	Low	Low	Moderate-High	Low-Moderate

Table Ap.6-8. Select Characteristics of Soils Underlying Segment 3S of the Proposed Project

Unit ID	Name	Description	Total Length (miles)	Percentage of Segment 3S (%)	Susceptibility to Erosion		Expansion Potential	Corrosion Potential	
					Wind	Sheet & Rill		Steel	Concrete
SSURGO Soil Survey CA671									
100	Arizo Gravelly Loamy Sand, 2 To 9% Slopes	Present on alluvial fans; parent material consists of alluvium derived from granite sources	0.8	1.8	High	Low-Moderate	1.5	Moderate	Low
105	Bryman Loamy Fine Sand, 0 To 2% Slopes	Found on fan remnants; parent material is alluvium derived from granite sources	0.2	0.5	High	Moderate	Low-Moderate	Moderate	Low

Unit ID	Name	Description	Total Length (miles)	Percentage of Segment 3S (%)	Susceptibility to Erosion		Expansion Potential	Corrosion Potential	
					Wind	Sheet & Rill		Steel	Concrete
112	Cajon Sand, 0 To 2 Percent Slopes	Present on alluvial fans; parent material consists of alluvium derived from granite sources	0.2	0.4	High	Low	Low	Low	Low
113	Cajon Sand, 2 To 9 Percent Slopes	Present on alluvial fans; parent material consists of alluvium derived from mixed sources	3.8	8.6	High	Low	Low	Low	Low
115	Cajon Gravelly Sand, 2 To 15 Percent Slopes	Present on alluvial fans; parent material consists of alluvium derived from granite sources	7.5	16.9	High	Low	Low	Low	Low
117	Cajon Sand, 0 To 2 Percent Slopes	Present on alluvial fans; parent material consists of alluvium derived from granite sources	0.4	1.0	High	Low-Moderate	Low	High	Moderate
120	Cave Loam, Dry, 0 To 2% Slopes	Found on fan remnants; parent material is alluvium derived from granite sources	0.8	1.8	6	Moderate-High	Low	Moderate	Moderate
124	Lavic-Norob Complex, 2 To 9% Slopes	Present on fan pediments; parent material is alluvium derived from granite	0.5	1.1	High	Moderate-High	Low-Moderate	High	Moderate-High
135	Joshua Loam, 2 To 5% Slopes	Found on fan remnants; parent material is alluvium derived from mixed sources	0.1	0.2	Moderate			High	High
136	Norob Sandy Loam, 2 To 5% Slopes	Found on alluvial flats; parent material is alluvium derived from mixed sources	0.3	0.7	Moderate	Moderate-High	Low-High	High	High
140	Lavic Loamy Fine Sand	Present on fan skirts and fan aprons; parent material is alluvium derived from granite sources	0.2	0.3	High	Low-Moderate	Low-Moderate	High	Moderate
141	Lovelace Loamy Sand, 5 To 9% Slopes	Found on alluvial flats; parent material is alluvium derived from mixed sources	0.5	1.1	High	Low-Moderate	Low	Moderate	Moderate
151	Nebona-Cudde-back Complex, 2 To 9 Percent Slopes*	Present on fan remnants; parent material consists of alluvium derived from mixed sources	1.9	4.4	Moderate-High	Moderate	Low	High	High
152	Norob-Halloran Complex, 0 To 5% Slopes*	Present on fan remnants; parent material consists of alluvium derived from granitic sources	2.2	5.0	High	Moderate	Low	High	High
159	Rosamond Loam, Saline-Alkali	Found on fan skirts; parent material consists of alluvium derived from granite	1.2	2.7	High	Moderate	Low	High	High

Unit ID	Name	Description	Total Length (miles)	Percentage of Segment 3S (%)	Susceptibility to Erosion		Expansion Potential	Corrosion Potential	
					Wind	Sheet & Rill		Steel	Concrete
168	Typic Haplargids-Yermo Complex, 8 To 30% Slopes*	Found on hills: parent material is alluvium derived from mixed sources	1.1	2.6	Moderate	Low	Low	Moderate	Low
169	Victorville Sandy Loam	Found on flood plains; parent material is alluvium derived from granite	0.6	1.3	Moderate-High	Moderate	Low-Moderate	Moderate	Moderate
171	Villa Loamy Sand	Found on flood plains; parent material is alluvium derived from granite	1.6	3.6	High	Moderate	Low	Moderate	Moderate
172	Villa Loamy Sand, Hummocky	Found on flood plains; parent material is alluvium derived from granite	0.2	0.5	High	Moderate	Low	Moderate	Moderate
STATSGO National Soil Survey - California									
S1024	Wasco-Rosamond-Cajon	Wasco: present on alluvial fans and flood plains; parent material derived from igneous and/or sedimentary rock; slopes are 0 to 5 percent. Rosamond is present on the lower margin of the alluvial fans between the sloping fans and the playas; parent material consists of alluvium derived from granitic rock; slopes are 0 to 2 percent. Cajon: present on alluvial fans, fan aprons, fan skirts, inset fans, and river terraces; parent material consists of alluvium derived from granitic rock; slopes are 0 to 15 percent.			Moderate-High	Low-Moderate	Low-Moderate	Low-High	Low-High
s1039	Norob-Halloran-Cajon-Bryman	Bryman: Found on fan remnants; parent material is alluvium derived from granite sources Cajon: present on alluvial fans, fan aprons, fan skirts, inset fans, and river terraces; parent material consists of alluvium derived from granitic rock; slopes are 0 to 15 percent							