

*Southern California Edison*  
**MESA PTC A.15-03-003**

**DATA REQUEST SET A.15-03-003 ED-SCE-01**

**To:** ENERGY DIVISION  
**Prepared by:** Jason Carson  
**Title:** Project Manager  
**Dated:** 05/22/2015

---

**Question Q.05:**

**Helicopter Use**

Page 3-84 indicates that helicopters "may use the potential staging yard locations, as needed." In the event the staging yard locations described in Table 3-7 cannot optimize flight time to structure locations, clarify if additional helicopter staging yards would be used. If additional helicopter staging areas would be required, provide approximate size of such areas.

**Response to Question Q.05:**

Helicopter use for the Mesa project would only involve pulling in sock lines during the 500 kV and 220 kV conductor stringing process, they will not be used for structure assembly or erection. Please refer to Chapter 3, Section 3.7.2.3 for further description of the use of helicopters for sock line threading.

No additional helicopter staging areas are currently anticipated to be required.