

TECHNICAL APPENDICES



DRAFT ENVIRONMENTAL ASSESSMENT

FOR
DEPARTMENT OF ENERGY LOAN GUARANTEE TO MOJAVE
SOLAR, LLC FOR THE ABENGOA MOJAVE SOLAR PROJECT
NEAR BARSTOW, CALIFORNIA

U.S. Department of Energy
Loan Guarantee Program Office
Washington, DC 20585

April 2011

APPENDICES

Appendix

- A Record of Public Contact
- B Interconnection System Impact Study
- C Southwest Gas Corporation Correspondence
- D Solar Plant Details
- E Water Regulations, Hydrology Report, DESCP, and SWPPP
- F Southern California Edison Lockhart Substation Project Description for Abengoa Solar, Inc.
- G Land Use
- H Visual
- I Air Quality
- J Noise
- K Geology and Soils
- L Paleontology Study
- M Biological Resources
 - M-1 Desert Tortoise Clearance and Relocation/Translocation Plan
 - M-2 Common Raven Monitoring, Management, and Control Plan
 - M-3 Burrowing Owl Monitoring and Mitigation Plan
- N Cultural Resources Study (Confidential)
- O Socioeconomics
- P Public Health and Safety
- Q Traffic
- R Correspondence
- S Environmental Protection Measures, Design Measures, and BMPs

APPENDIX A

RECORD OF PUBLIC CONTACT

[Home](#) → [sitingcases](#) → [abengoa](#) → [notices](#) → 2009-12-09 notice hearing

STATE OF CALIFORNIA – THE NATURAL RESOURCES AGENCY

Arnold Schwarzenegger, Governor

California Energy Commission

1516 Ninth Street
Sacramento, CA 95814
Website: www.energy.ca.gov
Consumer Website: www.ConsumerEnergyCenter.org
Children's Website: www.energyquest.ca.gov



*APPLICATION FOR CERTIFICATION
FOR THE
ABENGOA MOJAVE SOLAR PROJECT*

Docket No. 09-09-AFC-5

**NOTICE OF INFORMATIONAL HEARING
ENVIRONMENTAL SCOPING MEETING
AND PUBLIC SITE VISIT**

On August 10, 2009, Mojave Solar LLC, filed an Application for Certification (AFC) to construct and operate the Abengoa Mojave Solar (AMS) project, a 250 megawatt (MW) solar electric generating facility on approximately 1,765 acres located approximately nine miles northwest of the town of Hinkley in unincorporated San Bernardino County. The Energy Commission has exclusive jurisdiction to license this project and is considering the proposal under a twelve-month review process established by Public Resources Code, section 25540.6.

PLEASE TAKE NOTICE that the Energy Commission has designated a Committee of two commissioners to conduct proceedings on the AFC. The Committee has scheduled a Public Site Visit, Informational Hearing, and Environmental Scoping Meeting to discuss the proposed project as described below:

WEDNESDAY, December 9, 2009

Site Visit begins (bus leaves) at 1:00 p.m.

Public Informational Hearing & Environmental Scoping Meeting begins at 3:00 p.m.

Barstow City Hall
220 E. Mountain View Street
Barstow, California 92311
([Map](#))

Members of the public are invited to join the Committee on a tour of the proposed site. The Applicant will provide transportation to and from the site. For reservations, contact the Energy Commission Public Adviser's Office at (916) 654-4489, 800-822-6228, or e-mail: publicadviser@energy.state.ca.us. Please make your reservation on or before 12:00 noon, Monday, December 7, 2009, so we can assure you a space.

Background

The power plant licensing process, which incorporates requirements equivalent to the California Environmental Quality Act (CEQA), considers all relevant engineering and environmental aspects of the proposed project. It provides a public forum allowing the Applicant, Commission staff, governmental agencies, adjacent landowners, and members of the public to consider the advantages and disadvantages of the project, and to propose changes, mitigation measures, and alternatives as necessary.

On October 21, 2009, the Energy Commission began its review of the project. During the review period, it will determine whether the proposed project complies with applicable laws related to public health and safety, environmental impacts, and engineering requirements. During the preparation of its analysis, Commission staff may hold one or more public workshops. After Staff's analysis is completed, the Committee will hold evidentiary hearing(s) and prepare a Presiding Member's Proposed Decision (PMPD), based solely on the evidence presented during the hearing(s), recommending whether or not to approve the proposed project. The PMPD will then be considered by the full Energy Commission.

Project Description

The AMS facility is proposed for a 1,765 acre site approximately nine miles northwest of the site in the town of Hinkley, San Bernardino County, and six miles north of the intersection of Harper Lake Road and State Highway 58. The existing Solar Electric Generating Stations (SEGS) VIII and IX facilities, owned by NextEra™ Energy Resources, are located immediately northwest of the project site.

The project site is comprised of private property that was known as the Lockhart Ranch complex and used for agricultural and cattle production for over sixty years. The property is designated and also zoned Rural Living (RL) by the San Bernardino County General Plan.

The proposed project is a solar electric generating facility using solar parabolic trough technology to activate a heat transfer fluid. That fluid is then used to generate steam to drive steam turbine generators, generating electrical power. The project would have a combined nominal electrical output of 250-MW from twin, independently-operable solar fields, each feeding a 125-MW power island. The twin solar fields would be 884 acres and 800 acres, respectively, and joined at a transmission line interconnection substation, located on-site. An additional 81 acres, shared between the solar sites, would be utilized for drainage facilities for receiving and discharging of on-site and off-site drainage.

Natural gas for ancillary project purposes, such as auxiliary boilers, space heating, and similar uses, would be supplied by an existing natural gas pipeline that runs to the project boundary. Each power island would also have a diesel engine-driven firewater pump for fire protection and a diesel engine-driven backup generator for power plant essentials. The AMS project would connect to Southern California Edison Company's Kramer-Cool Water 230-kV transmission line, which is located adjacent to the southern border of the project site.

The project proposes to use wet cooling towers for power plant cooling and owns adjudicated water rights to the Harper Valley Groundwater Basin for this purpose. The groundwater supply is expected to be brackish and not suitable for municipal supply or other potable uses without treatment. The project proposes to use 2,163 acre-feet of water per year.

The project will include four 5-acre lined evaporation ponds for industrial wastewater. A sanitary septic system and on-site leach field will be used to dispose of sanitary wastewater.

If approved, construction of the generating facility, from site preparation and grading to commercial operation, is expected to take place from the fourth quarter of 2010 to the fourth quarter of 2012 (24 months total).

The engineering and environmental details of the proposed project are contained in the AFC. The AFC is available on the Energy Commission Web Page for this project, libraries in Eureka, San Francisco, Fresno, Los Angeles, San Diego, the Energy Commission's Library, California State Library, and at the following local area libraries: Adelanto Library; Apple Valley Library; Barstow Library; and Mojave Library.

Purpose of the Scoping Meeting and Informational Hearing

This Scoping Meeting and Informational Hearing provides an opportunity for members of the community in the project vicinity to obtain information and offer comments and concerns about the proposed project as well as identify potential environmental impacts for consideration during the Energy Commission's review of the proposal. The Applicant will explain plans for developing the project and the related facilities and Energy Commission staff will explain the administrative licensing process and Staff's role in reviewing the AFC.

Proposed Schedule and Issue Identification Report

To assist the parties and public in understanding the process, Staff shall file a proposed schedule for project review. Staff shall also file an Issue Identification Report (IIR) summarizing the major environmental and other issues it has identified regarding the project and what additional information is necessary to resolve issues of concern. The proposed schedule and Staff's report shall be filed no later than **noon on December 2, 2009**. The Applicant shall file its response, if any, no later than **noon on December 7, 2009**.

Public Adviser and Public Participation

The Energy Commission's Public Adviser's Office is available to assist the public in participating in the AFC review process. For information on how to participate, please contact the Public Adviser's Office at (916) 654-4489 or, 800-822-6228 or e-mail: [publicadviser@energy.state.ca.us].

If you have a disability and need assistance to participate in this event, contact Lourdes Quiroz at 916-654-5146 or e-mail: [lquiroz@energy.state.ca.us].

Contact Information


Questions of a legal or procedural nature should be directed to Paul Kramer, the Hearing Officer, at (916) 654-5103 or e-mail: [pkramer@energy.state.ca.us].

Technical questions concerning the Project should be addressed to Craig Hoffman, the Staff Project Manager, at (916) 654-4781, or by e-mail: [choffman@energy.state.ca.us].


Media inquiries should be directed to the Energy Commission's Office of Media and Communications at (916) 654-4989 or e-mail: [mediaoffice@energy.state.ca.us].

Information concerning the status of the project, as well as notices and other relevant documents, including the AFC, may be viewed on the Energy Commission's Internet web page at: www.energy.ca.gov/sitingcases/abengoa/. You may also subscribe to receive e-mail notification of all notices at www.energy.ca.gov/listservers.

Dated November 12, 2009, at Sacramento, California.



JULIA LEVIN
Commissioner and Presiding Member
Abengoa Mojave AFC Committee



JAMES D. BOYD
Vice Chair and Associate Member
Abengoa Mojave AFC Committee

Mailed to lists: POS, 7361, 7362, 7363, 7364

[Accessibility](#)

Copyright © 1994-2008 California Energy Commission, All Rights Reserved
State of California, Arnold Schwarzenegger, Governor

Last Modified: 11/17/09

CALIFORNIA ENERGY COMMISSION

1516 NINTH STREET
SACRAMENTO, CA 95814-5512
www.energy.ca.gov



March 16, 2010

**NOTICE OF AVAILABILITY
STAFF ASSESSMENT FOR THE PROPOSED
ABENGOA MOJAVE SOLAR PROJECT
(09-AFC-5)**

NOTICE OF PUBLIC WORKSHOPS

DOCKET
09-AFC-5

DATE MAR 16 2010REC'D MAR 17 2010

**Tuesday, April 6, 2010
Starting at 10:15 am**

**California Energy Commission
Fourth Floor North Conference Room A
1516 9th Street
Sacramento, CA 95814-5512
(Wheelchair Accessible)
(Map Attached)**

**To participate in the meeting by telephone,
please call: 800-369-2193 (toll-free in the U.S. and Canada)
Enter passcode: 54011**

**Wednesday, April 7, 2010
Starting at 1:00 pm**

**Barstow City Hall
220 E. Mountain View Street
Barstow, California 92311**

**(Wheelchair Accessible)
(Map Attached)**

**To participate in the meeting by telephone,
please call: 800-369-2193 (toll-free in the U.S. and Canada)
Enter passcode: 54011**

TO: MEMBERS OF THE PUBLIC

This notice is to inform you of the availability of the Staff Assessment (SA) for the Abengoa Mojave Solar project Application for Certification (09-AFC-5). The SA was published on **March**

16, 2010. The SA contains the California Energy Commission staff's engineering and environmental evaluation of the proposed Abengoa Mojave Solar project.

This notice is also to inform you that the Energy Commission staff will hold a workshop to discuss the SA and to further encourage public participation, regarding the proposed Abengoa Mojave Solar project and the Energy Commission's permitting process. The workshop will provide an opportunity for agencies, the public and other interested parties to present questions and comments on the SA. All interested agencies and members of the public are invited to participate. **The workshops will be held on Tuesday, April 6, 2010 starting at 10:15 am in Sacramento at the California Energy Commission's Fourth Floor North Conference Room A, 1516 9th Street and Wednesday, April 7, 2010 at 1:00 pm in Barstow at the Barstow City Hall, 220 E. Mountain View Street.**

Based on the workshop dialogue, written comments received regarding the SA, and additional information that will be gathered, the Energy Commission staff will revise the SA where appropriate and issue a Supplemental Staff Assessment (SSA).

The California Energy Commission encourages public participation in the review of the Abengoa Mojave Solar Application for Certification (09-AFC-5). **The public comment period for this SA is from Tuesday March 16, 2010 to Thursday, April 15, 2010.** Written comments on the SA should be provided to Craig Hoffman, Siting Project Manager, no later than 5:00 p.m., Thursday, April 15, 2010 at the address on this letterhead or by email to choffman@energy.state.ca.us. Technical or project schedule questions should be directed to Craig Hoffman at (916) 654-4781 or by email.

Following a 30-day public comment period on the Staff Assessment, a Supplemental Staff Assessment will be prepared and published based on Staff Assessment workshops and written comments, staff may refine its analysis, correct errors, and finalize conditions of certification to reflect areas where agreements have been reached with the parties and will then publish a Supplemental Staff Assessment (SSA). The SSA will be a limited document representing revisions and additions rather than a document including each technical section.

The Staff Assessment and Supplemental Staff Assessment will serve as staff's formal written testimony in evidentiary hearings to be held by the Energy Commission Committee assigned to hear this case. The Committee will hold evidentiary hearings and will consider the testimonies presented by staff, applicant, interveners, government agencies, and the public prior to preparing the Presiding Member's Proposed Decision. In the last step, the full Energy Commission will issue the final decision.

Summary of the Proposed Abengoa Mojave Solar

The proposed AMS project is a solar electric generating facility to be located on approximately 1,765 acres. The proposed project site is located approximately nine miles northwest of the Town of Hinkley in unincorporated San Bernardino County, approximately halfway between the City of Barstow and Kramer Junction (Highway 395 / Highway 58 junction). Project access is provided by Harper Lake Road, which is located approximately

twenty miles west of Barstow along the Highway 58 corridor. The project site is approximately six miles north of where Harper Lake Road intersects with Highway 58. The existing Solar Electric Generating Stations VIII and IX facilities, owned by NextEraTM Energy Resources, are located immediately northwest of the project site.

The project site is comprised of private property that was historically used as the Lockhart Ranch complex. The property has served as an agricultural and cattle center for over sixty years and, in that capacity, has utilized water from ground wells; farming activities have included flood irrigation and ultimately the pivot system of irrigation of quarter section areas. Currently there are no ranching or residential activities on the property, and there is only one active pivot irrigation field in production on the site.

The project would utilize solar parabolic trough technology to activate a heat transfer fluid. The proposed collector fields of parabolic trough solar collectors are modular in nature and comprise many parallel rows of solar collectors, aligned on a north-south axis. Each solar collector has a linear, parabolic-shaped reflector that focuses the sun's radiation on a linear receiver known as a heat collection element located at the focus of the parabola.

As heat transfer fluid is circulated through the solar field, light from the sun reflects off the solar collector's parabolic troughs and is concentrated on the heat collection elements located at the focal point of the parabola. This heat transfer fluid provides a high-temperature energy source which is used to generate steam in solar steam generators. As this steam expands through the steam turbine generators, electrical power is generated.

The project will have a combined nominal electrical output of 250 megawatts (MW) from twin, independently-operable solar fields, each feeding a 125-MW power island. The plant sites, identified as Alpha (the northwest portion of the Project area) and Beta (the southeast portion of the project area), will be 884 acres and 800 acres respectively and joined at an on-site transmission line interconnection substation to form one full-output transmission interconnection. This proposed substation, located at the southwest corner of the Beta solar field, is referred to as the "Hinkley" substation. An additional 81 acres shared between the plant sites will be utilized for receiving and discharging offsite stormwater drainage.

The applicant has a power purchase agreement with Pacific Gas and Electric.

Energy Commission Licensing Authority

The Energy Commission is responsible for reviewing and ultimately approving or denying all applications for construction and operation of thermal electric power plants, 50 MW and greater, proposed for construction in California. The Energy Commission's facility certification process carefully examines public health and safety, environmental impacts and engineering aspects of proposed power plants, and all related facilities such as electric transmission lines and natural gas and water pipelines. The Energy Commission is the lead agency under the California Environmental Quality Act (CEQA), and produces several environmental and decision documents rather than an Environmental Impact Report.

Summary of the California Energy Commission Staff's Conclusions

Based upon the information provided to date and the analysis completed to date for each technical section, staff has concluded that with implementation of staff's recommended mitigation measures described in the conditions of certification, all potential environmental impacts will be mitigated to a less than significant level. The project analysis complies with the requirements of the California Environmental Quality Act (CEQA). For a detailed review of potentially significant impacts and the related mitigation measures, please refer to each chapter of the SA.

Within the technical areas of **Air Quality, Biological Resources, Soil and Water Resources, Transmission System Engineering** and **Waste Management** additional analysis will be needed in regard to specific issues that are described in each section's summary of conclusions.

Staff also concludes that with implementation of staff's recommended mitigation measures described in the conditions of certification, the project would comply with all applicable laws, ordinances, regulations, and standards (LORS), with the exception of the **Soil and Water Resources** section.

The state has expressed a strong interest in developing its solar energy resources. However, the construction and operation of solar energy facilities requires the use of water, which state policy also protects. The Energy Commission must balance the state's interest in promoting solar energy development with its interest in conserving and protecting the state's water resources. Several projects currently proposed in the Mojave and Colorado deserts would use water for power plant cooling, which staff believes is contrary to the state's long term interest in maximizing solar power generation and minimizing adverse environmental impacts. This will be an especially critical issue in the renewable development areas that will be identified in the joint state/federal Renewable Energy Action Team's Desert Renewable Energy Conservation Plan (DRECP). Later this year, staff plans to file a request for an Energy Commission Order Instituting an Informational Proceeding to address the overall issue of water use by power plants. For a more detailed discussion of water policy and related LORS, see staff's technical analyses in the **Soil and Water Resources** section of the SA.

Public Resources, Contact Information and Additional Sources for Information

If you desire information on how to participate in the Energy Commission's review of the proposed project, please contact Jennifer Jennings, the Energy Commission's Public Adviser, at (916) 654-4489 or toll free in California at (800) 822-6228, or by email at: publicadviser@energy.state.ca.us.

To request special accommodations for those persons with disabilities, please contact Lourdes Quiroz, the Energy Commission's Equal Employment Opportunity Officer at lquiroz@energy.state.ca.us or by telephone (916) 654-5146. For those persons with limited English knowledge, request interpreter services by contacting the Project Manager, Craig Hoffman, at (916) 654-4781.

The status of the project, an electronic copy of the SA, copies of notices, and other relevant documents are also available on the Energy Commission's web site at:
<http://www.energy.ca.gov/sitingcases/abengoa>.

News media inquiries should be directed to Assistant Director, Susanne Garfield, at (916) 654-4989, or by email at: mediaoffice@energy.state.ca.us.

The SA will be available for review at the following San Bernardino County local libraries:

Barstow Branch Library
304 E. Buena Vista St.
Barstow, CA 92311

Adelanto Branch Library
11497 Bartlett Ave.
Adelanto, CA 92301

Victorville City Library
15011 Circle Dr.
Victorville, CA 92395

Kern County Library
Mojave Branch
16916 ½ Highway 14, Space D2
Mojave, CA 93501

Apple Valley Newton T. Bass
Branch Library
14901 Dale Evans Parkway
Apple Valley, CA 92307

Barstow Community College Library
2700 Barstow Road
Barstow, California 92311

Victor Valley College
18422 Bear Valley
Victorville CA 92392-5849

Copies are also available at the Energy Commission's Library in Sacramento, the California State Library in Sacramento, and at public libraries in Eureka, San Francisco, Los Angeles, Fresno, and San Diego. In addition, this information has been shared with those public agencies that would normally have jurisdiction but for the Energy Commission's exclusive authority to certify sites and related facilities.

If you would like a paper copy or CD of the SA, please fill out the enclosed form and return it to California Energy Commission, Attention: April Albright, Siting Project Assistant, at (916) 653-1640, or by e-mail at aalbright@energy.state.ca.us.

Sincerely,

Date: 3/16/10

Original signed by E. Allen for:
TERRENCE O'BRIEN, Deputy Director
Siting, Transmission and Environmental
Protection Division

Enclosure
Mailed to lists:
7285 - General
7286 - Property Owners

Please send me a paper copy / CD (circle one) of the California Energy Commission staff's Staff Assessment for the Abengoa Mojave Solar Application for Certification (09-AFC-5).

Name:

Address:

City/State/Zip:

FOLD HERE

California Energy Commission
Attention: April Albright
1516 Ninth Street, MS-15
Sacramento, CA 95814-5512

FOLD HERE

Staple or Tape closed.

SA WORKSHOP FOR ABENGOA MOJAVE SOLAR (09-AFC-5)

NOTICE OF PUBLIC WORKSHOP

Tuesday, April 6, 2010

Starting at 10:15 am

California Energy Commission
Fourth Floor North Conference Room A
1516 9th Street
Sacramento, CA 95814-5512

(Wheelchair Accessible)



SA WORKSHOP FOR ABENGOA MOJAVE SOLAR (09-AFC-5)


NOTICE OF PUBLIC WORKSHOP

Wednesday, April 7, 2010

Starting at 1:00 pm

**Barstow City Hall
220 E. Mountain View Street
Barstow, California 92311**

(Wheelchair Accessible)





**BEFORE THE ENERGY RESOURCES CONSERVATION AND DEVELOPMENT
COMMISSION OF THE STATE OF CALIFORNIA
1516 NINTH STREET, SACRAMENTO, CA 95814
1-800-822-6228 – WWW.ENERGY.CA.GOV**

**APPLICATION FOR CERTIFICATION
FOR THE *ABENGOA MOJAVE*
*SOLAR POWER PLANT***

APPLICANT

Emiliano Garcia Sanz
General Manager
Abengoa Solar Inc.
11500 West 13th Avenue
Lakewood, CO 80215
emiliano.garcia@solar.abengoa.com

Scott D. Frier
Chief Operating Officer
Abengoa Solar Inc.
13911 Park Ave., Ste. 206
Victorville, CA 92392
scott.frier@solar.abengoa.com

Tandy McMannes
2030 Addison Street, Suite 420
Berkeley, CA 94704
tandy.mcmannes@solar.abengoa.com

APPLICANT'S CONSULTANTS

Frederick H. Redell, PE
Engineering Manager
Abengoa Solar, Inc.
11500 West 13th Avenue
Lakewood, CO 80215
frederick.redell@solar.abengoa.com

COUNSEL FOR APPLICANT

Christopher T. Ellison
Ellison, Schneider & Harris
2600 Capitol Ave.
Sacramento, CA 95816
cte@eslawfirm.com

INTERESTED AGENCIES

California ISO
E-mail Preferred
e-recipient@caiso.com

***Docket No. 09-AFC-5*
PROOF OF SERVICE
(Revised 3/4/2010)**

INTERVENORS

California Unions for Reliable Energy ("CURE")
Tanya A. Gulesserian
Marc D. Joseph
Elizabeth Klebaner
Adams Broadwell Joseph & Cardozo
601 Gateway Boulevard, Suite 1000
South San Francisco, CA 94080
E-mail Preferred
tgulesserian@adamsbroadwell.com
eklebaner@adamsbroadwell.com

Luz Solar Partners Ltd., VIII
Luz Solar Partners Ltd., IX
Jennifer Schwartz
700 Universe Blvd
Juno Beach, FL 33408
jennifer.schwartz@nexteraenergy.com

ENERGY COMMISSION

***ANTHONY EGGERT**
Commissioner and Presiding Member
aeggert@energy.state.ca.us

JAMES D. BOYD
Vice Chairman and Associate Member
jboyd@energy.state.ca.us

Paul Kramer
Hearing Officer
pkramer@energy.state.ca.us

Craig Hoffman
Project Manager
choffman@energy.state.ca.us

Christine Hammond
Staff Counsel
chammond@energy.state.ca.us

Jennifer Jennings
Public Adviser's Office
publicadviser@energy.state.ca.us

DECLARATION OF SERVICE

I, April Albright, declare that on March 17, 2010, I served and filed copies of the attached Library Letter for; Request for Agency Comments on; and Notice of Availability of the Staff Assessment. The original document, filed with the Docket Unit, is accompanied by a copy of the most recent Proof of Service list, located on the web page for this project at: [\[http://www.energy.ca.gov/sitingcases/abengoa/index.html\]](http://www.energy.ca.gov/sitingcases/abengoa/index.html).

The document has been sent to both the other parties in this proceeding (as shown on the Proof of Service list) and to the Commission's Docket Unit, in the following manner:

(Check all that Apply)

For service to all other parties:

- ☒ sent electronically to all email addresses on the Proof of Service list;
- ☒ by personally delivery;
- ☒ by delivery on this date, for mailing with the United States Postal Service with first-class postage thereon fully prepaid, to the name and address of the person served, for mailing that same day in the ordinary course of business; that the envelope was sealed and placed for collection and mailing on that date to those addresses **NOT** marked "email preferred."

AND

For filing with the Energy Commission:

- ☒ **sending an original paper copy and one electronic copy, mailed and emailed respectively, to the address below (preferred method);**

OR

☐ depositing in the mail an original and 12 paper copies, as follows:

CALIFORNIA ENERGY COMMISSION

Attn: Docket No. 09-AFC-5
1516 Ninth Street, MS-4
Sacramento, CA 95814-5512
docket@energy.state.ca.us

I declare under penalty of perjury that the foregoing is true and correct, that I am employed in the county where this mailing occurred, and that I am over the age of 18 years and not a party to the proceeding.

Original signed by: _____
April Albright



BEFORE THE ENERGY RESOURCES CONSERVATION AND DEVELOPMENT
COMMISSION OF THE STATE OF CALIFORNIA
1516 NINTH STREET, SACRAMENTO, CA 95814
1-800-822-6228 – WWW.ENERGY.CA.GOV

**APPLICATION FOR CERTIFICATION FOR THE
ABENGOA MOJAVE SOLAR PROJECT**

DOCKET No. 09-AFC-5

**NOTICE OF AVAILABILITY OF THE PRESIDING MEMBER'S PROPOSED DECISION
AND
NOTICE OF COMMITTEE CONFERENCE
AND
NOTICE OF FULL COMMISSION HEARING**

I. NOTICE OF AVAILABILITY

On August 6, 2010, the Committee issued the Presiding Member's Proposed Decision (PMPD) for the **ABENGOA MOJAVE SOLAR PROJECT**. The 30-day public comment period on the PMPD ends on September 6, 2010. Copies of the PMPD have been sent to the Proof of Service list. The PMPD may also be viewed on the Commission's internet website at: [www.energy.ca.gov/sitingcases/abengoa].

For a printed copy, call the Energy Commission's Publications Unit at 916-654-5200, and ask for Publication No. **CEC 800-2010-008-PMPD**.

The parties in the case shall file and serve their written comments on the PMPD to the Proof of Service list and via e-mail **no later than 3 p.m. on September 6, 2010**.

II. NOTICE OF COMMITTEE CONFERENCE

PLEASE TAKE NOTICE that the Committee will hold a Committee Conference on the PMPD as follows:

**MONDAY, AUGUST 23, 2010
Beginning at 1:00 p.m.**

**California Energy Commission
Hearing Room B
1516 Ninth Street
Sacramento, CA 95814**

TELECONFERENCE OPTION: *You may participate in the Committee Conference by telephone and/or by computer via our "WebEx" web conferencing system. For details on how to participate, please see the "Participation through WebEx" directions attached to this Notice.*

Comments on the PMPD

The purpose of the Committee Conference is to consider oral and written comments on the PMPD from the parties, governmental agencies, and members of the public. The parties in the case shall file and serve their written comments on the PMPD to the Proof of Service list and via e-mail **no later than 3 p.m. on September 6, 2010.**

Members of the public and governmental agency representatives are encouraged to submit their written comments by the close of the 30-day review period. The Energy Commission encourages comments by e-mail. Please include your name or organization's name in the name of the file. Those submitting attached comments by electronic mail should provide them in either Microsoft Word format or as a Portable Document (.pdf) to [**docket@energy.state.ca.us**]. **One paper copy** must also be sent to the Energy Commission's Docket Unit, 1516 Ninth Street, MS-4, Sacramento, CA 95814. Identify all comments with "**Docket No. 09-AFC-5.**"

III. NOTICE OF COMMISSION HEARING

PLEASE TAKE NOTICE the full Commission will consider the PMPD, released on August 6, 2010, and the Errata, if applicable, for possible adoption as follows:

WEDNESDAY, September 8, 2010
Beginning at 10 a.m.

California Energy Commission
Hearing Room A
1516 Ninth Street
Sacramento, California 95814

The purpose of this hearing is to consider whether the Energy Commission should adopt, modify, or reject the PMPD. Parties and members of the public may participate and offer oral and written comments on the PMPD. Identify all comments with "**Docket No. 09-AFC-5.**"

Participating by Telephone at a Business Meeting

If you want to participate by telephone, call toll free 1-888-823-5065 on Business Meeting days after 10:01 a.m. (PDT). When asked, please answer "Business Meeting and Mr. Jerome Lee" and the operator will connect you into the meeting. Should you want to speak on a specific item, please inform the operator and provide the item number. The Business Meeting is also broadcast via **WebEx**, the Energy Commission's on-line meeting service. To listen to the meeting and view any presentations, please click the following link or paste it into your browser:

<https://energy.webex.com/energy/onstage/g.php?t=a&d=928463379>

You may also go to <https://energy.webex.com/ec> and enter Meeting Number **928 463 379**. The meeting password is "mtg@10am."

Public Participation

The Energy Commission's Public Adviser's Office is available to assist the public in participating in the application review process. For information on how to participate, please contact the Public Adviser's Office at (916) 654-4489 or (800) 822-6228 or by e-mail: **[publicadviser@energy.state.ca.us]**.

If you have a disability and need assistance to participate in this event, contact Lourdes Quiroz at (916) 654-5146 or e-mail: **[lquiroz@energy.state.ca.us]**. Media inquiries should be directed to the Office of Media and Public Communications at (916) 654-4989 or e-mail: **[mediaoffice@energy.state.ca.us]**.


Questions of a legal or procedural nature should be directed to Kourtney Vaccaro, the Hearing Officer, at (916) 654-4328 or e-mail: **[kvaccaro@energy.state.ca.us]**.

Technical questions concerning the Project should be addressed to Craig Hoffman, the Staff Project Manager, at (916) 654-4781, or by e-mail: **[choffman@energy.state.ca.us]**.

Media inquiries should be directed to the Energy Commission's Office of Media and Communications at (916) 654-4989 or e-mail: **[mediaoffice@energy.state.ca.us]**.

Information concerning the status of the project, as well as notices and other relevant documents, including the AFC, may be viewed on the Energy Commission's Internet web page at: **[www.energy.ca.gov/sitingcases/abengoa]**.

Dated: August 6, 2010, at Sacramento, California.



ANTHONY EGGERT
Commissioner and Presiding Member
Abengoa Mojave AFC Committee



JAMES D. BOYD
Vice Chair and Associate Member
Abengoa Mojave AFC Committee

**PARTICIPATION IN THE COMMITTEE CONFERENCE THROUGH WEBEX
THE ENERGY COMMISSION'S ON-LINE MEETING SERVICE**

1. COMPUTER LOG-ON WITH A DIRECT PHONE NUMBER:

- Please go to <https://energy.webex.com> and enter the **meeting number** unique to the specific hearing date:
- 8/23/10 meeting number: **925 188 458**
- When prompted, enter your information and the **meeting password**: **abengoa#2**

After you login, a prompt will appear on-screen for you to provide **your** phone number. In the **Number box**, type your area code and phone number and click OK. **You will receive a call back on your phone for the audio of the meeting.** International callers can use the "Country/Region" button to help make their connection.

2. COMPUTER LOG-ON FOR CALLERS WITH AN EXTENSION PHONE NUMBER, ETC:

- Please go to <https://energy.webex.com> and enter the **unique meeting number**:
- 8/23/10 - meeting number: **925 188 458**
- When prompted, enter your information and the **meeting password**: **abengoa#2**
- *After you login, a prompt will ask for your phone number. Click "CANCEL."*
- **Instead** call 1-866-469-3239 (toll-free in the U.S. and Canada). When prompted, enter the meeting number above and your unique Attendee ID number which is listed in the top left area of your screen after you login.

3. TELEPHONE ONLY (NO COMPUTER ACCESS):

- Call **1-866-469-3239** (toll-free in the U.S. and Canada) and when prompted enter the **meeting number**:
- 8/23/10 - meeting number: **925 188 458**

If you have difficulty joining the meeting, please call the WebEx Technical Support number at 1-866-229-3239. To see if your computer is compatible, visit [\[http://support.webex.com/support/system-requirements.html\]](http://support.webex.com/support/system-requirements.html).

Please be aware that the meeting's WebEx audio and on-screen activity may be recorded.

Mailed to lists: POS, 7361, 7362, 7363, 7364

Meeting Transcripts

Full transcripts can be found at:

<http://www.energy.ca.gov/sitingcases/abengoa/documents/>

INFORMATIONAL HEARING, SITE VISIT and
ENVIRONMENTAL SCOPING MEETING

BEFORE THE
CALIFORNIA ENERGY RESOURCES CONSERVATION
AND DEVELOPMENT COMMISSION

In the Matter of:)
)
Application for Certification for) Docket No.
the Abengoa Mojave Solar Project) 09-AFC-5
)
_____)

BARSTOW CITY HALL
220 E. MOUNTAIN VIEW STREET
BARSTOW, CALIFORNIA 92311

WEDNESDAY, DECEMBER 9, 2009

3:26 p.m.

Reported: Martha Nelson
Transcribed: Margo D. Hewitt, CET**00480
Contract No. 170-08-001

PETERS SHORTHAND REPORTING CORPORATION (916) 362-2345

COMMITTEE MEMBERS PRESENT

Julia Levin, Presiding Member

James Boyd, Associate Member

HEARING OFFICER AND ADVISORS

Paul Kramer, Hearing Officer

Sarah Michael, Advisor

Susannah Churchill, Advisor

STAFF AND CONSULTANTS PRESENT

Christine Hammond, Staff Attorney

Craig Hoffman, Project Manager

PUBLIC ADVISER

Loreen McMahon

James Davis

APPLICANT

Christopher T. Ellison, Attorney
Ellison, Schneider and Harris, LLP

Frederick Redell, Project Manager

Scott Frier, Chief Operating Officer
Abengoa Solar, Inc.

INTERVENOR

Elizabeth Klebaner, Attorney
Adams, Broadwell, Joseph and Cardozo
representing California Unions for Reliable Energy

ALSO PRESENT

Jeanette Hayhurst
City of Barstow

Scott Lisk

PETERS SHORTHAND REPORTING CORPORATION (916) 362-2345

I N D E X

	Page
Proceedings	1
Opening Remarks	1
Introductions	1
Background and Overview	6
Presentations	7
Hearing Officer	7
Public Adviser	15
Applicant	26/38
CEC Staff	55
Issues Identification Report	62
Proposed Schedule	63
California Unions for Reliable Energy	67
Schedule Discussion	68
Public Comment	80
Closing Remarks	99
Associate Member Boyd	99
Presiding Member Levin	99
Adjournment	99
Reporter/Transcriber Certificates	100

PREHEARING CONFERENCE
BEFORE THE
CALIFORNIA ENERGY RESOURCES CONSERVATION
AND DEVELOPMENT COMMISSION

In the Matter of:)
Application for Certification) Docket No. 09-AFC-5
For The Abengoa Mojave Solar)
Project)
-----)

CALIFORNIA ENERGY COMMISSION
HEARING ROOM B
1516 NINTH STREET
SACRAMENTO, CALIFORNIA

MONDAY, JUNE 21, 2010

1:15 P.M.

JAMES F. PETERS CSR, RPR
CERTIFIED SHORTHAND REPORTER
LICENSE NUMBER 10063

Contract No. 170-09-002

APPEARANCES

COMMITTEE MEMBERS

Anthony Eggert, Presiding Member

HEARING OFFICERS, ADVISERS

Kourtney Vaccaro, Hearing Officer

Lorraine White, adviser to Commissioner Anthony Eggert

Sarah Michael, adviser to Commissioner James D. Boyd

STAFF

Christine J. Hammond, Senior Staff Counsel

Craig Hoffman, Project Manager

APPLICANT

Gregory L. Wheatland, Esq.
Ellison, Schneider & Harris, LLP

Shane E. Conway, Esq.
Ellison, Schneider & Harris, LLP

Tandy McMannes
Abengoa Solar

Frederick Redell
Abengoa Solar

Matt Stucky
Abengoa Solar

INTERVENOR: CURE

Elizabeth Klebaner, Esq.
Adams Broadwell Joseph & Cardozo

INTERVENOR: COUNTY OF SAN BERNARDINO

Bart Brizee, Deputy County Counsel

APPEARANCES CONTINUED

ALSO PRESENT

James Brathovde
Lahontan Regional Water Quality Control Board

<u>INDEX</u>	<u>PAGE</u>
Opening remarks by Presiding Member Eggert	1
Introductions	1
Opening Remarks by Hearing Officer Vaccaro	4
Discussion of Topics not Ready for Hearing	7
Discussion of Topics Ready and Not Disputed	15
Project Description	15
Biological Resources	22
Hazardous Materials Management	24
Land Use	26
Socioeconomic Resources	26
Soil & Water	29
Traffic & Transportation	40
Worker Safety & Fire Protection	41
Discussion of Time Table	57
Closing Remarks by Presiding Member Eggert	68
Adjournment	70
Reporter's Certificate	71

PRESIDING MEMBER'S PROPOSED DECISION
BEFORE THE
CALIFORNIA ENERGY RESOURCES CONSERVATION
AND DEVELOPMENT COMMISSION

APPLICATION FOR)	
CERTIFICATION)	
)	
Abengoa Mojave)	
Solar Project)	Docket No.
)	09-AFC-5
_____)	

CALIFORNIA ENERGY COMMISSION

1516 9TH STREET

HEARING ROOM B

SACRAMENTO, CALIFORNIA

MONDAY, AUGUST 23, 2010

1:05 P.M.

TIFFANY C. KRAFT, CSR, RPR
CERTIFIED SHORTHAND REPORTER
LICENSE NUMBER 12277

EHLERT BUSINESS GROUP (916) 851-5976

APPEARANCES

COMMITTEE MEMBERS PRESENT

Anthony Eggert, Commissioner, Presiding Member

James D. Boyd, Vice Chair, Associate Member

HEARING OFFICER

Kourtney Vaccaro

ADVISORS

Sarah Michael

Lorraine White

STAFF AND CONSULTANTS PRESENT

Christine Hammond, Counsel

Craig Hoffman, Project Manager

Jennifer Jennings, Public Advisor

Alvin Greenburg, (telephonic)

APPLICANT

Ellison, Schneider & Harris, LLP

Christopher Ellison

Shane E. Conway

Abengoa Solar

Matt Stucky

Scott Frier

APPEARANCES (continued)

LOCAL GOVERNMENT

County of San Bernardino
Bart Brizzee
Peter Brierty
(via telephone)

EHLERT BUSINESS GROUP (916) 851-5976

INDEX

	Page
1. Call to Order	1
2. Applicant Comments	4
3. Staff Comments	7
4. County Comments	7
 Adjournment	 17
Reporter's Certificate	18

APPENDIX B

INTERCONNECTION SYSTEM IMPACT STUDY

Interconnection System Impact Study

Generation Interconnection

Harper Lake, LLC.

Harper Lake Solar Plant Project



California ISO
Your Link to Power

June 27, 2008

**This study has been completed in coordination with Southern California Edison
per the Large Generator Interconnection Procedures**

EXECUTIVE SUMMARY

Harper Lake, LLC (“HLLC”) applied to the California Independent System Operator (“CAISO”) for interconnection of the proposed Harper Lake Solar Plant Project (“HLSP Project”) pursuant to section 3.5 of the Large Generator Interconnection Procedures (“LGIP”) issued under the CAISO Tariff. The HLSP Project, a solar thermal generating facility to be located in Hinkley, California (San Bernardino County), approximately twelve miles east of Kramer Junction and just west of Harper Lake, will have a maximum net plant output of 250 MW. The HLSP Project will consist of two solar concentrated Siemens steam turbines and associated 230/13.8 kV generator transformers. HLLC proposes to interconnect the HLSP Project into the SCE electrical system and deliver energy and/or ancillary services to the California Independent System Operator (“CAISO”) Controlled Grid utilizing the existing Kramer-Cool Water No.1 230 kV radial transmission line. To interconnect the HLSP Project into the existing Kramer-Cool Water No.1 230 kV transmission line, a new substation will be needed. This substation (referred to in this study as “Hinkley”¹) is to be located approximately 12.5 miles east from the existing Kramer Substation and approximately 31.7 miles northwest of the existing Cool Water Substation. The substation will also be needed to accommodate queued behind generation projects and will allow SCE the ability to loop the existing Kramer-Cool Water No.1 230 kV transmission line and provide for the required generation tie-line position. The HLSP Project’s requested in-service date is January 1, 2010, with a commercial operation date of August 1, 2010.

SCE has performed the Interconnection System Impact Study (ISIS) to determine the adequacy of SCE’s electrical system, including that portion of SCE’s electrical system that is part of the CAISO Controlled Grid, to accommodate the HLSP Project. The Study was performed for two system conditions: a 2013 heavy summer with a one-in-ten load forecast and a 2013 light spring load forecast (65% of the heavy summer load). These conditions reflect the most critical expected loading condition for the transmission system in SCE’s service area. The study included all queued ahead generation projects in the study area ahead of the HLSP Project regardless of the in-service dates of such prior projects. The system load condition assumptions were based on the latest in-service date of all queued ahead projects. In addition to the 2013 year cases, SCE performed a sensitivity study to evaluate if the project could interconnect in advance of implementing any transmission facility upgrades, which have been identified to be triggered by a queued ahead generation project. Such sensitivity was conducted as a means of providing HLLC with the information required to evaluate the risk of congestion exposure while the facility upgrades are being implemented.

Results of the ISIS will be used as the basis to determine appropriate project cost allocation for facility upgrades in the Facilities Study. ***The study accuracy and results of the assessment of system adequacy are contingent on the accuracy of the technical data provided by HLLC.*** Any changes from the data provided could void the study results. The ISIS report provides detailed study assumptions and conditions of the system in which the ISIS was conducted.

¹ The final name of the substation is subject to change once SCE finalizes the substation name evaluation efforts.

Please be aware that a restudy may be required to reflect the system configuration if a higher queued generation or transmission project that was modeled in the system impact study withdraws or is modified in accordance with applicable tariff allowances.

CONCLUSION

To interconnect the HLSP Project in a manner that addresses the generation needs in the area, avoids short-lived “piece-meal” solutions, minimizes environmental impacts, minimizes overall cost exposure to rate-payers, minimizes service interruptions, minimizes the need for generation curtailments while upgrades are implemented, and provides the minimum set of facilities for the HLSP Project, thus minimizing upfront cost responsibility, the following upgrades are required:

1. Construction of a new breaker-and-a-half 230 kV Substation (Hinkley Substation), with a four bay position switchrack,² equipping only two positions with a total of five circuit breakers.
2. Installation of appropriate fully redundant and diverse telecommunication facilities to provide overall system protection.

Based on the study results, the existing SCE transmission facilities with only the above minimum set of facility upgrades required to interconnect the HLSP Project are not adequate to accommodate the HLSP Project when considering all other generation projects queued ahead.

Power Flow

Without implementing any of the transmission upgrades identified to be triggered by the queued ahead projects, the existing system does not have sufficient transmission capability to deliver the total output of all queued generation projects up to and including the HLSP Project. Severe problems were identified under both heavy summer and light spring load conditions that resulted in a base case which would not solve due to voltage levels in the Lugo Area that would be well below acceptable limits. Consequently, a number of upgrades will be necessary to reliably interconnect and deliver the HLSP Project output as discussed below.

BASE CASE CONDITIONS

To mitigate problems triggered by queued ahead projects requesting interconnection along the Lugo-Pisgah corridor or to the Pisgah 230 kV Substation and along the Lugo-Victor-Kramer-Control corridor, the following transmission upgrades previously identified to be triggered by such queued ahead projects were included in the initial studies:

- Expansion of the existing SCE Pisgah 230 kV Substation to include 500 kV facilities.

² Standard SCE bus structures provide for up to four bay positions, but only the required bays will be equipped as part of the HLSP Project.

- Removal of the existing Lugo-Pisgah No. 2 230 kV transmission line and replacement with a new Lugo-Pisgah 500 kV transmission line.³
- Looping of the existing Eldorado-Lugo 500 kV transmission into the new 500 kV Pisgah Substation.
- Looping of the existing Lugo-Pisgah No. 1 230 kV transmission line into 3 new substations (Desert View, Abelia and Galway) forming new Lugo-Desert View 230 kV, Abelia-Desert View 230 kV (normally open), Abelia-Galway 230 kV, and Pisgah-Galway 230 kV transmission lines.
- Construction of a third Lugo-Victor 230 kV transmission line.
- Installation of the 3rd Lugo 500/230 kV transformer bank.

With the addition of the HLSP Project and all previously identified transmission upgrades, new base case overload problems were identified. Specifically, the HLSP Project triggers the following impacts:

Summer Load Conditions

Kramer-Lugo No.1 and No.2 230 kV Transmission Lines (85.4% → 106.5%)

Spring Load Conditions

Kramer-Lugo No.1 and No.2 230 kV Transmission Lines (97.2% → 118.7%)

To mitigate these base case overload problems, additional transmission will be required to increase the transfer capability south of Kramer Substation. Such increase in transmission capability south of Kramer Substation can best be provided by the following:

- Construction of a new Cool Water-Desert View double-circuit 230 kV transmission line with the installation of one initial circuit.

SINGLE OUTAGE CONTINGENCY (N-1)

Without the above additional facility upgrades in place to mitigate the identified base case overload problems, the study determined that the system is also inadequate to accommodate the full output of the HLSP Project under specific single outage contingencies. Because the HLSP Project results in increasing power flows on transmission facilities that are currently monitored as part of existing Kramer SPS (loss of the Lugo-Kramer No.1 or No.2 230 kV transmission lines), the HLSP Project will need to be added to the existing Kramer SPS if the additional transmission upgrades identified to mitigate the base case overloads are not implemented. The addition of the HLSP Project to the Kramer SPS will increase the amount of generation

³ New right-of-way would be required west of the Mojave River to support a new 500 kV transmission line. A potential line routing alternative for this upgrade involves the use of existing right-of-way between the Mojave River and the Lugo Substation by removing both the existing Lugo-Pisgah No.1 and No.2 230 kV transmission lines and the construction of a new double-circuit 500 kV transmission line. One of the new 500 kV circuits would be used to connect to Pisgah and the other 500 kV circuit would be initially operated at 230 kV and connected to Desert View.

participating in the Kramer SPS from 863 MW to 1,113 MW. The actual amount of generation armed and tripped under the outage condition will be determined by the amount of power flow on the two Kramer-Lugo 230 kV transmission lines prior to the outage.

With the base case facility upgrades in place, the study determined that an SPS will still be needed to mitigate thermal and transient stability problems under loss of the Cool Water-Desert View and Lugo-Desert View 230 kV transmission lines. Outage of these lines results in loading the existing Kramer-Lugo No.1 and No.2 230 kV transmission lines as follows:

Overloaded Facility	Rating	Heavy Summer		Light Spring	
		Pre	Post	Pre	Post
Kramer-Lugo No.1 and No.2 230 kV T/Ls Loss of Cool Water-Desert View 230 kV T/L	1240 Amps (N) 1425 Amps (E)	N/A	106.5% 92.3%	N/A	118.7% 102.9%
Kramer-Lugo No.1 and No.2 230 kV T/Ls Loss of Lugo-Desert View 230 kV T/L	1240 Amps (N) 1425 Amps (E)	N/A	124.0% 107.4%	N/A	136.4% 118.3%

Under the loss of the Cool Water-Desert View 230 kV transmission line, the SPS should trip one of the HLSP generation units. Under the loss of the Lugo-Desert View 230 kV transmission line, the SPS should trip one of the HLSP generation units, as well as the generation projects directly connected to the Desert View Substation. Transfer tripping the generation projects directly connected to the Desert View Substation would not result in increasing the outage exposure of these projects, because the Desert View Substation would be connected in a radial fashion prior to adding the Cool Water-Desert View 230 kV transmission line. Such radial method of service would result in disconnecting from the source (Lugo Substation) without a second source line.

DOUBLE OUTAGE CONTINGENCY (N-2)

Without the above additional facility upgrades in place to mitigate the identified base case overload problems, the study determined that the system is also inadequate to accommodate the full output of the HLSP Project under specific double outage contingencies. The HLSP Project will need to be added to the existing Kramer SPS (loss of the Lugo-Kramer No.1 and No.2 230 kV transmission lines) if the additional transmission upgrades identified to mitigate the base case overloads are not implemented.

With the inclusion of the additional upgrades identified for mitigating the HLSP Project triggered base case thermal overloads, the study did not identify any N-2 thermal overload or transient stability problems for the local area. However, on an overall system level, the study determined that the total amount of Lugo Area generation export (South of Lugo and the Lugo-Vincent 500 kV transmission lines) is limited to approximately 7,800 MW. With the addition of more generation resources, in the North and East of Lugo areas, the amount of excess generation requiring export will eventually exceed 7,800 MW. To increase Lugo Area export limits, additional transmission capacity will be required. However, such requirement is not triggered solely by the addition of the HLSP Project, and therefore, such facility upgrades will be

evaluated and recommended as part of a larger study effort in the area (either through the RETI study process or the annual CAISO Transmission Expansion Planning Process).

Transient Stability

The study determined that with the inclusion of the additional upgrades identified for mitigating the HLSP Project triggered base case thermal overloads, the HLSP Project would not need to participate in the existing Kramer SPS. However, the study also identified that the tripping requirements for mitigating transient stability problems under the single line outage of the Lugo-Desert View 230 kV transmission line are more stringent than the tripping requirements for mitigating thermal overloads. Therefore, under this single line outage, an SPS will be required to trip the entire HLSP Project to mitigate transient stability problems identified in the ISIS.

Post-Transient Voltage

The study determined that without the facility upgrades identified under base case conditions, the HLSP Project aggravates previously identified voltage problems, including case non-convergence, which are indicative of a potential voltage collapse. The inclusion of the facility upgrades identified for queued ahead generation projects mitigate these problems.

Short-Circuit Duty

The short-circuit duty (SCD) analysis included all queued ahead generation projects, based on their application date, but did not model the corresponding transmission upgrades. The three-phase-to-ground short-circuit duty study identified two 500 kV, seven 230 kV, and four 115 kV substation locations requiring engineering review. The single-line-to-ground short circuit duty study identified two 500 kV, five 230 kV, and one 115 kV substation where duty was increased by more than 0.1 kA, and duty was in excess of 60% of the minimum circuit breaker rating.

Based on the SCD study results and engineering review, the addition of the HLSP Project triggers the need for circuit breaker replacement at the Kramer Substation. It should be noted that a number of projects have recently withdrawn from the interconnection queue or have modified technical parameters consistent with allowances under the LGIP. In addition, the transmission upgrades identified to mitigate the HLSP Project triggered base case overloads have not been included into the short-circuit duty analysis. Consequently, a reevaluation of short-circuit duty will be required as part of the Facilities Study to capture the recent generation interconnection queue withdrawals and modifications, as well as the facility upgrades associated with the mitigation plan identified in this analysis.

Deliverability Assessment

Separate studies entitled “Deliverability Assessments” were performed by the CAISO, which determined that the HLSP Project was not deemed deliverable to the Grid for Resource Adequacy (RA) purposes. The modeling assumptions for the Deliverability Assessment are different from the ones in this System Impact Study. For the details of the methodology and assumptions for Deliverability Assessment, please refer to the Baseline Generation Deliverability

Study – 2007 Q3 Study Plan posted at <http://www.caiso.com/1c44/1c44b5c31cce0.html>. In particular, the 2007 Q3 Deliverability Assessment modeled the following transmission upgrades:

- Lugo 500/230 kV No.3 Transformer Bank (AA-Bank)
- Kramer-Lugo No.3 230 kV Transmission Line⁴
- Victor-Lugo No.3 230 kV Transmission Line
- Replacement of the Lugo-Pisgah No.2 230 kV with a new 500 kV Transmission Line
- Operation of the remaining Lugo-Pisgah 230 kV line as two radial lines
 - Radial into Lugo connecting the new Desert View Substation
 - Radial into Pisgah connecting the new Abelia and new Galway Substations

The study did not include the new Cool Water-Desert View 230 kV transmission line(s) recommended in this study to mitigate the identified base case thermal overloads on the two Kramer-Lugo 230 kV transmission lines.

Cost Estimates

The ***Nonbinding*** Cost Estimate for the interconnection facilities and reliability network upgrades triggered by the HLSP Project is \$131.7⁵ million. The ***Nonbinding*** Cost Estimate for the maximum exposure for network upgrades triggered by queued ahead projects is \$257.0⁶ million. These estimates have been developed without detailed cost engineering and will be refined in the Facilities Study.

Facilities Study

A Facilities Study will be required for the HLSP Project. The Facilities Study will include detailed cost estimates for SCE network upgrades and direct assignment interconnection facilities required to interconnect the HLSP Project to the grid and should provide the following:

1. Develop cost estimates and schedule for the construction of a new Hinkley Substation to loop the existing Cool Water-Kramer No.1 230 kV transmission line. The Substation should consist of initially a 230 kV four-bay position with five circuit breakers to interconnect the project. (Case A).
2. Develop cost estimates and schedule for the looping of the existing Cool Water-Kramer 230 kV transmission line into the new Hinkley Substation (Case A).

⁴ SPS was not modeled due to unknown specifications. With SPS and the additional Kramer-Lugo No.3 230 kV Transmission Line, the HLSP Project would be deemed deliverable.

⁵ This cost estimate can increase to \$227.2 million (excluding right-of-way for Cool Water-Desert View 230 kV transmission line) depending on the final routing alternative selected for queued ahead generation triggered reliability upgrades.

⁶ This cost estimate can decrease to \$216.3 million (excluding right-of-way) depending on the final routing alternative selected for queued ahead generation triggered reliability upgrades.

3. Develop cost estimate and schedule for the protection and telecom requirements to support the new Hinkley Substation (Case A).
4. Develop cost estimates and schedule for the construction of a new Desert View substation to loop the existing Lugo-Pisgah No.2 230 kV transmission line. The Substation would be sized for 500/230/115 kV facilities and would be capable of ultimately accommodating four 500/230 kV transformer banks, but would initially be equipped with eight 230 kV bay positions (Second four-bay position - Case A, Initial four-bay position - Case B) and 13 circuit-breakers (Two are Case A, five are Case B, two are future, and remaining four are generation direct assignment).
5. Develop cost estimates and schedule for the removal of approximately 16 miles of existing Lugo-Pisgah No.1 230 kV transmission line between Lugo and proposed Desert View Substation (Case B).
6. Develop cost estimates and schedule for the construction of a new 16-mile double-circuit 500 kV Lugo-Desert View transmission line with one circuit energized at 500 kV and the second circuit initially energized at 230 kV (Case B).
7. Develop cost estimate and schedule for the protection and telecom requirements to support the new Desert View Substation (Case B).
8. Develop cost estimates and schedule for the installation of the third Lugo 500/230 kV transformer bank (Case B).
9. Develop cost estimates and schedule for the construction of a third Lugo-Victor 230 kV transmission line (Case B).
10. Develop cost estimates and schedule for the construction of a new 37-mile double-circuit 230 kV Cool Water-Desert View transmission line (2B-1590 ACSR) with one initial circuit (Case A).
11. Develop cost estimate and schedule for SPS required to trip HLSP under two specific single outage contingencies (Case A).
12. Review identified substation locations shown in Table 2-4 through Table 2-7 to evaluate the need for circuit breaker replacements and develop corresponding cost estimates.
13. Perform any technical assessment required to account for potential queued ahead generation project withdrawals (CAISO #109, #110, #114, #115, #116, and #120) consistent with the CAISO Petition for Waiver of Tariff Provisions to Accommodate Transition to Reformed Large Generator Interconnection Procedures, and Motion to Shorten Comment Period FERC Filing, if approved at FERC.
14. SCE and the CAISO to determine the appropriate classification of the identified Network Upgrades (i.e. Reliability Network Upgrades versus Delivery Network Upgrades).

CONTENTS

EXECUTIVE SUMMARY	ii
I. INTRODUCTION	1
II. STUDY CONDITIONS AND ASSUMPTIONS	2
A. Planning Criteria.....	2
B. Generation and Load Assumptions	4
C. HLLLC – Harper Lake Solar Project	8
D. Transmission Upgrades Included in the HLSP Base Cases	13
E. Existing Special Protection Systems	15
F. Power Flow Study	16
G. Transient Stability Study	18
H. Post-Transient Voltage Study	20
I. Short-Circuit Duty Study.....	20
J. Deliverability Assessment	21
K. Cost Estimates	21
L. Timelines for Implementing Facility Upgrades	22
III. GENERATOR ELECTRIC GRID FAULT RIDE-THROUGH CAPABILITY CRITERIA AND POWER FACTOR CRITERIA.....	22
IV. STUDY RESULTS	23
A. Power Flow Analysis.....	23
B. Transient Stability Analysis	38
C. Post-Transient Stability Analysis	39
D. Short Circuit Duty Study	39
E. Deliverability Assessment	42
V. COST ESTIMATES	43
VI. ESTIMATED PROJECT TIMELINES	45
VII. CONCLUSIONS	45

APPENDIX A – HEAVY SUMMER TRANSIENT STABILITY PLOTS

APPENDIX B – LIGHT SPRING TRANSIENT STABILITY PLOTS

HARPER LAKE, LLC. HARPER LAKE SOLAR PLANT PROJECT

SYSTEM IMPACT STUDY

June 27, 2008

I. INTRODUCTION

Harper Lake, LLC (“HLLC”) applied to the California Independent System Operator (“CAISO”) for interconnection of the proposed Harper Lake Solar Plant Project (“HLSP Project”) pursuant to section 3.5 of the Large Generator Interconnection Procedures (“LGIP”) issued under the CAISO Tariff. The HLSP Project, a solar thermal generating facility to be located in Hinkley, California (San Bernardino County), approximately twelve miles east of Kramer Junction and just west of Harper Lake, will have a maximum net plant output of 250 MW. The HLSP Project will consist of two solar concentrated Siemens steam turbines and associated 230/13.8 kV generator transformers. HLLC proposes to interconnect the HLSP Project into the SCE electrical system and deliver energy and/or ancillary services to the California Independent System Operator (“CAISO”) Controlled Grid utilizing the existing Kramer-Cool Water No.1 230 kV radial transmission lines. To interconnect the HLSP Project into the existing Kramer-Cool Water No.1 230 kV transmission line, a new substation will be needed. This substation (referred to in this study as “Hinkley”⁷) is to be located approximately 12.5 miles east from the existing Kramer Substation and approximately 31.7 miles northwest of the existing Cool Water Substation. The substation will also be needed to accommodate queued behind generation projects and will allow SCE the ability to loop the existing Kramer-Cool Water No.1 230 kV transmission line and provide for the required generation tie-line position. The HLSP Project’s requested in-service date is January 1, 2010, with a commercial operation date of August 1, 2010.

SCE has performed the Interconnection System Impact Study (ISIS) to determine the adequacy of SCE’s electrical system, including that portion of SCE’s electrical system that is part of the CAISO Controlled Grid, to accommodate the HLSP Project. The Study was performed for two system conditions: a 2013 heavy summer with a one-in-ten load forecast and a 2013 light spring load forecast (65% of the heavy summer load). These conditions reflect the most critical expected loading condition for the transmission system in SCE’s area. The study included all queued ahead generation projects in the study area ahead of the HLSP Project regardless of the in-service dates of such prior projects. The system load condition assumptions were based on the latest in-service date of all queued ahead projects. In addition to the 2013 year cases, SCE performed a sensitivity study to evaluate if the project could interconnect in advance of implementing any transmission facility upgrades which have been identified to be triggered by a queued ahead generation project. Such sensitivity was conducted as a means of providing HLLC with the information required to evaluate the risk of congestion exposure while the facility upgrades are being implemented.

⁷ The final name of the substation is subject to change once SCE finalizes the substation name evaluation efforts.

Results of the ISIS will be used as the basis to determine appropriate project cost allocation for facility upgrades in the Facilities Study. ***The study accuracy and results of the assessment of system adequacy are contingent on the accuracy of the technical data provided by HLLLC.*** Any changes from the data provided could void the study results. The ISIS report provides detailed Study assumptions and conditions of the system in which the ISIS was conducted.

II. STUDY CONDITIONS AND ASSUMPTIONS

A. Planning Criteria

The study was conducted by applying the NERC/WECC/CAISO Reliability Criteria. More specifically, the main criteria applicable to this study are as follows:

Power Flow Analysis

The following contingencies are considered for transmission and sub-transmission lines and 500/230 kV transformer banks (“AA-Banks”):

- Single Contingencies – Loss of one line or one AA-Bank and selected overlapping outages of one generating unit and one line
- Double Contingencies – Loss of two lines or one line and one AA-Bank identified as common mode failure elements (Outages of two AA-Banks are beyond the Planning Criteria)

The following reliability criteria are used:

Transmission Lines	Base Case	Limiting Component Normal Rating
	N-1	Limiting Component A-Rating
	N-2	Limiting Component B-Rating
AA-Banks (500/230 kV) Transformer Banks	Base Case	Normal Loading Rating
	Long Term & Short Term	As defined by SCE Operating Bulletin

System upgrades for transmission lines are generally recommended for all reliability criteria violations. Special Protection Systems (SPS) may be allowed for single contingency and credible double contingencies reliability criteria violations in place of system upgrades, provided that the SPS complies with the CAISO Planning Standards’ New Generator SPS Guidelines.

The following principles were used in determining whether congestion management, SPS, or facility upgrades are required to mitigate base case, single contingency, and/or double contingency overloads:

- Congestion management, as a means to mitigate base case overloads, can be used if it is determined to be manageable and CAISO Operations concurs with the

implementation. Congestion management to mitigate criteria violations may include curtailment of the proposed generation project in real time as needed.

- Facility upgrades will be required if it is determined that the use of congestion management for base case overloads is unmanageable.
- SPS will be recommended for criteria violations under outage conditions if it effectively mitigates system problems, does not jeopardize system integrity, does not exceed the current CAISO single and double contingency tripping limitations, does not adversely impact existing or proposed SPS in the area, and conforms to existing CAISO SPS Guidelines.
- Facility upgrades will be required if the use of an SPS is determined to be ineffective, system integrity is jeopardized, the amount of generation tripping exceeds the current CAISO single and double contingency tripping limitations, adverse impacts are identified to existing or proposed SPS in the area, or the SPS does not conform with the existing SPS Guidelines.

The following study method was implemented to assess the extent of possible congestion:

- a) Under Base Case with all transmission facilities in service, the system was evaluated with all existing interconnected generation and all generation requests in the area that have a queue position ahead of this request (pre-project). Included in the study are CAISO-approved transmission projects queued ahead of the generation interconnection request.
- b) Under Base Case with all transmission facilities in service, the system was reevaluated with the inclusion of the Project (post-project).

If the normal loading limits of facilities are exceeded in (a), the overload is identified as an existing overload that was triggered by a project in queue ahead of the HLSP Project. If the normal loading limits of facilities are exceeded in (b) and were not exceeded in (a), the overload is identified as triggered by the addition of the HLSP Project. The HLSP Project and other market participants in the area may be subjected to congestion management, potential upgrade cost and/or participation of any proposed SPS if the project addition aggravates or triggers the overload. Additionally, the HLSP Project may have to participate in mitigation of overloads triggered by subsequent projects in queue, subject to FERC protocols and policies.

Results of these studies should identify:

- a) If capacity is available to accommodate the proposed HLSP Project and all projects ahead in queue without the need for congestion management, SPS, or facility upgrades
- b) if base case overloads exist in the area after the addition of all projects in queue ahead of the HLSP Project

- c) if base case overloads are triggered in the area after the addition of the HLSP Project

The range of base case congestion for the HLSP Project will be determined by reducing market generation in the area including the HLSP Project. For single and double element outage conditions, the same methodology will be used to identify how much generation tripping is required in order to determine if the use of an SPS is appropriate. Use of an SPS will be deemed inappropriate if the total amount of generation reduction is found to exceed 1,150 MW under loss of one transmission element and 1,400 MW under loss of two transmission elements. These limits are established by the CAISO utilizing the current Spinning Reserve Criteria.

B. Generation and Load Assumptions

To simulate the SCE transmission system for analysis, the study used databases that were developed to conduct SCE's Annual CAISO Controlled Facilities Expansion Program. The study considered two load conditions: 2013 heavy summer and a 2013 light spring case which assumed 65% of heavy summer load forecast. In addition, the study evaluated conditions with dispatch of generation inside and outside of the SCE service territory and electrical system in a manner that maximized loadings in the north of Lugo area. This included adjusting SCE imports on the West-of-River (Path 46) and modeling all pertinent queued ahead generation projects in the vicinity of the HLSP Project. Generation assumptions are provided below in Table 1-1. Heavy summer and light spring load study assumptions are provided below in Tables 1-2 and Table 1-3 respectively.

Table 1-1
ACTIVE QUEUED GENERATION PROJECTS MODELED IN THE STUDY

CAISO Queue #	Interconnection Point	(MW)	Requested Operating Date
SCE WDT112	Casa Diablo 115kV	16.54	2007
11	Mountain Pass 115kV	63	2010
33	Control 115kV Bus	10	In-Service
SCE WDT164	Gale 115kV Bus	80	2006
58	Churchill-Bishop	62	2007
68	Pisgah	850	2009
83	Lugo-Pisgah 230kV	60	2008
89	Victor 230kV Bus	570	2010
106	Mohave 500 kV	635 ²	2009
109 ³	Pisgah 230kV	550	2010
110 ³	Pisgah 230kV	1400 ²	2013
114 ³	Lugo-Pisgah 230 kV	150	2008
115 ³	Lugo-Pisgah 230 kV	150	2008
116 ³	Lugo-Pisgah 230 kV	50	2008
118	Mohave 500 kV	550 ¹	2009
120 ³	Mohave 500 kV	1200 ²	2011
125	Kramer 230 kV	250	2010

¹ This project was initially included in the System Impact Study Plan but has since been withdrawn and was thus not modeled in the study.

² These projects were included in the base case but were not dispatched in the study for the following reasons:

- The projects are injecting power directly to the 500 kV bulk power system and do not contribute impacts to the 230 kV network used to interconnect the HLSP Project.
- These projects not dispatched will utilize available capacity on Path 46 and Path 49 thereby limiting the amount of power to no more than the established WECC Path Ratings.
- The amount of transmission capacity available to export Lugo Area excess power is less than the total amount of generation interconnection requests up to and including the HLSP Project. Consequently, congestion management will be required to ensure system dispatch conditions are such that the total amount of Lugo Area export is maintained to within limits.

³ These projects have been identified to be moved into the Transition Cluster in the CAISO's Petition for Waiver of Tariff Provisions to Accommodate Transition to Reformed Large Generator Interconnection Procedures, and Motion to Shorten Comment Period FERC Filing. If approved, these projects will need to be removed from the HLSP Project starting base cases and a Technical Study will be required to identify the revised system impacts.

Table 1-2
Heavy Summer Load (MW) Assumptions

SUBSTATION	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017
ALAMITOS	196	198	201	203	200	199	199.2	194	194	194
ANTELOPE-BAILEY	814	897	925	970	1037	729	738.3	805	825	833
ANTELOPE EAST	0	0	0	0	0	334	333.9	334	340	355
BARRE	736	743	804	816	830	837	847.5	854	864	877
BLYTHE	56	57	58	59	59	60	60.3	61	61	61
CAMINO	2	2	2	2	2	2	2.0	2	2	2
CENTER	507	513	522	528	529	527	527.9	532	535	538
CHEVMAIN	130	130	130	130	130	130	130.0	130	130	130
CHINO	758	776	930	960	974	993	998.3	1010	1018	1049
CIMA	1	1	1	1	1	1	1.0	1	1	1
DEL AMO	513	520	477	485	484	485	486.3	497	499	497
DEVERS - MIRAGE	1026	474	488	500	516	529	542.3	553	565	578
EAGLE MT.	2	2	2	2	2	2	2.0	2	2	2
EAGLE ROCK	203	205	208	210	213	215	210.3	212	213	214
EL CASCO	0	182	195	206	214	222	228.2	234	241	248
ELLIS	656	670	682	696	701	713	720.6	730	738	747
EL NIDO	366	369	373	377	378	378	378.7	377	379	380
ETIWANDA	620	645	668	687	703	720	730.7	745	759	777
ETIWANDA "AMERON"	70	70	70	70	70	70	70.0	70	70	70
GOLETA	280	284	287	291	292	292	293.0	295	296	297
GOULD	122	124	126	129	130	133	134.5	138	140	142
HINSON	557	562	569	573	571	570	568.5	568	570	570
JOHANNA	454	468	475	529	524	525	526.0	528	532	542
JURUPA (city Riverside)	0	270	273	276	275	276	275.4	277	276	276
KRAMER	335	359	376	389	398	407	416.0	420	426	447
LA CIENEGA	497	504	510	516	517	518	528.5	531	534	537
LA FRESA	684	691	699	705	704	703	702.8	706	708	709
LAGUNA BELL	596	602	607	613	612	612	612.4	614	616	616
LEWIS	548	553	564	569	573	577	575.7	576	579	577
LIGHTHIPE	521	528	533	540	540	541	542.4	541	544	545
MESA	607	615	627	638	639	642	641.2	644	649	651
MIRAGE	0	503	527	549	565	575	584.3	596	609	622
MIRA LOMA	826	849	745	767	779	785	804.0	822	784	780
MOORPARK	800	828	888	883	892	899	905.8	914	925	940
OAK VALLEY	0	0	0	0	0	0	0.0	0	0	0
OLINDA	410	428	437	446	451	456	460.1	469	474	479
PADUA	696	703	707	716	715	717	725.2	733	742	745
RECTOR	735	769	797	820	843	872	884.5	514	526	537
RIO HONDO	719	733	745	753	754	754	758.4	761	767	771
SAN BERNARDINO	628	632	646	662	672	682	689.5	702	716	725
SAN JOAQUIN	0	0	0	0	0	0	0.0	392	402	410
SANTA CLARA	621	638	628	672	682	692	699.2	704	713	722
SANTIAGO	756	788	815	846	867	881	896.4	910	923	943
SAUGUS	773	793	812	834	850	866	881.4	901	919	937
SPRINGVILLE	229	233	241	255	262	262	275.2	281	288	295
VALLEY	1742	1833	1916	1995	1769	1809	1848.7	1878	1927	1951
ALBERHILL	0	0	0	0	271	284	296.5	323	334	340
VESTAL	146	148	151	153	153	154	154.5	156	157	158
VICTOR	627	656	676	706	715	728	750.8	761	776	799
VIEJO	358	366	377	382	385	387	389.6	393	396	400
VILLA PARK	760	768	779	745	745	745	741.4	737	739	737
VISTA 66 KV	1052	772	783	797	809	819	825.9	835	900	919
VISTA 115 KV	686	589	601	613	614	614	621.3	623	627	630
WALNUT	737	748	752	758	759	758	756.4	758	758	759
Total	25,159	25,795	26,409	27,023	27,369	27,680	27,973	28,343	28,711	29,062

Southern California Edison Protected Materials, **Confidential: Contains Critical Energy Infrastructure Information (CEII)**

Table 1-3
Light Spring Load (MW) Assumptions

SUBSTATION	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017
ALAMITOS	127	129	131	132	130	130	129	126	126	126
ANTELOPE-BAILEY	529	583	602	630	674	474	480	523	536	541
ANTELOPE EAST	0	0	0	0	0	217	217	217	221	231
BARRE	478	483	522	530	539	544	551	555	562	570
BLYTHE	36	37	38	38	39	39	39	40	39	40
CAMINO	1	1	1	1	1	1	1	1	1	1
CENTER	329	334	339	343	344	342	343	346	348	349
CHEVMAIN	85	85	85	85	85	85	85	85	85	85
CHINO	493	504	605	624	633	645	649	657	661	682
CIMA	1	1	1	1	1	1	1	1	1	1
DEL AMO	334	338	310	315	315	315	316	323	325	323
DEVERS - MIRAGE	667	308	317	325	336	344	352	360	367	376
EAGLE MT.	1	1	1	1	1	1	1	1	1	1
EAGLE ROCK	132	134	135	137	138	140	137	138	139	139
EL CASCO	0	119	127	134	139	144	148	152	157	161
ELLIS	426	435	443	452	455	464	468	475	480	486
EL NIDO	238	240	243	245	245	246	246	245	247	247
ETIWANDA	403	419	434	446	457	468	475	485	494	505
ETIWANDA "AMERON"	46	46	46	46	46	46	46	46	46	46
GOLETA	182	184	187	189	190	190	190	191	193	193
GOULD	79	81	82	84	85	86	87	90	91	92
HINSON	362	365	370	372	371	370	370	370	370	370
JOHANNA	295	304	309	344	341	341	342	343	346	352
JURUPA (city Riverside)	0	176	178	179	179	179	179	180	180	180
KRAMER	218	234	245	253	258	264	270	273	277	291
LA CIENEGA	323	327	331	335	336	337	344	345	347	349
LA FRESA	445	449	454	458	458	457	457	459	460	461
LAGUNA BELL	387	391	395	398	398	398	398	399	400	401
LEWIS	356	360	367	370	372	375	374	375	376	375
LIGHTHIPE	339	343	347	351	351	352	353	351	353	354
MESA	394	400	408	414	415	417	417	419	422	423
MIRAGE	0	327	343	357	367	373	380	388	396	404
MIRA LOMA	537	552	484	499	506	510	523	534	510	507
MOORPARK	520	538	577	574	580	584	589	594	601	611
OAK VALLEY	0	0	0	0	0	0	0	0	0	0
OLINDA	266	278	284	290	293	297	299	305	308	312
PADUA	452	457	460	466	464	466	471	476	483	484
RECTOR	478	500	518	533	548	567	575	334	342	349
RIO HONDO	467	476	485	489	490	490	493	495	499	501
SAN BERNARDINO	408	411	420	430	437	443	448	456	465	471
SAN JOAQUIN	0	0	0	0	0	0	0	255	261	267
SANTA CLARA	403	415	408	437	443	450	454	458	463	469
SANTIAGO	491	512	530	550	564	573	583	592	600	613
SAUGUS	503	516	528	542	553	563	573	586	598	609
SPRINGVILLE	149	152	156	166	171	170	179	183	187	192
VALLEY	1133	1192	1246	1297	1150	1176	1202	1221	1252	1268
ALBERHILL	0	0	0	0	176	185	193	210	217	221
VESTAL	95	96	98	100	99	100	100	101	102	103
VICTOR	407	426	439	459	464	473	488	494	505	519
VIEJO	233	238	245	249	250	252	253	255	258	260
VILLA PARK	494	499	506	484	484	484	482	479	480	479
VISTA 66 KV	684	502	509	518	526	532	537	543	585	597
VISTA 115 KV	446	383	390	398	399	399	404	405	408	410
WALNUT	479	486	489	493	494	493	492	493	493	493
Total	16,353	16,767	17,166	17,565	17,790	17,992	18,182	18,423	18,662	18,890


Southern California Edison Protected Materials, **Confidential: Contains Critical Energy Infrastructure Information (CEII)**

C. HLLLC – Harper Lake Solar Plant Project

The Harper Lake Solar Plant (HLSP) Project is geographically located in Hinkley, California approximately twelve miles east of Kramer Junction and west of Harper Lake. Specifically, the project will be in San Bernardino County in portions of Township 11N, Range 6W, Sections 25, 28, 29, 30, 32, and 33. The HLSP Project will consist of two Siemens solar concentrated steam turbines with a total net output of 250 MW and their associated 230/13.8 kV generator step-up transformers. It should be noted that each unit is capable of 150 MW but the output will be limited to no more than 250 MW combined.

HLLLC requested the Point of Interconnection (POI) for the HLSP Project to be one of the existing Kramer-Cool Water (northern circuit) 230 kV transmission lines. The HLSP Project would be interconnected to this transmission line by constructing a new 230 kV switching substation, referred to in this study as Hinkley, in order to loop the existing Kramer-Cool Water No.1 230 kV transmission line. The HLSP Project would then be connected to the Hinkley Substation by a customer owned 230 kV generation tie-line as shown below in Figure 1-1. The HLSP Project requested an interconnection date of January 1, 2010 and commercial operating date of August 1, 2010.

Figure 1-1
HLLLC – Harper Lake Solar Plant Project
One-Line Diagram



The HLSP Project includes one solar concentrating thermal power plant, based on parabolic trough technology. The parabolic trough is a solar thermal energy collector constructed as a long parabolic mirror. Each solar trough mirror will track the sun throughout the day and reflect concentrated solar energy to a receiver tube known as a Dewar tube, which runs the length of the parabolic trough. The receiver tube is filled with a heat transfer fluid, such as oil, which absorbs the concentrated sunlight and is used to heat steam in a standard turbine generator. The high temperature oil circulates through a heat exchanger to generate steam which is used to run a conventional steam turbine. Dynamics data used to represent the steam turbine generator in the GE PSLF Dynamic Software, as provided by the project developer, are shown below in Table 1-4 (generator), Table 1-5 (excitation system), Table 1-6 (governor) and Table 1-7 (power system stabilizer).

TABLE 1-4
STEAM TURBINE GENERATOR MODEL (GENROU)

Variable	Value	Description
MVA	167.0	Generator MVA Base
Tpdo	9.191	D-axis transient rotor time constant, sec
Tppdo	0.043	D-axis sub-transient rotor time constant, sec
Tpqr	2.50	Q-axis transient rotor time constant, sec
Tppqr	0.15	Q-axis sub-transient rotor time constant, sec
H	3.33228	Inertia constant, sec
D	0.0	Damping factor, per-unit
Ld	2.36	D-axis synchronous reactance, per-unit
Lq	2.24	Q-axis synchronous reactance, per-unit
Lpd	0.267	D-axis transient reactance, per-unit
Lpq	0.473	Q-axis transient reactance, per-unit
Lppd	0.183	D-axis sub-transient reactance, per-unit
Lppq	0.183	Q-axis sub-transient reactance, per-unit
Ll	0.143	Stator leakage reactance, per-unit
S1	0.115	Saturation factor at 1.0 per-unit flux
S12	0.571	Saturation factor at 1.2 per-unit flux
Ra	0.0	Stator resistance, per-unit
Rcomp	0.0	Compounding resistance for voltage control, per-unit
Xcomp	0.0	Compounding reactance for voltage control, per-unit

TABLE 1-5
STEAM TURBINE EXCITATION SYSTEM MODEL (EXST4B)

Variable	Value	Description
Tr	0.02	Filter time constant, sec
Kpr	3.15	Proportional gain, per-unit
Kir	3.15	Integral gain, per-unit
Ta	0.02	Time constant, sec
Vrmax	1.00	Maximum controller output, per-unit
Vrmin	-0.87	Minimum controller output, per-unit
Kpm	1.00	Proportional gain of field voltage regulator, per-unit
Kim	0.00	Integral gain of field voltage regulator, per-unit
Vmmax	1.00	Maximum field voltage regulator output, per-unit
Vmmin	-0.87	Minimum field voltage regulator output, per-unit
Kg	0.00	Excitation limiter gain, per-unit
Kp	6.50	Potential source gain, per-unit
Angp	0.00	Phase angle of potential source, degrees
Ki	0.00	Current source gain, per-unit
Kc	0.08	Excitation regulation factor, per-unit
Xl	0.00	Main generator leakage reactance, per-unit
Vbmax	8.00	Maximum excitation voltage

TABLE 1-6
STEAM TURBINE GOVERNOR MODEL (GGOV1)

Variable	Value	Description
r	0.05	Permanent of droop, per-unit
rselect	1.0	Feedback signal for droop
Tpelec	1.0	Electrical power transducer time constant, sec
maxerr	0.05	Maximum value for speed error signal
minerr	-0.05	Minimum value for speed error signal
Kpgov	10.0	Governor proportional gain
Kigov	2.0	Governor integral gain
Kdgov	0.0	Governor derivative gain
Tdgov	1.0	Governor derivative controller time constant
vmax	1.0	Maximum valve position limit
Vmin	0.15	Minimum valve position limit
Tact	0.5	Actuator time constant
Kturb	1.5	Turbine gain
Wfnl	0.2	No load fuel flow, per-unit
Tb	0.5	Turbine lag time constant
Tc	0.0	Turbine lead time constant
Flag	1.0	Switch for fuel source characteristic
Teng	0.0	Transport lag time constant for diesel engine
Tfload	3.0	Load limiter time constant
Kpload	2.0	Load limiter proportional gain for PI controller
Kiload	0.67	Load limiter integral gain for PI controller
Ldref	1.0	Load limiter reference value, per-unit
Dm	0.0	Speed sensitivity coefficient, per-unit
ropen	0.10	Maximum valve opening rate, per-unit / second
rclose	-0.10	Minimum valve opening rate, per-unit / second
Kimw	0.002	Power controller (reset) gain
Pmwset	75.0	Power controller setpoint, MW
aset	0.01	Acceleration limiter setpoint, per-unit / second
Ka	10.0	Acceleration limiter gain
Ta	0.1	Acceleration limiter time constant, second
db	0.0	Speed governor dead band
Tsa	4.0	Temperature detection lead time constant, second
Tsb	5.0	Temperature detection lag time constant, second
rup	99.0	Maximum rate of load limit increase
rdown	-99.0	Minimum rate of load limit increase

TABLE 1-7
STEAM TURBINE POWER SYSTEM STABILIZER MODEL (PSS2A)

Variable	Value	Description
J1	1.0	Input signal #1 code
K1	0.0	Input signal #1 remote bus number
J2	3.0	Input signal #2 code
K2	0.0	Input signal #2 remote bus number
Tw1	2.0	First washout on signal #1, sec
Tw2	2.0	Second washout on signal #1, sec
Tw3	2.0	First washout on signal #2, sec
Tw4	0.0	Second washout on signal #2, sec
T6	0.0	Time constant on signal #1, sec
T7	2.0	Time constant on signal #2, sec
Ks2	0.2	Gain on signal #2
Ks3	1.0	Gain on signal #2
Ks4	1.0	Gain on signal #2
T8	0.5	Lead ramp tracking filter
T9	0.1	Lag ramp tracking filter
n	1.0	Order of ramp tracking filter
m	5.0	Order of ramp tracking filter
Ks1	10.0	Stabilizer gain
T1	0.25	Lead/lag time constant, sec
T2	0.04	Lead/lag time constant, sec
T3	0.20	Lead/lag time constant, sec
T4	0.03	Lead/lag time constant, sec
Vstmax	0.1	Stabilizer output max limit, per-unit
Vstmin	-0.1	Stabilizer output min limit, per-unit
a	1.0	Lead/lag num. gain (not in IEEE model)
Ta	0.0	Lead/lag time constant, sec (not in IEEE model)
Tb	0.0	Lead/lag time constant, sec (not in IEEE model)

D. Transmission Upgrades to be Included in the HLSP Project Base Cases

A number of transmission upgrades are needed to support queued ahead generation projects in the North of Lugo and East of Lugo areas. These projects, outlined below, were included into the base cases in order for the System Impact Study to determine if additional facilities would be needed to support the HLSP Project.

PISGAH AREA

The studies performed for the queued ahead generation projects in the Pisgah area identified a number of facility upgrades to be required. These upgrades involved the following:

- Expansion of the existing SCE Pisgah 230 kV Substation, sized to accommodate 500/230 kV facilities, with up to four 500/230 kV transformers, two sets of 200 MVar 500 kV capacitor banks, and four sets of 79.2 MVar 230 kV capacitor banks.
- Removal of one existing Lugo-Pisgah 230 kV transmission line and replacement with a new Lugo-Pisgah 500 kV transmission line.⁸
- Looping of the existing Lugo-Eldorado 500 kV transmission line into the new 500 kV portion of the expanded Pisgah Substation, by “cutting” the line near the Pisgah Substation and connecting each portion to the Pisgah Substation.
- Installation of appropriate fully redundant and diverse telecommunication facilities to support both a special protection system that would trip generation projects connecting to the Pisgah Substation under specific outage contingencies, as well as provide overall system protection.

LUGO TO PISGAH 230 kV CORRIDOR


Feasibility and System Impact Studies have been performed for four queued ahead projects that have requested interconnection to the existing 230 kV transmission facilities connecting the Lugo Substation with the Pisgah Substation. Because one of the existing lines has been identified to be removed in order to make room for a new 500 kV transmission line (as discussed above), only one of the two existing Lugo-Pisgah 230 kV transmission lines (northern circuit) will be available. This remaining Lugo-Pisgah 230 kV transmission line has a relatively low capacity value of 289 MVA (725 amps) with no emergency capability. The total amount of generation projects in queue ahead of the HLSP Project requesting interconnection to this transmission line is in excess of 400 MW. In order to interconnect these projects, three new substations will be required and the line will need to be “cut” into two segments, with one ultimately connecting to Lugo and the other ultimately connecting to

⁸ Actual design of these transmission upgrades will depend on many factors including the development of upgrade alternatives necessary to support a Proponent’s Environmental Assessment (PEA) and an Application for a Certificate of Public Convenience and Necessity (CPCN). Some of the alternatives that would be considered include, but are not limited to: 1) the removal of both existing single-circuits and replacement with a new 500 kV double-circuit transmission line, 2) the construction of a new single-circuit on new right-of-way without removing any existing facilities, and 3) a combination of both.

Pisgah, as shown below in Figure 1-2. The three new substations modeled in the base case include the following:

- New Desert View Substation, designed to ultimately accommodate 500/230/115 kV facilities, with up to four 500/230 kV transformer banks, and is assumed to be located approximately 16 miles east of the Lugo Substation and operated in a radial configuration to the Lugo Substation.
- New Abelia 230 kV Switching Station, designed as a collector substation for new generation interconnection projects, and is assumed to be located approximately 21 miles east of the new Desert View Substation.
- New Galway 230 kV Switching Station, designed as a collector substation for new generation interconnection projects, and is assumed to be located approximately 15 miles west of the Pisgah Substation.

Figure 1-2
Upgrades for Queued Ahead Generation Projects
Lugo-Pisgah 230 kV Transmission Corridor



In addition to the above three new substations, the line segment of the existing Lugo-Pisgah No.1 230 kV (northern circuit) transmission line may be rebuilt as part of the removal of the existing Lugo-Pisgah No.1 230 kV and replacement with 500 kV. One of the alternatives for the 500 kV upgrade involves utilizing existing right-of-way between Lugo Substation and the Mojave River. To allow for use of existing right-of-way, the alternative would involve the removal of both single circuit 230 kV lines and replacement with one new double-circuit 500 kV transmission line, with one of the circuits initially energized at 230 kV and connected to the remainder of the Lugo-Pisgah No.2 230 kV transmission line east of the Mojave River. If this alternative is not selected, then the existing Lugo-Pisgah No.1 230 kV transmission line will remain as is. As part of this ISIS, no upgrades were assumed on the existing Lugo-Pisgah No.1 230 kV transmission line.

LUGO TO CONTROL CORRIDOR

System Impact Studies and Technical Assessments have been performed for five queued ahead projects that have requested interconnection to transmission facilities north of Lugo (injecting power into the Victor and Control Substations). Results of these studies identified the need for a number of facility upgrades. These upgrades involved the following:

- Replacement of the existing 115 kV phase-shift transformer located at Inyo Substation with a greater phase-angle transformer.
- Construction of a new 230 kV transmission line between the Lugo Substation and Victor Substation (approximately 10-12 miles).
- Installation of third 500/230 kV transformer bank at Lugo Substation.
- Installation of appropriate fully redundant and diverse telecommunication facilities to support modification to existing special protection systems (Bishop, HDPP and Kramer SPS).

E. Existing Special Protection Systems

The SCE North of Lugo transmission system is equipped with three existing special protection systems to mitigate existing reliability issues under specific outage conditions. The addition of the HLSP Project may necessitate the need to upgrade some of these existing special protection systems, mainly the High Desert Power Project SPS and the Kramer SPS.

HIGH DESERT POWER PROJECT SPS

This SPS is designed to prevent transmission line or transformer bank overloads, as well as system instability. These problems could occur during high generation conditions under certain transmission component outages. The following outlines the outages that can result in the potential operation of the HDPP SPS:

Single Outages

1. Loss of Lugo-Victor No.1 230 kV Transmission Line
2. Loss of Lugo-Victor No.2 230 kV Transmission Line
3. Loss of Lugo 500/230 No.1 Transformer Bank (AA-Bank)
4. Loss of Lugo 500/230 No.2 Transformer Bank (AA-Bank)

Double Outages

1. Loss of Lugo-Victor No.1 and No.2 230 kV Transmission Lines
2. Loss of Lugo 500/230 kV No.1 and No.2 Transformer Banks (“Safety Net”)

Arming of the HDPP SPS is based on the Lugo-Victor No.1 and No.2 230 kV line flows, as well as the Lugo AA-Bank flows. The “Safety Net” is armed based on the sum flows of the two Lugo AA-Banks. Adding generation north of Lugo may result in changes to existing line

flows and may adversely affect the current arming levels. In addition to tripping generation under outage conditions, SCE System Operating Bulletin No.283 allows for curtailment of generation in the Victor Area when the SPS is inoperative.

KRAMER SPS

The Kramer SPS is designed to prevent transmission line or transformer bank overloads, as well as system instability in the Kramer Junction area. These problems could occur during high generation conditions under certain transmission component outages. The following outlines the outages that can result in the potential operation of the Kramer SPS:

Single Outages

1. Loss of Kramer-Inyokern-Randsburg No.1 115 kV Line
2. Loss of Kramer-Lugo No.1 230 kV Transmission Line
3. Loss of Kramer-Lugo No.2 230 kV Transmission Line

Double Outages

1. Loss of both Kramer-Lugo No.1 and No.2 230 kV Transmission Lines
2. Loss of both Lugo 500/230 kV No.1 and No.2 Transformer Banks (Safety Net)

In addition to tripping generation under outage conditions, SCE System Operating Bulletin No.209 allows for curtailment of generation in the Inyokern Area when the 115 kV portion of the SPS is inoperative. SCE System Operating Bulletin No.209 also allows for curtailment of generation in the Kramer area when the 230 kV portion of the SPS is inoperative.

Arming of the 115 kV Kramer SPS portion is based on Kramer-Inyokern-Randsburg No.3 115 kV line flow, while arming of the 230 kV Kramer SPS portion is based on Kramer-Lugo No.1 and No.2 230 kV line flows. The “Safety Net” is armed based on the sum flows of the two Lugo AA-Banks. Adding generation north of Lugo may result in changes to existing line flows and may adversely affect the current arming levels.

F. Power Flow Study

The HLSP Project ISIS considered two power flow study scenarios. Each case was derived from the most current CAISO Transmission Expansion Plan Study base cases. Further description of the case assumptions are provided below and are summarized in Table 1-8:

- a). SCE System with a 2013 Heavy Summer load forecast and all generation projects in queue ahead of the HLSP Project and associated upgrades if known, Case 1.

The study considered heavy load conditions with generation patterns and Path 46 imports dispatched in a manner that would stress the SCE system in the area of the interconnection of the HLSP Project. This was done in order to identify the extent of potential congestion. Generation in the area included regulatory must-take, all other existing generation in the North and East of Lugo areas, and all proposed generation

projects in queue ahead of the HLSP Project.

- b). SCE System with a 2013 Heavy Summer load forecast and all generation projects in queue ahead of the HLSP Project and associated upgrades, if known, and the inclusion of the HLSP Project, Case 2.

Case 1 modified to include the HLSP Project with a net generation of 250 MW.

- c). SCE System with a 2013 Light Spring load forecast and all generation projects in queue ahead of the HLSP Project and associated upgrades if known, Case 3

The study considered light load conditions with generation patterns and Path 46 imports dispatched in a manner that would stress the SCE system in the area of the interconnection of the HLSP Project. This was done in order to identify the extent of potential congestion. Generation in the area included regulatory must-take, all other existing generation in the North and East of Lugo areas, and all proposed generation projects in queue ahead of the HLSP Project.

- d). SCE System with a 2013 Light Spring load forecast and all generation projects in queue ahead of the HLSP Project and associated upgrades, if known, and the inclusion of the HLSP Project, Case 4

Case 3 modified to include the HLSP Project with a net generation of 250 MW.

In addition to these base cases, a few sensitivity cases were examined to adequately identify the extent of potential congestion amounts by the proposed in-service date of January 1, 2010.

TABLE 1-8
POWER FLOW STUDY ASSUMPTIONS (MW)

Area Assumptions	2013 Heavy Summer		2013 Light Spring	
	Case 1 Pre-Project	Case 2 Post-Project	Case 3 Pre-Project	Case 4 Post-Project
Generation	21,513	21,535	11,518	11,551
Import	7,142	7,144	7,482	7,482
Load	27,996	27,996	18,456	18,456
Losses	659	684	543	577
Path Flows and Area Imports				
East-of-River (Path 49)	5,167	5,165	5,851	5,852
West-of-River (Path 46)	7,667	7,667	8,136	8,139
Midway-Vincent (Path 26)	1,140	1,146	800	816
South of Kramer	832	1,022	900	1,108
Local Lugo Area (230 kV)	2,187	2,403	2,209	2,425
Lugo Area Export (500 kV)	7,714	7,844	7,469	7,637
South of Lugo	6,192	6,227	5,357	5,478
Mira Loma Area Import	6,558	6,572	5,426	5,553
So. California Import Transfer	14,147	14,367	14,340	14,297

G. Transient Stability Study

For transient stability evaluation, three-phase-to-ground faults with normal clearing are studied for single contingencies; single-line-to-ground faults with delayed clearing are studied for double contingencies according to NERC/WECC planning criteria. The evaluation was conducted for the critical single and double contingencies affecting the area of interest listed below in Table 1-9. All outage cases were evaluated with the assumption that existing SPS would operate as designed where required. Tripping of the HLSP Project will be included if stability studies indicate that an SPS for the HLSP Project is required. Study results were evaluated utilizing the applicable planning criteria as summarized in Table 1-10.

TABLE 1-9
TRANSIENT STABILITY CRITICAL STUDY CASES

Bus Fault Location		Fault Type	Fault Duration	Outage	SPS
Substation	Voltage				
Lugo	500 kV	30	4 cycles	Lugo-Rancho Vista 500 kV T/L	
Lugo	500 kV	30	4 cycles	Lugo-Mira Loma No.2 500 kV T/L	
Lugo	500 kV	30	4 cycles	Lugo-Vincent No.1 500 kV T/L	
Lugo	500 kV	30	4 cycles	Lugo-Victorville 500 kV	
Lugo	500 kV	30	4 cycles	Lugo-Pisgah No.1 500 kV T/L	
Victor	230 kV	30	6 cycles	Victor-Caldwell 230 kV T/L	
Kramer	230 kV	30	6 cycles	Kramer-Lugo No.1 230 kV T/L	Kramer
Lugo	230 kV	30	6 cycles	Lugo-Victor No.1 230 kV T/L	
Desert View	230 kV	30	6 cycles	Lugo-Desert View 230 kV T/L	
Kramer	115 kV	30	7 cycles	Kramer-Victor 115 kV Line	
Lugo	500 kV	10	12 cycles	Lugo-Mira Loma No.2 and No.3 500 kV T/Ls	
Lugo	500 kV	10	12 cycles	Lugo-Vincent No.1 and No.2 500 kV T/Ls	
Lugo	500 kV	10	12 cycles	Lugo-Pisgah No.1 and No.2 500 kV T/Ls	Other
Kramer	230 kV	10	12 cycles	Kramer-Lugo No.1 and No.2 230 kV T/Ls	Kramer
Lugo	230 kV	10	12 cycles	Lugo-Victor No.1 and No.2 230 kV T/Ls	HDPP
Kramer	115 kV	10	7 cycles	Kramer-Victor 115 kV and Kramer-Roadway-Victor 115 kV Lines	
Lugo	500 kV	10	12 cycles	Lugo-Victorville 500 kV	

Table 1-10
WECC DISTURBANCE-PERFORMANCE TABLE
OF ALLOWABLE EFFECTS ON OTHER SYSTEMS
(in addition to NERC requirements)

NERC and WECC Categories	Outage Frequency Associated with the Performance Category (Outage/Year)	Transient Voltage Dip Standard	Minimum Transient Frequency Standard	Post-Transient Voltage Deviation Standard (See Note 2)
A	Not Applicable	Nothing in Addition to NERC		
B	≥ 0.33	Not to exceed 25% at load buses or 30% at non-load buses. Not to exceed 20% for more than 20 cycles at load buses.	Not below 59.6 Hz for 6 cycles or more at a load bus	Not to exceed 5% at any bus
C	0.033 – 0.33	Not to exceed 30% at any bus. Not to exceed 20% for more than 40 cycles at load buses.	Not below 59.0 Hz for 6 cycles or more at a load bus	Not to exceed 10% at any bus
D	< 0.033	Nothing in Addition to NERC		

Note 2: As an example in applying the WECC Disturbance-Performance Table, Category B disturbance in one system shall not cause a transient voltage dip in another system that is greater than 20% for more than 20 cycles at load buses, or exceed 25% at load buses or 30% at non-load buses at any time other than during the fault.

H. Post-Transient Voltage Study

The power flow study voltage results were used as a screen to identify those contingencies that may require additional post-transient voltage studies. Single and double contingencies identified in the power flow to have a voltage drop in excess of 5% were selected for post-transient voltage analysis. The Post-transient voltage studies compare voltage deviations to the NERC/WECC/CAISO reliability requirements including the SCE guidelines of 7% for single contingency outages and 10% for double contingency outages, and identify those outages which result in a criteria violation. Mitigation measures will be recommended for any criteria violation identified.

I. Short-Circuit Duty Study

To determine the impact on short-circuit duty, within SCE's electrical system, after inclusion of the HLSP Project, the study calculated the maximum symmetrical three-phase-to-ground short-circuit duties. Generator and transformer data represented in the generator and transformer data sheets provided by the customer were utilized. Bus locations where short-circuit duty was increased with the proposed HLSP Project by at least 0.1 kA and the duty was in excess of 60% of the minimum breaker nameplate rating were flagged for further review. Upon completion of the detailed circuit breaker review, circuit breakers exposed to

fault currents in excess of 100 percent of their interrupting capacities will need to be replaced or upgraded, whichever is appropriate. It should be noted that other WECC entities may request specific information within the WECC process to evaluate potential impact to their respective systems for this project addition.

J. Deliverability Assessment

In accordance with LGIP sections 3.3.2 and 3.3.3, a Deliverability Assessment was performed to determine the qualified capacity of the Project from a Resource Adequacy perspective. The study focused on the ability of the system to accommodate the output of the Project to the aggregate of load under the conditions when resources are needed the most, such as during summer peak conditions when resource shortage is more likely to occur. For more details regarding Deliverability Assessment, including the methodology and modeling requirements for the deliverability base case, please refer to the following CAISO website link: <http://www.caiso.com/1c44/1c44b5c31cce0.html>.

As required by the LGIP, deliverability assessment results need to provide the following information for this Project regarding its level of deliverability:

- The amount of capacity that can be deemed deliverable without additional upgrade(s).
- The upgrade(s) needed for this project to be deemed fully deliverable.

Please note that upgrades identified through this deliverability assessment (Delivery Network Upgrades) are discretionary upgrades implemented for those customers who want their project to be fully deliverable. Generation projects may proceed to interconnect to the CAISO Controlled Grid without Delivery Network Upgrades provided that all the required Reliability Network Upgrades have been implemented. However, a developer's decision to interconnect without the identified Delivery Network Upgrade(s) could result in the project losing its eligibility to receive capacity payments, as allowed under the CPUC Resource Adequacy program.

K. Cost Estimates

Non-binding cost estimates will be derived for the “phased” portion of the facility upgrades identified as needed to reliably interconnect the HLSP Project to the grid. These estimates will be developed without the benefit of:

- Detailed substation site review,
- Detailed right-of-way review,
- Detailed telecommunication facility review,
- Detailed system protection review,
- Detailed weather studies,
- Detailed environmental assessments, and
- Preliminary engineering

These limitations could affect the scope of facilities, the phasing of the identified facilities, the cost, and the viability of the mitigation plans identified in this study.

L. Timelines for Implementing Facility Upgrades

Timelines for the completion of facility upgrades to accommodate new projects are based on a number of factors. For the most part, the driving factors include the following:

- Time requirements to prepare the Proponents Environmental Assessment (PEA) in support of an application for a Certificate of Public Convenience and Necessity (CPCN) or Permit to Construct (PTC)
- CPCN or PTC Application review and approval process (by State and Federal Agencies)
- Estimated material acquisition lead times
- Construction of facilities

III. GENERATOR ELECTRIC GRID FAULT RIDE-THROUGH CAPABILITY CRITERIA AND POWER FACTOR CRITERIA

WECC has adopted a Generator Electrical Grid Fault Ride-Through Capability Criteria. SCE currently supports a Low Voltage Ride-Through Criteria to ensure continued reliable service. The Criteria is summarized as follows:

1. Generator is to remain in-service during system faults (three phase faults with normal clearing and single-line-to-ground with delayed clearing) unless clearing the fault effectively disconnects the generator from the system.
2. During the transient period, a generator is required to remain in-service for the low voltage and frequency excursions specified in WECC Table W-1 as applied to the load bus constraint. These performance criteria are applied to the generator interconnection point, not to the generator terminals.
3. Generators may be tripped after the fault period if this action is intended as part of a SPS.
4. This Standard will not apply to individual units or to a site where the sum of the installed capabilities of all machines is less than 10 MVA, unless it can be proven that reliability concerns exist.
5. The performance criteria of this Standard may be satisfied with performance of the generators or by installing equipment to satisfy the performance criteria.
6. The performance criterion of this Standard applies to any generation independent of the interconnected voltage level.
7. No exemption from this Standard will be given because of minor impact to the interconnected system.

8. Existing generators that go through any refurbishments or any replacements are then required to meet this Standard.

IV. STUDY RESULTS

A. Power Flow Analysis

The study focused on identifying system thermal overload problems within SCE's service territory and electrical system.

Pre-Project Conditions

Previous studies for higher queued projects have identified significant thermal overloads and voltage depression in the Lugo and Pisgah areas. The base cases would not solve when all the higher queued projects were modeled without the corresponding system upgrades, due to system voltages being severely depressed to the point of collapsing. Not dispatching queued ahead projects with requested in-service dates later than 2010 resulted in solved base cases with thermal overloads on the following set of existing transmission facilities:

- Lugo-Pisgah No.1 and No.2 230 kV transmission lines
- Lugo-Victor No.1 and No.2 230 kV transmission lines
- Lugo 500/230 kV No.1 and No.2 transformer banks

The addition of the HLSP Project would aggravate overloads on the Lugo 500/230 kV transformer banks, as well as overloads on the two Lugo-Victor 230 kV transmission lines. Therefore, the system can not accommodate the addition of the HLSP Project without the system upgrades identified for the higher-queued projects.

Base Case Conditions

To determine whether additional facilities would be needed to support the HLSP Project, the system upgrades in the Lugo and Pisgah areas, as listed in Section II.D, were modeled. In addition, in order to provide acceptable base cases which would properly solve, some higher queued projects that would inject power directly into the 500 kV bulk power system at the Eldorado, Mohave, and Pisgah (proposed) 500 kV Substations were not dispatched in the study as indicated in Table 1-1.

With the above assumptions made and the proposed system upgrades in place, the studies identified that the addition of the HLSP Project triggers new base case overloads under both summer and spring load conditions as summarized below in Table 2-1, and illustrated in Figure 2-1 through Figure 2-4.

Table 2-1
Base Case Thermal Overloads with All Prior Triggered Upgrades Included

Overloaded Facility	Rating	Summer		Spring	
		Pre	Post	Pre	Post
Kramer-Lugo No.1 230 kV T/L	494 MVA 1240 Amps	85.4%	106.5%	97.2%	118.7%
Kramer-Lugo No.2 230 kV T/L	494 MVA 1240 Amps	85.4%	106.5%	97.2%	118.7%

Figure 2-1
Summer Power Flow Plot
Pre-Project with Reliability Upgrades for Queued Ahead Projects Modeled




Figure 2-2
Summer Power Flow Plot
Post-Project with Reliability Upgrades for Queued Ahead Projects Modeled




Figure 2-3
Spring Power Flow Plot
Pre-Project with Reliability Upgrades for Queued Ahead Projects Modeled





Figure 2-4
Spring Power Flow Plot
Post-Project with All Upgrades for Queued Ahead Projects Modeled



Based on these study results, the addition of the transmission upgrades needed to mitigate all prior queued overloads does not provide sufficient transmission capability south of Kramer to accommodate the addition of the HLSP Project. Therefore, the addition of the HLSP Project ***triggers the need for additional South of Kramer transmission capability*** under both summer and spring load conditions. Because pre-project loadings under spring load conditions are already near their maximum level, the full HLSP Project could be subject to potential congestion management if additional upgrades, beyond those identified to mitigate the pre-project overloads, are not implemented.

To mitigate the identified base case overload without implementing congestion management, additional transmission would be required to support increased south of Kramer flows. This additional transmission can be accomplished by one of the following two methods:

- Constructing a new double-circuit 230 kV transmission line with one initial circuit between Kramer and Lugo **or**
- Constructing a new double-circuit 230 kV transmission line with one initial circuit between the existing Cool Water 230 kV Substation and the new Desert View 230 kV Substation⁹.

Housing development in the Victorville and Lugo Substation (City of Hesperia) surrounding areas will make the first alternative extremely difficult to locate along existing right-of-way and terminate into the Lugo Substation. The second alternative will increase system reliability due to the added geographic diversity (different corridor) and avoid the possibility of adverse impacts to residential and commercial development. In addition, the second alternative is estimated to require approximately 37 miles of new right-of-way, whereas the first alternative is estimated to require approximately 48 miles of new right-of-way. Lastly, the second alternative addresses the need for additional transmission for renewable resources queued behind the HLSP Project that are located in the Cool Water Substation area.

The second alternative is the best option to pursue because it provides a transmission solution that addresses the generation needs in the area, avoids short-lived “piece-meal” solutions, minimizes environmental impacts, minimizes the overall cost exposure to rate-payers, minimizes service interruptions, minimizes the need for generation curtailments while upgrades are implemented, improves overall system reliability and provides the minimum set of facilities for the HLSP Project, thus minimizing upfront cost responsibility. Base case power flow plots with the inclusion of the second alternative are illustrated in Figure 2-5 and Figure 2-6 for summer and spring load conditions respectively.

⁹ Upgrade to the Lugo-Desert View 230 kV transmission line with 500 kV design construction standard, but initially energized at 230 kV, was assumed to be undertaken as part of the Lugo-Pisgah 500 kV upgrade triggered by a queued ahead generation project.

Figure 2-5
Summer Power Flow Plot
Post-Project with Additional Transmission Modeled to Increase South of Kramer





Figure 2-6
Spring Power Flow Plot
Post-Project with Additional Transmission Modeled to Increase South of Kramer



Single Contingency Outage Conditions (N-1)

As discussed above in Section II.E, the existing system already has an SPS in place which arms local Kramer area generation and trips under the specific transmission line outages shown below in Table 2-2.

Table 2-2
Existing Kramer SPS and Arming Thresholds

	South of Kramer Flow Arming Level	Amount of Generation Armed
Lugo-Kramer No.1 or No.2 230 kV transmission line	650 – 950 MW	Up to 480 MW
Lugo-Kramer No.1 and No.2 230 kV transmission lines	250 – 950 MW	Up to 810 MW

Because the addition of the HLSP Project results in increasing flows on these transmission facilities and the existing SPS are in place to maintain system reliability, the HLSP Project will need to participate in the Kramer SPS (loss of Lugo-Kramer No.1 or No.2 transmission lines) if additional transmission upgrades beyond those identified to mitigate the pre-project overloads are not implemented.

In addition to the transmission line outages above, the existing system also has in place two SPSs which arm and trip local Kramer and Victor area generation under the loss of one or both existing Lugo 500/230 kV transformer banks as shown below in Table 2-3.

Table 2-3
Existing HDPP and Kramer SPS Lugo AA-Bank Arming Thresholds

	Lugo AA-Bank Flow Arming Level	Amount of Generation Armed
Lugo No.1 or No.2 500/230 kV transformer bank	650 – 950 MW	Up to 480 MW
Lugo No.1 and No.2 500/230 kV transformer banks	1250 – 2050 MW	Up to 1,660 MW

Because a third transformer bank is proposed to be added to support a queued ahead generation project, the installation of the third transformer bank will provide for an additional 1120 MVA capability under base case conditions and 1230 MVA under a single bank outage contingency. The total MW additions, up to and including the HLSP Project, is 1,020 MW, which is less than the added capability of the third transformer bank. Consequently, continued reliance on the existing HDPP SPS and Kramer SPS to trip existing generation units which are currently participating in each SPS is recommended.

With the additional upgrades identified for mitigating the HLSP Project triggered base case thermal overloads, the study identified two single contingency outages which would require the need for the HLSP Project to participate in a new SPS. Under the loss of the Lugo-Desert View 230 kV transmission line, the generation that was connected in a radial manner to the

Desert View Substation (CAISO #114 and CAISO #116) would be transmitted north to the Cool Water Substation, where it would then head west to the Kramer Substation, and ultimately together with the HLSP Project, head south to the Lugo Substation overloading the Kramer-Lugo No.1 and No.2 230 kV transmission lines. Under the loss of the Cool Water-Desert View 230 kV transmission line, the generation of the HLSP Project would be transmitted south to Lugo overloading the existing Kramer-Lugo No.1 and No.2 230 kV transmission lines. Results of this outage are summarized below in Table 2-4, and illustrated in Figure 2-7 through Figure 2-10.

Table 2-4
Single Contingency Overload
All Prior Triggered Upgrades and HLSP Project Upgrades Included

Overloaded Facility	Rating	Summer		Spring	
		Pre	Post	Pre	Post
Kramer-Lugo No.1 <u>and</u> No.2 230 kV T/Ls Loss of Cool Water-Desert View 230 kV	1240 Amps (N) 1425 Amps (E)	N/A	106.5% 92.3%	N/A	118.7% 102.9%
Kramer-Lugo No.1 <u>and</u> No.2 230 kV T/Ls Loss of Lugo-Desert View 230 kV	1240 Amps (N) 1425 Amps (E)	N/A	124.0% 107.4%	N/A	136.4% 118.3%

Figure 2-7
Summer Power Flow Plot
Post-Project with Additional Upgrades for the HLSP Project Modeled
(Loss of Cool Water-Desert View 230 kV T/L)




Figure 2-8
Spring Power Flow Plot
Post-Project with Additional Upgrades for the HLSP Project Modeled
(Loss of Cool Water-Desert View 230 kV T/L)




Figure 2-9
Summer Power Flow Plot
Post-Project with Additional Upgrades for the HLSP Project Modeled
(Loss of Lugo-Desert View 230 kV T/L)





Figure 2-10
Spring Power Flow Plot
Post-Project with Additional Upgrades for the HLSP Project Modeled
(Loss of Lugo-Desert View 230 kV T/L)



The following two mitigation alternatives are feasible to mitigate the thermal overload identified under the loss of the Cool Water-Desert View 230 kV transmission line:

- Install the second circuit on the double-circuit 230 kV transmission line between Cool Water and the new Desert View Substations.
- Implement an SPS to trip one of the two generation units at the HLSP.

An SPS is recommended to mitigate the thermal overload identified under outage of the Lugo-Desert View 230 kV transmission line. The SPS would need to transfer trip the generation tie-line circuit breakers connecting the two generation projects at Desert View, as well as trip one of the two generation units at the HLSP.

It should be noted that transfer tripping the two generation projects connecting to the Desert View Substation would not result in increasing outage exposure to these two projects because under the pre-project upgrade condition, these two projects would be tripped for the same outage, since they would be disconnected from the source (Lugo Substation) without a second source line.

Local Area Outage Conditions (N-2)

Similar to the discussion for single outage conditions, the HLSP Project will need to participate in the Kramer SPS (loss of both Lugo-Kramer No.1 and No.2 transmission lines) if additional transmission upgrades beyond those identified to mitigate the pre-project overloads are not implemented. With the additional upgrades identified for mitigating the HLSP Project triggered base case thermal overloads, the study did not identify any additional N-2 thermal overload problems.

System Wide Double Contingency Outage Conditions (N-2)

In addition to the local area double outage conditions identified above, the study determined that the total amount of Lugo Area generation export (through South of Lugo and Lugo-Vincent 500 kV transmission lines) is limited to approximately 7,800 MW. With the addition of more generation resources in the North and East of Lugo areas, the amount of excess generation requiring export will eventually exceed 7,800 MW. Consequently, additional transmission capacity will be required if the total amount of area export is to be increased. However, such requirement is not triggered solely by the addition of the HLSP Project. Therefore, this facility upgrade will be evaluated and recommended as part of a larger study effort in the area (either through the RETI study process or the annual CAISO Transmission Expansion Planning Process).

B. Transient Stability Analysis

Transient stability studies were performed for the outages specified in Table 1-9. The HLSP Project was found to satisfy the low-voltage ride-through requirements, but will need to participate in the Kramer SPS (loss of one or both Lugo-Kramer No.1 and No.2 transmission lines) if additional transmission upgrades beyond those identified to mitigate the pre-project overloads are not implemented.

With the additional upgrades identified for mitigating the base case thermal overloads triggered by the HLSP Project, the study identified transient stability problems under the following outage conditions:

- Single outage of the Lugo-Desert View 230 kV transmission line.
- Double outage of the Kramer-Lugo No.1 and No.2 230 kV transmission lines.

The study determined that with the addition of the Cool Water-Desert View 230 kV transmission line, the HLSP Project will not need to participate in the existing Kramer SPS for a double outage of the Kramer-Lugo No.1 and No.2 230 kV transmission lines. However, the study identified that the tripping requirements for mitigating transient stability problems under a single outage of the Lugo-Desert View 230 kV transmission line are more stringent than the tripping requirements for mitigating thermal overloads. Under this outage, the SPS should include tripping of the entire HLSP. Transient stability plots for summer and spring load conditions are provided in Appendix A and Appendix B respectively.

C. Post-Transient Stability Analysis

As discussed in the power flow section of the report, the addition of the HLSP Project did not trigger any new post-transient voltage criteria violations. However, the study determined that without the facility upgrades identified under base case conditions, the HLSP Project aggravates previously identified voltage problems, including case non-convergence, which are indicative of a potential voltage collapse condition.

These voltage problems are found to be mitigated with the implementation of the pre-project transmission upgrades identified for queued ahead generation projects.

D. Short Circuit Duty Study

The short-circuit duty analysis included all the queued ahead generation projects based on their application date, including the corresponding transmission upgrades identified to date. The short-circuit duty study results shown below in Table 2-5 and Table 2-6 present the impact attributed to the addition of the HLSP Project, while the results shown below in Table 2-7 and Table 2-8 present the incremental impact attributed to the addition of the upgrades identified to be triggered by the HLSP Project.

Table 2-5
Three Phase (3PH)
Short Circuit Duty Study Results
Addition of the HLSP Project Only

Bus Name	Bus KV	Pre-Project		Post-Project		DELTA KA
		X/R	KA	X/R	KA	
LUGO	500	23.0	51.5	22.9	51.6	0.1
MIRA LOMA	500	24.0	39.8	23.9	39.9	0.1
SERRANO	500	24.4	33.6	24.4	33.7	0.1
WHIRLWIND	500	17.3	29.8	17.3	29.9	0.1
CHINO	230	16.7	50.5	16.7	50.6	0.1
HINKLEY	230	15.3	9.2	20.6	12.7	3.5
KRAMER	230	14.7	16.2	15.8	18.3	2.1
LUGO	230	37.7	49.0	36.7	49.4	0.4
MIRALOMA (W)	230	19.7	53.0	19.7	53.1	0.1
SYLMAR S	230	19.1	59.5	19.1	59.6	0.1
VICTOR	230	19.0	33.6	18.8	33.8	0.2
INYOKERN	115	3.7	7.3	3.7	7.4	0.1
KRAMER	115	10.9	23.4	11.4	24.1	0.7
VICTOR	115	20.0	24.5	19.9	24.6	0.1

Table 2-6
Single Line to Ground (SLG)
Short Circuit Duty Study Results
Addition of the HLSP Project Only

Bus Name	Bus KV	Pre-Project		Post-Project		DELTA KA
		X/R	KA	X/R	KA	
LUGO	500	12.9	42.7	12.9	42.8	0.1
ETIWANDA	230	17.5	57.8	17.5	57.9	0.1
KRAMER	230	10.9	13.4	10.9	15.5	2.1
LUGO	230	25.0	51.1	24.7	51.4	0.3
MIRA LOMA (W)	230	11.6	63.9	11.6	64.0	0.1
VICTOR	230	12.7	30.6	12.6	30.7	0.1
VICTOR	115	20.4	28.8	20.4	28.9	0.1

As can be seen, the three-phase-to-ground short-circuit duty study with only the HLSP Project identified four 500 kV, seven 230 kV, and three 115 kV substation locations requiring engineering review. The single-line-to-ground short-circuit duty study identified one 500 kV, five 230 kV and one 115 kV substations requiring engineering review. Detailed review of these substation locations will be performed as part of the Facilities Study for determination of breaker replacement need.

Table 2-7
Three Phase (3PH) Short Circuit Duty Study Results
Addition of Upgrades Triggered by the HLSP Project

Bus Name	Bus KV	Pre-Upgrades		Post-Upgrades		DELTA
		X/R	KA	X/R	KA	KA
ANTELOPE	500	21.2	32.6	21.2	32.7	0.1
ELDORADO	500	18.9	47.4	19.0	47.5	0.1
LUGO	500	22.9	51.6	23.4	52.3	0.7
MIRA LOMA	500	23.9	39.9	24.1	40.0	0.1
PISGAH	500	20.3	23.4	20.4	23.5	0.1
RANCHO VISTA	500	28.6	28.1	28.8	28.2	0.1
VINCENT	500	18.8	45.0	18.9	45.2	0.2
ANTELOPE	230	24.7	36.0	24.7	36.1	0.1
COOL WATER	230	30.1	11.5	28.4	17.0	5.5
DESERT VIEW	230	6.1	8.7	26.7	16.7	8
ETIWANDA	230	25.8	59.7	25.9	59.8	0.1
HINKLEY	230	20.6	12.7	19.6	13.4	0.7
KRAMER	230	15.8	18.3	15.6	18.9	0.6
LEWIS	230	21.5	46.0	21.6	46.1	0.1
LUGO	230	36.7	49.4	38.6	51.9	2.5
MIRA LOMA(E)	230	23.2	65.3	23.3	65.4	0.1
PARDEE	230	16.3	57.3	16.3	57.4	0.1
RANCHO VISTA	230	26.2	60.9	26.3	61.0	0.1
SAN BERNARDINO	230	21.5	40.1	21.5	40.2	0.1
VICTOR	230	18.8	33.8	18.5	34.5	0.7
VINCENT	230	24.1	60.9	24.1	61.0	0.1
VISTA	230	18.7	48.3	18.7	48.4	0.1
KRAMER	115	11.4	24.1	11.5	24.2	0.1
VICTOR	115	19.9	24.6	19.9	24.7	0.1

Table 2-8
Single Line to Ground (SLG) Short Circuit Duty Study Results
Addition of Upgrades Triggered by the HLSP Project

Bus Name	Bus KV	Pre-Project		Post-Project		DELTA
		X/R	KA	X/R	KA	KA
LUGO	500	12.9	42.8	13.0	43.1	0.3
MIRA LOMA	500	10.8	36.6	10.9	36.7	0.1
PISGAH	500	21.7	21.8	21.6	21.9	0.1
RANCHO VISTA	500	8.3	25.4	8.3	25.5	0.1
CHINO	230	12.5	40.6	12.5	40.7	0.1
COOL WATER	230	30.7	12.4	29.8	16.7	4.3
KRAMER	230	10.9	15.5	10.7	15.7	0.2
LUGO	230	24.7	51.4	25.1	53.5	2.1
MIRA LOMA (W)	230	13.3	56.9	13.4	57.0	0.1
PISGAH	230	29.8	44.4	29.8	44.5	0.1
RANCHO VISTA	230	16.4	61.5	16.5	61.6	0.1
VICTOR	230	12.6	30.7	12.5	31.1	0.4
VILLA PARK	230	15.8	44.3	15.8	44.4	0.1
VICTOR	115	20.4	28.9	20.4	29.0	0.1

As can be seen, the addition of the facility upgrades required to support the HLSP Project further increases three-phase-to-ground short-circuit duty at seven 500 kV, fifteen 230 kV, and two 115 kV substation locations requiring engineering review. The addition of the facility upgrades required to support the HLSP Project was found to further increase single-line-to-ground short-circuit duty at four 500 kV, nine 230 kV and one 115 kV substation locations requiring engineering review. Detailed review of these substation locations will be performed as part of the Facilities Study for determination of breaker replacement need.

As part of the System Impact Study, the substation locations identified without the facility upgrades required to support the HLSP Project were reviewed to determine the need for circuit breaker replacement, and to determine if the need was triggered by the HLSP Project. Based on the engineering review, the addition of the HLSP Project triggers the need for circuit breaker replacement at the Kramer Substation. Table 2-9 summarizes the results of the engineering review.

Table 2-9
Engineering Review of Circuit Breakers

Bus Name	Bus KV	Replace	Upgrade	Cost Allocation
KRAMER	230	5	0	Case A
LUGO	500	0	3	Case B
ETIWANDA	230	24	0	Case B
LAGUNA BELL	230	2	14	Case B
LUGO	230	3	2	Case B
PISGAH	230	12	0	Case B
INYOKERN	115	2	0	Case B
VICTOR	115	2	0	Case B

It should be noted that additional need for breaker replacements may be identified when considering the transmission upgrades identified to mitigate the HLSP Project triggered base case overloads. Consequently, the cost estimates provided in this report are for informational purposes only, as detailed review of substations identified in Table 2-7 and Table 2-8 will be performed as part of the Facilities Study.

E. Deliverability Assessment

Separate studies entitled “Deliverability Assessments” were performed by the CAISO, which determined that the HLSP Project is not deemed as deliverable to the grid for Resource Adequacy (RA) purposes. The modeling assumptions for the Deliverability Assessment are slightly different from the modeling assumptions in this ISIS. For details regarding the methodology and assumptions for performing the Deliverability Assessment, refer to the Baseline Generation Deliverability Study – 2007 Q3 Study Plan posted at: <http://www.caiso.com/1c5d/1c5ddc8a63cd0.pdf>.

In particular, the 2007 Q3 Deliverability Assessment modeled the following upgrades:

- Lugo 500/230 kV No.3 Transformer Bank (AA-Bank)

- Kramer-Lugo No. 3 230 kV Transmission Line¹⁰
- Victor-Lugo No.3 230 kV Transmission Line
- Replacement of the Lugo-Pisgah No.2 230 kV with a new 500 kV Transmission Line
- Operation of the remaining Lugo-Pisgah 230 kV line as two radial lines
 - Radial into Lugo connecting the new Desert View Substation
 - Radial into Pisgah connecting the new Abelia and new Galway Substations

The study did not include the new Cool Water-Desert View 230 kV transmission line(s) recommended in this study to mitigate the identified base case thermal overloads on the two Kramer-Lugo 230 kV transmission lines.

V. COST ESTIMATES

The cost estimates of facility upgrades that have been identified to mitigate planning criteria violations triggered by queued ahead projects, or by the addition of the HLSP Project, are provided below in Table 2-10. ***All cost estimates are rough, order of magnitude estimates and are non-binding.*** The *Nonbinding* Cost Estimate for the HLSP Project Facilities is \$131.7 million in 2010 dollars (the ITCC component will be collected via a Letter of Credit). The *Nonbinding* Cost Estimate for upgrades triggered by queued ahead projects is \$257.0 million, also in 2010 dollars.

¹⁰ SPS was not modeled due to unknown specifications. With SPS and the additional Kramer-Lugo No.3 Transmission Line, the HLSP Project would be deemed deliverable.

Table 2-10
Cost Estimates¹¹ Provided in Millions

Facility Upgrade	Triggered by Queued Ahead Project ¹² (CASE B)	Triggered by the HLSP Project (CASE A)
Install 3 rd Lugo 500/230 kV Transformer Bank	\$57.0	-
New Lugo-Victor No.3 230 kV Transmission Line including: <ul style="list-style-type: none"> 10-12 mile 230 kV line Lugo and Victor Substation work to support new line 115 kV line rearrangements to make room in existing right-of-way 	\$37.2	-
New 37-mile (approximate) Cool Water-Desert View double-circuit 230 kV Transmission Line (2B-1590 ACSR) with one initial circuit	-	\$110.0 ¹³
Equip one double-breaker 230 kV positions at Cool Water	-	\$3.3
New Desert View Substation (breaker-and-a-half) sized for ultimate four 500/230 kV transformers initially equipped as follows: <ul style="list-style-type: none"> Initial 4-bay position equipping two with 5 CBs Two other positions equipped with four CBs for genties, but cost not included in this estimate (direct assign costs to specific queued ahead projects) Second 4-bay position equipping one with two CBs (triggered by HLSP) 	\$10.0	\$4.7
Remove existing Lugo-Pisgah No.1 and No.2 230 kV transmission line sections between Lugo and Desert View	\$15.5 ¹⁴	-
New 16-mile double-circuit 500 kV transmission line	\$105.2	\$0.0 ¹⁵
New Hinkley 230 kV Substation 4-bay (breaker-and-a-half) with two positions initially equipped with five CBs	-	\$10.0
Circuit Breaker Upgrades: <ul style="list-style-type: none"> Lugo 500 kV (3) Laguna Bell 230 kV (14) and Lugo 230 kV (2) 	\$3.7	-
Circuit Breaker Replacements identified in Feasibility Study: <ul style="list-style-type: none"> Etiwanda 230 kV (24) and Mira Loma 230 kV (12)¹⁶ Kramer 230 kV (5) Laguna Bell 230 kV (2) and Lugo 230 kV (3) Inyokern 115 kV (2) and Victor 115 kV (2) 	\$28.4	\$2.7
Protection, Telecom, and Special Protection System	-	\$1.0
Total	\$257.0	\$131.7¹⁷

¹¹ Shown in 2010 Year Dollars and does not include any ITCC Tax.

¹² Cost of such additional facilities may later be assigned to the HLSP Project if modifications to queued ahead projects (consistent with LGIP) or project withdrawals result in the HLSP Project triggering the need for the upgrade (as determined by a restudy).

¹³ Estimate does not include the costs associated with right-of-way acquisition or cost associated with telecommunications. Installation of second circuit estimated at \$28.5 million.

¹⁴ Cost estimates assume alternative selected for queued ahead project result in construction of double-circuit 500 kV along existing right-of-way. If a different right-of-way is selected for queued ahead project, the \$15.5 million removal cost shown as triggered by queued ahead project will become the responsibility of HLSP.

¹⁵ Estimates are based on the same assumptions discussed in footnote 8. If a different route is selected, the Case B cost would be zero, and Case A cost would increase to \$80 million to reflect a new single-circuit 500 kV transmission line.

¹⁶ Excludes costs associated with station conversion from 63 kA to 80 kA.

¹⁷ Facility classification, interconnection or reliability, will be done as part of the Facilities Study.

VI. ESTIMATED PROJECT TIMELINES

A significant amount of transmission facilities are necessary to mitigate pre-project base case overloads, and single contingency and double contingency outage thermal overload problems, which are aggravated with the addition of the HLSP Project. These transmission upgrades require detailed environmental assessments sufficient to support filing for a Certificate of Public Convenience and Necessity (CPCN) at the California Public Utilities Commission (CPUC). As a result, the following timelines are SCE's best judgment based on past permitting requirements. Such timelines should be viewed as *nonbinding estimates* and are not meant to imply that a CPCN will be issued by the appropriate permitting agencies.

- a). The time required for the preparation of the Environmental Impact Statement and/or Environmental Impact Report, as required per CEQA and NEPA, is estimated at 18-24 months once a complete project scope is defined.
- b). The time required for review and approval by CPUC and other permitting agencies is estimated to range between 12-24 months once the application submittal is deemed complete by the permitting agencies.
- c). The time required to complete final engineering, material procurement and construction of the proposed scope of work is estimated to range between 18 and 24 months after obtaining project authorization and funding, receiving all necessary approvals and permits from the CPUC, and obtaining all other required regulatory agency approvals.

These activities are typically sequential in nature, and therefore, the overall timeline requirements range from 48 months to 72 months once a complete project scope is defined and preliminary engineering is complete. The complete project scope definition is typically done as part of the Interconnection Facilities Study, but can be advanced, subject to the availability of SCE available resources, under an Engineering and Design Letter Agreement. SCE will evaluate resource availability at the time a request for a Letter Agreement is made. It's also important to note that SCE cannot guarantee complete project scope definition under such Letter Agreements because the Facilities Studies may identify other issues that may not be known at the time a Letter Agreement is executed. However, these conditions are typically not the norm, and the work done in advance can help advance the project CPCN filing date.

VII. CONCLUSIONS

To interconnect the HLSP Project in a manner that addresses the generation needs in the area, avoids short-lived "piece-meal" solutions, minimizes environmental impacts, minimizes overall cost exposure to rate-payers, minimizes service interruptions, minimizes the need for generation curtailments while upgrades are implemented, and provides the minimum set of facilities for the HLSP Project, thus minimizing upfront cost responsibility, the following upgrades are required:

1. Construction of a new breaker-and-a-half 230 kV Substation (Hinkley Substation) with a four bay position switchrack,¹⁸ equipping only two positions with a total of five circuit breakers.
2. Installation of appropriate fully redundant and diverse telecommunication facilities to provide overall system protection.

Based on the study results, the existing SCE transmission facilities, with only the above minimum set of facility upgrades required to interconnect the HLSP Project, are not adequate to accommodate the HLSP Project, when considering all other generation projects queued ahead.

Power Flow

Without implementing any of the transmission upgrades identified to be triggered by the queued ahead projects, the existing system does not have sufficient transmission capability to deliver the total output of all queued generation projects, up to, and including, the HLSP Project. Severe problems were identified under both heavy summer and light spring load conditions that resulted in a base case which would not solve, due to voltage levels in the Lugo Area that would be well below acceptable limits. Consequently, a number of upgrades will be necessary to reliably interconnect and deliver the HLSP Project output as discussed below.

BASE CASE CONDITIONS

To mitigate problems triggered by queued ahead projects requesting interconnection along the Lugo-Pisgah corridor or to the Pisgah 230 kV Substation and along the Lugo-Victor-Kramer-Control corridor, the following transmission upgrades previously identified to be triggered by such queued ahead projects were included in the initial studies:

- Expansion of the existing SCE Pisgah 230 kV Substation to include 500 kV facilities.
- Removal of the existing Lugo-Pisgah No. 2 230 kV transmission line and replacement with a new Lugo-Pisgah 500 kV transmission line.¹⁹
- Looping of the existing Eldorado-Lugo 500 kV transmission into the new 500 kV Pisgah Substation.
- Looping of the existing Lugo-Pisgah No. 1 230 kV transmission line into 3 new substations (Desert View, Abelia and Galway) forming new Lugo-Desert View 230 kV, Abelia-Desert View 230 kV (normally open), Abelia-Galway 230 kV, and Pisgah-Galway 230 kV transmission lines.
- Construction of a third Lugo-Victor 230 kV transmission line.

¹⁸ Standard SCE bus structures provide for up to four bay positions, but only the required bays will be equipped as part of the HLSP Project.

¹⁹ New right-of-way would be required west of the Mojave River to support a new 500 kV transmission line. A potential line routing alternative for this upgrade involves the use of existing right-of-way between the Mojave River and the Lugo Substation by removing both the existing Lugo-Pisgah No.1 and No.2 230 kV transmission lines and the construction of a new double-circuit 500 kV line. One of the new 500 kV circuits would be used to connect to Pisgah, and the other 500 kV circuit would be initially operated at 230 kV and connected to Desert View.

- Installation of the 3rd Lugo 500/230 kV transformer bank.

With the addition of the HLSP Project and all previously identified transmission upgrades, new base case overload problems were identified. Specifically, the HLSP Project triggers the following impacts:

Summer Load Conditions

Kramer-Lugo No.1 and No.2 230 kV Transmission Lines (85.4% → 106.5%)

Spring Load Conditions

Kramer-Lugo No.1 and No.2 230 kV Transmission Lines (97.2% → 118.7%)

To mitigate these base case overload problems, additional transmission will be required to increase the transfer capability south of Kramer. Such increase in transmission capability south of Kramer can best be provided by the

- Construction of a new Cool Water-Desert View double-circuit 230 kV transmission line with the installation of one initial circuit.

SINGLE OUTAGE CONTINGENCY (N-1)

Without the above additional facility upgrades in place to mitigate the identified base case overload problems, the study determined that the system is also inadequate to accommodate the full output of the HLSP Project under specific single outage contingencies. Because the HLSP Project results in increasing power flows on transmission facilities that are currently monitored as part of existing Kramer SPS (loss of Lugo-Kramer No.1 or No.2 230 kV transmission lines), the HLSP Project will need to be added to the existing Kramer SPS if the additional transmission upgrades identified to mitigate the base case overloads are not implemented. The addition of the HLSP Project to the Kramer SPS will increase the amount of generation participating in the Kramer SPS from 863 MW to 1,113 MW. The actual amount of generation armed and tripped under the outage condition will be determined by the amount of power flow on the two Kramer-Lugo 230 kV transmission lines prior to the outage.

With the base case facility upgrades in place, the study determined that an SPS will still be needed to mitigate thermal and transient stability problems under the loss of the Cool Water-Desert View and Lugo-Desert View 230 kV transmission lines. Outage of these lines results in loading the existing Kramer-Lugo No.1 and No.2 230 kV transmission lines as follows:

Overloaded Facility	Rating	Heavy Summer		Light Spring	
		Pre	Post	Pre	Post
Kramer-Lugo No.1 and No.2 230 kV T/Ls Loss of Cool Water-Desert View 230 kV T/L	1240 Amps (N) 1425 Amps (E)	N/A	106.5% 92.3%	N/A	118.7% 102.9%
Kramer-Lugo No.1 and No.2 230 kV T/Ls Loss of Lugo-Desert View 230 kV T/L	1240 Amps (N) 1425 Amps (E)	N/A	124.0% 107.4%	N/A	136.4% 118.3%

Under the loss of the Cool Water-Desert View 230 kV transmission line, the SPS should trip one of the HLSP generation units. Under the loss of the Lugo-Desert View 230 kV transmission line, the SPS should trip one of the HLSP generation units, as well as the generation projects directly connected to the Desert View Substation. Transfer tripping the generation projects directly connected to the Desert View Substation would not result in increasing the outage exposure of these projects, because the Desert View Substation is connected in a radial fashion prior to adding the Cool Water-Desert View 230 kV transmission line. Such radial method of service would result in disconnecting from the source (Lugo Substation), without a second source line.

DOUBLE OUTAGE CONTINGENCY (N-2)

Without the above additional facility upgrades in place to mitigate the identified base case overload problems, the study determined that the system is also inadequate to accommodate the full output of the HLSP Project under specific double outage contingencies. The HLSP Project will need to be added to the existing Kramer SPS (loss of the Lugo-Kramer No.1 and No.2 230 kV transmission lines) if the additional transmission upgrades identified to mitigate the base case overloads are not implemented.

With the inclusion of the additional upgrades identified for mitigating the HLSP Project triggered base case thermal overloads, the study did not identify any N-2 thermal overload or transient stability problems for the local area. However, on an overall system level, the study determined that the total amount of Lugo Area generation export (South of Lugo and Lugo-Vincent 500 kV transmission lines) is limited to approximately 7,800 MW. With the addition of more generation resources in the North and East of Lugo areas, the amount of excess generation requiring export will eventually exceed 7,800 MW. To increase Lugo Area export limits, additional transmission capacity will be required. However, such requirement is not triggered solely by the addition of the HLSP Project, and therefore, such facility upgrades will be evaluated and recommended as part of a larger study effort in the area (either through the RETI study process or the annual CAISO Transmission Expansion Planning Process).

Transient Stability

The study determined that with the inclusion of the additional upgrades identified for mitigating the HLSP Project triggered base case thermal overloads, the HLSP Project will not need to participate in the existing Kramer SPS. However, the study identified that the tripping requirements for mitigating transient stability problems under single outage of the Lugo-Desert View 230 kV transmission line are more stringent than the tripping requirements for mitigating thermal overloads. Under this outage, the SPS should include tripping of the entire HLSP Project.

Post-Transient Voltage

The study determined that without the facility upgrades identified under base case conditions, the HLSP Project aggravates previously identified voltage problems, including case non-convergence, which are indicative of a potential voltage collapse. The inclusion of the facility upgrades identified for queued ahead generation projects mitigates these problems.

Short-Circuit Duty

The short-circuit duty (SCD) analysis included all queued ahead generation projects based on their application date, but did not model corresponding transmission upgrades. Three-phase-to-ground short-circuit duty study identified two 500 kV, seven 230 kV, and four 115 kV substation locations requiring engineering review. Single-line-to-ground short circuit duty study identified two 500 kV, five 230 kV and one 115 kV substation where duty was increased by more than 0.1 kA, and duty was in excess of 60% of the minimum circuit breaker rating.

Based on the SCD study results and engineering review, the addition of the HLSP Project triggers the need for circuit breaker replacement at the Kramer Substation. It should be noted that a number of projects have recently withdrawn from the interconnection queue or have modified technical parameters consistent with allowances under the LGIP. In addition, the transmission upgrades identified to mitigate the HLSP Project triggered base case overloads have not been included into the short-circuit duty analysis. Consequently, a reevaluation of short-circuit duty will be required as part of the Facilities Study to capture the recent generation interconnection queue withdrawals and modifications, as well as the facility upgrades associated with the mitigation plan identified in this analysis.

Deliverability Assessment

Separate studies entitled “Deliverability Assessments” were performed by the CAISO, which determined that the HLSP Project was not deemed deliverable to the Grid for Resource Adequacy (RA) purposes. The modeling assumptions for the Deliverability Assessment are different from the modeling assumptions in this System Impact Study. For details of the methodology and assumptions for performing the Deliverability Assessment, please refer to the Baseline Generation Deliverability Study – 2007 Q3 Study Plan posted at <http://www.caiso.com/1c5d/1c5ddc8a63cd0.pdf>. In particular, the 2007 Q3 Deliverability Assessment modeled the following transmission system upgrades:

- Lugo 500/230 kV No.3 Transformer Bank (AA-Bank);
- Kramer-Lugo No.3 230 kV Transmission Line;²⁰
- Victor-Lugo No.3 230 kV Transmission Line;
- Replacement of the Lugo-Pisgah No.2 230 kV with a new 500 kV Transmission Line;
- Operation of the remaining Lugo-Pisgah 230 kV line as two radial lines
 - Radial into Lugo connecting the new Desert View Substation;
 - Radial into Pisgah connecting the new Abelia and new Galway Substations.

The study did not include the new Cool Water-Desert View 230 kV transmission line(s) recommended in this study to mitigate the identified base case thermal overloads on the two Kramer-Lugo 230 kV transmission lines.

²⁰ SPS was not modeled due to unknown specifications. With SPS and the additional Kramer-Lugo No.3 Transmission Line, the HLSP Project would be deemed deliverable.

Cost Estimates

The ***Nonbinding*** Cost Estimate for the interconnection facilities and reliability network upgrades triggered by the HLSP Project is \$131.7²¹ million. The ***Nonbinding*** Cost Estimate for the maximum exposure for network upgrades triggered by queued ahead projects is \$257.0²² million. These estimates have been developed without detailed cost engineering, and will be refined in the Facilities Study.

Facilities Study

A Facilities Study will be required for the HLSP Project. The Facilities Study will include detailed cost estimates for SCE network upgrades and direct assignment interconnection facilities required to interconnect the HLSP Project to the grid and should:

1. Develop cost estimates and schedule for the construction of a new Hinkley Substation to loop the existing Cool Water-Kramer No.1 230 kV transmission line. The Substation should initially consist of a 230 kV four-bay position, with five circuit breakers to interconnect the project. (Case A)
2. Develop cost estimates and schedule for the looping of the existing Cool Water-Kramer 230 kV transmission line into the new Hinkley Substation. (Case A)
3. Develop cost estimate and schedule for the protection and telecom requirements to support the new Hinkley Substation. (Case A)
4. Develop cost estimates and schedule for the construction of a new Desert View substation to loop the existing Lugo-Pisgah No.1 230 kV transmission line. The Substation would be sized for 500/230/115 kV facilities and would be capable of ultimately accommodating four 500/230 kV transformer banks, but would initially be equipped with eight 230 kV bay positions. (Second four-bay position - Case A, Initial four-bay position - Case B) and 13 circuit-breakers (Four are Case A, five are Case B, and remaining 4 are generation direct assignment).
5. Develop cost estimates and schedule for the removal of approximately 16-miles of existing Lugo-Pisgah No.1 230 kV transmission line between Lugo and the proposed Desert View Substation. (Case B)
6. Develop cost estimates and schedule for the construction of a new 16-mile double-circuit 500 kV Lugo-Desert View transmission line with one circuit energized at 500 kV and the second circuit initially energized at 230 kV. (Case B)
7. Develop cost estimate and schedule for the protection and telecom requirements to support the new Desert View Substation. (Case B)

²¹ This cost estimate can increase to \$227.2 million (excluding right-of-way for Cool Water-Desert View 230 kV transmission line) depending on the final routing alternative selected for queued ahead generation triggered reliability upgrades.


²² This cost estimate can decrease to \$216.3 million (excluding right-of-way) depending on the final routing alternative selected for queued ahead generation triggered reliability upgrades.

8. Develop cost estimates and schedule for the installation of the third Lugo 500/230 kV transformer bank. (Case B)
9. Develop cost estimates and schedule for the construction of a third Lugo-Victor 230 kV transmission line. (Case B)
10. Develop cost estimates and schedule for the construction of a new 37-mile double-circuit 230 kV Cool Water-Desert View transmission line (2B-1590 ACSR) with one initial circuit. (Case A)
11. Develop cost estimate and schedule for the SPS required to trip the HLSP under two specific single outage contingencies. (Case A)
12. Review identified substation locations shown in Table 2-5 through Table 2-8 to evaluate the need for circuit breaker replacements and develop corresponding cost estimates.
13. Perform any technical assessment required to account for potential queued ahead generation project withdrawals (CAISO #109, #110, #114, #115, #116, and #120) consistent with the CAISO Petition for Waiver of Tariff Provisions to Accommodate Transition to Reformed Large Generator Interconnection Procedures, and Motion to Shorten Comment Period FERC Filing, if approved at FERC.
14. SCE and the CAISO to determine the appropriate classification of the identified Network Upgrades (i.e. Reliability Network Upgrades versus Delivery Network Upgrades.)

Interconnection System Impact Study


Appendix A – Stability Plots

BUS_VOLT_MAG FOR SCE North of Lugo



Harper Lake System Impact Study (TOT175)
 Heavy Summer Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo



Harper Lake System Impact Study (TOT175)
 Heavy Summer Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

1.20

0.20


-1.0 10.0

Time(sec)

0.2000 vbus	24086	LUGO	500.0	0	0.0	1	1	1.2000
0.2000 vbus	24701	KRAMER	230.0	0	0.0	1	1	1.2000
0.2000 vbus	24601	VICTOR	230.0	0	0.0	1	1	1.2000
0.2000 vbul	24702	KRAMER	115.0	0	0.0	1	1	1.2000
0.2000 vbul	24602	VICTOR	115.0	0	0.0	1	1	1.2000
0.7000 vbus	24156	VINCENT	500.0	0	0.0	1	1	1.2000


Thu Mar 27 11:51:31 2008

BUS_VOLT_MAG FOR SCE North of Lugo



Harper Lake System Impact Study (TOT175)
 Heavy Summer Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)


BUS_VOLT_MAG FOR SCE North of Lugo



Harper Lake System Impact Study (TOT175)
 Heavy Summer Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)


Thu Mar 27 11:51:38 2008

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Summer Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Summer Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Summer Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Summer Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Summer Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Summer Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Summer Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Summer Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Summer Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Summer Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Summer Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Summer Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo



Harper Lake System Impact Study (TOT175)
 Heavy Summer Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo



Harper Lake System Impact Study (TOT175)
 Heavy Summer Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

1.20

0.20


-1.0 10.0

Time(sec)

0.2000	vbus	24086	LUGO	500.0	0	0.0	1	1	1.2000
0.2000	vbus	24701	KRAMER	230.0	0	0.0	1	1	1.2000
0.2000	vbus	24601	VICTOR	230.0	0	0.0	1	1	1.2000
0.2000	vbul	24702	KRAMER	115.0	0	0.0	1	1	1.2000
0.2000	vbul	24602	VICTOR	115.0	0	0.0	1	1	1.2000
0.7000	vbus	24156	VINCENT	500.0	0	0.0	1	1	1.2000


Thu Mar 27 11:52:02 2008

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Summer Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
Heavy Summer Conditions: Year 2013
POST-PROJECT with Network Upgrades
N-0: Sensitivity Study Case
Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo



Harper Lake System Impact Study (TOT175)
 Heavy Summer Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Summer Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

Interconnection System Impact Study


Appendix B – Stability Plots

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo



Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

Figure 1 is a line graph showing the time response of the bus voltage (V_{bus}) and the voltage of the busbar (V_{bul}) for different fault locations (LUGO, KRAMER, VICTOR, VINCENT) and fault types (vbus, vbul). The x-axis is Time (sec) from -1.0 to 10.0. The y-axis is voltage from 0.20 to 1.20. The graph shows a sharp drop in voltage at $t=0$, followed by a recovery and oscillation. The solid blue line represents the bus voltage (V_{bus}) and the dashed lines represent the busbar voltage (V_{bul}) for different fault locations and types.

Time (sec)	0.2000 vbus	0.2000 vbus	0.2000 vbus	0.2000 vbul	0.2000 vbul	0.2000 vbul	0.7000 vbus	24086	LUGO	500.0	0	0.0	1	1	1.2000
-1.0	1.00	1.00	1.00	1.00	1.00	1.00	1.00	24701	KRAMER	230.0	0	0.0	1	1	1.2000
0.0	0.20	0.20	0.20	0.20	0.20	0.20	0.20	24601	VICTOR	230.0	0	0.0	1	1	1.2000
1.0	0.80	0.80	0.80	0.80	0.80	0.80	0.80	24702	KRAMER	115.0	0	0.0	1	1	1.2000
2.0	0.90	0.90	0.90	0.90	0.90	0.90	0.90	24602	VICTOR	115.0	0	0.0	1	1	1.2000
3.0	0.85	0.85	0.85	0.85	0.85	0.85	0.85	24156	VINCENT	500.0	0	0.0	1	1	1.2000
4.0	0.90	0.90	0.90	0.90	0.90	0.90	0.90								
5.0	0.85	0.85	0.85	0.85	0.85	0.85	0.85								
6.0	0.90	0.90	0.90	0.90	0.90	0.90	0.90								
7.0	0.85	0.85	0.85	0.85	0.85	0.85	0.85								
8.0	0.90	0.90	0.90	0.90	0.90	0.90	0.90								
9.0	0.85	0.85	0.85	0.85	0.85	0.85	0.85								
10.0	0.90	0.90	0.90	0.90	0.90	0.90	0.90								


Thu Mar 27 11:52:31 2008

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo




Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo



Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

BUS_VOLT_MAG FOR SCE North of Lugo



Harper Lake System Impact Study (TOT175)
 Heavy Spring Conditions: Year 2013
 POST-PROJECT with Network Upgrades
 N-0: Sensitivity Study Case
 Contains Critical Energy Infrastructure Information (CEII)

APPENDIX C

SOUTHWEST GAS CORPORATION CORRESPONDENCE

From: Nasrin Houston [Nasrin.Houston@swgas.com]
Sent: Monday, June 08, 2009 10:28 AM
To: Frederick Redell
Cc: Christopher.Glosemeyer@abencs.abengoa.com; scott.frier@solar.abengoa.com; Erich Trombley
Subject: RE: Gas Interconnection for Solar Project

Fred,

Our Engineering Planning has completed their study and determined that the existing 16-inch pipeline has sufficient capacity to serve the Mojave Solar project with 42Mcfh load at 30 psig delivery pressure. To serve the two solar plants at a minimum the following facilities are required.

- A tap off of the 16 inch pipeline which includes pressure regulation
- Gas line from the tap to each delivery location
- A high pressure meter set at each delivery location

I hope this information helps. If you have any questions please contact me.

Regards,

Nasrin Houston
 Industrial Gas Engineer
 Southwest Gas Corporation
 4300 West Tropicana Avenue
 Las Vegas, NV 89103
 P 702-365-2549I M 702-682-9395I F 702-740-9209
 E nasrin.houston@swgas.com

>>> Frederick Redell <fred@redellengineering.com> 5/27/2009 7:35 PM >>>
 Nasrin,

We are set as previously described; no changes needed. Please let me know when can have the engineering study available.

Thanks,
 -Fred

From: Nasrin Houston [Nasrin.Houston@swgas.com]
Sent: Wednesday, May 20, 2009 2:14 PM
To: Frederick Redell
Subject: RE: Gas Interconnection for Solar Project

Thank you Fred. I will watch for your email with the revised flow/pressure numbers.

Nasrin

>>> Frederick Redell <fred@redellengineering.com> 5/20/2009 1:58 PM >>>

Nasrin,

Attached is the project boundary and the approximate locations of the boilers in Google Earth format. You should be able to clearly see where your pipeline (Harper Lake Rd) intersects the project and is with respect to the service locations.

We are re-running our numbers on gas flows and pressures to make sure we have the right values. Please give me a day or so to confirm. Worst case we would need twice the flow and twice the pressure. This should still be well within the capability of that line but I want to be sure we need that before we proceed with those numbers.

Regards,
Fred

-----Original Message-----

From: Nasrin Houston [mailto:Nasrin.Houston@swgas.com]
Sent: Wednesday, May 20, 2009 11:42 AM
To: Frederick Redell
Subject: Re: Gas Interconnection for Solar Project

Thank you.

-----Original Message-----

From: Frederick Redell <fred@redellengineering.com>
To: Houston, Nasrin <Nasrin.Houston@swgas.com>

Sent: 5/20/2009 11:39:54 AM
Subject: RE: Gas Interconnection for Solar Project

Nasrin,

I was out of the office until just now and will put together Google files for your reference.

-Fred

From: Frederick Redell
Sent: Wednesday, May 13, 2009 8:58 AM
To: Frederick Redell; 'Nasrin Houston'
Cc: 'Christopher.Glosemeyer@abencs.abengoa.com'
Subject: RE: Gas Interconnection for Solar Project

Nasrin,

As we discussed on the phone, if I have 30 +/- 5 psig delivery pressure at each power island, that should be fine.

-Fred

The information in this electronic mail communication contains confidential information which is the property of the sender and may be protected by the attorney-client privilege and/or attorney work product doctrine. It is intended solely for the addressee. Access to this e-mail by anyone else is unauthorized by the sender. If you are not the intended recipient, you are hereby notified that any disclosure, copying, or distribution of the contents of this e-mail transmission or the taking or omission of any action in reliance thereon or pursuant thereto, is prohibited, and may be unlawful. If you received this e-mail in error, please notify us

immediately of your receipt of this message by e-mail and destroy this communication, any attachments, and all copies thereof. *Thank you for your cooperation.*

The information in this electronic mail communication contains confidential information which is the property of the sender and may be protected by the attorney-client privilege and/or attorney work product doctrine. It is intended solely for the addressee. Access to this e-mail by anyone else is unauthorized by the sender. If you are not the intended recipient, you are hereby notified that any disclosure, copying, or distribution of the contents of this e-mail transmission or the taking or omission of any action in reliance thereon or pursuant thereto, is prohibited, and may be unlawful. If you received this e-mail in error, please notify us immediately of your receipt of this message by e-mail and destroy this communication, any attachments, and all copies thereof. *Thank you for your cooperation.*

APPENDIX D

SOLAR PLANT DETAILS

APPENDIX D

DETAILED DESCRIPTION OF SOLAR POWER PLANT

Appendix D: Detail of Solar Power Plant

This appendix contains specific information and details of the AMSP power plant components, electrical processes, civil and physical construction, as well as plant operations. The information supplements the Proposed Action in Chapter 2 and provides context to Chapter 4. The start of commercial operation is planned for winter of 2012, subject to timing of regulatory approvals and the achievement of Project equipment procurement and construction milestones.

Major Solar Equipment and Material

The major pieces of equipment for the proposed solar portion of each plant are as follows:

- Solar collector arrays (SCA),
- SCA components: mirrors, HCEs, ball-joint connectors, etc.,
- HTF,
- SSG System,
- HTF freeze-protection heat exchangers,
- HTF pumps,
- HTF expansion vessels and tanks, and
- HTF piping headers.

Each solar field encompasses approximately 710 acres of the plant sites and utilizes solar trough technology similar to the nine existing SEGS units but with design improvements to enhance performance.

Solar Collector Arrays. The Solar Collector Arrays (SCAs) are the mirrored, parabolic trough structures. Each SCA will be 125 to 150 meters long. The SCA rotate around a north-south axis to track the sun through the sky during the day. The axis of rotation is located near the collector center of mass to minimize the required tracking power. The drive system will use hydraulic rams or electric motors to position the collector depending on final design. The closed-loop tracking system relies on a sun sensor or position feedback sensor for the precise alignment

Mirrors. The SCA are fitted with curved mirrors which are specifically engineered and manufactured for solar parabolic trough applications. The current state-of-the-art, low iron glass mirrors are highly reliable. There has been no long-term degradation in the reflective quality of the low-iron glass mirrors; ten year-old mirrors can be cleaned and brought back to like-new reflectivity. Long-term endurance of the mirror, as measured by the experience at SEGS, indicates that mirror life of 30 years or more can be expected for the Project.

Development of an efficient and cost-effective program for monitoring mirror reflectivity and washing is critical. Differing seasonal soiling rates (higher in the summer) require flexible procedures. Operations and Maintenance (O&M) procedures at the SEGS plants were well established and similar methods will be used for this Project. All cleaning methods use demineralized water for best effectiveness. The periodic monitoring of mirror reflectivity provides a valuable quality control tool for washing and helps to optimize wash labor. As a

general rule, the reflectivity of glass mirrors can be maintained near design levels with a good washing program.

Heat Collection Elements. The HCE consists of a steel tube with a selective surface, surrounded by an evacuated glass tube insulator. The coating gives it excellent selective heat transfer properties with a high solar absorptivity and low thermal emissivity. The HCE incorporates glass-to-metal seals and metal bellows to achieve the vacuum-tight enclosure. The vacuum enclosure serves primarily to protect the selective surface and to reduce heat losses by insulating it while having high transmissivity.

The outer glass cylinder has an anti-reflective coating on the outer surfaces to reduce transmissive losses through the glass tube. Typically, getters (metallic substances that are designed to absorb gas molecules) are installed in the vacuum space to absorb hydrogen and other gases that permeate into the vacuum annulus over time to maintain its insulating properties.

Connectors. It is expected that a hard-piped assembly with ball joints will be used to connect the SCAs to the headers and SCAs to each other, similar to those being used at the SEGS plants at Harper Dry Lake. Based upon experiences at SEGS, the ball joint assembly has a number of advantages over previous designs using flexhoses, including reduced failures, lower cost, lower head loss, and reduced heat losses.

Heat Transfer Fluid. It is expected that Therminol™ VP-1, Dowtherm A, or equivalent will be used as the HTF. These synthetic oils are special high-temperature oils with an excellent operating history and are widely used in solar thermal and other high-temperature heat transfer applications. These oils are aromatic hydrocarbons, specifically biphenyldiphenyl oxide. The oil is regulated as a hazardous material by the State of California.

Solar Steam Generator System. SSGs are designed differently than conventional gas-fired boilers in that they are “fired” with hot HTF instead of hot combustion gases. The design uses natural circulation steam drums with shell-and-tube evaporators. The SSG system includes heat exchangers for preheating the condensate, for steam production, for superheating the steam, and for reheating steam.

HTF Freeze Protection Heat Exchangers. To eliminate the problem of HTF freezing, steamfed shell-and-tube heat exchangers will be used to keep the HTF above 100 °F whenever the facility is offline and ambient temperature warrants. The auxiliary boilers will supply the heat for freeze protection. The use of steam-fed HTF heat exchangers reduces the number of individual emission sources (i.e. eliminates natural-gas-fired HTF heaters since an auxiliary boiler exists for other auxiliary purposes).

HTF Pumps. HTF pumps are used to circulate the HTF through the solar field and back to the power island for steam generation and are specifically designed for this high temperature oil

application. Pumps for high temperature applications typically include seal cooling and high temperature materials to preserve component function under extreme conditions.

HTF Expansion Vessels and Tanks. To accommodate the volumetric change that occurs when heating the HTF to the operating temperature, expansion vessels and tanks are required. Nitrogen will be used to provide a blanket on the headspace of the expansion vessels and tanks. The nitrogen blanket prevents oxidation and contamination of the HTF by reducing its exposure to atmospheric air. In the expansion vessels, the nitrogen also assists with meeting the net positive suction head requirements for the HTF pumps. HTF expansion tanks are at a lower pressure and temperature than expansion vessels to minimize HTF loss if venting is required during daily cyclical operations. It is anticipated that there will be eight expansion vessels and two overflow tanks on each power island.

HTF Piping Header. HTF is transported through the solar field using a supply-and-return header system. The header system assists in balancing flow through the SCA loops and their associated HCEs. Piping expansion loops will be located throughout the plant as required to maintain the composite pipe stress within ASME B31.3 code allowable limits. The composite pipe stress includes seismic and thermal stresses. It is anticipated that the solar field will be divided into sections with automatic or semiautomatic isolation valves. The isolation valves will either be triggered automatically (e.g., by ground acceleration in the event of an earthquake) or by the operator inside the control room. The isolation valves will be located to minimize the volume of HTF leakage during a pipe failure. The piping in the solar array will be designed and constructed to allow movement due to thermal expansion – the steel piping in the mirrored trough sections of the array will be connected to the HTF distribution headers with ball joints and the piping will not be rigidly mounted to foundations or other structures, structurally decoupling the system from seismic ground shaking in the event of an earthquake.

These following components comprise the working elements of each power island in the solar plant. Each power island is largely identical. As shown, major components of each Alpha and Beta power island include:

- Solar steam generators (SSG) and associated heat exchangers,
- One steam turbine-generator (STG) and condenser,
- Electrical switchyard with step-up transformer and auxiliary transformer,
- One wet cooling tower,
- One natural-gas-fired auxiliary boiler,
- Steam-fed HTF freeze protection heat exchangers,
- HTF expansion vessels and HTF expansion tanks,
- Firewater pump and pump house with associated diesel fuel tank,
- One raw water storage tank,
- One combined service water and firewater storage tank,
- Various water treatment storage tanks,
- Demineralized water storage tank, and
- Ancillary equipment.

Process Description

The power generation process and thermodynamic cycle employed by the Project at both the Alpha and Beta power islands is described below. The major elements of each power island include the following:

- One STG,
- SSGs and associated SSG heat exchangers,
- One water-cooled condenser,
- Feedwater pumps,
- One deaerator,
- Multiple feedwater heaters, and
- One wet cooling tower.

The proposed power cycle is the Rankine-with-reheat thermodynamic cycle with heat supplied via HTF, heated by the solar field to a temperature of approximately 740°F. Each plant site utilizes approximately 710 acres of the total land for solar thermal collector arrays. A preliminary heat balance diagram for the process is included in Figure D-1, Heat Balance Diagram.

Overall annual availability of the proposed Project facilities is expected to be a minimum of 95 percent, excluding non-daylight hours. The Project's capacity factor depends on the local solar insolation, but estimated to be approximately 600,000 to 630,000 megawatthours (MWh) per year net (both Plants combined) while operating for approximately 3,024 hours per year. This production estimate was made using the Solar Advisor Model software developed and maintained by the National Renewable Energy Laboratory.

The Project will use the Rankine-with-reheat thermodynamic cycle, described as follows:

- Process 1: The working fluid (water) is pumped from low to high pressure. During this process, steam extracted from the STG is used to preheat the water prior to entering the SSG system, which increases overall cycle efficiency.
- Process 2: The high pressure working fluid enters the SSG system where it is heated by the HTF to become superheated steam.
- Process 3: The superheated steam expands through the high pressure section of the steam turbine turning the generator to produce electricity. This steam is then reheated in a reheater that is part of the SSG system and sent to the low pressure steam turbine. All sections of the STG decrease the temperature and pressure of the steam with the low pressure section extracting the last available energy from the steam until the steam is operating under vacuum pressure.
- Process 4: The wet steam from the low pressure section of the steam turbine then enters the condenser where it is condensed back into a saturated liquid. The condensed liquid returns to Process 1.

The solar field provides the heat input in Process 2 and for the reheater in Process 3. As the HTF is circulated through the solar field, light from the sun reflects off the solar collector's parabolic troughs and is concentrated on the heat collection elements (HCEs) located at the focal point of the parabola. HTF flowing through these HCEs absorbs the heat and provides a high-temperature energy source for the Rankine Cycle.

Low quality waste heat is rejected in Process 4. As the turbine exhaust is condensed, the heat is transferred to the cooling-tower circulating water. The warm cooling tower circulating water carries the heat to the wet, mechanical draft cooling tower where the heat is rejected via evaporation and convection, returning cooled water to the condenser.

Steam Turbine-Generator

Each power island sends steam from the SSGs to the STG. The steam expands through the STG turbine blades to drive the steam turbine, which in turn drives the generator. The Project's STGs are expected to be two-casing, reheat type with multiple feedwater heater extraction points and axial low-pressure exhaust. The STG is equipped with accessories required to provide efficient, safe, and reliable operation, including the following:

- Governor system,
- Steam admission system,
- Gland seal system,
- Lubrication oil system including oil coolers and filters,
- Generator coolers, and
- Metal enclosures designed for outdoor service for STG auxiliary systems.

Electrical System Description

All of the net power produced by the proposed facility is currently expected to be delivered to the statewide transmission grid through the Project's interconnection with the existing Kramer-Cool Water 230 kV transmission line. Roughly 10% of the Project's output will be used onsite for plant auxiliaries such as pumps, control systems, and general facility loads including lighting and heating, ventilation, and air conditioning (HVAC). Some of the power needed for on-site uses will be converted from alternating current (AC) to direct current (DC) for power plant control systems and emergency backup systems such as lube oil pumps and the STG turning gear. The descriptions of the major electrical systems and equipment provided in the following text reflect AC power unless otherwise noted. One-line diagrams of the major electrical systems are presented in Figures D-2 through D-11, Electrical Diagrams.

Major Electrical Equipment and Systems

On each power island, power will be generated by its STG at 13.8 kV, depending on the final generator selection, and stepped up by a fan-cooled generator step-up transformer in the 230-kV power island switchyard for connection to the transmission interconnection. Plant auxiliary load will be from an auxiliary power transformer fed from the 230-kV power island switchyard

with a step-down transformer and distributed internally to the plant loads at 13.8 kV. There will be one emergency diesel engine-driven generator for each power island to provide standby power and facilitate plant shutdown in the event of power disruption. Each power island can be run independently.

Grounding and Surge Protection

All electrical systems are potentially susceptible to ground faults, lightning, and switching surges which could pose hazards to site personnel and electrical equipment if not properly grounded.

The station grounding system provides an adequate path to ground and bonding to permit the dissipation of current created by these events. The station-grounding grid will be designed for adequate capacity to withstand ground fault current and limit step and touch potentials in coordination with protective relaying and equipment purchased to limit the exposure to equipment and personnel.

Bare conductors will be installed below-grade in a grid pattern throughout the power island and solar field areas. Each junction of the grid will be bonded together by an exothermic weld or compression connection (above grade only). Soil resistivity readings will be used to determine the necessary numbers of ground rods and grid spacing to ensure safe step and touch potentials under severe fault conditions. Grounding stingers will be brought from the ground grid to connect to building steel and non-energized metallic parts of electrical equipment.

Electrical Generation

The Project's STGs will tie into a 230-kV onsite switchyard for each power island. Each 230-kV onsite switchyard will be a 230-kV single-breaker design, see Figure D-12. Each onsite switchyard connects to the interconnection substation on the Project site. The interconnection substation will be a 230-kV, four-position, breaker-and-a-half design consisting of one position for each of the power island interconnections.

Each generator will contain current transformers (CTs), surge arrestors, and neutral grounding transformers for protection and metering. The neutral grounding transformer will be approximately 20 kilovolt amps (kVA) on each unit. The eighteen CTs on each unit will be 8,000/5 amps (A). Surge arrestors will be metal oxide varistor (MOV) type rated for 30 kV Basic Insulation Level (BIL) to withstand high-voltage impulses.

Each generator will be connected to a main power transformer via an isolated phase bus (IPB). The IPB will be rated for 15 kV/8,000 A. Each IPB will be tapped with potential transformers and lightning arrestors for metering and protection. The potential transformers will be rated for 14.4/0.12 kV.

The main power transformer (MPT) will be approximately 175 megavolt-amps (MVA), 13.8/230 kV, two-winding, delta-wye grounded, 9 %Z (impedance) and fan-cooled (using oil-immersed natural circulation, multi-stage, forced air cooling). The neutral point of high-voltage winding will be solidly grounded. The main step-up transformer will have metal oxide surge arrestors connected to the high-voltage terminals and will have manual de-energized ("no-load") tap changers located in high-voltage windings to allow for a nominal secondary voltage plus or

minus five percent with a 2.5 percent differential to allow for generator output voltage variations. The step-up transformer will rest on a concrete pad with a perimeter berm, designed to contain the transformer non-PCB insulating oil in the event of a leak or spill, and will have a deluge-type fire protection system.

The power island switchyard will be located near the Generator Step-up (GSU) and will require a minimum 556 thousand circular mils (kcmil) size steel-reinforced, aluminum conductor (ACSR) from the interconnection substation to each transformer. Each switchyard will consist of two 245 kV switchyard circuit breaker for the protection of the line to the grid, with 245 kV, 1200 A disconnect switches on each side of the breaker for maintenance and isolation of the associated transformer. The switchyard breaker will be of the dead tank design with 1200/5 multi-ratio current transformers on each bushing. Additionally each circuit breaker will be equipped with 230/0.12 kV capacitor-controlled voltage transformers in a stand-alone cabinet for metering, synchronizing, and protection. Each circuit breaker shall be connected to each other with a 245 kV 1200 A bus to serve as the tie between the transmission line and the power transformers. This bus will be tubular aluminum alloy. Cable connections between the tube bus and equipment will be aluminum or aluminum alloy type cable. Tube, cables, and support structures will meet electrical and mechanical design standards. Each 245-kV bus will be equipped with 245/0.12 kV capacitor-controlled voltage transformers for metering and protection with the transmission line.

A disconnect switch will be located at the gen-tie line termination within the switchyard for line isolation. The switchyard will be equipped with sensitive 1200/5 A current transformers in each circuit breaker and 245/0.12 kV capacitor controlled voltage transformers located on the 230 kV switchyard bus for net revenue metering. Lightning arresters will be provided in the area of the takeoff towers to protect against surges due to lightning strikes and switching.

Electrical faults will be detected, isolated, and cleared in a safe and coordinated manner as soon as practical to ensure the safety of equipment, personnel, and the public. Protective relaying will meet Institute of Electrical and Electronic Engineers (IEEE) requirements and be coordinated with the interconnected transmission system owner.

Electrical System for Plant Auxiliaries

Power for each Plant's auxiliaries will be supplied at 13.8 kV from one non-redundant three-winding auxiliary power transformers (APT). Each APT is connected to the 15kV medium voltage switchgear via a 15 kV/1600 A non-segregated bus duct.

The APT will be approximately 20 MVA, 230/13.8 kV, two-winding, delta-wye grounded, 8 %Z (impedance) and fan-cooled (using oil-immersed natural circulation, multi-stage, forced air cooling). The neutral point of the low-voltage winding will be high-resistant grounded. The auxiliary step-up transformer will have metal oxide surge arrestors connected to the high-voltage terminals and have manual de-energized ("no-load") tap changers located in high-voltage windings to allow for a nominal secondary voltage plus or minus five percent with a 2.5 percent differential to allow for generator output voltage variations. The auxiliary power transformer will rest on a concrete pad with a perimeter berm designed to contain the

transformer non-PCB insulating oil in the event of a leak or spill and has a deluge-type fire protection system.

The 15 kV medium-voltage switchgear distributes power to the plant's 4-kV and 0.48-kV motors through auxiliary transformers. The low voltage side of each of the auxiliary transformers connects to the 480-Volt (V) switchgear. The 480-V switchgear distributes power to the plant's large 480-V loads and to the various 480-V motor control centers (MCCs) supplying power to the smaller plant loads. The MCCs distribute power to the plant's intermediate 480-V loads and to power panels serving small 480-V loads.

In the event of power loss by the APT, an emergency diesel engine-driven generator will supply power to the 15-kV switchgear for proper shutdown of the plant, under a load-shedding scheme. The standby generator will be equipped with synchronizing breakers for maintenance testing under normal load conditions.

DC Power Supply System

Each proposed Plant is equipped with a (direct current) DC power supply system consisting of a bank of 125-VDC batteries, a 125-VDC battery charger, metering, ground detectors, and distribution panels. Under normal operating conditions, the battery charger supplies DC power to the DC loads. The battery charger receives 480-V, three-phase AC power from the electrical distribution system serving plant auxiliaries. The battery charger continuously charges the battery bank while supplying DC power to the DC loads. Under abnormal or emergency conditions when AC power is not available, the battery bank supplies DC power directly to the DC loads. The battery bank will be sized to power the DC loads and essential-service AC loads through an inverter for a sufficient amount of time to provide for safe and damage-free shutdown of the power plant. Recharging the battery bank will occur whenever AC power is reestablished.

The DC power supply system will provide power for critical control circuits, power for control of the 13.8-kV, 4.16-kV and 480-V switchgear, and power for DC emergency backup systems. Proposed emergency backup systems include DC lighting and DC lube-oil and seal-oil pumps for the STG.

Essential Service AC System

An essential-service AC system (120 V, single-phase) will provide power to essential instrumentation, critical equipment loads, safety systems, and equipment protection systems that require uninterruptible AC power. The essential-service AC system and the DC power supply system will both be designed to ensure that critical safety and equipment protection control circuits are always energized and able to function in the event of unit trip or loss of AC power.

The proposed essential-service AC system consists of an inverter, a solid-state transfer switch, a manual bypass switch, an alternate AC source transformer and voltage regulator, and AC panel boards. The DC power supply system is the normal source of power to the essential-service AC system. Power flows from the DC power supply system through the inverter to the AC essential-service panel boards. The solid-state transfer switch continuously monitors both the

inverter output and the alternate AC source. Upon loss of the inverter output and without interruption of power, the transfer switch automatically transfers essential-service AC loads from the inverter output to the alternate AC source. The manual bypass switch enables isolation of the inverter and transfer switch for testing and maintenance without interruption of power to the essential-service AC loads.

Plant Auxiliary Systems

Auxiliary Boiler

One nominal 15,000-pound-per-hour auxiliary boiler will be included on each power island. This auxiliary boiler will be able to provide steam to the HTF freeze protection heat exchangers, steam turbine seal system, deaerator and other components while the SSG is offline. Once the plant commences normal operations, the use of the natural-gas-fired auxiliary boilers ceases. Each boiler will require approximately 21.5 million British thermal units per hour (MMBtu/hr) of natural gas at full load. The estimated annual natural gas usage for the Project (both auxiliary boilers combined) is 94,280 MMBtu.

Fuel Supply and Use

The auxiliary boilers will be fueled by natural gas supplied from an existing 16-inch diameter pipeline that runs to the project under Harper Lake Road. This pipeline was installed for the original six SEGS projects envisioned at Harper Dry Lake. SGC, the owner of the pipeline, confirms that excess capacity exists in the pipeline due to the sizing of the pipeline for the SEGS projects, which used natural gas to fire full-capacity boilers. No offsite pipeline facilities are proposed as a part of this Project. SGC was contacted and studied the demand requested and indicates that sufficient capacity exists to supply the Project.

Natural gas delivered to the Project site will flow through a revenue-quality flow meter, pressure regulation station, and filtering equipment and will provide gas to the auxiliary boilers. Safety pressure relief valves are provided downstream of the pressure regulation valves. The peak natural gas rate is 21.5 million British thermal units per hour (MMBtu/hr) for each auxiliary boiler. A maximum of 94,280 MMBtu/year of fuel consumption will be expected for each boiler. Table D-1 shows the typical composition of the natural gas used to fuel the Project's auxiliary boilers.

Table D-1: Typical Natural Gas Composition

Component	Mole Percent (%)
Methane, CH ₄	95
Ethane, C ₂ H ₆	2
Carbon dioxide, CO ₂	1
Nitrogen, N ₂	2
Total	100.0
Sulfur (grains per 100 dry standard cubic feet (dscf))	0.25
Higher Heating Value (Btu/scf)	1,025

Other Auxiliary Systems

The following plant auxiliary systems will control, protect, and support the power plant and its operation and are described below.

Distributed Control System

The Distributed Control System (DCS) will provide control, monitoring, alarm, and data storage functions for power plant systems. These include:

- Control of the STG, SSG System and balance-of-plant systems in a coordinated manner,
- Monitoring of operating parameters from plant systems and equipment,
- Visual display of the associated operating data to control operators and technicians,
- Detection of abnormal operating parameters and parameter trends,
- Provision of visual and audible alarms to apprise control operators of such conditions, and
- Storage and retrieval of historical operating data.

The DCS is a microprocessor-based system. Redundant capability is provided for critical DCS components such that no single component failure will cause a plant outage. The DCS consists of the following major components:

- Computer monitor-based control operator interface (redundant),
- Computer monitor-based control engineering work station,
- Multi-function processors (redundant),
- Input/output processors (redundant for critical control parameters),
- Field sensors and distributed processors (redundant for critical control parameters),
- Historical data archive, and
- Printers, data highways, data links, control cabling, and cable trays.

The DCS is linked to the control systems furnished by the STG supplier and to the solar field controls. These data links will provide STG control, monitoring, alarm, and data storage functions via the control operator interface and control technician workstation of the DCS. The DCS has a supervisory control over the solar field. The control of SCA is done at SCA level and networking back to DCS, the methods could be fiber optic, Ethernet link or wireless control.

Lighting System

The Project's lighting system will provide operations and maintenance personnel with illumination in both normal and emergency conditions. The system will consist primarily of AC lighting, but will include DC lighting for activities or emergency egress required during an outage of the plant's AC electrical system. The lighting system will also provide AC convenience outlets for portable lamps and tools. Lighting will be designed to provide the minimum illumination needed to achieve safety and security objectives and will be shielded and oriented

to focus illumination on the desired areas and minimize additional nighttime illumination in the site vicinity.

Cathodic Protection System

Cathodic protection systems protect against electrochemical corrosion of underground metal piping and structures. Underground metal structures will have necessary cathodic protection based on soil conditions.

Freeze Protection System

Freeze protection systems (heat tracing) will be employed to protect small water and condensate piping systems that cannot be easily drained. Also, due to the high freezing temperature of the solar field's HTF (54°F), steam-fed HTF Freeze Protection heat exchangers will be provided to protect the system during the night hours and colder months, in addition to electric heat tracing and insulation.

Service Air and Instrument Air Systems

The service air system supplies compressed air to hose connections located at intervals throughout the power plant. Compressors deliver compressed air at a regulated pressure to the service-air piping network.

The instrument air system provides dry, filtered air to pneumatic operators and devices throughout the power plant. Air from the service air system is dried, filtered, and pressure regulated prior to delivery to the instrument-air piping network.

Telemetry

The AMSP will utilize electronic systems to control equipment and facilities' operations over a large site. Because of the presence of various important Department of Defense (DOD) facilities/activities in the general area (e.g., Edwards Air Force Base, China Lake Naval Weapons Center and associated ranges), the Project is sensitive to the need to ensure that use of the electronic spectrum by the AMSP will not interfere with DOD activities. The Project will coordinate any telemetry selection with the DOD as needed to ensure compatibility.

HTF Leak Detection

Leak detection of HTF will be accomplished in a combination of ways. Small leaks, possible at ball joints or other connections, will be located based on daily inspection of the solar field. Those small leaks could then be corrected via repacking of joints or valves or by minor repairs if needed. The ability to isolate loops and sections of the field will allow for quick repairs. Larger sudden leaks are a greater concern. In order to identify and react to such leaks quickly, the Project is considering a combination of remote pressure sensing equipment and remote operating valves that will allow for isolation of large areas of the field, or possibly the entire field. Such features will be developed as part of the detail design process.

Process Water and Water Treatment **Steam Cycle Process Water**

Makeup water for the steam cycle must meet ASME Boiler Code for silica and dissolved solids. To meet these specifications, water will be processed through a demineralized water system. This system is anticipated to consist of multiple unit operations, concluding with mixed-bed demineralizers. Water produced by this system will only be used for makeup to the steam cycle. The demineralized water treatment will consist of a final stage of RO treatment and mixed-bed ion-exchange polishers. The reject stream from the RO treatment is recycled back to the RO surge tank, resulting in no net waste stream. The mixed-bed ion-exchange units are designed for regeneration off-site, and also have no waste stream associated with this process.

Additional conditioning of the condensate and feedwater circulating in the steam cycle will be provided by means of a chemical feed system. To minimize corrosion, an oxygen scavenger for dissolved oxygen control and an alkaline solution for pH control are fed into the condensate. To minimize scale formation in the SSG, a solution of disodium phosphate (DSP) and trisodium phosphate may be fed into each feedwater system. The chemical feed systems will include an oxygen scavenger feed tank, an alkaline solution (amine) feed tank, and a phosphate solution feed tank. The feed tanks will be provided with two full-capacity metering pumps.

A steam cycle sampling and analysis system will monitor the water quality at various points in the plant's steam cycle. The water quality data will be used to guide adjustments in water treatment processes and to determine the need for other corrective operational or maintenance measures. Steam and water samples are routed to a sample panel where steam samples are condensed and the pressure and temperature of all samples are reduced as necessary. The samples are then directed to automatic analyzers for continuous monitoring of conductivity and pH. All monitored values are indicated at the sample panel and critical values will be transmitted to the plant control room. Grab samples will be periodically obtained at the sample panel for chemical analyses that provide information on a range of water quality parameters.

Circulating Water Treatment

The blowdown from the circulating water/cooling tower system will be continually treated by lime-softening clarification (clarifier) and filtration processes, and then delivered to a clearwell. A portion of this stream will then be further treated for various plant uses that require higher purity water, such as SCA cleaning and steam system makeup. This will be a demand-based usage, where any excess flow out of the clearwell is simply recycled back to the cooling tower for further use in the circulating water system. The clarifier will use lime (calcium hydroxide) and soda ash (sodium carbonate) to precipitate hardness and alkalinity from the cooling tower blowdown water. Each of these systems will include a bulk dry storage bin, slurry makeup tank, and two full capacity delivery pumps. The clarifier also will use magnesium hydroxide slurry, a coagulant (ferric chloride), and a flocculent polymer to aid in settling/removing suspended solids in the clarification process. Each of these chemicals will include a bulk storage tank and two full capacity metering pumps.

The clarifier solids will be further concentrated in a thickener. The overflow or clear water from the thickener will be recycled as makeup to the cooling tower. The thickener solids stream will then be delivered to a mechanical filter press, where remaining water will be removed, again

for reuse in the cooling tower. This process will allow for an efficient use of the water while reducing the capital and operating expense of other processes. This process reduces the metals content in the water prior to use elsewhere in the system along with extracting these prior to discharge in the evaporation ponds.

The overflow water from the clarifier will be delivered to the clarified water tank, and then pumped through a set of pressure filters. The pressure filters contain typical standard sand and anthracite granular media, and will remove the small amount of solids that carry over from the clarifier. The pressure filters will be backwashed periodically to remove accumulated solids. This backwash water will be recycled back to the clarifier for treatment, so that there is no net waste stream from the pressure filters. The pressure filter product stream will then be directed to the clear well tank.

Following the clear well, the water will be treated by the Cooling Tower Reverse Osmosis (CTRO) system, in order to be utilized for other plant requirements. As pre-treatment to the CTRO process, ion-exchange-type softeners will be utilized to remove any dissolved hardness minerals that remain after the clarifier. The softeners will be periodically regenerated using a salt (sodium chloride) solution. The waste from the softeners will be separated so that backwash and rinse water from the softeners will be recycled back to the clarifier for reuse and the brine stream will be delivered to the evaporation ponds.

The product stream from the CTRO is delivered to the RO surge tank. The flow out of the clear well and through the CTRO is demand-based, so that any excess clear well water will be recycled back to the cooling tower for further use. This format will minimize water usage of the Plant.

The CTRO utilizes several stages of reverse osmosis (RO) treatment to remove most of the mineral content of the water. The reject stream from the CTRO process will be brackish water; and this will be discharged to the evaporation ponds. The CTRO process is designed to minimize the amount of waste water sent to the Ponds. The RO surge tank water is withdrawn as required, for further treatment and ultimately for use in SCA washing and steam cycle makeup.

Fire Protection

Fire protection systems will be provided to limit personnel injury, property loss, and Project downtime resulting from a fire. The systems include a fire protection water system and portable fire extinguishers. The Project's fire protection water system will be supplied from a dedicated 360,000-gallon portion of the 1,930,000-gallon service water storage tanks located on each Plant site. One electric and one diesel-fueled backup firewater pump, each with a capacity of 3,000 gallons per minute, will deliver water to the fire-protection water piping network on each Plant site. A smaller electric motor-driven jockey pump will maintain pressure in the piping network.

The piping network will be configured in a loop so that a piping failure could be isolated with shutoff valves without interrupting the supply of water to a majority of the loop. The piping network will supply fire hydrants located at intervals throughout the power island; a sprinkler deluge system at each unit transformer, HTF expansion tank and circulating pump area; and

sprinkler systems at the STG and in the operations and administration buildings. Portable fire extinguishers of appropriate sizes and types will be located throughout the plant site.

Wastewater

The water balance diagram shows the wastewater streams and the disposition of wastewater (water treatment system effluent) discharging to evaporation ponds. As discussed previously, the cooling tower blowdown will be processed with various processes, including clarification and reverse osmosis, prior to reuse to make SCA washing and steam system makeup water. The reject water will be ultimately discharged to evaporation ponds for final dewatering. The residual solids will remain in the pond for the duration of the plant life, as discussed below.

Wastewater sources include the following:

- Reverse Osmosis/Demineralizer system wastewater, and
- General plant drains from the oil water separator.

Cooling System

Each of the power islands include two cooling systems; 1) the steam cycle heat rejection system (e.g., cooling tower) and, 2) the closed cooling water system (equipment cooling), each of which is discussed below.

Steam Cycle Heat Rejection System

The cooling system for heat rejection from the steam cycle consists of a surface condenser, circulating water system, and a wet cooling tower. The surface condenser receives exhaust steam from the low pressure section of the STG and condenses it to liquid for return to the SSG. The surface condenser is a shell-and-tube heat exchanger with wet, saturated steam condensing on the shell side and circulating water flowing through the tubes to provide cooling. The warmed circulating water exits the condenser and flows to the cooling tower to be cooled and reused.

The circulating water is distributed among multiple cells of the counter-flow cooling towers, where it cascades downward through each cell fill and then collects in the cooling tower basin. The mechanical draft cooling tower employs electric motor-driven fans to move air upward through each cooling tower cell fill. The cascading circulating water is partially evaporated, and the evaporated water is dispersed into the atmosphere as part of the moist air leaving each cooling tower cell. Because of climatic conditions at the site, visible moisture plumes are expected to occur relatively infrequently and mainly in winter months; therefore, no need is expected for a plume-abated cooling tower.

The circulating water is cooled primarily through partial evaporation, and secondarily through heat transfer with the air. The cooled circulating water is pumped from the cooling tower basin back to the surface condenser and auxiliary cooling water system.

Closed Cooling Water System

The closed cooling water system uses water from the cooling tower for the purpose of cooling equipment including the STG lubrication oil cooler, the STG generator cooler, steam cycle sample coolers, large pumps, etc. The water picks up heat from the various equipment items being cooled and rejects the heat to the cooling tower through a closed loop heat exchanger.

Waste Generation and Management

Project wastes include industrial wastewater, sanitary wastewater, non-hazardous solid waste, hazardous solid waste, and hazardous liquid waste.

Evaporation Ponds for Industrial Wastewater

It is expected that each Plant site will have two double-lined evaporation ponds with a nominal surface area of five acres each for a total of ten acres per site or twenty acres for the entire Project. The ponds will be designed in accordance with Lahontan Regional Water Quality Control Board (RWQCB) requirements. Multiple ponds are planned to allow plant operations to continue in event that a pond needs to be taken out of service for some reason, e.g., needed maintenance. Each pond will have enough surface area so that the evaporation rate exceeds the cooling tower blowdown rate at maximum design conditions and at annual average conditions. Pond depth will be selected so that the ponds will not need to have residual solids removed during the life of the plant.

The pond liner system is expected to consist of a 60 mil high density polyethylene (HDPE) inner liner and a 50 mil HDPE outer liner. Between the liners is a synthetic drainage net that is used as part of the leachate collection and removal system (LCRS). Monitoring of the evaporation ponds will be required to detect the presence of liquid and/or constituents of concern. The LCRS will be monitored and a series of monitoring wells will also be used for the evaporation ponds. Based on the power plant process, chemicals used, and water quality, it is expected that the constituents of concern for this monitoring will include chloride, sodium, sulfate, TDS, biphenyl, diphenyl oxide, potassium, selenium, chromium and phosphate. The proposed detection monitoring program for the facility consists of monitoring the LCRS, lysimeters, and monitoring wells for the presence of liquid and/or constituents of concern.

Septic System for Sanitary Wastewater

The Project's sanitary system will collect wastewater from sanitary facilities such as sinks and toilets. This waste stream will be sent to onsite sanitary waste septic systems located at each power island. A sanitary septic system and onsite leach field will be used to dispose of sanitary wastewater on each power island. Project cooling water blowdown will be piped to lined, onsite evaporation ponds for each plant area. The ponds will be sized to retain all solids generated during the life of the plant. However, if required for maintenance, dewatered residues from the ponds could be sent to an appropriate offsite landfill as non-hazardous waste.

On-Site Bioremediation/Land Farm System

The Project will include bioremediation/land farm units to treat soil contaminated with HTF in the event of a leak or spill. The proposed bioremediation and land farm facilities will cover an area of approximately 1.5 acres on each plant site. Appropriate contamination level for

bioremediation and land farming of site-specific soils will be determined by Lahontan-approved testing to ensure the adequacy of the bioremediation/land farm unit design for HTF-contaminated soil. Contaminated soil that exceeds this level will be disposed of at an appropriate waste facility.

The bioremediation/land farm area will be designed in accordance with Lahontan RWQCB requirements and will include a leak detection system and monitoring wells. Treatment in the bioremediation unit involves the addition of nitrogen and phosphorous (i.e., fertilizers) as nutrients to the HTF-contaminated soil to stimulate consumption of HTF by the indigenous bacteria. The soil will remain in the bioremediation/land farm unit until concentrations are reduced to appropriate levels for use as fill material on the site.

Other Non-Hazardous Solid Waste

Construction, operation and maintenance of the Project will generate non-hazardous solid wastes typical of power generation or other industrial facilities. These wastes include scrap metal and plastic, insulation material, paper, glass, empty containers, and other miscellaneous solid wastes. These materials will be disposed of by means of contracted refuse collection and recycling services.

Hazardous Solid and Liquid Waste

Small quantities of hazardous wastes will be generated during Project construction and operation. Hazardous wastes generated during the construction phase include substances such as paint and primer, thinners, and solvents. Hazardous solid and liquid waste streams generated during Project operations include substances such as used HTF, used hydraulic fluids, oils, greases, filters, etc., as well as spent cleaning solutions and spent batteries. To the extent possible, both construction and operation-phase hazardous wastes will be recycled.

Hazardous Materials Management

There will be a variety of hazardous materials used and stored during construction and operation of the Project, as summarized below. Hazardous materials that will be used during construction include gasoline, diesel fuel, oil, lubricants, and small quantities of solvents and paints. All hazardous materials used during construction and operation will be stored onsite in storage tanks/vessels/containers that are specifically designed for the characteristics of the materials to be stored; as appropriate, the storage facilities will include the necessary secondary containment in case of tank/vessel failure.

Carbon steel tanks will be used at each Plant site to store sodium hydroxide solution (7,500-gallon capacity), sulfuric acid (10,000-gallon capacity), and lube oil and diesel fuel (6,500-gallon capacity each). Secondary containment will be provided for these tanks

A variety of safety-related plans and programs will be developed and implemented to ensure safe handling, storage, and use of hazardous materials (e.g., Hazardous Material Business Plan). Plant personnel will be supplied with appropriate personal protective equipment (PPE) and will be properly trained in the use of PPE and the handling, use, and cleanup of hazardous materials

used at the facility, as well as procedures to be followed in the event of a leak or spill. Adequate supplies of appropriate cleanup materials will be stored onsite.

Project Civil/Structural Features

The following text describe civil/structural features of the Project. The Project will be designed in conformance with the current edition of the California Building Code criteria for seismic conditions as detailed in the Geotechnical Evaluation.

SSG System, STG and Associated Equipment

The SSG System, STG and condenser will be supported on reinforced-concrete mat foundations. The one step-up transformer and GSU will be supported on reinforced-concrete mat foundations. Balance-of-plant (BOP) mechanical and electrical equipment will be supported on individual reinforced-concrete pads. BOP components/materials include piping, valves, cables, switches, etc. are not included with major equipment and are generally installed or erected onsite.

Solar Array Support Structures

Each solar collector array will be supported by structures (pylons) that connect the parabolic troughs to the drive mechanism. Each array will be supported by multiple individual foundations. Foundation design will be based on site-specific geotechnical conditions to ensure that the solar array pylons are able to support all loading conditions (including wind loading) at the proposed Project site. Preliminary designs based on geotechnical and soils studies include pier foundations and spread footings.

Buildings

The Project will include a warehouse and control/admin building located in each power island. Solar collector array assembly buildings will be installed in the northeast portion of the Alpha solar field, which will be later converted to warehouses. Other plant site “buildings” will include the water treatment building, as well as a number of pre-engineered enclosures for mechanical and electrical equipment. Building columns will be supported on reinforced-concrete mat foundations or individual spread footings and the structures will rest on reinforced concrete slabs. The total square footage of the various proposed Project buildings and pre-engineered enclosures (e.g., control/admin building, warehouse, electrical equipment enclosures, etc.) is approximately 185,000 square feet for the entire Project.

Water Storage Tanks

There will be a number of covered water tanks on each site including a 1,930,000-gallon raw water storage tank for short-term backup cooling water supply, with a portion (360,000 gallons) dedicated to the plant’s fire protection water system and a 1,930,000-gallon service water storage tank. There will also be a 164,500-gallon storage tank for storage of demineralized water. Water storage tanks will be vertical, cylindrical, field-erected steel tanks supported on foundations consisting of either a reinforced-concrete mat or a reinforced-concrete ring wall with an interior bearing layer of compacted sand supporting the tank bottom.

Roads, Fencing, Security

Only a small portion of the overall plant site will be paved, primarily the site access road and portions of the power island (paved parking lot and roads encircling the STG and SSG areas). In total, each power island will be approximately 20 acres with approximately 1.75 acres of paved area. The solar field will remain unpaved and without a gravel surface in order to prevent rock damage from SCA wash vehicle traffic. An approved dust suppression coating will be used on the dirt roadways within and around the solar field. Roads and parking areas located within the power island area and adjacent to the administration building and warehouse will be paved with asphalt and are included in the total above.

The Project solar field and support facilities' perimeter will be secured with chain-link metal-fabric fencing, six to eight feet tall. Controlled access gates will be located at the power island entrances and serve as normal access to the solar fields. Desert tortoise exclusion fencing will be installed at the base of the chain link fence and tortoise-proof gates will be utilized.

Natural Gas Supply

The natural gas pipeline to service the proposed Project exists in Harper Lake Road and interconnection will occur at the Project boundary; no offsite pipeline is required. Natural gas for the Project's ancillary purposes, such as the auxiliary boilers, space heating, and the like will be supplied by a Southwest Gas Corporation (SGC) owned pipeline that runs to the Project boundary near the Alpha power island. No offsite pipeline facilities are proposed as a part of this Project. SGC was contacted and studied the demand requested and indicates that sufficient capacity exists to supply the Project.

Existing Facilities

Southwest Gas Corporation (SGC) is the local service provider. The existing pipeline was installed to support the existing and previously planned SEGS projects at Harper Dry Lake. The line was sized to support up to six SEGS-style projects. Existing capacity is sufficient to support the minimal use of natural gas for this Project.

The interconnection will service both power islands independently. A pipeline will be installed within the Project boundary to support the Beta site power island from the interconnection location near the Alpha power island.

Proposed Onsite Routing

Starting at the tap station adjacent to the west side of the Alpha power island, the pipeline is routed underground to the Alpha power island metering and reducing station. A tee will be installed downstream the tap in the line to supply the Alpha power island and to route gas to the Beta power island. To supply the Beta power island an underground pipeline will be installed from the tee and extend west to a point north of the Beta power island, turn south and terminate at the Beta power island metering and reducing station. The total distance from the tee to the Beta metering and reducing station is approximately two miles.

Construction Practices

The natural gas pipeline will be constructed as part of the overall site construction. The pipeline will be installed in maintenance road right-of-ways to allow for future access if necessary. Prior to installation, the pipe will be laid along the route. Pipeline construction will take approximately one month and is expected to begin following the grubbing and clearing of the Project site and in coordination with mass grading. During non-work hours, the exposed trench will be covered with temporary coverings to provide safety. The pipe will have factory-applied corrosion protection coating. Joints will be welded and inspected using X-ray. The construction of the natural gas pipeline will consist of the following:

- *Trenching:* The optimal trench will be approximately 36 inches wide and four to ten feet deep. With loose soil, a trench up to eight feet wide at the top and three feet wide at the bottom may be required. The pipeline will be buried to provide a minimum cover of 36 inches. The excavated soil will be piled on one side of the trench and used for back filling after the pipe is installed.
- *Stringing:* Lengths of pipe are laid on wooden skids beside the open trench.
- *Installation:* This process consists of bending, welding, and coating the weld-joint areas of the pipe after it has been strung, padding the ditch with sand or fine spoil, and lowering the pipe string into the trench. Welding will meet the applicable standards and will be performed by qualified welders. Welds will be inspected in accordance with appropriate standards. Welds will undergo 100% inspection by an independent, qualified radiography contractor. All coating will be checked for defects and will be repaired before lowering the pipe into the trench.
- *Backfilling:* This process consists of returning spoil back into the trench around and on top of the pipe, ensuring that the surface is returned to its original grade or level. The backfill will be compacted to protect the stability of the pipe and to minimize subsequent subsidence.
- *Plating:* Consists of covering any open trench in areas of foot or vehicle traffic at the end of a workday. Plywood plates will be used in areas of foot or wildlife traffic and steel plates will be used in areas of vehicle crossing to ensure public safety. Plates will be removed at the start of each workday. Efforts will be made to minimize the length of open trench along the ROW.
- *Hydrostatic testing:* Consists of filling the pipeline with water, venting all air, increasing the pressure to the specified code requirements, and holding the pressure for a period of time. After hydrostatic testing, the test water will be chemically analyzed for contaminants and discharged to the surrounding area unless the analysis shows that the water is contaminated, in which case, the water will be trucked to an appropriate disposal facility.
- *Cleanup:* Consists of restoring the surface of the right-of-way by removing any construction debris, grading to the original grade and contour.

- *Commissioning:* consists of cleaning and drying the inside of the pipeline, purging air from the pipeline, and filling the pipeline with natural gas.

Metering

A gas-metering station will be required at the tap point to measure and record gas volumes. In addition, facilities will be installed to regulate the gas pressure and to remove any liquids or solid particles. The metering station at the tap point will require an area of approximately 5,000 square feet. In addition, the two plant metering sets will require a fenced enclosure of approximately 1,000 square feet.

Construction activities related to the metering station and metering sets will include grading a pad and installing above and below ground gas piping, metering equipment, gas conditioning, pressure regulation, and possibly pigging facilities. A distribution power line for metering-station-operation lighting, communication equipment, and perimeter chain link fencing for security will also be installed.

Operation

Isolation block valves will be installed at both ends of the pipeline. These valves will be manually controlled, lockable, gear-operated ball valves. A pipeline Supervisory Control and Data Acquisition (SCADA) system will provide flow rate and pressure data to SGC, the gas vendor, and pipeline owner. Communication with SGC or the gas vendor regarding pipeline operations will be by telephone lines or other means, such as Cellular Digital Pocket Data as appropriate.

AMSP Project Decommissioning

Although the AMSP is anticipated to operate for 30 years, it is possible that the facility could remain in operation for as many as 40 or more years. Possible reasons for closure could include, but would not be limited to, facility age, economic viability, cost of maintenance or upgrades, or damage considered beyond repair. Procedures for facility closure would largely depend on the circumstances and requirements at the time of decommissioning.

Facilities Closure

The AMSP is being designed for an operating life of 30 years. Depending on maintenance factors, at an appropriate point beyond the useful operating life, the project would cease operation and close. At that time, it would be necessary to ensure that closure occurs in a way that public health and safety and the environment are protected from adverse impacts.

Although the setting for this project does not appear to present any special or unusual closure circumstances, it is not possible to foresee what the situation would be in 30 years or more when the project ceases operation. Therefore, provisions would be made that provide the flexibility to address the circumstances at the time of closure. Facility closure would be consistent with laws, ordinances, regulations, and standards in effect at the time of closure.

Temporary closure is a cessation of facility operations for a period greater than would be required for routine maintenance, overhaul, or replacement of major plant equipment. Temporary closure could be initiated by damage to the facility resulting from events such as earthquakes, fires, or other natural occurrences, or due to short-term economic considerations. Permanent closure is a cessation of facility operations with no intent to restart. Permanent closure could result from a combination of facility age and economic considerations, from damage considered beyond repair, or for other reasons.

Temporary Closure

In the case of a temporary closure, AMSP would maintain round-the-clock security for the facilities and would notify the California Department of Environmental Quality (CDEQ) and other jurisdictional agencies. Depending on whether hazardous materials were released, a specific course of action would be followed, as outlined below.

A Risk Management and Mitigation Plan would be developed before operations began and would be implemented for the temporary halting of facility operations if there is no actual or threatened release of hazardous materials. The plan would ensure compliance with all applicable laws, ordinances, regulations, and standards and appropriate protection of public health, safety, and the environment. The plan could include draining and proper disposal of chemicals from storage tanks and other facility equipment, the safe shutdown of all plant equipment, and various other measures to protect equipment, onsite workers, the public, and the environment. Specific measures would depend on the expected duration and nature of the temporary closure. If the temporary closure did involve an actual or threatened release of hazardous materials to the environment, procedures would be developed and implemented, as provided for in a Hazardous Materials Business Plan. Procedures would include, but not be limited to, the following:

- Measures to control and ultimately prevent the continued release of hazardous materials
- Emergency response procedures to address the unique operating environment consistent with the nature of the temporary closure
- Training requirements for project personnel in hazardous material release response and control
- Requirements for notifying appropriate agencies and the public

All notifications and related actions would be conducted in accordance with the Emergency Planning and Community Right-To-Know Act. After the hazardous material release was resolved, temporary closure would proceed, corrective actions would be identified, and the Risk Management and Mitigation Plan would be followed.

Permanent Closure

If the AMSP remained economically viable, it could operate for 40 or more years, which would defer environmental impacts associated with closure and with the development of replacement power generating facilities. However, if the facility was no longer economically viable before useful life of equipment had expired, permanent closure could occur sooner.

A decommissioning plan outlining closure procedures would be developed and implemented, regardless of when permanent closure occurred. The decommissioning plan would be provided to the CDEQ and other jurisdictional agencies for review before permanent closure. The decommissioning plan would include procedures designed to ensure public health and safety, environmental protection, and compliance with applicable laws, ordinances, regulations, and standards. Abengoa Solar would maintain round-the-clock security for the AMSP during permanent closure activities until the facilities were determined safe without security.

Closure measures could range from extensive “mothballing” to the complete removal of equipment and other structures, depending on conditions at the time of closure. The decommissioning plan for the AMSP would address the following:

- Proposed decommissioning measures for all facilities constructed as part of the project
- Activities necessary for site restoration, if removal of all equipment and appurtenances was needed
- Provisions for recycling facility components, collection and disposal of hazardous wastes and resale of unused chemicals back to suppliers or other parties
- Decommissioning alternatives other than full restoration of the site
- Costs associated with the proposed decommissioning activities and the source of funds to implement these activities
- Conformance with applicable laws, ordinances, regulations, standards, and local/regional plans

H		G		F		E		D		C		B		A	
SYMBOLS (ON ONE-LINES)	DESCRIPTION	SYMBOLS (ON ONE-LINES)	DESCRIPTION	SYMBOLS (ON ONE-LINES)	DESCRIPTION	SYMBOLS (ON ONE-LINES)	DESCRIPTION	SYMBOLS (ON ONE-LINES)	DESCRIPTION	SYMBOLS (ON ONE-LINES)	DESCRIPTION	SYMBOLS (ON ONE-LINES)	DESCRIPTION	SYMBOLS (ON ONE-LINES)	DESCRIPTION
	DISCONNECT SWITCH		ELECTRIC HEATER ELEMENT		LOW VOLTAGE COMBINATION STARTER (*) NEMA SIZE		PROTECTIVE RELAY XX,YY - ANSI STANDARD DEVICE FUNCTION NUMBER ZZZZ - RELAY NUMBER IDENTIFICATION								
	FUSED DISCONNECT SWITCH		POTHEAD OR SERVICE HEAD		MEDIUM VOLTAGE STARTER WITH VACUUM CONTACTOR	<div>ANSI STANDARD DEVICE FUNCTIONS</div> <div>25 SYNCHRONISM CHECK DEVICE</div> <div>27 UNDERVOLTAGE RELAY</div> <div>32 DIRECTIONAL POWER RELAY</div> <div>40 FIELD RELAY</div> <div>43 MANUAL TRANSFER DEVICE</div> <div>46NC PHASE-BALANCE NEUTRAL CURRENT RELAY</div> <div>49X MACHINE OR TRANSFORMER THERMAL RELAY (X= M-MACHINE, T-TRANSFORMER, T1- TRANSFORMER 1 WINDING, T2- TRANSFORMER 2 WINDING, T3- TRANSFORMER 3 WINDING)</div> <div>50 INSTANTANEOUS OVERCURRENT RELAY</div> <div>51 AC TIME-OVERCURRENT RELAY</div> <div>50/51N RESIDUAL GROUND FAULT RELAY</div> <div>51TN TRANSFORMER NEUTRAL TIME-OVERCURRENT RELAY</div> <div>51G GROUND TIME OVERCURRENT RELAY</div> <div>51GS ZERO SEQUENCE GROUND TIME-OVERCURRENT RELAY</div> <div>51V VOLTAGE-RESTRAINED OVERCURRENT RELAY</div> <div>59 OVERVOLTAGE RELAY</div> <div>59NC UNBALANCED NEUTRAL OVERVOLTAGE RELAY</div> <div>63X PRESSURE SWITCH (X= T- TRANSFORMER, TCX- TAP CHANGER X ENCLOSURE TCY- TAP CHANGER Y ENCLOSURE)</div> <div>67 AC DIRECTIONAL OVERCURRENT RELAY</div> <div>71 LEVEL SWITCH</div> <div>81 FREQUENCY RELAY</div> <div>86X LOCK-OUT RELAY (X = B-BUS, C-CAPACITOR, F-FEEDER, G-GENERATOR, T-TRANSFORMER)</div> <div>87X DIFFERENTIAL PROTECTIVE RELAY (X = B-BUS, F-FEEDER, G-GENERATOR, T-TRANSFORMER, TL - TRANSMISSION LINE)</div> <div>11X MULTIPURPOSE RELAY (X = B-BUS, F-FEEDER, G-GENERATOR, T-TRANSFORMER, TL - TRANSMISSION LINE)</div>									
	FUSED CUTOUT SWITCH		FIXED RESISTOR		VACUUM CONTACTOR										
	HORN GAP ISOLATING SWITCH		TAPPED RESISTOR		LATCHING VACUUM CONTACTOR										
	LOW VOLTAGE CIRCUIT BREAKER DRAWOUT TYPE		ADJUSTABLE RESISTOR		SYNCHRONIZING BREAKER										
	LOW VOLTAGE CIRCUIT BREAKER		SINGLE OR THREE PHASE POWER TRANSFORMER WITH LOAD TAP CHANGER (*) KVA AND VOLTAGE RATING		MOTOR OPERATOR										
	MEDIUM VOLTAGE CIRCUIT BREAKER DRAWOUT TYPE		SINGLE OR THREE PHASE POWER TRANSFORMER (*) KVA AND VOLTAGE RATING		SOLID STATE METERING										
	TRANSMISSION LINE CIRCUIT BREAKER		PT- POTENTIAL TRANSFORMER (*) VOLTAGE LEVEL (**) QUANTITY		SOLID STATE CIRCUIT PROTECTOR/MULTI-FUNCTION RELAY										
	AC MOTOR (*) HORSEPOWER		INDUCTIVE REACTOR (*) RATING IN KVA AND IMPEDANCE IN		STATIC TRIP UNIT										
	GENERATOR		CURRENT TRANSFORMER ■ POLARITY MARK (*) RATIO (**) QUANTITY		SOLID STATE MOTOR CIRCUIT PROTECTOR										
	DIESEL GENERATOR		ZERO SEQUENCE CURRENT TRANSFORMER (*) RATIO (**) QUANTITY		VARIABLE SPEED DRIVE										
	LIGHTNING ARRESTOR		- NEUTRAL GROUNDING TRANSFORMER W/SECONDARY LOADING RESISTOR		SOFT START										
	EARTH SWITCH		PROTECTIVE RELAY (*) TYPE OF RELAY		= KIRK KEY INTERLOCK A-# KEY INTERCHANGE NUMBER L-O LOCK DEVICE OPEN E INTERLOCK BOLT EXTENDED										
	DISTRIBUTION PANEL (DCP, DP, HTP, IPP, LP, PP, UPSP)		BUS DUCT		= KIRK KEY										
<div>Figure 2-7(a)</div> <div><div>PRELIMINARY</div><div>DATE 17 FEB 09</div></div> <div><div>ABENCS</div><div>Abener Engineering and Construction Services, LLC</div><div>ST. LOUIS, MISSOURI</div></div> <div><div>ABENGOA SOLAR</div></div> <div><div>ABENER DRAWING NUMBER</div><div>XXXX-PLN-BBB-28-21-0001</div></div> <div><div>ELECTRICAL ONE LINE DIAGRAM</div><div>SYMBOLS LIST</div></div> <div><div>ABENGOA SOLAR</div><div>HARPER LAKE, CA</div></div> <div><div>BY MKB</div><div>DATE 2/09</div><div>APP'D CBT</div><div>DATE 17 FEB 09</div><div>JOB NO. 120010</div><div>REVISION</div></div> <div><div>CHECKED SVE</div><div>DATE 17 FEB 09</div><div>SCALE NONE</div><div>ISSUE DATE</div><div>PURPOSE OF ISSUE FOR REVIEW</div></div> <div><div>ED-0001</div><div>0</div></div>															

THIS DRAWING IS THE PROPERTY OF

ABENCS

Abener Engineering and Construction Services, LLC

INFORMATION AND KNOW-HOW HEREIN ARE CONFIDENTIAL AND PROPRIETARY AND MAY NOT BE USED, REPRODUCED, OR REVEALED TO OTHERS EXCEPT IN ACCORDANCE WITH THE TERMS OF A CONTRACT WITH OR OTHER WRITTEN PERMISSION OF Abener Engineering and Construction Services, LLC. ANY REPRODUCTIONS IN WHOLE OR PART INCLUDING SHOP DRAWINGS SHALL BEAR OR REFER TO THIS STAMP.

17 FEB 09

FOR REVIEW


ISSUE DATE

PURPOSE OF ISSUE

DESCRIPTION

Plot Date/Time/User: 17-Feb-09/3:31 PM/COMBU

17\PROJECTS\120010 ABOSLAR HARPER LAKE CALIFORNIA\CAD\120010\ELECTRICAL\ED-0001.DWG



- NOTES:
1. ADDITIONAL COMPONENTS FOR METERING AND PROTECTION WILL BE PROVIDED DURING DETAIL DESIGN.
 2. ALPHA SITE HAS PRIMARY EQUIPMENT DESIGNATIONS. BETA SITE SECONDARY EQUIPMENT DESIGNATIONS AND ARE IN PARENTHESIS (###).




Figure 2-7(g)

PRELIMINARY
DATE 17 FEB 09

ABENCS					
Abener Engineering and Construction Services, LLC					
ST. LOUIS, MISSOURI					
ABENG0A SOLAR					
ABENER DRAWING NUMBER					
XXXX-PLN-BBB-28-21-0109					
230KV METERING & RELAYING PROTECTION ZONE ONE LINE BETA SITE					
ABENG0A SOLAR			HARPER LAKE, CA		
DRAWN	BY	DATE	APP'D.	DATE	JOB NO.
CHKD	MKB	2/09	GST	17 FEB 09	120010
SCALE	NONE				DRAWING NO. ED-0109

REVISIONS				REVISIONS				REVISIONS				REVISIONS			
NO.	DATE	DESCRIPTION	BY	NO.	DATE	DESCRIPTION	BY	NO.	DATE	DESCRIPTION	BY	NO.	DATE	DESCRIPTION	BY

THE DRAWING IS THE PROPERTY OF	
ABENCS	
Abener Engineering and Construction Services, LLC	
INFORMATION AND KNOW-HOW HEREON ARE CONFIDENTIAL AND PROPRIETARY AND MAY NOT BE USED, REPRODUCED, OR REVEALED TO OTHERS EXCEPT IN ACCORDANCE WITH THE TERMS OF A CONTRACT WITH OR OTHER WRITTEN PERMISSION OF Abener Engineering and Construction Services, LLC. ANY REPRODUCTIONS IN WHOLE OR PART INCLUDING SHOP DRAWINGS SHALL BEAR OR BESE TO THIS STAMP.	
17 FEB 09	FOR REVIEW
ISSUE DATE	PURPOSE OF ISSUE




Figure 2-7(j)

ABENCS
Abener Engineering and Construction Services, LLC
ST. LOUIS, MISSOURI

ABENGOA SOLAR

ABENER DRAWING NUMBER
XXXX-PLN-BBB-28-21-0112

230KV METERING & RELAYING
ONE LINE - TL1A (TL1B)
ALPHA (BETA) SITE

ABENGOA SOLAR HARPER LAKE, CA

BY	DATE	APP'D.	DATE	JOB NO.	REVISION
MKB	2/09	GDT	17 Feb 09	120010	
CHECKED	576-06-1	576-06-1		DRAWING NO.	
SCALE	NONE			ED-0112	

0


THIS DRAWING IS THE PROPERTY OF
ABENCS
Abener Engineering and Construction Services, LLC

INFORMATION AND KNOW-HOW HEREON ARE CONFIDENTIAL AND PROPRIETARY AND
MAY NOT BE USED, REPRODUCED, OR REVEALED TO OTHERS EXCEPT IN ACCORDANCE
WITH THE TERMS OF A CONTRACT WITH OR OTHER WRITTEN PERMISSION OF Abener
Engineering and Construction Services, LLC. ANY REPRODUCTIONS IN WHOLE OR PART
INCLUDING SHOP DRAWINGS SHALL BEAR OR REFER TO THIS STAMP.

17 FEB 09	FOR REVIEW
ISSUE DATE	PURPOSE OF ISSUE

REVISIONS				REVISIONS				REVISIONS				REVISIONS			
NO.	DATE	DESCRIPTION	BY	BY	BY	NO.	DATE	DESCRIPTION	BY	BY	BY	NO.	DATE	DESCRIPTION	BY

REFERENCES				REFERENCES			
NO.	DATE	DESCRIPTION	BY	NO.	DATE	DESCRIPTION	BY



PRELIMINARY
DATE 17 FEB 09


Figure 2-7(i)

ABENCS Abener Engineering and Construction Services, LLC ST. LOUIS, MISSOURI						
ABENGEOA SOLAR						
ABENER DRAWING NUMBER XXXX-PLN-BBB-28-21-0111						
230KV METERING & RELAYING ONE LINE - APT1A (APT1B) ALPHA (BETA) SITE ABENGEOA SOLAR HARPER LAKE, CA						
DRAWN	BY	DATE	APP'D.	DATE	JOB NO.	REVISION
	MKB	2/09	GD7	17 FEB 09	120010	
CHECKED					DRAWING NO.	
					ED-0111	
SCALE	NONE					

REVISIONS					REVISIONS					REVISIONS					REFERENCES				
NO.	DATE	DESCRIPTION	BY	BY	BY	NO.	DATE	DESCRIPTION	BY	BY	BY	NO.	DATE	DESCRIPTION	BY	BY	BY	DESCRIPTION	

THIS DRAWING IS THE PROPERTY OF
ABENCS
Abener Engineering and Construction Services, LLC
INFORMATION AND KNOWHOW HEREIN ARE CONFIDENTIAL AND PROPRIETARY AND
MAY NOT BE USED, REPRODUCED, OR REVEALED TO OTHERS EXCEPT IN ACCORDANCE
WITH THE TERMS OF A CONTRACT WITH OR OTHER WRITTEN PERMISSION OF Abener
Engineering and Construction Services, LLC. ANY REPRODUCTIONS IN WHOLE OR PART
INCLUDING SHOP DRAWINGS SHALL BEAR OR REFER TO THIS STAMP.

17 FEB 09 FOR REVIEW
ISSUE DATE PURPOSE OF ISSUE



HINKLEY SUBSTATION
BREAKER AND A HALF TYPE

Figure 2-9

NOTES:
1. DESIGN BY OTHERS.

PRELIMINARY
DATE 19 FEB 09

ABENCS Abener Engineering and Construction Services, LLC ST. LOUIS, MISSOURI					
ABENGEOA SOLAR					
ABENER DRAWING NUMBER XXXX-PLN-BBB-28-21-0107					
GENERAL ONE-LINE DIAGRAM 230KV SUBSTATION UTILITY INTERCONNECTION ABENGEOA SOLAR HARPER LAKE, CA					
DRAWN	BY	DATE	APP'D.	JOB NO.	REVISION
	MKB	2/09	GD	120010	
CHECKED				DRAWING NO.	
				ED-0107	
SCALE	NONE				

NO.	DATE	DESCRIPTION	BY	BY	BY	NO.	DATE	DESCRIPTION	BY	BY	BY	NO.	DATE	DESCRIPTION	BY	BY	BY	NO.	DATE	DESCRIPTION	BY	BY	BY
1						1						1						1					
2						2						2						2					
3						3						3						3					
4						4						4						4					

THIS DRAWING IS THE PROPERTY OF ABENCS Abener Engineering and Construction Services, LLC INFORMATION AND KNOWHOW HEREON ARE CONFIDENTIAL AND PROPRIETARY AND MAY NOT BE USED, REPRODUCED, OR REVEALED TO OTHERS EXCEPT IN ACCORDANCE WITH THE TERMS OF A CONTRACT WITH OR OTHER WRITTEN PERMISSION OF Abener Engineering and Construction Services, LLC. ANY REPRODUCTION IN WHOLE OR PART INCLUDING SHOP DRAWINGS SHALL BEAR OR REFER TO THIS STAMP.	
19 FEB 09	FOR REVIEW
ISSUE DATE	PURPOSE OF ISSUE

APPENDIX E

WATER REGULATIONS, HYDROLOGY REPORT, DESCP, AND SWPPP

Laws, Ordinances, Regulations and Standards for Water Resources

Federal, state, county and local laws and ordinances applicable to water resources are listed in Table E-1 and discussed below.

Table E-1. Laws and Ordinances Applicable to Water Resources

Laws and Ordinances	Applicability and Requirements
Federal:	
Clean Water Act (CWA) Section 402, 33 USC Section 1342; 40 CFR Parts 112, 122 through 136	The objective of the CWA (1977) is to restore and maintain the chemical, physical, and biological integrity of the Nation's waters. The CWA regulates both direct and indirect discharges to waters of the U.S., including storm water discharges from construction and industrial activities.
State:	
California Constitution Article 10, Section 2	Prohibits waste or unreasonable use of water, regulates use and diversion of water, and requires conservation and reuse of water to the maximum extent possible.
The Porter-Cologne Water Quality Control Act; California Water Code Division 7, Chapter 1, Section 13000 et seq.	Requires the SWRCB and the nine RWQCBs to adopt water quality criteria to protect State waters, including identification of beneficial uses, narrative and numerical water quality standards, and implementation procedures.
Federal CWA, implemented by the State of California - California Storm Water Permitting Program: California Construction Storm Water Program, California Industrial Storm Water Program	Construction activities that disturb one or more acre are required to obtain coverage under California's General Construction Permit, which requires the development and implementation of a Storm Water Pollution Prevention Plan (SWPPP). Industrial activities with the potential to impact storm water discharges are required to obtain a NPDES permit for those discharges.
California Water Code Division 1, Chapter 6, Article 2, Section 461	Stipulates that the primary interest of the people of the state in conservation of available water resources requires the maximum reuse of reclaimed water in the satisfaction of requirements for beneficial uses of water.

Laws and Ordinances	Applicability and Requirements
California Water Code Division 2, Part 2, Chapter 1, Article 1, Section 1200 - Water Rights	Defines water subject to appropriation through application to the State Water Resources Control Board (SWRCB) as surface water and subterranean streams flowing through known and definite channels.
California Water Code Division 7, Chapter 4, Article 4, Section 13260 et seq	Requires filing with the appropriate RWQCB Report of Waste Discharge that could affect the water quality of the state, unless the requirement is waived pursuant to California Water Code section 13269 (a).
California Water Code Division 7, Chapter 7, Article 7, Sections 13550, 13551, 13552.6	Requires the use of recycled water for industrial purposes subject to recycled water availability, quality, quantity, cost, and public health impacts. Prohibits use of potable domestic quality water for non-potable uses if suitable recycled water is available.
California Water Code Division 7, Chapter 10, Article 3, Section 13751	Requires well completion report for constructing, altering, or destroying a water well, cathodic protection well, groundwater monitoring well, or geothermal heat exchange well.
State Water Resources Control Board Resolution 75-58	Encourages the use of wastewater for power plant cooling and sets an order of preference for water use for cooling purposes.
California Code of Regulations, Title 23, Division 3, Chapter 9, Chapter 15	Establishes requirements for waste discharge report and requirements specifying conditions for protection of water quality. Outlines classification and siting and construction criteria for waste management units and discharges of waste to land. Provides guidance for surface impoundments and Land Treatment Units, also stipulates operational and maintenance procedures to minimize mobility of waste materials.

Laws and Ordinances	Applicability and Requirements
California Code of Regulations, Title 22, Division 4, Chapter 15, Articles 1, 2, 3, 4, 4.1, 4.5, 5, and 5.5, Sections 64400.80 through 64445	<p>Requires periodic monitoring of water quality for potable water wells supplying a public water system (non-transient, non-community water systems).</p> <p>Regulated wells must be sampled for bacteriological quality once a month and the results submitted to the California Department of Health Services (DHS). The wells must also be monitored for inorganic chemicals once and organic chemicals quarterly during the year designated by the DHS. DHS will designate the year based on historical monitoring frequency and laboratory capacity.</p>
CEC Policy, adopted pursuant to Public Resources Code, Section 25300 et seq., 25523(a)	The CEC will approve the use of "fresh inland" water for cooling purposes by power plants only under certain circumstances. Requires submission of information to the CEC concerning proposed water resources and water quality protection in the AFC.
Local:	
San Bernardino County Ordinance Code, Title 3, Division 3, Chapter 6, Domestic Water Sources and Systems, Article 3, Water Wells	<p>Describes requirements for permitting, siting, constructing, and destroying groundwater wells.</p> <p>Stipulates conditions for abandonment and taking wells out of service. Describes water quality standards and requirements for the inspections of wells.</p>
San Bernardino County Ordinance Code, Title 3, Division 3, Chapter 8, Waste Management, Article 5, Liquid Waste Disposal	Article regards approval, permitting, and location requirements of liquid waste disposal systems.
San Bernardino County Ordinance Code, Title 6, Division 3, Chapter 3, Uniform Plumbing Code	Describes installation and inspection requirements for locating disposal/leach fields, and seepage pits.

5.17.1.1 Federal Laws

Clean Water Act of 1977 (including 1987 amendments) Section 402 and 402, 33 USC Section 1342; 40 CFR Parts 112, 122-136

The primary objective of the Clean Water Act (CWA) is to restore and maintain the chemical, physical, and biological integrity of the nation's surface waters. Pollutants regulated under the CWA include "priority" pollutants, including various toxic pollutants; "conventional" pollutants, such as biochemical oxygen demand, total suspended solids, oil and grease, and pH, and "non-conventional" pollutants, including any pollutant not identified as either conventional or priority.

The CWA regulates both direct and indirect discharges. The National Pollutant Discharge Elimination System (NPDES) Program (CWA §402) controls the direct discharges and storm water discharges into waters of the United States. NPDES permits contain industry-specific, technology-based limits and may also include additional water quality-based limits, and they establish pollutant-monitoring requirements. A NPDES permit may also include discharge limits based on federal or state water-quality criteria or standards. In 1987, the CWA was amended to include a program to address storm water discharges for industrial and construction activities. The Lahontan Regional Water Quality Control Board (RWQCB) administers both the NPDES and storm water discharge permits under the CWA in the project area.

According to the San Bernardino County Flood Control District, the 100-year floodplain has not been established for the Harper Dry Lake area.

5.17.1.2 State Laws and Ordinances

State of California Constitution Article 10, Section 2

Article 10, Section 2 of the California Constitution requires that water resources of the State be put to beneficial use to the fullest extent of which they are capable. This section prohibits the waste or unreasonable use, or unreasonable method of use or unreasonable method of diversion, of water.

Porter-Cologne Water Quality Control Act

Porter-Cologne Water Quality Control Act of 1967, Water Code Division 7, Chapter 1, Section 13000 *et seq.* requires the State Water Resources Control Board (SWRCB) and the nine RWQCBs to adopt water quality criteria to protect State waters. Those criteria include the identification of beneficial uses, narrative and numerical water quality standards, and implementation procedures. Water quality criteria for the proposed project area are contained in the Water Quality Control Plan for the Lahontan Region (Basin Plan) which was adopted in 1994 and is in the process of being amended. This plan sets numerical and/or narrative water quality standards controlling the discharge of wastes to the State's waters and land.

California Storm Water Permitting Program

California Construction Storm Water Program. Construction activities that disturb one acre or more are required to obtain coverage under California's General Permit for

Discharges of Storm Water Associated with Construction Activity, Water Quality Order 99-08-DWQ (General Construction Permit CAS 000002). Activities subject to permitting include clearing, grading, stockpiling, and excavation.

The General Construction Permit requires the development and implementation of a Storm Water Pollution Prevention Plan (SWPPP) that specifies Best Management Practices (BMPs) that will reduce or prevent construction pollutants from leaving the site in storm water runoff and will also minimize erosion associated with the construction project. The SWPPP must contain site map(s) that show the construction site perimeter, existing and proposed structures and roadways, storm water collection and discharge points, general topography both before and after construction, and drainage patterns across the site. Additionally, the SWPPP must describe the monitoring program to be implemented.

California Industrial Storm Water Program. Industrial activities with the potential to impact storm water discharges require a NPDES permit. In California, an Industrial Storm Water General Permit, Order 97-03-DWQ (General Industrial Permit CAS 000001) may be issued to regulate discharges associated with power generation facilities. The General Industrial Permit requires the implementation of management measures that will protect water quality. In addition, the discharger must develop and implement a SWPPP and a monitoring plan. Through the SWPPP, sources of pollutants are to be identified and the means to manage the sources to reduce storm water pollution described. The monitoring plan requires sampling of storm water discharges during the wet season and visual inspections during the dry season. A report must be submitted to the RWQCB each year by July 1 documenting the status of the program and monitoring results.

California Water Code

Division 1, Chapter 6, Article 2, Section 461. This law stipulates that the primary interest of the people of California in the conservation of all available water resources requires the maximum reuse of reclaimed water in the satisfaction of requirements for beneficial uses of water.

Division 2, Part 2, Chapter 1, Article 1, Section 1200 “Water Rights”. This law classifies water in one of three categories: surface water, percolating groundwater, and “subterranean streams that flow through known and definite channels”. Only surface water and subterranean stream water are within the permitting jurisdiction of the State Water Resources Control Board (SWRCB). Appropriation of those waters requires a SWRCB permit, and is subject to various permit conditions.

In establishing whether there is a condition of subterranean streams, the SWRCB uses a finding that there must be evidence of bed and banks and water flowing along a line of a surface stream (Sax 2002). Based on a review of the subsurface conditions at the Project site, there is no evidence to support that the groundwater is flowing in subterranean streams, and as such, there is no permit required for appropriation from the SWRCB.

Division 7, Chapter 4, Article 4, Section 13260 et seq. This law requires filing with the appropriate RWQCB a report of waste discharge (ROWD) that could affect the water quality of the State, unless the requirement is waived pursuant to Water Code Section

13269(a). The report shall describe the physical and chemical characteristics of the waste that could affect its potential to cause pollution or contamination. The report shall include the results of all tests required by regulations adopted by the board, any test adopted by the Department of Toxic Substances Control (DTSC) pursuant to Section 25141 of the Health and Safety Code for extractable, persistent, and bio-accumulative toxic substances in a waste or other material, and any other tests that the SWRCB or RWQCB may require.

Division 7, Chapter 7, Article 7, Section 13550. Use of recycled water is required for industrial purposes subject to recycled water being available and a number of criteria, including provisions that the quality and quantity of the recycled water are suitable for the use, the cost is reasonable, the use is not detrimental to public health, and the use will not impact downstream users or biological resources.

Division 7, Chapter 7, Article 7, Section 13551. A person or public agency, including a state agency, city, county, district, or any other political subdivision of the state, shall not use water from any source of quality suitable for potable domestic use for non-potable uses if suitable recycled water is available as provided in Section 13550.

Division 7, Chapter 7, Article 7, Section 13552.6. This law specifically identifies the use of potable domestic water for cooling towers as an unreasonable use of water within the meaning of Section 2 of Article 10 of the California Constitution, if suitable recycled water is available and the water meets the requirements set forth in Section 13550.

Division 7, Chapter 10, Article 3, Section 13751. Anyone who constructs, alters, abandons, or destroys a water well, cathodic protection well, groundwater monitoring well, or geothermal heat exchange well must file a well completion report with the DWR within 60 days from the date its construction, alteration, abandonment, or destruction is completed.

State Water Resources Control Board Resolution 75-58

On June 19, 1975, the SWRCB adopted the Water Quality Control Policy on the Use and Disposal of Inland Waters used for Power Plant Cooling. The purpose of the policy is to provide consistent statewide water quality principles and guidance for adoption of discharge requirements, and implementation actions for power plants that depend on inland waters for cooling. State policy encourages the use of wastewater for power plant cooling and sets the following order of preference for sources: 1) wastewater being discharged to the ocean; 2) ocean water; 3) brackish water from natural sources or irrigation return flows; 4) inland waste waters of low total dissolved solids (TDS); and 5) other inland waters. The criteria for the selection of water delivery options involve economic feasibility, engineering constraints such as cooling water composition and temperature and environmental considerations such as impacts on riparian habitat, groundwater levels, and surface and subsurface water quality.

California Code of Regulations

Title 23, Division 3, Chapter 9. The RWQCB must issue a report of waste discharge for discharges of waste to land pursuant to the Water Code. The report requires submittal of information regarding the proposed discharge, waste management unit design, and

monitoring program. Waste Discharge Requirements (WDRs) issued by the RWQCB establish construction and monitoring requirements for the proposed discharge. The SWRCB has adopted general waste discharge requirements (97-10-DWQ) for discharge to land by small domestic wastewater treatment systems.

Title 23, Division 3, Chapter 15. This regulation outlines siting, construction and monitoring requirements for waste discharges to land for landfills, surface impoundments, land treatment units and waste piles. The chapter provides closure and post-closure maintenance and monitoring requirements for Class II designated waste facilities and surface impoundments that are applicable to the project.

Title 22, Division 4, Chapter 15, Articles 1, 2, 3, 4, 4.1, 4.5, 5, and 5.5 Water Wells, Sections 64400.80 through 64445. These regulations require monitoring for potable water wells supplying public water systems, defined as non-transient, non-community water systems (serving 25 people or more for more than six months); the project will employ about 63 workers during normal MSP operations and 73 workers during the summer months. Regulated wells must be sampled for bacteria once a month and the results submitted to the DHS. The wells must also be monitored for inorganic chemicals once and organic chemicals quarterly during the year designated by the DHS. DHS will designate the year based on historical monitoring frequency and laboratory capacity.

Public Resources Code

CEC Policy adopted pursuant to Section 25300 et seq. In the 2003 “Integrated Energy Policy Report”, consistent with SWRCB Policy 75-58 and the Warren-Alquist Act, the CEC adopted a policy to approve the use of “fresh inland” water for cooling purposes by power plants only where alternative water supply sources and alternative cooling technologies are shown to be “environmentally undesirable” or “economically unsound.”

Section 25523(a). The Public Resources Code provides for the inclusion of requirements in a CEC License Decision to assure protection of environmental quality and requires submission of information to the CEC concerning proposed water resources and water quality protection.

The administering agencies for the State laws and ordinances are the CEC, the SWRCB, and the Lahontan RWQCB. The project will comply with all applicable State laws and ordinances related to water use and quality during construction and operation.

5.17.1.3 Local Laws and Ordinances

San Bernardino County

Ordinance Code, Title 3, Division 3, Chapter 6 - Domestic Water Sources and Systems, Article 3 – Water Wells, Section 33.0631 - Permits. This ordinance requires that no person or entity, as principal agent or employee, shall dig, drill, bore, drive, reconstruct or destroy (1) a well that is or has been used to produce or inject water (2) a cathodic protection well (3) an observation well or (4) an exploration well without first filing a written application to do so with the DEHS by receiving and retaining a valid permit as provided herein.

Ordinance Code, Title 3, Division 3, Chapter 6 - Domestic Water Sources and Systems, Article 3 – Water Wells, Section 33.0636 – General Location of Water Wells. This ordinance describes requirements for the general siting of water wells. It states that it shall be unlawful for any person or entity to drill, dig, excavate, or bore any water well at any location where sources of pollution or contamination are known to exist or existed, or where otherwise substantial risk exists that water from that location may become contaminated or polluted even though the well may be properly constructed and maintained. Every well shall be located an adequate distance from all potential sources of contamination and pollution.

Ordinance Code, Title 3, Division 3, Chapter 6 - Domestic Water Sources and Systems, Article 3 – Water Wells, Section 33.0638 – Well Surface and Subsurface Construction Features. This ordinance outlines the requirements for placement of the annular seal for water supply wells. It includes guidelines for the placement of a sample spigot on the pump discharge line of any water well used as a public water supply adjacent to the pump and on the distribution side of the check valve. It further states that a check valve shall be provided on the pump discharge line adjacent to the pump for all water wells. This ordinance states that all community water supply wells and individual domestic wells shall be provided with a pipe or other effective means through which chlorine or other approved disinfecting agents may be introduced directly into the well. It requires that a master meter or other suitable measuring device shall be located at each source facility and shall accurately register the quantity of water delivered to the distribution system from all community water supply wells serving a public water supply system. This ordinance outlines the requirements of the use of an air-relief vent, if present.

Ordinance Code, Title 3, Division 3, Chapter 6 - Domestic Water Sources and Systems, Article 3 – Water Wells, Section 33.0640 – Water Quality Standards. This ordinance states that water from all new, repaired, and reconstructed community water supply wells shall be tested and meet standards for microbiological, chemical, physical, and radiological quality in accordance with California Administrative Code, Title 22, “Domestic Water Quality and Monitoring.”

Ordinance Code, Title 3, Division 3, Chapter 6 - Domestic Water Sources and Systems, Article 3 – Water Wells, Section 33.0641 – Required Inspections of Wells. This ordinance requires that an inspection shall be requested of DEHS (a) at least 24 hours in advance of the filling of the annular space or conductor casing, (b) after the installation of the surface protective slab, pumping, and other required equipment, (c) and immediately before and during the destruction of a well; immediately after the well destruction, (d) and at any other time stipulated on the DEHS permit.

Ordinance Code, Title 3, Division 3, Chapter 6 - Domestic Water Sources and Systems, Article 3 – Water Wells, Section 33.0643 – Well Abandonment. This ordinance code states that if after 30 days of abandonment, the owner of an abandoned well has not declared the well to DEHS for proposed reuse per Section 33.0644, then the well shall be destroyed per Section 33.0631 of this Article. If any well is found by DEHS to be a hazard, whereby its continued existence is likely to cause damage to groundwater or to the public health and safety, DEHS shall direct the owner to destroy the well within a stated period. At the time of removal of a pump, the casing shall be provided with an adequate cap at the surface and shall be maintained so that it will not be a hazard to

health or safety until such time that the abandoned well is properly sealed from the bottom to the top.

Ordinance Code, Title 3, Division 3, Chapter 8 - Waste Management, Article 5 – Liquid Waste Disposal, Section 33.0892 – Approved Liquid Waste Disposal Systems. This ordinance states that no person or entity shall install, utilize, or control the use of any liquid waste disposal system within this jurisdiction unless it is (a) a system which complies with applicable portions of the Uniform Plumbing Code as amended and adopted by this jurisdiction and complies with DEHS standards, (b) a system which has been approved by the DEHS and the building authority of this jurisdiction or (c) an alternative liquid-waste disposal system which has been approved by the DEHS, the appropriate building official of this jurisdiction, and the appropriate California Regional Water Quality Control Board as protecting water quality, public health, and safety.

Ordinance Code, Title 3, Division 3, Chapter 8 - Waste Management, Article 5 – Liquid Waste Disposal, Section 33.0893 – Permits for Alternative Liquid Waste Disposal Systems. This ordinance states that no person or entity shall install any alternative liquid-waste disposal system without first obtaining a DEHS permit to do so and paying those fees to the DEHS as are set forth in the Chapter 2 of Division 6 of Title 1 of the San Bernardino County Code.

Ordinance Code, Title 3, Division 3, Chapter 8 - Waste Management, Article 5 – Liquid Waste Disposal, Section 33.0894 – Liquid Waste Disposal System Location Requirements. This ordinance states that location requirements shall be as stated in the DEHS Standards on file with the Clerk of the Board under the date of August 1992, as the same may be amended by the DEHS from time to time and approved by the Board of Supervisors. It further states that all liquid waste disposal systems within this jurisdiction shall be installed to comply with minimum Standards unless the conditions of a DEHS-issued permit otherwise allows.

Ordinance Code, Title 6, Division 3, Chapter 3 - Uniform Plumbing Code. This code describes installation and inspection requirements for locating disposal/leach fields, and seepage pits.



Merrell-Johnson Engineering, Inc.
CIVIL ENGINEERING ♦ SURVEYING

HYDROLOGY STUDY

For

MOJAVE SOLAR PROJECT HARPER DRY LAKE, CA

Prepared For:

MOJAVE SOLAR LLC
Victorville, CA
July, 2009

Prepared by:

Merrell-Johnson Engineering, Inc.

12138 Industrial Blvd., Suite 240
Victorville, CA 92395
(760) 241-6146

Job No. 3001

Brad S. Merrell
Principal Engineer
R.C.E. 49423 Exp. 09/30/10

Mark D. Rowan
Project Manager

TABLE OF CONTENTS

DISCUSSION

SECTION 1

Introduction
Project Location
Methodology
Description
 General
 Existing Condition
 Developed Condition
Conclusions & Recommendations

EXHIBITS

SECTION 2

Vicinity Map
U.S.G.S. Map
Proposed Development Plan
Drainage Plan

HYDROLOGY CALCULATIONS

SECTION 3

Topography Map
Off-site Hydrology Calculations
 Off-Site Hydrology Map
 Unit Hydrograph and Rational Calculations: 100-Year Storm
Exhibits
 Soil Map
 Isohyetal Map
 Unit Hydrograph Data Sheets

STORM DRAIN CAPACITY CALCULATIONS

SECTION 4

Channel Calculations
Roadway Crossing Calculations
 All Weather Crossings
 Channel Bottom Crossings
Exhibits
 San Bernardino County Flood Control District – Earth Channel Section

SECTION 1

DISCUSSION

INTRODUCTION

The purpose of this study was to determine the impact of the 100-year storm runoff flow from the watershed tributary to the proposed Mojave Solar Project site as delineated on the maps contained in this study. This study also examines measures to intercept the runoff flows and convey them around the project site to their historical flow locations along the northern and eastern boundaries of the property adjacent to Harper Dry Lake.

PROJECT LOCATION

The Mojave Solar Project site is located along the westerly boundary of Harper Dry Lake near the unincorporated area of Lockhart in northwesterly San Bernardino County. The project site location is highlighted on the attached vicinity map. This location was originally planned to be part of a larger solar electric generating system (SEGS) facility consisting of five separate generating facilities. Two of the five facilities were completed in the late 1980's. The Mojave Solar Project site is located on the location originally planned for two of the remaining facilities.

METHODOLOGY

The method in determining these peak runoff flows was the rational method for watershed areas under 640 acres and the unit hydrograph method for watershed areas over 640 acres as specified in the 1986 San Bernardino County Hydrology Manual. The existing offsite flow was examined and delineated from U.S.G.S. Maps: Lockhart, Kramer Junction, Kramer Hills, Twelve Gage Lake, Astley Rancho, and Wild Crossing. The computer program used for the rational method analysis routes runoff flows through the off-site sub-areas by modeling geometric channels. These channels are used for modeling the naturally occurring flowlines only and the improved channels do not exist within the off-site watershed areas.

A drainage plan was developed for the project site, modeled after the drainage plan originally prepared for the existing SEGS project. The storm runoff flow from the tributary area for Streams 8 & 9 was analyzed and compared to the identical tributary

area from the original SEGS study. The flows from the original study were slightly higher and the more conservative numbers were used to model the corresponding channels for the current project. Hoffman Road, which runs along the southern boundary of the existing SEGS facilities, is elevated several feet above the adjacent terrain forming an embankment which intercepts drainage flows tributary to the existing SEGS facilities and directs them eastward toward Harper Dry Lake. Storm runoff from portions of the drainage areas west of the Mojave Solar Project site will follow their historical flow paths and be intercepted by this existing embankment and be conveyed to Harper Dry Lake.

The off-site sheet flows tributary to the Mojave Solar Project will be intercepted along the southern and eastern boundaries of the site, conveyed around the project site within improved drainage channels, and outlet within their historical flow locations along the northern and easterly project boundaries. Measures will be employed to return the channelized flows to their historical sheet flow conditions as they leave the project site and flow into Harper Dry Lake.

The parameters of the off-site tributary sub-areas examined in this study are shown in Table A and are outlined on the attached U.S.G.S. map.

Table A

Sub-area	Elevation Difference (ft.)	Length (ft)	Area (Acres)	Avg. Slope (ft/ft)
Stream 3	65.0	7,356	210.5	0.0088
Stream 4	218.0	35,535	3520.0	0.0061
Stream 5	66.0	4,780	229.4	0.0138
Stream 6	834.0	72,811	12,134	0.0115
Stream 7	40.0	4,039	54.1	0.0099
Streams 8 & 9	802.0	74,334	42,142	0.0108
Stream 10	117.0	10,557	530	0.0111

DESCRIPTION

GENERAL:

The project site and tributary watershed area is comprised of generally vacant, undeveloped land with some scattered residences. Some land parcels within the tributary watershed area and most of the land parcels within the project boundaries were previously utilized for agricultural purposes and consist of disturbed land.

EXISTING CONDITION:

The project site is located along the south and west shores of Harper Dry Lake in an unincorporated area of San Bernardino County. The tributary watershed areas are generally sloping at less than 1.0 % from southwest to northeast towards the dry lake bed. Storm runoff flows begin as sheet flow within the upper reaches of the watershed and confluence as they approach the project site and the dry lake. The existing vegetation on the site consists of desert brush and vegetation in sandy surface soils.

There is evidence of minor runoff in the form of sheet flows across the project site. There is also some minor evidence of scour, within the tributary watershed area, from larger storm events that generally follow the existing swales as indicated on the enclosed U.S.G.S. maps. These existing swales disappear upstream of the project site due to previous agricultural activity and grading disturbances in the area. The 100-year flood plain has not been established for the Harper Dry Lake.

The results of this study are summarized in Table B. Calculations sheets are in Section 3 of this report.

Table B

Off-Site Sub-Area	Q₁₀₀ (cfs)
Stream 3	181
Stream 4	2,162
Stream 5	290
Stream 6	3,992
Stream 7	57
Streams 8 & 9	14,788
Stream 10	458

DEVELOPED CONDITION:

The proposed development for this site is a solar energy power generation plant. This plant site will include a power generation area, fields of solar panels, and various plant support areas. The proposed development plan for the Mojave Solar Project is attached to this report.

CONCLUSIONS AND RECOMMENDATIONS

During our field investigation of the site we observed the existing conditions as stated previously. The calculated 100-year storm runoff flows enter the site as sheet flows along seven (7) boundary sections as indicated on the attached drainage maps. The 100-year runoff flows crossing the project boundary sections are tabulated in Table B above.

A drainage plan has been developed for the project site. Drainage channels will be constructed to intercept the storm runoff as sheet flow along the southern and western boundaries of the project and to convey these storm flows around the project site. Storm runoff flows tributary to the western boundary of the project will be conveyed to the existing embankment of Hoffman Road where they will follow their historical flow path to Harper Dry Lake. Storm runoff flows tributary to the southern project boundary will be conveyed to a spreading ground constructed along the northern project boundary. This spreading ground will be designed to dissipate the energy of the runoff flow and return the flow to its historical sheet flow parameters as it leaves the project site and flows into the dry lake bed. The spreading ground will be designed to minimize disturbance of the dry lake bed and surrounding areas.

The channels will be designed and constructed following the flow design requirements of the San Bernardino County Flood Control District to include flow bulking, erosion protection, and free-board. Preliminary channel design requirements and channel data are summarized in Table C. of this report. The ultimate design of the storm channels and spreading ground is contingent upon the final site and grading plans for the project and will be designed in conjunction with the approved, engineer's plans for the site.

Preliminary calculations were performed for two all-weather channel crossings to the project. An all-weather crossing will be constructed on Harper Lake Road crossing drainage Channel A. A second all-weather crossing will be constructed on Lockhart Road crossing Channel D. These crossings will provide all-weather paved access to both power islands and access to adjacent property owners. These crossings will provide 24-hour, all-weather emergency access to the project and to adjacent properties. The final design of the crossings will be analyzed in conjunction with the approved engineer's plans for the project.


Table C
Preliminary Channel Data for Master Plan of Drainage

Channel	Bottom Width	Flow Depth	Length (ft)	Flow (cfs)	Avg. Slope (ft/ft)
A-1	180	6.0	11,400	14,788	0.0070
A-2	240	6.0	5,280	14,788	0.0040
A-3	260	6.0	2,300	210.5	0.0070
B	90	5.0	2,700	4,282	0.0057
C	55	5.0	4,770	2,162	0.0050
D	90	5.0	2,774	6,444	0.0097
E	65	4.0	13,520	1,477	0.0019
F	20	3.0	5,280	458	0.0070


SECTION 2

EXHIBITS

VICINITY MAP



U.S.G.S. MAP



Name: LOCKHART

Date: 7/27/2009

Scale: 1 inch equals 2000 feet


Location: 035° 00' 38.83" N 117° 19' 18.48" W NAD83


Caption: MOJAVE SOLAR PROJECT SITE

PROPOSED DEVELOPMENT PLAN




Merrell-Johnson Engineering, Inc.
CIVIL ENGINEERING • SURVEYING





MAP LOCATION



LEGEND

- PROPOSED ACCESS ROUTES
- EXISTING ACCESS ROUTES
- PROPOSED TRANSMISSION LINE
- PROPOSED GAS LINE



MOJAVE SOLAR PROJECT

MOJAVE SOLAR LLC



Figure 2-3a
PROJECT SITE MAP





PROJECT:
DATE: 07/16/09

DRAINAGE PLAN

EC

calhoun 12:31pm 22 July 2009 P:\3001-4 Harper Lake CEC\Hydrology grading.dwg - General arrangement Overall Merrell-Johnson Engineering, Inc.



- LEGEND**
- PROPOSED ACCESS ROUTES
 - EXISTING ACCESS ROUTES
 - PROPOSED TRANSMISSION LINE
 - PROPOSED GAS LINE
 - PROPOSED FENCE LINE
 - SECTION LINE
 - 1/4 SECTION LINE






MOJAVE SOLAR PROJECT

CONCEPTUAL GRADING INDEX

MOJAVE SOLAR LLC

Merrell-Johnson Engineering, Inc.

PROJECT: DATE: 07/22/09






MOJAVE SOLAR PROJECT

CONCEPTUAL GRADING
ALPHA FIELD (WEST)

MOJAVE SOLAR LLC

Merrell-Johnson
Engineering, Inc.


PROJECT:
DATE: 07/22/09



MOJAVE SOLAR PROJECT


Figure 2-3(g)
SECTIONS

MOJAVE SOLAR LLC




Merrell-Johnson
Engineering, Inc.


PROJECT:
DATE: 07/21/09




SECTION F-F
NOT TO SCALE




SECTION G-G
NOT TO SCALE



SECTION I-I
NOT TO SCALE



SECTION H-H
NOT TO SCALE




MOJAVE SOLAR PROJECT

Figure 2-3(i)
SECTIONS


MOJAVE SOLAR LLC




PROJECT:
DATE: 07/21/09



SECTION J-J
NOT TO SCALE



SECTION K-K
NOT TO SCALE






MOJAVE SOLAR LLC

MOJAVE SOLAR PROJECT

Figure 2-3(j)
SECTIONS




PROJECT:
DATE: 07/21/09



MOJAVE SOLAR PROJECT

Figure 2-3(k)
SECTIONS

MOJAVE SOLAR LLC



Merrell-Johnson
Engineering, Inc.

PROJECT:
DATE: 07/21/09

SECTION 3

HYDROLOGY CALCULATIONS

TOPOGRAPHY MAP

END OF SEGS VIII

SOUTH END OF SEGS IX

MOJAVE SOLAR PROJECT

HARPER LAKE
ROAD EXISTING
PAVED ACCESS



28

29

30

25

33


32

31

36


OFF-SITE HYDROLOGY CALCULATIONS

OFF-SITE HYDROLOGY MAP



Name: KRAMER HILLS
Date: 6/22/2009
Scale: 1 inch equals 1.894 miles

Location: Sec 34 T010N R005W CA San Bernardino
Caption: MOJAVE SOLAR PROJECT - OFF-SITE TRIBUTARY
AREAS



Name: LOCKHART

Date: 6/22/2009

Scale: 1 inch equals 2000 feet

Location: Sec 29 T011N R004W CA San Bernardino

Caption: MOJAVE SOLAR PROJECT - OFF-SITE TRIBUTARY FLOWS

UNIT HYDROGRAPH AND RATIONAL CALCULATIONS
100-YEAR STORM

STREAM 3

San Bernardino County Rational Hydrology Program

(Hydrology Manual Date - August 1986)

CIVILCADD/CIVILDESIGN Engineering Software, (c) 1989-2004 Version 7.0
Rational Hydrology Study Date: 04/11/08

ABENGOA SOLAR - HARPER LAKE - JOB 3001
SOUTHERN TRIBUTARY AREA - STREAM 3
NODE 31 - NODE 34
100-YEAR STORM EVENT - AMC II

MERRELL-JOHNSON ENGINEERING, INC.
12138 INDUSTRIAL BOULEVARD, SUITE 240
VICTORVILLE, CA 92395
(760) 241-6146 * FAX (760) 241-0566

***** Hydrology Study Control Information *****

Rational hydrology study storm event year is 100.0
Computed rainfall intensity:
Storm year = 100.00 1 hour rainfall = 1.200 (In.)
Slope used for rainfall intensity curve b = 0.7000
Soil antecedent moisture condition (AMC) = 2

Process from Point/Station 31.000 to Point/Station 32.000
**** INITIAL AREA EVALUATION ****

UNDEVELOPED (poor cover) subarea
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 1.000
Decimal fraction soil group D = 0.000
SCS curve number for soil(AMC 2) = 86.00
Pervious ratio(Ap) = 1.0000 Max loss rate(Fm)= 0.265(In/Hr)
Initial subarea data:
Initial area flow distance = 989.000(Ft.)
Top (of initial area) elevation = 2161.000(Ft.)
Bottom (of initial area) elevation = 2150.000(Ft.)
Difference in elevation = 11.000(Ft.)
Slope = 0.01112 s(%)= 1.11
TC = k(0.525)*[(length^3)/(elevation change)]^0.2
Initial area time of concentration = 20.370 min.
Rainfall intensity = 2.556(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area (Q=KCIA) is C = 0.807
Subarea runoff = 9.691(CFS)
Total initial stream area = 4.700(Ac.)
Pervious area fraction = 1.000
Initial area Fm value = 0.265(In/Hr)

Process from Point/Station 32.000 to Point/Station 33.000
**** IRREGULAR CHANNEL FLOW TRAVEL TIME ****

Depth of flow = 0.715(Ft.), Average velocity = 1.896(Ft/s)

***** Irregular Channel Data *****

Information entered for subchannel number 1 :

Point number	'X' coordinate	'Y' coordinate
1	0.00	1.00
2	10.00	0.00
3	20.00	1.00

Manning's 'N' friction factor = 0.035

Sub-Channel flow = 9.691(CFS)
' ' flow top width = 14.297(Ft.)
' ' velocity= 1.896(Ft/s)
' ' area = 5.110(Sq.Ft)
' ' Froude number = 0.559

Upstream point elevation = 2150.000(Ft.)
Downstream point elevation = 2130.000(Ft.)
Flow length = 2526.000(Ft.)
Travel time = 22.20 min.
Time of concentration = 42.57 min.
Depth of flow = 0.715(Ft.)
Average velocity = 1.896(Ft/s)
Total irregular channel flow = 9.691(CFS)
Irregular channel normal depth above invert elev. = 0.715(Ft.)
Average velocity of channel(s) = 1.896(Ft/s)

+++++
Process from Point/Station 32.000 to Point/Station 33.000
**** SUBAREA FLOW ADDITION ****

UNDEVELOPED (poor cover) subarea
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 1.000
Decimal fraction soil group D = 0.000
SCS curve number for soil(AMC 2) = 86.00
Pervious ratio(Ap) = 1.0000 Max loss rate(Fm)= 0.265(In/Hr)
Time of concentration = 42.57 min.
Rainfall intensity = 1.526(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area,(total area with modified rational method)(Q=KCIA) is C = 0.744
Subarea runoff = 57.823(CFS) for 54.800(Ac.)
Total runoff = 67.514(CFS)
Effective area this stream = 59.50(Ac.)
Total Study Area (Main Stream No. 1) = 59.50(Ac.)
Area averaged Fm value = 0.265(In/Hr)

+++++
Process from Point/Station 33.000 to Point/Station 34.000
**** IRREGULAR CHANNEL FLOW TRAVEL TIME ****

Depth of flow = 1.386(Ft.), Average velocity = 4.008(Ft/s)
***** Irregular Channel Data *****

Information entered for subchannel number 1 :

Point number	'X' coordinate	'Y' coordinate
1	0.00	2.00
2	6.00	0.00

3	14.00	0.00
4	20.00	2.00

Manning's 'N' friction factor = 0.035

Sub-Channel flow = 67.514(CFS)
 ' ' flow top width = 16.314(Ft.)
 ' ' velocity= 4.008(Ft/s)
 ' ' area = 16.846(Sq.Ft)
 ' ' Froude number = 0.695

Upstream point elevation = 2130.000(Ft.)
 Downstream point elevation = 2096.000(Ft.)
 Flow length = 3841.000(Ft.)
 Travel time = 15.97 min.
 Time of concentration = 58.54 min.
 Depth of flow = 1.386(Ft.)
 Average velocity = 4.008(Ft/s)
 Total irregular channel flow = 67.514(CFS)
 Irregular channel normal depth above invert elev. = 1.386(Ft.)
 Average velocity of channel(s) = 4.008(Ft/s)

+++++
 Process from Point/Station 33.000 to Point/Station 34.000
 **** SUBAREA FLOW ADDITION ****

UNDEVELOPED (poor cover) subarea
 Decimal fraction soil group A = 0.000
 Decimal fraction soil group B = 0.000
 Decimal fraction soil group C = 1.000
 Decimal fraction soil group D = 0.000
 SCS curve number for soil(AMC 2) = 86.00
 Pervious ratio(Ap) = 1.0000 Max loss rate(Fm)= 0.265(In/Hr)
 Time of concentration = 58.54 min. Tc
 Rainfall intensity = 1.221(In/Hr) for a 100.0 year storm
 Effective runoff coefficient used for area,(total area with modified
 rational method)(Q=KCIA) is C = 0.705
 Subarea runoff = 113.547(CFS) for 151.000(Ac.)
 Total runoff = 181.061(CFS) Q₁₀₀
 Effective area this stream = 210.50(Ac.)
 Total Study Area (Main Stream No. 1) = 210.50(Ac.)
 Area averaged Fm value = 0.265(In/Hr)
 End of computations, Total Study Area = 210.50 (Ac.)
 The following figures may
 be used for a unit hydrograph study of the same area.
 Note: These figures do not consider reduced effective area
 effects caused by confluences in the rational equation.

Area averaged pervious area fraction(Ap) = 1.000
 Area averaged SCS curve number = 86.0

STREAM 4

Unit Hydrograph Analysis

Copyright (c) CIVILCADD/CIVILDESIGN, 1989 - 2004, Version 7.0

Study date 04/11/08

+++++

San Bernardino County Synthetic Unit Hydrology Method
Manual date - August 1986

MERRELL-JOHNSON ENGINEERING, INC.
12138 INDUSTRIAL BOULEVARD, SUITE 240
VICTORVILLE, CA 92395
(760) 241-6146 * FAX (760) 241-0566

ABENGOA SOLAR - HARPER LAKE - JOB NO. 3001
SOUTHERN TRIBUTARY AREA - STREAM 4
100-YEAR STORM EVENT - AMC II

Storm Event Year = 100

Antecedent Moisture Condition = 2

English (in-lb) Input Units Used

English Rainfall Data (Inches) Input Values Used

English Units used in output format

Area averaged rainfall intensity isohyetal data:

Sub-Area (Ac.)	Duration (hours)	Isohyetal (In)
Rainfall data for year 100		
3520.00	1	1.20

Rainfall data for year 100		
3520.00	6	1.80

Rainfall data for year 100		
3520.00	24	3.00

+++++

***** Area-averaged max loss rate, Fm *****

SCS curve No.(AMCII)	SCS curve NO.(AMC 2)	Area (Ac.)	Area Fraction	Fp(Fig C6) (In/Hr)	Ap (dec.)	Fm (In/Hr)
84.0	84.0	3520.00	1.000	0.301	1.000	0.301

Area-averaged adjusted loss rate Fm (In/Hr) = 0.301

***** Area-Averaged low loss rate fraction, Yb *****

Area (Ac.)	Area Fract	SCS CN (AMC2)	SCS CN (AMC2)	S	Pervious Yield Fr
3520.00	1.000	84.0	84.0	1.90	0.505

Area-averaged catchment yield fraction, Y = 0.505

Area-averaged low loss fraction, Yb = 0.495

+++++

Watercourse length = 35535.00(Ft.)

Length from concentration point to centroid = 14679.00(Ft.)

Elevation difference along watercourse = 218.00(Ft.)

Mannings friction factor along watercourse = 0.030

Watershed area = 3520.00(Ac.)

Catchment Lag time = 1.132 hours

Unit interval = 10.000 minutes

Unit interval percentage of lag time = 14.7267

Hydrograph baseflow = 0.00(CFS)

Average maximum watershed loss rate(Fm) = 0.301(In/Hr)

Average low loss rate fraction (Yb) = 0.495 (decimal)

DESERT S-Graph Selected

Computed peak 5-minute rainfall = 0.569(In)

Computed peak 30-minute rainfall = 0.975(In)

Specified peak 1-hour rainfall = 1.200(In)

Computed peak 3-hour rainfall = 1.539(In)

Specified peak 6-hour rainfall = 1.800(In)

Specified peak 24-hour rainfall = 3.000(In)

Rainfall depth area reduction factors:

Using a total area of 3520.00(Ac.) (Ref: fig. E-4)

5-minute factor = 0.840 Adjusted rainfall = 0.478(In)

30-minute factor = 0.840 Adjusted rainfall = 0.818(In)

1-hour factor = 0.840 Adjusted rainfall = 1.007(In)

3-hour factor = 0.979 Adjusted rainfall = 1.507(In)

6-hour factor = 0.989 Adjusted rainfall = 1.781(In)

24-hour factor = 0.996 Adjusted rainfall = 2.987(In)

U n i t H y d r o g r a p h

+++++

Interval Number	'S' Graph Mean values	Unit Hydrograph ((CFS))
--------------------	--------------------------	----------------------------

(K = 21285.00 (CFS))

1	0.661	140.788
2	2.765	447.744
3	6.264	744.740
4	11.837	1186.333
5	22.529	2275.715
6	36.417	2956.120
7	47.224	2300.270
8	55.304	1719.720
9	61.229	1261.175
10	65.795	971.767
11	69.605	811.112
12	72.869	694.624

13	75.595	580.198
14	78.054	523.410
15	80.087	432.795
16	81.939	394.175
17	83.543	341.438
18	85.041	318.833
19	86.442	298.247
20	87.674	262.142
21	88.794	238.370
22	89.697	192.392
23	90.556	182.638
24	91.377	174.882
25	92.119	157.823
26	92.817	148.658
27	93.471	139.271
28	94.068	126.902
29	94.570	106.985
30	95.071	106.576
31	95.560	104.112
32	95.961	85.385
33	96.344	81.499
34	96.727	81.470
35	97.045	67.783
36	97.310	56.423
37	97.575	56.423
38	97.815	51.077
39	97.970	32.856
40	98.117	31.346
41	98.265	31.554
42	98.434	35.888
43	98.611	37.615
44	98.787	37.615
45	98.964	37.615
46	99.141	37.615
47	99.318	37.615
48	99.485	35.646
49	99.589	22.148
50	99.681	19.591
51	99.773	19.591
52	99.865	19.591
53	100.000	9.796

 Total soil rain loss = 1.22(In)
 Total effective rainfall = 1.77(In)
 Peak flow rate in flood hydrograph = 2162.03(CFS)

+++++
 24 - H O U R S T O R M
 R u n o f f H y d r o g r a p h

Hydrograph in 10 Minute intervals ((CFS))

Time(h+m)	Volume	Ac.Ft	Q(CFS)	0	550.0	1100.0	1650.0	2200.0
15+ 0	138.2017	243.44	Q	V				
15+10	141.9069	268.99	Q	V				
15+20	145.9632	294.49	Q	V				

15+30	150.3788	320.57		Q		V			
15+40	155.1809	348.64		Q		V			
15+50	160.4433	382.05		Q		V			
16+ 0	166.4324	434.81		Q		V			
16+10	174.2493	567.51			Q	V			
16+20	184.9586	777.50				Q			
16+30	198.8214	1006.44				V	Q		
16+40	217.4487	1352.34				V		Q	
16+50	243.9335	1922.79				V			Q
17+ 0	273.7134	2162.03	Q ₁₀₀			V			Q
17+10	298.3614	1789.44				V		Q	
17+20	318.3103	1448.29				V	Q		
17+30	334.4602	1172.49				Q	V		
17+40	348.0147	984.06					V		Q
17+50	359.8053	856.00					V		
18+ 0	370.1252	749.22			Q		V		
18+10	379.1683	656.53			Q		V		
18+20	387.3510	594.07			Q		V		
18+30	394.6133	527.24			Q		V		
18+40	401.3314	487.74			Q		V		
18+50	407.5403	450.76			Q		V		
19+ 0	413.4847	431.56			Q		V		
19+10	419.1475	411.12			Q		V		
19+20	424.4335	383.76			Q		V		
19+30	429.3908	359.90			Q		V		
19+40	433.9310	329.62			Q		V		
19+50	438.2862	316.19			Q		V		
20+ 0	442.4633	303.25			Q		V		
20+10	446.4211	287.34			Q		V		
20+20	450.2133	275.32			Q		V		
20+30	453.8356	262.98			Q		V		
20+40	457.2699	249.33			Q		V		
20+50	460.4983	234.38			Q		V		
21+ 0	463.6413	228.18			Q		V		
21+10	466.6721	220.03			Q		V		
21+20	469.5132	206.27		Q			V		
21+30	472.2622	199.58		Q			V		
21+40	474.9273	193.49		Q			V		
21+50	477.4339	181.98		Q			V		
22+ 0	479.8129	172.71		Q			V		
22+10	482.1275	168.04		Q			V		
22+20	484.3340	160.20		Q			V		
22+30	486.3794	148.49		Q			V		
22+40	488.3733	144.76		Q			V		
22+50	490.3348	142.41		Q			V		
23+ 0	492.2889	141.87		Q			V		
23+10	494.2186	140.09		Q			V		
23+20	496.1134	137.56		Q			V		
23+30	497.9753	135.17		Q			V		
23+40	499.8035	132.73		Q			V		
23+50	501.5927	129.90		Q			V		
24+ 0	503.3158	125.09		Q			V		

STREAM 5

San Bernardino County Rational Hydrology Program

(Hydrology Manual Date - August 1986)

CIVILCADD/CIVILDESIGN Engineering Software, (c) 1989-2004 Version 7.0
Rational Hydrology Study Date: 04/11/08

ABENGOA SOLAR - HARPER LAKE - JOB NO. 3001
SOUTHERN TRIBUTARY AREA - STREAM 5
NODE 51 - NODE 54
100-YEAR STORM EVENT - AMC II

MERRELL-JOHNSON ENGINEERING, INC.
12138 INDUSTRIAL BOULEVARD, SUITE 240
VICTORVILLE, CA 92395
(760) 241-6146 * FAX (760) 241-0566

***** Hydrology Study Control Information *****

Rational hydrology study storm event year is 100.0
Computed rainfall intensity:
Storm year = 100.00 1 hour rainfall = 1.200 (In.)
Slope used for rainfall intensity curve b = 0.7000
Soil antecedent moisture condition (AMC) = 2

Process from Point/Station 51.000 to Point/Station 52.000
**** INITIAL AREA EVALUATION ****

UNDEVELOPED (poor cover) subarea
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 1.000
Decimal fraction soil group D = 0.000
SCS curve number for soil(AMC 2) = 86.00
Pervious ratio(Ap) = 1.0000 Max loss rate(Fm)= 0.265(In/Hr)
Initial subarea data:
Initial area flow distance = 1000.000(Ft.)
Top (of initial area) elevation = 2133.000(Ft.)
Bottom (of initial area) elevation = 2124.000(Ft.)
Difference in elevation = 9.000(Ft.)
Slope = 0.00900 s(%)= 0.90
 $TC = k(0.525)*[(length^3)/(elevation\ change)]^{0.2}$
Initial area time of concentration = 21.346 min.
Rainfall intensity = 2.474(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area (Q=KCIA) is C = 0.804
Subarea runoff = 19.879(CFS)
Total initial stream area = 10.000(Ac.)
Pervious area fraction = 1.000
Initial area Fm value = 0.265(In/Hr)

Process from Point/Station 52.000 to Point/Station 53.000
**** IRREGULAR CHANNEL FLOW TRAVEL TIME ****

Depth of flow = 0.841(Ft.), Average velocity = 2.810(Ft/s)

***** Irregular Channel Data *****

Information entered for subchannel number 1 :

Point number	'X' coordinate	'Y' coordinate
1	0.00	1.00
2	10.00	0.00
3	20.00	1.00

Manning's 'N' friction factor = 0.035

Sub-Channel flow = 19.879(CFS)
' ' flow top width = 16.822(Ft.)
' ' velocity= 2.810(Ft/s)
' ' area = 7.074(Sq.Ft)
' ' Froude number = 0.764

Upstream point elevation = 2124.000(Ft.)
Downstream point elevation = 2100.000(Ft.)
Flow length = 1715.000(Ft.)
Travel time = 10.17 min.
Time of concentration = 31.52 min.
Depth of flow = 0.841(Ft.)
Average velocity = 2.810(Ft/s)
Total irregular channel flow = 19.879(CFS)
Irregular channel normal depth above invert elev. = 0.841(Ft.)
Average velocity of channel(s) = 2.810(Ft/s)

+++++
Process from Point/Station 52.000 to Point/Station 53.000
**** SUBAREA FLOW ADDITION ****

UNDEVELOPED (poor cover) subarea
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 1.000
Decimal fraction soil group D = 0.000
SCS curve number for soil(AMC 2) = 86.00
Pervious ratio(Ap) = 1.0000 Max loss rate(Fm)= 0.265(In/Hr)
Time of concentration = 31.52 min.
Rainfall intensity = 1.883(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area,(total area with modified rational method)(Q=KCIA) is C = 0.773
Subarea runoff = 97.062(CFS) for 70.300(Ac.)
Total runoff = 116.940(CFS)
Effective area this stream = 80.30(Ac.)
Total Study Area (Main Stream No. 1) = 80.30(Ac.)
Area averaged Fm value = 0.265(In/Hr)

+++++
Process from Point/Station 53.000 to Point/Station 54.000
**** IRREGULAR CHANNEL FLOW TRAVEL TIME ****

Depth of flow = 1.584(Ft.), Average velocity = 5.791(Ft/s)
***** Irregular Channel Data *****

Information entered for subchannel number 1 :

Point number	'X' coordinate	'Y' coordinate
1	0.00	2.00
2	6.00	0.00

3	14.00	0.00
4	20.00	2.00

Manning's 'N' friction factor = 0.035

Sub-Channel flow = 116.940(CFS)
 ' ' flow top width = 17.502(Ft.)
 ' ' velocity= 5.791(Ft/s)
 ' ' area = 20.192(Sq.Ft)
 ' ' Froude number = 0.950

Upstream point elevation = 2100.000(Ft.)
 Downstream point elevation = 2067.000(Ft.)
 Flow length = 2065.000(Ft.)
 Travel time = 5.94 min.
 Time of concentration = 37.46 min.
 Depth of flow = 1.584(Ft.)
 Average velocity = 5.791(Ft/s)
 Total irregular channel flow = 116.940(CFS)
 Irregular channel normal depth above invert elev. = 1.584(Ft.)
 Average velocity of channel(s) = 5.791(Ft/s)

+++++
 Process from Point/Station 53.000 to Point/Station 54.000
 **** SUBAREA FLOW ADDITION ****

UNDEVELOPED (poor cover) subarea
 Decimal fraction soil group A = 0.000
 Decimal fraction soil group B = 0.000
 Decimal fraction soil group C = 1.000
 Decimal fraction soil group D = 0.000
 SCS curve number for soil(AMC 2) = 86.00
 Pervious ratio(Ap) = 1.0000 Max loss rate(Fm)= 0.265(In/Hr)
 Time of concentration = 37.46 min. Tc
 Rainfall intensity = 1.669(In/Hr) for a 100.0 year storm
 Effective runoff coefficient used for area,(total area with modified
 rational method)(Q=KCIA) is C = 0.757
 Subarea runoff = 172.851(CFS) for 149.100(Ac.)
 Total runoff = 289.791(CFS) Q₁₀₀
 Effective area this stream = 229.40(Ac.)
 Total Study Area (Main Stream No. 1) = 229.40(Ac.)
 Area averaged Fm value = 0.265(In/Hr)
 End of computations, Total Study Area = 229.40 (Ac.)
 The following figures may
 be used for a unit hydrograph study of the same area.
 Note: These figures do not consider reduced effective area
 effects caused by confluences in the rational equation.

Area averaged pervious area fraction(Ap) = 1.000
 Area averaged SCS curve number = 86.0

STREAM 6

Unit Hydrograph Analysis

Copyright (c) CIVILCADD/CIVILDESIGN, 1989 - 2004, Version 7.0

Study date 04/11/08

+++++

San Bernardino County Synthetic Unit Hydrology Method
Manual date - August 1986

MERRELL-JOHNSON ENGINEERING, INC.
12138 INDUSTRIAL BOULEVARD, SUITE 240
VICTORVILLE, CA 92395
(760) 241-6146 * FAX (760) 241-0566

ABENGOA SOLAR - HARPER LAKE - JOB NO. 3001
SOUTHERN TRIBUTARY AREA - STREAM 6
100-YEAR STORM EVENT - AMC II

Storm Event Year = 100

Antecedent Moisture Condition = 2

English (in-lb) Input Units Used

English Rainfall Data (Inches) Input Values Used

English Units used in output format

Area averaged rainfall intensity isohyetal data:

Sub-Area (Ac.)	Duration (hours)	Isohyetal (In)
Rainfall data for year 100		
12134.00	1	1.20

Rainfall data for year 100		
12134.00	6	1.80

Rainfall data for year 100		
12134.00	24	3.00

+++++

***** Area-averaged max loss rate, Fm *****

SCS curve No.(AMCII)	SCS curve NO.(AMC 2)	Area (Ac.)	Area Fraction	Fp(Fig C6) (In/Hr)	Ap (dec.)	Fm (In/Hr)
84.0	84.0	12134.00	1.000	0.301	1.000	0.301

Area-averaged adjusted loss rate Fm (In/Hr) = 0.301

***** Area-Averaged low loss rate fraction, Yb *****

Area (Ac.)	Area Fract	SCS CN (AMC2)	SCS CN (AMC2)	S	Pervious Yield Fr
12134.00	1.000	84.0	84.0	1.90	0.505

Area-averaged catchment yield fraction, Y = 0.505

Area-averaged low loss fraction, Yb = 0.495

+++++

Watercourse length = 72811.00(Ft.)

Length from concentration point to centroid = 37330.00(Ft.)

Elevation difference along watercourse = 834.00(Ft.)

Mannings friction factor along watercourse = 0.030

Watershed area = 12134.00(Ac.)

Catchment Lag time = 1.882 hours

Unit interval = 15.000 minutes

Unit interval percentage of lag time = 13.2830

Hydrograph baseflow = 0.00(CFS)

Average maximum watershed loss rate(Fm) = 0.301(In/Hr)

Average low loss rate fraction (Yb) = 0.495 (decimal)

DESERT S-Graph Selected

Computed peak 5-minute rainfall = 0.569(In)

Computed peak 30-minute rainfall = 0.975(In)

Specified peak 1-hour rainfall = 1.200(In)

Computed peak 3-hour rainfall = 1.539(In)

Specified peak 6-hour rainfall = 1.800(In)

Specified peak 24-hour rainfall = 3.000(In)

Rainfall depth area reduction factors:

Using a total area of 12134.00(Ac.) (Ref: fig. E-4)

5-minute factor = 0.633 Adjusted rainfall = 0.360(In)

30-minute factor = 0.651 Adjusted rainfall = 0.634(In)

1-hour factor = 0.655 Adjusted rainfall = 0.786(In)

3-hour factor = 0.934 Adjusted rainfall = 1.436(In)

6-hour factor = 0.968 Adjusted rainfall = 1.742(In)

24-hour factor = 0.981 Adjusted rainfall = 2.943(In)

U n i t H y d r o g r a p h

+++++

Interval Number	'S' Graph Mean values	Unit Hydrograph ((CFS))
--------------------	--------------------------	----------------------------

(K = 48915.19 (CFS))

1	0.586	286.789
2	2.355	865.020
3	5.254	1418.074
4	9.433	2044.332
5	16.977	3689.955
6	29.170	5964.589
7	40.762	5670.281
8	49.581	4313.729
9	56.457	3363.143
10	61.590	2511.098
11	65.681	2001.043
12	69.147	1695.575

13	72.193	1489.740
14	74.756	1253.473
15	77.057	1125.604
16	79.076	987.872
17	80.830	857.745
18	82.405	770.455
19	83.837	700.472
20	85.166	650.030
21	86.432	619.171
22	87.547	545.490
23	88.587	508.615
24	89.429	412.097
25	90.219	386.158
26	90.968	366.693
27	91.690	352.855
28	92.334	315.049
29	92.955	304.202
30	93.541	286.583
31	94.074	260.362
32	94.526	221.332
33	94.978	220.912
34	95.429	220.524
35	95.815	188.960
36	96.160	168.933
37	96.506	168.933
38	96.844	165.602
39	97.105	127.667
40	97.344	116.953
41	97.583	116.953
42	97.804	107.791
43	97.945	69.263
44	98.078	64.974
45	98.211	64.974
46	98.353	69.446
47	98.512	77.780
48	98.671	77.969
49	98.831	77.969
50	98.990	77.969
51	99.150	77.969
52	99.309	77.969
53	99.465	76.275
54	99.567	49.732
55	99.650	40.609
56	99.733	40.609
57	99.816	40.609
58	99.899	40.609
59	100.000	20.304

 Total soil rain loss = 1.29(In)
 Total effective rainfall = 1.65(In)
 Peak flow rate in flood hydrograph = 3992.15(CFS)

+++++
 24 - H O U R S T O R M
 R u n o f f H y d r o g r a p h

 Hydrograph in 15 Minute intervals ((CFS))

Time(h+m)	Volume	Ac.Ft	Q(CFS)	0	1000.0	2000.0	3000.0	4000.0
15+ 0	427.6061	716.20			Q V			
15+15	444.4990	817.61			Q V			
15+30	464.4250	964.42			Q V			
15+45	487.4277	1113.33			Q			
16+ 0	513.6390	1268.63			Q			
16+15	545.1968	1527.40			V Q			
16+30	583.5320	1855.42			V V Q			
16+45	627.9356	2149.13			V V Q	Q		
17+ 0	680.2053	2529.86			V V	Q		
17+15	747.6562	3264.62			V		Q	
17+30	830.1387	3992.15	Q ₁₀₀		V			Q
17+45	908.5916	3797.12			V		Q	
18+ 0	975.7287	3249.44				V V		
18+15	1033.2340	2783.26				V V Q		
18+30	1081.2698	2324.93				Q V		
18+45	1122.5407	1997.51				V V		
19+ 0	1159.1337	1771.10				Q		
19+15	1192.2404	1602.37				Q		
19+30	1222.3729	1458.41				Q		
19+45	1250.4554	1359.19				Q		
20+ 0	1276.4807	1259.63				Q		
20+15	1300.6171	1168.20				Q		
20+30	1323.2345	1094.68				Q		
20+45	1344.5412	1031.25				Q		
21+ 0	1364.7511	978.16				Q		
21+15	1384.0156	932.40				Q		
21+30	1402.1429	877.36				Q		
21+45	1419.3292	831.82				Q		
22+ 0	1435.3044	773.20				Q		
22+15	1450.5768	739.18				Q		
22+30	1465.2420	709.80				Q		
22+45	1479.3316	681.94				Q		
23+ 0	1492.7729	650.56				Q		
23+15	1505.7633	628.73				Q		
23+30	1518.2575	604.72				Q		
23+45	1530.1823	577.16				Q		
24+ 0	1541.5291	549.18				Q		

STREAM 7

San Bernardino County Rational Hydrology Program

(Hydrology Manual Date - August 1986)

CIVILCADD/CIVILDESIGN Engineering Software, (c) 1989-2004 Version 7.0
Rational Hydrology Study Date: 04/11/08

ABENGOA SOLAR - HARPER LAKE - JOB NO. 3001
SOUTHERN TRIBUTARY AREA - STREAM 7
NODE 71 - NODE 73
100-YEAR STORM EVENT - AMC II

MERRELL-JOHNSON ENGINEERING, INC.
12138 INDUSTRIAL BOULEVARD, SUITE 240
VICTORVILLE, CA 92395
(760) 241-6146 * FAX (760) 241-0566

***** Hydrology Study Control Information *****

Rational hydrology study storm event year is 100.0
Computed rainfall intensity:
Storm year = 100.00 1 hour rainfall = 1.200 (In.)
Slope used for rainfall intensity curve b = 0.7000
Soil antecedent moisture condition (AMC) = 2

+++++
Process from Point/Station 71.000 to Point/Station 72.000
**** INITIAL AREA EVALUATION ****

UNDEVELOPED (poor cover) subarea
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 1.000
Decimal fraction soil group D = 0.000
SCS curve number for soil(AMC 2) = 86.00
Pervious ratio(Ap) = 1.0000 Max loss rate(Fm)= 0.265(In/Hr)
Initial subarea data:
Initial area flow distance = 1000.000(Ft.)
Top (of initial area) elevation = 2100.000(Ft.)
Bottom (of initial area) elevation = 2092.000(Ft.)
Difference in elevation = 8.000(Ft.)
Slope = 0.00800 s(%)= 0.80
TC = k(0.525)*[(length^3)/(elevation change)]^0.2
Initial area time of concentration = 21.855 min.
Rainfall intensity = 2.433(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area (Q=KCIA) is C = 0.802
Subarea runoff = 8.782(CFS)
Total initial stream area = 4.500(Ac.)
Pervious area fraction = 1.000
Initial area Fm value = 0.265(In/Hr)

+++++
Process from Point/Station 72.000 to Point/Station 73.000
**** IRREGULAR CHANNEL FLOW TRAVEL TIME ****

Depth of flow = 0.653(Ft.), Average velocity = 2.059(Ft/s)
***** Irregular Channel Data *****

```

-----
Information entered for subchannel number 1 :
Point number      'X' coordinate      'Y' coordinate
      1              0.00              1.00
      2             10.00              0.00
      3             20.00              1.00
Manning's 'N' friction factor =    0.035

```

```

-----
Sub-Channel flow =      8.782(CFS)
'      '      flow top width =     13.061(Ft.)
'      '      velocity=      2.059(Ft/s)
'      '      area =         4.265(Sq.Ft)
'      '      Froude number =      0.635

```

```

Upstream point elevation = 2092.000(Ft.)
Downstream point elevation = 2060.000(Ft.)
Flow length = 3039.000(Ft.)
Travel time = 24.60 min.
Time of concentration = 46.45 min.
Depth of flow = 0.653(Ft.)
Average velocity = 2.059(Ft/s)
Total irregular channel flow = 8.782(CFS)
Irregular channel normal depth above invert elev. = 0.653(Ft.)
Average velocity of channel(s) = 2.059(Ft/s)

```

```

*****
Process from Point/Station      72.000 to Point/Station      73.000
**** SUBAREA FLOW ADDITION ****

```

```

-----
UNDEVELOPED (poor cover) subarea
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 1.000
Decimal fraction soil group D = 0.000
SCS curve number for soil(AMC 2) = 86.00
Pervious ratio(Ap) = 1.0000      Max loss rate(Fm)=      0.265(In/Hr)
Time of concentration =      46.45 min. Tc
Rainfall intensity =      1.435(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area,(total area with modified
rational method)(Q=KCIA) is C = 0.734
Subarea runoff =      48.201(CFS) for 49.600(Ac.)
Total runoff =      56.983(CFS) Q100
Effective area this stream =      54.10(Ac.)
Total Study Area (Main Stream No. 1) =      54.10(Ac.)
Area averaged Fm value =      0.265(In/Hr)
End of computations, Total Study Area =      54.10 (Ac.)
The following figures may
be used for a unit hydrograph study of the same area.
Note: These figures do not consider reduced effective area
effects caused by confluences in the rational equation.

```

```

Area averaged pervious area fraction(Ap) = 1.000
Area averaged SCS curve number = 86.0

```

STREAM 10

San Bernardino County Rational Hydrology Program

(Hydrology Manual Date - August 1986)

CIVILCADD/CIVILDESIGN Engineering Software, (c) 1989-2004 Version 7.0
Rational Hydrology Study Date: 11/18/08

ABENGOA SOLAR - HARPER LAKE - JOB NO. 3001
NORTHWEST TRIBUTARY AREA - STREAM 10
NODE 11 - NODE 15
100-YEAR STORM EVENT - AMC II

MERRELL-JOHNSON ENGINEERING, INC.
12138 INDUSTRIAL BOULEVARD, SUITE 240
VICTORVILLE, CA 92395
(760) 241-6146 * FAX (760) 241-0566

***** Hydrology Study Control Information *****

Rational hydrology study storm event year is 100.0
Computed rainfall intensity:
Storm year = 100.00 1 hour rainfall = 1.200 (In.)
Slope used for rainfall intensity curve b = 0.7000
Soil antecedent moisture condition (AMC) = 2

Process from Point/Station 11.000 to Point/Station 12.000
**** INITIAL AREA EVALUATION ****

UNDEVELOPED (poor cover) subarea
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 1.000
Decimal fraction soil group D = 0.000
SCS curve number for soil(AMC 2) = 86.00
Pervious ratio(Ap) = 1.0000 Max loss rate(Fm)= 0.265(In/Hr)
Initial subarea data:
Initial area flow distance = 986.000(Ft.)
Top (of initial area) elevation = 2202.000(Ft.)
Bottom (of initial area) elevation = 2177.000(Ft.)
Difference in elevation = 25.000(Ft.)
Slope = 0.02535 s(%)= 2.54
TC = $k(0.525)*[(length^3)/(elevation\ change)]^{0.2}$
Initial area time of concentration = 17.254 min.
Rainfall intensity = 2.871(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area (Q=KCIA) is C = 0.817
Subarea runoff = 23.455(CFS)
Total initial stream area = 10.000(Ac.)
Pervious area fraction = 1.000
Initial area Fm value = 0.265(In/Hr)

Process from Point/Station 12.000 to Point/Station 13.000
**** IRREGULAR CHANNEL FLOW TRAVEL TIME ****

Depth of flow = 0.814(Ft.), Average velocity = 3.176(Ft/s)

***** Irregular Channel Data *****

Information entered for subchannel number 1 :

Point number	'X' coordinate	'Y' coordinate
1	0.00	1.00
2	5.00	0.00
3	10.00	0.00
4	15.00	1.00

Manning's 'N' friction factor = 0.035

Sub-Channel flow = 23.455(CFS)
' ' flow top width = 13.141(Ft.)
' ' velocity= 3.176(Ft/s)
' ' area = 7.384(Sq.Ft)
' ' Froude number = 0.747

Upstream point elevation = 2177.000(Ft.)
Downstream point elevation = 2150.000(Ft.)
Flow length = 2201.000(Ft.)
Travel time = 11.55 min.
Time of concentration = 28.80 min.
Depth of flow = 0.814(Ft.)
Average velocity = 3.176(Ft/s)
Total irregular channel flow = 23.455(CFS)
Irregular channel normal depth above invert elev. = 0.814(Ft.)
Average velocity of channel(s) = 3.176(Ft/s)

Process from Point/Station 12.000 to Point/Station 13.000
**** SUBAREA FLOW ADDITION ****

UNDEVELOPED (poor cover) subarea
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 1.000
Decimal fraction soil group D = 0.000
SCS curve number for soil(AMC 2) = 86.00
Pervious ratio(Ap) = 1.0000 Max loss rate(Fm)= 0.265(In/Hr)
Time of concentration = 28.80 min.
Rainfall intensity = 2.006(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area,(total area with modified rational method)(Q=KCIA) is C = 0.781
Subarea runoff = 55.188(CFS) for 40.200(Ac.)
Total runoff = 78.642(CFS)
Effective area this stream = 50.20(Ac.)
Total Study Area (Main Stream No. 1) = 50.20(Ac.)
Area averaged Fm value = 0.265(In/Hr)

Process from Point/Station 13.000 to Point/Station 14.000
**** IRREGULAR CHANNEL FLOW TRAVEL TIME ****

Depth of flow = 1.270(Ft.), Average velocity = 3.787(Ft/s)
***** Irregular Channel Data *****

Information entered for subchannel number 1 :

Point number	'X' coordinate	'Y' coordinate
1	0.00	2.00

2	10.00	0.00
3	20.00	0.00
4	30.00	2.00

Manning's 'N' friction factor = 0.035

 Sub-Channel flow = 78.642(CFS)
 ' ' flow top width = 22.700(Ft.)
 ' ' velocity= 3.787(Ft/s)
 ' ' area = 20.765(Sq.Ft)
 ' ' Froude number = 0.698

Upstream point elevation = 2150.000(Ft.)
 Downstream point elevation = 2120.000(Ft.)
 Flow length = 3299.000(Ft.)
 Travel time = 14.52 min.
 Time of concentration = 43.32 min.
 Depth of flow = 1.270(Ft.)
 Average velocity = 3.787(Ft/s)
 Total irregular channel flow = 78.642(CFS)
 Irregular channel normal depth above invert elev. = 1.270(Ft.)
 Average velocity of channel(s) = 3.787(Ft/s)

+++++
 Process from Point/Station 13.000 to Point/Station 14.000
 **** SUBAREA FLOW ADDITION ****

 UNDEVELOPED (poor cover) subarea
 Decimal fraction soil group A = 0.000
 Decimal fraction soil group B = 0.000
 Decimal fraction soil group C = 1.000
 Decimal fraction soil group D = 0.000
 SCS curve number for soil(AMC 2) = 86.00
 Pervious ratio(Ap) = 1.0000 Max loss rate(Fm)= 0.265(In/Hr)
 Time of concentration = 43.32 min.
 Rainfall intensity = 1.507(In/Hr) for a 100.0 year storm
 Effective runoff coefficient used for area,(total area with modified
 rational method)(Q=KCIA) is C = 0.742
 Subarea runoff = 174.242(CFS) for 176.000(Ac.)
 Total runoff = 252.885(CFS)
 Effective area this stream = 226.20(Ac.)
 Total Study Area (Main Stream No. 1) = 226.20(Ac.)
 Area averaged Fm value = 0.265(In/Hr)

+++++
 Process from Point/Station 14.000 to Point/Station 15.000
 **** IRREGULAR CHANNEL FLOW TRAVEL TIME ****

 Depth of flow = 1.490(Ft.), Average velocity = 4.531(Ft/s)
 ***** Irregular Channel Data *****

 Information entered for subchannel number 1 :

Point number	'X' coordinate	'Y' coordinate
1	0.00	4.00
2	20.00	0.00
3	50.00	0.00
4	70.00	4.00

 Manning's 'N' friction factor = 0.035

Sub-Channel flow = 252.885(CFS)
' ' flow top width = 44.902(Ft.)
' ' velocity= 4.531(Ft/s)
' ' area = 55.811(Sq.Ft)
' ' Froude number = 0.716

Upstream point elevation = 2120.000(Ft.)
Downstream point elevation = 2085.000(Ft.)
Flow length = 4071.000(Ft.)
Travel time = 14.97 min.
Time of concentration = 58.30 min.
Depth of flow = 1.490(Ft.)
Average velocity = 4.531(Ft/s)
Total irregular channel flow = 252.885(CFS)
Irregular channel normal depth above invert elev. = 1.490(Ft.)
Average velocity of channel(s) = 4.531(Ft/s)



+++++
Process from Point/Station 14.000 to Point/Station 15.000
**** SUBAREA FLOW ADDITION ****

UNDEVELOPED (poor cover) subarea
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 1.000
Decimal fraction soil group D = 0.000
SCS curve number for soil(AMC 2) = 86.00
Pervious ratio(Ap) = 1.0000 Max loss rate(Fm)= 0.265(In/Hr)
Time of concentration = 58.30 min. Tc
Rainfall intensity = 1.224(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area,(total area with modified
rational method)(Q=KCIA) is C = 0.705
Subarea runoff = 204.728(CFS) for 303.800(Ac.)
Total runoff = 457.612(CFS) Q₁₀₀
Effective area this stream = 530.00(Ac.)
Total Study Area (Main Stream No. 1) = 530.00(Ac.)
Area averaged Fm value = 0.265(In/Hr)
End of computations, Total Study Area = 530.00 (Ac.)
The following figures may
be used for a unit hydrograph study of the same area.
Note: These figures do not consider reduced effective area
effects caused by confluences in the rational equation.

Area averaged pervious area fraction(Ap) = 1.000
Area averaged SCS curve number = 86.0


EXHIBITS

SOILS MAP



INDEX MAP

SAN BERNARDINO COUNTY **HYDROLOGY MANUAL** **HYDROLOGIC SOILS GROUP MAP** **FOR** **SOUTHCENTRAL AREA**



ISOHYETAL MAP

Topographic map of San Bernardino County, California, showing the Project Site and Valley Area. The map includes a grid with coordinates (T 25 S to T 1 S, R 8 W to R 1 W) and labels for various locations such as TROHA, HINKLE, BARSTOW, LENWOOD, AGOETT, MT. AFTON, LUDLOW, VICTORVILLE, APPLE VALLEY, and LUCERNE VALLEY. The Project Site is marked with a circle and the text "PROJECT SITE". The Valley Area is marked with a circle and the text "SEE VALLEY AREA". The map also shows contour lines and a scale bar.

HYDROLOGY MANUAL

APPROVED BY <u>[Signature]</u>			
FLOOD CONTROL ENGINEER			
DATE	SCALE	FILE NO.	BOOK NO.

UNIT HYDROGRAPH DATA SHEETS

PROJECT: ABENGOA SOLAR DATE: 12 APRIL 2008
STREAM 2
 ENGINEER: MARK ROWAN

1. Enter the design storm return frequency (years) 100
2. Enter catchment lag (hours) 24
3. Enter the catchment area (acres) 1,133
4. Enter baseflow (cfs/square mile) Ø
5. Enter S-Graph proportions (decimal)

Valley: Developed	<u> </u>
Foothill	<u> </u>
Mountain	<u> </u>
Valley: Undeveloped	<u> </u>
Desert	<u>1.0</u>
6. Enter maximum loss rate, F_m (inch/hour) AMC II 0.31
7. Enter low loss fraction, \bar{Y} (decimal) 0.49
8. Enter watershed area-averaged 5-minute point rainfall (inches)* 0.58
- Enter watershed area-averaged 30-minute point rainfall (inches)* 0.98
- Enter watershed area-averaged 1-hour point rainfall (inches)* 1.2
- Enter watershed area-averaged 3-hour point rainfall (inches)* 1.6
- Enter watershed area-averaged 6-hour point rainfall (inches)* 1.8
- Enter watershed area-averaged 24-hour point rainfall (inches)* 3.0
9. Enter 24-hour storm unit interval (minutes) 5

*Note: enter values unadjusted by depth-area factors

PROJECT: ABENGOA SOLAR DATE: 12 APRIL 2008
STREAM 4
ENGINEER: MARK ROWAN

1. Enter the design storm return frequency (years) 100
2. Enter catchment lag (hours) 24
3. Enter the catchment area (acres) 3,520
4. Enter baseflow (cfs/square mile) 0
5. Enter S-Graph proportions (decimal)
Valley: Developed _____
Foothill _____
Mountain _____
Valley: Undeveloped _____
Desert 1.0
6. Enter maximum loss rate, F_m (inch/hour) AMC II 0.31
7. Enter low loss fraction, \bar{Y} (decimal) 0.49
8. Enter watershed area-averaged 5-minute point rainfall (inches)* 0.58
Enter watershed area-averaged 30-minute point rainfall (inches)* 0.98
Enter watershed area-averaged 1-hour point rainfall (inches)* 1.2
Enter watershed area-averaged 3-hour point rainfall (inches)* 1.6
Enter watershed area-averaged 6-hour point rainfall (inches)* 1.8
Enter watershed area-averaged 24-hour point rainfall (inches)* 3.0
9. Enter 24-hour storm unit interval (minutes) 15

*Note: enter values unadjusted by depth-area factors

PROJECT: ABENGOA SOLAR DATE: 12 APRIL 2008
STREAM 6
ENGINEER: MARK ROWAN

1. Enter the design storm return frequency (years) 100
2. Enter catchment lag (hours) 24
3. Enter the catchment area (acres) 12,134
4. Enter baseflow (cfs/square mile) Ø
5. Enter S-Graph proportions (decimal)
Valley: Developed _____
Foothill _____
Mountain _____
Valley: Undeveloped _____
Desert 1.0
6. Enter maximum loss rate, F_m (inch/hour) AMC II 0.31
7. Enter low loss fraction, \bar{Y} (decimal) 0.49
8. Enter watershed area-averaged 5-minute point rainfall (inches)* 0.58
Enter watershed area-averaged 30-minute point rainfall (inches)* 0.98
Enter watershed area-averaged 1-hour point rainfall (inches)* 1.2
Enter watershed area-averaged 3-hour point rainfall (inches)* 1.6
Enter watershed area-averaged 6-hour point rainfall (inches)* 1.8
Enter watershed area-averaged 24-hour point rainfall (inches)* 3.0
9. Enter 24-hour storm unit interval (minutes) 15

*Note: enter values unadjusted by depth-area factors


Curve (1) Numbers of Hydrologic Soil-Cover Complexes For Pervious Areas-AMC II

Cover Type (3)	Quality of Cover (2)	Soil Group			
		A	B	C	D
<u>NATURAL COVERS -</u>					
Barren (Rockland, eroded and graded land)		78	86	91	93
Chaparral, Broadleaf (Manzonita, ceanothus and scrub oak)	Poor	53	70	80	85
	Fair	40	63	75	81
	Good	31	57	71	78
Chaparral, Narrowleaf (Chamise and redshank)	Poor	71	82	88	91
	Fair	55	72	81	86
Grass, Annual or Perennial	Poor	67	78	86	89
	Fair	50	69	79	84
	Good	38	61	74	80
Meadows or Cienegas (Areas with seasonally high water table, principal vegetation is sod forming grass)	Poor	63	77	85	88
	Fair	51	70	80	84
	Good	30	58	71	78
Open Brush (Soft wood shrubs - buckwheat, sage, etc.)	Poor	62	76	84	88
	Fair	46	66	77	83
	Good	41	63	75	81
Woodland (Coniferous or broadleaf trees predominate. Canopy density is at least 50 percent.)	Poor	45	66	77	83
	Fair	36	60	73	79
	Good	25	55	70	77
Woodland, Grass (Coniferous or broadleaf trees with canopy density from 20 to 50 percent)	Poor	57	73	82	86
	Fair	44	65	77	82
	Good	33	58	72	79
<u>URBAN COVERS -</u>					
Residential or Commercial Landscaping (Lawn, shrubs, etc.)	Good	32	56	69	75
Turf (Irrigated and mowed grass)	Poor	58	74	83	87
	Fair	44	65	77	82
	Good	33	58	72	79
<u>AGRICULTURAL COVERS -</u>					
Fallow (Land plowed but not tilled or seeded)		77	86	91	94

SAN BERNARDINO COUNTY


HYDROLOGY MANUAL

**CURVE NUMBERS
FOR
PERVIOUS AREAS**




SAN BERNARDINO COUNTY
HYDROLOGY MANUAL

INFILTRATION RATE FOR
PERVIOUS AREAS VERSUS
SCS CURVE NUMBERS



SAN BERNARDINO COUNTY
 HYDROLOGY MANUAL

**INTENSITY - DURATION
 CURVES
 CALCULATION SHEET**





PROJECT LOCATION HARPER LAKE

NOTES STREAMS 2, 4, AND 6

SAN BERNARDINO COUNTY
HYDROLOGY MANUAL

AREA - AVERAGED
MASS RAINFALL
PLOTING SHEET






SAN BERNARDINO COUNTY

HYDROLOGY MANUAL

SAN BERNARDINO COUNTY FLOOD CONTROL DISTRICT			
DESERT AREA			
SCHUYTALS			
X-100 YEAR 6 HOUR			
BASED ON U.S.D.C. NOAA ATLAS 2, ET			
APPROVED BY <i>[Signature]</i>			
FLOOD CONTROL ENGINEER			
DATE	SCALE	FILE NO.	DRAWN
1982	1" = 5.0M	WFO-1	11"



SAN BERNARDINO COUNTY **HYDROLOGY MANUAL**

SAN BERNARDINO COUNTY
FLOOD CONTROL DISTRICT

DESERT AREA

ISOHYETALS
X₄ - 100 YEAR 24 HOUR
BASED ON U.S.D.C. NO. AA. ATLAS-2, 1973

APPROVED BY *B. D. Lopez*
FLOOD CONTROL ENGINEER


DATE 1982	SCALE 1" = 6 MI.	FILE NO. WRG-1	DRAWG. NO. 12 of 12
--------------	---------------------	-------------------	------------------------




SAN BERNARDINO COUNTY

HYDROLOGY MANUAL

HYDROLOGIC SOILS GROUP MAP FOR SOUTHCENTRAL AREA



INDEX MAP



\bar{n} = 0.015

1. Drainage area has fairly uniform, gentle slopes
2. Most watercourses either improved or along paved streets
3. Groundcover consists of some grasses - large % of area impervious
4. Main water course improved channel or conduit

\bar{n} = 0.020

1. Drainage area has some graded and non-uniform, gentle slopes
2. Over half of the area watercourses are improved or paved streets
3. Groundcover consists of equal amount of grasses and impervious area
4. Main watercourse is partly improved channel or conduit and partly greenbelt (see $n = 0.025$)

\bar{n} = 0.025

1. Drainage area is generally rolling with gentle side slopes
2. Some drainage improvements in the area - streets and canals
3. Groundcover consists mostly of scattered brush and grass and small % impervious
4. Main watercourse is straight channels which are turfed or with stony beds and weeds on earth bank (greenbelt type)



\bar{n} = 0.030

1. Drainage area is generally rolling with rounded ridges and moderate side slopes
2. No drainage improvements exist in the area
3. Groundcover includes scattered brush and grasses
4. Watercourses meander in fairly straight, unimproved channels with some boulders and lodged debris

\bar{n} = 0.040

1. Drainage area is composed of steep upper canyons with moderate slopes in lower canyons
2. No drainage improvements exist in the area
3. Groundcover is mixed brush and trees with grasses in lower canyons
4. Watercourses have moderate bends and are moderately impeded by boulders and debris with meandering courses

\bar{n} = 0.050

1. Drainage area is quite rugged with sharp ridges and steep canyons
2. No drainage improvements exist in the area
3. Groundcover, excluding small areas of rock outcrops, includes many trees and considerable underbrush
4. Watercourses meander around sharp bends, over large boulders and considerable debris obstruction

\bar{n} = 0.200

1. Drainage area has comparatively uniform slopes
2. No drainage improvements exist in the area
3. Groundcover consists of cultivated crops or substantial growths of grass and fairly dense small shrubs, cacti, or similar vegetation
4. Surface characteristics are such that channelization does not occur

SAN BERNARDINO COUNTY

HYDROLOGY MANUAL

**BASIN FACTOR
DESCRIPTIONS**

Merrell-Johnson Engineering, Inc.
12138 Industrial Boulevard, Suite 240
Victorville, CA 92392
(760) 241-6146 Fax: (760) 241-0566

Date: Page of

Project Name:
Job No:

CALCULATION OF LOW LOSS FRACTION, \bar{Y}

$$\begin{aligned} S &= (1000 / CN) - 10 \\ &= (1000 / 84) - 10 \\ &= \underline{11.90 - 10} \end{aligned}$$

CN = 84 OPEN BRUSH
"POOR COVER"

$$\underline{\underline{S = 1.90}}$$

$$Y = \frac{(P_{24} - 0.2S)^2}{(P_{24} + 0.8S)P_{24}}$$

$$= \frac{(3.0 - 0.2(1.9))^2}{(3.0 + 0.8(1.9))3.0}$$

$$= \frac{(2.62)^2}{(4.52)3.0}$$

$$= \frac{6.8644}{13.56}$$

$$\underline{\underline{Y = 0.51}}$$

$$\bar{Y} = 1 - Y$$

$$= 1 - 0.51$$

$$\underline{\underline{\bar{Y} = 0.49}}$$

SECTION 4

STORM DRAIN CAPACITY CALCULATIONS

CHANNEL CALCULATIONS

ABENGOA SOLAR
Q100 FLOW = 14,788 CUBIC FEET PER SECOND
CHANNEL A1 @ 0.7%

d	5.98	
M	2.00	
m	3	
b	180	
A	1166.22081	
Rn	5.35372596	
n	0.03	Dirt Lined Channel
S	0.007	Minimum Channel Slope
V	12.6828639	
Q	14791.0198	
desired Q	14788	Q 100 Standard Flood Flow
delta	3.01983951	

5.98	d	Flow depth
2 ; 3	m	Side slope (run) as in rise over run w/ rise =1
180	b	base width
	A	Cross sectional area
0.03	n	manning coef.
0.70%	S	Channel Slope

Right-of-Way Calculations

Flow Depth =	5.98	FT
Velocity =	12.68	FtPS
Bulk Depth =	8.97	FT
Free Board =	3	FT
Total Depth =	11.97	FT
Dike Width =	18	FT
Bottom Width =	180	FT

R/W=2[5' + 2(Freeboard) + Dike] + 2(d Total) + 3(d Total) + Bottom Width

R/W = 298 FT

ABENGOA SOLAR
Q100 FLOW = 14,788 CUBIC FEET PER SECOND
CHANNEL A2 @ 0.4%

d	5.96	
M	2.00	
m	3	
b	240	
A	1520.013	
Rn	5.473318	
n	0.03	Dirt Lined Channel
S	0.004	Minimum Channel Slope
V	9.729593	
Q	14789.11	
desired Q	14788	Q 100 Standard Flood Flow
delta	1.112466	

5.96	d	Flow depth
2 ; 3	m	Side slope (run) as in rise over run w/ rise =1
240	b	base width
	A	Cross sectional area
0.03	n	manning coef.
0.40%	S	Channel Slope

Right-of-Way Calculations

Flow Depth =	5.96	FT
Velocity =	9.73	FtPS
Bulk Depth =	8.94	FT
Free Board =	3	FT
Total Depth =	11.94	FT
Dike Width =	18	FT
Bottom Width =	240	FT

$R/W = 2[5' + 2(\text{Freeboard}) + \text{Dike}] + 2(d \text{ Total}) + 3(d \text{ Total}) + \text{Bottom Width}$

R/W = 358 FT

ABENGOA SOLAR
Q100 FLOW = 21,232 CUBIC FEET PER SECOND
CHANNEL A3 @ 0.7%

d	5.97	
M	2.00	
m	3	
b	260	
A	1641.882	
Rn	5.513922	
n	0.03	Dirt Lined Channel
S	0.007	Minimum Channel Slope
V	12.93462	
Q	21237.12	
desired Q	21232	Q 100 Standard Flood Flow
delta	5.118728	

5.97	d	Flow depth
2 ; 3	m	Side slope (run) as in rise over run w/ rise =1
260	b	base width
	A	Cross sectional area
0.03	n	manning coef.
0.70%	S	Channel Slope

Right-of-Way Calculations

Flow Depth =	5.97	FT
Velocity =	12.93	FtPS
Bulk Depth =	8.96	FT
Free Board =	3	FT
Total Depth =	11.96	FT
Dike Width =	18	FT
Bottom Width =	260	FT

$R/W = 2[5' + 2(\text{Freeboard}) + \text{Dike}] + 2(d \text{ Total}) + 3(d \text{ Total}) + \text{Bottom Width}$

R/W = 378 FT

ABENGOA SOLAR
Q100 FLOW = 4,282 CUBIC FEET PER SECOND
CHANNEL B

d	4.56	
M	2.00	
m	3	
b	90	
A	462.7224	
Rn	3.893038	
n	0.03	Dirt Lined Channel
S	0.0057	Minimum Channel Slope
V	9.254666	
Q	4282.342	
desired Q	4282	Q 100 Standard Flood Flow
delta	0.3416	

4.56	d	Flow depth
2 ; 3	m	Side slope (run) as in rise over run w/ rise =1
90	b	base width
	A	Cross sectional area
0.03	n	manning coef.
0.57%	S	Channel Slope

Right-of-Way Calculations

Flow Depth =	4.56	FT
Velocity =	9.25	FtPS
Bulk Depth =	6.84	FT
Free Board =	3	FT
Total Depth =	9.84	FT
Dike Width =	18	FT
Bottom Width =	90	FT

$R/W = 2[5' + 2(\text{Freeboard}) + \text{Dike}] + 2(d \text{ Total}) + 3(d \text{ Total}) + \text{Bottom Width}$

R/W = 197 FT

ABENGOA SOLAR
Q100 FLOW = 2,162 CUBIC FEET PER SECOND
CHANNEL C

d	4.20	
M	2.00	
m	3	
b	55	
A	274.7201	
Rn	3.369496	
n	0.03	Dirt Lined Channel
S	0.005	Minimum Channel Slope
V	7.872134	
Q	2162.633	
desired Q	2162	Q 100 Standard Flood Flow
delta	0.633182	

4.2	d	Flow depth
2 ; 3	m	Side slope (run) as in rise over run w/ rise =1
55	b	base width
	A	Cross sectional area
0.03	n	manning coef.
0.50%	S	Channel Slope

Right-of-Way Calculations

Flow Depth =	4.20	FT
Velocity =	7.87	FtPS
Bulk Depth =	6.29	FT
Free Board =	2	FT
Total Depth =	8.29	FT
Dike Width =	18	FT
Bottom Width =	55	FT

$R/W = 2[5' + 2(\text{Freeboard}) + \text{Dike}] + 2(d \text{ Total}) + 3(d \text{ Total}) + \text{Bottom Width}$

R/W = 150 FT

ABENGOA SOLAR
Q100 FLOW = 6,444 CUBIC FEET PER SECOND
CHANNEL D

d	4.97	
M	2.00	
m	3	
b	90	
A	508.4781	
Rn	4.188403	
n	0.03	Dirt Lined Channel
S	0.0097	Minimum Channel Slope
V	12.676	
Q	6445.47	
desired Q	6444	Q 100 Standard Flood Flow
delta	1.470406	

4.97	d	Flow depth
2 ; 3	m	Side slope (run) as in rise over run w/ rise =1
90	b	base width
	A	Cross sectional area
0.03	n	manning coef.
0.97%	S	Channel Slope

Right-of-Way Calculations

Flow Depth =	4.97	FT
Velocity =	12.68	FtPS
Bulk Depth =	7.45	FT
Free Board =	3	FT
Total Depth =	10.45	FT
Dike Width =	18	FT
Bottom Width =	90	FT

$R/W = 2[5' + 2(\text{Freeboard}) + \text{Dike}] + 2(d \text{ Total}) + 3(d \text{ Total}) + \text{Bottom Width}$

R/W = 200 FT

ABENGOA SOLAR
Q100 FLOW = 1,477 CUBIC FEET PER SECOND
CHANNEL E

d	4.06	
M	2.00	
m	3.00	
b	65	
A	304.8531	
Rn	3.362645	
n	0.03	Dirt Lined Channel
S	0.0019	Minimum Channel Slope
V	4.84613	
Q	1477.358	
desired Q	1477	Q 100 Standard Flood Flow
delta	0.357869	

4.06	d	Flow depth
2 ; 3	m	Side slope (run) as in rise over run w/ rise =1
100	b	base width
	A	Cross sectional area
0.03	n	manning coef.
0.19%	S	Channel Slope

Right-of-Way Calculations

Flow Depth =	4.06	FT
Velocity =	4.85	FtPS
Bulk Depth =	4.06	FT
Free Board =	2	FT
Total Depth =	6.06	FT
Dike Width =	18	FT
Bottom Width =	65	FT

$R/W = 2[5' + 2(\text{Freeboard}) + \text{Dike}] + 2(d \text{ Total}) + 3(d \text{ Total}) + \text{Bottom Width}$

R/W = 149 FT

ABENGOA SOLAR
Q100 FLOW = 458 CUBIC FEET PER SECOND
CHANNEL F

d	2.74	
M	2.00	
m	2.00	
b	20	
A	69.8152	
Rn	2.164567	
n	0.03	Dirt Lined Channel
S	0.0063	Minimum Channel Slope
V	6.578828	
Q	459.3022	
desired Q	458	Q 100 Standard Flood Flow
delta	1.302213	

2.74	d	Flow depth
2 ; 2	m	Side slope (run) as in rise over run w/ rise =1
20	b	base width
	A	Cross sectional area
0.03	n	manning coef.
0.63%	S	Channel Slope

Right-of-Way Calculations

Flow Depth =	2.74	FT
Velocity =	6.58	FtPS
Bulk Depth =	4.11	FT
Free Board =	2	FT
Total Depth =	6.11	FT
Dike Width =	15	FT
Bottom Width =	20	FT

$R/W = 2[5' + 2(\text{Freeboard}) + \text{Dike}] + 2(d \text{ Total}) + 3(d \text{ Total}) + \text{Bottom Width}$

R/W = 92 FT

ROADWAY CROSSING CALCULATIONS

ALL-WEATHER CROSSING – HARPER LAKE ROAD

HY-8 Culvert Analysis Report

Table 1 - Summary of Culvert Flows at Crossing: Harper Lake Road

Headwater Elevation (ft)	Total Discharge (cfs)	Culvert 1 Discharge (cfs)	Roadway Discharge (cfs)	Iterations
2053.18	0.00	0.00	0.00	1
2055.76	2218.20	2218.20	0.00	1
2057.25	4436.40	4436.40	0.00	1
2058.46	6654.60	6654.60	0.00	1
2059.48	8872.80	8872.80	0.00	1
2060.51	11091.00	11091.00	0.00	1
2061.51	13309.20	13309.20	0.00	1
2062.17	14788.00	14788.00	0.00	1
2063.49	17745.60	17745.60	0.00	1
2064.89	19963.80	19963.80	0.00	1
2066.31	22182.00	22058.90	121.71	5

Rating Curve Plot for Crossing: Harper Lake Road

Total Rating Curve
Crossing: Harper Lake Road





Table 2 - Culvert Summary Table: Culvert 1

Total Discharge (cfs)	Culvert Discharge (cfs)	Headwater Elevation (ft)	Inlet Control Depth (ft)	Outlet Control Depth (ft)	Flow Type	Normal Depth (ft)	Critical Depth (ft)	Outlet Depth (ft)	Tailwater Depth (ft)	Outlet Velocity (ft/s)	Tailwater Velocity (ft/s)
0.00	0.00	2053.18	0.000	0.000	0-NF	0.000	0.000	0.000	0.000	0.000	0.000
2218.20	2218.20	2055.76	2.579	2.579	1-S2n	0.975	1.403	1.112	1.615	8.865	5.646
4436.40	4436.40	2057.25	4.066	4.066	1-S2n	1.463	2.273	1.823	2.447	10.820	7.403
6654.60	6654.60	2058.46	5.275	5.275	1-S2n	1.937	3.006	2.441	3.118	12.126	8.667
8872.80	8872.80	2059.48	6.300	6.300	1-S2n	2.310	3.615	2.997	3.704	13.173	9.683
11091.00	11091.00	2060.51	7.325	7.325	1-S2n	2.667	4.195	3.515	4.232	14.052	10.549
13309.20	13309.20	2061.51	8.331	8.331	1-S2n	3.020	4.726	3.986	4.718	14.879	11.309
14788.00	14788.00	2062.17	8.990	8.990	1-S2n	3.223	5.072	4.307	5.025	15.338	11.770
17745.60	17745.60	2063.49	10.308	10.308	5-S2n	3.629	5.703	4.892	5.602	16.266	12.611
19963.80	19963.80	2064.89	11.709	11.709	5-S2n	3.934	6.155	5.321	6.008	16.892	13.184
22182.00	22058.90	2066.31	13.126	13.126	5-S2n	4.206	6.551	5.694	6.398	17.508	13.715

Inlet Elevation (invert): 2053.18 ft, Outlet Elevation (invert): 2052.82 ft

Culvert Length: 50.00 ft, Culvert Slope: 0.0072


Culvert Performance Curve Plot: Culvert 1



Water Surface Profile Plot for Culvert: Culvert 1

Crossing - Harper Lake Road, Design Discharge - 14788.0 cfs

Culvert - Culvert 1, Culvert Discharge - 14788.0 cfs



Site Data - Culvert 1

Site Data Option: Culvert Invert Data

Inlet Station: 100.00 ft

Inlet Elevation: 2053.18 ft

Outlet Station: 150.00 ft

Outlet Elevation: 2052.82 ft

Number of Barrels: 7

Culvert Data Summary - Culvert 1

Barrel Shape: Arch-Box, Concrete

Barrel Span: 32.00 ft

Barrel Rise: 10.00 ft

Barrel Material: Concrete

Barrel Manning's n: 0.0120 (top and sides)

Manning's n: 1.4lf (bottom)

Inlet Type: Conventional

Inlet Edge Condition: Mitered to Conform to Slope

Inlet Depression: None

Table 3 - Downstream Channel Rating Curve (Crossing: Harper Lake Road)

Flow (cfs)	Water Surface Elev (ft)	Depth (ft)	Velocity (ft/s)	Shear (psf)	Froude Number
0.00	2053.18	0.00	0.00	0.00	0.00
2218.20	2054.80	1.62	5.65	0.71	0.79
4436.40	2055.63	2.45	7.40	1.07	0.84
6654.60	2056.30	3.12	8.67	1.36	0.88
8872.80	2056.88	3.70	9.68	1.62	0.90
11091.00	2057.41	4.23	10.55	1.85	0.92
13309.20	2057.90	4.72	11.31	2.06	0.93
14788.00	2058.20	5.02	11.77	2.19	0.94
17745.60	2058.78	5.60	12.61	2.45	0.96
19963.80	2059.19	6.01	13.18	2.62	0.97
22182.00	2059.58	6.40	13.71	2.79	0.98

Tailwater Channel Data - Harper Lake Road

Tailwater Channel Option: Trapezoidal Channel

Bottom Width: 240.00 ft

Side Slope (H:V): 2.00 (1:1)

Channel Slope: 0.0070

Channel Manning's n: 0.0300

Channel Invert Elevation: 2053.18 ft

Roadway Data for Crossing: Harper Lake Road

Roadway Profile Shape: Constant Roadway Elevation

Crest Length: 240.00 ft

Crest Elevation: 2066.00 ft

Roadway Surface: Paved

Roadway Top Width: 44.00 ft

ALL-WEATHER CROSSING – LOCKHART ROAD

HY-8 Culvert Analysis Report

Table 1 - Summary of Culvert Flows at Crossing: Lockhart Road

Headwater Elevation (ft)	Total Discharge (cfs)	Culvert 1 Discharge (cfs)	Roadway Discharge (cfs)	Iterations
2035.25	0.00	0.00	0.00	1
2038.03	966.60	966.60	0.00	1
2039.65	1933.20	1933.20	0.00	1
2040.91	2899.80	2899.80	0.00	1
2042.06	3866.40	3866.40	0.00	1
2043.21	4833.00	4833.00	0.00	1
2044.32	5799.60	5799.60	0.00	1
2045.06	6444.00	6444.00	0.00	1
2046.95	7732.80	7732.80	0.00	1
2048.64	8699.40	8699.40	0.00	1
2050.38	9666.00	9666.00	0.00	1

Rating Curve Plot for Crossing: Lockhart Road

Total Rating Curve Crossing: Lockhart Road





Table 2 - Culvert Summary Table: Culvert 1

Total Discharge (cfs)	Culvert Discharge (cfs)	Headwater Elevation (ft)	Inlet Control Depth (ft)	Outlet Control Depth (ft)	Flow Type	Normal Depth (ft)	Critical Depth (ft)	Outlet Depth (ft)	Tailwater Depth (ft)	Outlet Velocity (ft/s)	Tailwater Velocity (ft/s)
0.00	0.00	2035.25	0.000	0.000	0-NF	0.000	0.000	0.000	0.000	0.000	0.000
966.60	966.60	2038.03	2.783	2.783	1-S2n	0.963	1.553	1.157	1.599	9.866	6.486
1933.20	1933.20	2039.65	4.399	4.399	1-S2n	1.454	2.504	1.921	2.416	11.885	8.436
2899.80	2899.80	2040.91	5.657	5.657	1-S2n	1.927	3.299	2.587	3.075	13.244	9.809
3866.40	3866.40	2042.06	6.809	6.809	1-S2n	2.302	4.015	3.194	3.648	14.310	10.895
4833.00	4833.00	2043.21	7.956	7.956	1-S2n	2.659	4.625	3.752	4.162	15.233	11.811
5799.60	5799.60	2044.32	9.067	9.067	1-S2n	3.014	5.211	4.276	4.634	16.053	12.608
6444.00	6444.00	2045.06	9.808	9.808	1-S2n	3.217	5.578	4.607	4.931	16.574	13.088
7732.80	7732.80	2046.95	11.699	11.699	5-S2n	3.621	6.271	5.237	5.488	17.547	13.955
8699.40	8699.40	2048.64	13.386	13.386	5-S2n	3.924	6.751	5.691	5.880	18.230	14.539
9666.00	9666.00	2050.38	15.131	15.131	5-S2n	4.209	7.208	6.118	6.253	18.913	15.080

Inlet Elevation (invert): 2035.25 ft, Outlet Elevation (invert): 2034.75 ft

Culvert Length: 50.00 ft, Culvert Slope: 0.0100


Culvert Performance Curve Plot: Culvert 1



Water Surface Profile Plot for Culvert: Culvert 1

Crossing - Lockhart Road, Design Discharge - 6444.0 cfs

Culvert - Culvert 1, Culvert Discharge - 6444.0 cfs



Site Data - Culvert 1

Site Data Option: Culvert Invert Data

Inlet Station: 100.00 ft

Inlet Elevation: 2035.25 ft

Outlet Station: 150.00 ft

Outlet Elevation: 2034.75 ft

Number of Barrels: 3

Culvert Data Summary - Culvert 1

Barrel Shape: Arch-Box, Concrete

Barrel Span: 28.00 ft

Barrel Rise: 10.00 ft

Barrel Material: Concrete

Barrel Manning's n: 0.0120 (top and sides)

Manning's n: 1.4lf (bottom)

Inlet Type: Conventional

Inlet Edge Condition: Mitered to Conform to Slope

Inlet Depression: None

Table 3 - Downstream Channel Rating Curve (Crossing: Lockhart Road)

Flow (cfs)	Water Surface Elev (ft)	Depth (ft)	Velocity (ft/s)	Shear (psf)	Froude Number
0.00	2035.00	0.00	0.00	0.00	0.00
966.60	2036.60	1.60	6.49	0.97	0.92
1933.20	2037.42	2.42	8.44	1.46	0.98
2899.80	2038.07	3.07	9.81	1.86	1.02
3866.40	2038.65	3.65	10.89	2.21	1.04
4833.00	2039.16	4.16	11.81	2.52	1.06
5799.60	2039.63	4.63	12.61	2.80	1.08
6444.00	2039.93	4.93	13.09	2.98	1.09
7732.80	2040.49	5.49	13.96	3.32	1.11
8699.40	2040.88	5.88	14.54	3.56	1.12
9666.00	2041.25	6.25	15.08	3.78	1.13

Tailwater Channel Data - Lockhart Road

Tailwater Channel Option: Trapezoidal Channel

Bottom Width: 90.00 ft

Side Slope (H:V): 2.00 (1:1)

Channel Slope: 0.0097

Channel Manning's n: 0.0300

Channel Invert Elevation: 2035.00 ft

Roadway Data for Crossing: Lockhart Road

Roadway Profile Shape: Constant Roadway Elevation




Crest Length: 90.00 ft

Crest Elevation: 2051.00 ft


Roadway Surface: Paved

Roadway Top Width: 44.00 ft

CHANNEL BOTTOM CROSSING DETAILS



NOTES:

1. ALL CONCRETE TO BE CLASS "B".
2. L = SHOWN ON PLANS, H = 3' MIN., 6' MAX.
3. DRAINAGE EASEMENT REQUIRED.
4. AREA SHOWN THUS  SHALL BE COMPACTED TO 90% RELATIVE DENSITY PER STANDARD SPECIFICATION 3.04.03.
5. REINFORCED BLOCK WALL AND FOOTING PERMITTED.


SAN BERNARDINO COUNTY ROAD DEPARTMENT

DATE: J.E.M. 7-66

M. A. Nicholas
COUNTY ENGINEER

CUTOFF WALL FOR
DRAINAGE CHANNEL

200



NOTE

PAVEMENT SHALL BE CONSTRUCTED OF 3" MIN. THICK ASPHALT CONCRETE.

SAN BERNARDINO COUNTY ROAD DEPARTMENT

DATE: P.V.C. 7-65

M. A. Nicholas
COUNTY ENGINEER

CHANNEL CROSSING


200a

EXHIBITS

***SAN BERNARDINO COUNTY
FLOOD CONTROL DISTRICT
CHANNEL SECTIONS***

SAN BERNARDINO COUNTY FLOOD CONTROL DISTRICT DESIGN CRITERIA

- 1) Hydrology calculations shall adhere to the San Bernardino County Hydrology Manual.
- 2) Structural calculations shall adhere to the Los Angeles County Flood Control District Structural Design Manual and to the State of California Department of Transportation Bridge Planning and Design Manuals and the Standard Plans
- 3) Basin structural design shall adhere to the Los Angeles County Flood Control District Design Manual for Debris Dams and Basins.
- 4) Hydraulic design shall adhere to the Los Angeles County Flood Control District Hydraulic Design Manual and to the State of California Department of Transportation Highway Design Manual. Lined drainage facilities shall be designed with a bulking factor of 50% increase in water depth when there are no facilities to remove debris. Closed conduit systems shall be designed with a surface backup system to handle a Q_{100} frequency storm, a bulking factor of 50% increase in Q_{100} and a debris basin system to remove debris. Culverts under roadways, except when connected to lined open channels, shall be designed in accordance with Caltrans Highway Design Manual.
- 5) Earth channel design shall adhere to the following:
 - a) Bulk depth
 - i) For graded earth channels, use $d_{bulk} = 1.5d_{water}$.
 - ii) For natural drainage courses, compute d_{bulk} based upon $Q_{bulk} = 2 Q_{100}$
 - b) For total depth use $d_{total} = d_{bulk} + \text{freeboard}$
 - * When " V " < 6 f.p.s. - use $d_{water} + 2'$ freeboard
 - 8 f.p.s. > " V " < 26 f.p.s. use $d_{bulk} + 2'$ freeboard " V " = velocity
 - " V " > 28 f.p.s. use $d_{bulk} + 3'$ freeboard
 - c) Dike width
 - When bottom width = 12' to 40' use dike width + 15'
 - bottom width = 40' or more use dike width = 18'



EARTH CHANNEL SECTION

SAN BERNARDINO COUNTY FLOOD CONTROL DISTRICT		
REVISIONS	DWN. BY	DATE
	FILE NO.	
	S.P. 100	

EARTH CHANNEL SECTION

-
- The diagram illustrates a cross-section of a dike or levee. Key dimensions and labels include:
- right-of-way**: The total width of the area.
 - R/W = 2 [5' + 2 (freeboard) + dike + 2 (d Total)] + bottom width**: The formula for the right-of-way width.
 - 5'**: The width of the top flat section on each side.
 - dike**: The width of the top flat section.
 - bottom width**: The width of the base, labeled as **12' min.**
 - level**: The top surface of the dike.
 - freeboard**: The height above the water level.
 - d bulk**: The height of the bulkhead.
 - d water**: The height of the water.
 - d total**: The total height from the base to the top level.
 - 2:1**: The slope ratio on both sides.
 - existing ground**: The ground level on the right side, indicated by a hatched line.

SAN BERNARDINO COUNTY FLOOD CONTROL DISTRICT		
REVISIONS	DWN. BY	DATE
	FILE NO.	
	S.P. 100	



Merrell-Johnson Engineering, Inc.
CIVIL ENGINEERING ♦ SURVEYING

**CONSTRUCTION DRAINAGE, EROSION, AND SEDIMENT CONTROL /
STORMWATER POLLUTION PREVENTION PLAN**

For

MOJAVE SOLAR PROJECT
HARPER DRY LAKE, CA

Prepared For:

MOJAVE SOLAR LLC
Victorville, CA
July, 2009

Prepared by:

Merrell-Johnson Engineering, Inc.

12138 Industrial Blvd., Suite 240
Victorville, CA 92395
(760) 241-6146

Job No. 3001

Brad S. Merrell

Principal Engineer

R.C.E. 49423 Exp. 09/30/10

12138 Industrial Blvd., Suite 240 • Victorville, CA 92395 • (760) 241-6146 • Fax (760) 241-0566
128 E. Fredricks St. • Barstow, CA 92311 • (760) 256-2068 • Fax (760) 256-0418

INTRODUCTION

This Administrative Draft of the Construction Drainage, Erosion, and Sediment Control / Stormwater Pollution Prevention Plan is submitted as part of the “Application for Certification” for the Mojave Solar Project. Upon completion of the final improvement plans for the project, including the final grading, drainage, and erosion control plans, this DESCP/SWPPP plan will be finalized, signed by the engineer of record, and submitted to the government agencies having jurisdiction over the project.

Storm Water Pollution Prevention Plan

For:
MOJAVE SOLAR PROJECT
ADMINISTRATIVE DRAFT
GRADING PERMIT: _____
BUILDING PERMIT: _____

Prepared for:
ABENGOA SOLAR INC.
13911 Park Avenue, Suite 206
Victorville, CA 92392

Contractor:
(tba)

Project Site Location/Address:
Harper Dry Lake, CA

Contractor's Storm Water Pollution Prevention Manager
(tba)

SWPPP Prepared by:
Merrell-Johnson Engineering, Inc.
12138 Industrial Blvd., Suite 240
Victorville, CA 92395
(760) 241-6146
Project# 3001

SWPPP Preparation Date:
07/28/09

Estimated Project Dates:
Start of Construction: _____ Completion of Construction: _____

WDID# / Receipt of Notice Of Intent following page

The WDID# / Receipt of Notice of Intent to be inserted here by owner.

WDID No.: _____

Contents

Section 100 SWPPP Certifications and Approval	100-1
100.1 SWPPP Certification by Preparer.....	100-1
100.2 Owner Approval and Certification of SWPPP	100-2
100.3 Annual Compliance Certification	100-3
Section 200 SWPPP Amendments	200-1
200.1 SWPPP Amendment Certification and Approval	200-1
200.2 Amendment Log.....	200-4
Section 300 Introduction and Project Description	300-1
300.1 Introduction and Project Description	300-1
300.2 Unique Site Features	300-1
300.3 Construction Site Estimates	300-1
300.4 Project Schedule/Water Pollution Control Schedule	300-2
300.5 Contact Information/List of Responsible Parties.....	300-2
Section 400 References	400-1
Section 500 Body of SWPPP	500-1
500.1 Objectives	500-1
500.2 Vicinity Map.....	500-2
500.3 Pollutant Source Identification and BMP Selection	500-2
500.3.1 Inventory of Materials and Activities that May Pollute Storm Water	500-2
500.3.2 Existing (pre-construction) Control Measures	500-4
500.3.3 Nature of Fill Material and Existing Data Describing the Soil	500-4
500.3.4 Erosion Control	500-4
500.3.5 Sediment Control	500-6
500.3.6 Tracking Control.....	500-7
500.3.7 Wind Erosion Control	500-7
500.3.8 Non-Storm Water Control.....	500-8
500.3.9 Waste Management and Materials Pollution Control	500-9
500.3.10 Cost Breakdown for Water Pollution Control	500-10
500.4 Water Pollution Control Drawings (WPCDs)	500-10
500.5 Construction BMP Maintenance, Inspection, and Repair	500-11
500.6 Post-Construction Storm Water Management.....	500-11
500.6.1 Post-Construction Control Practices	500-11
500.6.2 Operation/Maintenance after Project Completion	500-12

500.7	Training	500-12
500.8	List of Subcontractors	500-13
500.9	Other Plans/Permits	500-13
Section 600 Monitoring Program and Reports		600-13
600.1	Site Inspections	600-13
600.2	Non-Compliance Reporting	600-14
600.3	Record Keeping and Reports	600-14
600.4	Sampling and Analysis Plan for Sediment	600-15
600.5	Sampling and Analysis Plan for Non-Visible Pollutants	600-15
600.5.1	Scope of Monitoring Activities	600-15
600.5.2	Monitoring Strategy	600-17
600.5.3	Monitoring Preparation	600-19
600.5.4	Analytical Constituents	600-20
600.5.5	Sample Collection and Handling	600-20
600.5.6	Sample Analysis	600-24
600.5.7	Quality Assurance/Quality Control	600-26
600.5.8	Data Management and Reporting	600-26
600.5.9	Data Evaluation	600-26
600.5.10	Change of Conditions	600-27

SWPPP Attachments

Attachment A	Vicinity Map
Attachment B	Water Pollution Control Drawings
Attachment C	BMP Consideration Checklist
Attachment D	Computation Sheet for Determining Runoff Coefficients
Attachment E	Computation Sheet for Determining Run-on Discharges
Attachment F	Notice of Intent (NOI)
Attachment G	Program for Maintenance, Inspection, and Repair of Construction Site BMPs
Attachment H	Storm Water Quality Construction Site Inspection Checklist
Attachment I	Trained Contractor Personnel Log
Attachment J	Subcontractor Notification Letter and Log
Attachment K	Notice of Non-Compliance
Attachment L	SWPPP and Monitoring Program Checklist
Attachment M	Annual Certification of Compliance Form
Attachment N	Other Plans/Permits
Attachment O	Water Pollution Control Cost Breakdown

Attachment P Notice of Termination (NOT)
Attachment Q..... BMPs Selected for the Project
Attachment R..... Sampling Activity Log
Attachment SConstruction Material and Pollutant Testing Guidance Table – Non-Visible Pollutants
Attachment T Discharge Reporting Log

Contents

Exhibit 1.....Construction Schedule

Exhibit 2**Soils Report

Exhibit 3**Hydrology Report

Exhibit 4.....Change of Information (COI) Form

**Due to the size of this report, only the cover sheets are attached in Exhibit 2 and 3.
Please refer to the full report supplied upon request from owner for detail and information needed.

Section 100

SWPPP Certifications and Approval

100.1 SWPPP Certification by Preparer

Project Name: MOJAVE SOLAR PROJECT

ADMINISTRATIVE DRAFT

Project Number: GRADING PERMIT: _____
BUILDING PERMIT: _____

"I certify under a penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to ensure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, to the best of my knowledge and belief, the information submitted is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Preparer's Signature

Date

Brad S. Merrell R.C.E 49423

Preparer's Name and Title

(760) 241-6146

Telephone Number

100.2 Owner Approval and Certification of SWPPP

**Owner's (or Authorized Representative)
Approval and Certification of the
Storm Water Pollution Prevention Plan**

Project Name: MOJAVE SOLAR PROJECT

ADMINISTRATIVE DRAFT
Project Number: GRADING PERMIT: _____
BUILDING PERMIT: _____

"I certify under a penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to ensure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, to the best of my knowledge and belief, the information submitted is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Owner (or Authorized Representative) Signature

Date

Name and Title

Telephone Number

100.3 Annual Compliance Certification

By July 1 of each year, the Owner shall complete an Annual Certification of Compliance stating compliance with the terms and conditions of the Permit and the SWPPP. The blank Annual Certification of Compliance Form is included in Attachment M. Completed Annual Certifications of Compliance and Approvals can be found in the following pages.

Section 200

SWPPP Amendments

200.1 SWPPP Amendment Certification and Approval

This SWPPP shall be amended:

- Whenever there is a change in construction or operations which may affect the discharge of pollutants to surface waters, groundwater(s), or a municipal separate storm sewer system (MS4); or
- If any condition of the Permits is violated or the general objective of reducing or eliminating pollutants in storm water discharges has not been achieved. If the RWQCB determines that a Permit violation has occurred, the SWPPP shall be amended and implemented within 14-calendar days after notification by the RWQCB;
- Annually, prior to the defined rainy season; and
- When deemed necessary by the Owner.

The following items will be included in each amendment:

- Who requested the amendment.
- The location of proposed change.
- The reason for change.
- The original BMP proposed, if any.
- The new BMP proposed.

The amendments for this SWPPP, along with the Owner's Certification and the Owner approval, can be found in the following pages. Amendments are listed in the Amendment Log in section 200.2

This Administrative Draft of the Construction Drainage, Erosion, and Sediment Control/Stormwater Pollution Prevention Plan is submitted as part of the "Application for Certification" for the Mojave Solar Project. Upon completion of the final improvement plans for the project, including the final grading and drainage plans, a final DESCP/SWPPP plan will be prepared, signed by the engineer of record, and submitted to the government agencies having jurisdiction over the project.

SWPPP Amendment No.

Project Name: **MOJAVE SOLAR PROJECT**

ADMINISTRATIVE DRAFT

GRADING PERMIT: _____

Project Number: **BUILDING PERMIT: _____**

**Preparer Certification of the
Storm Water Pollution Prevention Plan Amendment**

"I certify under a penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to ensure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, to the best of my knowledge and belief, the information submitted is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Preparer's Signature

Date

Preparer's Name and Title

Telephone Number

**Owner (or Owner's Authorized Representative) Approval of the
Storm Water Pollution Prevention Plan Amendment**

"I certify under a penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to ensure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, to the best of my knowledge and belief, the information submitted is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Owner (or Authorized Representative) Signature

Date

Name and Title

Telephone Number

200.2 Amendment Log

Project Name: MOJAVE SOLAR PROJECT

ADMINISTRATIVE DRAFT

Project Number: GRADING PERMIT: _____
BUILDING PERMIT: _____

Amendment No.	Date	Brief Description of Amendment	Prepared By

Section 300

Introduction and Project Description

300.1 Introduction and Project Description

This project is located along the south and west shores of Harper Dry Lake in an unincorporated area near the community of Lockhart, in San Bernardino County. Property includes Section 33, portions of Sections 28, 29, 30, and 32 of Township 11N, Range 4W, SBBM. Project has been sectioned into three areas; Alpha West, Alpha East and Beta.

Improvements include removal of abandoned one story buildings and structures to replace with parabolic solar collectors, foundations and pipings aligned on a north-south direction. Site will also include cooling plants with wet cooling tower, generator and evaporative ponds. See civil plans for details.

300.2 Unique Site Features

Existing Harper Lake Road is currently paved. Improvements include widening road as shown on civil plans.

Stormwater runoff at the site is predominantly sheet flow from the south and flows to the north. Drainage channels will capture and direct waters to protect power plants, solar panels, and maintenance roads. See civil plans for details.

300.3 Construction Site Estimates

The following are estimates of the construction site:

Construction site area	<u>1,765</u>	acres
Percentage impervious area before construction	<u>100</u>	%
Runoff coefficient before construction ⁽¹⁾	<u>0.742 (1)</u>	
Percentage impervious area after construction	<u>97.9</u>	%
Runoff coefficient after construction ⁽¹⁾	<u>0.7542 (1)</u>	
Anticipated storm water flow on to the construction site ⁽²⁾	<u>21,928 (2)</u>	cfs

⁽¹⁾ Calculations are shown in Attachment D

⁽²⁾ Calculations are shown in Attachment E

300.4 Project Schedule/Water Pollution Control Schedule

Construction Time-Schedule is found as Exhibit 1 of final report.

In addition to the time-schedule, the contractor assigned will mobilize and develop temporary construction facilities and lay down areas. These areas will move locations due to construction phasing and as needed to site changes. Temporary facilities may include but not limited to:

Trailer offices

Chemical Toilets

Parking for workers

Equipment Parking

Equipment/Tools Storage Areas

Lay Down Areas as needed

Security Areas at entrances of site with Tire Washes as needed.

300.5 Contact Information/List of Responsible Parties

The Storm Water Pollution Prevention Manager (SWPPM) assigned to this project is:

(tba)

(tba)

The SWPPM shall have primary responsibility and significant authority for the implementation, maintenance, inspection and amendments to the approved SWPPP. The SWPPM will be available at all times throughout the duration of the project. Duties of the SWPPM include but are not limited to:

- Ensuring full compliance with the SWPPP and the Permit
- Implementing all elements of the SWPPP, including but not limited to:
 - Implementation of prompt and effective erosion and sediment control measures
 - Implementing all non-storm water management, and materials and waste

management activities such as: monitoring discharges (dewatering, diversion devices); general site clean-up; vehicle and equipment cleaning, fueling and maintenance; spill control; ensuring that no materials other than storm water are discharged in quantities which will have an adverse effect on receiving waters or storm drain systems; etc.

- Pre-storm inspections
- Storm event inspections
- Post-storm inspections
- Routine inspections as specified in the project's specifications or described in the SWPPP
- Updates/ Amendments to the SWPPP, as needed
- Preparing annual compliance certification for owner's, or owner's authorized representative, signature
- Ensuring elimination of all unauthorized discharges
- The SWPPM shall be assigned authority by the Contractor to mobilize crews in order to make immediate repairs to the control measures
- Coordinate with the Contractor to assure all of the necessary corrections/repairs are made immediately, and that the project complies with the SWPPP, the Permit and approved plans at all times
- Submitting Notices of Discharge and reports of Illicit Connections or Illegal Discharges

Section 400

References

The following documents are made a part of this SWPPP by reference:

- Project plans and specifications No. (final plans pending), dated (_____), prepared by Merrell- Johnson Engineering, Inc.
- State Water Resources Control Board (SWRCB) Order No. 99-08-DWQ, National Pollutant Discharge Elimination System (NPDES) General Permit No. CAS000002, Waste Discharge Requirements (WDRs) for Discharges of Storm Water Runoff Associated with Construction Activity.
- California Stormwater BMP Handbook – Construction, January 2003
- Geotechnical Evaluation, dated May 15, 2009, prepared by Ninyo & Moore Geotechnical and Enviromental Sciences Consultants, Project No. 105879004. (Cover Sheet enclosed for reference as Exhibit 2).
- Hydrology Study, (Cover Sheet for reference as Exhibit 3)
-

Section 500

Body of SWPPP

500.1 Objectives

This Storm Water Pollution Prevention Plan (SWPPP) has six main objectives:

- Identify all pollutant sources, including sources of sediment that may affect the quality of storm water discharges associated with construction activity (storm water discharges) from the construction site, and
- Identify non-storm water discharges, and
- Identify, construct, implement in accordance with a time schedule, and maintain Best Management Practices (BMPs) to reduce or eliminate pollutants in storm water discharges and authorized non-storm water discharges from the construction site during construction, and
- Develop a maintenance schedule for BMPs installed during construction designed to reduce or eliminate pollutants after construction is completed (post-construction BMPs).
- Identify a sampling and analysis strategy and sampling schedule for discharges from construction activity which discharge directly into water bodies listed on Attachment 3 of the Permit (Clean Water Act Section 303(d) [303(d)] Water Bodies listed for Sedimentation).
- For all construction activity, identify a sampling and analysis strategy and sampling schedule for discharges that have been discovered through visual monitoring to be potentially contaminated by pollutants not visually detectable in the runoff.

This SWPPP conforms with the required elements of the General Permit No. CAS000002 issued by the State of California, State Water Resources Control Board (SWRCB). This SWPPP will be modified and amended to reflect any amendments to the Permit or any changes in construction or operations that may affect the discharge of pollutants from the construction site to surface waters, groundwaters, or the municipal separate storm sewer system (MS4). The SWPPP will also be amended if it is in violation of any condition of the Permit or has not achieved the general objective of reducing pollutants in storm water discharges. The SWPPP shall be readily available on-site for the duration of the project.

500.2 Vicinity Map

The construction project vicinity map showing the project location, surface water boundaries, geographic features, construction site perimeter, and general topography, is located in Attachment A. The project's Title Sheet provides more detail regarding the project location and is also included in Attachment A.

500.3 Pollutant Source Identification and BMP Selection

500.3.1 Inventory of Materials and Activities that May Pollute Storm Water

The following is a list of construction materials that will be used and activities that will be performed that will have the potential to contribute pollutants, other than sediment, to storm water runoff (control practices for each activity are identified in the Water Pollution Control Drawings (WPCDs) and/or in Sections 500.3.4 through 500.3.9:

- Vehicle fluids including grease, oil, petroleum, and coolants.
- Asphaltic emulsions associated with asphalt-concrete paving operations.
- Cement materials associated with PCC paving operations and drainage structures.
- Base and subbase materials.
- Solvents, thinners, and acids.
- Raw landscaping materials and wastes.
- BMP materials.
- PCC rubble.
- General litter.
- Demobilizations associated with construction facilities and laydown areas being relocated/removed.
- Concrete curing compounds and operations.

Construction activities that have the potential to contribute sediment to storm water discharges include:

- Clear and grub operations.
- Grading operations.
- Soil import operations.
- Utility excavation operations.
- Sandblasting operations.
- Welding and pipe coating operations.
- Hydrostatic testings.
- Trenching.
- Paving operations.
- Boring operations.
- Delivery/transportation operations.
- Foundation/structure construction operations.
- Vehicle and equipment cleaning, fueling, and maintenance.
- Paint.
- Wash out and Clean up of equipment.

Attachment C lists all Best Management Practices (BMPs) that have been selected for implementation in this project. Implementation and location of BMPs are shown on the WPCDs in Attachment B. Narrative descriptions of BMPs to be used during the project are listed by category in each of the following SWPPP sections. Attachment Q includes a list, and/or copies of the fact sheets of all the BMPs selected for this project.

500.3.2 Existing (pre-construction) Control Measures

The following are existing (pre-construction) control measures encountered within the project site:

- There are no known control measures on this site.
-
-
-
-
-

500.3.3 Nature of Fill Material and Existing Data Describing the Soil

Refer to Geotechnical Evaluation Report for soil data.

Existing site features that, as a result of past usage, may contribute pollutants to storm water (e.g., toxic materials that are known to have been treated, stored, disposed, spilled, or leaked onto the construction site) include:

-
-
-
-

500.3.4 Erosion Control

Erosion control, also referred to as soil stabilization, consists of source control measures that are designed to prevent soil particles from detaching and becoming transported in storm water runoff. Erosion control BMPs protect the soil surface by covering and/or binding soil particles. This project will incorporate erosion control measures required by

the contract documents, and other measures selected by the Contractor, SWPPP Manager, or Owner. This project will implement the following practices for effective temporary and final erosion control during construction:

- 1) Preserve existing vegetation where required and when feasible.
- 2) Apply temporary erosion control to remaining active and non-active areas as required by the California Stormwater BMPs Handbook – Construction, and the contract documents. Reapply as necessary to maintain effectiveness.
- 3) Implement temporary erosion control measures at regular intervals throughout the defined rainy season to achieve and maintain the contract's disturbed soil area requirements. Implement erosion control prior to the defined rainy season.
- 4) Stabilize non-active areas as soon as feasible after the cessation of construction activities.
- 5) Control erosion in concentrated flow paths by applying erosion control blankets, erosion control seeding, and lining swales as required in the contract documents.

- 6) At completion of construction, apply permanent erosion control to all remaining disturbed soil areas.

Sufficient erosion control materials will be maintained on-site to allow implementation in conformance with Permit requirements and described in this SWPPP. This includes implementation requirements for active areas and non-active areas that require deployment before the onset of rain.

Implementation and locations of temporary erosion control BMPs are shown on the Water Pollution Control Drawings (WPCDs) in Attachment B and/or described in this section. The BMP Consideration Checklist in Attachment C indicates the BMPs that will be implemented to control erosion on the construction site; these are:

- EC-1, Scheduling
- EC-2, Preservation of Existing Vegetation
- EC-5, Soil Binders *(DO NOT use EC-4, Hydroseeding as a "Potential Alternative" as listed in latest edition of CASQA BMP Handbook for this project.)

- EC-7, Geotextiles and Mats
- EC-9, Earth Dikes and Drainage Swales
- EC-10, Velocity Dissipation Devices
- EC-11, Slope Drains
- EC-13, Polyacrylamide*

Temporary concentrated flow conveyance controls consists of a system of measures or BMPs that are used alone or in combination to intercept, divert, convey and discharge concentrated flows with a minimum of soil erosion, both on-site and downstream (off-site). Temporary concentrated flow conveyance controls may be required to direct run-on around or through the project in a non-erodible fashion. The Contractor's Storm water Pollution Prevention Manager shall implement such practices and assure continued compliance throughout project.

* Due to the nature of this project, Hydroseeding as a form of Erosion Control for soil stabilization will hinder this project and its' purpose. Alternative measures are listed above, which include and are not limited to EC-13, Polyacrylamides as approved by owner and meet the Local, State and Federal requirements.

500.3.5 Sediment Control

Sediment controls are structural measures that are intended to complement and enhance the selected erosion control measures and reduce sediment discharges from active construction areas. Sediment controls are designed to intercept and settle out soil particles that have been detached and transported by the force of water. This project will incorporate sediment control measures required by the contract documents, and other measures selected by the Contractor, SWPPP Manager, or Owner.

Sufficient quantities of temporary sediment control materials will be maintained on-site throughout the duration of the project, to allow implementation of temporary sediment controls in the event of predicted rain, and for rapid response to failures or emergencies, in conformance with other Permit requirements and as described in this SWPPP. This includes implementation requirements for active areas and non-active areas before the onset of rain.

Implementation and locations of temporary sediment control BMPs are shown on the Water Pollution Control Drawings (WPCDs) in Attachment B. The BMP Consideration

Checklist in Attachment C indicates all the BMPs that will be implemented to control sediment on the construction site; these are:

- SE-1, Silt Fence
- SE-4, Check Dams
- SE-5, Fiber Rolls
- SE-6, Gravel Bag Berm
- SE-8, Sandbag Barrier
- SE-9, Straw Bale Barrier
- SE-10, Storm Drain Inlet Protection

Temporary sediment control practices include those practices that intercept and slow or detain the flow of storm water to allow sediment to settle and be trapped. These practices can be used alone or in combination of above list. The Contractor's Storm water Pollution Prevention Manager shall implement such practices and assure continued compliance throughout project.

500.3.6 Tracking Control

The following BMPs have been selected to reduce sediment tracking from the construction site onto private or public roads:

- SE-7, Street Sweeping and Vacuuming
- TC-1, Stabilized Construction Entrance/Exit
- TC-2, Stabilized Construction Roadway
- TC-3, Entrance/Outlet Tire Wash

Tracking control also consists of preventing or reducing vehicle tracking from entering a storm drain or watercourse. The Contractor's Storm water Pollution Prevention Manager shall implement such practices and assure continued compliance throughout project.

500.3.7 Wind Erosion Control

The following BMPs have been selected to control dust from the construction site:

- WE-1, Wind Erosion Control
- Cover all trucks hauling soils and other loose materials or maintain adequate freeboard.
-

Wind erosion consists of applying water or other dust palliatives as necessary to prevent or alleviate dust nuisance. The Constructor's Storm water Pollution Prevention Manager shall implement such practices and assure continued compliance throughout project.

500.3.8 Non-Storm Water Control

An inventory of construction activities and potential non-storm water discharges is provided in Section 5.3.1. The BMP Consideration Checklist in Attachment C and the following list indicates the BMPs that have been selected to control non-storm water pollution on the construction site. Implementation and locations of some non-storm water control BMPs are shown on the Water Pollution Control Drawings (WPCDs) in Attachment B. A narrative description of each BMP follows.

- NS-6, Illicit Connection/Illegal Discharge Detection and Reporting
- NS-8, Vehicle and Equipment Cleaning
- NS-9, Vehicle and Equipment Fueling
- NS-10, Vehicle and Equipment Maintenance
- NS-1 Water Conservation Practices
- NS-3, Paving and Grinding Operations
- NS-7, Potable Water/Irrigation Practices
- NS-12, Concrete Curing
- NS-13, Concrete Finishing
- Place drip pans or absorbent materials under heavy equipment when not in use.
- Inspect all heavy equipment and vehicles regularly for signs of leaks.

- Use proper storage and handling techniques for all concrete curing compounds, oils, grease and other petroleum by-products, preventing runoff or spills.
- Inform workers of the importance of preventing spills and measures to take should a spill occur. Train workers in Good Housekeeping Practices according with local, state, and federal regulations. Report spills in appropriate compliance reports.

Non-storm water management best management practices (BMPs) are source control BMPs that prevent pollution by limiting or reducing potential pollutants at their source before they come in contact with storm water. These practices involve day-to-day operations of the construction site and are under the control of the Contractor. These are also referred to as "good housekeeping practices", which involve keeping a clean, orderly construction site.

500.3.9 Waste Management and Materials Pollution Control

An inventory of construction activities, materials, and wastes is provided in Section 5.3.1. The BMP Consideration Checklist in Attachment C and the following list indicates the BMPs that have been selected to handle materials and control construction site wastes. A narrative description of each BMP follows.

- WM-1, Material Delivery and Storage
- WM- 2, Material Use
- WM-3, Stockpile Management
- WM-4, Spill Prevention and Control
- WM-5, Solid Waste Management
- WM-9, Sanitary/Septic Waste Management
- Provide weekly maintenance for portable toilets by a licensed sanitary service and dispose of wastes according to regulations. Anchor portable toilets during periods of heavy winds.
- WM-6, Hazardous Waste Management
- WM-7, Contaminated Soil Management
- WM-8, Concrete waste Management

- WM-10, Liquid Waste Management
- Place covers over stockpiles prior to forecasted storm events and during windy conditions. In addition, place sediment controls at the foot of stockpiled materials.
- Maintain spill cleanup sheets, material inventory sheet, emergency contact numbers, and methods for spill cleanup information clearly posted in storage area.
- Spill cleanup materials should include, but not limited to a minimum of, absorbent materials, tools to manage (such as brooms, shovels, rakes, squeegees, water-tight containers, and personnel protective gear), and a spill berm that will hold the amount of the largest container.
- Inform personnel of all cleanup supplies and procedures including reporting spills of toxic or hazardous materials to the Project Manager or assignee regardless of size.

Waste management and materials pollution control BMPs, like non-storm water management BMPs, are source control BMPs that prevent pollution by limiting or reducing potential pollutants at their source before they come in contact with storm water. The objective is to reduce the opportunity for rainfall, handling, storing, and disposing of wastes to come into storm water discharges. These BMPs listed above mainly involve day-to-day operations of "good housekeeping practices". The Contractor's Storm water Pollution Prevention Manager shall implement such practices and assure continued compliance throughout project.

500.3.10 Cost Breakdown for Water Pollution Control

A cost breakdown itemizing the contract lump sum for water pollution control has been developed for this project and included in Attachment O. The cost breakdown reflects the items of work, quantities and costs for BMPs shown in the SWPPP, except for those construction site BMPs and permanent BMPs that are shown on the project plans and for which there is a contract item of work.

500.4 Water Pollution Control Drawings (WPCDs)

The Water Pollution Control Drawings can be found in Attachment B of the SWPPP.

500.5 Construction BMP Maintenance, Inspection, and Repair

Inspections will be conducted as follows:

- Prior to a forecast storm
- after a rain event that causes runoff from the construction site
- at 24-hour intervals during extended rain events
- at any other time(s) or intervals of time specified in the contract documents

Completed inspection checklists will be kept with the SWPPP.

A tracking or follow-up procedure shall follow any inspection that identifies deficiencies in BMPs. A program for Maintenance, Inspection and Repair of BMPs is shown in Attachment G.

500.6 Post-Construction Storm Water Management

500.6.1 Post-Construction Control Practices

The following are the post-construction BMPs that are to be used at this construction site after all construction is complete:

- On-site Oil/Water Separators at the power islands
- Swales
- Curb and gutters
- Drainage Channels
- Berms and Dikes
-

Sheet flow within the solar field will be managed through the construction of internal drainage facilities designed to capture storm water and allow it to percolate and evaporate within the fields. Refer to Water Resource AFC Application, Section 5.17 for details.

500.6.2 Operation/Maintenance after Project Completion

The post-construction BMPs that are described above will be funded and maintained by Owner.

500.7 Training

Section 300.5 shows the name of the Contractor's Storm Water Pollution Prevention Manager (SWPPM). This person has received the following training:

- (tba)
-
-
-

The training log showing formal and informal training of various Contractor personnel is shown in Attachment I.

Contractors and subcontractors are responsible for familiarizing their personnel with the information contained in the SWPPP. All new employees will be trained by staff familiar with these topics.

As required by the SWRCB, individuals responsible for SWPPP preparation, implementation, and permit compliance will be appropriately trained and training will be documented. This includes those personnel responsible for installation, inspection, maintenance, and repair of BMPs. Those responsible for overseeing, revising and amending the SWPPP shall also receive and document their training. Monitoring and inspection activities will only be conducted by individuals who have had additional training specific for this purpose.

Contractor is responsible for all on-site situations regarding compliance with this SWPPP, California Regional Water Quality Control Board, California Stormwater Quality Association, Environmental Protection Agency, as well as, other local, state and federal regulations of stormwater control. If contractor disagrees with this SWPPP contents, it shall be brought to the attention of the preparer prior to beginning construction.

This SWPPP was prepared by Brad S. Merrell R.C.E. 49423
Merrell - Johnson Engineering, Inc.
12138 Industrial Blvd., Suite# 240
Victorville, CA 92395
(760) 241-6146.

500.8 List of Subcontractors

All contractors and subcontractors will be notified of the requirement for storm water management measures during the project. A list of contractors will be maintained and included in the SWPPP. If subcontractors change during the project, the list will be updated accordingly. The subcontractor notification letter and log is included in the SWPPP as Attachment J.

500.9 Other Plans/Permits

Attachment N includes copies of other local, state, and federal plans and permits. Following is a list of the plans and permits included in Attachment N:

- State Water Resources Control Board (SWRCB) Order No. 99-08-DWQ, National Pollutant Discharge Elimination System (NPDES) General Permit No. CAS000002, Waste Discharge Requirements (WDRs) for Discharges of Storm Water Runoff Associated with Construction Activity.

Section 600

Monitoring Program and Reports

600.1 Site Inspections

The SWPPM will inspect the site prior to a forecast storm, after a rain event that causes runoff from the construction site, at 24-hour intervals during extended rain events, and as specified in the contract documents. The results of all inspections and assessments will be documented. Copies of the completed inspection checklists will be maintained with the

SWPPP. Site inspections conducted for monitoring purposes will be performed using the inspection checklist shown in Attachment H.

The name(s) and contact number(s) of the assigned inspection personnel are listed below:

Assigned inspector: (tba)

Contact phone: (tba)

600.2 Non-Compliance Reporting

If a discharge occurs or if the project receives a written notice of non-compliance, the Contractor will immediately notify the Owner and will file a written report to the Owner within 7 days of the discharge or notice. The Owner is responsible for filing a written report to the Regional Water Quality Control Board (RWQCB) within 30 days of identification of non-compliance. Corrective measures will be implemented immediately following the discharge, notice or order. A sample Notice of Non-Compliance (NONC) form is provided in Attachment K. All discharges will be documented on a Discharge Reporting Log using the example form in Attachment T.

The report to the Owner and to the RWQCB will contain the following items:

- The date, time, location, nature of operation, and type of unauthorized discharge, including the cause or nature of the notice or order,
- The control measures (BMPs) deployed before the discharge event, or prior to receiving notice or order,
- The date of deployment and type of control measures (BMPs) deployed after the discharge event, or after receiving the notice or order, including additional measures installed or planned to reduce or prevent re-occurrence, and
- An implementation and maintenance schedule for any affected BMPs

600.3 Record Keeping and Reports

Records shall be retained for a minimum of three years for the following items:

- Site inspections
- Compliance certifications
- Discharge reports
- Approved SWPPP document and amendments

600.4 Sampling and Analysis Plan for Sediment

This project does not have the potential to discharge directly to a water body listed as impaired due to Sedimentation/Siltation and/or Turbidity pursuant to Clean Water Act, Section 303(d).

Sampling and Analysis Plan for Non-Visible Pollutants

This Sampling and Analysis Plan (SAP) for Non-Visible Pollutants describes the sampling and analysis strategy and schedule for monitoring non-visible pollutants in storm water discharges from the project site and off-site activities directly related to the project, in accordance with the requirements of Section B of the General Permit, including SWRCB Resolution 2001-046.



600.5.1 Scope of Monitoring Activities

The following construction materials, wastes or activities, as identified in Section 500.3.1, are potential sources of non-visible pollutants to storm water discharges from the project. Storage, use, and operational locations are shown on the WPCDs in Attachment B.

- Harper Dry Lake is not listed in the 303d List of Water Bodies for the Lahontan Region, approved by USEPA, July 2003, latest report titled, "2003 CWA Section 303(d) List of Water Quality Limited Segment".
- Per our meetings and discussions with the Regional Water Board this Section for Sampling of Non-Visible Pollutant to storm water discharges from the project have been omitted due to the area of this project. On-site storm water will be held and percolated on-site.


Attachment A

Vicinity Map



Legend

Plant Site Boundary



MOJAVE SOLAR PROJECT

Figure 5.3-1

Plant Site and Survey Area

MOJAVE SOLAR LLC

Merrell-Johnson Engineering, Inc.

PROJECT:

DATE: 04-20-2009

Attachment B

Water Pollution Control Drawings (WPCDs)

[illegible]

HYDRAULIC MULCH, HYDROSEEDING, SOIL BINDERS, OR APPROVED EQUAL BY COUNTY OF SAN BERNARDINO STAFF SHALL BE USED IN ALL DISTURBED SOIL AREAS INCLUDING GRADED LOTS, CHANNELS AND ROADS.

THIS PRELIMINARY CONTROL PLAN IN ADDITION TO THE SWPPP (STORM WATER POLLUTION PREVENTION PLAN) PREPARED ON THE DATE LISTED BELOW FOR THIS PROJECT SHALL BE REVIEWED AND APPROVED BY THE STATE OF CALIFORNIA AND SHALL CONFORM WITH THE REQUIRED ELEMENTS OF THE STATE WATER RESOURCES CONTROL BOARD (SWRCB). THE SWPPP REPORT WILL BE MODIFIED AND AMENDED BY THE CONTRACTOR TO REFLECT ANY CHANGES AND AMENDMENTS DUE TO SITE CONDITIONS.

[illegible]

	PERIMETER/TORTOISE FENCE
	AREA BOUNDARY
	PROPOSED DRAINAGE CHANNEL
	PROPOSED PAVEMENT
	TC-2, STABILIZED CONSTRUCTION ROADWAY
	SE-7, STREET SWEEPING AND VACUUMING
	STORMWATER DISCHARGE LOCATIONS
	EC-4, EARTH DUMPS AND DRAINAGE SWALES
	EC-3, PROTECT EXISTING VEGETATION
	SE-1, CUT FENCE
	EC-5, FIBER ROLL
	SE-8, SAND/GRAVEL BAG BARRIER
	TC-2, STABILIZED CONSTRUCTION ENTRANCE/EXIT
	BM-6, CONCRETE MATT MANAGEMENT

ELECTRIC:	EDISON INTERNATIONAL 58555 RAMONA ROAD BOSTON, CALIFORNIA (760) 252-6451
GAS:	SOUTHWEST GAS 13471 MARIPOSA ROAD VICTORVILLE, CALIFORNIA (760) 241-8120
TELEPHONE:	VERIZON 16071 MOJAVE DR. BLVD VICTORVILLE, CA 92395 (760) 245-0394
WATER:	PERMANENT WELL
DISPOSAL:	NONE
SEWER:	SEPTIC SYSTEM

OWNER:
ABENGOA SOLAR
13911 PARK AVENUE, SUITE #206

(TRA)

THE CONTRACTOR IS REQUIRED BY GOVERNMENT CODE 4216 "CALIFORNIA WE CALL LAW" TO CALL DIG ALERT AT LEAST TWO (2) WORKING DAYS BEFORE DIGGING. CONTRACTOR IS REQUIRED BY SAME CODE TO NON-EXPOSE TO THE POINT OF NO CONFLICT 24" ON EITHER SIDE OF THE UNDERGROUND FACILITY SO YOU CAN DETERMINE ITS EXACT LOCATION BEFORE USING POWER EQUIPMENT.



**BEFORE
YOU DIG**

1-800-422-4133
DERGROUND SERVICE ALERT
At least 2 weeks before doing any work to avoid digging




SCALE: 1" = 1000'

¹ THE INFORMATION ON THESE DRAWING IS ACCURATE FOR WATER POLLUTION CONTROL PURPOSES ONLY

- [illegible]


1. PRIOR TO CONSTRUCTION THE CONTRACTOR SHALL CONTACT ALL UTILITY COMPANIES TO DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL UTILITIES AND SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO PROTECT ALL EXISTING FACILITIES FROM DAMAGE DURING CONSTRUCTION.
2. ANY SURVEY MONUMENTS PRESENTING AN OBSTACLE TO CONSTRUCTION SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.
3. THE CONTRACTOR AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR THE PROTECTION OF ALL EXISTING UTILITIES AND FACILITIES. IF ANY DAMAGE TO ANY EXISTING UTILITY OR FACILITY IS CAUSED BY THE CONTRACTOR, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REPAIR OF SUCH DAMAGE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING FACILITIES FROM DAMAGE DURING CONSTRUCTION.




**STORM WATER POLLUTION CONTROL
CONSTRUCTION NOTES**

- [illegible]


PRELIMINARY

 <p>McConnell-Johnson Engineering, Inc.</p> <p>12136 INDIANOLA BLVD. #240 FREMONT, CALIFORNIA 92395 (714) 341-0586 (714) 341-0586 FAX</p>	<p>MOJAVE SOLAR EROSION CONTROL ALPHA & BETA</p>	<p>FOR: ABENGOA SOLAR</p>	<p>SHEET 2 OF 5</p>
	<p>DRAWN BY: WML DATE: 07/28/09 DESIGNED BY: WML DATE:</p>	<p>APPROVED BY: WML DATE: 07/28/09</p>	<p>SCALE: AS SHOWN</p>




SEE SHEET 4

SEE SHEET 5




STORM WATER POLLUTION CONTROL
CONSTRUCTION NOTES

- [illegible]



PRELIMINARY
Not For Construction

 <p>Merrell-Johnson Engineering, Inc.</p> <p>12128 INDUSTRIAL BLVD. #400 HOUSTON, TEXAS 77060 (713) 241-6145 (713) 241-6146 (713) 241-0268</p>	<p>MOJAVE SOLAR EROSION CONTROL ALPHA WEST</p>		<p>SCALE: AS SHOWN</p>	<p>JOB NO. 3001</p>	<p>SHEET 35</p>
	<p>FOR: ABENGOA SOLAR</p>		<p>OWNER BY: JMS 07/28/09</p>	<p>DESIGNED BY: DATE:</p>	<p>APPROVED BY: DATE:</p>

Attachment C

BMP Consideration Checklist

CONSTRUCTION SITE BMPs CONSIDERATION CHECKLIST					
The BMPs listed here should be considered for every project. Those BMPs that are not included in the SWPPP must be checked as "Not Used" with a brief statement describing why it is not being used.					
EROSION CONTROL BMPs					
BMP No.	BMP	CONSIDERED FOR PROJECT	CHECK IF USED	CHECK IF NOT USED	IF NOT USED, STATE REASON
EC-1	Scheduling		✓		
EC-2	Preservation of Existing Vegetation		✓		
EC-3	Hydraulic Mulch	✓			
EC-4	Hydroseeding			✓	NOT EFFICIENT FOR THIS PROJECT
EC-5	Soil Binders	✓			
EC-6	Straw Mulch	✓			
EC-7	Geotextiles & Mats	✓			
EC-8	Wood Mulching	✓			
EC-9	Earth Dikes & Drainage Swales		✓		
EC-10	Velocity Dissipation Devices	✓			
EC-11	Slope Drains	✓			
EC-12	Streambank Stabilization			✓	NO STREAMS ON OR NEAR SITE
EC-13	Polyacrylamide	✓			

CONSTRUCTION SITE BMPs CONSIDERATION CHECKLIST					
The BMPs listed here should be considered for every project. Those BMPs that are not included in the SWPPP must be checked as "Not Used" with a brief statement describing why it is not being used.					
SEDIMENT CONTROL BMPs					
BMP No.	BMP	CONSIDERED FOR PROJECT	CHECK IF USED	CHECK IF NOT USED	IF NOT USED, STATE REASON
SE-1	Silt Fence		✓		
SE-2	Sediment Basin			✓	NOT EFFECTIVE FOR THIS SITE
SE-3	Sediment Trap			✓	NOT EFFECTIVE FOR THIS SITE
SE-4	Check Dam		✓		
SE-5	Fiber Rolls	✓			
SE-6	Gravel Bag Berm		✓		
SE-7	Street Sweeping and Vacuuming		✓		
SE-8	Sand Bag Barrier		✓		
SE-9	Straw Bale Barrier	✓			
SE-10	Storm Drain Inlet Protection		✓		
SE-11	Chemical Treatment		✓		
WIND EROSION CONTROL BMPs					
WE-1	Wind Erosion Control		✓		
TRACKING CONTROL BMPs					
TR-1	Stabilized Construction Entrance/Exit		✓		
TR-2	Stabilized Construction Roadway		✓		
TR-3	Entrance/Outlet Tire Wash		✓		

CONSTRUCTION SITE BMPs CONSIDERATION CHECKLIST					
The BMPs listed here should be considered for every project. Those BMPs that are not included in the SWPPP must be checked as "Not Used" with a brief statement describing why it is not being used.					
NON-STORM WATER MANAGEMENT BMPs					
BMP No.	BMP	CONSIDERED FOR PROJECT	CHECK IF USED	CHECK IF NOT USED	IF NOT USED, STATE REASON
NS-1	Water Conservation Practices		✓		
NS-2	Dewatering Operations	✓			
NS-3	Paving and Grinding Operations		✓		
NS-4	Temporary Stream Crossing			✓	NO STREAMS ON OR NEAR SITE
NS-5	Clear Water Diversion			✓	NO WATERS ON OR NEAR SITE
NS-6	Illicit Connection/ Discharge		✓		
NS-7	Potable Water/Irrigation	✓			
NS-8	Vehicle and Equipment Cleaning		✓		
NS-9	Vehicle and Equipment Fueling		✓		
NS-10	Vehicle and Equipment Maintenance		✓		
NS-11	Pile Driving Operations			✓	NO PILE DRIVING EQUIPMENT ESTIMATED FOR THIS PROJECT
NS-12	Concrete Curing		✓		
NS-13	Concrete Finishing	✓			
NS-14	Material and Equipment Use Over Water			✓	NO WATERS ON OR NEAR SITE
NS-15	Demolition Adjacent to Water			✓	NO WATERS ON OR NEAR SITE
NS-16	Temporary Batch Plants		✓		

CONSTRUCTION SITE BMPs CONSIDERATION CHECKLIST					
The BMPs listed here should be considered for every project. Those BMPs that are not included in the SWPPP must be checked as "Not Used" with a brief statement describing why it is not being used.					
WASTE MANAGEMENT AND MATERIALS POLLUTION CONTROL BMPs					
BMP No.	BMP	CONSIDERED FOR PROJECT	CHECK IF USED	CHECK IF NOT USED	IF NOT USED, STATE REASON
WM-1	Material Delivery and Storage		✓		
WM-2	Material Use		✓		
WM-3	Stockpile Management		✓		
WM-4	Spill Prevention and Control		✓		
WM-5	Solid Waste Management		✓		
WM-6	Hazardous Waste Management		✓		
WM-7	Contaminated Soil Management		✓		
WM-8	Concrete Waste Management		✓		
WM-9	Sanitary/Septic Waste Management		✓		
WM-10	Liquid Waste Management		✓		

Attachment D

Computation Sheet for Determining Runoff Coefficients

* Hydrology Report included in Attachment S

Total Site Area = 1765 Acres (A)

Existing Site Conditions (TBD IN FINAL REPORT)

Impervious Site Area ¹ = 0.0 Acres (B)

Impervious Site Area Runoff Coefficient ^{2, 4} = N/A (C)

Pervious Site Area ³ = 1765 Acres (D)

Pervious Site Area Runoff Coefficient ⁴ = 0.742 (E)

Existing Site Area Runoff Coefficient $\frac{(B \times C) + (D \times E)}{(A)}$ = 0.742 (F)

Proposed Site Conditions (after construction) (TBD IN FINAL REPORT)

Impervious Site Area ¹ = 37.3 Acres (G)

Impervious Site Area Runoff Coefficient ^{2, 4} = 0.95 (H)

Pervious Site Area ³ = 1727.7 Acres (I)

Pervious Site Area Runoff Coefficient ⁴ = 0.75 (J)

Proposed Site Area Runoff Coefficient $\frac{(G \times H) + (I \times J)}{(A)}$ = 0.7542 (K)

1. Includes paved areas, areas covered by buildings, and other impervious surfaces.
2. Use 0.95 unless lower or higher runoff coefficient can be verified.
3. Includes areas of vegetation, most unpaved or uncovered soil surfaces, and other pervious areas.
4. Refer to local Hydrology Manual for typical C values.
5. *Hydrology ESTIMATES are supplied if original report was not provided when SWPPP was submitted.

Attachment E

Computational Sheet for Determining Run-on Discharges

Existing Site Conditions

Area Runoff Coefficient	=	$\frac{\text{Varies-See}}{\text{Hydrology Study}}$	(A)
Area Rainfall Intensity	=	$\frac{\text{Varies- See}}{\text{Hydrology Study}}$	(B)
Drainage Area	=	$\frac{58,820 \text{ Acres}}{\text{See Hydrology Study}}$	(C)
Site Area Run-on Discharge (A) x (B) x (C)	=	$\frac{21,928 \text{ ft}^3/\text{sec}}{\text{See Hydrology Study}}$	(D)

Attachment F

Notice of Intent (NOI)

Attachment F

to be inserted here in

Final report

Attachment G

Program for Maintenance, Inspection, and Repair of Construction Site BMPs

<i>The contractor shall use the following guidelines for maintenance, inspection, and repair of BMPs identified in the SWPPP</i>		
BEST MANAGEMENT PRACTICES (BMPs)	INSPECTION FREQUENCY (all controls)	MAINTENANCE/REPAIR PROGRAM
TEMPORARY EROSION CONTROL BMPs*		
EC-1	Minimum requirement	*See CASQA BMP Handbook for repairs and potential alternatives. Inspect prior to rain, during rain events, and weekly during construction phasing.
EC-2	Minimum requirement	
EC-3	Applicability to site conditions	
EC-4	Applicability to site conditions	
EC-5	Applicability to site conditions	
EC-6	Applicability to site conditions	
EC-7	Applicability to site conditions	
EC-8	Applicability to site conditions	
EC-9	Applicability to site conditions	
EC-10	Applicability to site conditions	
EC-11	Applicability to site conditions	
EC-12	Applicability to site conditions	
EC-13	Applicability to site conditions	
TEMPORARY SEDIMENT CONTROL BMPs**		
SE-1	Applicability to site conditions	**See CASQA BMP Handbook for repairs and potential alternatives. Inspect prior to rain, during rain events, and weekly during construction phasing. Replacement of BMP is expected and on going until construction is done.
SE-2	Applicability to site conditions	
SE-3	Applicability to site conditions	
SE-4	Applicability to site conditions	
SE-5	Applicability to site conditions	
SE-6	Minimum requirement	
SE-7	Minimum requirement	
SE-8	Minimum requirement	
SE-9	Omitted as sediment control	
SE-10	Applicability to site conditions	
SE-11	Applicability to site conditions	
WIND EROSION CONTROL BMPs		
WE-1	As necessary due to weather or as instructed by inspector	See CASQA handbook
TRACKING CONTROL BMPs		
TC-1	As site conditions change	Stabilize to reduce tracking of dirt, mud, and other sediments onto public roads. Repair when tracking is noticeable.
TC-2	As site conditions change	
TC-3	As site conditions change	

<i>The contractor shall use the following guidelines for maintenance, inspection, and repair of BMPs identified in the SWPPP</i>		
BEST MANAGEMENT PRACTICES (BMPs)	INSPECTION FREQUENCY (all controls)	MAINTENANCE/REPAIR PROGRAM
NON-STORM WATER MANAGEMENT BMPs***		
NS-1	Minimum requirement.	***Applies to all phases of construction.
NS-2	As site conditions change	
NS-3	Minimum requirement	
NS-4	As site conditions change	
NS-5	As site conditions change	
NS-6	As site conditions change	
NS-7	As site conditions change	
NS-8	Minimum requirement	
NS-9	As site conditions change	
NS-10	Minimum requirement	
NS-11	As site conditions change	
NS-12	Minimum requirement	
NS-13	As site conditions change	
NS-14	As site conditions change	
NS-15	As site conditions change	
NS-16	As site conditions change	
WASTE MANAGEMENT AND MATERIALS POLLUTION CONTROL BMPs		
WM-1	Minimum Requirement	Inspect for damages weekly
WM-2	Minimum Requirement	Inspect for damages weekly
WM-3	Minimum Requirement	Inspect for damages weekly
WM-4	Minimum Requirement	Keep clean up materials by use ares
WM-5	Minimum Requirement	Police site. See CASQA BMP Manual.
WM-6	Minimum Requirement	Construction foreman inspects site daily.
WM-7	Minimum Requirement	Inspect for damages weekly
WM-8	Minimum Requirement	Inspect weekly for damages.
WM-9	Minimum Requirement	Arrange regular collection.
WM-10	Minimum Requirement	Inspect for damages weekly.

Attachment H

Storm Water Quality Construction Site Inspection Checklist

GENERAL INFORMATION				
Project Name				
Project N°				
Contractor				
Inspector's Name				
Inspector's Title				
Signature				
Date of Inspection				
Inspection Type (Check Applicable)	<input type="checkbox"/> Prior to forecast rain <input type="checkbox"/> After a rain event <input type="checkbox"/> 24-hr intervals during extended rain <input type="checkbox"/> Other _____			
Season (Check Applicable)	<input type="checkbox"/> Rainy <input type="checkbox"/> Non-Rainy			
Storm Data	Storm Start Date & Time:		Storm Duration (hrs):	
	Time elapsed since last storm (Circle Applicable Units)	Min. Hr. Days	Approximate Rainfall Amount (inches)	

PROJECT AREA SUMMARY AND DISTURBED SOIL AREA (DSA) SIZE	
Total Project Area	_____ Acres
Field Estimate of Active DSAs	_____ Acres
Field Estimate of Non-Active DSAs	_____ Acres

INSPECTION OF BMPs				
BMP	Yes	No	N/A	Corrective Action
Preservation of Existing Vegetation				
Is temporary fencing provided to preserve vegetation in areas where no construction activity is planned?				
Location:				
Location:				
Location:				
Location:				
Erosion Control				
Does the applied temporary erosion control provide 100% coverage for the affected areas?				
Are any non-vegetated areas that may require temporary erosion control?				
Is the area where erosion controls are used required free from visible erosion?				
Location:				
Location:				
Location:				
Location:				
Temporary Linear Sediment Barriers (Silt Fence, Fiber Rolls, Sandbag Barriers, etc.)				
Are temporary linear sediment barriers properly installed, functional and maintained?				
Are temporary linear sediment barriers free of accumulated litter?				
Is the built-up sediment less than 1/3 the height of the barrier?				
Are cross barriers installed where necessary and properly spaced?				
Location:				
Location:				
Location:				
Location:				
Location:				
Storm Drain Inlet Protection				
Are storm drain inlets internal to the project properly protected?				
Are storm drain inlet protection devices in working order and being properly maintained?				
Location:				
Location:				
Location:				
Location:				
Location:				
Sediment Basins				

INSPECTION OF BMPs				
BMP	Yes	No	N/A	Corrective Action
Are basins designed in accordance with the requirements of the General Permit?				
Are basins maintained to provide the required retention/detention?				
Are basin controls (inlets, outlets, diversions, weirs, spillways, and racks) in working order?				
Location:				
Location:				
Location:				
Location:				
Stockpiles				
Are all locations of temporary stockpiles, including soil, hazardous waste, and construction materials in approved areas?				
Are stockpiles protected from run-on, run-off from adjacent areas and from winds?				
Are stockpiles located at least 15 m from concentrated flows, downstream drainage courses and storm drain inlets?				
Are required covers and/or perimeter controls in place?				
Location:				
Location:				
Location:				
Location:				
Concentrated Flows				
Are concentrated flow paths free of visible erosion?				
Location:				
Location:				
Location:				
Location:				
Tracking Control				
Is the entrance stabilized to prevent tracking				
Is the stabilized entrance inspected daily to ensure that it is working properly				
Are points of ingress/egress to public/private roads inspected and swept and vacuumed as needed?				
Are all paved areas free of visible sediment tracking or other particulate matter?				
Location:				
Location:				
Location:				
Location:				
Wind Erosion Control				
Is dust control implemented?				

INSPECTION OF BMPs				
BMP	Yes	No	N/A	Corrective Action
Location:				
Location:				
Location:				
Location:				
Dewatering Operations				
Are all one-time dewatering operations covered by the General Permit inspected before and as they occur and BMPs implemented as necessary during discharge?				
Is ground water dewatering handled in conformance with the dewatering permit issued by the RWQCB?				
Is required treatment provided for dewatering effluent?				
Location:				
Location:				
Location:				
Location:				
Vehicle & Equipment Fueling, Cleaning, and Maintenance				
Are vehicle and equipment fueling, cleaning and maintenance areas reasonably clean and free of spills, leaks, or any other deleterious material?				
Are vehicle and equipment fueling, cleaning and maintenance activities performed on an impermeable surface in dedicated areas?				
If no, are drip pans used?				
Are dedicated fueling, cleaning, and maintenance areas located at least 15 m away from downstream drainage facilities and watercourses and protected from run-on and runoff?				
Is wash water contained for infiltration/ evaporation and disposed of appropriately?				
Is on-site cleaning limited to washing with water (no soap, soaps substitutes, solvents, or steam)?				
On each day of use, are vehicles and equipment inspected for leaks and if necessary, repaired?				
Location:				
Location:				
Location:				
Location:				
Waste Management & Materials Pollution Control				
Are material storage areas and washout areas protected from run-on and runoff, and located at least 15 m from concentrated flows and downstream drainage facilities?				
Are all material handling and storage areas clean; organized; free of spills, leaks, or any other deleterious material; and stocked with appropriate clean-up supplies?				
Are liquid materials, hazardous materials, and hazardous wastes stored in temporary containment facilities?				
Are bagged and boxed materials stored on pallets?				

INSPECTION OF BMPs				
BMP	Yes	No	N/A	Corrective Action
Are hazardous materials and wastes stored in appropriate, labeled containers?				
Are proper storage, clean-up, and spill-reporting procedures for hazardous materials and wastes posted in open, conspicuous and accessible locations adjacent to storage areas?				
Are temporary containment facilities free of spills and rainwater?				
Are temporary containment facilities and bagged/boxed materials covered?				
Are temporary concrete washout facilities designated and being used?				
Are temporary concrete washout facilities functional for receiving and containing concrete waste and are concrete residues prevented from entering the drainage system?				
Do temporary concrete washout facilities provide sufficient volume and freeboard for planned concrete operations?				
Are concrete wastes, including residues from cutting and grinding, contained and disposed of off-site or in concrete washout facilities?				
Are spills from mobile equipment fueling and maintenance properly contained and cleaned up?				
Is the site free of litter?				
Are trash receptacles provided in the yard, field trailer areas, and at locations where workers congregate for lunch and break periods?				
Is litter from work areas collected and placed in watertight dumpsters?				
Are waste management receptacles free of leaks?				
Are the contents of waste management receptacles properly protected from contact with storm water or from being dislodged by winds?				
Are waste management receptacles filled at or beyond capacity?				
Location:				
Location:				
Location:				
Location:				
Temporary Water Body Crossing or Encroachment				
Are temporary water body crossings and encroachments constructed appropriately?				
Does the project conform to the requirements of the 404 permit and/or 1601 agreement?				
Location:				
Location:				
Location:				
Location:				
Illicit Connection/ Discharge				
Is there any evidence of illicit discharges or illegal dumping on the project site?				

INSPECTION OF BMPs				
BMP	Yes	No	N/A	Corrective Action
If yes, has the Owner/Operator been notified?				
Location:				
Location:				
Location:				
Location:				
Discharge Points				
Are discharge points and discharge flows free from visible pollutants?				
Are discharge points free of any significant sediment transport?				
Location:				
Location:				
Location:				
Location:				
SWPPP Update				
Does the SWPPP and Project Schedule adequately reflect the current site conditions and contractor operations?				
Are all BMPs shown on the water pollution control drawings installed in the proper location(s) and according to the details in the SWPPP?				
Location:				
Location:				
Location:				
Location:				
General				
Are there any other potential concerns at the site?				
Location:				
Location:				
Location:				
Location:				
Storm Water Monitoring				
Does storm water discharge directly to a water body listed in the General Permit as impaired for sediment/sedimentation or turbidity?				
If yes, were samples for sediment/sedimentation or turbidity collected pursuant to the sampling and analysis plan in the SWPPP?				
Did the sampling results indicate that the discharges are causing or contributing to further impairment?				
If yes, were the erosion/sediment control BMPs improved or maintained to reduce the discharge of sediment to the water body?				

INSPECTION OF BMPs				
BMP	Yes	No	N/A	Corrective Action
Were there any BMPs not properly implemented or breaches, malfunctions, leakages or spills observed which could result in the discharge of pollutants to surface waters that would not be visually detectable in storm water?				
If yes, were samples for non-visually detectable pollutants collected pursuant to the sampling and analysis plan during rain events?				
If sampling indicated pollution of the storm water, were the leaks, breaches, spills, etc. cleaned up and the contaminated soil properly disposed of?				
Were the BMPs maintained or replaced?				
Were soil amendments (e.g., gypsum, lime) used on the project?				
If yes, were samples for non-visually detectable pollutants collected pursuant to the sampling and analysis plan in the SWPPP?				
If sampling indicated pollution of the storm water by the use of the soil amendments, is there a contingency plan for retention onsite of the polluted storm water?				
Did storm water contact stored materials or waste and run off the construction site? (Materials not in watertight containers, etc.)				
If yes, were samples for non-visually detectable pollutants collected pursuant to the sampling and analysis plan in the SWPPP?				

Attachment I

Trained Contractor Personnel Log

Storm Water Management Training Log

Project Name: _____

Project Number/Location: APN:

Storm Water Management Topic: (check as appropriate)

- ☐ Erosion Control
 - ☐ Wind Erosion Control
 - ☐ Non-storm water management
 - ☐ Storm Water Sampling
 - ☐ Sediment Control
 - ☐ Tracking Control
 - ☐ Waste Management and Materials Pollution Control

Specific Training Objective: _____

Location: _____ Date: _____

Instructor: _____ Telephone: _____

Course Length (hours): _____

Attendee Roster (attach additional forms if necessary)

[illegible]

Name	Company	Phone

COMMENTS:

Attachment J

Subcontractor Notification Letter and Notification Log

SWPPP Notification

Company
Address
City, State, ZIP

Dear Sir/Madam,

Please be advised that the California State Water Resources Control Board has adopted the General Permit (General Permit) for Storm Water Discharges Associated with Construction Activity (CAS000002). The goal of these permits is prevent the discharge of pollutants associated with construction activity from entering the storm drain system, ground and surface waters.

[Owner] has developed a Storm Water Pollution Prevention Plan (SWPPP) in order to implement the requirements of the Permits.

As a subcontractor, you are required to comply with the SWPPP and the Permits for any work that you perform on site. Any person or group who violates any condition of the Permits may be subject to substantial penalties in accordance with state and federal law. You are encouraged to advise each of your employees working on this project of the requirements of the SWPPP and the Permits. A copy of the Permits and the SWPPP are available for your review at the construction office. Please contact me if you have further questions.

Sincerely,

Name
Title

SUBCONTRACTOR NOTIFICATION LOG

Project Name: _____

Project Number/Location: _____

SUBCONTRACTOR COMPANY NAME	CONTACT NAME	ADDRESS	PHONE NUMBER	PAGER/ FIELD PHONE	DATE NOTIFICATION LETTER SENT	TYPE OF WORK

USE ADDITIONAL PAGES AS NECESSARY

Attachment K

EXAMPLE OF:

Notice of Non-Compliance

To: Name of Owner [City/Agency Engineer]/Regional Board Staff Date: Insert Date

Subject: Notice of Non-Compliance

Project Name: Insert Project Name

Project Number/Location: Project number

In accordance with the NPDES Statewide Permit for Storm Water Discharges Associated with Construction Activity, the following instance of discharge is noted:

Date, time, and location of discharge

Insert description and date of event

Nature of the operation that caused the discharge

insert description of operation

Initial assessment of any impact cause by the discharge

insert assessment

Existing BMP(s) in place prior to discharge event

list BMPs in place

Date of deployment and type of BMPs deployed after the discharge.

BMPs deployed after the discharge (with dates)

Steps taken or planned to reduce, eliminate and/or prevent recurrence of the discharge

insert steps taken to prevent recurrence

Implementation and maintenance schedule for any affected BMPs

insert implementation and maintenance schedule

If further information or a modification to the above schedule is required, notify the contact person below.

Name of Contact Person

Title

Company

Telephone Number

Signature

Date

Attachment L

Storm Water Pollution Prevention Plan (SWPPP) and Monitoring Program Checklist

CONSTRUCTION PROJECT: _____

PREPARER: _____

CONTRACT NO: _____

SECTION A: STORM WATER POLLUTION PREVENTION PLAN (SWPPP)				
CHECK IF ADDRESSED N/A IF NOT APPLICABLE	SWPPP Section	ITEM	GENERAL PERMIT REF.	COMMENTS
	100	SWPPP Certification and Approval	C.10	
	100.1	SWPPP Certification	C.10	
	100.2	SWPPP Approval	C.10	
	200	SWPPP Amendments	A.4.a, A.16	
	200.1	Amendment number and date entered into SWPPP – Amendment Log	A.4.a, A.16	
	200.2	Amendment Certification and Approval	A.4.a, A.16	
	300	Introduction/Project Description		
	300.1	Project Description and Location (narrative)	A.5.a.1	
	300.2	Unique Site Features (narrative)	A.5.a.1	
	300.4	Project Schedule (narrative and graphical)	A.5.c.5	
	400	References	A.14	
	500.2	Vicinity Map (narrative or graphic)	A.5.a.1	
	500.2	Site perimeter	A.5.a.1	
	500.2	Geographic Features	A.5.a.1	
	500.2	General topography	A.5.a.1	
	500.4	Water Pollution Control Drawings (WPCDs) (graphic or narrative)	A.5.a.2	
	500.4	Site perimeter	A.5.a.2	

SECTION A: STORM WATER POLLUTION PREVENTION PLAN (SWPPP)				
CHECK IF ADDRESSED N/A IF NOT APPLICABLE	SWPPP Section	ITEM	GENERAL PERMIT REF.	COMMENTS
	500.4	Existing and proposed buildings, lots, and roadways	A.5.a.2	
	500.4	Storm water collection and discharge points	A.5.a.2	
	500.4	General topography before and after construction	A.5.a.2	
	500.4	Anticipated discharge location(s)	A.5.a.2	
	500.4	Drainage patterns including the entire relevant drainage areas	A.5.a.2	
	500.4	Temporary on-site drainage(s)	A.5.a.2	
	500.3	Pollutant Source and BMP Identification (narrate/ or indicate on site map)	A.5.b	
		Drainage	A.5.b.1	
	500.4	Drainage patterns after major grading	A.5.b.1	
	500.4	Slopes after major grading	A.5.b.1	
	Attach. E	Calculations for storm water run-on	A.5.b.1	
	500.4	BMPs that divert off-site drainage from passing through site	A.5.b.1	
	500.4	Storm Water Inlets	A.5.b.2	
	500.4	Drainage patterns to storm water inlets or receiving water	A.5.b.2	
	500.4	BMPs that protect storm water inlets or receiving water	A.5.b.2	
		Site History (narrative; if possible, indicate location(s) on the Water Pollution Control Drawings)	A.5.b	
	500.3.3	Nature of fill material and data describing the soil. Description of toxic materials treated, stored, disposed, spilled or leaked on site	A.5.b.3	
	500.3.8 & 500.3.9	BMPs that minimize contact of contaminants with storm water	A.5.b.3	
		Location of Areas Designated for:	A.5.b.4	
	500.3.8 & 500.4	Vehicle storage & service	A.5.b.4	
	500.3.8 & 500.4	Equipment storage, cleaning, maintenance	A.5.b.4	
	500.3.9 & 500.4	Soil or waste storage	A.5.b.4	
	500.3.9 & 500.4	Construction material loading, unloading, storage and access	A.5.b.4	
	500.3.8 & 500.3.9	Areas outside of physical site (yards, borrow areas, etc.)		
		BMP Locations or Descriptions for:	A.5.b.5	
	500.3.9 & 500.4	Waste handling and disposal areas	A.5.b.5	

SECTION A: STORM WATER POLLUTION PREVENTION PLAN (SWPPP)				
CHECK IF ADDRESSED N/A IF NOT APPLICABLE	SWPPP Section	ITEM	GENERAL PERMIT REF.	COMMENTS
	500.3.9 & 500.4	On-site storage and disposal of construction materials and waste	A.5.b.5	
	500.3.8, 500.3.9 & 500.4	Minimum exposure of storm water to construction materials, equipment, vehicles, waste	A.5.b.5	
	500.6	Post Construction BMPs	A.5.b.6	
	500.6.1	Listing or Description of Post-construction BMPs	A.5.b.6	
	500.4	Location of post-construction BMPs	A.5.b.6	
	500.6.2	Parties responsible for long-term maintenance	A.5.b.6	
		Additional Information	A.5.c	
	500.3.1	Description of other pollutant sources and BMPs	A.5.c.1	
	500.3.2	Pre-construction control practices	A.5.c.1	
	500.3.1	Inventory of materials and activities that may pollute storm water	A.5.c.2	
	500.3.8 & 500.3.9	BMPs to reduce/eliminate potential pollutants listed in the inventory	A.5.c.2	
	300.4	Runoff coefficient (before & after)	A.5.c.3	
	300.4	Percent impervious (before & after)	A.5.c.3	
	Attach. F	Copy of the NOT	A.5.c.4	
	300.3	Construction activity schedule	A.5.c.5	
	300.5	Contact information	A.5.c.6	
	500.4.1	SOIL STABILIZATION (EROSION CONTROL)	A.6	
		The SWPPP shall include:	A.6.a-c	
	500.4	Areas of vegetation on site	A.6.a.1	
	500.4	Areas of soil disturbance that will be stabilized during rainy season	A.6.a.2	
	500.4	Areas of soil disturbance which will be exposed during any part of the rainy season	A.6.a.3	
	300.4	Implementation schedule for erosion control measures	A.6.a.4	
	500.3.4	BMPs for erosion control	A.6.b	
	500.3.7	BMPs to control wind erosion	A.6.c	
	500.3.5	SEDIMENT CONTROL	A.8	
	500.3.5 & 500.4	Description/Illustration of BMPs to prevent increase of sediment load in discharge	A.8	

SECTION A: STORM WATER POLLUTION PREVENTION PLAN (SWPPP)				
CHECK IF ADDRESSED N/A IF NOT APPLICABLE	SWPPP Section	ITEM	GENERAL PERMIT REF.	COMMENTS
	300.4, 500.3.5	Implementation schedule for sediment control measures	A.8	
	500.3.6	BMPs to control sediment tracking	A.8	
	500.3.8 & 500.3.9	NON-STORM WATER MANAGEMENT	A.9	
	500.3.8 & 500.3.9	Description of non-storm water discharges to receiving waters	A.9	
	500.3.8 & 500.3.9	Locations of discharges	A.9	
	500.3.8 & 500.3.9	Description of BMPs	A.9	
	300.5	Name and phone number of person responsible for non-storm water management	A.9	
	500.6	POST-CONSTRUCTION	A.10	
	500.6.1	Description of post-construction BMPs	A.10	
	500.6.2	Operation/Maintenance of BMPs after project completion (including short-term funding, long-term funding and responsible party)	A.10	
	500.5	MAINTENANCE, INSPECTIONS, AND REPAIR	A.11	
	300.5, 600.1	Name and phone number of person(s) responsible for inspections	A.11	
	600.1, Attach. H	Complete inspection checklist: date, weather, inadequate BMPs, visual observations of BMPs, corrective action, inspector's name, title, signature	A.11.a-f	
		OTHER REQUIREMENTS	A.12-16	
	500.7	Documentation of all training	A.12	
	500.8	List of Contractors/Subcontractors	A.13	

SECTION B: MONITORING AND REPORTING REQUIREMENTS				
CHECK IF ADDRESSED N/A IF NOT APPLICABLE	SWPPP Section	ITEM	GENERAL PERMIT REF.	COMMENTS
	600.1	Description of Site Inspection Plans	B.3	
	100.3	Compliance certification (annually 7/1)	B.4	
	600.2	Discharge reporting	B.5	
	600.3	Keep records of all inspections, compliance certifications, and noncompliance reports on site for a period of at least three years	B.6	
	600.4	Sampling and Analysis Plan for Sediment	B.7	

SECTION B: MONITORING AND REPORTING REQUIREMENTS				
CHECK IF ADDRESSED N/A IF NOT APPLICABLE	SWPPP Section	ITEM	GENERAL PERMIT REF.	COMMENTS
	600.5	Sampling and Analysis Plan for Non-Visible Pollutants	B.8	

SECTION C: STANDARD PROVISIONS FOR CONSTRUCTION ACTIVITIES				
CHECK IF ADDRESSED N/A IF NOT APPLICABLE	SWPPP Section	ITEM	GENERAL PERMIT REF.	COMMENTS
	100.1	Signed SWPPP Certification	C.9,10	

Attachment M

Annual Certification of Compliance Form

Project Name: _____

Project Number: _____

Company Name: _____

Address: _____

Construction Start Date: _____ **Completion Date:** _____

This project is in compliance with the General Permit and this SWPPP (check yes or no) ☐ **YES** ☐ **NO**

Description of Work:

description of work

Work Now in Progress:

work in progress

Work Planned for Next 12 Months:

work planned

"I certify under penalty of law that, during the past 12 months, the construction activities are in compliance with the requirements of the General Permit and this SWPPP. This Certification is based upon the site inspections required in Section B, Item 3 of the General Permit. This document was prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, to the best of my knowledge and belief, the information submitted is, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Owner (or Authorized Representative) Signature

Date

Name and Title

Telephone Number

Attachment N

Other Plans and Permits

- A. Copy of SWRCB Permit (CAS0000002)
Original Permit is posted on site.
Enclosed is a list of SWRCB and RWQCB Contacts.

STATE WATER RESOURCES CONTROL BOARD (SWRCB)
ORDER NO. 99 - 08 - DWQ
NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES)
GENERAL PERMIT NO. CAS000002

WASTE DISCHARGE REQUIREMENTS (WDRS)
FOR
DISCHARGES OF STORM WATER RUNOFF ASSOCIATED WITH
CONSTRUCTION ACTIVITY

The State Water Resources Control Board finds that:

1. Federal regulations for controlling pollutants in storm water runoff discharges were promulgated by the U.S. Environmental Protection Agency (USEPA) on November 16, 1990 (40 Code of Federal Regulations (CFR) Parts 122, 123, and 124). The regulations require discharges of storm water to surface waters associated with construction activity including clearing, grading, and excavation activities (except operations that result in disturbance of less than five acres of total land area and which are not part of a larger common plan of development or sale) to obtain an NPDES permit and to implement Best Available Technology Economically Achievable (BAT) and Best Conventional Pollutant Control Technology (BCT) to reduce or eliminate storm water pollution.

On December 8, 1999 federal regulations promulgated by USEPA (40CFR Parts 9, 122, 123, and 124) expanded the NPDES storm water program to include storm water discharges from municipal separate storm sewer systems (MS4s) and construction sites that were smaller than those previously included in the program. Federal regulation 40 CFR § 122.26(b)(15) defines small construction activity as including clearing, grading, and excavating that result in land disturbance of equal to or greater than one acre or less than five acres or is part of a larger common plan of development or sale. Permit applications for small construction activities are due by March 10, 2003.

2. This General Permit regulates pollutants in discharges of storm water associated with construction activity (storm water discharges) to surface waters, except from those areas on Tribal Lands; Lake Tahoe Hydrologic Unit; construction projects which disturb less than one acre, unless part of a larger common plan of development or sale; and storm water discharges which are determined ineligible for coverage under this General Permit by the California Regional Water Quality Control Boards (RWQCBs). Attachment 1 contains addresses and telephone numbers of each RWQCB office.
3. This General Permit does not preempt or supersede the authority of local storm water management agencies to prohibit, restrict, or control storm water discharges to separate storm sewer systems or other watercourses within their jurisdiction, as allowed by State and Federal law.

4. To obtain authorization for proposed storm water discharges to surface waters, pursuant to this General Permit, the landowner (discharger) must submit a Notice of Intent (NOI) with a vicinity map and the appropriate fee to the SWRCB prior to commencement of construction activities. In addition, coverage under this General Permit shall not occur until the applicant develops a Storm Water Pollution Prevention Plan (SWPPP) in accordance with the requirements of Section A of this permit for the project. For proposed construction activity conducted on easements or on nearby property by agreement or permission, or by an owner or lessee of a mineral estate (oil, gas, geothermal, aggregate, precious metals, and/or industrial minerals) entitled to conduct the activities, the entity responsible for the construction activity must submit the NOI and filing fee and shall be responsible for development of the SWPPP.
5. If an individual NPDES Permit is issued to a discharger otherwise subject to this General Permit or if an alternative General Permit is subsequently adopted which covers storm water discharges regulated by this General Permit, the applicability of this General Permit to such discharges is automatically terminated on the effective date of the individual permit or the date of approval for coverage under the subsequent General Permit.
6. This action to adopt an NPDES permit is exempt from the provisions of the California Environmental Quality Act (Public Resources Code Section 21100, et seq.) in accordance with section 13389 of the California Water Code.
7. The SWRCB adopted the California Ocean Plan, and the RWQCBs have adopted and the SWRCB has approved Water Quality Control Plans (Basin Plans). Dischargers regulated by this General Permit must comply with the water quality standards in these Basin Plans and subsequent amendments thereto.
8. The SWRCB finds storm water discharges associated with construction activity to be a potential significant sources of pollutants. Furthermore, the SWRCB finds that storm water discharges associated with construction activities have the reasonable potential to cause or contribute to an excursion above water quality standards for sediment in the water bodies listed in Attachment 3 to this permit.
9. It is not feasible at this time to establish numeric effluent limitations for pollutants in storm water discharges from construction activities. Instead, the provisions of this General Permit require implementation of Best Management Practices (BMPs) to control and abate the discharge of pollutants in storm water discharges.
10. Discharges of non-storm water may be necessary for the completion of certain construction projects. Such discharges include, but are not limited to: irrigation of vegetative erosion control measures, pipe flushing and testing, street cleaning, and dewatering. Such discharges are authorized by this General Permit as long as they (a) do comply with Section A.9 of this General Permit, (b) do not cause or contribute to violation of any water quality standard, (c) do not violate any other provision of this

General Permit, (d) do not require a non-storm water permit as issued by some RWQCBs, and (e) are not prohibited by a Basin Plan. If a non-storm water discharge is subject to a separate permit adopted by a RWQCB, the discharge must additionally be authorized by the RWQCB permit.

11. Following adoption of this General Permit, the RWQCBs shall enforce the provisions herein including the monitoring and reporting requirements.
12. Following public notice in accordance with State and Federal laws and regulations, the SWRCB in a public meeting on June 8, 1998, heard and considered all comments. The SWRCB has prepared written responses to all significant comments.
13. This Order is an NPDES permit in compliance with section 402 of the Clean Water Act (CWA) and shall take effect upon adoption by the SWRCB provided the Regional Administrator of the USEPA has no objection. If the USEPA Regional Administrator objects to its issuance, the General Permit shall not become effective until such objection is withdrawn.
14. This General Permit does not authorize discharges of fill or dredged material regulated by the U.S. Army Corps of Engineers under CWA section 404 and does not constitute a waiver of water quality certification under CWA section 401.
15. The Monitoring Program and Reporting Requirements are modified in compliance with a judgment in the case of San Francisco BayKeeper, et al. v. State Water Resources Control Board. The modifications include sampling and analysis requirements for direct discharges of sediment to waters impaired due to sediment and for pollutants that are not visually detectable in runoff that may cause or contribute to an exceedance of water quality objectives.
16. Storm water discharges associated with industrial activity that are owned or operated by municipalities serving populations less than 100,000 people are no longer exempt from the need to apply for or obtain a storm water discharge permit. A temporary exemption, which was later extended by USEPA, was provided under section 1068(c) of the Intermodal Surface Transportation and Efficiency Act (ISTEA) of 1991. Federal regulation 40 CFR § 122.26(e)(1)(ii) requires the above municipalities to submit permit application by March 10, 2003.
17. This permit may be reopened and modified to include different monitoring requirements for small construction activity than for construction activity over five (5) acres.

IT IS HEREBY ORDERED that all dischargers who file an NOI indicating their intention to be regulated under the provisions of this General Permit shall comply with the following:

A. DISCHARGE PROHIBITIONS:

1. Authorization pursuant to this General Permit does not constitute an exemption to applicable discharge prohibitions prescribed in Basin Plans, as implemented by the nine RWQCBs.
2. Discharges of material other than storm water which are not otherwise authorized by an NPDES permit to a separate storm sewer system (MS4) or waters of the nation are prohibited, except as allowed in Special Provisions for Construction Activity, C.3.
3. Storm water discharges shall not cause or threaten to cause pollution, contamination, or nuisance.
4. Storm water discharges regulated by this General Permit shall not contain a hazardous substance equal to or in excess of a reportable quantity listed in 40 CFR Part 117 and/or 40 CFR Part 302.

B. RECEIVING WATER LIMITATIONS:

1. Storm water discharges and authorized nonstorm water discharges to any surface or ground water shall not adversely impact human health or the environment.
2. The SWPPP developed for the construction activity covered by this General Permit shall be designed and implemented such that storm water discharges and authorized nonstorm water discharges shall not cause or contribute to an exceedance of any applicable water quality standards contained in a Statewide Water Quality Control Plan and/or the applicable RWQCB's Basin Plan.
3. Should it be determined by the discharger, SWRCB, or RWQCB that storm water discharges and/or authorized nonstorm water discharges are causing or contributing to an exceedance of an applicable water quality standard, the discharger shall:
 - a. Implement corrective measures immediately following discovery that water quality standards were exceeded, followed by notification to the RWQCB by telephone as soon as possible but no later than 48 hours after the discharge has been discovered. This notification shall be followed by a report within 14-calendar days to the appropriate RWQCB, unless otherwise directed by the RWQCB, describing (1) the nature and cause of the water quality standard exceedance; (2) the BMPs currently being implemented; (3) any additional BMPs which will be implemented to

prevent or reduce pollutants that are causing or contributing to the exceedance of water quality standards; and (4) any maintenance or repair of BMPs. This report shall include an implementation schedule for corrective actions and shall describe the actions taken to reduce the pollutants causing or contributing to the exceedance.

- b. The discharger shall revise its SWPPP and monitoring program immediately after the report to the RWQCB to incorporate the additional BMPs that have been and will be implemented, the implementation schedule, and any additional monitoring needed.
- c. Nothing in this section shall prevent the appropriate RWQCB from enforcing any provisions of this General Permit while the discharger prepares and implements the above report.

C. SPECIAL PROVISIONS FOR CONSTRUCTION ACTIVITY:

- 1. All dischargers shall file an NOI and pay the appropriate fee for construction activities conducted at each site as required by Attachment 2: Notice of Intent--General Instructions.
- 2. All dischargers shall develop and implement a SWPPP in accordance with Section A: Storm Water Pollution Prevention Plan. The discharger shall implement controls to reduce pollutants in storm water discharges from their construction sites to the BAT/BCT performance standard.
- 3. Discharges of non-storm water are authorized only where they do not cause or contribute to a violation of any water quality standard and are controlled through implementation of appropriate BMPs for elimination or reduction of pollutants. Implementation of appropriate BMPs is a condition for authorization of non-storm water discharges. Non-storm water discharges and the BMPs appropriate for their control must be described in the SWPPP. Wherever feasible, alternatives which do not result in discharge of nonstorm water shall be implemented in accordance with Section A.9. of the SWPPP requirements.
- 4. All dischargers shall develop and implement a monitoring program and reporting plan in accordance with Section B: Monitoring Program and Reporting Requirements.
- 5. All dischargers shall comply with the lawful requirements of municipalities, counties, drainage districts, and other local agencies regarding discharges of storm water to separate storm sewer systems or other watercourses under their jurisdiction, including applicable requirements in municipal storm water management programs developed to comply with NPDES permits issued by the RWQCBs to local agencies.

6. All dischargers shall comply with the standard provisions and reporting requirements contained in Section C: Standard Provisions.
7. The discharger may terminate coverage for a portion of the project under this General Permit when ownership of a portion of this project has been transferred or when a phase within this multi-phase project has been completed. When ownership has transferred, the discharger must submit to its RWQCB a Change of Information Form (COI) Attachment 4 with revised site map and the name, address and telephone number of the new owner(s). Upon transfer of title, the discharger should notify the new owner(s) of the need to obtain coverage under this General Permit. The new owner must comply with provisions of Sections A. 2. (c) and B. 2. (b) of this General Permit. To terminate coverage for a portion of the project when a phase has been completed, the discharger must submit to its RWQCB a COI with a revised map that identifies the newly delineated site.
8. The discharger may terminate coverage under this General Permit for a complete project by submitting to its RWQCB a Notice of Termination Form (NOT), and the post-construction BMPs plan according to Section A.10 of this General Permit. Note that a construction project is considered complete only when all portions of the site have been transferred to a new owner; or the following conditions have been met:
 - a. There is no potential for construction related storm water pollution,
 - b. All elements of the SWPPP have been completed,
 - c. Construction materials and waste have been disposed of properly,
 - d. The site is in compliance with all local storm water management requirements, and
 - e. A post-construction storm water management plan is in place as described in the site's SWPPP.
9. This General Permit expires five years from the date of adoption.

D. REGIONAL WATER QUALITY CONTROL BOARD (RWQCB) AUTHORITIES:

1. RWQCBs shall:
 - a. Implement the provisions of this General Permit. Implementation of this General Permit may include, but is not limited to requesting the submittal of SWPPPS, reviewing SWPPPs, reviewing monitoring reports, conducting compliance inspections, and taking enforcement actions.
 - b. Issue permits as they deem appropriate to individual dischargers, categories of dischargers, or dischargers in a geographic area. Upon issuance of such permits by a RWQCB, the affected dischargers shall no longer be regulated by this General Permit.
2. RWQCBs may require, on a case-by-case basis, the inclusion of an analysis of potential downstream impacts on receiving waterways due to the permitted construction.
3. RWQCBs may provide information to dischargers on the development and implementation of SWPPPs and monitoring programs and may require revisions to SWPPPs and monitoring programs.
4. RWQCBs may require dischargers to retain records for more than three years.
5. RWQCBs may require additional monitoring and reporting program requirements including sampling and analysis of discharges to water bodies listed in Attachment 3 to this permit. Additional requirements imposed by the RWQCB should be consistent with the overall monitoring effort in the receiving waters.
6. RWQCBs may issue individual NPDES permits for those construction activities found to be ineligible for coverage under this permit.

CERTIFICATION

The undersigned, Administrative Assistant to the Board, does hereby certify that the foregoing is a full, true, and correct copy of an order duly and regularly adopted at a meeting of the State Water Resources Control Board held on August 19, 1999.

AYE: James M. Stubchaer
Mary Jane Forster
John W. Brown
Arthur G. Baggett, Jr.

NO: None

ABSENT: None

ABSTAIN: None

_____/s/
Maureen Marché
Administrative Assistant to the Board

SECTION A: STORM WATER POLLUTION PREVENTION PLAN

1. Objectives

A Storm Water Pollution Prevention Plan (SWPPP) shall be developed and implemented to address the specific circumstances for each construction site covered by this General Permit. The SWPPP shall be certified in accordance with the signatory requirements of section C, Standard Provision for Construction Activities (9). The SWPPP shall be developed and amended or revised, when necessary, to meet the following objectives:

- a. Identify all pollutant sources including sources of sediment that may affect the quality of storm water discharges associated with construction activity (storm water discharges) from the construction site, and
- b. Identify non-storm water discharges, and
- c. Identify, construct, implement in accordance with a time schedule, and maintain Best Management Practices (BMPs) to reduce or eliminate pollutants in storm water discharges and authorized nonstorm water discharges from the construction site during construction, and
- d. Develop a maintenance schedule for BMPs installed during construction designed to reduce or eliminate pollutants after construction is completed (post-construction BMPs).
- e. Identify a sampling and analysis strategy and sampling schedule for discharges from construction activity which discharge directly into water bodies listed on Attachment 3. (Clean Water Act Section 303(d) [303(d)] Water Bodies listed for Sedimentation).
- f. For all construction activity, identify a sampling and analysis strategy and sampling schedule for discharges that have been discovered through visual monitoring to be potentially contaminated by pollutants not visually detectable in the runoff.

2. Implementation Schedule

- a. For construction activity commencing on or after adoption of this General Permit, the SWPPP shall be developed prior to the start of soil-disturbing activity in accordance with this Section and shall be implemented concurrently with commencement of soil-disturbing activities.
- b. Existing permittees engaging in construction activities covered under the terms of the previous General Construction Permit SWPPP (WQ Order No.92-08-DWQ) shall continue to implement their existing SWPPP and shall implement any

necessary revisions to their SWPPP in accordance with this Section of the General Permit in a timely manner, but in no case more than 90-calender days from the date of adoption of this General Permit.

- c. For ongoing construction activity involving a change of ownership of property, the new owner shall review the existing SWPPP and amend if necessary, or develop a new SWPPP within 45-calender days.
- d. Existing permittees shall revise their SWPPP in accordance with the sampling and analysis modifications prior to August 1, 2001. For ongoing construction activity involving a change of ownership the new owner shall review the existing SWPPP and amend the sampling and analysis strategy, if required, within 45 days. For construction activity commencing after the date of adoption, the SWPPP shall be developed in accordance with the modification language adopted.

3. Availability

The SWPPP shall remain on the construction site while the site is under construction during working hours, commencing with the initial construction activity and ending with termination of coverage under the General Permit.

4. Required Changes

- a. The discharger shall amend the SWPPP whenever there is a change in construction or operations which may affect the discharge of pollutants to surface waters, ground waters, or a municipal separate storm sewer system (MS4). The SWPPP shall also be amended if the discharger violates any condition of this General Permit or has not achieved the general objective of reducing or eliminating pollutants in storm water discharges. If the RWQCB determines that the discharger is in violation of this General Permit, the SWPPP shall be amended and implemented in a timely manner, but in no case more than 14-calendar days after notification by the RWQCB. All amendments should be dated and directly attached to the SWPPP.
- b. The RWQCB or local agency with the concurrence of the RWQCB may require the discharger to amend the SWPPP.

5. Source Identification

The SWPPP shall include: (a) project information and (b) pollutant source identification combined with an itemization of those BMPs specifically chosen to control the pollutants listed.

- a. Project Information

- (1) The SWPPP shall include a vicinity map locating the project site with respect to easily identifiable major roadways, geographic features, or landmarks. At a minimum, the map must show the construction site perimeter, the geographic features surrounding the site, and the general topography.
- (2) The SWPPP shall include a site map(s) which shows the construction project in detail, including the existing and planned paved areas and buildings.
 - (a) At a minimum, the map must show the construction site perimeter; existing and proposed buildings, lots, roadways, storm water collection and discharge points; general topography both before and after construction; and the anticipated discharge location(s) where the storm water from the construction site discharges to a municipal storm sewer system or other water body.
 - (b) The drainage patterns across the project area must clearly be shown on the map, and the map must extend as far outside the site perimeter as necessary to illustrate the relevant drainage areas. Where relevant drainage areas are too large to depict on the map, map notes or inserts illustrating the upstream drainage areas are sufficient.
 - (c) Temporary on-site drainages to carry concentrated flow shall be selected to comply with local ordinances, to control erosion, to return flows to their natural drainage courses, and to prevent damage to downstream properties.
3. Information presented in the SWPPP may be represented either by narrative or by graphics. Where possible, narrative descriptions should be plan notes. Narrative descriptions which do not lend themselves to plan notes can be contained in a separate document which must be referenced on the plan.

b. Pollutant Source and BMP Identification

The SWPPP shall include a description of potential sources which are likely to add pollutants to storm water discharges or which may result in nonstorm water discharges from the construction site. Discharges originating from off-site which flow across or through areas disturbed by construction that may contain pollutants should be reported to the RWQCB.

The SWPPP shall:

- (1) Show drainage patterns and slopes anticipated after major grading activities are completed. Runoff from off-site areas should be prevented from flowing through areas that have been disturbed by construction unless appropriate conveyance systems are in place. The amount of anticipated storm water run-on must be considered to determine the appropriateness of the BMPs chosen. Show all calculations for anticipated storm water run-on, and describe all BMPs implemented to divert off-site drainage described in section A. 5 a. (2) (c) around or through the construction project.
- (2) Show the drainage patterns into each on-site storm water inlet point or receiving water. Show or describe the BMPs that will protect operational storm water inlets or receiving waters from contaminated discharges other than sediment discharges, such as, but not limited to: storm water with elevated pH levels from contact with soil amendments such as lime or gypsum; slurry from sawcutting of concrete or asphalt ;washing of exposed aggregate concrete; concrete rinse water; building washing operations; equipment washing operations; minor street washing associated with street delineation; and/or sealing and paving activities occurring during rains.
- (3) Show existing site features that, as a result of known past usage, may contribute pollutants to storm water, (e.g., toxic materials that are known to have been treated, stored, disposed, spilled, or leaked onto the construction site). Show or describe the BMPs implemented to minimize the exposure of storm water to contaminated soil or toxic materials.
- (4) Show areas designated for the (a) storage of soil or waste, (b) vehicle storage and service areas, (c) construction material loading, unloading, and access areas, (d) equipment storage, cleaning, and maintenance areas.
- (5) Describe the BMPs for control of discharges from waste handling and disposal areas and methods of on-site storage and disposal of construction materials and construction waste. Describe the BMPs designed to minimize or eliminate the exposure of storm water to construction materials, equipment, vehicles, waste storage areas, or service areas. The BMPs described shall be in compliance with Federal, State, and local laws, regulations, and ordinances.
- (6) Describe all post-construction BMPs for the project, and show the location of each BMP on the map. (Post-construction BMPs consist of permanent features designed to minimize pollutant discharges, including sediment, from the site after construction has been completed.) Also, describe the agency or parties to be the responsible party for long-term maintenance of these BMPs.

- (7) Show the locations of direct discharge from the construction site into a Section 303(d) list water body. Show the designated sampling locations in the receiving waters, which represent the prevailing conditions of the water bodies upstream of the construction site discharge and immediately downstream from the last point of discharge.
- (8) Show the locations designated for sampling the discharge from areas identified in Section A. 5. b. (2), (3), and (4) and Section A. 5. c. (1) and (2). Samples shall be taken should visual monitoring indicate that there has been a breach, malfunction, leakage, or spill from a BMP which could result in the discharge in storm water of pollutants that would not be visually detectable, or if storm water comes into contact with soil amendments or other exposed materials or contamination and is allowed to be discharged. Describe the sampling procedure, location, and rationale for obtaining the uncontaminated sample of storm water.

c. Additional Information

- (1) The SWPPP shall include a narrative description of pollutant sources and BMPs that cannot be adequately communicated or identified on the site map. In addition, a narrative description of preconstruction control practices (if any) to reduce sediment and other pollutants in storm water discharges shall be included.
- (2) The SWPPP shall include an inventory of all materials used and activities performed during construction that have the potential to contribute to the discharge of pollutants other than sediment in storm water. Describe the BMPs selected and the basis for their selection to eliminate or reduce these pollutants in the storm water discharges.
- (3) The SWPPP shall include the following information regarding the construction site surface area: the size (in acres or square feet), the runoff coefficient before and after construction, and the percentage that is impervious (e.g., paved, roofed, etc.) before and after construction.
- (4) The SWPPP shall include a copy of the NOI, and the Waste Discharge Identification (WDID) number. Should a WDID number not be received from the SWRCB at the time construction commences, the discharger shall include proof of mailing of the NOI, e.g., certified mail receipt, copy of check, express mail receipt, etc.
- (5) The SWPPP shall include a construction activity schedule which describes all major activities such as mass grading, paving, lot or parcel

improvements at the site and the proposed time frame to conduct those activities.

- (6) The SWPPP shall list the name and telephone number of the qualified person(s) who have been assigned responsibility for prestorm, poststorm, and storm event BMP inspections; and the qualified person(s) assigned responsibility to ensure full compliance with the permit and implementation of all elements of the SWPPP, including the preparation of the annual compliance evaluation and the elimination of all unauthorized discharges.

6. Erosion Control

Erosion control, also referred to as “soil stabilization” is the most effective way to retain soil and sediment on the construction site. The most efficient way to address erosion control is to preserve existing vegetation where feasible, to limit disturbance, and to stabilize and revegetate disturbed areas as soon as possible after grading or construction. Particular attention must be paid to large mass-graded sites where the potential for soil exposure to the erosive effects of rainfall and wind is great. Mass graded construction sites may be exposed for several years while the project is being built out. Thus, there is potential for significant sediment discharge from the site to surface waters.

At a minimum, the discharger/operator must implement an effective combination of erosion and sediment control on all disturbed areas during the rainy season. These disturbed areas include rough graded roadways, slopes, and building pads. Until permanent vegetation is established, soil cover is the most cost-effective and expeditious method to protect soil particles from detachment and transport by rainfall. Temporary soil stabilization can be the single-most important factor in reducing erosion at construction sites. The discharger shall consider measures such as: covering with mulch, temporary seeding, soil stabilizers, binders, fiber rolls or blankets, temporary vegetation, permanent seeding, and a variety of other measures.

The SWPPP shall include a description of the erosion control practices, including a time schedule, to be implemented during construction to minimize erosion on disturbed areas of a construction site. The discharger must consider the full range of erosion control BMPs. The discharger must consider any additional site-specific and seasonal conditions when selecting and implementing appropriate BMPs. The above listed erosion control measures are examples of what should be considered and are not exclusive of new or innovative approaches currently available or being developed.

- a. The SWPPP shall include:

- (1) An outline of the areas of vegetative soil cover or native vegetation onsite which will remain undisturbed during the construction project.
 - (2) An outline of all areas of soil disturbance including cut or fill areas which will be stabilized during the rainy season by temporary or permanent erosion control measures, such as seeding, mulch, or blankets, etc.
 - (3) An outline of the areas of soil disturbance, cut, or fill which will be left exposed during any part of the rainy season, representing areas of potential soil erosion where sediment control BMPs are required to be used during construction.
 - (4) A proposed schedule for the implementation of erosion control measures.
- b. The SWPPP shall include a description of the BMPs and control practices to be used for both temporary and permanent erosion control measures.
 - c. The SWPPP shall include a description of the BMPs to reduce wind erosion at all times, with particular attention paid to stock-piled materials.

7. Stabilization

- (1) All disturbed areas of the construction site must be stabilized. Final stabilization for the purposes of submitting a NOT is satisfied when:
 - All soil disturbing activities are completed AND EITHER OF THE TWO FOLLOWING CRITERIA ARE MET:
 - A uniform vegetative cover with 70 percent coverage has been established OR:
 - equivalent stabilization measures have been employed. These measures include the use of such BMPs as blankets, reinforced channel liners, soil cement, fiber matrices, geotextiles, or other erosion resistant soil coverings or treatments.
- (2) Where background native vegetation covers less than 100 percent of the surface, such as in arid areas, the 70 percent coverage criteria is adjusted as follows: If the native vegetation covers 50 percent of the ground surface, 70 percent of 50 percent ($.70 \times .50 = .35$) would require 35 percent total uniform surface coverage.

8. Sediment Control

The SWPPP shall include a description or illustration of BMPs which will be implemented to prevent a net increase of sediment load in storm water discharge relative to preconstruction levels. Sediment control BMPs are required at appropriate locations along the site perimeter and at all operational internal inlets to the storm drain system at all times during the rainy season. Sediment control practices may include filtration devices and barriers (such as fiber rolls, silt fence, straw bale barriers, and gravel inlet filters) and/or settling devices (such as sediment traps or basins). Effective filtration devices, barriers, and settling devices shall be selected, installed and maintained properly. A proposed schedule for deployment of sediment control BMPs shall be included in the SWPPP. These are the most basic measures to prevent sediment from leaving the project site and moving into receiving waters. Limited exemptions may be authorized by the RWQCB when work on active areas precludes the use of sediment control BMPs temporarily. Under these conditions, the SWPPP must describe a plan to establish perimeter controls prior to the onset of rain.

During the nonrainy season, the discharger is responsible for ensuring that adequate sediment control materials are available to control sediment discharges at the downgrade perimeter and operational inlets in the event of a predicted storm. The discharger shall consider a full range of sediment controls, in addition to the controls listed above, such as straw bale dikes, earth dikes, brush barriers, drainage swales, check dams, subsurface drain, sandbag dikes, fiber rolls, or other controls. At a minimum, the discharger/operator must implement an effective combination of erosion and sediment control on all disturbed areas during the rainy season.

If the discharger chooses to rely on sediment basins for treatment purposes, sediment basins shall, at a minimum, be designed and maintained as follows:

Option 1: Pursuant to local ordinance for sediment basin design and maintenance, provided that the design efficiency is as protective or more protective of water quality than Option 3.

OR

Option 2: Sediment basin(s), as measured from the bottom of the basin to the principal outlet, shall have at least a capacity equivalent to 3,600 cubic feet of storage per acre draining into the sediment basin. The length of the basin shall be more than twice the width of the basin. The length is determined by measuring the distance between the inlet and the outlet; and the depth must not be less than three feet nor greater than five feet for safety reasons and for maximum efficiency.

OR

Option 3: Sediment basin(s) shall be designed using the standard equation:

$$As=1.2Q/Vs$$

Where: As is the minimum surface area for trapping soil particles of a certain size; Vs is the settling velocity of the design particle size chosen; and $Q=C \times I \times A$ where Q is the discharge rate measured in cubic feet per second; C is the runoff coefficient; I is the precipitation intensity for the 10-year, 6-hour rain event and A is the area draining into the sediment basin in acres. The design particle size shall be the smallest soil grain size determined by wet sieve analysis, or the fine silt sized (0.01mm) particle, and the Vs used shall be 100 percent of the calculated settling velocity.

The length is determined by measuring the distance between the inlet and the outlet; the length shall be more than twice the dimension as the width; the depth shall not be less than three feet nor greater than five feet for safety reasons and for maximum efficiency (two feet of storage, two feet of capacity). The basin(s) shall be located on the site where it can be maintained on a year-round basis and shall be maintained on a schedule to retain the two feet of capacity;

OR

Option 4: The use of an equivalent surface area design or equation, provided that the design efficiency is as protective or more protective of water quality than Option 3.

A sediment basin shall have a means for dewatering within 7-calendar days following a storm event. Sediment basins may be fenced if safety (worker or public) is a concern.

The outflow from a sediment basin that discharges into a natural drainage shall be provided with outlet protection to prevent erosion and scour of the embankment and channel.

The discharger must consider any additional site-specific and seasonal conditions when selecting and designing sediment control BMPs. The above listed sediment control measures are examples of what should be considered and are not exclusive of new or innovative approaches currently available or being developed.

The SWPPP shall include a description of the BMPs to reduce the tracking of sediment onto public or private roads at all times. These public and private roads shall be inspected and cleaned as necessary. Road cleaning BMPs shall be discussed in the SWPPP and will not rely on the washing of accumulated sediment or silt into the storm drain system.

9. Non-Storm Water Management

Describe all non-storm water discharges to receiving waters that are proposed for the construction project. Non-storm water discharges should be eliminated or reduced to the extent feasible. Include the locations of such discharges and descriptions of all BMPs designed for the control of pollutants in such discharges. Onetime discharges shall be monitored during the time that such discharges are occurring. A qualified person should be assigned the responsibility for ensuring that no materials other than storm water are discharged in quantities which will have an adverse effect on receiving waters or storm drain systems (consistent with BAT/BCT), and the name and contact number of that person should be included in the SWPPP document.

Discharging sediment-laden water which will cause or contribute to an exceedance of the applicable RWQCB's Basin Plan from a dewatering site or sediment basin into any receiving water or storm drain without filtration or equivalent treatment is prohibited.

10. Post-Construction Storm Water Management

The SWPPP shall include descriptions of the BMPs to reduce pollutants in storm water discharges after all construction phases have been completed at the site (Post-Construction BMPs). Post-Construction BMPs include the minimization of land disturbance, the minimization of impervious surfaces, treatment of storm water runoff using infiltration, detention/retention, biofilter BMPs, use of efficient irrigation systems, ensuring that interior drains are not connected to a storm sewer system, and appropriately designed and constructed energy dissipation devices. These must be consistent with all local post-construction storm water management requirements, policies, and guidelines. The discharger must consider site-specific and seasonal conditions when designing the control practices. Operation and maintenance of control practices after construction is completed shall be addressed, including short-and long-term funding sources and the responsible party.

11. Maintenance, Inspection, and Repair

The SWPPP shall include a discussion of the program to inspect and maintain all BMPs as identified in the site plan or other narrative documents throughout the entire duration of the project. A qualified person will be assigned the responsibility to conduct inspections. The name and telephone number of that person shall be listed in the SWPPP document. Inspections will be performed before and after storm events and once each 24-hour period during extended storm events to identify BMP effectiveness and implement repairs or design changes as soon as feasible depending upon field conditions. Equipment, materials, and workers must be available for rapid response to failures and emergencies. All corrective maintenance to BMPs shall be performed as soon as possible after the conclusion of each storm depending upon worker safety.

For each inspection required above, the discharger shall complete an inspection checklist. At a minimum, an inspection checklist shall include:

- a. Inspection date.

- b. Weather information: best estimate of beginning of storm event, duration of event, time elapsed since last storm, and approximate amount of rainfall (inches).
- c. A description of any inadequate BMPs.
- d. If it is possible to safely access during inclement weather, list observations of all BMPs: erosion controls, sediment controls, chemical and waste controls, and non-storm water controls. Otherwise, list result of visual inspection at relevant outfall, discharge point, or downstream location and projected required maintenance activities.
- e. Corrective actions required, including any changes to SWPPP necessary and implementation dates.
- f. Inspectors name, title, and signature.

The dischargers shall prepare their inspection checklists using the inspection checklist form provided by the SWRCB or RWQCB or on forms that contain the equivalent information.

12. Training

Individuals responsible for SWPPP preparation, implementation, and permit compliance shall be appropriately trained, and the SWPPP shall document all training. This includes those personnel responsible for installation, inspection, maintenance, and repair of BMPs. Those responsible for overseeing, revising, and amending the SWPPP shall also document their training. Training should be both formal and informal, occur on an ongoing basis when it is appropriate and convenient, and should include training/workshops offered by the SWRCB, RWQCB, or other locally recognized agencies or professional organizations.

13. List of Contractors/Subcontractors

The SWPPP shall include a list of names of all contractors, (or subcontractors) and individuals responsible for implementation of the SWPPP. This list should include telephone numbers and addresses. Specific areas of responsibility of each subcontractor and emergency contact numbers should also be included.

14. Other Plans

This SWPPP may incorporate by reference the appropriate elements of other plans required by local, State, or Federal agencies. A copy of any requirements incorporated by reference shall be kept at the construction site.

15. Public Access

The SWPPP shall be provided, upon request, to the RWQCB. The SWPPP is considered a report that shall be available to the public by the RWQCB under section 308(b) of the Clean Water Act.

16. Preparer Certification

The SWPPP and each amendment shall be signed by the landowner (discharger) or his representative and include the date of initial preparation and the date of each amendment.

SECTION B: MONITORING PROGRAM AND REPORTING REQUIREMENTS

1. Required Changes

The RWQCB may require the discharger to conduct additional site inspections, to submit reports and certifications, or perform sampling and analysis.

2. Implementation

- a. The requirements of this Section shall be implemented at the time of commencement of construction activity (see also Section A. 2. Implementation Schedule). The discharger is responsible for implementing these requirements until construction activity is complete and the site is stabilized.
- b. For ongoing construction activity involving a change in ownership of property covered by this General Permit, the new owner must complete a NOI and implement the requirements of this Section concurrent with the change of ownership. For changes of information, the owner must follow instructions in C. 7. Special Provisions for Construction Activity of the General Permit.

3. Site Inspections

Qualified personnel shall conduct inspections of the construction site prior to anticipated storm events, during extended storm events, and after actual storm events to identify areas contributing to a discharge of storm water associated with construction activity. The name(s) and contact number(s) of the assigned inspection personnel shall be listed in the SWPPP. Pre-storm inspections are to ensure that BMPs are properly installed and maintained; post-storm inspections are to assure that the BMPs have functioned adequately. During extended storm events, inspections shall be required each 24-hour period. Best Management Practices (BMPs) shall be evaluated for adequacy and proper implementation and whether additional BMPs are required in accordance with the terms of the General Permit (see language in Section A. 11. Maintenance, Inspection, and Repair). Implementation of nonstorm water discharge BMPs shall be verified and their

effectiveness evaluated. One time discharges of non-storm water shall be inspected when such discharges occur.

4. Compliance Certification

Each discharger or qualified assigned personnel listed by name and contact number in the SWPPP must certify annually that construction activities are in compliance with the requirements of this General Permit and the SWPPP. This Certification shall be based upon the site inspections required in Item 3 of this Section. The certification must be completed by July 1 of each year.

5. Noncompliance Reporting

Dischargers who cannot certify compliance, in accordance with Item 4 of this Section and/or who have had other instances of noncompliance excluding exceedances of water quality standards as defined in section B. 3. Receiving Water Limitations Language, shall notify the appropriate RWQCB within 30 days. Corrective measures should be implemented immediately following discovery that water quality standards were exceeded. The notifications shall identify the noncompliance event, including an initial assessment of any impact caused by the event; describe the actions necessary to achieve compliance; and include a time schedule subject to the modifications by the RWQCB indicating when compliance will be achieved. Noncompliance notifications must be submitted within 30-calendar days of identification of noncompliance.

6. Monitoring Records

Records of all inspections, compliance certifications, and noncompliance reporting must be retained for a period of at least three years from the date generated. With the exception of noncompliance reporting, dischargers are not required to submit these records.

7. Monitoring Program for Sedimentation/Siltation

Dischargers of storm water associated with construction activity that directly enters a water body listed in Attachment 3 shall conduct a sampling and analysis program for the pollutants (sedimentation/siltation or turbidity) causing the impairment. The discharger shall monitor for the applicable parameter. If the water body is listed for sedimentation or siltation, samples should be analyzed for Settleable Solids (ml/l) and Total Suspended Solids (mg/l). Alternatively or in addition, samples may be analyzed for suspended sediment concentration according to ASTM D3977-97. If the water body is listed for turbidity, samples should be analyzed for turbidity (NTU). Discharges that flow through tributaries that are not listed in Attachment 3 or that flow into Municipal Separate Storm Sewer Systems (MS4) are not subject to these sampling and analysis requirements. The sampling and analysis parameters and procedures must be designed to determine whether the BMPs installed and maintained prevent discharges of sediment from contributing to impairment in receiving waters.

Samples shall be collected during the first two hours of discharge from rain events which result in a direct discharge to any water body listed in Attachment 3. Samples shall be collected during daylight hours (sunrise to sunset). Dischargers need not collect more than four (4) samples per month. All samples shall be taken in the receiving waters and shall be representative of the prevailing conditions of the water bodies. Samples shall be collected from safely accessible locations upstream of the construction site discharge and immediately downstream from the last point of discharge.

For laboratory analysis, all sampling, sample preservation, and analyses must be conducted according to test procedures under 40 CFR Part 136. Field samples shall be collected and analyzed according to the specifications of the manufacturer of the sampling devices employed. Portable meters shall be calibrated according to manufacturer's specification. All field and/or laboratory analytical data shall be kept in the SWPPP document, which is to remain at the construction site at all times until a Notice of Termination has been submitted and approved.

8. Monitoring Program for Pollutants Not Visually Detectable in Storm Water

A sampling and analysis program shall be developed and conducted for pollutants which are not visually detectable in storm water discharges, which are or should be known to occur on the construction site, and which could cause or contribute to an exceedance of water quality objectives in the receiving water. Pollutants that should be considered for inclusion in this sampling and analysis program are those identified in Sections A.5.b. and A.5.c.

Construction materials and compounds that are not stored in water-tight containers under a water-tight roof or inside a building are examples of materials for which the discharger may have to implement sampling and analysis procedures. The goal of the sampling and analysis is to determine whether the BMPs employed and maintained on site are effective in preventing the potential pollutants from coming in contact with storm water and causing or contributing to an exceedance of water quality objectives in the receiving waters. Examples of construction sites that may require sampling and analysis include: sites that are known to have contaminants spilled or spread on the ground; sites where construction practices include the application of soil amendments, such as gypsum, which can increase the pH of the runoff; or sites having uncovered stockpiles of material exposed to storm water. Visual observations before, during, and after storm events may trigger the requirement to collect samples. Any breach, malfunction, leakage, or spill observed which could result in the discharge of pollutants to surface waters that *would* not be visually detectable in storm water shall trigger the collection of a sample of discharge. Samples shall be collected at all discharge locations which drain the areas identified by the visual observations and which can be safely accessed. For sites where sampling and analysis is required, personnel trained in water quality sampling procedures shall collect storm water samples. A sufficiently large sample of storm water that has not come in contact with the disturbed soil or the materials stored or used on-site

(uncontaminated sample) shall be collected for comparison with the discharge sample. Samples shall be collected during the first two hours of discharge from rain events that occur during daylight hours and which generate runoff.

The uncontaminated sample shall be compared to the samples of discharge using field analysis or through laboratory analysis. Analyses may include, but are not limited to, indicator parameters such as: pH, specific conductance, dissolved oxygen, conductivity, salinity, and TDS.

For laboratory analysis, all sampling, sample preservation, and analyses must be conducted according to test procedures under 40 CFR Part 136. Field discharge samples shall be collected and analyzed according to the specifications of the manufacturer of the sampling devices employed. Portable meters shall be calibrated according to manufacturer's specification. All field and/or analytical data shall be kept in the SWPPP document, which is to remain at the construction site at all times until a *Notice of Termination* has been submitted and approved.

SECTION C: STANDARD PROVISIONS FOR CONSTRUCTION ACTIVITY

1. Duty to Comply

The discharger must comply with all of the conditions of this General Permit. Any permit noncompliance constitutes a violation of the Clean Water Act (CWA) and the Porter-Cologne Water Quality Control Act and is grounds for enforcement action and/or removal from General Permit coverage.

The discharger shall comply with effluent standards or prohibitions established under Section 307(a) of the CWA for toxic pollutants within the time provided in the regulations that establish these standards or prohibitions, even if this General Permit has not yet been modified to incorporate the requirement.

2. General Permit Actions

This General Permit may be modified, revoked and reissued, or terminated for cause. The filing of a request by the discharger for a General Permit modification, revocation and reissuance, or termination, or a notification of planned changes or anticipated noncompliance does not annul any General Permit condition.

If any toxic effluent standard or prohibition (including any schedule of compliance specified in such effluent standard or prohibition) is promulgated under Section 307(a) of the CWA for a toxic pollutant which is present in the discharge and that standard or prohibition is more stringent than any limitation on the pollutant in this General Permit, this General Permit shall be modified or revoked and reissued to conform to the toxic effluent standard or prohibition and the dischargers so notified.

3. Need to Halt or Reduce Activity Not a Defense

It shall not be a defense for a discharger in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of this General Permit.

4. Duty to Mitigate

The discharger shall take all responsible steps to minimize or prevent any discharge in violation of this General Permit, which has a reasonable likelihood of adversely affecting human health or the environment.

5. Proper Operation and Maintenance

The discharger shall at all times properly operate and maintain any facilities and systems of treatment and control (and related appurtenances) which are installed or used by the discharger to achieve compliance with the conditions of this General Permit and with the requirements of Storm Water Pollution Prevention Plans (SWPPP). Proper operation and maintenance also includes adequate laboratory controls and appropriate quality assurance procedures. Proper operation and maintenance may require the operation of backup or auxiliary facilities or similar systems installed by a discharger when necessary to achieve compliance with the conditions of this General Permit.

6. Property Rights

This General Permit does not convey any property rights of any sort or any exclusive privileges, nor does it authorize any injury to private property or any invasion of personal rights, nor does it authorize any infringement of Federal, State, or local laws or regulations.

7. Duty to Provide Information

The discharger shall furnish the RWQCB, State Water Resources Control Board, or USEPA, within a reasonable time, any requested information to determine compliance with this General Permit. The discharger shall also furnish, upon request, copies of records required to be kept by this General Permit.

8. Inspection and Entry

The discharger shall allow the RWQCB, SWRCB, USEPA, and/or, in the case of construction sites which discharge through a municipal separate storm sewer, an authorized representative of the municipal operator of the separate storm sewer system receiving the discharge, upon the presentation of credentials and other documents as may be required by law, to:

- a. Enter upon the discharger's premises at reasonable times where a regulated construction activity is being conducted or where records must be kept under the conditions of this General Permit;
- b. Access and copy at reasonable times any records that must be kept under the conditions of this General Permit;
- c. Inspect at reasonable times the complete construction site, including any off-site staging areas or material storage areas, and the erosion/sediment controls; and
- d. Sample or monitor at reasonable times for the purpose of ensuring General Permit compliance.

9. Signatory Requirements

- a. All Notice of Intent (NOIs), Notice of Terminations (NOTs), SWPPPs, certifications, and reports prepared in accordance with this Order submitted to the SWRCB shall be signed as follows:
 - (1) For a corporation: by a responsible corporate officer. For the purpose of this Section, a responsible corporate officer means: (a) a president, secretary, treasurer, or vice president of the corporation in charge of a principal business function, or any other person who performs similar policy or decision-making functions for the corporation, or (b) the manager of the construction activity if authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures;
 - (2) For a partnership or sole proprietorship: by a general partner or the proprietor, respectively; or
 - (3) For a municipality, State, Federal, or other public agency: by either a principal executive officer, ranking elected official, or duly authorized representative. The principal executive officer of a Federal agency includes the chief executive officer of the agency or the senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency (e.g., Regional Administrator of USEPA).
- b. All SWPPPs, reports, certifications, or other information required by the General Permit and/or requested by the RWQCB, SWRCB, USEPA, or the local storm water management agency shall be signed by a person described above or by a duly authorized representative. A person is a duly authorized representative if:
 - (1) The authorization is made in writing by a person described above and retained as part of the SWPPP; or

- (2) The authorization specifies either an individual or a position having responsibility for the overall operation of the construction activity, such as the position of manager, operator, superintendent, or position of equivalent responsibility, or an individual or position having overall responsibility for environmental matters for the company. (A duly authorized representative may thus be either a named individual or any individual occupying a named position).
- c. If an authorization is no longer accurate because a different individual or position has responsibility for the overall operation of the construction activity, a new authorization must be attached to the SWPPP prior to submittal of any reports, information, or certifications to be signed by the authorized representative.

10. Certification

Any person signing documents under Section C, Provision 9 above, shall make the following certification:

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, to the best of my knowledge and belief, the information submitted is, true, accurate, and complete.

I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

11. Anticipated Noncompliance

The discharger will give advance notice to the RWQCB and local storm water management agency of any planned changes in the construction activity which may result in noncompliance with General Permit requirements.

12. Penalties for Falsification of Reports

Section 309(c)(4) of the CWA provides that any person who knowingly makes any false material statement, representation, or certification in any record or other document submitted or required to be maintained under this General Permit, including reports of compliance or noncompliance shall upon conviction, be punished by a fine of not more than \$10,000 or by imprisonment for not more than two years or by both.

13. Oil and Hazardous Substance Liability

Nothing in this General Permit shall be construed to preclude the institution of any legal action or relieve the discharger from any responsibilities, liabilities, or penalties to which the discharger is or may be subject to under Section 311 of the CWA.

14. Severability

The provisions of this General Permit are severable; and, if any provision of this General Permit or the application of any provision of this General Permit to any circumstance is held invalid, the application of such provision to other circumstances and the remainder of this General Permit shall not be affected thereby.

15. Reopener Clause

This General Permit may be modified, revoked and reissued, or terminated for cause due to promulgation of amended regulations, receipt of USEPA guidance concerning regulated activities, judicial decision, or in accordance with 40 Code of Federal Regulations (CFR) 122.62, 122.63, 122.64, and 124.5.

16. Penalties for Violations of Permit Conditions

- a. Section 309 of the CWA provides significant penalties for any person who violates a permit condition implementing Sections 301, 302, 306, 307, 308, 318, or 405 of the CWA or any permit condition or limitation implementing any such section in a permit issued under Section 402. Any person who violates any permit condition of this General Permit is subject to a civil penalty not to exceed \$27,500 per calendar day of such violation, as well as any other appropriate sanction provided by Section 309 of the CWA.
- b. The Porter-Cologne Water Quality Control Act also provides for civil and criminal penalties which in some cases are greater than those under the CWA.

17. Availability

A copy of this General Permit shall be maintained at the construction site during construction activity and be available to operating personnel.

18. Transfers

This General Permit is not transferable. A new owner of an ongoing construction activity must submit a NOI in accordance with the requirements of this General Permit to be authorized to discharge under this General Permit. An owner who sells property covered

by this General Permit shall inform the new owner of the duty to file a NOI and shall provide the new owner with a copy of this General Permit.

19. Continuation of Expired Permit

This General Permit continues in force and effect until a new General Permit is issued or the SWRCB rescinds this General Permit. Only those dischargers authorized to discharge under the expiring General Permit are covered by the continued General Permit.

SWRCB AND RWQCB CONTACT LIST

Division of Water Quality

P.O. Box 1977

Sacramento, CA 95812-1977

(916) 341-5537 FAX: (916) 341-5543

Web Page: http://www.waterboards.ca.gov/water_issues/programs/stormwater/Email: stormwater@waterboards.ca.gov**CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARDS****NORTH COAST REGION (1)**

5550 Skylane Blvd, Ste. A

Santa Rose, CA 95403

(707) 576-2220 FAX: (707) 523-0135

<http://www.waterboards.ca.gov/rwqcb1>**CENTRAL COAST REGION (3)**

895 Aerovista Place, Ste 101

San Luis Obispo, CA 93401

(805) 549-3147 FAX: (805) 543-0397

<http://www.waterboards.ca.gov/rwqcb3>**LAHONTAN REGION (6 SLT)**

2501 Lake Tahoe Blvd.

South Lake Tahoe, CA 96150

(530) 542-5400 FAX: (530) 544-2271

<http://www.waterboards.ca.gov/rwqcb6>**SAN FRANCISCO BAY REGION (2)**

1515 Clay Street, Ste. 1400

Oakland, CA 94612

(510) 622-2300 FAX: (510) 622-2640

<http://www.waterboards.ca.gov/rwqcb2>**LOS ANGELES REGION (4)**320 W. 4th Street, Ste. 200

Los Angeles, CA 90013

(213) 576-6600 FAX: (213) 576-6640

<http://www.waterboards.ca.gov/rwqcb4>**VICTORVILLE OFFICE (6V)**

15428 Civic Drive, Ste. 100

Victorville, CA 92392-2383

(760) 241-6583 FAX: (760) 241-7308

<http://www.waterboards.ca.gov/rwqcb6>**CENTRAL VALLEY REGION (5S)**

11020 Sun Center Dr., #200

Rancho Cordova, CA 95670-6114

(916) 464-3291 FAX: (916) 464-4645

<http://www.waterboards.ca.gov/rwqcb5>**COLORADO RIVER BASIN REGION (7)**

73-720 Fred Waring Dr., Ste. 100

Palm Desert, CA 92260

(760) 346-7491 FAX: (760) 341-6820

<http://www.waterboards.ca.gov/rwqcb7>**FRESNO BRANCH OFFICE (5F)**

1685 E St.

Fresno, CA 93706

(559) 445-5116 FAX: (559) 445-5910

<http://www.waterboards.ca.gov/rwqcb5>**SANTA ANA REGION (8)**

California Tower

3737 Main Street, Ste. 500

Riverside, CA 92501-3339

<http://www.waterboards.ca.gov/rwqcb8>**REDDING BRANCH OFFICE (5R)**

415 Knollcrest Drive, Ste. 100

Redding, CA 96002

(530) 224-4845 FAX: (530) 224-4857

<http://www.waterboards.ca.gov/rwqcb5>**SAN DIEGO REGION (9)**

9174 Sky Park Court, Ste. 100

San Diego, CA 92123-4340

(858) 467-2952 FAX: (858) 571-6972

<http://www.waterboards.ca.gov/rwqcb9>**STATE OF CALIFORNIA**

Arnold Schwarzenegger, Governor

CALIFORNIA ENVIRONMENTAL


PROTECTION AGENCY

Terry Tamminen, Secretary

STATE WATER RESOURCES

CONTROL BOARD

Arthur Baggett Jr., Chairman



Attachment O

Water Pollution Control Cost Breakdown

Pending Final Construction Plans and Specifications.

Attachment P

Notice of Termination



Linda S. Adams
*Secretary for
Environmental Protection*

State Water Resources Control Board

Division of Water Quality

1001 I Street • Sacramento, California 95814 • (916) 341-5537
Mailing Address: P.O. Box 1977 • Sacramento, California • 95812-1977
FAX (916) 341-5543 • Internet Address: <http://www.waterboards.ca.gov/stormwtr/index.html>



Arnold Schwarzenegger
Governor

To: Storm Water Permit Holder

RE: NOTICE OF TERMINATION OF COVERAGE UNDER THE GENERAL
CONSTRUCTION STORM WATER PERMIT (GENERAL PERMIT)

In order for us to terminate your coverage under the General Permit, please complete and submit the enclosed Notice of Termination (NOT) your local Regional Water Quality Control Board (RWQCB). Refer to the last page of the NOT packet for RWQCB locations.

Submittal of a NOT does not guarantee termination and outstanding invoices are still valid. If your NOT is denied, you will be required to continue complying with the requirements of the General Permit and all outstanding invoice(s) are due. You will be notified of your NOT status by the RWQCB or State Water Resources Control Board. Approval of your Notice of Termination does not relieve you from paying any applicable outstanding invoices.

Should you have any questions regarding this matter, please contact your local RWQCB at the number listed on the back page of the NOT package, or the Storm Water Unit at (916) 341-5537.

Sincerely,

Storm Water Unit
Division of Water Quality

Enclosure

SEND TO YOUR LOCAL RWQCB FOR APPROVAL

State of California
State Water Resources Control Board

NOTICE OF TERMINATION

OF COVERAGE UNDER THE NPDES GENERAL PERMIT NO. CAS000002
FOR DISCHARGES OF STORM WATER
ASSOCIATED WITH CONSTRUCTION ACTIVITY

Submission of this Notice of Termination constitutes notice that the owner (and his/her agent) of the site identified on this form is no longer authorized to discharge storm water associated with construction activity by NPDES General Permit No. CAS000002.

I. WDID NO. _____

II. OWNER

COMPANY NAME _____ CONTACT PERSON _____

STREET ADDRESS _____ TITLE _____

CITY _____ STATE _____ ZIP _____ PHONE _____

III. CONSTRUCTION SITE INFORMATION

A. DEVELOPER NAME _____ **CONTACT PERSON** _____

STREET ADDRESS _____ TITLE _____

CITY _____ CA _____ ZIP _____ PHONE _____

B. SITE ADDRESS _____ **COUNTY** _____

CITY _____ CA _____ ZIP _____ PHONE _____

IV. BASIS OF TERMINATION

_____ 1. The construction project is complete and the following conditions have been met.

- All elements of the Storm Water Pollution Prevention Plan have been completed.
- Construction materials and waste have been disposed of properly.
- The site is in compliance with all local storm water management requirements.
- A post-construction storm water operation and management plan is in place.

Date of project completion ____/____/____

_____ 2. Construction activities have been suspended, either temporarily _____ or indefinitely _____ and the following conditions have been met.

- All elements of the Storm Water Pollution Prevention Plan have been completed.
- Construction materials and waste have been disposed of properly.
- All denuded areas and other areas of potential erosion are stabilized.
- An operation and maintenance plan for erosion and sediment control is in place.
- The site is in compliance with all local storm water management requirements.

Date of suspension ____/____/____ Expected start up date ____/____/____

_____ 3. Site can not discharge storm water to waters of the United States (check one).

SEND TO YOUR LOCAL RWQCB FOR APPROVAL

_____ All storm water is retained on site.

_____ All storm water is discharged to evaporation or percolation ponds offsite.

- _____ 4. Discharge of storm water from the site is now subject to another NPDES general permit or an individual NPDES permit.

NPDES Permit No. _____ Date coverage began ____/____/____

- _____ 5. There is a new owner of the identified site. Date of owner transfer ____/____/____

Was the new owner notified of the General Permit requirements? YES ____ NO ____

NEW OWNER INFORMATION

COMPANY NAME _____ CONTACT PERSON _____

STREET ADDRESS _____ TITLE _____

CITY _____ STATE _____ ZIP _____ PHONE _____

V. EXPLANATION OF BASIS OF TERMINATION (Attach site photographs - see instructions).

VI. CERTIFICATION:

I certify under penalty of law that all storm water discharges associated with construction activity from the identified site that are authorized by NPDES General Permit No. CAS000002 have been eliminated or that I am no longer the owner of the site. I understand that by submitting this Notice of Termination, I am no longer authorized to discharge storm water associated with construction activity under the general permit, and that discharging pollutants in storm water associated with construction activity to waters of the United States is unlawful under the Clean Water Act where the discharge is not authorized by a NPDES permit. I also understand that the submittal of this Notice of Termination does not release an owner from liability for any violations of the general permit or the Clean Water Act.

PRINTED NAME _____ TITLE _____

SIGNATURE: _____ DATE ____/____/____

REGIONAL WATER BOARD USE ONLY

This Notice of Termination has been reviewed, and I recommend termination of coverage under the subject NPDES general permit.

Printed Name _____ Region No. _____

Signature _____ Date ____/____/____

NOT effective date:

Date: ____/____/____

**INSTRUCTIONS FOR COMPLETING
NOTICE OF TERMINATION
FOR CONSTRUCTION ACTIVITY**

Who May File

Dischargers who are presently covered under NPDES General Permit No. CAS000002 for discharge of storm water associated with construction activity may submit a Notice of Termination when they meet one of the following criteria.

1. The construction project has been completed and the following conditions have been met: all elements of the Stormwater Pollution Prevention Plan have been completed; construction materials and equipment maintenance waste have been disposed of properly; the site is in compliance with all local storm water management requirements including erosion/sediment control requirements and the appropriate use permits have been obtained; and a post-construction storm water operation and management plan is in place.
2. Construction activities have been suspended, either temporarily or indefinitely and the following conditions have been: all elements of the Stormwater Pollution Prevention Plan have been completed; construction materials and equipment maintenance waste have been disposed of properly; all denuded areas and other areas of potential erosion are stabilized; an operation and maintenance plan for erosion and sediment control is in place; and the site is in compliance with all local storm water management requirements including erosion/sediment control requirements.
The date construction activities were suspended, and the expected date construction activities will start up again should be provided.
3. Construction site can not discharge storm water to waters of the United States. Please indicate if all storm water is retained on site or if storm water is collected offsite.
4. Discharge of construction storm water from the site is now subject to another NPDES general permit or an individual NPDES permit. The general permit or individual permit NPDES number and date coverage began should be provided.
5. There is a new owner of the identified site. If ownership or operation of the facility has been transferred then the previous owner must submit a Notice of Termination and the new owner must submit a Notice of Intent for coverage under the general permit. The date of transfer and information on the new owner should be provided.
Note that the previous owner may be liable for discharge from the site until the new owner files a Notice of Intent for coverage under the general permit.

Where to File

Submit the Notice of Termination to the Executive Officer of the Regional Water Quality Control Board responsible for the area in which the facility is located. See attached. Submittal of a NOT does not guarantee termination and outstanding invoices are still valid. If the Executive Officer, or his designated staff, agrees with the basis of termination, the Notice of Termination will be transmitted to the State Water Board for processing at which time it will be determined if any outstanding invoices are still valid. Approval of your Notice of Termination does not relieve you from paying any applicable outstanding invoices. If the Executive Officer, or his designated staff, does not agree with the basis of termination, the Notice of Termination will be returned. The Regional Water Board may also inspect your site prior to accepting the basis of termination.

LINE-BY-LINE INSTRUCTIONS

All necessary information must be provided on the form. Type or print in the appropriate areas only. Submit additional information, if necessary, on a separate sheet of paper.

SECTION I--WDID NO.

The WDID No. is a number assigned to each discharger covered under the General Permit. If you do not know your WDID No., please call the State Water Board or Regional Water Board and request it prior to submittal of the Notice of Termination.

SECTION II--OWNER

Enter the owner of the construction site's official or legal name (This should correspond with the name on the Notice of Intent submitted for the site), address of the owner, contact person, and contact person's title and telephone number.

SECTION III--CONSTRUCTION SITE INFORMATION

In Part A, enter the name of the developer (or general contractor), address, contact person, and contact person's title and telephone number. The contact person should be the construction site manager completely familiar with the construction site and charged with compliance and oversight of the general permit. This information should correspond with information on the Notice of Intent submitted for the site.

In Part B, enter the address, county, and telephone number (if any) of the construction site. Construction sites that do not have a street address must attach a legal description of the site.

SECTION IV--BASIS OF TERMINATION

Check the category which best defines the basis of your termination request. See the discussion of the criteria in the Who May File section of these instructions. Provide dates and other information requested. Use the space under Explanation of Basis of Termination heading.

SECTION V--EXPLANATION OF BASIS OF TERMINATION

Please explain the basis or reasons why you believe your construction site is not required to comply with the General Permit. To support your explanation, provide a site map and photograph of your site.

SECTION VI--CERTIFICATION

This section must be completed by the owner of the site.

The Notice of Termination must be signed by:

For a Corporation: a responsible corporate officer

For a Partnership or Sole Proprietorship: a general partner or the proprietor, respectively.

For a Municipality, State, or other Non-Federal Public Agency: either a principal executive officer or ranking elected official.

For a Federal Agency: either the chief or senior executive officer of the agency.

CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARDS

NORTH COAST REGION (1)

5550 Skylane Blvd, Ste. A
Santa Rose, CA 95403
(707) 576-2220 FAX: (707) 523-0135
<http://www.waterboards.ca.gov/rwqcb1>

SAN FRANCISCO BAY REGION (2)

1515 Clay Street, Ste. 1400
Oakland, CA 94612
(510) 622-2300 FAX: (510) 622-2640
<http://www.waterboards.ca.gov/rwqcb2>

CENTRAL COAST REGION (3)

895 Aerovista Place, Ste 101
San Luis Obispo, CA 93401
(805) 549-3147 FAX: (805) 543-0397
<http://www.waterboards.ca.gov/rwqcb3>

LOS ANGELES REGION (4)

320 W. 4th Street, Ste. 200
Los Angeles, CA 90013
(213) 576-6600 FAX: (213) 576-6640
<http://www.waterboards.ca.gov/rwqcb4>

LAHONTAN REGION (6 SLT)

2501 Lake Tahoe Blvd.
South Lake Tahoe, CA 96150
(530) 542-5400 FAX: (530) 544-2271
<http://www.waterboards.ca.gov/rwqcb6>

VICTORVILLE OFFICE (6V)

14440 Civic Drive, Ste. 200
Victorville, CA 92392-2383
(760) 241-6583 FAX: (760) 241-7308
<http://www.waterboards.ca.gov/rwqcb6>

CENTRAL VALLEY REGION (5S)

11020 Sun Center Dr., #200
Rancho Cordova, CA 95670-6114
(916) 464-3291 FAX: (916) 464-4645
<http://www.waterboards.ca.gov/rwqcb5>

FRESNO BRANCH OFFICE (5F)

685 E St.
Fresno, CA 93706
(559) 445-5116 FAX: (559) 445-5910
<http://www.waterboards.ca.gov/rwqcb5>

REDDING BRANCH OFFICE (5R)

415 Knollcrest Drive, Ste. 100
Redding, CA 96002
(530) 224-4845 FAX: (530) 224-4857
<http://www.waterboards.ca.gov/rwqcb5>

COLORADO RIVER BASIN REGION (7)

73-720 Fred Waring Dr., Ste. 100
Palm Desert, CA 92260
(760) 346-7491 FAX: (760) 341-6820
<http://www.waterboards.ca.gov/rwqcb7>

SANTA ANA REGION (8)

California Tower
3737 Main Street, Ste. 500
Riverside, CA 92501-3339
<http://www.waterboards.ca.gov/rwqcb8>

SAN DIEGO REGION (9)

9174 Sky Park Court, Ste. 100
San Diego, CA 92123-4340
(858) 467-2952 FAX: (858) 571-6972
<http://www.waterboards.ca.gov/rwqcb9>

STATE OF CALIFORNIA

Arnold Schwarzenegger, Governor

CALIFORNIA ENVIRONMENTAL PROTECTION AGENCY

Terry Tamminen, Secretary

STATE WATER RESOURCES CONTROL BOARD

Arthur Baggett Jr., Chairman



Attachment Q

BMPs Selected for the Project
BMPs used are listed in Attachment B, G, I and O.

Attachment R

Sampling Activity Log

HAS BEEN OMITTED FROM THIS REPORT

PLEASE REFER TO SECTION 600.5.1

Attachment S

Pollutant Testing Guidance Table

HAS BEEN OMITTED FROM THIS REPORT
PLEASE REFER TO SECTION 600.5.1

Attachment T

Discharge Reporting Log

Project Name: _____

Project Number: _____

[illegible]

Exhibit 1

Construction Schedule

Can be supplied by Contractor upon request.

Exhibit 2

Soils Report

Cover sheet attached for reference only.
Owner will provide full report upon request

**GEOTECHNICAL EVALUATION
MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA**

PREPARED FOR:

Mojave Solar, LLC
13911 Park Avenue, Suite 206
Victorville, California 92392

PREPARED BY:

Ninyo & Moore
Geotechnical and Environmental Sciences Consultants
5710 Ruffin Road
San Diego, California 92123

May 15, 2009
Project No. 105879004

Exhibit 3

Hydrology Report

Cover sheet attached for reference only.
Owner will provide full report upon request



Merrell-Johnson Engineering, Inc.
CIVIL ENGINEERING ♦ SURVEYING

HYDROLOGY STUDY

For

MOJAVE SOLAR PROJECT HARPER DRY LAKE, CA

Prepared For:

MOJAVE SOLAR LLC
Victorville, CA
July, 2009

Prepared by:

Merrell-Johnson Engineering, Inc.

12138 Industrial Blvd., Suite 240
Victorville, CA 92395
(760) 241-6146

Job No. 3001

Brad S. Merrell
Principal Engineer
R.C.E. 49423 Exp. 09/30/10

Mark D. Rowan
Project Manager

Exhibit 4

Change of Information (COI) Form

For the General Construction Permit No. CAS000002

**NEW OWNER INFORMATION AND
CHANGE OF INFORMATION (COI) FORM FOR THE
GENERAL CONSTRUCTION PERMIT NO. CAS0000002**

Owners Name: _____
WDID No.: _____
Prepared By: _____

Date: _____
Date of Last NOI Change: _____
Signature of Preparer: _____

	Area Transferred (acres) ¹ column 1	Area Remaining (acres) ² column 2	Lot/Tract Numbers Transferred	Contact Person and Company Name of NewOwner(s)	Address(es) of the New Owner(s)	Phone # of New Owner	Is Const/Post Construction Complete? Yes/No	Date of Ownership Transfer
1								
2								
3								
4								
5								
6								
7								
8								
9								
10								

¹Use approximate area (in acres) if no exact figure is available.
²Calculate running total in this column as follows:
Enter in column 2, line 1, the area from NOI minus the area in column 1.
Enter in column 2, line 2, the area in column 2, line 1, minus the area in line 2, column 1.
Enter in column 2, line 3, the area in column 2, line 2, minus the area in line 3, column 1, and so forth.

CONDITONS OF CERTIFICATION FROM CALIFORNIA ENERGY COMMISSION

CONDITIONS OF CERTIFICATION

DRAINAGE EROSION AND SEDIMENTATION CONTROL PLAN (DESCP)

SOIL & WATER-1 Prior to site mobilization, the project owner shall obtain the Compliance Project Manager's (CPM) approval for a site specific DESCP that ensures protection of water quality and soil resources of the project site and all linear facilities for both the construction and operation phases of the project. This plan shall address appropriate methods and actions, both temporary and permanent, for the protection of water quality and soil resources, demonstrate no increase in off-site flooding potential, and identify all monitoring and maintenance activities. The project owner shall complete all engineering plans, reports, and documents necessary for the CPM to conduct a review of the proposed project and provide a written evaluation as to whether the proposed grading, drainage improvements, and flood management activities comply with all requirements presented herein. The plan shall be consistent with the

grading and drainage plan as required by Condition of Certification **CIVIL-1** and shall contain the following elements:

- **Vicinity Map:** A map shall be provided indicating the location of all project elements with depictions of all major geographic features to include watercourses, washes, irrigation and drainage canals, major utilities, and sensitive areas.
- **Site Delineation:** The site and all project elements shall be delineated showing boundary lines of all construction areas and the location of all existing and proposed structures, underground utilities, roads, and drainage facilities. Adjacent property owners shall be identified on the plan maps. All maps shall be presented at a legible scale
- **Drainage:** The DESCP shall include the following elements:
 - a. Topography. Topography for off-site areas are required to define the existing upstream tributary areas to the site and downstream to provide enough definition to map the existing storm water flow and flood hazard. Spot elevations shall be required where relatively flat conditions exist.
 - b. Proposed Grade. Proposed grade contours shall be shown at a scale appropriate for delineation of on-site ephemeral washes, drainage ditches, and tie-ins to the existing topography. A clear indication of on-site storm water containment features (berm, etc.) should also be delineated.
 - c. Hydrology. Existing and proposed hydrologic calculations for on-site areas and off-site areas that drain to the site; include maps showing the drainage area boundaries and sizes in acres, topography and typical overland flow directions, and show all existing, interim, and proposed drainage infrastructure and their intended direction of flow.
 - d. Hydraulics. Provide hydraulic calculations to support the selection and sizing of the on-site drainage network, diversion facilities and BMPs.
 - e. Containment. Description of on-site storm water containment features. Indicate how the project will maintain a “no discharge” status.
- **Watercourses and Critical Areas:** The DESCP shall show the location of all on-site and nearby watercourses including washes, irrigation and drainage canals, and drainage ditches, and shall indicate the proximity of those features to the construction site. Maps shall identify high hazard flood prone areas.

- **Clearing and Grading:** The plan shall provide a delineation of all areas to be cleared of vegetation and areas to be preserved. The plan shall provide elevations, slopes, locations, and extent of all proposed grading as shown by contours, cross-sections, cut/fill depths or other means. The locations of any disposal areas, fills, or other special features shall also be shown. Existing and proposed topography tying in proposed contours with existing topography shall be illustrated. The DESCP shall include a statement of the quantities of material excavated at the site, whether such excavations or fill is temporary or permanent, and the amount of such material to be imported or exported or a statement explaining that there would be no clearing and/or grading conducted for each element of the project. Areas of no disturbance shall be properly identified and delineated on the plan maps.
- **Soil Wind and Water Erosion Control:** The plan shall describe soil treatments to be used during construction and operation of the proposed project for both road and non-road surfaces including specifically identifying all chemical based dust palliatives, soil bonding, and weighting agents appropriate for use at the proposed project site that would not cause adverse effects to vegetation; BMPs shall include measures designed to prevent wind and water erosion including application of chemical dust palliatives after rough grading to limit water use. All dust palliatives, soil binders, and weighting agents shall be approved by the CPM prior to use.
- **Project Schedule:** The DESCP shall identify on the topographic site map the location of the site-specific BMPs to be employed during each phase of construction (initial grading, project element construction, and final grading/stabilization). BMP implementation schedules shall be provided for each project element for each phase of construction.
- **Best Management Practices:** The DESCP shall show the location, timing, and maintenance schedule of all erosion- and sediment-control BMPs to be used prior to initial grading, during project element excavation and construction, during final grading/stabilization, and after construction. BMPs shall include measures designed to control dust and stabilize construction access roads and entrances. The maintenance schedule shall include post-construction maintenance of treatment-control BMPs applied to disturbed areas following construction.
- **Erosion Control Drawings:** The erosion-control drawings and narrative shall be designed, stamped and sealed by a professional engineer or erosion-control specialist.

- **Agency Comments:** The DESCP shall include copies of recommendations from the County of San Bernardino and RWQCB.
- **Monitoring Plan:** Monitoring activities shall include routine measurement of the volume of accumulated sediment in the on-site containment berms, drainage ditches, and storm water diversions. The monitoring plan shall be part of the channel maintenance plan in Condition of Certification SOIL&WATER-3.

Verification: The DESCP shall be consistent with the grading and drainage plan as required by Condition of Certification **CIVIL-1**, and relevant portions of the DESCP shall be submitted to the Chief Building Official (CBO) for review and approval. In addition, the project owner shall do all of the following:

1. No later than sixty (60) days prior to start of site mobilization, the project owner shall submit a copy of the DESCP to the County of San Bernardino and the RWQCB for review and comment. The CPM shall consider comments received from San Bernardino County and RWQCB and approve the DESCP based on comments as appropriate.
2. During construction, the project owner shall provide an analysis in the monthly compliance report on the effectiveness of the drainage, erosion, and sediment control measures and the results of monitoring and maintenance activities.
3. Once operational, the project owner shall provide in the annual compliance report information on the results of storm water BMP monitoring and maintenance activities. The project owner shall also indicate what maintenance activities were completed to maintain the project's on-site storm water flow.
4. Provide the CPM with two (2) copies each of all monitoring or compliance reports.

WASTE DISCHARGE REQUIREMENTS

SOIL&WATER-2 The project owner shall comply with the Waste Discharge Requirements (WDRs) established in Soil and Water Resources Appendices C, D, and E for the construction and operation of the surface impoundments (evaporation ponds), land treatment units, and storm water management system. These requirements relate to discharges, or potential discharges, of waste that could affect the quality of waters of the state, and were developed in consultation with staff of the State Water Resources Control Board and/or the applicable California Regional Water Quality Control Board (hereafter "Water Boards"). It is the Commission's intent that these requirements be enforceable by both the Commission and the Water Boards. In furtherance of that objective, the Commission hereby delegates the enforcement of these requirements, and associated monitoring,

inspection and annual fee collection authority, to the Water Boards. Accordingly, the Commission and the Water Board shall confer with each other and coordinate, as needed, in the enforcement of the requirements. The project owner shall pay the annual waste discharge permit fee associated with this facility to the Water Boards. In addition, the Water Boards may "prescribe" these requirements as waste discharge requirements pursuant to Water Code Section 13263 solely for the purposes of enforcement, monitoring, inspection, and the assessment of annual fees, consistent with Public Resources Code Section 25531, subdivision (c).

Verification: No later than sixty (60) days prior to any wastewater or storm water discharge or use of land treatment units, the AMS project shall provide documentation to the CPM, with copies to the Lahontan RWQCB, demonstrating compliance with the WDRs established in Appendices C, D, and E. Any changes to the design, construction, or operation of the ponds, treatment units, or storm water system shall be requested in writing to the CPM, with copies to the Lahontan RWQCB, and approved by the CPM, in consultation with the Lahontan RWQCB, prior to initiation of any changes. The AMS project shall provide to the CPM, with copies to the Lahontan RWQCB, all monitoring reports required by the WDRs, and fully explain any violations, exceedances, enforcement actions, or corrective actions related to construction or operation of the ponds, treatment units, or storm water system.

CHANNEL MAINTENANCE PROGRAM

SOIL&WATER-3 The AMS project shall develop and implement a Channel Maintenance Program for routine maintenance of the AMS Project storm water channels. The program shall include all channel maintenance as needed to protect the integrity of the channels from erosion and sedimentation.

- A. Purpose and Objectives. The program goals shall be to maintain storm water channels over the life of the project to meet their original design capacity for flood protection and conveyance and maintain groundwater recharge. Channels must have adequate capacity to convey the maximum designed flood stage flow and still maintain two feet of freeboard.
- B. Channel Maintenance Area. The channel maintenance area shall be defined as the AMS project engineered channels, which would extend to the top of the channel bank and include access roads and easements on top of the banks.
- C. Channel Maintenance Activities
 - i. Sediment Removal. Sediment shall be removed if: (1) the effective channel flood capacity has been reduced to less than the design discharge; (2) appurtenant hydraulic structures are

prevented from functioning as intended; or (3) a permanent, non-erodible barrier to instream flows has developed.

- ii. Vegetation Management. Vegetation shall be managed in and adjacent to the channels to maintain hydraulic capacity. Vegetation management shall include control of invasive and nonnative vegetation.
- iii. Bank Protection and Grade Control Repairs. Bank protection and grade control structure repairs shall be conducted by the AMS project to repair eroding banks, incising toes, scoured channel beds, and as preventative erosion protection. The AMS project shall implement instream repairs when channel damage: (1) causes or could cause significant damage to the AMS project, adjacent property, or the structural elements of the channels; (2) is a public safety concern; (3) negatively affects groundwater recharge; or (4) negatively affects channel mitigation vegetation.
- iv. Routine Channel Maintenance. Routine channel maintenance shall include: trash and debris removal to maintain channel design capacity; repair and installation of fences, gates and signs; and grading and other repairs to restore the original contour of access roads and levees (if applicable).

D. Channel Maintenance Plan and Reporting

- 1. Channel Maintenance Plan. The Channel Maintenance Plan shall include: (1) the maintenance standards for each project channel; (2) policies to guide decision-making to ensure the maintenance standards are enforced; (3) procedures and BMPs to implement to ensure implementation of the policies; and (4) procedures and BMPs for sediment management, vegetation management, trash and debris removal, fence repairs, and access road maintenance.
- 2. Channel Maintenance Reporting. The following plans and reports shall be submitted to the CPM each year as part of the Annual Compliance Report:
 - a. Channel Maintenance Workplans. These workplans shall describe the planned “major” maintenance activities and extent of work to be accomplished.
 - b. Annual Channel Maintenance Report. This report shall specify which maintenance activities were completed during the year including type of work, location, and measure of the activity (e.g. cubic yards of sediment removed). This report

Verification: At least sixty (60) days before the start of project operation, the AMS project shall submit to the CPM a Channel Maintenance Plan for review and approval. The AMS project shall provide written notification to the CPM at least sixty (60) days in advance of any planned changes to the Channel Maintenance Plan.

In addition, the project owner shall:

1. Implement the Channel Maintenance Plan in Item D (Channel Maintenance Plan and Reporting);
2. Ensure that the AMS project Construction and Operations Managers receive training on the Channel Maintenance Plan; and
3. As part of the AMS project Annual Compliance Report, submit an Annual Channel Maintenance Report that specifies which maintenance activities were completed during the year including type of work, location, and measure of the activity (e.g. cubic yards of sediment removed).

PROJECT GROUNDWATER WELLS

SOIL&WATER-4 Pre-Well Installation. The project owner shall construct and operate up to two on-site groundwater wells that produce water from the Harper Valley Groundwater Basin and two backup wells. The project owner shall ensure that the wells are completed in accordance with all applicable state and local water well construction requirements. If the perched water table is present where new wells will be constructed, the project wells shall be designed to prevent cross-connection between the lower quality perched groundwater and the upper aquifer. Prior to the start of well construction activities, the project owner shall submit for review and comment a well construction packet to the County of San Bernardino, in accordance with the County of San Bernardino Code Title 2, Division 3, Chapter 6, Article 5, containing the documentation, plans, and fees normally required for the county's well permit, with copies to the CPM. The project shall not construct a well or extract and use groundwater until the CPM provides approval to construct and operate the well.

Post-Well Installation. The project owner shall provide documentation to the CPM that the well has been properly completed. In accordance with California's Water Code section 13754, the driller of the well shall submit to the DWR a Well Completion Report for each well installed. A copy of the Well Completion Report shall be included in the documentation submitted to the CPM.

Groundwater Well Abandonment. On property controlled by the project owner, the project owner shall protect groundwater resources by abandoning all groundwater wells that are constructed in such a manner that the screen interval of the well intercepts both the poor quality perched water and deeper aquifer water (uQal). These groundwater wells shall be abandoned in accordance with all applicable state and local water well abandonments requirements, including the California Department of Water Resources Bulletins 74-81 & 74-90. Prior to the start of well construction activities, the project owner shall submit for review and comment a well abandonment packet to the County of San Bernardino, in accordance with the County of San Bernardino Code Title 3, Division 3, Article 3, containing the documentation, plans, and fees normally required for the county's well abandonment permit, with copies to the CPM. The project shall not abandon a well until the CPM provides approval.

Verification: The project owner shall ensure the Well Completion Reports are submitted and shall ensure compliance with all State and county water well standards and requirements for the life of the wells. The project owner shall do all of the following:

1. No later than sixty (60) days prior to the construction of the on-site groundwater wells, the project owner shall submit a Groundwater Monitoring and Management Plan to the County of San Bernardino for review and comment (see Condition of Certification **SOIL&WATER-6**).
2. No later than sixty (60) days prior to the abandonment and construction of the on-site groundwater wells, the project owner shall submit to the CPM a copy of the water well abandonment and construction packet submitted to the County of San Bernardino for review and comment.
3. No later than thirty (30) days prior to the construction of the on-site water supply wells, the project owner shall submit a copy of any written comments received from the County of San Bernardino indicating whether the proposed well abandonment and construction activities comply with all county well requirements and meet the requirements established by the county's water well permit program.
4. No later than sixty (60) days after installation of each well at the project site, the project owner shall provide to the CPM copies of the Well Completion Reports submitted to the DWR by the well driller. The project owner shall submit to the CPM, together with the Well Completion Report, a copy of well drilling logs, water quality analyses, and any inspection reports.
5. During well construction and for the operational life of the well, the project owner shall submit two (2) copies to the CPM for review and approval any proposed well construction or operation changes.

6. The project owner shall provide the CPM with (2) two copies of all monitoring and other reports required for compliance with the County of San Bernardino water well standards and operation requirements.
7. No later than fifteen (15) days after completion of the on-site water supply wells, the project owner shall submit documentation to the CPM confirming that well drilling activities were conducted in compliance with Title 23, California Code of Regulations, Chapter 15, Discharges of Hazardous Wastes to Land, (23 CCR, sections 2510 et seq.) requirements and that any on-site drilling sumps used for project drilling activities were removed in compliance with 23 CCR section 2511(c).

CONSTRUCTION AND OPERATIONS WATER USE

SOIL&WATER-5 The proposed project's use of groundwater for all construction and operations activities shall not exceed 2,160 acre-feet per year. The quantity of the groundwater used for project construction and operation shall be reported to ensure compliance with this condition. Prior to the use of groundwater for construction, the project owner shall install and maintain metering devices as part of the water supply and distribution system to document project water use and to monitor and record in gallons per day the total volume(s) of water supplied to the project from this water source. The metering devices shall be operational for the life of the project.

Verification: Beginning six (6) months after the start of construction, the project owner shall prepare a semi-annual summary report of the amount of water used for construction purposes. The summary shall include the monthly range and monthly average of daily water usage in gallons per day.

At least sixty (60) days prior to the start of construction of the proposed project, the project owner shall submit to the CPM a copy of evidence that metering devices have been installed and are operational.

The project owner shall prepare an annual summary report, which will include maximum daily and monthly usage in gallons per day and the total monthly and annual usage in acre-feet. Following the first year of operation, the annual summary report will summarize the annual usage in tabular form. For calculating the total water use, the term "year" will correspond to the date established for the annual compliance report submittal.

GROUNDWATER LEVEL MONITORING, MITIGATION, AND REPORTING

SOIL&WATER-6 The project owner shall submit a Groundwater Monitoring and Reporting Plan to the CPM for review and approval. This plan shall consist of two parts as defined by Conditions of Certification **SOIL&WATER-6** and **-7**. **SOIL&WATER-6** describes the requirements for establishing a groundwater well monitoring network and monitoring groundwater levels in that network. **SOIL&WATER-7** describes the

requirements for monitoring groundwater quality in the network. Mitigation for impacts related to project induced groundwater level declines or degradation in groundwater quality are provide in each condition of certification. All work and reporting under these conditions of certification shall be conducted under the supervision of a licensed California professional geologist or engineer.

The Groundwater Level Monitoring and Reporting Plan shall provide detailed methodology for monitoring background and site groundwater levels. Monitoring shall include pre-construction, construction, and project operation conditions. The primary objective for the monitoring is to establish a baseline of pre-construction groundwater level trends that can be quantitatively compared against observed and simulated trends near the project pumping wells and near potentially impacted existing wells during project construction and over the life of project operation. The project owner shall:

A. Prior to Project Construction

1. Well Reconnaissance. Conduct a well reconnaissance to investigate and document condition of existing water supply wells within the monitoring area provided access is granted by the well owner). The monitoring area shall be defined by the 20-foot contour of simulated groundwater drawdown induced by AMS project pumping at the end of the project life (as presented in Appendix B Figure Soil and Water 3). Notices shall be sent by registered mail to each well owner identified within monitoring area that provide the following information:
 - a. A summary of the proposed project with an explanation of how the groundwater levels are expected to be lowered due to the AMS project groundwater pumping;
 - b. An option for the well owner to be provided a copy of the Groundwater Monitoring and Report Plan as approved by the CPM and all reports prepared in compliance with the CPM-approved plan;
 - c. The project owner's contact name, address, and telephone where the well owner can obtain more information; and
 - d. The address and telephone number of the Energy Commission.
2. Monitoring Plan. Submit a Groundwater Level Monitoring and Reporting Plan to the CPM for review and approval at least sixty (60) days prior to construction. This plan shall include at a minimum:

- a. The monitoring plan and network of monitoring wells shall make use of two of the four project production wells (once installed), all monitoring wells installed to comply with Waste Discharge Requirements for the evaporation ponds and land treatment unit associated with the project, and the BLM marsh water supply well. In addition, and at least three additional existing wells in the Harper Lake area shall be incorporated into the program. The final well selection shall be based on access being granted by the owners and by BLM and that the wells are deemed by the CPM to be of suitable location and construction to satisfy the requirements for the monitoring program. Some Harper Lake area wells are already monitored, and these wells can be included as part of the network if they meet the objectives of the monitoring program.
- b. A scaled map showing the project site, boundary, location of all wells within the monitoring area, and location of wells selected for the monitoring network. The map shall also include relevant natural (e.g., faults, playa lake, etc.) and man-made features that are existing and proposed as part of the AMS project.
- c. Available well construction information, drilling and well installation methods, and borehole lithology for all wells in the monitoring area.
- d. For monitoring network wells, report the results of a wellhead elevation survey that record: the location and elevation of the well; the location and elevation of the top of the well casing reference point for all water level measurements (the measurement point); and the coordinate system and datum for the survey measurements.
- e. A description of how groundwater measurements will be collected and reported. All groundwater level measurements shall be made to the nearest **1/100 of a foot**.
- f. A description of the groundwater level measurements and reporting protocols and quality assurance/quality control plan.
- g. Information about the AMS project wells shall be added to a revised plan submitted to the CPM for review and approval within sixty (60) days after the project wells are installed.
- h. A description of the reporting requirements presented below, including a statistical analyses conducted on the data collected, the thresholds employed to determine impact

- i. A schedule for measuring water levels in all wells in the monitoring network.
 - j. The plan shall be signed and stamped by a licensed California professional geologist or engineer.
- 3. Monitoring. Before the start of project construction, collect groundwater levels from all existing wells within the monitoring network, in accordance with the requirements in the Groundwater Level Monitoring and Reporting Plan, to establish pre-construction conditions.
 - 4. Reporting. A report documenting the pre-construction monitoring results shall be submitted to the CPM after measuring groundwater levels in network wells. At a minimum, the report shall contain: a tabular summary of the network wells; the water level measurements; and dates of the water level measurements; diagrams showing water levels in the wells over time (hydrographs); a map of groundwater elevation contours and calculated gradients; and conclusions regarding groundwater level trends and recommendations for future monitoring and the likelihood of potential interferences to existing wells made by a licensed California professional geologist or engineer.

B. During Construction:

- 5. Collect groundwater levels within the monitoring network on a quarterly basis throughout the construction period. Perform statistical trend analysis for groundwater levels data using linear regression or a non-parametric test such as Kendall-Theil Robust Line, or other appropriate statistical analysis. Assess the significance of apparent trends using appropriate statistical analysis and compare to observed background trends in other monitored wells in the sub-basin.
- 6. After measuring groundwater levels in network wells, submit to the CPM a report of pre-project groundwater levels, present a summary of available climatic information (monthly average temperature and rainfall records from the nearest weather station), and provide a comparison and assessment of water level data relative to the spatial trends simulated by the USGS Mojave River Basin Model (USGS2001). This report shall also contain a tabular summary of the wells, current and historical water level measurements, and dates of water level measurements; a map of the groundwater elevation contours

and calculated gradients; and conclusion and recommendations of a licensed California professional geologist or engineer.

C. During Operation:

7. On a quarterly basis for the first year of operation and semi-annually thereafter for the following four years, collect groundwater level measurements from all wells identified in the groundwater monitoring network. Quarterly operational parameters (i.e., pumping rate and days on which pumping occurred) of the groundwater supply wells shall be monitored.
8. On an annual basis, perform statistical trend analysis (using linear regression or a non-parametric test such as Kendall-Theil Robust Line, or other appropriate statistical analysis) on water levels, compare water levels and trends to pre-project conditions, present a summary of available climatic information (monthly average temperature and rainfall records from the nearest weather station), and provide a comparison and assessment of water level data relative to the assumptions and spatial trends simulated by the USGS Mojave River Basin Model (USGS2001). The magnitude and significance of any trends shall be evaluated. Based on comparisons between pre-project, project, and background water level trends, **the project owner shall estimate the groundwater level change attributed to project pumping.** These calculations shall be supported using a tabular summary of the wells, current and historical water level measurements, a map of the groundwater elevation contours; calculated gradients; and conclusion and recommendations of a licensed California professional geologist or engineer.

D. Mitigation:

9. If groundwater levels have been lowered more than 20 feet below pre-construction levels in an offsite well and monitoring data indicates the water level decline is attributed to project pumping, then the project owner shall assess the impact to the water column above the pump and well screen and related impact to well yield.
10. Mitigation shall be provided to well owners that experience 20 feet or more of project-induced drawdown if well monitoring data confirms project pumping **causes all or a portion of the drawdown and either the previously submerged well screen has been exposed or the well yield or performance has been reduced such that the well fails to meet demand.** The type and extent of mitigation shall be determined by the amount of water level decline induced by the project, the type of impact, and site specific well construction and water use characteristics.

If an impact is determined to be caused by drawdown from more than one source, the level of mitigation provided shall be proportional to the amount of drawdown induced by the project relative to other sources. In order to be eligible, a well owner must provide documentation of the well location and construction, including pump intake depth, and evidence that the well was constructed in use before project pumping was initiated. The mitigation of impacts shall be determined as follows:

- a. Increased Electrical Usage. If project pumping has lowered a well's water levels and increased pumping lifts, increased energy costs shall be calculated. Payment or reimbursement for the increased costs shall be provided at the option of the affected well owner. In the absence of specific electrical use data supplied by the well owner, the following formula shall be used to calculate the additional electrical usage:

$$\text{Increased Cost for Energy} = (\text{change in lift/total hydraulic head}) \times (\text{total energy consumption times costs/unit of energy})$$

Where:

$$\text{change in lift (ft)} = \text{calculated change in water level in the well}$$

$$\text{total hydraulic head (ft)} = (\text{elevation head}) + (\text{discharge pressure head})$$

$$\text{elevation head (ft)} = (\text{wellhead discharge pressure gauge elevation}) - (\text{water level elevation in well during pumping})$$

$$\text{discharge pressure head (ft)} = (\text{pressure in pounds per square inch at wellhead discharge gauge}) \times (2.31 \text{ to convert psi to feet of water})$$

The project owner shall submit to the CPM for review and approval the documentation showing which well owners must be compensated for increased energy costs and that the proposed amount is sufficient compensation to comply with the provisions of this condition.

- i. Any reimbursements (either lump sum or annual) to impacted well owners shall be only to those well owners whose wells were in service within six months

of the Commission decision and within the 20-foot contour interval established in Item A above.

- ii. The project owner shall notify all owners of the impacted wells within one month of the CPM approval of the compensation analysis for increase energy costs.
- iii. Compensation shall be provided on either a one-time lump-sum basis, or on an annual basis, as described below.

Annual Compensation. Compensation provided on an annual basis shall be calculated prospectively for each year by estimating energy costs that will be incurred to provide the additional lift required as a result of the project. With the permission of the impacted well owner, the project owner shall provide energy meters for each well or well field affected by the project. The impacted well owner to receive compensation must provide documentation of energy consumption in the form of meter readings or other verification of fuel consumption. For each year after the first year of operation, the project owner shall include an adjustment for any deviations between projected and actual energy costs for the previous calendar year.

One-Time Lump-Sum Compensation. Compensation provided on a one-time lump-sum basis shall be based on a well-interference analysis, assuming the maximum project-pumping rate of 2,160 AF/y. Compensation associated with increased pumping lift for the life of the project shall be estimated as a lump sum payment as follows:

- i. The current cost of energy to the affected party considering time of use or tiers of energy cost applicable to the party's billing of electricity from the utility providing electric service, or a reasonable equivalent if the party independently generates their electricity;
 - ii. An annual inflation factor for energy cost of 3 percent; and
 - iii. A net present value determination assuming a term of 30 years and a discount rate of 9 percent;
- b. **Well Screen Exposure.** If groundwater monitoring data indicate project pumping has lowered water levels below the top of the well screen, and the well yield is shown no longer meet pre-project demand, compensation shall be provided to

diagnose and treat and well screen encrustation. Reimbursement shall be provided at an amount equal to the customary local cost of performing the necessary diagnosis and maintenance for well screen fouling. Should well yield reductions reoccur, the project owner shall provide payment or reimbursement for either periodic maintenance throughout the life of the project or replacement of the well.

- c. Well Yield. If project pumping has lowered water levels to significantly impact well yield so that it can no longer meet its intended purpose, causes the well to go dry, or cause casing collapse, payment or reimbursement of an amount equal to the cost of deepening or replacing the well shall be provided to accommodate these effects. Payment or reimbursement shall be at an amount equal to the customary local cost of deepening the existing well or constructing a new well of comparable design and yield (only deeper). The demand for water, which determines the required well yield, shall be determined on a per well basis using well owner interviews and field verification of property conditions and water requirements compiled as part of the pre-project well reconnaissance. Well yield shall be considered significantly impacted if it is incapable of meeting 100 percent of the well owner's maximum daily demand and 5-year average annual demand – assuming the pre-project well yield documented by the initial well reconnaissance met or exceeded these yield levels. The contribution of project pumping to observed decreases in observed well yield shall be determined by interpretation of the groundwater monitoring data collected and shall take into consideration the effect of other nearby pumping wells, basin-wide trends, and the condition of the well prior to the commencement of project pumping.
- d. The project owner shall notify any owners of the impacted wells within one month of the CPM approval of the compensation analysis.
- e. Pump Lowering. In the event that groundwater is lowered as a result of project pumping to an extent where pumps are exposed but well screens remain submerged, the pumps shall be lowered to maintain production in the well. The project shall reimburse the impacted well owner for the costs associated with lowering pumps in proportion to the project's contribution to the lowering of the groundwater table that resulted in the impact.
- f. Deepening of Wells. If the groundwater is lowered enough as a result of project pumping that well screens and/or pump intakes are exposed, and pump lowering is not an option,

such affected wells shall be deepened or replacement wells constructed. The project shall reimburse the impacted well owner for all costs associated with deepening existing wells or constructing replacement wells in proportion to the project's contribution to the lowering of the water table that resulted in the impact.

E. Monitoring Program Evaluation:

11. After the first five-year operational and monitoring period, and every subsequent 5-year period, the CPM shall evaluate the data and determine if the monitoring program water level measurement frequencies should be revised or eliminated. Revision or elimination of any monitoring program elements shall be based on the consistency of the data collected.

Verification: The project owner shall do all of the following:

1. At least sixty (60) days prior to project construction, the project owner shall submit to the CPM, for review and approval, a comprehensive plan (Groundwater Level Monitoring and Reporting Plan) presenting all the data and information required in Item A above. The project owner shall submit to the both the CPM all calculations and assumptions made in development of the plan.
2. During project construction, the project owner shall submit to the CPM quarterly reports presenting all the data and information required in Item B above. The project owner shall submit to the CPM all calculations and assumptions made in development of the report data and interpretations.
3. No later than sixty (60) days after commencing project operation, the project owner shall provide to the CPM, for review and approval, documentation showing that any mitigation to private well owners during project construction was satisfied, based on the requirements of the property owner as determined by the CPM.
4. During project operation, the project owner shall submit to CPM, applicable quarterly, semi-annual, and annual reports presenting all the data and information required in Item C above. The project owner shall submit to the CPM all calculations and assumptions made in development of report data and interpretations, calculations, and assumptions used in development of any reports.
5. The project owner shall provide mitigation as described in Item D above, if the CPM's inspection of the monitoring information confirms project-induced changes to water levels and water level trends relative to measured pre-project water levels, and well yield has been lowered by project pumping. The type and extent of mitigation shall be determined by the amount of water level decline and site-specific well construction and water use characteristics. The mitigation of impacts will be determined as set forth in Item D above.

6. No later than 30 days after CPM approval of the well drawdown analysis, the project owner shall submit to the CPM for review and approval all documentation and calculations describing necessary compensation for energy costs associated with additional lift requirements.
7. The project owner shall submit to the CPM all calculations, along with any letters signed by the well owners indicating agreement with the calculations, and the name and phone numbers of those well owners that do not agree with the calculations.
8. If mitigation includes monetary compensation, the project owner shall provide documentation to the CPM that compensation payments have been made by March 31 of each year of project operation or, if a lump-sum payment is made, payment shall be made by March 31 of the following year. Within 30 days after compensation is paid, the project owner shall submit to the CPM a compliance report describing compensation for increased energy costs necessary to comply with the provisions of this condition.
9. After the first 5-year operational and monitoring period, and every subsequent 5-year period, the project owner shall submit a 5-year monitoring report to the CPM for review and approval. This report shall contain all monitoring data collected and provide a summary of the findings and a recommendation about whether the frequency of water level measurements should be revised or eliminated.
10. During the life of the project, the project owner shall provide to the CPM all monitoring reports, complaints, studies, and other relevant data within 10 days of being received by the project owner.

GROUNDWATER QUALITY MONITORING, MITIGATION, AND REPORTING

SOIL&WATER-7 A water quality baseline of pre-construction conditions shall be established for all wells in the monitoring network established by Condition of Certification **SOIL&WATER-6**, including all monitoring wells that are installed to comply with Waste Discharge Requirements for the evaporation ponds and land treatment unit associated with the project, the existing BLM well and any retrofitted or newly installed BLM marsh water supply well. The primary objectives for the monitoring is to establish pre-construction and project related groundwater quality impacts that can be quantitatively evaluated to avoid, minimize, or mitigate significant adverse impacts to wells in the network from potential degradation in the quality of groundwater.

A. Plan. The project owner shall submit a Groundwater Quality Monitoring and Reporting Plan to the CPM for review and approval at least sixty (60) days prior to project construction. The Groundwater Quality Monitoring and Reporting Plan shall be a part of the Groundwater Monitoring and Reporting Plan required under

Condition of Certification **SOIL&WATER-6**, and shall include at a minimum:

1. A compilation of historical water quality data that can be used to establish baseline water quality conditions and compare with project water quality monitoring.
2. Where insufficient historical water quality data is available, identify additional sampling and analysis that will be completed prior to project construction to establish pre-project trends in water quality.
3. A description of the methodology for monitoring background and groundwater quality in all wells that are within the monitoring network established in Condition of Certification **SOIL&WATER-6**.
4. A description of the water quality analysis to be conducted on water samples collected from each well in the monitoring network. This description will include the purpose of each water quality analysis.
5. A description of the groundwater sample collection method for each analysis to be performed.
6. A description of the quality assurance/quality control that will be built into the sample collection and reporting protocol.
7. A description of the reporting requirements presented below, including a statistical analyses that will be performed on the data collected and a description of the mitigation that would be required for significant water quality impacts.
8. A schedule for monitoring all wells in the monitoring network.

B. Report During Pre-Construction. At least sixty (60) days prior to project construction, all groundwater quality monitoring data shall be submitted to the CPM for review and approval. The report shall include the following:

9. An assessment of pre-project groundwater quality with groundwater samples analyzed for TDS, chloride, nitrates, major cations and anions, and oxygen-18 and deuterium isotopes. These analyses, and particularly the stable isotope data, can be useful for identifying partially evaporated water sources and assessing their contributions to the quality of water produced by wells.

10. For the BLM marsh water supply well, at least two (2) groundwater samples shall be collected and analyzed for TDS, sodium, selenium, and oxygen-18 and deuterium isotopes. These analyses, and particularly the stable isotope data, can be useful for identifying partially evaporated water sources and assessing their contributions to the quality of water produced by wells.
11. The data shall be tabulated, summarized, and submitted to the CPM for review and approval. The data summary shall include the estimated range (minimum and maximum values), average, and median for each constituent analyzed. The data shall also be analyzed using the Mann-Kendall test for trend to assess whether pre-project water quality trends, if any, are statistically significant.

C. Monitor. During project construction and operation, the project owner shall semi-annually monitor the quality of groundwater semi-annually. The monitoring shall include:

12. Collection of groundwater samples from all monitoring network wells and analysis of these samples for TDS, chloride, nitrates, cations and anions, and oxygen-18 and deuterium isotopes. The BLM marsh water supply well shall also be analyzed for sodium and selenium. These analyses, and particularly the stable isotope data, can be useful for identifying partially evaporated water sources and assessing their contributions to the quality of water produced by wells.

D. Reporting During Construction and Operation. During project construction and operation, the project owner shall submit water quality reports semi-annually to the CPM and BLM. The groundwater quality data shall be tabulated, summarized, and analyzed to compare water quality to pre-project conditions. This analysis shall include analyses of trends and for contrast with the pre-project data as follows:

13. Water quality trends shall be analyzed using the Mann-Kendall test. Trends in the data shall be compared and contrasted to pre-project trends, if any.
14. If no significant water quality trends exist in the water quality data or the data set is insufficient to assess trends, the water quality data shall be combined for each well and contrasted to the pre-project well water quality data set.
15. The contrast between pre-project and water quality mean or median concentrations shall be compared using an Analysis of

Variance (ANOVA). A parametric ANOVA (for example, an F-test) can be conducted on the two data sets if the residuals between observed and expected values are normally distributed and have equal variance, or the data can be transformed to an approximately normal distribution. If the data cannot be represented by a normal distribution, then a nonparametric ANOVA shall be conducted (for example, the Kruskal-Wallis test). If a statistically significant difference is identified between the two data sets, the monitoring data are inconsistent with random differences between the pre-project and baseline data indicating a significant water quality impact from project pumping may be occurring.

16. If based on the water quality data the CPM and BLM determines that the quality of the water produced by the marsh water-supply well has been impacted by project pumping (exceeds pre-project constituent concentrations in TDS, chloride, nitrates, sodium, or selenium concentrations for three consecutive years) such that the water quality adversely affects the well's intended purpose, the project owner shall provide treatment or a new water supply to either meet or exceed pre-project water quality conditions.

E. Monitoring Program Evaluation. After the first five-year operational and monitoring period, and every subsequent 5-year period, the CPM shall evaluate the data and determine if the groundwater quality data collection frequencies and constituent list monitored should be revised or eliminated. Revision or elimination of any monitoring program elements shall be based on the consistency of the data collected.

Verification: The project owner shall complete the following:

1. At least sixty (60) days prior to construction, a Groundwater Quality Monitoring and Reporting Plan in compliance with Item A shall be submitted to the CPM for review and approval.
2. At least thirty (30) days prior to the start of construction, a pre-construction groundwater quality report in compliance with Item B shall be submitted to the CPM for review and approval.
3. Semi-annually, by March 31 and September 31, the project owner shall submit Groundwater Quality Reports in compliance with Item D to the CPM for review and approval and to the BLM for review.
4. After the first 5-year operational and monitoring period, and every subsequent 5-year period, the project owner shall submit a 5-year monitoring report to the CPM, for review and approval, that contains all groundwater quality data

collected and provides a summary of the findings and a recommendation about whether the frequency of groundwater quality data collection should be revised or eliminated.

5. During the life of the project, the project owner shall provide to the CPM all monitoring reports, complaints, studies, and other relevant data within 10 days of being received by the project owner.

WASTEWATER COLLECTION SYSTEM REQUIREMENTS

SOIL&WATER-8 The project owner shall recycle and reuse all process wastewater streams to the extent practicable. Prior to transport and offsite disposal of any facility operation wastewaters that are not suitable for treatment and reuse on-site, the project owner shall test and classify the stored wastewater to determine proper management and disposal requirements. The project manager shall ensure that the wastewater is transported and disposed of in accordance with the wastewater's characteristics and classification and all applicable LORS (including any CCR Title 22 Hazardous Waste and Title 23 Waste Discharges to Land requirements).

Verification: Prior to transport and offsite disposal of any facility operation wastewaters that are not suitable for treatment and reuse on-site, the project owner shall test and classify the stored wastewater to determine proper management and disposal requirements. All records of this testing and classification shall be maintain at the project site. The project manager shall ensure that the wastewater is transported and disposed of in accordance with the wastewater's characteristics and classification and all applicable LORS (including any CCR Title 22 Hazardous Waste and Title 23 Waste Discharges to Land requirements).

SEPTIC SYSTEM AND LEACH FIELD REQUIREMENTS

SOIL&WATER-9 Prior to the start of construction of the sanitary waste system, the project owner shall submit to the County of San Bernardino for review and comment, and to the CPM for review and approval, plans for the construction and operation of the project's proposed sanitary waste septic system and leach field. These plans shall comply with the requirements set forth in County of San Bernardino Code Title 3, Division 3, Chapter 8, Waste Management, Article 5, Liquid Waste Disposal and Title 6, Division 3, Chapter 3, and the Uniform Plumbing Code. Project construction shall not proceed until the CPM has approved the plans. The project owner shall remain in compliance with the San Bernardino County codes requirements for the life of the project.

Verification: Sixty (60) days prior to the start of commercial operations, the project owner shall submit to the County of San Bernardino appropriate fees and plans for review and comment for the construction and operation of the project's sanitary waste septic system and leach field. A copy of these plans shall be

simultaneously submitted to the CPM for review and approval. The plans shall demonstrate compliance with the sanitary waste disposal facility requirements of County of San Bernardino Codes Title 3, Division 3, Chapter 8, Waste Management, Article 5, Liquid Waste Disposal and Title 6, Division 3, Chapter 3, and the Uniform Plumbing Code.

NON-TRANSIENT, NON-COMMUNITY WATER SYSTEM

SOIL&WATER-10: The Project is subject to the requirement of Title 22, Article 3, Sections 64400.80 through 64445 for a non-transient, non-community water system (serving 25 people or more for more than six months). Pursuant to this requirement, the project owner shall obtain a permit from the County of San Bernardino to operate a non-transient, non-community water system.

Verification: The project owner shall obtain a permit to operate a non-transient, non-community water system with the County of San Bernardino at least sixty (60) days prior to commencement of construction at the site. The project owner shall supply updates annually for all monitoring requirements and submittals to County of San Bernardino related to the permit, and proof of annual renewal of the operating permit.

SOIL&WATER-11 As a conservation method, the project owner shall annually sequester a volume of Free Production Allowance (FPA) equal to the annual volume of groundwater pumped for the AMS project. This sequestration is subject to and defined by the following:

- The project owner shall exercise all option rights identified in the AFC and thereby acquire groundwater Base Annual Production rights totaling 10,478 AF/y.
- Sequester means that the project owner retain and refrain from exercising groundwater FPA use rights which the project owner could exercise under the Mojave Basin Area Adjudication.
- The project owner shall sequester annually a volume of groundwater equal to that year's volume of groundwater used for the AMS project, up to a maximum annual volume of 2,160 acre-feet.
- Sequestration shall continue annually for the life of the project.
- The annual sequestration of FPA is not intended to affect the Watermaster's implementation of the Mojave Basin Area Adjudication.
- Sequestered water would not be considered by the Energy Commission to be produced water subject to any replacement water obligation under the Mojave Basin Area Adjudication.

Verification: The volume of FPA sequestered shall be documented in the Annual Compliance Report submitted to the CPM and Watermaster. This documentation shall include a table showing the annual and cumulative total FPA sequestered.

SOIL&WATER-12 Under conditions stated below, the project owner may be required to contribute up to \$50,000 annually, for the life of the AMS project, towards the Mojave Water Agency's (MWA) turf replacement program, high-efficiency toilet program, or other water conservation program as approved by the CPM. This condition serves as a conservation measure.

The project owner's contribution to the MWA conservation program shall be an amount necessary to conserve groundwater equal in volume to the difference between the annual AMS project's water use and annual groundwater sequestered. If the project owner demonstrates that the annual or cumulative water sequestered equals or exceeds project water use, then no contribution to the MWA conservation program is required. Within the \$50,000 limit, the project owner shall ensure that the amount contributed to the water conservation program is adjusted on an annual basis to maintain the required amount of water conservation. The contribution shall be made the same month each year as established by the first year's contribution.

If the project owner proposes to change or add water conservation programs that can be funded for the purposes of this condition, a plan must be provided showing which programs are proposed, how much water savings can be achieved, and how much funding is proposed. The plan shall be provided for CPM review and approval in consultation with the Mojave Water Agency prior to the proposed date of change in water conservation programs.

Verification: The project owner shall do the following:

1. The project owner shall submit to the CPM the following documentation as part of the Annual Compliance Report:
 - a. A copy of the receipt from the MWA for the annual contribution; and
 - b. An accounting of the following:
 - i. The annual and cumulative volume of groundwater used by the project in acre-feet per year;
 - ii. The annual and cumulative volume of FPA sequestered by the project in acre-feet per year;
 - iii. The numerical difference between annual and cumulative totals in Items i and ii above; and

- iv. The annual and cumulative monetary contribution and estimated annual and cumulative volume of water conserved by the project owner's contribution to MWA's turf replacement program, high-efficiency toilet program, or other water conservation program approved by the CPM.
- 2. If the project owner proposes to reduce the amount of the annual contribution based on the water conservation achieved through previous contributions, the project owner shall provide a plan demonstrating how the adjusted amount will ensure the water conservation program meets the requirements of this condition. The plan shall be provided for CPM review and approval 60 days prior to the annual contribution anniversary date.




FIGURE E-1
100-YEAR FLOODPLAIN
CROSSED BY LOCKHART-TORTILLA TELECOMMUNICATION LINE





FIGURE E-2
100-YEAR FLOODPLAIN
CROSSED BY KRAMER-VICTOR TELECOMMUNICATION LINE



Source: NAIP 2005; Mojave Solar, LLC 2009





Figure E-3
Potential Jurisdictional Waters of the U.S. and State



Source: Mojave Solar LLC 2010; AECOM 2010; Edison 2011



Proposed New SCE Lockhart Substation Site	Proposed Telecommunication Path	SPS Alignment Field Verified Waters (AECOM) Jurisdiction	Freeways (TBM, 2010)
Existing Substation (SCE, 2010)	Kramer-Lockhart Path	U.S. and State Unvegetated Wash	Highways (TBM, 2010)
Mojave Solar (Abengoa Solar Inc.) Plant Site	Kramer-Victor Path	State Unvegetated Wash	Major Roads (TBM, 2010)
Existing Poles on Telecom Route	Lockhart-Tortilla Path	State Vegetated Swale	Minor Roads (TBM, 2010)
Existing Poles within 100ft of Jurisdictional Waters	Coolwater-Tortilla Path	U.S. and State Unvegetated Wash 100ft Buffer	Railroads (TBM, 2010)
	Pole Intersect Area	State Unvegetated Wash 100ft Buffer	
	Existing Poles to be Replaced	State Vegetated Swale 100ft Buffer	

LEGEND -

Potential Jurisdictional Waters of the U.S.

Unvegetated Wash (20.44 acres)

Potential Jurisdictional Waters of the State



Unvegetated Wash (10.08 acres)

Vegetated Swale (4.88 acres)

SPS Alignment

**PROPOSED NEW SCE LOCKHART
SUBSTATION PORTIONS OF ROUTE
REQUIRING INTERSET POLES**

E-5



Source: Mojave Solar LLC 2010; AECOM 2010; ESRI 2011



APPENDIX F

SOUTHERN CALIFORNIA EDISON LOCKHART SUBSTATION PROJECT DESCRIPTION FOR ABENGOA SOLAR, INC.

The April 15, 2010 Lockhart Substation Project Description is a draft description of the substation, interconnect and fiber-optic telecommunication system prepared by SCE. This description was used in generating the project description in the EA, however it should be noted that the description was modified between April 2010 and January 2011 to accommodate minor modifications to the proposed SPS upgrades and design assumptions. Changes to the description are accounted for in the EA project description, Chapter 2.0. The construction equipment and workforce projections found in the April 15, 2010 tables were used in the impact analysis and are therefore included in this appendix as reference.

SOUTHERN CALIFORNIA EDISON
LOCKHART SUBSTATION
PROJECT DESCRIPTION
FOR ABENGOA SOLAR INC.

Dated: April 15, 2010

LOCKHART SUBSTATION PROJECT DESCRIPTION

Table of Contents

1.0	Project Overview
2.0	Project Location
3.0	Lockhart Substation
3.1	Substation Design and Equipment
3.2	Substation Construction
3.2.1	Grading and Ground Disturbance
	Table 1: Substation Materials and Estimated Volumes
3.2.2	Construction Yard/Staging Areas
3.2.3	Geotechnical Studies
3.2.4	Below Grade Construction
3.2.5	Equipment Installation
3.2.6	Hazards and Hazardous Materials
3.2.7	Waste Management
3.2.8	Post-Construction Cleanup
3.2.9	Construction Equipment Personnel and Temporary Facilities
	Table 2: Construction Equipment and Personnel Use Estimations
4.0	Transmission Lines and Related Structures
4.1	Transmission Line and Related Structures Design and Equipment
4.1.1	220 kV Transmission Line Loop-In Design
4.1.2	Existing 220 kV Transmission Line Structure Modification/Replacement Design
4.1.3	220 kV Generation Tie Line Extension Design
4.2	Transmission Line and Related Structures Construction
4.2.1	Transmission Line Access and Spur Roads
4.2.2	Marshalling Yard/Staging Areas
4.2.3	Temporary Bypass Facilities
4.2.4	Construction of New 220 kV Transmission Structures
4.2.5	Removal of Existing 220 kV Transmission Structure
4.2.6	Wire Stringing of 220 kV Conductor
4.2.7	Housekeeping and Construction Site Cleanup
	Table 3: Ground Disturbance Table – Transmission Line Construction
4.2.8	Operation and Maintenance
4.2.9	Labor and Equipment
	Table 4: Construction Equipment and Workforce Estimates by Activity- 220 kV Loop-In Lines
	Table 5: Construction Equipment and Workforce Estimates by Activity- 220 kV Generation Tie Line Connection on SCE Property
	Table 6: Construction Equipment and Workforce Estimates by Activity- Transmission Line Structure Removal

- 5.0 Distribution System for Station Light and Power
 - 5.1 Distribution System Design and Equipment
 - Table 7: Construction Equipment and Workforce Estimates by Activity-12kV Hutt Station Light & Power
 - 5.2 Distribution System Construction
- 6.0 Telecommunication System
 - 6.1 Telecommunication System Design and Equipment
 - Table 8: Summary of Proposed Telecommunications Fiber Optic Cables Estimates
 - 6.2 Telecommunication System Construction
 - Table 9: Telecommunications Labor Force and Construction Equipment Estimates
 - Table 10: Construction Equipment and Workforce Estimates by Activity – Construct Kramer-Victor Fiber Optic Cable
 - Table 11: Ground Disturbance Kramer-Victor Fiber-Optic Cable
- 7.0 Figures
 - Figure 1: Proposed New SCE Lockhart Substation Site
 - Figure 2: Proposed New SCE Lockhart Substation and Associated Electrical Lines
 - Figure 3-1: Overview of Proposed New Telecommunication Fiber Optic Cables for the Lockhart Project
 - Figure 3-2: Proposed New Telecommunication Fiber Optic Cable Connecting Kramer Substation to New Lockhart Substation
 - Figure 3-3: Proposed New Telecommunication Fiber Optic Cable Connecting New Lockhart Substation to Tortilla Substation
 - Figure 3-4: Proposed New Telecommunication Fiber Optic Cable Connecting Tortilla Substation to Coolwater Substation (Not Built – In Permitting Phase)
 - Figure 3-5: Proposed New Telecommunication Fiber Optic Cable Connecting New SCE Lockhart Substation to Abengoa Alpha and Beta Facilities
 - Figure 3-6: Proposed New Telecommunication Fiber Optic Cable Connecting Kramer Substation to Victor Substation
 - Figure 3-7: Proposed New Telecommunication Facility at Tortilla Substation
 - Figure 4-1: 220 kV Lattice Steel Tower Configuration
 - Figure 4-2: 220 kV Tubular Steel Pole Configuration
 - Figure 5: Distribution Pole Configuration
 - Figure 6: Cross Sections
 - Figure 7: Typical 115 kV H-Frame Subtransmission Structure

PROJECT DESCRIPTION

Abengoa Solar Inc. (Abengoa) applied to the California Independent System Operator (CAISO) for interconnection of a new 250 MW solar generation Lockhart Project currently referred to as the *Abengoa Mojave Solar Project* (AMSP). Abengoa requested and paid for Interconnection Studies in accordance with the CAISO Large Generation Interconnect Procedures (LGIP) Tariff. The CAISO assigned Queue Position 125 to the AMSP. All applicable interconnection studies have been completed for the AMSP, and Abengoa is currently negotiating the execution of the Large Generator Interconnection Agreement (LGIA) under an “Energy Only” service arrangement with the implementation of Special Protection System (SPS). Such service arrangement could result in the need to implement congestion management protocols which could result in the curtailment of generation resources in the area during times when total generation production in the area exceeds the total area transmission capability.

1.0 Project Overview

Southern California Edison (SCE) proposes to construct the Lockhart Substation and associated facilities to interconnect the 250 MW AMSP to SCE’s existing Cool Water-Kramer No.1 220 kV transmission line (Lockhart Project). This project description is prepared for Abengoa for use in its California Energy Commission (CEC) Application for Certification (AFC) (docket 09-AFC-05) and Bureau of Land Management (BLM) Environmental Impact Statement (EIS). Major components of the Lockhart Project are summarized below:

- *Lockhart Substation:* Construct a new 220 kV Substation to loop-in the existing Cool Water-Kramer No. 1 220 kV transmission line and to provide two 220 kV line positions to terminate two new 220 kV generation tie lines (gen-ties) owned by AMSP.
- *Transmission Lines:* Loop the existing Cool Water-Kramer No. 1 220 kV transmission line into the new Lockhart Substation. The transmission loop would require construction of approximately 3,000 feet of new transmission line segments (comprised of two line segments of approximately 1,500 feet each) creating the new Lockhart-Kramer and Cool Water-Lockhart 220 kV transmission lines.
- *Generation Tie Line Connections:* Connect the two AMSP-built gen-ties into the SCE-owned Lockhart Substation. This work involves construction of two single spans of conductors between the Lockhart switchrack and the last AMSP-owned tower(s).
- *Distribution Systems:* Connect the existing Hutt 12 kV distribution circuit out of the Hutt Poletop Substation replacing one and removing one existing pole approximately 40 feet north of the Lockhart Substation. A range of approximately 200-400 feet of underground conduit would be installed from the replaced pole to the substation to provide a path for one of the two required sources of station light and power. Provide temporary power for the construction of both the proposed Lockhart Substation and the AMSP facilities.
- *Telecommunications Facilities:* Install fiber optic communication cables, associated poles, conduits, and other telecommunication facilities to provide diverse path routing of

communications required for the AMSP interconnection, and to provide communications redundancy at the two AMSP power blocks. Facilities would include construction of a telecommunications room at Tortilla Substation. Work would also include installing communication paths between the Victor, Roadway, Tortilla, Kramer, Lockhart, and Cool Water Substations.

This project description is based on planning level assumptions. Further details will be made available upon completion of preliminary and final engineering, identification of field conditions, verification of availability of materials and equipment, and compliance with applicable environmental and permitting requirements. With regards to construction work activities, SCE anticipates working typical construction schedules; however, the actual construction hours may vary.

2.0 Project Location

The Lockhart Substation would be located on private land within the boundaries of the new AMSP solar generation facility, approximately 5.5 miles north-east of the intersection of California State Highway 58 and Harper Lake Road in the County of San Bernardino (see Figure 1). At this time, the extent of the SCE portion of the overall facility property would be approximately 8 to 10 acres including the Lockhart Substation, minimum 10-foot wide safety buffers, access for new loop-in line segments, and two gen-ties. To accommodate the proposed Lockhart Substation location within Abengoa's identified property and to allow for future access to the substation, a corridor (transmission right-of-way (ROW)) would also be provided to SCE along the southern boundary of the AMSP paralleling the AMSP water drainage channel. Abengoa would provide temporary construction yards/staging areas, approximately 4 acres combined, necessary for substation, transmission, distribution systems, and telecommunication facilities to construct the Lockhart Project.

The electrical distribution system to provide station light and power would tap into the existing Hutt 12 kV distribution circuit that is in immediate proximity to the Lockhart Substation site.

The telecommunication facilities, needed to provide adequate line protection, would require the installation of new fiber optic cable from: 1) SCE's Kramer Substation to Lockhart Substation on an existing distribution pole line (see Figure 3-1), 2) SCE's proposed Lockhart Substation to SCE's Tortilla Substation on existing distribution pole lines and approximately 1,500 feet of new underground and approximately 11,000 feet of new overhead pole line (see Figure 3-2), 3) SCE's Tortilla Substation to SCE's Cool Water Substation on existing distribution pole lines (see Figure 3-2), and 4) SCE's Lockhart to the AMSP Alpha and Beta plant sites (two routes are required to each plant site as shown in Figure 3-4). In addition, a new telecommunication facility would be required within SCE's Tortilla Substation (see Figure 3-6).

Abengoa elected to interconnect to SCE's transmission system with the implementation of a Special Protection System (SPS). Implementation of the SPS would enable the AMSP to operate under an "Energy Only" service arrangement. The telecommunication facilities needed for the SPS would require the installation of new fiber optic cable from SCE's Victor Substation to

SCE's Kramer Substation on the existing Kramer-Victor 115 kV line (see Figure 3-5), and the installation of an optical repeater site would be required at SCE's Roadway Substation.

3.0 Lockhart Substation

The Lockhart Substation would be a 220 kV switching station with internal measurements of approximately 450 feet by 550 feet. Lockhart Substation would be an unattended collector station (no power transformation) surrounded by a wall or chain-link fence with two gates (see Figure 2).

3.1 Substation Design and Equipment

SCE would engineer, design, construct, and test the proposed Lockhart Substation. The substation would consist of a six-bay 220 kV switchrack. One bay position would be utilized to loop the SCE Cool Water-Kramer No. 1 220 kV transmission line. Two of the bays would be used to terminate the two AMSP gen-ties. The three remaining positions would be available for future use.

Lockhart Substation would be initially equipped with:

- Two (2) overhead 220 kV buses
- Seven (7) 220 kV circuit breakers
- 220 kV disconnect switches
- One (1) Mechanical Electrical Equipment Room (MEER)
- Light and power transformers
- Station lighting
- Back-up generator

3.2 Substation Construction

3.2.1 Grading and Ground Disturbance

Because the Lockhart Substation would be located within the boundaries of the AMSP, the grading of the substation site would be included within the solar developer's overall grading design. Therefore, SCE would neither prepare a grading and drainage plan, nor would SCE apply for grading permits from the County of San Bernardino. Prior to Abengoa's submittal of the site grading application to the County, SCE would review and approve that portion of the grading design pertaining to the substation location. Abengoa would carry out site grading in accordance with the developer's county approved grading plans.

Also, land disturbance areas and earth moving quantities, including vehicle emissions at the substation location are included within the AMSP facilities application.

Upon completion of the site preparation by the developer, SCE would assume responsibility for the remainder of the Lockhart Substation construction including the installation of a temporary chain-link fence surrounding the construction site.

Access to the substation site for both construction and operation would be gained through the solar facilities internal road network from its main access on Harper Lake Road. This internal road network would be paved as identified in the AMSP facility application.

Table 1 below provides the approximate area of land disturbance at the Lockhart Substation site within the substation fences, and the approximate volume and type of earth materials that would be used or disposed by SCE during Substation construction.

Table 1: Substation Materials and Estimated Volumes

Element	Material	Approximate Volume (yd³)
Substation Equipment Foundations	Concrete	1,350
Equipment and cable trench excavations *	Soil	1,530
Cable Trenches**	Concrete	25
Internal Driveway	Asphalt concrete	440
	Class II aggregate base	630
Substation Rock Surfacing	Rock, nominal 1 to 1-1/2 inch per SCE Standard	2,400

Notes to Table 1

- * Excavation “spoils” would be placed on site during the below-ground construction phase to the extent possible.
- ** Standard cable trench elements are factory fabricated, delivered to the site and installed by crane. Intersections are cast in place concrete.

3.2.2 Construction Yard/Staging Areas

Abengoa would provide a temporary staging yard, approximately 1.5 acres, necessary to construct the Lockhart Substation.

3.2.3 Geotechnical Studies

Prior to the start of construction, Abengoa would conduct a geotechnical study of the substation site and the transmission line routes, including an evaluation of the depth to the water table, evidence of faulting, liquefaction potential, physical properties of subsurface soils, soil resistivity, slope stability, and the presence of hazardous materials.

3.2.4 Below Grade Construction

After the substation site is graded, below grade facilities would be installed. Below grade facilities include a ground grid, underground conduit, trenches, and all required foundations. The design of the ground grid would be based on soil resistivity measurements collected during a geotechnical investigation prior to the construction.

3.2.5 Equipment Installation

Above grade installation of substation facilities (i.e., buses, circuit breakers, steel structures, and the MEER) would commence after the below grade structures are in place.

3.2.6 Hazards and Hazardous Materials

Construction and operation of the Lockhart Substation would require the limited use of hazardous materials such as fuels, lubricants, and cleaning solvents. SCE would comply with all applicable laws relating to hazardous materials use, storage, and disposal. A Stormwater Pollution Prevention Plan (SWPPP) would also be prepared by Abengoa for the Lockhart Substation Project.

3.2.7 Waste Management

Construction of the Lockhart Substation would result in the generation of various waste materials including soil, vegetation, and sanitation waste (portable toilets). Soil excavated for the Lockhart Substation site would either be used as fill or disposed of off-site at an appropriately licensed waste facility. Sanitation waste (i.e., human generated waste) would be disposed of according to the sanitation waste management practices.

3.2.8 Post-Construction Cleanup

Any damage to existing roads as a result of construction would be repaired, to the extent possible, once construction is completed in accordance with local agency requirements. Following completion of construction activities, SCE would also restore all areas that were temporarily disturbed by construction of the Lockhart Substation to as close to preconstruction conditions as possible, or where applicable, to the conditions agreed upon between the landowner and SCE. In addition, all construction materials and debris would be removed from the area and recycled or properly disposed of off-site. SCE would conduct a final inspection to ensure that cleanup activities were successfully completed.

3.2.9 Construction Equipment Personnel and Temporary Facilities

The estimated elements, materials, number of personnel and equipment required for construction of the Lockhart Substation are summarized below in Table 2 and include construction of the telecommunications room at Tortilla Substation. In addition to the information provided in Table 2, a temporary contractor office trailer and equipment trailer would be placed within the proposed substation construction area during the construction phase of the Lockhart Substation Project.

Construction would be performed by either SCE construction crews or its contractors. Contractor construction personnel would be managed by SCE construction management personnel. SCE anticipates a total of approximately 14 construction personnel working on any given day. SCE also anticipates that crews would work concurrently whenever possible; however, the estimated deployment and number of crew members would be dependent upon

County permitting, material availability, and construction scheduling. For example, electrical equipment (such as substation MEER, wiring, and circuit breaker) installation may occur while transmission line construction would be proceeding.

Table 2: Construction Equipment and Personnel Use Estimations

Activity and number of Personnel	Number of Work Days	Equipment and Quantity	Duration of Use (Hours/Day)
Survey (2 people)	10	2-Survey Trucks (Gasoline)	8
Grading (8 people)	40	1-Dozer (Diesel)	4
		2-Loader (Diesel)	4
		1-Scraper (Diesel)	3
		1-Grader (Diesel)	3
		1-Water Truck (Diesel)	2
		2-4X4 Backhoe (Diesel)	2
		1-4X4 Tamper (Diesel)	2
		1-Tool Truck (Gasoline)	2
		1-Pickup 4X4 (Gasoline)	2
Fencing (4 people)	25	1-Bobcat (Diesel)	8
		1-Flatbed Truck (Gasoline)	2
		1-Crewcab Truck (Gasoline)	4
Civil (8 people)	70	1-Excavator (Diesel)	4
		1-Foundationauger (Diesel)	5
		2-Backhoes (Diesel)	3
		1-Dump truck (Diesel)	2
		1-Cement truck (Diesel)	2
		1-Skip Loader (Diesel)	3
		1-Water Truck (Diesel)	3
		2-Bobcat Skid Steer (Diesel)	3
		1-Forklift (Propane)	4
		1-17TonCrane (Diesel)	2 hours/day for 45 days
		1-Tool Truck (Gasoline)	3
MEER (4 people)	40	1-Carry-all Truck (Gasoline)	3
		1-Stake Truck (Gasoline)	2
Electrical (8 people)	90	2-Scissor Lifts (Propane)	3
		2-Manlifts (Propane)	3
		1-Reach Manlift (Propane)	4
		1-15 ton Crane (Diesel)	3
		1-Tool Trailer	3
		2-Crew Trucks (Gasoline)	2

Activity and number of Personnel	Number of Work Days	Equipment and Quantity	Duration of Use (Hours/Day)
Wiring (2 people)	50	1-Manlift (Propane) 1-Tool Trailer	4 3
Maintenance Crew Equipment Check (2 people)	45	2-Maintenance Trucks (Gasoline) 1- Wiring Truck (Gasoline)	4 3
Testing (2 people)	80	1-Crew Truck (Gasoline)	3
Asphalting (6 people)	50	2-Paving Roller (Diesel) 1-Asphalt Paver (Diesel) 1-Stake Truck (Gasoline) 1-Tractor (Diesel) 1-Dump Truck (Diesel) 2-Crew Trucks (Gasoline) 1-Asphalt Curb Machine (Diesel)	4 4 4 3 3 2 3

4.0 Transmission Lines and Related Structures

SCE's transmission line requirements for the Lockhart Substation interconnection to the Cool Water-Kramer No. 1 220 kV transmission line would consist of the following components: 1) 220 kV transmission line loop-in, 2) existing 220 kV transmission line structure modification/replacement, and 3) 220 kV gen-tie extension. Each of these components is described below.

4.1 Transmission Line and Related Structures Design and Equipment

4.1.1 220 kV Transmission Line Loop-In Design

The proposed Lockhart Substation would be connected to the Coolwater-Kramer No. 1 220 kV transmission line via loop-in transmission segments. The two loop-in line segments would create two new separate transmission lines: the Coolwater-Lockhart 220 kV transmission line; and the Kramer-Lockhart 220 kV transmission line. Each transmission line segment into the Lockhart Substation would be approximately 1,500 feet long (see Figure 2).

The proposed loop-in of the existing Coolwater-Kramer No. 1 220 kV transmission line would require approximately four double circuit transmission structures to enter the Lockhart Substation. The exact combination of new tubular steel poles (TSP) and/or lattice steel towers (LST) needed for the loop-in would be determined during detailed engineering (see Figures 4-1 and 4-2).

Two of the 220 kV double circuit structures would be constructed just outside of the substation fence or wall. The other two structures would be used to re-route the Coolwater-Kramer No. 1 220 kV transmission line into Lockhart Substation. The conductor utilized would be a single 1590 kcmil “Lapwing” ACSR conductor per phase.

The section of line connecting the existing Coolwater-Kramer No. 1 220 kV transmission line to the first structure outside of Lockhart Substation would require a new right of way, as shown in Figure 2, between SCE’s existing ROW and the new Lockhart Substation facilities.

4.1.2 Existing 220 kV Transmission Line Structure Modification/Replacement Design

To support the loop-in, one existing double circuit transmission structure may need to be removed. However, the exact number of towers to be removed would be determined during detailed engineering.

4.1.3 220 kV Generation Tie Line Extension Design

The proposed Lockhart Substation design would involve bringing two 220 kV gen-tie segments into a 220 kV position. SCE understands that there would be one customer-owned double circuit structure outside the SCE-owned Lockhart Substation facilities to support connection of the two customer gen-ties.

SCE’s scope of work would involve connecting the gen-ties from the customer owned dead end structures to the appropriate 220 kV position inside Lockhart Substation. The span needed for this connection is estimated to be up to 300 feet depending on the location of the transmission line tower relative to Lockhart Substation. The conductor utilized would be a single 1590 kcmil “Lapwing” Aluminum Conductor Steel Reinforced (ACSR) per phase.

4.2 Transmission Line and Related Structures Construction

Construction activities would consist of the receiving and handling of construction materials, rehabilitation of existing and creation of new access roads for construction activities, site preparation, assembly and erection of structures, removal of existing structure(s), stringing of conductors, and site cleanup.

4.2.1 Transmission Line Access and Spur Roads

This portion of the Lockhart Substation Project would involve construction within existing and new ROWs. Existing public roads, as well as existing transmission line roads would be used as much as possible during construction of this project. However, the project would require new transmission line roads to access the new transmission line segments and structure locations. Transmission line roads are classified into two groups; access roads and spur roads. Access roads are through roads that run between tower sites along a ROW and serve as the main transportation route along line ROWs. Spur roads are roads that lead from access roads and terminate at one or more structure sites.

Rehabilitation work may be necessary in some locations along the existing transmission line roads to accommodate construction activities. This work may include the re-grading and repair of existing access, spur roads and associated drainage hardware. These roads would be cleared of vegetation; blade-graded to remove potholes, ruts, and other surface irregularities; and re-compacted to provide a smooth and dense riding surface capable of supporting heavy construction equipment. The graded road would have a minimum drivable width of 14 feet with 2 feet of shoulder on each side (depending upon field conditions).

Similar to rehabilitation of existing roads, all new road alignments would first be cleared and grubbed of vegetation; roads would be blade-graded to remove potholes, ruts, and other surface irregularities; fill material would be deposited where necessary; and roads would be re-compacted to provide a smooth and dense riding surface capable of supporting heavy construction equipment. The graded road would have a minimum drivable width of 14 feet with 2 feet of shoulder on each side, but may be wider depending on final engineering requirements and field conditions. New road gradients would be leveled so that any sustained grade would not exceed 12 percent. Drainage hardware would be installed where necessary to ensure adequate drainage of the road to reduce erosion and rutting. All curves would have a radius of curvature of not less than 50 feet measured at the center line of the usable road surface. The new roads would typically have turnaround areas near the structure locations.

4.2.2 Marshalling Yard/Staging Areas

A marshalling yard would be required for the construction of the transmission line loop-in segments and the gen-tie connection to SCE's proposed Lockhart Substation. A temporary equipment and material staging area would also be established for short-term utilization within AMSP property as needed.

Equipment and materials to be stored at the temporary equipment and material staging area may include:

- Construction trailer
- Construction equipment
- Conductor/wire reels
- Transmission structure components
- Overhead ground wire/Optical ground wire cable
- Hardware
- Insulators
- Consumables, such as fuel and joint compound
- Portable sanitation facilities
- Waste materials for salvaging, recycling, and/or disposal

The size of the temporary equipment and material staging area would be dependent upon a detailed site inspection and would take into account, where practical, suggestions by the SCE crew foreman or the SCE contractor selected to do the work. An area of approximately 0.5 to 1.5 acres would be required. Additional temporary areas may be required for crew "show up" yards and would be used for temporary parking. Land disturbed at the temporary equipment and

material staging area would be restored, to the extent possible, to preconstruction conditions following the completion of construction.

4.2.3 Temporary Bypass Facilities

SCE may temporarily transfer the existing Coolwater-Kramer No 2 220 kV conductor to temporary structures during the removal and replacement of the existing Coolwater-Kramer No. 1 220 kV structures. Upon completion of the construction of the 220 kV replacement structures and dismantling of the existing 220 kV structure to a level below the conductor attachment height, the existing conductor would be transferred over from the temporary structures and attached to the new 220 kV structures. The exact number of temporary transmission structures and the related ground disturbance would not be known until final engineering is performed.

4.2.4 Construction of New 220 kV Transmission Structures

The proposed sites for the new structures would first be graded and/or cleared of vegetation as required to provide a reasonably level and vegetation-free surface for footing and structure construction. The temporary laydown area, approximately 200 feet by 200 feet (0.92 acre), required for the assembly of the structures would also be cleared of vegetation and graded as required to provide a reasonably level and vegetation-free surface for the laydown, assembly, and erection of the structures. Erection of the structure would require an erection crane to be set up adjacent to and 60 feet from the centerline of the structure. A crane pad would be located within the laydown area used for structure assembly. If the existing terrain is not suitable to support crane activities, a temporary 50 feet by 50 feet (0.06 acre) crane pad would be constructed.

The structures would require drilled, poured-in-place, concrete footings that would form the structure foundation. Actual footing diameters and depths for each of the structure foundations would depend on the soil conditions and topography at the site and would be determined during final engineering.

The foundation process starts with the excavation of the hole for the structure. The hole would be excavated using truck or track-mounted auger with various diameter augers to match the diameter requirements of the structure. The excavated material would be distributed at the structure site, used as fill for the new roads or substation site, or used in the rehabilitation of existing access roads. Alternatively, the excavated soil may be disposed of at an off-site disposal facility in accordance with all applicable laws.

Following excavation of the foundation footing for each structure, steel reinforced rebar cage(s) would be set in the excavated footing holes, anchor bolts and/or stub angles would be set in place, precision would be verified by a surveyor, and concrete would then be placed. The steel reinforced rebar cage(s) would be assembled off site and delivered to the structure location by flatbed truck. A typical transmission structure would require approximately 50-80 cubic yards of concrete delivered to the structure location depending upon the type of structure being constructed, soil conditions, and topography at each site. The transmission structure footings would project approximately 1-4 feet above the ground level.

During construction, existing commercial ready-mix concrete supply facilities would be used where feasible. If commercial ready-mix concrete supply facilities do not exist within the general area of need, a temporary concrete batch plant would be set up. If necessary, approximately two acres of land would be sub-partitioned from the temporary equipment and material staging area within the Lockhart Substation site/property for a temporary concrete batch plant. Equipment would include a central mixer unit (drum type); three silos for injecting concrete additives, fly ash, aggregate, and cement; a water tank; portable pumps; a pneumatic injector; and a loader for handling concrete additives not in the silos. Dust emissions would be controlled by watering the area and by sealing the silos and transferring the fine particulates pneumatically between the silos and the mixers.

The assembly would consist of hauling the structure components from the staging yard to their designated structure location using semi-trucks with 40-foot trailers and off loaded at site. Crews would then assemble portions of each structure on the ground at the structure location, while on the ground, the top section may be pre-configured with the necessary insulators and wire-stringing hardware before being set in place. An 80-ton all-terrain or rough-terrain crane would be used to position the base section on top of previously prepared foundation. When the base section is secured, the remaining portions of the structure would then be placed upon the base section and bolted together.

After construction is completed, the transmission structure site would be graded such that water would run toward the direction of the natural drainage. In addition, drainage would be designed to prevent ponding and erosive water flows that could cause damage to the structure footing. The graded area would be compacted and would be capable of supporting heavy vehicular traffic.

4.2.5 Removal of Existing 220 kV Transmission Structure

Transmission line facilities planned to be removed would include an existing 220 kV transmission structure, and associated hardware (i.e. insulators, vibration dampeners, suspension clamps, ground wire clamps, shackles, links, nuts, bolts, washers, cotters pins, insulator weights, and bond wires). The existing access routes would be used to reach the structure site, but some rehabilitation work on these routes may be necessary before removal activities begin. In addition, grading may be necessary to establish a temporary laydown area approximately 150 feet by 150 feet (0.52 acre) adjacent to the existing structure for equipment and material staging during the structure removal. A crane truck or rough terrain crane would be used to support the structure during dismantle and removal. A crane pad would be located within the laydown area used for structure assembly. If the existing terrain is not suitable to support crane activities, a temporary 50 feet by 50 feet (0.06 acre) crane pad would be constructed. The existing structure footings would be removed to a depth of approximately 2 feet below ground level. Holes would be filled, compacted, and the area would be smoothed to match surrounding grade.

SCE may temporarily transfer the existing 220 kV conductor to temporary structures during the removal and replacement of the existing 220 kV structure. Upon completion of the construction of the 220 kV replacement structures and dismantling of the existing 220 kV structure to a level

below the conductor attachment height, the existing conductor would be transferred over from the temporary structures and attached to the new 220 kV structures.

4.2.6 Wire-Stringing of 220 kV Conductor

Wire-stringing would include all activities associated with the installation of conductors, including the installation of primary conductor and overhead ground wire (OHGW), vibration dampeners, weights, spacers, and suspension and dead-end hardware assemblies. Insulators and stringing sheaves (rollers or travelers) would be typically attached during the steel erection process.

A standard wire-stringing plan would include a sequence of events starting with determination of wire pulls and wire pull equipment set-up positions. Advanced planning by supervision determines circuit outages, pulling times, and safety protocols to ensure that safe and effective installation of wire is accomplished.

Wire-stringing activities would be conducted in accordance with SCE specifications that are similar to process methods detailed in Institute of Electrical and Electronics Engineers Standard 524-2003, Guide to the Installation of Overhead Transmission Line Conductors.

Wire pulls would include the length of any given continuous wire installation process between two selected points along the line. Wire pulls would be selected, where possible, based on availability of dead-end structures at the ends of each pull, geometry of the line as affected by points of inflection, terrain, and suitability of stringing and splicing equipment setups. In some cases, it may be preferable to select an equipment setup position between two suspension structures. Anchor rods would then be installed to provide dead-ending capability for wire sagging purposes, and also to provide a convenient splicing area.

To ensure the safety of workers and the public, safety devices such as traveling grounds, guard structures, and radio-equipped public safety roving vehicles and linemen would be in place prior to the initiation of wire-stringing activities.

The following four steps describe the wire installation activities proposed by SCE:

- **Step 1: Sock Line, Threading:** Typically, a lightweight sock line would be passed from structure to structure, which would be threaded through the wire rollers in order to engage a camlock device that would secure the pulling sock in the roller. This threading process would continue between all structures through the rollers of a particular set of spans selected for a conductor pull.
- **Step 2: Pulling:** The sock line would be used to pull-in the conductor pulling cable. The conductor pulling cable would be attached to the conductor using a special swivel joint to prevent damage to the wire and to allow the wire to rotate freely to prevent complications from twisting as the conductor unwinds off the reel. A piece of hardware known as a running board would be installed to properly feed the conductor into the roller. This device keeps the bundle conductor from wrapping during installation.

- Step 3: Splicing, Sagging, and Dead-ending: After the conductor is pulled-in, the conductor would be sagged to proper tension and dead-ended to structures.
- Step 4: Clipping-in, Spacers: After the conductor is dead-ended, the conductors would be secured to all tangent structures; a process called clipping in. Once this is complete, spacers, if applicable, would be attached between the bundled conductors of each phase to keep uniform separation between each conductor.

The dimensions of the area needed for the stringing setups associated with wire installation are variable and depend upon terrain. The preferred minimum area needed for tensioning equipment set-up sites would require approximately 150 feet by 500 feet (1.72 acres). The preferred minimum area needed for pulling equipment set-up sites would require approximately 150 feet by 300 feet (1.03 acres). Crews though can work from within slightly smaller areas when space is limited. Each stringing operation would include one puller positioned at one end and one tensioner and wire reel stand truck positioned at the other end.

Stringing equipment that cannot be positioned at either side of a dead-end transmission structure would require installation of temporary field snubs (i.e. anchoring and dead-end hardware) to sag conductor wire to the correct tension.

The puller and tensioner set-up locations would require level areas to allow for maneuvering of the equipment. When possible, these locations would be located on existing level areas and existing roads to minimize the need for grading and cleanup. The final number and locations of the puller and tensioner sites would be determined during detailed engineering for the Lockhart Project based on the construction methods chosen by SCE or its contractor.

An overhead ground wire (OHGW) or optical ground wire (OPGW) for shielding would be installed on the transmission line and would be installed in the same manner as the conductor. The OHGW or OPGW would typically be installed in conjunction with the conductor, depending upon various factors including line direction, inclination, and accessibility.

4.2.7 Housekeeping and Construction Site Cleanup

During construction, water trucks may be used to minimize the quantity of airborne dust created by construction activities. Any damage to existing roads as a result of construction would be repaired, to the extent possible, once construction is complete.

SCE would restore, to the extent possible, all areas that are temporarily disturbed by Lockhart Substation Project activities (including equipment and material staging yard, pull and tension sites, and structure laydown and assembly sites) to preconstruction conditions following the completion of construction. Restoration may include grading and restoration of sites to original contours and reseeding where appropriate. In addition, all construction materials and debris would be removed from the area and recycled or properly disposed of at an off-site disposal facility in accordance with all applicable laws. SCE would conduct a final inspection to ensure that cleanup activities are successfully completed.

Table 3 below provides information on temporary and permanent land disturbance areas related to construction of the transmission lines.

Table 3: Ground Disturbance Table – Transmission Line Construction

Lockhart Project Feature	Site Quantity	Disturbed Acreage Calculation (L x W)	Acres Disturbed During Construction	Acres to be restored	Acres Permanently Disturbed
Modify Existing 220 kV Lattice Steel Tower (1)	0	150' x 150'	0	0	0.000
Remove Existing 220 kV Lattice Steel Tower (1)	1	150' x 150'	0.517	0.517	0.000
Temporary Conductor Field Snub/Transfer Area (2)	6	200' x 150'	4.132	4.132	0.000
Construct New 220 kV Lattice Steel Tower (3)	4	200' x 200'	1.837	1.200	0.637
Construct New 220 kV Gen-Tie Structure (5)	0	200' x 200'	0	0	0.000
Conductor & OHGW Stringing Setup Area - Puller (6)	3	300' x 150'	3.099	3.099	0.000
Conductor & OHGW Stringing Setup Area - Tensioner (7)	3	500' x 150'	5.165	5.165	0.000
New Access/Spur Roads (8)	0.6	linear miles x 14' wide	1.018	0.000	1.018
Lockhart Sub - Material & Equipment Staging Area	1	approx. 1.5 acres	1.500	1.500	0.000
Total Estimated (6)			17.268	15.613	1.6552

Notes to Table 3:
1. Includes the removal of existing conductor, teardown of existing structure, and removal of foundation 2' below ground surface.
2. Includes area needed for temporary conductor transfer towers and/or conductor removal, field snubs, and splicing new conductor; area to be restored after construction.
3. Includes foundation installation, structure assembly & erection, and conductor & OHGW attachment; a majority of the area to be restored after construction; a portion of ROW beneath and within 35' of the LST to remain permanently cleared of vegetation and access area of 25' around structure; area to be permanently disturbed for each 220 kV LST equals 0.3183 acres.
4. Includes foundation installation, structure assembly & erection, and conductor & OHGW attachment; a majority of the area to be restored after construction; a portion of ROW beneath and within 25' of the LST to remain permanently cleared of vegetation and access area of 25' around structure; area to be permanently disturbed for each LST equals 0.2173 acres.
5. Includes foundation installation, structure assembly & erection, and conductor & OHGW attachment; a majority of the area to be restored after construction; a portion of area within 25' of the structure to remain permanently cleared of vegetation; approximately 0.057 acre would be permanently disturbed for the structure.
6. Based on 9,000' conductor reel lengths, number of circuits, and route design.
7. Based on length of road in miles x road width of 14'.
8. The disturbed acreage calculations are estimates based upon SCE's preferred area of use for the described Project feature, the width of the existing right-of-way, or the width of the proposed right-of-way and, they do not include any new access/spur road information; they are subject to revision based upon final engineering and review of the Project by SCE's Construction Manager and/or Contractor awarded the Project.
Note: All data provided in this table is based on planning level assumptions and may change following completion of more detailed engineering, identification of field conditions, availability of material, and equipment, and any environmental and/or permitting requirements.

4.2.8 Operation and Maintenance

Following the completion of Lockhart Project construction, operation and maintenance of the new lines would commence. SCE would conduct operation, inspection, and maintenance activities at least once a year, in compliance with CPUC General Order No. 165. The frequency of inspection and maintenance activities would depend upon weather effects and any unique problems that may arise due to such variables as substantial storm damage or vandalism.

4.2.9 Labor and Equipment

Construction of the Lockhart Project would be performed by SCE crews or its contract personnel and supervised by SCE's Lockhart Substation Project administration and inspection. The estimated number of persons and types of equipment required for each phase of transmission line construction for the Lockhart Substation Project is shown in Tables 4, 5, and 6 below.

TABLE 4
CONSTRUCTION EQUIPMENT AND WORKFORCE ESTIMATES BY ACTIVITY
TO CONSTRUCT NEW 220 KV LOOP-IN LINES
LOCKHART SUBSTATION PROJECT

Work Activity				Activity Production			
Primary Equipment Description	Estimated Horse-Power	Probable Fuel Type	Primary Equipment Quantity	Estimated Workforce	Estimated Schedule (Days)	Duration of Use (Hrs/Day)	Estimated Production Per Day
Survey (1)				4	6		0.5 Miles
3/4-Ton Pick-up Truck, 4x4	200	Gas	2		6	8	1 Mile/Day and Construction Support
Temporary Equipment & Material Staging Area (2)				4			
1-Ton Crew Cab, 4x4	300	Diesel	1			2	
30-Ton Crane Truck	300	Diesel	1			2	
Water Truck	350	Diesel	1		Duration of Project		
10,000 lb Rough Terrain Fork Lift	200	Diesel	1			5	
Truck, Semi, Tractor	350	Diesel	1			1	
Roads & Landing Work (4)				5	4		0.5 Miles & 4 Pads
1-Ton Crew Cab, 4x4	300	Diesel	2		4	2	0.5 Miles/Day &
Road Grader	350	Diesel	1		4	4	0.66 Structure Pads/Day
Backhoe/Front Loader	350	Diesel	1		4	6	
10-cu. yd. Dump Truck	350	Diesel	2		4	8	

TABLE 4
CONSTRUCTION EQUIPMENT AND WORKFORCE ESTIMATES BY ACTIVITY
TO CONSTRUCT NEW 220 KV LOOP-IN LINES
LOCKHART SUBSTATION PROJECT

Work Activity				Activity Production			
Primary Equipment Description	Estimated Horse-Power	Probable Fuel Type	Primary Equipment Quantity	Estimated Workforce	Estimated Schedule (Days)	Duration of Use (Hrs/Day)	Estimated Production Per Day
Drum Type Compactor	250	Diesel	1		4	4	
Track Type Dozer	350	Diesel	1		4	6	
Lowboy Truck/Trailer	500	Diesel	2		2	2	
Install LST Foundations (5)				9	6		4 LSTs
1-Ton Crew Cab Flat Bed, 4x4	300	Diesel	2		6	2	
30-Ton Crane Truck	300	Diesel	1		6	5	
Backhoe/Front Loader	200	Diesel	1		6	8	
Auger Truck	500	Diesel	1		6	8	0.50 LST/Day
10-cu. yd. Dump Truck	350	Diesel	2		6	8	
10-cu. yd. Concrete Mixer Truck	425	Diesel	4		4	5	
LST Steel Haul (6)				6	4		4 LSTs
1-Ton Crew Cab Flat Bed, 4x4	300	Diesel	2		4	2	
10,000 lb Rough Terrain Fork Lift	200	Diesel	1		4	6	1 LST/Day
40' Flat Bed Truck/Trailer	350	Diesel	1		4	8	
LST Steel Assembly (7)				14	11		4 LSTs
3/4-Ton Pick-up Truck, 4x4	300	Diesel	3		11	4	
1-Ton Crew Cab Flat Bed, 4x4	300	Diesel	2		11	4	
10,000 lb Rough Terrain Fork Lift	200	Diesel	1		11	6	0.25 LST/Day
30-Ton Crane Truck	300	Diesel	2		11	8	
Compressor Trailer	350	Diesel	2		11	6	
LST Erection (8)				8	16		4 LSTs
3/4-Ton Pick-up Truck, 4x4	300	Diesel	2		16	5	0.13 LST/Day
1-Ton Crew Cab Flat Bed, 4x4	300	Diesel	2		16	5	

TABLE 4
CONSTRUCTION EQUIPMENT AND WORKFORCE ESTIMATES BY ACTIVITY
TO CONSTRUCT NEW 220 KV LOOP-IN LINES
LOCKHART SUBSTATION PROJECT

Work Activity				Activity Production			
Primary Equipment Description	Estimated Horse-Power	Probable Fuel Type	Primary Equipment Quantity	Estimated Workforce	Estimated Schedule (Days)	Duration of Use (Hrs/Day)	Estimated Production Per Day
Compressor Trailer	120	Diesel	1		16	6	
80-Ton Rough Terrain Crane	350	Diesel	1		16	6	
Install Conductor & OHGW (9)				16	6		0.6 Circuit Miles
3/4-Ton Pick-up Truck, 4x4	300	Diesel	2		6	8	
1-Ton Crew Cab Flat Bed, 4x4	300	Diesel	2		6	8	
Wire Truck/Trailer	350	Diesel	2		6	2	
Dump Truck (Trash)	350	Diesel	1		5	2	
20,000 lb. Rough Terrain Fork Lift	350	Diesel	1		6	2	
22-Ton Manitex	350	Diesel	1		6	8	
30-Ton Manitex	350	Diesel	2		6	6	
Splicing Rig	350	Diesel	1		6	2	
Splicing Lab	300	Diesel	1		4	2	0.25 miles/day
Spacing Cart	10	Diesel	1		4	8	
Static Truck/Tensioner	350	Diesel	1		6	2	
3 Drum Straw line Puller	300	Diesel	1		6	4	
60lk Puller	525	Diesel	1		6	3	
Sag Cat w/ 2 winches	350	Diesel	1		6	2	
580 Case Backhoe	120	Diesel	1		6	2	
D8 Cat	300	Diesel	1		6	3	
Lowboy Truck/Trailer	500	Diesel	1		6	2	
Restoration (10)				7	3		0.5 Miles
1-Ton Crew Cab, 4x4	300	Diesel	2		3	2	
Road Grader	350	Diesel	1		3	6	
Backhoe/Front Loader	350	Diesel	1		3	6	
Drum Type Compactor	250	Diesel	1		3	6	0.5 Mile/Day
Track Type Dozer	350	Diesel	1		3	6	
Lowboy Truck/Trailer	300	Diesel	1		3	3	

TABLE 5
CONSTRUCTION EQUIPMENT AND WORKFORCE ESTIMATES BY ACTIVITY
TO CONSTRUCT NEW 220 KV GEN-TIE CONNECTION ON SCE PROPERTY
LOCKHART SUBSTATION PROJECT

Work Activity				Activity Production			
Primary Equipment Description	Estimated Horse-Power	Probable Fuel Type	Primary Equipment Quantity	Estimated Workforce	Estimated Schedule (Days)	Duration of Use (Hrs/Day)	Estimated Production Per Day
Survey (1)				4	2		500 feet
3/4-Ton Pick-up Truck, 4x4	200	Gas	2		2	8	1 Mile/Day
Temporary Equipment & Material Staging Area (2)				4			
1-Ton Crew Cab, 4x4	300	Diesel	1			2	
Water Truck	350	Diesel	1			8	
30-Ton Crane Truck	300	Diesel	1		Duration of Project	2	
10,000 lb Rough Terrain Fork Lift	200	Diesel	1			5	
Truck, Semi, Tractor	350	Diesel	1			1	
Roads & Landing Work (3)				5	2		0.1 Miles & 1 Pad
1-Ton Crew Cab, 4x4	300	Diesel	2		2	2	
Road Grader	350	Diesel	1		1	4	
10-cu. yd. Dump Truck	350	Diesel	2		2		
Backhoe/Front Loader	350	Diesel	1		2	6	0.5 Miles/Day & 2 Structure Pads/Day
Drum Type Compactor	250	Diesel	1		2	4	
Track Type Dozer	350	Diesel	1		2	6	
Lowboy Truck/Trailer	500	Diesel	2		2	2	
Install TSP Foundation (4)				7	2		1 TSP
1-Ton Crew Cab Flat Bed, 4x4	300	Diesel	3		2	2	
30-Ton Crane Truck	300	Diesel	1		2	5	
Backhoe/Front Loader	200	Diesel	1		1	8	2 TSPs/Day
Auger Truck	500	Diesel	1		2	8	
10-cu. yd. Dump Truck	350	Diesel	2		2	8	
10-cu. yd. Concrete Mixer Truck	425	Diesel	3		1	3	
TSP Haul (5)				3	1		1 TSP
3/4-Ton Pick-up Truck, 4x4	300	Diesel	1		1	5	4 TSPs/Day

TABLE 5
CONSTRUCTION EQUIPMENT AND WORKFORCE ESTIMATES BY ACTIVITY
TO CONSTRUCT NEW 220 KV GEN-TIE CONNECTION ON SCE PROPERTY
LOCKHART SUBSTATION PROJECT

Work Activity				Activity Production			
Primary Equipment Description	Estimated Horse-Power	Probable Fuel Type	Primary Equipment Quantity	Estimated Workforce	Estimated Schedule (Days)	Duration of Use (Hrs/Day)	Estimated Production Per Day
Flat Bed Truck/Trailer	350	Diesel	1		1	8	
80-Ton Rough Terrain Crane	350	Diesel	1		1	6	
TSP Assembly (6)				8	1		1 TSP
3/4-Ton Pick-up Truck, 4x4	300	Diesel	2		1	5	
1-Ton Crew Cab Flat Bed, 4x4	300	Diesel	2		1	5	2 TSPs/Day
Compressor Trailer	120	Diesel	1		1	5	
80-Ton Rough Terrain Crane	350	Diesel	1		1	6	
TSP Erection (7)				8	1		1 TSP
3/4-Ton Pick-up Truck, 4x4	300	Diesel	2		1	5	
1-Ton Crew Cab Flat Bed, 4x4	300	Diesel	2		1	5	2 TSPs/Day
Compressor Trailer	120	Diesel	1		1	5	
80-Ton Rough Terrain Crane	350	Diesel	1		1	6	
Install Conductor & OPGW (8)				16	4		0.1 Circuit Miles
3/4-Ton Pick-up Truck, 4x4	300	Diesel	4		4	8	0.2 miles/day
1-Ton Crew Cab Flat Bed, 4x4	300	Diesel	4		4	8	
Wire Truck/Trailer	350	Diesel	4		2	2	
Dump Truck (Trash)	350	Diesel	1		4	2	
20,000 lb. Rough Terrain Fork Lift	350	Diesel	1		4	2	
22-Ton Manitex	350	Diesel	1		4	8	
30-Ton Manitex	350	Diesel	4		4	6	
Splicing Rig	350	Diesel	2		4	2	
Splicing Lab	300	Diesel	2		2	2	
Spacing Cart	10	Diesel	2		2	8	
Static Truck/Tensioner	350	Diesel	1		2	2	
3 Drum Straw line Puller	300	Diesel	2		2	4	

TABLE 5
CONSTRUCTION EQUIPMENT AND WORKFORCE ESTIMATES BY ACTIVITY
TO CONSTRUCT NEW 220 KV GEN-TIE CONNECTION ON SCE PROPERTY
LOCKHART SUBSTATION PROJECT

Work Activity				Activity Production			
Primary Equipment Description	Estimated Horse-Power	Probable Fuel Type	Primary Equipment Quantity	Estimated Workforce	Estimated Schedule (Days)	Duration of Use (Hrs/Day)	Estimated Production Per Day
60lk Puller	525	Diesel	1		2	3	
Sag Cat w/ 2 winches	350	Diesel	2		2	2	
580 Case Backhoe	120	Diesel	1		4	2	
D8 Cat	300	Diesel	2		2	3	
Lowboy Truck/Trailer	500	Diesel	1		4	2	
Restoration (9)				7	3		0.5 Miles
1-Ton Crew Cab, 4x4	300	Diesel	2		3	2	
Road Grader	350	Diesel	1		1	6	
Backhoe/Front Loader	350	Diesel	1		1	6	
Drum Type Compactor	250	Diesel	1		1	6	0.5 Mile/Day
Track Type Dozer	350	Diesel	1		1	6	
Lowboy Truck/Trailer	300	Diesel	1		3	3	

TABLE 6
CONSTRUCTION EQUIPMENT AND WORKFORCE ESTIMATES BY ACTIVITY
TRANSMISSION LINE STRUCTURE REMOVAL

Work Activity				Activity Production			
Primary Equipment Description	Estimated Horse-Power	Probable Fuel Type	Primary Equipment Quantity	Estimated Workforce	Estimated Schedule (Days)	Duration of Use (Hrs/Day)	Estimated Production Per Day
Temporary Equipment & Material Staging Area(2)				4			
1-Ton Crew Cab, 4x4	300	Diesel	1			2	
30-Ton Crane Truck	300	Diesel	1			2	
Water Truck	350	Diesel	1		Duration of Project	8	
10,000 lb Rough Terrain Fork Lift	200	Diesel	1			5	
Truck, Semi, Tractor	350	Diesel	1			1	
Roads & Landing Work (3)				5	2		.5 Miles & 3 Pads
1-Ton Crew Cab, 4x4	300	Diesel	2		2	2	
Road Grader	350	Diesel	1		2	4	
Backhoe/Front Loader	350	Diesel	1		2	6	
Drum Type Compactor	250	Diesel	1		2	4	0.5 Miles/Day & 2 Structure Pads/Day
Track Type Dozer	350	Diesel	1		2	6	
Excavator	300	Diesel	1		2	6	
Lowboy Truck/Trailer	500	Diesel	1		2	2	
LST Removal (4)				8	2		1 LSTs
3/4-Ton Pick-up Truck, 4x4	300	Diesel	2		2	6	
1-Ton Crew Cab Flat Bed, 4x4	300	Diesel	2		2	6	0.75 LST/Day
Compressor Trailer	120	Diesel	1		2	6	
80-Ton Rough Terrain Crane	350	Diesel	1		2	6	
Remove Foundations (5)				9	1		3 LSTs
1-Ton Crew Cab Flat Bed, 4x4	300	Diesel	2		1	2	0.50 LST/Day
Backhoe/Front Loader	200	Diesel	1		6	8	
Auger Truck	500	Diesel	1		8	8	
10-cu. yd. Dump Truck	350	Diesel	2		8	8	

TABLE 6
CONSTRUCTION EQUIPMENT AND WORKFORCE ESTIMATES BY ACTIVITY
TRANSMISSION LINE STRUCTURE REMOVAL

Work Activity				Activity Production			
Primary Equipment Description	Estimated Horse-Power	Probable Fuel Type	Primary Equipment Quantity	Estimated Workforce	Estimated Schedule (Days)	Duration of Use (Hrs/Day)	Estimated Production Per Day
Compressor Trailer	120	Diesel	1	2	6		
LST Steel Haul (6)				4	1		3 LSTs
1-Ton Crew Cab Flat Bed, 4x4	300	Diesel	1		1	2	
10,000 lb Rough Terrain Fork Lift	200	Diesel	1		1	6	1 LST/Day
40' Flat Bed Truck/Trailer	350	Diesel	1		1	8	
Transfer Conductor (9)				16	3		.5 Circuit Miles
3/4-Ton Pick-up Truck, 4x4	300	Diesel	2		3	8	
1-Ton Crew Cab Flat Bed, 4x4	300	Diesel	2		3	8	
Wire Truck/Trailer	350	Diesel	2		3	2	
Dump Truck (Trash)	350	Diesel	1		5	2	
20,000 lb. Rough Terrain Fork Lift	350	Diesel	1		3	2	
22-Ton Manitex	350	Diesel	1		3	8	
30-Ton Manitex	350	Diesel	2		3	6	
Splicing Rig	350	Diesel	1		3	2	
Splicing Lab	300	Diesel	1		3	2	1 tower/day
Spacing Cart	10	Diesel	1		3	8	
Static Truck/Tensioner	350	Diesel	1		3	2	
3 Drum Straw line Puller	300	Diesel	1		3	4	
60lk Puller	525	Diesel	1		3	3	
Sag Cat w/ 2 winches	350	Diesel	1		3	2	
580 Case Backhoe	120	Diesel	1		3	2	
D8 Cat	300	Diesel	1		3	3	
Lowboy Truck/Trailer	500	Diesel	1		3	2	
Restoration (11)				7	3		.5 Miles
1-Ton Crew Cab, 4x4	300	Diesel	2		3	2	0.5 Mile/Day
Road Grader	350	Diesel	1		1	6	
Backhoe/Front Loader	350	Diesel	1		1	6	

TABLE 6
CONSTRUCTION EQUIPMENT AND WORKFORCE ESTIMATES BY ACTIVITY
TRANSMISSION LINE STRUCTURE REMOVAL

Work Activity				Activity Production			
Primary Equipment Description	Estimated Horse-Power	Probable Fuel Type	Primary Equipment Quantity	Estimated Workforce	Estimated Schedule (Days)	Duration of Use (Hrs/Day)	Estimated Production Per Day
Drum Type Compactor	250	Diesel	1		1	6	
Track Type Dozer	350	Diesel	1		3	6	
Lowboy Truck/Trailer	300	Diesel	1		2	3	

5.0 Distribution System for Station Light and Power

The following elements describe the distribution requirements for one of the two required sources of Lockhart Substation station light and power.

5.1 Distribution System Design and Equipment

The Hutt 12 kV distribution circuit out of Hutt Poletop Substation is assumed to remain in place and; therefore, it would be the source to provide station light and power to the Lockhart Substation. The Lockhart Project calls for rearranging the existing Hutt 12 kV overhead distribution circuit where it terminates at the central site for the proposed Lockhart Substation at approximately the location of an existing distribution pole located near Roy Street and a private dirt road. This distribution pole would need to be removed as well as the pole to the north in order to make room for the new Lockhart Substation.

A new distribution riser pole would be installed from an existing pole on the west side of the proposed Lockhart Substation. (see Figure 5). An Omni-rupter switch would be installed on the distribution 12 kV riser pole along with the distribution riser. Approximately 200-400 feet of two five inch conduits would be installed to a new 12 kV station light and power rack location within Lockhart Substation adjacent to the MEER. Portions of these facilities could also be utilized for installation of the required telecommunication fiber optic cables into Lockhart Substation (described below in Section 6.0, Telecommunication System).

The 12 kV Hutt distribution circuit would extend through one of the new five inch conduits with 1/0 aluminum jacketed concentric neutral (JCN), cross-linked polyethylene (CLP) cable to connect the existing overhead tap line to the back-up station light and power transformers mounted on the 12 kV rack within the substation.

SCE's construction requirements for temporary power would be a 200 amp, 120/240 volt, 3-phase, 4-wire panel. An open delta transformer bank would be installed on an existing 12 kV distribution pole to the west of the proposed Lockhart Substation.

TABLE 7
LOCKHART SUBSTATION
CONSTRUCTION EQUIPMENT AND WORKFORCE ESTIMATES BY ACTIVITY
12KV HUTT STATION LIGHT & POWER

Work Activity				Estimated Workforce	Estimated Schedule (Days)	Activity Production
Primary Equipment Description	Estimated Horse-Power	Probable Fuel Type	Primary Equipment Quantity		Duration of Use (Hrs/Day)	Estimated Production Per Day
Trenching, Structure Excavation(1)				4	1	
1-Ton Crew Cab	300	Diesel	1		1	2
Backhoe Front Loader	300	Diesel	1		1	8
Dump Truck	300	Diesel	1		1	4
Overhead Line Work(2)				4	2	
1-Ton Crew Cab, 4x4	300	Diesel	1		2	2
55' Double Bucket Truck	350	Diesel	1		2	8
Underground Cable Pulling and Makeup (3)				4	1	
55' Double Bucket Truck	350	Diesel	1		1	8
1-Ton Crew Cab, 4x4	300	Diesel	1		1	2
Hydraulic Rewind Puller	300	Diesel	1		1	6

Crew size assumptions:

1. Trenching and Conduit Installation = one 4-man crew
2. Overhead Line Work = one 4-man crew
3. Underground Cable Pulling and Makeup = one 4-man crew

5.2 Distribution System Construction

A lay down area within the SCE-owned Lockhart Substation property or within AMSP property as needed would be required to store any materials needed during construction. One line truck and a companion vehicle with a four man crew would be utilized to perform the work each day. SCE anticipates

working typical construction schedules, however the actual construction hours may vary. Land disturbance for distribution construction activities would be within the AMSP property and included in AMSP's disturbance area.

6.0 Telecommunication System

The following elements describe the requirements for Lockhart Substation telecommunication facilities.

6.1 Telecommunication System Design and Equipment

A telecommunication system would be required in order to provide transmission line protection, SPS, monitoring, and remote operation capabilities of the electrical equipment at Lockhart Substation.

To provide line protection, the telecommunications system would extend diverse communication paths utilizing fiber-optic cables to connect Lockhart Substation to the SCE telecommunication network via SCE's Kramer Substation, SCE's Tortilla Substation, and also to the AMSP Alpha and Beta power facilities. In addition, a telecommunication path between SCE's Tortilla Substation and SCE's Cool Water Substation is currently undergoing permitting as part of a separate project and would also be used for the required line protection (see Figure 3-1, Figure 3-2, Figure 3-3 and Figure 3-4). In addition, a new telecommunication facility would be required at SCE's Tortilla Substation (see Figure 3-6). This telecommunications facility is needed to support the additional telecommunication equipment to be installed at Tortilla Substation.

To provide for the required SPS, SCE telecommunications would install a fiber optic cable between SCE's existing Kramer Substation and SCE's existing Victor Substation. SCE has evaluated the possibility of installing a telecommunication ADSS fiber optic cable on the existing Kramer-Victor 115 kV pole line. The completion of the initial evaluation identified that the SCE's Kramer-Victor 115 kV pole line is adequate to support the ADSS fiber optic cable. However, approximately 30 new wood or lightweight steel interset poles would have to be installed in specific areas within existing ROW to support ground clearance requirements. The number and exact location, as well as type of interset poles would be determined during final engineering (see Figure 3-5).

It is anticipated that the total distance of the combined telecommunication routes would be approximately 85 miles.

As described in detail below, certain portions of the fiber optic cable would be constructed on existing overhead distribution and transmission wood and light duty steel poles, while other portions of the cable would be constructed on new overhead structures and newly constructed underground conduit system(s). For a breakdown of new versus existing components refer to the Table 8 below.

Telecommunications Equipment:

- New overhead/underground 48-strand fiber optic cables to connect the Lockhart Substation site/property to SCE's Kramer and Tortilla Substations, and AMSP's Alpha and Beta Substations.
- New overhead/underground 96-strand fiber optic cables to connect SCE's Kramer Substation to SCE's Victor Substation.
- New fiber optic multiplex equipment and channel equipment in the Lockhart Substation MEER.
- New telecommunications room within SCE's existing Tortilla Substation.
- New fiber optic multiplex equipment and channel equipment at SCE's Kramer, Tortilla, Coolwater, Roadway, Lugo Substations and any other location necessary to support the communication requirements for the Lockhart Project.
- Replacement of existing poles if required, to be determined during final engineering.

Cable Route, SCE's Kramer Substation to Lockhart Substation:

From SCE's Kramer Substation, proceed north from the MEER building approximately 800' feet installing underground cable in an existing underground trench. Continue west approximately 525 feet installing underground cable in existing underground conduit. Continue north approximately 725 feet installing underground cable in existing underground conduit to pole 1793491E rise up.

Continue north approximately 2,000 feet installing ADSS overhead cable on existing overhead structures, continue east on ROW approximately 63,500 feet installing overhead cable on existing overhead structures. Continue north on Harper Lake Road approximately 5,700 feet installing overhead cable on existing overhead structures, continue east on Lockhart Road approximately 11,000 feet installing overhead cable on existing overhead structures to pole 4488408E where path would continue south approximately 5,700 feet installing overhead cable on new overhead structures to be installed for station light and power for Lockhart Substation. Install riser and continue for approximately 1,000 feet installing underground cable in new underground conduit structures to Lockhart Substation MEER.

Cable Route, SCE's Lockhart Substation to SCE's Tortilla Substation:

From Lockhart Substation, proceed south from the MEER for approximately 1,000 feet installing underground cable in new underground conduit to a new pole with riser. From this point continue west on existing overhead H-frame subtransmission structures within SCE's existing Coolwater-Kramer 115 kV ROW for approximately 11,000 feet (see Figure 7).. A riser would be installed on the last pole near the intersection with Harper Lake Road. Continue south on Harper Lake Road for approximately 400 feet installing new underground cable and conduit to pole 4349976E where a new riser would be installed. Continue south on Harper Lake Road to HWY 58 for approximately 26,000 feet installing ADSS overhead cable on existing overhead structures.

From HWY 58 continue east for approximately 52,600 feet installing overhead cable on existing overhead structures. Continue south on Summerset Road for approximately 5,300 feet installing overhead cable on existing overhead structures. Continue east on Community Boulevard for approximately 10,600 feet installing overhead cable on existing overhead structures to Lenwood Road. Continue south for approximately 13,500 feet installing overhead cable on existing overhead structures. Continue south on Sun Valley Drive for approximately 2,000 feet installing overhead cable on existing overhead structures. Continue northeast on the existing SCE Poco 33 kV pole line for approximately 25,000 to Avenue I installing overhead cable on existing overhead structures. Continue south approximately 1,850 feet installing overhead cable on existing overhead structures. Continue south crossing over Interstate 15 for approximately 425 feet to pole 1847916E on I Street and continue south approximately 4,500 feet to Siderite Road installing overhead cable on the existing overhead structures.

From Siderite Road continue east for approximately 1,400 feet installing overhead cable on existing overhead structures. Continue northwest on SCE's existing Kramer-Tortilla 115 kV ROW for approximately 6,100 feet installing overhead cable on existing overhead structures to pole 2263364E drop down existing riser, continue east for approximately 500 feet installing underground cable in existing underground conduit to SCE's Tortilla Substation MEER.

Cable Route, SCE's Lockhart Substation to AMSP's Alpha and Beta Power Facilities:

Routing of second diverse path routed fiber-optic cable from Lockhart Substation to AMSP's Alpha and Beta power facilities would be dependent on easements and paths provided by Abengoa.

Cable Route, SCE's Victor Substation to Kramer Substation:

The Victor Substation to Kramer Substation fiber optic cable would consist of a proposed fiber optic communications path between SCE's existing Victor Substation and Kramer Substation (see Table 10 and 11). The Victor Substation to Kramer Substation fiber optic cable would proceed approximately 225' northwest from the Victor MEER in a new underground conduit to a new riser to be installed on 115 kV pole 4409452E. From this new line riser, approximately 14,750 feet of new overhead fiber optic cable would be installed on the existing Kramer-Victor 115 kV overhead structures, which generally parallel Hwy 395 towards the Kramer Substation. A new riser drop down, approximately 500' of new underground conduit, a new line riser would be required to cross under 287 kV transmission lines owned by the Los Angeles Department of Water and Power (LADWP). From this point, the new fiber optic cable would be installed on the existing Kramer-Victor 115 kV overhead structures for approximately 4,300 feet. A new riser drop down, approximately 500' of new underground conduit, a new line riser would be required to cross under SCE's Kramer-Lugo 220 kV transmission lines. From this point, the new fiber optic cable would again be installed on the existing Kramer-Victor 115 kV overhead structures for approximately 6,400 feet where it would then be routed in and out of SCE's Roadway 115 kV Substation. To route into SCE's Roadway 115 kV Substation MEER, a new riser drop down and approximately 350 feet of new underground conduit would be required. To route out of SCE's Roadway 115 kV Substation MEER, approximately 575 feet of new cable would be installed on existing underground conduit, approximately 600 feet of new cable would

be installed on new underground conduit, and a new line riser would be required. From this point, approximately 570 feet of new overhead cable would be installed back to the Kramer-Victor 115 kV line where it would then head north for approximately 155,000 feet towards the Kramer Substation. A new riser drop down would be required on the last Kramer-Victor 115 kV pole just outside the Kramer Substation and approximately 1,000 feet of new underground conduit towards the Kramer Substation MEER would complete the fiber optic communications path between SCE's existing Victor Substation and Kramer Substation. Approximately 30 new wood or lightweight steel interset poles would have to be installed in specific areas within existing ROW to support ground clearance requirements as stated earlier in this document. The number and exact location, as well as type of interset poles would be determined during final engineering.

Cable Route, SCE's Tortilla Substation to Coolwater Substation:

The Tortilla-Coolwater fiber optic cable is needed to complete the path for the required line protection. However, it is currently undergoing permitting as part of a separate project and is included here as a reference. However, if the other project is cancelled or delayed, this fiber optic cable is still required for the Lockhart Project.

Proposed cable route: From the Coolwater GS Communication Room proceed east approximately 196 feet and south approximately 789 feet installing underground cable in existing underground conduit to the existing riser pole 2311957E, go up existing riser and continue west approximately 910 feet installing overhead cable on existing overhead structures to pole 2311962E, continue south approximately 255 feet installing overhead cable on existing overhead structures to riser pole 2311963E, and continue south approximately 1,026 feet installing underground cable in underground conduit to riser pole 1847660E, go up riser and continue west approximately 3,071 feet installing overhead cable on existing overhead structures to pole 2311982E, continue south approximately 500 feet installing overhead cable on existing overhead structures to pole 83120S, continue west approximately 16,675 feet installing overhead cable on existing overhead structures to pole 430515S, continue south approximately 420 feet installing overhead cable on existing overhead structures to pole 430514S, continue west approximately 17,903 feet installing overhead cable on existing overhead structures to pole 1771073E, continue south approximately 200 feet installing overhead cable on existing overhead structures to pole 1771075E, continue west approximately 14,931 feet installing overhead cable on existing overhead structures to pole 1730385E, continue north approximately 300 feet installing overhead cable on existing overhead structures to pole 1730387E, continue west approximately 268 feet installing overhead cable on existing overhead structures to pole 4699300E, continue south approximately 75 feet installing overhead cable on existing overhead structures to "no tag" pole, continue west approximately 322 feet installing overhead cable on existing overhead structures to new riser pole 4645190E, install riser on pole drop down riser and continue north and east approximately 395 feet installing underground cable in new underground conduit to existing substation cable trench, continue north approximately 45 installing underground cable in existing substation cable trench into the MEER in Tortilla Substation.

Table 8 – Summary of Proposed Telecommunications Fiber Optic Cables Estimates

	Kramer to Lockhart	Lockhart to Tortilla	Victor to Kramer	Tortilla to Coolwater*
Fiber-Optic Cable Length (Proposed)	92,000 ft (18 miles)	164,000 ft (31 miles)	185,000 ft (35 miles)	57,900 ft (11 miles)
Total Length Underground (U.G.)	3,100 ft	1,900 ft.	2,300 ft	2460 ft
-Existing U.G. Conduits	2,000 ft.	500 ft.	700 ft	2460 ft
-New U.G. Conduits Needed	1,100 ft.	1,400 ft.	1600 ft	0
Total Length Overhead (O.H.)	88,000 ft.	162,000 ft.	182,700 ft	55,440 ft
-Existing O.H.	82,000 ft.	150,000 ft	182,700 ft	55,440 ft
-New O.H.	6,000 ft.	12,000 ft	0 ft	0
-Existing Poles	250	600	226	220
-New Poles Required	30	55	30	0
Estimated Ground Disturbance	7,500 sq ft	13,700 sq ft.	226,500 sq ft	3,400 sq ft.
Time and Resources to Construct (4 men per crew)	38 Crew Days	64 Crew Days	154 Crew Days	19 Crew Days
Total Man Days Required	152 Man Days	256 Man Days	755 Man Days	97 Man Days

Note: These figures are desktop estimates and may change based upon final engineering.

* Tortilla to Coolwater fiber-optic cable is in the permitting phase in a separate project and is included in this table only should it be required to be constructed as part of the Lockhart Project.

6.2 Telecommunication System Construction

Construction Activities

SCE would utilize SCE's existing Victor, Roadway, Kramer, Tortilla, and Coolwater Substations as well as SCE's Barstow Service Center and the proposed Lockhart Substation as marshalling yards to support the installation of the telecommunications facilities required for this project. SCE or contractor crews would use standard construction methods to construct the required fiber optic cables. The crews would comply with all rules, regulations and standards with interdepartments and other agencies while in their performance of the construction phase.

Portions of the fiber optic cable would be constructed on existing overhead distribution and transmission wood and light duty steel poles. In addition, portions of the cable would be constructed on new overhead structures and newly constructed underground conduit system(s), subject to determination through final engineering. This project description is based on planning level assumptions. Exact details would be determined following completion of preliminary and final engineering, identification of field conditions, availability of labor, material, and equipment, and compliance with applicable environmental and permitting requirements.

Generally no hazardous materials would be used in installing underground conduit, new wood communication poles, and the stringing of fiber-optic cables. There is generally no need for local services or utilities (such as water). Waste generated (empty cable reels, cut-off pieces of fiber cable) would be disposed of at existing SCE facilities.

Table 9 - Telecommunications Labor Force and Construction Equipment Estimates

Construction Element	Number of Personnel	Equipment Requirements
Cable Construction	4	2 – Bucket Trucks (Diesel) 1 – Pick-up (Diesel) 2 – Cable Dollies 1 – Single Drum Puller (Diesel) 1 – 2 Axle Trailer
Receive and Load Out Materials	4	1 – 5-Ton Forklift (Diesel) 1 – Pick-up (Diesel)
Cleanup	4	2 – Bucket Trucks (Diesel) 1 – Pick-up (Diesel)

**TABLE 10
CONSTRUCTION EQUIPMENT AND WORKFORCE ESTIMATES BY ACTIVITY
CONSTRUCT KRAMER-VICTOR FIBER OPTIC CABLE**

Work Activity				Activity Production			
Primary Equipment Description	Estimated Horse-Power	Probable Fuel Type	Primary Equipment Quantity	Estimated Workforce	Estimated Schedule (Days)	Duration of Use (Hrs/Day)	Estimated Production Per Day
Survey (1)				4	4		34 Miles/Intersect Poles
½-Ton Pick-up Truck, 4x4	200	Gas	2		4	8	12 Mile/Day
Marshalling Yard (2)				4			
1-Ton Crew Cab, 4x4	300	Diesel	1			2	
30-Ton Crane Truck	300	Diesel	1			2	
10,000 lb Rough Terrain Fork Lift	200	Diesel	1		Duration of Project	5	
4000 gallon Water Truck	350	Diesel	1			8	
Truck, Semi, Tractor	350	Diesel	1			1	
Roads (3)				5	17		34 Miles
1-Ton Crew Cab, 4x4	300	Diesel	2		17	2	2 Miles/Day
Road Grader	350	Diesel	1		17	4	
Backhoe/Front Loader	350	Diesel	1		17	6	

TABLE 10
CONSTRUCTION EQUIPMENT AND WORKFORCE ESTIMATES BY ACTIVITY
CONSTRUCT KRAMER-VICTOR FIBER OPTIC CABLE

Work Activity				Activity Production			
Primary Equipment Description	Estimated Horse-Power	Probable Fuel Type	Primary Equipment Quantity	Estimated Workforce	Estimated Schedule (Days)	Duration of Use (Hrs/Day)	Estimated Production Per Day
Drum Type Compactor	250	Diesel	1		17	4	
Track Type Dozer	350	Diesel	1		17	6	
Excavator	300	Diesel	1		9	6	
Lowboy Truck/Trailer	500	Diesel	1		9	2	
Install 5 foot Crossarm (4)				8	23		34 Miles Approx 900 Poles
1-Ton Crew Cab Flat Bed, 4x4	300	Diesel	3		23	2	40 Crossarms /Day
Bucket Truck	300	Diesel	2		23	5	
Install LWS Poles (5)				10	8		Intersect 30 LWS Poles
1-Ton Crew Cab Flat Bed, 4x4	300	Diesel	3		8	2	4 Poles /Day
Auger Truck	500	Diesel	1		8	8	
Backhoe/Front Loader	200	Diesel	1		18	8	
Steel Pole Haul (6)				8	3		30 LWS Poles
¾-Ton Pick-up Truck, 4x4	300	Diesel	2		3	5	12 steel Poles/Day
30-Ton Crane Truck	300	Diesel	1			4	
40' Flat Bed Truck/Trailer	350	Diesel	2		3	8	
Install Fiber Optic Cable (7)				8	11		34 Circuit Miles
¾-Ton Pick-up Truck, 4x4	300	Diesel	2		11	8	3 miles/day 1800 foot reel
1-Ton Crew Cab Flat Bed, 4x4	300	Diesel	4		11	8	
Bucket Truck	350	Diesel	2		11	8	
Splicing Lab	300	Diesel	1		3	2	
3 Drum Straw line Puller/Tensioner	300	Diesel	1		6	6	
Restoration (8)				7	34		34 Miles
1-Ton Crew Cab, 4x4	300	Diesel	2		34	2	1 Mile/Day
Road Grader	350	Diesel	1		34	6	
Water Truck	350	Diesel	1		34	8	

TABLE 10
CONSTRUCTION EQUIPMENT AND WORKFORCE ESTIMATES BY ACTIVITY
CONSTRUCT KRAMER-VICTOR FIBER OPTIC CABLE

Work Activity				Activity Production			
Primary Equipment Description	Estimated Horse-Power	Probable Fuel Type	Primary Equipment Quantity	Estimated Workforce	Estimated Schedule (Days)	Duration of Use (Hrs/Day)	Estimated Production Per Day
Backhoe/Front Loader	350	Diesel	1		34	6	
Drum Type Compactor	250	Diesel	1		34	6	
Track Type Dozer	350	Diesel	1		34	6	
Lowboy Truck/Trailer	300	Diesel	1		34	3	

Crew Size Assumptions:

#1 Survey = one 4-man crew
#2 Marshalling Yards = one 4-man crew
#3 Road Work = one 5-man crew
#4 Install 5 foot Crossarm = two 4-man crew
#5 Install LWS Poles = one 10-man crew
#6 Steel Pole Haul = one 8-man crew
#7 Install Fiber Optic Cable = two 4-man crews
#8 Restoration = one 7-man crew

Table 11 - Ground Disturbance Kramer-Victor Fiber-Optic Cable

Project Feature	Site Quantity	Disturbed Acreage Calculation (L x W)	Acres Disturbed During Construction	Acres to be Restored	Acres Permanently Disturbed
Construct New Light Weight Steel Pole (1)	30	75' x 75'	3.9	2.4	1.5
Fiber Optic Setup Area - Tensioner (2)	18	40' x 60'	1.0	1.0	0.0
Fiber Optic Splicing Setup Areas (2)	18	20' x 30'	0.2	0.2	0.0
New Access Roads (3)	0.1	linear miles x 14' wide	0.1	0.0	0.1
Total Estimated (5)			5.2	3.6	1.6

Notes:

2. Includes structure assembly & erection, conductor & ADSS installation. Area to be restored after construction. Portion of R/W within 25' of the Tubular Steel Pole and within 10' of Light Weight Steel Pole, and H-Frame to remain cleared of vegetation. Permanently disturbed areas for TSP=0.06 acre, LWS=0.05 acre, and H-Frame=0.06acre.

3. Based on 9,000' conductor reel lengths, number of circuits, and route design.

4. Based on approximate length of road in miles x road width of 14'.
5. The disturbed acreage calculations are estimates based upon SCE's preferred area of use for the described project feature, the width of the existing right-of-way, or the width of the proposed right-of-way and, they do not include any new access/spur road information; they are subject to revision based upon final engineering and review of the project by SCE's Construction Manager and/or Contractor awarded project.

Footing / Base Volume and Area Calculations:
Average TSP depth 30ft deep, 7ft diameter, qty 1 per TSP: earth removed for footing = 42.8 cu. yds.; surface area = 38.5 sq.ft.
Average LWS depth 12ft deep, 2.5ft diameter, qty 1 per LWS: earth removed for pole base = 2.2 cu. yds.; surface area = 4.9 sq. ft.
Average Wood H-Frame depth 12ft deep, 2.5ft diameter, qty 2 per H-Frame: earth removed for pole base = 4.4 cu. yds.; surface area = 9.8 sq. ft.




FIGURE 1
PROPOSED NEW SCE LOCKHART
SUBSTATION SITE

Features depicted herein are planning level accuracy, and intended for informational purposes only. Distances and locations may be distorted at this scale. Always consult with the proper legal documents or agencies regarding such features.
© Real Properties - Survey and Mapping.

Thomas Bros. Maps is a registered trademark of Rand McNally & Company. Reproduced with permission granted by Rand McNally & Company.
© Rand McNally & Company. All rights reserved.

Legend




Proposed New SCE Lockhart Substation Site
Mohave Solar (Abengoa Solar Inc.) Plant Site

Existing 220kV Transmission Lines (SCE, 2009)
Existing 115kV Subtransmission Line (SCE, 2009)
Minor Roads (TBM, 2008)




0 0.25 0.5 1 Miles

SUBSTATION DETAILS



SITE PLAN



**FIGURE 2
PROPOSED NEW SCE LOCKHART
SUBSTATION AND ASSOCIATED
ELECTRICAL LINES**

Features depicted herein are planning level accuracy, and intended for informational purposes only. Distances and locations may be distorted at this scale. Always consult with the proper legal documents or agencies regarding such features.
© Real Properties - Survey and Mapping.





Note: CONCEPTUAL ENGINEERING, DO NOT SPOT



**FIGURE 3-1
OVERVIEW OF PROPOSED NEW
TELECOMMUNICATION FIBER OPTIC
CABLES FOR THE LOCKHART PROJECT**

Features depicted herein are planning level accuracy, and intended for informational purposes only. Distances and locations may be distorted at this scale. Always consult with the proper legal documents or agencies regarding such features.
© Real Properties - Survey and Mapping.
Thomas Bros. Maps is a registered trademark of Rand McNally & Company. Reproduced with permission granted by Rand McNally & Company.
© Rand McNally & Company. All rights reserved.






FIGURE 3-2
PROPOSED NEW TELECOMMUNICATION
FIBER OPTIC CABLE CONNECTING
KRAMER SUBSTATION TO NEW
LOCKHART SUBSTATION

Features depicted herein are planning level accuracy, and intended for informational purposes only. Distances and locations may be distorted at this scale. Always consult with the proper legal documents or agencies regarding such features.
© Real Properties - Survey and Mapping.
Thomas Bros. Maps is a registered trademark of Rand McNally & Company. Reproduced with permission granted by Rand McNally & Company.
© Rand McNally & Company. All rights reserved.

Legend


Proposed Telecommunication Path

- Kramer-Lockhart Path
- Kramer-Victor Path
- Lockhart-Tortilla Path

- Proposed Lockhart Substation
- Existing Substation (SCE, 2010)
- Mohave Solar (Abengoa Solar Inc.) Plant Site

- Freeways (TBM, 2008)
- Highways (TBM, 2008)
- Minor Roads (TBM, 2008)
- Railroads (TBM, 2008)

- City Boundary (TBM, 2008)
- Hydrology Areas (TBM, 2008)**
 - Perennial
 - Dry






FIGURE 3-3
PROPOSED NEW TELECOMMUNICATION
FIBER OPTIC CABLE CONNECTING NEW
LOCKHART SUBSTATION TO
TORTILLA SUBSTATION

Features depicted herein are planning level accuracy, and intended for informational purposes only. Distances and locations may be distorted at this scale. Always consult with the proper legal documents or agencies regarding such features.
© Real Properties - Survey and Mapping.
Thomas Bros. Maps is a registered trademark of Rand McNally & Company. Reproduced with permission granted by Rand McNally & Company.
© Rand McNally & Company. All rights reserved.

Legend


Proposed Telecommunication Path

- Lockhart-Tortilla Path
- Kramer-Lockhart Path
- Coolwater-Tortilla Path (Under Permitting)

- Proposed Lockhart Substation
- Existing Substation (SCE, 2010)

- Freeways (TBM, 2008)
- Highways (TBM, 2008)
- Major Roads (TBM, 2008)
- Minor Roads (TBM, 2008)
- Railroads (TBM, 2008)

- City Boundary (TBM, 2008)
- Hydrology Areas (TBM, 2008)**
- Perennial
- Dry








FIGURE 3-4
PROPOSED NEW TELECOMMUNICATION FIBER OPTIC CABLE CONNECTING TORTILLA SUBSTATION TO COOLWATER SUBSTATION (NOT BUILT - IN PERMITTING PHASE)

Features depicted herein are planning level accuracy, and intended for informational purposes only. Distances and locations may be distorted at this scale. Always consult with the proper legal documents or agencies regarding such features.
© Real Properties - Survey and Mapping.

Thomas Bros. Maps is a registered trademark of Rand McNally & Company. Reproduced with permission granted by Rand McNally & Company.
© Rand McNally & Company. All rights reserved.

Legend

Proposed Telecommunication Path

- Coolwater-Tortilla Path (Under Permitting)
- Lockhart-Tortilla Path

Existing Substation (SCE, 2010)

- Existing Substation (SCE, 2010)

Freeways (TBM, 2008)

- Freeways (TBM, 2008)

Highways (TBM, 2008)

- Highways (TBM, 2008)

Major Roads (TBM, 2008)

- Major Roads (TBM, 2008)

Minor Roads (TBM, 2008)

- Minor Roads (TBM, 2008)

Railroads (TBM, 2008)

- Railroads (TBM, 2008)

City Boundary (TBM, 2008)

- City Boundary (TBM, 2008)

Hydrology Areas (TBM, 2008)

- Perennial
- Dry

0 0.25 0.5 1 Miles

P:\GISData\Projects\MasterData\Major Transmission Projects\LockhartTortilla\TortillaToCoolwater\Rev2\Figure 3-4 Proposed Telecomm TortillaToCoolwater Rev2.mxd DATE: 4/02/2010

Proposed SCE Fiber-Optic Cables
From Lockhart to Abengoa
Alpha & Beta Facilities

HARPER
DRY LAKE

FO Cable to Alpha

FO Cable to Beta

Blue Lines = Proposed Fiber-Optic (FO) Cables for Diverse Communication Path

M G S Conservation Area

Superior-Cronese DWMA

Map Source: Abengo Mojave Solar Project

FIGURE 3-5

**PROPOSED NEW TELECOMMUNICATION FIBER
OPTIC CABLES CONNECTING NEW SCE
LOCKHART SUBSTATION TO ABENGOA
ALPHA AND BETA FACILITIES**



Features depicted herein are planning level accuracy, and intended for informational purposes only. Distances and locations may be distorted at this scale. Always consult with the proper legal documents or agencies regarding such features.
© Real Properties - Survey and Mapping.

LEGEND

— PROPOSED NEW LOCKHART SUBSTATION TO ABENGOA FACILITIES FIBER OPTIC CABLE

NOTE: MAP FOR PROPOSED NEW TELECOMMUNICATION FIBER OPTIC CABLES ONLY,
REFER TO PROPOSED NEW SCE LOCKHART SUBSTATION LOCATION ON FIGURE 1.





FIGURE 3-6
PROPOSED NEW TELECOMMUNICATION
FIBER OPTIC CABLE CONNECTING
KRAMER SUBSTATION TO
VICTOR SUBSTATION

Features depicted herein are planning level accuracy, and intended for informational purposes only. Distances and locations may be distorted at this scale. Always consult with the proper legal documents or agencies regarding such features.
© Real Properties - Survey and Mapping.
Thomas Bros. Maps is a registered trademark of Rand McNally & Company. Reproduced with permission granted by Rand McNally & Company.
© Rand McNally & Company. All rights reserved.

Legend


Proposed Telecommunication Path


- Kramer-Victor Path
- Kramer-Lockhart Path
- Lockhart-Tortilla Path
- Coolwater-Tortilla Path (Under Permitting)

- Proposed Lockhart Substation
- Existing Substation (SCE, 2010)
- Mohave Solar (Abengoa Solar Inc.) Plant Site

- Freeways (TBM, 2008)
- Highways (TBM, 2008)
- Railroads (TBM, 2008)

- County Boundary (TBM, 2008)
- City Boundary (TBM, 2008)
- Hydrology Areas (TBM, 2008)**
- Perennial
- Dry





NOTE: For illustrative purposes, not to scale.

DOUBLE 220KV






FIGURE 4-1
220KV LATTICE STEEL
TOWER CONFIGURATION

**DOUBLE CIRCUIT
220KV TSP**





**SINGLE CIRCUIT
220KV TSP**




**FIGURE 4-2
220KV TUBULAR STEEL
POLE CONFIGURATION**

Typical Pole Heads/Clearance







SECTION A - A



SECTION B - B



SECTION C - C



SECTION D - D

**FIGURE 6
CROSS SECTIONS**

115KV H-FRAME




FIGURE 7
TYPICAL 115 KV H-FRAME SUBTRANSMISSION STRUCTURE

Features depicted herein are planning level accuracy, and intended for informational purposes only. Distances and locations may be distorted at this scale. Always consult with the proper legal documents or agencies regarding such features.
© Real Properties, Survey and Mapping

Best Management Practices (BMP's)

BMP NO.	BMP DESCRIPTION
AIR QUALITY	
AIR-1	The construction activities would be in compliance with AQMD requirements, as applicable to the project,
AESTHETICS AND VISUAL RESOURCES	
AES-1	LSTs and TSPs would be galvanized steel with a dulled grey finish that minimizes reflected light.
AES-2	Insulators that minimize reflection of light would be utilized.
AES-3	Substation equipment would have materials that minimize reflective light.
AES-4	If chain link fence is used, it would have a dulled-finish.
AES-5	The substation lighting would be designed to be manually operated for non-routine nighttime work.
BIOLOGICAL RESOURCES	
BIO-1	Preconstruction biological clearance surveys would be conducted to identify special-status plants and wildlife.
BIO-2	SCE would prepare a Worker Environmental Awareness Program (WEAP). All construction crews and contractors would be required to participate in WEAP training prior to starting work on the project.
BIO-3	All transmission and subtransmission towers and poles would be designed to be avian-safe in accordance with the suggested practices for Avian Protection on Power Lines: the State of the Art in 2006 (Avian Power Line Interaction Committee 2006).
CULTURAL RESOURCES	
CR-1	A cultural resource inventory of the project area would be conducted for cultural resources prior to any disturbance. All surveys would be conducted and documented as per applicable laws, regulations, and guidelines.
CR-2	To the extent feasible, all ground-disturbing activities shall be sited to avoid or minimize impacts to cultural resources listed as, or potentially-eligible for listing as, unique archaeological sites, historical resources, or historic properties.
CR-3	A protective buffer zone would be established and maintained around each recorded archaeological site within or immediately adjacent to the ROW.
PALEONTOLOGY RESOURCES	
PALEO-1	A paleontologist would conduct a pre-construction field survey of the project area.
PALEO-2	Prior to construction, a certified paleontologist would supervise monitoring of construction excavations.
GEOLOGY AND SOILS	
GEO-1	Prior to final design of substation facilities, and transmission and, a

	combined geotechnical engineering and engineering geology study would be conducted to identify site-specific geologic conditions and potential geologic hazards in sufficient detail to support sound engineering practices.
GEO-2	For new substation construction, specific requirements for seismic design would be followed based on the Institute of Electrical and Electronic Engineers' 693 "Recommended Practices for Seismic Design of Substations".
GEO-3	New access roads, where required, would be designed to minimize ground disturbance during grading.
GEO-4	Cut and fill slopes would be minimized by a combination of benching and following natural topography where feasible.
GEO-5	Any disturbed areas associated with temporary construction would be returned to preconstruction conditions (to the extent feasible) after the completion of project construction.
HAZARDS AND HAZARDOUS WASTE	
HAZ-1	A Phase I ESA would be performed at each new or expanded substation location and along newly acquired transmission subtransmission line ROWs.
HAZ-2	SCE would implement standard fire prevention and response practices for the construction activities.
HAZ-3	As applicable, SCE would follow fire codes per Cal Fire Power Line Fire Prevention Fire Guide requirements for vegetation clearance during construction of the project to reduce the fire hazard potential.
HAZ-4	<p>Hazardous materials and waste handling would be managed in accordance with the following SCE plans and programs:</p> <ul style="list-style-type: none"> • <i>Spill Prevention, Countermeasure, and Control Plan (SPCC Plan)</i>. In accordance with Title 40 of the CFR, Part 112, SCE would prepare a SPCC for proposed and/or expanded substations, as applicable. • <i>Hazardous Materials Business Plans (HMBPs)</i>. Prior to operation of new or expanded substations, SCE would prepare or update and submit, in accordance with Chapter 6.95 of the CHSD, and Title 22 CCR, an HMBP, as applicable. • <i>Storm Water Pollution Prevention Plan (SWPPP)</i>: A project-specific construction SWPPP would be prepared and implemented prior to the start of construction of the transmission line and substation. • <i>Health and Safety Program</i>: SCE would prepare and implement a health and safety program to address site-specific health and safety issues. • <i>Hazardous Materials and Hazardous Waste Handling</i>: A project-specific hazardous materials management and hazardous waste management program would be developed prior to initiation of the

	<p>project. Material Safety Data Sheets would be made available to all Project workers</p> <p>• <i>Emergency Release Response Procedures:</i> An Emergency Response Plan detailing responses to releases of hazardous materials would be developed prior to construction activities. All construction personnel, including environmental monitors, would be aware of state and federal emergency response reporting guidelines.</p>
HAZ-5	Hazardous materials would be used or stored and disposed of in accordance with Federal, State, and Local regulations.
HAZ-6	The substation would be grounded to limit electric shock and surges that could ignite fires.
HAZ-7	All construction and demolition waste would be removed and transported to an appropriately permitted disposal facility.
HYDROLOGY AND WATER QUALITY	
HYDRO-1	Construction equipment would be kept out of flowing stream channels as feasible.
HYDRO-2	Towers would be located to avoid active drainage channels, especially downstream of steep hill slope areas, to minimize the potential for damage.
LAND USE	
LAND USE-1	SCE shall provide 14 days of advance notice of the start of construction to property owners located within 300 feet of construction-related activities.
NOISE	
NOISE-1	SCE would comply with local noise ordinances.
TRANSPORTATION AND TRAFFIC	
TRANS-1	Traffic control services would be used for equipment, supply delivery, and conductor stringing, as applicable.
TRANS-2	Construction traffic would be scheduled for off-peak hours to the extent feasible and would not block emergency equipment routes.
TRANS-3	If work requires modifications or activities within local roadway and railroad ROWs, appropriate permits would be obtained prior to the commencement of construction activities.

APPENDIX G

LAND USE

Appendix G: Land Use Appendix

San Bernardino General Plan Goals and Policies for the Desert Region.

Land Use Policy applicable to the Desert Region:

Policy D/LU 1.3. Utilize Rural Living (RL) areas to buffer Resource Conservation (RC) areas from more intensive land uses.

County-wide Land Use Policies:

Policy LU 1.1 Develop a well-integrated mix of residential, commercial, industrial, and public uses that meet the social and economic needs of the residents in the three geographic regions of the county: Valley, Mountain, and Desert.

Policy LU 1.2 The design and siting of new development would meet locational and development standards to ensure compatibility of the new development with adjacent land uses and community character.

Policy LU 1.3 Promote a mix of land uses that are fiscally self-sufficient.

Policy LU 4.1 Protect areas best suited for industrial activity by virtue of their location and other criteria from residential and other incompatible uses.

Policy LU 11.1 Foster intergovernmental cooperation among Federal, state, and local agencies on key land use decisions.

Policy LU 11.2 Establish a “review area” around each state, military, or other Federal installation, and review development proposals within each review area with the appropriate agency.

Conservation Element

Conservation Policies applicable to the Desert Region:

Policy D/CO 1.1 Encourage the greater retention of existing native vegetation for new development projects to help conserve water, retain soil in place, and reduce air pollutants.

Policy D/CO 1.2 Require future land development practices to be compatible with the existing topography and scenic vistas, and protect the natural vegetation.

Policy D/CO 1.4 Reduce disturbances to fragile desert soils as much as practicable in order to reduce fugitive dust. The county shall consider the following in the development of provisions to limit clearing:

- a) Parcels of 1 acre or larger shall not be disturbed or cleared of natural vegetation unless for the installation of building pads, driveways, landscaping, agriculture, or other reasonable uses associated with the primary use of the land, including fire clearance areas.
- b) Fire abatement or local clean-up efforts shall be accomplished by mowing or means other than land scraping whenever possible to minimize fugitive dust and

windblown sand. When de-brushing or blading is considered the most feasible alternative, additional methods shall be required for erosion control.

- c) The County Office of Building and Safety may issue permits for further grading or clearance of vegetation subject to proper review.

Policy D/CO 1.5 Mechanical removal of vegetation shall be minimized and limited to the building pad, driveway, and areas prepared for permitted accessory uses.

Policy D/CO 1.8 Require future development to utilize water conservation techniques.

Policy D/CO 1.9 Promote conservation of water by implementing the following policies/actions:

- a) Encourage the use of pervious paving materials on commercial, industrial and institutional parking areas. Large parking areas should consider using landscape areas as depressions to receive and percolate runoff as an alternative.
- b) If a wastewater treatment system is developed within the region, the system which would reclaim the treated effluent and make it available for public or private landscape purposes.

Policy D/CO 1.12 Development requiring tract maps or conditional use permits within the county Biological Resources Overlay for desert tortoise shall prepare and submit a focused biological resources survey and a desert tortoise protocol survey per U.S. Fish and Wildlife requirements.

Policy D/CO 1.13 The County shall support the preparation of a regional Habitat Conservation Plan (HCP) for the desert tortoise and the Mojave Ground Squirrel. This support shall be in the form of providing its fair share portion of the funding to develop desert tortoise and ground squirrel HCP in cooperation with other local jurisdictions, the U. S. Fish and Wildlife Service, Department of Fish and Game and Bureau of Land Management. Funds may be obtained from developer fees in the appropriate habitats.

Policy D/CO 3.1 Protect the Night Sky by providing information about and enforcing existing ordinances:

- a) Provide information about the Night Sky ordinance and lighting restrictions with each land use or building permit application.
- b) Review exterior lighting as part of the design review process.

Policy D/CO 3.2 All outdoor lighting, including street lighting, shall be provided in accordance with the Night Sky Protection Ordinance and shall only be provided as necessary to meet safety standards.

Conservation Policies for Desert Agricultural Land and Soils:

Policy D/CO 4.2 The conversion of agricultural land to non-agricultural uses shall be discouraged unless the proposed use can be demonstrated to be preferable in terms of economic development, and resource availability and resource conservation.

Policy D/CO 5.1 Desert playas shall not be used for habitable structures nor have large quantities of waters applied to them, except for mining operations or to maintain existing wetlands.

Conservation Policies for Desert Cultural and Paleontological Resources:

Policy D/CO 6.1 Identify and protect significant cultural resources from damage or destruction.

Policy D/CO 6.2 Inventory Cultural Resources, encouraging inputs from the local historical society and committees.

Policy D/CO 6.3 Prepare a Historical/Archeological Overlay for community plan areas in developing land use designations and the formulation and evaluation of plan amendments and development proposals to provide a more systematic and streamlined method of protecting important cultural resources.

County-wide Conservation Element Policies:

Policy CO 2.1 The county would coordinate with state and Federal agencies and departments to ensure that their programs to preserve rare and endangered species and protect areas of special habitat value, as well as conserve populations and habitats of commonly occurring species, are reflected in reviews and approvals of development programs.

Policy CO 2.3 In addition to conditions of approval that may be required for specific future development proposals, the county shall establish long-term comprehensive plans for the county's role in the protection of native species because preservation and conservation of biological resources are statewide, Regional, and local issues that directly affect development rights. The conditions of approval of any land use application approved with the Biological Resources (BR) overlay district shall incorporate the mitigation measures identified in the report required by Section 82.13.030 (Application requirements), to protect and preserve the habitats of the identified plants and/or animals.

Policy CO 2.4 All discretionary approvals requiring mitigation measures for impacts to biological resources would include the condition that the mitigation measures be monitored and modified, if necessary, unless a finding is made that such monitoring is not feasible.

County-wide Cultural/Paleontological Resource Conservation:

Policy CO 3.1 Identify and protect important archaeological and historic cultural resources in areas of the County that have been determined to have known cultural resource sensitivity.

Policy CO 3.2 Identify and protect important archaeological and historic cultural resources in all lands that involves disturbance of previously undisturbed ground.

Policy CO 3.4 The County would comply with Government Code Section 65352.2 (SB 18) by consulting with tribes as identified by the California Native American Heritage Commission on all General Plan and specific plan actions.

Policy CO 3.5 Ensure that important cultural resources are avoided or minimized to protect Native American beliefs and traditions.

County-wide Conservation of Air Quality:

Policy CO 4.2 Coordinate air quality improvement technologies with the South Coast Air Quality Management District (SCAQMD) and the Mojave Air Quality Management District (MAQMD) to improve air quality through reductions in pollutants from the region.

County-wide Water Conservation:

Policy CO 5.2 The county Water Masters would continue to monitor the county's adjudicated groundwater basins to ensure a balanced hydrological system in terms of withdrawal and replenishment of water from groundwater basins.

Policy CO 5.3 The county would promote conservation of water and maximize the use of existing water resources by promoting activities/measures that facilitate the reclamation and reuse of water and wastewater.

Policy CO 5.4 Drainage courses would be kept in their natural condition to the greatest extent feasible to retain habitat, allow some recharge of groundwater basins and resultant savings. The feasibility of retaining features of existing drainage courses would be determined by evaluating the engineering feasibility and overall costs of the improvements to the drainage courses balanced with the extent of the retention of existing habitat and recharge potential.

County-wide Conservation of Soils and Agricultural Resources:

Policy CO 6.1 Protect prime agricultural lands from the adverse effects of urban encroachment, particularly increased erosion and sedimentation, trespass, and non-agricultural land development.

Policy CO 6.3 Preservation of prime and statewide important soils types, as well as areas exhibiting viable agricultural operations would be considered as an integral portion of the Open Space element when reviewing development proposals.

Policy CO 6.4 Provide and maintain a viable and diverse agricultural industry in San Bernardino County.

Energy Element

Policy CO 8.1 Maximize the beneficial effects and minimize the adverse effects associated with the siting of major energy facilities. The county would site energy facilities equitably in order to minimize net energy use and consumption of natural resources, and avoid inappropriately burdening certain communities. Energy planning should conserve energy and reduce peak load demands, reduce natural resource consumption, minimize environmental impacts, and treat local communities fairly in providing energy efficiency programs and locating energy facilities.

Policy CO 8.2 Conserve energy and minimize peak load demands through the efficient production, distribution and use of energy.

Policy CO 8.3 Assist in efforts to develop alternative energy technologies that have minimum adverse effect on the environment, and explore and promote newer opportunities for the use of alternative energy sources.

Policy CO 10.1 Electric infrastructure is essential to serve growth and development in the county. Effective planning for electrical infrastructure requires collaboration between the major utilities and the county.

Policy CO 10.2 The location of electric facilities should be consistent with the county's General Plan, and the General Plan should recognize and reflect the need for new and upgraded electric facilities.

Safety Element

Policy S 8.1. Ensure the safety of airport operations and surrounding land uses Programs

- c) Adopt the Land Use Compatibility / Aviation chart as applicable to all discretionary and ministerial applications for Safety Overlay Districts delineated on the Hazards Overlay Maps. Safety areas are defined as follows:
 - (1) That area defined within an adopted Airport Comprehensive Land Use Plan
 - (2) That area defined within an adopted Interim Airport Land Use Plan (where there is no adopted Airport Comprehensive Land Use Plan)
 - (3) That area defined within a low-altitude/high-speed corridor designated for military aircraft operations.

APPENDIX H

VISUAL

Appendix H: Visual Resource

Conformity of Mojave Solar Project with the San Bernardino County General Plan.

The County Development Code implements the San Bernardino General Plan by classifying and regulating the uses of land within unincorporated San Bernardino County; by preserving and protecting the County's important agricultural, cultural, natural, open space and scenic resources; and by protecting and promoting the public health, safety, comfort, convenience, prosperity, and general welfare of residents and businesses in the County (San Bernardino County. 2009c). More specifically, the purposes of the Development Code are to:

- [a] Provide standards and guidelines for the continuing orderly growth and development of the County that will assist in protecting the character and identity of San Bernardino County and its distinct communities.
- [b] Conserve and protect the County's important agriculture, cultural, natural, open space and scenic resources.
- [c] Create a comprehensive and stable pattern of land uses upon which to plan transportation, water supply, sewerage, energy, drainage/flood control and other public facilities and utilities.
- [d] Encourage the most appropriate uses of land in order to prevent overcrowding of land and avoid undue concentration of population, and maintain and protect the value of property.
- [e] Ensure compatibility between different types of development and land use.

According to the San Bernardino General Plan, Circulation and Infrastructure Element,

A highway's designation as "scenic" depends upon the amount of natural landscape can be seen by individuals traveling along its route and the extent to which development intrudes upon this view. The boundaries of a scenic corridor generally encompass the land adjacent to and visible from the highway, using a motorist's line of sight. A reasonable boundary is selected when the view extends to the distant horizon. No restrictions are placed on officially designated scenic highways in terms of improvements or further development, but all proposed Projects are reviewed by Caltrans and the appropriate agencies to ensure the protection of the scenic corridors to the maximum extent feasible.

Because the issue of scenic routes or corridors touches on a number of the elements of the General Plan, the goals and policies for this issue could be placed in any one of these elements. The County has determined, however, that the primary goal of scenic routes is to conserve the scenic qualities of these routes and has therefore included the goals and policies for scenic routes into the Conservation Element.

Table H-1: Conformity of Mojave Solar Project with the San Bernardino County General Plan

Provision	Conformity
Land Use Element	
Desert Region Goal D/LU 2: Establish locational criteria for future development within the region to ensure compatibility between uses and with the character and vision that is desired for the region.	Yes. Implementation of the proposed Project would have no effect on the County's ability to establish criteria for locating future development in the region.
Desert Region Goal D/LU 3: Ensure that commercial and industrial development within the region is compatible with the rural desert character and meets the needs of local residents.	Yes. Implementation of the proposed Project would have no effect on the County's ability to ensure that commercial and industrial development is compatible with the area's character while meeting the needs of the public. Additionally, the AMSP is compatible with the existing character of the adjacent SEGS VIII and IX facilities that were constructed in the 1990s.
Desert Region Policy D/LU 3.1: The County shall develop standards for commercial development within the region to best reflect the character of the region. Standards may include, but not be limited to signage, screening, pedestrian access, parking, and buffering between adjacent land uses.	Yes. Implementation of the Project would have no effect on the County's ability to develop standards for commercial development.
Circulation Element	
Desert Region Goal D/CI 1: Ensure a safe and effective transportation system that provides adequate traffic movement while preserving the rural desert character of the region.	Yes. Implementation of the proposed Project would have no effect on the County's ability to ensure a safe and effective transportation system while preserving the desert's character. Local roads internal to the Project would be improved.
Desert Region Policy D/CI 1.2: Design roads to follow natural contours, avoid grid pattern streets, and minimize cuts and fills and disturbance of natural resources and trees wherever possible.	Yes. Access to the proposed Project would be provided by the existing Harper Lake Road, which would be improved. Existing roads in the area follow a grid pattern on flat terrain, which would follow the County's policy to the extent feasible.
GOAL D/CI 2: Ensure that infrastructure improvements are compatible with the natural environment of the region.	Yes. Infrastructure of the proposed Project would be compatible with the natural environment of the region because the proposed solar fields and power islands would be situated on flat, planar lands in a desert environment with high solar insolation.
D/CI 2.1: Retain the natural channel bottom for all storm water drainage facilities and flood control channels when such facilities are required for a specific development. This protects wildlife corridors and prevents loss of critical habitat in the region.	Yes. New drainage channels would have natural bottoms and sidewalls would be armored with a gabion mattress. Wildlife movement into the AMSP/Lockhart Substation would be restricted by perimeter chain link fencing with tortoise barriers.

Provision	Conformity
Desert Region Goal D/CI 3: Encourage property maintenance to enhance regional aesthetics with the promotion of water and soil conservation, recycling, and proper solid waste disposal.	Yes. Water recycling is proposed as part of the AMSP, soil erosion would be minimized during Project construction, and solid waste disposal would be conducted in accordance with applicable local, state, and federal regulations.
Conservation Element	
Countywide Goal CO 1: The County will maintain to the greatest extent possible natural resources that contribute to the quality of life within the County.	Yes. Implementation of the AMSP/Lockhart Substation would have no effect on the County's ability to maintain the County's natural resources. The AMSP/Lockhart Substation site is substantially disturbed and has no designation for any resources with the exception of rural resources.
Countywide Policy CO 1.2: The preservation of some natural resources requires the establishment of a buffer area between the resource and developed areas. The County will continue the review of the Land Use Designations for unincorporated areas within one mile of any state or federally designated scenic area, national forest, national monument, or similar area, to ensure that sufficiently low development densities and building controls are applied to protect the visual and natural qualities of these areas.	Yes. Implementation of the AMSP/Lockhart Substation would have no effect on the County's ability to review land use designations in unincorporated areas to protect the visual and natural qualities of the areas near state or federally designated scenic areas, national forests, national monuments, or similar areas. The proposed AMSP/Lockhart Substation site is zoned RL which allows electric power generation and it avoids areas that are zoned RC, which are areas typically near undeveloped Federal lands.
Desert Region Goal D/CO 1: Preserve the unique environmental features and natural resources of the Desert Region, including native wildlife, vegetation, water, and scenic vistas.	Yes. Implementation of the AMSP/Lockhart Substation would have no effect on the County's ability to preserve the Desert Region's scenic vistas. The AMSP/Lockhart Substation site is mostly fallow farmland with one currently irrigated crop circle and the site is not located within a designated scenic area.
Desert Region Policy D/CO 1.2: Require future land development practices to be compatible with the existing topography and scenic vistas, and protect the natural vegetation.	Yes. Implementation of the AMSP/Lockhart Substation would have no effect on the County's ability to require future development to be compatible with the existing topography, scenic vistas, and natural vegetation. The AMSP/Lockhart Substation site is mostly fallow farmland with one currently irrigated crop circle and the site does not currently support native desert vegetation.

Provision	Conformity
Desert Region Policy D/CO 1.3: Require retention of existing native vegetation for new development Projects, particularly Joshua trees, Mojave yuccas and creosote rings, and other species protected by the Development Code and other regulations.	Yes. Implementation of the AMSP/Lockhart Substation would have no effect on the County's ability to require future development to retain existing native vegetation for new development Projects. The AMSP/Lockhart Substation site has no Joshua trees, Mojave yuccas and creosote rings, and other species protected by the Development Code and other regulations.
Desert Region Goal D/CO 2: Encourage utilization of renewable energy resources.	Yes. The AMSP is a commercial solar project.
Desert Region Goal D/CO 3: Preserve the dark night sky as a natural resource in the Desert Region communities.	Yes. The AMSP/Lockhart Substation would not affect the night sky in Desert Region communities in California. Project lights that would be turned on at night include: (1) A minimal number of lights would be installed on free-standing poles around the site. These lights would be on for nighttime maintenance activities. Lights would be shielded, directional, and lowest intensity practicable for intended purposes. (2) Vehicle-mounted lights for night maintenance activities (mainly mirror washing).
Desert Region Policy D/CO 3.1: Protect the Night Sky by providing information about and enforcing existing ordinances: b. Review exterior lighting as part of the design review process.	Yes. Implementation of the AMSP/Lockhart Substation would have no effect on the County's ability to provide public information regarding the Night Sky ordinance the County's ability to enforce the ordinance.
Desert Region Policy D/CO 3.2: All outdoor lighting, including street lighting, shall be provided in accordance with the Night Sky Protection Ordinance and shall only be provided as necessary to meet safety standards.	Yes. The AMSP/Lockhart Substation is designed with lighting designed to comply with the Night Sky Protection Ordinance.
Open Space Element	
Countywide Goal OS 4: The County will preserve and protect cultural resources throughout the County, including parks, areas of regional significance, and scenic, cultural, and historic sites that contribute to a distinctive visual experience for visitors and quality of life for County residents.	Yes. Implementation of the AMSP/Lockhart Substation would have no effect on the County's parks, areas of regional significance, scenic areas, or visually important sites that contribute to a distinctive visual experience for visitors and quality of life for County residents.
Countywide Goal OS 5: The County will maintain and enhance the visual character of scenic routes in the County.	Yes. The AMSP/Lockhart Substation would not be visible from SR 58, and eligible State Scenic Highway, because of topographic screening.

Provision	Conformity
Countywide Policy OS 5.3 The County desires to retain the scenic character of visually important roadways throughout the County. A “scenic route” is a roadway that has scenic vistas and other scenic and aesthetic qualities that over time have been found to add beauty to the County. Therefore, the County designates the following routes as scenic highways and applies all applicable policies to development on these routes.	Yes. The AMSP/Lockhart Substation would not be visible from any County designated scenic route.
Countywide Policy OS 7.5: Require that natural landform and ridgelines be preserved by using the following measures: Keep cuts and fills to an absolute minimum during the development of the area. Require the grading contours that do occur to blend with the natural contours onsite or to look like contours that would naturally occur. Encourage the use of custom foundations in order to minimize disruption of the natural landform. Require that units located in the hillsides be so situated that roof lines will blend with and not detract from the natural ridge outline.	Yes. The AMSP/Lockhart Substation site was selected because of its flat terrain. The Project will not affect ridgelines. Proposed rooflines are shallow gable and shallow shed roofs, in keeping with the flat desert terrain of the AMSP/Lockhart Substation site.
Desert Region Goal D/OS 1: Preserve open space lands to ensure that the rural desert character of the region is maintained.	Yes. The AMSP/Lockhart Substation is located immediately adjacent to two existing transmission lines: the SCE owned Coolwater-Kramer 230kV and the Los Angeles Department of Water and Power (LADWP) owned 500-kV Mead-Adelanto transmission line, both of which are located adjacent to the southern border of the Mojave Solar Project. The existing landscape is crossed by existing overhead high-voltage electric transmission lines; therefore, the AMSP/Lockhart Substation would be compatible with other existing structures in the vicinity.

Table H-2: Conformity of Mojave Solar Project with the San Bernardino County Development Code

Provision	Conformity
83.02.060 Screening and Buffering This Section provides standards for the screening and buffering of adjoining land uses, equipment, and outdoor storage areas, and surface parking areas. Multi-family and nonresidential land uses shall comply with the requirements of this Section. (a) Screening between different land uses.	No. The Applicant does not propose to install plant material or solid masonry walls as architectural screening for the AMSP/Lockhart Substation.

Provision	Conformity
<p>(1) An opaque screen consisting of plant material and a solid masonry wall, a minimum of 6 feet in height, shall be installed along parcel boundaries whenever a commercial or industrial development adjoins a residential land use zoning district.</p> <p>(2) The maximum height of walls shall comply with the provisions of Chapter 83.06 (Fences, Hedges, and Walls)</p> <p>(3) The walls shall be architecturally treated or landscaped on both sides to avoid the appearance of unfinished precision block, subject to the approval of the Director.</p> <p>(4) Minimum sizes of plant materials shall conform to the requirements in Subsection 83.10.070 (d) (Landscape Standards Minimum sizes of plant materials).</p> <p>(b) Mechanical equipment, loading docks, and refuse areas.</p> <p>(1) Roof or ground mounted mechanical equipment (e.g., air conditioning, heating, ventilation ducts and exhaust, etc.), loading docks, refuse storage areas, and utility services shall be screened from public view from adjoining public street and rights-of-way and surrounding area(s) zoned for residential or open space uses.</p> <p>(2) The method of screening shall be architecturally compatible with other on-site development in terms of colors, materials, and architectural style.</p> <p>(3) Landscaping shall be installed adjacent to the walls at the discretion of the Director.</p> <p>(c) Outdoor storage areas.</p> <p>(1) The use of outdoor areas for storage purposes shall be subject to the following standards:</p> <p>(A) Outside storage areas shall be screened with a solid sight-obscuring wall not less than six feet nor more than eight feet in height, of a type and design approved by the Director. The wall shall include sight-obscuring gates. The wall and gate(s) shall be continuously maintained in good repair; and</p> <p>(B) Stored materials shall be kept below the level of the fence or other screening mechanism.</p> <p>(C) Site operations in conjunction with outdoor storage, including the loading and unloading of materials and equipment, shall be conducted</p>	

Provision	Conformity
<p>entirely within a walled area.</p> <p>(D) Exterior storage shall comply with Title 3 (Health and Sanitation and Animal Regulations) of the County Code.</p> <p>(2) Incidental outdoor storage shall be allowed, subject to the above standards. Outdoor storage categorized as a primary land use shall be subject to the applicable permitting requirements identified in Division 2 (Land Use Zoning Districts and Allowed Land Uses) and the above standards.</p>	
<p>83.06 (Fences, Hedges, and Walls)</p> <p>83.06.030 General Height Limitations</p> <p>Fences, hedges, and walls may be erected/maintained within required setback areas to the heights identified below:</p> <p>Commercial land use zoning districts – front & side street = 4 ft; Interior side & rear = 10 ft</p> <p>Industrial land use zoning districts – front & side street = 6 ft; Interior side & rear = 10 ft</p> <p>All other land use zoning districts – front & side street = 4 ft; Interior side & rear = 6 ft</p>	<p>No. The Applicant proposes to fence the perimeter of the AMSP/Lockhart Substation for safety and security reasons. The Applicant does not propose to plant hedges or construct fences or walls as part of the AMSP/Lockhart Substation.</p>
<p>83.06.040 Measurement of Fence or Wall Height</p> <p>(a) The height of a fence or wall shall be measured from the finished grade at the location in which the fence or wall is to be located.</p> <p>(b) Where there is a difference in the ground level between two adjacent parcels, the height of a fence or wall constructed along the property line shall be determined by using the finish grade of the lowest contiguous parcel.</p>	<p>No. The Applicant proposes to fence the perimeter of each of the AMSP/Lockhart Substation area for safety and security reasons. The Applicant does not propose to plant hedges or construct fences or walls as part of the AMSP/Lockhart Substation.</p>
<p>83.06.050 Walls Required Between Different Land Use Zoning Districts</p> <p>Walls shall be provided and maintained between different land use zoning districts in the following manner:</p> <p>(a) Nonresidential or multi-family. Where a nonresidential land use district abuts property in any residential land use zoning district or a Multiple Residential Land Use Zoning District abuts property in a Single Residential Land Use Zoning District, a solid masonry wall shall be constructed on the land use zoning district boundary line consistent with the height limitations contained in Table 83-6. If a public right-of-way separates a nonresidential district from any residential district</p>	<p>No. The AMSP/Lockhart Substation does not have walls separating land uses. The Applicant proposes to fence the perimeter of the AMSP/Lockhart Substation area for safety and security reasons. The Applicant does not propose to construct walls as part of the AMSP/Lockhart Substation.</p>

Provision	Conformity
<p>or multi-family residential district from a Single Residential Land Use Zoning District, this wall requirement may not apply. Also, this requirement shall not apply to the Rural Commercial (CR) Land Use Zoning District in the Desert Region.</p> <p>(b) Industrial. Where an industrial land use zoning district abuts property in a nonindustrial land use zoning district, a solid masonry wall, a minimum of 6 feet in height, shall be constructed on the land use zoning district boundary line.</p> <p>(c) Design and construction. Walls shall be of solid masonry construction and shall be of a decorative design when in view of public rights-of-way subject to the approval of the Director.</p> <p>(d) Modification of requirements. The Director may waive or modify requirements for walls between different land use zoning districts where a solid masonry wall already exists on the abutting property if the following findings can be made in a positive manner:</p> <p>(1) The existing wall meets, or would be modified to conform to, the intent of this Chapter.</p> <p>(2) Suitable landscaping would be installed adjacent to the existing wall to supplement and enhance the desired physical separation.</p> <p>(3) The existing wall would be protected to prevent vehicle damage, if necessary.</p> <p>(4) Concurrence of the abutting property owner(s) would be obtained, to modify the existing wall to meet the requirements of this Chapter.</p>	
<p>Chapter 83.07 Glare and Outdoor Lighting 83.07.040 Glare and Outdoor Lighting - Mountain and Desert Regions</p> <p>This Section provides standards for outdoor lighting in the Mountain and Desert Regions, unless exempt in compliance with Subsection 83.07.040(e) (Exempt lighting and fixtures), below.</p> <p>(a) Residential, commercial and industrial land use zoning districts. The following standards shall apply to all structures and freestanding outdoor light fixtures in all land use zoning districts.</p> <p>(2) Shielding requirements. New permitted lighting for new construction, unless exempt in compliance with Subsection 83.07.040(e) (Exempt lighting and fixtures), below, shall be shielded in compliance with the requirements outlined in Table 83-7</p>	<p>Yes. The Applicant plans to minimize trespass light by shielding light fixtures, and plans to eliminate glare from the AMSP/Lockhart Substation by controlling the orientation of the mirrors.</p>

Provision	Conformity
<p>(Shielding Requirements for Outdoor Lighting in the Mountain Region and Desert Region), in order to preclude light pollution or light trespass on:</p> <p>(A) Adjacent property;</p> <p>(B) Other property within the line of sight (direct or reflected) of the light source; or</p> <p>(C) Members of the public who may be traveling on adjacent roadways or rights-of-way.</p> <p>(b) Determination of light trespass. Light trespass shall be determined in compliance with Subsection 83.07.030(a), above.</p> <p>(d) Additional standards for off-site signs (billboards) and on-site signs. Lighting fixtures used to illuminate a new off-site sign and exterior illuminated on-site signs shall be mounted on the top of the sign structure and shall comply with the shielding requirements.</p>	
<p>Chapter 83.10 Landscaping Standards</p> <p>83.10.020 Applicability</p> <p>(a) New uses, structures, and subdivisions. The following land use Projects shall include plans for landscaping, consisting of trees, shrubs, flowers, ground covers, hardscape materials, fencing, walls, or a combination thereof, in the locations and amounts specified in this Chapter. The landscaping shall be installed before issuance of the final Certificate of Occupancy or final Building Permit, except for extensions granted by the Director in compliance with Subsection 83.10.040 (Waiver or Modification of Landscaping Requirements).</p> <p>1. Single-family residential subdivisions (containing 5 or more parcels), multi-family residential Projects, and nonresidential Projects, except as may be exempted by Section 83.10.030 (Exemptions from Landscaping Requirements), below.</p> <p>2. Building Permit applications for sites or developments that are within the service area of a public or private water purveyor that has adopted a water conservation policy.</p>	<p>No. The Applicant does not propose to plant landscaping throughout the AMSP/Lockhart Substation site as part of the project. The Applicant proposes to install minimal amounts of native Xeriscape landscaping outside the entrances to the control room and administrative building.</p>
<p>83.10.050 Landscape Plans</p> <p>(a) Landscape plans required. Landscape plans shall be submitted to the Department for Projects specified in Section 83.10.020 (Applicability), above.</p>	<p>No. The Applicant does not propose to provide a Landscape Plan for the proposed project. The Applicant proposes to install minimal amounts of native Xeriscape landscaping outside the entrances to the control room and administrative building.</p>

Provision	Conformity
<p>(b) Content. Landscape plans shall contain information as specified in the instructions for preparing landscape plans provided by the Department.</p> <p>(c) Review and approval. After initial application, the Director shall review each landscape plan to verify its compliance with the provisions of this Chapter.</p> <p>(d) Statement of surety. When required by the Director, a statement of surety in the form of cash, performance bond, letter of credit, or certificate of deposit in an amount equal to 120 percent of the total value of all plant materials, irrigation, installation, and maintenance shall be posted with the County for a two-year period. The Director may require statements of surety for phased development Projects, a legitimate delay in landscape installation due to seasonal requirements (including adverse weather conditions) and similar circumstances where it may not be advisable or desirable to install all of a Project's landscaping before occupancy of a site.</p>	
<p>83.10.060 Landscape Area Requirements</p> <p>(a) General requirements.</p> <p>(1) Setbacks. Setback and open space areas required by this Development Code shall be landscaped, except where a required setback is occupied by a sidewalk or driveway or where a required setback is screened from public view.</p> <p>(2) Unused areas. Areas of a Project site not intended for a specific use shall be landscaped, unless exempt in compliance with Section 83.10.030 (Exemptions from Landscaping Requirements).</p> <p>(3) Parking areas. Parking areas shall be landscaped in compliance with Chapter 83.11 (Off-Street Parking and Loading). Parking lot area shall not be counted as part of the total lot area when computing the minimum landscaped area in compliance with Table 83-12 nor shall the parking lot landscaping be counted as part of the minimum landscaping required.</p> <p>(4) Minimum area. Projects specified in Section 83.10.020 (Applicability) shall provide and maintain landscaped areas in compliance with Table 83-12 (Minimum Landscaped Area). No</p>	<p>No. The Applicant does not propose to plant landscaping throughout the AMSP/Lockhart Substation site as part of the project. The Applicant proposes to install minimal amounts of native Xeriscape landscaping outside the entrances to the control room and administrative building.</p>

Provision	Conformity
landscaped area having a width of less than five feet shall be considered in the minimum landscaping requirement.	
<p>83.10.070 Landscape Standards</p> <p>Landscaping shall be designed, installed, and maintained as provided in this Section.</p> <p>(a) General design standards. The design of landscaped areas shall incorporate the following features:</p> <p>(1) Coordinated planting design. Planting design shall coordinate new plant materials and their growth requirements with the climate, soil, orientation, water courses, existing vegetation, fire prevention needs, related natural resources and man-made facilities. Landscaping shall be an integral part of the overall Project design and not simply located in excess space after parking areas and structures have been planned.</p> <p>(2) Minimal maintenance intensive landscaping. Maintenance intensive landscaping shall be minimal and shall be located near primary use areas.</p> <p>(3) Plants and materials. Landscaping may include lawn, ground cover, trees, shrubs, and other live plant materials. Landscaping may also include small amounts of accessory decorative outdoor landscape elements (e.g., ponds, fountains, sculpture, and paved or decorated surfaces), excluding driveways, parking, and storage areas.</p> <p>(6) Screening. Landscaping shall be required to screen storage areas, trash enclosures, and parking areas (except residential driveways). Above ground public utilities, such as, but not limited to electrical substations, water storage facilities and treatment plants, shall also be provided with perimeter landscape screening to the extent possible. Freeway and state highway rights-of-way shall also be provided with landscape screening to minimize their aesthetic impacts on adjacent uses. See Section 83.02.060 (Screening and Buffering).</p> <p>(7) Phased development. Graded areas proposed for development in a later phase shall be planted with annual grasses and shall be maintained in a weed-free condition until development occurs, if the later phase will not begin construction within six months of completion of the previous phase.</p>	<p>No. The Applicant does not propose to plant landscaping throughout the AMSP/Lockhart Substation site as part of the project. The Applicant proposes to install minimal amounts of native Xeriscape landscaping outside the entrances to the control room and administrative building.</p>

Provision	Conformity
<p>(b) Plant materials. Plant materials shall be selected and installed to comply with the following requirements:</p> <p>(1) Considerations when selecting plant materials. Attention shall be given to appearance, height, spread, growth rate, moisture requirements, potential root damage, disease, pest susceptibility, climate adaptability, soil type, slope, function, and decreased maintenance.</p> <p>(2) Existing plant materials. Healthy, existing plant materials shall be used to meet landscape requirements wherever possible. Existing trees and plants shall be retained on site, unless otherwise approved in writing by the Director or the proper removal permit is granted in compliance with Division 6 (Plant Protection and Management).</p> <p>(3) Mix of plant materials. A mix of plant materials shall be provided in a variety of container sizes. The mix of plant materials shall include trees, shrubs and attractive erosion preventing ground cover. Use of one predominant species shall be avoided to prevent spread of disease.</p> <p>(4) Location and spacing. Plant materials shall be located in areas appropriate to their known climatic and environmental requirements and spaced to allow mature growth. Trees and shrubs shall be planted so that at maturity they do not interfere with service lines and clear sight triangles.</p> <p>(5) Native and drought-tolerant plant materials. Native plant materials or locally adaptable drought-tolerant plantings capable of surviving the prevailing climatic and soil conditions with a minimum of supplemental water shall be emphasized.</p> <p>(6) Trees. Trees planted near public sidewalks or curbs shall be of a species and installed in a manner that prevents physical damage to sidewalks, curbs, gutters, and other public improvements. Trees shall be planted in areas of public view adjacent to structures, either individually or in grove effect, at the equivalent of one tree per 30 linear feet of building area. Additional trees shall be provided in compliance with Table 83-13 (Minimum Landscape</p>	

Provision	Conformity
<p>Requirements).</p> <p>(7) Water requirements. At least seventy-five percent of the plants selected in non-turf areas shall be well suited to the climate of the region and require minimal water once established in the landscape. Plants that require similar water needs shall be grouped together and shall be irrigated separately.</p> <p>(8) Mulch. In order to reduce evaporation, competition for water, weed growth and damage to trees and shrubs, a minimum of three inches of mulch shall be added in non-turf areas to the soil surface after planting and within 18 inches of tree trunks. Plant types and landscaping applications that are intolerant to or inappropriate for mulch shall be excluded from this requirement.</p> <p>(9) Non-plant groundcover materials. Gravel, colored rock, bark and other similar materials shall not be used as a sole groundcover material. These materials may be used, however, in place of paving materials in functional activity areas (e.g., patios, rear entry walks, etc.) or as non-plant groundcover for up to 20 percent of the total landscaped area.</p> <p>(c) Required quantities of plant material. The minimum quantity of trees, shrubs, and groundcover shall be as follows:</p> <p>(1) General landscaping. For general landscaping, the specifications listed in Table 83-13 (Minimum Quantities of Plant Materials) shall apply. Additional quantities may be required for boundary landscaping, interior parking landscaping [see Section 83.11.080(I)], screening, and slope stabilization.</p> <p>(2) Slope stabilization. In addition to general landscaping, slopes shall be protected from erosion by suitable ground cover that includes a combination of drought tolerant plants and hardscape components. Decorative rock, boulders or other suitable hardscape material may be utilized, but live plant materials shall comprise the dominant visual character. Trees and shrubs may be used as a part of slope landscaping where appropriate. Slope areas shall not be included in the overall required area of a site to be landscaped, and slope landscaping shall not be included in the overall landscape requirements.</p>	

Provision	Conformity
(e) Irrigation. Except where Xeriscaping is specifically designed and intended not to be irrigated, landscaped areas shall be provided with a permanent automatic irrigation system(s) coordinated to meet the needs of various planting areas.	
<p>83.10.080 Regional Landscaping Requirements</p> <p>(c) Desert Region. In the Desert Region the following additional landscaping standards shall apply:</p> <p>(1) Existing desert native plants, or any part thereof except the fruit, shall not be removed without a removal permit issued in compliance with Division 6 (Plant Protection and Management). In addition, replacement of desert native plants shall be in compliance with Division 6 (Plant Protection and Management), except as provided for in this Subsection.</p> <p>(A) Recommended plant materials include, but are not limited to, native, succulent, drought- and infestation-tolerant deciduous and evergreen varieties. The use of turf shall be minimized. A list of recommended plant materials for the Desert Region is available at the Department to assist developers in preparing their landscaping plans.</p> <p>(B) Joshua trees shall be relocated on site, unless otherwise specifically allowed in writing by the Director.</p> <p>(2) A minimum of 15 feet of the front yard and street side yard setback areas of a parcel shall be landscaped using Xeriscape type landscaping and hardscape materials in any combination. For sites where no disturbance of land within setbacks is proposed, landscaping shall not be required.</p> <p>(3) Unpaved parking lots shall not be required to be landscaped. Only those parking lots required to be paved shall be landscaped in compliance in Section 83.11.080 (Landscape Requirements for Parking Areas).</p>	<p>No. The Applicant does not propose to plant landscaping throughout the AMSP/Lockhart Substation site as part of the project. The Applicant proposes to install minimal amounts of native Xeriscape landscaping outside the entrances to the control room and administrative building.</p>
<p>83.13 Sign Regulations</p> <p>83.13.020 Applicability</p> <p>The sign standards provided in this Chapter shall apply to signs in all land use zoning districts in the County. Only signs authorized by this Chapter shall</p>	<p>Yes. The Applicant would comply with the sign regulations and provisions of the County's Development Code. The Applicant may desire to install a freestanding onsite sign at the perimeter of the site.</p>

Provision	Conformity
be allowed in that land use zoning district, unless otherwise expressly provided in this Chapter.	
83.13.030 Sign Permits and Exemptions (a) Sign permits and registration. A person shall not erect a sign regulated by this Chapter without first obtaining appropriate permits from the Building Division and registration with the Code Enforcement Division. Signs shall be erected in compliance with the provisions of this Development Code and applicable specific plans. (c) Exempt signs. The following signs shall be exempt from the requirements of this Development Code and applicable specific plans: (4) Utility company signs identifying conduits, cables, dangerous conditions, or providing other notices of this type.	Yes. As noted in Development Code 83.13.030, utility companies are exempt from the requirement for a sign permit.

Table H-3: Conformity of Mojave Solar Project with the San Bernardino County Ordinance 3900

Provision	Conformity
87.0921 Glare and Outdoor Lighting – Mountain and Desert Areas. (a) The intent of this section is: to encourage effective, non-detrimental lighting; to maintain night-time safety, utility, security and productivity; and to encourage lighting practices and systems which will minimize light pollution, glare and light trespass, conserve energy and resources and curtail the degradation of the night time visual environment.	Yes. The AMSP/Lockhart Substation would comply with Ordinance 3900 by design of light fixtures and placement of light sources. The AMSP/Lockhart Substation would have directional lighting, lenses, and shields to minimize light trespass, light spill, and sky glow.

APPENDIX I

AIR QUALITY

PROJECT DESCRIPTION

The proposed AMS project is a solar electric generating facility totaling 250 MW located on approximately 1,765 acres. The project consists of two separate 125 MW power units, identified as Alpha (northwest) and Beta (southwest). The project would utilize a 21.5 million Btu/hr natural gas-fueled auxiliary heat transfer fluid (HTF) heater on each power unit to reduce startup time and to keep the temperature of the HTF above its freezing point (54 °F).

The proposed solar energy facility would use a 6 cell wet cooling tower for power plant cooling on each power unit. Water would be supplied from onsite groundwater wells, and would be treated as necessary for cooling tower and other onsite uses. The project would also have several other operating emission sources including: 1) HTF expansion vessels and HTF overflow tanks at each power unit with vent emission control systems; 2) an HTF piping system for each power unit; 3) two diesel-fueled 346 horsepower firewater pump engines for fire protection; 4) two diesel-fueled 4,160 horsepower emergency generators; 5) a contaminated soil bio-remediation area; 6) on-site mobile equipment needed for site maintenance (mirror washing) and operation; and 7) offsite vehicle emissions associated with truck hauling of raw materials (fuel and water treatment chemicals) and waste water evaporation pond solids, and employee commute trips.

The applicant is currently proposing the use of groundwater from wells to be constructed onsite to supply plant site raw water needs. Therefore, no offsite water pipelines are proposed to be constructed. Additionally process wastewater would be kept onsite in evaporation ponds and sanitary wastewater would be sent to an onsite sanitary waste septic system, so no offsite industrial waste water or sewer pipelines are proposed to be constructed.

The project also proposes an electrical interconnection to Southern California Edison's (SCE's) transmission system. SCE has proposed significant system-wide upgrades to the transmission system. The onsite transmission line construction would include a new 230KV Hinkley substation and transmission gen-tie lines (11,460 feet for Alpha and 4,430 for Beta). Therefore, no offsite transmission line construction is required to interconnect the project.

The project would connect with an existing Southwest Gas Corporation natural gas pipeline that is located adjacent to the Alpha power unit. Therefore, no offsite gas pipeline construction is required for this project.

PROJECT CONSTRUCTION

The total duration of project construction for AMS is estimated to be approximately 26 months. Different areas within the project site and the construction laydown areas would be disturbed at different times over the construction period. Total construction disturbance area would be approximately 1,765 acres. The maximum acreage disturbed on any one day during construction is estimated by the applicant to be 200 acres. Combustion emissions would result from the off-road construction equipment, including diesel construction equipment used for site grading, excavation, and construction of onsite structures, and water and soil binder spray trucks used to control construction

dust emissions. Fuel combustion emissions also would result from exhaust from on-road construction vehicles, including heavy duty diesel trucks used to deliver materials, other diesel trucks used during construction, and worker personal vehicles and pickup trucks used to transport workers to and from and around the construction site. Fugitive dust emissions would result from site grading/excavation activities, installation of new onsite transmission lines, water and gas pipelines, construction of power plant facilities, roads, and substations, and vehicle travel on paved/unpaved roads.

The applicant's maximum daily and average annual emission estimates, that include the applicant's fugitive dust mitigation assumptions and fleet average off-road equipment emission factors, are provided below in **Air Quality Tables 6 and 7.**

Air Quality Table 6
AMS Construction - Maximum Daily Emissions ^a

	NOx	SOx	CO	VOC	PM10	PM2.5
Onsite Construction Emissions						
Onsite Construction Equipment	583.1	0.6	310.9	97.3	25.9	25.7
Fugitive dust	--	--	--	--	145.4	30.5
Subtotal of Onsite Emissions	583.1	0.6	310.9	97.3	171.3	56.2
Offsite Construction Emissions						
Paved Road Dust	--	--	--	--	10.2	0.3
Track-out Dust	--	--	--	--	5.9	1.0
Delivery/Hauling Exhaust	97.5	0.1	29.5	7.1	4.4	4.4
Worker Travel Exhaust	54.4	0.5	469.5	39.6	3.8	3.8

Source: AS 2009a, ESH 2009c, ESH 2010e, ESH 2010g

^a - The maximum daily emissions do not always occur on the same day for each pollutant or occur concurrently for the separate construction activities.

Air Quality Table 7
AMS Construction – Average Annual Emissions (tons/year)

	NOx	SOx	CO	VOC	PM10	PM2.5
Onsite Construction Emissions						
Onsite Construction Equipment	68.9	0.1	34.7	11.0	4.0	4.0
Fugitive dust	--	--	--	--	12.8	2.7
Subtotal of Onsite Emissions	68.9	0.1	34.7	11.0	16.8	6.7
Offsite Emissions						
Paved Road Dust	--	--	--	--	1.2	0.0
Track-out Dust	--	--	--	--	0.7	0.1
Delivery/Hauling Exhaust	12.5	0.0	3.8	0.9	0.57	0.56
Worker Travel Exhaust	7.2	0.1	60.8	5.2	0.46	0.46

Source: AS 2009a, ESH 2009c, ESH 2010e, ESH 2010g

The emissions presented in **Air Quality Table 7** represents annual values averaged over the 26 month construction period and not maximum annual emissions. The applicant submitted revised construction emission estimates on February 2nd. Staff's review of these emission estimates indicated that: 1) the fugitive dust emission estimate procedure was oversimplified and not conservative; 2) trip length estimates were not realistic and did not match other information provided in the AFC; and 3) that dated emission factors were used for both the on-road and off-road equipment. Staff performed a separate corrected emission estimate. The results of staff's corrected emission estimate are provided in **Air Quality Table 8**. The purpose of this revised emission analysis is primarily to confirm that the project does not trigger a General Conformity analysis and for staff to obtain a better understanding of the construction elements and their potential for near-field nuisance impacts to residents located on or near the project fence line.

Air Quality Table 8
AMS Construction – Staff Emission Estimate

	NOx	SOx	CO	VOC	PM10	PM2.5
Maximum Daily Emissions (lb/day) ^a						
Onsite Construction Equipment	598.4	0.6	841.0	240.4	31.2	29.6
Onsite Fugitive dust	---	---	---	---	1,102.0	211.4
Subtotal of Onsite Emissions	598.4	0.6	841.0	240.4	1,133.2	240.0
Offsite Vehicle Emissions	135.9	0.7	475.5	53.3	7.8	6.8
Offsite Fugitive Dust Emissions	---	---	---	---	29.9	0.0
Subtotal of Offsite Emissions	135.9	0.7	475.5	53.3	37.7	6.8
Maximum Daily Total	734.4	1.3	1,316.6	293.7	1,170.9	247.8
Maximum Annual Emissions (tons/year) ^b						
Onsite Construction Equipment	47.5	0.0	61.8	19.2	2.8	2.6
Onsite Fugitive dust	---	---	---	---	78.7	14.9
Subtotal of Onsite Emissions	47.5	0.0	61.8	19.2	81.4	17.5
Offsite Vehicle Emissions	17.2	0.1	75.1	7.7	1.1	0.8
Offsite Fugitive Dust Emissions	---	---	---	---	3.9	0.0
Subtotal of Offsite Emissions	17.2	0.1	75.1	7.7	4.9	0.8
Maximum Daily Total	64.7	0.2	136.9	26.9	86.3	18.3

Source: Staff Analysis (CEC 2010o)

^a - Maximum daily and monthly emissions for all criteria would occur during Month 6, except PM10 which would have its peak emissions during Month 5.

^b - Maximum annual emissions (worst-case consecutive twelve month period for onsite and offsite emissions) do not occur during the same periods for all pollutants: for PM10 and PM2.5 the peak occurs during months 1 to 12; for NOx the peak occurs during months 2 through 13; for VOC the peak occurs during months 4 through 15; for CO the peak occurs during months 6 through 17; and for SOx the peak occurs during months 10 through 21 of the 26 month construction schedule.

Staff's construction emission estimate is fairly close to the applicant's emission estimate for certain activities and pollutants. The major divergence is in the particulate emission estimates, where staff believes that the applicant did not use an estimation technique appropriate to the complexity of the construction required for this project. However, staff's major finding from this analysis is that the worst-case annual construction

emissions would not trigger a General Conformity analysis for the project. Staff's emission calculations, in Adobe Acrobat File format, have been docketed separately from the Supplemental Staff Assessment (SSA)⁵.

PROJECT OPERATION

The AMS facility would be a nominal 250 Megawatt (MW) parabolic solar trough thermal solar electrical generating facility (AS 2009a). The direct air pollutant emissions from power generation are minimal; however, there are required auxiliary equipment and maintenance activities necessary to operate and maintain the facility. The facility includes two 125 MW power blocks with identical stationary operating equipment, with one noted exception, and maintenance activity requirements.

The AMS onsite stationary and mobile emission sources are as follows:

- Two 21.5 MMBtu natural gas-fueled auxiliary HTF heaters, one per power block, used to maintain the temperature of the HTF above freezing during cold months and pre-warming for daily startup year-round;
- Two 6-cell wet-cooling towers, one per power block, each to provide cooling and heat rejection from a single power block process;
- Two 346-hp diesel-fired emergency fire water pump engines, one per power block;
- Two 4,160-hp diesel engine-driven emergency generators, one per power block;
- One 2,000 gallon gasoline tank and one 2,000 gallon diesel tank that would refuel onsite dedicated vehicles for both power blocks;
- Eight HTF expansion vessels and two HTF overflow tanks on each power block, that would be serviced by HTF venting control systems;
- Two separate HTF piping systems for each power block with a total facility component count of 3,247 valves, 8,120 flanges/connectors⁶, 24 pump seals, and 16 pressure relief valves.
- Spent HTF waste loadout;
- Two bio-remediation/ land farm units, one per power block, to treat HTF contaminated soils; and
- Onsite diesel and gasoline fueled maintenance vehicles used for mirror washing and other maintenance/operation support activities.

The emissions from the spent HTF waste loadout, bioremediation/land farm units, and diesel tanks are negligible, they do not require permitting by the MDAQMD, and are not included in the VOC emission estimates for the facility or discussed further in this section.

⁵ The Excel file format for these calculations can be provided to parties upon request.

⁶ Staff increased the number of flanges/connectors to a value of 4,060 per unit to be consistent with the component count ratios of other currently analyzed projects using HTF piping systems. This revision has a very minor effect on the emission estimate for the HTF piping system.

The applicant⁷ provided both onsite and offsite emission estimates using the following assumptions to develop the hourly, daily, and annual onsite emissions estimates for AMS operation:

A. Maximum Hourly Emissions

- Both auxiliary HTF heaters, the cooling towers, one emergency generator engine, the HTF vent, and the HTF piping system all operate for the full hour.
- The gasoline tank has a 1,000 gallon loading event.
- The onsite diesel vehicles (SCA cleaning truck, evacuation truck, etc) and gasoline vehicles (stakebed truck, ranger truck, welding truck, etc) hourly emissions are based on the annual emissions divided by 8,760 hours per year.

B. Maximum Daily Emissions

- Both auxiliary HTF heaters operate for 24 hours.
- Both cooling towers operate for 16 hours.
- The emergency generator engines operate for a total of one hour.
- The HTF vent system operates for eight hours.
- The HTF piping system fugitive emissions have been recalculated by staff, consistent with the procedures developed by Kern County Air Pollution Control District that consider the properties of the HTF during the daily operation cycle, where it is assumed that for 16 hours per day the HTF in the piping system is consistent with the properties of a light liquid and for 8 hours per day the HTF in the piping system is consistent with the properties of a heavy liquid. The specific emission factors used are as follows:

Piping Component	Light Liquid Emission Factor (lb/hr/source)	U.S.EPA Reference Table	Heavy Liquid Emission Factor (lb/hr/source)	U.S.EPA Reference Table
Valves	5.55E-04	Table 2-9 (100 ppm)	1.90E-05	Table 2-4 (Heavy Oil)
Pump Seals	1.86E-03	Table 2-9 (100 ppm)	5.30E-05	Table 2-12 (Zero Factor)
Flanges/Connectors	1.65E-05	Table 2-12 (Zero Factor)	1.65E-05	Table 2-12 (Zero Factor)
Pressure Relief Valves	9.85E-02	Table 2-5 (<10,000 ppm)	1.90E-05	Table 2-4 (Heavy Oil)

Source: USEPA 1995.

Note: for pressure relief valves the in service emission factors are for gas service, rather than light liquid service.

These emission factors may not assume appropriate control efficiencies for the inspection and maintenance program required by MDAQMD. Staff will update this emission estimate, if necessary, after further consideration of the effectiveness of the inspection and maintenance program.

- The gasoline tank has a 1,000 gallon loading event and 200 gallons of vehicle refueling.

⁷ Assumptions regarding the gasoline tank emissions have been updated by staff to reflect both maximum emission events per hour and per day and also reflect that the gasoline tank will be required to have both Phase I and Phase II vapor balance controls.

- The onsite diesel vehicles (SCA cleaning truck, evacuation truck, etc) and gasoline vehicles (stakebed truck, ranger truck, welding truck, etc) hourly emissions are based on the annual emissions divided by 365 days per year.

C. Maximum Annual Emissions

- Both auxiliary HTF heaters operate for 4,380 hours per year.
- Both cooling towers operate for 5,840 hours per year.
- The emergency fire pump engines and emergency generator engines operate for 50 hours per year each⁸.
- The HTF vent system operates for 2,920 hours per year.
- The HTF piping system daily fugitive emissions multiplied by 365 days per year.
- The gasoline tank has an annual throughput of 18,000 gallons.
- The diesel vehicles (SCA cleaning truck, evacuation truck, etc) and gasoline vehicles (stakebed truck, ranger truck, welding truck, etc) emissions are based on a total annual vehicle miles traveled (VMT) of 40,000 and 102,040, respectively.

The AMS onsite stationary source and mobile equipment emissions, including fugitive PM10 emissions, for the entire facility are estimated and summarized in **Air Quality Table 9**.

⁸ This basis is updated from the applicant's assumption of 52 hours based on a regulatory limit of 50 hours for engine testing and maintenance operation.

Air Quality Table 9
AMS Operation - Maximum Hourly, Daily, and Annual Onsite Emissions

	Maximum Hourly Emissions (lbs/hr)					
Emission Source	NOx	SOx	CO	VOC	PM10	PM2.5
Auxiliary HTF Heaters	0.47	0.03	1.63	0.46	0.32	0.32
Cooling Towers	--	--	--	--	4.48	4.48
Emergency Fire Pump Engines	0.00	0.00	0.00	0.00	0.00	0.00
Emergency Generator Engines	46.61	0.04	3.78	0.92	0.33	0.33
HTF Expansion Tanks/Venting Systems	--	--	--	1.14	--	--
HTF Piping Systems	--	--	--	3.56	--	--
Gasoline Storage Tank	--	--	--	0.42	--	--
Maintenance Vehicles (all types)	0.38	0.00	0.23	0.07	0.03	0.03
Operations Fugitive Dust	--	--	--	--	4.25	0.90
Total Maximum Hourly Emissions	47.46	0.07	5.64	6.57	9.41	6.06
Emission Source	Maximum Daily Emissions (lbs/day)					
Auxiliary HTF Heaters	11.36	0.60	39.22	11.08	7.65	7.65
Cooling Towers	--	--	--	--	71.74	71.74
Emergency Fire Pump Engines	0.00	0.00	0.00	0.00	0.00	0.00
Emergency Generator Engines	46.61	0.04	3.78	0.92	0.33	0.33
HTF Expansion Tanks/Venting Systems	--	--	--	9.10	--	--
HTF Piping Systems	--	--	--	58.51	--	--
Gasoline Storage Tank	--	--	--	0.63	--	--
Maintenance Vehicles (all types)	9.21	0.02	5.49	1.65	0.61	0.61
Operations Fugitive Dust	--	--	--	--	102.10	21.70
Total Maximum Daily Emissions	67.18	0.66	48.49	81.89	182.43	102.03
Emission Source	Annual Emissions (tons/year)					
Auxiliary HTF Heaters	0.52	0.03	1.79	0.51	0.35	0.35
Cooling Towers	--	--	--	--	13.09	13.09
Emergency Fire Pump Engines	0.11	0.00	0.10	0.01	0.01	0.01
Emergency Generator Engines	2.33	0.00	0.19	0.05	0.02	0.02
HTF Expansion Tanks/Venting Systems	--	--	--	1.66	--	--
HTF Piping Systems	--	--	--	10.68	--	--
Gasoline Storage Tank	--	--	--	0.01	--	--
Maintenance Vehicles (all types)	1.68	0.00	1.00	0.30	0.11	0.11
Operations Fugitive Dust	--	--	--	--	18.63	3.96
Total Annual Emissions	4.64	0.03	3.08	13.22	32.21	17.54

Source: AS 2009a, ESH 2009c, ESH 2010e, ESH 2010g, ESH 2010k, and Staff Analysis.

In addition to the onsite stationary and mobile emission sources there are offsite deliveries (fuel, water treatment chemicals, periodic evaporation pond solids waste haul trips, etc.) and daily employee trips. The following assumptions were used by the applicant to develop daily and annual offsite mobile source emissions estimates for AMS operation:

A. Maximum Daily Emissions

- For delivery vehicles the daily emission were based on the annual emissions divided by 260 (deliveries occur on weekdays).
- For employee commuting the daily emissions were based on the annual emissions divided by 365 days per year (employees work every day).

B. Maximum Annual Emissions

- 12,540 gasoline delivery vehicle VMT (medium duty gasoline vehicles size was assumed).
- 12,540 diesel delivery vehicle VMT (heavy duty diesel trucks were assumed).
- 1,241,000 employee commuting VMT based on an average of 68 commuting employees per day, 365 days per year, with a 50 mile round trip commute distance.

The AMS offsite mobile source emissions estimated by the applicant, including fugitive PM10 emissions, are summarized in **Air Quality Table 10**.

Air Quality Table 10
AMS Operation - Applicant Calculated Maximum
Daily and Annual Offsite Emissions

	Maximum Daily Emissions (lbs/day)					
Emission Source	NOx	SOx	CO	VOC	PM10	PM2.5
Diesel Delivery Vehicles	1.65	0.00	0.46	0.12	0.08	0.07
Gasoline Delivery Vehicles	0.1	0.00	0.63	0.05	0.00	0.00
Employee Vehicles	3.77	0.03	37.67	3.13	0.31	0.30
Total Maximum Daily Emissions	5.52	0.03	38.76	3.30	0.39	0.37
	Annual Emissions (tons/year)					
Emission Source						
Diesel Delivery Vehicles	0.21	0.00	0.06	0.02	0.01	0.01
Gasoline Delivery Vehicles	0.01	0.00	0.08	0.01	0.00	0.00
Employee Vehicles	0.69	0.01	6.88	0.57	0.06	0.06
Total Annual Emissions	0.91	0.01	7.02	0.60	0.07	0.07

Source: AS 2009a, ESH 2009c, ESH 2010e, ESH 2010g

Staff does not believe that the applicant's emission estimate assumptions for trip length or daily emissions are reasonable, nor did the applicant include fugitive road dust emissions in the offsite emissions estimate. Therefore, staff provided a revised set of assumptions and emission calculations, using emission factors from a more recent version of the ARB EMFAC model, which have been docketed separately (CEC 2010o). The results of Staff's offsite emission calculations are shown in **Air Quality Table 11**.

Air Quality Table 11
AMS Operation – Staff Calculated Maximum Daily and Annual Offsite Emissions

	Maximum Daily Emissions (lbs/day)					
Emission Source	NOx	SOx	CO	VOC	PM10	PM2.5
Delivery Vehicles	13.71	0.02	4.66	1.13	0.67	0.57
Employee Vehicles	4.16	0.06	41.42	4.35	0.53	0.34
Fugitive Dust	--	--	--	--	5.38	0
Total Maximum Daily Emissions	17.87	0.08	46.08	5.49	6.58	0.91
	Annual Emissions (tons/year)					
Emission Source						
Delivery Vehicles	0.63	0.00	0.21	0.05	0.03	0.03
Employee Vehicles	0.71	0.01	7.04	0.74	0.09	0.06
Fugitive Dust	--	--	--	--	0.86	0
Total Annual Emissions	1.33	0.01	7.25	0.79	0.98	0.08

Source: Staff Analysis (CEC 2010o) of vehicle trip data provided in ESH 2010g

The emissions presented in **Air Quality Table 11** are representative of 2013 fleet average vehicle emission factors. The offsite emissions during operation, with the exception of fugitive dust emissions, will go down over time as employee vehicles and delivery trucks are replaced with newer lower emitting models. Staff's emission calculations, in Adobe Acrobat File format, have been docketed separately from the SSA⁹.

PROJECT CONSTRUCTION AND OPERATION OVERLAP

The Alpha and Beta Units may be developed in phases. Although there could be some overlap of construction and commercial operation, staff does not anticipate this overlap to be the maximum worst case scenario. Construction emissions are considerably higher than operating emissions and the maximum construction emissions occur early in the overall construction process (first six months), so any overlap after the maximum construction period is assumed not to create a new maximum emissions scenario. Therefore, staff concludes that the overlapping emissions and impacts during this overlapping period would be no worse than the worst-case construction impacts and has not performed any additional impact assessment of the construction/operation overlapping period.

INITIAL COMMISSIONING AND CLOSURE

Initial commissioning refers to a period prior to beginning commercial operation when the equipment undergoes initial tests. Because of this proposed project's use of a non-fuel fired generating technology, staff does not expect major changes in emissions from the facility commissioning activities compared to that of normal operation.

Closure and decommissioning, as a one-time limited duration event, would have emissions that are similar in type and magnitude, but likely lower than, the construction emissions as discussed above.

⁹ The Excel file format for these calculations can be provided to parties upon request.

Construction Emissions Summary Tables

Parameter	Units	NOx	CO	VOC	SOX	PM10	PM2.5	CO ₂ ⁽²⁾
Onsite Construction Emissions								
Fugitive Dust-Phase I	Lbs/day	-	-	-	-	145.4	30.5	-
	Tons/Period	-	-	-	-	9.34	1.96	-
Fugitive Dust-Phase II	Lbs/day	-	-	-	-	2.9	0.6	-
	Tons/Period	-	-	-	-	0.6	0.1	-
Fugitive Dust-Phase III	Lbs/day	-	-	-	-	11.5	2.4	-
	Tons/Period	-	-	-	-	2.8	0.6	-
Fugitive Dust-Phase IV	Lbs/day	-	-	-	-	57.6	12.1	-
	Tons/Period	-	-	-	-	15.1	3.2	-
Equipment Exhaust-Phase I	Lbs/day	583.1	197.9	66.2	0.57	25.89	25.66	-
	Tons/Period	38.5	13.1	4.4	0.04	1.71	1.69	5706
Equipment Exhaust-Phase II	Lbs/day	14.8	6.3	1.8	0.018	0.68	0.68	-
	Tons/Period	3.2	1.4	0.4	0.004	0.15	0.15	1060
Equipment Exhaust-Phase III	Lbs/day	138.1	83.2	26.8	0.16	8.69	8.61	-
	Tons/Period	36.4	22.0	7.1	0.04	2.29	2.27	8988
Equipment Exhaust-Phase IV	Lbs/day	249.1	135.2	41.6	0.26	15.71	15.57	-
	Tons/Period	71.2	38.7	11.9	0.07	4.49	4.45	16638
Offsite Construction Emissions								
Paved Road Dust	Lbs/day	-	-	-	-	10.19	0.27	-
	Tons/Period	-	-	-	-	2.61	0.07	-
Track-out Dust	Lbs/day	-	-	-	-	5.88	0.993	-
	Tons/Period	-	-	-	-	1.5	0.254	-
Delivery/Hauling Exhaust	Lbs/day	97.5	29.5	7.1	0.12	4.43	4.39	-
	Tons/Period	27	8.2	1.96	0.032	1.23	1.22	3259
Worker Travel-Exhaust (bused and non-bused)	Lbs/day	54.4	469.5	39.6	0.47	3.79	3.78	-
	Tons/Period	15.6	131.7	11.2	0.12	1.0	1.0	11324

Notes:

1. Daily maximum emissions for equipment exhaust can be found on Table C.5-5. Daily average emissions are presented here as they represent site activity and emissions levels over the course of the project.
2. CO₂e emissions are calculated and totaled on Table C.5-5. CO₂e emissions for the construction period are ~ 43,015 metric tons.

Based upon the applicant's best estimate, the maximum daily onsite emissions will be as follows:

1. Fugitive dust emissions will be the greatest during the Phase I grading and site preparation period.
2. Exhaust emissions will peak during Phases II-IV (month 15 or 16).

Estimated Maximum Daily Onsite Emissions (lbs/day)

Phase	Category	NOx	CO	VOC	SOx	PM10	PM2.5
I	Fugitive Dust	-	-	-	-	145.4	30.5
	Exhaust	583	198	66.2	0.57	25.9	25.7
<i>Total Phase I</i>		<i>583</i>	<i>198</i>	<i>66.2</i>	<i>0.57</i>	<i>171.3</i>	<i>56.2</i>
II-IV	Fugitive Dust	-	-	-	-	72.0	15.1
	Exhaust	556	311	70.2	0.60	34.6	34.2
<i>Total Phases II-IV</i>		<i>556</i>	<i>311</i>	<i>70.2</i>	<i>0.60</i>	<i>106.6</i>	<i>49.3</i>

Estimated onsite emissions in terms of tons per year (tons per period normalized based on a period of 26 months, 2.167 yrs).

	NOx	CO	VOC	SOx	PM10	PM2.5	CO2
Tons/Period	149.3	75.2	23.8	0.15	36.4	14.5	32392
Tons/Yr	68.9	34.7	11.0	0.07	16.8	6.66	14948

All construction emissions (onsite and offsite) in terms of tons per year are compared to the applicable conformity threshold levels in the table below (including fugitive dust and exhaust based emissions).

	NOx	CO	VOC	SOx	PM10	PM2.5	CO2e
Construction Emissions, tpy	88.6	99.3	17.1	0.14	19.8	7.85	21677
Conformity Threshold, tpy	100 ¹	na	50/100 ²	na	70	na	na
Conformity Analysis Required	No	No	No	No	No	No	na

1 The site is located in the portion of San Bernardino County that lies within the “moderate” ozone NA area. As such, the applicable conformity threshold for NOx for NA areas in or outside of an ozone transport area is 100 tpy.

2 The site is located in the portion of San Bernardino County that lies within the “moderate” ozone NA area. As such the applicable conformity threshold for VOC for NA areas outside of an ozone transport area is 100 tpy, and for areas inside an ozone transport area the VOC threshold is 50 tpy.

3 The site region is attainment for CO, SOx, and NO2, therefore no conformity thresholds apply.

Operational Emissions Summary Tables

HTF Auxiliary Heaters (2 units)

	NOx	CO	VOC	SOx	PM10	PM2.5	CO2e
Lbs/hr	0.473	1.63	0.461	0.0252	0.319	0.319	-
Lbs/day	11.4	39.2	11.1	0.604	7.65	7.65	-
Tons/Yr	0.518	1.79	0.505	0.0276	0.349	0.349	11000

Cooling Towers (2 units)

	NOx	CO	VOC	SOx	PM10	PM2.5	CO2e
Lbs/hr	-	-	-	-	4.48	4.48	-
Lbs/day	-	-	-	-	71.74	71.74	-
Tons/Yr	-	-	-	-	13.09	13.09	-

HTF Venting/Control System (2 Systems)

	NOx	CO	VOC	SOx	PM10	PM2.5	CO2e
Lbs/hr	-	-	1.138	-	-	-	-
Lbs/day	-	-	9.1	-	-	-	-
Tons/Yr	-	-	1.66	-	-	-	-

HTF Component Fugitives (2 Solar Fields)

	NOx	CO	VOC	SOx	PM10	PM2.5	CO2e
Lbs/hr	-	-	2.44	-	-	-	-
Lbs/day	-	-	26.42	-	-	-	-
Tons/Yr	-	-	4.82	-	-	-	-

HTF Waste Load-out Fugitives

	NOx	CO	VOC	SOx	PM10	PM2.5	CO2e
Lbs/hr	-	-	0.0013	-	-	-	-
Lbs/day	-	-	0.0013	-	-	-	-
Tons/Yr	-	-	0.0000078	-	-	-	-

Emergency Fire Pump Systems (2 units)

	NOx	CO	VOC	SOx	PM10	PM2.5	CO2e
Lbs/hr	4.27	3.96	0.30	0.0031	0.23	0.23	-
Lbs/day	4.27	3.96	0.30	0.0031	0.23	0.23	-
Tons/Yr	0.11	0.10	0.01	0.0001	0.006	0.006	8.9

(1) These engines do not run in the same hour or on the same day for purposes of readiness testing.

Emergency Electrical Generators (2 units)

	NOx	CO	VOC	SOx	PM10	PM2.5	CO2e
Lbs/hr	93.21	7.57	1.85	0.07	0.66	0.66	-
Lbs/day	93.21	7.57	1.85	0.07	0.66	0.66	-
Tons/Yr	2.42	0.20	0.05	0.002	0.017	0.017	202

(1) These engines do not run in the same hour or on the same day for purposes of readiness testing.

Diesel Storage Tank (1 unit)

	NOx	CO	VOC	SOx	PM10	PM2.5	CO2e
Lbs/hr	-	-	0.0005	-	-	-	-
Lbs/day	-	-	0.0108	-	-	-	-
Tons/Yr	-	-	0.002	-	-	-	-

Gasoline Storage Tank (1 unit)

	NOx	CO	VOC	SOx	PM10	PM2.5	CO2e
Lbs/hr	-	-	0.027	-	-	-	-
Lbs/day	-	-	0.64	-	-	-	-
Tons/Yr	-	-	0.117	-	-	-	-

Onsite Operations Vehicles

	NOx	CO	VOC	SOx	PM10	PM2.5	CO2e
Lbs/hr	0.384	0.229	0.069	0.00068	0.0256	0.0256	-
Lbs/day	9.21	5.485	1.65	0.0164	0.614	0.614	-
Tons/Yr	1.68	1.0	0.301	0.003	0.112	0.112	131.92

(1) Daily values are the annual values converted to lbs and divided by 365.

(2) Hourly values are the daily values divided by 24.

Operations Fugitive Dust

	NOx	CO	VOC	SOx	PM10	PM2.5	CO2e
Lbs/hr	-	-	-	-	4.25	0.90	-
Lbs/day	-	-	-	-	102.1	21.7	-
Tons/Yr	-	-	-	-	18.6	4.0	-

(1) Hourly values are daily values divided by 24.

Maximum Operational Emissions for Purposes of NSR Applicability and Offset Mitigation

	NOx	CO	VOC	SOx	PM10	PM2.5	CO2e
Lbs/hr	47.1	5.42	5.0	0.06	5.13	5.13	-
Lbs/day	58.0	43.0	48.2	0.64	79.7	79.7	-
Tons/Yr	3.1	2.1	7.2	0.03	13.5	13.5	11211
MDAQMD Offset Thresholds Tons/yr	25	100	25	25	15	na	na
Offsets Required	No	No	No	No	No	No	na
Conformity Threshold, tpy ⁴	100	na	50/100	na	70	na	na
Conformity Analysis Required	No	No	No	No	No	No	na

Notes:

1. The IC engines (generators and fire pumps) will not be run during the same hour or the same day.
2. Fugitive dust from operations is not included per MDAQMD NSR rule.
3. Operations vehicle emissions are not included per the MDAQMD NSR rule.
4. The site is located in the portion of San Bernardino County that lies within the "moderate" ozone NA area. As such, the applicable conformity threshold for NOx for NA areas in or outside of an ozone transport area is 100 tpy.
The site is located in the portion of San Bernardino County that lies within the "moderate" ozone NA area. As such the applicable conformity threshold for VOC for NA areas outside of an ozone transport area is 100 tpy, and for areas inside an ozone transport area the VOC threshold is 50 tpy.
The site region is attainment for CO, SOx, and NO2, therefore no conformity thresholds apply.

All operational emissions (including fugitive dust and vehicle based emissions) in terms of tons per year are compared to the applicable conformity threshold levels in the table below.

	NOx	CO	VOC	SOx	PM10	PM2.5	CO2e
Facility Emissions, tpy	4.73	3.1	7.47	0.033	32.17	17.57	11343
Conformity Threshold, tpy	100	na	50/100	na	70	na	na
Conformity Analysis Required	No	No	No	No	No	No	na
<p>The site is located in the portion of San Bernardino County that lies within the "moderate" ozone NA area. As such, the applicable conformity threshold for NOx for NA areas in or outside of an ozone transport area is 100 tpy.</p> <p>The site is located in the portion of San Bernardino County that lies within the "moderate" ozone NA area. As such the applicable conformity threshold for VOC for NA areas outside of an ozone transport area is 100 tpy, and for areas inside an ozone transport area the VOC threshold is 50 tpy.</p> <p>The site region is attainment for CO, SOx, and NO2, therefore no conformity thresholds apply.</p>							

5/11/2010 01:40:15 PM

Urbemis 2007 Version 9.2.4

Combined Annual Emissions Reports (Tons/Year)

File Name: C:\Work\Projects\Abengoa Mojave Solar\For EA\Urbemis\Lockhart Substation.urb924

Project Name: Lockhart Substation

Project Location: San Bernadino County

On-Road Vehicle Emissions Based on: Version : Emfac2007 V2.3 Nov 1 2006

Off-Road Vehicle Emissions Based on: OFFROAD2007

Summary Report:

CONSTRUCTION EMISSION ESTIMATES

	<u>ROG</u>	<u>NOx</u>	<u>CO</u>	<u>SO2</u>	<u>PM10 Dust</u>	<u>PM10 Exhaust</u>	<u>PM10</u>	<u>PM2.5 Dust</u>	<u>PM2.5 Exhaust</u>	<u>PM2.5</u>	<u>CO2</u>
2011 TOTALS (tons/year unmitigated)	0.46	4.15	5.29	0.01	0.04	0.18	0.21	0.01	0.16	0.17	1,049.62
2012 TOTALS (tons/year unmitigated)	0.24	2.12	2.71	0.00	0.02	0.09	0.11	0.01	0.09	0.09	570.86

Construction Unmitigated Detail Report:

CONSTRUCTION EMISSION ESTIMATES Annual Tons Per Year, Unmitigated

	<u>ROG</u>	<u>NOx</u>	<u>CO</u>	<u>SO2</u>	<u>PM10 Dust</u>	<u>PM10 Exhaust</u>	<u>PM10</u>	<u>PM2.5 Dust</u>	<u>PM2.5 Exhaust</u>	<u>PM2.5</u>	<u>CO2</u>
2011	0.46	4.15	5.29	0.01	0.04	0.18	0.21	0.01	0.16	0.17	1,049.62
Building 01/01/2011-02/04/2011	0.04	0.39	0.50	0.00	0.00	0.02	0.02	0.00	0.02	0.02	96.46
Building Off Road Diesel	0.01	0.10	0.04	0.00	0.00	0.01	0.01	0.00	0.01	0.01	10.55
Building Vendor Trips	0.02	0.27	0.20	0.00	0.00	0.01	0.01	0.00	0.01	0.01	53.74
Building Worker Trips	0.01	0.02	0.26	0.00	0.00	0.00	0.00	0.00	0.00	0.00	32.18
Building 02/07/2011-05/13/2011	0.18	1.50	1.62	0.00	0.01	0.07	0.08	0.00	0.06	0.06	337.49
Building Off Road Diesel	0.09	0.70	0.33	0.00	0.00	0.03	0.03	0.00	0.03	0.03	96.93
Building Vendor Trips	0.06	0.76	0.55	0.00	0.01	0.03	0.04	0.00	0.03	0.03	150.47
Building Worker Trips	0.02	0.04	0.74	0.00	0.00	0.00	0.01	0.00	0.00	0.00	90.10
Building 05/16/2011-07/08/2011	0.06	0.54	0.76	0.00	0.01	0.02	0.03	0.00	0.02	0.02	148.45
Building Off Road Diesel	0.01	0.08	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00	10.98
Building Vendor Trips	0.04	0.43	0.31	0.00	0.00	0.02	0.02	0.00	0.02	0.02	85.98

Phase Assumptions

Phase: Paving 7/16/2012 - 9/21/2012 - Asphaltting

Acres to be Paved: 2.84

Off-Road Equipment:

- 1 Off Highway Tractors (267 hp) operating at a 0.65 load factor for 3 hours per day
- 1 Off Highway Trucks (479 hp) operating at a 0.57 load factor for 3 hours per day
- 1 Other Equipment (190 hp) operating at a 0.62 load factor for 4 hours per day
- 1 Pavers (100 hp) operating at a 0.62 load factor for 4 hours per day
- 1 Paving Equipment (104 hp) operating at a 0.53 load factor for 3 hours per day
- 2 Rollers (95 hp) operating at a 0.56 load factor for 4 hours per day

Phase: Building Construction 1/23/2012 - 3/23/2012 - Maintenance Crew Equipment Check

Off-Road Equipment:

- 2 Other Equipment (190 hp) operating at a 0.62 load factor for 4 hours per day

Phase: Building Construction 1/1/2011 - 2/4/2011 - Fencing

Off-Road Equipment:

- 1 Other Equipment (190 hp) operating at a 0.62 load factor for 2 hours per day
- 1 Other Material Handling Equipment (191 hp) operating at a 0.59 load factor for 4 hours per day
- 1 Tractors/Loaders/Backhoes (108 hp) operating at a 0.55 load factor for 8 hours per day

Phase: Building Construction 2/7/2011 - 5/13/2011 - Civil

Off-Road Equipment:

- 1 Bore/Drill Rigs (291 hp) operating at a 0.75 load factor for 5 hours per day
- 1 Cranes (399 hp) operating at a 0.43 load factor for 1 hours per day
- 1 Excavators (168 hp) operating at a 0.57 load factor for 4 hours per day
- 2 Off Highway Trucks (479 hp) operating at a 0.57 load factor for 2 hours per day
- 3 Skid Steer Loaders (44 hp) operating at a 0.55 load factor for 3 hours per day
- 2 Tractors/Loaders/Backhoes (108 hp) operating at a 0.55 load factor for 3 hours per day
- 1 Water Trucks (189 hp) operating at a 0.5 load factor for 3 hours per day

Phase: Building Construction 5/16/2011 - 7/8/2011 - MEER

Off-Road Equipment:

- 2 Other Equipment (190 hp) operating at a 0.62 load factor for 3 hours per day

5/11/2010 01:40:15 PM

Phase: Building Construction 7/11/2011 - 11/11/2011 - Electrical

Off-Road Equipment:

- 1 Cranes (399 hp) operating at a 0.43 load factor for 3 hours per day
- 1 Other Equipment (190 hp) operating at a 0.62 load factor for 3 hours per day

Phase: Building Construction 11/14/2011 - 1/20/2012 - Wiring

Off-Road Equipment:

- 2 Other Equipment (190 hp) operating at a 0.62 load factor for 4 hours per day

Phase: Building Construction 3/26/2012 - 7/13/2012 - Testing

Off-Road Equipment:

- 1 Other Equipment (190 hp) operating at a 0.62 load factor for 3 hours per day

Urbemis 2007 Version 9.2.4

Combined Annual Emissions Reports (Tons/Year)

File Name:

Project Name: Transmission Lines

Project Location: San Bernadino County

On-Road Vehicle Emissions Based on: Version : Emfac2007 V2.3 Nov 1 2006

Off-Road Vehicle Emissions Based on: OFFROAD2007

Summary Report:

CONSTRUCTION EMISSION ESTIMATES

	<u>ROG</u>	<u>NOx</u>	<u>CO</u>	<u>SO2</u>	<u>PM10 Dust</u>	<u>PM10 Exhaust</u>	<u>PM10</u>	<u>PM2.5 Dust</u>	<u>PM2.5 Exhaust</u>	<u>PM2.5</u>	<u>CO2</u>
2011 TOTALS (tons/year unmitigated)	0.36	3.41	2.49	0.00	2.99	0.13	3.12	0.63	0.12	0.74	612.00

Construction Unmitigated Detail Report:

CONSTRUCTION EMISSION ESTIMATES Annual Tons Per Year, Unmitigated

	<u>ROG</u>	<u>NOx</u>	<u>CO</u>	<u>SO2</u>	<u>PM10 Dust</u>	<u>PM10 Exhaust</u>	<u>PM10</u>	<u>PM2.5 Dust</u>	<u>PM2.5 Exhaust</u>	<u>PM2.5</u>	<u>CO2</u>
2011	0.36	3.41	2.49	0.00	2.99	0.13	3.12	0.63	0.12	0.74	612.00
Fine Grading 01/03/2011-01/06/2011	0.01	0.08	0.04	0.00	0.15	0.00	0.15	0.03	0.00	0.03	10.18
Fine Grading Dust	0.00	0.00	0.00	0.00	0.15	0.00	0.15	0.03	0.00	0.03	0.00
Fine Grading Off Road Diesel	0.01	0.08	0.03	0.00	0.00	0.00	0.00	0.00	0.00	0.00	9.69
Fine Grading On Road Diesel	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Fine Grading Worker Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.50
Mass Grading 01/03/2011-03/21/2011	0.03	0.26	0.12	0.00	2.03	0.01	2.04	0.42	0.01	0.43	37.46
Mass Grading Dust	0.00	0.00	0.00	0.00	2.03	0.00	2.03	0.42	0.00	0.42	0.00
Mass Grading Off Road Diesel	0.03	0.26	0.08	0.00	0.00	0.01	0.01	0.00	0.01	0.01	33.13
Mass Grading On Road Diesel	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Mass Grading Worker Trips	0.00	0.00	0.04	0.00	0.00	0.00	0.00	0.00	0.00	0.00	4.33
Trenching 01/07/2011-01/19/2011	0.02	0.23	0.08	0.00	0.00	0.01	0.01	0.00	0.01	0.01	29.85
Trenching Off Road Diesel	0.02	0.23	0.07	0.00	0.00	0.01	0.01	0.00	0.01	0.01	28.87

5/11/2010 04:05:43 PM

Trenching Worker Trips	0.00	0.00	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.98
Building 01/20/2011-01/25/2011	0.01	0.08	0.10	0.00	0.00	0.00	0.00	0.00	0.00	0.00	20.37
Building Off Road Diesel	0.00	0.03	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00	3.71
Building Vendor Trips	0.00	0.05	0.04	0.00	0.00	0.00	0.00	0.00	0.00	0.00	10.42
Building Worker Trips	0.00	0.00	0.05	0.00	0.00	0.00	0.00	0.00	0.00	0.00	6.24
Building 01/26/2011-02/18/2011	0.07	0.64	0.53	0.00	0.00	0.02	0.03	0.00	0.02	0.02	122.12
Building Off Road Diesel	0.04	0.39	0.13	0.00	0.00	0.01	0.01	0.00	0.01	0.01	47.13
Building Vendor Trips	0.02	0.24	0.17	0.00	0.00	0.01	0.01	0.00	0.01	0.01	46.90
Building Worker Trips	0.01	0.01	0.23	0.00	0.00	0.00	0.00	0.00	0.00	0.00	28.08
Building 02/21/2011-03/08/2011	0.04	0.33	0.33	0.00	0.00	0.01	0.02	0.00	0.01	0.01	70.31
Building Off Road Diesel	0.02	0.16	0.06	0.00	0.00	0.01	0.01	0.00	0.01	0.01	20.32
Building Vendor Trips	0.01	0.16	0.11	0.00	0.00	0.01	0.01	0.00	0.01	0.01	31.27
Building Worker Trips	0.00	0.01	0.15	0.00	0.00	0.00	0.00	0.00	0.00	0.00	18.72
Building 03/09/2011-03/16/2011	0.04	0.37	0.23	0.00	0.00	0.01	0.01	0.00	0.01	0.01	64.67
Building Off Road Diesel	0.03	0.29	0.10	0.00	0.00	0.01	0.01	0.00	0.01	0.01	39.67
Building Vendor Trips	0.01	0.08	0.06	0.00	0.00	0.00	0.00	0.00	0.00	0.00	15.63
Building Worker Trips	0.00	0.00	0.08	0.00	0.00	0.00	0.00	0.00	0.00	0.00	9.36
Fine Grading 03/17/2011-03/21/2011	0.01	0.05	0.02	0.00	0.11	0.00	0.11	0.02	0.00	0.02	6.30
Fine Grading Dust	0.00	0.00	0.00	0.00	0.11	0.00	0.11	0.02	0.00	0.02	0.00
Fine Grading Off Road Diesel	0.01	0.05	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00	5.97
Fine Grading On Road Diesel	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Fine Grading Worker Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.33
Building 03/22/2011-03/23/2011	0.01	0.14	0.08	0.00	0.00	0.00	0.01	0.00	0.00	0.00	20.36
Building Off Road Diesel	0.01	0.11	0.04	0.00	0.00	0.00	0.00	0.00	0.00	0.00	12.03
Building Vendor Trips	0.00	0.03	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00	5.21
Building Worker Trips	0.00	0.00	0.03	0.00	0.00	0.00	0.00	0.00	0.00	0.00	3.12
Mass Grading 03/22/2011-04/11/2011	0.01	0.12	0.05	0.00	0.54	0.00	0.55	0.11	0.00	0.12	16.32
Mass Grading Dust	0.00	0.00	0.00	0.00	0.54	0.00	0.54	0.11	0.00	0.11	0.00

5/11/2010 04:05:43 PM

Mass Grading Off Road Diesel	0.01	0.12	0.04	0.00	0.00	0.00	0.00	0.00	0.00	0.00	15.16
Mass Grading On Road Diesel	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Mass Grading Worker Trips	0.00	0.00	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00	1.16
Fine Grading 03/24/2011-03/25/2011	0.00	0.03	0.02	0.00	0.07	0.00	0.07	0.02	0.00	0.02	4.04
Fine Grading Dust	0.00	0.00	0.00	0.00	0.07	0.00	0.07	0.02	0.00	0.02	0.00
Fine Grading Off Road Diesel	0.00	0.03	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00	3.79
Fine Grading On Road Diesel	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Fine Grading Worker Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.25
Demolition 03/28/2011-03/29/2011	0.00	0.03	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00	4.08
Fugitive Dust	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Demo Off Road Diesel	0.00	0.03	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00	3.76
Demo On Road Diesel	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.13
Demo Worker Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.19
Demolition 03/30/2011-04/01/2011	0.01	0.05	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00	6.03
Fugitive Dust	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Demo Off Road Diesel	0.00	0.04	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00	5.55
Demo On Road Diesel	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.20
Demo Worker Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.28
Building 04/04/2011-04/04/2011	0.00	0.02	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00	5.15
Building Off Road Diesel	0.00	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.98
Building Vendor Trips	0.00	0.01	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00	2.61
Building Worker Trips	0.00	0.00	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00	1.56
Building 04/05/2011-04/07/2011	0.02	0.19	0.12	0.00	0.00	0.01	0.01	0.00	0.01	0.01	32.69
Building Off Road Diesel	0.01	0.15	0.05	0.00	0.00	0.01	0.01	0.00	0.00	0.00	20.19
Building Vendor Trips	0.00	0.04	0.03	0.00	0.00	0.00	0.00	0.00	0.00	0.00	7.82
Building Worker Trips	0.00	0.00	0.04	0.00	0.00	0.00	0.00	0.00	0.00	0.00	4.68
Fine Grading 04/08/2011-04/11/2011	0.00	0.03	0.02	0.00	0.07	0.00	0.07	0.02	0.00	0.02	4.20
Fine Grading Dust	0.00	0.00	0.00	0.00	0.07	0.00	0.07	0.02	0.00	0.02	0.00

5/11/2010 04:05:43 PM

Fine Grading Off Road Diesel	0.00	0.03	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00	3.98
Fine Grading On Road Diesel	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Fine Grading Worker Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.22
Trenching 04/12/2011-04/15/2011	0.00	0.02	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00	3.56
Trenching Off Road Diesel	0.00	0.02	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00	3.37
Trenching Worker Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.19
Building 04/18/2011-05/13/2011	0.06	0.59	0.55	0.00	0.00	0.02	0.03	0.00	0.02	0.02	123.28
Building Off Road Diesel	0.03	0.31	0.10	0.00	0.00	0.01	0.01	0.00	0.01	0.01	39.97
Building Vendor Trips	0.02	0.26	0.19	0.00	0.00	0.01	0.01	0.00	0.01	0.01	52.11
Building Worker Trips	0.01	0.01	0.26	0.00	0.00	0.00	0.00	0.00	0.00	0.00	31.20
Building 05/16/2011-05/23/2011	0.01	0.13	0.15	0.00	0.00	0.01	0.01	0.00	0.00	0.01	31.04
Building Off Road Diesel	0.01	0.05	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00	6.05
Building Vendor Trips	0.01	0.08	0.06	0.00	0.00	0.00	0.00	0.00	0.00	0.00	15.63
Building Worker Trips	0.00	0.00	0.08	0.00	0.00	0.00	0.00	0.00	0.00	0.00	9.36

Phase Assumptions

Phase: Demolition 3/28/2011 - 3/29/2011 - LST Removal

Building Volume Total (cubic feet): 22500

Building Volume Daily (cubic feet): 2250

On Road Truck Travel (VMT): 31.25

Off-Road Equipment:

1 Cranes (350 hp) operating at a 0.43 load factor for 6 hours per day

4 Off Highway Trucks (300 hp) operating at a 0.57 load factor for 6 hours per day

1 Other Equipment (120 hp) operating at a 0.62 load factor for 6 hours per day

Phase: Demolition 3/30/2011 - 4/1/2011 - Remove Foundations

Building Volume Total (cubic feet): 22500

Building Volume Daily (cubic feet): 2250

On Road Truck Travel (VMT): 31.25

Off-Road Equipment:

2 Off Highway Trucks (350 hp) operating at a 0.57 load factor for 8 hours per day

5/11/2010 04:05:43 PM

- 2 Other Equipment (300 hp) operating at a 0.62 load factor for 2 hours per day
- 1 Other General Industrial Equipment (120 hp) operating at a 0.51 load factor for 6 hours per day
- 1 Tractors/Loaders/Backhoes (200 hp) operating at a 0.55 load factor for 8 hours per day

Phase: Fine Grading 1/3/2011 - 1/6/2011 - Roads and Landing Work

Total Acres Disturbed: 14.51

Maximum Daily Acreage Disturbed: 3.63

Fugitive Dust Level of Detail: Default

20 lbs per acre-day

On Road Truck Travel (VMT): 0

Off-Road Equipment:

- 1 Graders (350 hp) operating at a 0.61 load factor for 4 hours per day
- 1 Off Highway Trucks (350 hp) operating at a 0.57 load factor for 8 hours per day
- 2 Other Equipment (300 hp) operating at a 0.62 load factor for 2 hours per day
- 1 Other General Industrial Equipment (500 hp) operating at a 0.51 load factor for 2 hours per day
- 1 Other Material Handling Equipment (250 hp) operating at a 0.59 load factor for 4 hours per day
- 1 Rubber Tired Dozers (350 hp) operating at a 0.59 load factor for 6 hours per day
- 1 Tractors/Loaders/Backhoes (350 hp) operating at a 0.55 load factor for 6 hours per day

Phase: Fine Grading 3/17/2011 - 3/21/2011 - Restoration

Total Acres Disturbed: 14.51

Maximum Daily Acreage Disturbed: 3.63

Fugitive Dust Level of Detail: Default

20 lbs per acre-day

On Road Truck Travel (VMT): 0

Off-Road Equipment:

- 1 Graders (350 hp) operating at a 0.61 load factor for 6 hours per day
- 1 Off Highway Trucks (300 hp) operating at a 0.57 load factor for 3 hours per day
- 2 Other Equipment (300 hp) operating at a 0.62 load factor for 2 hours per day
- 1 Plate Compactors (250 hp) operating at a 0.43 load factor for 6 hours per day
- 1 Rubber Tired Dozers (350 hp) operating at a 0.59 load factor for 6 hours per day
- 1 Tractors/Loaders/Backhoes (350 hp) operating at a 0.55 load factor for 6 hours per day

Phase: Fine Grading 3/24/2011 - 3/25/2011 - Gen-Tie Roads & Landing Work

Total Acres Disturbed: 14.51

5/11/2010 04:05:43 PM

Maximum Daily Acreage Disturbed: 3.63

Fugitive Dust Level of Detail: Default

20 lbs per acre-day

On Road Truck Travel (VMT): 0

Off-Road Equipment:

1 Excavators (300 hp) operating at a 0.57 load factor for 6 hours per day

1 Graders (350 hp) operating at a 0.61 load factor for 4 hours per day

1 Off Highway Trucks (500 hp) operating at a 0.57 load factor for 2 hours per day

2 Other Equipment (30 hp) operating at a 0.62 load factor for 2 hours per day

1 Plate Compactors (250 hp) operating at a 0.43 load factor for 4 hours per day

1 Rubber Tired Dozers (350 hp) operating at a 0.59 load factor for 6 hours per day

1 Tractors/Loaders/Backhoes (350 hp) operating at a 0.55 load factor for 6 hours per day

Phase: Fine Grading 4/8/2011 - 4/11/2011 - Gen-Tie Restoration

Total Acres Disturbed: 14.51

Maximum Daily Acreage Disturbed: 3.63

Fugitive Dust Level of Detail: Default

20 lbs per acre-day

On Road Truck Travel (VMT): 0

Off-Road Equipment:

1 Graders (350 hp) operating at a 0.61 load factor for 6 hours per day

1 Off Highway Trucks (300 hp) operating at a 0.57 load factor for 3 hours per day

2 Other Equipment (300 hp) operating at a 0.62 load factor for 2 hours per day

1 Plate Compactors (250 hp) operating at a 0.43 load factor for 6 hours per day

1 Rubber Tired Dozers (350 hp) operating at a 0.59 load factor for 6 hours per day

1 Tractors/Loaders/Backhoes (350 hp) operating at a 0.55 load factor for 6 hours per day

Phase: Mass Grading 1/3/2011 - 3/21/2011 - Temporary Equipment and Material Staging Area

Total Acres Disturbed: 14.51

Maximum Daily Acreage Disturbed: 3.63

Fugitive Dust Level of Detail: Default

20 lbs per acre-day

On Road Truck Travel (VMT): 0

Off-Road Equipment:

1 Cranes (300 hp) operating at a 0.43 load factor for 2 hours per day

Page: 1

5/11/2010 04:05:43 PM

- 1 Forklifts (200 hp) operating at a 0.3 load factor for 5 hours per day
- 1 Off Highway Trucks (350 hp) operating at a 0.57 load factor for 1 hours per day
- 1 Other Equipment (300 hp) operating at a 0.62 load factor for 2 hours per day
- 1 Water Trucks (350 hp) operating at a 0.5 load factor for 4 hours per day

Phase: Mass Grading 3/22/2011 - 4/11/2011 - Gen-Tie Temporary Equipment & Material Staging

Total Acres Disturbed: 14.51

Maximum Daily Acreage Disturbed: 3.63

Fugitive Dust Level of Detail: Default

20 lbs per acre-day

On Road Truck Travel (VMT): 0

Off-Road Equipment:

- 1 Cranes (300 hp) operating at a 0.43 load factor for 2 hours per day
- 1 Off Highway Trucks (350 hp) operating at a 0.57 load factor for 1 hours per day
- 1 Other Equipment (300 hp) operating at a 0.62 load factor for 2 hours per day
- 1 Rough Terrain Forklifts (200 hp) operating at a 0.6 load factor for 5 hours per day
- 1 Water Trucks (350 hp) operating at a 0.5 load factor for 8 hours per day

Phase: Trenching 1/7/2011 - 1/19/2011 - Install LST Foundations

Off-Road Equipment:

- 1 Cranes (300 hp) operating at a 0.43 load factor for 5 hours per day
- 3 Off Highway Trucks (500 hp) operating at a 0.57 load factor for 8 hours per day
- 2 Other Equipment (300 hp) operating at a 0.62 load factor for 2 hours per day
- 1 Tractors/Loaders/Backhoes (200 hp) operating at a 0.55 load factor for 8 hours per day

Phase: Trenching 4/12/2011 - 4/15/2011 - Trenching, Structure Excavation

Off-Road Equipment:

- 1 Off Highway Trucks (300 hp) operating at a 0.57 load factor for 4 hours per day
- 1 Other Equipment (300 hp) operating at a 0.62 load factor for 2 hours per day
- 1 Tractors/Loaders/Backhoes (300 hp) operating at a 0.55 load factor for 8 hours per day

Phase: Building Construction 2/21/2011 - 3/8/2011 - LST Erection

Off-Road Equipment:

- 1 Cranes (350 hp) operating at a 0.43 load factor for 6 hours per day
- 2 Off Highway Trucks (300 hp) operating at a 0.57 load factor for 5 hours per day

5/11/2010 04:05:43 PM

- 2 Other Equipment (300 hp) operating at a 0.62 load factor for 5 hours per day
- 1 Other General Industrial Equipment (120 hp) operating at a 0.51 load factor for 6 hours per day

Phase: Building Construction 1/20/2011 - 1/25/2011 - LST Steel Haul

Off-Road Equipment:

- 1 Forklifts (200 hp) operating at a 0.3 load factor for 6 hours per day
- 1 Off Highway Trucks (350 hp) operating at a 0.57 load factor for 8 hours per day
- 2 Other Equipment (300 hp) operating at a 0.62 load factor for 2 hours per day

Phase: Building Construction 1/26/2011 - 2/18/2011 - LST Steel Assembly

Off-Road Equipment:

- 2 Cranes (300 hp) operating at a 0.43 load factor for 8 hours per day
- 1 Forklifts (200 hp) operating at a 0.3 load factor for 6 hours per day
- 3 Off Highway Trucks (300 hp) operating at a 0.57 load factor for 4 hours per day
- 2 Other Equipment (300 hp) operating at a 0.62 load factor for 4 hours per day
- 2 Other General Industrial Equipment (350 hp) operating at a 0.51 load factor for 6 hours per day

Phase: Building Construction 3/9/2011 - 3/16/2011 - Install Conductor & OHGW

Off-Road Equipment:

- 3 Bore/Drill Rigs (350 hp) operating at a 0.75 load factor for 2 hours per day
- 1 Concrete/Industrial Saws (10 hp) operating at a 0.73 load factor for 8 hours per day
- 2 Cranes (350 hp) operating at a 0.43 load factor for 8 hours per day
- 1 Forklifts (350 hp) operating at a 0.3 load factor for 2 hours per day
- 3 Off Highway Trucks (350 hp) operating at a 0.57 load factor for 2 hours per day
- 7 Other Equipment (300 hp) operating at a 0.62 load factor for 8 hours per day
- 1 Other General Industrial Equipment (525 hp) operating at a 0.51 load factor for 3 hours per day
- 1 Other Material Handling Equipment (500 hp) operating at a 0.59 load factor for 2 hours per day
- 1 Rubber Tired Loaders (300 hp) operating at a 0.54 load factor for 3 hours per day
- 1 Tractors/Loaders/Backhoes (120 hp) operating at a 0.55 load factor for 2 hours per day

Phase: Building Construction 3/22/2011 - 3/23/2011 - Gen-Tie Install Conductor & GW

Off-Road Equipment:

- 3 Cranes (350 hp) operating at a 0.43 load factor for 8 hours per day
- 3 Off Highway Trucks (350 hp) operating at a 0.57 load factor for 2 hours per day
- 3 Other Equipment (300 hp) operating at a 0.62 load factor for 8 hours per day

5/11/2010 04:05:43 PM

- 5 Other General Industrial Equipment (350 hp) operating at a 0.51 load factor for 6 hours per day
- 1 Other Material Handling Equipment (525 hp) operating at a 0.59 load factor for 6 hours per day
- 2 Rubber Tired Dozers (500 hp) operating at a 0.59 load factor for 2 hours per day
- 1 Tractors/Loaders/Backhoes (120 hp) operating at a 0.55 load factor for 2 hours per day

Phase: Building Construction 4/4/2011 - 4/4/2011 - Gen-Tie LST Steel Haul

Off-Road Equipment:

- 1 Off Highway Trucks (350 hp) operating at a 0.57 load factor for 8 hours per day
- 1 Other Equipment (300 hp) operating at a 0.62 load factor for 2 hours per day
- 1 Rough Terrain Forklifts (200 hp) operating at a 0.6 load factor for 6 hours per day

Phase: Building Construction 4/5/2011 - 4/7/2011 - Gen-Tie Transfer Conductor

Off-Road Equipment:

- 3 Bore/Drill Rigs (350 hp) operating at a 0.75 load factor for 2 hours per day
- 1 Concrete/Industrial Saws (10 hp) operating at a 0.73 load factor for 8 hours per day
- 2 Cranes (350 hp) operating at a 0.43 load factor for 8 hours per day
- 3 Off Highway Trucks (350 hp) operating at a 0.57 load factor for 2 hours per day
- 7 Other Equipment (300 hp) operating at a 0.62 load factor for 8 hours per day
- 1 Other General Industrial Equipment (525 hp) operating at a 0.51 load factor for 3 hours per day
- 1 Other Material Handling Equipment (500 hp) operating at a 0.59 load factor for 2 hours per day
- 1 Rough Terrain Forklifts (350 hp) operating at a 0.6 load factor for 2 hours per day
- 1 Rubber Tired Loaders (300 hp) operating at a 0.54 load factor for 3 hours per day
- 1 Tractors/Loaders/Backhoes (120 hp) operating at a 0.55 load factor for 2 hours per day

Phase: Building Construction 4/18/2011 - 5/13/2011 - Overhead Line Work

Off-Road Equipment:

- 3 Off Highway Trucks (350 hp) operating at a 0.57 load factor for 8 hours per day
- 2 Other Equipment (300 hp) operating at a 0.62 load factor for 2 hours per day

Phase: Building Construction 5/16/2011 - 5/23/2011 - Underground Cable Pulling and Makeup

Off-Road Equipment:

- 1 Off Highway Trucks (350 hp) operating at a 0.57 load factor for 8 hours per day
- 1 Other Equipment (300 hp) operating at a 0.62 load factor for 2 hours per day
- 1 Other General Industrial Equipment (300 hp) operating at a 0.51 load factor for 6 hours per day

Urbemis 2007 Version 9.2.4

Combined Annual Emissions Reports (Tons/Year)

File Name:

Project Name: Telecommunication System

Project Location: San Bernadino County

On-Road Vehicle Emissions Based on: Version : Emfac2007 V2.3 Nov 1 2006

Off-Road Vehicle Emissions Based on: OFFROAD2007

Summary Report:

CONSTRUCTION EMISSION ESTIMATES

	<u>ROG</u>	<u>NOx</u>	<u>CO</u>	<u>SO2</u>	<u>PM10 Dust</u>	<u>PM10 Exhaust</u>	<u>PM10</u>	<u>PM2.5 Dust</u>	<u>PM2.5 Exhaust</u>	<u>PM2.5</u>	<u>CO2</u>
2011 TOTALS (tons/year unmitigated)	0.33	3.09	1.84	0.00	5.53	0.11	5.64	1.16	0.10	1.26	488.88

Construction Unmitigated Detail Report:

CONSTRUCTION EMISSION ESTIMATES Annual Tons Per Year, Unmitigated

	<u>ROG</u>	<u>NOx</u>	<u>CO</u>	<u>SO2</u>	<u>PM10 Dust</u>	<u>PM10 Exhaust</u>	<u>PM10</u>	<u>PM2.5 Dust</u>	<u>PM2.5 Exhaust</u>	<u>PM2.5</u>	<u>CO2</u>
2011	0.33	3.09	1.84	0.00	5.53	0.11	5.64	1.16	0.10	1.26	488.88
Building 01/10/2011-02/01/2011	0.05	0.51	0.45	0.00	0.00	0.02	0.02	0.00	0.02	0.02	95.94
Building Off Road Diesel	0.03	0.31	0.13	0.00	0.00	0.01	0.01	0.00	0.01	0.01	36.67
Building Vendor Trips	0.02	0.19	0.14	0.00	0.00	0.01	0.01	0.00	0.01	0.01	37.07
Building Worker Trips	0.01	0.01	0.18	0.00	0.00	0.00	0.00	0.00	0.00	0.00	22.20
Mass Grading 01/10/2011-05/23/2011	0.08	0.79	0.31	0.00	2.77	0.03	2.79	0.58	0.03	0.60	104.45
Mass Grading Dust	0.00	0.00	0.00	0.00	2.76	0.00	2.76	0.58	0.00	0.58	0.00
Mass Grading Off Road Diesel	0.08	0.78	0.25	0.00	0.00	0.03	0.03	0.00	0.02	0.02	97.02
Mass Grading On Road Diesel	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Mass Grading Worker Trips	0.00	0.00	0.06	0.00	0.00	0.00	0.00	0.00	0.00	0.00	7.43
Building 02/02/2011-03/04/2011	0.05	0.45	0.49	0.00	0.00	0.02	0.02	0.00	0.02	0.02	104.20
Building Off Road Diesel	0.02	0.18	0.06	0.00	0.00	0.01	0.01	0.00	0.01	0.01	24.01
Building Vendor Trips	0.02	0.25	0.18	0.00	0.00	0.01	0.01	0.00	0.01	0.01	50.16

5/11/2010 04:58:50 PM

Building Worker Trips	0.01	0.01	0.25	0.00	0.00	0.00	0.00	0.00	0.00	0.00	30.03
Trenching 03/07/2011-03/16/2011	0.01	0.10	0.04	0.00	0.00	0.00	0.00	0.00	0.00	0.00	13.03
Trenching Off Road Diesel	0.01	0.10	0.03	0.00	0.00	0.00	0.00	0.00	0.00	0.00	12.41
Trenching Worker Trips	0.00	0.00	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.62
Building 03/17/2011-03/21/2011	0.01	0.09	0.07	0.00	0.00	0.00	0.00	0.00	0.00	0.00	17.25
Building Off Road Diesel	0.00	0.05	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00	6.79
Building Vendor Trips	0.00	0.03	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00	6.54
Building Worker Trips	0.00	0.00	0.03	0.00	0.00	0.00	0.00	0.00	0.00	0.00	3.92
Fine Grading 03/22/2011-04/05/2011	0.04	0.46	0.16	0.00	1.78	0.02	1.80	0.37	0.01	0.39	65.10
Fine Grading Dust	0.00	0.00	0.00	0.00	1.78	0.00	1.78	0.37	0.00	0.37	0.00
Fine Grading Off Road Diesel	0.04	0.46	0.15	0.00	0.00	0.02	0.02	0.00	0.01	0.01	63.40
Fine Grading On Road Diesel	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Fine Grading Worker Trips	0.00	0.00	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00	1.70
Fine Grading 04/06/2011-05/23/2011	0.08	0.71	0.33	0.00	0.98	0.03	1.01	0.20	0.02	0.23	88.91
Fine Grading Dust	0.00	0.00	0.00	0.00	0.98	0.00	0.98	0.20	0.00	0.20	0.00
Fine Grading Off Road Diesel	0.08	0.71	0.30	0.00	0.00	0.03	0.03	0.00	0.02	0.02	84.70
Fine Grading On Road Diesel	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Fine Grading Worker Trips	0.00	0.00	0.03	0.00	0.00	0.00	0.00	0.00	0.00	0.00	4.21

Phase Assumptions

Phase: Fine Grading 3/22/2011 - 4/5/2011 - Install Fiber Optic Cable

Total Acres Disturbed: 11.53

Maximum Daily Acreage Disturbed: 2.88

Fugitive Dust Level of Detail: Low

Onsite Cut/Fill: 2500 cubic yards/day; Offsite Cut/Fill: 0 cubic yards/day

On Road Truck Travel (VMT): 0

Off-Road Equipment:

2 Off Highway Trucks (350 hp) operating at a 0.57 load factor for 8 hours per day

8 Other Equipment (300 hp) operating at a 0.62 load factor for 8 hours per day

5/11/2010 04:58:50 PM

Phase: Fine Grading 4/6/2011 - 5/23/2011 - Restoration

Total Acres Disturbed: 11.53

Maximum Daily Acreage Disturbed: 2.88

Fugitive Dust Level of Detail: Default

20 lbs per acre-day

On Road Truck Travel (VMT): 0

Off-Road Equipment:

- 1 Graders (350 hp) operating at a 0.61 load factor for 6 hours per day
- 1 Off Highway Trucks (300 hp) operating at a 0.57 load factor for 3 hours per day
- 2 Other Equipment (300 hp) operating at a 0.62 load factor for 2 hours per day
- 1 Plate Compactors (250 hp) operating at a 0.43 load factor for 6 hours per day
- 1 Rubber Tired Dozers (350 hp) operating at a 0.59 load factor for 6 hours per day
- 1 Tractors/Loaders/Backhoes (350 hp) operating at a 0.55 load factor for 6 hours per day
- 1 Water Trucks (350 hp) operating at a 0.5 load factor for 8 hours per day

Phase: Mass Grading 1/10/2011 - 5/23/2011 - Marshalling Yard

Total Acres Disturbed: 11.53

Maximum Daily Acreage Disturbed: 2.88

Fugitive Dust Level of Detail: Default

20 lbs per acre-day

On Road Truck Travel (VMT): 0

Off-Road Equipment:

- 1 Cranes (300 hp) operating at a 0.43 load factor for 2 hours per day
- 1 Off Highway Trucks (350 hp) operating at a 0.57 load factor for 1 hours per day
- 1 Other Equipment (300 hp) operating at a 0.62 load factor for 2 hours per day
- 1 Rough Terrain Forklifts (200 hp) operating at a 0.6 load factor for 5 hours per day
- 1 Water Trucks (350 hp) operating at a 0.5 load factor for 8 hours per day

Phase: Trenching 3/7/2011 - 3/16/2011 - Install LWS Poles

Off-Road Equipment:

- 1 Off Highway Trucks (500 hp) operating at a 0.57 load factor for 8 hours per day
- 3 Other Equipment (300 hp) operating at a 0.62 load factor for 2 hours per day
- 1 Tractors/Loaders/Backhoes (200 hp) operating at a 0.55 load factor for 8 hours per day

Phase: Building Construction 1/10/2011 - 2/1/2011 - Roads

5/11/2010 04:58:50 PM

Off-Road Equipment:

- 1 Excavators (300 hp) operating at a 0.57 load factor for 6 hours per day
- 1 Graders (350 hp) operating at a 0.61 load factor for 4 hours per day
- 1 Off Highway Trucks (500 hp) operating at a 0.57 load factor for 2 hours per day
- 2 Other Equipment (300 hp) operating at a 0.62 load factor for 2 hours per day
- 1 Plate Compactors (250 hp) operating at a 0.43 load factor for 4 hours per day
- 1 Rubber Tired Dozers (350 hp) operating at a 0.59 load factor for 6 hours per day
- 1 Tractors/Loaders/Backhoes (350 hp) operating at a 0.55 load factor for 6 hours per day

Phase: Building Construction 2/2/2011 - 3/4/2011 - Install 5 foot Crossarm

Off-Road Equipment:

- 2 Off Highway Trucks (300 hp) operating at a 0.57 load factor for 5 hours per day
- 3 Other Equipment (300 hp) operating at a 0.62 load factor for 2 hours per day

Phase: Building Construction 3/17/2011 - 3/21/2011 - Steel Pole Haul

Off-Road Equipment:

- 3 Off Highway Trucks (300 hp) operating at a 0.57 load factor for 5 hours per day
- 2 Other Equipment (350 hp) operating at a 0.62 load factor for 8 hours per day

gigawatt-hours (GWh). Ancillary services²³ include regulation, spinning reserve, non-spinning reserve, voltage support, and black start capability. Individual generation resources can be built and operated to provide only one specific service. Alternatively, a resource may be able to provide one or all of these services, depending on its design and constantly changing system needs and operations.

California is actively pursuing policies to reduce GHG emissions that include adding non-GHG emitting renewable generation resources to the system mix. The generation of electricity using fossil fuels, even in a back-up generator at a thermal solar plant, produces air emissions known as greenhouse gases in addition to the criteria air pollutants that have been traditionally regulated under the federal and state Clean Air Acts. Greenhouse gas emissions contribute to the warming of the earth's atmosphere, leading to climate change.

PROJECT CONSTRUCTION

Construction of industrial facilities such as power plants requires coordination of numerous equipment and personnel. The concentrated on-site activities result in short-term, unavoidable increases in vehicle and equipment emissions that include greenhouse gases. The construction would last approximately 26 months. The greenhouse gas emissions estimate, for the entire construction period, provided by the applicant²⁴ is below in **Greenhouse Gas Table 2**.

Greenhouse Gas Table 2
Estimated AMS Potential Construction Greenhouse Gas Emissions

	CO ₂ -Equivalent (MTCO ₂ E) ^{a,b}
Onsite Equipment (all four phases)	29,661
Delivery Vehicles	2,984
Construction Worker Vehicles	10,369
Entire Construction Period Total	43,015 ^c

Source: ESH 2010g.

^a One metric tonne (MT) equals 1.1 short tons or 2,204.6 pounds or 1,000 kilograms.

^b The vast majority of the CO₂E emissions, over 99%, is CO₂ from construction combustion sources.

^c Staff performed a separate construction emission estimate and determined considerably lower total construction period CO₂ emissions than estimated by the applicant, but has retained the more conservative applicant estimate. Staff's estimate shows higher on-road equipment emissions (delivery and worker vehicles emissions), but substantially lower off-road equipment emissions due to two main factors: 1) the applicant estimated emissions for a large number of onsite on-road equipment as if they were off-road equipment. The applicant did not appear to apply load factors to adjust the off-road equipment horsepower hour estimate down from 100 percent load.

²³ See page CEC 2009b, page 95.

²⁴ As noted in the Air Quality Section staff may be re-estimating certain construction emissions which would revise some of the values in **Greenhouse Gas Table 2**. If so, staff will provide a revised construction GHG emission estimate as part of a Staff Assessment Addendum.

PROJECT OPERATIONS

Operations GHG emissions are shown in **Greenhouse Gas Table 3**. Operation of the AMS would cause GHG emissions from the auxiliary boiler, fire pump engine, emergency generator engine, maintenance fleet and employee trips, and sulfur hexafluoride emissions from new electrical component equipment.

Greenhouse Gas Table 3
Estimated AMS Potential Operating Greenhouse Gas Emissions

	Annual CO ₂ -Equivalent (MTCO ₂ E) ^a
Auxiliary HTF Heaters ^b	10,018
Emergency Generator Engine ^b	183.2
Fire Pump Engine ^b	8.1
Maintenance Vehicles ^b	119.6
Delivery Vehicles ^b	31.3
Employee Vehicles ^b	512.7
Equipment Leakage (SF ₆)	10.5
Total Project GHG Emissions – MTCO₂E ^b	10,884
Facility MWh per year	600,000
Facility GHG Emission Rate (MTCO ₂ E/MWh)	0.018

Sources: ESH 2010g

^a One metric tonne (MT) equals 1.1 short tons or 2,204.6 pounds or 1,000 kilograms.

^b The vast majority of the CO₂E emissions, over 99%, is CO₂ from these emission sources.

Greenhouse Gas Table 3 shows what the proposed project, as permitted, could potentially emit in greenhouse gases on an annual basis. All emissions are converted to CO₂-equivalent and totaled. Electricity generation GHG emissions are generally dominated by CO₂ emissions from the carbon-based fuels; other sources of GHG are typically small and also are more likely to be easily controlled or reused/recycled. For this solar project the primary fuel, solar energy, is greenhouse gas free, but there is natural gas use in the two auxiliary HTF heaters used for morning startup and for freeze protection, and gasoline and diesel fuel use in the maintenance vehicles, offsite delivery vehicles, staff and employee vehicles, the two fire water pump engines, and the two emergency generator engines. Another GHG emission source for this proposed project is SF₆ from electrical equipment leakage.

The proposed project is estimated to emit, directly from primary and secondary emission sources on an annual basis, nearly 11,000 metric tonnes of CO₂-equivalent GHG emissions per year. AMS, as a renewable energy generation facility, is determined by rule to comply with the Greenhouse Gas Emission Performance Standard requirements of SB 1368 (Chapter 11, Greenhouse Gases Emission Performance Standard, Article 1, Section 2903 [b][1]). Regardless, AMS has an estimated GHG emission rate of 0.018 MTCO₂E/MWh, well below the Greenhouse Gas Emission Performance Standard of 0.500 MTCO₂/MWh.

Item 85:**Information Required:**

Please provide DPM emission factors from construction activities and a health risk assessment for diesel construction equipment emissions.

Response:

The Applicant originally requested additional time for this item but was able to obtain the necessary vendor information in time to respond with this filing.

The emissions factors for DPM from construction activities are clearly presented in Table C.5-5 of the AFC. Exhaust DPM data for the majority of the construction related equipment is presented on page 3 of the Construction Equipment Exhaust Emissions (titled 2010 Equipment Emissions Factors). In addition, DPM emissions factors are presented in Table C.5-5 of the AFC at the following sheet locations: (1) Truck Delivery and Site Support Vehicle Emissions, and (2) Worker Travel Emissions.

The construction screening HRA requested by CEC staff was performed using the following assumptions as follows:

- The three highest construction offsite MIR receptors were chosen based upon the construction modeling as revised per the data requests in the Air Quality section above.
- Cancer risk and chronic hazard indices were computed using the screening methodology as outlined in the South Coast AQMD (Health Risk Assessment Guidance for Analyzing Cancer Risks from Mobile Source Diesel Emissions, December 2002, and HRA guidance for Analyzing Cancer Risks from Mobile Source Diesel Idling Emissions for CEQA Air Quality Analysis, August 2003).
- A cancer inhalation unit risk value of $0.0003 \text{ (ug/m}^3\text{)}^{-1}$ was used.
- A cancer chronic inhalation REL of $5.0 \text{ (ug/m}^3\text{)}^{-1}$ was used.
- No acute inhalation REL exists for diesel PM.
- The adjustment factor applied to the final risk and hazard index values was based upon a construction work schedule of 10 hrs/day, 6 days/week, 50 weeks/year, for 26 months (2.167 yrs), i.e., lifetime exposure adjustment (LEA) factor value of 0.0106.

With respect to emissions from diesel fueled engines, use of the diesel PM exposure factors noted above are approved by CARB for the characterization of diesel engine exhaust and subsequent risk exposures. The diesel PM factor includes the range of fuel bound, and potentially emitted metals, PAHs, and a wide variety of other semi-volatile

substances. CARB notes the following in Appendix K of the current HARP Users Manual:

- The surrogate for whole diesel exhaust is diesel PM. PM10 is the basis for the potential risk calculations.
- When conducting an HRA, the potential cancer risk from inhalation exposure to diesel PM will outweigh the potential non-cancer health effects.
- When comparing whole diesel exhaust to speciated diesel exhaust, potential cancer risk from inhalation exposure to whole diesel exhaust will outweigh the multi-pathway cancer risk from the speciated compounds. For this reason, there will be few situations where an analysis of multi-pathway risk is necessary.

With respect to diesel particulate related risk values, the following should be noted:

- The US Department of Energy (DOE) as well as the US Environmental Protection Agency (EPA) have disagreed with the CARB/OEHHA and South Coast AQMD positions on the relative threat and relative contribution of diesel exhaust to “toxic” air pollution, and neither of the agencies, including the EPA’s prestigious Health Effects Institute identify diesel exhaust as a “known” carcinogen, since the scientific studies show only “weak” cancer links. EPA and DOE believe that the studies relied upon by CARB and SCAQMD are flawed in that they use a problematic elemental carbon surrogate for ambient diesel particulate matter and ignored a significant portion of PM2.5 captured at the SCAQMD’s own monitoring stations. In view of these conflicting studies, we suggest that caution be used in the decision making process regarding diesel PM and its associated risks, i.e., the actual risks may be much lower than those calculated by screening method herein. For these reasons, the risk table below reports the construction risk values using DPM only, and the inhalation pathway.

The following table presents the results of the screening level assessment of health risks from the construction phase.

Construction Screening HRA Summary					
MIR #	Annual, ug/m ³ (met year)	UTM E	UTM N	Cancer Risk	Chronic HI
Phase I					
1	0.48412 (2003)	470329.33	3875250.00	1.54 E-6	0.001
2	0.46946 (2004)	470329.33	3875250.00	1.49 E-6	0.001
3	0.46336 (2002)	470329.33	3875250.00	1.47 E-6	0.001
Phase II-IV					

1	0.72114 (2003)	470329.33	3875250.00	2.29 E-6	0.0015
2	0.69931 (2004)	470329.33	3875250.00	2.22 E-6	0.0015
3	0.69022 (2002)	470329.33	3875250.00	2.19 E-6	0.0015

Item 86:**Information Required:**

Please provide DPM emission factors for on-site solar field and equipment maintenance activities in pounds per day and tons per year. This value can be submitted as a single number estimate of total emissions from all vehicular sources used on-site.

Response:

Table C.1-7, provided in Appendix C.1 of the AFC, has been slightly revised and is attached (tables included with Data Request Item 6). This table indicates the DPM emissions and emissions factors used to estimate on-site facility operations and maintenance emissions. DPM emissions values presented in the original table, as well as the revised table, are given in terms of lbs/VMT, lbs/hp-hr, lbs/avg day, lbs/year, and tons/yr. DPM emissions in terms of lbs/day, although given, are not used in the HRA since an acute REL has not been established for DPM.

Item 87:

This item is linked to the items 84 and 85 and the Applicant has requested an extension of this item in connection to the letter "Abengoa Mojave Solar Project (09-AFC-5): Notice Pursuant to 20 CCR 1716(f): Data Request Set 1 (nos. 1-93)" dated November 11, 2009 and docketed regarding this item. The Applicant mistakenly omitted this item from the aforementioned letter.

Item 88:**Information Required:**

Please provide a cumulative PM2.5 emissions estimate on a daily and yearly basis when fugitive dust emissions are added to the DPM emissions from the above stationary and mobile sources, assuming that all DPM from diesel engines are PM2.5.

Response:

Please see Response to Item 29 above.

terms of lbs/VMT, lbs/hp-hr, lbs/avg day, lbs/year, and tons/yr. DPM emissions in terms of lbs/day, although given, are not used in the HRA since an acute REL has not been established for DPM.

Item 87 (Initial Response, per Extension Request):

Information Required:

Please conduct a health risk assessment for diesel emissions from vehicles involved in on-site solar field and equipment maintenance activities during plant operations.

Response:

Revised emissions values and operational scenarios for the facility were re-evaluated using HARP. The revised HRA values for the facility are as follows:

Boilers, Stationary Engines, Cooling Towers, HTF System, Mobile Ops Vehicles		
Risk Category	MIR Project Values	Applicable Significance Threshold
Cancer Risk	6.85 E-6	See Table 5.10-4 in Section 5.1 (Air Quality)
Chronic Hazard Index	0.00992	
Acute Hazard Index	0.0087	
Cancer Burden	0.0001 ¹	
MIR Receptor #: 302 , and location 473151mE, 3873400mN. Acute MIR, Receptor #130, HI=0.026, 469945mE, 3874500mN.		

* No acute REL has been established for diesel PM.

¹ The 10⁻⁶ MIR radius is located ~1815 ft. from the site center. The estimated population within this radius is less than 100 individuals, therefore the cancer burden is 0.0001

The input and output files applicable to the revised HRA are included on the CD which accompanies these responses.

Item 88 (Revised):

Information Required:

Please provide a cumulative PM_{2.5} emissions estimate on a daily and yearly basis when fugitive dust emissions are added to the DPM emissions from the above stationary and mobile sources, assuming that all DPM from diesel engines are PM_{2.5}.

Response:

Please see the emissions summary table in response to Item 29 above.

Table C.5-7 Offsite Equipment and Manpower Schedules
Offsite Construction Vehicles

VEHICLE TYPE	HP	Fuel Type	Load Factor (%)	USAGE DESCRIPTION
Off-Site Flat Bed Trucks (From Rail Facility)	200	gasoline		Material Hauling
Off-Site Asphalt Trucks	200	diesel		Asphalt Hauling
Off-Site Concrete Trucks	310	diesel		Concrete Delivery
Off-Site Construction Worker Commute	180	gasoline		Personal vehicle (see commute table below)
Off-Site Dump Trucks	275	diesel		Material Hauling
Off-Site Low Boy Trucks (From Rail Facility)	250	diesel		Material Hauling
Off-Site Pickup Trucks	200	gasoline		Light duty material hauling
Off-Site Pipe Hauling Trucks (From Rail Facility)	250	diesel		Piping material hauling
Off-Site Water Trucks	250	diesel		Dust suppression water
Off-Site Fuel/Lube Trucks	200	gasoline		Mobile fuel & lubrication services
Off-Site HTF Delivery Trucks (From Rail Facility)	250	diesel		Delivery of HTF (transfer from rail yard)
Off-Site Box Van Trucks	200	diesel		Material Hauling (Small items / Dry Requirement Items)

Note: Use separate sheet (Site Construction Equipment) for on-site vehicles

Average Vehicle Miles Traveled per Day and Number of Vehicles

VEHICLE TYPE	Mi./ Veh.-Day*	Number																									
		M1	M2	M3	M4	M5	M6	M7	M8	M9	M10	M11	M12	M13	M14	M15	M16	M17	M18	M19	M20	M21	M22	M23	M24	M25	M26
Off-Site Flat Bed Trucks (From Rail Facility)	50	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	3	3	3	3	3	3	3	2	2
Off-Site Asphalt Trucks	50	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	3	3	3	3	2	
Off-Site Concrete Trucks	50	1	12	46	46	55	55	55	55	55	55	55	55	55	55	55	55	55	55	55	55	46	46	46	37	14	4
Off-Site Dump Trucks	50	1	1	1	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Off-Site Low Boy Trucks (From Rail Facility)	50	1	1	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	1	1
Off-Site Pickup Trucks	50	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	1	1	1	1	0	0
Off-Site Pipe Hauling Trucks (From Rail Facility)	50	0	0	0	0	0	0	0	0	0	0	3	4	5	5	5	5	5	5	4	2	0	0	0	0	0	0
Off-Site Water Trucks	50	1	1	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Off-Site Fuel/Lube Trucks	50	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	0	0
Off-Site HTF Delivery Trucks (From Rail Facility)	50	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	2	2	2	2	2	2	2	2
Off-Site Box Van Trucks	50	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2	2	2	2	2	2	2	2	2	1	0

Daily Mileage Accumulation

VEHICLE TYPE	Mi./ Veh.-Day*	Vehicle-Miles-Traveled (mi/day)																									
		M1	M2	M3	M4	M5	M6	M7	M8	M9	M10	M11	M12	M13	M14	M15	M16	M17	M18	M19	M20	M21	M22	M23	M24	M25	M26
Off-Site Flat Bed Trucks (From Rail Facility)	50	50	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	150	150	150	150	150	150	150	100	100
Off-Site Asphalt Trucks	50	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Off-Site Concrete Trucks	50	50	600	2,300	2,300	2,750	2,750	2,750	2,750	2,750	2,750	2,750	2,750	2,750	2,750	2,750	2,750	2,750	2,750	2,750	2,300	2,300	2,300	2,300	1,850	700	200
Off-Site Dump Trucks	50	50	50	50	50	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Off-Site Low Boy Trucks (From Rail Facility)	50	50	50	50	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	50	50
Off-Site Pickup Trucks	50	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	50	50	50	50	0	
Off-Site Pipe Hauling Trucks (From Rail Facility)	50	0	0	0	0	0	0	0	0	0	150	200	250	250	250	250	250	250	250	200	100	0	0	0	0	0	
Off-Site Water Trucks	50	50	50	50	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Off-Site Fuel/Lube Trucks	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	0	
Off-Site HTF Delivery Trucks (From Rail Facility)	50	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	50	100	100	100	100	100	100	100	
Off-Site Box Van Trucks	50	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	100	100	100	100	100	100	100	100	100	50	0

Const Period
Delivery data
diesel VMT gasoline VMT
1429750 94600

Off-Site Construction Workers Bussing Adjustments

Total		173	244	321	411	680	862	898	948	968	998	1086	1081	1127	1149	1144	1139	1162	1155	1130	1069	1051	946	885	607	217	138
Solar Collector Array Facility (included in Total)					10	150	298	298	298	298	298	298	298	298	298	298	298	298	298	298	298	298	298	298	150		
Supervisors/Management/Admin (included in Total)		8	24	35	45	65	75	75	75	75	85	85	85	85	85	85	85	85	80	75	75	75	55	55	55	30	15
Final Off-Site Construction Worker Commute (people, not vehicles)		M1	M2	M3	M4	M5	M6	M7	M8	M9	M10	M11	M12	M13	M14	M15	M16	M17	M18	M19	M20	M21	M22	M23	M24	M25	M26
Day Shift - non Bussed		49	79	107	137	219	247	256	269	274	285	307	306	317	323	322	320	326	322	314	299	294	260	244	175	77	46
Day Shift - Bussed		124	165	215	275	461	575	602	640	655	668	734	730	765	781	777	774	791	790	776	731	717	657	612	403	140	92
Evening Shift - non Bussed							25	25	25	25	28	28	28	28	28	28	28	28	26	25	25	25	18	18	18		
Evening Shift - Bussed (if available)							15	15	15	15	17	17	17	17	17	17	17	16	15	15	15	11	11	11	11		

check cells	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE
* Maximum One-way haul distance (backhaul not included since trucks are not dedicated to site or project)																											
Day shift non-bussed total worker vehicles assuming 20% carpool	39	63	85	109	175	198	205	215	219	228	246	245	254	258	257	256	261	258	251	239	235	208	195	140	61	37	
Day shift total buses (roundtrips)	3	3	4	6	10	12	13	13	14	14	15	15	16	16	16	16	16	16	16	15	15	14	8	3	2		
Evening shift total worker vehicles assuming no bussing and 20% carpool	0	0	0	0	0	32	32	32	32	36	36	36	36	36	36	36	36	36	34	32	32	23	23	23	0	0	
Total Vehicle Trips (non-bussed) per month	847	1359	1832	2348	3763	4932	5087	5302	5388	5680	6059	6037	6235	6330	6308	6287	6386	6274	6085	5822	5745	4967	4704	3509	1320	787	
Total Bussed Vehicles Trips per month	55	74	96	123	207	258	270	287	293	299	329	327	342	350	348	346	354	354	348	327	321	294	274	181	63	41	

Max workers per month (assume pre day is same value): 1162
Avg workers per month (assume pre day is same value): 830
Assume all trips for worker commute are from Barstow: 60 miles roundtrip
(1) delivery trips from BNSF Barstow and urban area
(2) commute trips from Barstow urban area or commute staging area
(3) delivery trips only one way as non-dedicated to site
(4) commute trip distance is roundtrip
(5) assume bus capacity is 48 people
(6) assume evening shift is all non-bussed

62350 gasoline
15050 diesel
1266350 diesel
4300 diesel
50525 gasoline
5375 diesel
51600 diesel
3225 diesel
26875 gasoline
18275 diesel
20425 diesel
Total 1524350

5674 people
1672 people
6173 people
14648 people
479 people
290 people

Total Trips 119390
Total VMT 7163370

FIXED ROOF TANK EMISSION CALCULATION

Reference: AP-42, Section 7.1, 9/97

Emissions Scenario

***** Input *****	X	: PTE
		: Actual
Number of Similar Tanks:	1	Year: Any
Stored Substance ID:	Diesel Fuel	Tank Cap. 2000 gallons
Tank ID:	Tank 1	Kn = 70.175 * Eq 41
Vapor Molecular Wt.:	130	Table 6*
Vapor Pressure (psia):	0.00648	Table 6*
Tank Diameter (ft):	6	
Tank Height/Length (ft):	9.5	
Avg. Vapor Space Height (ft):	4	
Avg. Diurnal Temp Change (degF):	28	Table 4 (Phoenix data used to simulate site)*
Paint Factor:	1	
Small Tank Adj. Factor:	1	
Product Factor:	1	* Section 19.1.2.2.3.3
Turnover Factor:	0.59	
Throughput (gals/yr):	25000	

Intermediate Calculations

TP =	25.00
Q =	0.01
D =	22.19
H =	2.03
T =	5.29

***** Output *****	Single Tank	All Tanks
Uncontrolled Emissions		
Breathing Loss (lb/yr):	3.66	3.66
Working Loss (lb/yr):	0.30	0.30
Total VOC Losses (lb/yr):	3.96	3.96
Controlled Emissions		
Control System Eff. (frac):	0	0
Total VOC Losses (lb/yr):	3.96	3.96
(lb/day):	0.0108	0.0108
(lb/hr):	0.0005	0.0005
(TPY):	0.0020	0.0020

Additional References: *API Bulletin #2518, October 1991
TTECI-2007

GASOLINE TANK EMISSION CALCULATION

Reference: AP-42, Section 5.2, 6/08

***** Input *****

Facility Type/ID:

Facility Tank

Program is Applicable to All Grades/Types of Gasoline

UNDERGROUND TANK FILLING lb/1000 gal * Table 5.2-7 Values

Balanced Submerged Filling: 0.3 Phase 1 Varc

Submerged Filling: 0

Splash Filling: 0

Tank Breathing: 1

Spillage: 0.7

VEHICLE REFUELING

Controlled: 0

Uncontrolled: 11

Tank Throughput (gals/yr): 18000

Intermediate Calculations

TP = 18

EF = 13

***** Output *****

Total VOC Losses (lb/yr): 234

(lb/day): 0.64

(lb/hr): 0.027

(TPY): 0.117

* Enter 0 for any category which is not applicable.

Operations Vehicle Emissions from Site Deliveries

Operations Site Delivery Emissions

Deliveries per Avg Month:	38	
Per trip delivery VMT:	50	
Total monthly VMT:	1900	
Total annual VMT:	22800	
Fraction annual VMT (gas)	0.5	
Fraction annual VMT (die:	0.5	Daily VMT*
Annual gasoline VMT:	11400	44
Annual diesel VMT:	11400	44

*Daily VMT based on 260 days/year.

Emissions Factors (lbs/vmt)							
NOx	CO	VOC	SOx	PM10	CO2		
0.03422	0.009532	0.002411	0.00004	0.001556	4.04823	Diesel	
0.00202	0.01296	0.001125	0.000015	0.000098	1.4488	MD Gas	
Max Daily Emissions (lbs)							
NOx	CO	VOC	SOx	PM10	CO2	PM2.5	
1.5004	0.4179	0.1057	0.0018	0.0682	177.4993	0.0676	Diesel
0.0886	0.5682	0.0493	0.0007	0.0043	63.5243	0.0043	MD Gas
Tons per Const Period							
0.1951	0.0543	0.0137	0.0002	0.0089	23.0749	0.0088	Diesel
0.0115	0.0739	0.0064	0.0001	0.0006	8.2582	0.0006	MD Gas

Ref: MDAB, Emfac 2007, V2.3, Nov 2006
LDPs (gas and diesel), 1966-2010

HTF System Component Count and Fugitive Emissions Estimate
Mohave Solar Project

Component	Count #	Service	EF lb/hr/src	Hrs/day	lbs/hr	lbs/day	lbs/yr	tons/yr
Valves								
Sealed Bellows	0	Gas/Vapor	0	0	0.000	0.000	0.000	0.000
		& Lt. Liquid	0	0	0.000	0.000	0.000	0.000
		Fuel/N.Gas	0	0	0.000	0.000	0.000	0.000
		Gas Vapor	0	0	0.000	0.000	0.000	0.000
		Lt. Liquid	0.0002517	16	0.817	13.076	4772.856	2.386
AQMD Approved I&M	3247	Hvy. Liquid	0	0	0.000	0.000	0.000	0.000
Pumps								
Sealess Type	0	Lt. Liquid	0	0	0.000	0.000	0.000	0.000
Double Mech Seals or Equivalent	24	Lt. Liquid	0.0008448	16	0.020	0.324	118.407	0.059
Single Mech Seal	0	Hvy. Liquid	0	0	0.000	0.000	0.000	0.000
Compressors	0	Gas/Vapor	0	0	0.000	0.000	0.000	0.000
Flanges/Connectors	1550	All	0.0000165	16	0.026	0.409	149.358	0.075
PRVs	16	Gas	0.098546	8	1.577	12.614	4604.069	2.302
Process Drains	0	All	0	0	0.000	0.000	0.000	0.000
Open-ended Lines	0	Lt. Liquid	0.003307	0	0.000	0.000	0.000	0.000
Totals					2.44	26.42	9644.69	4.82
Operating Days/Yr:	365							

Decomposition By Products:

Comment	CAS #	Substance ID	% wt of Total VOC	Fraction of VOC, wt	lbs/hr	lbs/day	lbs/yr	tons/yr
MSDS Trace Amount		Benzene	5	0.05	0.122	1.321	482.235	0.241
MSDS Trace Amount		Phenol	5	0.05	0.122	1.321	482.235	0.241
HTF Composition Value		Biphenyl	26.5	0.265	0.647	7.002	2555.843	1.278
			0	0	0.000	0.000	0.000	0.000
		***	0	0	0.000	0.000	0.000	0.000

Notes:

- (1) VOC BACT for component system is I&M program. Leaks not to exceed 100 ppmv for all components.
- (2) VOC BACT is accepted as achieved in practice.
- (3) Ref: Kern County APCD, Engineering Analysis, Beacon Hill Solar Project, Project No. 090717, DOC 0369004A.
- (4) CEC, FSA, Beacon Hill Solar, August 2009, 08-AFC-2, CEC-700-2009-005-FSA.
- (5) Decomposition data from HTF manufacturer and related MSDS.
- (6) All drains, vents, and inline relief valves are capped and they are included as "connectors".
- (7) In line relief valves relieve light liquid from high pressure to successively lower pressures.
- (8) The only relief valves to atmosphere are from Nitrogen blanketed vapor space (gas) on tanks and cleaning system.

Table C.5-7 Offsite Equipment and Manpower Schedules
Offsite Construction Vehicles

VEHICLE TYPE	HP	Fuel Type	Load Factor (%)	USAGE DESCRIPTION
Off-Site Flat Bed Trucks (From Rail Facility)	200	gasoline		Material Hauling
Off-Site Asphalt Trucks	200	diesel		Asphalt Hauling
Off-Site Concrete Trucks	310	diesel		Concrete Delivery
Off-Site Construction Worker Commute	180	gasoline		Personal vehicle (see commute table below)
Off-Site Dump Trucks	275	diesel		Material Hauling
Off-Site Low Boy Trucks (From Rail Facility)	250	diesel		Material Hauling
Off-Site Pickup Trucks	200	gasoline		Light duty material hauling
Off-Site Pipe Hauling Trucks (From Rail Facility)	250	diesel		Piping material hauling
Off-Site Water Trucks	250	diesel		Dust suppression water
Off-Site Fuel/Lube Trucks	200	gasoline		Mobile fuel & lubrication services
Off-Site HTF Delivery Trucks (From Rail Facility)	250	diesel		Delivery of HTF (transfer from rail yard)
Off-Site Box Van Trucks	200	diesel		Material Hauling (Small items / Dry Requirement Items)

Note: Use separate sheet (Site Construction Equipment) for on-site vehicles

Average Vehicle Miles Traveled per Day and Number of Vehicles

VEHICLE TYPE	Mi./ Veh.-Day*	Number																									
		M1	M2	M3	M4	M5	M6	M7	M8	M9	M10	M11	M12	M13	M14	M15	M16	M17	M18	M19	M20	M21	M22	M23	M24	M25	M26
Off-Site Flat Bed Trucks (From Rail Facility)	50	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	3	3	3	3	3	3	3	2	2
Off-Site Asphalt Trucks	50	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	3	3	3	3	2	
Off-Site Concrete Trucks	50	1	12	46	46	55	55	55	55	55	55	55	55	55	55	55	55	55	55	55	55	46	46	46	37	14	4
Off-Site Dump Trucks	50	1	1	1	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Off-Site Low Boy Trucks (From Rail Facility)	50	1	1	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	1	1
Off-Site Pickup Trucks	50	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	1	1	1	1	0	0
Off-Site Pipe Hauling Trucks (From Rail Facility)	50	0	0	0	0	0	0	0	0	0	0	3	4	5	5	5	5	5	5	4	2	0	0	0	0	0	0
Off-Site Water Trucks	50	1	1	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Off-Site Fuel/Lube Trucks	50	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	0	0
Off-Site HTF Delivery Trucks (From Rail Facility)	50	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	2	2	2	2	2	2	2	2
Off-Site Box Van Trucks	50	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2	2	2	2	2	2	2	2	2	1	0

Daily Mileage Accumulation

VEHICLE TYPE	Mi./ Veh.-Day*	Vehicle-Miles-Traveled (mi/day)																									
		M1	M2	M3	M4	M5	M6	M7	M8	M9	M10	M11	M12	M13	M14	M15	M16	M17	M18	M19	M20	M21	M22	M23	M24	M25	M26
Off-Site Flat Bed Trucks (From Rail Facility)	50	50	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	150	150	150	150	150	150	150	100	100
Off-Site Asphalt Trucks	50	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Off-Site Concrete Trucks	50	50	600	2,300	2,300	2,750	2,750	2,750	2,750	2,750	2,750	2,750	2,750	2,750	2,750	2,750	2,750	2,750	2,750	2,750	2,300	2,300	2,300	2,300	1,850	700	200
Off-Site Dump Trucks	50	50	50	50	50	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Off-Site Low Boy Trucks (From Rail Facility)	50	50	50	50	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	50	50
Off-Site Pickup Trucks	50	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	50	50	50	50	50	0	
Off-Site Pipe Hauling Trucks (From Rail Facility)	50	0	0	0	0	0	0	0	0	0	150	200	250	250	250	250	250	250	250	200	100	0	0	0	0	0	
Off-Site Water Trucks	50	50	50	50	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Off-Site Fuel/Lube Trucks	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	0	
Off-Site HTF Delivery Trucks (From Rail Facility)	50	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	50	100	100	100	100	100	100	100	
Off-Site Box Van Trucks	50	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	100	100	100	100	100	100	100	100	100	50	0

Const Period

Delivery data

diesel VMT

gasoline VMT

1429750

94600

Off-Site Construction Workers Bussing Adjustments

Total		173	244	321	411	680	862	898	948	968	998	1086	1081	1127	1149	1144	1139	1162	1155	1130	1069	1051	946	885	607	217	138
Solar Collector Array Facility (included in Total)					10	150	298	298	298	298	298	298	298	298	298	298	298	298	298	298	298	298	298	298	150		
Supervisors/Management/Admin (included in Total)		8	24	35	45	65	75	75	75	75	85	85	85	85	85	85	85	85	80	75	75	75	55	55	55	30	15
Final Off-Site Construction Worker Commute (people, not vehicles)		M1	M2	M3	M4	M5	M6	M7	M8	M9	M10	M11	M12	M13	M14	M15	M16	M17	M18	M19	M20	M21	M22	M23	M24	M25	M26
Day Shift - non Bussed		49	79	107	137	219	247	256	269	274	285	307	306	317	323	322	320	326	322	314	299	294	260	244	175	77	46
Day Shift - Bussed		124	165	215	275	461	575	602	640	655	668	734	730	765	781	777	774	791	790	776	731	717	657	612	403	140	92
Evening Shift - non Bussed							25	25	25	25	28	28	28	28	28	28	28	28	26	25	25	25	18	18	18		
Evening Shift - Bussed (if available)							15	15	15	15	17	17	17	17	17	17	17	16	15	15	15	11	11	11	11		

check cells	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE
* Maximum One-way haul distance (backhaul not included since trucks are not dedicated to site or project)																											
Day shift non-bussed total worker vehicles assuming 20% carpool	39	63	85	109	175	198	205	215	219	228	246	245	254	258	257	256	261	258	251	239	235	208	195	140	61	37	
Day shift total buses (roundtrips)	3	3	4	6	10	12	13	13	14	14	15	15	16	16	16	16	16	16	16	15	15	14	13	8	3	2	
Evening shift total worker vehicles assuming no bussing and 20% carpool	0	0	0	0	0	32	32	32	32	36	36	36	36	36	36	36	36	36	34	32	32	23	23	23	0	0	
Total Vehicle Trips (non-bussed) per month	847	1359	1832	2348	3763	4932	5087	5302	5388	5680	6059	6037	6235	6330	6308	6287	6386	6274	6085	5822	5745	4967	4704	3509	1320	787	
Total Bussed Vehicles Trips per month	55	74	96	123	207	258	270	287	293	299	329	327	342	350	348	346	354	354	348	327	321	294	274	181	63	41	

Max workers per month (assume pre day is same value):

Avg workers per month (assume pre day is same value):

Assume all trips for worker commute are from Barstow:

(1) delivery trips from BNSF Barstow and urban area

(2) commute trips from Barstow urban area or commute staging area

(3) delivery trips only one way as non-dedicated to site

(4) commute trip distance is roundtrip

(5) assume bus capacity is 48 people

(6) assume evening shift is all non-bussed

62350

gasoline

15050

diesel

1266350

diesel

4300

diesel

50525

diesel

5375

gasoline

51600

diesel

3225

diesel

26875

gasoline

18275

diesel

20425

diesel

Total

1524350

5674

people

1672

people

6173

people

14648

people

479

people

290

people

Total

119390

7163370

6561

393658

Table C.5-6
Estimated Construction Equipment Identification and Use Rates

EQUIPMENT DESCRIPTION			HP	FUEL TYPE	USAGE DESCRIPTION	
SITE GRADING						
TRUCK	PICKUP	.5 TONS- 4 X 2	190	Gas	Grading Supervisors / Grade Checkers	(1) Superintendent or (1) Grade Checker
TRUCK	FUEL/LUBE	6 Tons - 4X2	223	Diesel	Fueling / Maintenance of Grading Equipment	(1) Mechanic's Helper
TRUCK	PICKUP	1.0 TONS- 4 X 4	190	Diesel	Grading Maintenance/Mechanics	(1) Mechanic and (1) Mechanic's Helper
14 M MOTOR GRADER	GRADING EQUIPMENT	47,133 LB	174	Diesel	Earth Moving	(1) Heavy Equipment Operator
623G SCRAPER	GRADING EQUIPMENT	23 CY	313	Diesel	Earth Moving	(1) Heavy Equipment Operator
657G SCRAPER	GRADING EQUIPMENT	44 CY	313	Diesel	Earth Moving	(1) Heavy Equipment Operator
825 H COMPACTOR	GRADING EQUIPMENT	72,164 LB	114	Diesel	Earth Moving	(1) Heavy Equipment Operator
631 WATER PULL (10K)	GRADING EQUIPMENT	10,000 GALLON	223	Diesel	Earth Moving	(1) Heavy Equipment Operator
D6 DOZERS	GRADING EQUIPMENT	44,418 LB	144	Diesel	Earth Moving	(1) Heavy Equipment Operator
414E INDUSTRIAL LOADER	GRADING EQUIPMENT	1 CY	89	Diesel	Site clean-up / Maintenance	(1) Heavy Equipment Operator
WATER TRUCK	GRADING EQUIPMENT	4,000 GALLON	223	Diesel	Site clean-up / Maintenance	(1) Heavy Equipment Operator
TRUCK	DUMP TRUCK	6 CY	223	Diesel	Site clean-up / Maintenance	(1) Heavy Equipment Operator
POWER BLOCK AND HTF AREA						
AUTO	CAR 4-DOOR	STANDARD	190	Gas	Administrative and personnel vehicle for site usage	
TRUCK	PICKUP	.5 TONS- 4 X 2	190	Gas	General construction usage vehicle	
TRUCK	PICKUP	.75 TONS- 4 X 2	190	Gas	General construction usage vehicle	
TRUCK	PICKUP	.75 TONS- 4 X 4	200	Diesel	General construction usage vehicle	
TRUCK	PICKUP - CREW CAB	.75 TONS- 4 X 4	200	Diesel	General construction usage vehicle	
TRUCK	PICKUP	1.0 TONS- 4 X 4	200	Diesel	General construction usage vehicle	
TRUCK	FLATBED	2 TONS- 4 X 2	200	Diesel	On-site material hauling	
TRUCK	FLATBED	6 TONS- 4 X 2	200	Diesel	On-site material hauling	
TRUCK	FLATBED	15 TONS- 4 X 2	200	Diesel	On-site material hauling	
TRUCK	FLATBED	30 TONS- 6 X 4	250	Diesel	On-site material hauling	
TRUCK	A-FRAME	4 X 4	200	Gas	On-site material hauling	
TRUCK	LUBE/GREASE		223	Diesel	Lube/grease truck for on-site construction vehicle maintenance	
TRUCK	CHERRY PICKER	NON-INSULATED	185	Diesel	Small crane for light duty lifting	
TRUCK	DUMP TRUCK	6 CY	223	Diesel	On-site material hauling	
TRUCK	DUMP TRUCK	12 CY	223	Diesel	On-site material hauling	
TRUCK	DUMP TRUCK	20 CY	223	Diesel	On-site material hauling	
TRACTOR	TRUCK TRACTOR	30 TONS 6X4	80	Diesel	Trailer pulling and general construction usage	
TRACTOR	TRUCK TRACTOR	60 TONS 6X4	80	Diesel	Trailer pulling and general construction usage	
TRACTOR	WHEEL, W/TOW HITCH	50 HP	80	Diesel	Trailer pulling and general construction usage	
CRANE	TELESCOPIC JIB, SELF	PROP. 5 TONS	185	Diesel	Small crane for light duty lifting	
CRANE	TELESCOPIC JIB, SELF	PROP. 10 TONS	185	Diesel	Small crane for light duty lifting	
CRANE	TELESCOPIC JIB, SELF	PROP. 15 TONS	185	Diesel	Small crane for light duty lifting	
CRANE	TELESCOPIC JIB	TRUCK - 20 TONS	191	Diesel	Small crane for medium duty lifting	
CRANE	TELESCOPIC JIB	TRUCK - 25 TONS	191	Diesel	Small crane for medium duty lifting	
CRANE	TELESCOPIC JIB	TRUCK - 30 TONS	191	Diesel	Small crane for medium duty lifting	
CRANE	TELESCOPIC JIB	TRUCK - 70 TONS	191	Diesel	Small crane for medium duty lifting	
CRANE	FIXED JIB, CRAWLER	20 TONS	191	Diesel	Small crane for medium duty lifting	
CRANE	FIXED JIB, CRAWLER	30 TONS	191	Diesel	Small crane for medium duty lifting	
CRANE	FIXED JIB, CRAWLER	40 TONS	191	Diesel	Small crane for medium duty lifting	
CRANE	FIXED JIB, CRAWLER	120 TONS	191	Diesel	Small crane for medium duty lifting	
CRANE	FIXED JIB, CRAWLER	165 TONS	250	Diesel	Large crane for heavy duty lifting	
CRANE	FIXED JIB, CRAWLER	400 TONS	350	Diesel	Large crane for heavy duty lifting	
PILING	DRILLING FRAME	AUGER	218	Diesel	Drilling machine for pier foundations	
PILING	DRILLING FRAME	AUGER	218	Diesel	Drilling machine for pier foundations	
COMPRESSOR	DIESEL(ROTARY SCREW)	250 CFM	37	Diesel	Air compressor for pneumatic construction tools and equipment	
COMPRESSOR	DIESEL(ROTARY SCREW)	365 CFM	37	Diesel	Air compressor for pneumatic construction tools and equipment	
COMPRESSOR	DIESEL(ROTARY SCREW)	600 CFM	37	Diesel	Air compressor for pneumatic construction tools and equipment	
CONCRETE	CONCRETE MIXER	6 SACK	223	Diesel	Concrete mixer for small foundations and supports	
CONCRETE	CONCRETE MIXER	16 SACK (1 CY)	223	Diesel	Concrete mixer for small foundations and supports	
CONCRETE	VIBRATOR GASOLINE	2.4 HP,2 IN HEAD	2.4	Gas	Small area compaction	
CONCRETE	POWER TROWEL,4 BLADE	36 IN DIA	5	Gas	Concrete finishing tool	
CONCRETE	SITE DUMPER	.75 CY, DIESEL	5	Diesel	On-site material hauling	
WELDING EQUIPMENT	PORTABLE DIESEL	300 AMPERES	25	Diesel	Welding equipment	
WELDING EQUIPMENT	PORTABLE DIESEL	400 AMPERES	25	Diesel	Welding equipment	
PIPING EQUIPMENT	CUTTING & BEVELLING	1 - 4 INCHES	10	Diesel	Pipe fitting and preparation	
PIPING EQUIPMENT	CUTTING & BEVELLING	6 - 20 INCHES	10	Diesel	Pipe fitting and preparation	
PIPING EQUIPMENT	CUTTING & BEVELLING	22 - 30 INCHES	15	Diesel	Pipe fitting and preparation	
PUMP	DIAPHRAGM	4 INCHES SUCTION	10	Gas	Small pump for sumps and general construction usage	
ELECTRIC EQUIP/TOOL	GENERATOR SET	10 KW	50	Gas	Small generator for construction tools	
ASPHALT EQUIPMENT	PAVER/FINISHER	10 FEET WIDE	100	Diesel	Pavement finishing	
ASPHALT EQUIPMENT	SPREADER TRAILER,GAS	2000 GAL, SPRAY	100	Gas	Pavement spreading	

ID #	Category for Main Sheet Calcs
1	Bore/Drill Rigs/Pile Drivers
2	Cement Mixers
3	Industrial/Concrete Saws
4	Cranes
5	Crawler Tractors/Dozers
6	Crushing/Processing Eq.
7	Dump and Tender Trucks
8	Excavators
9	Forklifts/Aerial Lifts/Booms
10	Generators/Compressors
11	Graders
12	Off Highway Tractors
13	Off Highway Trucks
14	Other Const. Eq.-Diesel
15	Pavers
16	Paving Eq./Surfacing Eq.
17	Plate Compactors
18	Rollers/Compactors
19	Rough Terrain Forklifts
20	Rubber Tired Dozers
21	Rubber Tired Loaders
22	Scrapers
23	Signal Boards/Light Sets
24	Skid Steer Loaders
25	Tractors/Loaders/Backhoes
26	Trenchers
27	Welders
28	Other Const. Eq.-Gasoline

AUTO	CAR 4-DOOR	STANDARD	10					1	1	1	1	1	1	1	1	2	2	2
TRUCK	PICKUP	5 TONS- 4 X 2	10					1	1	1	1	1	1	1	1	2	2	2
TRUCK	PICKUP	.75 TONS- 4 X 2	10								1	2	4	6	8	10	12	12
TRUCK	PICKUP	.75 TONS- 4 X 4	10					2	2	4	6	8	12	12	12	12	12	12
TRUCK	PICKUP - CREW CAB	.75 TONS- 4 X 4	10															
TRUCK	PICKUP	1.0 TONS- 4 X 4	10								1	1	1	1	1	1	1	1
TRUCK	FLATBED	2 TONS- 4 X 2	10								1	1	1	1	1	1	1	1
TRUCK	FLATBED	6 TONS- 4 X 2	10							1	1	1	1	1	1	1	1	1
TRUCK	FLATBED	15 TONS- 4 X 2	10															1
TRUCK	FLATBED	30 TONS- 6 X 4	10															
TRUCK	A-FRAME	4 X 4	10					2	4	4	4	4	4	4	4	4	4	4
TRUCK	LUBE/GREASE		10															
TRUCK	CHERRY PICKER	NON-INSULATED	10															
TRUCK	DUMP TRUCK	6 CY	10															
TRUCK	DUMP TRUCK	12 CY	10											1	1	1	1	1
TRUCK	DUMP TRUCK	20 CY	10											1	1			
TRACTOR	TRUCK TRACTOR	30 TONS 6X4	10					1	1	1	1	1	1	1				
TRACTOR	TRUCK TRACTOR	60 TONS 6X4	10							1	1	1						
TRACTOR	WHEEL, W/TOW HITCH	50 HP	10					3	4	6	6	6	6	8	8	8	8	8
CRANE	TELESCOPIC JIB, SELF	PROP. 5 TONS	10							1	1	1	1	1				
CRANE	TELESCOPIC JIB, SELF	PROP. 10 TONS	10												1	1	1	1
CRANE	TELESCOPIC JIB, SELF	PROP. 15 TONS	10					1	1	3	4	6	6	8	8	8	8	8
CRANE	TELESCOPIC JIB	TRUCK - 20 TONS	10						2	4	6	8	8	8	8	8	8	8
CRANE	TELESCOPIC JIB	TRUCK - 25 TONS	10					2	2	2	2	2	2	2	2	2	2	2
CRANE	TELESCOPIC JIB	TRUCK - 30 TONS	10					1										
CRANE	TELESCOPIC JIB	TRUCK - 70 TONS	10						1	1	1	1	2	2	2	2	2	2
CRANE	FIXED JIB, CRAWLER	20 TONS	10															
CRANE	FIXED JIB, CRAWLER	30 TONS	10															
CRANE	FIXED JIB, CRAWLER	40 TONS	10															
CRANE	FIXED JIB, CRAWLER	120 TONS	10															
CRANE	FIXED JIB, CRAWLER	165 TONS	10															
CRANE	FIXED JIB, CRAWLER	400 TONS	10															
PILING	DRILLING FRAME	AUGER	10					1										
PILING	DRILLING FRAME	AUGER	10						1	1	1	1						
COMPRESSOR	DIESEL(ROTARY SCREW)	250 CFM	10						1									
COMPRESSOR	DIESEL(ROTARY SCREW)	365 CFM	10						1	1	1	1	1	1	1	1	1	1
COMPRESSOR	DIESEL(ROTARY SCREW)	600 CFM	10							1	1	2	2	2	2	4	4	4
CONCRETE	CONCRETE MIXER	6 SACK	10					1										
CONCRETE	CONCRETE MIXER	16 SACK (1 CY)	10					2	4	4	4	4	4	4	4	4	4	4
CONCRETE	VIBRATOR GASOLINE	2.4 HP, 2 IN HEAD	10						1	1	1							
CONCRETE	POWER TROWEL, 4 BLADE	36 IN DIA	10						1	2	2	2	2	1	1	1	1	1
CONCRETE	SITE DUMPER	.75 CY, DIESEL	10						1	1	1	1	1	1	1		1	1
WELDING EQUIPMENT	PORTABLE DIESEL	300 AMPERES	10							1								
WELDING EQUIPMENT	PORTABLE DIESEL	400 AMPERES	10						2	8	20	20	20	22	22	22	22	22
PIPING EQUIPMENT	CUTTING & BEVELLING	1 - 4 INCHES	10															
PIPING EQUIPMENT	CUTTING & BEVELLING	6 - 20 INCHES	10															1
PIPING EQUIPMENT	CUTTING & BEVELLING	22 - 30 INCHES	10							1	1	1	1	1	1	1	1	1
PUMP	DIAPHRAGM	4 INCHES SUCTION	10					1	1	1	1	1	1	1	1	1	1	1
ELECTRIC EQUIP/TOOL	GENERATOR SET	10 KW	10					1	1	1	1	1	1	1	1	1	1	1
ASPHALT EQUIPMENT	PAVER/FINISHER	10 FEET WIDE	10															
ASPHALT EQUIPMENT	SPREADER TRAILER, GAS	2000 GAL. SPRAY	10															
Monthly Equipment Onsite, #				0	0	1	9	28	41	65	70	79	85	91	92	97	99	101

SOLAR FIELD			Hours/Day*															
AUTO	CAR 4-DOOR	STANDARD	20	1	1	1	1	1	1	1	1	1	1	1	2	2	2	2
TRUCK	PICKUP	.75 TONS- 4 X 2	20	3	5	5	7	10	10	10	10	10	10	10	10	10	10	10
TRUCK	PICKUP	.75 TONS- 4 X 4	20		5	5	10	10	10	10	10	10	10	10	10	10	10	10
TRUCK	PICKUP - CREW CAB	.75 TONS- 4 X 4	20											1	1	1	1	1
TRUCK	FLATBED	2 TONS- 4 X 2	20															
TRUCK	FLATBED	6 TONS- 4 X 2	20		1	1	1	1	1	1	1	1	1	1	1	1	1	2
TRUCK	FLATBED	15 TONS- 4 X 2	20															
TRUCK	A-FRAME	4 X 4	20	2	2	4	4	4	4	4	4	4	4	4	4	4	4	4
TRUCK	CHERRY PICKER	NON-INSULATED	20	1														
TRUCK	DUMP TRUCK	6 CY	20	1	1	1	1	1	1	1								
TRUCK	DUMP TRUCK	12 CY	20	1	1	1	1	1	1	1	1	1	1	2	2	2	2	2
TRUCK	DUMP TRUCK	20 CY	20			1	1	1	1									
TRACTOR	TRUCK TRACTOR	30 TONS 6X4	20															
TRACTOR	TRUCK TRACTOR	60 TONS 6X4	20															
TRACTOR	WHEEL, W/TOW HITCH	50 HP	20		4	8	12	16	16	16	16	16	16	16	16	16	16	16
CRANE	TELESCOPIC JIB, SELF	PROP. 15 TONS	20	2	2	2	2	2	4	4	6	8	8	8	8	8	8	8
CRANE	TELESCOPIC JIB	TRUCK - 20 TONS	20		4	5	5	10	10	10	10	10	10	10	10	10	10	10
CRANE	TELESCOPIC JIB	TRUCK - 25 TONS	20	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
CRANE	TELESCOPIC JIB	TRUCK - 50 TONS	20															
CRANE	FIXED JIB	TRUCK - 60 TONS	20															
CRANE	FIXED JIB, CRAWLER	20 TONS	20	1	1	1	1	1	1	2	2	2	2	2	2	3	3	3
COMPRESSOR	DIESEL(ROTARY SCREW)	250 CFM	20		1	1	1	1										
COMPRESSOR	DIESEL(ROTARY SCREW)	365 CFM	20	2	2	2	4	5	5	5	5	5	5	5	5	5	5	5
COMPRESSOR	DIESEL(ROTARY SCREW)	600 CFM	20									1	1	1	1	2	2	3
CONCRETE	CONCRETE MIXER	6 SACK	20	1	1	1	1	1	2	2	2	2	2	2	2	2	2	1
CONCRETE	CONCRETE MIXER	16 SACK (1 CY)	20	1	1	1	2	2	2	2	2	2	2	2	2	2	1	1
CONCRETE	VIBRATOR GASOLINE	2.4 HP 2 IN HEAD	20		1	1	1	1	1	1	1	1	1					
CONCRETE	POWER TROWEL 4 BLADE	36 IN DIA	20			1	1	1	1	1	1	1	1	1	1			
CONCRETE	SITE DUMPER	.75 CY, DIESEL	20	1	1	1	1	1	1	1	1	1	1	1	1	1		
WELDING EQUIPMENT	PORTABLE GASOLINE	200 AMPERES	20															
WELDING EQUIPMENT	PORTABLE DIESEL	400 AMPERES	20			10	25	25	25	25	25	25	25	25	25	25	25	25
PIPING EQUIPMENT	CUTTING & BEVELLING	6 - 20 INCHES	20									1	1	1	1	1	1	1
PUMP	DIAPHRAGM	4 INCHES SUCTION	20	1	1	1	1	1	1	1	1							
ELECTRIC EQUIP/TOOL	GENERATOR SET	10 KW	20					1	1	1	1							
ASPHALT EQUIPMENT	PAVER/FINISHER	10 FEET WIDE	20															

Monthly Equipment Onsite,#			21	35	55	84	96	99	99	101	104	102	104	103	105	103	105
Total Monthly Equipment Onsite All Phases: #			89	103	124	161	192	208	167	174	186	190	198	198	205	205	209

Avg to Max EQ Use Rates by Phase			
	monthly	monthly	ratio
	avg # of EQ on site	max # of EQ on site	max/avg
Site grading/prep phase 1	68	68	1.00
Site grading/prep phase 2	3	3	1.00
Power block/HTF area phase	68	101	1.48
Solar field phase	89.5	107	1.20

Notes:
HP values are equipment category averages per Applicant or Sacramento County per Table C.5-5.

[illegible]

2	2	2	2	2	2	2	1	1	1	1	1307200	28
12	12	12	12	10	10	8	8	6	4	3	204250	28
12	12	12	12	12	12	8	8	8	5	4	6209200	28
		1	1	1	1	1	1	1	1		8557000	14
1	1	1	1	1	1	1					344000	14
1	1	1	1	1	1	1	1				645000	14
1	1	1	1	1	1	1	1				688000	14
1	1	1	1	1							559000	14
1	1	1	1	1	1						258000	13
							1				53750	13
4	4	4	4	4	4	4	4	4	3	2	3569000	28
		1									47945	7
					1	1	1	1			159100	9
			1	1	1	1	1	1			287670	7
1	1	1									383560	7
											239725	7
											51600	12
											51600	12
8	8	8	8	8	6	6	6	4	3	2	2373600	12
											198875	9
1											198875	9
8	8	8	8	8	8	8	8	7	4	4	5568500	9
8	8	8	8	8	8	8	8	8	6	4	6159750	4
2	2	2	2	2	2	2	2	2	2	2	1888990	4
											41065	4
2	1	1	1	1	1	1	1	1	1	1	1231950	4
1	1	1	1	1	1	1	1	1	1	1	451715	4
								1	1	1	123195	4
								1			41065	4
									1		41065	4
				1	1	1					75250	4
									1		161250	4
											46870	1
											140610	1
											7955	10
1	1	1	2	2	2	2	1	1	1	1	206830	10
4	4	4	4	4	4	4	4	2	2	2	461390	2
											47945	2
2	2										2397250	2
											1548	2
1	1	1									20425	2
1	1										13975	2
											5375	27
22	22	22	22	22	22	22	20	20	20	10	2289750	27
						1	1				6450	14
1	1	1	1	1	1	1	1	1	1		23650	14
1	1	1	1	1	1	1	1	1			61275	14
1	1	1	1								34400	28
1	1	1	1	1	1	1	1	1	1	1	258000	28
											21500	15
											21500	28
100	98	97	97	93	92	85	81	74	57	40	48237443	

2	2	2	2	2	2	2	2	2	2	2	1	3349700	28
10	10	10	10	10	10	10	10	10	8	8	4	18791000	28
10	10	10	10	10	10	10	10	10	10	10	7	20382000	14
1	1	1	1	1	1	1	1	1	1	1	1	1376000	14
1	1	1	1	1	1	1	1	1	1	1	1	86000	28
2	2	2	2	2	2	2	2	2	2	2	1	3096000	14
						1	1					172000	14
4	4	4	4	4	4	4	4	4	4	3	2	8342000	28
												79550	9
												671230	7
2	2	2	2	1	1	1	1	1	1	1	1	3356150	7
												287670	7
							1					34400	12
								1				34400	12
16	16	16	16	16	16	16	16	13	12	12	6	12212000	12
8	8	8	8	8	8	8	8	6	6	4	3	12320350	9
10	10	10	10	10	10	10	10	8	8	3	1	17740080	9
1	1	1	1	1	1	1	1	1	1	1	1	2135380	9
						1	1	1	1	1	1	410650	9
								1				82130	9
3	3	3	3	3	3	3	3	3	3	3	2	4763540	9
												103200	10
6	6	6	6	6	6	6	6	6	6	4	2	4300000	10
3	3	3	3	2	2	2	2	2	1	1	1	1169600	10
1												2013690	2
1												2493140	2
												7224	17
												19350	17
												27950	7
						1						10750	27
25	20	20	20	20	20	20	20	20	20	19	10	5633000	27
1	1	1	1	1	1	1	1	1	1	1		68800	14
												38700	28
												86000	28
										1		86000	15
107	100	100	100	98	101	101	94	88	78	44		126563534	
210	201	200	200	194	196	189	178	165	138	87		199468787	Total

Table 5.2-1. Estimated Fuel Use Summary for the Project

System	Units	Per Hour	Per Day	Per Year
Auxiliary Boiler (each)	MMscf	0.021	0.504	46.0
Fire Pump Engine (each)	gallons	≤3.8	≤3.8	~198
Emergency Generator (each)	gallons	≤86.7	≤86.7	~4506

Diesel fuel at 139,000 BTU/gal. See Appendix C.1 for specific information.

All engines (diesel emergency generators and fire pump engines) will only be tested for <30 minutes on any given day. Thus, engine fuel uses shown above are actual for ½-hour intervals.

Each boiler may be operated a maximum of 24 hours per day. Annual fuel use is based on 4380 hrs/yr at 50% load.

5.2.1.3 Climate and Meteorology

The proposed site west-northwest of Barstow, California, within the western portion of San Bernardino County, experiences the following climate and meteorology patterns.

The Mojave Desert Air Basin (MDAB) is an assemblage of mountain ranges interspersed with long broad valleys that often contain dry lakes. Many of the lower mountains which exist in this vast terrain rise from 1,000 to 4,000 feet above the valley floor. Prevailing winds in the MDAB are out of the west and southwest. These prevailing winds are due to the proximity of the MDAB to coastal and central regions and the blocking nature of the Sierra Nevada mountains to the north. Air masses pushed onshore in southern California by differential heating are channeled through the MDAB. The MDAB is separated from the southern California coastal and central California valley regions by mountains (highest elevation approximately 10,000 feet), whose passes form the main channels for these air masses. The Antelope Valley is bordered in the northwest by the Tehachapi Mountains, separated from the Sierra Nevada mountains in the north by the Tehachapi Pass (3,800 ft elevation). The Antelope Valley is bordered in the south by the San Gabriel Mountains, bisected by Soledad Canyon (3,300 ft). The Mojave Desert is bordered in the southwest by the San Bernardino Mountains, separated from the San Gabriels by the Cajon Pass (4,200 ft). A lesser channel lies between the San Bernardino Mountains and the Little San Bernardino Mountains (the Morongo Valley).

The Palo Verde Valley portion of the Mojave Desert lies in the low desert, at the eastern end of a series of valleys (notably the Coachella Valley) whose primary channel is the San Geronio Pass (2,300 ft) between the San Bernardino and San Jacinto Mountains.

During the summer, the MDAB is generally influenced by a Pacific Subtropical High cell that sits off the coast, inhibiting cloud formation and encouraging daytime solar heating. The MDAB is rarely influenced by cold air masses moving south from Canada and Alaska, as these frontal systems are weak and diffuse by the time they reach the desert. Most desert

moisture arrives from infrequent warm, moist and unstable air masses from the south. The MDAB averages between three and seven inches of precipitation per year (from 16 to 30 days with at least 0.01 inches of precipitation). The MDAB is classified as a dry-hot desert climate (BWh), with portions classified as dry-very hot desert (BWbh), to indicate at least three months have maximum average temperatures over 100.4° F.

The climatic pattern for the Project region is a typical desert climate within the Mediterranean climate classification. The warmest month for the region is typically July, with the coldest month being December. The month with the highest precipitation is usually February. The western Mojave Desert region experiences a large number of days each year with sunshine, generally 345+ days per year. The region also traditionally experiences excellent visibility, i.e., greater than 10 miles or more 95 percent of the time.

Representative climatic data for the Project area was derived from the Barstow Station (#040519), period of record 1/1/1903 to 3/31/1980. A summary of data from this site indicates the following:

- Average maximum daily temperature: 80.3°F
- Average minimum daily temperature: 47.5°F
- Highest mean maximum annual temperature: 78.3°F
- Lowest mean minimum annual temperature: 45.6°F
- Mean annual precipitation: 16.78 inches (in.)
- Highest recorded temperature: 115 °F (1995)
- Lowest recorded temperature: 12 °F (1996)

Air quality is determined primarily by the type and amount of pollutants emitted into the atmosphere, the nature of the emitting source, the topography of the air basin, and the local meteorological conditions. In the Project area, inversions and light winds can result in conditions for pollutants to accumulate in the region.

The predominant winds in the Project area are shown in Figures 5.2-1 to 5.2-5. Winds in the Project region are generally westerly (southwest through northwest), with a very much less frequent component of easterly winds. The data displayed in Figures 5.2-2 through 5.2-5 are the quarterly wind roses for the Daggett Airport Automated Surface Observing System (ASOS) site for the 2001-2004 calendar years. Calm conditions occur approximately 7.62% of the time for the Daggett Airport ASOS instruments, with the annual average wind speed being 4.87 m/s. Statistical data for the annual patterns for the Daggett Airport ASOS site is summarized in Appendix C.2.

Based on discussions with the Mojave Desert Air Quality Management District (MDAQMD), meteorological data representative of the site (presented in Appendix C.2) can be derived from the Daggett Airport ASOS station. As discussed in detail later, Daggett Airport ASOS

surface data were combined with Desert Rock, Nevada radiosonde data for 2001-2004 using the AERMOD meteorological processing programs and guidance documents.

5.2.1.4 Regulatory Environment

Although a regulatory compliance analysis (LORS) is presented in Section 5.2.5, there are several MDAQMD regulations that directly affect the permitting and review process, such as the Determination of Compliance (DOC) for the proposed Project as follows:

- New Source Review (NSR) Regulation XIII Rule 1303 requires that Best Available Control Technology (BACT) be applied to:
 - (1) Any new Permit Unit which emits, or has the Potential to Emit, 25 pounds per day or more of any Nonattainment Air Pollutant shall be equipped with BACT.
 - (2) Any Modified Permit Unit which emits, or has the Potential to Emit, 25 pounds per day or more of any Nonattainment Air Pollutant shall be equipped with BACT.
 - (3) Any new or Modified Facility which emits, or has the Potential to Emit, 25 tons per year or more of any Nonattainment Air Pollutant shall be equipped with BACT for each new Permit Unit.
- Per Regulation XIII Rule 1303, provide all required emissions mitigations prior to the commencement of construction of the source.
- Provide an impact analysis per Regulation XIII Rule 1302.
- Per Regulation XIII Rule 1302, demonstrate prior to the issuance of the Authority to Construct (ATC) that all major stationary sources owned or operated by the Applicant, which are subject to emissions limitations, are either in compliance or on a schedule for compliance with all applicable emissions limitations under the Clean Air Act (CAA).

In addition the following should be noted:

- The MDAQMD NSR rule (Regulation XIII) defines cargo carriers as trains, trucks and off-road vehicles dedicated to, or an integral part of, a specific facility.
- For purposes of calculating potential to emit, fugitive emissions from operations are not included unless the source is listed in one of the categories of sources per 40 CFR 51.165(a)(1)(iv)(C).
- For purposes of calculating potential to emit, secondary emissions from operations are not included in the sources PTE calculations.

As such, the operational emissions from fugitive sources and on-site dedicated vehicles are not included in the source's potential to emit calculations.

DISTRICT CONDITIONS

District Final Determination of Compliance Conditions (MDAQMD 2010b)

Application No. 00010710 and 00010711 (Two - 21.5 MMBtu/hr Natural Gas Fired Auxiliary Boilers)

EQUIPMENT DESCRIPTION

Two 21.5 MMBtu/hr natural gas fired auxiliary boilers with low-NOx burner systems.

AQ-1 Operation of this equipment shall be conducted in compliance with all data and specifications submitted with the application under which this permit is issued unless otherwise noted below.

Verification: The project owner shall make the site available for inspection of records by representatives of the District, ARB, and the Energy Commission.

AQ-2 This equipment shall be exclusively fueled with pipeline quality natural gas and shall be operated and maintained in strict accord with the recommendations of its manufacturer or supplier and/or sound engineering principles.

Verification: The project owner shall make the site available for inspection of records by representatives of the District, ARB, and the Energy Commission.

AQ-3 Emissions from this equipment shall not exceed the following hourly emission limits, verified by fuel use and an initial or annual compliance tests as applicable for each pollutant:

a. NOx as NO₂:

0.237 lb/hr operating at 100% load (based on 9.0 ppmvd corrected to 3% O₂ and averaged over one hour)

b. CO:

0.817 lb/hr operating at 100% load (based on 50 ppmvd corrected to 3% O₂ and averaged over one hour)

c. VOC as CH₄:

0.231 lb/hr operating at 100% load

d. SOx as SO₂:

0.0126 lb/hr operating at 100% load

e. PM_{10/2.5}:

0.159 lb/hr operating at 100% load

Verification: As part of the Annual Compliance Report, the project owner shall include information demonstrating compliance with boiler operating emission rates.

AQ-4 Prior to the expiration date each year, after the completion of construction the project owner shall have this equipment tuned, as specified by Rule 1157(I), Tuning Procedure.

Verification: The project owner shall make the site available for inspection of records by representatives of the District, ARB, and the Energy Commission.

AQ-5 The project owner shall maintain an operations log for this equipment on-site and current for a minimum of five (5) years, and said log shall be provided to District personnel on request. The operations log shall include the following information at a minimum:

- a. Cumulative annual fuel use in cubic feet or operation in hours;
- b. Annual tune-up verification;
- c. Results of annual compliance testing;
- d. Any permanent changes made to the equipment that would affect air pollutant emissions, and indicate when changes were made.

Verification: The project owner shall make the site available for inspection of records and equipment by representatives of the District, ARB, and the Energy Commission.

AQ-6 The project owner shall perform initial compliance tests on this equipment in accordance with the MDAQMD Compliance Test Procedural Manual. The test report shall be submitted to the District within 180 days of initial start up:

- a. NO_x as NO₂ in ppmvd at 3% oxygen and lb/hr (measured per USEPA Reference Methods 19 and 20).
- b. VOC as CH₄ in ppmvd at 3% oxygen and lb/hr (measured per USEPA Reference Methods 25A and 18).
- c. CO in ppmvd at 3% oxygen and lb/hr (measured per USEPA Reference Method 10).
- d. PM_{10/2.5} in mg/m³ at 3% oxygen and lb/hr (measured per USEPA Reference Methods 5 and 202 or CARB Method 5).
- e. Flue gas flow rate in dscf per minute.
- f. Opacity (measured per USEPA reference Method 9).

Verification: The project owner shall notify the District and the CPM within fifteen (15) working days before the execution of the compliance test required in this condition. The test results shall be submitted to the District and to the CPM within 180 days of initial start up.

AQ-7 The project owner shall perform annual compliance tests on this equipment in accordance with the MDAQMD Compliance Test Procedural Manual. The test

report shall be submitted to the District no later than six weeks prior to the expiration date of this permit. The following compliance tests are required:

- a. NO_x as NO₂ in ppmvd at 3% oxygen and lb/hr (measured per USEPA Reference Methods 19 and 20).
- b. CO in ppmvd at 3% oxygen and lb/hr (measured per USEPA Reference Method 10).

Verification: The project owner shall notify the District and the CPM within fifteen (15) working days before the execution of the compliance test required in this condition. The test results shall be submitted to the District and to the CPM within the timeframe required by this condition.

AQ-8 Annual fuel usage shall not exceed 45.9 MMscf verified by annual fuel usage records.

Verification: As part of the Annual Compliance Report, the project owner shall include information demonstrating compliance with boiler annual fuel use limit.

Application No. 00010906 and 00010907 (Two - HTF Ullage Expansion Tank)

EQUIPMENT DESCRIPTION

Two HTF ullage/expansion tanks.

AQ-9 Operation of this equipment shall be conducted in compliance with all data and specifications submitted with the application under which this permit is issued unless otherwise noted below.

Verification: The project owner shall make the site available for inspection of records by representatives of the District, ARB, and the Energy Commission.

AQ-10 This system shall store only HTF, specifically the condensable fraction of the vapors vented from the ullage system.

Verification: The project owner shall make the site available for inspection of records by representatives of the District, ARB, and the Energy Commission.

AQ-11 The expansion tanks (5), nitrogen-condensing tank and two vertical HTF storage tanks shall be operated at all times under a nitrogen blanket.

Verification: The project owner shall make the site available for inspection of records by representatives of the District, ARB, and the Energy Commission.

AQ-12 The ullage/expansion system nitrogen venting shall be carried out only through vents which have vapor condensing coolers which shall be maintained at or below 120 degrees Fahrenheit.

Verification: The project owner shall provide the District and CPM manufacturer design specifications showing compliance with this condition at least 30 days prior to the installation of the ullage/expansion vent system. The project owner shall have active temperature gauges that can be inspected to show compliance with this condition.

AQ-13 The HTF storage tank shall have in place a properly operating liquid HTF air cooler which shall maintain the tank at or below 165 degrees Fahrenheit.

Verification: The project owner shall provide the District and CPM manufacturer design specifications showing compliance with this condition at least 30 days prior to the installation of the HTF storage tanks. The project owner shall have active temperature gauges that can be inspected to show ongoing compliance with this condition.

AQ-14 The nitrogen condensing tanks shall be maintained at or below 176 degrees Fahrenheit.

Verification: The project owner shall provide the District and CPM manufacturer design specifications showing compliance with this condition at least 30 days prior to the installation of the nitrogen condensing tanks. The project owner shall have active temperature gauges that can be inspected to show ongoing compliance with this condition.

AQ-15 Vent release and HTF storage tank temperatures shall be monitored in accordance with a District approved Inspection, Monitoring and Maintenance plan.

Verification: The project owner shall provide the District for review and approval and the CPM for review the required Inspection, Monitoring and Maintenance plan at least 30 days prior to the installation of the HTF storage tanks and vent systems.

AQ-16 The project owner shall establish an inspection and maintenance program to determine, repair, and log leaks in HTF piping network, storage tanks, distillation units and expansion tanks. Inspection and maintenance program and documentation shall be available to District staff upon request.

- a. All pumps, compressors and pressure relief devices (pressure relief valves or rupture disks) shall be electronically, audio, or visually inspected once every operating day.
- b. All accessible valves, fittings, pressure relief devices (PRDs), hatches, pumps, compressors, etc. shall be inspected quarterly using a leak detection device such as a Foxboro OVA 108 calibrated for methane.
- c. VOC leaks greater than 100-ppmv shall be tagged (with date and concentration) and repaired within seven calendar days of detection.
- d. VOC leaks greater than 10,000-ppmv shall be tagged and repaired within 24-hours of detection.
- e. The project owner shall maintain a log of all VOC leaks exceeding 10,000-ppmv, including location, component type, and repair made.
- f. The project owner shall maintain record of the amount of HTF replaced on a monthly basis for a period of five (5) years.

- g. The project owner shall maintain record of the amount of HTF degradation products removed from system on a monthly basis for a period of five (5) years
- h. Any detected leak exceeding 100-ppmv and not repaired in 7-days and 10,000-ppmv not repaired within 24-hours shall constitute a violation of this Authority to Construct ATC/Permit to Operate (PTO).
- i. The project owner shall place an adequate number of isolation valves in the Heat transfer Fluid (HTF) pipe loops so as to be able to isolate a solar panel collector loop in the event of a leak of fluid. These valves shall be actuated automatically, manually, and remotely, or locally as determined during detailed engineering design. The detailed engineering design drawings showing the number, location, and type of isolation valves shall be provided to the District for review and approval prior to the commencement of the solar array construction.

Verification: The inspection and maintenance plan shall be submitted to the CPM for review and approval at least 30 days before taking delivery of the HTF. As part of the Annual Compliance Report, the project owner shall provide the quantity of used HTF fluid removed from the system and the amount of new HTF fluid added to the system each year. The project owner shall make the site available for inspection of HTF piping Inspection and Maintenance Program records and HTF system equipment by representatives of the District, ARB, and the Energy Commission.

AQ-17 The project owner shall submit to the District a compliance test protocol within sixty (60) days of start-up and shall conduct all required compliance/certification tests in accordance with a District-approved test plan. Thirty (30) days prior to the compliance/certification tests the project owner shall provide a written test plan for District review and approval. Written notice of the compliance/certification test shall be provided to the District ten (10) days prior to the tests so that an observer may be present. A written report with the results of such compliance/certification tests shall be submitted to the District within forty-five (45) days after testing.

Verification: The project owner shall provide a compliance test protocol to the District for approval and CPM for review at least no later than sixty (60) days after start-up and submit a test plan to the District for approval and CPM for review at least thirty (30) days prior to the compliance tests. The project owner shall notify the District and the CPM within ten (10) working days before the execution of the compliance tests required in **AQ-18** and **AQ-19**, and the test results shall be submitted to the District and to the CPM within forty-five (45) days after the tests are conducted.

AQ-18 The project owner shall perform the following initial compliance tests on this equipment in accordance with the MDAQMD Compliance Test Procedural Manual. The test report shall be submitted to the District within 180 days of initial start up. The following compliance tests are required:

- a. VOC as CH₄ in ppmvd and lb/hr (measured per USEPA Reference Methods 25A and 18 or equivalent).

- b. Benzene in ppmvd at and lb/hr (measured per CARB method 410 or equivalent).

Verification: The project owner shall submit the test results to the District and to the CPM within 180 days after initial start up.

AQ-19 The project owner shall perform the following annual compliance tests on this equipment in accordance with the MDAQMD Compliance Test Procedural Manual. The test report shall be submitted to the District no later than six weeks prior to the expiration date of this permit. The following compliance tests are required:

- a. VOC as CH₄ in ppmvd and lb/hr (measured per USEPA Reference Methods 25A and 18 or equivalent).
- b. Benzene in ppmvd and lb/hr (measured per CARB method 410 or equivalent).

Additionally, records of all compliance tests shall be maintained on site for a period of five (5) years and presented to District personnel upon request.

Verification: As part of the Annual Compliance Report, the project owner shall include the test results demonstrating compliance with this condition and the project owner shall make the site available for inspection of records by representatives of the District, ARB, and the Energy Commission.

AQ-20 Emissions from this equipment may not exceed the following emission limits, based on a calendar day summary:

- a. VOC as CH₄ – 4.55 lb/day, verified by compliance test.
- b. Benzene – 1.9 lb/day, verified by compliance test.

Verification: As part of the Annual Compliance Report, the project owner shall include the test results demonstrating compliance with this condition and the project owner shall make the site available for inspection of records by representatives of the District, ARB, and the Energy Commission.

AQ-21 If current non-criteria substances become regulated as toxic or hazardous substances and are used in this equipment, the project owner shall submit to the District a plan demonstrating how compliance will be achieved and maintained with such regulations.

Verification: The project owner shall submit a compliance plan of the toxic or hazardous substances for District approval and CPM review if current non-criteria substances in the HTF become regulated as toxic or hazardous substances.

Application No. 00010947 and 00010948 (Two Cooling Towers)

EQUIPMENT DESCRIPTION

Two 6-cell cooling towers with drift eliminator rate of 0.0005% and water circulation rate of 90,000 gpm.

AQ-22 Operation of this equipment shall be conducted in compliance with all data and specifications submitted with the application under which this permit is issued unless otherwise noted below.

Verification: The project owner shall make the site available for inspection of records and equipment by representatives of the District, ARB, and the Energy Commission.

AQ-23 This equipment shall be operated and maintained in strict accord with the recommendations of its manufacturer or supplier and/or sound engineering principles.

Verification: The project owner shall make the site available for inspection of records and equipment by representatives of the District, ARB, and the Energy Commission.

AQ-24 The drift rate shall not exceed 0.0005 percent with a maximum circulation rate of 90,000 gallons per minute. The maximum hourly PM10 emission rate shall not exceed 2.24 pounds per hour, as calculated per the written District-approved protocol.

Verification: The manufacturer guarantee data for the drift eliminator, showing compliance with this condition, shall be provided to the CPM and the District 30 days prior to cooling tower operation. As part of the Annual Compliance Report the project owner shall include information on operating emission rates to demonstrate compliance with this condition.

AQ-25 The project owner shall perform weekly specific conductivity tests of the blow-down water to indirectly measure total dissolved solids (TDS). Quarterly tests of the blow-down water will be done to confirm the relationship between conductance and TDS. The TDS shall not exceed 10,000 ppm on a calendar monthly basis.

Verification: The cooling tower recirculation water TDS content test results shall be provided to representatives of the District, ARB, and the Energy Commission upon request.

AQ-26 The project owner shall conduct all required cooling tower water tests in accordance with a District-approved test and emissions calculation protocol. Thirty (30) days prior to the first such test the project owner shall provide a written test and emissions calculation protocol for District review and approval.

Verification: The project owner shall provide an emissions calculation and water sample testing protocol to the District for approval and CPM for review at least 30 days prior to the first cooling tower water test.

AQ-27 This equipment shall not be operated for more than 5,840 hours per rolling twelve month period.

Verification: The project owner shall submit to the CPM the cooling tower operating data demonstrating compliance with this condition as part of the Annual Operation Report.

AQ-28 The project owner shall maintain an operations log for this equipment on-site and current for a minimum of five (5) years, and said log shall be provided to District personnel on request. The operations log shall include the following information at a minimum:

- a. Total operation time (hours per day, hours per month, and hours per rolling twelve month period); and
- b. The date and result of each blow-down water test in TDS ppm, and the resulting mass emission rate.

Verification: The project owner shall make the site available for inspection of records and equipment by representatives of the District, ARB, and the Energy Commission.

AQ-29 A maintenance procedure shall be established that states how often and what procedures will be used to ensure the integrity of the drift eliminators. This procedure is to be kept onsite and available to District personnel on request.

Verification: The project owner shall make available at request the written drift eliminator maintenance procedures for inspection by representatives of the District, ARB, and the Energy Commission.

Application No. 00010712 and 00010713 (Two - 4,190 HP Emergency IC Engine)

EQUIPMENT DESCRIPTION

Two - Tier II 4,190 HP diesel fueled emergency generator engines, each driving a generator.

AQ-30 This equipment shall be installed, operated and maintained in strict accord with those recommendations of the manufacturer/supplier and/or sound engineering principles which produce the minimum emissions of contaminants. Unless otherwise noted, this equipment shall also be operated in accordance with all data and specifications submitted with the application for this permit.

Verification: The project owner shall make the site available for inspection of equipment and records by representatives of the District, ARB, and the Energy Commission

AQ-31 This unit shall only be fired on ultra-low sulfur diesel fuel, whose sulfur concentration is less than or equal to 0.0015% (15 ppm) on a weight per weight basis per CARB Diesel or equivalent requirements.

Verification: The project owner shall make the site available for inspection of equipment and fuel purchase records by representatives of the District, ARB, and the Energy Commission.

AQ-32 A non-resettable hour meter with a minimum display capability of 9,999 hours shall be installed and maintained on this unit to indicate elapsed engine operating time. (Title 17 CCR §93115.10(e)(1)).

Verification: At least thirty (30) days prior to the installation of the engine, the project owner shall provide the District and the CPM the specification of the hour meter.

AQ-33 This unit shall be limited to use for emergency power, defined as in response to a fire or when utility back-feed power is not available. In addition, this unit shall be operated no more than 0.5 hours per day and 50 hours per year for testing and maintenance, excluding compliance source testing. Time required for source testing will not be counted toward the 50 hour per year limit.

Verification: The project owner shall make the site available for inspection of records and equipment by representatives of the District, ARB, and the Energy Commission.

AQ-34 The project owner shall maintain a operations log for this unit current and on-site, either at the engine location or at a on-site location, for a minimum of two (2) years, and for another year where it can be made available to the District staff within five (5) working days from the District's request, and this log shall be provided to District, State and Federal personnel upon request. The log shall include, at a minimum, the information specified below:

- a. Date of each use and duration of each use (in hours);
- b. Reason for use (testing & maintenance, emergency, required emission testing);
- c. Calendar year operation in terms of fuel consumption (in gallons) and total hours; and,
- d. Fuel sulfur concentration (the project owner may use the supplier's certification of sulfur content if it is maintained as part of this log).

Verification: The project owner shall submit records required by this condition that demonstrating compliance with the sulfur content and engine use limitations of conditions **AQ-28** and **AQ-30** in the Annual Compliance Report, including a photograph showing the annual reading of engine hours. The project owner shall make the site available for inspection of records by representatives of the District, ARB, and the Energy Commission.

AQ-35 This unit shall not be used to provide power to the interconnecting utility and shall be isolated from the interconnecting utility when operating.

Verification: The project owner shall make the site available for inspection of records and equipment by representatives of the District, ARB, and the Energy Commission.

AQ-36 This engine may operate in response to notification of impending loss of utility back-feed power if the interconnected utility has ordered an outage to the plant or expects to order such outages at a particular time, the engine is operated no more than 30 minutes prior to the forecasted outage, and the engine is shut down immediately after the utility advises that the outage is no longer imminent or in effect.

Verification: The project owner shall make the site available for inspection of records and equipment by representatives of the District, ARB, and the Energy Commission.

AQ-37 No two permitted stationary emergency engines (emergency generators or emergency fire pump engines) ~~Equipment with valid District permit numbers E0XXXX, E0XXXX, E0XXXX and E0XXXX shall not be~~ readiness tested on the same calendar day.

Verification: The project owner shall make the site available for inspection of records and equipment by representatives of the District, ARB, and the Energy Commission.

AQ-38 This engine shall exhaust through a stack at a minimum height of 60 feet.

Verification: The project owner shall make the site available for inspection of equipment by representatives of the District, ARB, and the Energy Commission.

AQ-39 This unit is subject to the requirements of the Airborne Toxic Control Measure (ATCM) for Stationary Compression Ignition Engines (Title 17 CCR 93115). In the event of conflict between these conditions and the ATCM, the more stringent shall govern.

Verification: Not necessary.

AQ-40 This unit is subject to the requirements of the Federal National Source Performance Standards (NSPS) for Stationary Compression Ignition Internal Combustion Engines (40 CFR Part 60 Subpart IIII).

Verification: The project owner shall submit the engine specifications at least 30 days prior to purchasing the engines for review and approval demonstrating that the engines meet NSPS and ARB ATCM emission limit requirements at the time of engine purchase.

Application No. 00010714 and 00010715 (Two - 346 HP Emergency IC Engine)

EQUIPMENT DESCRIPTION

Two - Tier III 346 HP diesel fueled emergency generator engines, each driving a fire suppression water pump.

AQ-41 This equipment shall be installed, operated and maintained in strict accord with those recommendations of the manufacturer/supplier and/or sound engineering principles which produce the minimum emissions of contaminants. Unless otherwise noted, this equipment shall also be operated in accordance with all data and specifications submitted with the application for this permit.

Verification: The project owner shall make the site available for inspection of equipment and records by representatives of the District, ARB, and the Energy Commission

AQ-42 This unit shall only be fired on ultra-low sulfur diesel fuel, whose sulfur concentration is less than or equal to 0.0015% (15 ppm) on a weight per weight basis per CARB Diesel or equivalent requirements.

Verification: The project owner shall make the site available for inspection of equipment and fuel purchase records by representatives of the District, ARB, and the Energy Commission.

AQ-43 A non-resettable hour meter with a minimum display capability of 9,999 hours shall be installed and maintained on this unit to indicate elapsed engine operating time. (Title 17 CCR §93115.10(e)(1)).

Verification: At least thirty (30) days prior to the installation of the engine, the project owner shall provide the District and the CPM the specification of the hour timer.

AQ-44 This unit shall be limited to use for emergency fire suppression, defined as in response to a fire or due to low fire water pressure. In addition, this unit shall be operated no more than 50 hours per year for testing and maintenance, excluding compliance source testing. Time required for source testing will not be counted toward the 50 hour per year limit. The 50 hour limit can be exceeded when the emergency fire pump assembly is driven directly by a stationary diesel fueled CI engine operated per and in accord with the National Fire Protection Association (NFPA) 25 - "Standard for the Inspection, Testing, and Maintenance of Water-Based Fire Protection Systems," 1998 edition. This requirement includes usage during emergencies. {Title 17 CCR 93115.3(n)}

Verification: The project owner shall make the site available for inspection of records and equipment by representatives of the District, ARB, and the Energy Commission.

AQ-45 The project owner shall maintain a operations log for this unit current and on-site, either at the engine location or at a on-site location, for a minimum of two (2) years, and for another year where it can be made available to the District staff within five (5) working days from the District's request, and this log shall be provided to District, State and Federal personnel upon request. The log shall include, at a minimum, the information specified below:

- a. Date of each use and duration of each use (in hours);
- b. Reason for use (testing & maintenance, emergency, required emission testing);
- c. Calendar year operation in terms of fuel consumption (in gallons) and total hours; and,
- d. Fuel sulfur concentration (the project owner may use the supplier's certification of sulfur content if it is maintained as part of this log).

Verification: The project owner shall submit records required by this condition that demonstrating compliance with the sulfur content and engine use limitations of conditions **AQ-42, AQ-44, and AQ-46** in the Annual Compliance Report, including a photograph showing the annual reading of engine hours. The project owner shall make the site available for inspection of records by representatives of the District, ARB, and the Energy Commission.

AQ-46 No two permitted stationary emergency engines (emergency generators or emergency fire pump engines) ~~Equipment with valid District permit numbers E0XXXX, E0XXXX, E0XXXX and E0XXXX~~ shall not be readiness tested on the same calendar day.

Verification: The project owner shall make the site available for inspection of records and equipment by representatives of the District, ARB, and the Energy Commission.

AQ-47 This engine shall exhaust through a stack at a minimum height of 60 feet.

Verification: The project owner shall make the site available for inspection of equipment by representatives of the District, ARB, and the Energy Commission.

AQ-48 This unit is subject to the requirements of the Airborne Toxic Control Measure (ATCM) for Stationary Compression Ignition Engines (Title 17 CCR 93115). In the event of conflict between these conditions and the ATCM, the requirements of the ATCM shall govern.

Verification: Not necessary.

AQ-49 This unit is subject to the requirements of the Federal National Source Performance Standards (NSPS) for Stationary Compression Ignition Internal Combustion Engines (40 CFR Part 60 Subpart IIII).

Verification: The project owner shall submit the engine specifications at least 30 days prior to purchasing the engines for review and approval demonstrating that the engines meet NSPS and ARB ATCM emission limit requirements at the time of engine purchase.

Application No. 00010995 (One – Gasoline Storage Tank)

EQUIPMENT DESCRIPTION

One – Above ground gasoline storage tank and fuel receiving and dispensing equipment.

AQ-50 The toll-free telephone number that must be posted is 1-800-635-4617.

Verification: The project owner shall make the site available for inspection of records by representatives of the District, ARB, and the Energy Commission.

AQ-51 The project owner shall maintain a log of all inspections, repairs, and maintenance on equipment subject to Rule 461. Such logs or records shall be maintained at the facility for at least two (2) years and shall be available to the District upon request.

Verification: The project owner shall make the site available for inspection of records by representatives of the District, ARB, and the Energy Commission.

AQ-52 Any modifications or changes to the piping or control fitting of the vapor recovery system require prior approval from the District.

Verification: The project owner shall make the site available for inspection of records by representatives of the District, ARB, and the Energy Commission.

AQ-53 The gasoline vapor vent pipe(s) are to be equipped with pressure relief valve(s) per applicable CARB requirements.

Verification: The project owner shall make the site available for inspection of records by representatives of the District, ARB, and the Energy Commission.

AQ-54 The project owner shall perform the following tests within 60 days of construction completion and annually thereafter in accordance with the applicable CARB test methods.

The District shall be notified a minimum of 10 days prior to performing the required tests with the final results submitted to the District within 30 days of completion of the tests.

The District shall receive passing test reports no later than six (6) weeks prior to the expiration date of this permit.

Verification: The project owner shall notify the District at least 10 days prior to performing the required tests. The test results shall be submitted to the District within 30 days of completion of the tests and shall be made available to the CPM if requested.

AQ-55 The annual throughput of gasoline shall not exceed 25,000 gallons per year. Throughput Records shall be kept on site and available to District personnel upon request. Before this annual throughput can be increased the facility may be required to submit to the District a site specific Health Risk Assessment in accord with a District approved plan. In addition public notice and/or comment period may be required.

Verification: The project owner shall submit to the CPM gasoline throughput records demonstrating compliance with this condition as part of the Annual Compliance Report. The project owner shall maintain on site the annual gasoline throughput records and shall make the site available for inspection of records by representatives of the District, ARB, and the Energy Commission.

AQ-56 The project owner shall install, operate, and maintain CARB approved Phase I and Phase II vapor recovery systems on the proposed facility gasoline tank and dispensing system. The Phase I and Phase II vapor recovery systems will meet all applicable CARB standards at the time of installation for the systems selected.

Verification: The project owner shall make the site available for inspection of records by representatives of the District, ARB, and the Energy Commission.

AQ-57 The California Air Resources Board (CARB) has established a timeline for Aboveground Storage Tanks (AST) Enhanced Vapor Recovery (EVR) system implementation. Pursuant to CARB requirements and State mandated retrofits, the project owner shall ensure that this tank meets all the applicable requirements within the designated timeframes. Prior to conducting any modifications the project owner shall obtain a District approved Authority to Construct (ATC) Permit. See the following link for AST EVR Timeline: http://o3.arb.ca.gov/vapor/asttimeline_123009.pdf

Verification: The project owner shall provide the District and the CPM documentation, at least 30 days prior to installation, showing that the tank at the time of installation will meet appropriate ARB EVR requirements.

REFERENCES

- AD 2010a - Atmospheric Dynamics / G. Darvin (TN 56545). Revised Mojave Solar 1-hour NO₂ Modeling Assessment, dated 5/3/2010. Submitted to CEC on 5/4/2010.
- ARB 2005 - California Air Resources Board. Characterization of Ambient PM₁₀ and PM_{2.5} in California, Technical Report. June 2005.
- ARB 2010a - California Air Resources Board. California Ambient Air Quality Standards available on ARB Website. <http://www.arb.ca.gov/aqs/aqs.htm>. Accessed February, 2010.
- ARB 2010b - California Air Resources Board. Air Designation Maps available on ARB website. <http://www.arb.ca.gov/design/adm/adm.htm>. Accessed February, 2010.
- ARB 2010c - California Air Resources Board. California Ambient Air Quality Data Statistics available on ARB website. <http://www.arb.ca.gov/adam/welcome.html>. Accessed February, 2010.
- AS 2009a- Abengoa Solar Inc. / E. Garcia (TN 52813). Application for Certification for Mojave Solar Project (09-AFC-5), dated 7/2009. Submitted to CEC on 8/10/2009.
- AS 2009b- Abengoa Solar Inc. / E. Garcia (TN 53375). Data Adequacy Supplement for Mojave Solar Project (09-AFC-5), dated 9/24/2009. Submitted to CEC on 9/24/2009.
- CCR 2006. California Code of Regulations, Chapter 3 (CEQA Guidelines), Article 17, §§15250—15253 as amended on July 11, 2006.
- CEC 2010g - CEC / M. Layton (TN 55783). Comments on Preliminary Determination of Compliance (PDOC), dated 3/8/2010.
- CEC 2010o - CEC (TN 56745). Energy Commission Staff Estimate for Construction & On-road Operation Emissions. Submitted to Dockets 5/19/2010.
- ESH 2009c - Ellison, Schneider and Harris / C. Ellison (TN 54243). Written Responses to Data Request Set 1 (nos. 1-93), dated 11/23/09. Submitted to CEC on 11/24/2009.
- ESH 2010e - Ellison, Schneider and Harris / C. Ellison (TN 54756). Supplemental Written Response to Data Request Set 1A (nos. 1-93) for Air Quality and Public Health, dated 1/11/10. Submitted to CEC on 1/11/2010.

Appendix C

Air Quality & Public Health Supporting Documentation

APPENDIX C.1

Calculation of Maximum Hourly, Daily, and Annual Emissions

Tables presented in this Appendix are as follows:

C.1-1	Auxiliary Boilers #1 and #2 Emissions
C.1-2	Auxiliary Boilers #1 and #2 HAP Emissions
C.1-3	Emergency Generators #1 and #2 Emissions
C.1-4	Fire Pump Engines #1 and #2 Emissions
C.1-5	Cooling Towers #1 and #2 Emissions
C.1-6	Cooling Towers #1 and #2 HAP Emissions
C.1-7	Dedicated Site Vehicle Emissions

Also included in this appendix:

Attachment C.1-1	HTF Fugitive Venting and System Loss Emissions
Attachment C.1-2	Engine Specification Sheets
Attachment C.1-3	Auxiliary Boiler Specification Sheets
Attachment C.1-4	Cooling Tower Specification Sheets
Attachment C.1-5	Diesel Fuel Analysis Data
Attachment C.1-6	Natural Gas Fuel Analysis Data
Attachment C.1-7	HTF MSDS
Attachment C.1-8	Vehicle Use Rate and Growth Data (1980-2020)

Table C.1-1 Boilers #1 and #2
Calculation of Criteria Pollutant Emissions for Boilers Firing Gaseous Fuels
Boiler Operation Mode: Normal firing mode

Ops Hr/Day: 24 Worst Case
Ops Hr/Yr: 4380

of Units: 2
Fuel Type: Nat Gas

Calculation of Criteria Pollutant Emissions from Each Identical Unit

Compound	Emission Factor, lb/MMscf (1)	Maximum				All Units			
		Hourly Emissions, lb/hr (2)	Daily Emissions, lb/day	Annual Emissions, lbs/yr	Annual Emissions, ton/yr (3)	Maximum Hourly Emissions, lb/hr	Maximum Daily Emissions, lb/day	Maximum Annual Emissions, lbs/yr	Annual Emissions, ton/yr
NOx	1.13E+01	2.37E-01	5.68E+00	5.18E+02	2.59E-01	4.73E-01	1.14E+01	1.04E+03	5.18E-01
CO	3.90E+01	8.17E-01	1.96E+01	1.79E+03	8.95E-01	1.63E+00	3.92E+01	3.58E+03	1.79E+00
VOC	1.10E+01	2.31E-01	5.54E+00	5.05E+02	2.53E-01	4.61E-01	1.11E+01	1.01E+03	5.05E-01
SOx	6.00E-01	1.26E-02	3.02E-01	2.76E+01	1.38E-02	2.52E-02	6.04E-01	5.51E+01	2.76E-02
PM10	7.60E+00	1.59E-01	3.83E+00	3.49E+02	1.75E-01	3.19E-01	7.65E+00	6.98E+02	3.49E-01
PM2.5	7.60E+00 lbs/mmBtu	1.59E-01	3.83E+00	3.49E+02	1.75E-01	3.19E-01	7.65E+00	6.98E+02	3.49E-01
CO2	1.17E+02	2.51E+03	6.03E+04	1.10E+07	5.51E+03	5.03E+03	1.21E+05	2.20E+07	1.10E+04
Methane	1.30E-02	2.80E-01	6.71E+00	1.22E+03	6.12E-01	5.59E-01	1.34E+01	2.45E+03	1.22E+00
N2O	2.21E-04	4.74E-03	1.14E-01	2.08E+01	1.04E-02	9.48E-03	2.28E-01	4.15E+01	2.08E-02
CO2e									1.10E+04
Notes:	(1) natural gas criteria pollutant EF factors (2) Based on maximum hourly boiler fuel use of 1025 and fuel HHV of 1025 (3) Based on maximum annual boiler fuel use of 1025 and fuel HHV of 1025 (4) LNBs only with GCPs (5) PM2.5 = PM10								
					Btu/scf gives	21.5	MMBtu/hr/boiler		
					Btu/scf gives	0.0210	MMscf/hr/boiler.		
					Btu/scf gives	47.085	MMBtu/yr/boiler		
					Btu/scf gives	45.9366	MMscf/yr/boiler.		

Refs: (1) EFs from AP-42, Section 1.4, 7/98, and SCAQMD Rules 1146, and 1146.1.
(2) GHG EFs from CCAR General Protocol, June 2006.

Table C.1-2 Boiler #1 and #2
Calculation of Noncriteria Pollutant Emissions for Boilers Firing Gaseous Fuels
Boiler Operation Mode: Normal firing mode
Ops Hr/Day: 24 **Worst Case**
Ops Hr/Yr: 4380

of Units: 2
Fuel Type: Nat Gas

Calculation of Noncriteria Pollutant Emissions from Each Identical Unit

Compound	Emission Factor, lb/MMscf (1)	Maximum					All Units			
		Hourly Emissions, lb/hr (2)	Daily Emissions, lb/day	Annual Emissions, lbs/yr	Annual Emissions, ton/yr (3)	Maximum Hourly Emissions, lb/hr	Maximum Daily Emissions, lb/day	Maximum Annual Emissions, lbs/yr	Annual Emissions, ton/yr	
Acetaldehyde	4.61E-03	9.67E-05	2.32E-03	4.44E-03	2.22E-06	1.93E-04	4.64E-03	8.88E-03	4.44E-06	
Acrolein	4.51E-03	9.46E-05	2.27E-03	4.35E-03	2.17E-06	1.89E-04	4.54E-03	8.69E-03	4.35E-06	
Ammonia	(5)	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	
Benzene	2.43E-03	5.10E-05	1.22E-03	2.34E-03	1.17E-06	1.02E-04	2.45E-03	4.68E-03	2.34E-06	
1,3-Butadiene	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	
Ethylbenzene	2.25E-03	4.72E-05	1.13E-03	2.17E-03	1.08E-06	9.44E-05	2.27E-03	4.34E-03	2.17E-06	
Formaldehyde	4.75E-03	9.96E-05	2.39E-03	4.58E-03	2.29E-06	1.99E-04	4.78E-03	9.15E-03	4.58E-06	
Hexane	6.30E-03	1.32E-04	3.17E-03	6.07E-03	3.04E-06	2.64E-04	6.34E-03	1.21E-02	6.07E-06	
Naphthalene	2.37E-04	4.97E-06	1.19E-04	2.28E-04	1.14E-07	9.94E-06	2.39E-04	4.57E-04	2.28E-07	
PAHs (4)	8.10E-05	1.70E-06	4.08E-05	7.80E-05	3.90E-08	3.40E-06	8.16E-05	1.56E-04	7.80E-08	
Propylene	4.63E-01	9.71E-03	2.33E-01	4.46E-01	2.23E-04	1.94E-02	4.66E-01	8.92E-01	4.46E-04	
Propylene oxide	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	
Toluene	3.23E-02	6.78E-04	1.63E-02	3.11E-02	1.56E-05	1.36E-03	3.25E-02	6.22E-02	3.11E-05	
Xylene	1.87E-02	3.92E-04	9.41E-03	1.80E-02	9.01E-06	7.84E-04	1.88E-02	3.60E-02	1.80E-05	
		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	
		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	
		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	
		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	
		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	
		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	
		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	
		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	
		0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	

Notes:
(1) natural gas HAPs emission factors
(2) Based on maximum hourly boiler fuel use of 1025 Btu/scf gives
and fuel HHV of 1025
(3) Based on maximum annual boiler fuel use of 47,085 Btu/scf gives
and fuel HHV of 1025
(4) Polycyclic aromatic hydrocarbons, excluding naphthalene (treated separately).
(5) LNB only with GCPs

Refs:
CARB Catref Database, Heater, NG, SCC 31000404
SDAPCD, B17, Toxics EFs Database

Table C.1-3 EXPECTED INTERNAL COMBUSTION ENGINE EMISSIONS

Liquid Fuel

of Identical Engines: 2

Emergency Generator

Mfg: Caterpillar

Stack Data

Engine #: 3516C-HD TA

Height: 46 Ft.

Kw 2500 approx.

Diameter: 1 Ft.

BHP: 4190

Temp: 922 deg F

RPM: -

ACFM: 19049

Fuel: #2 Diesel

input the mfg ACFM or calculate per Exhaust sheet)

Fuel Use: 173.3 Gph (1)

Area: 0.785 Sq.Ft.

FuelHHV: 139000 Btu/gal

Velocity: 404 Ft/Sec

mmbtu/hr: 24.09 HHV

Max Daily Op Hrs: 1

Max Annual Op Hrs: 52

If the engines will operate less than an hour for purposes of testing, use the final emissions values on page 2.

Fuel Wt: 6.87 Lbs/gal

Fuel S: 0.0015 % wt.

Fuel S: 0.10305 Lbs/1000 gal

SO₂: 0.2061 Lbs/1000 gal

		Single Engine				All Engines			
EFs (g/bhp-hr)		Lb/Hr	Lb/Day	Lbs/Yr	Tons/Yr	Lb/Hr	Lb/Day	Lbs/Yr	Tons/Yr
NO _x	5.05	46.61	46.61	2423.56	1.212	93.21	93.21	4847.11	2.42
CO	0.41	3.78	3.78	196.76	0.098	7.57	7.57	393.53	0.20
VOC	0.1	0.92	0.92	47.99	0.024	1.85	1.85	95.98	0.05
PM ₁₀	0.036	0.33	0.33	17.28	0.009	0.66	0.66	34.55	0.017
SO _x	NA	0.04	0.04	1.86	0.0009	0.07	0.07	3.71	0.002
	lbs/gal								
CO ₂	22.38	3878	3878	201680	101	7757	7757	403359	202
Methane	0.0003	0.05	0.05	2.70	0.001	0.10	0.10	5.41	0.003
N ₂ O	0.0001	0.02	0.02	0.90	0.0005	0.03	0.03	1.80	0.0009
CO ₂ e					101.0				202.0

Notes:

1. fuel consumption based on 0.055 gal/hp-hr (avg EPA and SCAQMD values)
if no value given by mfg for specific engine.
2. PM₁₀ equals PM_{2.5}.
3. PM₁₀ used in HRA to represent DPM emissions.
4. GHG EFs from CCAR General Protocol, June 2006.

Page 2

Max Daily Op Time: 0.5 hrs

Max Annual # Tests: 52

		Single Engine				All Engines			
		Lb/Hr	Lb/Day	Lbs/Yr	Tons/Yr	Lb/Hr	Lb/Day	Lbs/Yr	Tons/Yr
NO _x		23.30	23.30	1211.78	0.61	46.61	46.61	2423.56	1.21
CO		1.89	1.89	98.38	0.05	3.78	3.78	196.76	0.10
VOC		0.46	0.46	24.00	0.01	0.92	0.92	47.99	0.02
PM ₁₀		0.17	0.17	8.64	0.0043	0.33	0.33	17.28	0.0086
SO _x		0.02	0.02	0.93	0.0005	0.04	0.04	1.86	0.0009
CO ₂		1939	1939	100840	50	3878	3878	201680	101
Methane		0.03	0.03	1.35	0.00	0.05	0.05	2.70	0.00
N ₂ O		0.01	0.01	0.45	0.00	0.02	0.02	0.90	0.00
CO ₂ e					50.50				101.01

Liquid Fuel

Emergency Fire Pump

Mfg: John Deere

Engine #: 6090H

Kw 0 approx.

BHP: 346

RPM: -

Fuel: #2 Diesel

Fuel Use: 7.6 Gph (1)

FuelHHV 139000 Btu/gal

mmbtu/hr 1.06 HHV

of Identical Engines: 2

Stack Data

Height: 46 Ft.

Diameter: 0.67 Ft.

Temp: 821 deg F

ACFM: 2643

input the mfg ACFM or calculate per Exhaust sheet)

Area: 0.353 Sq.Ft.

Velocity: 125 Ft/Sec

Max Daily Op Hrs: 1

Max Annual Op Hrs: 52

If the engines will operate less than an hour for purposes of testing, use the final emissions values on page 2.

Fuel Wt: 6.87 Lbs/gal

Fuel S: 0.0015 % wt.

Fuel S: 0.10305 Lbs/1000 gal

SO2: 0.2061 Lbs/1000 gal

Single Engine					All Engines				
EFs (g/bhp-hr)	Lb/Hr	Lb/Day	Lbs/Yr	Tons/Yr	Lb/Hr	Lb/Day	Lbs/Yr	Tons/Yr	
NOx	2.8	2.13	2.13	110.96	0.055	4.27	4.27	221.93	0.11
CO	2.6	1.98	1.98	103.04	0.052	3.96	3.96	206.08	0.10
VOC	0.2	0.15	0.15	7.93	0.004	0.30	0.30	15.85	0.01
PM10	0.15	0.11	0.11	5.94	0.003	0.23	0.23	11.89	0.006
SOx	NA	0.0016	0.0016	0.0815	0.0000	0.0031	0.0031	0.1629	0.0001
	lbs/gal								
CO2	22.38	170	170	8845	4	340	340	17689	9
Methane	0.0003	0.0023	0.0023	0.1186	0.0001	0.0046	0.0046	0.2371	0.0001
N2O	0.0001	0.0008	0.0008	0.0395	0.0000	0.0015	0.0015	0.0790	0.0000
CO2e				4.4					8.9

Notes:

1. fuel consumption based on 0.055 gal/hp-hr (avg EPA and SCAQMD values)
if no value given by mfg for specific engine.
2. PM10 equals PM2.5.
3. PM10 used in HRA to represent DPM emissions.
4. GHG EFs from CCAR General Protocol, June 2006.

Page 2

Max Daily Op Time: 0.5 hrs

Max Annual # Tests: 52

Single Engine					All Engines				
	Lb/Hr	Lb/Day	Lbs/Yr	Tons/Yr	Lb/Hr	Lb/Day	Lbs/Yr	Tons/Yr	
NOx	1.07	1.07	55.48	0.03	2.13	2.13	110.96	0.06	
CO	0.99	0.99	51.52	0.03	1.98	1.98	103.04	0.05	
VOC	0.0762	0.0762	3.9630	0.0020	0.1524	0.1524	7.9260	0.0040	
PM10	0.0572	0.0572	2.9722	0.0015	0.1143	0.1143	5.9445	0.0030	
SOx	0.0008	0.0008	0.0407	0.0000	0.0016	0.0016	0.0815	0.0000	
CO2	85	85	4422	2	170	170	8845	4	
Methane	0.0011	0.0011	0.0593	0.0000	0.0023	0.0023	0.1186	0.0001	
N2O	0.0004	0.0004	0.0198	0.0000	0.0008	0.0008	0.0395	0.0000	
CO2e				2.21				4.43	

Table C.1-5 Cooling Towers #1 and #2

Cooling Tower Particulate Emissions					
# of Identical Towers: Operational Schedule:	2		Days/Yr 365	Hrs/Yr 5840	Per Tower
	Hrs/day 16	Hrs/Yr 5840			
Pumping rate of recirculation pumps (gal/min)					90,000.0
Flow of cooling water (lbs/hr)					44,982,000.0
Avg TDS of circ water (mg/l or ppmw)					9,968.0
Flow of dissolved solids (lbs/hr)					448380.58
Fraction of flow producing drift*					0.31
Control efficiency of drift eliminators, %	0.0005				0.000005
Calculated drift rate (lbs water/hr)					224.9
PM10 emissions (lbs/hr)					0.69
PM10 emissions (lbs/day)					11.12
PM10 emissions (tpy)					2.03
PM2.5 fraction of PM10 per CARB CEIDARS App A.					0.60
PM2.5 emissions (lbs/hr)					0.42
PM2.5 emissions (lbs/day)					6.67
PM2.5 emissions (tpy)					1.22
					0.12
					1.85
					0.34
					0.07
					1.11
					0.20
					1.39
					22.24
					4.06
					0.83
					13.34
					2.44

Notes:

Based on Method AP 42, Section 13.4, Jan 1995

*Technical Report EPA-600-7-79-251a, Page 63

Effects of Pathogenic and Toxic Materials Transported Via Cooling Device Drift - Volume 1.

Cooling Tower Stack Parameters

Base Elevation	2060	feet amsl
Number of Cells	6	
Length of Cooling Tower	325.00	feet
Width of Cooling Tower	54.00	feet
Height of Cooling Tower (to fan deck)	37.00	feet agl
Cell Release Height (fan shroud exit)	51.00	feet agl
Flow/Fan Discharge for each Cell	1,310,000	ACFM
Inlet air temperature (ambient):	variable	deg F
Discharge air temperature:	variable	deg F

Table C.1-6

Calculation of Hazardous and Toxic Pollutant Emissions from Cooling Towers

Cells per Tower:	6	Max Tower Drift Rate:	224.9	lbs/hr	Op Hrs/Day:	16	Makeup Water TDS:	ppm
# of Identical Towers:	2				Op Hrs/Yr:	5840	Blowdown TDS	1700
							Avg Tower Flow TDS:	9968
							C of C:	5834
								5.86

Constituent	Concentration in Cooling Tower Water	Total Single Tower			Emissions, lb/hr	Emissions, ton/yr	Single Cell Emissions, lb/day	Emissions, ton/yr	Total All Towers		
		Emissions, lb/hr	Emissions, lb/day	Emissions, ton/yr					Emissions, lb/hr	Emissions, lb/day	Emissions, ton/yr
Manganese	2.5	3.30E-03	5.27E-02	9.63E-03	5.49E-04	1.60E-03	8.79E-03	1.60E-03	6.59E-03	1.05E-01	1.93E-02
Magnesium	59	7.78E-02	1.24E+00	2.27E-01	1.30E-02	3.79E-02	2.07E-01	3.79E-02	1.56E-01	2.49E+00	4.54E-01
Lead	0.0034	4.48E-06	7.17E-05	1.31E-05	7.47E-07	2.18E-06	1.20E-05	2.18E-06	8.97E-06	1.43E-04	2.62E-05
Arsenic	0.0097	1.28E-05	2.05E-04	3.74E-05	2.13E-06	6.23E-06	3.41E-05	6.23E-06	2.56E-05	4.09E-04	7.47E-05
Aluminum	0.02	2.64E-05	4.22E-04	7.70E-05	4.40E-06	1.28E-05	7.03E-05	1.28E-05	5.27E-05	8.44E-04	1.54E-04
Chromium	0.0048	6.33E-06	1.01E-04	1.85E-05	1.05E-06	3.08E-06	1.69E-05	3.08E-06	1.27E-05	2.03E-04	3.70E-05
Cadmium	0.002	2.64E-06	4.22E-05	7.70E-06	4.40E-07	1.28E-06	7.03E-06	1.28E-06	5.27E-06	8.44E-05	1.54E-05
Selenium	0.013	1.71E-05	2.74E-04	5.01E-05	2.86E-06	8.34E-06	4.57E-05	8.34E-06	3.43E-05	5.49E-04	1.00E-04
Zinc	0.04	5.27E-05	8.44E-04	1.54E-04	8.79E-06	2.57E-05	1.41E-04	2.57E-05	1.05E-04	1.69E-03	3.08E-04
Mercury	0.0000002	2.64E-10	4.22E-09	7.70E-10	4.40E-11	1.28E-10	7.03E-10	1.28E-10	5.27E-10	8.44E-09	1.54E-09
Copper	0.0071	9.36E-06	1.50E-04	2.73E-05	1.56E-06	4.56E-06	2.50E-05	4.56E-06	1.87E-05	3.00E-04	5.47E-05
Silver	0.002	2.64E-06	4.22E-05	7.70E-06	4.40E-07	1.28E-06	7.03E-06	1.28E-06	5.27E-06	8.44E-05	1.54E-05
Nickel	0.004	5.27E-06	8.44E-05	1.54E-05	8.79E-07	2.57E-06	1.41E-05	2.57E-06	1.05E-05	1.69E-04	3.08E-05
*	0	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
*	0	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
*	0	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
*	0	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
*	0	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
*	0	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
*	0	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
*	0	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00

Notes:

- (1) Water analysis data supplied by project applicant.
- (2) maximum value of either Ryken and Wetlands Supply Wells data
- (3) blowdown TDS from water balance data supplied by applicant

Support Data for Tables C.1-1 through C.1-6
Harper Lake

Emission Equipment Operating / Test Hours (Total for Alpha and Beta Fields)

DESCRIPTION	Quantity (ea)	Type	Fuel Rating (ea)	Fuel Type	Daily Operating Hours (ea)	Emergency Test Hours per year (ea)
Auxiliary Boiler	2	Firetube Boiler	987 lb/hr	Natural Gas	12	n/a
Diesel Generator	2	Engine	173.3 gph	Diesel	n/a	52
Diesel Fire Pumps	2	Engine	23.5 gph	Diesel	n/a	52
Cooling Water Tower	2	Wet Cooling Drift	n/a	n/a	16	n/a
HTF Emissions	2	Vent Vapor	n/a	HTF	0.25	n/a

Support Data for Tables C.1-1 through C.1-6

Harper Lake

Emission Stack Parameters - Total for Alpha and Beta Fields

DESCRIPTION	Quantity (ea)	Type	Height (ft)	Diameter (ft)	Temperature (°F)	Exhaust Flowrate (ea)	Emissions (t/yr)	Products of Combustion
Auxiliary Boiler	2	Firetube Boiler	80	1.7	301	20,660 lbs/hr	NOx = 9 ppm CO = 50 ppm	CO ₂ = 7.7% H ₂ O = 16.9% N ₂ = 71.7% O ₂ = 3.8% SO ₂ = 0%
Diesel Generator	2	Engine	46	1	922	19,049 cfm	EPA T3	
Diesel Fire Pumps	2	Engine	46	0.67	821	2643 cfm	EPA T3	
Cooling Water Tower	2	Wet Cooling Drift	52	n/a	100	8,748,000 cfm	PM ₁₀ = 2 lb/hr	n/a
HTF Emissions	2	Vent Vapor	35	1	182	64,450 cft/day	95.9 lb/day VOC, 25.9 lb/day HAP	n/a

Table C.1-7 Operational Emissions from Dedicated On-Site Vehicles

Composite Emissions Factors for Gasoline On-Road Fueled Vehicles

lbs/VMT					
NOx	CO	VOC	SOx	PM10	CO2
0.001564	0.009596	0.000882	0.000014	0.000107	1.461717

Ref: MDAB, Emfac 2007, V2.3, Nov 2006
On Road Vehicles (1970-2014)
MD Gasoline Trucks

Composite Emissions Factors for Diesel On-Road Fueled Vehicles

lbs/VMT					
NOx	CO	VOC	SOx	PM10	CO2
0.021605	0.006966	0.001621	0.000001	0.000003	4.047915

Ref: MDAB, Emfac 2007, V2.3, Nov 2006
On-Road Heavy Duty Diesels (1970-2014)

Average Emissions Factors for Diesel Off-Road Fueled Vehicles

lbs/Hp-Hr				
NOx	CO	VOC	SOx	PM10
0.0061	0.0035	0.0011	0.000007	0.0004
Avg onsite equipment speed (mph): 5				
Avg HP of proposed onsite off-road equipment: 100				
Estimated onsite off-road equipment mileage per ye 24000				
lbs/hr				
0.61	0.35	0.11	0.0007	0.04
lbs/VMT				
0.122	0.070	0.022	0.00014	0.008

EFs from Exhaust-Main Sheet

CO2 EF Data from SCAQMD EMFAC 2007, Version 2.3
Heavy-Heavy Duty Diesel Truck Values, Rev 03/07
AQMD Website, 3-2-09
Scenario Year 2014

Estimated number of gasoline fueled vehicles dedicated to site operations: 32
Estimated total annual mileage for gasoline fueled vehicles: 105040

Estimated number of diesel fueled vehicles dedicated to site operations: 19
Estimated total annual mileage for diesel fueled vehicles: 13000

Avg On-site VMT/day 389

Estimated Onsite On-Road Gasoline Vehicle Emissions

	NOx	CO	VOC	SOx	PM10	PM2.5	CO2	Methane	N2O	CO2e
lbs/yr	164.3	1008.0	92.6	1.5	11.2	11.2	153538.8	32.7	17.3	159604.0
tons/yr	0.082	0.504	0.046	0.0007	0.0056	0.0056	76.769	0.016	0.009	79.802
lbs/avg day	0.450	2.762	0.254	0.0040	0.0308	0.0307	420.654	0.090	0.048	437.271

Estimated Onsite On-Road Diesel Vehicle Emissions

	NOx	CO	VOC	SOx	PM10	PM2.5	CO2	Methane	N2O	CO2e
lbs/yr	280.9	90.6	21.1	0.013	0.04	0.04	52622.9	2.7	1.7	53201.3
tons/yr	0.140	0.045	0.011	0.0000	0.0000	0.0000	26.311	0.001	0.001	26.601
lbs/avg day	0.769	0.248	0.058	0.0000	0.0001	0.0001	144.172	0.007	0.005	145.757

Estimated Onsite Off-Road Diesel Equipment Emissions

	NOx	CO	VOC	SOx	PM10	PM2.5	CO2	Methane	N2O	CO2e
lbs/yr	2928.000	1680.000	528.000	3.360	192.000	192.0000	101112.000	2.232	0.000	101158.9
tons/yr	1.464	0.840	0.264	0.0017	0.096	0.096	50.556	0.001	0.000	50.579
lbs/avg day	8.022	4.603	1.447	0.0092	0.526	0.526	277.019	0.006	0.000	277.148

Totals	NOx	CO	VOC	SOx	PM10	PM2.5	CO2	Methane	N2O	CO2e
tons/yr	1.687	1.389	0.321	0.002	0.102	0.102	153.637	0.019	0.010	156.982

Estimated Fugitive PM10/PM2.5 from Onsite Operations Unpaved Road Travel (General Site Operations)

Estimated Onsite Unpaved Road travel: 389 VMT/day

Estimated vehicle weight using onsite unpaved road 5 tons

Road surface silt content: 5.3 %

EPA AP-42, Section 13.2.2, Eq. 1a

Calc 1

Calc 2

EF PM10

EF PM2.5

Control Efficiency

Emission Fraction

lbs/day tons/yr

PM10 88.7 16.2

PM2.5 18.8 3.4

Controls %Reduction Fraction

Watering	55	0.55
Speed Limit:	44	0.44
***	0	0
***	0	0

per South Coast AQMD Fugitive Dust Mitigation Tables, Rev 4/2007.

Support Data for Table C.1-7 - Onsite Operations Vehicle Data

Diesel Vehicles				
Type	# on site	each VMT/yr	total annual VMT	
SCA Cleaning Truck	4	3000	12000	
Evacuation Truck	2	500	1000	Emer use only
Crane	2	500	1000	Emer use only
Boom Forklift	2	500	1000	Emer use only
Small Tractor	5	3200	16000	
Backhoe/Loader	2	500	1000	Emer use only
Skip Loader	2	2500	5000	
		Total VMT	37000	

Gasoline Vehicles				
Type	# on site	each VMT/yr	total annual VMT	
Forklift	2	1500	3000	
Stakebed Truck	2	3000	6000	
Ranger Truck	17	2120	36040	
Ford F-150	4	4500	18000	
SUV Hybrid	2	10000	20000	Not included in emissions calcs
Welding Truck	2	3000	6000	
Ford F-350	3	12000	36000	
		Total VMT	105040	

All data supplied by HLSGS Project Team

ATTACHMENT C.1-1 NITROGEN VENTING OF THE HEAT TRANSFER FLUID SYSTEM


The heat transfer fluid will be comprised either of Therminol VP-1 produced by Solutia, Inc. or DowTherm A produced by Dow Chemical Company. Both materials are comprised of diphenyl ether (73-73.5%) and biphenyl (26.5-27%). Material Safety Data Sheets of both materials are presented following this analysis. These materials in gaseous form represent VOCs with biphenyl also constituting a HAP.

The HTF storage system will consist of 4 tanks per 125-140 MW plant, each tank being 12' diameter by 48' long. Nitrogen will be used to blanket the HTF in the storage tanks. Because of the thermal expansion of the HTF, nitrogen will be vented to the atmosphere on a daily basis from the HTF storage tanks in order to maintain the tanks at constant pressure. The nitrogen vented to the atmosphere will include small amounts of HTF. Emissions are calculated by considering the daily venting of nitrogen due to the expansion of the HTF and the vapor pressure of the HTF at the release temperature.

The amount of daily nitrogen that will be released is determined by the volume increase of the HTF. At the beginning of the day, the heat transfer fluid and the nitrogen will be at 560 °F, and the nitrogen will be at 47.7 psia. These conditions will remain the same in the storage tanks throughout the day. The fluid circulating in the system, however, will absorb heat and expand.


The HTF in the return side of the solar field is shown by bold lines in the figure below. The HTF in this piping will heat up from 560 °F to 740 °F during the day. The volume of this piping is 106,141 cubic feet. The increase in temperature reduces the density of the HTF from 51.2 lb/ft³ to 43.9 lb/ft³, thereby increasing the volume by 16.62%. The increase in volume of the heat transfer fluid in this piping is thus 8,824 cubic feet, or

$$0.1662(53,070 \text{ ft}^3) = 8,824 \text{ ft}^3$$



Heating up the return side of the solar field from 560°F to 740°F.

The HTF in the supply side of the solar field is shown by bold lines in the figure below. The HTF in this piping contains a volume of 47,063 cubic feet, which heats from 560 to 650 °F during TES and steam generation bypass conditions. The increase in temperature reduces the density of the HTF from 51.2 lb/ft³ to 47.69 lb/ft³ thereby increasing the volume by 7.40%. This yields an expansion volume of 3,484 cubic feet.



The supply piping heats up from 560°F to 650°F

The total daily expansion of the HTF is thus 12,308 cubic feet.

At the conditions within the storage tank before expansion (560°F and 47.7 psia), Vapor pressure of HTF is 29.8 psia from Solutia Therminol VP1 properties
HTF mole fraction is HTF vapor pressure 29.8/ total pressure 47.7 = 0.6245

Nitrogen mole fraction is $1.0 - 0.6245 = 0.3755$

Gas constant = 10.731

Assume that the initial vapor space in the expansion tanks is 100 cft

Total initial moles = total pressure 47.4 * total volume 100 cft / 10.731 / initial temp 560°F

Nitrogen moles = nitrogen mole fraction 0.3755 * total moles = 0.4354

At the conditions after expansion (740°F and 160.8 psia),

Vapor pressure of HTF is 147.1 psia from Solutia Therminol VP1 properties

HTF mole fraction is HTF vapor pressure 147.1 / total pressure 160.8 = 0.9151

Nitrogen mole fraction is $1.0 - 0.9151 = 0.0848$

Gas constant = 10.731

Since all of the expansion is vented, the vapor space in the expansion tanks remains at 100 cft

Total moles w/expansion = total pressure 160.8 * total volume 100 cft / 10.731 / expansion temp 740°F

Nitrogen moles w/expansion = nitrogen mole fraction 0.0848 * total moles = 1.25

The high pressure nitrogen and HTF mixture is directed to a compartment in the HTF storage system, where the mixture is expanded and cooled to 16.3 psia and 194 °F, respectively. The HTF vapor will be in saturation at 194 °F, which corresponds to a vapor pressure of 0.0491 psia.

HTF mole fraction is HTF vapor pressure 0.0491 / total pressure 16.3 = 0.0030

Nitrogen mole fraction is $1.0 - 0.0030 = 0.9970$

Nitrogen vented is the difference between the initial amount of nitrogen and the amount of nitrogen the vapor space can hold after expansion.

Nitrogen moles vented = $1.25 - 0.4354 = 0.8157$

Total vented moles = nitrogen moles vented 0.8157 / nitrogen mole fraction 0.9970 = 0.8157

Total vented volume = total moles 0.8157 * 10.731 * temperature 194F / pressure 16.3 = 104.6 cft

This vented volume is based on the assumption that the initial vapor space was 100cft. We know that the actual expansion volume is 12,308 cft. The scale up ratio for the volume must also be used for the total vented moles.

Scale up ratio = 12,308 actual / 104.6 assumed = 117.62

Actual total vented moles = assumed basis 0.8157 * scale up ratio 117.62 = 95.94

Actual HTF vented moles = actual total vented moles 95.94 * HTF mole fraction 0.0030 = 0.2889

HTF mass vented = HTF moles * HTF molecular weight 166 = **47.95 lbs per 140 MW plant**

Maximum VOC emissions from the nitrogen venting are thus 47.95 lb/day (16.8 tons/year) per plant with a maximum of 27% or 12.95 lb/day (2.36 tons/year) comprised of biphenyl, a HAP. Since the expansion is expected to take place over the course of an hour in the morning, the daily emissions are represented by the maximum hourly emissions.

ATTACHMENT C.1-2
ENGINE SPECIFICATION SHEETS

DIESEL GENERATOR SET

CATERPILLAR®




Image shown may not
reflect actual package.

STANDBY

**2500 kW 3125 kVA
60 Hz 1800 rpm 480 Volts**

Caterpillar is leading the power generation marketplace with Power Solutions engineered to deliver unmatched flexibility, expandability, reliability, and cost-effectiveness.

FEATURES

FUEL/EMISSIONS STRATEGY

- EPA Tier 2

DESIGN CRITERIA

- The generator set accepts 100% rated load in one step per NFPA 110 and meets ISO 8528-5 transient response.

UL 2200

- UL 2200 listed packages available. Certain restrictions may apply. Consult with your Caterpillar Dealer.

FULL RANGE OF ATTACHMENTS

- Wide range of bolt-on system expansion attachments, factory designed and tested

SINGLE-SOURCE SUPPLIER

- Fully prototype tested with certified torsional vibration analysis available

WORLDWIDE PRODUCT SUPPORT

- Caterpillar® dealers provide extensive post sale support including maintenance and repair agreements
- Caterpillar dealers have over 1,600 dealer branch stores operating in 200 countries
- The Cat® S•O•SSM program cost effectively detects internal engine component condition, even the presence of unwanted fluids and combustion by-products

CAT 3516C-HD TA DIESEL ENGINE

- Reliable, rugged, durable design
- Field-proven in thousands of applications worldwide
- Four-stroke-cycle diesel engine combines consistent performance and excellent fuel economy with minimum weight

CAT SR5 GENERATOR

- Matched to the performance and output characteristics of Caterpillar engines
- UL 1446 Recognized
- Class H insulation system

CAT EMCP 3 SERIES CONTROL PANELS

- Simple user friendly interface and navigation
- Scalable system to meet a wide range of customer needs
- Integrated Control System and Communications Gateway

STANDBY 2500 kW 3125 kVA

60 Hz 1800 rpm 480 Volts



FACTORY INSTALLED STANDARD & OPTIONAL EQUIPMENT

System	Standard	Optional
Air Inlet	<ul style="list-style-type: none"> • Single element canister type air cleaner • Service indicator 	<ul style="list-style-type: none"> • Dual element & heavy duty air cleaners (with pre-cleaners) • Air inlet adapters & shutoff
Cooling	<ul style="list-style-type: none"> • Radiator with guard (43°C) • Coolant drain line with valve • Fan and belt guards • Caterpillar Extended Life Coolant • Low coolant level & high temperature alarm or shutdown 	<ul style="list-style-type: none"> • Radiator duct flange • Jacket water heater
Exhaust	<ul style="list-style-type: none"> • Dry exhaust manifold • Flanged faced outlets 	<ul style="list-style-type: none"> • Mufflers and Silencers • Stainless steel exhaust flex fittings • Elbows, flanges, expanders & Y adapters
Fuel	<ul style="list-style-type: none"> • Secondary fuel filters • Fuel priming pump • Flexible fuel lines • Fuel cooler* *Not included with packages without radiators 	<ul style="list-style-type: none"> • Water separator • Duplex fuel filter
Generator SR5	<ul style="list-style-type: none"> • Class H insulation • Class H temperature (125°C prime/150°C standby) 	<ul style="list-style-type: none"> • Oversize & premium generators • Anti-condensation space heater • Bearing temperature detector • Stator temperature detector
Power Termination	<ul style="list-style-type: none"> • Bus bar (NEMA and IEC meachanicallug holes) -right side standard • Top and bottom cable entry 	<ul style="list-style-type: none"> • Circuit breakers, UL listed, 3 pole with shunt trip, 80% or 100% rated, choice of trip units, manual or electrically operated (low voltage only) • Circuit breakers, IEC compliant, 3 or 4 pole with shunt trip (low voltage only), choice of trip units, manual or electrically operated • Shroud cover for bottom cable entry • Power terminations can be located on the left and/or rear as an option. Also, multiple circuit breakers can be ordered (up to 3)
Governor	<ul style="list-style-type: none"> • ADEM™ 3 	<ul style="list-style-type: none"> • Load share module
Control Panels	<ul style="list-style-type: none"> • User Interface panel (UIP) - rear mount (standard) • EMCP3.1 Genset Controller • Speed adjust (on panel) • AC&DC customer wiring area (right side) • CAT digital voltage regulator (CDVR) with KVAR/PF control, 3-phase sensing • Emergency Stop Pushbutton 	<ul style="list-style-type: none"> • EMCP 3,3 • Option for right or left mount UIP • Local & remote annunciator modules • Load share module • Discrete I/O module • Generator temperature monitoring & protection • Voltage Adjust (on panel)
Lube	<ul style="list-style-type: none"> • Lubricating oil and filter • Oil drain line with valves • Fumes disposal • Gear type lube oil pump 	<ul style="list-style-type: none"> • Oil level regulator • Deep sump oil pan • Electric & air prelube pumps • Manual prelube with sump pump • Duplex oil filter
Mounting	<ul style="list-style-type: none"> • Structural steel tube • Anti-vibration mounts (shipped loose) 	<ul style="list-style-type: none"> • Isolator removal
Starting/Charging	<ul style="list-style-type: none"> • 24 volt starting motor(s) • Batteries with rack and cables • Battery disconnect switch 	<ul style="list-style-type: none"> • Battery chargers (10&20AMP) • 45 amp charging alternator • Oversize batteries • Ether starting aid • Heavy duty starting motors • Barring device (manual) • Air starting motor with control & silencer
General	<ul style="list-style-type: none"> • Right-hand service • Paint - Caterpillar Yellow except rails and radiators are gloss black • SAE standard rotation • Flywheel and flywheel housing - SAE No. 00 	<ul style="list-style-type: none"> • CSA certification • EU Certificate of Conformance
Note	Standard and optional equipment may vary for UL 2200 Listed Packages. UL 2200 Listed packages may have oversized generators with a different temperature rise and motor starting characteristics.	

STANDBY 2500 ekW 3125 kVA

60 Hz 1800 rpm 480 Volts



SPECIFICATIONS

CAT GENERATOR

Frame.....1842
Excitation..... Permanent Magnet
Pitch..... 0.6667
Number of poles.....4
Number of bearings..... 2
Number of leads..... 6
Insulation..... UL 1446 Recognized Class H with
tropicalization and antiabrasion
IP Rating..... Drip Proof IP22
Alignment..... Closed Coupled
Overspeed capability..... 125%
Wave form..... 2%
Paralleling kit/Droop transformer..... Standard
Voltage regulator.3 Phase sensing with selectable volts/Hz
Voltage regulationLess than +/- 1/2% (steady state)
Less than +/- 1/2% (w/3% speed change)
Telephone influence factor.....Less than 50
Harmonic distortion..... Less than 5%

CAT DIESEL ENGINE

3516C-HD ATAAC, V-16,4 stroke, water-cooled
Bore..... 170.00 mm (6.69 in)
Stroke..... 215.00 mm (8.46 in)
Displacement.....78.08 L (4764.73 in³)
Compression Ratio..... 14.7:1
Aspiration..... TA
Fuel System..... Electronic unit injection
Governor Type..... ADEM3

CAT EMCP3 CONTROL PANELS

EMCP 3.1 (standard)
EMCP 3.2 & 3.3 (Optional)
24 Volt DC control
Generator instruments designed to meet UL/CSA/CE
Integral generator terminal box
Single location for customer connection
MODBUS isolated data link (RS0485 half-duplex)
supports serial communication at data rate up to 33.6
kbaud
Auto start/stop control
True RMS metering, 3-phase
• Digital indication for:
-RPM
-Operating hours
-Oil pressure
-Coolant temperature
- System DC volts
--L-L volts, L-N volts, phase amps, Hz
-Ekw, kVA, kVAR, kW-hr, %kW, PF
• Shutdowns with indicating lights for:
-Low oil pressure
-High coolant temperature
- Low coolant level
- Overspeed
-Overspeed
-Emergency stop
- Failure to start (over crank)
• Programmable protective relay functions:
- Under and over voltage
- Under and over frequency
- Reverse power
- Overcurrent (phase & total)
-

STANDBY 2500 ekW 3125 kVA

60 Hz 1800 rpm 480 Volts



TECHNICAL DATA

Open Generator Set - - 1800 rpm/60 Hz/480 Volts		DM8266	
EPA Tier 2		~ 4190 HP	
Generator Set Package Performance Genset Power rating @ 0.8 pf Genset Power rating with fan		3125 kVA 2500 ekW	
Coolant to aftercooler Coolant to aftercooler temp max		50 ° C	122 ° F
Fuel Consumption 100% load with fan 75% load with fan 50% load with fan		655.9 L/hr 509.6 L/hr 372.3 L/hr	173.3 Gal/hr 134.6 Gal/hr 98.4 Gal/hr
Cooling System¹ Air flow restriction (system) Air flow (max @ rated speed for radiator arrangement) Engine Coolant capacity with radiator/exp. tank Engine coolant capacity Radiator coolant capacity		0.12 kPa 2800 m ³ /min 504.0 L 233.0 L 271.0 L	0.48 in. water 98881 cfm 133.1 gal 61.6 gal 71.6 gal
Inlet Air Combustion air inlet flow rate		198.0 m ³ /min	6992.3 cfm
Exhaust System Exhaust stack gas temperature Exhaust gas flow rate Exhaust flange size (internal diameter) Exhaust system backpressure (maximum allowable)		494.4 ° C 539.4 m ³ /min 203.2 mm 6.7 kPa	921.9 ° F 19048.7 cfm 8.0 in 26.9 in. water
Heat Rejection Heat rejection to coolant (total) Heat rejection to exhaust (total) Heat rejection to aftercooler Heat rejection to atmosphere from engine Heat rejection to atmosphere from generator		830 kW 2478 kW 763 kW 161 kW 106.9 kW	47202 Btu/min 140924 Btu/min 43392 Btu/min 9156 Btu/min 6079.4 Btu/min
Alternator² Motor starting capability @ 30% voltage dip Frame Temperature Rise		6559 skVA 1842 150 ° C	270 ° F
Lube System Sump refill with filter		401.3 L	106.0 gal
Emissions (Nominal)³ NOx g/hp-hr CO g/hp-hr HC g/hp-hr PM g/hp-hr		5.05 g/hp-hr .41 g/hp-hr .1 g/hp-hr .036 g/hp-hr	

¹ For ambient and altitude capabilities consult your Caterpillar dealer. Air flow restriction (system) is added to existing restriction from factory.

² UL 2200 Listed packages may have oversized generators with a different temperature rise and motor starting characteristics. Generator temperature rise is based on a 40 degree C ambient per NEMA MG1-32.

³ Emissions data measurement procedures are consistent with those described in EPA CFR 40 Part 89, Subpart D & E and ISO8178-1 for measuring HC, CO, PM, NOx. Data shown is based on steady state operating conditions of 77°F, 28.42 in HG and number 2 diesel fuel with 35° API and LHV of 18,390 btu/lb. The nominal emissions data shown is subject to instrumentation, measurement, facility and engine to engine variations. Emissions data is based on 100% load and thus cannot be used to compare to EPA regulations which use values based on a weighted cycle.

STANDBY 2500 ekW 3125 kVA

60 Hz 1800 rpm 480 Volts



RATING DEFINITIONS AND CONDITIONS

Meets or Exceeds International Specifications: AS1359, CSA, IEC60034, ISO 3046, ISO 8528, NEMA MG 1-33, UL508A, 98/37/EC

Standby - Output available with varying load for the duration of the interruption of the normal source power. Average power output is 70% of the standby power rating. Typical operation is 200 hours per year, with maximum expected usage of 500 hours per year. Standby power in accordance with ISO 8528. Fuel stop power in accordance with ISO 3046. Standby ambients shown indicate ambient temperature at 100% load which results in a coolant top tank temperature just below the shutdown temperature.

Ratings are based on SAE J1349 standard conditions. These ratings also apply at ISO 3046 standard conditions.

Fuel rates are based on fuel oil of 35° API [16° C (60° F)] gravity having an LHV of 42 780 kJ/kg (18,390 Btu/lb) when used at 29° C (85° F) and weighing 838.9 g/liter (7.001 lbs/U.S. gal.). Additional ratings may be available for specific customer requirements, contact your Caterpillar representative for details. For information regarding Low Sulfur fuel and Biodiesel capability, please consult your Caterpillar dealer.

STANDBY 2500 ekW 3125 kVA

60 Hz 1800 rpm 480 Volts



DIMENSIONS

Package Dimensions		
Length	7073.1 mm	278.47 in
Width	2569.2 mm	101.15 in
Height	3003.5 mm	118.25 in
Weight	18 441 kg	40,655 lb

NOTE: For reference only - do not use for installation design. Please contact your local dealer for exact weight and dimensions. (General Dimension Drawing #2924201).

Performance No.: DM8266

Feature Code: 516DE5L

Gen. Arr. Number: 2523944

Source: U.S. Sourced

March 04 2008

11953998

www.CAT-ElectricPower.com

© 2008 Caterpillar
All rights reserved.

Materials and specifications are subject to change without notice.
The International System of Units (SI) is used in this publication.

CAT, CATERPILLAR, SAFETY.CAT.COM their respective logos, "Caterpillar Yellow," and the POWER EDGE trade dress, as well as corporate and product identity used herein, are trademarks of Caterpillar and may not be used without permission.




JOHN DEERE

PowerTech™ Plus

6090H Diesel Engine

for Generator Set Applications



6090HF Engine shown

General Data

Model	6090HF485	Aspiration	Air-to-Air
Number of cylinders	6	Length-- mm (in)	1208 (47.6)
Displacement-- L (cu in)	9 (549)	Width-- mm (in)	630 (24.8)
Bore and Stroke-- mm (in)	118.4 x 136.0 (4.66 x 5.35)	Height-- mm (in)	1113 (43.8)
Compression Ratio	16.0 : 1	Weight, dry-- kg (lb)	901 (1986)
Engine Type	In-line, 4-Cycle		

Ratings

Prime power at 60 Hz (1800)	235 kW (315 hp)
Standby power at 60 Hz (1800)	258 kW (346 hp)


Prime power is the nominal power an engine is capable of delivering with a variable load for an unlimited number of hours per year. This rating conforms to ISO 3046 and SAE J1995.

Standby power is the nominal engine power available at varying load factors for up to 500 hours per year. This rating conforms to ISO 3046 and SAE J1995. The calculated generator set rating range for standby applications is based on minimum engine power (nominal -5%) to provide 100% meet-or-exceed performance for assembled standby generator sets.

Certifications

- CARB
- EPA Tier 3


Dimensions



PowerTech™ Plus 6090H Diesel Engine

for Generator Set Applications

Performance curve



Performance data

Hz (rpm)	Generator efficiency %	Fan power		Power factor	Calculated generator set output			
		kW	hp		Prime		Standby	
					kWe	kVa	kWe	kVa
60 (1800)	90-94	15.5	20.8	0.8	197-206	247-258	218-228	273-285

Features and Benefits

4-Valve Cylinder Head

- The 4-valve cylinder head provides excellent airflow. New 4-valve U-flow head design

High Pressure Common Rail Fuel System (HPCR) and Engine Control Unit (ECU)

- The HPCR fuel system provides variable common-rail pressure, multiple injections, and higher injection pressures, up to 1600 bar (23,000 PSI). It also controls fuel injection timing and provides precise control for the start, duration, and end of the injection

Cooled Exhaust Gas Recirculation (EGR)

- EGR cools and mixes measured amounts of cooled exhaust gas with incoming fresh air to lower peak combustion temperatures, thereby reducing NOx

Variable Geometry Turbocharger (VGT)

- Varies exhaust pressure based on load and speed to ensure proper EGR flow; greater low-speed maintaining low-speed torque, transient response time, and peak torque. It enables an engine to meet emissions regulations with better fuel economy and the lowest installed costs

Air-to-Air Aftercooled

- This is the most efficient method of cooling intake air to help reduce engine emissions while maintaining low-speed torque, transient response time, and peak torque. It enables an engine to meet emissions regulations with better fuel economy and the lowest installed costs



JOHN DEERE

John Deere Electronic Engine Controls

- Electronic engine controls monitor critical engine functions providing warning and/or shutdown to prevent costly engine repairs; eliminates need for add-on governing components; all lowering total installed costs. Snapshot diagnostic data that can be retrieved using commonly available diagnostic service tools
- New common wiring interface connector for vehicles or available OEM instrumentation packages; new solid conduit and "T" connectors to reduce wiring stress, greater durability and improved appearance
- Factory installed engine mounted ECU or remote mounted ECU, wiring harness and associated components
- Industry standard SAE J1939 interface which communicates with other vehicle systems, eliminating redundant sensors and reducing vehicle installed cost

Compact Size

- Lower installed cost
- Mounting points are the same as Tier 2/Stage II engine models

Engine Performance

- Block loading capability provided with standard electronic governor control

Additional Features

- Self-adjusting poly-vee fan drive
- Single-piece low friction piston
- Low-pressure fuel system with "auto prime" features
- Directed fan air for cooling



2801 W. Ridgeway Ave.
Box 5100
Waterloo, IA 50704-5100
Phone: 800.553.6446
Fax: 319.292.5075

Usine de Saran
La Foulonnerie - B.P. 11.13
45401 Fleury les Aubrais Cedex
France
Phone: 33.2.38.82.61.19
Fax: 33.2.38.82.60.00

All values at rated speed and power with standard options unless otherwise noted.
Specifications and design subject to change without notice.

Litho in U.S.A. (08-10) © 2008 JOHN DEERE


* ~ 52 lb FUEL/HR @ 340 hp. ≈ 7.6 gph.

**PowerTech™ Plus**

6090H

Diesel Engine

for Generator Set Applications



6090HF Engine shown

General Data

Model 6090HF485

Number of cylinders 6

Displacement-- L (cu in) 9 (549)

Bore and Stroke-- mm (in) 118.4 x 136.0 (4.66 x 5.35)

Compression Ratio 16.0 : 1

Engine Type In-line, 4-Cycle

Aspiration Air-to-Air

Length-- mm (in) 1208 (47.6)

Width-- mm (in) 630 (24.8)

Height-- mm (in) 1113 (43.8)

Weight, dry-- kg (lb) 901 (1986)

Ratings

Prime power at 60 Hz (1800)

235 kW (315 hp)

Standby power at 60 Hz (1800)

258 kW (346 hp)


Prime power is the nominal power an engine is capable of delivering with a variable load for an unlimited number of hours per year. This rating conforms to ISO 3046 and SAI J1995.

Standby power is the nominal engine power available at varying load factors for up to 500 hours per year. This rating conforms to ISO 3046 and SAE J1995. The calculated generator set rating range for standby applications is based on minimum engine power (nominal -5%) to provide 100% meet-or-exceed performance for assembled standby generator sets.

Certifications

- CARB
- EPA Tier 3

Dimensions



Photographs may show non-standard equipment.


PowerTech™ Plus

6090H

Diesel Engine

for Generator Set Applications

Performance curve



Performance data

Hz (rpm)	Generator efficiency %	Fan power			Calculated generator set output			
		kW	hp	Power factor	Prime	Standby		
					kWe	kVa	kWe	kVa
60 (1800)	90-94	15.5	20.8	0.8	197-206	247-258	218-228	273-285

Features and Benefits

4-Valve Cylinder Head

- The 4-valve cylinder head provides excellent airflow. New 4-valve U-flow head design

High Pressure Common Rail Fuel System (HPCR) and Engine Control Unit (ECU)

- The HPCR fuel system provides variable common-rail pressure, multiple injections, and higher injection pressures, up to 1600 bar (23,000 PSI). It also controls fuel injection timing and provides precise control for the start, duration, and end of the injection

Cooled Exhaust Gas Recirculation (EGR)

- EGR cools and mixes measured amounts of cooled exhaust gas with incoming fresh air to lower peak combustion temperatures, thereby reducing NOx

Variable Geometry Turbocharger (VGT)

- Varies exhaust pressure based on load and speed to ensure proper EGR flow; greater low-speed maintaining low-speed torque, transient response time, and peak torque. It enables an engine to meet emissions regulations with better fuel economy and the lowest installed costs

Air-to-Air Aftercooled

- This is the most efficient method of cooling intake air to help reduce engine emissions while maintaining low-speed torque, transient response time, and peak torque. It enables an engine to meet emissions regulations with better fuel economy and the lowest installed costs

John Deere Electronic Engine Controls

- Electronic engine controls monitor critical engine functions providing warning and/or shutdown to prevent costly engine repairs; eliminates need for add-on governing components; all lowering total installed costs. Snapshot diagnostic data that can be retrieved using commonly available diagnostic service tools
- New common wiring interface connector for vehicles or available OEM instrumentation packages; new solid conduit and “T” connectors to reduce wiring stress, greater durability and improved appearance
- Factory installed engine mounted ECU or remote mounted ECU, wiring harness and associated components
- Industry standard SAE J1939 interface which communicates with other vehicle systems, eliminating redundant sensors and reducing vehicle installed cost

Compact Size


- Lower installed cost
- Mounting points are the same as Tier 2/Stage II engine models

Engine Performance

- Block loading capability provided with standard electronic governor control

Additional Features

- Self-adjusting poly-vee fan drive
- Single-piece low friction piston
- Low-pressure fuel system with “auto-prime” feature
- Directed top-liner cooling



John Deere Power Systems

3801 W. Ridgeway Ave.

PO Box 5100

Waterloo, IA 50704-5100

Phone: 800.553.6446

Fax: 319.292.5075 John Deere Power Systems

Usine de Saran

La Foulonnerie - B.P. 11.13

45401 Fleury les Aubrais Cedex

France

Phone: 33.2.38.82.61.19

Fax: 33.2.38.82.60.00

All values at rated speed and power with standard options unless otherwise noted.

Specifications and design subject to change without notice.

Litho in U.S.A. (08-10) © 2008 JOHN DEERE

Please use the PDF version of this document for printing.

ATTACHMENT C.1-3

AUXILIARY BOILER SPECIFICATION SHEETS

Auxiliary Boiler Operational Data and Specification Sheets

Natural Gas Requirement

Mojave Solar Project at Harper Lake

		Boilers		Flow		Units		Conversions	
Connected Load (max instantaneous load) (cu ft/hr)		41,829		21.5		MMBtu/hr		1028 Btu/scf	
Minimum Load (cu ft/hr)		-		0		MMBtu/hr		1000000 MM	
Average load (cu ft/hr)		41,829		21.5		MMBtu/hr		24 hours/day	
Daily Maximum Load (cu ft/day)		1,003,891		516		MMBtu/day			
Daily Minimum Load (cu ft/day)		-		0		MMBtu/day			
Daily Average Load (cu ft/day)		501,946		258		MMBtu/day			
Requested Delivery Pressure (psig)		30 < P < 150 at each power island							
Proposed Meter Location		On each power island. Connection can be made at Harper Lake and easement can be provided to route pipeline to remote power island. See attached map.							

Assumptions:

- Natural gas requirement is shown for entire project. Two individual connections are desired though.
- Boilers operate at full load when operating
- Boilers operate 12 hours per day 365 days per year
- Boilers can operate 0 hours per day
- Boilers can operate 24 hours per day

Boiler Exhaust Flow Vs. Load

Load	100%	75%	50%	25%
ACFM @ Stack	6184	5066	3944	2695
DSCFM @ 3% O2	3589	2683	1772	779



**STANDARD SPECIFICATION
FOR D-TYPE
SHOP-ASSEMBLED INDUSTRIAL WATERTUBE
STEAM GENERATING EQUIPMENT**

I. SCOPE

- A. This specification shall govern the construction features, materials, fabrication, inspection, and preparation for shipment of "package type" shop-assembled, watertube steam generating equipment complete with burner assembly, necessary appurtenances, controls and auxiliary equipment mounted to the maximum practical extent (allowed by shipping clearances) as an integral unit on a steel base so as to make a complete self-contained assembly.
- B. Any deviation from this specification must be specifically approved prior to submittal of proposed bid. All requests for approval of design deviations shall be presented in writing at least ten (10) days prior to bid date.

II. GENERAL REQUIREMENTS

- A. Proposal:
 - 1. Complete description, drawings, and material specifications and performance shall accompany each proposal.
- B. Guarantee:
 - 1. The boiler manufacturer shall guarantee the steam generating capacity and thermal efficiency as stated herein, while the unit is being fired at 100% load with the primary fuel at the specified operating conditions.
 - 2. Performance and efficiency tests shall be conducted immediately after completion of startup. The manufacturer must have a representative in attendance at the time the test is conducted.
 - 3. All equipment is to be guaranteed against defective design, workmanship, or material for one year from date of initial operation, but not to exceed 18 months from date of shipment or date equipment meets ready-to-ship status.



C. Standards and Codes:

1. The following regulatory codes, standards, and publications, in effect on date of invitation for bids, form a part of this specification. All applicable components shall be designed and constructed in accordance with these codes, with additions or modifications as required by this specification.
 - a. ASME Boiler and Pressure Vessel Code
 - b. ASME Power Test Code
 - c. ABMA Manual of Industry Standards

D. Instructions and Data Sheets:

1. The manufacturer shall furnish ASME Manufacturer's Data Sheets, five (5) copies of operating instruction manuals, and certified prints.

III. PROCESS DESIGN REQUIREMENTS

A. Operating Conditions:

1. Design Continuous Capacity _____ Lbs/hr
2. Design Pressure _____ PSIG
3. Operating Pressure _____ PSIG
4. Final Steam Temperature _____ °F
5. Feedwater Temperature _____ °F
6. Boiler Efficiency* _____ %
7. Elevation above Sea Level _____ Ft
8. Combustion Air Temperature _____ °F
9. Electrical Characteristics _____ Volts _____ Phase _____ Hertz
10. Primary Fuel _____ Supply Pressure
11. Standby Fuel _____ Supply Pressure
12. Insurance Requirements _____

* Unmeasured losses of up to 1% can be used.

B. General Conditions:

1. This specification covers the furnishing of steam generating unit(s) each to develop the above stated maximum steam capacities. Each steam generating unit shall consist of a two drum D-type, shop-assembled, package type watertube boiler assembly with integrally-mounted burner and fan (shipping clearances permitting), controls, and other necessary appurtenances so as to make a complete self-contained unit that can be readily transported by common carrier, with a minimum of disassembly insofar as shipping clearances permit.
2. Material shall be as specified herein. Material not specifically stipulated shall be of the best commercial quality. All materials shall be free from defects that might affect the serviceability of the finished product.
3. Steam leaving the boiler shall not contain more than 1 ppm TDS if superheated steam or 0.5% moisture if saturated steam with boiler water concentrations not exceeding the values as recommended by the ABMA for the applicable operating pressure.
4. Boiler parameters shall be as defined below:
 - a. Radiant heating surfaces shall be calculated on a flat projected basis.
 - b. Furnace volume shall be determined with the furnace limit being considered as not extending beyond the first row of water screen tubes or superheater tubes, whichever first comes in contact with the furnace's exit flue gases.
6. The furnace side walls, roof, floor, front & rear walls shall be 100% water-cooled membrane surface. Membrane design will consist of 2" OD tubes on 4" centerlines, with membrane fins between tubes. The adjacent fins of each outboard furnace and convection tube shall be continuously seal-welded together, forming a water-cooled, gas-tight inner seal. The inboard row of finned tubes between the furnace and convection zone shall be seal-welded together to prevent short-circuiting of flue gas from the furnace to the boiler flue gas outlet. Boiler shall be designed for minimum refractory. Burner throat shall be refractory-free.

7. No part of the boiler drums shall be directly exposed to furnace radiation. Refractory shall be utilized to protect from radiant heat.
8. The furnace shall be designed to restrict flame impingement and permit long flame travel. Furnaces shall be provided with the necessary water-cooled radiant surface to assure the reduction of the furnace exit gas temperatures to a maximum of 2100°F prior to entry into the convection zone.

IV. BOILER DESIGN REQUIREMENTS

- A. The boiler shall be of the conventional, two drum, D-Type design, constructed in accordance with Section 1 of the ASME Boiler and Pressure Vessel Code for the specified design pressure and shall bear the ASME standard symbol.
 1. Drums shall be fusion welded, radio-graphed and stress-relieved. They shall be complete with all necessary connections, a 12" x 16" manway opening in each head with cover and yokes, internal piping for feedwater, chemical feed, and continuous blowdown. The upper drum shall include adequate steam separating equipment to assure the specified steam quality. The lower drum shall include a slotted inverted channel to assure uniform blowoff. All internal fittings and pipe must be adequately supported and removable for maintenance purposes.
 - a. Steam drum diameter shall not be less than ____" I.D.
 - b. Water drum diameter shall not be less than 24".
 - c. Each steam drum shall be equipped with the proper connections for the following accessories:
 1. Steam outlet
 2. Flanged safety valves
 3. Feedwater inlet
 4. Continuous blowdown
 5. Feedwater regulator
 6. Auxiliary low water cutoff
 7. Water column
 8. Chemical feed
 9. Vent
 10. Sootblower

- d. Each water drum shall be equipped with a flanged blowoff connection.
 - e. All connections larger than 2" shall be flanged.
2. All tubes shall be 2" O.D., electric resistance welded, and shall be designed and arranged to provide for natural circulation in the proper direction at all loads. Tubes of variable diameter, such as swaged tubes, shall not be permitted. No tube shall enter the lower drum below the horizontal drum centerline or enter the steam drum above the minimum water level. Tubes shall not have any reverse bends or "pockets" which would prevent complete drainage of the boiler through the lower blowoff opening. All tubes are to be rolled in holes drilled true and radially, to afford full parallel bearing in the drum plate. Each tube hole shall be serrated to assure the tightest possible mechanical joint. All tubes shall be a minimum of 0.105" wall thickness.
 3. All tubes in the furnace shall be membrane finned construction except those in the area where the gases leave the furnace and enter the convection section. The outboard row in the convection section shall be membrane finned tubes except in the area where the flue gases leave the boiler. Fins shall be ¼"x 1" steel, fused continuously to opposite sides of the tubes by electric welding. Membrane finned construction which utilizes a fin-to-tube weld on only one side is not acceptable.
 4. The steam generating units shall be provided with a 100% welded gas-tight enclosure. Refractory gas seals are not allowed. The seal shall be formed entirely by finned tube walls and intermediate headers, continuously seal-welded together forming a gas-tight water-cooled enclosure. The external casing shall be 12-gauge steel or corrugated aluminum and shall completely enclose the unit with the exception of the four drum heads. The drum heads shall be insulated in the field by others. The steam drum shall be insulated and cased with 12-gauge steel. The average surface temperature of the casing shall not exceed 50°F over ambient temperature with a surface wind velocity of two feet per second while the boiler is operating at full capacity.
 5. All insulating materials shall be not less than first quality, as used in the best commercial practices, and shall conform substantially to the following:

- a. Sides, roof, floor, front & rear walls of the steam generating unit are to be completely covered with a minimum thickness of 3 inches of 1000°F insulating blanket of the fiber glass or mineral wool type. Insulation over the top of the steam drum is to be a minimum of 3 inches thick 1000°F insulating blanket of the fiber glass or mineral wool type.
6. The steam generating unit shall be supported by steel base beams.
7. The exterior steel surfaces of each unit shall be completely cleaned by solvent cleaning, scraping, or grinding and have one (1) coat each of high heat resistant primer and finish coat. Corrugated aluminum parts of the outer casing (if applicable) need not be painted.
8. Each unit shall be equipped with the following appurtenances, all of which are to conform to the best standards of power plant practice.
 - a. Observation Ports - Three(3) or more are to be located at strategic points in the furnace target wall. These ports are to be of a type to assure tight shutoff and permit lens change when the steam generating unit is in operation. The target wall observation ports and the burner register observation ports shall afford full furnace vision.
 - b. Furnace Access - An access opening, 15" x 18" minimum other than the burner register, shall be provided to the boiler furnace area. The access opening shall be gasketed and shall have a 1/4" steel cover with handles and shall be secured properly for a gas tight seal.
 - c. Convection Access - An access opening or openings shall be provided for inspection of the convection tube bank. The opening shall be furnished complete with insulated cover plate or plates, gasketing, handles, bolts, and nuts.

9. Each steam generator, as specified herein, shall be provided with the following boiler trim equipment. This equipment shall be factory-mounted, complete with integral connecting piping, valves, and fittings. All valves and control apparatus are to be designed for the specific application for which they are utilized in full compliance with the regulatory codes hereinbefore specified. Drain lines, as applicable, shall terminate with a valve 5 feet above operating floor level. If clearances do not permit shipment of all apparatus mounted on the unit, the subassemblies affected can be shipped loose for field mounting by others:
 - a. Safety valves
 - b. Blowoff valves
 - c. Water column
 - (1) The water column shall include an integral probe for low water fuel cutout, and high and low water bell alarm.
 - d. Water gauge and gauge valves with chain and handles for floor level operation.
 - e. Auxiliary low water cutoff
 - (1) In addition to the safety device to be furnished with the water column, an auxiliary low water cutout assembly is to be furnished. The auxiliary low water cutout is to be of the float type.
 - f. Continuous blowdown stop valve
 - g. Continuous blowdown control valve
 - h. Vent valve
 - i. Chemical feed and check valve
 - j. Steam gauge valve
 - k. Main steam non-return valve
 - l. Main steam stop valve
 - m. Interconnecting spool piece with vent & drain valves
10. Each unit shall be furnished with a feedwater control system. The system shall include a three-valve block and bypass, and shall incorporate a control valve having a pressure drop of no more than 15 psig at design capacity.
 - a. Feed stop valve
 - b. Feed check valve
 - c. Feedwater bypass valves

11. If heavy oil firing is required, an automatic valve-in-head type sootblower system is to be furnished, factory-mounted to the steam generating unit. Sootblower elements must be perpendicular to the tubes. Each boiler tube lane in the convection zone is to be cleaned by an element orifice. Systems employing alternate lane blowing are not acceptable. Each system shall include a chain-operated steam supply shutoff valve and drain valve. When present fuels do not require sootblowers, the unit shall be provided with sootblower wall boxes and bearings for future installation of elements and heads.

V. ECONOMIZER

Vendor shall furnish one (1) economizer per boiler to recover the waste heat from the hot boiler exhaust gas. The economizer unit shall be a packaged, rectangular, unit that is double-cased and insulated. The economizer internal casing shall be 10-gauge, seal-welded (gas tight) steel, externally insulated with 2" of heavy-duty blanket insulation and externally cased with corrugated lagging. The gas side connections on the economizer shall be plate flange type with drilling for bolt holes to align with adjacent components. The water side connections shall be flanged. The economizer shall include vent and drain connections and appropriate closures. The unit shall incorporate lifting lugs to facilitate loading & unloading and shall be designed so that access for tube inspection can be achieved by either access doors in the economizer or from adjacent ductwork incorporating access doors.

The economizer shall be a horizontal tube, counter-current flow design arranged to allow the boiler exhaust to travel vertically upward and the feedwater to flow vertically downward. The economizer shall not be allowed to steam and shall be capable of operating at 100% load without having to bypass any flue gas or feedwater. Tube arrangement shall be square pitch, to allow for ease of cleaning with lane sootblowers (applicable if firing fuel oils). Tube returns shall not be finned in order to ensure ease of maintenance.

Tube diameter shall be 2" and the unit shall be completely drainable by gravity. Tube material shall be SA-178A. Tubes shall be bare or utilize extended (finned) surface, depending on the fuel(s) being fired and good engineering practice to avoid clogging. Maximum fin density shall be ____ fins/inch. The tube sheets shall contact only the fin tips without contacting the actual tube wall itself.

Header material shall be SA106B and use RFWN flanged connections. Header wall thickness and flange rating shall be dependent on economizer design pressure. Plastic-lined headers shall not be acceptable. Tube-to-header connections shall be all welded. Bonded fittings or compression fittings shall not be acceptable and are not permitted under ASME Section 1 guidelines.



All pressure parts shall conform to the applicable provisions of the current ASME Section 1 code. The economizer shall be properly named and code stamped. The design pressure of the economizer shall exceed the design pressure of the boiler.

The following equipment shall also be supplied as part of the complete economizer assembly package:

1. Structural support steel.
2. Interconnecting boiler-to-economizer transition ductwork (insulation in the field by others). Provide expansion joints as required.
3. Sootblower assembly if firing heavy oils (steam supply shut-off valve & steam piping by others).
4. Interconnecting feedwater piping from economizer feedwater outlet to boiler feedwater inlet.
5. Temperature gauges with thermowells for local measurement of gas and water inlet & outlet temperatures.
6. Ductwork to transition from economizer gas outlet to stack and/or flue gas exhaust ductwork.

VI. TESTS

- A. Prior to shipment, the manufacturer shall perform the following tests as applicable to the steam generating units:
 1. Before being enclosed in the setting, the pressure vessels shall receive a hydrostatic test as required by Section 1 of the ASME Boiler and Pressure Vessel Code. The manufacturer shall furnish properly executed ASME Manufacturer's Data Sheets as required by ASME code.

VII. STEAM GENERATOR FIELD ENGINEERING SERVICES

- A. The steam generating unit manufacturer shall furnish, at their per diem rate, the services of a competent service engineer to supervise and assist in effecting boiler boil-out, boiler/burner startup, adjustments, testing, and instruction of operating personnel.
 1. Manufacturer's proposal shall state the predicted period of time incorporated in the offering for field engineering services.



VIII. LOW-NOX BURNER

A. GENERAL

This section addresses the design, fabrication, testing and supply of low-NOx packaged burner system(s), suitable for installation on ___PPH packaged watertube boilers.

The packaged burner equipment shall be designed to fire natural gas or #2 oil (or #6 oil or other) and provide sufficient heat input for the maximum boiler capacity and pressure as outlined below. The burner will also be designed to minimize NOx and CO emission such that the NOx and CO stated in Section C will not be exceeded. If flue gas recirculation (FGR) is required in addition to low NOx burners to meet the specified performance, the vendor shall specify the amount and type of FGR (forced or induced) required.

In addition, the burner excess oxygen levels at full load shall not exceed those stated in Section C.

The packaged burner shall include all equipment to deliver a functional burner system. All functional components such as burner, windbox, ignitor, forced-draft fan, fuel trains, burner management system & combustion/feedwater controls shall be provided and arranged by the boiler vendor to assure component compatibility, unit responsibility & a single-source responsibility.

All components shall be factory-mounted, wired and tested, as far as practicable, at the burner manufacturer's factory in order to minimize field installation and start-up time.

The packaged burner system shall be designed in strict accordance with the applicable code requirements of NFPA 85, latest edition.

Burner package shall be supplied by CB-NATCOM.

B. DESIGN CONDITIONS

Fuel Data

Fuel type	_____
Fuel HHV	_____ BTU/lb
Fuel pressure available	_____ PSIG
Viscosity	_____ (if applicable)
Ignitor fuel	_____ Natural gas
	_____ Propane gas
Fuel analysis	Gas : % per volume
	Oil : % per weight

(An analysis must be provided in order to guarantee emissions)



C. PERFORMANCE GUARANTEES

The packaged burner equipment shall guarantee as a minimum the performance parameters as outlined below. If the vendor fails to meet any of its performance guarantees, the vendor, at his own expense, shall modify, adjust or replace all related components, until all performance guarantees are met.

1. The NO_x emission shall not exceed _____ lb/MMBTU when firing natural gas and shall not exceed _____ lb/MMBTU when firing oil. These limits shall not be exceeded from 25-100% load.
2. The CO emissions shall not exceed _____ lb/MMBTU when firing natural gas or oil. These limits shall not be exceeded from 25-100% load.
3. The burner excess air level from 50% to 100% firing rate shall not exceed _____ % for both natural gas and oil.
4. The burner turndown capacity shall not be less than ____:1 when firing natural gas and not be less than ____:1 when firing oil. The NO_x and CO emissions shall not exceed their guaranteed values throughout the gas and oil operating range.
5. The burner shall fire over the entire operating range with no flame impingement on the side or rear heating surfaces.

D. EQUIPMENT REQUIREMENTS

1. GENERAL

The following will describe the minimum equipment requirements for each component of the low NO_x packaged system:

The low NO_x burner, complete with oil and gas burner units, will be mounted and dimensionally checked at the factory prior to shipment. If shipping conditions permit, the forced draft fan and motor shall also be factory-mounted. Main fuel control and pressure regulating valves will be supplied by the vendor but shipped loose for field installation by others.

2. LOW NO_x BURNER ASSEMBLY

The burner assembly will be a proven design developed specifically for Low-NO_x emissions. Basis of design shall be the CB-Natcom burner.



The burner shall be an axial flow type based on low to moderate swirling air jet aerodynamics. It shall use intensive and on-line adjustable fuel staging to control and minimize NOx formation. It shall use a combination of swirl and central core bluff-body effect to stabilize the flame. A preset ratio of tangential to axial momentum shall be used to effectively produce the required flame shape for a given furnace geometry. The flame shape and concentration properties within the furnace confinement shall be determined by appropriate computer simulation.

The gas burner shall be a low NOx lance-style spud design, with all gas lances mounted to an external gas manifold assembly located outside the windbox. The gas lances shall be externally removable for service and cleaning without having to enter the windbox or boiler and shall be removable while the burner is firing oil, thus not requiring the boiler to be shut down. Gas burner designs that utilize manifolds located inside the windbox are not acceptable due to potential risk associated with eventually undetectable gas leakage. Each of the gas injectors shall be fully adjustable on-line for flow, injection angle rotation and axial translation to generate an efficient staged fuel combustion that can minimize NOx and CO formation within the constraint of the furnace boundary and physical environment.

The burner throat shall be fully metallic and straight cylindrical for maximum air-cooling effect. No divergent refractory throat that results in loss of air mixing velocity and that leads the air flow to widen at burner outlet and cause flame impingement on side walls will be accepted.

The oil atomizer shall be of the non pre-mix type using constant differential steam to oil pressure. The oil injector internal atomizing steam and oil orifices shall also be adjustable by the sole replacement of a spacer washer. This allows for the adaptation of the penetration of the steam atomized oil jets in the combustion air to quickly reach optimum performance for the given fuel oil. With these unique adaptability features, required combustion performances can be easily obtained upon start-up, with no boiler downtime. The burner vendor shall include and describe all tools required to perform oil tip cleaning.

The burner front plate shall be of sufficient size to accommodate openings with carrier sleeves for each of the oil units, ignitor and gas lances. Openings for two sight ports each with sight glass and one scanner port with scanner mount complete with cooling air connection and scanner ball swivel assembly shall be supplied.

3. IGNITORS

The ignitor shall be gas-electric and provide sufficient ignition heat input using either natural gas or propane.

The ignitor shall meet NFPA Class 3 requirements.



The ignitor shall be supplied complete with flexible steel, braided gas hose and flexible electrical harness assembly connecting the ignitor spark plug to the ignition transformer. The ignitor transformer shall be 6,000 volts maximum to minimize the occurrence of high voltage short circuits and be mounted in a NEMA 12 enclosure located on the windbox.

The ignitor shall use combustion air from the burner forced draft fan and not require an independent source of combustion air. No flame rods shall be used for ignitor flame detection.

4. WINDBOX

The windbox assembly shall be a low velocity plenum of adequate aerodynamic design to achieve optimum air distribution at the burner inlet to insure flame axial symmetry. Computer simulation showing the air velocity vector distribution to be within 10% from the mean with a swirl number less than 0.01 at the burner inlet shall be supplied with the burner technical documentation.

The windbox shall be manufactured with ¼" ASTM A-36 steel plate, properly stiffened with heavy duty square tubes. It shall be fitted with lifting lugs and contain an opening with mounting studs to accept the burner front plate.

5. FUEL PIPING TRAINS

The oil, atomizing steam, ignition and main gas piping trains shall be factory assembled, wired and tested, and shipped as integral parts of the burner windbox assembly. These trains shall include all steam traps, tubing to limit devices, and all necessary fittings. The piping shall be arranged in a neat and accessible manner. These trains must fully comply with NFPA 8501.

The train shall be assembled and tested at the factory, and while it is to be shipped as a separate assembly, field installation shall only require bolting a flange connection and electrical connection from pre-wired valves to terminal strips.

Fuel oil and atomizing steam piping shall be Schedule 80 with 300 lb. malleable iron screwed fittings; valves shall be cast iron and bronze with threaded ends. Main and ignitor gas piping shall be Schedule 40 with 150 lb. Malleable iron fittings, 2" and under, aluminum body vent valve, threaded 2" and under, flanged 2-1/2" and over. The ignitor valves shall be brass and aluminum with threaded ends.

6. PILOT GAS PIPING TRAIN

One (1) pilot gas piping train shall be provided with the following major components pre-piped and installed on the windbox. Pilot gas system shall be designed for uninterrupted natural gas supply pressure of _____ PSIG. Equipment shall include, but no be limited to, the following:

- Two (2) Manual shut-off valve
- One (1) Pilot gas pressure regulator
- Two (2) Electrically operated shut-off valves
- One (1) Electrically operated vent valve between both shut-off valves
- One (1) 2-1/2" Pilot gas pressure gauge with shut-off cock
- One (1) "Y" type strainer
- One (1) Flexible hose

7. MAIN FUEL GAS PIPING TRAIN

One (1) fuel gas piping train with the following major pre-piped components installed on the windbox. Fuel gas piping system shall be designed for use with natural gas supplied to the regulator at _____ PSIG.

- Two (2) 3-1/2" burner pressure gauges with shut-off cock
- One (1) Leak test cock
- One (1) Low fuel gas pressure switch
- One (1) High fuel gas pressure switch
- Two (2) Electrically operated shut-off valves
- One (1) Electrically operated vent valve between both shut-off valves
- One (1) Flow control valve
- One (1) Manual shut-off cock
- One (1) Flexible hose

8. MAIN FUEL OIL PIPING TRAIN

One (1) fuel oil piping train with the following major pre-piped components installed on the windbox. Fuel oil piping system shall be designed for use with oil supplied to the regulator at _____ PSIG.

- Two (2) Manual shut-off valve
- One (1) "Y" type strainer
- One (1) Oil pressure regulator
- Two (2) 3-1/2" pressure gauges with shut-off cock
- One (1) Low oil pressure switch
- One (1) Electrically operated oil shut-off valve
- One (1) Flow control valve
- One (1) Flexible hose

9. MAIN ATOMIZING STEAM PIPING TRAIN

One (1) steam atomizing piping train with the following major pre-piped components installed on the windbox. Atomizing piping system shall be designed for use with saturated steam supplied to the regulator at _____ PSIG.

Two (2)	Atomizing manual shut-off valve
One (1)	"Y" type strainer
One (1)	Steam trap with isolation and bypass valves
Two (2)	3-1/2" pressure gauges with shut-off cock
One (1)	Electrically operated steam shut-off valve
One (1)	Low atomizing steam pressure switch
One (1)	Atomizing steam pressure regulating valve
One (1)	Flexible hose

10. BURNER MANAGEMENT SYSTEM

Provide an electronic solid state automatic, non-recycling Burner Management System (BMS), arranged to comply with NFPA-8501, I.R.I., and Factory Mutual Standards. The system shall be completely installed in a NEMA-12 cabinet mounted on the burner windbox. The Burner Management System shall operate from the 120 V, 1 PH, 60 Hz power source. The electronic Burner Management System shall be fully automatic and include a pre-wired factory tested microprocessor based Flame Safeguard System *Fireye E110/E300* or equal. The controls shall be fail-safe where component failure within the control or presence of actual or simulated flame prior to start-up will prevent burner operation. The following major components shall be completely installed in the Burner Management cabinet unless noted:

One (1)	Flame control with mounting rack
One (1)	Control circuit breaker
Three (3)	Momentary pushbuttons <ul style="list-style-type: none">- Sequence Start- Alarm Acknowledge- Lamp Test
One (1)	Emergency Stop (Mushroom red button)
One (1)	Fan On-Off-Auto selector switch
One (1)	Fuel selector switch
One (1)	Water level alarm bell
One (1)	Limit or Flame failure horn

First out annunciator shall display a minimum of the following:

Power on	Purge in progress
Ignitor on	Fuel gas on
Flame failure	FD fan failure
Low combustion air	High water cut-off
Low water alarm	Low water cut-off
High fuel gas pressure	Low fuel gas pressure
Low pressure instrument air	Low oil pressure
Low atomizing steam pressure	High steam pressure cut off



Miscellaneous Burner Management equipment completely installed on burner windbox.

- One (1) Fan air pressure switch (Minimum air flow)
- One (1) Purge air flow switch
- One (1) UV flame scanner – Fireye or equal

11. COMBUSTION CONTROLS

The combustion control shall be a fully-metered, cross-limited type supplied with instrumentation shipped loose for mounting in customer's piping in the field. The steam pressure controller shall be a multi loop type and shall be installed in the NEMA-12 BMS control panel. The steam pressure transmitter shall be shipped loose for field mounting.

12. FORCED DRAFT FAN

The F.D. fan shall be provided with all required dampers to control combustion air. The fan shall be a non-overloading, centrifugal type 1,800 RPM unit with grease-lubricated antifriction bearings and a direct-connected TEFC ____ V / 3 PH / 60 Hz motor drive. The fan sizing shall have a minimum margin of 10% volume and 21% static pressure above design requirements at an ambient temperature of ____ F.

ATTACHMENT C.1-4
COOLING TOWER SPECIFICATION SHEETS

Cooling Tower Institute
Inquiry Bid Form

Mechanical Draft Cooling Tower

Sheet 1 of 3

CUSTOMER ABENCS Solar Plant Phoenix, AZ	MANUFACTURER <div style="display: flex; align-items: center;"> <div> Cooling Tower Depot, Inc. 651 Corporate Circle Golden, CO 80401 Phone (720) 746-1234 Fax (720) 746-1110 </div> </div>
Specification No:	Proposal No.:
Inquiry No:	Date: Orig. August 17, 2007
Date: Orig. Rev	Date: Rev. 4-Jan-08
All data set forth herein is in accordance with definitions and standards published by the Cooling Tower Institute.	
GENERAL	Selection HEAVY DUTY INDUSTRIAL COUNTERFLOW Tower Model CFF-544834-8I-36 Type INDUCED DRAFT COUNTERFLOW
DESIGN & OPERATING CONDITIONS	Circulating Water Flow, u.s. gpm/ 90,000 Hot (inlet) Water Temp., deg F 92.1 Cold (outlet) Water Temp., deg F 80.3 Wet Bulb Temp., deg F Inlet 72.0 Ambient Tower Pump Head, ft. 29.5 Total Fan B.H.P., (Driver Output) 230.60 X 8.00 = 1,844.80 Drift Loss, % of circulating flow 0.001 Evaporation Loss (at design), % 1.55 Design Wind Load, lbs./sq. ft. PER IBC Mi./hr. Design Seismic Load % G PER IBC Tower Site (ground level, roof, etc.) GROUND LEVEL Elevation Above Sea Level, ft. 690.00 Tower Exposure UNOBSTRUCTED
STRUCTURAL DETAILS	Number of Cells 6 Fans per Cell 1 Total Number of Fans 6 Nominal Cell Dimensions, L x W 54 X 48 = 2,592 Overall Tower Dimensions, L x W 432 X 48 = 20,736 Height - Basin Curb to Fan Deck, ft. 34 Fan Stack Height, ft. 10 Overall Tower Height, ft. 44 Inside Basin Dimensions, L x W 438 X 54 = 23652 Column Extensions, Perimeter, ft. 4 (below basin curb) Interior, ft. 4 Anchorage PERIMETER

Cooling Tower Institute
Inquiry Bid Form

Mechanical Draft Cooling Tower

Sheet 2 of 3

Proposal No.:

STRUCTURAL DETAILS (Continued)		
Hot Water Inlet - Number		6
Nominal Diameter, in.		30
Description		TERMINATES ONE FOOT OUTSIDE OF TOWER WITH STD ANSI FLANGE
Height Inlet Above Basin Curb, ft.		23.00
Access to Top of Tower		ONE FIBERGLASS LADDER AND ONE FIBERGLASS STAIR
Shipping Weight, lbs.		910,000
Operating Weight, lbs.		1,200,000
MATERIALS OF CONSTRUCTION		
Framework Members		HIGH STRENGTH PULTRUDED FIBERGLASS
Casing		12 OZ. FIRE RETARDANT FIBERGLASS
Fill Media		10 MIL PVC FILM PACK FILL
Fill Support		HIGH STRENGTH PULTRUDED FIBERGLASS
Drift Eliminators		15 MIL CELLULAR PVC
Spacer		PVC
Fan Stacks		FIBERGLASS
Louver Material		12 OZ. FIRE RETARDANT FRP
Partitions		12 OZ. FIRE RETARDANT FIBERGLASS
Fan Deck		NON-SKID FRP
Water Distribution - Type		LOW PRESSURE DOWNSPRAY
Material		FRP HEADER/PVC LATERALS
Lumber Pre-Treatment		N/A
Type of Treatment		N/A
Items Treated		N/A
Splashers or Spray Nozzles		POLYPROPYLENE
Stairway and Handrail		FIBERGLASS
Structural Connectors		304 SERIES SS
Ring Joint Connectors		304 SERIES SS
Bolts, Nuts, Washers		304 SERIES SS
Anchor Connectors		304 SERIES SS
Screws		304 SERIES SS
Mechanical Equipment Support		Galvanized Steel
Anchor Bolts - Material		304 SERIES SS
Furnished by		BY CTD
Cold Water Basin - Material		CONCRETE
Furnished by		BY OTHER
Basin Accessories, by Mfg.		NONE
MECHANICAL EQUIPMENT		
Fans		
Number		6
Type or Model		APT-36H-7
Manufacturer		HUDSON PRODUCTS
Diameter, ft.		36
Number of Blades		7


Cooling Tower Institute
Inquiry Bid Form

Mechanical Draft Cooling Tower

Sheet 3 of 3

Proposal No.:

MECHANICAL EQUIPMENT (Continued)	
Fans	
Fan Speed, rpm	102.7
Tip Speed, fpm	11609
BHP per Fan, Driver Output	230.6
Blade Material	FIBERGLASS REINFORCED VINYL ESTER
Hub Material	EPOXY COATED
Total Static Pressure, in H ₂ O	0.614
Velocity Pressure, in H ₂ O	0.142
Air Delivery per Fan, ACFM	1,310,000
Fan Static Efficiency, %	65.0
Fan Total Efficiency, %	80.0
Speed Reducer	
Number	6
Type	RIGHT ANGLE, SPIRAL BEVEL
Model	1713
Manufacturer	AMARILLO
Reduction Ratio	17.34:1
AGMA Mechanical H.P. Rating	544
Service Factor at Rated H.P. of Driver	2.18
Number of Reductions	2
Drive Shaft	
Number	6
Type	FULL FLOATING NON-LUBRICATED
Model	LRX650.625
Manufacturer	ADDAX
Rated HP	520
Drive Shaft Material	COMPOSITE
Coupling Material	316 STAINLESS STEEL
Driver	
Number	6
Kind	ELECTRIC MOTOR
Type	TOTALLY ENCLOSED FAN COOLED (TEFC)
Manufacturer	BALDOR, TOSHIBA, US MOTOR OR EQUAL
Full Load Speed, RPM	1800
Electric Characteristics - phase/cycles/volts	3/60/480
Rated HP	250
ADDITIONAL DATA:	

[illegible]

NOTES:

ATTACHMENT C.1-5
DIESEL FUEL ANALYSIS DATA

Typical Diesel Fuel Analysis Data

Parameter	Average Data
Carbon %	85.86
Hydrogen %	13.35
Oxygen %	0.65
Nitrogen %	0.097
Sulfur %	0.0015 – 0.05
Ash %	0.01
Btu/gal (HHV)	~139,000
Lbs/gal	~6.87
Data derived from AB2588 fuel testing for sources in the South Coast AQMD. Total number of samples used for averages = 10.	

ATTACHMENT C.1-6
NATURAL GAS FUEL ANALYSIS DATA

Typical Natural Gas Composition

Component	Molar Percent (%)
Methane, CH ₄	96.11
Ethane, C ₂ H ₆	1.80
Propane, C ₃ H ₈	0.30
Butane, C ₄ H ₁₀	0.10
Pentane, C ₅ H ₁₂	0.00
Hexane, C ₆ H ₁₂	0.03
Carbon Dioxide, CO ₂	1.24
Nitrogen, N ₂	0.04
Total	100.00
Sulfur (grains per 100 dry standard cubic feet (dscf))	~0.20
Higher Heating Value (Btu/scf)	~1,020 – 1,025

ATTACHMENT C.1-7

HTF MSDS

Solutia Inc.

Material Safety Data Sheet

1. PRODUCT AND COMPANY IDENTIFICATION

Product name: THERMINOL® VP1 Heat transfer fluid

Reference Number: 000000000211

Date: 05/16/2006

Company Information:

United States:

Solutia Inc.
575 Maryville Center Drive, P.O. Box 66760
St. Louis, MO 63166-6760
Emergency telephone: Chemtrec: 1-800-424-9300
International Emergency telephone: Chemtrec: 703-527-3887
Non-Emergency telephone: 1-314-674-6661

Canada:

Solutia Canada Inc.
6800 St. Patrick Street
LaSalle, PQ H8N 2H3
Emergency telephone: CANUTEC: 1-613-996-6666
Non-Emergency telephone: 1-314-674-6661

Mexico:

Solutia MEXICO, S. DE R.L. DE C.V.
Prol. Paseo de la Reforma 2654
Local 501, Piso-5
Col. Lomas Altas
11950 Mexico, D.F.
Emergency telephone: SETIQ: (in Mexico) 01-800-002-1400
Non-Emergency telephone: (in Mexico) 01-55-5259-6800

Brazil:

Solutia Brazil Ltd.
Avenue Carlos Marcondes, 1200
CEP: 12241-420-São José dos Campos/SP-Brazil
Emergency telephone: 55 12 3932 7100 (PABX)
Non-Emergency telephone: 55 11 3365 1800 (PABX)

2. HAZARDS IDENTIFICATION

EMERGENCY OVERVIEW

Form:	liquid
Colour:	clear to colourless
Odour:	characteristic

WARNING STATEMENTS

WARNING!
Causes eye irritation
Causes skin irritation
Causes respiratory tract irritation
Contains material which can cause liver and nerve damage

POTENTIAL HEALTH EFFECTS

Likely routes of exposure:	eye and skin contact inhalation
Eye contact:	Highly irritating to eyes.
Skin contact:	Highly irritating to skin. Prolonged or repeated skin contact may result in irritant dermatitis.
Inhalation:	Severely irritating if inhaled. No more than slightly toxic if inhaled. Significant adverse health effects are not expected to develop under normal conditions of exposure.
Ingestion:	No more than slightly toxic if swallowed. Significant adverse health effects are not expected to develop if only small amounts (less than a mouthful) are swallowed.
Signs and symptoms of overexposure:	headache fatigue nausea/vomiting indigestion abdominal pain tremors
Target organs/systems:	May cause liver damage May cause nerve damage

Refer to Section 11 for toxicological information.

3. COMPOSITION/INFORMATION ON INGREDIENTS

<u>Components</u>	<u>CAS No.</u>	<u>Average concentration</u>	<u>Concentration range</u>	<u>Units</u>
diphenyl ether	101-84-8	73.5		%
biphenyl	92-52-4	26.5		%

4. FIRST AID MEASURES

If in eyes:	Immediately flush with plenty of water for at least 15 minutes. If easy to do, remove any contact lenses. Get medical attention. Remove material from skin and clothing.
If on skin:	Immediately flush the area with plenty of water. Remove contaminated clothing. Wash skin gently with soap as soon as it is available. Get medical attention. Wash clothing before reuse.
If inhaled:	Remove patient to fresh air. If not breathing, give artificial respiration. If breathing is difficult give oxygen. Remove material from eyes, skin and clothing.

If swallowed: Immediate first aid is not likely to be required.
A physician or Poison Control Center can be contacted for advice.
Wash heavily contaminated clothing before reuse.

5. FIRE FIGHTING MEASURES

Fire point: 127 C

Hazardous products of combustion: carbon monoxide (CO); carbon dioxide; hydrocarbons

Extinguishing media: Water spray, foam, dry chemical, or carbon dioxide

Unusual fire and explosion hazards: None known

Fire fighting equipment: Firefighters, and others exposed, wear self-contained breathing apparatus.
Equipment should be thoroughly decontaminated after use.

Miscellaneous advice: This product is not classified as a fire-resistant heat transfer fluid.
Precautions to avoid sources of ignitions should be taken.

6. ACCIDENTAL RELEASE MEASURES

Personal precautions: Use personal protection recommended in section 8.

Environmental precautions: Keep out of drains and water courses.

Methods for cleaning up: Contain large spills with dikes and transfer the material to appropriate containers for reclamation or disposal. Absorb remaining material or small spills with an inert material and then place in a chemical waste container. Flush spill area with water.

Refer to Section 13 for disposal information and Sections 14 and 15 for reportable quantity information.

7. HANDLING AND STORAGE

Handling

Avoid contact with eyes, skin and clothing.
Avoid breathing vapour or mist.
Keep container closed.
Use with adequate ventilation.
Wash thoroughly after handling.
Precautions against ignitions and fire should be taken with this product.
Heat transfer fluids are intended for INDIRECT heating purposes ONLY.
This product has not been approved for food grade use.

Emptied containers retain vapour and product residue. Observe all recommended safety precautions until container is cleaned, reconditioned or destroyed. Do not cut, drill, grind or weld on or near this container. The reuse of this material's container for non industrial purposes is prohibited and any reuse must be in consideration of the data provided in this material safety data sheet.

Storage

General: Stable under normal conditions of handling and storage.

8. EXPOSURE CONTROLS/PERSONAL PROTECTION

Airborne exposure limits: (ml/m3 = ppm)

THERMINOL® VP1 No specific occupational exposure limit has been established.

biphenyl ACGIH TLV: 0.2 ml/m3 ; mist ; 8-hr TWA
OSHA PEL: 0.2 ml/m3 ; 1.0 mg/m3 ; ; 8-hr TWA
Mexican OEL: 0.2 ml/m3 ; 1.5 mg/m3 ; ; 8-hr TWA
Mexican OEL: 0.6 ml/m3 ; 4 mg/m3 ; ; 15-min STEL

diphenyl ether ACGIH TLV: 1 ml/m3 ; ; 8-hr TWA
ACGIH TLV: 2 ml/m3 ; ; 15-min STEL
OSHA PEL: 1 ml/m3 ; 7 mg/m3 ; ; 8-hr TWA
Mexican OEL: 1 ml/m3 ; 7 mg/m3 ; ; 8-hr TWA
Mexican OEL: 2 ml/m3 ; 14 mg/m3 ; ; 15-min STEL

Eye protection: Wear safety goggles.
Have eye flushing equipment available.

Hand protection: Wear chemical resistant gloves.
Consult the glove/clothing manufacturer to determine the appropriate type
glove/clothing for a given application.
See Solutia Glove Facts for permeation data.

Body protection: Wear suitable protective clothing.
Consult the glove/clothing manufacturer to determine the appropriate type
glove/clothing for a given application.
Wear full protective clothing if exposed to splashes.
Wash contaminated skin promptly.
Launder contaminated clothing and clean protective equipment before reuse.
Wash thoroughly after handling.
Have safety shower available at locations where skin contact can occur.

Respiratory protection: Avoid breathing vapour or mist.
Use approved respiratory protection equipment (full facepiece recommended) when
airborne exposure limits are exceeded.
If used, full facepiece replaces the need for face shield and/or chemical goggles.
Consult the respirator manufacturer to determine the appropriate type of equipment for
a given application.
Observe respirator use limitations specified by the manufacturer.

Ventilation: Provide natural or mechanical ventilation to control exposure levels below airborne
exposure limits.
If practical, use local mechanical exhaust ventilation at sources of air contamination
such as processing equipment.

Components referred to herein may be regulated by specific Canadian provincial legislation. Please refer to exposure
limits legislated for the province in which the substance will be used.

9. PHYSICAL AND CHEMICAL PROPERTIES

Flash point:	110 C	Pensky-Martens closed tester
	124 C	Cleveland Open Cup

Autoignition temperature:	612 C	ASTM D-2155
Density:	1.06 g/cm3 @ 25 C	
Boiling point :	257 C	
Crystallising point :	12 C	
Water solubility:	~25 mg/l	

NOTE: These physical data are typical values based on material tested but may vary from sample to sample. Typical values should not be construed as a guaranteed analysis of any specific lot or as specifications for the product.

10. STABILITY AND REACTIVITY

Conditions to avoid:	All sources of ignition.
Materials to avoid:	Contact with strong oxidizing agents.
Hazardous reactions:	Hazardous polymerization does not occur.
Hazardous decomposition products:	None known;

11. TOXICOLOGICAL INFORMATION

This product has been tested for toxicity. Results from Solutia sponsored studies or from the available public literature are described below.

Acute animal toxicity data

Oral:	LD50 , rat, 2,050 mg/kg , No more than slightly toxic
Dermal:	LD50 , rabbit, > 5,010 mg/kg , Practically nontoxic after skin application in animal studies.
Inhalation:	LC50 , rat, 2.66 mg/l , 4 h, Toxic based on animal inhalation exposure studies.
Skin irritation:	rabbit , Slightly irritating to skin., 24 h
Repeat dose toxicity:	rat , , inhalation, 13 weeks , , Produced effects on body weight, serum enzymes and/or organ weights in repeat dose studies.
Repeat dose toxicity:	rat , , gavage, 26 weeks. , Produced effects on body weight, serum enzymes and/or organ weights in repeat dose studies. Effects only observed at very high dose levels.
Target organs affected	kidneys, liver, spleen
Repeat dose toxicity:	rat , , diet, subchronic, , Repeated oral exposure produced liver and kidney changes in animal models.
Target organs affected	liver, kidneys
Developmental toxicity:	rat, gavage, , No effects on offspring observed in laboratory animals in the presence of maternal toxicity.

Mutagenicity: No genetic effects were observed in standard tests using bacterial and animal cells.

Components

Data from Solutia studies and/or the available scientific literature on the components of this material which have been identified as hazardous chemicals under the criteria of the OSHA Hazard Communication Standard (29 CFR 1910.1200) or the Canadian Hazardous Products Act are discussed below.

biphenyl Chronic exposure has been reported to cause headache, fatigue, nausea, indigestion, abdominal pain, tremor, central and peripheral nerve damage and liver injury.
Slightly toxic following oral administration.
Practically nontoxic after skin application in animal studies.
Practically non irritating to skin (rabbit).
Slightly irritating to eyes (rabbit).
No mortality or signs of toxicity at the highest level achievable.
Irritating to respiratory system in animal models.
Produced effects on body weight, serum enzymes and/or organ weights in repeat dose studies.
Produced no dermal sensitization (guinea pigs).
No effects on offspring observed in laboratory animals in the presence of maternal toxicity.
No genetic effects were observed in standard tests using bacterial and animal cells.

diphenyl ether Predictive patch testing on human volunteers did not produce irritation or sensitization.
Slightly toxic following oral administration.
Practically nontoxic after skin application in animal studies.
Slightly irritating to eyes (rabbit).
Slightly irritating to skin (rabbit).
Repeated exposure produced respiratory tract irritation in animal models.
Repeated exposure produced eye irritation in animal models.
No genetic effects were observed in standard tests using bacterial and animal cells.

12. ECOLOGICAL INFORMATION

Environmental Toxicity

Invertebrates	48 h, EC50	Water flea (<i>Daphnia magna</i>)	2.4 mg/l
Fish:	96 h, LC50	Rainbow trout (<i>Oncorhynchus mykiss</i>)	7.6 mg/l
	96 h, LC50	Fathead minnow (<i>Pimephales promelas</i>)	24 mg/l
Algae:	96 h, EC50	Algae (<i>Selenastrum capricornutum</i>)	1.3 mg/l
Biodegradation	Modified SCAS (OECD 302A) Primary degradation 99 %		

13. DISPOSAL CONSIDERATIONS

US EPA RCRA Status: This material when discarded may be a hazardous waste as that term is defined by the Resource Conservation and Recovery Act (RCRA), 40 CFR 261.24, due to its toxicity characteristic. This material should be analyzed in accordance with Method 1311 for the compound(s) below.

US EPA RCRA	D018	Compound/Characteristic:	BENZENE
-------------	------	--------------------------	---------

hazardous waste number:

Disposal considerations: Incineration

Miscellaneous advice: This product meets the criteria for a synthetic used oil under the U.S. EPA Standards for the Management of Used Oil (40 CFR 279). Those standards govern recycling and disposal in lieu of 40 CFR 260 -272 of the Federal hazardous waste program in states that have adopted these used oil regulations. Consult your attorney or appropriate regulatory official to be sure these standards have been adopted in your state. Recycle or burn in accordance with the applicable standards.
Solutia operates a used fluid return program for certain fluids under these used oil standards. Contact your Sales Representative for details.
This product should not be dumped, spilled, rinsed or washed into sewers or public waterways.

14. TRANSPORT INFORMATION

The data provided in this section is for information only. Please apply the appropriate regulations to properly classify your shipment for transportation.

US DOT

Proper shipping name: ENVIRONMENTALLY HAZARDOUS SUBSTANCE, LIQUID, N.O.S.
biphenyl
Hazard Class: 9
Hazard Identification number: UN3082
Packing Group: Packing Group III
Transport label: Class 9
Special provisions: This material meets the definition of a marine pollutant.
Other: Applies ONLY to containers with an RQ or for shipments in bulk via water transportation.

Canadian TDG

Other: Not regulated for transport.

Reportable Quantity/Limit

US DOT RQ 100 lb *biphenyl*
Package size containing reportable amount: 377 lb

ICAO/IATA Class

Other: See DOT Information

15. REGULATORY INFORMATION

All components are in compliance with the following inventories: U.S. TSCA, EU EINECS, Canadian DSL, Australian AICS, Korean, Japanese ENCS, Phillipine PICCS, Chinese

Canadian WHMIS classification: D2(A) - Materials Causing Other Toxic Effects
D2(B) - Materials Causing Other Toxic Effects

SARA Hazard Notification:

Hazard Categories Under Title III Rules (40 CFR 370): Immediate
Delayed

Product name: THERMINOL® VP1 Heat transfer fluid
Solutia Inc. Material Safety Data Sheet
Reference Number: 000000000211

Page 8 / 8
Date: 05/16/2006
Version 5.2/E

Section 302 Extremely Hazardous Substances: Not applicable

Section 313 Toxic Chemical(s): biphenyl

CERCLA Reportable Quantity:

100 lbs biphenyl

For this/these chemicals, release of more than the Reportable Quantity to the environment in a 24 hour period requires notification to the National Response Center (800-424-8802 or 202-426-2675).

This product has been classified in accordance with the hazard criteria of the Canadian Controlled Products Regulation and the MSDS contains all the information required by the Canadian Controlled Products Regulation.

Refer to Section 11 for OSHA/HPA Hazardous Chemical(s) and Section 13 for RCRA classification.

Safety data sheet also created in accordance with Brazilian law NBR 14725

16. OTHER INFORMATION

Product use: Heat transferring agents

Reason for revision: Significant changes to the following section(s); Section 1

	Health	Fire	Reactivity	Additional Information
Suggested NFPA Rating	2	1	0	
Suggested HMIS Rating:	2	1	0	G

Prepared by the Solutia Hazard Communication Group. Please consult Solutia @ 314-674-6661 if further information is needed.

TM, ® is a registered trademark of Solutia Inc.

SOLUTIA is a trademark of Solutia Inc.

Responsible Care® is a registered trademark of the American Chemistry Council.

Although the information and recommendations set forth herein (hereinafter "Information") are presented in good faith and believed to be correct as of the date hereof, Solutia Inc. makes no representations as to the completeness or accuracy thereof. Information is supplied upon the condition that the persons receiving same will make their own determination as to its suitability for their purposes prior to use. In no event will Solutia Inc. be responsible for damages of any nature whatsoever resulting from the use of or reliance upon Information. NO REPRESENTATIONS OR WARRANTIES, EITHER EXPRESS OR IMPLIED, OF MERCHANTABILITY, FITNESS FOR A PARTICULAR PURPOSE OR OF ANY OTHER NATURE ARE MADE HEREUNDER WITH RESPECT TO INFORMATION OR THE PRODUCT TO WHICH INFORMATION REFERS.

THERMINOL® VP-1

Heat Transfer Fluid by Solutia

Vapor Phase/
Liquid Phase
Heat Transfer Fluid

54°F to
750°F



+400°C

+700°F

+350°C

+600°F

+300°C

+500°F

+250°C

+400°F

+200°C

+300°F

+150°C

+200°F

+100°C

+100°F

+50°C

0°F

0°C

0°F

-50°C

-100°F

LIQUID USE RANGE

LIQUID USE RANGE

-50°F 0°F 50°F 100°F 150°F 200°F 250°F 300°F 350°F
 -50°C 0°C 50°C 100°C 150°C

LIQUID
12°C (54°F)

OPTIMUM USE RANGE

LIQUID
12°C TO 400°C (54°F TO 750°F)

Therminol® VP-1 heat transfer fluid is specifically designed to meet the demanding requirements of vapor phase systems. It combines exceptional heat stability and low viscosity for efficient, dependable, uniform performance in a wide optimum use range of 12°C to 400°C.


THERMINOL® VP-1

Heat Transfer Fluid by **Solutia**

TABLE OF CONTENTS

Typical Properties	1
Liquid Properties of Therminol VP-1	2
Vapor Properties of Therminol VP-1	4
Physical and Chemical Characteristics	6
Fire Safety Considerations	6
Start-up and Shut-down Procedures	7
Toxicity and Handling	7

VAPOR USE RANGE



THERMINOL VP-1

Appearance	Clear, water-white liquid
Composition	Biphenyl and diphenyl oxide
Moisture Content, Maximum	300 ppm
Chlorine	< 10 ppm
Sulfur	< 10 ppm
Neutralization Number	< 0.2 mg KOH/g
Copper Corrosion (ASTM D-130)	<< 1 a
Flash Point, Open Cup (ASTM D-92)	124 °C (255 °F)
Closed Cup (Pensky-Martens)	110 °C (230 °F)
Fire Point (ASTM D-92)	127 °C (260 °F)
Autoignition Temperature (ASTM D-2155)	621 °C (1150 °F)
Kinematic Viscosity at 40 °C	2.48 mm ² /s (cSt)
at 100 °C	0.99 mm ² /s (cSt)
Density at 25 °C	1060 kg/m ³ (8.85 lb/gal)
Specific Gravity (60 °F/60 °F)	1.069
Coefficient of Thermal Expansion at 200 °C	0.000979/°C (0.000544/°F)
Average Molecular Weight	166
Crystallization Point	12 °C (54 °F)
Volume Contraction Upon Freezing	6.27%
Volume Expansion Upon Melting	6.69%
Surface Tension in Air at 25 °C	36.6 dyn/cm
Heat of Fusion	97.3 kJ/kg (41.8 Btu/lb)
Normal Boiling Point	257 °C (495 °F)
Heat of Vaporization at Maximum Use Temperature 400 °C	206 kJ/kg (88.7 Btu/lb)
Specific Resistivity at 20 °C	6.4 x 10 ¹¹ ohm-cm
Optimum Use Range, Liquid	12 °C-400 °C (54 °F-750 °F)
Vapor	260 °C-400 °C (500 °F-750 °F)
Maximum Film Temperature	425 °C (800 °F)
Pseudocritical Temperature	499 °C (930 °F)
Pseudocritical Pressure	33.1 bar (480 psia)
Pseudocritical Density	327 kg/m ³ (20.4 lb/ft ³)

* These data are based upon samples tested in the laboratory and are not guaranteed for all samples.
Write us for complete sales specifications for Therminol VP-1 fluid.

† Does not constitute an express warranty. See NOTICE on the last page of this bulletin.

LIQUID PROPERTIES OF THERMINOL

Temperature		Liquid Density			Liquid Heat Capacity		Liquid Enthalpy**	
°F	°C	lb/gal	lb/ft ³	kg/m ³	Btu/lb-°F [cal/g-°C]	kJ/kg-K	Btu/lb	kJ/kg
54	12	8.93	66.8	1071	0.364	1.52	0.0	0.0
60	16	8.91	66.7	1068	0.366	1.53	2.3	5.4
80	27	8.84	66.1	1059	0.374	1.57	9.8	22.7
100	38	8.76	65.5	1050	0.382	1.60	17.3	40.2
120	49	8.69	65.0	1041	0.390	1.63	25.0	58.2
140	60	8.61	64.4	1032	0.397	1.66	32.9	76.4
160	71	8.53	63.8	1023	0.405	1.69	40.9	95.1
180	82	8.46	63.3	1014	0.412	1.73	49.1	114.1
200	93	8.38	62.7	1004	0.420	1.76	57.4	133.4
220	104	8.31	62.1	995	0.427	1.79	65.9	153.1
240	116	8.23	61.6	986	0.435	1.82	74.5	173.1
260	127	8.15	61.0	977	0.442	1.85	83.3	193.5
280	138	8.07	60.4	967	0.449	1.88	92.2	214.2
300	149	7.99	59.8	958	0.457	1.91	101.2	235.3
320	160	7.91	59.2	948	0.464	1.94	110.4	256.7
340	171	7.83	58.6	939	0.471	1.97	119.8	278.4
360	182	7.75	58.0	929	0.478	2.00	129.3	300.5
380	193	7.67	57.4	919	0.485	2.03	138.9	322.9
400	204	7.59	56.8	909	0.492	2.06	148.7	345.6
420	215	7.50	56.1	899	0.499	2.09	158.6	368.6
440	227	7.42	55.5	889	0.506	2.12	168.7	392.0
460	238	7.33	54.9	879	0.514	2.15	178.9	415.7
480	249	7.25	54.2	868	0.521	2.18	189.2	439.8
495	257	7.18	53.7	860	0.526	2.20	197.0	457.4
500	260	7.16	53.5	857	0.528	2.21	199.7	464.1
520	271	7.07	52.8	847	0.535	2.24	210.3	488.8
540	282	6.97	52.2	835	0.542	2.27	221.1	513.8
560	293	6.88	51.4	824	0.549	2.30	232.0	539.2
580	304	6.78	50.7	812	0.556	2.33	243.0	564.9
600	316	6.68	50.0	800	0.563	2.36	254.2	590.9
620	327	6.58	49.2	788	0.570	2.39	265.5	617.2
640	338	6.47	48.4	775	0.578	2.42	277.0	643.9
660	349	6.36	47.6	762	0.586	2.45	288.7	671.0
680	360	6.25	46.7	749	0.594	2.48	300.5	698.4
700	371	6.13	45.9	734	0.602	2.52	312.4	726.2
720	382	6.01	44.9	720	0.612	2.56	324.6	754.4
740	393	5.88	43.9	704	0.622	2.60	336.9	783.1
750	399	5.81	43.4	696	0.627	2.62	343.1	797.6
760	404	5.74	42.9	687	0.633	2.65	349.4	812.2
780	416	5.59	41.8	670	0.646	2.70	362.2	842.0
800	427	5.43	40.6	651	0.662	2.77	375.3	872.4

* These data are based upon samples tested in the laboratory and are not guaranteed for all samples. Write us for complete sales specifications for Therminol VP-1 fluid.

** The enthalpy basis is liquid at the crystallizing point, 53.6 °F (12 °C).

† Does not constitute an express warranty. See NOTICE on the last page of this bulletin.

VP-1 HEAT TRANSFER FLUID

Liquid Thermal Conductivity			Liquid Viscosity			Vapor Pressure				Temperature	
Btu/ ft-hr-°F	kcal/ m-hr-°C	W/m-K	lb/ft-hr	cSt [mm²/s]	cP [mPa.s]	psia	mm Hg	kgf/cm²	kPa	°F	°C
0.0792	0.1179	0.1370	13.26	5.12	5.48					54	12
0.0790	0.1176	0.1367	11.84	4.58	4.89					58	16
0.0784	0.1167	0.1357	8.64	3.37	3.57	0.0004	0.019	0.00003	0.0026	60	27
0.0778	0.1158	0.1346	6.60	2.60	2.73	0.0010	0.054	0.00007	0.0071	100	38
0.0772	0.1148	0.1334	5.23	2.08	2.16	0.0026	0.134	0.00018	0.0178	120	49
0.0765	0.1138	0.1323	4.26	1.707	1.761	0.0059	0.307	0.00042	0.0409	140	60
0.0758	0.1128	0.1310	3.55	1.434	1.467	0.0127	0.655	0.00087	0.0874	160	71
0.0750	0.1117	0.1298	3.01	1.228	1.244	0.0254	1.31	0.00179	0.175	180	82
0.0743	0.1106	0.1285	2.59	1.067	1.071	0.0483	2.50	0.00339	0.333	200	93
0.0735	0.1094	0.1271	2.26	0.938	0.934	0.0872	4.51	0.00613	0.602	220	104
0.0727	0.1082	0.1257	1.990	0.834	0.823	0.151	7.81	0.0106	1.04	240	116
0.0719	0.1070	0.1243	1.769	0.749	0.731	0.251	13.0	0.0177	1.73	260	127
0.0710	0.1057	0.1228	1.585	0.677	0.655	0.404	20.9	0.0284	2.78	280	138
0.0701	0.1044	0.1213	1.430	0.617	0.591	0.629	32.5	0.0442	4.33	300	149
0.0692	0.1030	0.1197	1.298	0.566	0.537	0.951	49.2	0.0669	6.56	320	160
0.0683	0.1017	0.1181	1.185	0.522	0.490	1.40	72.6	0.0986	9.67	340	171
0.0674	0.1002	0.1165	1.086	0.483	0.449	2.02	105	0.142	13.9	360	182
0.0664	0.0988	0.1148	1.001	0.450	0.414	2.85	147	0.200	19.6	380	193
0.0654	0.0973	0.1131	0.926	0.421	0.383	3.94	204	0.277	27.2	400	204
0.0644	0.0958	0.1113	0.859	0.395	0.355	5.35	277	0.376	36.9	420	216
0.0633	0.0942	0.1095	0.800	0.372	0.331	7.15	370	0.503	49.3	440	227
0.0622	0.0926	0.1076	0.748	0.352	0.309	9.41	487	0.661	64.9	460	238
0.0611	0.0910	0.1057	0.700	0.333	0.290	12.2	631	0.858	84.2	480	249
0.0603	0.0897	0.1043	0.668	0.321	0.276	14.7	760	1.03	101	495	257
0.0600	0.0893	0.1038	0.658	0.317	0.272	15.6	808	1.10	108	500	260
0.0588	0.0876	0.1018	0.620	0.303	0.256	19.8	1020	1.39	136	520	271
0.0577	0.0858	0.0998	0.585	0.289	0.242	24.8	1280	1.74	171	540	282
0.0565	0.0841	0.0977	0.553	0.278	0.229	30.7	1590	2.16	211	560	293
0.0552	0.0822	0.0956	0.524	0.267	0.217	37.6	1940	2.64	259	580	304
0.0540	0.0804	0.0934	0.498	0.257	0.206	45.7	2360	3.21	315	600	316
0.0527	0.0785	0.0912	0.474	0.248	0.1958	55.1	2850	3.87	380	620	327
0.0514	0.0765	0.0890	0.451	0.241	0.1866	65.8	3400	4.63	454	640	338
0.0501	0.0746	0.0867	0.431	0.234	0.1781	78.1	4040	5.49	539	660	349
0.0488	0.0726	0.0844	0.412	0.227	0.1703	92.1	4760	6.47	635	680	360
0.0474	0.0705	0.0820	0.394	0.222	0.1630	108	5580	7.58	743	700	371
0.0460	0.0685	0.0796	0.378	0.217	0.1562	125	6490	8.82	865	720	382
0.0446	0.0663	0.0771	0.363	0.213	0.1500	145	7510	10.2	1000	740	393
0.0439	0.0653	0.0759	0.356	0.211	0.1470	156	8060	11.0	1070	750	399
0.0431	0.0642	0.0746	0.349	0.210	0.1441	167	8640	11.7	1150	760	404
0.0417	0.0620	0.0721	0.335	0.207	0.1387	191	9890	13.4	1320	780	415
0.0402	0.0598	0.0695	0.323	0.205	0.1336	218	11300	15.3	1500	800	427



VAPOR PROPERTIES OF THERMINOL

Temperature		Vapor Density		Vapor Heat Capacity		Heat of Vaporization		Vapor Enthalpy***	
°F	°C	lb/ft ³	kg/m ³	Btu/lb-°F [cal/g-°C]	kJ/kg-K	Btu/lb	kJ/kg	Btu/lb	kJ/kg
54	12			0.233	0.98	180.3	419.0	180.3	419.0
60	16			0.236	0.99	179.4	417.1	181.8	422.5
80	27	0.00001	0.00017	0.245	1.03	176.8	411.1	186.6	433.7
100	38	0.00003	0.00046	0.254	1.06	174.3	405.1	191.6	445.3
120	49	0.00007	0.00110	0.263	1.10	171.7	399.2	196.8	457.3
140	60	0.00015	0.00245	0.272	1.14	169.2	393.3	202.1	469.8
160	71	0.00032	0.00507	0.280	1.17	166.7	387.5	207.6	482.6
180	82	0.00061	0.00985	0.289	1.21	164.2	381.8	213.3	495.8
200	93	0.00113	0.0181	0.298	1.25	161.8	376.1	219.2	509.5
220	104	0.00199	0.0318	0.306	1.28	159.4	370.4	225.2	523.5
240	116	0.00334	0.0535	0.315	1.32	156.9	364.8	231.4	537.9
260	127	0.00541	0.0866	0.323	1.35	154.5	359.2	237.8	552.7
280	138	0.00846	0.136	0.331	1.39	152.2	353.7	244.3	567.9
300	149	0.0128	0.206	0.340	1.42	149.8	348.2	251.0	583.5
320	160	0.0189	0.303	0.348	1.45	147.4	342.7	257.9	599.4
340	171	0.0273	0.437	0.356	1.49	145.1	337.2	264.8	615.6
360	182	0.0384	0.615	0.363	1.52	142.7	331.7	272.0	632.2
380	193	0.0529	0.848	0.371	1.55	140.4	326.3	279.3	649.1
400	204	0.0717	1.15	0.379	1.58	138.0	320.8	286.7	666.4
420	216	0.0954	1.53	0.386	1.62	135.6	315.3	294.2	683.9
440	227	0.125	2.00	0.394	1.65	133.2	309.7	301.9	701.7
460	238	0.162	2.59	0.401	1.68	130.8	304.1	309.7	719.9
480	249	0.206	3.31	0.408	1.71	128.4	298.5	317.6	738.2
495	257	0.246	3.93	0.414	1.73	126.6	294.2	323.6	752.1
500	260	0.260	4.17	0.416	1.74	125.9	292.7	325.6	756.9
520	271	0.325	5.20	0.423	1.77	123.4	286.9	333.7	775.7
540	282	0.401	6.43	0.430	1.80	120.9	281.0	342.0	794.8
560	283	0.492	7.87	0.437	1.83	118.3	274.9	350.2	814.1
580	304	0.597	9.57	0.444	1.86	115.6	268.7	358.6	833.6
600	316	0.720	11.5	0.451	1.89	112.9	262.3	367.1	853.2
620	327	0.862	13.8	0.458	1.91	110.0	255.8	375.6	873.0
640	338	1.03	16.4	0.464	1.94	107.1	249.0	384.2	893.0
660	349	1.22	19.5	0.471	1.97	104.1	242.0	392.8	913.0
680	360	1.43	22.9	0.478	2.00	101.0	234.7	401.4	933.1
700	371	1.68	26.9	0.485	2.03	97.7	227.1	410.1	953.3
720	382	1.96	31.4	0.492	2.06	94.2	219.1	418.8	973.5
740	393	2.29	36.6	0.500	2.09	90.6	210.6	427.5	993.7
760	398	2.47	39.5	0.504	2.11	88.7	206.2	431.9	1003.8
760	404	2.66	42.6	0.508	2.12	86.8	201.7	436.2	1013.9
780	416	3.08	49.4	0.516	2.16	82.6	192.1	444.9	1034.0
800	427	3.57	57.2	0.526	2.20	78.1	181.6	453.4	1054.0

* Vapor properties given are for saturated vapor.

** These data are based upon samples tested in the laboratory and are not guaranteed for all samples. Write us for complete sales specifications for Therminol VP-1 fluid.

*** The enthalpy basis is liquid at the crystallizing point, 53.6 °F (12 °C).

† Does not constitute an express warranty. See NOTICE on the last page of this bulletin.

VAPOR THERMAL CONDUCTIVITY AND VISCOSITY

Vapor Thermal Conductivity			Vapor Viscosity			Temperature	
Btu/ ft-hr-°F	kcal/ m-hr-°C	W/m-K	lb/ft-hr	cSt [mm²/s]	cP [mPa-s]	°F	°C
0.0047	0.0069	0.0081	0.0138		0.0057	54	12
0.0048	0.0071	0.0082	0.0140		0.0058	60	16
0.0051	0.0076	0.0088	0.0145		0.0060	68	20
0.0054	0.0081	0.0094	0.0150		0.0062	75	24
0.0057	0.0086	0.0099	0.0156		0.0064	82	28
0.0061	0.0090	0.0105	0.0161	2720	0.0067	90	32
0.0064	0.0095	0.0111	0.0167	1360	0.0069	98	37
0.0068	0.0100	0.0117	0.0172	723	0.0071	105	42
0.0071	0.0106	0.0123	0.0178	405	0.0074	113	46
0.0074	0.0111	0.0129	0.0183	238	0.0076	120	50
0.0078	0.0116	0.0135	0.0189	146	0.0078	128	54
0.0082	0.0121	0.0141	0.0194	92.8	0.0080	135	58
0.0085	0.0127	0.0147	0.0200	61.0	0.0083	143	63
0.0089	0.0132	0.0154	0.0206	41.3	0.0085	150	67
0.0092	0.0138	0.0160	0.0211	28.8	0.0087	158	72
0.0096	0.0143	0.0166	0.0217	20.5	0.0090	165	76
0.0100	0.0149	0.0173	0.0222	15.0	0.0092	173	80
0.0104	0.0154	0.0179	0.0228	11.1	0.0094	180	84
0.0107	0.0160	0.0186	0.0234	8.41	0.0097	188	88
0.0111	0.0166	0.0192	0.0239	6.47	0.0099	195	92
0.0115	0.0171	0.0199	0.0245	5.05	0.0101	203	96
0.0119	0.0177	0.0206	0.0250	3.99	0.0103	210	100
0.0123	0.0183	0.0213	0.0256	3.20	0.0106	218	104
0.0126	0.0187	0.0218	0.0260	2.73	0.0107	225	108
0.0127	0.0189	0.0220	0.0261	2.59	0.0108	233	112
0.0131	0.0195	0.0226	0.0267	2.12	0.0110	240	116
0.0135	0.0201	0.0233	0.0272	1.75	0.0113	248	120
0.0139	0.0207	0.0240	0.0278	1.46	0.0115	255	124
0.0143	0.0213	0.0248	0.0284	1.22	0.0117	263	128
0.0147	0.0219	0.0255	0.0289	1.04	0.0120	270	132
0.0152	0.0225	0.0262	0.0294	0.882	0.0122	278	136
0.0156	0.0232	0.0269	0.0300	0.754	0.0124	285	140
0.0160	0.0238	0.0277	0.0306	0.649	0.0126	293	144
0.0164	0.0244	0.0284	0.0311	0.560	0.0128	300	149
0.0169	0.0251	0.0292	0.0316	0.486	0.0131	308	153
0.0173	0.0257	0.0299	0.0322	0.423	0.0133	315	158
0.0177	0.0264	0.0307	0.0327	0.369	0.0135	323	162
0.0180	0.0267	0.0310	0.0330	0.345	0.0136	330	166
0.0182	0.0270	0.0314	0.0332	0.323	0.0137	338	170
0.0186	0.0277	0.0322	0.0338	0.283	0.0140	345	170
0.0191	0.0284	0.0330	0.0343	0.248	0.0142	353	173

PHYSICAL AND CHEMICAL CHARACTERISTICS

Therminol® VP-1 is a eutectic mixture of 73.5% diphenyl oxide and 26.5% biphenyl. It is usable as a liquid or as a boiling-condensing heat transfer medium up to 750 °F (400 °C). It is miscible and interchangeable (for top-up or design purposes) with other similarly constituted diphenyl-oxide/biphenyl fluids.

Fluid Parameters Which Influence Design

The physical characteristics of Therminol VP-1 heat transfer fluid should be considered in the general arrangement of any heat transfer system in which it is to be used.

Therminol VP-1 has a low viscosity between its melting point (54 °F, 12 °C) and the temperature at which it vaporizes. In geographic areas where the system may be exposed to temperatures below this level, all piping that may contain the fluid in its liquid state should be heat traced.

Therminol VP-1 is exceptionally heat stable. However, care must be taken to avoid overheating, which could lead to deposition of solids on the heating surfaces of the vaporizer. Circulation rates in the heater should be selected to limit skin temperatures to reasonable values, with due consideration to the cost of replacing damaged fluid and the cost of maintaining an adequate heat flux. This is normally accomplished by the vaporizer or heater manufacturer in the course of recommending a particular unit and stipulating its operating parameters.

Under normal operating conditions, a vapor phase fluid will accumulate low-boiling contaminants such as air, water and degradation products. These noncondensables must be vented from the system to avoid aberrations in temperature control. Each user, or group of users if arranged in series, that operates after the same control valve should have at least one vapor accumulator (VA) installed for detecting and venting noncondensables. This is especially true if close temperature control is needed.

The physical and thermodynamic properties of Therminol VP-1 can be found on pages 2-5.

FIRE SAFETY CONSIDERATIONS

Leaks from pipes, valves or joints that saturate insulation are potentially hazardous because of the wicking effect and large surface exposure. Under such conditions, along with high temperatures, many organic liquids can spontaneously ignite. Leaks should be promptly repaired and the contaminated insulation replaced.

Leaks from a direct-fired vaporizer into the fire chamber normally result in burning of the vapor. Obviously, this should be avoided.

When vapor leaks from a pressurized system to the atmosphere, it is condensed by the relatively cold air which it contacts. This causes formation of a fog of tiny liquid droplets. Fogs of combustible liquids, of sufficiently high concentration in air, will burn if ignited. The fogs are flammable even though the overall temperature of the fog-air mixture may be below the flash point of the liquid and even though the vapor saturation concentration is below the flammable level.

The combustion of a fog-air mixture can result in an explosion, much like the combustion of a flammable vapor-air mixture. Such a fog-air mixture, however, does not normally ignite spontaneously. An ignition source is necessary, together with a sufficient concentration of the combustible fog.

Good safety practice in design, maintenance and operation can circumvent the potential dangers associated with pressurized organic vapor systems. In addition, further safeguards can be provided through the installation of special safety systems.

For further information on such safety devices for vapor phase systems, refer to the Solutia Central Engineering Study on this topic, available in reprint from the American Institute of Chemical Engineers* (CEP Technical Manual, Volume 10, "Loss Prevention").

*1. G. C. Vincent and W. B. Howard, Hydrocarbon Mist Explosions, Part I – Prevention by Explosion Suppression.

*2. G. C. Vincent and R. C. Nelson, W. B. Howard and W. W. Russell, Hydrocarbon Mist Explosions, Part II – Prevention by Water Fog.

START-UP AND SHUT-DOWN PROCEDURES

Vapor System Start-up

There are several ways to start up vapor phase heating systems, but they generally contain these basic steps:

1. Open the vacuum system connection to the vapor system and wait until a steady-state vacuum is reached.
2. Close all valves to isolate the vapor system from the vacuum system.
3. Wait approximately 15 minutes and note any significant increase in pressure in the system. (This step is necessary to ensure that the system is fully closed.)
4. Introduce Therminol VP-1 to the vaporizer (or reboiler) and gradually heat to operating temperature. Periodically open the vacuum connections on the vent accumulators to evacuate the noncondensables. Continue venting until the temperature indicators show that hot vapor has reached the vent accumulators.

System Shut-down, Vacuum Draining

When the system is to be drained to a vacuum vessel, the shut-down procedure is as follows:

1. Cut off the heat source from the system.
2. Open the drain line to the vacuum vessel. (The liquid in the system will continue to flash into the drain until the vapor pressure of the liquid reaches the vacuum being pulled.)
3. When the liquid level stops dropping, introduce nitrogen to break the vacuum. The remaining liquid will drain relatively quickly.

System Shut-down, Pressure Draining

For draining into a pressure vessel, the procedure is only slightly different:

1. Make sure the available nitrogen pressure is less than the relief pressure of the vapor system.
2. Cut off the heat source.
3. Introduce nitrogen to the system.
4. Open the drain line to the pressure vessel.
5. Close the drain line after the system is drained.
6. Open all high-point vacuum connections to purge and help cool the system.

TOXICITY AND HANDLING

Toxicity

The rat acute oral LD50 of Therminol VP-1 heat transfer fluid is 2.05 grams/kilogram, administered as the undiluted material. When held in continuous 24-hour contact with rabbit skin, the dermal LD50 was estimated to be greater than 5.01 grams/kilogram. Thus, Therminol VP-1 is considered to be slightly toxic by ingestion in single doses and practically non-toxic by single dermal applications.

When 0.1 milliliter of undiluted Therminol VP-1 was placed into the conjunctival sac of the rabbit's eye, a slight degree of irritation resulted. The average score of the 24-, 48- and 72-hour readings was 3.8 on a scale of 110.0. All eyes had regained a normal appearance 72 hours after they were dosed.

A mild degree of irritation resulted when 0.5 milliliter of Therminol VP-1 was held in continuous 24-hour contact with intact and abraded rabbit skin. The Primary Irritation Index was 2.9 on a scale of 8.0.

Rats were exposed to a stream of air which was passed through Therminol VP-1 and led directly into the experimental chamber. Due to its low volatility, there was essentially no vaporization of test material, and the animals survived both the six-hour exposure and the subsequent 14-day observation period without observable effects.

THERMINOL[®] VP-1

Heat Transfer Fluid by **Solutia**

SAFETY AND HANDLING: Material Safety Data Sheets may be obtained from Environmental Operations, Industrial Products Group, Solutia Inc. Heat transfer fluids are intended only for indirect heating purposes. Under no circumstances should this product contact or in any way contaminate food, animal feed, food products, food packaging materials, food chemicals, pharmaceuticals or any items which may directly or indirectly be ultimately ingested by humans. Any contact may contaminate these items to the extent that their destruction may be required. Precautions against ignitions and fires should be taken with this product.

NOTICE: Although the information and recommendations set forth herein (hereinafter "Information") are presented in good faith and believed to be correct as of the date hereof, Solutia Inc. makes no representations or warranties as to the completeness or accuracy thereof. Information is supplied upon the condition that the persons receiving same will make their own determination as to its suitability for their purposes prior to use. In no event will Solutia Inc. be responsible for damages of any nature whatsoever resulting from the use of or reliance upon Information or the product to which Information refers. Nothing contained herein is to be construed as a recommendation to use any product, process, equipment or formulation in conflict with any patent, and Solutia Inc. makes no representation or warranty, express or implied, that the use thereof will not infringe any patent. NO REPRESENTATIONS OR WARRANTIES, EITHER EXPRESS OR IMPLIED, OF MERCHANTABILITY, FITNESS FOR A PARTICULAR PURPOSE OR OF ANY OTHER NATURE ARE MADE HEREUNDER WITH RESPECT TO INFORMATION OR THE PRODUCT TO WHICH INFORMATION REFERS.

WORLDWIDE SALES OFFICES

UNITED STATES

For order assistance

Please call our Customer Service Department, toll free at (800) 426-2463.

For technical assistance

Please call our Technical Service Hotline, toll free at (800) 433-6997.

Houston

1800 West Loop South
Suite 1360
Houston, Texas 77027
Tel: (713) 850-0088
Fax: (713) 850-0096

St. Louis

P.O. Box 66760
St. Louis, Missouri 63166-6760
Tel: (314) 674-1000
Fax: (314) 674-6331

INTERNATIONAL SALES OFFICES

Argentina

Solutia Argentina S.R.L.
Alicia Moreau de Justo 1050,
3rd Floor
1107 Puerto Madero
Buenos Aires, Argentina
Tel: 54-1-331-4077
Fax: 54-1-331-7481

Australia

Solutia Australia Pty. Ltd.
Level 1, 437 Canterbury Road
Surrey Hills, Victoria 3127
Australia
Tel: 61-3-9888-4589
Fax: 61-3-9888-4582

Belgium

Solutia Europe N.V./S.A.
Rue Laid Burniat, 3
Parc Scientifique - Fleming
B-1348 Louvain-la-Neuve (Sud)
Belgium
Tel: 32 10 48 12 11
Fax: 32 10 48 12 12

Brazil

Solutia Brazil Ltda.
Rua Gomes de Carvalho
1306-60, Andar 04547-005
Sao Paulo, SP, Brazil
Tel: 55-11-5087-3000
Fax: 55-11-5087-3030

Canada

Solutia Canada Inc.
2233 Argenta Road
P.O. Box 787
Mississauga, Ontario
L5M 2G4 Canada
Tel: 905-826-9222
Fax: 905-826-3119

China-PRC

Solutia Chemical Co. Ltd., Suzhou
9th Floor, Kings Tower
16 Shi Shan Road
Suzhou New District, PRC 215011
Tel: 86-512-825-3191
Fax: 86-512-825-0417

Colombia

Solutia Colombia Ltda.
Carrera 7 No. 71-21
Torre B, ofc.: 906
Santa Fe de Bogota, DC
Colombia
Tel: 571-317-48-20
Fax: 571-317-48-20

India

Solutia Chemicals India Private
Limited
205-207, 'Midas'
Sahar Plaza Complex
Andheri-Kurla Road
Andheri (E)
Mumbai 400 059 India
Tel: 91 22 8302862/64
Fax: 91 22 8310059

Japan

Solutia Japan Ltd.
Shinkawa Sanko Building
Second Floor
1-13-17, Shinkawa, Chuoh-ku
Tokyo 104-0033, Japan
Tel: (03) 3523 2080
Fax: (03) 3523 2070

Korea

Solutia Korea Ltd.
3rd Floor, Anglican Church Building
3-7, Jeong-dong, Joong-gu,
Seoul 100-120, Korea
Tel: 82-2-736-7112
Fax: 82-2-739-5049

Malaysia

Solutia Hang Kong Ltd.
Malaysia Branch
12th Floor (1309-B)
Kelana Parkview Tower
No. 1 Jalan SS 6/2
Kelana Jaya
47301 Petaling Jaya
Selangor, Malaysia
Tel: 60-3-704-0279
Fax: 60-3-704-4067

Mexico

Solutia Mexico, S. de R.L. de C.V.
Edificio Torre Esmeralda
Bldv. Manuel Avila Camacho
No. 40, Piso 12
Colonia Lomas de Chapultepec
11000 Mexico, D.F.
Tel: 525-202-5600
Fax: 525-202-0979

Singapore

Solutia Singapore Pte. Ltd.
101 Thomson Road
#19-01/02 United Square
Singapore 307591
Tel: 65-355-7239
Fax: 65-254-3138

Taiwan

Solutia Taiwan Inc.
2F, 124 Chung Cheng Road
Shin Lin District, Taipei
Taiwan, R.O.C.
Tel: 886-2-2835-1666
Fax: 886-2-8866-2703

Thailand

Solutia Thailand Ltd.
19th Floor, SCB Park Plaza
19 Ratchadapisek Road
Laadiao, Chatuchak
Bangkok, Thailand 10900
Tel: 66-2-937-8860
Fax: 66-2-937-8865

Venezuela

Solutia Venezuela SRL
Avenida Francisco de Miranda
Edificio Parque Cristal
Torre Oeste, Piso 13 Ofc 13-4
Los Palos Grandes
Caracas 1062, Venezuela
Tel: 582-285-50-37
Fax: 582-285-71-13

Visit our new website at
www.therminol.com.



Solutia
P.O. Box 66760
St. Louis, MO 63166-6760
Tel: (314) 674-1000

Litho in U.S.A.
® Registered Trademark of Solutia Inc.
© Solutia Inc., 1999. All rights reserved.
♻️ Printed on recycled paper



Material Safety Data Sheet

The Dow Chemical Company

Product Name: DOWTHERM* A HEAT TRANSFER FLUID

Issue Date: 08/03/2007
Print Date: 06 Aug 2007

The Dow Chemical Company encourages and expects you to read and understand the entire (M)SDS, as there is important information throughout the document. We expect you to follow the precautions identified in this document unless your use conditions would necessitate other appropriate methods or actions.

1. Product and Company Identification

Product Name
DOWTHERM* A HEAT TRANSFER FLUID

COMPANY IDENTIFICATION
The Dow Chemical Company
2030 Willard H. Dow Center
Midland, MI 48674
USA

Customer Information Number: 800-258-2436

EMERGENCY TELEPHONE NUMBER

24-Hour Emergency Contact: 989-636-4400
Local Emergency Contact: 989-636-4400

2. Hazards Identification

Emergency Overview

Color: Colorless to yellow

Physical State: Liquid

Odor: Aromatic

Hazards of product:

CAUTION! May cause skin irritation. May cause respiratory tract irritation. Keep upwind of spill. Highly toxic to fish and/or other aquatic organisms.

OSHA Hazard Communication Standard

This product is a "Hazardous Chemical" as defined by the OSHA Hazard Communication Standard, 29 CFR 1910.1200.

Potential Health Effects

Eye Contact: May cause pain disproportionate to the level of irritation to eye tissues. May cause slight temporary eye irritation. Vapor may cause eye irritation experienced as mild discomfort and redness.

Skin Contact: Repeated contact may cause skin burns. Symptoms may include pain, severe local redness, swelling, and tissue damage. Prolonged or repeated contact may cause skin irritation.

* Indicates a Trademark

Skin Absorption: Prolonged skin contact is unlikely to result in absorption of harmful amounts.

Inhalation: Excessive exposure may cause irritation to upper respiratory tract (nose and throat) and lungs. May cause headache and nausea due to odor.

Ingestion: Low toxicity if swallowed. Small amounts swallowed incidentally as a result of normal handling operations are not likely to cause injury; however, swallowing larger amounts may cause injury. In animals, effects have been reported on the following organs: Kidney. Liver.

Effects of Repeated Exposure: The data presented are for the following material: Diphenyl oxide (vapour): Observations in animals include: Respiratory effects. The data presented are for the following material: (biphenyl) In humans, effects have been reported on the following organs: Central nervous system. Liver. Peripheral nervous system. In animals, effects have been reported on the following organs: Gastrointestinal tract. Kidney. May cause nausea and vomiting. May cause abdominal discomfort or diarrhea.

Cancer Information: Contains component(s) which have caused cancer in laboratory animals. However, the component(s) is/are not genotoxic, and the relevance of cancer to humans is unknown.

Birth Defects/Developmental Effects: Contains component(s) which, in laboratory animals, have been toxic to the fetus only at doses toxic to the mother.

Reproductive Effects: In animal studies on component(s), effects on reproduction were seen only at doses that produced significant toxicity to the parent animals.

3. Composition Information

Component	CAS #	Amount
Diphenyl oxide	101-84-8	73.0 %
Biphenyl	92-52-4	27.0 %

4. First-aid measures

Eye Contact: Flush eyes thoroughly with water for several minutes. Remove contact lenses after the initial 1-2 minutes and continue flushing for several additional minutes. If effects occur, consult a physician, preferably an ophthalmologist.

Skin Contact: Wash skin with plenty of water.

Inhalation: Move person to fresh air; if effects occur, consult a physician.

Ingestion: If swallowed, seek medical attention. Do not induce vomiting unless directed to do so by medical personnel.

Notes to Physician: If burn is present, treat as any thermal burn, after decontamination. No specific antidote. Treatment of exposure should be directed at the control of symptoms and the clinical condition of the patient.

5. Fire Fighting Measures

Extinguishing Media: Water fog or fine spray. Dry chemical fire extinguishers. Carbon dioxide fire extinguishers. Foam. Do not use direct water stream. May spread fire. General purpose synthetic foams (including AFFF type) or protein foams are preferred if available. Alcohol resistant foams (ATC type) may function. Water fog, applied gently may be used as a blanket for fire extinguishment.

Fire Fighting Procedures: Keep people away. Isolate fire and deny unnecessary entry. Do not use direct water stream. May spread fire. Burning liquids may be moved by flushing with water to protect personnel and minimize property damage. Water fog, applied gently may be used as a blanket for fire extinguishment. Contain fire water run-off if possible. Fire water run-off, if not contained, may cause environmental damage. Review the "Accidental Release Measures" and the "Ecological Information" sections of this (M)SDS.

Special Protective Equipment for Firefighters: Wear positive-pressure self-contained breathing apparatus (SCBA) and protective fire fighting clothing (includes fire fighting helmet, coat, trousers, boots, and gloves). Avoid contact with this material during fire fighting operations. If contact is likely, change to full chemical resistant fire fighting clothing with self-contained breathing apparatus. If this is

not available, wear full chemical resistant clothing with self-contained breathing apparatus and fight fire from a remote location. For protective equipment in post-fire or non-fire clean-up situations, refer to the relevant sections.

Unusual Fire and Explosion Hazards: Violent steam generation or eruption may occur upon application of direct water stream to hot liquids. Liquid mist of this product can burn. Flammable concentrations of vapor can accumulate at temperatures above flash point; see Section 9. Dense smoke is produced when product burns.

Hazardous Combustion Products: During a fire, smoke may contain the original material in addition to combustion products of varying composition which may be toxic and/or irritating. Combustion products may include and are not limited to: Carbon monoxide. Carbon dioxide.

6. Accidental Release Measures

Steps to be Taken if Material is Released or Spilled: Contain spilled material if possible. Collect in suitable and properly labeled containers. See Section 13, Disposal Considerations, for additional information.

Personal Precautions: Keep upwind of spill. Ventilate area of leak or spill. Keep unnecessary and unprotected personnel from entering the area. Use appropriate safety equipment. For additional information, refer to Section 8, Exposure Controls and Personal Protection. Refer to Section 7, Handling, for additional precautionary measures.

Environmental Precautions: Prevent from entering into soil, ditches, sewers, waterways and/or groundwater. See Section 12, Ecological Information. Spills or discharge to natural waterways is likely to kill aquatic organisms.

7. Handling and Storage

Handling

General Handling: Avoid contact with skin and clothing. Avoid breathing vapor. Wash thoroughly after handling. Use with adequate ventilation. Keep container closed. Spills of these organic materials on hot fibrous insulations may lead to lowering of the autoignition temperatures possibly resulting in spontaneous combustion. See Section 8, EXPOSURE CONTROLS AND PERSONAL PROTECTION.

Storage

Store away from incompatible materials. See STABILITY AND REACTIVITY section.

8. Exposure Controls / Personal Protection

Exposure Limits

Component	List	Type	Value
Diphenyl oxide	ACGIH	TWA Vapor.	1 ppm
	ACGIH	STEL Vapor.	2 ppm
	OSHA Table Z-1	PEL Vapor.	7 mg/m3 1 ppm
Biphenyl	ACGIH	TWA	0.2 ppm
	OSHA Table Z-1	PEL	1 mg/m3 0.2 ppm

Personal Protection

Eye/Face Protection: Use safety glasses. If exposure causes eye discomfort, use a full-face respirator.

Skin Protection: When prolonged or frequently repeated contact could occur, use protective clothing chemically resistant to this material. Selection of specific items such as faceshield, boots, apron, or full-body suit will depend on the task.

Hand protection: Use gloves chemically resistant to this material when prolonged or frequently repeated contact could occur. Examples of preferred glove barrier materials include: Viton. Polyethylene. Polyvinyl chloride ("PVC" or "vinyl"). Styrene/butadiene rubber. Polyvinyl alcohol ("PVA"). Ethyl vinyl alcohol laminate ("EVAL"). Examples of acceptable glove barrier materials include: Butyl rubber. Neoprene. Chlorinated polyethylene. Natural rubber ("latex"). Nitrile/butadiene rubber ("nitrile" or "NBR"). NOTICE: The selection of a specific glove for a particular application and duration of use in a workplace should also take into account all relevant workplace factors such as, but not limited to: Other chemicals which may be handled, physical requirements (cut/puncture protection, dexterity, thermal protection), potential body reactions to glove materials, as well as the instructions/specifications provided by the glove supplier.

Respiratory Protection: Atmospheric levels should be maintained below the exposure guideline. When respiratory protection is required for certain operations, use an approved air-purifying respirator. The following should be effective types of air-purifying respirators: Organic vapor cartridge with a particulate pre-filter.

Ingestion: Use good personal hygiene. Do not consume or store food in the work area. Wash hands before smoking or eating.

Engineering Controls

Ventilation: Provide general and/or local exhaust ventilation to control airborne levels below the exposure guidelines.

9. Physical and Chemical Properties

Physical State	Liquid
Color	Colorless to yellow
Odor	Aromatic
Flash Point - Closed Cup	113 °C (235 °F) <i>Closed Cup</i>
Flammable Limits In Air	Lower: 0.8 %(V) <i>Literature</i> Upper: 7.0 %(V) <i>Literature</i>
Autoignition Temperature	599 °C (1,110 °F) <i>Literature</i>
Vapor Pressure	0.025 mmHg @ 25 °C <i>Literature</i>
Boiling Point (760 mmHg)	257 °C (495 °F) <i>Literature</i>
Vapor Density (air = 1)	>1.0 <i>Literature</i>
Specific Gravity (H2O = 1)	1.050 - 1.075 25 °C/25 °C <i>Literature</i>
Freezing Point	12.0 °C (53.6 °F) <i>Literature</i>
Melting Point	12.0 °C (53.6 °F) <i>Literature</i>
Solubility in Water (by weight)	13.8 ppm @ 60 °F <i>Literature</i>
pH	Not applicable
Kinematic Viscosity	3.51 mm ² /s @ 25 °C <i>Literature</i>

10. Stability and Reactivity

Stability/Instability

Thermally stable at typical use temperatures.

Conditions to Avoid: Exposure to elevated temperatures can cause product to decompose.

Incompatible Materials: Avoid contact with oxidizing materials.

Hazardous Polymerization

Will not occur.

Thermal Decomposition

Decomposition products depend upon temperature, air supply and the presence of other materials. Decomposition products can include trace amounts of: Benzene. Phenol.

11. Toxicological Information**Acute Toxicity****Ingestion**

LD50, Rat > 2,000 mg/kg

Skin Absorption

The dermal LD50 has not been determined.

Repeated Dose Toxicity

The data presented are for the following material: Diphenyl oxide (vapour): Observations in animals include: Respiratory effects. The data presented are for the following material: (biphenyl) In humans, effects have been reported on the following organs: Central nervous system. Liver. Peripheral nervous system. In animals, effects have been reported on the following organs: Gastrointestinal tract. Kidney. May cause nausea and vomiting. May cause abdominal discomfort or diarrhea.

Chronic Toxicity and Carcinogenicity

Contains component(s) which have caused cancer in laboratory animals. However, the component(s) is/are not genotoxic, and the relevance of cancer to humans is unknown.

Developmental Toxicity

Contains component(s) which, in laboratory animals, have been toxic to the fetus only at doses toxic to the mother. Contains component(s) which did not cause birth defects in laboratory animals.

Reproductive Toxicity

In animal studies on component(s), effects on reproduction were seen only at doses that produced significant toxicity to the parent animals.

Genetic Toxicology

In vitro genetic toxicity studies were negative. Animal genetic toxicity studies were negative.

12. Ecological Information**CHEMICAL FATE**

Data for Component: Diphenyl oxide

Movement & Partitioning

Bioconcentration potential is moderate (BCF between 100 and 3000 or Log Pow between 3 and 5). Potential for mobility in soil is low (Koc between 500 and 2000).

Henry's Law Constant (H): 2.2E-04 atm*m3/mole; 25 °C Estimated

Partition coefficient, n-octanol/water (log Pow): 4.21 Measured

Partition coefficient, soil organic carbon/water (Koc): 820 - 1,950 Estimated

Bioconcentration Factor (BCF): 196 - 470; fish; Measured

Persistence and Degradability

Biodegradation under aerobic static laboratory conditions is high (BOD20 or BOD28/ThOD > 40%). Material is expected to biodegrade only very slowly (in the environment). Fails to pass OECD/EEC tests for ready biodegradability.

Indirect Photodegradation with OH Radicals

Rate Constant	Atmospheric Half-life	Method
9.84E-12 cm3/s	1.1 d	Estimated

OECD Biodegradation Tests:

Biodegradation	Exposure Time	Method
6.3 %	28 d	OECD 301C Test

Biological oxygen demand (BOD):

BOD 5	BOD 10	BOD 20	BOD 28
72 - 76 %	80 - 91 %	82 - 99 %	

Chemical Oxygen Demand: 2.19 mg/mg

Theoretical Oxygen Demand: 2.63 mg/mg

Data for Component: **Biphenyl**

Movement & Partitioning

Bioconcentration potential is moderate (BCF between 100 and 3000 or Log Pow between 3 and 5). Potential for mobility in soil is low (Koc between 500 and 2000).

Henry's Law Constant (H): 4.08E-4 atm*m3/mole; 25 °C Measured

Partition coefficient, n-octanol/water (log Pow): 3.98 Measured

Partition coefficient, soil organic carbon/water (Koc): 500 - 630 Estimated

Bioconcentration Factor (BCF): 340 - 1,900; fish; Measured

Persistence and Degradability

Material is readily biodegradable. Passes OECD test(s) for ready biodegradability.

Indirect Photodegradation with OH Radicals

Rate Constant	Atmospheric Half-life	Method
6.77E-12 cm3/s	1.6 d	Estimated

OECD Biodegradation Tests:

Biodegradation	Exposure Time	Method
100 %	28 d	OECD 301D Test

Theoretical Oxygen Demand: 3.01 mg/mg

ECOTOXICITY

Fish Acute & Prolonged Toxicity

LC50, fathead minnow (*Pimephales promelas*), 96 h: 9.6 mg/l

Aquatic Invertebrate Acute Toxicity

LC50, water flea *Daphnia magna*, static, 48 h: 0.29 mg/l

13. Disposal Considerations

DO NOT DUMP INTO ANY SEWERS, ON THE GROUND, OR INTO ANY BODY OF WATER. All disposal practices must be in compliance with all Federal, State/Provincial and local laws and regulations. Regulations may vary in different locations. Waste characterizations and compliance with applicable laws are the responsibility solely of the waste generator. DOW HAS NO CONTROL OVER THE MANAGEMENT PRACTICES OR MANUFACTURING PROCESSES OF PARTIES HANDLING OR USING THIS MATERIAL. THE INFORMATION PRESENTED HERE PERTAINS ONLY TO THE PRODUCT AS SHIPPED IN ITS INTENDED CONDITION AS DESCRIBED IN MSDS SECTION: Composition Information. FOR UNUSED & UNCONTAMINATED PRODUCT, the preferred options include sending to a licensed, permitted: Incinerator or other thermal destruction device. As a service to its customers, Dow can provide names of information resources to help identify waste management companies and other facilities which recycle, reprocess or manage chemicals or plastics, and that manage used drums. Telephone Dow's Customer Information Group at 1-800-258-2436 or 1-989-832-1556 (U.S.), or 1-800-331-6451 (Canada) for further details.

14. Transport Information

DOT Non-Bulk

Proper Shipping Name: ENVIRONMENTALLY HAZARDOUS SUBSTANCES, LIQUID, NOS

Technical Name: BIPHENYL

Hazard Class: 9 ID Number: UN3082 Packing Group: PG III

DOT Bulk

Proper Shipping Name: ENVIRONMENTALLY HAZARDOUS SUBSTANCES, LIQUID, NOS

Technical Name: BIPHENYL

Hazard Class: 9 ID Number: UN3082 Packing Group: PG III

Product Name: DOWTHERM® A HEAT TRANSFER FLUID

Issue Date: 08/03/2007

IMDG

Proper Shipping Name: ENVIRONMENTALLY HAZARDOUS SUBSTANCES, LIQUID, NOS
Technical Name: BIPHENYL

Hazard Class: 9 **ID Number:** UN3082 **Packing Group:** PG III

EMS Number: F-A,S-F

Marine pollutant: No

ICAO/IATA

Proper Shipping Name: ENVIRONMENTALLY HAZARDOUS SUBSTANCES, LIQUID, NOS
Technical Name: BIPHENYL

Hazard Class: 9 **ID Number:** UN3082 **Packing Group:** PG III

Cargo Packing Instruction: 914

Passenger Packing Instruction: 914

Additional Information

Reportable quantity: 370 lb – BIPHENYL

This information is not intended to convey all specific regulatory or operational requirements/information relating to this product. Additional transportation system information can be obtained through an authorized sales or customer service representative. It is the responsibility of the transporting organization to follow all applicable laws, regulations and rules relating to the transportation of the material.

15. Regulatory Information

OSHA Hazard Communication Standard

This product is a "Hazardous Chemical" as defined by the OSHA Hazard Communication Standard, 29 CFR 1910.1200.

Superfund Amendments and Reauthorization Act of 1986 Title III (Emergency Planning and Community Right-to-Know Act of 1986) Sections 311 and 312

Immediate (Acute) Health Hazard	Yes
Delayed (Chronic) Health Hazard	Yes
Fire Hazard	No
Reactive Hazard	No
Sudden Release of Pressure Hazard	No

Superfund Amendments and Reauthorization Act of 1986 Title III (Emergency Planning and Community Right-to-Know Act of 1986) Section 313

This product contains the following substances which are subject to the reporting requirements of Section 313 of Title III of the Superfund Amendments and Reauthorization Act of 1986 and which are listed in 40 CFR 372.

Component	CAS #	Amount
Biphenyl	92-52-4	27.0%

Pennsylvania (Worker and Community Right-To-Know Act): Pennsylvania Hazardous Substances List and/or Pennsylvania Environmental Hazardous Substance List:

The following product components are cited in the Pennsylvania Hazardous Substance List and/or the Pennsylvania Environmental Substance List, and are present at levels which require reporting.

Component	CAS #	Amount
Diphenyl oxide	101-84-8	73.0%
Biphenyl	92-52-4	27.0%

Pennsylvania (Worker and Community Right-To-Know Act): Pennsylvania Special Hazardous Substances List:

To the best of our knowledge, this product does not contain chemicals at levels which require reporting under this statute.

Product Name: DOWTHERM® A HEAT TRANSFER FLUID

Issue Date: 08/03/2007

California Proposition 65 (Safe Drinking Water and Toxic Enforcement Act of 1986)

This product contains no listed substances known to the State of California to cause cancer, birth defects or other reproductive harm, at levels which would require a warning under the statute.

US. Toxic Substances Control Act

All components of this product are on the TSCA Inventory or are exempt from TSCA Inventory requirements under 40 CFR 720.30

CEPA - Domestic Substances List (DSL)

All substances contained in this product are listed on the Canadian Domestic Substances List (DSL) or are not required to be listed.

16. Other Information

Hazard Rating System

NFPA

Health

Fire

Reactivity

1

1

0

Recommended Uses and Restrictions

A heat transfer agent - For industrial use. Dow recommends that you use this product in a manner consistent with the listed use. If your intended use is not consistent with Dow's stated use, please contact Dow's Customer Information Group.

Revision

Identification Number: 1007176 / 0000 / Issue Date 08/03/2007 / Version: 1.1

Most recent revision(s) are noted by the bold, double bars in left-hand margin throughout this document.

Legend

N/A	Not available
W/W	Weight/Weight
OEL	Occupational Exposure Limit
STEL	Short Term Exposure Limit
TWA	Time Weighted Average
ACGIH	American Conference of Governmental Industrial Hygienists, Inc.
DOW IHG	Dow Industrial Hygiene Guideline
WEEL	Workplace Environmental Exposure Level
HAZ DES	Hazard Designation
Action Level	A value set by OSHA that is lower than the PEL which will trigger the need for activities such as exposure monitoring and medical surveillance if exceeded.

The Dow Chemical Company urges each customer or recipient of this (M)SDS to study it carefully and consult appropriate expertise, as necessary or appropriate, to become aware of and understand the data contained in this (M)SDS and any hazards associated with the product. The information herein is provided in good faith and believed to be accurate as of the effective date shown above. However, no warranty, express or implied, is given. Regulatory requirements are subject to change and may differ between various locations. It is the buyer's/user's responsibility to ensure that his activities comply with all federal, state, provincial or local laws. The information presented here pertains only to the product as shipped. Since conditions for use of the product are not under the control of the manufacturer, it is the buyer's/user's duty to determine the conditions necessary for the safe use of this product. Due to the proliferation of sources for information such as manufacturer-specific (M)SDSs, we are not and cannot be responsible for (M)SDSs obtained from any source other than ourselves. If you have obtained an (M)SDS from another source or if you are not sure that the (M)SDS you have is current, please contact us for the most current version.

ATTACHMENT C.1-8

VEHICLE USE AND GROWTH RATES (1980-2020)


POPULATION AND VEHICLE TRENDS REPORT

MOJAVE DESERT AIR BASIN

Vehicle Population

All Vehicles

By Number of Vehicles



Passenger Cars | Light-Duty Trucks 1 (<3,750 lbs) | Light-Duty Trucks 2 (3,751-5,750 lbs)
 Medium-Duty Trucks (5,751-8,500 lbs) | Light Heavy-Duty Trucks 1 (8,501-10,000 lbs)
 Medium Heavy-Duty Trucks (14,001-33,000 lbs) | Light Heavy-Duty Trucks 2 (10,001-14,000 lbs)
 Heavy Heavy-Duty Trucks (>33,000lbs) | Urban Buses | Motorcycles | Motor Homes | School Buses | Other Buses
 [New-Query]

Year	Number of Vehicles	Year	Number of Vehicles
1980	160,823	2001	560,579
1981	164,766	2002	575,301
1982	171,723	2003	618,084
1983	190,544	2004	650,784
1984	239,494	2005	703,353
1985	253,690	2006	690,924
1986	277,582	2007	679,810
1987	329,144	2008	701,710
1988	347,746	2009	725,436
1989	366,429	2010	750,014
1990	443,767	2011	771,369
1991	453,079	2012	793,346
1992	459,169	2013	815,965
1993	467,238	2014	838,566
1994	474,636	2015	861,829
1995	481,293	2016	881,065
1996	490,361	2017	900,741
1997	492,418	2018	920,874
1998	502,792	2019	941,470
1999	518,445	2020	962,539
2000	532,579		

[Download Data]

Source: EMFAC2007 ver2.3(Apr03-Default Activity) found [here](#)


POPULATION AND VEHICLE TRENDS REPORT

MOJAVE DESERT AIR BASIN

Daily Vehicle Miles Traveled

All Vehicles

By Thousands of Miles / Day



Passenger Cars | Light-Duty Trucks 1 (<3,750 lbs) | Light-Duty Trucks 2 (3,751-5,750 lbs)
 Medium-Duty Trucks (5,751-8,500 lbs) | Light Heavy-Duty Trucks 1 (8,501-10,000 lbs)
 Medium Heavy-Duty Trucks (14,001-33,000 lbs) | Light Heavy-Duty Trucks 2 (10,001-14,000 lbs)
 Heavy Heavy-Duty Trucks (>33,000lbs) | Urban Buses | Motorcycles | Motor Homes | School Buses | Other Buses
 [New-Query]


Year	Thousands of Miles / Day	Year	Thousands of Miles / Day
1980	6,745	2001	26,444
1981	6,895	2002	27,185
1982	7,070	2003	29,211
1983	7,766	2004	30,291
1984	10,341	2005	34,411
1985	11,130	2006	33,169
1986	12,323	2007	32,059
1987	14,480	2008	32,869
1988	15,516	2009	33,820
1989	16,740	2010	34,880
1990	20,896	2011	35,840
1991	21,369	2012	36,871
1992	21,670	2013	37,963
1993	21,858	2014	39,050
1994	22,192	2015	40,184
1995	22,712	2016	41,055
1996	23,028	2017	41,960
1997	23,498	2018	42,884
1998	23,888	2019	43,811
1999	24,575	2020	44,740
2000	24,999		

[Download Data]

Source: EMFAC2007 ver2.3(Apr03-Default Activity) found [here](#)

POPULATION AND VEHICLE TRENDS REPORT

MOJAVE DESERT AIR BASIN
Daily Vehicle Fuel Consumption (Gasoline and Diesel)
All Vehicles
 By Thousands of Gallons / Day



Gasoline | Diesel
 Passenger Cars | Light-Duty Trucks 1 (<3,750 lbs) | Light-Duty Trucks 2 (3,751-5,750 lbs)
 Medium-Duty Trucks (5,751-8,500 lbs) | Light Heavy-Duty Trucks 1 (8,501-10,000 lbs)
 Medium Heavy-Duty Trucks (14,001-33,000 lbs) | Light Heavy-Duty Trucks 2 (10,001-14,000 lbs)
 Heavy Heavy-Duty Trucks (>33,000lbs) | Urban Buses | Motorcycles | Motor Homes | School Buses | Other Buses
 [New-Query]


Year	Thousands of Gallons / Day	Year	Thousands of Gallons / Day
1980	700	2001	1,937
1981	723	2002	1,958
1982	722	2003	2,142
1983	783	2004	2,153
1984	1,015	2005	2,623
1985	1,066	2006	2,485
1986	1,143	2007	2,351
1987	1,287	2008	2,392
1988	1,363	2009	2,434
1989	1,464	2010	2,499
1990	1,699	2011	2,583
1991	1,717	2012	2,660
1992	1,738	2013	2,745
1993	1,707	2014	2,841
1994	1,716	2015	2,933
1995	1,748	2016	3,022
1996	1,749	2017	3,095
1997	1,792	2018	3,167
1998	1,807	2019	3,238
1999	1,850	2020	3,306
2000	1,862		

[Download Data]

Source: pending

POPULATION AND VEHICLE TRENDS REPORT

MOJAVE DESERT AIR BASIN
Human Population
By Number of People



Source: Developed using reports from the California Department of Finance. [See references](#)

Modeling Support Data

Tables presented in this Appendix are as follows:

C.2-1	Daggett Wind Rose Frequency (Count) Distribution
C.2-2	Daggett Wind Rose Frequency (Normalized) Distribution
C.2-3	Barstow Regional Climate Summary
C.2-4	Mohave Desert Air Basin Historical Air Quality Data
C.2-5	Building Dimensions and Height Data
C.2-6	Operational Impacts Summary

In addition, this appendix contains the following Figures:

C.2-1a,b,c	Proposed Facility Plot Plan
C.2-2	Expanded View of Process Area
C.2-3	BPIP Model Output
C.2-4a, b	Receptor Grids
C.2-5	Mohave Desert Air District Monitoring Stations

Modeling input/output files are included in the enclosed CD's.

Station ID: 23161
 Year: 2001 2002 2003 2004
 Date Range: Jan 1 - Dec 31
 Time Range: 00:00 - 23:00

Run ID: DAGGETT/FAA AIRPORT

Table C.2-1 (5 pages)

Annual - All Months

Frequency Distribution (Count)

	Wind Direction (Blowing From) / Wind Speed (m/s)						
	0.5 - 2.1	2.1 - 3.6	3.6 - 5.7	5.7 - 8.8	8.8 - 11.1	>= 11.1	Total
348.75-11.25	172	178	58	26	5	2	441
11.25-33.75	146	225	114	61	6	2	554
33.75-56.25	196	375	217	41	6	1	836
56.25-78.75	250	539	374	77	4	0	1244
78.75-101.25	252	506	297	117	26	4	1202
101.25-123.75	224	249	106	56	9	0	644
123.75-146.25	175	114	39	26	7	0	361
146.25-168.75	174	107	24	29	1	1	336
168.75-191.25	175	97	25	15	2	2	316
191.25-213.75	127	89	45	64	20	16	361
213.75-236.25	182	185	199	714	408	266	1954
236.25-258.75	384	684	1472	1616	975	710	5841
258.75-281.25	567	1756	3971	1995	548	440	9277
281.25-303.75	469	1389	2363	1229	85	34	5569
303.75-326.25	279	505	669	247	11	1	1712
326.25-348.75	151	200	127	22	3	0	503
Total	3923	7198	10100	6335	2116	1479	33719

Frequency of Calm Winds: 2568
 Average Wind Speed: 4.87 m/s

Station ID: 23161
 Year: 2001 2002 2003 2004
 Date Range: Sep 1 - Nov 30
 Time Range: 00:00 - 23:00

Run ID: DAGGETT/FAA AIRPORT

Autumn Months (Sep-Nov)

Frequency Distribution (Count)

	Wind Direction (Blowing From) / Wind Speed (m/s)						
	0.5 - 2.1	2.1 - 3.6	3.6 - 5.7	5.7 - 8.8	8.8 - 11.1	>= 11.1	Total
348.75-11.25	50	29	13	11	4	1	108
11.25-33.75	48	51	29	19	2	0	149
33.75-56.25	64	115	50	8	1	0	238
56.25-78.75	76	184	122	15	0	0	397
78.75-101.25	78	176	82	25	5	0	366
101.25-123.75	62	74	28	11	1	0	176
123.75-146.25	51	33	7	5	0	0	96
146.25-168.75	58	43	14	7	1	0	123
168.75-191.25	56	39	7	6	0	0	108
191.25-213.75	44	21	10	12	10	5	102
213.75-236.25	62	60	60	139	70	39	430
236.25-258.75	135	195	454	300	110	88	1282
258.75-281.25	202	519	1113	364	81	63	2342
281.25-303.75	129	423	561	188	17	3	1321
303.75-326.25	76	139	130	30	1	0	376
326.25-348.75	44	33	19	6	0	0	102
Total	1235	2134	2699	1146	303	199	8460

Frequency of Calm Winds: 744
 Average Wind Speed: 4.20 m/s

Station ID: 23161
 Year: 2001 2002 2003 2004
 Date Range: Mar 1 - May 31
 Time Range: 00:00 - 23:00

Run ID: DAGGETT/FAA AIRPORT

Spring Months (Mar-May)

Frequency Distribution (Count)

	Wind Direction (Blowing From) / Wind Speed (m/s)						
	0.5 - 2.1	2.1 - 3.6	3.6 - 5.7	5.7 - 8.8	8.8 - 11.1	>= 11.1	Total
348.75-11.25	45	56	25	10	1	0	137
11.25-33.75	25	54	27	24	2	2	134
33.75-56.25	41	94	63	14	1	1	214
56.25-78.75	34	115	84	14	0	0	247
78.75-101.25	34	84	58	16	2	0	194
101.25-123.75	38	41	20	6	4	0	109
123.75-146.25	20	14	5	6	1	0	46
146.25-168.75	22	14	3	4	0	0	43
168.75-191.25	27	14	5	1	0	1	48
191.25-213.75	24	21	12	15	4	6	82
213.75-236.25	25	40	50	224	176	159	674
236.25-258.75	36	98	323	538	426	388	1809
258.75-281.25	61	298	925	662	265	230	2441
281.25-303.75	78	253	596	420	42	21	1410
303.75-326.25	53	140	176	105	5	0	479
326.25-348.75	28	57	32	9	1	0	127
Total	591	1393	2404	2068	930	808	8523

Frequency of Calm Winds: 329
 Average Wind Speed: 6.10 m/s

Station ID: 23161
 Year: 2001 2002 2003 2004
 Date Range: Jun 1 - Aug 31
 Time Range: 00:00 - 23:00

Run ID: DAGGETT/FAA AIRPORT

Summer Months (Jun-Aug)

Frequency Distribution (Count)

	Wind Direction (Blowing From) / Wind Speed (m/s)						
	0.5 - 2.1	2.1 - 3.6	3.6 - 5.7	5.7 - 8.8	8.8 - 11.1	>= 11.1	Total
348.75-11.25	36	77	12	1	0	0	126
11.25-33.75	29	76	30	0	0	0	135
33.75-56.25	25	97	59	9	0	0	190
56.25-78.75	28	83	75	15	0	0	201
78.75-101.25	15	79	74	25	12	2	207
101.25-123.75	14	39	28	24	2	0	107
123.75-146.25	17	24	23	14	5	0	83
146.25-168.75	10	9	5	17	0	1	42
168.75-191.25	7	5	9	7	2	1	31
191.25-213.75	11	11	15	25	3	4	69
213.75-236.25	13	28	62	296	141	51	591
236.25-258.75	19	130	432	651	320	110	1662
258.75-281.25	45	282	1141	701	133	64	2366
281.25-303.75	50	238	776	498	14	6	1582
303.75-326.25	36	117	271	97	2	1	524
326.25-348.75	33	78	62	4	2	0	179
Total	388	1373	3074	2384	636	240	8321

Frequency of Calm Winds: 226
 Average Wind Speed: 5.60 m/s

Station ID: 23161

Run ID: DAGGETT/FAA AIRPORT

Year: 2001 2002 2003 2004

Date Range: Check Date Range Report

Time Range: 00:00 - 23:00

Winter Months (Dec-Feb)

Frequency Distribution (Count)

Wind Direction (Blowing From) / Wind Speed (m/s)							
	0.5 - 2.1	2.1 - 3.6	3.6 - 5.7	5.7 - 8.8	8.8 - 11.1	>= 11.1	Total
348.75-11.25	41	16	8	4	0	1	70
11.25-33.75	44	44	28	18	2	0	136
33.75-56.25	66	69	45	10	4	0	194
56.25-78.75	112	157	93	33	4	0	399
78.75-101.25	125	167	83	51	7	2	435
101.25-123.75	110	95	30	15	2	0	252
123.75-146.25	87	43	4	1	1	0	136
146.25-168.75	84	41	2	1	0	0	128
168.75-191.25	85	39	4	1	0	0	129
191.25-213.75	47	36	8	12	3	1	107
213.75-236.25	82	57	27	55	21	17	259
236.25-258.75	193	261	260	127	119	124	1084
258.75-281.25	259	654	788	268	69	83	2121
281.25-303.75	212	475	423	122	12	4	1248
303.75-326.25	113	108	91	15	3	0	330
326.25-348.75	46	32	14	3	0	0	95
Total	1706	2294	1908	736	247	232	8391

Frequency of Calm Winds: 1268

Average Wind Speed: 3.56 m/s

Station ID: 23161
 Year: 2001 2002 2003 2004
 Date Range: Jan 1 - Dec 31
 Time Range: 00:00 - 23:00

Run ID: DAGGETT/FAA AIRPORT

Table C.2-2 (5 pages)

Annual - All Months

Frequency Distribution
 (Normalized)

Wind Direction (Blowing From) / Wind Speed (m/s)							
	0.5 - 2.1	2.1 - 3.6	3.6 - 5.7	5.7 - 8.8	8.8 - 11.1	>= 11.1	Total
348.75-11.25	0.005101	0.005279	0.001720	0.000771	0.000148	0.000059	0.013079
11.25-33.75	0.004330	0.006673	0.003381	0.001809	0.000178	0.000059	0.016430
33.75-56.25	0.005813	0.011121	0.006436	0.001216	0.000178	0.000030	0.024793
56.25-78.75	0.007414	0.015985	0.011092	0.002284	0.000119	0.000000	0.036893
78.75-101.25	0.007474	0.015006	0.008808	0.003470	0.000771	0.000119	0.035648
101.25-123.75	0.006643	0.007385	0.003144	0.001661	0.000267	0.000000	0.019099
123.75-146.25	0.005190	0.003381	0.001157	0.000771	0.000208	0.000000	0.010706
146.25-168.75	0.005160	0.003173	0.000712	0.000860	0.000030	0.000030	0.009965
168.75-191.25	0.005190	0.002877	0.000741	0.000445	0.000059	0.000059	0.009372
191.25-213.75	0.003766	0.002639	0.001335	0.001898	0.000593	0.000475	0.010706
213.75-236.25	0.005398	0.005487	0.005902	0.021175	0.012100	0.007889	0.057950
236.25-258.75	0.011388	0.020285	0.043655	0.047926	0.028915	0.021056	0.173226
258.75-281.25	0.016815	0.052077	0.117767	0.059165	0.016252	0.013049	0.275127
281.25-303.75	0.013909	0.041193	0.070079	0.036448	0.002521	0.001008	0.165159
303.75-326.25	0.008274	0.014977	0.019840	0.007325	0.000326	0.000030	0.050773
326.25-348.75	0.004478	0.005931	0.003766	0.000652	0.000089	0.000000	0.014917
Total	0.116344	0.213470	0.299534	0.187876	0.062754	0.043863	0.923841

Frequency of Calm Winds: 7.62%
 Average Wind Speed: 4.87 m/s

Station ID: 23161
 Year: 2001 2002 2003 2004
 Date Range: Sep 1 - Nov 30
 Time Range: 00:00 - 23:00

Run ID: DAGGETT/FAA AIRPORT

Autumn Months (Sep-Nov)

Frequency Distribution (Normalized)

Wind Direction (Blowing From) / Wind Speed (m/s)							
	0.5 - 2.1	2.1 - 3.6	3.6 - 5.7	5.7 - 8.8	8.8 - 11.1	>= 11.1	Total
348.75-11.25	0.005910	0.003428	0.001537	0.001300	0.000473	0.000118	0.012766
11.25-33.75	0.005674	0.006028	0.003428	0.002246	0.000236	0.000000	0.017612
33.75-56.25	0.007565	0.013593	0.005910	0.000946	0.000118	0.000000	0.028132
56.25-78.75	0.008983	0.021749	0.014421	0.001773	0.000000	0.000000	0.046927
78.75-101.25	0.009220	0.020804	0.009693	0.002955	0.000591	0.000000	0.043262
101.25-123.75	0.007329	0.008747	0.003310	0.001300	0.000118	0.000000	0.020804
123.75-146.25	0.006028	0.003901	0.000827	0.000591	0.000000	0.000000	0.011348
146.25-168.75	0.006856	0.005083	0.001655	0.000827	0.000118	0.000000	0.014539
168.75-191.25	0.006619	0.004610	0.000827	0.000709	0.000000	0.000000	0.012766
191.25-213.75	0.005201	0.002482	0.001182	0.001418	0.001182	0.000591	0.012057
213.75-236.25	0.007329	0.007092	0.007092	0.016430	0.008274	0.004610	0.050827
236.25-258.75	0.015957	0.023050	0.053664	0.035461	0.013002	0.010402	0.151537
258.75-281.25	0.023877	0.061348	0.131560	0.043026	0.009574	0.007447	0.276832
281.25-303.75	0.015248	0.050000	0.066312	0.022222	0.002009	0.000355	0.156147
303.75-326.25	0.008983	0.016430	0.015366	0.003546	0.000118	0.000000	0.044444
326.25-348.75	0.005201	0.003901	0.002246	0.000709	0.000000	0.000000	0.012057
Total	0.145981	0.252246	0.319031	0.135461	0.035816	0.023522	0.912057

Frequency of Calm Winds: 8.79%
 Average Wind Speed: 4.20 m/s

Station ID: 23161
 Year: 2001 2002 2003 2004
 Date Range: Mar 1 - May 31
 Time Range: 00:00 - 23:00

Run ID: DAGGETT/FAA AIRPORT

Spring Months (Mar-May)

Frequency Distribution (Normalized)

Wind Direction (Blowing From) / Wind Speed (m/s)

	0.5 - 2.1	2.1 - 3.6	3.6 - 5.7	5.7 - 8.8	8.8 - 11.1	>= 11.1	Total
348.75-11.25	0.005280	0.006570	0.002933	0.001173	0.000117	0.000000	0.016074
11.25-33.75	0.002933	0.006336	0.003168	0.002816	0.000235	0.000235	0.015722
33.75-56.25	0.004811	0.011029	0.007392	0.001643	0.000117	0.000117	0.025109
56.25-78.75	0.003989	0.013493	0.009856	0.001643	0.000000	0.000000	0.028980
78.75-101.25	0.003989	0.009856	0.006805	0.001877	0.000235	0.000000	0.022762
101.25-123.75	0.004459	0.004811	0.002347	0.000704	0.000469	0.000000	0.012789
123.75-146.25	0.002347	0.001643	0.000587	0.000704	0.000117	0.000000	0.005397
146.25-168.75	0.002581	0.001643	0.000352	0.000469	0.000000	0.000000	0.005045
168.75-191.25	0.003168	0.001643	0.000587	0.000117	0.000000	0.000117	0.005632
191.25-213.75	0.002816	0.002464	0.001408	0.001760	0.000469	0.000704	0.009621
213.75-236.25	0.002933	0.004693	0.005866	0.026282	0.020650	0.018655	0.079080
236.25-258.75	0.004224	0.011498	0.037897	0.063123	0.049982	0.045524	0.212249
258.75-281.25	0.007157	0.034964	0.108530	0.077672	0.031092	0.026986	0.286402
281.25-303.75	0.009152	0.029684	0.069928	0.049278	0.004928	0.002464	0.165435
303.75-326.25	0.006218	0.016426	0.020650	0.012320	0.000587	0.000000	0.056201
326.25-348.75	0.003285	0.006688	0.003755	0.001056	0.000117	0.000000	0.014901
Total	0.069342	0.163440	0.282060	0.242638	0.109117	0.094802	0.961399

Frequency of Calm Winds: 3.86%
 Average Wind Speed: 6.10 m/s

Station ID: 23161
 Year: 2001 2002 2003 2004
 Date Range: Jun 1 - Aug 31
 Time Range: 00:00 - 23:00

Run ID: DAGGETT/FAA AIRPORT

Summer Months (Jun-Aug)

Frequency Distribution (Normalized)

Wind Direction (Blowing From) / Wind Speed (m/s)							
	0.5 - 2.1	2.1 - 3.6	3.6 - 5.7	5.7 - 8.8	8.8 - 11.1	>= 11.1	Total
348.75-11.25	0.004326	0.009254	0.001442	0.000120	0.000000	0.000000	0.015142
11.25-33.75	0.003485	0.009134	0.003605	0.000000	0.000000	0.000000	0.016224
33.75-56.25	0.003004	0.011657	0.007090	0.001082	0.000000	0.000000	0.022834
56.25-78.75	0.003365	0.009975	0.009013	0.001803	0.000000	0.000000	0.024156
78.75-101.25	0.001803	0.009494	0.008893	0.003004	0.001442	0.000240	0.024877
101.25-123.75	0.001682	0.004687	0.003365	0.002884	0.000240	0.000000	0.012859
123.75-146.25	0.002043	0.002884	0.002764	0.001682	0.000601	0.000000	0.009975
146.25-168.75	0.001202	0.001082	0.000601	0.002043	0.000000	0.000120	0.005047
168.75-191.25	0.000841	0.000601	0.001082	0.000841	0.000240	0.000120	0.003726
191.25-213.75	0.001322	0.001322	0.001803	0.003004	0.000361	0.000481	0.008292
213.75-236.25	0.001562	0.003365	0.007451	0.035573	0.016945	0.006129	0.071025
236.25-258.75	0.002283	0.015623	0.051917	0.078236	0.038457	0.013220	0.199736
258.75-281.25	0.005408	0.033890	0.137123	0.084245	0.015984	0.007691	0.284341
281.25-303.75	0.006009	0.028602	0.093258	0.059849	0.001682	0.000721	0.190121
303.75-326.25	0.004326	0.014061	0.032568	0.011657	0.000240	0.000120	0.062973
326.25-348.75	0.003966	0.009374	0.007451	0.000481	0.000240	0.000000	0.021512
Total	0.046629	0.165004	0.369427	0.286504	0.076433	0.028843	0.972840

Frequency of Calm Winds: 2.72%
 Average Wind Speed: 5.60 m/s

Station ID: 23161
 Year: 2001 2002 2003 2004
 Date Range: Check Date Range Report
 Time Range: 00:00 - 23:00

Run ID: DAGGETT/FAA AIRPORT

Winter Months (Dec-Feb)

Frequency Distribution (Normalized)

	Wind Direction (Blowing From) / Wind Speed (m/s)						
	0.5 - 2.1	2.1 - 3.6	3.6 - 5.7	5.7 - 8.8	8.8 - 11.1	>= 11.1	Total
348.75-11.25	0.004886	0.001907	0.000953	0.000477	0.000000	0.000119	0.008342
11.25-33.75	0.005244	0.005244	0.003337	0.002145	0.000238	0.000000	0.016208
33.75-56.25	0.007866	0.008223	0.005363	0.001192	0.000477	0.000000	0.023120
56.25-78.75	0.013348	0.018711	0.011083	0.003933	0.000477	0.000000	0.047551
78.75-101.25	0.014897	0.019902	0.009892	0.006078	0.000834	0.000238	0.051841
101.25-123.75	0.013109	0.011322	0.003575	0.001788	0.000238	0.000000	0.030032
123.75-146.25	0.010368	0.005125	0.000477	0.000119	0.000119	0.000000	0.016208
146.25-168.75	0.010011	0.004886	0.000238	0.000119	0.000000	0.000000	0.015254
168.75-191.25	0.010130	0.004648	0.000477	0.000119	0.000000	0.000000	0.015374
191.25-213.75	0.005601	0.004290	0.000953	0.001430	0.000358	0.000119	0.012752
213.75-236.25	0.009772	0.006793	0.003218	0.006555	0.002503	0.002026	0.030866
236.25-258.75	0.023001	0.031105	0.030986	0.015135	0.014182	0.014778	0.129186
258.75-281.25	0.030866	0.077941	0.093910	0.031939	0.008223	0.009892	0.252771
281.25-303.75	0.025265	0.056608	0.050411	0.014539	0.001430	0.000477	0.148731
303.75-326.25	0.013467	0.012871	0.010845	0.001788	0.000358	0.000000	0.039328
326.25-348.75	0.005482	0.003814	0.001668	0.000358	0.000000	0.000000	0.011322
Total	0.203313	0.273388	0.227386	0.087713	0.029436	0.027649	0.848886

Frequency of Calm Winds: 15.11%
 Average Wind Speed: 3.56 m/s

BARSTOW, CALIFORNIA

Table C.2-3 (3 Pages)

NCDC 1961-1990 Monthly Normals

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Annual
Mean Max. Temperature (F)	57.0	62.2	69.9	78.6	85.5	92.1	92.8	91.1	85.0	77.4	66.1	58.7	76.4
Highest Mean Max. Temperature (F)	64.7	71.3	79.1	83.8	92.5	100.4	97.4	95.8	92.1	84.4	74.7	65.8	78.3
Year Highest Occurred	1986	1976	1974	1972	1989	1990	1980	1964	1977	1979	1966	1970	1989
Lowest Mean Max. Temperature (F)	49.0	56.1	57.7	72.2	81.2	87.4	86.6	84.4	77.8	69.9	57.9	51.7	73.9
Year Lowest Occurred	1979	1973	1969	1983	1976	1979	1976	1971	1974	1969	1961	1967	1968
Mean Temperature (F)	42.5	47.0	54.1	63.0	70.5	77.7	79.8	78.2	72.1	63.0	52.0	44.3	62.0
Highest Mean Temperature (F)	48.1	54.6	61.6	67.9	75.3	84.8	83.7	81.8	77.3	66.6	58.0	49.7	63.4
Year Highest Occurred	1965	1976	1974	1967	1989	1990	1966	1983	1977	1979	1965	1970	1986
Lowest Mean Temperature (F)	36.2	39.7	44.7	57.0	66.6	73.7	74.8	73.8	66.0	56.9	45.1	37.6	60.0
Year Lowest Occurred	1963	1964	1969	1983	1976	1979	1976	1971	1974	1976	1976	1983	1988
Mean Min. Temperature (F)	28.0	31.9	38.4	47.3	55.4	63.2	66.6	65.3	59.1	48.7	37.8	29.9	47.6
Highest Mean Min. Temperature (F)	34.0	37.9	44.1	53.7	59.3	69.2	70.8	68.6	62.6	53.7	43.5	35.5	49.8
Year Highest Occurred	1981	1976	1967	1967	1984	1990	1969	1982	1983	1983	1965	1965	1986
Lowest Mean Min. Temperature (F)	19.0	21.9	30.9	41.5	50.5	60.0	62.5	61.1	54.2	41.7	30.8	22.8	45.6
Year Lowest Occurred	1963	1964	1965	1987	1987	1979	1961	1975	1974	1976	1976	1983	1988
Mean Precipitation (in.)	0.37	0.57	0.56	0.73	2.00	1.91	2.51	2.71	2.60	1.43	0.77	0.62	16.78
Highest Precipitation (in.)	1.73	2.21	2.11	2.86	6.01	5.09	9.41	9.06	8.46	8.15	4.33	5.08	27.34
Year Highest Occurred	1983	1973	1968	1981	1987	1986	1988	1984	1974	1985	1978	1986	1974
Lowest Precipitation (in.)	0.00	0.02	0.00	0.00	0.07	0.00	0.22	0.37	0.11	0.00	0.00	0.00	7.45
Year Lowest Occurred	1970	1984	1984	1989	1967	1990	1980	1964	1968	1989	1989	1976	1967
Heating Degree Days (F)	698.	504.	354.	121.	17.	0.	0.	0.	9.	111.	395.	642.	2851.
Cooling Degree Days (F)	0.	0.	16.	61.	188.	381.	459.	409.	222.	49.	5.	0.	1790.

Western Regional Climate Center, wrcc@dri.edu

BARSTOW, CALIFORNIA (040519)

Period of Record Monthly Climate Summary

Period of Record : 1/ 1/1903 to 3/31/1980

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Annual
Average Max. Temperature (F)	59.8	64.8	70.0	77.6	86.0	95.8	102.4	100.4	93.8	82.4	69.5	60.7	80.3
Average Min. Temperature (F)	31.5	35.4	39.7	45.5	52.4	60.3	66.6	64.7	57.9	47.6	37.1	31.3	47.5
Average Total Precipitation (in.)	0.72	0.59	0.61	0.21	0.08	0.12	0.27	0.31	0.26	0.27	0.37	0.51	4.33
Average Total Snow/Fall (in.)	0.7	0.1	0.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.4	1.3
Average Snow Depth (in.)	0	0	0	0	0	0	0	0	0	0	0	0	0

Percent of possible observations for period of record.

Max. Temp.: 71.9% Min. Temp.: 71.8% Precipitation: 72.2% Snowfall: 71.4% Snow Depth: 71.4%

Check [Station Metadata](#) or [Metadata graphics](#) for more detail about data completeness.

Western Regional Climate Center, wrcc@dri.edu

BARSTOW FIRE STATION, CALIFORNIA

Period of Record General Climate Summary - Temperature

Station:(040521) BARSTOW FIRE STATION														
From Year=1980 To Year=2008														
	Monthly Averages			Daily Extremes				Monthly Extremes				Max. Temp.		T
	Max.	Min.	Mean	High	Date	Low	Date	Highest Mean	Year	Lowest Mean	Year	>= 90 F	<= 32 F	
	F	F	F	F	dd/yyyy or yyyymmdd	F	dd/yyyy or yyyymmdd	F	-	F	-	# Days	# Days	
January	60.6	34.4	47.5	78	15/1996	12	14/2007	53.2	1996	44.1	2007	0.0	0.0	11
February	64.7	38.0	51.3	87	26/1986	18	01/1985	60.5	1995	47.1	2001	0.0	0.0	5
March	70.9	42.7	56.9	92	20/1997	26	05/1985	62.4	2004	50.8	2006	0.3	0.0	1
April	78.4	48.4	63.4	98	30/1981	30	02/1999	69.8	1989	55.5	1983	3.4	0.0	0
May	86.6	55.1	70.9	107	28/2003	32	10/1980	77.2	1997	62.7	1991	13.1	0.0	0
June	96.6	63.1	79.9	112	22/1995	43	01/1988	84.4	2006	75.0	1982	25.6	0.0	0
July	102.0	69.0	85.5	115	28/1995	48	06/1986	90.2	2006	78.9	1986	30.5	0.0	0
August	100.8	67.8	84.3	112	08/1997	51	25/1987	88.1	1998	80.2	1989	30.1	0.0	0
September	93.7	61.2	77.4	109	03/1995	40	30/1982	81.5	2003	70.2	1986	23.1	0.0	0
October	82.2	51.1	66.7	101	01/1980	33	30/1981	73.3	1988	61.0	1981	6.2	0.0	0
November	68.7	40.9	54.8	89	04/1989	20	20/1994	64.0	1995	48.0	1994	0.0	0.0	4
December	59.2	33.4	46.3	76	14/1988	8	22/1990	51.9	1980	41.2	1990	0.0	0.0	14
Annual	80.4	50.4	65.4	115	19950728	8	19901222	67.9	1996	62.8	1982	132.3	0.0	38
Winter	61.5	35.3	48.4	87	19860226	8	19901222	53.3	1996	44.9	1985	0.0	0.0	32
Spring	78.6	48.7	63.7	107	20030528	26	19850305	67.8	1997	58.0	1991	16.8	0.0	2
Summer	99.8	66.7	83.2	115	19950728	43	19880601	86.1	2007	79.1	1983	86.2	0.0	0
Fall	81.5	51.1	66.3	109	19950903	20	19941120	72.1	1995	61.9	1985	29.3	0.0	4

Table updated on Apr 28, 2009

For monthly and annual means, thresholds, and sums:

Months with 5 or more missing days are not considered

Years with 1 or more missing months are not considered

Seasons are climatological not calendar seasons

Winter = Dec., Jan., and Feb. Spring = Mar., Apr., and May

Summer = Jun., Jul., and Aug. Fall = Sep., Oct., and Nov.

Table C.2-4 (3 Pages)

MOJAVE DESERT AQMD

EXCEEDANCES OF STANDARDS AND MAXIMUM CONCENTRATIONS

2006

STATION	OZONE					CARBON MONOXIDE					NITROGEN DIOXIDE			SULFUR DIOXIDE			
	days over state std	days over federal 1hr/8hr	max 8hr ppm	max 1hr ppm	avg 1hr ppm	days over state 1hr/8hr	days over federal 1hr/8hr	max 8hr ppm	max 1hr ppm	avg 1hr ppm	days over state std	max 1hr ppm	avg 1hr ppm	days over state 24hr/1h	max 24hr ppm	max 1hr ppm	avg 1hr ppm
29P ADOBE	na	na/na	inc	inc	inc	na/na	na/na	na	na	na	na	na	na	na/na	na	na	na
BARSTOW	4	0 / 6	0.094	0.112	0.031	0/0	0/0	1.1	3.5	0.2	0	0.082	0.022	na/na	na	na	na
HESPERIA	22	2 / 18	0.124	0.148	0.038	na/na	na/na	na	na	na	na	na	na	na/na	na	na	na
PHELAN	25	2 / 19	0.111	0.137	0.045	na/na	na/na	na	na	na	na	na	na	na/na	na	na	na
TRONA	0	0 / 0	0.084	0.091	0.038	NM	NM	NM	NM	NM	0	0.050	0.005	0/0	0.004	0.033	0.001
VICTORVILLE	9	1 / 6	0.105	0.136	0.032	0/0	0/0	1.5	2.2	0.3	0	0.079	0.020	0/0	0.005	0.018	0.001
LANCASTER AVAQMD	22	2 / 16	0.105	0.132	0.036	0/0	0/0	1.6	3.2	0.2	0	0.066	0.015	na/na	na	na	na
Apple Valley	na	na/na	na	na	na	na/na	na/na	na	na	na	na	na	na	na/na	na	na	na
29P MARINES	4	0 / 0	0.084	0.100	0.041	0/0	0/0	inc	inc	inc	inc	inc	inc	0/0	inc	inc	inc
MCLB	na	na/na	na	na	na	na/na	na/na	na	na	na	inc	inc	inc	na/na	na	na	na
MDAQMD Totals	36	3 / 30	0.124	0.148	0.037	0/0	0/0	1.5	3.5	0.3	0	0.082	0.015	0	0.005	0.033	0.001

STATION	WIND SPEED (MPH)					TEOM (PM10) (ug/m3)				TEMP (deg F)			HUMIDITY (%)			SOLAR RAD
	PEAK SPEED		AVERAGE SPEED			max 1hr pm10 avg	max daily pm10 avg	days avg over 50ug/m3	monthly avg pm10	max 1hr tmp	min 1hr tmp	monthly avg tmp	max 1hr RH %	min 1hr RH %	monthly avg RH %	Avg daily solar Radiation
	days w/1hr >40mph	max peak mph	days 24hr avg >30mph	max 1hr avg mph	avg hourly mph											
29P ADOBE	na	na	na	na	na	NM	NM	NM	NM	na	na	na	na	na	na	NM
BARSTOW	12	47	0	28	7.2	NM	NM	NM	NM	112	21	65	94	1	32	NM
HESPERIA	6	48	0	29	7.1	NM	NM	NM	NM	101	28	62	NM	NM	NM	NM
PHELAN	6	50	1	34	7.4	NM	NM	NM	NM	97	28	59	NM	NM	NM	NM
TRONA	20	52	6	35	5.5	882	184	11	23	112	24	68	NM	NM	NM	NM
VICTORVILLE	8	65	2	36	7.2	940	168	34	32	103	24	62	NM	NM	NM	0.328
LANCASTER AVAQMD	1	44	0	23	4.8	198	66	0	24	105	24	62	100	9	40	NM
Apple Valley	na	na	na	na	na	na	na	na	na	na	na	na	na	na	na	NM
29P MARINES	4	47	0	28	6.1	909	208	24	28	114	27	70	96	3	28	NM
MCLB	na	na	na	na	na	na	na	na	na	na	na	na	na	na	na	NM
LUCERNE	na	na	na	na	na	NM	NM	NM	NM	na	na	na	NM	NM	NM	NM
MDAQMD Totals	30	65	8	36	6.9	940	184	41	27	112	21	63	94	1	32	0.328

NM: Never Monitored

na: not active

Note: Included in MDAQMD totals are Barstow, Hesperia, Phelan, 29Palms, Trona, and Victorville.

06/14

2007

Air Quality Management District

EXCEEDANCES OF STANDARDS AND MAXIMUM CONCENTRATIONS

2007

STATION	OZONE					CARBON MONOXIDE					NITROGEN DIOXIDE			SULFUR DIOXIDE			
	days	days	max	max	avg	days	days	max	max	avg	days	max	avg	days	max	max	avg
	over	over	8hr	1hr	1hr	over	over	8hr	1hr	1hr	over	1hr	1hr	over	24hr	1hr	1hr
	state	federal	ppm	ppm	ppm	state	federal	ppm	ppm	ppm	state	ppm	ppm	state	ppm	ppm	ppm
	std	1hr/8hr				1hr/8hr	1hr/8hr				std			24hr/1h			
BARSTOW	2	0 / 3	0.088	0.099	0.032	0/0	0/0	0.7	1.4	0.126	0	0.073	0.020	na/na	na	na	na
HESPERIA	24	2 / 21	0.109	0.132	0.040	na/na	na/na	na	na	na	na	na	na	na/na	na	na	na
PHELAN	18	0 / 8	0.095	0.119	0.046	na/na	na/na	na	na	na	na	na	na	na/na	na	na	na
TRONA	0	0 / 0	0.084	0.094	0.040	NM	NM	NM	NM	NM	0	0.055	0.004	0/0	0.005	0.014	0.001
VICTORVILLE	7	0 / 6	0.090	0.107	0.033	0/0	0/0	1.6	2.1	0.237	0	0.071	0.018	0/0	0.005	0.009	0.001
LANCASTER AVAQMD	16	0 / 14	0.101	0.118	0.038	0/0	0/0	1.2	2.5	0.202	0	0.064	0.014	na/na	na	na	na
29P MARINES	0	0 / 0	0.083	0.094	0.042	0/0	0/0	inc	inc	inc	inc	inc	inc	0/0	inc	inc	inc
MDAQMD Totals	29	2 / 26	0.109	0.132	0.038	0/0	0/0	1.6	2.1	0.181	0	0.073	0.014	0	0.005	0.014	0.001

STATION	WIND SPEED (MPH)					TEOM (PM10) (ug/m3)				TEMP (deg F)			HUMIDITY (%)			R RAD
	PEAK SPEED		AVERAGE SPEED			max	max	days	monthly	max	min	monthly	max	min	monthly	Avg Daily Solar Radiation Langley's
	days	max	days	max	avg	1hr	daily	avg	avg	1hr	1hr	avg	1hr	1hr	avg	
	w/1hr	peak	24hr avg	1hr avg	hourly	pm10	pm10	over	pm10	tmp	tmp	tmp	RH	RH	RH	
	>40mph	mph	>30mph	mph	mph	ug/m3	ug/m3	50ug/m3	ug/m3	Deg F	Deg F	Deg F	%	%	%	
BARSTOW	13	52	0	28	7.4	NM	NM	NM	NM	111	12	66	97	0	28	NM
HESPERIA	7	50	0	30	7.6	NM	NM	NM	NM	107	18	62	NM	NM	NM	NM
PHELAN	4	45	0	29	7.4	NM	NM	NM	NM	99	14	60	NM	NM	NM	NM
TRONA	7	46	5	35	6.5	865	133	11	19	114	8	69	NM	NM	NM	NM
VICTORVILLE	15	52	2	32	7.2	950	239	35	35	107	16	63	NM	NM	NM	0.337
LANCASTER AVAQMD	2	42	0	26	4.9	267	86	8	24	109	15	63	97	8	36	NM
29P MARINES	8	55	1	31	6.4	732	251	17	29	117	18	70	100	3	27	NM
MDAQMD Totals	28	52	6	35	7.2	950	239	40	27	114	0	64	97	0	28	0.337

NM: Never Monitored

na: not active

inc: incomplete

Note: Included in MDAQMD totals are Barstow, Hesperia, Phelan, 29Palms, Trona, and Victorville.

01/14
2008

Air Quality Management District

EXCEEDANCES OF STANDARDS AND MAXIMUM CONCENTRATIONS

2008

STATION	OZONE					CARBON MONOXIDE					NITROGEN DIOXIDE			SULFUR DIOXIDE			
	days over state	days over federal	max 8hr ppm	max 1hr ppm	avg 1hr ppm	days over state	days over federal	max 8hr ppm	max 1hr ppm	avg 1hr ppm	days over state	max 1hr ppm	avg 1hr ppm	days over state	max 24hr ppm	max 1hr ppm	avg 1hr ppm
	1hr/8hr	8hr				1hr/8hr	1hr/8hr				std			24h/1h			
BARSTOW	5 / 23	7	0.097	0.104	0.033	0/0	0/0	1.2	1.4	0.111	0	0.081	0.019	na/na	na	na	na
HESPERIA	29 / 80	58	0.107	0.132	0.041	na/na	na/na	na	na	na	na	na	na	na/na	na	na	na
PHELAN	32 / 73	50	0.106	0.130	0.046	na/na	na/na	na	na	na	na	na	na	na/na	na	na	na
TRONA	3 / 23	7	0.094	0.100	0.037	NM	NM	NM	NM	NM	0	0.062	0.004	0/0	0.004	0.036	0.001
VICTORVILLE	16 / 58	32	0.098	0.109	0.035	0/0	0/0	1.0	1.4	0.215	0	0.074	0.016	0/0	0.002	0.006	0.001
LANCASTER AVAQMD	18 / 59	39	0.103	0.116	0.038	0/0	0/0	1.0	2.2	0.167	0	0.062	0.013	na/na	na	na	na
29P MARINES	0 / 15	8	0.085	0.093	0.039	0/0	0/0	inc	inc	inc	inc	inc	inc	0/0	inc	inc	inc
MDAQMD Totals	47 / 89	72	0.107	0.132	0.038	0/0	0/0	1.2	1.4	0.163	0	0.081	0.013	0	0.004	0.036	0.001

STATION	WIND SPEED (MPH)					TEOM (PM10) (ug/m3)				TEMP (deg F)			HUMIDITY (%)			SOLAR RAD
	PEAK SPEED		AVERAGE SPEED			max 1hr	max daily	days avg	monthly avg	max 1hr	min 1hr	monthly avg	max 1hr	min 1hr	monthly avg	Avg Daily Solar Radiation
	w/1hr >40mph	peak mph	24hr avg >30mph	1hr avg mph	hourly mph	pm10 ug/m3	pm10 ug/m3	over 50ug/m3	pm10 ug/m3	tmp Deg F	tmp Deg F	tmp Deg F	RH %	RH %	RH %	Langley's
BARSTOW	40	84	8	48	8.3	NM	NM	NM	NM	107	28	66	95	0	31	NM
HESPERIA	12	53	1	33	7.4	NM	NM	NM	NM	103	28	62	NM	NM	NM	NM
PHELAN	10	58	2	36	7.4	NM	NM	NM	NM	97	26	60	NM	NM	NM	NM
TRONA	20	53	4	32	5.7	886	157	22	23	123	28	69	NM	NM	NM	NM
VICTORVILLE	20	59	1	34	7.2	927	286	23	31	103	23	62	NM	NM	NM	0.337
LANCASTER AVAQMD	0	40	0	23	4.9	690	153	16	25	108	27	64	104	8	39	NM
29P MARINES	7	55	2	32	6.3	951	368	44	32	112	28	70	100	3	31	NM

Table C.2-5 Equipment Dimensions

DESCRIPTION	Quantity	Height (ft)	Length (ft)	Width (ft)	Diameter (ft)	Weight (lb)	Force (lb/ft ²)
Warehouse (21)	2	16.5	170.0	80.0			
Water Treatment Building (11)	2	16.5	50.4	36.4			
HTF Electrical Buildings (27)	2	16.5	49.2	26.2			
Cooling Tower Electrical Buildings (26)	2	16.5	57.0	20.0			
Closed Cycle Cooling Buildings (13.1)	2	30.0	39.7	18.9			
Diesel Generator Building (23)	2	30.0	40.0	12.0			
Auxiliary Boiler Building (29)	2	30.0	50.0	28.6			
HTF Pump House (4) *pumps are out in the open. Not housed. Individual pumps are 8.5 wide by 25.5 long by 9.5 high. Full area of all 5 pumps are ~ 60x100 ft including maintenance area.	2	15.5	20.5	14.0		65000.0	
Power Plant E&C Buildings (22; part of building 10)	2	23.0	81.5	70.0			
Central E&C and Operations Building (10)	2	32.0	111.0	25.0			
Mirror Modules Assembly Factory (off-powerblock, NE part of solar field)	2	44.0	295.3	282.5			
Cooling Towers (12.1)	2	44.0	324.0	54.0		1200000.0	68.6
Steam Generation (5.1) *Steam generations are kept outside	2	50.0	198.0	70.0			
STG Building (7.1 AND 8.1 are extents of building)	2	72.5	142.1	107.8			
Feedwater Heater 1 (centerline elevation) (inside 5.1)	2	4.0	15.8		2.9		
Feedwater Heater 2 (centerline elevation) (inside 5.1)	2	4.5	28.8		3.3		
Feedwater Heater 3 (centerline elevation) (inside 5.1)	2	4.0	28.8		3.3		
Feedwater Heater 4 (centerline elevation) (inside 5.1)	2	4.0	28.5		3.0		
Feedwater Heater 5 (centerline elevation) (inside 5.1)	2	4.0	31.4		3.8		
Feedwater Heater 6 (centerline elevation) (inside 5.1)	2	4.0	28.5		3.0		
Oil Preheaters (centerline elevation) (inside 5.1)	2	6.8	23.0		4.8		
Boilers (centerline elevation) (inside 5.1)	8	8.3	36.0		6.0		
Boiler Drums (centerline elevation) (inside 5.1)	4	32.8	26.3		5.5		
Superheaters (centerline elevation) (inside 5.1)	4	7.5	27.0		6.0		
Reheaters (centerline elevation) (inside 5.1)	4	8.0	41.0		6.5		
Deaerator (centerline elevation) (inside 5.1)	2	40.0	40.7		11.9	86200.0	
Generator Step-Up Transformer 148-175MVA (168.4MVA) (14)	4	26.0	30.0	20.0		572990.0	955.0
Auxiliary Unit Transformers 60-70MVA (60MVA) (14)	4	25.7	31.3	16.7		305210.0	583.9
Auxiliary Unit Transformers 10MVA (outside building 27)	2	13.6	13.1	13.0		59500.0	349.4
Auxiliary Unit Transformers 6MVA (out in the solar field by the Well Pumps)	2	8.3	11.8	11.2		44500.0	339.2
Auxiliary Unit Transformers 4MVA (out in the solar field by the Well Pumps)	2	8.3	11.8	11.2		44500.0	339.2
Auxiliary Unit Transformers 3500KVA (outside building 22)	8	6.3	5.8	7.5		20000.0	457.1
Auxiliary Unit Transformers 3000KVA (outside building 27)	2	6.3	5.8	7.5		20000.0	457.1
Auxiliary Unit Transformers 750KVA (outside building 26)	6	6.0	5.8	6.6		14100.0	368.1
Auxiliary Unit Transformers 2500KVA (located out in the solar field)	8	5.7	5.5	5.1		7400.0	265.6
Major Pipe Rack Running East to West (no number)	2		550.9	20.0			
Steam Turbine (of entire STG assembly; includes HP/IP/LP Turbine, generator centerline elevation; excludes condenser) inside of 8.1 building *dimensions are from Siemens; should match layout.	2	24.8	94.1	29.5		386779.0	~4000-5000
Generator (rotor centerline elevation) (inside of 8.1 building)	2	24.8	28.1	12.0		329590.0	~4000-5000

Storage Tank Descriptions and Dimensions

DESCRIPTION	Quantity	Volume (ft ³)	Volume (gal)	Max Fill (gal)	Type	Height (ft)	Length (ft)	Width (ft)	Diameter (ft)	Weight (lb)	Force (lb/ft ²)
Shop Fab Tanks (Continuous Blowdown)	2	154	1,152			6.35			5.56	8,642	356
Shop Fab Tanks (Intermittent Blowdown Tank)	2	227	1,698			6.35			6.75	12,693	355
Shop Fab Tanks (Power Plant Condensate Receiver)	2	377	2,820			11.91			6.35	21,106	667
Shop Fab Tanks (Waste Slurry Tank)	2	1,571	11,750			7.94			15.87	86,918	439
Shop Fab Tanks (CC Expansion Tank)	2	113	846			6.35			4.76	6,373	358
Field Erected Tanks (HTF Expansion Tanks) (3)	16	5,429	40,608			48.00			12.00	0	0
Field Erected Tanks (HTF Overflow Tanks) (6)	4	31,776	237,703			35.00			34.00	1,751,007	1,929
Field Erected Tanks (RO Reject Water) (33)	2	7,069	52,877			15.87			23.81	390,124	876
Field Erected Tanks (RO Water) (31)	2	9,974	74,613			31.75			20.00	551,038	1,754
Field Erected Tanks (CT Blowdown Water) (30)	2	19,244	143,952			27.78			27.78	1,061,274	1,751
Field Erected Tanks (Service Water/Fire Water) (16)	2	96,208	719,689			39.69			55.56	5,293,928	2,184
Field Erected Tanks (Raw Water) (17)	2	257,701	1,927,739			33.34			99.21	14,165,370	1,832
Diesel Generator Day Tank (part of 23)	2	24	180			33.34	2	3	99.21	14,166,104	1,832
Diesel Storage Tank (24)	2	873	6,528			4.00			7.75	48,687	1,032
Nitrogen Storage Vessel (inside area marked 34)	2	2,488	18,612			18.50	22		12.00	129,319	1,143





Figure C.2-1a

NOTE:
 COORDINATES SHOWN HEREON ARE GRID
 COORDINATES BASED ON CALIFORNIA STATE
 PLANE ZONE 5, NAD83. TO GET GROUND
 DISTANCE/COORDINATES MULTIPLY BY THE
 COMBINATION FACTOR OF 1.00018256217

MOJAVE SOLAR PROJECT

PROJECT SITE MAP

STATE PLANE COORDINATES

SCALE: 1" = 800'

MOJAVE SOLAR LLC

Merrell-Johnson Engineering, Inc.

PROJECT:
 DATE: 05/06/09

10-2009, 8 May 2009, P:\3001-4 Mojave Solar - General Improvement Area Map - Marrell-Johnson Engineering, Inc.





Figure C.2-1b

NOTE:
COORDINATES SHOWN HEREON ARE GRID
COORDINATES BASED ON CALIFORNIA STATE
PLANE ZONE 5, NAD83. TO GET GROUND
DISTANCE/COORDINATES MULTIPLY BY THE
COMBINATION FACTOR OF 1.00018256217

MOJAVE SOLAR PROJECT
PROJECT SITE MAP
STATE PLANE COORDINATES

0 400' 800' 1200'
SCALE: 1" = 800'

MOJAVE SOLAR LLC

Marrell-Johnson Engineering, Inc.

PROJECT:
DATE: 05/06/09





Figure C.2-1c

NOTE:
 COORDINATES SHOWN HEREON ARE GRID
 COORDINATES BASED ON CALIFORNIA STATE
 PLANE ZONE 5, NAD83. TO GET GROUND
 DISTANCE/COORDINATES MULTIPLY BY THE
 COMBINATION FACTOR OF 1.00018256217

MOJAVE SOLAR PROJECT

PROJECT SITE MAP

STATE PLANE COORDINATES

0 400' 800' 1200'

SCALE: 1" = 800'


MOJAVE SOLAR LLC

Merrell-Johnson Engineering, Inc.

PROJECT:
 DATE: 05/06/09


41
40
39
38
37
36
35
34
33
32
31
30
29
28
27
26
25
24
23
22
21
20
19
18
17
16
15
14
13
12
11
10
9
8
7
6
5
4
3
2
1

Figure C.2-2



3	EXPANSION VESSELS
4	HTF PUMPS HOUSE
5.1	UNIT #1 - STEAM GENERATOR
5.2	OVERFLOW VESSELS
7.1	UNIT #1 - BFW HEATERS, DA, BFW PUMPS AND BRINE CONCENTRATOR
7.2	UNIT #1 - YG AREA
8.1	UNIT #1 - YG AREA
8.2	DCS ROOM
9	CENTRAL E&C AND OPERATIONS BUILDING (OFFICES & MAINT. SHOPS)
10	WATER TREATMENT BUILDING
12.1	UNIT #1 - COOLING TOWER
12.2	UNIT #1 - CLOSED LOOP COOLING SYSTEM (CLCS)
13.1	SWITCHYARD
13.2	WATER/WASTEWATER TREATMENT SYSTEMS
14	FIREWATER/COOLING TOWER MAKE UP TANK
15	RAW WATER TANK
16	FUTURE RAW WATER CLARIFIER/FILTERS
17	CONTROL ROOM
18	LUNCH ROOM
19	WAREHOUSE
20	CONTROL ELECTRICAL POWER ROOM
21	DIESEL GENERATOR
22	DG FUEL OIL STORAGE TANK
23	SUBSTATION RELAY HOUSE
24	CT ELECTRICAL BUILDING
25	HTF ELECTRICAL ROOM
26	13.8KV DUCT BANK-TIE BETWEEN ALPHA & BETA SITE
27	AUXILIARY BOILER
28	COOLING TOWER BLOWDOWN TANK
29	R.O. WATER TANK
30	R.O. REJECT WATER TANK
31	POLISHED WATER TANK
32	NITROGEN UNIT
33	OILY WATER SLUMP & OIL/WATER SEPARATOR

PRELIMINARY



ABENCS
Abener Engineering and Construction Services,
ST. LOUIS, MISSOURI

ABENGOA SOLAR
ABENER DRAWING NUMBER

CENTRAL PLANT LAYOUT
FOR ALPHA (WET COOL) PLANT
HARPER LAKE, CA

BY	DATE	APP'D.	DATE	JOB NO.	REVISION
TLF				120010	
DRAWING NO.				MD-L103	
SCALE				1"=100'-0"	

NO.	DATE	DESCRIPTION	BY	BY	BY

NO.	DATE	DESCRIPTION	BY	BY	BY

NO.	DATE	DESCRIPTION	BY	BY	BY

NO.	DATE	DESCRIPTION	BY	BY	BY

THIS DRAWING IS THE PROPERTY
OF
ABENCS
Abener Engineering and Construction Services, LLC
INFORMATION AND KNOW-HOW HEREON ARE CONFIDENTIAL AND
PROPRIETARY AND MAY NOT BE USED, REPRODUCED, OR REVEALED
TO OTHERS EXCEPT IN ACCORDANCE WITH THE TERMS OF A
CONTRACT WITH OR OTHER WRITTEN PERMISSION OF Abener
Engineering and Construction Services, LLC. ANY REPRODUCTIONS IN
WHOLE OR IN PART WITHOUT THE WRITTEN PERMISSION OF Abener
Engineering and Construction Services, LLC ARE PROHIBITED.
TO THIS STAMP FOR REVIEW

ISSUE DATE	PURPOSE OF ISSUE

Figure C.2-3

Mojave Solar One - Alpha Block BPIP Structures (Beta Block Identical)




Figure C.2-4a

Mojave Solar One - Property Fencelines and Nearby Receptors




Figure C.2-4b





Figure C.2-5

Mojave Desert Air Basin Monitoring Stations (2006-2008)



Protocol for Increments Analysis

Overview of Requirements for Increments Analysis

The federal Prevention of Significant Deterioration (PSD) program is intended to ensure that economic growth in areas with good air quality occurs without causing the deterioration of that air quality to unhealthful levels. The PSD program contains a number of requirements that apply to new or modified sources of air pollution that are located in clean air areas.

These PSD program requirements, applied on a pollutant-specific basis, include conducting an increments analysis to demonstrate that no increments will be exceeded as a result of the proposed new or modified source.

The MS1 project is **not** expected to trigger the requirements of the PSD program. Therefore, no increment analysis is proposed at this time.

Should a determination be made in the future that the PSD regulations apply, or emissions levels are such that PSD becomes applicable, a protocol will be submitted which will outline the required review, analyses, and methodologies to be used.

Health Risk Assessment Support Data

Health Risk Assessment Process, Goals, Assumptions, and Uses

“In recent years, the public has become increasingly aware of the presence of harmful chemicals in our environment. Many people express concerns about pesticides and other foreign substances in food, contaminants in drinking water, and toxic pollutants in the air. Others believe these concerns are exaggerated or unwarranted. How can we determine which of these potential hazards really deserve attention? How do we, as a society, decide where to focus our efforts and resources to control these hazards? When we hear about toxic threats that affect us personally, such as the discovery of industrial waste buried in our neighborhood or near our children’s school, how concerned should we be?

Health risk assessment is a scientific tool designed to help answer these questions. Government agencies rely on risk assessments to help them determine which potential hazards are the most significant. Risk assessments can also guide regulators in abating environmental hazards. Members of the public who learn the basics of risk assessment can improve their understanding of both real and perceived environmental hazards, and they can work more effectively with decision makers on solutions to environmental problems.

Chemicals can be either beneficial or harmful, depending on a number of factors, such as the amounts to which we are exposed. Low levels of some substances may be necessary for good health, but higher levels may be harmful. Health risk assessments are used to determine if a particular chemical poses a significant risk to human health and, if so, under what circumstances. Could exposure to a specific chemical cause significant health problems? How much of the chemical would someone have to be exposed to before it would be dangerous? How serious could the health risks be? What activities might put people at increased risk?

If it were possible to prevent all human exposure to all hazardous chemicals, there would be no need for risk assessment. However, the total removal of harmful pollutants from the environment is often infeasible or impossible, and many naturally occurring substances also pose health risks. Risk assessment helps scientists and regulators identify serious health hazards and determine realistic goals for reducing exposure to toxics so that there is no significant health threat to the public.

Estimating the hazards posed by toxic chemicals in the environment involves the compilation and evaluation of complex sets of data. Government regulators, therefore, turn to specialists to perform or assist with risk assessments. These specialists include scientists with degrees in toxicology (the study of the toxic effects of chemicals) and epidemiology (the study of disease or illness in populations) as well as physicians, biologists, chemists, and engineers.

The term “health risk assessment” is often misinterpreted. People sometimes think that a risk assessment will tell them whether a current health problem or symptom was caused by exposure

to a chemical. This is not the case. Scientists who are searching for links between chemical exposures and health problems in a community may conduct an epidemiologic study. These studies typically include a survey of health problems in a community and a comparison of health problems in that community with those in other cities, communities, or the population as a whole.

Although they are both important, health risk assessments and epidemiologic studies have different objectives. Most epidemiologic studies evaluate whether *past* chemical exposures may be responsible for documented health problems in a specific group of people. In contrast, health risk assessments are used to estimate whether current or future chemical exposures will pose health risks to a broad population, such as a city or a community. Scientific methods used in health risk assessment cannot be used to link individual illnesses to past chemical exposures, nor can health risk assessments and epidemiologic studies prove that a specific toxic substance caused an individual's illness.

The U.S. Environmental Protection Agency (U.S. EPA) is a leading risk assessment agency at the federal level. In California, the Office of Environmental Health Hazard Assessment (OEHHA) in the California Environmental Protection Agency (Cal/EPA) has the primary responsibility for developing procedures and practices for performing health risk assessments. Other agencies within Cal/EPA, such as the Department of Pesticide Regulation and the Department of Toxic Substances Control, have extensive risk assessment programs of their own but work closely with OEHHA.

The Department of Pesticide Regulation uses risk assessments to make regulatory decisions concerning safe pesticide uses. The Department of Toxic Substances Control uses risk assessments to determine requirements for the management and cleanup of hazardous wastes. OEHHA's health risk assessments are used by the Air Resources Board to develop regulations governing toxic air contaminants, and by the Department of Health Services to develop California's drinking water standards. These agencies' decisions take into account the seriousness of potential health effects along with the economic and technical feasibility of measures that can reduce the health risks.

Health risk assessment requires both sound science and professional judgment and is a constantly developing process. Cal/EPA is nationally recognized for developing new procedures that improve the accuracy of risk assessments. Cal/EPA also works closely with U.S. EPA in all phases of risk assessment.

The risk assessment process is typically described as consisting of four basic steps: hazard identification, exposure assessment, dose-response assessment, and risk characterization. Each of these steps will be explained in the following text.

Hazard Identification

In the first step, hazard identification, scientists determine the types of health problems a chemical could cause by reviewing studies of its effects in humans and laboratory animals. Depending on the chemical, these health effects may include short-term ailments, such as headaches; nausea; and eye, nose, and throat irritation; or chronic diseases, such as cancer. Effects on sensitive populations, such as pregnant women and their developing fetuses, the elderly, or those with health problems

(including those with weakened immune systems), must also be considered. Responses to toxic chemicals will vary depending on the amount and length of exposure. For example, short-term exposure to low concentrations of chemicals may produce no noticeable effect, but continued exposure to the same levels of chemicals over a long period of time may eventually cause harm. An important step in hazard identification is the selection of key research studies that can provide accurate, timely information on the hazards posed to humans by a particular chemical. The selection of a study is based upon factors such as whether the study has been peer reviewed by qualified scientists, whether the study's findings have been verified by other studies, and the species tested (human studies provide the best evidence). Some studies may involve humans that have been exposed to the chemical, while others may involve studies with laboratory animals.

Human data frequently are useful in evaluating human health risks associated with chemical exposures. Human epidemiologic studies typically examine the effects of chemical exposure on a large number of people, such as employees exposed to varying concentrations of chemicals in the workplace. In many cases, these exposures took place prior to the introduction of modern worker-safety measures.

One weakness of occupational studies is that they generally measure the effects of chemicals on healthy workers and do not consider children, the elderly, those with pre-existing medical conditions, or other sensitive groups. Since occupational studies are not controlled experiments, there may be uncertainties about the amount and duration of exposure or the influence of lifestyle choices, such as smoking or alcohol use, on the health of workers in the studies. Exposure of workers to other chemicals at the same time may also influence and complicate the results.

Laboratory studies using human volunteers are better able to gauge some health effects because chemical exposures can then be measured with precision. But these studies usually involve small numbers of people and, in conformance with ethical and legal requirements, use only adults who agree to participate in the studies. Moreover, laboratory studies often use simple measurements that identify immediate responses to the chemical but might miss significant, longer-term health effects. Scientists can also use physicians' case reports of an industrial or transportation accident in which individuals were unintentionally exposed to a chemical. However, these reports may involve very small numbers of people, and the level of exposure to the chemical could be greater than exposures to the same chemical in the environment. Nevertheless, human studies are preferred for risk assessment, so OEIHA makes every effort to use them when they are available.

Because the effects of the vast majority of chemicals have not been studied in humans, scientists must often rely on animal studies to evaluate a chemical's health effects. Animal studies have the advantage of being performed under controlled laboratory conditions that reduce much of the uncertainty related to human studies. If animal studies are used, scientists must determine whether a chemical's health effects in humans are likely to be similar to those in the animals tested. Although effects seen in animals can also occur in humans, there may be subtle or even significant differences in the ways humans and experimental animals react to a chemical. Comparison of human and animal metabolism may be useful in selecting the animal species that should be studied, but it is often not possible to determine which species is most like humans in its response to a chemical exposure. However, if similar effects were found in more than one species, the results would strengthen the evidence that humans may also be at risk.

Exposure Assessment

In exposure assessment, scientists attempt to determine how long people were exposed to a chemical; how much of the chemical they were exposed to; whether the exposure was continuous or intermittent; and how people were exposed – through eating, drinking water and other liquids, breathing, or skin contact. All of this information is combined with factors such as breathing rates, water consumption, and daily activity patterns to estimate how much of the chemical was taken into the bodies of those exposed.

People can be exposed to toxic chemicals in various ways. These substances can be present in the air we breathe, the food we eat, or the water we drink. Some chemicals, due to their particular characteristics, may be both inhaled and ingested. For example, airborne chemicals can settle on the surface of water, soil, leaves, fruits, vegetables, and forage crops used as animal feed. Cows, chickens, or other livestock can become contaminated when eating, drinking, or breathing the chemicals present in the air, water, feed, and soil. Fish can absorb the chemicals as they swim in contaminated water or ingest contaminated food. Chemicals can be absorbed through the skin, so infants and children can be exposed simply by crawling or playing in contaminated dirt. They can also ingest chemicals if they put their fingers or toys in their mouths after playing in contaminated dirt. Chemicals can also be passed on from nursing mothers to their children through breast milk.

To estimate exposure levels, scientists rely on air, water, and soil monitoring; human blood and urine samples; or computer modeling. Although monitoring of a pollutant provides excellent data, it is time consuming, costly, and typically limited to only a few locations. For those reasons, scientists often rely on computer modeling, which uses mathematical equations to describe how a chemical is released and to estimate the speed and direction of its movement through the surrounding environment. Modeling has the advantage of being relatively inexpensive and less time consuming, provided all necessary information is available and the accuracy of the model can be verified through testing.

Computer modeling is often used to assess chemical releases from industrial facilities. Such models require information on the type of chemicals released, facilities' hours of operation, industrial processes that release the chemicals, smokestack height and temperature, any pollution-control equipment that is used, surrounding land type (urban or rural), local topography and meteorology, and census data regarding the exposed population.

In all health risk assessments, scientists must make assumptions in order to estimate human exposure to a chemical. For example, scientists assessing the effects of air pollution may need to make assumptions about the time people spend outdoors, where they are more directly exposed to pollutants in the ambient air, or the time they spend in an area where the pollution is greatest. An assessment of soil contamination may require scientists to make assumptions about people's consumption of fruits and vegetables that may absorb soil contaminants.

To avoid underestimating actual human exposure to a chemical, scientists often look at the range of possible exposures. For example, people who jog in the afternoon, when urban air pollution levels are highest, would have much higher exposures to air pollutants than people who come home after work and relax indoors. Basing an exposure estimate on a value near the higher end of

a range of exposure levels (closer to the levels experienced by the jogger than by the person remaining indoors) provides a realistic worst-case estimate of exposure. These kinds of conservative assumptions, which presume that people are exposed to the highest amounts of a chemical that can be considered credible, are referred to as “health-protective” assumptions.

Dose-Response Assessment

In dose-response assessment, scientists evaluate the information obtained during the hazard identification step to estimate the amount of a chemical that is likely to result in a particular health effect in humans.

An established principle in toxicology is that “the dose makes the poison.” For example, a commonplace chemical like table salt is harmless in small quantities, but it can cause illness in large doses. Similarly, hydrochloric acid, a hazardous chemical, is produced naturally in our stomachs but can be quite harmful if taken in large doses.

Scientists perform a dose-response assessment to estimate how different levels of exposure to a chemical can impact the likelihood and severity of health effects. The dose-response relationship is often different for many chemicals that cause cancer than it is for those that cause other kinds of health problems.

Cancer Effects

For chemicals that cause cancer, the general assumption in risk assessment has been that there are no exposures that have “zero risk” unless there is clear evidence otherwise. In other words, even a very low exposure to a cancer-causing chemical may result in cancer if the chemical happens to alter cellular functions in a way that causes cancer to develop. Thus, even very low exposures to carcinogens might increase the risk of cancer, if only by a very small amount.

Several factors make it difficult to estimate the risk of cancer. Cancer appears to be a progressive disease because a series of cellular transformations is thought to occur before cancer develops. In addition, cancer in humans often develops many years after exposure to a chemical. Also, the best information available on the ability of chemicals to cause cancer often comes from studies in which a limited number of laboratory animals are exposed to levels of chemicals that are much higher than the levels humans would normally be exposed to in the environment. As a result, scientists use mathematical models based on studies of animals exposed to high levels of a chemical to estimate the probability of cancer developing in a diverse population of humans exposed to much lower levels. The uncertainty in these estimates may be rather large. To reduce these uncertainties, risk assessors must stay informed of new scientific research. Data from new studies can be used to improve estimates of cancer risks.

Non-cancer Effects

Non-cancer health effects (such as asthma, nervous system disorders, birth defects, and developmental problems in children) typically become more severe as exposure to a chemical increases. One goal of dose-response assessment is to estimate levels of exposure that pose only a low or negligible risk for non-cancer health effects. Scientists analyze studies of the health effects of a chemical to develop this estimate. They take into account such factors as the quality of the scientific studies, whether humans or laboratory animals were studied, and the degree to which some people may be more sensitive to the chemical than others. The estimated level of exposure

that poses no significant health risks can be reduced to reflect these factors.

Risk Characterization

The last step in risk assessment brings together the information developed in the previous three steps to estimate the risk of health effects in an exposed population. In the risk characterization step, scientists analyze the information developed during the exposure and dose-response assessments to describe the resulting health risks that are expected to occur in the exposed population. This information is presented in different ways for cancer and non-cancer health effects, as explained below.

Cancer Risk

Cancer risk is often expressed as the maximum number of new cases of cancer projected to occur in a population of one million people due to exposure to the cancer-causing substance over a 70-year lifetime. For example, a cancer risk of one in one million means that in a population of one million people, not more than one additional person would be expected to develop cancer as the result of the exposure to the substance causing that risk.

An individual's actual risk of contracting cancer from exposure to a chemical is often less than the theoretical risk to the entire population calculated in the risk assessment. For example, the risk estimate for a drinking-water contaminant may be based on the health-protective assumption that the individual drinks two liters of water from a contaminated source daily over a 70-year lifetime. However, an individual's actual exposure to that contaminant would likely be lower due to a shorter time of residence in the area. Moreover, an individual's risk not only depends on the individual's exposure to a specific chemical but also on his or her genetic background (i.e., a family history of certain types of cancer); health; diet; and lifestyle choices, such as smoking or alcohol consumption.

Cancer risks presented in risk assessments are often compared to the overall risk of cancer in the general U.S. population (about 250,000 cases for every one million people) or to the risk posed by all harmful chemicals in a particular medium, such as the air. The cancer risk from breathing current levels of pollutants in California's ambient air over a 70-year lifetime is estimated to be 760 in one million.

Non-cancer Risk

Non-cancer risk is usually determined by comparing the actual level of exposure to a chemical to the level of exposure that is not expected to cause any adverse effects, even in the most susceptible people. Levels of exposure at which no adverse health effects are expected are called "health reference levels," and they generally are based on the results of animal studies. However, scientists usually set health reference levels much lower than the levels of exposure that were found to have no adverse effects in the animals tested. This approach helps to ensure that real health risks are not underestimated by adjusting for possible differences in a chemical's effects on laboratory animals and humans; the possibility that some humans, such as children and the elderly, may be particularly sensitive to a chemical; and possible deficiencies in data from the animal studies.

Depending on the amount of uncertainty in the data, scientists may set a health reference level 100 to 10,000 times lower than the levels of exposure observed to have no adverse effects in

animal studies. Exposures above the health reference level are not necessarily hazardous, but the risk of toxic effects increases as the dose increases. If an assessment determines that human exposure to a chemical exceeds the health reference level, further investigation is warranted.

Risk managers rely on risk assessments when making regulatory decisions, such as setting drinking water standards, or developing plans to clean up hazardous waste sites. Risk managers are responsible for protecting human health, but they must also consider public acceptance, as well as technological, economic, social, and political factors, when arriving at their decisions. For example, they may need to consider how much it would cost to remove a contaminant from drinking water supplies or how seriously the loss of jobs would affect a community if a factory were to close due to the challenge of meeting regulatory requirements that are set at the most stringent level.

Health risk assessments can help risk managers weigh the benefits and costs of various alternatives for reducing exposure to chemicals. For example, a health risk assessment of a hazardous waste site could help determine whether placing a clay cap over the waste to prevent exposure would offer the same health protection as the more costly option of removing the waste from the site.

One of the most difficult questions of risk management is: How much risk is acceptable? While it would be ideal to completely eliminate all exposure to hazardous chemicals, it is usually not possible or feasible to remove all traces of a chemical once it has been released into the environment. The goal of most regulators is to reduce the health risks associated with exposure to hazardous pollutants to a negligibly low level.

Regulators generally presume that a one-in-one million risk of cancer from life-long exposure to a hazardous chemical is an "acceptable risk" level because the risk is extremely low compared to the overall cancer rate. If a drinking water standard for a cancer-causing chemical were set at the level posing a "one-in-one million" risk, it would mean that not more than one additional cancer case (beyond what would normally occur in the population) would potentially occur in a population of one million people drinking water meeting that standard over a 70-year lifetime.

Actual regulatory standards for chemicals or hazardous waste cleanups may be set at less stringent risk levels, such as one in 100,000 (not more than one additional cancer case per 100,000 people) or one in 10,000 (not more than one additional cancer case per 10,000 people). These less stringent risk levels are often due to economic or technological considerations. Regulatory agencies generally view these higher risk levels to be acceptable if there is no feasible way to reduce the risks further."¹

The exposure and dose-response estimates for the project analysis were conducted using HARP (Version 1.4a).

¹ A Guide to Health Risk Assessment, CalEPA-Office of Environmental Health Hazard Assessment, 1001 I Street, Sacramento, Ca. 95812, (est. 2001).

The following tables summarize the results of the HRA performed by the proposed MS1 facility.

TABLE C.4-1 CRITERIA AND AIR TOXIC POLLUTANTS EMITTED FROM MS1 FACILITY

NOx	Diesel Particulate Matter
CO	Metals (Cooling Tower)
VOC*	Acetaldehyde
SOx	Acrolein
PM10/PM2.5	Benzene
1-3 Butadiene	Ethylbenzene
Formaldehyde	Hexane
PAHs	Naphthalene
Propylene	Propylene Oxide
Toluene	Xylenes

TABLE C.4-2 HEALTH EFFECTS SIGNIFICANT THRESHOLD LEVELS

Agency	Significance Thresholds	
	MDAQMD	State of California
Cancer Risk per million	Moderate Risk $>1 \times 10^{-6}$	≤ 1.0 without T-BACT ≤ 10.0 with T-BACT
Acute HI	Significant Risk $\geq 100 \times 10^{-6}$	1.0
Chronic HI	HI ≥ 10	1.0
Cancer Burden	Significant Health Risk $\geq 10 \times 10^{-6}$ HI ≥ 1	1.0

No specific health related studies were identified which pertain to the local project area for any identified toxic air pollutant or identified specific population.

The other assumptions used in running the HARP program were as follows:

- Emission rates for non-criteria pollutants are taken from AFC Section 5.2, and from Appendix C.1.
- Number of residents affected is based upon the updated 2000 population data for those census tracts or portions of census tracts which lie within the maximum impact receptor radius of the proposed facility.
- All receptors were treated as residential receptors, which allows for the assumption that the MIR, if assumed residential, will represent the highest risk and no other receptor will show risks higher than the MIR. This deletes the need for running worker risks. The HARP risk run options as recommended by South Coast AQMD (Chico, 10-20-05) were utilized (i.e., for cancer – 70-year and derived adjusted method; for chronic – 70-year and derived OEHHHA method; for acute – no options).
- Deposition velocity is taken to be 0.02 m/s, as recommended by ARB for controlled emission sources.
- Fraction of residents with gardens is taken to be 0.15 which is likely conservatively high for the rural (desert) area near the project site.
- Fraction of produce grown at home is taken to be 0.15, which is also likely to be conservatively high for the rural (desert) area near the project site.

The HARP program is a tool that assists with the programmatic requirements of the Air Toxics Hot Spots Program, and it can be used for preparing health risk assessments for other related programs such as air toxic control measure development or facility permitting applications. HARP is a computer based risk assessment program which combines the tools of emission inventory database, facility prioritization, air dispersion modeling, and risk assessment analysis. Use of HARP promotes statewide consistency in the area of risk assessment, increases the efficiency of evaluating potential health impacts, and provides a cost effective tool for developing facility health risk assessments. HARP may be used on single sources, facilities with multiple sources, or multiple facilities in close proximity to each other. The receptor grid used in HARP was the same as the grid used in the air quality impact analysis (AERMOD). The AERMOD files used in the HARP analysis were processed via the HARP On-Ramp program.

The HARP program results for acute and chronic inhalation and chronic non-inhalation exposures, cancer burden and individual cancer risk (workplace and residential) for the proposed sources are included in this Appendix.

The modeling results show that the maximum modeled cancer risk (MIR) from MS1 is expected to be 2.59×10^{-7} . This risk is well below the ten in one million level (with T-BACT), and the MDAQMD significance value. The chronic and acute non-cancer hazard indices are 0.00208 and 0.0101, respectively (at the cancer MIR location). Both are well below the significant impact level of 1.0. The MIR was located offsite approximately 453 feet from the site grid center. At this radius there are no impacted populations, therefore the total cancer burden was calculated to be 0.0, which is also well below the state threshold value of 1.0, as well as being below the MDAQMD Rule 1320 significance level of 0.5. Detailed calculations and results for each significant receptor are included in the modeling results, which are being submitted electronically.

TABLE C.4-3 HEALTH RISK ASSESSMENT SUMMARY (MIR)		
Stationary Sources Only		
Risk Category	Facility Values	Applicable Significance Threshold
Cancer Risk	2.59×10^{-7}	$\leq 10.0 \times 10^{-6}$
Chronic Hazard Index	0.00208	1.0
Acute Hazard Index	0.0101	1.0
Cancer Burden	0	0.5
Facility MIR location coordinates are: Cancer risk and chronic MIR – 469945mE, 3874500mN Acute MIR location coordinates are: Acute MIR – 469945mE, 3874500mN		

The calculated health effects as summarized above do not exceed the district significance threshold values, therefore the health effects would be considered “not significant” and may even be “zero”. These HRA results are also provided on the air modeling CD. Due to length of the results output files, hard copies are not included in this appendix.

The following tables and figures are presented at the end of this appendix:

- Table C.4-4 Sensitive Receptor Listing for the Primary Impact Area
- Table C.4-5 OEHHA/CARB Risk Assessment Health Values
- Table C.4-6 Census Tract Numbers, and Population Data
- Table C.4-7 3 Highest MIR Locations and Risk Values
- Figure C.4-1 Census Tracts in the Site Area
- Figure C.4-2 6-Mile Radius Zone Map
- Figure C.4-3 3 Highest Cancer MIR Locations

Risk Assessment input and output files are included on the modeling CD.

Table C.4-4 Identified Sensitive Receptors and Distances from Site
Harper Lake Solar Generating Station

Receptor ID	Google Earth Data				Dist. From Site, m.	Dist. From Site, ft.	Receptor #	NAD27		
	UTM Em	UTM Nm	Elev., ft.	Site				UTM Em	UTM Nm	Elev. ft.
Kramer Junction	470569	3874265	2062	na	20120.7	na	1	470696	3874280	2013
worker	450560	3872148	2522	3241.5	3241.5	66016.0	2	450687	3872163	2473
worker	468349	3876627	2068	2082.1	2082.1	10635.4	3	468476	3876642	2019
res	450580	3872334	2491	19704.1	19704.1	65889.2	4	450707	3872349	2442
worker	450971	3872223	2478	20689.6	20689.6	64649.1	5	451098	3872238	2429
res	449883	3874649	2471	24559.0	24559.0	67882.5	6	450010	3874664	2422
res-Boron	447224	3881891	2848	28376.3	28376.3	80578.1	7	447351	3881906	2799
sch	442195	3873904	2469	33941.5	33941.5	93102.6	8	442322	3873919	2420
pre-sch	436634	3873603	2411	33955.5	33955.5	111361.9	9	436761	3873618	2362
worker	436622	3873505	2413	34508.3	34508.3	111408.0	10	436749	3873520	2364
res-Hinkley	436184	3877180	2414	14069.9	14069.9	113221.9	11	436311	3877195	2365
sch-Barstow	481797	3865786	2165	79407.7	79407.7	46163.3	12	481924	3865801	2116
hosp-Barstow	490882	3861107	2188	24202.3	24202.3	100378.8	13	491009	3861122	2139
unk (res-farm)	498280	3861300	2255	201.6	201.6	661.3	14	498407	3861315	2206
unk (res-farm)	470768	3874297	2062	947.7	947.7	3109.3	15	470895	3874312	2013
unk (res-farm)	469724	3874694	2067	2467.0	2467.0	8094.1	16	469851	3874709	2018
unk (res-farm)	468687	3875860	2070	339.5	339.5	1114.0	17	468814	3875875	2021
unk (res-farm)	470358	3873999	2072	957.6	957.6	3142.0	18	470485	3874014	2023
unk (res-farm)	469629	3874082	2079	854.1	854.1	2802.5	19	469756	3874097	2030
unk (res-farm)	469823	3873849	2077	2003.7	2003.7	6574.1	20	469950	3873864	2028
unk (res-farm)	469753	3872435	2129	2279.1	2279.1	7477.7	21	469880	3872450	2080
unk (res-farm)	469693	3872161	2140	1053.8	1053.8	3457.4	22	469820	3872176	2091
unk (res-farm)	471622	3874305	2047					471749	3874320	1998

Table C.4-5

OEHHA/CARB Consolidated Risk Value Summary Table

(14 pages total)

Table 1
CONSOLIDATED TABLE OF OEHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES*

CONSOLIDATED TABLE OF CHEMICALS AT PROVED RISK ASSESSMENT HEALTH VALUES															
Substance	Chemical Abstract Number	Noncancer Effects						Cancer Risk							
		Acute Inhalation (µg/m ³)	Date [*] Value Reviewed [Added]	8-Hour Inhalation (µg/m ³)	Date [*] Value Reviewed [Added]	Chronic Inhalation (µg/m ³)	Date [*] Value Reviewed [Added]	Chronic Oral (mg/kg-d)	Date [*] Value Reviewed [Added]	Inhalation Unit Risk (µg/m ³) ⁻¹	Inhalation Cancer Potency Factor (mg/kg-d) ⁻¹	Date [*] Value Reviewed [Added]	Oral Slope Factor (mg/kg-d) ⁻¹	Date [*] Value Reviewed [Added]	M [*] W A F
ACETALDEHYDE	75-07-0	4.7E+02	12/08	3.0E+02	12/08	1.4E+02	12/08			2.7E-06	1.0E-02	4/99 [5/93]			1
ACETAMIDE	60-35-5									2.0E-05	7.0E-02	4/99			1
ACROLEIN	107-02-8	2.5E+00	12/08	7.0E-01	12/08	3.5E-01	12/08								1
ACRYLAMIDE	79-06-1									1.3E-03	4.5E+00	4/99 [7/90]			1
ACRYLIC ACID	79-10-7	6.0E+03	4/99												1
ACRYLONITRILE	107-13-1					5.0E+00	12/01			2.9E-04	1.0E+00	4/99 [1/91]			1
ALLYL CHLORIDE	107-05-1									6.0E-06	2.1E-02	4/99			1
2-AMINOANTHRAQUINONE	117-79-3									9.4E-06	3.3E-02	4/99			1
AMMONIA	7664-41-7	3.2E+03	4/99			2.0E+02	2/00								1
ANILINE	62-53-3									1.6E-06	5.7E-03	4/99			1
ARSENIC AND COMPOUNDS (INORGANIC) ^{TAC}	7440-38-2 1016 [1015]	2.0E-01	12/08	1.5E-02	12/08	1.5E-02	12/08	3.5E-06	12/08	3.3E-03 ^{TAC}	1.2E+01	7/90	1.5E+00	10/00	1
ARSINE	7784-42-1	2.0E-01	12/08	1.5E-02	12/08	1.5E-02	12/08								1
ASBESTOS ^{TAC H}	1332-21-4									1.9E-04 ^{TAC H}	2.2E+02	3/86			333.33
BENZENE ^{TAC}	71-43-2	1.3E+03	4/99			6.0E+01	2/00			2.9E-05 ^{TAC}	1.0E-01	1/85			1
BENZIDINE (AND ITS SALTS) values also apply to:	92-87-5									1.4E-01	5.0E+02	4/99 [1/91]			1
Benzidine based dyes	1020									1.4E-01	5.0E+02	4/99 [1/91]			1
Direct Black 38	1937-37-7									1.4E-01	5.0E+02	4/99 [1/91]			1
Direct Blue 6	2602-46-2									1.4E-01	5.0E+02	4/99 [1/91]			1
Direct Brown 95 (technical grade)	16071-86-6									1.4E-01	5.0E+02	4/99 [1/91]			1
BENZYL CHLORIDE	100-44-7	2.4E+02	4/99							4.9E-05	1.7E-01	4/99			1
BERYLLIUM AND COMPOUNDS	7440-41-7 [1021]					7.0E-03	12/01	2.0E-03	12/01	2.4E-03	8.4E+00	4/99 [7/90]			1
BIS(2-CHLOROETHYL)ETHER (Dichloroethyl ether)	111-44-4									7.1E-04	2.5E+00	4/99			1
BIS(CHLOROMETHYL)ETHER	542-88-1									1.3E-02	4.6E+01	4/99 [1/91]			1
BROMINE AND COMPOUNDS	7726-95-6 [1040]														1
POTASSIUM BROMATE	7758-01-2									1.4E-04	4.9E-01	4/99 [10/93]			1

Table 1
CONSOLIDATED TABLE OF OEHAH/ARB APPROVED RISK ASSESSMENT HEALTH VALUES*

CONSOLIDATED TABLE OF OLIMPIATRAC APPROVED RISK ASSESSMENT HEALTH VALUES															
Substance	Chemical Abstract Number	Noncancer Effects						Cancer Risk							
		Acute Inhalation (µg/m ³)	Date Value Reviewed [Added]	8-Hour Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Oral (mg/kg-d)	Date Value Reviewed [Added]	Inhalation Unit Risk (µg/m ³) ⁻¹	Inhalation Cancer Potency Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	Oral Slope Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	M* W A F
1,3-BUTADIENE ^{TAC}	106-99-0					2.0E+01	1/01			1.7E-04 TAC	6.0E-01	7/92			1
CADMIUM AND COMPOUNDS ^{TAC}	7440-43-9 [1045]					2.0E-02	1/01	5.0E-04	10/00	4.2E-03 TAC	1.5E+01	1/87			1
CARBON DISULFIDE	75-15-0	6.2E+03	4/99			8.0E+02	5/02								1
CARBON MONOXIDE	630-08-0	2.3E+04	4/99												1
CARBON TETRACHLORIDE ^{TAC} (Tetrachloromethane)	56-23-5	1.9E+03	4/99			4.0E+01	1/01			4.2E-05 TAC	1.5E-01	9/87			1
CHLORINATED PARAFFINS	108171-26-2									2.5E-05	8.9E-02	4/99			1
CHLORINE	7782-50-5	2.1E+02	4/99			2.0E-01	2/00								1
CHLORINE DIOXIDE	10049-04-4					6.0E-01	1/01								1
4-CHLORO-O-PHENYLENEDIAMINE	95-83-0									4.6E-06	1.8E-02	4/99			1
CHLOROBENZENE	108-90-7					1.0E+03	1/01								1
CHLORODIFLUOROMETHANE (see Fluorocarbons)															
CHLOROFORM ^{TAC}	67-66-3	1.5E+02	4/99			3.0E+02	4/00			5.3E-06 TAC	1.9E-02	12/90			1
Chlorophenols	1060														1
PENTACHLOROPHENOL	87-86-5									5.1E-06	1.8E-02	4/99			1
2,4,6-TRICHLOROPHENOL	88-06-2									2.0E-05	7.0E-02	4/99 [1/91]			1
CHLOROPICRIN	76-06-2	2.9E+01	4/99			4.0E-01	12/01								1
p-CHLORO-o-TOLUIDINE	95-69-2									7.7E-05	2.7E-01	4/99			1
CHROMIUM 6+ ^{TAC} values also apply to:	18540-29-9					2.0E-01	1/01	2.0E-02	10/00	1.5E-01 TAC	5.1E+02	1/86	Ø		1
Barium chromate	10294-40-3					2.0E-01	1/01	2.0E-02	10/00	1.5E-01 TAC	5.1E+02	1/86	Ø		0.2053
Calcium chromate	13765-19-0					2.0E-01	1/01	2.0E-02	10/00	1.5E-01 TAC	5.1E+02	1/86	Ø		0.3332
Lead chromate	7758-97-6					2.0E-01	1/01	2.0E-02	10/00	1.5E-01 TAC	5.1E+02	1/86	Ø		0.1609
Sodium dichromate	10588-01-9					2.0E-01	1/01	2.0E-02	10/00	1.5E-01 TAC	5.1E+02	1/86	Ø		0.397
Strontium chromate	7789-06-2					2.0E-01	1/01	2.0E-02	10/00	1.5E-01 TAC	5.1E+02	1/86	Ø		0.2554
CHROMIUM TRIOXIDE (as chromic acid mist)	1333-82-0					2.0E-03	1/01	2.0E-02	10/00	1.5E-01 TAC	5.1E+02	1/86	Ø		0.52
COPPER AND COMPOUNDS	7440-50-8 [1067]	1.0E+02	4/99												1
p-CRESIDINE	120-71-8														1
CRESOLS (mixtures of)	1319-77-3					6.0E+02	1/01			4.3E-05	1.5E-01	4/99			1
m-CRESOL	108-39-4					6.0E+02	1/01								1

Table 1
CONSOLIDATED TABLE OF OEHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES*

Substance	Chemical Abstract Number	Noncancer Effects						Cancer Risk					
		Acute Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Inhalation (µg/m ³)	Date Value Reviewed [Added]	8-Hour Inhalation (µg/m ³)	Chronic Oral (mg/kg-d)	Date Value Reviewed [Added]	Inhalation Unit Risk (µg/m ³) ⁻¹	Inhalation Cancer Potency Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	Oral Slope Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]
o-CRESOL	95-48-7			6.0E+02	1/01								1
p-CRESOL	106-44-5			6.0E+02	1/01								1
CUPFERRON	135-20-6								6.3E-05	2.2E-01	4/99		1
Cyanide Compounds (inorganic)	57-12-5 1073	3.4E+02	4/99	9.0E+00	4/00								1
HYDROGEN CYANIDE (Hydrocyanic acid)	74-90-8	3.4E+02	4/99	9.0E+00	4/00								1
2,4-DIAMINODANISOLE	615-05-4								6.6E-06	2.3E-02	4/99		1
2,4-DIAMINOTOLUENE	95-80-7								1.1E-03	4.0E+00	4/99		1
1,2-DIBROMO-3-CHLOROPROPANE (DBCP)	96-12-8								2.0E-03	7.0E+00	4/99		1
p-DICHLOROBENZENE	106-46-7			8.0E+02	1/01				1.1E-05	4.0E-02	4/99		1
3,3-DICHLOROBENZIDINE	91-94-1								3.4E-04	1.2E+00	4/99		1
1,1-DICHLOROETHANE (Ethylene dichloride)	75-34-3								1.6E-06	5.7E-03	4/99		1
1,1-DICHLOROETHYLENE ... (see Vinylidene Chloride)													
DI(2-ETHYLHEXYL)PHTHALATE (DEHP)	117-81-7								2.4E-06	8.4E-03	4/99	8.4E-03	10/00
DIESEL EXHAUST ... (see Particulate Emissions from Diesel-Fueled Engines)													
DIETHANOLAMINE	111-42-2			3.0E+00	12/01								
p-DIMETHYLAMINOAZOBENZENE	60-11-7								1.3E-03	4.6E+00	4/99		1
N,N-DIMETHYL FORMAMIDE	68-12-2			8.0E+01	1/01								1
2,4-DINITROTOLUENE	121-14-2								8.9E-05	3.1E-01	4/99		1
1,4-DIOXANE	123-91-1	3.0E+03	4/99	3.0E+03	4/00				7.7E-06	2.7E-02	4/99		1
EPICHLOROHYDRIN (1-Chloro-2,3-epoxypropane)	106-89-8	1.3E+03	4/99	3.0E+00	1/01				2.3E-05	8.0E-02	4/99		1
1,2-EPOXYBUTANE	106-88-7			2.0E+01	1/01								1
ETHYL BENZENE	100-41-4			2.0E+03	2/00				2.5E-06	8.7E-3	11/07		1
ETHYL CHLORIDE (Chloroethane)	75-00-3			3.0E+04	4/00								1
ETHYLENE DIBROMIDE ^{TAC} (1,2-Dibromoethane)	106-93-4			8.0E-01	12/01				7.1E-05 ^{TAC}	2.5E-01	7/85		1
ETHYLENE DICHLORIDE ^{TAC} (1,2-Dichloroethane)	107-06-2			4.0E+02	1/01				2.1E-05 ^{TAC}	7.2E-02	9/85		1
ETHYLENE GLYCOL	107-21-1			4.0E+02	4/00								1
ETHYLENE GLYCOL BUTYL ETHER ... (see Glycol ethers)													

Table 1
CONSOLIDATED TABLE OF OEHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES°

CONSOLIDATED TABLE OF OLIMPIADAP APPROVED RISK ASSESSMENT HEALTH VALUES															
Substance	Chemical Abstract Number	Noncancer Effects							Cancer Risk						
		Acute Inhalation (µg/m ³)	Date Value Reviewed [Added]	8-Hour Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Oral (mg/kg-d)	Date Value Reviewed [Added]	Inhalation Unit Risk (µg/m ³) ⁻¹	Inhalation Cancer Potency Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	Oral Slope Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	M* W A F
ETHYLENE OXIDE ^{TAC} (1,2-Epoxyethane)	75-21-8					3.0E+01	1/01			8.8E-05 ^{TAC}	3.1E-01	11/87			1
ETHYLENE THIOUREA Fluorides	96-45-7 1101	2.4E+02	4/99			1.3E+01	8/03	4.0E-02	8/03	1.3E-05	4.5E-02	4/99			1
HYDROGEN FLUORIDE (Hydrofluoric acid)	7664-39-3	2.4E+02	4/99			1.4E+01	8/03	4.0E-02	8/03						1
FORMALDEHYDE ^{TAC}	50-00-0	5.5E+01	12/08	9.0E+00	12/08	9.0E+00	12/08			6.0E-06 ^{TAC}	2.1E-02	3/92			1
GLUTARALDEHYDE	111-30-8					8.0E-02	1/01								1
GLYCOL ETHERS	1115														1
ETHYLENE GLYCOL BUTYL ETHER – EGBE	111-76-2	1.4E+04	4/99												1
ETHYLENE GLYCOL ETHYL ETHER – EGEE	110-80-5	3.7E+02	4/99[1/92]			7.0E+01	2/00								1
ETHYLENE GLYCOL ETHYL ETHER ACETATE – EGEEA	111-15-9	1.4E+02	4/99			3.0E+02	2/00								1
ETHYLENE GLYCOL METHYL ETHER – EGME	109-86-4	9.3E+01	4/99			6.0E+01	2/00								1
ETHYLENE GLYCOL METHYL ETHER ACETATE – EGMEA	110-49-6					9.0E+01	2/00								1
HEXACHLOROBENZENE	118-74-1									5.1E-04	1.8E+00	4/99 [1/91]			1
HEXACHLOROCYCLOHEXANES (mixed or technical grade)	608-73-1									1.1E-03	4.0E+00	4/99 [1/91]	4.0E+00	10/00 [1/92]	1
alpha- HEXACHLOROCYCLOHEXANE	319-84-6									1.1E-03	4.0E+00	4/99 [1/91]	4.0E+00	10/00 [1/92]	1
beta- HEXACHLOROCYCLOHEXANE	319-85-7									1.1E-03	4.0E+00	4/99 [1/91]	4.0E+00	10/00 [1/92]	1
gamma- HEXACHLOROCYCLOHEXANE (Lindane)	58-89-9									1.1E-03	4.0E+00	4/99 [1/91]	4.0E+00	10/00 [1/92]	1
n-HEXANE	110-54-3									3.1E-04	1.1E+00	4/99	1.1E+00	10/00	1
HYDRAZINE	302-01-2					7.0E+03	4/00								1
HYDROCHLORIC ACID (Hydrogen chloride)	7647-01-0	2.1E+03	4/99			2.0E-01	1/01			4.9E-03	1.7E+01	4/99 [7/90]			1
HYDROGEN BROMIDE ... (see Bromine & Compounds)						9.0E+00	2/00								1
HYDROGEN CYANIDE ... (see Cyanide & Compounds)															
HYDROGEN FLUORIDE ... (see Fluorides & Compounds)															

Table 1
CONSOLIDATED TABLE OF OEHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES*

CONDENSED TABLE OF ULTIMATE RISK ASSESSMENT REALITY VALUES															
Substance	Chemical Abstract Number	Noncancer Effects						Cancer Risk							
		Acute Inhalation (µg/m ³)	Date Value Reviewed [Added]	8-Hour Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Oral (mg/kg-d)	Date Value Reviewed [Added]	Inhalation Unit Risk (µg/m ³) ⁻¹	Inhalation Cancer Potency Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	Oral Slope Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	M* W A F
HYDROGEN SELENIDE ... (see Selenium & Compounds)															
HYDROGEN SULFIDE	7783-06-4	4.2E+01	4/99[7/90]			1.0E+01	4/00								1
ISOPHORONE	78-59-1					2.0E+03	12/01								
ISOPROPYL ALCOHOL (Isopropanol)	67-63-0	3.2E+03	4/99			7.0E+03	2/00								1
LEAD AND COMPOUNDS ^{TAC,†*} (inorganic) values also apply to:	7439-92-1 1128 [1130]									1.2E-05 _{TAC}	4.2E-02	4/97	8.5E-03	10/00	1
Lead acetate	301-04-2									1.2E-05 _{TAC}	4.2E-02	4/97	8.5E-03	10/00	0.637
Lead phosphate	7446-27-7									1.2E-05 _{TAC}	4.2E-02	4/97	8.5E-03	10/00	0.7659
Lead subacetate	1335-32-6									1.2E-05 _{TAC}	4.2E-02	4/97	8.5E-03	10/00	0.7696
LINDANE ... (see gamma-Hexachlorocyclohexane)															
MALEIC ANHYDRIDE	108-31-6					7.0E-01	12/01								1
MANGANESE AND COMPOUNDS	7439-96-5 [1132]			1.7E-01	12/08	9.0E-02	12/08								1
MERCURY AND COMPOUNDS (INORGANIC)	7439-97-6 [1133]	6.0E-01	12/08	6.0E-02	12/08	3.0E-02	12/08	1.6E-04	12/08						1
Mercuric chloride	7487-94-7	6.0E-01	12/08	6.0E-02	12/08	3.0E-02	12/08	1.6E-04	12/08						1
METHANOL	67-56-1	2.8E+04	4/99			4.0E+03	4/00								1
METHYL BROMIDE (Bromomethane)	74-83-9	3.9E+03	4/99			5.0E+00	2/00								1
METHYL tertiary-BUTYL ETHER	1634-04-4					8.0E+03	2/00			2.6E-07	1.8E-03	11/99			1
METHYL CHLOROFORM (1,1,1-Trichloroethane)	71-55-6	6.8E+04	4/99			1.0E+03	2/00								1
METHYL ETHYL KETONE (2-Butanone)	78-93-3	1.3E+04	4/99												1
METHYL ISOCYANATE	624-83-9					1.0E+00	12/01								1
METHYL MERCURY ... (see Mercury & Compounds)															
4,4'-METHYLENE BIS (2-CHLOROANILINE) (MOCA)	101-14-4									4.3E-04	1.5E+00	4/99			1
METHYLENE CHLORIDE ^{TAC} (Dichloromethane)	75-09-2	1.4E+04	4/99			4.0E+02	2/00			1.0E-06 _{TAC}	3.5E-03	7/89			1
4,4'-METHYLENE DIANILINE (AND ITS DICHLORIDE)	101-77-9					2.0E+01	12/01			4.6E-04	1.6E+00	4/99	1.6E+00	10/00	1
METHYLENE DIPHENYL ISOCYANATE	101-68-8					7.0E-01	1/01								1
MICHLER'S KETONE (4,4'-Bis(dimethylamino)benzophenone)	90-94-8									2.5E-04	8.6E-01	4/99			1
N-NITROSODI-n-BUTYLAMINE	924-16-3									3.1E-03	1.1E+01	4/99 [1/92]			1

Table 1
CONSOLIDATED TABLE OF OEHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES*

Substance	Chemical Abstract Number	Noncancer Effects						Cancer Risk							
		Acute Inhalation (µg/m ³)	Date Value Reviewed [Added]	8-Hour Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Oral (mg/kg-d)	Date Value Reviewed [Added]	Inhalation Unit Risk (µg/m ³) ⁻¹	Inhalation Cancer Potency Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	Oral Slope Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	M* W A F
N-NITROSODI-n-PROPYLAMINE	621-64-7									2.0E-03	7.0E+00	4/99 [1/91]			1
N-NITROSODIETHYLAMINE	55-18-5									1.0E-02	3.6E+01	4/99 [1/91]			1
N-NITROSODIMETHYLAMINE	62-75-9									4.6E-03	1.6E+01	4/99 [1/91]			1
N-NITROSODIPHENYLAMINE	86-30-6									2.6E-06	9.0E-03	4/99 [1/91]			1
N-NITROSO-N-METHYLETHYLAMINE	10595-95-6									6.3E-03	2.2E+01	4/99 [7/90]			1
N-NITROSOMORPHOLINE	59-89-2									1.9E-03	6.7E+00	4/99 [7/92]			1
N-NITROSOPIPERIDINE	100-75-4									2.7E-03	9.4E+00	4/99 [7/92]			1
N-NITROSOPIRROLIDINE	930-55-2									6.0E-04	2.1E+00	4/99 [7/90]			1
NAPHTHALENE ... (see Polycyclic aromatic hydrocarbons) NICKEL AND COMPOUNDS ^{TAC} values also apply to:	7440-02-0 [1145]	6.0E+00	4/99			5.0E-02	2/00	5.0E-02	10/00	2.6E-04 ^{TAC}	9.1E-01	8/91			1
Nickel acetate	373-02-4	6.0E+00	4/99			5.0E-02	2/00	5.0E-02	10/00	2.6E-04 ^{TAC}	9.1E-01	8/91			0.3321
Nickel carbonate	3333-67-3	6.0E+00	4/99			5.0E-02	2/00	5.0E-02	10/00	2.6E-04 ^{TAC}	9.1E-01	8/91			0.4945
Nickel carbonyl	13463-39-3	6.0E+00	4/99			5.0E-02	2/00	5.0E-02	10/00	2.6E-04 ^{TAC}	9.1E-01	8/91			0.3438
Nickel hydroxide	12054-48-7	6.0E+00	4/99			5.0E-02	2/00	5.0E-02	10/00	2.6E-04 ^{TAC}	9.1E-01	8/91			0.6332
Nickelocene	1271-28-9	6.0E+00	4/99			5.0E-02	2/00	5.0E-02	10/00	2.6E-04 ^{TAC}	9.1E-01	8/91			0.4937
NICKEL OXIDE Nickel refinery dust from the pyrometallurgical process	1313-99-1 1146	6.0E+00 6.0E+00	4/99 4/99			1.0E-01 5.0E-02	2/00 2/00	5.0E-02 5.0E-02	10/00 10/00	2.6E-04 ^{TAC} 2.6E-04 ^{TAC}	9.1E-01 9.1E-01	8/91 8/91			1 0.7859
Nickel subsulfide	12035-72-2	6.0E+00	4/99			5.0E-02	2/00	5.0E-02	10/00	2.6E-04 ^{TAC}	9.1E-01	8/91			0.2443
NITRIC ACID	7697-37-2	8.6E+01	4/99												1
NITROGEN DIOXIDE	10102-44-0	4.7E+02	4/99[1/92]												1
p-NITROSODIPHENYLAMINE	156-10-5									6.3E-06	2.2E-02	4/99			1
OZONE	10028-15-6	1.8E+02	4/99[1/92]												1
PARTICULATE EMISSIONS FROM DIESEL-FUELED ENGINES ^{TAC} [1]	9901					5.0E+00 ^{TAC}	8/98			3.0E-04 ^{TAC}	1.1E+00	8/98			1
PENTACHLOROPHENOL ... (see Chlorophenols)															

Table 1
CONSOLIDATED TABLE OF OEHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES*

CONSOLIDATED TABLE OF OLIMPIRADAR APPROVED RISK ASSESSMENT HEALTH VALUES															
Substance	Chemical Abstract Number	Noncancer Effects						Cancer Risk							
		Acute Inhalation (µg/m ³)	Date Value Reviewed [Added]	8-Hour Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Oral (mg/kg-d)	Date Value Reviewed [Added]	Inhalation Unit Risk (µg/m ³) ⁻¹	Inhalation Cancer Potency Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	Oral Slope Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	M* W A F
PERCHLOROETHYLENE ^{TAC} (Tetrachloroethylene)	127-18-4	2.0E+04	4/99			3.5E+01 ^{TAC}	10/91			5.9E-06 ^{TAC}	2.1E-02	10/91			1
PHENOL	108-95-2	5.8E+03	4/99			2.0E+02	4/00								1
PHOSGENE	75-44-5	4.0E+00	4/99												1
PHOSPHINE	7803-51-2					8.0E-01	9/02								1
PHOSPHORIC ACID	7664-38-2					7.0E+00	2/00								1
PTHALIC ANHYDRIDE	85-44-9					2.0E+01	1/01								1
PCB (POLYCHLORINATED BIPHENYLS) (unspiculated mixture) [lowest risk] ☼	1336-36-3									2.0E-05	7.0E-02	4/99	7.0E-02	10/00	1
PCB (POLYCHLORINATED BIPHENYLS) (unspiculated mixture) [low risk] ☼	1336-36-3									1.1E-04	4.0E-01*		4.0E-01*		1
PCB (POLYCHLORINATED BIPHENYLS) (unspiculated mixture) [high risk] ☼	1336-36-3									5.7E-04	2.0E+00	4/99	2.0E+00	10/00	1
PCB (POLYCHLORINATED BIPHENYLS) (speciated) ☼															
3,3',4,4'-TETRACHLOROBIPHENYL (PCB 77)	32598-13-3					4.0E-01	8/03	1.0E-04	8/03	3.8E-03	1.3E+01	8/03	1.3E+01	8/03	1
3,4,4',5'-TETRACHLOROBIPHENYL (PCB 81)	70362-50-4					4.0E-01	8/03	1.0E-04	8/03	3.8E-03	1.3E+01	8/03	1.3E+01	8/03	1
2,3,3',4,4'-PENTACHLOROBIPHENYL (PCB 105)	32598-14-4					4.0E-01	8/03	1.0E-04	8/03	3.8E-03	1.3E+01	8/03	1.3E+01	8/03	1
2,3,4,4',5'-PENTACHLOROBIPHENYL (PCB 114)	74472-37-0					8.0E-02	8/03	2.0E-05	8/03	1.9E-02	6.5E+01	8/03	6.5E+01	8/03	1
2,3',4,4',5'-PENTACHLOROBIPHENYL (PCB 118)	31508-00-6					4.0E-01	8/03	1.0E-04	8/03	3.8E-03	1.3E+01	8/03	1.3E+01	8/03	1
2,3',4,4',5'-PENTACHLOROBIPHENYL (PCB 123)	65510-44-3					4.0E-01	8/03	1.0E-04	8/03	3.8E-03	1.3E+01	8/03	1.3E+01	8/03	1
3,3',4,4',5'-PENTACHLOROBIPHENYL (PCB 126)	57465-28-8					4.0E-04	8/03	1.0E-07	8/03	3.8E+00	1.3E+04	8/03	1.3E+04	8/03	1
2,3,3',4,4',5'-HEXACHLOROBIPHENYL (PCB 156)	38380-08-4					8.0E-02	8/03	2.0E-05	8/03	1.9E-02	6.5E+01	8/03	6.5E+01	8/03	1
2,3,3',4,4',5'-HEXACHLOROBIPHENYL (PCB 157)	69782-90-7					8.0E-02	8/03	2.0E-05	8/03	1.9E-02	6.5E+01	8/03	6.5E+01	8/03	1

Table 1
CONSOLIDATED TABLE OF OEHHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES^a

CONSOLIDATED TABLE OF ULTIMATE APPROVED RISK ASSESSMENT HEALTH VALUES															
Substance	Chemical Abstract Number	Noncancer Effects						Cancer Risk							
		Acute Inhalation (ug/m ³)	Date Value Reviewed [Added]	8-Hour Inhalation (ug/m ³)	Date Value Reviewed [Added]	Chronic Inhalation (ug/m ³)	Date Value Reviewed [Added]	Chronic Oral (mg/kg-d)	Date Value Reviewed [Added]	Inhalation Unit Risk (ug/m ³) ⁻¹	Inhalation Cancer Potency Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	Oral Slope Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	M W A F
2,3',4,4',5,5'-HEXACHLOROBIPHENYL (PCB 167)	52663-72-6					4.0E+00	8/03	1.0E-03	8/03	3.8E-04	1.3E+00	8/03	1.3E+00	8/03	1
3,3',4,4',5,5'-HEXACHLOROBIPHENYL (PCB 169)	32774-16-6					4.0E-03	8/03	1.0E-06	8/03	3.8E-01	1.3E+03	8/03	1.3E+03	8/03	1
2,3',4,4',5,5'-HEPTACHLOROBIPHENYL (PCB 189)	39635-31-9					4.0E-01	8/03	1.0E-04	8/03	3.8E-03	1.3E+01	8/03	1.3E+01	8/03	1
POLYCHLORINATED DIBENZO-P-DIOXINS (PCDD) (Treated as 2,3,7,8-TCDD for HRA) ^{TAC}	1085 1086					4.0E-05	2/00	1.0E-08	10/00	3.8E+01 TAC	1.3E+05	8/86	1.3E+05 TAC	8/86	1
2,3,7,8- ^{TAC} P-DIOXIN	1746-01-6					4.0E-05	2/00	1.0E-08	10/00	3.8E+01 TAC	1.3E+05	8/86	1.3E+05 TAC	8/86	1
1,2,3,7,8-PENTACHLORODIBENZO-P-DIOXIN	40321-76-4					4.0E-05	8/03	1.0E-08	8/03	3.8E+01	1.3E+05	8/03	1.3E+05	8/03	1
1,2,3,4,7,8-HEXACHLORODIBENZO-P-DIOXIN	39227-28-6					4.0E-04	2/00	1.0E-07	10/00	3.8E+00	1.3E+04	4/99	1.3E+04	10/00	1
1,2,3,6,7,8-HEXACHLORODIBENZO-P-DIOXIN	57653-85-7					4.0E-04	2/00	1.0E-07	10/00	3.8E+00	1.3E+04	4/99	1.3E+04	10/00	1
1,2,3,7,8,9-HEXACHLORODIBENZO-P-DIOXIN	19408-74-3					4.0E-04	2/00	1.0E-07	10/00	3.8E+00	1.3E+04	4/99	1.3E+04	10/00	1
1,2,3,4,6,7,8-HEPTACHLORODIBENZO-P-DIOXIN	35822-46-9					4.0E-03	2/00	1.0E-06	10/00	3.8E-01	1.3E+03	4/99	1.3E+03	10/00	1
1,2,3,4,6,7,8,9-OCTACHLORODIBENZO-P-DIOXIN	3268-87-9					4.0E-01	8/03	1.0E-04	8/03	3.8E-03	1.3E+01	8/03	1.3E+01	8/03	1
POLYCHLORINATED DIBENZOFURANS (PCDF) ^{TAC} (Treated as 2,3,7,8-TCDD for HRA)	1080					4.0E-05	2/00	1.0E-08	10/00	3.8E+01 TAC	1.3E+05	8/86	1.3E+05 TAC	8/86	1
2,3,7,8-TETRACHLORODIBENZOFURAN	5120-73-19					4.0E-04	2/00	1.0E-07	10/00	3.8E+00	1.3E+04	4/99	1.3E+04	10/00	1
1,2,3,7,8-PENTACHLORODIBENZOFURAN	57117-41-6					8.0E-04	2/00	2.0E-07	10/00	1.9E+00	6.5E+03	4/99	6.5E+03	10/00	1
2,3,4,7,8-PENTACHLORODIBENZOFURAN	57117-31-4					8.0E-05	2/00	2.0E-08	10/00	1.9E+01	6.5E+04	4/99	6.5E+04	10/00	1
1,2,3,4,7,8-HEXACHLORODIBENZOFURAN	70648-26-9					4.0E-04	2/00	1.0E-07	10/00	3.8E+00	1.3E+04	4/99	1.3E+04	10/00	1

Table 1
CONSOLIDATED TABLE OF OEHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES^o

CONSOLIDATED TABLE OF CERITAPAK EFFECTS RISK ASSESSMENT HEALTH VALUES															
Substance	Chemical Abstract Number	Noncancer Effects						Cancer Risk							
		Acute Inhalation (µg/m ³)	Date Value Reviewed [Added]	8-Hour Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Oral (mg/kg-d)	Date Value Reviewed [Added]	Inhalation Unit Risk (µg/m ³) ⁻¹	Inhalation Cancer Potency Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	Oral Slope Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	M W A F
1,2,3,6,7,8- HEXACHLORODIBENZOFURAN	57117-44-9					4.0E-04	2/00	1.0E-07	10/00	3.8E+00	1.3E+04	4/99	1.3E+04	10/00	1
1,2,3,7,8,9- HEXACHLORODIBENZOFURAN	72918-21-9					4.0E-04	2/00	1.0E-07	10/00	3.8E+00	1.3E+04	4/99	1.3E+04	10/00	1
2,3,4,6,7,8- HEXACHLORODIBENZOFURAN	60851-34-5					4.0E-04	2/00	1.0E-07	10/00	3.8E+00	1.3E+04	4/99	1.3E+04	10/00	1
1,2,3,4,6,7,8- HEPTACHLORODIBENZOFURAN	67562-39-4					4.0E-03	2/00	1.0E-06	10/00	3.8E-01	1.3E+03	4/99	1.3E+03	10/00	1
1,2,3,4,7,8,9- HEPTACHLORODIBENZOFURAN	55673-89-7					4.0E-03	2/00	1.0E-06	10/00	3.8E-01	1.3E+03	4/99	1.3E+03	10/00	1
1,2,3,4,6,7,8,9- OCTACHLORODIBENZOFURAN	39001-02-0					4.0E-01	8/03	1.0E-04	8/03	3.8E-03	1.3E+01	8/03	1.3E+01	8/03	1
POLYCYCLIC AROMATIC HYDROCARBON (PAH) ^o [Treated as B(a)P for HRA]	1150 1151									1.1E-03	3.9E+00	4/99 [4/94]	1.2E+01	10/00 [4/94]	1
BENZO(A)ANTHRACENE [*]	56-55-3									1.1E-04	3.9E-01	4/99 [4/94]	1.2E+00	10/00 [4/94]	1
BENZO(A)PYRENE [*]	50-32-8									1.1E-03	3.9E+00	4/99 [4/94]	1.2E+01	10/00 [4/94]	1
BENZO(B)FLUORANTHENE [*]	205-99-2									1.1E-04	3.9E-01	4/99 [4/94]	1.2E+00	10/00 [4/94]	1
BENZO(J)FLUORANTHENE [*]	205-82-3									1.1E-04	3.9E-01	4/99 [4/94]	1.2E+00	10/00 [4/94]	1
BENZO(K)FLUORANTHENE [*]	207-08-9									1.1E-04	3.9E-01	4/99 [4/94]	1.2E+00	10/00 [4/94]	1
CHRYSENE [*]	218-01-9									1.1E-05	3.9E-02	4/99 [4/94]	1.2E-01	10/00 [4/94]	1
DIBENZO(A,H)ACRIDINE [*]	226-36-8									1.1E-04	3.9E-01	4/99 [4/94]	1.2E+00	10/00 [4/94]	1
DIBENZO(A,H)ANTHRACENE [*]	53-70-3									1.2E-03	4.1E+00	4/99 [4/94]	4.1E+00	10/00 [4/94]	1
DIBENZO(A,J)ACRIDINE [*]	224-42-0									1.1E-04	3.9E-01	4/99 [4/94]	1.2E+00	10/00 [4/94]	1
DIBENZO(A,E)PYRENE [*]	192-65-4									1.1E-03	3.9E+00	4/99 [4/94]	1.2E+01	10/00 [4/94]	1
DIBENZO(A,H)PYRENE [*]	189-64-0									1.1E-02	3.9E+01	4/99 [4/94]	1.2E+02	10/00 [4/94]	1

Table 1
CONSOLIDATED TABLE OF OEHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES°

CONSOLIDATED TABLE OF ULTIMATE APPROVED RISK ASSESSMENT HEALTH VALUES															
Substance	Chemical Abstract Number	Noncancer Effects						Cancer Risk							
		Acute Inhalation (ug/m ³)	Date Value Reviewed [Added]	8-Hour Inhalation (ug/m ³)	Date Value Reviewed [Added]	Chronic Inhalation (ug/m ³)	Date Value Reviewed [Added]	Chronic Oral (mg/kg-d)	Date Value Reviewed [Added]	Inhalation Unit Risk (ug/m ³) ⁻¹	Inhalation Cancer Potency Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	Oral Slope Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	M* W A F
DIBENZO(A,I)PYRENE [*]	189-55-9									1.1E-02	3.9E+01	4/99 [4/94]	1.2E+02	10/00 [4/94]	1
DIBENZO(A,L)PYRENE [*]	191-30-0									1.1E-02	3.9E+01	4/99 [4/94]	1.2E+02	10/00 [4/94]	1
7H-DIBENZO(C,G)CARBAZOLE [*]	194-59-2									1.1E-03	3.9E+00	4/99 [4/94]	1.2E+01	10/00 [4/94]	1
7,12-DIMETHYLBENZ(A)ANTHRACENE [*]	57-97-6									7.1E-02	2.5E+02	4/99 [4/94]	2.5E+02	10/00 [4/94]	1
1,6-DINITROPYRENE [*]	42397-64-8									1.1E-02	3.9E+01	4/99 [4/94]	1.2E+02	10/00 [4/94]	1
1,8-DINITROPYRENE [*]	42397-65-9									1.1E-03	3.9E+00	4/99 [4/94]	1.2E+01	10/00 [4/94]	1
INDENO(1,2,3-C,D)PYRENE [*]	193-39-5									1.1E-04	3.9E-01	4/99 [4/94]	1.2E+00	10/00 [4/94]	1
3-METHYLCHOLANTHRENE [*]	56-49-5									6.3E-03	2.2E+01	4/99 [4/94]	2.2E+01	10/00 [4/94]	1
5-METHYLCHRYSENE [*]	3697-24-3									1.1E-03	3.9E+00	4/99 [4/94]	1.2E+01	10/00 [4/94]	1
NAPHTHALENE	91-20-3					9.0E+00	4/00			3.4E-05	1.2E-01	8/04			1
5-NITROACENAPHTHENE [*]	602-87-9									3.7E-05	1.3E-01	4/99 [4/94]	1.3E-01	10/00 [4/94]	1
6-NITROCHRYSENE [*]	7496-02-8									1.1E-02	3.9E+01	4/99 [4/94]	1.2E+02	10/00 [4/94]	1
2-NITROFLUORENE [*]	607-57-8									1.1E-05	3.9E-02	4/99 [4/94]	1.2E-01	10/00 [4/94]	1
1-NITROPYRENE [*]	5522-43-0									1.1E-04	3.9E-01	4/99 [4/94]	1.2E+00	10/00 [4/94]	1
4-NITROPYRENE [*]	57835-92-4									1.1E-04	3.9E-01	4/99 [4/94]	1.2E+00	10/00 [4/94]	1
POTASSIUM BROMATE..... ... (see Bromine & Compounds)															
1,3-PROPANE SULFONE	1120-71-4									6.9E-04	2.4E+00	4/99			1
PROPYLENE (PROPENE)	115-07-1					3.0E+03	4/00								1
PROPYLENE GLYCOL MONOMETHYL ETHER	107-98-2					7.0E+03	2/00								1
PROPYLENE OXIDE	75-56-9	3.1E+03	4/99			3.0E+01	2/00			3.7E-06	1.3E-02	4/99 [7/90]			1
SELENIUM AND COMPOUNDS	7782-49-2 [1170]					2.0E+01	12/01								1
HYDROGEN SELENIDE	7783-07-5	5.0E+00	4/99												1
Selenium sulfide	7446-34-6					2.0E+01	12/01								1

Table 1
CONSOLIDATED TABLE OF OEHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES^o

Substance	Chemical Abstract Number	Noncancer Effects						Cancer Risk					
		Acute Inhalation (µg/m ³)	Date Value Reviewed [Added]	8-Hour Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Inhalation (µg/m ³)	Date Value Reviewed [Added]	Inhalation Unit Risk (µg/m ³) ⁻¹	Inhalation Cancer Potency Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	Oral Slope Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	M* W A F
SILICA [CRYSTALLINE, RESPIRABLE]	1175												1
SODIUM HYDROXIDE	1310-73-2	8.0E+00	4/99			3.0E+00	2/05						1
STYRENE	100-42-5	2.1E+04	4/99			9.0E+02	4/00						1
SULFATES	9960	1.2E+02	4/99										1
SULFUR DIOXIDE	7446-09-5	6.6E+02	4/99 [192]										1
SULFURIC ACID AND OLEUM	9961	1.2E+02	4/99			1.0E+00	12/01						1
SULFURIC ACID	7664-93-9	1.2E+02	4/99			1.0E+00	12/01						1
SULFUR TRIOXIDE	7446-71-9	1.2E+02	4/99			1.0E+00	12/01						1
OLEUM	8014-95-7	1.2E+02	4/99			1.0E+00	12/01						1
1,1,2,2-TETRACHLOROETHANE	79-34-5							5.8E-05	2.0E-01	4/99			1
TETRACHLOROPHENOLS													
... (see Chlorophenols)													
2,4,5-TRICHLOROPHENOL													
... (see Chlorophenols)													
2,4,6-TRICHLOROPHENOL													
... (see Chlorophenols)													
THIOACETAMIDE	62-55-5												
TOLUENE	108-88-3	3.7E+04	4/99					1.7E-03	6.1E+00	4/99			1
<i>Toluene diisocyanates</i>	26471-62-5					3.0E+02	4/00						1
TOLUENE-2,4-DIISOCYANATE	584-84-9					7.0E-02	1/01	1.1E-05	3.9E-02	4/99			1
TOLUENE-2,6-DIISOCYANATE	91-08-7					7.0E-02	1/01	1.1E-05	3.9E-02	4/99			1
1,1,2-TRICHLOROETHANE (Vinyl trichloride)	79-00-5					7.0E-02	1/01	1.1E-05	3.9E-02	4/99			1
TRICHLOROETHYLENE ^{TAC}	79-01-6							1.6E-05	5.7E-02	4/99			1
TRIETHYLAMINE	121-44-8	2.8E+03	4/99			6.0E+02	4/00	2.0E-06 TAC	7.0E-03	10/90			1
URETHANE (Ethyl carbamate)	51-79-6					2.0E+02	9/02						1
<i>Vanadium Compounds</i>	N/A							2.9E-04	1.0E+00	4/99 [7/90]			1
<i>Vanadium (fume or dust)</i>	7440-62-2	3.0E+01	4/99										1
VANADIUM PENTOXIDE	1314-62-1	3.0E+01	4/99										1
VINYL ACETATE	108-05-4					2.0E+02	12/01						1
VINYL CHLORIDE ^{TAC} (Chloroethylene)	75-01-4	1.8E+05	4/99					7.8E-05 TAC	2.7E-01	12/90			1
VINYLDENE CHLORIDE (1,1-Dichloroethylene)	75-35-4					7.0E+01	1/01						1



Table 1
CONSOLIDATED TABLE OF OEHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES°

Substance	Chemical Abstract Number	Noncancer Effects							Cancer Risk						
		Acute Inhalation (µg/m ³)	Date Value Reviewed [Added]	8-Hour Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Oral (mg/kg-d)	Date Value Reviewed [Added]	Inhalation Unit Risk (µg/m ³) ⁻¹	Inhalation Cancer Potency Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	Oral Slope Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	M W A F
XYLENES (mixed isomers)	1330-20-7	2.2E+04	4/99				7.0E+02	4/00							1
m-XYLENE	108-38-3	2.2E+04	4/99				7.0E+02	4/00							1
o-XYLENE	95-47-6	2.2E+04	4/99				7.0E+02	4/00							1
p-XYLENE	106-42-3	2.2E+04	4/99				7.0E+02	4/00							1

Table 1
CONSOLIDATED TABLE OF OEHHHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES*

<p>Purpose: The purpose of this reference table is to provide a quick list of all health values that have been approved by the Office of Environmental Health Hazard Assessment (OEHHHA) and the Air Resources Board (ARB) for use in facility health risk assessments conducted for the AB 2588 Air Toxics Hot Spots Program. The OEHHHA has developed and adopted new risk assessment guidelines that update and replace the California Air Pollution Control Officers Association's (CAPCOA) Air Toxics "Hot Spots" Program Revised 1992 Risk Assessment Guidelines, October 1993. The OEHHHA has adopted four technical support documents for these guidelines, which can be found on their website (http://www.oehha.ca.gov/air/hot_spots/index.html). This table lists the OEHHHA adopted inhalation and oral cancer slope factors, noncancer acute Reference Exposure Levels (RELs), and inhalation and oral noncancer chronic RELs. OEHHHA is still in the process of adopting new health values. Therefore, new health values will periodically be added to, or deleted from, this table. Users of this table are advised to monitor the OEHHHA website (www.oehha.ca.gov) for any updates to the health values.</p> <p>May 2008 update: The Air Resources Board adopted amendments to the AB 2588 Air Toxics "Hot Spots" Emission Inventory Criteria and Guidelines Regulation (Title 17, California Code of Regulations, Section 93300.5) on November 16, 2006. The amendments became effective on September 26, 2007, after approval from the Office of Administrative Law. Under the new amendments, the substances previously listed in Appendix A-1 (Substances For Which Emissions Must Be Quantified) and Appendix F (Criteria For Inputs For Risk Assessment Using Screening Air Dispersion Modeling) of the ARB's Air Toxics "Hot Spots" Emission Inventory Criteria and Guidelines (EICG) (July 1997) have been removed from this table. Substances written in <i>italics</i> do not have explicit OEHHHA approved health values, but are included in this table to clarify applicability of OEHHHA adopted health effects values to individual or grouped substances listed in the Air Toxics "Hot Spots" Emission Inventory Criteria and Guidelines. Appendix A-1 list of "Substances For Which Emissions Must Be Quantified".</p>	<p>▼ Chemical Abstract Service Number (CAS): For chemical groupings and mixtures where a CAS number is not applicable, the 4-digit code used in the Air Toxics "Hot Spots" Emission Inventory Criteria and Guidelines (EICG) Report is listed. The 4-digit codes enclosed in brackets [] are codes that have been phased out, but may still appear on previously reported Hot Spots emissions. For information on the origin and use of the 4-digit code, see the EICG report.</p> <p>◆ Date Value Reviewed [Added]: These columns list the date that the health value was last reviewed by OEHHHA and the Scientific Review Panel, and/or approved for use by CAPCOA is listed within the brackets [].</p> <ul style="list-style-type: none"> • April 1999 is listed for the cancer potency values and noncancer acute RELs, which have been adopted by the OEHHHA as part of the AB 2588 Hot Spot Risk Assessment Guidelines. • February 2000, April 2000, January 2001, and December 2001 are listed for the first set of 22, the second set of 22, the third set of 16, the third set of 22, and the fourth set of 12 noncancer chronic RELs, respectively. The chronic REL for carbon disulfide was adopted in May 2002. Chronic RELs for phosphine and triethylamine were adopted in September 2002. Chronic RELs for fluorides including hydrogen fluoride were adopted August 2003. Chronic REL for silica [crystalline respirable] was adopted February 2005. • October 2000 is listed for the oral chronic RELs and oral cancer slope factors. • Cancer potency value adopted for naphthalene in August 2004. The inhalation and oral cancer potency values for ethyl benzene were adopted in November 2007. • For the substances identified as Toxic Air Contaminants, the Air Resources Board hearing date is listed. The dates for acetaldehyde, benzo[a]pyrene, and methyl tertiary-butyl ether represent the dates the values were approved by the Scientific Review Panel. • On December 19, 2008, OEHHHA adopted new acute, 8-hour, and chronic RELs for acetaldehyde, acrolein, arsenic, formaldehyde, and mercury. The most current health values can be found at: http://www.oehha.ca.gov/air/airtox.html. Note that the 8-hour RELs are not included in the HARP program. These health factors will be added after OEHHHA approves the Guidelines Manual (Part V). <p>Note: 1. OEHHHA presents the new oral RELs in micrograms (µg/kg-d) and we converted them to milligrams (mg/kg-d) for consistency.</p> <p>2. Acute RELs with longer averaging periods (i.e., 4-hour, 6-hour, and 7-hour) will now use the 1-hour averaging period. The affected chemicals are: arsenic & inorganic arsenic compounds, benzene, carbon disulfide, carbon tetrachloride, chloroform, ethylene glycol monoethyl ether, ethylene glycol dimethyl ether, and ethylene glycol monomethyl ether.</p> <p>3. At OEHHHA's direction, the chronic oral REL for arsenic does not apply to arsine because arsine is a gas and not particle associated.</p>	<p>* Inhalation cancer potency factor: The "unit risk factor" has been replaced in the new risk assessment algorithms by a factor called the "inhalation cancer potency factor". Inhalation cancer potency factors are expressed as units of inverse dose [i.e., (mg/kg-day)⁻¹]. They were derived from unit risk factors [units = (µg/m³)⁻¹] by assuming that a receptor weighs 70 kilograms and breathes 20 cubic meters of air per day. The inhalation potency factor is used to calculate a potential inhalation cancer risk using the new risk assessment algorithms defined in the OEHHHA, Air Toxics Hot Spots Program, Part IV, Technical Support Document for Exposure Assessment and Stochastic Analysis (September 2000).</p> <p>◆ Molecular Weight Adjustment Factor: Molecular weight adjustment factors (MWAFF) are only to be used when a toxic metal has a cancer potency factor. For most of the Hot Spots toxic metals, the OEHHHA cancer potency factor applies to the weight of the toxic metal atom contained in the overall compound. Some of the Hot Spots compounds contain various elements along with the toxic metal atom (e.g., "Nickel hydroxide", CAS number 12054-48-7, has a formula of H₂NiO₂). Therefore, an adjustment to the reported pounds of the overall compound is needed before applying the OEHHHA cancer potency factor for "Nickel and compounds" to such a compound. This ensures that the cancer potency factor is applied only to the fraction of the overall weight of the emissions that are associated with health effects of the metal. In other cases, the Hot Spots metals are already reported as the metal atom equivalent (e.g., CAS 7440-02-0, "Nickel"), and these cases do not use any further molecular weight adjustment. (Refer to Note [7] in Appendix A. List of Substances in the EICG Report for further information on how the emissions of various Hot Spots metal compounds are reported.) The appropriate molecular weight adjustment factors (MWAFF) to be used along with the OEHHHA cancer potency factors for Hot Spots metals can be found in the MWAFF column of this table.</p>	<p>So, for example, assume 100 pounds of "Nickel hydroxide" emissions are reported under CAS number 12054-48-7. To get the Nickel atom equivalent of these emissions, multiply by the listed MWAFF (0.6332) for Nickel hydroxide:</p> <ul style="list-style-type: none"> • 100 pounds x 0.6332 = 63.32 pounds of Nickel atom equivalent <p>This step should be completed prior to applying the OEHHHA cancer potency factor for "Nickel and compounds" in a calculation for a prioritization score or risk assessment calculation. (For more information see Chapter 8 of OEHHHA's document, The Air Toxics Hot Spots Program Guidance Manual for Preparation of Health Risk Assessments.)</p> <p>Note: The value listed in the MWAFF column for Asbestos is not a molecular weight adjustment. This is a conversion factor for adjusting mass to fibers or structures. See Appendix C of OEHHHA's document The Air Toxics Hot Spots Program Guidance Manual for Preparation of Health Risk Assessments for more information on Asbestos, or see the EICG report for reporting guidance. Also see the Asbestos footnote (designated by the symbol H)</p>
--	---	--	---

Table 1
CONSOLIDATED TABLE OF OEHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES°

N/A	Not Applicable
TAC	Toxic Air Contaminant: The Air Resources Board has identified this substance as a Toxic Air Contaminant.
H	Asbestos: The units for the Inhalation Cancer Potency factor for asbestos are (100 PCM fibers/m ³) ⁻¹ . A conversion factor of 100 fibers/0.003 µg can be multiplied by a receptor concentration of asbestos expressed in µg/m ³ . Unless other information necessary to estimate the concentration (fibers/m ³) of asbestos at receptors of interest is available. A unit risk factor of 1.9 E 10 ⁻⁴ (µg/m ³) ⁻¹ and an inhalation cancer potency factor of 2.2 E 10 ⁻² (mg/kg BW • day) ⁻¹ are available. For more information on asbestos quantity conversion factors, see Appendix C of OEHA's <i>The Air Toxics Hot Spots Program Risk Assessment Guidelines</i> ; Part II, <i>Technical Support Document for Describing Available Cancer Potency Factors</i> , and Appendix C of OEHA's document <i>The Air Toxics Hot Spots Program Guidance Manual for Preparation of Health Risk Assessments</i> .
Q	Hexavalent Chromium: The oral cancer slope factor for chromium 6+ and compounds has been withdrawn by the Office of Environmental Health Hazard Assessment.
	Inorganic Lead: Inorganic Lead was identified by the Air Resources Board as a Toxic Air Contaminant in April 1997. Since information on noncancer health effects show no identified threshold, no Reference Exposure Level has been developed. The document, <i>Risk Management Guidelines for New, Modified, and Existing Sources of Lead</i> , March 2001, has been developed by ARB and OEHA staff for assessing noncancer health impacts from sources of lead. See Appendix F of OEHA's document <i>The Air Toxics Hot Spots Program Guidance Manual for Preparation of Health Risk Assessments</i> for an overview of how to evaluate noncancer impacts from exposure to lead using these risk management guidelines.
Φ	Polycyclic Aromatic Hydrocarbons (PAHs): These substances are PAH or PAH-derivatives that have OEHA-developed Potency Equivalency Factors (PEFs) which were approved by the Scientific Review Panel in April 1994 (see ARB document entitled <i>Benzofluorene as a Toxic Air Contaminant</i>). PAH inhalation slope factors listed here have been adjusted by the PEFs. See Appendix G of OEHA's document <i>The Air Toxics Hot Spots Program Guidance Manual for Preparation of Health Risk Assessments</i> for more information. See section 8.2.3 of OEHA's <i>The Air Toxics Hot Spots Program Guidance Manual for Preparation of Health Risk Assessments</i> for conducting health risks when total (unspecified) PAHs are reported.
	Polychlorinated Biphenyls: (unspecified mixtures) Lowest Risk: For use in cases where congeners with more than four chlorines comprise less than one-half percent of total polychlorinated biphenyls. High Risk: For use in cases where congeners with more than four chlorines do not comprise less than one-half percent of total polychlorinated biphenyls. Low Risk: This number would not ordinarily be used in the Hot Spots program. Chronic Oral: The chronic oral value is U.S. EPA's 1996 oral Reference Dose for Aroclor-1254.
Q	Polychlorinated Biphenyls (specified): Values calculated using WHO ₉₇ TEF procedure. See OEHA memo dated August 29, 2003.
•	Polychlorinated Dibenzop-dioxins and Polychlorinated Dibenzofurans (also referred to as chlorinated dioxins and dibenzofurans): The OEHA has adopted the World Health Organization 1997 (WHO ₉₇) Toxicity Equivalency Factor scheme for evaluating the cancer risk due to exposure to samples containing mixtures of polychlorinated dibenzo-p-dioxins (PCDD) and polychlorinated dibenzofurans (PCDF) and determining cancer risks for a number of specific PCB congeners. See Appendix A of OEHA's <i>Technical Support Document For Describing Available Cancer Potency Factors</i> for more information about the scheme. See Appendix E of OEHA's <i>The Air Toxics Hot Spots Program Guidance Manual for Preparation of Health Risk Assessments</i> for the methodology for calculating 2,3,7,8-equivalents for PCDD, PCDFs and a number of specific PCB congeners. See section 8.2.3 of OEHA's <i>The Air Toxics Hot Spots Program Guidance Manual for Preparation of Health Risk Assessments</i> for conducting health risks when total (unspecified) chlorinated dioxins and furans are reported.
¶	Particulate Emissions from Diesel-Fueled Engines: The inhalation cancer potency factor and chronic REL were derived from whole diesel exhaust and should be used only for impacts from the inhalation pathway. The inhalation impacts from speciated emissions from diesel-fueled engines are already accounted for in the inhalation cancer potency factor and REL. However, at the discretion of the risk assessor, speciated emissions from diesel-fueled engines may be used to estimate acute noncancer health impacts or the contribution to cancer risk for the non-inhalation exposure pathway. See Appendix D of OEHA's document <i>The Air Toxics Hot Spots Program Guidance Manual for Preparation of Health Risk Assessments</i> for more information.

MSDS Number: B2347 ***** Effective Date: 11/17/99 ***** Supercedes: 12/08/96

MSDS **Material Safety Data Sheet**

From: Mallinckrodt Baker, Inc.
222 Red School Lane
Phillipsburg, NJ 08865

MBI

All non-emergency questions should be directed to Customer Service (1-800-582-2537) for assistance.

24 Hour Emergency Telephone: 908-859-2151
CHEMTREC: 1-800-424-9300
National Response in Canada
CANUTEC: 613-996-8666
Outside U.S. And Canada
Chemtrec: 703-527-3887

NOTE: CHEMTREC, CANUTEC and National Response Center emergency numbers to be used only in the event of chemical emergencies involving a spill, leak, fire, exposure or accident involving chemicals.

BIPHENYL

1. Product Identification

Synonyms: Diphenol; 1,1'biphenyl; phenylbenzene
CAS No.: 92-52-4
Molecular Weight: 154.21
Chemical Formula: C12H10

2. Composition/Information on Ingredients

Ingredient	CAS No	Percent	Hazardous
Biphenyl	92-52-4	90 - 100%	Yes

3. Hazards Identification

Emergency Overview

WARNING! HARMFUL IF SWALLOWED, INHALED OR ABSORBED THROUGH SKIN. CAUSES IRRITATION TO SKIN, EYES AND RESPIRATORY TRACT. MAY AFFECT LIVER, CENTRAL AND PERIPHERAL NERVOUS SYSTEMS. MAY CAUSE ALLERGIC SKIN REACTION.

Potential Health Effects

Inhalation:

Inhalation of dust or vapors can irritate the mucous membranes and respiratory tract. Other symptoms may parallel those from ingestion exposure.

Ingestion:

Exerts toxic effects on the central nervous system and liver. Symptoms may include headache, diffuse gastro-intestinal pain, nausea, numbness, body aches, and general fatigue.

Skin Contact:

May cause irritation. May be absorbed through the skin with symptoms paralleling those from ingestion exposure. May cause allergic reaction in sensitive individuals.

Eye Contact:

Vapors and dust cause eye irritation.

Chronic Exposure:

Chronic exposure may cause peripheral nerve damage and liver injury.

Aggravation of Pre-existing Conditions:

No information found.

4. First Aid Measures

Inhalation:

Remove to fresh air. If not breathing, give artificial respiration. If breathing is difficult, give oxygen. Get medical attention.

Ingestion:

Induce vomiting immediately as directed by medical personnel. Never give anything by mouth to an unconscious person. Get medical attention.

Skin Contact:

Immediately flush skin with plenty of soap and water for at least 15 minutes while removing contaminated clothing and shoes. Get medical attention. Wash clothing before reuse. Thoroughly clean shoes before reuse.

Eye Contact:

Immediately flush eyes with plenty of water for at least 15 minutes, lifting lower and upper eyelids occasionally. Get medical attention immediately.

5. Fire Fighting Measures

Fire:

Flash point: 113C (235F) CC

Autoignition temperature: 540C (1004F)

Flammable limits in air % by volume:

lcl: 0.6; ucl: 5.8

Explosion:

Above the flash point, explosive vapor-air mixtures may be formed. Fine dust dispersed in air in sufficient concentrations, and in the presence of an ignition source is a potential dust explosion hazard.

Fire Extinguishing Media:

Water spray, dry chemical, alcohol foam, or carbon dioxide. Water or foam may cause frothing.

Special Information:

In the event of a fire, wear full protective clothing and NIOSH-approved self-contained breathing apparatus with full facepiece operated in the pressure demand or other positive pressure mode.

6. Accidental Release Measures

Remove all sources of ignition. Ventilate area of leak or spill. Wear appropriate personal protective equipment as specified in Section 8. Spills: Clean up spills in a manner that does not disperse dust into the air. Use non-sparking tools and equipment. Reduce airborne dust and prevent scattering by moistening with water. Pick up spill for recovery or disposal and place in a closed container. US Regulations (CERCLA) require reporting spills and releases to soil, water and air in excess of reportable quantities. The toll free number for the US Coast Guard National Response Center is (800) 424-8802.

7. Handling and Storage

Keep in a tightly closed container, stored in a cool, dry, ventilated area. Protect against physical damage. Isolate from incompatible substances. Containers of this material may be hazardous when empty since they retain product residues (dust, solids); observe all warnings and precautions listed for the product.

8. Exposure Controls/Personal Protection

Airborne Exposure Limits:

-OSHA Permissible Exposure Limit (PEL):

0.2 ppm (TWA).

-ACGIH Threshold Limit Value (TLV):

0.2 ppm (TWA)

Ventilation System:

A system of local and/or general exhaust is recommended to keep employee exposures below the Airborne Exposure Limits. Local exhaust ventilation is generally preferred because it can control the emissions of the contaminant at its source, preventing dispersion of it into the general work area. Please refer to the ACGIH document, *Industrial Ventilation, A Manual of Recommended Practices*, most recent edition, for details.

Personal Respirators (NIOSH Approved):

If the exposure limit is exceeded and engineering controls are not feasible, a half-face respirator with an organic vapor cartridge and particulate filter (NIOSH type N95 or better filter) may be worn for up to ten times the exposure limit or the maximum use concentration specified by the appropriate regulatory agency or respirator supplier, whichever is lowest. A full-face piece respirator with an organic vapor cartridge and particulate filter (NIOSH N 100 filter) may be worn up to 50 times the exposure limit, or the maximum use concentration specified by the appropriate regulatory agency or respirator supplier, whichever is lowest. If oil particles (e.g. lubricants, cutting fluids, glycerine, etc.) are present, use a NIOSH type R or P particulate filter. For emergencies or instances where the exposure levels are not known, use a full-face piece positive-pressure, air-supplied respirator. WARNING: Air-purifying respirators do not protect workers in oxygen-deficient atmospheres.

Skin Protection:

Wear impervious protective clothing, including boots, gloves, lab coat, apron or coveralls, as appropriate, to prevent skin contact.

Eye Protection:

Use chemical safety goggles and/or full face shield where dusting or splashing of solutions is possible. Maintain eye wash fountain and quick-drench facilities in work area.

9. Physical and Chemical Properties

Appearance:

White crystals.

Odor:

Pleasant, peculiar odor.

Solubility:

Insoluble in water.

Specific Gravity:

1.041

pH:

No information found.

% Volatiles by volume @ 21C (70F):

0

Boiling Point:

254 - 255C (489 - 491F)

Melting Point:

69 - 70C (156 - 158F)

Vapor Density (Air=1):

5.31

Vapor Pressure (mm Hg):

0.005 @ 20.4C (68F)

Evaporation Rate (BuAc=1):

No information found.

10. Stability and Reactivity

Stability:

Stable under ordinary conditions of use and storage.

Hazardous Decomposition Products:

Carbon dioxide and carbon monoxide may form when heated to decomposition.

Hazardous Polymerization:

Will not occur.

Incompatibilities:

Strong oxidizers.

Conditions to Avoid:

Heat, flame, ignition sources, dusting and incompatibles.

11. Toxicological Information**Toxicological Data:**

Oral rat LD50 2400 mg/kg; Skin rabbit LD50: > 5010 mg/kg; Irritation (std Draize) rabbit: eye = 100 mg, mild. Investigated as a tumorigen and mutagen.

Carcinogenicity:

EPA / IRIS classification: Group D1 - Not classifiable as a human carcinogen.

-----\Cancer Lists\-----			
Ingredient	---NTP Carcinogen---		
	Known	Anticipated	IARC Category
Biphenyl (92-52-4)	No	No	None

12. Ecological Information**Environmental Fate:**

No information found.

Environmental Toxicity:

No information found.

13. Disposal Considerations

Whatever cannot be saved for recovery or recycling should be managed in an appropriate and approved waste disposal facility. Processing, use or contamination of this product may change the waste management options. State and local disposal regulations may differ from federal disposal regulations. Dispose of container and unused contents in accordance with federal, state and local requirements.

14. Transport Information**International (Water, I.M.O.)****Proper Shipping Name:** ENVIRONMENTALLY HAZARDOUS SUBSTANCES, SOLID, N.O.S. (DIPHENYL)**Hazard Class:** 9**UN/NA:** UN3077**Packing Group:** III**Information reported for product/size:** 1KG**International (Air, I.C.A.O.)****Proper Shipping Name:** ENVIRONMENTALLY HAZARDOUS SUBSTANCES, SOLID, N.O.S. (DIPHENYL)**Hazard Class:** 9**UN/NA:** UN3077**Packing Group:** III**Information reported for product/size:** 1KG**15. Regulatory Information**

-----\Chemical Inventory Status - Part 1\-----				
Ingredient	TSCA	EC	Japan	Australia
Biphenyl (92-52-4)	Yes	Yes	Yes	Yes

-----\Chemical Inventory Status - Part 2\-----				
Ingredient	Korea	--Canada--		
		DSL	NDSL	Phil.
Biphenyl (92-52-4)	Yes	Yes	No	Yes

-----\Federal, State & International Regulations - Part 1\-----				
Ingredient	-SARA 302-		-SARA 313-	
	RQ	TPQ	List	Chemical Catg.
Biphenyl (92-52-4)	No	No	Yes	No

-----\Federal, State & International Regulations - Part 2\-----			
Ingredient	CERCLA	-RCRA-	
		261.33	-TSCA- 8 (d)
Biphenyl (92-52-4)	100	No	No

Chemical Weapons Convention: No TSCA 12(b): No CDTA: Yes
 SARA 311/312: Acute: Yes Chronic: Yes Fire: No Pressure: No
 Reactivity: No (Pure / Solid)

Australian Hazchem Code: None allocated.

Poison Schedule: None allocated.

WHMIS:

This MSDS has been prepared according to the hazard criteria of the Controlled Products Regulations (CPR) and the MSDS contains all of the information required by the CPR.

16. Other Information

NFPA Ratings: Health: 2 Flammability: 1 Reactivity: 0

Label Hazard Warning:

WARNING! HARMFUL IF SWALLOWED, INHALED OR ABSORBED THROUGH SKIN. CAUSES IRRITATION TO SKIN, EYES AND RESPIRATORY TRACT. MAY AFFECT LIVER, CENTRAL AND PERIPHERAL NERVOUS SYSTEMS. MAY CAUSE ALLERGIC SKIN REACTION.

Label Precautions:

Avoid contact with eyes, skin and clothing.

Avoid breathing dust.

Keep container closed.

Use only with adequate ventilation.

Wash thoroughly after handling.

Label First Aid:

In case of contact, immediately flush eyes or skin with plenty of water for at least 15 minutes while removing contaminated clothing and shoes. Wash clothing before reuse. If inhaled, remove to fresh air. If not breathing, give artificial respiration. If breathing is difficult, give oxygen. If swallowed, induce vomiting immediately as directed by medical personnel. Never give anything by mouth to an unconscious person. In all cases, get medical attention.

Product Use:

Laboratory Reagent.

Revision Information:

MSDS Section(s) changed since last revision of document include: 8.

Disclaimer:

Mallinckrodt Baker, Inc. provides the information contained herein in good faith but makes no representation as to its comprehensiveness or accuracy. This document is intended only as a guide to the appropriate precautionary handling of the material by a properly trained person using this product. Individuals receiving the information must exercise their independent judgment in determining its appropriateness for a particular purpose. MALLINCKRODT BAKER, INC. MAKES NO REPRESENTATIONS OR WARRANTIES, EITHER EXPRESS OR IMPLIED, INCLUDING WITHOUT LIMITATION ANY WARRANTIES OF MERCHANTABILITY, FITNESS FOR A PARTICULAR PURPOSE WITH RESPECT TO THE INFORMATION SET FORTH HEREIN OR THE PRODUCT TO WHICH THE INFORMATION REFERS. ACCORDINGLY, MALLINCKRODT BAKER, INC. WILL NOT BE RESPONSIBLE FOR DAMAGES RESULTING FROM USE OF OR RELIANCE UPON THIS INFORMATION.

Prepared by: Environmental Health & Safety

Phone Number: (314) 654-1600 (U.S.A.)

Table C.4-6

CENSUS FINDINGS

<u>Map ID</u>	<u>Tract Number</u>	<u>Total Population</u>	<u>Population in Radius</u>	<u>Total Area(sq.mi.)</u>	<u>Area in Radius(sq.mi.)</u>
T1	0116.00	6151	505.2	1369.86	112.52

Table C.4-7 Three Highest MIR Locations and Risk Values

RECEPTORS WITH HIGHEST CANCER RISK

REC	TYPE	CANCER	CHRONIC	ACUTE	UTME	UTMN	ZONE
130	GRID	2.59E-07	2.08E-03	1.01E-02	469945	3874500	11
131	GRID	2.53E-07	1.68E-03	9.45E-03	469945	3874550	11
302	GRID	2.28E-07	1.53E-03	4.79E-03	473151	3873400	11

RECEPTORS WITH HIGHEST CHRONIC HI

REC	TYPE	CANCER	CHRONIC	ACUTE	UTME	UTMN	ZONE
130	GRID	2.59E-07	2.08E-03	1.01E-02	469945	3874500	11
131	GRID	2.53E-07	1.68E-03	9.45E-03	469945	3874550	11
302	GRID	2.28E-07	1.53E-03	4.79E-03	473151	3873400	11

RECEPTORS WITH HIGHEST ACUTE HI

REC	TYPE	CANCER	CHRONIC	ACUTE	UTME	UTMN	ZONE
130	GRID	2.59E-07	2.08E-03	1.01E-02	469945	3874500	11
113	GRID	1.23E-07	1.08E-03	1.01E-02	469919	3874450	11
112	GRID	1.68E-07	1.31E-03	9.86E-03	469919	3874500	11

Figure C.4-1
Census Tracts in Site Area




Figure C.4-2
6-Mile Radius Zone Map





Figure C.4-3
3 Highest Cancer MIR Locations



Construction Emissions and Impact Analysis

Construction Phases

Construction of MS1 is expected to last approximately 26 months. The construction will occur in the following four main phases:

- Site preparation;
- Foundation work;
- Construction/installation of major structures; and,
- Installation of major equipment.

Construction Schedule

The construction sequence for power plant construction includes the following general steps: (1) mobilization, (2) site preparation and grading, (3) foundation construction, (4) major equipment installation including the solar array field and offsite linears (if required), (5) balance of plant construction, (6) testing and commissioning.

The total site acreage is 1765 acres, with an additional 13 acres included in the site acreage to be disturbed during construction, bringing the total site acreage for purposes of construction to 1778 acres. The final site, i.e., acres inside the proposed fence line will be 1632 acres. The maximum acreage disturbed on any one day during construction will be 160 acres. The site is essentially flat. As such, the site will require moderate grading and leveling prior to construction of the power blocks, support systems, solar array field, and site buildings. Site preparation includes finish grading, excavation of footings and foundations, and backfilling operations. After site preparation is finished, the construction of the foundations and structures is expected to begin. Once the foundations and structures are finished, installation and assembly of the mechanical and electrical equipment are scheduled to commence.

Fugitive dust emissions from the construction of MS1 will result from:

- Dust entrained during site preparation and finish grading/excavation at the construction site;
- Dust entrained during offsite travel on paved and unpaved surfaces;
- Dust entrained during aggregate and soil loading and unloading operations; and
- Wind erosion of areas disturbed during construction activities.

Combustion emissions during construction will result from:

- Exhaust from the Diesel construction equipment used for site preparation, grading, excavation, and construction of onsite structures;
- Exhaust from water trucks used to control construction dust emissions;
- Exhaust from Diesel-powered welding machines, electric generators, air compressors, and water pumps;

- Exhaust from pickup trucks and Diesel trucks used to transport workers and materials around the construction site;
- Exhaust from Diesel trucks used to deliver concrete, fuel, and construction supplies to the construction site; and,
- Exhaust from automobiles used by workers to commute to the construction site.

To determine the potential worst-case daily construction impacts, exhaust and dust emission rates have been evaluated for each source of emissions. Worst-case daily dust emissions are expected to occur during the first months of construction when site preparation occurs. The worst-case daily exhaust emissions are expected to occur during the middle of the construction schedule during the installation of the major mechanical equipment. Annual emissions are based on the average equipment mix and use rates during the construction period. Daily emissions are derived from the annual values using the estimated construction time frame.

Available Mitigation Measures

The following mitigation measures are proposed to control exhaust emissions from the Diesel heavy equipment used during construction of MS1:

- The applicant will have an on-site construction mitigation manager who will be responsible for the implementation and compliance of the construction mitigation program. The documentation of the ongoing implementation and compliance with the proposed construction mitigations will be provided on a periodic basis.
- All unpaved roads and disturbed areas in the project and laydown construction sites will be watered as frequently as necessary to control fugitive dust. The frequency of watering will be on a minimum schedule of four (4) times during the daily construction activity period. Watering may be reduced or eliminated during periods of precipitation.
- Onsite vehicle speeds will be limited to <15 miles per hour on unpaved areas within the project construction site.
- The construction site entrance(s) will be posted with visible speed limit signs.
- All construction equipment vehicle tires will be inspected and cleaned as necessary to be free of dirt prior to leaving the construction site via paved roadways.
- Gravel ramps will be provided at the tire cleaning area.
- All unpaved exits from the construction site will be graveled or treated to reduce track-out to public roadways.
- All construction vehicles will enter the construction site through the treated entrance roadways, unless an alternative route has been provided.

- Construction areas adjacent to any paved roadway will be provided with sandbags or other similar measures as specified in the construction Storm Water Pollution Prevention Plan (SWPPP) to prevent runoff to roadways.
- All paved roads within the construction site will be cleaned on a periodic basis (or less during periods of precipitation), to prevent the accumulation of dirt and debris.
- The first 500 feet of any public roadway exiting the construction site will be cleaned on a periodic basis (or less during periods of precipitation), using wet sweepers or air filtered dry vacuum sweepers, when construction activity occurs or on any day when dirt or runoff from the construction site is visible on the public roadways.
- Any soil storage piles and/or disturbed areas that remains inactive for longer than 10 days will be covered, or shall be treated with appropriate dust suppressant compounds.
- All vehicles that are used to transport solid bulk material on public roadways and that have the potential to cause visible emissions will be covered, or the materials shall be sufficiently wetted and loaded onto the trucks in a manner to minimize fugitive dust emissions. A minimum freeboard height of two (2) feet will be required on all bulk materials transport.
- Wind erosion control techniques (such as windbreaks, water, chemical dust suppressants, and/or vegetation) will be used on all construction areas that may be disturbed. Any windbreaks installed to comply with this condition will remain in place until the soil is stabilized or permanently covered with vegetation.
- Disturbed areas will be re-vegetated as soon as practical.

To mitigate exhaust emissions from construction equipment, the applicant is proposing the following:

- The applicant will work with the construction contractor to utilize to the extent feasible, EPA-ARB Tier 2/Tier 3 engine compliant equipment for equipment over 100 horsepower.
- Insure periodic maintenance and inspections per the manufacturers specifications.
- Reduce idling time through equipment and construction scheduling.
- Use California low sulfur diesel fuels (≤ 15 ppmw S).

Estimation of Emissions with Mitigation Measures

Tables C.5-1 through C.5-3 show the estimated average daily and annual onsite heavy equipment exhaust and fugitive dust emissions with recommended mitigation measures. Detailed emission calculations are included in Table C.5-5.

TABLE C.5-1 AVERAGE DAILY ONSITE EMISSIONS DURING CONSTRUCTION, POUNDS PER DAY

	NO_x	CO	VOC	SO_x	PM10/PM2.5
Construction Fugitive Dust	0	0	0	0	883.92/185.62
Equipment and Vehicle Exhaust	80.13	40.56	12.2	0.26	5.00/4.90
Total =	80.13	40.6	12.2	0.26	888.92/190.52

TABLE C.5-2 AVERAGE ANNUAL ONSITE EMISSIONS DURING CONSTRUCTION, TONS PER YEAR

	NO_x	CO	VOC	SO_x	PM10/PM2.5
Construction Fugitive Dust	0	0	0	0	30.5/6.4
Equipment and Vehicle Exhaust	7.9	4.1	1.23	0.034	0.5/0.5
Total =	7.9	4.1	1.23	0.034	31.0/6.9

TABLE C.5-3 ANNUAL ONSITE EMISSIONS DURING CONSTRUCTION, TONS PER CONSTRUCTION PERIOD (26 MONTHS)

	NO_x	CO	VOC	SO_x	PM10/PM2.5
Construction Fugitive Dust	0	0	0	0	66.1/13.9
Equipment and Vehicle Exhaust	17.2	8.8	2.7	0.074	1.1/1.1
Total =	17.2	8.8	2.7	0.074	67.2/15.0

Analysis of Ambient Impacts from Facility Construction

Ambient air quality impacts from emissions during the construction of MS1 were estimated using an air quality dispersion modeling analysis. The modeling analysis considers the construction site location, the surrounding topography, and the sources of emissions during construction, including vehicle and equipment exhaust emissions and fugitive dust.

Existing Ambient Levels

As with the modeling analysis of project operating impacts (Section 5.2), monitoring stations delineated in Section 5.2 were used to establish the ambient background levels for the construction impact modeling analysis. Table 5.2-15 showed the maximum concentrations of NO_x, SO₂, CO, PM2.5 and PM10 recorded for 2006 through 2008 at those monitoring stations.

Dispersion Model

As in the analysis of project operating impacts, the USEPA-approved model AERMOD (version 07026) was used to estimate ambient impacts from construction activities. A detailed discussion of the AERMOD model and the associated processing programs AERSURFACE, AERMET, and AERMAP is included in Section 5.2.

The emission sources for the construction site were grouped into two categories: exhaust emissions and dust emissions. Combustion equipment exhaust emissions were modeled as

twenty-four (24) 3.048 meter high point sources (exhaust parameters of 750 Kelvin, 64.681 m/s velocity, and 0.1524m diameter) placed at regular 150-meter intervals around a 160-acre construction area (conservatively assumed to be the 80-acre area of the alpha power block and extending to the east, and an equivalent 80-acre area across the public roadway extending from the property fenceline to the west). Construction fugitive dust emissions were modeled as area sources covering the 160-acre construction area described above with an effective height of 0.5 meters. Combustion emissions were assumed to occur for 20 hours/day (3 AM to 11 PM) while fugitive dust emissions were assumed to be continuous (24 hours/day). The construction impacts modeling analysis generally used the same modeling options, receptor locations and meteorological data as used for the project operating impact analysis. Since maximum impacts due to fugitive emissions from construction activities are expected to occur at or near the property boundary, only the 50-meter spaced downwash and fenceline receptor grids were used for modeling construction impacts. Also, to reduce run times for the area sources modeled for fugitive dust and the large number of point sources modeled for mobile combustion source equipment, the TOXICS keyword was used for modeling construction impacts. A detailed discussion of the receptor locations and meteorological data is included in Section 5.2.

To determine the construction impacts on short-term ambient standards (24 hours and less), the estimated worst-case daily onsite construction emission levels shown in Table C.5-1 were used. For pollutants with annual average ambient standards, the annual onsite emission levels shown in Table C.5-2 were used.

Modeling Results

Based on the emission rates of NO_x, SO₂, CO, PM_{2.5}, and PM₁₀, the modeling options, receptor grids, and meteorological data, AERMOD calculates short-term and annual ambient impacts for each pollutant. As mentioned above, the modeled 1-hour, 3-hour 8-hour, and 24-hour ambient impacts are based on the worst-case daily emission rates of NO_x, SO₂, CO, PM_{2.5}, and PM₁₀ spread over the estimated daily hours of operation. The annual impacts are based on the annual emission rates of these pollutants.

The annual average concentrations of NO₂ were computed following the revised USEPA guidance for computing these concentrations (August 9, 1995 Federal Register, 60 FR 40465). The annual average was calculated using the ambient ratio method (ARM) with the national default value of 0.75 for the annual average NO₂/NO_x ratio.

The modeling analysis results are shown in Table C.5-4. Also included in the table are the maximum background levels that have occurred in the last three years and the resulting total ambient impacts.

TABLE C.5-4 MODELED MAXIMUM CONSTRUCTION IMPACTS

Pollutant	Averaging Time	Maximum Construction Impacts (µg/m ³)	Background (µg/m ³)	Total Impact (µg/m ³)	State Standard (µg/m ³)	Federal Standard (µg/m ³)
NO ₂ ^a	1-hour	12.5	154	166.5	339	-
	Annual	0.98	42	43.0	57	100
SO ₂	1-hour	0.041	94	94	655	-
	3-hour	0.039	23	23	-	1300
	24-hour	0.016	13	13	105	365

	Annual	0.006	3	3	-	80
CO	1-hour 8-hour	6.3 3.9	4025 1789	4031 1793	23,000 10,000	40,000 10,000
PM10	24-hour Annual ^b	436 23.8	154 38.4	590 62.2	50 20	150 -
PM2.5	24-hour Annual ^b	92 5.0	28 10.4	120 15.4	- 12	35 15.0

Notes:

^aARM applied for annual average, using national default 0.75 ratio.

^bAnnual Arithmetic Mean.

AAQS are only exceeded for fugitive dust emissions (PM10 and PM2.5). It should be noted that modeled MS1 construction impacts are not unusual in comparison to modeled fugitive dust impacts for most construction sites; in practice, construction sites that use good dust suppression techniques and low-emitting vehicles typically would not be expected to cause exceedances of ambient air quality standards. The input and output modeling files are being provided electronically to the appropriate agencies.

Attachment - Detailed Emission Calculations

Table C.5-5 Construction Emissions Calculations

Table C.5-6 Construction Equipment Schedules

Table C.5-7 Offsite Equipment and Construction Manpower Schedules

Table C.5-8 MDAB EMFAC Output

Table C.5-9 EMFAC Composite EF Calculations

Table C.5-10 Construction Impact Summary

Table C.5-5 Construction Emission Totals

Construction Activity Main Site	lbs/day				tons per const period				tons per year			
	NOx	CO	VOC	SOx	PM10	PM2.5	NOx	CO	VOC	SOx	PM10	PM2.5
Construction Equipment-Exhaust	79.9	38.0	12.0	0.1	5.00	4.90	17.1	8.1	2.60	0.10	1.06	1.05
Construction Site-Fugitive Dust	0.000	0.000	0.000	0.000	883.90	185.60	0.000	0.000	0.000	0.000	66.10	13.90
Construction Dust-Other	0.000	0.000	0.000	0.000	0.00	0.00	0.000	0.000	0.000	0.000	0.00	0.00
Site Delivery-Vehicle Exhaust	70.30	21.30	5.10	0.084	3.20	3.17	19.65	5.94	1.42	0.024	0.900	0.890
Site Support-Vehicle Exhaust	0.230	2.560	0.220	0.003	0.022	0.022	0.064	0.710	0.062	0.001	0.006	0.006
Worker Travel-Vehicle Exhaust	20.78	132.9	11.60	0.160	1.05	1.05	5.81	37.10	3.25	0.044	0.290	0.290
Track Out-Fugitive Dust	0.000	0.000	0.000	0.000	5.46	0.920	0.000	0.000	0.000	0.000	1.40	0.24
Unpaved Roads-Fugitive Dust	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Paved Roads-Fugitive Dust	0.000	0.000	0.000	0.000	0.780	0.020	0.000	0.000	0.000	0.000	0.200	0.010
<i>Offsite Linear Emissions are included in the above sector calculations, i.e., acreages, equipment types and use rates, schedules, etc.</i>												
TOTALS	171.2	194.8	28.9	0.3	899.4	195.7	42.6	51.9	7.33	0.17	69.96	16.39
Modeling Emissions	80.13	40.56	12.22	0.10	888.92	190.52	17.16	8.81	2.66	0.10	67.17	14.96

Total Const Months: 26

Total Const Years: 2.17

CONSTRUCTION EQUIPMENT EXHAUST EMISSIONS

Project: Mojave Solar One

Assumptions:

1. The average diesel engine employed in construction equipment use consumes fuel at a rate of:
Ref: EPA, NR-009b Publication, November 2002.
Ref: Sacramento County APCD Const. Program Data, V. 6.0.3, 3/2007.
Ref: EPA, NR-009c Publication, EPA 420-P-04-009, April 2004.
Ref: Niland Energy Project, IID, AFC Vol 2, App A.
Ref: South Coast AQMD PR XXI, Draft Staff Report, 3-15-95, and SCAQMD CEQA Manual, 11/03.
The above noted references present fuel consumption values which range from 0.050 to 0.064 gal/hp-hr for diesel engines used in construction related equipment. The value of 0.060 gal/hp-hr was chosen as a reasonable upper mid-range value for construction emissions calculations.

0.06 gal/hp-hr

2. Construction equipment exhaust emissions will be calculated on an annual basis using the site specific equipment list, HP ratings, hours of use, days of use, etc. Annual emissions will be apportioned to daily values based on the estimated construction period time on site.

3. The equipment list derived from the South Coast AQMD (12/2006) will be used to establish the various equipment categories. Data produced by the Sacramento APCD was used to establish the average HP ratings for each equipment category. HP rating data was supplemented by data from SCAQMD CEQA Handbook (Table A9-8-C) if not available from Sacramento APCD.

4. Construction Schedule:	20	hrs/day	Construction Totals:	430	hrs/month
	5	days/week		11180	hrs/const period
	21.5	days/month		559	days/const period
	26	months			

5. Anticipated Construction Start Year: 2010

Project supplied equipment list and use rates were consolidated into the following categories:
See Tables C.5-6 and C.5-7 for estimated HP values, use rates, etc.

Equipment Category	Avg HP	# of Units Used for Project	Avg Use Rate Hrs/day	# of Days On Site (each)	Total Hrs/Day	Total Hp-Hrs per Day	Total Hrs per Const Period	Total Hp-Hrs per Const Period
Bore/Drill Rigs/Pile Drivers	0	0	0	0	0	0	0	12000
Cement Mixers	0	0	0	0	0	0	0	448672
Industrial/Concrete Saws	0	0	0	0	0	0	0	0
Cranes	0	0	0	0	0	0	0	545600
Crawler Tractors/Dozers	0	0	0	0	0	0	0	0
Crushing/Processing Eq.	0	0	0	0	0	0	0	0
Dump and Tender Trucks	0	0	0	0	0	0	0	370800
Excavators	0	0	0	0	0	0	0	0
Forklifts/Aerial Lifts/Booms	0	0	0	0	0	0	0	2208500
Generators/Compressors	0	0	0	0	0	0	0	327200
Graders	0	0	0	0	0	0	0	1203460
Off Highway Tractors	0	0	0	0	0	0	0	434000
Off Highway Trucks	0	0	0	0	0	0	0	14500
Other Const. Eq.-Diesel	0	0	0	0	0	0	0	7450
Pavers	0	0	0	0	0	0	0	5000
Paving Eq./Surfacing Eq.	0	0	0	0	0	0	0	0
Plate Compactors	0	0	0	0	0	0	0	1236
Rollers/Compactors	0	0	0	0	0	0	0	0
Rough Terrain Forklifts	0	0	0	0	0	0	0	0
Rubber Tired Dozers	0	0	0	0	0	0	0	0
Rubber Tired Loaders	0	0	0	0	0	0	0	0
Scrapers	0	0	0	0	0	0	0	0
Signal Boards/Light Sets	0	0	0	0	0	0	0	0
Skid Steer Loaders	0	0	0	0	0	0	0	0
Tractors/Loaders/Backhoes	0	0	0	0	0	0	0	0
Trenchers	0	0	0	0	0	0	0	0
Welders	0	0	0	0	0	0	0	369250
Other Const. Eq.-Gasoline	0	0	0	0	0	0	0	20400

*includes equipment and use rates for proposed offsite linears.

Estimated Const Period Hp-Hrs 5968068

Estimated Const Period Fuel Use 358084 gals

Equip. Type	HP	2010 Equipment Emissions Factors					
		lbs/hp-hr CO	VOC lbs/hp-hr	NOx lbs/hp-hr	SOx lbs/hp-hr	PM10 lbs/hp-hr	
Bore/Drill Rigs/Pile Drivers	0	0.001400	0.000400	0.004700	0.000008	0.000200	
Cement Mixers	0	0.003800	0.001400	0.006500	0.000009	0.000400	
Industrial/Concrete Saws	0	0.006400	0.002500	0.006100	0.000008	0.000600	
Cranes	0	0.001400	0.000500	0.004900	0.000005	0.000200	
Crawler Tractors/Dozers	0	0.004300	0.001100	0.008500	0.000008	0.000500	
Crushing/Processing Eq.	0	0.002500	0.000900	0.010200	0.000011	0.000300	
Dump and Tender Trucks	0	0.001300	0.000400	0.002600	0.000004	0.000100	
Excavators	0	0.003800	0.000800	0.006400	0.000007	0.000400	
Forklifts/Aerial Lifts/Booms	0	0.002100	0.000600	0.003800	0.000004	0.000300	
Generators/Compressors	0	0.005800	0.002200	0.006100	0.000008	0.000600	
Graders	0	0.002000	0.000700	0.007200	0.000008	0.000300	
Off Highway Tractors	0	0.004900	0.001300	0.010100	0.000008	0.000600	
Off Highway Trucks	0	0.001500	0.000500	0.004600	0.000005	0.000200	
Other Const. Eq. -Diesel	0	0.005900	0.002100	0.005600	0.000007	0.000500	
Pavers	0	0.004400	0.001400	0.008100	0.000007	0.000700	
Paving Eq./Surfacing Eq.	0	0.006600	0.002800	0.005300	0.000006	0.000600	
Plate Compactors	0	0.001800	0.000300	0.002100	0.000004	0.000100	
Rollers/Compactors	0	0.003500	0.001000	0.006200	0.000006	0.000500	
Rough Terrain Forklifts	0	0.004200	0.000900	0.007400	0.000008	0.000400	
Rubber Tired Dozers	0	0.003500	0.000700	0.006400	0.000005	0.000300	
Rubber Tired Loaders	0	0.003600	0.000800	0.006600	0.000007	0.000400	
Scrapers	0	0.002900	0.001000	0.009900	0.000009	0.000400	
Signal Boards/Light Sets	0	0.002500	0.000500	0.003000	0.000006	0.000100	
Skid Steer Loaders	0	0.005000	0.001600	0.004900	0.000007	0.000400	
Tractors/Loaders/Backhoes	0	0.003000	0.000800	0.004700	0.000005	0.000400	
Trenchers	0	0.004000	0.001300	0.007600	0.000006	0.000600	
Welders	0	0.002300	0.000700	0.004100	0.000004	0.000400	
Other Const. Eq. -Gasoline	0.0	0.003300	0.000900	0.006500	0.000006	0.000400	

SCAQMD off-road emissions factor database, website, 12/2006. Load factor adjustments incorporated.
EFs are for equipment inventory year 2010.

Equip. Type	Construction Period Emissions, lbs					
	CO	VOC	NOx	SOx	PM10	PM2.5
Bore/Drill Rigs/Pile Drivers	17	5	56	0	2	
Cement Mixers	1705	628	2916	4	179	
Industrial/Concrete Saws	0	0	0	0	0	
Cranes	764	273	2673	3	109	
Crawler Tractors/Dozers	0	0	0	0	0	
Crushing/Processing Eq.	0	0	0	0	0	
Dump and Tender Trucks	482	148	964	1	37	
Excavators	0	0	0	0	0	
Forklifts/Aerial Lifts/Booms	4638	1325	8392	9	663	
Generators/Compressors	1898	720	1996	3	196	
Graders	2407	842	8665	10	361	
Off Highway Tractors	2127	564	4383	3	260	
Off Highway Trucks	22	7	67	0	3	
Other Const. Eq.-Diesel	44	16	42	0	4	
Pavers	22	7	41	0	4	
Paving Eq./Surfacing Eq.	0	0	0	0	0	
Plate Compactors	2	0	3	0	0	
Rollers/Compactors	0	0	0	0	0	
Rough Terrain Forklifts	0	0	0	0	0	
Rubber Tired Dozers	0	0	0	0	0	
Rubber Tired Loaders	0	0	0	0	0	
Scrapers	0	0	0	0	0	
Signal Boards/Light Sets	0	0	0	0	0	
Skid Steer Loaders	0	0	0	0	0	
Tractors/Loaders/Backhoes	0	0	0	0	0	
Trenchers	0	0	0	0	0	
Welders	849	258	1514	1	148	
Other Const. Eq.-Gasoline	1219	332	2400	2	148	
Totals	CO	VOC	NOx	SOx	PM10	PM2.5
	16194	5127	34112	37	2114	2095.00
	lbs per const. period	2.6	17.1	0.0	1.06	1.05
	tons per const. period	9.2	61.0	0.07	3.78	3.75
	Average lbs/day =	38.0	79.9	0.1	5.0	4.9
	Estimated Maximum lbs/day =	622.9	1312.0	1.4	81.31	80.58
	Average lbs/month =	3.74	7.87	0.01	0.49	0.48
	Average tons/year =					

CARB-CEIDARS, Updated Size Fractions for PM Profiles: PM2.5 = 0.991 of PM10 ; Diesel Vehicle Exhaust
CO2 EF: CCAR General Protocol, June 2006, for CA-Low Sulfur Diesel combustion.

	CO2
lbs per const period	7863526
tons per const period	3932

Other Assumptions and References:

1. Trench construction times per: Southern Regional Water Pipeline Alliance, 3/08.
Optimum trench construction progress rate is 80m (260ft) per day.
Non-optimum trench construction progress rate is 30m (100 ft) per day.
An average progress of 180 ft/day is used where applicable.
2. Paving speeds can range from 3 to 15 m/min depending on asphalt delivery rates and required compaction thickness.
A minimum paving speed of 3 m/min (10 ft/min or 600 ft/hr) is used where applicable.
The minimum speed is based upon a 3" compacted layer, 12 ft lane width, with an asphalt delivery rate of ~140 tons/hr.
Ref: Asphalt Paving Speed, Pavement Worktip No. 31, AAPA, 11/2001.
3. Estimation of maximum daily emissions is extremely variable. Some projects provide estimated manpower and equipment use schedules, but even this data usually leads to a wide range of assumptions being made in order to estimate equipment exhaust emissions for a maximum work day. The methodology used in this analysis assumes that the estimated maximum day represents the ratio of the number of pieces of equipment on site on any day during the maximum month as compared to the number of pieces of equipment on site on any day during an average month.

CONSTRUCTION PHASE-Main Project Site Fugitive Dust Emissions**MRI Level 2 Analysis**

Acres Subject to Construction Disturbance Activities:	1778	
Max Acres Subject to Construction Disturbance Activities on any day:	160	***
Emissions Factor for PM10 Uncontrolled, tons/acre/month:	0.0144	
PM2.5 fraction of PM10 (per CARB CEIDARS Profiles):	0.21	
Activity Levels:		
Hrs/Day:	20	
Days/Wk:	6	
Days/Month:	21.5	
Const Period, Months:	26	2.2 years
Const Period, Days:	559	
Wet Season Adjustment (Per AP-42, Section 13.2.2, Figure 13.2.2-1, 12/03)		
Mean # days/year with rain >= 0.01 inch:	30	
Mean # months/yr with rain >= 0.01 inch:	1	
Adjusted Const Period, Months:	23.83	
Adjusted Const Period, Days:	494	

Controls for Fugitive Dust:

Proposed watering schedule is every 3.2 Hours

SCAQMD Mitigation Measures, Table XI-A, 4/07

3.2 hour watering interval yields 61 % control of PM10/PM2.5

Speed control of onsite const traffic to <= 15 mph = 44 % control

Calculated % control based on mitigations proposed	78	% control
Conservative control % used for emissions estimate	78	% control
	0.22	release fraction

Emissions: Controlled	PM10	PM2.5
tons/month	0.507	0.106
tons/period	12.081	2.537
Max lbs/day	47.2	9.902

Cut and Fill Data:

Total cu/yds:	4158000	***
10^3 cu/yds:	4158	
MRI PM10 emissions factor, tons/1000 cu.yds:	0.059	
PM10 uncontrolled emissions, tons/period:	245.32	
Cut and Fill Activity Period, months:	6.0	
Cut and Fill Activity Period, days:	129.0	
PM10 Controlled Emissions:	tons/period	53.97
PM2.5 Controlled Emissions:	tons/period	11.33
PM10 Controlled Emissions:	tons/month	9.00
PM2.5 Controlled Emissions:	tons/month	1.89
PM10 Controlled Emissions:	max lbs/day	836.8
PM2.5 Controlled Emissions:	max lbs/day	175.7

Emissions Totals:	PM10	PM2.5
tons/period	66.1	13.9
tons/month	9.5	2.0
max lbs/day	883.9	185.6

Ref: MRI Report, South Coast AQMD Project No. 95040, March 1996, Level 2 Analysis Procedure.

MRI Report factor of 0.011 tons/acre/month is based on 168 hours per month of const activity.

For an activity rate of 220 hrs/month, the adjusted EF would be 0.0144 tons/acre/month.

*** includes surface area and trench cut and fill for proposed offsite linears.

PAVED ROAD FUGITIVE DUST EMISSIONS

(associated with construction traffic)

Length of Paved Road used for/by Construction Access: 1 miles, roundtrip distance***

Avg weight of vehicular equipment on road: 10.9 tons (range 2 - 42 tons)

Road surface silt loading factor: 0.06 g/m2 (range 0.03 - 400 g/m2)

Particle size multiplier factors:	PM10	0.016	lb/VMT
	PM2.5	0.0024	lb/VMT

C factors (brake and tire wear):	PM10	0.00047	lb/VMT
	PM2.5	0.00036	lb/VMT

Avg vehicle speed on road: 25 mph (range 10-55 mph)

Number of vehicles per day:	349	VMT/day: 349
		VMT/month: 7503.5
Number of construction work days per month:	21.5	VMT/period: 178808.4

Total vehicles per month: 7503.5

Number of construction work months: 23.83 after wet season adjustment*

Total vehicles per construction period: 178808.4

	PM10	PM2.5
Calc 1	0.060	0.060
Calc 2	2.807	2.807
Calc 3	0.002	0.0000

lb/VMT

Emissions	PM10	PM2.5
lbs/day	0.78	0.02
lbs/month	16.86	0.36
lbs/period	401.75	8.50
tons/period	0.20	0.00

* see main const dust site page for this value

EPA, AP-42, Section 13.2.1, March 2006, updated 9/2008.

*** Note: fugitive roadway emissions from construction traffic are based on the use of a 0.5 mile section of Harper Lake Rd. (paved). Harper Lake Rd extends from Hwy 58 to the site entrance, and is used by a number of entities. Allocation of emissions from the project traffic will be based on a 1 mile roundtrip adjacent to the project site.

CONSTRUCTION PHASE - Truck Delivery and Site Support Vehicle Emissions

Ref: MDAB, Emfac 2007, V2.3, Nov 2006
On-Road Heavy Duty Diesels (1966-2010)
On Road Medium Duty Gas (1996-2010)

Delivery Vehicle Use Rates		Emissions Factors (lbs/vmt)				
		NOx	CO	VOC	SOx	CO2
Const Days per Period:	559	0.03422	0.009532	0.002411	0.00004	0.001556
Const Period VMT Diesel:	1143800					4.04823
Avg Daily Diesel VMT:	2046	0.00202	0.01296	0.001125	0.000015	0.000098
Const Period VMT Gasoline:	75680					1.4488
Avg Daily Gasoline VMT:	135					
		Daily Emissions (lbs)				
		NOx	CO	VOC	SOx	CO2
		70.019	19.504	4.933	0.082	8283.301
		0.273	1.755	0.152	0.002	0.013
		Tons per Const Period				
		19.570	5.451	1.379	0.023	2315.183
		0.076	0.490	0.043	0.001	0.004
						MD Gas
						Diesel
						MD Gas

Site Support Vehicle Use Rates		Emissions Factors (lbs/vmt)				
		NOx	CO	VOC	SOx	CO2
Gasoline Vehicle VMT Period	161945					
Avg Daily Gasoline VMT:	290	0.000791	0.008821	0.000769	0.000009	0.000075
Diesel Vehicle VMT Period:	132075					
Avg Daily Diesel VMT:	236	0.000006	0.000003	0.000001	0.000001	0.000001
		0.2292	2.5555	0.2228	0.0026	0.0217
		0.0014	0.0007	0.0002	0.0002	0.0002
		0.0640	0.7143	0.0623	0.0007	66.8623
		0.0004	0.0002	0.0001	0.0001	0.0955
						tons/period
						tons/period
						gasoline
						diesel
						0.0061
						0.0001

Avg haul distance: to the site from BNSF Barstow railyard and immediate supply area.
Ref: MDAB, Emfac 2007, V2.3, Nov 2006
LDPs (gas and diesel), 1966-2010

VMT totals include other site support VMT from Tables 5.2E-6 and 5.2E-7.

CARB-CEIDARS, Updated Fractions for PM Profiles: PM2.5 = 0.991 of PM10 for Diesel Exhaust, and 0.998 for Gasoline Vehicles.

It should be noted that these emissions are not necessarily new emissions to the regional air shed. A significant portion of the truck services will be derived from the existing regional truck services vehicle pool, and as such these truck emissions would most likely be involved in deliveries in the area regardless of whether or not the proposed facility is constructed. As such, a major portion of the above estimated emissions would not be considered as additions to the air shed.

CONSTRUCTION PHASE - Worker Travel - Emissions

Ref: MDAB, Emfac 2007, V2.3, Nov 2007
On Road Vehicles (1966-2010)
LDP/LDT Weighted Avg Efs

Max # of Workers/Day:	1162	
Avg # of Workers/Day:	830	
Avg Occupancy/Vehicle:	1.2	
Round Trips/Day:	214	
Avg Roundtrip Distance:	52	miles
VTMT/Day:	11106	
VTMT/Const Period:	6208254	
Total Const Days:	559	

Emissions Factors (lbs/VMT)					
NOx	CO	VOC	SOx	PM10	CO2
0.00111	0.01108	0.00092	0.00001	0.00009	0.91102
Avg. Daily Emissions (lbs)					
NOx	CO	VOC	SOx	PM10	
12.328	123.054	10.218	0.111	1.000	10117.78
Tons per Const Period					
3.4456	34.3937	2.8558	0.0310	0.2794	2827.921

Total Bus VMT/Const Period:
Avg Bus VMT/Const Day:

Ref: MDAB, Emfac 2007, V2.3, Nov 20
On Road Vehicles (1966-2010)
Bus Carriers

Emissions Factors (lbs/VMT)					
NOx	CO	VOC	SOx	PM10	CO2
0.013846	0.016154	0.002308	0.000077	0.000077	3.846
Avg. Daily Emissions (lbs)					
NOx	CO	VOC	SOx	PM10	CO2
8.451	9.859	1.409	0.047	0.047	2347.305
Tons per Const Period					
2.362	2.756	0.394	0.013	0.013	656.072

It should be noted that these emissions are not necessarily new emissions to the regional air shed. A significant portion of the workers will be derived from the existing work force pool in the urban regional area, and as such these workers would most likely be involved in projects in the area regardless of whether or not the proposed facility is constructed. As such, a major portion of the above estimated emissions would not be considered as additions to the air shed.

CONSTRUCTION PHASE - Trackout Emissions

Paved Road Length (miles):	0.1	estimated roundtrip trackout distance	
Daily # of Vehicles:	349		
Avg Vehicle Weight (tons):	10.9	PM10	PM2.5*
Total Unadjusted VMT/day	34.9	0.207	
Particle Size Multipliers	PM10	2.807	
lb/VMT	0.023	0.001	0.0002 lb/VMT
C factor, lb/VMT	0.00047	5.457	0.9223 lbs/day
Road Sfc Silt Loading (g/m^2):	0.28	0.059	0.0099 tons/month
# of Active Trackout Points:	2	1.40	0.2363 tons/period
Added Trackout Miles:	PM10		
Trackout VMT/day:	4188	Default Silt Load Values for Paved Road Types	
Final Adjusted VMT/day	4223	Freeway	0.02 g/m2
Final Adjusted VMT/month	90792	Arterial	0.036 g/m2
Final Adjusted VMT/period	2163582	Collector	0.036 g/m2
Construction days/month:	21.5	Local	0.28 g/m2
Construction months/period:	23.8	Rural	1.6 g/m2
Control Applied to Trackout:		Sweeping and Cleaning (Water washing)	
Control Efficiency, %	90	0.9	Release Factor = 0.1

* PM2.5 fraction of PM10 assumed to be 0.169 (CARB CEIDARS updated fraction values) for paved roads.

EPA, AP-42, Section 13.2.1, Proposed revisions dated 9/2008.

Use silt loading factor from default values for road type if no site specific data is available.

Trackout effects approximately 260 ft of roadway arriving and departing from the site access point.

See the mileage note on the paved road calculation sheet.

CO₂e Emissions Estimates

Total CO₂ emissions from diesel combustion: 6970 tons/period

Total CO₂ emissions from gasoline combustion: 2883 tons/period

Approximate methane fraction of CO₂ for diesel combustion: 0.000051

Approximate N₂O fraction of CO₂ for diesel combustion: 0.000032

Approximate methane fraction of CO₂ for gasoline combustion: 0.000213

Approximate N₂O fraction of CO₂ for gasoline combustion: 0.000113

Estimated methane from diesel combustion: 0.35547 tons/period

Estimated N₂O from diesel combustion: 0.22304 tons/period

Estimated methane from gasoline combustion: 0.614079 tons/period

Estimated N₂O from gasoline combustion: 0.325779 tons/period

Estimated methane CO₂e from diesel combustion: 7.46487 tons/period

Estimated N₂O CO₂e from diesel combustion: 69.1424 tons/period

Estimated methane CO₂e from gasoline combustion: 12.89566 tons/period

Estimated N₂O CO₂e from gasoline combustion: 100.9915 tons/period

Total CO₂e emissions from construction 10043 tons/period

9039 metric tons/period

CCAR General Protocol, June 2006, Version 2.1.

IPCC SAR values for methane and N₂O.

Average Vehicle Weight Estimate for Construction Period

Vehicle Type	Weight tons	# Vehicles per day	Frac. of total vehicles
Passenger Cars	2	214	0.613
LD Pickups	3	17	0.049
MD Pickups	4	4	0.011
HD Loaded*	40	51	0.146
HD Unloaded*	20	51	0.146
Buses	20	12	0.034
		349	0.966

Weighted Avg Vehicle Weight, tons : 10.9

* Ref: Liberty Energy XXIII DEIR, City of Banning, CA., Aspen Environmental Group, June 2

Table C.5-6
Estimated Construction Equipment Identification and Use Rates

EQUIPMENT DESCRIPTION			HP	FUEL TYPE	USAGE DESCRIPTION	
TRUCK	PICKUP	5 TONS- 4 X 2	190	Gas	Grading Supervisors / Grade Checkers	(1) Superintendent or (1) Grade Checker
TRUCK	FUEL/LUBE	6 Tons - 4X2	250	Diesel	Fueling / Maintenance of Grading Equipment	(1) Mechanic's Helper
TRUCK	PICKUP	1.0 TONS- 4 X 4	200	Diesel	Grading Maintenance/Mechanics	(1) Mechanic and (1) Mechanic's Helper
14 M MOTOR GRADER	GRADING EQUIPMENT	47,133 LB	258	Diesel	Earth Moving	(1) Heavy Equipment Operator
823G SCRAPER	GRADING EQUIPMENT	23 CY	330	Diesel	Earth Moving	(1) Heavy Equipment Operator
857G SCRAPER	GRADING EQUIPMENT	44 CY	487	Diesel	Earth Moving	(1) Heavy Equipment Operator
825 H COMPACTOR	GRADING EQUIPMENT	72,184 LB	354	Diesel	Earth Moving	(1) Heavy Equipment Operator
831 WATER PULL (10K)	GRADING EQUIPMENT	10,000 GALLON	425	Diesel	Earth Moving	(1) Heavy Equipment Operator
D6 DOZERS	GRADING EQUIPMENT	44,418 LB	200	Diesel	Earth Moving	(1) Heavy Equipment Operator
414E INDUSTRIAL LOADER	GRADING EQUIPMENT	1 CY	89	Diesel	Site clean-up / Maintenance	(1) Heavy Equipment Operator
WATER TRUCK	GRADING EQUIPMENT	4,000 GALLON	300	Diesel	Site clean-up / Maintenance	(1) Heavy Equipment Operator
TRUCK	DUMP TRUCK	6 CY	250	Diesel	Site clean-up / Maintenance	(1) Heavy Equipment Operator
AUTO	CAR 4-DOOR	STANDARD	190	Gas	Administrative and personnel vehicle for site usage	
TRUCK	PICKUP	5 TONS- 4 X 2	190	Gas	General construction usage vehicle	
TRUCK	PICKUP	7.5 TONS- 4 X 2	190	Gas	General construction usage vehicle	
TRUCK	PICKUP	7.5 TONS- 4 X 4	200	Diesel	General construction usage vehicle	
TRUCK	PICKUP - CREW CAB	7.5 TONS- 4 X 4	200	Diesel	General construction usage vehicle	
TRUCK	PICKUP	1.0 TONS- 4 X 4	200	Diesel	General construction usage vehicle	
TRUCK	FLATBED	2 TONS- 4 X 2	200	Diesel	On-site material hauling	
TRUCK	FLATBED	6 TONS- 4 X 2	200	Diesel	On-site material hauling	
TRUCK	FLATBED	15 TONS- 4 X 2	200	Diesel	On-site material hauling	
TRUCK	FLATBED	30 TONS- 6 X 4	250	Diesel	On-site material hauling	
TRUCK	A-FRAME	4 X 4	200	Gas	On-site material hauling	
TRUCK	LUBE/GREASE		250	Diesel	Lube/grease truck for on-site construction vehicle maintenance	
TRUCK	CHERRY PICKER	NON-INSULATED	185	Diesel	Small crane for light duty lifting	
TRUCK	DUMP TRUCK	6 CY	250	Diesel	On-site material hauling	
TRUCK	DUMP TRUCK	12 CY	300	Diesel	On-site material hauling	
TRUCK	DUMP TRUCK	20 CY	300	Diesel	On-site material hauling	
TRACTOR	TRUCK TRACTOR	30 TONS 6X4	100	Diesel	Trailer pulling and general construction usage	
TRACTOR	TRUCK TRACTOR	60 TONS 6X4	100	Diesel	Trailer pulling and general construction usage	
TRACTOR	WHEEL, W/TOW HITCH	50 HP	50	Diesel	Trailer pulling and general construction usage	
CRANE	TELESCOPIC JIB, SELF	PROP. 5 TONS	185	Diesel	Small crane for light duty lifting	
CRANE	TELESCOPIC JIB, SELF	PROP. 10 TONS	185	Diesel	Small crane for light duty lifting	
CRANE	TELESCOPIC JIB, SELF	PROP. 15 TONS	185	Diesel	Small crane for light duty lifting	
CRANE	TELESCOPIC JIB	TRUCK - 20 TONS	220	Diesel	Small crane for medium duty lifting	
CRANE	TELESCOPIC JIB	TRUCK - 25 TONS	220	Diesel	Small crane for medium duty lifting	
CRANE	TELESCOPIC JIB	TRUCK - 30 TONS	220	Diesel	Small crane for medium duty lifting	
CRANE	TELESCOPIC JIB	TRUCK - 70 TONS	220	Diesel	Small crane for medium duty lifting	
CRANE	FIXED JIB, CRAWLER	20 TONS	220	Diesel	Small crane for medium duty lifting	
CRANE	FIXED JIB, CRAWLER	30 TONS	220	Diesel	Small crane for medium duty lifting	
CRANE	FIXED JIB, CRAWLER	40 TONS	220	Diesel	Small crane for medium duty lifting	
CRANE	FIXED JIB, CRAWLER	120 TONS	220	Diesel	Small crane for medium duty lifting	
CRANE	FIXED JIB, CRAWLER	165 TONS	250	Diesel	Large crane for heavy duty lifting	
CRANE	FIXED JIB, CRAWLER	400 TONS	350	Diesel	Large crane for heavy duty lifting	
PILING	DRILLING FRAME	AUGER	300	Diesel	Drilling machine for pier foundations	
PILING	DRILLING FRAME	AUGER	300	Diesel	Drilling machine for pier foundations	
COMPRESSOR	DIESEL(ROTARY SCREW)	250 CFM	80	Diesel	Air compressor for pneumatic construction tools and equipment	
COMPRESSOR	DIESEL(ROTARY SCREW)	365 CFM	80	Diesel	Air compressor for pneumatic construction tools and equipment	
COMPRESSOR	DIESEL(ROTARY SCREW)	600 CFM	80	Diesel	Air compressor for pneumatic construction tools and equipment	
CONCRETE	CONCRETE MIXER	6 SACK	300	Diesel	Concrete mixer for small foundations and supports	
CONCRETE	CONCRETE MIXER	16 SACK (1 CY)	300	Diesel	Concrete mixer for small foundations and supports	
CONCRETE	VIBRATOR, GASOLINE	2.4 HP, 2 IN HEAD	2.4	Gas	Small area compaction	
CONCRETE	POWER TROWEL, 4 BLADE	36 IN DIA	5	Gas	Concrete finishing tool	
CONCRETE	SITE DUMPER	.75 CY, DIESEL	5	Diesel	On-site material hauling	
WELDING EQUIPMENT	PORTABLE DIESEL	300 AMPERES	25	Diesel	Welding equipment	
WELDING EQUIPMENT	PORTABLE DIESEL	400 AMPERES	25	Diesel	Welding equipment	
PIPING EQUIPMENT	CUTTING & BEVELLING	1 - 4 INCHES	10	Diesel	Pipe fitting and preparation	
PIPING EQUIPMENT	CUTTING & BEVELLING	6 - 20 INCHES	10	Diesel	Pipe fitting and preparation	
PIPING EQUIPMENT	CUTTING & BEVELLING	22 - 30 INCHES	15	Diesel	Pipe fitting and preparation	
PUMP	DIAPHRAGM	4 INCHES SUCTION	10	Gas	Small pump for sumps and general construction usage	
ELECTRIC EQUIP/TOOL	GENERATOR SET	10 KW	50	Gas	Small generator for construction tools	
ASPHALT EQUIPMENT	PAVER/FINISHER	10 FEET WIDE	100	Diesel	Pavement finishing	
ASPHALT EQUIPMENT	SPREADER TRAILER, GAS	2000 GAL, SPRAY	100	Gas	Pavement spreading	

- ID #
- Category for Main Sheet Calcs
- 1
- Bore/Drill Rigs/Pile Drivers
- 2
- Cement Mixers
- 3
- Industrial/Concrete Saws
- 4
- Cranes
- 5
- Crawler Tractors/Dozers
- 6
- Crushing/Processing Eq.
- 7
- Dump and Tender Trucks
- 8
- Excavators
- 9
- Forklifts/Aerial Lifts/Booms
- 10
- Generators/Compressors
- 11
- Graders
- 12
- Off Highway Tractors
- 13
- Off Highway Trucks
- 14
- Other Const. Eq.-Diesel
- 15
- Pavers
- 16
- Paving Eq./Surfacing Eq.
- 17
- Plate Compactors
- 18
- Rollers/Compactors
- 19
- Rough Terrain Forklifts
- 20
- Rubber Tired Dozers
- 21
- Rubber Tired Loaders
- 22
- Scrapers
- 23
- Signal Boards/Light Sets
- 24
- Skid Steer Loaders
- 25
- Tractors/Loaders/Backhoes
- 26
- Trenchers
- 27
- Welders
- 28
- Site Support-Gasoline
- 29
- Site Support-Diesel
- 30
- Other Const. Eq.-Gasoline

[illegible]

[illegible]

Table C.8-7 Offsite Equipment and Manpower Schedules
Offsite Construction Vehicles

VEHICLE TYPE	HP	Fuel Type	Load Factor (%)	USAGE DESCRIPTION
Off-Site Flat Bed Trucks (From Rail Facility)	200	gasoline		Material Hauling
Off-Site Asphalt Trucks	200	diesel		Asphalt Hauling
Off-Site Cement Trucks	310	diesel		Concrete Delivery
Off-Site Construction Worker Commute	100	gasoline		Personnel Vehicles (See separate table below)
Off-Site Dump Trucks	275	diesel		Material Hauling
Off-Site Low Boy Trucks (From Rail Facility)	250	diesel		Material Hauling
Off-Site Pickup Trucks	200	gasoline		Light duty material hauling
Off-Site Pipe Hauling Trucks (From Rail Facility)	250	diesel		Piping material hauling
Off-Site Water Trucks	250	diesel		Dust suppression water
Off-Site Fuel/Lube Trucks	200	gasoline		Mobile fuel & lubrication services
Off-Site HTF Delivery Trucks (From Rail Facility)	250	diesel		Delivery of HTF (transfer from rail yard)
Off-Site Box Van Trucks	200	diesel		Material Hauling (Small Items / Dry Requirement Items)

Note: Use separate sheet (Site Construction Equipment) for on-site vehicles

Average Vehicle Miles Traveled per Day and Number of Vehicles

VEHICLE TYPE	MI/ Veh.-Day	Number																									
		M1	M2	M3	M4	M5	M6	M7	M8	M9	M10	M11	M12	M13	M14	M15	M16	M17	M18	M19	M20	M21	M22	M23	M24	M25	M26
Off-Site Flat Bed Trucks (From Rail Facility)	40	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	3	3	3	3	3	3	3	2	2
Off-Site Asphalt Trucks	40	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Off-Site Cement Trucks	40	1	12	46	46	55	55	55	55	55	55	55	55	55	55	55	55	55	55	55	55	46	46	46	46	37	14
Off-Site Dump Trucks	40	1	1	1	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Off-Site Low Boy Trucks (From Rail Facility)	40	1	1	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	1	1
Off-Site Pickup Trucks	40	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Off-Site Pipe Hauling Trucks (From Rail Facility)	40	0	0	0	0	0	0	0	0	0	3	4	5	5	5	5	5	5	5	4	2	0	0	0	0	0	0
Off-Site Water Trucks	40	1	1	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Off-Site Fuel/Lube Trucks	40	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	0
Off-Site HTF Delivery Trucks (From Rail Facility)	40	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Off-Site Box Van Trucks	40	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2	2	2	2	2	2	2	2	2	1	0

VEHICLE TYPE	MI/ Veh.-Day	Vehicle-Miles-Traveled (mi/day)																									
		M1	M2	M3	M4	M5	M6	M7	M8	M9	M10	M11	M12	M13	M14	M15	M16	M17	M18	M19	M20	M21	M22	M23	M24	M25	M26
Off-Site Flat Bed Trucks (From Rail Facility)	40	40	80	80	80	80	80	80	80	80	80	80	80	80	80	80	80	80	120	120	120	120	120	120	120	80	80
Off-Site Asphalt Trucks	40	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Off-Site Cement Trucks	40	40	480	1,840	1,840	2,200	2,200	2,200	2,200	2,200	2,200	2,200	2,200	2,200	2,200	2,200	2,200	2,200	2,200	2,200	2,200	1,840	1,840	1,840	1,480	560	160
Off-Site Dump Trucks	40	40	40	40	40	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Off-Site Low Boy Trucks (From Rail Facility)	40	40	40	40	80	80	80	80	80	80	80	80	80	80	80	80	80	80	80	80	80	80	80	80	80	40	40
Off-Site Pickup Trucks	40	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	40	40	40	40	0	0
Off-Site Pipe Hauling Trucks (From Rail Facility)	40	0	0	0	0	0	0	0	0	0	120	160	200	200	200	200	200	200	200	160	80	0	0	0	0	0	0
Off-Site Water Trucks	40	40	40	40	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Off-Site Fuel/Lube Trucks	40	40	40	40	40	40	40	40	40	40	40	40	40	40	40	40	40	40	40	40	40	40	40	40	40	40	0
Off-Site HTF Delivery Trucks (From Rail Facility)	40	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	40	80	80	80	80	80	80	80	80
Off-Site Box Van Trucks	40	0	0	0	0	0	0	0	0	0	0	0	0	0	0	80	80	80	80	80	80	80	80	80	80	40	0

Off-Site Construction Worker Bussing Arrangements

Total	173	244	321	411	680	862	898	948	968	998	1088	1081	1127	1149	1144	1139	1162	1155	1130	1069	1061	946	886	807	217	138
Solar Collector Array Facility (included in Total)				10	150	298	298	298	298	298	298	298	298	298	298	298	298	298	298	298	298	298	298	150		
Supervisors/Management/Admin (included in Total)	8	24	35	45	65	75	75	75	75	85	85	85	85	85	85	85	85	85	80	75	75	55	55	30	15	
Final Off-Site Construction Worker Commute (people, not vehicles)	M1	M2	M3	M4	M5	M6	M7	M8	M9	M10	M11	M12	M13	M14	M15	M16	M17	M18	M19	M20	M21	M22	M23	M24	M25	M26
Day Shift - non Bussed	49	79	107	137	219	247	256	289	274	285	307	317	323	322	320	326	322	314	299	294	260	244	175	77	46	
Day Shift - Bussed	124	165	215	275	461	575	602	640	655	668	734	730	765	781	777	774	791	790	776	731	717	657	612	403	140	92
Evening Shift - non Bussed						25	25	25	25	28	28	28	28	28	28	28	28	26	25	25	25	18	18			
Evening Shift - Bussed (if available)						15	15	15	15	17	17	17	17	17	17	17	17	16	15	15	15	11	11			
	check cells	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE

	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE	TRUE
Day shift total worker vehicles assuming 20% carpool	39	63	65	109	175	198	205	215	219	228	246	245	254	258	257	256	261	258	251	239	235	208	195	140	61	37	
Day shift total buses (roundtrips)	3	3	4	8	10	12	13	13	14	14	15	15	16	16	16	16	16	16	16	15	15	14	13	8	3	2	
Evening shift total worker vehicles assuming no bussing and 20% carpool	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Total Vehicle Trips (non-bussed) per month	847	1359	1832	2348	3763	4932	5087	5302	5388	5680	6059	6037	6235	6330	6308	6287	6386	6274	6085	5822	5745	4967	4704	3509	1320	787	
Total Bussed Vehicles Trips per month	55	74	96	123	207	258	270	287	293	299	329	327	342	350	348	346	354	354	348	327	321	294	274	181	63	41	

Max workers per month (assume pre day is same value):

Avg workers per month (assume pre day is same value):

Assume all trips for delivery and worker commute are from Barstow:

(1) delivery trips from BNSF Barstow and urban area

(2) commute trips from Barstow urban area or commute staging area

(3) delivery trips only one way as non-dedicated to site

(4) commute trips are two way for all modes

(5) assume bus capacity is 48 people

(6) assume evening shift is all non-bussed

Totals
1247 gasoline
301 diesel
25327 diesel
86 diesel
1011 diesel
108 gasoline
1032 diesel
65 diesel
538 gasoline
366 diesel
409 diesel

30487
Delivery data
diesel gasoline
VMT VMT
1143800 75640

VMT
49880 gasoline
12040 diesel
1013080 diesel
3440 diesel
40420 diesel
4300 gasoline
41280 diesel
2580 diesel
21500 gasoline
14620 diesel
16340 diesel

Total VMT
119390
6208254
341171

Title : MDAB-2010
Version : Emfac2007 V2.3 Nov 1 2006
Run Date : 2009/04/28 13:41:13
Scen Year: 2010 -- All model years in the range 1966 to 2010 selected
Season : Annual
Area : Mojave Desert Air Basin Average
I/M Stat : Enhanced Basic (2005) -- Using I/M schedule for area 69 San Bernardino (MD)
Emissions: Tons Per Day

Table C.5-8

- - - Light Duty Passenger Cars - - -				- - - - Light Duty Trucks - - - -				- - - - Medium Duty Trucks - - - -				- - - - H e a v y D u t y T r u c k s - - -							Urban Buses	Motor- cycles	All Vehicles
Non-cat	Cat	Diesel	Total	Non-cat	Cat	Diesel	Total	Non-cat	Cat	Diesel	Total	Gasoline Trucks			Diesel Trucks	Total HD Trucks					

Vehicles	4762.	321674.	913.	327349.	5407.	223284.	6734.	235425.	914.	85631.	7171.	93715.	891.	13894.	14784.	36230.	51014.	178.	42332.	750014.	
VMT/1000	93.	13737.	26.	13856.	135.	10030.	265.	10430.	22.	3871.	333.	4226.	10.	271.	281.	5474.	5755.	26.	587.	34881.	
Trips	18897.	2026910.	5027.	2050830.	21842.	1399050.	41371.	1462270.	7081.	900250.	87940.	995270.	9365.	65222.	74588.	258418.	333006.	712.	84656.	4926750.	

Reactive Organic Gas Emissions																					
Run Exh	0.62	1.11	0.00	1.74	0.93	1.35	0.02	2.30	0.18	0.51	0.05	0.75	0.05	0.18	0.24	5.90	6.14	0.03	2.28	13.24	
Idle Exh	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.02	0.00	0.02	0.00	0.00	0.00	0.70	0.70	0.00	0.00	0.72	
Start Ex	0.11	1.22	0.00	1.33	0.13	1.08	0.00	1.21	0.05	0.62	0.00	0.67	0.11	0.14	0.25	0.00	0.25	0.00	0.22	3.69	

Total Ex	0.74	2.33	0.00	3.07	1.07	2.43	0.02	3.51	0.23	1.15	0.05	1.44	0.17	0.33	0.50	6.60	7.10	0.03	2.49	17.65	

Diurnal	0.03	0.26	0.00	0.30	0.04	0.21	0.00	0.25	0.00	0.05	0.00	0.06	0.00	0.00	0.00	0.00	0.00	0.00	0.09	0.70	
Hot Soak	0.06	0.34	0.00	0.40	0.07	0.26	0.00	0.33	0.01	0.08	0.00	0.09	0.01	0.00	0.01	0.00	0.01	0.00	0.04	0.87	
Running	0.37	1.00	0.00	1.38	0.26	1.25	0.00	1.51	0.03	0.59	0.00	0.62	0.05	0.05	0.10	0.00	0.10	0.00	0.18	3.79	
Resting	0.02	0.15	0.00	0.17	0.02	0.13	0.00	0.15	0.00	0.03	0.00	0.03	0.00	0.00	0.00	0.00	0.00	0.00	0.04	0.41	

Total	1.23	4.09	0.00	5.32	1.47	4.28	0.02	5.76	0.27	1.91	0.05	2.24	0.22	0.38	0.61	6.60	7.21	0.03	2.85	23.41	

Carbon Monoxide Emissions																					
Run Exh	8.08	37.91	0.02	46.01	11.77	45.41	0.16	57.34	3.55	13.70	0.30	17.55	1.83	5.06	6.89	23.37	30.25	0.19	29.68	181.03	
Idle Exh	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.11	0.01	0.12	0.00	0.02	0.03	2.72	2.75	0.00	0.00	2.87	
Start Ex	0.66	14.35	0.00	15.01	0.78	14.00	0.00	14.78	0.40	7.45	0.00	7.85	0.99	2.42	3.41	0.00	3.41	0.02	0.91	41.98	

Total Ex	8.74	52.26	0.02	61.02	12.55	59.42	0.16	72.12	3.96	21.26	0.30	25.52	2.82	7.50	10.32	26.09	36.41	0.21	30.59	225.88	

Oxides of Nitrogen Emissions																					
Run Exh	0.48	3.92	0.04	4.45	0.69	5.97	0.46	7.11	0.17	2.46	1.95	4.58	0.05	1.05	1.10	87.41	88.51	0.18	0.83	105.67	
Idle Exh	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.02	0.02	0.00	0.00	0.00	6.25	6.25	0.00	0.00	6.27	
Start Ex	0.03	1.03	0.00	1.06	0.03	1.14	0.00	1.17	0.01	1.28	0.00	1.29	0.02	0.29	0.30	0.00	0.30	0.00	0.03	3.86	

Total Ex	0.51	4.95	0.04	5.51	0.72	7.11	0.46	8.29	0.18	3.74	1.97	5.90	0.07	1.33	1.40	93.66	95.06	0.18	0.86	115.79	

Carbon Dioxide Emissions (000)																					
Run Exh	0.05	5.49	0.01	5.55	0.07	5.00	0.10	5.17	0.01	2.71	0.19	2.92	0.01	0.19	0.20	10.70	10.90	0.05	0.09	24.69	
Idle Exh	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.37	0.37	0.00	0.00	0.38	
Start Ex	0.00	0.16	0.00	0.17	0.00	0.14	0.00	0.14	0.00	0.08	0.00	0.08	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.40	

Total Ex	0.05	5.65	0.01	5.72	0.08	5.14	0.10	5.32	0.02	2.80	0.19	3.01	0.01	0.20	0.21	11.08	11.28	0.05	0.10	25.47	

PM10 Emissions																					
Run Exh	0.00	0.18	0.00	0.19	0.00	0.26	0.01	0.27	0.00	0.09	0.01	0.11	0.00	0.00	0.00	3.79	3.79	0.00	0.02	4.39	
Idle Exh	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.10	0.10	0.00	0.00	0.10	
Start Ex	0.00	0.02	0.00	0.02	0.00	0.02	0.00	0.02	0.00	0.01	0.00	0.01	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.05	

Total Ex	0.00	0.20	0.00	0.20	0.00	0.28	0.01	0.30	0.00	0.10	0.01	0.12	0.00	0.00	0.00	3.89	3.89	0.00	0.03	4.54	

TireWear	0.00	0.12	0.00	0.12	0.00	0.09	0.00	0.09	0.00	0.04	0.00	0.04	0.00	0.00	0.00	0.21	0.21	0.00	0.00	0.47	
BrakeWr	0.00	0.19	0.00	0.19	0.00	0.14	0.00	0.14	0.00	0.05	0.00	0.06	0.00	0.00	0.00	0.16	0.17	0.00	0.00	0.57	

Total	0.01	0.51	0.00	0.52	0.01	0.50	0.02	0.53	0.00	0.19	0.02	0.21	0.00	0.01	0.01	4.26	4.27	0.00	0.03	5.57	

Lead	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
SOx	0.00	0.06	0.00	0.06	0.00	0.05	0.00	0.05	0.00	0.03	0.00	0.03	0.00	0.00	0.00	0.11	0.11	0.00	0.00	0.25	

Fuel Consumption (000 gallons)																					
Gasoline	7.21	587.97	0.00	595.18	10.26	536.58	0.00	546.84	2.42	290.29	0.00	292.71	1.45	21.47	22.92	0.00	22.92	1.05	15.52	1474.21	
Diesel	0.00	0.00	0.93	0.93	0.00	0.00	9.12	9.12	0.00	0.00	17.15	17.15	0.00	0.00	0.00	997.05	997.05	3.52	0.00	1027.76	

Table C.5-9

EMFAC Composite Emissions Factor Conversion

EMFAC 2007, V2.3, Nov 2006

County: MDAB
 Year: 2010
 Model Years: 1966-2010

EMFAC Burden Output										
	LDP(gas)	LDP(diesel)	LDT(gas)	LDT(diesel)	MDT(gas)	MDT(diesel)	HDT(gas)	HDT(diesel)	Buses	Motorcycles
Daily VMT/1000	13830	26	10165	265	3893	333	281	5474	26	587
Daily VMT	13830000	26000	10165000	265000	3893000	333000	281000	5474000	26000	587000
ROG, tpd	5.32	0.001	5.74	0.02	2.19	0.05	0.61	6.6	0.03	2.85
CO, tpd	61	0.02	71.96	0.16	25.22	0.3	10.32	26.09	0.21	30.59
NOx, tpd	5.47	0.04	7.83	0.46	3.93	1.97	1.4	93.66	0.18	0.86
CO2, tpd	(x 1000) > 5710	10	5220	100	2820	190	210	11080	50	100
PM10, tpd	0.52	0.001	0.53	0.001	0.19	0.02	0.01	4.26	0.001	0.03
SOx, tpd	0.06	0.001	0.05	0.001	0.03	0.001	0.001	0.11	0.001	0.001
Composite Efs										
	LDP(gas)	LDP(diesel)	LDT(gas)	LDT(diesel)	MDT(gas)	MDT(diesel)	HDT(gas)	HDT(diesel)	Buses	Motorcycles
	g/VMT	g/VMT	g/VMT	g/VMT	g/VMT	g/VMT	g/VMT	g/VMT	g/VMT	g/VMT
ROG	0.35	0.00	0.51	0.0018	0.51	0.00	1.97	1.09	1.05	4.40
CO	4.00	0.00	6.42	0.0143	5.88	0.02	33.32	4.32	7.33	47.28
NOx	0.36	0.00	0.70	0.0411	0.92	0.13	4.52	15.52	6.28	1.33
CO2	374.55	0.66	465.86	8.9245	657.14	12.46	677.96	1836.24	1744.58	154.55
PM10	0.03	0.00	0.05	0.0001	0.04	0.00	0.03	0.71	0.03	0.05
SOx	0.0039	0.0001	0.0045	0.0001	0.0070	0.0001	0.0032	0.0182	0.0349	0.0015
Composite Efs										
	LDP(gas)	LDP(diesel)	LDT(gas)	LDT(diesel)	MDT(gas)	MDT(diesel)	HDT(gas)	HDT(diesel)	Buses	Motorcycles
	lb/VMT	lb/VMT	lb/VMT	lb/VMT	lb/VMT	lb/VMT	lb/VMT	lb/VMT	lb/VMT	lb/VMT
ROG	0.000769	0.000000	0.001129	0.000004	0.001125	0.000007	0.004342	0.002411	0.002308	0.009710
CO	0.008821	0.000003	0.014158	0.000031	0.012957	0.000043	0.073452	0.009532	0.016154	0.104225
NOx	0.000791	0.000006	0.001541	0.000091	0.002019	0.000285	0.009964	0.034220	0.013846	0.002930
CO2	0.825741	0.001446	1.027054	0.019675	1.448754	0.027477	1.494662	4.048228	3.846154	0.340716
PM10	0.000075	0.000000	0.000104	0.000000	0.000098	0.000003	0.000071	0.001556	0.000077	0.000102
SOx	0.000009	0.000000	0.000010	0.000000	0.000015	0.000000	0.000007	0.000040	0.000077	0.000003
Weighted Avg LDP/LDT Gasoline										
	g/VMT		lb/VMT	Calc 1	0.424					
ROG	0.418		0.00092	Calc 2	0.576					
CO	5.027		0.01108							
NOx	0.503		0.00111							
CO2	413.2		0.91102							
PM10	0.040		0.00009							
SOx	0.004		0.00001							
	LDP(gas)	LDP(diesel)	LDT(gas)	LDT(diesel)	MDT(gas)	MDT(diesel)	HDT(gas)	HDT(diesel)	Buses	Motorcycles
Annual VMT	5.05E+09	9.49E+06	3.71E+09	9.67E+07	1.42E+09	1.22E+08	1.03E+08	2.00E+09	9.49E+06	2.14E+08
Daily Fuel Use, 10^3 gal	595.18	0.93	546.84	9.12	292.71	17.15	22.92	997.05	4.57	15.52
Daily Fuel Use, gals	595180	930	546840	9120	292710	17150	22920	997050	4570	15520
Annual Fuel Use, gals	217240700	339450	199596600	3328800	106839150	6259750	8365800	363923250	1668050	5664800
Average Miles/gallon	23.2	28.0	18.6	29.1	13.3	19.4	12.3	5.5	5.7	37.8

Table C.5-10 Modeling Inputs/Results for Mojave Solar One Construction Impacts (Combustion Sources as 24 Point Sources)

Short Term Impacts (24 hrs and less)										Long Term Impacts (annual)					
	NOx	CO	SOx	PM10	PM2.5					NOx	CO	SOx	PM10	PM2.5	
Combustion (lbs/day)	80.13	40.56	0.26	5.00	4.90	Combustion (tons/year)				7.92	4.07	0.034	0.49	0.48	
Combustion (hrs/day)	20	20	20	20	20	Combustion (days/year)**				260	260	260	260	260	
Combustion (lbs/hr)	4.01	2.03	0.01	0.25	0.25	Combustion (hrs/day)				20	20	20	20	20	
Combustion (g/sec)	5.05E-01	2.56E-01	1.64E-03	3.15E-02	3.09E-02	Combustion (lbs/hr)**				2.17	1.12	0.01	0.13	0.13	
Construction Dust (lbs/day)				883.92	185.62	Combustion (g/sec)				2.73E-01	1.40E-01	1.17E-03	1.69E-02	1.66E-02	
Construction Dust (hrs/day)				24		Construction Dust (tons/year)							30.51	6.42	
Construction Dust (lbs/hr)				36.83	7.73	Construction Dust (days/year)							260	260	
Construction Dust (g/sec)				4.64E+00	9.75E-01	Construction Dust (hrs/day)							24	24	
160.00 acres															
647,497 m ² 24 Pt.Srcs															
Combustion (g/s/src)	2.103E-02	1.065E-02	6.825E-05	1.313E-03	1.286E-03	Combustion (g/s/src)				1.139E-02	5.854E-03	4.890E-05	7.048E-04	6.904E-04	
Construction Dust (g/s/m ²)				7.167E-06	1.505E-06	Construction Dust (g/s/m ²)							1.356E-06	2.852E-07	
AERMOD Results (ug/m ³)															
Combustion Only															
1-hour Max	12.522	6.338	0.041	0.78137											
3-hour Max			0.039	0.75074											
8-hour Max		3.902		0.48102											
24-hour Max			0.016	0.30929	0.30310	Annual				1.312		0.006	0.08117	0.07951	
All Particulate Sources															
24-hour Max				436.14722	91.59913	All Particulate Sources									
1-hour NO2 w/ OLM	12.522	for Max 1-hr O3 (ppm)			0.136	Annual NO2 w/ ARM				0.984	based on ARM Ratio of:			5.03420	
Background (ug/m ³)						Background (ug/m ³)							75%		
1-hour Max	154	4025	94												
3-hour Max			23												
8-hour Max		1789													
24-hour Max			13	154	28	Annual				42		3	38.4	10.4	
Total + Background (ug/m ³)															
1-hour Max	166.5	4031	94.04			Total + Background (ug/m ³)									
3-hour Max			23.04												
8-hour Max		1793													
24-hour Max			13.02	590	120	Annual				42.98		3.01	62.2	15.4	

**Even for construction projects taking less than 12-months or 7 days/wk, the hourly emissions for modeling are still based on total tons (projects<12 months) or tons/year (projects>12months) divided by 365 days since all days in the met dataset (i.e., all 12 months and all 365 days - i.e., 7 days/week) are modeled.

APPENDIX C.6

Evaluation of Best Available Control Technology

To evaluate BACT for the emergency engines and cooling towers, a number of California air district BACT determinations were reviewed.

Diesel Fired IC Engine BACT

BACT levels for the diesel fired IC engines are shown in Table C.6-1.

TABLE C.6-1 SUMMARY OF BACT RECOMMENDATIONS FROM DISTRICT GUIDANCE FOR DIESEL FIRED CI-IC ENGINES					
	NO _x , g/bhp	CO, g/bhp	VOC, g/bhp	SO _x , %S wt.	PM ₁₀ , g/bhp
CI-IC Engines	2.8 - 6.19	0.37-3.7	0.07 - 1.5	≤ 0.05	0.07 - 0.40
Tier II*	4.5	2.6	0.3	≤ 0.05	0.15
Tier III*	2.8-4.5	2.6-3.7	0.2-0.3	LSDF	0.15-0.22
*For the proposed engine hp categories and estimated mfg year (2010).					

The proposed diesel engines will also comply with the EPA Tier standards as applicable based upon engine size, year of manufacture, and service category.

The proposed fire pump diesel engine will comply with the CARB proposed Air Toxic Control Measure (ACTM) for Stationary Compression Ignition Engine (as amended). Since the FP engine is classified as emergency standby, with a rating greater than 50 hp, and operational hours consistent with NFPA 25 requirements, the PM10 performance standard to be met will be 0.22g/hp-hr using CARB certified diesel fuel. In addition the engine will comply with AQMD Rules and the Tier standards as delineated in Title 13 CCR Section 2423, based upon engine size, year of manufacture, and service category.

The proposed engines will also comply with NSPS Subpart IIII standards per 40 CFR 60.4205. Table C.6-2 presents the emissions standards for the proposed engines.

TABLE C.6-2 SUMMARY OF SUBPART IIII EMISSIONS LIMITS FOR DIESEL FIRED CI-IC ENGINES					
	NO _x + NMHC, g/bhp	CO, g/bhp	VOC, g/bhp	SO _x , %S wt.	PM ₁₀ , g/bhp
EGS Engine ¹	7.9	8.5	1.0	-	0.40
FP Engine (~346 hp)	3.0	2.6	0.2	-	0.15
*For the proposed engine hp categories and estimated mfg year (2010).					
¹ Emissions limits in 40 CFR 89.112 converted from g/Kw-hr to g/hp-hr by 0.74 factor.					

BACT as proposed in Section 5.2, Table 5.2-10 will insure compliance with the Subpart IIII emissions requirements.

Cooling Towers

The cooling towers will meet a drift fraction rate of 0.0005% (0.000005). This limit is proposed as BACT for these cooling towers. The drift limit of 0.000005 will be achieved by using high efficiency drift eliminators.

HTF System

BACT for the HTF storage and distribution system is described in detail in Appendix C.1 (Attachment C.1-1). BACT for the HTF system will consist of the following:

- Nitrogen blankets on the HTF storage tanks.
- Monitoring of the nitrogen system to insure tank blanketing is sufficient to minimize HTF losses.
- Daily inspections of the tanks and distribution system for the presence of leaks in the areas of valves, flanges, and pump seals.
- Continuous maintenance of the system.
- Proper handling of HTF during delivery, transfer to the system, and waste disposal.

Auxiliary Boilers

The auxiliary boilers (2) will be meet BACT through the use of natural gas (clean fuel), and the use of low NO_x burners (LNB). These units will operate an average of 12 hours per day (24 hours per day operation is possible). The units are rated at ~21.5 mmbtu/hr each. Full load firing is expected to consume fuel at a rate of 258 mmbtu/day (each). BACT decisions made by the South Coast AQMD during the period 9-15-2000 through 7-11-2003 for boilers in this size range showed the following:

- NO_x BACT range is 9-15 ppmv @ 3% O₂.
- CO BACT range is 50-100 ppmv @ 3% O₂.
- SO_x, VOC, and PM₁₀/PM_{2.5} BACT is the use of clean fuels.

The auxiliary boilers as proposed are showing NO_x at a BACT level of 9 ppmv at 3% O₂, and CO at a BACT level of 50 ppmv @ 3% O₂. The use of natural gas would be considered BACT for SO_x, VOC, and PM₁₀/PM_{2.5}. As such, the proposed boilers meet BACT.

Offset Listing

The MS1 project, pursuant to the MDAQMD NSR rule is **not** required to purchase or acquire sufficient emission reduction credits to offset the proposed project emissions due to its anticipated status as a non-major source. NSR rule required amounts of ERCs are delineated in Table C.7-1.

TABLE C.7-1 MDAQMD EMISSION BANK CREDITS REQUIRED BY MS1

	Emission Reduction Credits (lbs/yr)				
	PM ₁₀	VOC	NO _x	SO ₂	CO
Total Emission Credits Required to Mitigate MS1 Project Emissions Per District NSR Rule	0	0	0	0	0

* Values derived from Section 5.2.

MDAQMD offset thresholds are implemented on a “facility” basis. For new facilities the offset thresholds are compared to the facility potential to emit (PTE). Section 5.2, Table 5.2-7 indicates that the proposed facility PTE emissions are well below the Rule 1303 offset thresholds. Therefore, offsets pursuant to the MDAQMD NSR rule are not required.

Cumulative Impacts Analysis Protocol

Potential cumulative air quality impacts are not expected to occur or result from the MS1 Project due to the extremely low operational emissions from the proposed solar facility. As such, a cumulative impact analysis is not required at this time.

Air District Permitting Application Forms

This appendix contains the applicable air district permitting application forms for the identified devices and/or processes subject to district permitting jurisdiction. These application forms in conjunction with Volumes I and II of the AFC (specifically the Project Description Section, the Air Quality Section, and the Public Health Section) constitute the facility's application for an Authority/Permit to Construct pursuant to MDAQMD Rule 1306.

MOJAVE DESERT AIR QUALITY MANAGEMENT DISTRICT

14306 Park Avenue, Victorville, CA 92392-2310

(760) 245-1661 Facsimile: (760) 245-2022

www.mdaqmd.ca.gov


Eldon Heaston

Executive Director

APPLICATION FOR AUTHORITY TO CONSTRUCT AND PERMIT TO OPERATE

Page 1 of 2: please type or print

REMIT \$226.00 WITH THIS DOCUMENT (\$129.00 FOR CHANGE OF OWNER)

1. Permit To Be Issued To (company name to receive permit): Mojave Solar LLC		1a. Federal Tax ID No.:	
2. Mailing/Billing Address (for above company name): 13911 Park Avenue, Suite 206, Victorville, CA 92392-2407			
3. Facility or Business License Name (for equipment location): Mojave Solar LLC			
4. Facility Address - Location of Equipment (if same as for company, enter "Same"): No address yet, use "same"		Location UTM or Lat/Long: 470036mE, 3874396mN NAD27	
5. Contact Name/Title: Emiliano Garcia, Manager	Email Address: emiliano.garcia@solar.abengoa.com	Phone/Fax Nos.: P: (303) 925-8500 / F: (303) 928-8510	
6. Application is hereby made for Authority To Construct (ATC) and Permit To Operate (PTO) the following equipment: Mojave Solar I Project (See AFC Air Quality section and appendices for equipment details)			
Air Pollution Control Equipment, if any (note that most APCE require a separate application): See AFC Air Quality section and Appendices for APCE details.			
7. Application is for: <input checked="" type="checkbox"/> New Construction <input type="checkbox"/> Modification* <input type="checkbox"/> Change of Owner*		For modification or change of owner: *Current Permit Number:	
8. Type of Organization (check one): <input type="checkbox"/> Individual Owner <input type="checkbox"/> Partnership <input checked="" type="checkbox"/> Corporation <input type="checkbox"/> Utility <input type="checkbox"/> Local Agency <input type="checkbox"/> State Agency <input type="checkbox"/> Federal Agency			
9. General Nature of Business: Solar Electric Power Generation		Principal Product: Electricity	SIC Code (if known): 4911
10. Distances (feet and direction to closest): see AFC Fenceline _____ Residence _____ Business _____ School _____			
11. Facility Annual Throughput by Quarters (percent): 25 % 25 % 25 % 25 % Jan-Mar Apr-Jun Jul-Sep Oct-Dec		12. Expected Facility Operating Hours: 16 7 52 5840 Hrs/Day Days/Wk Wks/Yr Total Hrs/Yr	
13. Do you claim Confidentiality of Data (if yes, state nature of data on reverse in Remarks)? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
14. Signature of Responsible Official: 		Official Title: General Manager	
Typed or Printed Name of Responsible Official: Emiliano Garcia		Phone Number: (303) 925-8500	Date Signed: 7-20-09
- For District Use Only -			
Application Number:	Invoice Number:	Permit Number:	Company/Facility Number:

MOJAVE DESERT AIR QUALITY MANAGEMENT DISTRICT GENERAL APPLICATION, continued

Page 2 of 2: please type or print

15. Stack Emissions Information:

Stack No.	FT. agl Stack Height	FT. Stack Diameter	F deg Exhaust Temp	ACFM Exhaust Flow Rate	FT/SEC Exhaust Velocity
1	see AFC Appendix C.1 and C.2 for all stack related data				
2					
3					
4					
	additional stacks				
5					
6					
7					
8					
9					
10					
11					
12					

13

14

15

16

17

18

19

20

21

22

23

24

25

Stack Height is the distance above ground level to discharge point (feet)

Stack Diameter is the diameter (or equivalent circular diameter) of discharge point (nearest tenth foot)

If using cross-sectional area (A in square feet), equivalent diameter is $D = (1.273A)^{0.5}$

Exhaust Temp in degrees F, actual or estimated to nearest 50 deg F

Exhaust Flow Rate at discharge point in actual cubic feet per minute (ACFM)

Exhaust Velocity in feet per second, design or measured

16. Remarks (basis for confidentiality of data, process description, modification description, etc.):

None, See AFC Sections on Air Quality and Public Health, and Appendices.

If you wish to specify process information as proprietary or confidential, space is provided for this purpose.
The kinds and rates of emissions may not be held confidential: emissions are subject to public disclosure.

MOJAVE DESERT AIR QUALITY MANAGEMENT DISTRICT

14306 Park Avenue, Victorville, CA 92392-2310

(760) 245-1661 Facsimile: (760) 245-2022

www.mdaqmd.ca.gov


Eldon Heaston

Executive Director

APPLICATION FOR EXTERNAL COMBUSTION ENGINE (BOILER, ETC.) ONLY

Page 1 of 2: please type or print

REMIT \$226.00 WITH THIS DOCUMENT (\$129.00 FOR CHANGE OF OWNER)

1. Permit To Be Issued To (company name to receive permit): Mojave Solar LLC		1a. Federal Tax ID No.:
2. Mailing/Billing Address (for above company name): 13911 Park Avenue, Suite 206, Victorville, CA 92392-2407		
3. Facility or Business License Name (for equipment location): Mojave Solar LLC		
4. Facility Address - Location of Equipment (if same as for company, enter "Same"): No address yet, use "same"		Facility UTM or Lat/Long: 470036, 3874396
5. Contact Name/Title: Emiliano Garcia, Manager	Email Address: emiliano.garcia@solar.abengoa.com	Phone/Fax Nos.: P: (303) 925-8500 / F: (303) 928-8510
6. Application is hereby made for Authority To Construct (ATC) and Permit To Operate (PTO) the following equipment: Auxiliary Boiler #1		
7. Application is for: <input checked="" type="checkbox"/> New Construction <input type="checkbox"/> Modification* <input type="checkbox"/> Change of Owner*		For modification or change of owner: *Current Permit Number: _____
8. Type of Organization (check one): <input type="checkbox"/> Individual Owner <input type="checkbox"/> Partnership <input checked="" type="checkbox"/> Corporation <input type="checkbox"/> Utility <input type="checkbox"/> Local Agency <input type="checkbox"/> State Agency <input type="checkbox"/> Federal Agency		
9. Distances (feet and direction to closest): SEE AFC Fenceline _____ Residence _____ Business _____ School _____		
10. General Nature of Business: Solar Power Generating Facility	11. Principal Product: Electrical Power	
12. Facility Annual Throughput by Quarters (percent): see AFC % _____ % _____ % _____ % Jan-Mar Apr-Jun Jul-Sep Oct-Dec	13. Facility Operating Hours: see AFC Hrs/Day Days/Wk Wks/Yr Total Hrs/Yr	
14. Do you claim Confidentiality of Data (if yes, state nature of data in attachment)? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
15. Signature of Responsible Official: 	Official Title: General Manager	
Typed or Printed Name of Responsible Official: Emiliano Garcia	Phone Number: (303) 925-8500	Date Signed: 7-20-09
- For District Use Only -		
Application Number:	Invoice Number:	Permit Number:
		Company/Facility Number:

**MOJAVE DESERT AIR QUALITY MANAGEMENT DISTRICT
EXTERNAL COMBUSTION APPLICATION, continued**

Page 2 of 2: please type or print

16. INFORMATION ON EQUIPMENT:

☒ Boiler ☐ Dryer ☐ Furnace ☐ Heater ☐ Kiln ☐ Oven ☐ Other, specify: _____
 Manufacturer: Nebraska
 Model No.: D-Type Serial No.: _____
 Maximum heat input rating (use Higher Heating Value) 21.5 MMBtu/hr or kW
 Burner Manufacturer: _____ Burner Model No.: _____
 Number of burners: _____ Burner max heat input rating: _____ MMBtu/hr or kW
 Percent excess air (or n/a): _____ Operating temps (C or F): _____ Av. _____ Max _____
 Specify Primary Fuel (*attach fuel analysis for these fuels specifying HHV and sulfur content):
☒ Natural Gas ☐ LPG (Propane) ☐ CARB Diesel ☐ Coal* ☐ Petroleum Coke*
☐ Digester Gas* ☐ Landfill Gas* ☐ Refinery Gas* ☐ Other, * specify: _____
 Max hourly primary fuel usage: 0.021 Fuel units (ft³, gal, etc.): mmscf
 If secondary fuel is proposed, specify: _____ Max hourly usage: _____
 Feedstock type and max process rate (specify units): _____
 Unit Lat/Long or UTM Coordinates: see AFC Appendix C.2
 Max annual hours: 4380 Exhaust Stack Height (feet): _____ Inside Diameter (inches): _____

17. EMISSION CONTROLS: Check all that apply:

☒ Low NOx Burner ☐ Oxygen Trim ☐ Flue or Exhaust Gas Recirculation (FGR or EGR)
☐ Oxidation Catalyst ☐ Selective Catalytic Reduction (SCR) ☐ Selective Non-Catalytic Reduction (SNCR)
☐ Afterburner ☐ ESP ☐ Baghouse ☐ Other - Please specify: _____

18. MAX EMISSION RATES (CONTROLLED):

Pollutant	Concentration ppmvd or gr/dscf	Mass pounds/hour
Oxides of Nitrogen (NOx)	see AFC	
Oxides of Sulfur (SOx)		
Carbon Monoxide (CO)		
Total Particulates (TSP or PM30)		
Coarse Respirable Particulates (PM10)		
Fine Respirable Particulates (PM2.5)		
Total Organics (TOG)		
Volatile Organic Compounds (VOC, ROG or NMOG)		

19. DRYERS ONLY Check one:

☐ Centrifugal ☐ Chip ☐ Fluidized Bed ☐ Rotary ☐ Spray ☐ Other, specify: _____

20. FURNACE ONLY Check one:

☐ Annealing ☐ Burnoff ☐ Calcining ☐ Crucible ☐ Cupola ☐ Diffusion ☐ Electric ☐ Forge ☐ Pot
☐ Holding ☐ Heat Treating ☐ Melting ☐ Reveratory ☐ Rotary ☐ Sweating ☐ Oxide Growth

21. OVEN ONLY Check one:

☐ Bakery ☐ Baking ☐ Curing ☐ Drying ☐ Fluidized Bed ☐ Stripping ☐ Solder Reflow
☐ Roasting, specify type: _____ Firing Method: ☐ Direct ☐ Indirect

MOJAVE DESERT AIR QUALITY MANAGEMENT DISTRICT

14306 Park Avenue, Victorville, CA 92392-2310

(760) 245-1661 Facsimile: (760) 245-2022

www.mdaqmd.ca.gov


Eldon Heaston

Executive Director

APPLICATION FOR EXTERNAL COMBUSTION ENGINE (BOILER, ETC.) ONLY

Page 1 of 2: please type or print

REMIT \$226.00 WITH THIS DOCUMENT (\$129.00 FOR CHANGE OF OWNER)

1. Permit To Be Issued To (company name to receive permit): Mojave Solar LLC		1a. Federal Tax ID No.:
2. Mailing/Billing Address (for above company name): 13911 Park Avenue, Suite 206, Victorville, CA 92392-2407		
3. Facility or Business License Name (for equipment location): Mojave Solar LLC		
4. Facility Address - Location of Equipment (if same as for company, enter "Same"): No address yet, use "same"		Facility UTM or Lat/Long: 470036, 3874396
5. Contact Name/Title: Emiliano Garcia, Manager	Email Address: emiliano.garcia@solar.abengoa.com	Phone/Fax Nos.: P: (303) 925-8500 / F: (303) 928-8510
6. Application is hereby made for Authority To Construct (ATC) and Permit To Operate (PTO) the following equipment: Auxiliary Boiler #2		
7. Application is for: <input checked="" type="checkbox"/> New Construction <input type="checkbox"/> Modification* <input type="checkbox"/> Change of Owner*		For modification or change of owner: *Current Permit Number: _____
8. Type of Organization (check one): <input type="checkbox"/> Individual Owner <input type="checkbox"/> Partnership <input checked="" type="checkbox"/> Corporation <input type="checkbox"/> Utility <input type="checkbox"/> Local Agency <input type="checkbox"/> State Agency <input type="checkbox"/> Federal Agency		
9. Distances (feet and direction to closest): SEE AFC Fenceline _____ Residence _____ Business _____ School _____		
10. General Nature of Business: Solar Power Generating Facility	11. Principal Product: Electrical Power	
12. Facility Annual Throughput by Quarters (percent): see AFC % _____ % _____ % _____ % Jan-Mar Apr-Jun Jul-Sep Oct-Dec	13. Facility Operating Hours: see AFC Hrs/Day Days/Wk Wks/Yr Total Hrs/Yr	
14. Do you claim Confidentiality of Data (if yes, state nature of data in attachment)? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
15. Signature of Responsible Official: 	Official Title: General Manager	
Typed or Printed Name of Responsible Official: Emiliano Garcia	Phone Number: (303) 925-8500	Date Signed: 7-20-09
- For District Use Only -		
Application Number:	Invoice Number:	Permit Number:
		Company/Facility Number:

MOJAVE DESERT AIR QUALITY MANAGEMENT DISTRICT

EXTERNAL COMBUSTION APPLICATION, continued

Page 2 of 2: please type or print

16. INFORMATION ON EQUIPMENT:

☒ Boiler ☐ Dryer ☐ Furnace ☐ Heater ☐ Kiln ☐ Oven ☐ Other, specify: _____

Manufacturer: Nebraska

Model No.: D-Type Serial No.: _____

Maximum heat input rating (use Higher Heating Value) 21.5 MMBtu/hr or kW

Burner Manufacturer: _____ Burner Model No.: _____

Number of burners: _____ Burner max heat input rating: _____ MMBtu/hr or kW

Percent excess air (or n/a): _____ Operating temps (C or F): _____ Av. _____ Max _____

Specify Primary Fuel (*attach fuel analysis for these fuels specifying HHV and sulfur content):

☒ Natural Gas ☐ LPG (Propane) ☐ CARB Diesel ☐ Coal* ☐ Petroleum Coke*

☐ Digester Gas* ☐ Landfill Gas* ☐ Refinery Gas* ☐ Other,* specify: _____

Max hourly primary fuel usage: 0.021 Fuel units (ft³, gal, etc.): mmscf

If secondary fuel is proposed, specify: _____ Max hourly usage: _____

Feedstock type and max process rate (specify units): _____

Unit Lat/Long or UTM Coordinates: see AFC Appendix C.2

Max annual hours: 4380 Exhaust Stack Height (feet): _____ Inside Diameter (inches): _____

17. EMISSION CONTROLS: Check all that apply:

☒ Low NOx Burner ☐ Oxygen Trim ☐ Flue or Exhaust Gas Recirculation (FGR or EGR)

☐ Oxidation Catalyst ☐ Selective Catalytic Reduction (SCR) ☐ Selective Non-Catalytic Reduction (SNCR)

☐ Afterburner ☐ ESP ☐ Baghouse ☐ Other - Please specify: _____

18. MAX EMISSION RATES (CONTROLLED):

Pollutant	Concentration ppmvd or gr/dscf	Mass pounds/hour
Oxides of Nitrogen (NOx)	see AFC	
Oxides of Sulfur (SOx)		
Carbon Monoxide (CO)		
Total Particulates (TSP or PM30)		
Coarse Respirable Particulates (PM10)		
Fine Respirable Particulates (PM2.5)		
Total Organics (TOG)		
Volatile Organic Compounds (VOC, ROG or NMOG)		

19. DRYERS ONLY Check one:

☐ Centrifugal ☐ Chip ☐ Fluidized Bed ☐ Rotary ☐ Spray ☐ Other, specify: _____

20. FURNACE ONLY Check one:

☐ Annealing ☐ Burnoff ☐ Calcining ☐ Crucible ☐ Cupola ☐ Diffusion ☐ Electric ☐ Forge ☐ Pot

☐ Holding ☐ Heat Treating ☐ Melting ☐ Reverbatory ☐ Rotary ☐ Sweating ☐ Oxide Growth

21. OVEN ONLY Check one:

☐ Bakery ☐ Baking ☐ Curing ☐ Drying ☐ Fluidized Bed ☐ Stripping ☐ Solder Reflow

☐ Roasting, specify type: _____ Firing Method: ☐ Direct ☐ Indirect


MOJAVE DESERT AIR QUALITY MANAGEMENT DISTRICT
 14306 Park Avenue, Victorville, CA 92392-2310
 (760) 245-1661 Facsimile: (760) 245-2022

www.mdaqmd.ca.gov
Eldon Heaston
 Executive Director

APPLICATION FOR INTERNAL COMBUSTION ENGINE (I.C.E.) ONLY

Page 1 of 2: please type or print

REMIT \$226.00 WITH THIS DOCUMENT (\$129.00 FOR CHANGE OF OWNER)

1. Permit To Be Issued To (company name to receive permit): Mojave Solar LLC		1a. Federal Tax ID No.:
2. Mailing/Billing Address (for above company name): 13911 Park Avenue, Suite 206, Victorville, CA 92392-2407		
3. Facility or Business License Name (for equipment location): Mojave Solar LLC		
4. Facility Address - Location of Equipment (if same as for company, enter "Same"): No address yet, use "same"		Facility UTM or Lat/Long: 470036, 3874396
5. Contact Name/Title: Emiliano Garcia, Manager	Email Address: emiliano.garcia@solar.a bengoa.com	Phone/Fax Nos.: P: (303) 925-8500 / F: (303) 928- 8510
6. Application is hereby made for Authority To Construct (ATC) and Permit To Operate (PTO) the following equipment: Emergency Generator Engine #1		
7. Application is for: <input checked="" type="checkbox"/> New Construction <input type="checkbox"/> Modification* <input type="checkbox"/> Change of Owner*		For modification or change of owner: *Current Permit Number: _____
8. Type of Organization (check one): <input type="checkbox"/> Individual Owner <input type="checkbox"/> Partnership <input checked="" type="checkbox"/> Corporation <input type="checkbox"/> Utility <input type="checkbox"/> Local Agency <input type="checkbox"/> State Agency <input type="checkbox"/> Federal Agency		
9. Distances (feet and direction to closest): see AFC _____ Fenceline _____ Residence _____ Business _____ School _____		
10. General Nature of Business: Solar Power Generating Facility		11. Principal Product: Electrical Power
12. Facility Annual Throughput by Quarters (percent): see AFC % _____ % _____ % _____ % Jan-Mar Apr-Jun Jul-Sep Oct-Dec		13. Expected Operating Hours of IC Engine: see AFC Hrs/Day Days/Wk Wks/Yr Total Hrs/Yr
14. Do you claim Confidentiality of Data (if yes, state nature of data in attachment)? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
15. Signature of Responsible Official: 		Official Title: General Manager
Typed or Printed Name of Responsible Official: Emiliano Garcia		Phone Number: (303) 925-8500 Date Signed: 7-20-09
- For District Use Only -		
Application Number:	Invoice Number:	Permit Number: Company/Facility Number:

MOJAVE DESERT AIR QUALITY MANAGEMENT DISTRICT
I.C.E. APPLICATION, continued

Page 2 of 2: please type or print

16. INFORMATION ON I.C.E.:

Manufacturer: Caterpillar - See mfg spec sheets in Appendix C.1
 Model No.: 3516C-HDTA Serial No.: _____
 Number of Cylinders: 16 Year of Manufacture: _____
 Rating: 4190 BHP Speed: 1800 RPM
 I.C.E. is? ☒ New ☐ Existing Date Installed (MM/YYYY): _____
 Prime ☐ Standby ☐ Emergency ☒ Portable (Yes or No)? _____
 CARB engine certification Family: _____ Certification EO#: _____
 Is this engine included in a Demand Response plan?: Yes ☐ No ☒
 Type of Fuel(s): Natural Gas ☐ Digester Gas ☐ Ethanol ☐ Landfill Gas ☐
 Propane ☐ CARB Diesel ☒ Methanol ☐ Other: _____
 Max fuel usage per hour: 173.3 Fuel units (ft³, gal, etc.): gal/hr

Engine Lat/Long or UTM Coordinates: see AFC

Exhaust Stack Height (feet): 46 Inside Diameter (inches): 12 Y/N: Vertical? Y Capped? N

Is this I.C.E. (select all that apply): see AFC Appendix C.1

Direct Injected? ☐ After Cooled? ☐
 Turbo Charged? ☐ Inter Cooled? ☐
 Timing Retarded? ☐ Other - Please specify: _____

17. EMISSION RATES:

Pollutant	at Max.Load	Units	Origin of Emission Rate data:	
			Manufacturer or	Source Test
Oxides of Nitrogen (NOx)	<u>see AFC</u>	_____	_____	_____
Oxides of Sulfur (SOx)	_____	_____	_____	_____
Carbon Monoxide (CO)	_____	_____	_____	_____
Particulates (PM10)	_____	_____	_____	_____
Total Hydrocarbons (VOC)	_____	_____	_____	_____

18. EMISSION CONTROL EQUIPMENT: Add on emission control equipment? ☐ Yes ☐ No

If yes: Manufacturer: _____ Model No.: _____
 Serial No.: _____ *CARB EO#: _____
 Type: SCR: ☐ Particulate Trap*: ☐ Ammonia Injection: ☐ Water Injection: ☐
 Non-S CR: ☐ Exhaust Gas Recirc*: ☐ Oxidation Catalyst*: ☐
 Other - Please specify: _____

19. INFORMATION OF ITEM BEING POWERED: This I.C.E. is used to power:

Electrical Generator ☒ Compressor ☐ Pump ☐
 Paint Spray Gun ☐ Conveyor or Drive ☐ Fire Pump ☐

Other - Please specify: _____

Manufacturer: _____
 Model No.: _____ Serial No.: _____
 Type, Size or Rating: 2500 kw


MOJAVE DESERT AIR QUALITY MANAGEMENT DISTRICT
 14306 Park Avenue, Victorville, CA 92392-2310
 (760) 245-1661 Facsimile: (760) 245-2022

www.mdaqmd.ca.gov
Eldon Heaston
 Executive Director

APPLICATION FOR INTERNAL COMBUSTION ENGINE (I.C.E.) ONLY

Page 1 of 2: please type or print

REMIT \$226.00 WITH THIS DOCUMENT (\$129.00 FOR CHANGE OF OWNER)

1. Permit To Be Issued To (company name to receive permit): Mojave Solar LLC		1a. Federal Tax ID No.:	
2. Mailing/Billing Address (for above company name): 13911 Park Avenue, Suite 206, Victorville, CA 92392-2407			
3. Facility or Business License Name (for equipment location): Mojave Solar LLC			
4. Facility Address - Location of Equipment (if same as for company, enter "Same"): No address yet, use "same"		Facility UTM or Lat/Long: 470036, 3874396	
5. Contact Name/Title: Emiliano Garcia, Manager		Email Address: emiliano.garcia@solar.a bengoa.com	Phone/Fax Nos.: P: (303) 925-8500 / F: (303) 928- 8510
6. Application is hereby made for Authority To Construct (ATC) and Permit To Operate (PTO) the following equipment: Emergency Generator Engine #2			
7. Application is for: <input checked="" type="checkbox"/> New Construction <input type="checkbox"/> Modification* <input type="checkbox"/> Change of Owner*		For modification or change of owner: *Current Permit Number: _____	
8. Type of Organization (check one): <input type="checkbox"/> Individual Owner <input type="checkbox"/> Partnership <input checked="" type="checkbox"/> Corporation <input type="checkbox"/> Utility <input type="checkbox"/> Local Agency <input type="checkbox"/> State Agency <input type="checkbox"/> Federal Agency			
9. Distances (feet and direction to closest): see AFC Fenceline _____ Residence _____ Business _____ School			
10. General Nature of Business: Solar Power Generating Facility		11. Principal Product: Electrical Power	
12. Facility Annual Throughput by Quarters (percent): see AFC % _____ % _____ % _____ % Jan-Mar Apr-Jun Jul-Sep Oct-Dec		13. Expected Operating Hours of IC Engine: see AFC Hrs/Day Days/Wk Wks/Yr Total Hrs/Yr	
14. Do you claim Confidentiality of Data (if yes, state nature of data in attachment)? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
15. Signature of Responsible Official: 		Official Title: General Manager	
Typed or Printed Name of Responsible Official: Emiliano Garcia		Phone Number: (303) 925-8500	Date Signed: 7-20-09
- For District Use Only -			
Application Number:	Invoice Number:	Permit Number:	Company/Facility Number:

MOJAVE DESERT AIR QUALITY MANAGEMENT DISTRICT
I.C.E. APPLICATION, continued

Page 2 of 2: please type or print

16. INFORMATION ON I.C.E.:

Manufacturer: Caterpillar - See mfg spec sheets in Appendix C.1
 Model No.: 3516C-HDTA Serial No.: _____
 Number of Cylinders: 16 Year of Manufacture: _____
 Rating: 4190 BHP Speed: 1800 RPM
 I.C.E. is? ☒ New ☐ Existing Date Installed (MM/YYYY): _____
 Prime ☐ Standby ☐ Emergency ☒ Portable (Yes or No)? _____
 CARB engine certification Family: _____ Certification EO#: _____
 Is this engine included in a Demand Response plan?: Yes ☐ No ☒
 Type of Fuel(s): Natural Gas ☐ Digester Gas ☐ Ethanol ☐ Landfill Gas ☐
 Propane ☐ CARB Diesel ☒ Methanol ☐ Other: _____
 Max fuel usage per hour: 173.3 Fuel units (ft³, gal, etc.): gal/hr

Engine Lat/Long or UTM Coordinates: see AFC

Exhaust Stack Height (feet): 46 Inside Diameter (inches): 12 Y/N: Vertical? Y Capped? N

Is this I.C.E. (select all that apply): see AFC Appendix C.1

Direct Injected? ☐ After Cooled? ☐
 Turbo Charged? ☐ Inter Cooled? ☐
 Timing Retarded? ☐ Other - Please specify: _____

17. EMISSION RATES:

Pollutant	at Max.Load	Units	Origin of Emission Rate data:	
			Manufacturer or	Source Test
Oxides of Nitrogen (NOx)	see AFC			
Oxides of Sulfur (SOx)				
Carbon Monoxide (CO)				
Particulates (PM10)				
Total Hydrocarbons (VOC)				

18. EMISSION CONTROL EQUIPMENT: Add on emission control equipment? ☐ Yes ☐ No

If yes: Manufacturer: _____ Model No.: _____
 Serial No.: _____ *CARB EO#: _____
 Type: SCR: ☐ Particulate Trap*: ☐ Ammonia Injection: ☐ Water Injection: ☐
 Non-S CR: ☐ Exhaust Gas Recirc*: ☐ Oxidation Catalyst*: ☐
 Other - Please specify: _____

19. INFORMATION OF ITEM BEING POWERED: This I.C.E. is used to power:

Electrical Generator ☒ Compressor ☐ Pump ☐
 Paint Spray Gun ☐ Conveyor or Drive ☐ Fire Pump ☐

Other - Please specify: _____

Manufacturer: _____
 Model No.: _____ Serial No.: _____
 Type, Size or Rating: 2500 kw


MOJAVE DESERT AIR QUALITY MANAGEMENT DISTRICT
 14306 Park Avenue, Victorville, CA 92392-2310
 (760) 245-1661 Facsimile: (760) 245-2022

www.mdaqmd.ca.gov
Eldon Heaston
 Executive Director

APPLICATION FOR INTERNAL COMBUSTION ENGINE (I.C.E.) ONLY

Page 1 of 2: please type or print

REMIT \$226.00 WITH THIS DOCUMENT (\$129.00 FOR CHANGE OF OWNER)

1. Permit To Be Issued To (company name to receive permit): Mojave Solar LLC		1a. Federal Tax ID No.:
2. Mailing/Billing Address (for above company name): 13911 Park Avenue, Suite 206, Victorville, CA 92392-2407		
3. Facility or Business License Name (for equipment location): Mojave Solar LLC		
4. Facility Address - Location of Equipment (if same as for company, enter "Same"): No address yet, use "same"		Facility UTM or Lat/Long: 470036, 3874396
5. Contact Name/Title: Emiliano Garcia, Manager	Email Address: emiliano.garcia@solar.a bengoa.com	Phone/Fax Nos.: P: (303) 925-8500 / F: (303) 928- 8510
6. Application is hereby made for Authority To Construct (ATC) and Permit To Operate (PTO) the following equipment: Fire Pump Engine #1		
7. Application is for: <input checked="" type="checkbox"/> New Construction <input type="checkbox"/> Modification* <input type="checkbox"/> Change of Owner*		For modification or change of owner: *Current Permit Number: _____
8. Type of Organization (check one): <input type="checkbox"/> Individual Owner <input type="checkbox"/> Partnership <input checked="" type="checkbox"/> Corporation <input type="checkbox"/> Utility <input type="checkbox"/> Local Agency <input type="checkbox"/> State Agency <input type="checkbox"/> Federal Agency		
9. Distances (feet and direction to closest): see AFC _____ Fenceline _____ Residence _____ Business _____ School _____		
10. General Nature of Business: Solar Power Generating Facility		11. Principal Product: Electrical Power
12. Facility Annual Throughput by Quarters (percent): see AFC % _____ % _____ % _____ % Jan-Mar Apr-Jun Jul-Sep Oct-Dec		13. Expected Operating Hours of IC Engine: see AFC Hrs/Day Days/Wk Wks/Yr Total Hrs/Yr
14. Do you claim Confidentiality of Data (if yes, state nature of data in attachment)? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
15. Signature of Responsible Official: 		Official Title: General Manager
Typed or Printed Name of Responsible Official: Emiliano Garcia		Phone Number: (303) 925-8500 Date Signed: 7-20-09
- For District Use Only -		
Application Number:	Invoice Number:	Permit Number: Company/Facility Number:

MOJAVE DESERT AIR QUALITY MANAGEMENT DISTRICT
I.C.E. APPLICATION, continued

Page 2 of 2: please type or print

16. INFORMATION ON I.C.E.:

Manufacturer: John Deere - See AFC Appendix C.1 for mfg data
 Model No.: 6090H Serial No.: _____
 Number of Cylinders: 6 Year of Manufacture: _____
 Rating: 346 BHP Speed: _____ RPM
 I.C.E. is? ☒ New ☐ Existing Date Installed (MM/YYYY): _____
 Prime ☐ Standby ☐ Emergency ☒ Portable (Yes or No)? _____
 CARB engine certification Family: _____ Certification EO#: _____
 Is this engine included in a Demand Response plan?: Yes ☐ No ☒
 Type of Fuel(s): Natural Gas ☐ Digester Gas ☐ Ethanol ☐ Landfill Gas ☐
 Propane ☐ CARB Diesel ☒ Methanol ☐ Other: _____
 Max fuel usage per hour: 7.6 Fuel units (ft³, gal, etc.): gal/hr

Engine Lat/Long or UTM Coordinates: see AFC

Exhaust Stack Height (feet): 46 Inside Diameter (inches): 8 Y/N: Vertical? Y Capped? N

Is this I.C.E. (select all that apply): see AFC

Direct Injected? ☐ After Cooled? ☐
 Turbo Charged? ☐ Inter Cooled? ☐
 Timing Retarded? ☐ Other - Please specify: _____

17. EMISSION RATES:

Pollutant	at Max.Load	Units	Origin of Emission Rate data:	
			Manufacturer or	Source Test
Oxides of Nitrogen (NOx)	<u>see AFC</u>	_____	_____	_____
Oxides of Sulfur (SOx)	_____	_____	_____	_____
Carbon Monoxide (CO)	_____	_____	_____	_____
Particulates (PM10)	_____	_____	_____	_____
Total Hydrocarbons (VOC)	_____	_____	_____	_____

18. EMISSION CONTROL EQUIPMENT: Add on emission control equipment? ☐ Yes ☐ No

If yes: Manufacturer: _____ Model No.: _____
 Serial No.: _____ *CARB EO#: _____
 Type: SCR: ☐ Particulate Trap*: ☐ Ammonia Injection: ☐ Water Injection: ☐
 Non-S CR: ☐ Exhaust Gas Recirc*: ☐ Oxidation Catalyst*: ☐
 Other - Please specify: _____

19. INFORMATION OF ITEM BEING POWERED: This I.C.E. is used to power:

Electrical Generator ☐ Compressor ☐ Pump ☐
 Paint Spray Gun ☐ Conveyor or Drive ☐ Fire Pump ☒

Other - Please specify: _____
 Manufacturer: _____
 Model No.: _____ Serial No.: _____
 Type, Size or Rating: _____


MOJAVE DESERT AIR QUALITY MANAGEMENT DISTRICT
 14306 Park Avenue, Victorville, CA 92392-2310
 (760) 245-1661 Facsimile: (760) 245-2022

www.mdaqmd.ca.gov
Eldon Heaston
 Executive Director

APPLICATION FOR INTERNAL COMBUSTION ENGINE (I.C.E.) ONLY

Page 1 of 2: please type or print

REMIT \$226.00 WITH THIS DOCUMENT (\$129.00 FOR CHANGE OF OWNER)

1. Permit To Be Issued To (company name to receive permit): Mojave Solar LLC		1a. Federal Tax ID No.:
2. Mailing/Billing Address (for above company name): 13911 Park Avenue, Suite 206, Victorville, CA 92392-2407		
3. Facility or Business License Name (for equipment location): Mojave Solar LLC		
4. Facility Address - Location of Equipment (if same as for company, enter "Same"): No address yet, use "same"		Facility UTM or Lat/Long: 470036, 3874396
5. Contact Name/Title: Emiliano Garcia, Manager	Email Address: emiliano.garcia@solar.a bengoa.com	Phone/Fax Nos.: P: (303) 925-8500 / F: (303) 928- 8510
6. Application is hereby made for Authority To Construct (ATC) and Permit To Operate (PTO) the following equipment: Fire Pump Engine #2		
7. Application is for: <input checked="" type="checkbox"/> New Construction <input type="checkbox"/> Modification* <input type="checkbox"/> Change of Owner*		For modification or change of owner: *Current Permit Number: _____
8. Type of Organization (check one): <input type="checkbox"/> Individual Owner <input type="checkbox"/> Partnership <input checked="" type="checkbox"/> Corporation <input type="checkbox"/> Utility <input type="checkbox"/> Local Agency <input type="checkbox"/> State Agency <input type="checkbox"/> Federal Agency		
9. Distances (feet and direction to closest): see AFC _____ Fenceline _____ Residence _____ Business _____ School _____		
10. General Nature of Business: Solar Power Generating Facility		11. Principal Product: Electrical Power
12. Facility Annual Throughput by Quarters (percent): see AFC % _____ % _____ % _____ % Jan-Mar Apr-Jun Jul-Sep Oct-Dec		13. Expected Operating Hours of IC Engine: see AFC Hrs/Day Days/Wk Wks/Yr Total Hrs/Yr
14. Do you claim Confidentiality of Data (if yes, state nature of data in attachment)? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
15. Signature of Responsible Official: 		Official Title: General Manager
Typed or Printed Name of Responsible Official: Emiliano Garcia		Phone Number: (303) 925-8500 Date Signed: 7-20-09
- For District Use Only -		
Application Number:	Invoice Number:	Permit Number: Company/Facility Number:

MOJAVE DESERT AIR QUALITY MANAGEMENT DISTRICT
I.C.E. APPLICATION, continued

Page 2 of 2: please type or print

16. INFORMATION ON I.C.E.:

Manufacturer: John Deere - See AFC Appendix C.1 for mfg data
 Model No.: 6090H Serial No.: _____
 Number of Cylinders: 6 Year of Manufacture: _____
 Rating: 346 BHP Speed: _____ RPM
 I.C.E. is? ☒ New ☐ Existing Date Installed (MM/YYYY): _____
 Prime ☐ Standby ☐ Emergency ☒ Portable (Yes or No)? _____
 CARB engine certification Family: _____ Certification EO#: _____
 Is this engine included in a Demand Response plan?: Yes ☐ No ☒
 Type of Fuel(s): Natural Gas ☐ Digester Gas ☐ Ethanol ☐ Landfill Gas ☐
 Propane ☐ CARB Diesel ☒ Methanol ☐ Other: _____
 Max fuel usage per hour: 7.6 Fuel units (ft³, gal, etc.): gal/hr
 Engine Lat/Long or UTM Coordinates: see AFC
 Exhaust Stack Height (feet): 46 Inside Diameter (inches): 8 Y/N: Vertical? Y Capped? N
 Is this I.C.E. (select all that apply): see AFC
 Direct Injected? ☐ After Cooled? ☐
 Turbo Charged? ☐ Inter Cooled? ☐
 Timing Retarded? ☐ Other - Please specify: _____

17. EMISSION RATES:

Pollutant	at Max.Load	Units	Origin of Emission Rate data:	
			Manufacturer or	Source Test
Oxides of Nitrogen (NOx)	see AFC			
Oxides of Sulfur (SOx)				
Carbon Monoxide (CO)				
Particulates (PM10)				
Total Hydrocarbons (VOC)				

18. EMISSION CONTROL EQUIPMENT: Add on emission control equipment? ☐ Yes ☐ No

If yes: Manufacturer: _____ Model No.: _____
 Serial No.: _____ *CARB EO#: _____
 Type: SCR: ☐ Particulate Trap*: ☐ Ammonia Injection: ☐ Water Injection: ☐
 Non-S CR: ☐ Exhaust Gas Recirc*: ☐ Oxidation Catalyst*: ☐
 Other - Please specify: _____

19. INFORMATION OF ITEM BEING POWERED: This I.C.E. is used to power:

Electrical Generator ☐ Compressor ☐ Pump ☐
 Paint Spray Gun ☐ Conveyor or Drive ☐ Fire Pump ☒

Other - Please specify: _____
 Manufacturer: _____
 Model No.: _____ Serial No.: _____
 Type, Size or Rating: _____

APPENDIX J

NOISE

APPENDIX J

ACOUSTIC FUNDAMENTALS

Acoustics is the scientific study that evaluates perception, propagation, absorption, and reflection of sound waves. Sound is a mechanical form of radiant energy, transmitted by a pressure wave through a solid, liquid, or gaseous medium. Sound that is loud, disagreeable, unexpected, or unwanted is generally defined as noise; consequently, the perception of sound is subjective in nature and can vary substantially from person to person. Common sources of environmental noise and noise levels are presented in Table J-1.

A sound wave is initiated in a medium by a vibrating object (e.g., vocal chords, the string of a guitar, the diaphragm of a radio speaker). The wave consists of minute variations in pressure, oscillating above and below the ambient atmospheric pressure. The number of pressure variation cycles occurring per second is referred to as the frequency of the sound wave and is expressed in hertz.

Directly measuring sound pressure fluctuations would require the use of a very large and cumbersome range of numbers. To avoid this and have a more usable numbering system, the decibel (dB) scale was introduced. A sound level expressed in decibels is the logarithmic ratio of two like pressure quantities, with one pressure quantity being a reference sound pressure. For sound pressure in air the standard reference quantity is generally considered to be 20 micropascals, which directly corresponds to the threshold of human hearing. The use of the decibel is a convenient way to handle the millionfold range of sound pressures to which the human ear is sensitive. A decibel is logarithmic; it does not follow normal algebraic methods and cannot be directly added. For example, a 65-dB source of sound, such as a truck, when joined by another 65-dB source results in a sound amplitude of 68 dB, not 130 dB (i.e., doubling the source strength increases the sound pressure by 3 dB). A sound level increase of 10 dB corresponds to 10 times the acoustical energy, and an increase of 20 dB equates to a hundredfold increase in acoustical energy.

The loudness of sound perceived by the human ear depends primarily on the overall sound pressure level and frequency content of the sound source. The human ear is not equally sensitive to loudness at all frequencies in the audible spectrum. To better relate overall sound levels and loudness to human perception, frequency-dependent weighting networks were developed. The standard weighting networks are identified as A through E. There is a strong correlation between the way humans perceive sound and A-weighted sound levels (dBA). For this reason the A-weighted sound level can be used to predict community response to noise from the environment,

including noise from transportation and stationary sources. Sound levels expressed as dB in this section are A-weighted sound levels, unless noted otherwise.

Table J-1. Typical A-Weighted Noise Levels

Common Outdoor Activities	Noise Level (dBA)	Common Indoor Activities
Jet fly-over at 1000 feet	— 110 —	Rock band
Gas lawn mower at 3 feet	— 100 —	
Diesel truck at 50 feet at 50 mph	— 90 —	Food blender at 3 feet
Noisy urban area, daytime	— 80 —	Garbage disposal at 3 feet
Gas lawn mower, 100 feet	— 70 —	Vacuum cleaner at 10 feet
Commercial area		Normal speech at 3 feet
Heavy traffic at 300 feet	— 60 —	Large business office
Quiet urban daytime	— 50 —	Dishwasher next room
Quiet urban nighttime	— 40 —	Theater, large conference room (background)
Quiet suburban nighttime	— 30 —	Library
Quiet rural nighttime	— 20 —	Bedroom at night, concert
	— 10 —	Broadcast/recording studio
Lowest threshold of human hearing	— 0 —	Lowest threshold of human hearing

Source: Caltrans 2009a

Noise can be generated by a number of sources, including mobile sources (transportation noise sources) such as automobiles, trucks, and airplanes and stationary sources (nontransportation

noise sources) such as construction sites, machinery, and commercial and industrial operations. As acoustic energy spreads through the atmosphere from the source to the receiver, noise levels attenuate (decrease) depending on ground absorption characteristics, atmospheric conditions, and the presence of physical barriers (walls, building facades, berms). Noise generated from mobile sources generally attenuate at a rate of 4.5 dB per doubling of distance (dB/DD). Stationary noise sources spread with more spherical dispersion patterns that attenuate at a rate of 6 dB to 7.5 dB/DD.

Atmospheric conditions such as wind speed, turbulence, temperature gradients, and humidity may additionally alter the propagation of noise and affect levels at a receiver. Furthermore, the presence of a large object (e.g., barrier, topographic features, and intervening building façades) between the source and the receptor can provide significant attenuation of noise levels at the receiver. The amount of noise level reduction or “shielding” provided by a barrier primarily depends on the size of the barrier, the location of the barrier in relation to the source and receivers, and the frequency spectra of the noise. Natural barriers such as berms, hills, or dense woods, and human-made features such as buildings and walls may be used as noise barriers.

Noise Descriptors

The intensity of environmental noise fluctuates over time, and several different descriptors of time-averaged noise levels are used. The selection of a proper noise descriptor for a specific source depends on the spatial and temporal distribution, duration, and fluctuation of both the noise source and the environment. The noise descriptors most often used to describe environmental noise are defined below:

- **L_{max}** (Maximum Noise Level): The highest A/B/C weighted integrated noise level occurring during a specific period of time.
- **L_{min}** (Minimum Noise Level): The lowest A/B/C weighted integrated noise level during a specific period of time.
- **Peak**: The highest weighted or unweighted instantaneous peak-to-peak value occurring during a measurement period.
- **L_n** (Statistical Descriptor): The noise level exceeded n% of a specific period of time, generally accepted as an hourly statistic. An L₁₀ would be the noise level exceeded 10% of the measurement period.
- **L_{eq}** (Equivalent Noise Level): The energy mean (average) noise level. The steady state sound level which, in a specified period of time contains the same acoustical energy as a varying sound level over the same time period.

- **L_{dn}** (Day-Night Noise Level): The 24-hour L_{eq} with a 10-dB “penalty” applied during nighttime noise-sensitive hours, 10:00 p.m. through 7:00 a.m. The L_{dn} attempts to account for the fact that noise during this specific period of time is a potential source of disturbance with respect to normal sleeping hours.
- **CNEL** (Community Noise Equivalent Level): The CNEL is similar to the L_{dn} described above, but with an additional 5-dB “penalty” for the noise-sensitive hours between 7:00 p.m. to 10:00 p.m., which are typically reserved for relaxation, conversation, reading, and television. If using the same 24-hour noise data, the CNEL is typically 0.5 dB higher than the L_{dn} .
- **SEL** (Sound Exposure Level): The SEL describes the cumulative exposure to sound energy over a stated period of time.
- **SENEL** (Single Event Noise Exposure Level): An SEL where the measurement period is defined by the start and end times of a single noise event, such as an automobile passby, aircraft flyover, or individual industrial operations.

EFFECTS OF NOISE ON HUMANS

Excessive and chronic exposure to elevated noise levels can result in auditory and nonauditory effects in humans. Auditory effects of noise on people are those relating to temporary or permanent hearing loss caused by loud noises. Nonauditory effects of exposure to elevated noise levels are those relating to behavioral and physiological effects. The nonauditory behavioral effects of noise on humans is primarily associated with the subjective effects of annoyance, nuisance, and dissatisfaction; which lead to interference with activities such as communications, sleep, and learning. The nonauditory physiological health effects of noise on humans has been the subject of considerable research efforts attempting to discover correlations between exposure to elevated noise levels and health problems, such as hypertension and cardiovascular disease. The mass of research infers that noise-related health issues are predominantly the result of behavioral stressors and not a direct noise-induced response. The extent to which noise contributes to nonauditory health effects remains a subject of considerable research, with no definitive conclusions.

The degree to which noise results in annoyance and interference is highly subjective and may be influenced by a number of nonacoustic factors. The number and effect of these nonacoustic environmental and physical factors vary depending on individual characteristics of the noise environment such as sensitivity, level of activity, location, time of day, and length of exposure. One key aspect in the prediction of human response to new noise environments is the individual level of adaptation to an existing noise environment. The greater the change in the noise levels that are attributed to a new noise source, relative to the environment an individual has become accustomed too, the less tolerable the new noise source will be viewed.

A change in sound level of 1 dB is generally not perceivable by humans, excluding controlled conditions and pure tones. Outside of controlled laboratory conditions the average human ear barely perceives a change of 3 dB. A change of 5 dB generally fosters a noticeable change in human response, and an increase of 10 dB is subjectively heard as a doubling of loudness.

APPENDIX K

GEOLOGY AND SOILS

**GEOTECHNICAL EVALUATION
MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA**

PREPARED FOR:

Mojave Solar, LLC
13911 Park Avenue, Suite 206
Victorville, California 92392

PREPARED BY:

Ninyo & Moore
Geotechnical and Environmental Sciences Consultants
5710 Ruffin Road
San Diego, California 92123

May 15, 2009
Project No. 105879004

May 15, 2009
Project No. 105879004


Mr. Scott Frier
Mojave Solar, LLC
13911 Park Avenue, Suite 206
Victorville, California 92392

Subject: Geotechnical Evaluation
Mojave Solar Project
Lockhart, California

Dear Mr. Frier:

In accordance with your authorization, we have performed a geotechnical evaluation for the proposed Mojave Solar Project in Lockhart, California. This report presents our geotechnical findings, conclusions, and recommendations regarding the proposed project. Our report was prepared in accordance with our proposal dated January 22, 2009. We appreciate the opportunity to be of service on this project.


Sincerely,
NINYO & MOORE


Andres Bernal, G.E.
Senior Project Engineer




Francis O. Moreland, C.E.G.
Senior Geologist




Gregory T. Farrand, C.E.G.
Principal Geologist

FOM/ABS/GTF/gg

Distribution: (2) Addressee
(3) Mr. Frederick Redell; Redell Engineering, Inc.

TABLE OF CONTENTS

	<u>Page</u>
1. INTRODUCTION	1
2. SCOPE OF SERVICES	1
3. SITE DESCRIPTION	2
4. PROJECT DESCRIPTION.....	2
5. FIELD EXPLORATION AND LABORATORY TESTING.....	4
5.1. Exploratory Borings.....	4
5.2. Exploratory Test Pits	4
5.3. Laboratory Testing.....	4
5.4. Fault Trench.....	5
5.5. Percolation Testing	5
5.6. Geophysical Survey	5
6. GEOLOGY AND SUBSURFACE CONDITIONS	6
6.1. Regional Geologic Setting	6
6.2. Site Geology	7
6.2.1. Lake Deposits.....	7
6.2.2. Older Alluvium	7
6.3. Groundwater	7
6.4. Faulting and Seismicity	8
6.4.1. Surface Fault Rupture	9
6.4.2. Ground Motion.....	9
6.4.3. Liquefaction	10
6.4.4. Dynamic Settlement of Saturated Soils.....	11
6.4.5. Ground Subsidence	12
6.4.6. Lateral Spread	12
6.4.7. State of California Earthquake Fault Zone.....	12
6.5. Landsliding	13
6.6. Subsidence Due to Groundwater Withdrawal	14
7. CONCLUSIONS	14
8. RECOMMENDATIONS.....	15
8.1. Earthwork	15
8.1.1. Site Preparation	15
8.1.2. Excavation Characteristics	16
8.1.3. Remedial Grading for Building Pad and Equipment Areas	16
8.1.4. Remedial Grading for Exterior Flatwork	17
8.1.5. Materials for Fill	17
8.1.6. Compacted Fill	18
8.1.7. Slopes	19

8.1.8.	Temporary Excavation and Shoring.....	19
8.1.9.	Drainage	20
8.2.	Seismic Design Considerations	21
8.3.	Foundations.....	21
8.3.1.	Shallow Footings.....	22
8.3.2.	Lateral Resistance	22
8.3.3.	Static Settlement	22
8.3.4.	Mat Foundations.....	22
8.4.	Deep Foundations	23
8.4.1.	Axial Pile Capacity	24
8.4.2.	Lateral Capacity	24
8.4.3.	Construction Considerations for Cast-In-Drilled-Hole (CIDH) Piles	26
8.5.	Slab-on-Grade.....	28
8.6.	Concrete Flatwork.....	28
8.7.	Preliminary Pavement Design.....	29
8.8.	Corrosion	30
8.9.	Concrete Placement	30
9.	LIMITATIONS.....	31
10.	REFERENCES	33

Tables

Table 1 – Principal Active Faults	8
Table 2 – 2007 California Building Code Seismic Design Criteria.....	21
Table 3 – Axial Pile Capacity Evaluation	24
Table 4 – Lateral Load Capacity 18-inch-diameter CIDH Pile	25
Table 5 – Summary of Single Pile Lateral Load Capacity 24-inch-diameter CIDH Pile.....	25
Table 6 – Summary of Single Pile Lateral Load Capacity 60-inch-diameter CIDH Pile.....	26
Table 7 – Lateral Load Group Reduction Factors.....	26
Table 8 – Recommended Pavement Sections	29

Figures

Figure 1 – Site Location Map	
Figure 2 – Geotechnical Map	
Figure 3 – Fault Location Map	
Figure 4 – Special Studies Zone Map	
Figure 5 – Acceleration Response Spectra	

Appendices

Appendix A – Boring and Test Pit Logs
Appendix B – Laboratory Testing
Appendix C – Fault Trench Log
Appendix D – Percolation Testing Results
Appendix E – Resistivity Survey
Appendix F – Typical Earthwork Guidelines

1. INTRODUCTION

In accordance with your request and our proposal dated January 22, 2009, we have performed a geotechnical evaluation for the proposed Mojave Solar Project (MSP) located in Lockhart, California (Figure 1). We previously performed a preliminary geotechnical evaluation (Ninyo & Moore, 2007), and an updated preliminary geotechnical and fault hazard evaluation (Ninyo & Moore, 2008) for the Harper Lake Solar project, which occupied a smaller site than the current project. The results of our previous evaluations are incorporated into this report. This report presents our conclusions regarding the geotechnical conditions at the subject site and our recommendations for the design of this project.

2. SCOPE OF SERVICES

Ninyo & Moore's scope of services for this project included review of pertinent background data, performance of a geologic reconnaissance, subsurface evaluation, fault evaluation, and engineering analysis with regard to the proposed project. Specifically, we performed the following tasks:

- Reviewing background data listed in the Selected References section of this report. The data reviewed included geotechnical reports, topographic maps, geologic data, fault maps, and a site plan for the project.
- Performing a geologic reconnaissance of the proposed site, including the observation and mapping of geologic conditions and the evaluation of possible geologic hazards which may impact the proposed project.
- Marking of proposed exploratory excavation locations prior to contacting Underground Service Alert (USA) for utility clearance.
- Performing subsurface exploration consisting of excavation, logging, and sampling of 68 exploratory borings and eight exploratory test pits. Bulk samples were collected at selected intervals and transported to our laboratory for testing.
- Performing a fault evaluation consisting of the excavation, logging, sampling, and observation of one fault trench.
- Performing five electrical resistivity surveys.
- Performing six percolation tests.

- Performing geotechnical laboratory testing of selected samples.
- Preparing this report presenting our findings, conclusions, and recommendations for the design of the project.

3. SITE DESCRIPTION

The MSP project site is located east and west of Harper Lake Road and north and south of Lockhart Road near the town of Lockhart, in San Bernardino County, California. The property includes Section 33 and portions of Sections 28, 29, 30, and 32 within Township 11N - Range 4W, San Bernardino Base Meridian (SBBM). The site is relatively flat with a gentle downward slope toward Harper Lake to the northeast. Portions of the property have been used for agricultural purposes in the past but have now been fallow for several years. Structures on the site consist of an abandoned general store with basement, buildings and structures associated with an alfalfa processing plant, several farm houses, barns, and out buildings, several reservoirs and cisterns, irrigation equipment, and several wells. Elevations on the main solar project site range from approximately 2,020 feet above mean sea level (MSL) near the northeastern end of the site on Harper Lake, to approximately 2,105 feet MSL at the southwest corners of Sections 30 and 33. Vegetation generally consists of a sparse to moderate growth of weeds and brush, and moderately sized trees at farm house sites and used as windbreaks.

4. PROJECT DESCRIPTION

The site is proposed as a solar power project utilizing solar thermal technology. The project is divided into two main areas designated Alpha and Beta. Major solar equipment improvements at the Alpha and Beta areas are expected to consist of:

- Parabolic trough solar array installation, including:
 - Placement of foundations to support the solar arrays
 - Heat transfer fluid piping with support foundations
- Power Block, including:
 - Steam turbine generator(s)
 - Steam generator/thermal storage
 - Condenser and cooling tower

- Switchyard and transmission poles
 - Control, equipment, and administration buildings
- Ancillary Equipment/Facilities, including:
 - Emergency power source
 - Water/wastewater treatment facilities

The parabolic trough solar array collector field is modular in nature and comprises many parallel rows of single-axis-tracking parabolic trough solar collectors. The solar collectors are aligned on a north-south direction and will be supported by foundations designed to withstand the anticipated loading for the installation. Each solar collector has a parabolic-shaped reflector that focuses the sun's direct beam radiation on a linear receiver pipe located at the focus of the parabola. The reflectors are mobile and track the sun from east to west during the diurnal cycle to ensure that the sun is continuously focused on the linear receiver.

The heat transfer fluid is heated up to approximately 750° F as it circulates through piping along the solar array collector field and returns to the power block. The heat transfer fluid piping is then routed to a steam generator where the fluid is used to produce high-pressure steam for turbine electricity generators.

Cooling for the plant will include a cooling tower designed to diffuse the low quality heat from the process. The cooling tower will be installed on the power block near the condenser. Water treatment for the process water will be housed in a water treatment building on the power block. Should the plant be water-cooled, blow-down water from the wet cooling tower will be routed to lined evaporation ponds to be located at a lower elevation than the cooling tower and likely near the northern end of the site; no evaporation ponds would be needed if dry cooling is used.

The project will include an emergency power source, either from a back feed of the on-site switchyard with a dedicated transformer, or from an emergency generator; which will be used to safely shut down the system in the event of a power failure. This system along with the rest of the power plant will be monitored and controlled from the control room building located near the power block.

5. FIELD EXPLORATION AND LABORATORY TESTING

Our field exploration of the subject site included a geologic reconnaissance and subsurface exploratory work conducted on June 7, and August 24 through August 30, 2006, and April 2 through 10, 2009. The boring, test pit, trench, percolation testing, and resistivity survey locations were selected based on the results of our background geotechnical review, field reconnaissance, and the proposed project elements presented in the Mojave Solar One site plan prepared by Merrell Johnson Engineering (2009). Prior to commencing the subsurface exploration, USA was notified for mark-out of the existing utilities. The purpose of the borings and test pits was to evaluate subsurface conditions and to collect soil samples for laboratory testing. The purpose of the fault trench was to evaluate for the presence of active faulting. The approximate locations of the borings, test pits, percolation testing, resistivity surveys, and the fault trench are shown on Figure 2.

5.1. Exploratory Borings

The subsurface evaluation consisted of drilling 68 borings with 8-inch diameter augers. The borings were drilled with a truck-mounted, continuous flight hollow-stem auger drill. Samples were collected at selected depths and were transported to our laboratory for testing. Boring depths ranged from approximately 11.5 to 51.5 feet. Detailed logs of the borings are presented in Appendix A.

5.2. Exploratory Test Pits

Eight exploratory test pits were excavated to depths of up to approximately 13 feet. The test pits were excavated using a JCB 215S rubber-tire backhoe with a 24-inch bucket. Bulk samples were collected at selected depths and were transported to our laboratory for testing. The test pits were backfilled with excavated soils. Detailed logs of the test pits are presented in Appendix A.

5.3. Laboratory Testing

Laboratory testing of representative soils samples included in-situ dry density and moisture content, grain size analysis, Atterberg limits, consolidation, shear strength, expansion index,

soil corrosivity tests, and R-value. The results of the in-situ dry density and moisture testing are presented on the boring logs presented in Appendix A. The results of other laboratory tests performed are presented in Appendix B.

5.4. Fault Trench

An Alquist-Priolo earthquake fault zone has been mapped extending into the northeastern corner of the site. An exploratory fault trench was excavated across the mapped fault zone to evaluate the presence of an active fault within this area. The exploratory fault trench was excavated to a depth of approximately 6 feet and had a length of approximately 1,400 feet. The trench was excavated using a CAT 420 rubber-tired backhoe with a 24-inch bucket. The fault trench log was prepared by scraping the trench sidewalls to produce a fresh surface and mapping the northern face of the trench as shown in Appendix C. The fault trench was back-filled with spoils near the optimum moisture content and compacted to a relative compaction of 90 percent, as evaluated by American Society for Testing and Materials (ASTM) D 1557.

5.5. Percolation Testing

Six percolation tests were performed at the site on April 6 and 9, 2009 in proposed evaporation pond and land farm locations. These percolation test locations are shown on Figure 2 as PT-1 through PT-6. The results of our percolation testing and a description of the field procedure are presented in Appendix D.

5.6. Geophysical Survey

On April 10, 2009 five soil electrical resistivity surveys, shown on Figure 2 as R-1 through R-5, were performed at the power blocks and interconnect substation sites in the Alpha and Beta areas of the project. The data were collected in general accordance with the ASTM Test Method G57 using an Advanced Geosciences, Inc. Supersting R8 earth resistivity meter and four electrodes in a Wenner configuration. Soil resistivity measurements were collected at electrode spacings of 2, 5, 10, 15, 20, 30, 40, 50, 60, and 80 feet (except for R-1 with a

maximum spacing of 60 feet), along two perpendicular traverses. The results of the resistivity survey and details regarding the data collection are presented in Appendix E. In general, the resistivity data collected are of good quality, with good agreement between orthogonal traverses indicating a fairly homogenous medium.

6. GEOLOGY AND SUBSURFACE CONDITIONS

Our findings regarding regional and site geology and groundwater conditions at the subject site are provided in the following sections.

6.1. Regional Geologic Setting

The project area is situated in the eastern portion of the Mojave Desert Geomorphic Province. This geomorphic province encompasses an area that extends approximately 250 miles from the intersection of the San Andreas and Garlock Faults on the west to the Nevada and Arizona borders on the east. The western end of the province is bounded by the San Andreas and Garlock Faults. The province is up to 100 miles wide and is generally bounded by the Garlock Fault, Tehachapi Mountains, and Basin and Range to the north and to the south by the Transverse Ranges (Norris and Webb, 1990). In general, the province consists of broad alluviated valleys underlain by sedimentary, metamorphic, and igneous rocks. The Mojave Desert Province within the project area generally consists of Tertiary- and Quaternary-age igneous and sedimentary rock, and older alluvium.

The Mojave Desert Province is traversed by a group of sub-parallel faults and fault zones trending roughly northwest. Several of these faults, shown on Figure 3, are considered active faults. The Lenwood-Lockhart, Helendale, San Andreas, and Garlock faults are active fault systems located northwest and southwest of the project area. The Harper Lake Fault Zone, and Blackwater and Calico faults are active fault systems located northeast and east of the project area. An unnamed active fault, which has been mapped as a State of California Special Studies Zone, extends through the northeastern portion of the project site (Figure 4). Major tectonic activity associated with these and other faults within this regional tectonic frame-

work consists primarily of strike-slip (lateral) movement. Further discussion of faulting relative to the site is provided in the Faulting and Seismicity section of this report.

6.2. Site Geology

Geologic units observed during our subsurface exploration included lake deposits and older alluvium. Generalized descriptions of the earth units are provided in the subsequent sections.

6.2.1. Lake Deposits

Lake deposits were encountered in test pit TP-3, located on the northeastern corner of the proposed solar project site where it extends onto Harper Lake. As observed, the lake deposits generally consisted of damp to saturated, loose to medium dense, silt and sand, and soft to firm clay. Salt deposition was common on the surface of the lake deposits.

6.2.2. Older Alluvium

Older alluvium underlies the project site, except in the vicinity of test pit TP-3 which was excavated in the Harper Lake area. As encountered, the alluvium generally consists of damp to saturated, loose to very dense, silty and clayey fine to coarse sand with occasional layers of gravel, silt and clay, and wet, hard, fine sandy and silty clay. Some layers of caliche consisting of strongly cemented layers of sand and silt were encountered in several of the test pits.

6.3. Groundwater

Groundwater was encountered in test pits TP-3 and TP-5 and boring B-10 in the vicinity of Harper Lake at depths of approximately 4, 9 and 10 feet, respectively. Groundwater was encountered in borings B-35 and B-44 in the Alpha power block at depths of approximately 32 and 33 feet, respectively, and in borings B-53 and B-62 in the Beta power block at depths of approximately 27 and 31 feet, respectively. Based on our review of groundwater depth records for nearby wells (California Department of Water Resources, 2009), we anticipate that the regional groundwater table at the subject site is at a depth of more than 100 feet. However, according to our observations, perched groundwater may be encountered at a depth of approximately 4 feet below

the ground surface (bgs) in the vicinity of Harper Lake and at a depth of approximately 27 feet bgs in the Alpha and Beta power blocks. Fluctuations in the groundwater level may occur due to variations in water levels in Harper Lake, rainfall, irrigation, groundwater pumping, ground surface topography, subsurface geologic conditions and structure, and other factors.

6.4. Faulting and Seismicity

The project site is located in a seismically active area, as is the majority of southern California, and the potential for strong ground motion in the project area is considered significant during the design life of the proposed structures. In addition, a portion of the subject site is located within a State of California Earthquake Fault Zone (formerly known as an Alquist-Priolo Special Studies Zone). Figure 3 shows the approximate site location relative to the major faults in the region. The active Lenwood-Lockhart-Old Woman Springs fault is located approximately 2,300 feet southwest of the site.

Table 1 lists selected principal known active faults that may affect the subject site, the approximate fault-to-site distances, and the maximum moment magnitude (M_{max}) as published by the Cao, et al. (2003) for the California Geological Survey (CGS). The approximate fault-to-site distances were calculated using the computer program FRISKSP (Blake, 2001).

Table 1 – Principal Active Faults

Fault	Approximate Fault-to-Site Distance ¹ miles (kilometers)	Maximum Moment Magnitude ² (M_{max})
Lenwood-Lockhart-Old Woman Springs	2,300 ft (0.7)	7.5
Helendale - S. Lockhardt	6.6 (10.6)	7.3
Gravel Hills - Harper Lake	9.0 (14.5)	7.1
Blackwater	15.4 (24.7)	7.1
Calico - Hidalgo	24.2 (39.0)	7.3
Landers	32.3 (52.0)	7.3
Garlock (East)	34.3 (55.2)	7.5
Garlock (West)	41.6 (66.9)	7.3
San Andreas (Mojave)	47.7 (76.7)	7.4
San Andreas (San Bernardino)	50.6 (81.4)	7.5
Notes: ¹ Blake, 2001 ² Cao, et al., 2003		

The principal seismic hazards at the subject site are surface fault rupture, ground motion, liquefaction, dynamic settlement, dynamic compaction, ground subsidence, lateral spreading, and landslides. A brief description of these hazards and the potential for their occurrences on site are discussed below.

6.4.1. Surface Fault Rupture

Based on our review of the referenced literature and our site reconnaissance, the project site is located in close proximity to the Lenwood-Lockhart-Old Woman Springs fault. Therefore, the probability of damage from surface fault rupture is considered to be moderate at the site. Significant potential for lurching or cracking of the ground surface also exists.

6.4.2. Ground Motion

The 2007 California Building Code (CBC) recommends that the design of structures be based on the horizontal peak ground acceleration (PGA) having a 2 percent probability of exceedance in 50 years which is defined as the Maximum Considered Earthquake (MCE). The statistical return period for PGA_{MCE} is approximately 2,475 years. In addition, 2007 CBC recommends that a site-specific ground motion analysis should be performed for sites located within 10 km of an active fault. The site-specific ground motion analysis includes probabilistic and deterministic methods in conformance with American Society of Civil Engineers (ASCE) 7-05 guidelines.

The site-specific probabilistic seismic hazard analysis (PSHA) was performed using the computer program FRISKSP developed by Blake (2001). The probabilistic analysis incorporates uncertainties in time, recurrence intervals, size, and location (along faults) of hypothetical earthquakes. This method thus accounts for likelihood (rather than certainty) of occurrence and provides levels of ground acceleration that might be more reasonably hypothesized for a finite exposure period. FRISKSP calculates the probability of experiencing various ground accelerations at a site over a period of time and the probability of exceeding expected ground accelerations within the lifetime of the pro-

posed structure from the significant earthquakes within a specific radius of search. For the present case, a search radius of 62 miles (i.e., 100 kilometers) was selected. The earthquake magnitudes used in this program are based on the current CGS fault model. In evaluating the seismic hazards associated with the site, we have used an attenuation relation proposed by Boore, et al. (1997) for Soil Class D (stiff soil). The probabilistic MCE acceleration response spectrum for the site is presented on Figure 5.

The deterministic seismic hazard analysis was performed by computing the median spectral response acceleration for characteristic earthquakes acting individually on known active faults within the region based on attenuation relationships published by Sadigh, et al. (1997) and Boore, et. al. (1997) and the fault data presented in Table 1. The MCE ground motion was modeled by scaling the largest median spectral response acceleration computed at each period by 150 percent. The deterministic MCE acceleration response spectrum from our analysis is presented on Figure 5.

In accordance with ASCE 7-05, the site-specific design acceleration response spectrum shall be considered as the lesser of the probabilistic and deterministic MCE acceleration response spectra computed at each period of interest multiplied by a 2/3 scaling factor. The recommended site-specific design acceleration response spectrum is presented on Figure 5. This spectrum should be used for structural design of the proposed buildings at the site. Response modification and importance factors should be applied to the recommended site-specific spectrum, as appropriate.

6.4.3. Liquefaction

Liquefaction is the phenomenon in which loosely deposited granular soils with silt and clay contents of less than approximately 35 percent and non-plastic silts located below the water table undergo rapid loss of shear strength when subjected to strong earthquake-induced ground shaking. Ground shaking of sufficient duration results in the loss of grain-to-grain contact due to a rapid rise in pore water pressure, and causes the soil to behave as a fluid for a short period of time. Liquefaction is known generally to occur in

saturated or near-saturated cohesionless soils at depths shallower than 50 feet below the ground surface. Factors known to influence liquefaction potential include composition and thickness of soil layers, grain size, relative density, groundwater level, degree of saturation, and both intensity and duration of ground shaking.

The liquefaction potential of subsurface soils at the Alpha and Beta power blocks was evaluated using the soil sampler blow counts recorded at various depths in exploratory borings B-44 and B-62, respectively, and our laboratory test results. The liquefaction analysis was based on the National Center for Earthquake Engineering Research (NCEER) procedure (Youd, et al., 1997) developed from the methods originally recommended by Seed and Idriss (1982) using the computer program LiquefyPro (CivilTech Software, 2007). A perched groundwater table located at a depth of 27 feet below the existing ground surface was used in our liquefaction evaluation of the Alpha and Beta power blocks. Our liquefaction analysis indicates that minor zones within the medium dense granular soil layers occurring below the assumed groundwater level and up to a depth of approximately 37 feet below the ground surface are susceptible to liquefaction during the design seismic event.

6.4.4. Dynamic Settlement of Saturated Soils

As a result of liquefaction, the proposed structures may be subject to several hazards, including liquefaction-induced settlement. In order to estimate the amount of post-earthquake settlement, the method proposed by Tokimatsu and Seed (1987) was used in which the seismically induced cyclic stress ratios and corrected N-values are related to the volumetric strain of the soil. The amount of soil settlement during a strong seismic event depends on the thickness of the liquefiable layers and the density and/or consistency of the soils.

Under the current conditions, post-earthquake total settlements of up to approximately 1 and 1.5 inches were calculated for the Alpha and Beta power blocks, respectively. Based on the guidelines presented in CGS Special Publication 117 (2008) and assuming relatively discontinuous subsurface stratigraphy across the site, we estimate differential

settlement on the order of 1/2 inch over a horizontal distance of 40 feet at the Alpha power block and 3/4 inch over a horizontal distance of 40 feet at the Beta power block.

6.4.5. Ground Subsidence

Based on the design curves developed by Ishihara (1995) and considering the thickness of the non-liquefiable surface layer (above the historic high groundwater table) overlying the liquefiable soil layer, ground subsidence or seismically induced bearing failure is not a design consideration for the project.

6.4.6. Lateral Spread

Lateral spread of the ground surface during an earthquake usually takes place along weak shear zones that have formed within a liquefiable soil layer. Lateral spread has generally been observed to take place in the direction of a free-face (i.e., retaining wall, slope, channel, etc.) but has also been observed to a lesser extent on ground surfaces with gentle slopes. An empirical model developed by Youd, et al. (2002) is typically used to predict the amount of horizontal ground displacement within a site. For sites located in proximity to a free-face, the amount of lateral ground displacement is correlated with the distance of the site from the free-face. Other factors such as earthquake magnitude, distance from the causative fault, thickness of the liquefiable layers, and the fines content and particle sizes of the liquefiable layers also influence the amount of lateral ground displacement.

Based on the relatively level topography of the site, the thickness and depth of the potentially liquefiable soil layer, and the corrected sampler blow counts (i.e., $[N1]_{60-CS}$) within the liquefiable layers that are in excess of 15, seismically induced lateral spread is not a design consideration for the project.

6.4.7. State of California Earthquake Fault Zone

As noted, a designated State of California Earthquake Fault Zone (formerly known as an Alquist-Priolo Special Studies Zone) has been mapped extending into the northern portion of the eastern side of the site as an unnamed fault indicated on Figure 4. To mitigate

the hazard of surface faulting to structures for human occupancy, the Alquist-Priolo Earthquake Fault Zoning Act was passed in 1972. This act designates an earthquake fault zone which extends to either side of the surface trace of an active fault (i.e., a fault that exhibits evidence of ground displacement in the last 11,000 years). Pursuant to the act, these faults and associated earthquake fault zones are plotted on topographic maps. Before a structure for human occupancy can be permitted within an earthquake fault zone, a fault evaluation and written report for the site must be prepared by a licensed geologist. If an active fault is found, a structure for human occupancy needs to be set back from the fault 50 feet or more.

Our literature review (California Department of Conservation Division of Mines and Geology [CDMG], 1987) indicates that the mapping of the unnamed fault associated with the earthquake fault zone is based on aligned tonal lineaments, a subtle scarp in Holocene alluvium, and the linear western shoreline of Harper Lake. The actual presence of this fault has not been established. The earthquake recurrence interval and maximum moment magnitude for earthquakes on this fault have also not been determined.

No evidence of faulting was observed during our geologic reconnaissance of the site. Trenching of this mapped fault was performed as part of our previous evaluation to check for its presence. The evaluation consisted of the excavation, logging, and sampling of an approximately 1,400-foot long fault trench extending across the Alquist-Priolo fault zone. The fault trench logs are presented in Appendix C. Evidence of active faulting was not encountered during our fault evaluation. The mappable units observed did not exhibit displacement, offset, or other evidence of faulting (fault gouge, slickensides, or mineralization).

6.5. Landsliding

Based on our review of referenced geologic maps, literature and topographic maps, landslides, or indications of deep-seated landsliding were not noted underlying the project site. The potential for significant large-scale slope instability at the site is not a design consideration.

6.6. Subsidence Due to Groundwater Withdrawal

Based on our review of well records for three wells on Lockhart Road, east of Harper Lake Road, the groundwater level at the site was at a depth of 18 feet in 1919, 95 feet in 1953, and 176 feet in 1996 shortly after most agricultural pumping ended in Lockhart. The groundwater level has since risen to a depth of approximately 140 feet. It is our understanding that groundwater withdrawal for the MSP is anticipated to be less than the recharge of the aquifer and therefore we expect the groundwater level to continue to rise. We do not anticipate significant additional subsidence at MSP unless future pumping lowers the groundwater level below the historic low of 176 feet.

7. CONCLUSIONS

Based on our review of the referenced background data and geologic field reconnaissance, it is our opinion that construction of the proposed project is feasible from a geotechnical standpoint. Preliminary geotechnical considerations include the following:

- The project site is generally underlain by older alluvium and minor areas of lake deposits.
- In general, excavation of the alluvial material and lake deposits should be achievable with earth-moving equipment in good operating condition. Variations of in-place moisture content will be encountered; therefore, aeration or moisture conditioning during compaction should be anticipated. If encountered, cemented caliche deposits will necessitate heavy ripping during grading.
- The near-surface soils are generally compressible and considered unsuitable in the current condition for structural support.
- Groundwater was measured during our subsurface exploration at an approximate depth of 27 feet bgs in the Alpha and Beta power blocks and at an approximate depth of 4 feet bgs in the vicinity of Harper Lake. Fluctuations in the groundwater level should be expected due to variations in seasonal precipitation and other factors.
- The Lenwood-Lockhart-Old Woman Springs fault is located approximately 2,300 feet southwest of the site and is capable of generating an earthquake with a moment magnitude of 7.5.
- A State of California Earthquake Fault Zone has been mapped in the northeastern corner of the site. Based on the results of our literature review, site reconnaissance, and our fault trench evaluation, there is no evidence of active faulting.

- Based on the guidelines presented in CGS Special Publication 117 (2008), we estimate liquefaction differential settlement on the order of 1/2 inch over a horizontal distance of 40 feet at the Alpha power block and of 1-1/4 inches over a horizontal distance of 40 feet at the Beta power block.
- Our laboratory testing indicates that the site lake deposits can be considered corrosive according to Caltrans (2003) corrosion guidelines.

8. RECOMMENDATIONS

In the following sections, we present our geotechnical recommendations for the design and construction of the proposed facilities and associated improvements. These recommendations are based on our evaluation of the site geotechnical conditions, and our assumptions regarding the planned developments. Further geotechnical evaluation and engineering analyses may be provided once specific details regarding the structure sizes and foundation loads are available.

8.1. Earthwork

Grading plans were not available at the time of our present evaluation. We anticipate that site grading will generally consist of the preparation of building and equipment foundation pads, preparation of flatwork subgrade, as well as utility trench backfill. In addition, Typical Earthwork Guidelines for the project are included as Appendix F. In the event of a conflict in recommendations, the recommendations presented below should supersede those in Appendix F.

8.1.1. Site Preparation

The project site should be cleared and grubbed prior to grading. Clearing and grubbing should consist of the substantial removal of building foundations and basements, septic tanks and leach fields, cisterns, vegetation and other deleterious materials from the areas to be graded. Wells to be destroyed should be destroyed in accordance with San Bernardino County and State of California Department of Water Resources guidelines. Clearing and grubbing should extend beyond the proposed excavation and fill areas. The

debris generated during clearing and grubbing should be removed from areas to be graded and disposed at a legal dumpsite away from the site.

8.1.2. Excavation Characteristics

Based on our subsurface exploration and our experience with similar materials, it is our opinion that the on-site soils are generally excavatable with heavy-duty earthmoving equipment in good working condition. Excavations close to or below the groundwater will encounter wet and loose or soft ground conditions. Wet soils may be subject to pumping under heavy equipment loads. Heavy ripping will be needed for efficient grading of cemented caliche deposits.

8.1.3. Remedial Grading for Building Pad and Equipment Areas

Due to the compressible nature of the near-surface soils, we recommend that the existing site soils (topsoil and/or alluvium) be removed from the building pad and equipment foundation areas and replaced with granular soils with low to very low expansion potential (i.e., an Expansion Index [EI] of 50 or less as evaluated in accordance with ASTM D 4829). The removal operation should extend to a depth of 5 feet below the bottom of the structural footings or to groundwater, whichever is less. For the purpose of this report, a building pad or equipment foundation area is defined as the area underlying any settlement-sensitive structure and extending a horizontal distance of 5 feet beyond the limits of the structure and extending downward at a 1:1 (horizontal to vertical) inclination. Deeper removals may be needed if unsuitable materials are exposed at the excavation bottom during grading. The depth and extent of the removal should be further evaluated in the field by Ninyo & Moore.

The resultant excavation subgrade should be scarified to a depth of 8 inches, moisture conditioned to a moisture content of 3 to 5 percent above the laboratory optimum and recompact to a relative compaction of 90 percent as evaluated by ASTM Test Method D 1557.

If wet soils are encountered in the remedial excavations the subsequent drying and additional handling of these soils may be needed. Loose, soft, or otherwise deleterious material encountered at the bottom of excavation should be overexcavated and recompact in accordance with the recommendations provided herein. Additional stabilization efforts may be used in lieu of the additional removal at the bottom of the excavations, Ninyo & Moore should be consulted regarding the usage of an approximately 1-foot thick layer of crushed aggregate in the bottom of the excavation in conjunction with geosynthetic materials or placement of a lean concrete mud mat.

8.1.4. Remedial Grading for Exterior Flatwork

To reduce the potential for differential movement due to compressible soils, we recommend that granular soils with generally low to very low expansion potential (i.e., an EI of less than 50) be placed below the exterior flatwork areas to a depth of 3 feet below the bottom of the flatwork. The low expansive material should extend horizontally beyond the edge of the flatwork or pavement to a distance of 3 feet. The subgrade soils should be compacted to a relative compaction of 90 percent as evaluated by ASTM D1557.

8.1.5. Materials for Fill

Granular on-site soils with an organic content of less than 3 percent by volume (or 1 percent by weight) are suitable for use as fill. Fill soils should be free of trash, debris, roots, vegetation, organics, or other deleterious materials. Fill and utility trench backfill materials should not contain rocks or lumps over 3 inches in largest dimension, and not more than 30 percent larger than 3/4 inch. Larger chunks, if generated during excavation, may be broken into acceptably sized pieces or disposed of off site. Any imported fill material should be a low or very low expansion potential (i.e., an EI of 50 or less as evaluated by ASTM D 4829) granular soil. Imported materials should also be non-corrosive in accordance with the Caltrans (2003) corrosion guidelines. Materials for use as fill should be evaluated by the geotechnical consultant's representative prior to filling or importing. The contractor should be responsible for the uniformity of imported materials brought to the site.

8.1.6. Compacted Fill

Prior to placement of compacted fill, the contractor should request an evaluation of the exposed ground surface by Ninyo & Moore. Unless otherwise recommended, the exposed ground surface should then be scarified to a depth of approximately 8 inches and watered or dried, as needed, to achieve moisture contents generally above the optimum moisture content. The scarified materials should then be compacted to a relative compaction of 90 percent as evaluated in accordance with ASTM D 1557. The evaluation of compaction by the geotechnical consultant should not be considered to preclude any requirements for observation or approval by governing agencies. It is the contractor's responsibility to notify the geotechnical consultant and the appropriate governing agency when project areas are ready for observation, and to provide reasonable time for that review.

Fill materials should be moisture conditioned to generally above the laboratory optimum moisture content prior to placement. The optimum moisture content will vary with material type and other factors. Moisture conditioning of fill soils should be generally consistent within the soil mass.

Prior to placement of additional compacted fill material following a delay in the grading operations, the exposed surface of previously compacted fill should be prepared to receive fill. Preparation may include scarification, moisture conditioning, and recompaction.

Compacted fill should be placed in horizontal lifts of approximately 8 inches in loose thickness. Prior to compaction, each lift should be watered or dried as needed to achieve a moisture content generally above the laboratory optimum, mixed, and then compacted by mechanical methods to a relative compaction of 90 percent as evaluated by ASTM D 1557. Successive lifts should be treated in a like manner until the desired finished grades are achieved.

8.1.7. Slopes

Unless otherwise recommended by Ninyo & Moore (or another qualified geotechnical consultant) and approved by the regulating agencies, cut and fill slopes should not be steeper than 2:1 (horizontal to vertical). Compaction of the face of fill slopes should be performed by backrolling at intervals of 4 feet or less in vertical slope height, or as dictated by the capability of the available equipment, whichever is less. Fill slopes should be backrolled utilizing a sheepfoot-type roller. Care should be taken to maintain the desired moisture conditions and/or reestablish them, as needed, prior to backrolling. The placement, moisture conditioning, and compaction of fill slope materials should be done in accordance with the recommendations presented in the Compacted Fill section of this report.

Site runoff should not be permitted to flow over the tops of slopes. Positive drainage should be established away from the top of slopes. This may be accomplished by utilizing brow ditches placed at the top of slopes to divert surface runoff away from the slope face where drainage devices are not otherwise available.

The on-site soils will be susceptible to erosion; therefore, the project plans and specifications should contain design features and construction requirements to mitigate erosion of on-site soils during and after construction. Slopes and other exposed ground surfaces should be appropriately planted with protective ground cover or otherwise stabilized.

8.1.8. Temporary Excavation and Shoring

Trenches and excavations should be designed and constructed in accordance with Occupational Safety and Health Administration (OSHA) regulations. These regulations provide trench sloping and shoring design parameters for trenches up to 20 feet deep based on the soil types encountered. Trenches over 20 feet deep should be designed by the contractor's engineer based on site-specific geotechnical analyses. For planning purposes, we recommend that the following OSHA soil classifications be used:

Older Alluvium and Lake Deposits Type C

Upon making the excavations, the soil/rock classifications and excavation performance should be evaluated in the field by Ninyo & Moore or another qualified geotechnical consultant in accordance with OSHA regulations. Recommendations for temporary shoring can be provided, if requested.

Temporary excavations should be constructed in accordance with OSHA recommendations. For trench or other excavations, OSHA requirements regarding personnel safety should be met by using appropriate shoring (including trench boxes) or by laying back the slopes no steeper than 1.5:1 (horizontal to vertical) in Type C soil. Temporary excavations that encounter seepage or caving may need shoring or may be stabilized by placing sandbags or gravel along the base of the seepage zone. Excavations encountering seepage or caving should be evaluated on a case-by-case basis. On-site safety of personnel is the responsibility of the construction contractor(s).

8.1.9. Drainage

Roof, pad, and slope drainage should be diverted away from slopes and structures to suitable discharge areas by nonerodible devices (e.g., gutters, downspouts, concrete swales, etc.). Positive drainage adjacent to structures should be established and maintained. Positive drainage may be accomplished by providing drainage away from the foundations of structures at a gradient of 2 percent or steeper for a distance of 5 feet or more outside the building perimeter, and further maintained by a graded swale leading to an appropriate outlet, in accordance with the recommendations of the project civil engineer and/or landscape architect.

Surface drainage on the site should be provided so that water is not permitted to pond. A gradient of 2 percent or steeper should be maintained over the pad area and drainage patterns should be established to divert and remove water from the site to appropriate outlets.

Care should be taken by the contractor during final grading to preserve any berms, drainage terraces, interceptor swales or other drainage devices on or adjacent to the

property. Drainage patterns established at the time of final grading should be maintained for the life of the project. The property maintenance personnel should be made very clearly aware that altering drainage patterns might be detrimental to slope stability and foundation performance.

8.2. Seismic Design Considerations

Design of the proposed improvements should be in accordance with the requirements of governing jurisdictions and applicable building codes. Table 2 presents the seismic design parameters for the site in accordance with CBC (2007) guidelines and mapped spectral acceleration parameters (United States Geological Survey [USGS], 2008).

Table 2 – 2007 California Building Code Seismic Design Criteria

Seismic Design Factors	Value
Site Class	D
Site Coefficient, F_a	1.028
Site Coefficient, F_v	1.551
Mapped Spectral Acceleration at 0.2-second Period, S_s	1.179g
Mapped Spectral Acceleration at 1.0-second Period, S_1	0.449g
Spectral Acceleration at 0.2-second Period Adjusted for Site Class, S_{MS}	1.212g
Spectral Acceleration at 1.0-second Period Adjusted for Site Class, S_{M1}	0.697g
Design Spectral Response Acceleration at 0.2-second Period, S_{DS}	0.808g
Design Spectral Response Acceleration at 1.0-second Period, S_{D1}	0.465g

8.3. Foundations

The following foundation design parameters are provided based on our geotechnical analysis. The foundation design parameters are not intended to preclude differential movement of soils. Minor cracking (considered tolerable) of foundations may occur. It is anticipated that the majority of the proposed structures will be founded on shallow footings or mat foundations. Solar arrays and electricity distribution towers may be supported on deep foundations. The following sections present our foundation recommendations. More specific recommendations may be provided after review of proposed building plans.

8.3.1. Shallow Footings

Shallow spread or continuous footings, founded in compacted fill may be designed using an allowable bearing capacity of 2,000 pounds per square foot (psf). These allowable bearing capacities may be increased by one-third when considering loads of short duration such as wind or seismic forces. Spread footings should be founded 18 inches below the adjacent grade. Continuous footings should have a width of 15 inches and isolated footings should be 24 inches in width. The spread footings should be reinforced in accordance with the recommendations of the project structural engineer.

8.3.2. Lateral Resistance

For resistance of footings to lateral loads, we recommend an allowable passive pressure of 250 psf per foot of depth be used up to a value of 2,500 psf. This value assumes that the ground is horizontal for a distance of 10 feet, or three times the height generating the passive pressure, whichever is larger. We recommend that the upper one-foot of soil not protected by pavement or a concrete slab be neglected when calculating passive resistance.

For frictional resistance to lateral loads, we recommend a coefficient of friction of 0.35 be used between soil and concrete. The allowable lateral resistance can be taken as the sum of the frictional resistance and passive resistance provided the passive resistance does not exceed one-half of the total allowable resistance. The passive resistance values may be increased by one-third when considering loads of short duration such as wind or seismic forces.

8.3.3. Static Settlement

We estimate that the proposed facilities, designed and constructed as recommended herein, will undergo total settlement on the order of 1 inch. Differential settlement on the order of 1/2 inch over a horizontal span of 40 feet should be expected.

8.3.4. Mat Foundations

Due to the anticipated static and dynamic settlements, the structural engineer may consider a structurally rigid mat foundation for settlement sensitive buildings and

equipment foundations. Mat foundations placed on compacted granular fill with generally very low to low expansion potential (i.e., an EI of 50 or less) may be designed using an allowable bearing capacity of 2,500 psf. This allowable bearing capacity may be increased by one-third when considering loads of short duration such as wind or seismic forces. Thickness and reinforcement of the mat foundation should be in accordance with the recommendations of the project structural engineer.

A mat foundation is a large concrete slab, designed by a structural engineer for specific use, to interface one or more columns or pieces of equipment with the foundation soil. It may encompass the entire foundation footprint or only a portion. The mat contact stresses are generally lower than other shallow foundation types due to distribution of stress over a larger area and stress compensation from excavated soils.

The appropriate allowable contact pressure(s) beneath the bases of mat foundations will vary with their size, shape, and other factors. The contact pressure beneath the mats should not exceed the allowable bearing pressure values of 2,500 psf. The mat foundation may be designed using a coefficient of subgrade reaction, K_v , of 250 kips per cubic foot (kcf). This value is based on a unit square foot area and should be adjusted for the planned mat size. The coefficient of subgrade reaction, K_b , for a mat of a specific width may be evaluated using the following equation:

$$K_b = K_v[(b+1)/2b]^2$$

Where, **b** is the width of the foundation in feet.

8.4. Deep Foundations

Based on our discussions with the project engineer and the observed site conditions, we anticipate that cast-in-drilled-hole (CIDH) piles will be used for the project. We evaluated 18- and 24-inch diameter CIDH piles for the solar array supports and 60-inch diameter CIDH piles for the 85- to 90-foot high transmission poles.

8.4.1. Axial Pile Capacity

The allowable loads for the CIDH piles were analyzed using the computer program AllPile (CivilTech, 2007) based on assumed pile lengths. The calculated pile capacities are based on frictional capacity and end bearing. Tension capacities are based on the downward frictional capacity and include the pile weight. A pile spacing of three pile diameters on center or more should be maintained. The results of ultimate axial pile capacity and service load evaluation for a factor of safety of 2.0 are summarized in Table 3.

Table 3 – Axial Pile Capacity Evaluation

CIDH Pile Diameter (inches)	Pile Length (feet)	Ultimate Downward Capacity (kips)	Design (Service) Loads (kips)	
			Compression	Tension
18	15	48	24	9
18	20	66	33	15
18	25	92	46	23
24	15	75	37	14
24	20	100	50	23
24	25	134	67	34
60	15	364	182	79
60	20	428	214	92
60	25	512	256	128

8.4.2. Lateral Capacity

Our analyses did not account for dynamic loads due to inertial loads from the structure during the design earthquake. However, we assumed that the dynamic loads would not be higher than the lateral capacities for each pile. Maximum moments generated by the indicated deflections are based on geotechnical considerations. We recommend that the maximum moment capacities of the piles be evaluated by the structural engineer. Lateral capacities for pile lengths and embedment conditions that are different from those assumed in our analyses may be different than those presented below.

Lateral capacities based on fixed-head and free-head conditions for 18- and 24-inch diameter CIDH piles with 15 foot length and 60-inch diameter CIDH piles with 25 foot length as summarized in Tables 4, 5 and 6, respectively.

**Table 4 – Lateral Load Capacity
18-inch-diameter CIDH Pile**

Pile Design Parameters	Fixed-Head		Free-Head	
Lateral Deflection of Shaft Head (inch)	0.25	0.50	0.25	0.50
Design Shaft Length (feet)	15	15	15	15
Lateral Load (kips)	25	51	9	18
Maximum Positive Moment (kips-foot)	109.2	223.3	34.7	69.3
Depth to Maximum Positive Moment (feet)	0.0	0.0	5.8	5.8
Maximum Negative Moment (kips-foot)	-24.5	-49.9	-5.6	0.0
Depth to Maximum Negative Moment (feet)	8.6	8.5	10.0	15.0
Depth to Zero Deflection (feet)	11.7	11.8	9.8	10.2

**Table 5 – Summary of Single Pile Lateral Load Capacity
24-inch-diameter CIDH Pile**

Pile Design Parameters	Fixed-Head		Free-Head	
Lateral Deflection of Shaft Head (inch)	0.25	0.50	0.25	0.50
Design Shaft Length (feet)	15	15	15	15
Lateral Load (kips)	38	76	12.5	24.5
Maximum Positive Moment (kips-foot)	218.3	437.5	52.7	103.3
Depth to Maximum Positive Moment (feet)	0.0	0.0	6.2	6.1
Maximum Negative Moment (kips-foot)	-17.9	-35.8	0.0	0.0
Depth to Maximum Negative Moment (feet)	10.0	10.0	15.0	15.0
Depth to Zero Deflection (feet)	12.6	12.6	10.9	11.1

**Table 6 – Summary of Single Pile Lateral Load Capacity
60-inch-diameter CIDH Pile**

Pile Design Parameters	Fixed-Head		Free-Head	
	0.25	0.50	0.25	0.50
Lateral Deflection of Shaft Head (inch)	0.25	0.50	0.25	0.50
Design Shaft Length (feet)	25	25	25	25
Lateral Load (kips)	190	370	53	102
Maximum Positive Moment (kips-foot)	2316.7	4516.7	383.3	737.5
Depth to Maximum Positive Moment (feet)	0.0	0.0	11.1	11.1
Maximum Negative Moment (kips-foot)	-51.0	-99.2	0.0	0.0
Depth to Maximum Negative Moment (feet)	19.7	19.7	25.0	25.0
Depth to Zero Deflection (feet)	22.2	22.5	19.4	19.7

For lateral loading, piles in a group may be considered to act individually when the center-to-center spacing is greater than 3D (where, D is the diameter of the pile) in the direction normal to loading and greater than 8D in the direction parallel to loading. The following table presents the lateral load reduction factors to be applied for various pile spacings for in-line loading.

Table 7 – Lateral Load Group Reduction Factors

Center-to-Center Pile Spacing for In-Line Loading	Group Efficiency (Ratio of Lateral Resistance of Pile in a Group to Single Pile)
8D	1.00
7D	0.94
6D	0.88
5D	0.82
4D	0.76
3D	0.70

8.4.3. Construction Considerations for Cast-In-Drilled-Hole (CIDH) Piles

Construction of CIDH piles should be observed by the geotechnical consultant during drilling to evaluate if the piles have been extended to the recommended depths. The

drilled holes should be cleaned of loose soil and gravel. It is the contractor's responsibility to take the appropriate measures to provide for the integrity of the drilled holes and to see that the holes are cleaned and straight and that sloughed loose soil is removed from the bottom of the hole prior to the placement of concrete. Drilled CIDH piles should be checked for alignment and plumbness during installation. The amount of acceptable misalignment of a pile is approximately 3 inches from the plan location but may be reduced based on design criteria. The center-to-center spacing of piles should be no less than three times the nominal diameter of the pile.

Groundwater was encountered in our exploratory borings at depths of approximately 4 feet bgs in the vicinity of Harper Lake and 27 feet bgs in the older alluvium areas. As a result, we anticipate that groundwater may be encountered in the drilled holes for the CIDH piles. It is recommended that the contractor considers appropriate measures during construction to reduce the potential for caving of the drilled holes, including the use of steel casing and/or drilling mud. In addition, we recommend placement of concrete by tremie method to see that the aggregate and cement do not segregate during concrete placement.

Contractors with proven records in the installation of CIDH piles should be considered. We recommend that the drilling equipment have a rated torque of 20,000 foot-pounds or more. During construction, a certified deep foundation inspector should document the diameter, depth, vertical alignment, and the nature of the materials encountered at each pile location. Reinforcing steel and concrete placement should be continuously observed by Ninyo & Moore. A quality control report should be submitted for each pile stating, in writing, that the design details have been observed and meet the requirements.

We recommend that the use of pile integrity testing be considered to evaluate the installed condition of the piles. Pile integrity tests may be performed as low strain dynamic (sonic echo) testing. If performed, the pile integrity tests should be performed under the direction of the design engineer and be monitored in the field by Ninyo & Moore.

8.5. Slab-on-Grade

We recommend that conventional, slab-on-grade floors, underlain by compacted fill materials of generally very low to low expansion potential, be 5 inches in thickness and be reinforced with No. 3 reinforcing bars spaced 18 inches on center each way. The reinforcing bars should be placed near the mid-height of the slab. As a means to help reduce shrinkage cracks, we recommend that the slabs be provided with expansion joints at intervals of approximately 12 feet each way. The slab reinforcement and expansion joint spacing should be designed by the project structural engineer.

If moisture sensitive floor coverings are to be used, we recommend that slabs be underlain by a vapor retarder and capillary break system consisting of a 10-mil polyethylene (or equivalent) membrane placed over 4 inches of medium to coarse, clean sand or pea gravel and overlain by an additional 2 inches of sand to help protect the membrane from puncture during placement and to aid in concrete curing. The exposed subgrade should be moistened prior to the placement of concrete.

8.6. Concrete Flatwork

Exterior concrete flatwork should be 4 inches in thickness and should be reinforced with No. 3 reinforcing bars placed at 24 inches on-center both ways. No vapor retarder is needed for exterior flatwork. To reduce the potential manifestation of distress to exterior concrete flatwork due to movement of the underlying soil, we recommend that such flatwork be installed with crack-control joints at appropriate spacing as designed by the structural engineer. Exterior slabs should be underlain by 4 inches of clean sand. The subgrade soils should be treated as indicated in the Remedial Grading for Exterior Flatwork section of this report. Positive drainage should be established and maintained adjacent to flatwork.

8.7. Preliminary Pavement Design

We understand that asphalt concrete-paved access drives and parking areas will be constructed on the site. For planning purposes we are providing preliminary pavement designs. Laboratory testing was performed on a representative sample of the on-site soils to evaluate R-value. The test was in general accordance with California Test (CT) Method 301 and the result is presented in Appendix B. The test result indicates an R-value of 61 for the sample tested. We have used this value for the preliminary design of flexible pavements at the project site. Actual pavement recommendations should be based on R-value tests performed on bulk samples of the soils that are exposed at the finished subgrade elevations in the areas to be paved once grading operations have been performed. For design we have used a Traffic Index of 5.0 for parking areas and site driveways and 6.0 for truck traffic. The preliminary recommended pavement sections are as follows:

Table 8 – Recommended Pavement Sections

Area	R-Value	Traffic Index	Asphalt Concrete (inches)	Class 2 Aggregate Base (inches)
Parking and Driveways	61	5.0	3.0	4.0
Truck Traffic	61	6.0	4.0	4.0

If traffic loads are different from those assumed, the pavement design should be re-evaluated. In addition, we recommend that the upper 12 inches of the subgrade and the Class 2 aggregate base be compacted to a relative compaction of 95 percent as evaluated by ASTM D 1557.

We suggest that consideration be given to using Portland cement concrete (PCC) pavement in areas where dumpsters will be stored and where refuse trucks will stop and load. Experience indicates that refuse truck traffic can significantly shorten the useful life of asphalt concrete sections. We recommend that in these areas, 6-inch thick PCC pavement with a flexural strength of 600 pounds per square inch (psi) reinforced with No. 3 bars, 18 inches

on center, be placed over 12 inches of very low to low expansive soil compacted to a relative compaction of 95 percent as evaluated by ASTM D 1557.

8.8. Corrosion

Laboratory testing was performed on representative samples of the on-site soils to evaluate pH and electrical resistivity, as well as chloride and sulfate contents. The samples tested were representative of the older alluvium and of the lake deposits. The pH and electrical resistivity tests were performed in accordance with CT 643 and the sulfate and chloride tests were performed in accordance with CTs 417 and 422, respectively. These laboratory test results are presented in Appendix B.

The results of the corrosivity testing indicated electrical resistivity ranging from 3,015 to 10,720 ohm-cm for older alluvium and 154 ohm-cm for lake deposits; soil pH ranging from 7.1 to 7.7 for older alluvium and 7.7 for lake deposits; chloride content ranging from 25 to 380 parts per million (ppm) for older alluvium and 11,200 ppm for lake deposits; and, sulfate content ranging from 0.002 to 0.011 percent (i.e., 20 to 110 ppm) for older alluvium and 0.99 percent (i.e., 9,900 ppm) for lake deposits. Based on Caltrans criteria, older alluvium would be classified as non-corrosive. However, lake deposits would be classified as corrosive, which is defined as having soil with more than 500 ppm chlorides, more than 0.2 percent sulfates, or a pH less than 5.5. We recommend that a corrosion engineer be consulted for further evaluation of soil corrosivity at the site.

8.9. Concrete Placement

Concrete in contact with soil or water that contains high concentrations of water-soluble sulfates can be subject to premature chemical and/or physical deterioration. As stated above, the soil samples tested in this evaluation indicated a water-soluble sulfate contents ranging from 0.002 to 0.011 percent by weight in older alluvium areas and 0.99 percent (i.e., 9,900 ppm) for lake deposits. According to the American Concrete Institute (ACI) guideline 318-05, the potential for sulfate attack is negligible for water-soluble sulfate content of up to about

0.10 percent and severe for water-soluble sulfate content of 0.2 to 2.0 percent by weight in soils. Therefore, the older alluvium may be considered to have a negligible potential for sulfate attack and the lake deposits have severe potential for water-soluble sulfate attack. Based on ACI (2005) criteria, Type II cement may be used for concrete construction in older alluvium areas. Type V cement should be used for any structures constructed on the lake deposits. However, due to the potential variability of site soils, consideration should be given to using Type V cement and concrete with a water-cement ratio no higher than 0.45 by weight for normal weight aggregate concrete and a 28-day compressive strength of 4,500 psi or more for the project.

9. LIMITATIONS

The preliminary field evaluation, laboratory testing, and geotechnical analyses presented in this geotechnical report have been conducted in general accordance with current practice and the standard of care exercised by geotechnical consultants performing similar tasks in the project area. No warranty, expressed or implied, is made regarding the conclusions, recommendations, and opinions presented in this report. There is no evaluation detailed enough to reveal every subsurface condition. Variations may exist and conditions not observed or described in this report may be encountered during construction. Uncertainties relative to subsurface conditions can be reduced through additional subsurface exploration. Additional subsurface evaluation will be performed upon request. Please also note that our evaluation was limited to assessment of the geotechnical aspects of the project, and did not include evaluation of structural issues, environmental concerns, or the presence of hazardous materials.

This document is intended to be used only in its entirety. No portion of the document, by itself, is designed to completely represent any aspect of the project described herein. Ninyo & Moore should be contacted if the reader requires additional information or has questions regarding the content, interpretations presented, or completeness of this document.

This report is intended for preliminary design purposes only. It does not provide sufficient data to prepare an accurate bid by contractors. It is suggested that the bidders and their geotechnical consultant perform an independent evaluation of the subsurface conditions in the project areas. The independent evaluations may include, but not be limited to, review of other geotechnical reports prepared for the adjacent areas, site reconnaissance, and additional exploration and laboratory testing.

Our conclusions, recommendations, and opinions are based on an analysis of the observed site conditions. If geotechnical conditions different from those described in this report are encountered, our office should be notified, and additional recommendations, if warranted, will be provided upon request. It should be understood that the conditions of a site could change with time as a result of natural processes or the activities of man at the subject site or nearby sites. In addition, changes to the applicable laws, regulations, codes, and standards of practice may occur due to government action or the broadening of knowledge. The findings of this report may, therefore, be invalidated over time, in part or in whole, by changes over which Ninyo & Moore has no controls.

This report is intended exclusively for use by the client. Any use or reuse of the findings, conclusions, and/or recommendations of this report by parties other than the client is undertaken at said parties' sole risk.

10. REFERENCES

- American Concrete Institute (ACI), 2005, ACI 318-05 Building Code Requirements for Structural Concrete and Commentary.
- Applied Geotechnical Engineering, Inc., 1990, Fault Investigation, Unnamed Harper Lake Fault Zone, Harper Lake, San Bernardino County: dated March 2.
- Blake, Thomas F., 2001, FRISKSP Version 4.00, Probabilistic Earthquake Hazard Analysis Computer Program.
- Boore, D.M., Joyner, W.B., and Fumal, T.E., 1997, Equations for Estimating Horizontal Response Spectra and Peak Acceleration from Western North American Earthquakes: A Summary of Recent Work, Seismological Research Letters, Vol. 68, No. 1, pp. 128-153.
- California Building Standards Commission (CBSC), 2007, California Building Code (CBC), Title 24, Part 2, Volumes 1 and 2.
- California Department of Conservation Division of Mines and Geology, 1986, Geologic Map of the San Bernardino Quadrangle: Scale 1:250,000.
- California Department of Conservation Division of Mines and Geology, 1987, Recently Active Traces of the Blackwater, Harper, Lockhart and Related Faults near Barstow, San Bernardino County; FER-189 (unpublished): dated July 20.
- California Department of Conservation Division of Mines and Geology, 1988, State of California Special Studies Zones, Lockhart Quadrangle, Official Map: dated March 1.
- California Department of Conservation Division of Mines and Geology, 1998, Maps of Known Active Fault Near-Source Zones in California and Adjacent Portions of Nevada: dated February.
- California Department of Conservation Division of Mines and Geology, 1999, Seismic Shaking Hazards Maps of California: Map Sheet 48.
- California Department of Transportation, 2003, Corrosion Guidelines, Version 1.0, Division of Engineering Services, Materials Engineering and Testing Services, Corrosion Technology Branch: dated September.
- California Geologic Survey, 2008, Guidelines for Evaluation and Mitigating Seismic Hazards in California: Special Publication 117.
- California Department of Water Resources, 2009, Groundwater level Data website: <http://wdl.water.ca.gov/gw/>.
- Cao, T., Bryant, W.A., Rowshandel, B., Branum, D., and Wills, C.J., California Geological Survey (CGS), 2003, the Revised 2002 California Probabilistic Seismic Hazard Maps.

- CivilTech Software, 2007, AllPile (Version 7.9a), A Computer Program for Lateral, Downward (compression), Uplift, Settlement, Group Analysis of Piles.
- CivilTech Software, 2007, LiquefyPro (Version 5.5j), A Computer Program for Liquefaction and Settlement Analysis.
- County of San Bernardino, 1992, On-Site Waste Water Disposal System, Soil Percolation (PERC) Test Report Standards: dated August.
- Ishihara, K., 1995, Effects of At-Depth Liquefaction on Embedded Foundations During Earthquakes, Proceedings of the Tenth Asian Regional Conference on Soil Mechanics and Foundation Engineering, August 29 through September 2, Beijing, China, Vol. 2, pp. 16-25.
- Jennings, C.W., 1994, Fault Activity Map of California and Adjacent Areas: California Division of Mines and Geology, California Geologic Data Map Series, Map No. 6, Scale 1:750,000.
- Merrell Johnson Engineering, 2009, Mojave Solar One Site Plan.
- Ninyo & Moore, 2007, Preliminary Geotechnical and Fault Hazard Evaluation, Harper Lake Solar Project, Lockhart, California: dated October 3.
- Ninyo & Moore, 2008, Update Preliminary Geotechnical and Fault Hazard Evaluation, Harper Lake Solar Project, Lockhart, California: dated May 30.
- Ninyo & Moore, In-House Proprietary Data.
- Norris, R. M. and Webb, R. W., 1990, Geology of California, Second Edition: John Wiley & Sons, Inc.
- Public Works Standards, Inc., 2006, "Greenbook," Standard Specifications for Public Works Construction.
- Sadigh, K., Chang, C.Y., Egan, J.A., Makdisi, F., and Youngs, R.R., 1997, Attenuation Relations for Shallow Crustal Earthquakes Based on California Strong Motion Data, Seismological Research Letters, Volume 68, Number 1: dated January/February.
- Seed, H.B. and Idriss, I.M., 1982, Ground Motions and Soil Liquefaction During Earthquakes: Earthquake Engineering Research Institute Monograph.
- Sneed, M., Ikehara, M.E., Stork, S. V., Amelung, F., and Galloway, D. L., 2003, Detection and Measurement of Land Subsidence Using Interferometric Synthetic Aperture Radar and Global Positioning System, San Bernardino County, Mojave Desert, California: U.S. Geological Survey Water-Resources Investigations Report 03-4015.

- Tokimatsu, K., and Seed, H.B., 1987, Evaluation of Settlements in Sands Due to Earthquake Shaking, *Journal of Geotechnical Engineering*, American Society of Civil Engineers, 113(8), 861-878.
- United States Department of the Interior, Bureau of Reclamation, 1998, *Engineering Geology Field Manual*.
- United States Geological Survey/California Geological Survey, 2003, Probabilistic Seismic Hazards Assessment Model for California.
- United States Geological Survey, 1973, Twelve Gauge Lake Quadrangle, California, San Bernardino County, 7.5-Minute Series (Topographic): Scale 1:24,000.
- United States Geological Survey, 1986, Lockhart Quadrangle, California, San Bernardino County, 7.5-Minute Series (Topographic): Scale 1:24,000
- United States Geological Survey, 2009 Ground Motion Parameter Calculator v. 5.0.8, World Wide Web, <http://earthquake.usgs.gov/research/hazmaps/design/>.
- Youd, T.L., and Idriss, I.M. (Editors), 1997, Proceedings of the NCEER Workshop on Evaluation of Liquefaction Resistance of Soils, Salt Lake City, Utah, January 5 through 6, 1996, NCEER Technical Report NCEER-97-0022, Buffalo, New York.
- Youd, T.L., Hansen, C.M., and Bartlett, S.F., 2002, Revised Multilinear Regression Equations for Prediction of Lateral Spread Displacement: *Journal of Geotechnical and Geoenvironmental Engineering*, Vol. 128, No. 12, pp. 1007-1017.



REFERENCE: 2005 THOMAS GUIDE FOR SAN BERNARDINO AND RIVERSIDE COUNTIES, STREET GUIDE AND DIRECTORY.



NOTE: ALL DIMENSIONS, DIRECTIONS AND LOCATIONS ARE APPROXIMATE.

Ninyo & Moore

SITE LOCATION MAP

FIGURE

PROJECT NO.

DATE


105879004

5/09

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA


1

5-5-09 105879004_Harper_Lake\105879004_Fig2_bar_lsc.mxd



LEGEND

- | | | | | | |
|--|---|--|--|--|-------------------------------|
| | APPROXIMATE BORING LOCATION | | ALPHA POWER BLOCK | | BETA BOUNDARY |
| | APPROXIMATE PERCOLATION TEST LOCATION | | BETA MIRROR | | BETA DISTURBANCE AREA |
| | APPROXIMATE TEST PIT LOCATION | | BETA PONDS LANDFARM | | BETA DRAINAGE CHANNEL |
| | APPROXIMATE RESISTIVITY SURVEY LOCATION | | BETA POWER BLOCK | | COMMON BOUNDARY |
| | APPROXIMATE FAULT TRENCH LOCATION | | CONSTRUCTION LAYDOWN | | CONSTRUCTION LAYDOWN BOUNDARY |
| | ALPHA DRAINAGE CHANNELS | | CONTOURS | | TRANS INTERCONNECT BOUNDARY |
| | ALPHA MIRROR | | APPROXIMATE LOCATION OF GEOLOGIC CONTACT | | |
| | ALPHA PONDS LANDFARM | | | | |
- NOTES: TD=APPROXIMATION DEPTH IN FEET
Qld LAKE DEPOSITS
Qoa OLDER ALLUVIUM



NOTE: ALL DIRECTIONS, DIMENSIONS AND LOCATIONS ARE APPROXIMATE

REFERENCE: MERRELL JOHNSON ENGINEERING, 2009
MOJAVE SOLAR ONE SITE PLAN

Ninyo & Moore

PROJECT NO.

105879004

DATE

5/09

GEOTECHNICAL MAP

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

FIGURE

2




fig. 3 105879004 fault

AFTER NORRIS AND WEBB, 1990

Ningo & Moore

FAULT LOCATION MAP

FIGURE

3


PROJECT NO.

DATE


MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

105879004

5/09



APPROXIMATE SCALE



LEGEND

Special Studies Zone Boundaries

- The boundaries are delineated as straight-line segments that connect encircled turning points so as to define special studies zone areas

- FAULT TRENCH

NOTE: ALL DIMENSIONS, DIRECTIONS AND LOCATIONS ARE APPROXIMATE.

REFERENCE: STATE OF CALIFORNIA SPECIAL STUDIES ZONES, LOCKHART QUADRANGLE, DATED MARCH 1, 1988.

Ninyo & Moore

SPECIAL STUDIES ZONE MAP

FIGURE

PROJECT NO.

DATE

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

4

105879004

5/09

PERIOD (seconds)	SITE-SPECIFIC DESIGN RESPONSE SPECTRUM Sa, (g)
0.000	0.365
0.030	0.365
0.050	0.428
0.075	0.511
0.100	0.596
0.115	0.646
0.150	0.707
0.200	0.785


$$S_{DS} = 0.785 > 0.9 \times 0.869$$

$$S_{MS} = 1.178$$

PERIOD (seconds)	SITE-SPECIFIC DESIGN RESPONSE SPECTRUM Sa, (g)
0.300	0.865
0.400	0.869
0.500	0.836
0.575	0.796
0.750	0.703
1.000	0.584
1.500	0.420
2.000	0.321

$$S_{D1} = 0.642$$

$$S_{M1} = 0.963$$



NOTES:

1. Probabilistic Acceleration Response Spectra (ARS) is for Maximum Considered Earthquake (MCE) with ground motion having 2% probability of exceedance in 50 years using Boore et al. (1997) attenuation relationship for Site Class D (stiff soil profile).
2. Deterministic ARS is 150% of the largest median values from attenuation relationships by Sadigh et al. (1997) and Abrahamson and Silva (1997) considering a magnitude 7.5 event on the Lenwood-Lockhart-Old Woman Springs fault located approximately 0.7 km from the site. Deterministic ARS conforms with lower bound limit per ASCE 7-05 Section 21.2.2.
3. Site-Specific Design ARS is the lesser of spectral ordinates of deterministic and probabilistic ARS at each period per ASCE 7-05 Section 21.2.3. Site-Specific Design ARS conforms with lower bound limit per ASCE 7-05 Section 21.3.
4. Mapped Design ARS computed from ASCE 7 mapped spectral ordinates modified for Site Class D with 2/3 scaling factor per ASCE 7-05 Section 11.4. Presented for comparison.
5. ARS curves for horizontal ground motion assume 5% damping and do not include response modification factor or importance factor.
6. Seismic Design Category D per 2007 CBC Section 1613A.5.6.

Ninyo & Moore		ACCELERATION RESPONSE SPECTRA	FIGURE 5
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	
105879004	5/09		

APPENDIX A

BORING AND TEST PIT LOGS

Field Procedure for the Collection of Disturbed Samples

Disturbed soil samples were obtained in the field using the following methods.

Bulk Samples

Bulk samples of representative earth materials were obtained from the exploratory borings and test pits. The samples were bagged and transported to the laboratory for testing.

The Standard Penetration Test (SPT) Sampler

Disturbed drive samples of earth materials were obtained by means of a Standard Penetration Test sampler. The sampler is composed of a split barrel with an external diameter of 2 inches and an unlined internal diameter of 1-3/8 inches. The sampler was driven into the ground 12 to 18 inches with a 140-pound hammer free-falling from a height of 30 inches in general accordance with ASTM D 1586. The blow counts were recorded for every 6 inches of penetration; the blow counts reported on the logs are those for the last 12 inches of penetration. Soil samples were observed and removed from the sampler, bagged, sealed and transported to the laboratory for testing.


Field Procedure for the Collection of Relatively Undisturbed Samples

Relatively undisturbed soil samples were obtained in the field using the following methods.

The Modified Split-Barrel Drive Sampler

The sampler, with an external diameter of 3.0 inches, was lined with 1-inch long, thin brass rings with inside diameters of approximately 2.4 inches. The sample barrel was driven into the ground with the weight of a hammer in general accordance with ASTM D 3550. The driving weight was permitted to fall freely. The approximate length of the fall, the weight of the hammer, and the number of blows per foot of driving are presented on the boring logs as an index to the relative resistance of the materials sampled. The samples were removed from the sample barrel in the brass rings, sealed, and transported to the laboratory for testing.















DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	BORING LOG EXPLANATION SHEET
	Bulk	Driven						
0								<p>Bulk sample.</p> <p>Modified split-barrel drive sampler.</p> <p>No recovery with modified split-barrel drive sampler.</p> <p>Sample retained by others.</p> <p>Standard Penetration Test (SPT).</p> <p>No recovery with a SPT.</p> <p>Shelby tube sample. Distance pushed in inches/length of sample recovered in inches.</p> <p>No recovery with Shelby tube sampler.</p> <p>Continuous Push Sample.</p> <p>Seepage.</p> <p>Groundwater encountered during drilling.</p> <p>Groundwater measured after drilling.</p>
5			XX/XX					
10								
15							SM	<p>ALLUVIUM:</p> <p>Solid line denotes unit change.</p> <p>Dashed line denotes material change.</p> <p>Attitudes: Strike/Dip</p> <p>b: Bedding</p> <p>c: Contact</p> <p>j: Joint</p> <p>f: Fracture</p> <p>F: Fault</p> <p>cs: Clay Seam</p> <p>s: Shear</p> <p>bss: Basal Slide Surface</p> <p>sf: Shear Fracture</p> <p>sz: Shear Zone</p> <p>sbs: Sheared Bedding Surface</p>
20								<p>The total depth line is a solid line that is drawn at the bottom of the boring.</p>




BORING LOG

EXPLANATION OF BORING LOG SYMBOLS

PROJECT NO.	DATE Rev. 01/03	FIGURE
-------------	--------------------	--------


U.S.C.S. METHOD OF SOIL CLASSIFICATION				
MAJOR DIVISIONS		SYMBOL		TYPICAL NAMES
COARSE-GRAINED SOILS (More than 1/2 of soil >No. 200 sieve size)	GRAVELS (More than 1/2 of coarse fraction > No. 4 sieve size)		GW	Well graded gravels or gravel-sand mixtures, little or no fines
			GP	Poorly graded gravels or gravel-sand mixtures, little or no fines
			GM	Silty gravels, gravel-sand-silt mixtures
			GC	Clayey gravels, gravel-sand-clay mixtures
	SANDS (More than 1/2 of coarse fraction <No. 4 sieve size)		SW	Well graded sands or gravelly sands, little or no fines
			SP	Poorly graded sands or gravelly sands, little or no fines
			SM	Silty sands, sand-silt mixtures
			SC	Clayey sands, sand-clay mixtures
FINE-GRAINED SOILS (More than 1/2 of soil <No. 200 sieve size)	SILTS & CLAYS Liquid Limit <50		ML	Inorganic silts and very fine sands, rock flour, silty or clayey fine sands or clayey silts with
			CL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean
			OL	Organic silts and organic silty clays of low plasticity
	SILTS & CLAYS Liquid Limit >50		MH	Inorganic silts, micaceous or diatomaceous fine sandy or silty soils, elastic silts
			CH	Inorganic clays of high plasticity, fat clays
			OH	Organic clays of medium to high plasticity, organic silty clays, organic silts
HIGHLY ORGANIC SOILS			Pt	Peat and other highly organic soils

GRAIN SIZE CHART		
CLASSIFICATION	RANGE OF GRAIN SIZE	
	U.S. Standard Sieve Size	Grain Size in Millimeters
BOULDERS	Above 12"	Above 305
COBBLES	12" to 3"	305 to 76.2
GRAVEL Coarse Fine	3" to No. 4	76.2 to 4.76
	3" to 3/4"	76.2 to 19.1
	3/4" to No. 4	19.1 to 4.76
SAND Coarse Medium Fine	No. 4 to No. 200	4.76 to 0.075
	No. 4 to No. 10	4.76 to 2.00
	No. 10 to No. 40	2.00 to 0.420
	No. 40 to No. 200	0.420 to 0.075
SILT & CLAY	Below No. 200	Below 0.075




Ninyo & Moore	U.S.C.S. METHOD OF SOIL CLASSIFICATION
--------------------------	---

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/07/09</u> BORING NO. <u>B-1</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,080' ± (MSL)</u>	SHEET <u>1</u> OF <u>1</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
								DESCRIPTION/INTERPRETATION	
0							SM	<u>OLDER ALLUVIUM:</u> Brown, dry to damp, loose to medium dense, silty fine to coarse SAND.	
5			19	1.8	108.7			Medium dense.	
10			18					Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/07/09.	
15								<u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
20									




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-1

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/07/09</u> BORING NO. <u>B-2</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,070' ± (MSL)</u>	SHEET <u>1</u> OF <u>1</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
								DESCRIPTION/INTERPRETATION	
0							SM	<u>OLDER ALLUVIUM:</u> Brown, dry to damp, loose to medium dense, silty fine to coarse SAND.	
5			20					Medium dense to dense.	
10			64	2.3	119.9			Dense.	
15								Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/07/09.	
20								<u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-2

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/07/09</u> BORING NO. <u>B-3</u> GROUND ELEVATION <u>2,060' ± (MSL)</u> SHEET <u>1</u> OF <u>1</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
	Bulk	Driven						DESCRIPTION/INTERPRETATION	
0							SM	<u>OLDER ALLUVIUM:</u> Brown, dry to damp, loose to medium dense, silty fine to coarse SAND.	
5			19	2.9	111.5				
10			26					Dense.	
15								Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/07/09. Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
20									



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-3

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/07/09</u> BORING NO. <u>B-4</u> GROUND ELEVATION <u>2,045' ± (MSL)</u> SHEET <u>1</u> OF <u>1</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>		
	Bulk	Driven						DESCRIPTION/INTERPRETATION		
0							SM	<u>OLDER ALLUVIUM:</u> Brown, dry to damp, medium dense to dense, silty fine to coarse SAND.		
5			75	4.9	116.9			Very dense.		
10			44					Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/07/09. Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.		
15										
20										



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-4

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED	BORING NO.				
	Bulk	Driven						4/07/09	B-5				
								GROUND ELEVATION	2,095' ± (MSL)	SHEET	1	OF	1
								METHOD OF DRILLING 8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)					
								DRIVE WEIGHT	140 lbs. (Auto-Trip Hammer)	DROP	30"		
								SAMPLED BY	BTM	LOGGED BY	BTM	REVIEWED BY	JG
								DESCRIPTION/INTERPRETATION					
0							SM	OLDER ALLUVIUM: Brown, dry to damp, medium dense, silty fine to coarse SAND.					
5			15	2.9	111.2								
10			57					Very dense.					
15								Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/07/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.					
20													



BORING LOG


MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.
105879004



DATE
5/09


FIGURE
A-5

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/09/09</u> BORING NO. <u>B-7</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,055' ± (MSL)</u>	SHEET <u>1</u> OF <u>1</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
								DESCRIPTION/INTERPRETATION	
0							SM	<u>OLDER ALLUVIUM:</u> Brown, dry to damp, loose to medium dense, silty fine to coarse SAND.	
5			20	2.4	110.3			Medium dense.	
10			16					Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/09/09.	
15								<u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
20									




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-7

DEPTH (feet)	SAMPLES	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED	BORING NO.
							4/06/09	B-8
							GROUND ELEVATION	SHEET
							2,040' ± (MSL)	1 OF 1
							METHOD OF DRILLING	
							8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)	
							DRIVE WEIGHT	DROP
							140 lbs. (Auto-Trip Hammer)	30"
							SAMPLED BY	LOGGED BY
							MAH	MAH
							REVIEWED BY	RJ
DESCRIPTION/INTERPRETATION								
0		64	5.3	108.2		SM	OLDER ALLUVIUM: Brown, dry to damp, loose to medium dense, silty fine to coarse SAND.	
5							Damp; dense.	
10	22						Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/06/09.	
15							Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
20								




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-8

DEPTH (feet)	BULK DRIVEN	SAMPLES	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/06/09</u> BORING NO. <u>B-9</u>		
								GROUND ELEVATION <u>2,035' ± (MSL)</u> SHEET <u>1</u> OF <u>1</u>		
METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>		
SAMPLED BY <u>MAH</u> LOGGED BY <u>MAH</u> REVIEWED BY <u>RI</u>								DESCRIPTION/INTERPRETATION		
0							SM	OLDER ALLUVIUM: Brown, dry to damp, loose to medium dense, silty fine to coarse SAND.		
5			33					Damp; dense to very dense.		
10			26	3.4	110.4			Medium dense; fine to medium sand.		
15								Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/06/09. Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.		
20										



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-9

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED	BORING NO.				
	Bulk	Driven						4/07/09	B-10				
								GROUND ELEVATION	2,025' ± (MSL)	SHEET	1	OF	1
								METHOD OF DRILLING 8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)					
								DRIVE WEIGHT	140 lbs. (Auto-Trip Hammer)	DROP	30"		
								SAMPLED BY	BTM	LOGGED BY	BTM	REVIEWED BY	JG
								DESCRIPTION/INTERPRETATION					
0							SM	<u>OLDER ALLUVIUM:</u> Brown, damp to moist, loose to medium dense, silty fine to coarse SAND.					
5			13										
								Saturated.					
10			24										
								Total Depth = 11.5 feet. Groundwater encountered at a depth of approximately 8 feet during drilling. Backfilled shortly after drilling on 4/07/09.					
								<u>Note:</u> Groundwater may rise to a level higher than that measured in borehole due to seasonal variations in precipitation and several other factors as discussed in the report.					
15													
20													



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-10

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/07/09</u> BORING NO. <u>B-11</u> GROUND ELEVATION <u>2,100' ± (MSL)</u> SHEET <u>1</u> OF <u>1</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>		
	Bulk	Driven						DESCRIPTION/INTERPRETATION		
0							SM	<u>OLDER ALLUVIUM:</u> Brown, dry to damp, medium dense, silty fine to coarse SAND.		
5			26					Dense.		
10			58	3.2	111.4			Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/07/09.		
15								<u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.		
20										

Ninyo & Moore

BORING LOG


MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.
105879004

DATE
5/09


FIGURE
A-11

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/07/09</u> BORING NO. <u>B-12</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,085' ± (MSL)</u>	SHEET <u>1</u> OF <u>1</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
								DESCRIPTION/INTERPRETATION	
0							SM	<u>OLDER ALLUVIUM:</u> Brown, dry to damp, medium dense, silty fine to coarse SAND.	
5			48	6.2	109.5			Damp; dense.	
10			39					Very dense.	
15								Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/07/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
20									




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-12

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/09/09</u> BORING NO. <u>B-13</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,065' ± (MSL)</u>	SHEET <u>1</u> OF <u>1</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
								DESCRIPTION/INTERPRETATION	
0							SM	OLDER ALLUVIUM: Brown, dry to damp, medium dense, silty fine to coarse SAND.	
5			31	2.3	112.5				
10			41					Very dense. Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/09/09.	
15								<u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
20									




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-13

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/09/09</u> BORING NO. <u>B-14</u> GROUND ELEVATION <u>2,055' ± (MSL)</u> SHEET <u>1</u> OF <u>1</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>		
	Bulk	Driven						DESCRIPTION/INTERPRETATION		
0							SM	<u>OLDER ALLUVIUM:</u> Brown, dry to damp, medium dense, silty fine to coarse SAND.		
5			48	4.7	114.4			Dense.		
10			31					Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/09/09.		
15								<u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.		
20										




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-14

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/07/09</u> BORING NO. <u>B-16</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,035' ± (MSL)</u>	SHEET <u>1</u> OF <u>1</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
								DESCRIPTION/INTERPRETATION	
0							SM	OLDER ALLUVIUM: Brown, damp to moist, loose to medium dense, silty fine to coarse SAND.	
5			33	4.5	115.2				
10			26					Dense.	
15								Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/07/09. Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
20									




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-16

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/09/09</u> BORING NO. <u>B-17</u> GROUND ELEVATION <u>2,065' ± (MSL)</u> SHEET <u>1</u> OF <u>2</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
	Bulk	Driven						DESCRIPTION/INTERPRETATION	
0							SM	OLDER ALLUVIUM: Brown, dry to damp, loose to medium dense, silty fine to coarse SAND.	
5			40	1.9	116.0			Medium dense.	
10			26					Dense.	
15			80/11"					Very dense.	
20									




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-17

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/09/09</u> BORING NO. <u>B-17</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,065' ± (MSL)</u> SHEET <u>2</u> OF <u>2</u>	METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
								DESCRIPTION/INTERPRETATION	
20			27				SM	<p><u>OLDER ALLUVIUM: (Continued)</u> Brown, dry to damp, dense, silty fine to medium SAND.</p>	
25								<p>Total Depth = 21.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/09/09.</p> <p><u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.</p>	
30									
35									
40									





BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-18

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/09/09</u> BORING NO. <u>B-18</u> GROUND ELEVATION <u>2,060' ± (MSL)</u> SHEET <u>1</u> OF <u>2</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>		
	Bulk	Driven						DESCRIPTION/INTERPRETATION		
0							SM	<u>OLDER ALLUVIUM:</u> Brown, dry to damp, medium dense, silty fine to coarse SAND.		
5			45	1.8	116.9			Dense.		
10			44					Very dense.		
15			38					Medium dense.		
20							CH	Brown, damp, very stiff, sandy CLAY.		




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-19

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/09/09</u> BORING NO. <u>B-18</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,060' ± (MSL)</u> SHEET <u>2</u> OF <u>2</u>	METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u>	DROP <u>30"</u>
								SAMPLED BY <u>BTM</u>	LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>
DESCRIPTION/INTERPRETATION									
20			18				CH	OLDER ALLUVIUM: (Continued) Brown, damp, very stiff, sandy CLAY.	
25								Total Depth = 21.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/09/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
30									
35									
40									





BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-20

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/09/09</u> BORING NO. <u>B-19</u> GROUND ELEVATION <u>2,065' ± (MSL)</u> SHEET <u>1</u> OF <u>2</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
	Bulk	Driven						DESCRIPTION/INTERPRETATION	
0							SW-SM	<u>OLDER ALLUVIUM:</u> Brown, dry to damp, medium dense, well-graded SAND with silt.	
5			56	2.3	114.2			Dense.	
10			47					Very dense.	
15			66					Dense; fine sand.	
20							CL	Brown, damp, very stiff, sandy CLAY.	




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-21

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/09/09</u> BORING NO. <u>B-19</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,065' ± (MSL)</u>	SHEET <u>2</u> OF <u>2</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
								DESCRIPTION/INTERPRETATION	
20			17				CL	<p>OLDER ALLUVIUM: (Continued) Brown, damp, very stiff, sandy CLAY.</p>	
25								<p>Total Depth = 21.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/09/09.</p> <p><u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.</p>	
30									
35									
40									




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-22

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/09/09</u> BORING NO. <u>B-20</u> GROUND ELEVATION <u>2,070' ± (MSL)</u> SHEET <u>1</u> OF <u>2</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
	Bulk	Driven						DESCRIPTION/INTERPRETATION	
0							SM	<u>OLDER ALLUVIUM:</u> Brown, dry to damp, medium dense, silty fine to coarse SAND.	
5			61	4.1	116.8			Dense.	
10			65					Very dense.	
15			52					Damp; dense.	
20									



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-23

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/09/09</u> BORING NO. <u>B-20</u> GROUND ELEVATION <u>2,070' ± (MSL)</u> SHEET <u>2</u> OF <u>2</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>		
	Bulk	Driven						DESCRIPTION/INTERPRETATION		
20			27				SM	<u>OLDER ALLUVIUM: (Continued)</u> Brown, damp, dense, silty fine to medium SAND.		
25								Total Depth = 21.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/09/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.		
30										
35										
40										



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-24

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/09/09</u> BORING NO. <u>B-21</u> GROUND ELEVATION <u>2,070' ± (MSL)</u> SHEET <u>1</u> OF <u>2</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>
	Bulk	Driven						
0							SM	OLDER ALLUVIUM: Brown, dry to damp, loose to medium dense, silty fine to coarse SAND.
5			37	4.2	118.7			Medium dense.
10			31					Dense.
15			72					Very dense.
20							CL	Brown, damp, very stiff, sandy CLAY.

Ninyo & Moore


BORING LOG


MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.
105879004

DATE
5/09

FIGURE
A-25

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/09/09</u> BORING NO. <u>B-21</u> GROUND ELEVATION <u>2,070' ± (MSL)</u> SHEET <u>2</u> OF <u>2</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
	Bulk	Driven						DESCRIPTION/INTERPRETATION	
20			19				CL	<p>OLDER ALLUVIUM: (Continued) Brown, damp, very stiff, sandy CLAY.</p>	
25								<p>Total Depth = 21.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/09/09.</p> <p><u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.</p>	
30									
35									
40									




BORING LOG

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA


PROJECT NO.	DATE	FIGURE
105879004	5/09	A-26

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/06/09</u> BORING NO. <u>B-22</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,060' ± (MSL)</u>	SHEET <u>1</u> OF <u>1</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>MAH</u> LOGGED BY <u>MAH</u> REVIEWED BY <u>RI</u>	
								DESCRIPTION/INTERPRETATION	
0							SM	<u>OLDER ALLUVIUM:</u> Brown, damp, medium dense, silty fine to coarse SAND.	
5			19						
10			60	2.2	109.5			Dense.	
15								Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/06/09. Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
20									




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-27

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/06/09</u> BORING NO. <u>B-23</u> GROUND ELEVATION <u>2,050' ± (MSL)</u> SHEET <u>1</u> OF <u>1</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>MAH</u> LOGGED BY <u>MAH</u> REVIEWED BY <u>RI</u>		
	Bulk	Driven						DESCRIPTION/INTERPRETATION		
0							SM	OLDER ALLUVIUM: Brown, damp, loose, silty fine to coarse SAND.		
5			12	2.1	108.5					
10			26					Dense.		
15								Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/06/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.		
20										




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-28

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/07/09</u> BORING NO. <u>B-24</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,040' ± (MSL)</u>	SHEET <u>1</u> OF <u>1</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
								DESCRIPTION/INTERPRETATION	
0							SM	<u>OLDER ALLUVIUM:</u> Brown, damp, loose to medium dense, silty fine to coarse SAND.	
5			17					Medium dense.	
10			27	10.5	110.6			Moist.	
15								Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/07/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
20									



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-29

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/07/09</u> BORING NO. <u>B-25</u> GROUND ELEVATION <u>2,035' ± (MSL)</u> SHEET <u>1</u> OF <u>1</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>		
	Bulk	Driven						DESCRIPTION/INTERPRETATION		
0							SM	OLDER ALLUVIUM: Brown, dry to damp, loose to medium dense, silty fine to coarse SAND. Medium dense.		
5			22	3.5	110.8					
10			21				Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/07/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.			
15										
20										




BORING LOG

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA


PROJECT NO.	DATE	FIGURE
105879004	5/09	A-30

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/09/09</u> BORING NO. <u>B-26</u> GROUND ELEVATION <u>2,050' ± (MSL)</u> SHEET <u>1</u> OF <u>1</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>		
	Bulk	Driven						DESCRIPTION/INTERPRETATION		
0							SM	OLDER ALLUVIUM: Brown, dry to damp, medium dense, silty fine to coarse SAND.		
5			62	4.7	121.7			Dense.		
10			17					Damp to moist; medium dense.		
15								Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/09/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.		
20										



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-31


DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/07/09</u> BORING NO. <u>B-27</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,060' ± (MSL)</u>	SHEET <u>1</u> OF <u>1</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>.30"</u>	
								SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
								DESCRIPTION/INTERPRETATION	
0							SM	<u>OLDER ALLUVIUM:</u> Brown, dry to damp, loose to medium dense, silty fine to coarse SAND.	
5			18					Medium dense.	
10			31	24.3	97.9			Moist to wet; micaceous.	
15								Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/07/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
20									



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-32

DEPTH (feet)		BULK DRIVEN	SAMPLES	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED	BORING NO.
									4/08/09	B-28
									2,060' ± (MSL)	SHEET 1 OF 1
									8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)	
									140 lbs. (Auto-Trip Hammer)	DROP 30"
									BTM	LOGGED BY BTM REVIEWED BY JG
DESCRIPTION/INTERPRETATION										
0								SM	OLDER ALLUVIUM: Brown, dry to damp, loose to medium dense, silty fine to coarse SAND.	
5				17	2.3	112.6			Medium dense.	
10				33					Dense to very dense.	
15									Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/08/09.	
20									Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/08/09</u> BORING NO. <u>B-29</u> GROUND ELEVATION <u>2,055' ± (MSL)</u> SHEET <u>1</u> OF <u>1</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
	Bulk	Driven						DESCRIPTION/INTERPRETATION	
0							SM	OLDER ALLUVIUM: Brown, dry to damp, loose to medium dense, silty fine to coarse SAND.	
5			38	6.5	120.4			Damp; medium dense.	
10			21					Dense.	
15								Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/08/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
20									



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-34

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/07/09</u> BORING NO. <u>B-30</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,060' ± (MSL)</u>	SHEET <u>1</u> OF <u>1</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
								DESCRIPTION/INTERPRETATION	
0							SM	OLDER ALLUVIUM: Brown, dry to damp, loose to medium dense, silty fine to coarse SAND.	
5			42	6.8	116.5			Damp; medium dense to dense.	
10			23					Dense.	
15								Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/07/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
20									

Ninyo & Moore

BORING LOG

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.
105879004

DATE
5/09

FIGURE
A-35

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED	BORING NO.				
	Bulk	Driven						4/07/09	B-31				
								GROUND ELEVATION	2,080' ± (MSL)	SHEET	1	OF	1
								METHOD OF DRILLING 8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)					
								DRIVE WEIGHT	140 lbs. (Auto-Trip Hammer)	DROP	30"		
								SAMPLED BY	BTM	LOGGED BY	BTM	REVIEWED BY	JG
								DESCRIPTION/INTERPRETATION					
0							SM	OLDER ALLUVIUM: Brown, dry to damp, medium dense, silty fine to coarse SAND.					
5			49	8.9	113.9			Damp; dense.					
10			22										
15								Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/07/09.					
20								Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.					

Ninyo & Moore

BORING LOG


MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.
105879004

DATE
5/09


FIGURE
A-36

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/07/09</u> BORING NO. <u>B-32</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,090' ± (MSL)</u>	SHEET <u>1</u> OF <u>1</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
								DESCRIPTION/INTERPRETATION	
0							SM	OLDER ALLUVIUM: Brown, dry to damp, medium dense, silty fine to coarse SAND.	
5			29	3.3	117.5			Dense.	
10								Damp; fine to medium sand.	
15								Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/07/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
20									




BORING LOG
 MOJAVE SOLAR PROJECT
 LOCKHART, CALIFORNIA

PROJECT NO. 105879004	DATE 5/09	FIGURE A-37
--------------------------	--------------	----------------


DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED	BORING NO.				
	Bulk	Driven						4/03/09	B-33				
								GROUND ELEVATION	2,050' ± (MSL)	SHEET	1	OF	2
								METHOD OF DRILLING 8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)					
								DRIVE WEIGHT	140 lbs. (Auto-Trip Hammer)	DROP	30"		
								SAMPLED BY	BTM	LOGGED BY	BTM	REVIEWED BY	RI
								DESCRIPTION/INTERPRETATION					
0							SM	OLDER ALLUVIUM: Brown, dry, medium dense, silty fine SAND.					
5			18										
10			67	4.8	125.4			Damp; dense; fine to medium sand.					
15			23					Fine sand.					
20													
								BORING LOG MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA					
PROJECT NO. 105879004								DATE 5/09		FIGURE A-38			

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/03/09</u> BORING NO. <u>B-33</u> GROUND ELEVATION <u>2,050' ± (MSL)</u> SHEET <u>2</u> OF <u>2</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>RI</u>	
	Bulk	Driven						DESCRIPTION/INTERPRETATION	
20			85/11"	3.7	122.8	SM		OLDER ALLUVIUM: (Continued) Brown, damp, very dense, silty fine SAND.	
25			27					Moist; dense; fine to medium sand.	
30								Total Depth = 26.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/03/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
35									
40									




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-39

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/02/09</u> BORING NO. <u>B-34</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,050' ± (MSL)</u>	SHEET <u>1</u> OF <u>2</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>RI</u>	
								DESCRIPTION/INTERPRETATION	
0							SM	<u>OLDER ALLUVIUM:</u> Brown, dry, dense, silty fine to coarse SAND.	
5			58						
10			41					Very dense.	
15			32	3.9	114.2			Medium dense.	
20									



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-40

DEPTH (feet)	SAMPLES	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED	BORING NO.
							4/02/09	B-34
							GROUND ELEVATION	SHEET
							2,050' ± (MSL)	2 OF 2
							METHOD OF DRILLING 8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)	
							DRIVE WEIGHT	DROP
							140 lbs. (Auto-Trip Hammer)	30"
							SAMPLED BY	LOGGED BY
							BTM	BTM
							REVIEWED BY	RI
							DESCRIPTION/INTERPRETATION	
20		42				SM	OLDER ALLUVIUM: (Continued) Brown, dry to damp, very dense, silty fine to coarse SAND.	
25		53	8.5	114.9			Reddish brown; damp; dense; fine sand.	
30							Total Depth = 26.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/02/09.	
35							Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
40								



BORING LOG

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.	DATE	FIGURE
105879004	5/09	A-41

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/08/09</u> BORING NO. <u>B-35</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,055' ± (MSL)</u>	SHEET <u>1</u> OF <u>3</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
								DESCRIPTION/INTERPRETATION	
0							SM	OLDER ALLUVIUM: Brown, dry to damp, medium dense, silty fine to coarse SAND.	
5			27					Dense.	
10			45	5.3	118.6				
15			20					Damp; medium dense to dense.	
20									

Ninyo & Moore

BORING LOG

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.
105879004

DATE
5/09

FIGURE
A-42

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/08/09</u> BORING NO. <u>B-35</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,055' ± (MSL)</u>	SHEET <u>2</u> OF <u>3</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
DESCRIPTION/INTERPRETATION									
20			36				SM	OLDER ALLUVIUM: (Continued) Brown, damp to moist, medium dense, silty fine to medium SAND.	
25			39					Very dense; silty fine sand.	
30			79					Wet; silty fine to coarse sand.	
35			12				SC	Brown, saturated, medium dense, clayey fine to medium SAND.	
40									

Ninyo & Moore

BORING LOG


MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.
105879004


DATE
5/09

FIGURE
A-43

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/08/09</u> BORING NO. <u>B-35</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,055' ± (MSL)</u>	SHEET <u>3</u> OF <u>3</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
								DESCRIPTION/INTERPRETATION	
40			38				SC	OLDER ALLUVIUM: (Continued) Brown, saturated, medium dense, clayey fine to medium SAND.	
							CH	Brown, wet, hard, fine sandy silty CLAY.	
45			17					Very stiff.	
50			43					Hard.	
55								Total Depth = 51.5 feet. Groundwater encountered at a depth of approximately 32 feet during drilling. Backfilled shortly after drilling on 4/08/09.	
60								<u>Note:</u> Groundwater may rise to a level higher than that measured in borehole due to relatively slow rate of seepage in clay and several other factors as discussed in the report. Please refer to the report for groundwater monitoring recommendations.	



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-44

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED	BORING NO.				
	Bulk	Driven						4/02/09	B-36				
								GROUND ELEVATION	2,050' ± (MSL)	SHEET	1	OF	2
								METHOD OF DRILLING 8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)					
								DRIVE WEIGHT	140 lbs. (Auto-Trip Hammer)	DROP	30"		
								SAMPLED BY	BTM	LOGGED BY	BTM	REVIEWED BY	RI
								DESCRIPTION/INTERPRETATION					
0							SP-SM	OLDER ALLUVIUM: Brown, dry, medium dense, poorly graded SAND with silt.					
5			18										
10			61	4.0	117.0			Damp; dense.					
15			25										
20													
								BORING LOG MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA					
PROJECT NO. 105879004				DATE 5/09		FIGURE A-45							


DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/02/09</u> BORING NO. <u>B-36</u> GROUND ELEVATION <u>2,050' ± (MSL)</u> SHEET <u>2</u> OF <u>2</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>RI</u>		
	Bulk	Driven						DESCRIPTION/INTERPRETATION		
20			90/11"	5.0	116.2		SP-SM	OLDER ALLUVIUM: (Continued) Brown, damp, very dense, poorly graded SAND with silt.		
25			20					Medium dense to dense.		
30								Total Depth = 26.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/02/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.		
35										
40										

BORING LOG


MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.	DATE	FIGURE
105879004	5/09	A-46

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED	BORING NO.		
	Bulk	Driven						4/03/09	B-37		
								GROUND ELEVATION	SHEET	OF	
								METHOD OF DRILLING	8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)		
								DRIVE WEIGHT	140 lbs. (Auto-Trip Hammer)	DROP	30"
								SAMPLED BY	BTM	LOGGED BY	BTM
										REVIEWED BY	RI
DESCRIPTION/INTERPRETATION											
20			44	3.2	114.1		SM	OLDER ALLUVIUM: (Continued) Brown, damp, dense, silty fine to coarse SAND.			
25			30					Fine sand.			
30								Total Depth = 26.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/03/09.			
35								<u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.			
40											




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-48

	BORING LOG MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
	PROJECT NO.	DATE	FIGURE
	105879004	5/09	A-49

20
25
30
35
40


DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/02/09</u> BORING NO. <u>B-39</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,055' ± (MSL)</u>	SHEET <u>1</u> OF <u>2</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>RI</u>	
								DESCRIPTION/INTERPRETATION	
0							SM	OLDER ALLUVIUM: Brown, dry to damp, dense, silty fine to coarse SAND.	
5			46	9.4	105.3			Damp.	
10			37					Very dense.	
15			44	5.6	120.7			Dense.	
20									




BORING LOG


MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO. 105879004	DATE 5/09	FIGURE A-51
--------------------------	--------------	----------------

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/02/09</u> BORING NO. <u>B-39</u> GROUND ELEVATION <u>2,055' ± (MSL)</u> SHEET <u>2</u> OF <u>2</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>RI</u>		
	Bulk	Driven						DESCRIPTION/INTERPRETATION		
20			55				SM	OLDER ALLUVIUM: (Continued) Brown, damp, very dense, silty fine to coarse SAND.		
25			69	6.8	113.2			Dense.		
30								Total Depth = 26 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/02/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.		
35										
40										



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-52

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED	BORING NO.				
	Bulk	Driven						4/03/09	B-40				
								GROUND ELEVATION	2,055' ± (MSL)	SHEET	1	OF	2
								METHOD OF DRILLING 8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)					
								DRIVE WEIGHT	140 lbs. (Auto-Trip Hammer)	DROP	30"		
								SAMPLED BY	BTM	LOGGED BY	BTM	REVIEWED BY	RI
								DESCRIPTION/INTERPRETATION					
0							SM	OLDER ALLUVIUM: Brown, dry to damp, medium dense, silty fine to coarse SAND.					
5			28										
10			27					Dense; fine to medium sand.					
15			43										
20													
								BORING LOG					
								MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA					
								PROJECT NO.	DATE	FIGURE			
								105879004	5/09	A-53			

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/03/09</u> BORING NO. <u>B-40</u> GROUND ELEVATION <u>2,055' ± (MSL)</u> SHEET <u>2</u> OF <u>2</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>RI</u>		
	Bulk	Driven						DESCRIPTION/INTERPRETATION		
20			30				SM	OLDER ALLUVIUM: (Continued) Brown, damp, dense, silty fine to medium SAND.		
25			85					Very dense.		
30								Total Depth = 26.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/03/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.		
35										
40										

Ninyo & Moore

BORING LOG


MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.
105879004

DATE
5/09


FIGURE
A-54

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/03/09</u> BORING NO. <u>B-41</u> GROUND ELEVATION <u>2,055' ± (MSL)</u> SHEET <u>1</u> OF <u>2</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>RI</u>		
	Bulk	Driven						DESCRIPTION/INTERPRETATION		
0							SW-SM	<u>OLDER ALLUVIUM:</u> Brown, damp, medium dense, well-graded SAND with silt.		
5			19							
10			49	7.5	116.0			Dense.		
15			14					Medium dense.		
20										



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-55

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/03/09</u> BORING NO. <u>B-41</u> GROUND ELEVATION <u>2,055' ± (MSL)</u> SHEET <u>2</u> OF <u>2</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>RI</u>	
	Bulk	Driven						DESCRIPTION/INTERPRETATION	
20			43	2.3	120.9		SW-SM	OLDER ALLUVIUM: (Continued) Brown, damp, dense, well-graded SAND with silt.	
25			18				CL	Brown, damp, very stiff, fine sandy CLAY.	
30								Total Depth = 26.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/03/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
35									
40									



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-56

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/02/09</u>	BORING NO. <u>B-42</u>
	Bulk	Driven						GROUND ELEVATION <u>2,055' ± (MSL)</u>	SHEET <u>1</u> OF <u>2</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u>	DROP <u>30"</u>
								SAMPLED BY <u>BTM</u>	LOGGED BY <u>BTM</u> REVIEWED BY <u>RI</u>
DESCRIPTION/INTERPRETATION									

0							SW-SM	OLDER ALLUVIUM: Brown, dry to damp, medium dense, well-graded SAND with silt.
5								
			8					
10								
			46	2.2	118.6		Dense.	
15								
			23					
20								

Ninyo & Moore

BORING LOG

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.
105879004

DATE
5/09

FIGURE
A-57

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED	BORING NO.				
	Bulk	Driven						4/02/09	B-42				
								GROUND ELEVATION	2,055' ± (MSL)	SHEET	2	OF	2
								METHOD OF DRILLING 8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)					
								DRIVE WEIGHT	140 lbs. (Auto-Trip Hammer)	DROP	30"		
								SAMPLED BY	BTM	LOGGED BY	BTM	REVIEWED BY	RI
								DESCRIPTION/INTERPRETATION					
20			87/11"	5.0	122.7	[Pattern]	SM	<p>OLDER ALLUVIUM: (Continued)</p> <p>Brown, damp, very dense, silty fine SAND.</p>					
25			31					<p>Dense.</p>					
30								<p>Total Depth = 26.5 feet.</p> <p>Groundwater not encountered during drilling.</p> <p>Backfilled shortly after drilling on 4/02/09.</p> <p><u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.</p>					
35													
40													

BORING LOG

MOJAVE SOLAR PROJECT

LOCKHART, CALIFORNIA

PROJECT NO.

105879004

DATE

5/09

FIGURE

A-58

0				SM	<u>OLDER ALLUVIUM:</u> Brown, dry to damp, very dense, silty fine to coarse SAND.
5					
10					
15					
20					




DEPTH (feet)	SAMPLES	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/03/09</u> BORING NO. <u>B-43</u>		
							GROUND ELEVATION <u>2,055' ± (MSL)</u> SHEET <u>2</u> OF <u>2</u>		
							METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)</u>		
							DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>		
							SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>RI</u>		
							DESCRIPTION/INTERPRETATION		
20	■	68			■	SM	<p><u>OLDER ALLUVIUM:</u> (Continued) Brown, damp, dense, silty fine to medium SAND.</p>		
25	▲	28			■				
30							<p>Total Depth = 26.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/03/09.</p> <p><u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.</p>		
35									
40									

BORING LOG







MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO. 105879004	DATE 5/09	FIGURE A-60
--------------------------	--------------	----------------

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/02/09</u> BORING NO. <u>B-44</u> GROUND ELEVATION <u>2,055' ± (MSL)</u> SHEET <u>1</u> OF <u>3</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>RI</u>	
	Bulk	Driven						DESCRIPTION/INTERPRETATION	
0							SM	<u>OLDER ALLUVIUM:</u> Brown, dry to damp, dense, silty fine to coarse SAND.	
5			28						
10			47	1.4	115.4			Fine sand.	
15			27						
20									



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-61

DEPTH (feet)	SAMPLES Bulk Driven	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/02/09</u> BORING NO. <u>B-44</u> GROUND ELEVATION <u>2,055' ± (MSL)</u> SHEET <u>2</u> OF <u>3</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>RI</u>		
							DESCRIPTION/INTERPRETATION		
20		73	6.8	118.1		SM	OLDER ALLUVIUM: (Continued) Brown, damp, very dense, silty fine to medium SAND.		
25		20					Medium dense to dense; fine sand.		
30		21	4.9	116.6			Micaceous. Wet. Saturated.		
35		17				SC	Brown, moist, medium dense, clayey SAND.		
40							Dense; micaceous.		

Ninyo & Moore

BORING LOG

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.
105879004

DATE
5/09

FIGURE
A-62

DEPTH (feet)	SAMPLES Bulk Driven	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED	BORING NO.
							4/02/09	B-44
							GROUND ELEVATION	SHEET
							2,055' ± (MSL)	3 OF 3
							METHOD OF DRILLING	
							8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)	
							DRIVE WEIGHT	DROP
							140 lbs. (Auto-Trip Hammer)	30"
							SAMPLED BY	LOGGED BY
							BTM	BTM
							REVIEWED BY	RI
DESCRIPTION/INTERPRETATION								
40		23				SC	ALLUVIUM: (Continued) Brown, moist, dense, silty clayey SAND; micaceous.	
						CL	Grayish brown, moist, hard, silty fine sandy CLAY.	
45		22						
50		32	24.6	97.1				
							Total Depth = 51.5 feet. Groundwater encountered at a depth of approximately 33 feet during drilling. (Perched) Backfilled shortly after drilling on 4/02/09. <u>Note:</u> Groundwater may rise to a level higher than that measured in borehole due to seasonal variations in precipitation and several other factors as discussed in the report.	
55								
60								

Ninyo & Moore

BORING LOG

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.
105879004

DATE
5/09

FIGURE
A-63

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/02/09</u> BORING NO. <u>B-45</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,055' ± (MSL)</u>	SHEET <u>1</u> OF <u>2</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>RI</u>	
								DESCRIPTION/INTERPRETATION	
0							SM	OLDER ALLUVIUM: Brown, dry to damp, medium dense, silty fine to coarse SAND.	
5			31						
10			23					Dense; fine to medium sand.	
15			37	4.6	119.3			Medium dense; fine to coarse sand.	
20									

Ninyo & Moore


BORING LOG

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.
105879004

DATE
5/09

FIGURE
A-64

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/02/09</u> BORING NO. <u>B-45</u> GROUND ELEVATION <u>2,055' ± (MSL)</u> SHEET <u>2</u> OF <u>2</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>RI</u>		
	Bulk	Driven						DESCRIPTION/INTERPRETATION		
20			48				SM	OLDER ALLUVIUM: (Continued) Brown, damp, very dense, silty fine to medium SAND.		
25			48	5.3	117.7			Dense; fine to coarse sand.		
30								Total Depth = 26.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/02/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.		
35										
40										

BORING LOG


MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.
105879004

DATE
5/09


FIGURE
A-65

DEPTH (feet)	SAMPLES	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED	BORING NO.	
							4/03/09	B-46	
							GROUND ELEVATION	SHEET	OF
							2,055' ± (MSL)	1	2
							METHOD OF DRILLING		
							8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)		
							DRIVE WEIGHT	DROP	
							140 lbs. (Auto-Trip Hammer)	30"	
							SAMPLED BY	LOGGED BY	REVIEWED BY
							BTM	BTM	RI
							DESCRIPTION/INTERPRETATION		
0						SM	OLDER ALLUVIUM: Brown, dry to damp, dense, silty fine to coarse SAND.		
5		54	7.9	110.8					
10		22					Fine to medium sand.		
15		59	10.8	114.2					
20									




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-66

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/03/09</u> BORING NO. <u>B-46</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,055' ± (MSL)</u>	SHEET <u>2</u> OF <u>2</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>RI</u>	
								DESCRIPTION/INTERPRETATION	
20			58				SM	<u>OLDER ALLUVIUM: (Continued)</u> Brown, damp, very dense, silty fine to medium SAND.	
25			68	5.7	109.6				
30								Total Depth = 26 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/03/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
35									
40									




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-67

DEPTH (feet)	SAMPLES Bulk Driven	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED	BORING NO.
							4/03/09	B-47
							GROUND ELEVATION	SHEET
							2,055' ± (MSL)	1 OF 1
							METHOD OF DRILLING	
							8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)	
							DRIVE WEIGHT	DROP
							140 lbs. (Auto-Trip Hammer)	30"
							SAMPLED BY	LOGGED BY
							BTM	BTM
							REVIEWED BY	RI
DESCRIPTION/INTERPRETATION								
0						SM	OLDER ALLUVIUM: Brown, dry to damp, dense, silty fine to medium SAND.	
5		54	3.5	115.0				
10		26						
15							Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/03/09. Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
20								




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-68

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/02/09</u> BORING NO. <u>B-48</u> GROUND ELEVATION <u>2,055' ± (MSL)</u> SHEET <u>1</u> OF <u>2</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>RI</u>	
	Bulk	Driven						DESCRIPTION/INTERPRETATION	
0							SM	OLDER ALLUVIUM: Brown, dry to damp, dense, silty fine to coarse SAND.	
5			23						
10			76	3.9	120.6			Very dense; fine sand.	
15			33					Dense to very dense.	
20									




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-69

DEPTH (feet)	SAMPLES Bulk Driven	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED	BORING NO.
							GROUND ELEVATION	SHEET
							4/02/09	B-48
							2,055' ± (MSL)	2 OF 2
							METHOD OF DRILLING 8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)	
							140 lbs. (Auto-Trip Hammer)	DROP 30"
							SAMPLED BY BTM	LOGGED BY BTM REVIEWED BY RI
DESCRIPTION/INTERPRETATION								
20		88	5.3	118.0		SM	OLDER ALLUVIUM: (Continued) Brown, damp, very dense, silty fine to coarse SAND.	
25		30					Dense; fine sand.	
30							Total Depth = 26.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/02/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
35								
40								





BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-70

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/03/09</u> BORING NO. <u>B-49</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,055' ± (MSL)</u> SHEET <u>1</u> OF <u>2</u>	METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)</u>
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>RI</u>	
								DESCRIPTION/INTERPRETATION	
0							SM	OLDER ALLUVIUM: Brown, damp, dense, silty fine to coarse SAND.	
5			26						
10			88					Very dense.	
15			36					Fine to medium sand.	
20									




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-71

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/03/09</u> BORING NO. <u>B-49</u> GROUND ELEVATION <u>2,055' ± (MSL)</u> SHEET <u>2</u> OF <u>2</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>RI</u>		
	Bulk	Driven						DESCRIPTION/INTERPRETATION		
20			90/11"				SM	OLDER ALLUVIUM: (Continued) Brown, damp, very dense, silty fine to coarse SAND.		
25			28					Dense.		
30								Total Depth = 26.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/03/09.		
35								<u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.		
40										




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-72

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/03/09</u> BORING NO. <u>B-50</u> GROUND ELEVATION <u>2,055' ± (MSL)</u> SHEET <u>1</u> OF <u>2</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>RI</u>		
	Bulk	Driven						DESCRIPTION/INTERPRETATION		
0							SM	OLDER ALLUVIUM: Brown, dry to damp, dense, silty fine to coarse SAND.		
5			26							
10			29					Medium dense.		
15			29					Dense.		
20										




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-73

DEPTH (feet)	SAMPLES	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED	BORING NO.	
							4/03/09	B-50	
							GROUND ELEVATION	SHEET	OF
							2,055' ± (MSL)	2	2
							METHOD OF DRILLING		
							8" Diameter Hollow-Stem Auger (AT B-52) (Cal Pac Drilling)		
							DRIVE WEIGHT	DROP	
							140 lbs. (Auto-Trip Hammer)	30"	
							SAMPLED BY	LOGGED BY	REVIEWED BY
							BTM	BTM	RI
DESCRIPTION/INTERPRETATION									
20		67				SM	OLDER ALLUVIUM: (Continued) Brown, damp, dense, silty fine to medium SAND.		
25		32					Total Depth = 26.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/03/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.		
30									
35									
40									




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-74

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/06/09</u> BORING NO. <u>B-51</u> GROUND ELEVATION <u>2,055' ± (MSL)</u> SHEET <u>1</u> OF <u>2</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>MAH</u> LOGGED BY <u>MAH</u> REVIEWED BY <u>RI</u>	
	Bulk	Driven						DESCRIPTION/INTERPRETATION	
0							SM	<u>OLDER ALLUVIUM:</u> Brown, dry to damp, medium dense, silty fine to coarse SAND.	
5			74	4.6	127.2			Very dense.	
10			26					Damp; dense.	
15			38					Medium dense.	
20									




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-75

DEPTH (feet)	SAMPLES Bulk Driven	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED	BORING NO.
							GROUND ELEVATION	SHEET
							4/06/09	B-51
							2,055' ± (MSL)	2 OF 2
							METHOD OF DRILLING 8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)	
							140 lbs. (Auto-Trip Hammer)	DROP 30"
							SAMPLED BY MAH	LOGGED BY MAH REVIEWED BY RI
							DESCRIPTION/INTERPRETATION	
20		21				SM	OLDER ALLUVIUM: (Continued) Brown, damp, dense, silty fine to coarse SAND.	
25		71				SC	Brown, damp, very dense, clayey SAND.	
30							Total Depth = 26.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/06/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
35								
40								






BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-76

DEPTH (feet)	SAMPLES Bulk Driven	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED	BORING NO.
							4/08/09	B-52
							GROUND ELEVATION	SHEET
							2,055' ± (MSL)	1 OF 2
							METHOD OF DRILLING	
							8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)	
							DRIVE WEIGHT	DROP
							140 lbs. (Auto-Trip Hammer)	30"
							SAMPLED BY	LOGGED BY
							BTM	BTM
							REVIEWED BY	JG
DESCRIPTION/INTERPRETATION								
0						SM	OLDER ALLUVIUM: Brown, dry to damp, medium dense, silty fine to medium SAND.	
5		29					Dense.	
10		25	5.6	124.0			Medium dense; fine to coarse sand.	
15		21					Dense.	
20								




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-77

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/08/09</u> BORING NO. <u>B-52</u> GROUND ELEVATION <u>2,055' ± (MSL)</u> SHEET <u>2</u> OF <u>2</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
	Bulk	Driven						DESCRIPTION/INTERPRETATION	
20			47				SM	<u>OLDER ALLUVIUM:</u> (Continued) Brown, dry to damp, dense, silty fine to coarse SAND.	
25			26				CL	Brown, damp, hard, sandy CLAY.	
30								Total Depth = 26.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/08/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
35									
40									




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-78

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/08/09</u> BORING NO. <u>B-53</u>	
	Bulk Driven							GROUND ELEVATION <u>2,055' ± (MSL)</u>	SHEET <u>1</u> OF <u>3</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
								DESCRIPTION/INTERPRETATION	
0							SM	<u>OLDER ALLUVIUM:</u> Brown, dry to damp, medium dense, silty fine to medium SAND.	
5			36					Very dense.	
10			26	10.5	110.4			Damp; medium dense; fine to coarse sand.	
15			22					Dense.	
20									





BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-79

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/08/09</u> BORING NO. <u>B-53</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,055' ± (MSL)</u>	SHEET <u>2</u> OF <u>3</u>
METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>								DESCRIPTION/INTERPRETATION	
20			55				SM	OLDER ALLUVIUM: (Continued) Brown, damp, dense, silty fine to coarse SAND.	
25			20				CH	Brown, damp, very stiff to hard, sandy silty CLAY; micaceous.	
30			41					Wet; hard.	
35			31				SM	Brown, wet, dense, silty fine to coarse SAND; scattered gravel; micaceous.	
40									



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-80

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/08/09</u> BORING NO. <u>B-53</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,055' ± (MSL)</u>	SHEET <u>3</u> OF <u>3</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
								DESCRIPTION/INTERPRETATION	
40			18				SM	OLDER ALLUVIUM: (Continued) Brown, wet, medium dense, silty fine to coarse SAND.	
45			25					Dense; silty fine sand; micaceous.	
							CL	Grayish brown, wet, very stiff, fine sandy silty CLAY; micaceous.	
50			14					Total Depth = 51.5 feet. Groundwater encountered at a depth of approximately 27 feet during drilling. Backfilled shortly after drilling on 4/08/09. <u>Note:</u> Groundwater may rise to a level higher than that measured in borehole due to relatively slow rate of seepage in clay and several other factors as discussed in the report. Please refer to the report for groundwater monitoring recommendations.	
55									
60									

Ninyo & Moore

BORING LOG


MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.
105879004

DATE
5/09


FIGURE
A-81

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/08/09</u> BORING NO. <u>B-54</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,055' ± (MSL)</u>	SHEET <u>1</u> OF <u>2</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
								DESCRIPTION/INTERPRETATION	
0							SM	<u>OLDER ALLUVIUM:</u> Brown, dry to damp, medium dense, silty fine to coarse SAND.	
5			21					Dense.	
10			40	6.3	111.3			Medium dense.	
15			18						
20							SC	Brown, damp, dense, silty clayey SAND.	



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-82

DEPTH (feet)	SAMPLES	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED	BORING NO.	
							4/08/09	B-54	
							GROUND ELEVATION	SHEET	OF
							2,055' ± (MSL)	2	2
							METHOD OF DRILLING 8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)		
							DRIVE WEIGHT	DROP	
							140 lbs. (Auto-Trip Hammer)	30"	
							SAMPLED BY	LOGGED BY	REVIEWED BY
							BTM	BTM	JG
DESCRIPTION/INTERPRETATION									
20		47				SC	OLDER ALLUVIUM: (Continued) Brown, damp to moist, dense, silty clayey SAND.		
25		21				CL	Brown, damp, hard, silty sandy CLAY.		
30							Total Depth = 26.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/08/09. Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.		
35									
40									



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-83


DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/08/09</u> BORING NO. <u>B-55</u> GROUND ELEVATION <u>2,055' ± (MSL)</u> SHEET <u>1</u> OF <u>1</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>		
	Bulk	Driven						DESCRIPTION/INTERPRETATION		
0							SM	OLDER ALLUVIUM: Brown, dry to damp, loose to medium dense, silty fine to medium SAND. Medium dense.		
5			18							
							CL	Brown, damp, very stiff, silty CLAY.		
10			35	6.4	108.1		SM	Brown, damp, medium dense, silty fine to coarse SAND.		
								Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/08/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.		
15										
20										

BORING LOG



MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA


PROJECT NO.	DATE	FIGURE
105879004	5/09	A-84

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED	BORING NO.				
	Bulk	Driven						4/06/09	B-56				
								GROUND ELEVATION	2,058' ± (MSL)	SHEET	1	OF	2
								METHOD OF DRILLING 8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)					
								DRIVE WEIGHT	140 lbs. (Auto-Trip Hammer)	DROP	30"		
								SAMPLED BY	MAH	LOGGED BY	MAH	REVIEWED BY	RI
								DESCRIPTION/INTERPRETATION					
0							SM	OLDER ALLUVIUM: Brown, damp, medium dense, silty fine to coarse SAND.					
5			34					Very dense.					
10			32	8.1	108.9			Medium dense.					
15			27					Dense.					
20													




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-85

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/06/09</u> BORING NO. <u>B-56</u> GROUND ELEVATION <u>2,058' ± (MSL)</u> SHEET <u>2</u> OF <u>2</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>MAH</u> LOGGED BY <u>MAH</u> REVIEWED BY <u>RI</u>	
	Bulk	Driven						DESCRIPTION/INTERPRETATION	
20			84				SM	<u>OLDER ALLUVIUM: (Continued)</u> Brown, damp, very dense, silty fine to coarse SAND; scattered fine gravel.	
25			22				CL	Brown, damp, hard, CLAY.	
30								Total Depth = 26.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/06/09. Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
35									
40									



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-86

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/08/09</u> BORING NO. <u>B-57</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,055' ± (MSL)</u> SHEET <u>1</u> OF <u>2</u>	METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u>	DROP <u>30"</u>
								SAMPLED BY <u>BTM</u>	LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>
DESCRIPTION/INTERPRETATION									
0							SM	OLDER ALLUVIUM: Brown, dry to damp, loose to medium dense, silty fine to medium SAND.	
5			16					Medium dense.	
10			37	2.9	110.0				
15			22					Dense; silty fine to medium sand.	
20							CH	Brown, damp, hard, sandy CLAY.	




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-87



DEPTH (feet)	SAMPLES	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/08/09</u> BORING NO. <u>B-57</u>		
							GROUND ELEVATION <u>2,055' ± (MSL)</u> SHEET <u>2</u> OF <u>2</u>		
							METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>		
							DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>		
							SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>		
							DESCRIPTION/INTERPRETATION		
20		42				CH	OLDER ALLUVIUM: (Continued) Brown, damp to moist, hard, sandy CLAY.		
25		25							
30							Total Depth = 26.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/08/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.		
35									
40									


BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-88

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/06/09</u> BORING NO. <u>B-58</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,060' ± (MSL)</u>	SHEET <u>1</u> OF <u>2</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>MAH</u> LOGGED BY <u>MAH</u> REVIEWED BY <u>RI</u>	
								DESCRIPTION/INTERPRETATION	
0							SM	OLDER ALLUVIUM: Brown, dry to damp, loose to medium dense, silty fine to coarse SAND.	
5			45	7.1	116.5			Damp; dense.	
10			13					Medium dense.	
15			26						
20									




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-89

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/06/09</u> BORING NO. <u>B-58</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,060' ± (MSL)</u>	SHEET <u>2</u> OF <u>2</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>MAH</u> LOGGED BY <u>MAH</u> REVIEWED BY <u>RI</u>	
DESCRIPTION/INTERPRETATION									
20			17				SC	<u>OLDER ALLUVIUM: (Continued)</u> Brown, damp, medium dense, clayey SAND.	
25			39				CL	Brown, damp, hard, CLAY.	
30								Total Depth = 26.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/06/09. Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
35									
40									



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-90

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/06/09</u> BORING NO. <u>B-59</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,060' ± (MSL)</u> SHEET <u>1</u> OF <u>2</u>	METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>MAH</u> LOGGED BY <u>MAH</u> REVIEWED BY <u>RI</u>	
									DESCRIPTION/INTERPRETATION
0							SM	OLDER ALLUVIUM: Brown, dry to damp, loose to medium dense, silty fine to coarse SAND.	
5			37					Very dense.	
10			38	12.3	115.1			Medium dense.	
15			17						
20									



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-91


DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/06/09</u> BORING NO. <u>B-59</u> GROUND ELEVATION <u>2,060' ± (MSL)</u> SHEET <u>2</u> OF <u>2</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>MAH</u> LOGGED BY <u>MAH</u> REVIEWED BY <u>RI</u>		
	Bulk	Driven						DESCRIPTION/INTERPRETATION		
20			63				SM	OLDER ALLUVIUM: (Continued) Brown, damp, dense, silty fine to coarse SAND. Brown, damp, hard, sandy CLAY.		
25			22				CL			
30								Total Depth = 26.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/06/09. Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.		
35										
40										

BORING LOG


MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA


PROJECT NO.	DATE	FIGURE
105879004	5/09	A-92

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/06/09</u> BORING NO. <u>B-60</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,060' ± (MSL)</u>	SHEET <u>1</u> OF <u>2</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>MAH</u> LOGGED BY <u>MAH</u> REVIEWED BY <u>RI</u>	
								DESCRIPTION/INTERPRETATION	
0							SM	<u>OLDER ALLUVIUM:</u> Brown, dry to damp, loose to medium dense, fine to coarse SAND.	
5			24	8.1	114.0			Damp; medium dense.	
10			14					Moist.	
15			28						
20									




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-93

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/06/09</u> BORING NO. <u>B-60</u> GROUND ELEVATION <u>2,060' ± (MSL)</u> SHEET <u>2</u> OF <u>2</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>MAH</u> LOGGED BY <u>MAH</u> REVIEWED BY <u>RI</u>		
	Bulk	Driven						DESCRIPTION/INTERPRETATION		
20			38				SM	<u>OLDER ALLUVIUM: (Continued)</u> Brown, damp, very dense, silty fine to coarse SAND.		
25			25					Medium dense.		
30								Total Depth = 26.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/06/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.		
35										
40										




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-94

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/06/09</u> BORING NO. <u>B-61</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,060' ± (MSL)</u>	SHEET <u>1</u> OF <u>2</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>MAH</u> LOGGED BY <u>MAH</u> REVIEWED BY <u>RJ</u>	
								DESCRIPTION/INTERPRETATION	
0							SM	OLDER ALLUVIUM: Brown, dry to damp, medium dense, silty fine to coarse SAND.	
5			46	6.2	115.8			Damp; dense.	
10			23					Trace clay.	
15			40					Medium dense.	
20									




BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-95

DEPTH (feet)	SAMPLES Bulk Driven	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED	BORING NO.
							GROUND ELEVATION	SHEET
							4/06/09	B-61
							2,060' ± (MSL)	2 OF 2
							METHOD OF DRILLING 8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)	
							DRIVE WEIGHT 140 lbs. (Auto-Trip Hammer)	DROP 30"
							SAMPLED BY MAH	LOGGED BY MAH REVIEWED BY RI
							DESCRIPTION/INTERPRETATION	
20		28				SM	OLDER ALLUVIUM: (Continued) Brown, damp to moist, dense, silty fine to coarse SAND.	
						CL	Brown, damp, hard, CLAY.	
25		35					Total Depth = 26.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/06/09.	
							Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
30								
35								
40								



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-96

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/08/09</u> BORING NO. <u>B-62</u> GROUND ELEVATION <u>2,060' ± (MSL)</u> SHEET <u>1</u> OF <u>3</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
	Bulk	Driven						DESCRIPTION/INTERPRETATION	
0							SM	<u>OLDER ALLUVIUM:</u> Brown, dry to damp, medium dense, silty fine to medium SAND.	
5			22					Dense.	
10			32	5.4	113.5			Medium dense.	
15			16					Damp; silty fine sand.	
20									



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-97

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/08/09</u> BORING NO. <u>B-62</u> GROUND ELEVATION <u>2,060' ± (MSL)</u> SHEET <u>2</u> OF <u>3</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>	
	Bulk	Driven						DESCRIPTION/INTERPRETATION	
20			38				SM	OLDER ALLUVIUM: (Continued) Brown, damp, medium dense, silty fine to medium SAND.	
25			18				CL	Brown, damp, very stiff, sandy CLAY.	
30			16				SM	Brown, wet, medium dense, silty fine SAND; micaceous. Saturated.	
35			15					Silty fine to medium sand.	
40							ML	Brown, wet, medium dense, fine sandy SILT.	

BORING LOG

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.	DATE	FIGURE
105879004	5/09	A-98

DEPTH (feet)	SAMPLES	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED	BORING NO.	
							4/08/09	B-62	
							GROUND ELEVATION	SHEET	OF
							2,060' ± (MSL)	3	3
							METHOD OF DRILLING		
							8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)		
							DRIVE WEIGHT	DROP	
							140 lbs. (Auto-Trip Hammer)	30"	
							SAMPLED BY	LOGGED BY	REVIEWED BY
							BTM	BTM	JG
DESCRIPTION/INTERPRETATION									
40		20				ML	OLDER ALLUVIUM: (Continued) Brown, wet, medium dense to dense, fine sandy SILT; micaceous.		
45		19				SM	Brown, wet, medium dense, silty fine SAND; micaceous.		
50		46					Very dense; silty fine to coarse sand.		
55							Total Depth = 51.5 feet. Groundwater encountered at a depth of approximately 31 feet during drilling. Backfilled shortly after drilling on 4/08/09.		
60							Note: Groundwater may rise to a level higher than that measured in borehole due to seasonal variations in precipitation and several other factors as discussed in the report.		

Ninyo & Moore

BORING LOG

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.
105879004

DATE
5/09

FIGURE
A-99

DEPTH (feet)	BULK DRIVEN	SAMPLES	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/06/09</u> BORING NO. <u>B-63</u>	
								GROUND ELEVATION <u>2,060' ± (MSL)</u> SHEET <u>1</u> OF <u>1</u>	
METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
SAMPLED BY <u>MAH</u> LOGGED BY <u>MAH</u> REVIEWED BY <u>RI</u>								DESCRIPTION/INTERPRETATION	
0							SM	<u>OLDER ALLUVIUM:</u> Brown, dry to damp, loose to medium dense, silty fine to coarse SAND.	
5			14					Trace clay.	
10			29	3.4	111.7			Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/06/09.	
15								<u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
20									

Ninyo & Moore

BORING LOG


MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.
105879004



DATE
5/09


FIGURE
A-100

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/06/09</u> BORING NO. <u>B-64</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,060' ± (MSL)</u>	SHEET <u>1</u> OF <u>2</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>MAH</u> LOGGED BY <u>MAH</u> REVIEWED BY <u>RJ</u>	
								DESCRIPTION/INTERPRETATION	
0							SM	<u>OLDER ALLUVIUM:</u> Brown, dry to damp, medium dense, silty fine to coarse SAND.	
5			21					Damp; dense; caliche in shoe.	
10			37	7.6	114.4			Medium dense.	
15			22					Damp to moist; dense.	
20									



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-101

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/06/09</u> BORING NO. <u>B-64</u> GROUND ELEVATION <u>2,060' ± (MSL)</u> SHEET <u>2</u> OF <u>2</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>MAH</u> LOGGED BY <u>MAH</u> REVIEWED BY <u>RI</u>	
	Bulk	Driven						DESCRIPTION/INTERPRETATION	
20			44				SM	<u>OLDER ALLUVIUM: (Continued)</u> Brown, damp to moist, dense, silty fine to coarse SAND.	
25			19				CL	Brown, moist, very stiff, sandy CLAY.	
30								Total Depth = 26.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/06/09. Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
35									
40									



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-102

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/06/09</u> BORING NO. <u>B-65</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,060' ± (MSL)</u>	SHEET <u>1</u> OF <u>1</u>
								METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>	
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>MAH</u> LOGGED BY <u>MAH</u> REVIEWED BY <u>RI</u>	
								DESCRIPTION/INTERPRETATION	
0							SM	OLDER ALLUVIUM: Brown, dry, medium dense, silty fine to coarse SAND.	
5			36	11.1	112.1			Damp to moist.	
10			16					Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/06/09.	
15								<u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.	
20									

Ninyo & Moore

BORING LOG


MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.
105879004

DATE
5/09

FIGURE
A-103

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/08/09</u> BORING NO. <u>B-66</u> GROUND ELEVATION <u>2,055' ± (MSL)</u> SHEET <u>1</u> OF <u>1</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>		
	Bulk	Driven						DESCRIPTION/INTERPRETATION		
0							SM	OLDER ALLUVIUM: Brown, dry to damp, medium dense, silty fine to coarse SAND.		
5			21	3.1	117.6			Medium dense.		
10			27					Dense.		
15								Total Depth = 11.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/08/09. <u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.		
20										



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-104

DEPTH (feet)	SAMPLES	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED	BORING NO.
							GROUND ELEVATION	SHEET
							4/08/09	B-67
							2,060' ± (MSL)	1 OF 2
							METHOD OF DRILLING 8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)	
							140 lbs. (Auto-Trip Hammer)	DROP 30"
							SAMPLED BY BTM	LOGGED BY BTM REVIEWED BY JG
DESCRIPTION/INTERPRETATION								
0						SM	OLDER ALLUVIUM: Brown, dry to damp, medium dense, silty fine to coarse SAND.	
5		25					Dense.	
10		42	4.3	113.7			Damp; medium dense to dense.	
15		23					Dense.	
20								

Ninyo & Moore


BORING LOG


MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.
105879004

DATE
5/09


FIGURE
A-105

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/08/09</u> BORING NO. <u>B-67</u> GROUND ELEVATION <u>2,060' ± (MSL)</u> SHEET <u>2</u> OF <u>2</u> METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u> DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u> SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>JG</u>		
	Bulk	Driven						DESCRIPTION/INTERPRETATION		
20			85				SM	<p><u>OLDER ALLUVIUM: (Continued)</u> Brown, damp, very dense, clayey silty fine to coarse SAND.</p>		
25			34							
30								<p>Total Depth = 26.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/08/09.</p> <p><u>Note:</u> Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.</p>		
35										
40										



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-106

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED <u>4/06/09</u> BORING NO. <u>B-68</u>	
	Bulk	Driven						GROUND ELEVATION <u>2,060' ± (MSL)</u> SHEET <u>1</u> OF <u>2</u>	METHOD OF DRILLING <u>8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)</u>
								DRIVE WEIGHT <u>140 lbs. (Auto-Trip Hammer)</u> DROP <u>30"</u>	
								SAMPLED BY <u>BTM</u> LOGGED BY <u>BTM</u> REVIEWED BY <u>RI</u>	
								DESCRIPTION/INTERPRETATION	
0							SM	OLDER ALLUVIUM: Brown, dry, loose to medium dense, silty, fine to coarse SAND.	
5			7						
10			31	3.1	112.3			Medium dense.	
15			16						
20									



BORING LOG		
MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		
PROJECT NO. 105879004	DATE 5/09	FIGURE A-107

DEPTH (feet)	SAMPLES		BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DATE DRILLED	BORING NO.				
	Bulk	Driven						4/06/09	B-68				
								GROUND ELEVATION	2,060' ± (MSL)	SHEET	2	OF	2
								METHOD OF DRILLING 8" Diameter Hollow-Stem Auger (Mobile B-61) (Cal Pac Drilling)					
								DRIVE WEIGHT	140 lbs. (Auto-Trip Hammer)	DROP	30"		
								SAMPLED BY	BTM	LOGGED BY	BTM	REVIEWED BY	RI
								DESCRIPTION/INTERPRETATION					
20			48				SM	OLDER ALLUVIUM: (Continued) Brown, damp, dense, silty fine to coarse SAND.					
25			19				CL	Brown, damp, very stiff, fine sandy CLAY.					
30								Total Depth = 26.5 feet. Groundwater not encountered during drilling. Backfilled shortly after drilling on 4/06/09. Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.					
35													
40													

BORING LOG

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.
105879004

DATE
5/09

FIGURE
A-108

Explanation of Test Pit, Core, Trench and Hand Auger Log Symbols

PROJECT NO. _____ DATE _____

EXCAVATION LOG EXPLANATION SHEET

DEPTH (FEET)	SAMPLES		MOISTURE (%)	DRY DENSITY (PCF)	CLASSIFICATION U.S.C.S.	FILL: Bulk sample. Dashed line denotes material change. Drive sample. Sand cone performed. Seepage Groundwater encountered during excavation. No recovery with drive sampler. Groundwater encountered after excavation. Sample retained by others. Shelby tube sample. Distance pushed in inches/length of sample recovered in inches No recovery with Shelby tube sampler.
	Bulk	Driven Sand Cone				
0					SM	
1					ML	
2						
3					SM	
4						
5						


SCALE: 1 inch = 1 foot

FIGURE

TEST PIT LOG

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO. 105879004
DATE 5/09



SCALE = 1 in./2.5 ft.


DEPTH (FEET)		SAMPLES	MOISTURE (%)	DRY DENSITY (PCF)	CLASSIFICATION U.S.C.S.	DESCRIPTION
		Bulk				
		Driven				
		Sand Cone				
0					ML	<u>ALLUVIUM:</u> Brown, damp, medium dense, fine to medium sandy SILT; micaceous; scattered roots and root hairs.
2.5					SM	<u>Scattered caliche deposits.</u> Reddish brown, damp to moist, medium dense, silty fine to medium SAND; micaceous.
5						Scattered caliche deposits.
7.5					SC	Grayish brown, damp to moist, medium dense, clayey fine to medium SAND.
10						Scattered caliche deposits, Total Depth = 9 feet. Groundwater not encountered. Backfilled on 08/30/06.
12.5						
15						

DATE EXCAVATED 08/30/06 TEST PIT NO. TP-1
GROUND ELEVATION 2042' ± (MSL) LOGGED BY CAT
METHOD OF EXCAVATION Rubber Tire Backhoe
LOCATION See Geotechnical Map

TEST PIT LOG

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO. 105879004
DATE 5/09



SCALE = 1 in./2.5 ft.

DEPTH (FEET)			MOISTURE (%)	DRY DENSITY (PCF)	CLASSIFICATION U.S.C.S.	DESCRIPTION
Bulk	Driven	Sand Cone				
0					SM	ALLUVIUM: Brown, damp, medium dense, fine to medium silty SAND.
2.5					SC	Reddish brown, damp to moist, medium dense, clayey fine to coarse SAND.
5						
7.5						Moist to wet.
10						Strongly caliche-cemented layer.
12.5						
15						Total Depth = 10.5 feet. Groundwater not encountered. Backfilled on 08/30/06.

DATE EXCAVATED 08/30/06 TEST PIT NO. TP-2
GROUND ELEVATION 2029' ± (MSL) LOGGED BY CAT
METHOD OF EXCAVATION Rubber Tire Backhoe
LOCATION See Geotechnical Map

TEST PIT LOG

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO. 105879004 DATE 5/09


DEPTH (FEET)		SAMPLES			MOISTURE (%)	DRY DENSITY (PCF)	CLASSIFICATION U.S.C.S.	DATE EXCAVATED	TEST PIT NO.	TP-3
		Bulk	Driven	Sand Cone				GROUND ELEVATION	LOGGED BY	CAT
								METHOD OF EXCAVATION		
								LOCATION	See Geotechnical Map	
								DESCRIPTION		
0							ML	LAKE DEPOSITS:		
							CL	Light brown, damp, medium dense SILT.		
								Brown, damp to moist, soft CLAY.		
2.5							SP	Brown, wet, loose, fine to coarse SAND.		
								(Caving in upper 4')		
5							CL+SP	Brown, saturated, soft CLAY, interbedded with brown, loose, fine to coarse SAND.		
7.5										
10										
12.5								Soft to firm CLAY interbedded with medium dense SAND.		
15										
								Total Depth = 13 feet.		
								Groundwater encountered at approximately 4 feet.		
								Backfilled on 08/30/06.		

SCALE = 1 in./2.5 ft.

TEST PIT LOG

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO. 105879004
DATE 5/09




SCALE = 1 in./2.5 ft.

DEPTH (FEET)		SAMPLES		MOISTURE (%)	DRY DENSITY (PCF)	CLASSIFICATION U.S.C.S.	DATE EXCAVATED	TEST PIT NO.	TP-4
		Bulk	Driven	Sand Cone			GROUND ELEVATION	LOGGED BY	CAT
							2062' ± (MSL)		
							METHOD OF EXCAVATION	Rubber Tire Backhoe	
							LOCATION	See Geotechnical Map	
							DESCRIPTION		
							ALLUVIUM: Reddish brown, damp, medium dense, silty fine to coarse SAND; few scattered strongly cemented (concreted) zones.		
							Light grayish brown, medium dense to dense; scattered caliche deposits; scattered strongly concreted zones with some grayish brown clay.		
							Total Depth = 11 feet. Groundwater not encountered. Backfilled on 06/07/06.		

TEST PIT LOG

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO. 105879004
DATE 5/09




DEPTH (FEET)		SAMPLES	MOISTURE (%)		DRY DENSITY (PCF)	CLASSIFICATION U.S.C.S.	DESCRIPTION		
			Bulk	Driven	Sand Cone				
0							ALLUVIUM: Reddish brown, damp, medium dense, silty fine to medium SAND.	DATE EXCAVATED 06/07/06	TEST PIT NO. TP-5
2.5								GROUND ELEVATION 2028' ± (MSL)	LOGGED BY CAT
5							Damp to moist; fine to coarse sand; trace of clay; few strongly cemented (concreted) zones.	METHOD OF EXCAVATION Rubber Tire Backhoe	
7.5							Moist to wet.	LOCATION See Geotechnical Map	
10							Saturated.		
12.5							Total Depth = 10 feet.		
15							Groundwater encountered at approximately 9 feet.		
							Backfilled on 06/07/06.		

TEST PIT LOG

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO. 105879004
DATE 5/09



DEPTH (FEET)	SAMPLES			MOISTURE (%)	DRY DENSITY (PCF)	CLASSIFICATION U.S.C.S.	DESCRIPTION
	Bulk	Driven	Sand Cone				
0						SW-SM	ALLUVIUM: Reddish brown, loose to medium dense, silty, gravelly, well graded SAND; with silt; trace gravel; few strongly cemented (concreted) zones.
2.5							
5							
7.5						SM	Reddish brown, damp, medium dense to dense, silty fine to coarse SAND; abundant strongly concreted zones, very difficult to excavate.
10							
12.5							
15							


Total Depth = 10 feet.
Groundwater not encountered.
Backfilled on 06/07/06.

TEST PIT LOG

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.
105879004

DATE
5/09




DEPTH (FEET)			MOISTURE (%)	DRY DENSITY (PCF)	CLASSIFICATION U.S.C.S.	DATE EXCAVATED 06/07/06 TEST PIT NO. TP-7		
Bulk	Driven	Sand Cone				GROUND ELEVATION 2090' ± (MSL)	LOGGED BY CAT	
						METHOD OF EXCAVATION Rubber Tire Backhoe		
						LOCATION See Geotechnical Map		
						DESCRIPTION		
					SM	ALLUVIUM: Reddish brown, damp, medium dense, silty, gravelly, fine to coarse SAND; few strongly cemented (concreted) zones.		
						Dark brown; trace of clay; scattered caliche deposits; scattered strongly cemented zones.		
						Total Depth = 7 feet. Groundwater not encountered. Backfilled on 06/07/06.		

TEST PIT LOG

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO. 105879004 DATE 5/09



SCALE = 1 in./2.5 ft.


DATE EXCAVATED		06/07/06	TEST PIT NO.		TP-8
GROUND ELEVATION		2100' ± (MSL)	LOGGED BY		CAT
METHOD OF EXCAVATION Rubber Tire Backhoe					
LOCATION See Geotechnical Map					
DESCRIPTION					
ALLUVIUM:		Brown, damp, medium dense, silty fine to coarse SAND.			
		Reddish brown; scattered caliche deposits; scattered strongly cemented zones (from 2' to 4').			
		Damp to moist; cohesionless (caving in).			
		Total Depth = 9 feet, caving at 4 feet. Groundwater not encountered. Backfilled on 06/07/06.			

DEPTH (FEET)	SAMPLING			MOISTURE (%)	DRY DENSITY (PCF)	CLASSIFICATION U.S.C.S.
	Bulk	Driven	Sand Cone			
0						SM
2.5						
5						
7.5						
10						
12.5						
15						

TEST PIT LOG

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.	DATE
105879004	5/09



DEPTH (FEET)			MOISTURE (%)	DRY DENSITY (PCF)	CLASSIFICATION U.S.C.S.	DATE EXCAVATED 06/07/06 TEST PIT NO. TP-9		
Bulk	Driven	Sand Cone				GROUND ELEVATION 2150'± (MSL)	LOGGED BY CAT	
SAMPLES						METHOD OF EXCAVATION Rubber Tire Backhoe		
						LOCATION See Geotechnical Map		
						DESCRIPTION		
					SM	ALLUVIUM: Brown, damp, medium dense to dense, silty fine to coarse SAND; scattered caliche deposits; scattered strongly cemented (concreted) zones.		
					ML	Yellowish brown; some fine gravel. Brown, damp, medium dense to dense, fine to medium sandy SILT; scattered strongly cemented zones.		
					SM	Light grayish brown, damp, medium dense to dense, silty, gravelly, fine to coarse SAND; scattered strongly concreted zones.		
						Total Depth = 11 feet. Groundwater not encountered. Backfilled on 06/07/06.		

TEST PIT LOG

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO. 105879004
DATE 5/09

DEPTH (FEET)		SAMPLES			MOISTURE (%)	DRY DENSITY (PCF)	CLASSIFICATION U.S.C.S.	DATE EXCAVATED	TEST PIT NO.	GROUND ELEVATION	LOGGED BY	METHOD OF EXCAVATION	LOCATION	DESCRIPTION
Bulk	Driven	Sand Cone												
							SM	06/07/06	TP-10	2150' ± (MSL)	CAT	Rubber Tire Backhoe	See Geotechnical Map	<p>ALLUVIUM: Brown, damp, medium dense to dense, silty fine to coarse SAND; scattered caliche deposits; scattered strongly cemented (concreted) zones.</p> <p>Fine sand.</p> <p>Fine to coarse sand.</p> <p>Brown, damp, medium dense to dense, fine sandy SILT; scattered strongly concreted zones.</p> <p>Light grayish brown, damp, medium dense to dense, silty, gravelly fine to coarse SAND; scattered strongly concreted zones.</p> <p>Total Depth = 10 feet. Groundwater not encountered. Backfilled on 06/07/06.</p>

SCALE = 1 in./2.5 ft.

APPENDIX B

LABORATORY TESTING

Classification

Soils were visually and texturally classified in accordance with the Unified Soil Classification System (USCS) in general accordance with ASTM D 2488. Soil classifications are indicated on the logs of the exploratory excavations in Appendix A.

Gradation Analysis

Gradation analysis tests were performed on selected representative soil samples in general accordance with ASTM D 422. The grain-size distribution curves are shown on Figures B-1 through B-19. These test results were utilized in evaluating the soil classifications in accordance with the USCS.

200 Wash

An evaluation of the percentage of particles passing the No. 200 sieve in a selected soil sample was performed in general accordance with ASTM D 1140. The test results are presented on Figure B-20.

Atterberg Limits

A test was performed on a selected representative fine-grained soil sample to evaluate the liquid limit, plastic limit, and plasticity index in general accordance with ASTM D 4318. The test results were utilized to evaluate the soil classification in accordance with the USCS. The test results and classification is shown on Figure B-21.

Consolidation Tests

Consolidation tests were performed on selected relatively undisturbed soil samples in general accordance with ASTM D 2435. The samples were inundated during testing to represent adverse field conditions. The percent of consolidation for each load cycle was recorded as a ratio of the amount of vertical compression to the original height of the sample. The results of the tests are summarized on Figures B-22 through B-24.

Direct Shear Tests

Direct shear tests were performed on relatively undisturbed samples in general accordance with ASTM D 3080 to evaluate the shear strength characteristics of selected materials. The samples were inundated during shearing to represent adverse field conditions. The results are shown on Figures B-25 through B-36.

Proctor Density Tests

The maximum dry density and optimum moisture content of a selected representative soil sample was evaluated using the modified Proctor method in general accordance with ASTM D 1557. The test results are summarized on Figure B-37.


Soil Corrosivity Tests

Soil pH, and resistivity tests were performed on representative samples in general accordance with CT Method 643. The soluble sulfate and chloride content of selected samples were evaluated in general accordance with CT 417 and CT 422, respectively. The test results are presented on Figure B-38.

R-Value

The resistance value, or R-value, for site soils was evaluated in general accordance with CT 301. Samples were prepared and evaluated for exudation pressure and expansion pressure. The equilibrium R-value is reported as the lesser or more conservative of the two calculated results. The test results are shown on Figure B-39.

GRAVEL		SAND			FINES	
Coarse	Fine	Coarse	Medium	Fine	SILT	CLAY




Symbol	Sample Location	Depth (ft)	Liquid Limit	Plastic Limit	Plasticity Index	D ₁₀	D ₃₀	D ₆₀	C _u	C _c	Passing No. 200 (%)	USCS
●	B-8	5.0-6.5	--	--	--	--	--	--	--	--	16	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 422-63 (02)

<i>Ninyo & Moore</i>		GRADATION TEST RESULTS	FIGURE B-1
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	
105879004	5/09		

GRAVEL		SAND			FINES	
Coarse	Fine	Coarse	Medium	Fine	SILT	CLAY




Symbol	Sample Location	Depth (ft)	Liquid Limit	Plastic Limit	Plasticity Index	D ₁₀	D ₃₀	D ₆₀	C _u	C _c	Passing No. 200 (%)	USCS
●	B-8	10.0-11.5	--	--	--	--	--	--	--	--	18	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 422-63 (02)

<i>Ninyo & Moore</i>		GRADATION TEST RESULTS	FIGURE B-2
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	
105879004	5/09		

GRAVEL		SAND			FINES	
Coarse	Fine	Coarse	Medium	Fine	SILT	CLAY




Symbol	Sample Location	Depth (ft)	Liquid Limit	Plastic Limit	Plasticity Index	D ₁₀	D ₃₀	D ₆₀	C _u	C _c	Passing No. 200 (%)	USCS
●	B-19	5.0-6.5	--	--	--	0.06	0.32	0.72	12.0	2.4	11	SW-SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 422-63 (02)

Ninyo & Moore		GRADATION TEST RESULTS	FIGURE B-3
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	
105879004	5/09		

GRAVEL		SAND			FINES	
Coarse	Fine	Coarse	Medium	Fine	SILT	CLAY




Symbol	Sample Location	Depth (ft)	Liquid Limit	Plastic Limit	Plasticity Index	D ₁₀	D ₃₀	D ₆₀	C _u	C _c	Passing No. 200 (%)	USCS
●	B-22	5.0-6.5	--	--	--	--	--	--	--	--	12.4	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 422-63 (02)

<i>Ninyo & Moore</i>		GRADATION TEST RESULTS	FIGURE B-4
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	
105879004	5/09		

GRAVEL		SAND			FINES	
Coarse	Fine	Coarse	Medium	Fine	SILT	CLAY




Symbol	Sample Location	Depth (ft)	Liquid Limit	Plastic Limit	Plasticity Index	D ₁₀	D ₃₀	D ₆₀	C _u	C _c	Passing No. 200 (%)	USCS
●	B-22	10.0-11.5	--	--	--	--	--	--	--	--	12.4	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 422-63 (02)

<i>Ninyo & Moore</i>		GRADATION TEST RESULTS	FIGURE B-5
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	
105879004	5/09		

GRAVEL		SAND			FINES	
Coarse	Fine	Coarse	Medium	Fine	SILT	CLAY




Symbol	Sample Location	Depth (ft)	Liquid Limit	Plastic Limit	Plasticity Index	D ₁₀	D ₃₀	D ₆₀	C _u	C _c	Passing No. 200 (%)	USCS
●	B-33	15.0-16.5	--	--	--	--	--	--	--	--	16	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 422-63 (02)

Ninyo & Moore		GRADATION TEST RESULTS	FIGURE B-6
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	
105879004	5/09		

GRAVEL		SAND			FINES	
Coarse	Fine	Coarse	Medium	Fine	SILT	CLAY




Symbol	Sample Location	Depth (ft)	Liquid Limit	Plastic Limit	Plasticity Index	D ₁₀	D ₃₀	D ₆₀	C _u	C _c	Passing No. 200 (%)	USCS
●	B-36	5.0-6.5	--	--	--	0.07	0.20	0.63	9.0	0.9	11.8	SP-SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 422-63 (02)

Ninyo & Moore		GRADATION TEST RESULTS	FIGURE B-7
PROJECT NO.	DATE		
105879004	5/09		

GRAVEL		SAND			FINES	
Coarse	Fine	Coarse	Medium	Fine	SILT	CLAY




Symbol	Sample Location	Depth (ft)	Liquid Limit	Plastic Limit	Plasticity Index	D ₁₀	D ₃₀	D ₆₀	C _u	C _c	Passing No. 200 (%)	USCS
●	B-40	10.0-11.5	--	--	--	--	--	--	--	--	15	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 422-63 (02)

Ninyo & Moore		GRADATION TEST RESULTS		FIGURE
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		B-8
105879004	5/09			

GRAVEL		SAND			FINES	
Coarse	Fine	Coarse	Medium	Fine	SILT	CLAY




Symbol	Sample Location	Depth (ft)	Liquid Limit	Plastic Limit	Plasticity Index	D ₁₀	D ₃₀	D ₆₀	C _u	C _c	Passing No. 200 (%)	USCS
●	B-41	5.0-6.5	--	--	--	0.07	0.27	0.70	9.5	1.4	10	SW-SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 422-63 (02)

<i>Ninyo & Moore</i>		GRADATION TEST RESULTS	FIGURE B-9
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	
105879004	5/09		

GRAVEL		SAND			FINES	
Coarse	Fine	Coarse	Medium	Fine	SILT	CLAY




Symbol	Sample Location	Depth (ft)	Liquid Limit	Plastic Limit	Plasticity Index	D ₁₀	D ₃₀	D ₆₀	C _u	C _c	Passing No. 200 (%)	USCS
●	B-42	15.0-16.5	--	--	--	0.06	0.28	1.00	18.2	1.4	11.6	SW-SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 422-63 (02)

Ningo & Moore		GRADATION TEST RESULTS		FIGURE
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		B-10
105879004	5/09			

GRAVEL		SAND			FINES	
Coarse	Fine	Coarse	Medium	Fine	SILT	CLAY




Symbol	Sample Location	Depth (ft)	Liquid Limit	Plastic Limit	Plasticity Index	D ₁₀	D ₃₀	D ₆₀	C _u	C _c	Passing No. 200 (%)	USCS
●	B-44	15.0-16.5	--	--	--	--	--	--	--	--	17	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 422-63 (02)

Ninyo & Moore		GRADATION TEST RESULTS		FIGURE
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		B-11
105879004	5/09			

GRAVEL		SAND			FINES	
Coarse	Fine	Coarse	Medium	Fine	SILT	CLAY




Symbol	Sample Location	Depth (ft)	Liquid Limit	Plastic Limit	Plasticity Index	D ₁₀	D ₃₀	D ₆₀	C _u	C _c	Passing No. 200 (%)	USCS
●	B-46	10.0-11.5	--	--	--	--	--	--	--	--	24	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 422-63 (02)

<i>Ninyo & Moore</i>		GRADATION TEST RESULTS	FIGURE B-12
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	
105879004	5/09		

GRAVEL		SAND			FINES	
Coarse	Fine	Coarse	Medium	Fine	SILT	CLAY




Symbol	Sample Location	Depth (ft)	Liquid Limit	Plastic Limit	Plasticity Index	D ₁₀	D ₃₀	D ₈₀	C _u	C _c	Passing No. 200 (%)	USCS
●	B-49	15.0-16.5	--	--	--	--	--	--	--	--	22	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 422-63 (02)

Ningo & Moore		GRADATION TEST RESULTS		FIGURE
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		B-13
105879004	5/09			

GRAVEL		SAND			FINES	
Coarse	Fine	Coarse	Medium	Fine	SILT	CLAY




Symbol	Sample Location	Depth (ft)	Liquid Limit	Plastic Limit	Plasticity Index	D ₁₀	D ₃₀	D ₆₀	C _u	C _c	Passing No. 200 (%)	USCS
●	B-62	15.0-16.5	--	--	--	--	--	--	--	--	42	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 422-63 (02)

<i>Ninyo & Moore</i>		GRADATION TEST RESULTS	FIGURE B-14
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	
105879004	5/09		

GRAVEL		SAND			FINES	
Coarse	Fine	Coarse	Medium	Fine	SILT	CLAY




Symbol	Sample Location	Depth (ft)	Liquid Limit	Plastic Limit	Plasticity Index	D ₁₀	D ₃₀	D ₆₀	C _u	C _c	Passing No. 200 (%)	USCS
●	B-62	30.0-31.5	--	--	--	--	--	--	--	--	33	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 422-63 (02)

Ninyo & Moore		GRADATION TEST RESULTS		FIGURE
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		B-15
105879004	5/09			

GRAVEL		SAND			FINES	
Coarse	Fine	Coarse	Medium	Fine	SILT	CLAY




Symbol	Sample Location	Depth (ft)	Liquid Limit	Plastic Limit	Plasticity Index	D ₁₀	D ₃₀	D ₆₀	C _u	C _c	Passing No. 200 (%)	USCS
●	B-62	35.0-36.5	--	--	--	--	--	--	--	--	17	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 422-63 (02)

Ninyo & Moore		GRADATION TEST RESULTS			FIGURE
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA			B-16
105879004	5/09				

GRAVEL		SAND			FINES	
Coarse	Fine	Coarse	Medium	Fine	SILT	CLAY




Symbol	Sample Location	Depth (ft)	Liquid Limit	Plastic Limit	Plasticity Index	D ₁₀	D ₃₀	D ₆₀	C _u	C _c	Passing No. 200 (%)	USCS
●	B-62	45.0-46.5	--	--	--	--	--	--	--	--	23	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 422-63 (02)

Ninyo & Moore		GRADATION TEST RESULTS		FIGURE
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		B-17
105879004	5/09			

GRAVEL		SAND			FINES	
Coarse	Fine	Coarse	Medium	Fine	SILT	CLAY




Symbol	Sample Location	Depth (ft)	Liquid Limit	Plastic Limit	Plasticity Index	D ₁₀	D ₃₀	D ₆₀	C _u	C _c	Passing No. 200 (%)	U.S.C.S
●	TP-4	8.0-10.0	--	--	--	--	--	--	--	--	15	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 422-63 (02)

Ninyo & Moore		GRADATION TEST RESULTS		FIGURE
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		B-18
105879004	5/09			

GRAVEL		SAND			FINES	
Coarse	Fine	Coarse	Medium	Fine	SILT	CLAY



Symbol	Sample Location	Depth (ft)	Liquid Limit	Plastic Limit	Plasticity Index	D ₁₀	D ₃₀	D ₆₀	C _u	C _c	Passing No. 200 (%)	U.S.C.S
●	TP-6	1.0-3.0	--	--	--	0.09	0.34	0.88	10.4	1.5	9	SW-SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 422-63 (02)

Ninyo & Moore		GRADATION TEST RESULTS		FIGURE
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		B-19
105879004	5/09			


SAMPLE LOCATION	SAMPLE DEPTH (FT)	DESCRIPTION	PERCENT PASSING NO. 4	PERCENT PASSING NO. 200	USCS (TOTAL SAMPLE)
B-44	25-26.5	Silty SAND	94	23	SM
B-44	35-36.5	Clayey SAND	100	46	SC
B-44	45-46.5	Sandy CLAY	100	55	CL
TP-2	0.0-2.0	Silty SAND	100	22	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 1140-00

<i>Ninyo & Moore</i>		NO. 200 SIEVE ANALYSIS	FIGURE B-20
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	
105879004	5/09		

SYMBOL	LOCATION	DEPTH (FT)	LIQUID LIMIT, LL	PLASTIC LIMIT, PL	PLASTICITY INDEX, PI	USCS CLASSIFICATION (Fraction Finer Than No. 40 Sieve)	USCS (Entire Sample)
●	B-18	20.0-21.5	55	23	32	CH	CH
■	B-35	45.0-46.5	66	31	35	CH	CH
◆	B-41	25.0-26.5	25	18	7	CL	CL
○	B-44	35.0-36.5	32	21	11	CL	SC
□	TP-3	1.0-2.0	44	25	19	CL	CL


NP - INDICATES NON-PLASTIC



PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 4318-05


Ninyo & Moore		ATTERBERG LIMITS TEST RESULTS	FIGURE B-21
PROJECT NO. 105879004	DATE 5/09		

MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA




PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 2435-04

Ninyo & Moore		CONSOLIDATION TEST RESULTS	FIGURE B-22
PROJECT NO.	DATE		
105879004	5/09	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	





PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 2435-04

Ningo & Moore		CONSOLIDATION TEST RESULTS	FIGURE B-23
PROJECT NO.	DATE		
105879004	5/09	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	



PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 2435-04


		CONSOLIDATION TEST RESULTS	FIGURE B-24
PROJECT NO.	DATE		
105879004	5/09	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	



Description	Symbol	Sample Location	Depth (ft)	Shear Strength	Cohesion, c (psf)	Friction Angle, ϕ (degrees)	Soil Type
Silty SAND	—●—	B-5	5.0-6.5	Peak	110	35	SM
Silty SAND	- - X - -	B-5	5.0-6.5	Ultimate	10	34	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 3080-04


Ninyo & Moore		DIRECT SHEAR TEST RESULTS	FIGURE
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	B-25
105879004	5/09		



Description	Symbol	Sample Location	Depth (ft)	Shear Strength	Cohesion, c (psf)	Friction Angle, ϕ (degrees)	Soil Type
Silty SAND	—●—	B-21	5.0-6.5	Peak	460	36	SM
Silty SAND	- - X - -	B-21	5.0-6.5	Ultimate	100	32	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 3080-04


Ninyo & Moore		DIRECT SHEAR TEST RESULTS	FIGURE B-26
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	
105879004	5/09		



Description	Symbol	Sample Location	Depth (ft)	Shear Strength	Cohesion, c (psf)	Friction Angle, ϕ (degrees)	Soil Type
Silty SAND	—●—	B-23	5.0-6.5	Peak	30	41	SM
Silty SAND	- - X - -	B-23	5.0-6.5	Ultimate	20	33	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 3080-04


Ninyo & Moore		DIRECT SHEAR TEST RESULTS		FIGURE
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		B-27
105879004	5/09			



Description	Symbol	Sample Location	Depth (ft)	Shear Strength	Cohesion, c (psf)	Friction Angle, ϕ (degrees)	Soil Type
Silty SAND	—●—	B-28	5.0-6.5	Peak	260	33	SM
Silty SAND	- - X - -	B-28	5.0-6.5	Ultimate	80	31	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 3080-04


Ninyo & Moore		DIRECT SHEAR TEST RESULTS		FIGURE
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		B-28
105879004	5/09			



Description	Symbol	Sample Location	Depth (ft)	Shear Strength	Cohesion, c (psf)	Friction Angle, ϕ (degrees)	Soil Type
Silty SAND	—●—	B-34	5.0-6.5	Peak	330	37	SM
Silty SAND	- - X - -	B-34	5.0-6.5	Ultimate	20	34	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 3080-04


Ninyo & Moore		DIRECT SHEAR TEST RESULTS	FIGURE
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	B-29
105879004	5/09		



Description	Symbol	Sample Location	Depth (ft)	Shear Strength	Cohesion, c (psf)	Friction Angle, ϕ (degrees)	Soil Type
Silty SAND	—●—	B-38	5.0-6.5	Peak	170	37	SM
Silty SAND	- - X - -	B-38	5.0-6.5	Ultimate	0	33	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 3080-04


Ninyo & Moore		DIRECT SHEAR TEST RESULTS	FIGURE B-30
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	
105879004	5/09		



Description	Symbol	Sample Location	Depth (ft)	Shear Strength	Cohesion, c (psf)	Friction Angle, ϕ (degrees)	Soil Type
Silty SAND	—●—	B-45	5.0-6.5	Peak	520	34	SM
Silty SAND	- - X - -	B-45	5.0-6.5	Ultimate	110	34	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 3080-04


Ninyo & Moore		DIRECT SHEAR TEST RESULTS		FIGURE
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		B-31
105879004	5/09			



Description	Symbol	Sample Location	Depth (ft)	Shear Strength	Cohesion, c (psf)	Friction Angle, ϕ (degrees)	Soil Type
Silty SAND	—●—	B-50	10.0-11.5	Peak	260	32	SM
Silty SAND	- - X - -	B-50	10.0-11.5	Ultimate	100	31	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 3080-04


Ninyo & Moore		DIRECT SHEAR TEST RESULTS		FIGURE
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		B-32
105879004	5/09			



Description	Symbol	Sample Location	Depth (ft)	Shear Strength	Cohesion, c (psf)	Friction Angle, ϕ (degrees)	Soil Type
Silty SAND	—●—	B-51	5.0-6.5	Peak	560	35	SM
Silty SAND	- - X - -	B-51	5.0-6.5	Ultimate	140	31	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 3080-04


Ninyo & Moore		DIRECT SHEAR TEST RESULTS		FIGURE
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		B-33
105879004	5/09			



Description	Symbol	Sample Location	Depth (ft)	Shear Strength	Cohesion, c (psf)	Friction Angle, ϕ (degrees)	Soil Type
Silty SAND	—●—	B-61	5.0-6.5	Peak	480	34	SM
Silty SAND	- - X - -	B-61	5.0-6.5	Ultimate	10	32	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 3080-04


Ninyo & Moore		DIRECT SHEAR TEST RESULTS	FIGURE
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	B-34
105879004	5/09		



Description	Symbol	Sample Location	Depth (ft)	Shear Strength	Cohesion, c (psf)	Friction Angle, ϕ (degrees)	Soil Type
Silty SAND	—●—	B-66	5.0-6.5	Peak	210	36	SM
Silty SAND	- - X - -	B-66	5.0-6.5	Ultimate	0	34	SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 3080-04


Ninyo & Moore		DIRECT SHEAR TEST RESULTS		FIGURE
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		B-35
105879004	5/09			



Description	Symbol	Sample Location	Depth (ft)	Shear Strength	Cohesion, c (psf)	Friction Angle, ϕ (degrees)	Soil Type
Well Graded SAND with Silt	—●—	TP-6	1.0-3.0	Peak	190	40	SW-SM
Well Graded SAND with Silt	- - X - -	TP-6	1.0-3.0	Ultimate	70	32	SW-SM

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 3080-04 ON A SAMPLE REMOLDED TO 90% RELATIVE COMPACTION

Ningo & Moore		DIRECT SHEAR TEST RESULTS		FIGURE
PROJECT	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		B-36
105879004	5/09			



Sample Location	Depth (ft)	Soil Description	Maximum Dry Density (pcf)	Optimum Moisture Content (%)
TP-6	1.0-3.0	Reddish Brown Well Graded SAND with Silt	130.0	7.0
Dry Density and Moisture Content Values Corrected for Oversize (ASTM D 4718-87)			N/A	N/A

PERFORMED IN GENERAL ACCORDANCE WITH ☒ ASTM D 1557-02 ☐ ASTM D 698-00a METHOD ☒ A ☐ B ☐ C

<i>Ninyo & Moore</i>		PROCTOR DENSITY TEST RESULTS	FIGURE
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	B-37
105879004	5/09		

SAMPLE LOCATION	SAMPLE DEPTH (FT)	pH ¹	RESISTIVITY ¹ (Ohm-cm)	SULFATE CONTENT ²		CHLORIDE CONTENT ³ (ppm)
				(ppm)	(%)	
B-3	0-5.0	7.1	6,298	20	0.002	295
B-8	0-5.0	7.7	10,050	30	0.003	90
B-31	0-5.0	7.0	10,720	30	0.003	145
B-47	0-5.0	7.1	10,050	30	0.003	150
B-62	10.0-11.5	6.4	10,050	110	0.011	380
TP-3	1.0-2.0	7.7	154	9900	0.990	11200
TP-4	2.0-4.0	7.1	3,015	100	0.010	25

¹ PERFORMED IN GENERAL ACCORDANCE WITH CALIFORNIA TEST METHOD 643

² PERFORMED IN GENERAL ACCORDANCE WITH CALIFORNIA TEST METHOD 417

³ PERFORMED IN GENERAL ACCORDANCE WITH CALIFORNIA TEST METHOD 422

<i>Ninyo & Moore</i>		CORROSIVITY TEST RESULTS	FIGURE B-38
PROJECT NO.	DATE		
105879004	5/09	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	


SAMPLE LOCATION	SAMPLE DEPTH (FT)	SOIL TYPE	R-VALUE
B-38	0.0-5.0	SM	61

PERFORMED IN GENERAL ACCORDANCE WITH ASTM D 2844-01/CT 301


<i>Ninyo & Moore</i>		R-VALUE TEST RESULTS	FIGURE
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	B-39
105879004	5/09		

APPENDIX C
FAULT TRENCH LOG

MATCHLINE, SEE BELOW



MATCHLINE, SEE FIGURE B-2




MATCHLINE, SEE ABOVE

LEGEND

- (A) OLDER ALLUVIUM:
BROWN, DAMP, MEDIUM DENSE TO DENSE, SILTY FINE TO MEDIUM SAND, SOME COARSE SAND, SOME FAINT CROSS BEDDING; GENERALLY MASSIVE; SCATTERED ROOTS.
- (B) BROWN, DAMP, MEDIUM DENSE SILTY FINE TO MEDIUM SAND; CALICHE CONCENTRATION.
- (C) GRADED BED SEQUENCE:
BROWN, DAMP, DENSE, CLAYEY, FINE SANDY SILT GRADING DOWN TO FINE TO MEDIUM SANDY SILT; MICACEOUS; SCATTERED PINHOLE VOIDS.
- (D) BROWN, DAMP, DENSE, CLAYEY FINE, SANDY SILT GRADING DOWN TO FINE TO MEDIUM SANDY SILT; MICACEOUS; SCATTERED PINHOLE VOIDS.
- (E) BROWN, DAMP TO MOIST, MEDIUM DENSE TO DENSE, FINE SANDY SILT GRADING UP TO SILTY FINE TO MEDIUM SAND; MICACEOUS; SCATTERED PINHOLE VOIDS.
- (F) BROWN, DAMP TO MOIST, MEDIUM DENSE TO DENSE, SILTY FINE TO COARSE SANDY SILT GRADING UP TO FINE TO MEDIUM SANDY SILT; MICACEOUS.
- (G) BROWN, DAMP, MEDIUM DENSE TO DENSE, FINE SANDY SILT GRADING DOWN TO FINE TO COARSE SANDY SILT; MICACEOUS.
- (H) BROWN, DAMP, MEDIUM DENSE TO DENSE, FINE SANDY SILT GRADING DOWN TO FINE TO COARSE SANDY SILT; MICACEOUS.
- (I) BROWN, DAMP, MEDIUM DENSE TO DENSE, FINE SANDY SILT GRADING DOWN TO FINE TO COARSE SANDY SILT; MICACEOUS.
- (J) LIGHT GRAYISH BROWN, DAMP, MEDIUM DENSE, FINE TO COARSE SANDY SILT; MICACEOUS.
- (K) BROWN, DAMP, MEDIUM DENSE TO DENSE, FINE SANDY SILT GRADING DOWN TO FINE TO COARSE SANDY SILT; MICACEOUS.
- (L) BROWN, DAMP, MEDIUM DENSE TO DENSE, FINE SANDY SILT GRADING DOWN TO FINE TO COARSE SANDY SILT; MICACEOUS.
- (M) YELLOWISH BROWN, DAMP TO MOIST, DENSE, FINE SANDY SILT; MICACEOUS.
- (N) YELLOWISH BROWN, DAMP TO MOIST, MEDIUM DENSE TO DENSE, SILTY FINE TO COARSE SAND; MICACEOUS.
- (O) GRAYISH BROWN, DAMP TO MOIST, DENSE TO MEDIUM DENSE, SILTY FINE TO COARSE SAND; MICACEOUS.
- (P) GRAYISH BROWN, DAMP, MEDIUM DENSE, SILTY FINE TO COARSE SAND; SOME FINE GRAVEL.
- (Q) YELLOWISH BROWN, DAMP, DENSE, FINE SANDY SILT GRADING DOWN TO SILTY FINE TO MEDIUM SAND; MICACEOUS.
- (R) BROWN, DAMP, MEDIUM DENSE TO DENSE, FINE SANDY SILT GRADING DOWN TO FINE TO COARSE SANDY SILT; MICACEOUS; TRACE CLAY IN UPPER PORTION.
- (S) GRAY, DAMP, DENSE, FINE TO COARSE SANDY SILT; MICACEOUS (IN SOME AREAS TO GRAVELLY FINE TO COARSE SAND).
- (T) BROWN, DAMP, DENSE, FINE SANDY SILT GRADING DOWN TO SILTY FINE TO MEDIUM SAND, MICACEOUS.
- (U) GRAYISH BROWN, DAMP, DENSE, SILTY FINE TO COARSE SAND; MICACEOUS.
- (V) REDDISH BROWN, DAMP, MODERATELY CEMENTED SILTY FINE GRAINED SANDSTONE, MICACEOUS.
- (W) BROWN, DAMP, DENSE, FINE SANDY SILT GRADING DOWN TO SILTY FINE TO COARSE SAND; MICACEOUS.
- (X) BROWN, DAMP, DENSE, FINE SANDY SILT GRADING DOWN TO SILTY FINE TO COARSE SAND; MICACEOUS.
- (Y) GRAYISH BROWN, DAMP, DENSE, SILTY FINE GRAVELLY, FINE TO COARSE SAND; MICACEOUS.
- (Z) GRAYISH TO REDDISH BROWN, DAMP, DENSE, FINE SANDY SILT, TRACE CLAY; MICACEOUS.

- (AA) REDDISH BROWN, DAMP TO MOIST, DENSE, SILTY FINE TO MEDIUM SAND; MICACEOUS; TRACE COARSE SAND.
- (A) GRADES TO BROWN, DAMP, MEDIUM DENSE TO DENSE, SILTY, FINE, GRAVELLY FINE TO COARSE SAND; MASSIVE MICACEOUS (CHANNEL DEPOSITS).
- (B) GRADES TO LIGHT GRAY, DAMP, DENSE, SANDY SILT.

APPROXIMATE SCALE



NOTE: ALL DIMENSIONS, DIRECTIONS AND LOCATIONS ARE APPROXIMATE

Ninyo & Moore


TRENCH LOG

PROJECT NO.	DATE
105879004	5/09


FIGURE

C-1


MOJAVE SOLAR PROJECT
LOCKHART, CALIFORNIA




FOR LEGEND, SEE FIGURE B-1




<i>Ninyo & Moore</i>		TRENCH LOG	FIGURE
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	C-2
105879004	5/09		




FOR LEGEND, SEE FIGURE B-1




Ninyo & Moore		TRENCH LOG	FIGURE
PROJECT NO.	DATE		
105879004	5/09	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	C-3







FOR LEGEND, SEE FIGURE B-1



<i>Ninyo & Moore</i>		TRENCH LOG	FIGURE
PROJECT NO.	DATE		
105879004	5/09	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA	C-5



FOR LEGEND, SEE FIGURE B-1



Ninyo & Moore		TRENCH LOG		FIGURE
PROJECT NO.	DATE	MOJAVE SOLAR PROJECT LOCKHART, CALIFORNIA		C-6
105879004	5/09			

APPROXIMATE SCALE



NOTE: ALL DIMENSIONS, DIRECTIONS AND LOCATIONS ARE APPROXIMATE

FOR LEGEND, SEE FIGURE B-1

Ningo & Moore

FIGURE




TRENCH LOG

C-7

MOLAVE SOLAR PROJECT
LOCKHART, CALIFORNIA

PROJECT NO.
105879004

DATE
5/09



APPENDIX D

PERCOLATION TESTING RESULTS

Ninyo & Moore performed six percolation tests within the proposed evaporation pond and land farm areas at the subject site. The percolation tests are numbered PT-1 through PT-6 and their locations are shown on Figure 2. The percolation test borings were advanced on April 3, 2009 with a truck mounted, 8-inch diameter, continuous flight auger drill. The materials encountered in the borings consisted of old alluvium. As encountered, the alluvial materials generally consisted of light brown to brown, dry to damp, loose to medium dense, silty fine to coarse sand. The depth to the regional groundwater table at the site is anticipated to be on the order of 150 feet. Perched groundwater, however, was encountered in several of our borings at a depth of approximately 28 to 32 feet. Groundwater levels at the site may fluctuate due to seasonal variations, groundwater withdrawal or injection, or other factors.

Percolation testing was performed on April 6 and 9, 2009 at the approximate locations shown on Figure 2. The percolation tests were performed in general accordance with County of San Bernardino Department of Public Health guidelines presented in On-Site Waste Water Disposal System (OWWDS, 1992). Test holes were drilled approximately 3 feet deep and 6 inches in diameter. Approximately 2 inches of gravel was placed on the bottom of the hole. Varying lengths of 2-inch, perforated pipe were installed in an upright position on top of the gravel layer and then backfilled with approximately 1/2 cubic foot of gravel.

Each test hole was presoaked for 4 hours. To begin the percolation testing procedure, the test holes were filled with 12 inches of water. The test holes were given 30 minutes to percolate more than 5 inches of water. If 5 inches of water or more percolate within 30 minutes, then the fast test can be performed. Five of our tests were eligible for the fast test which consists of taking readings every ten minutes for the next hour. Test holes were refilled after each reading. Percolation test PT-6 did not percolate 5 inches of water in 30 minutes. The standard percolation test was performed consisting of taking readings every 30 minutes for the next four hours, refilling the test hole after each reading. The percolation rate was so slow in PT-6 that the test was terminated after one hour. Percolation test results were adjusted in accordance with the San Bernardino County Department of Public Health correction calculation for gravel-packed test holes. Adjusted percolation test results were 7, 9, 7, 4, 3, and more than 535 minutes per inch for tests PT-1 through PT-6, respectively. The percolation test borings were backfilled on April 6 and 9, 2009 at the conclusion of testing. Percolation test results are presented on the following tables.

Test Date - 4/06/09						PT - 1	
Approximate Test Hole Diameter - 6.0 in				Approximate Test Hole Depth - 3.0 ft.			
Test performed and recorded by: BTM							
t ₁	d ₁	t ₂	d ₂	Δt	Δd	Rate	Adjusted Rate
						(R, mpi)	(R, mpi)
0	2.50	10	2.77	10	0.27	3.1	6.8
11	2.50	21	2.76	10	0.26	3.2	7.0
21	2.50	31	2.75	10	0.25	3.3	7.3
32	2.50	42	2.75	10	0.25	3.3	7.3
44	2.50	54	2.75	10	0.25	3.3	7.3
55	2.50	65	2.75	10	0.25	3.3	7.3

Test Date - 4/06/09						PT - 2	
Approximate Test Hole Diameter - 6.0 in				Approximate Test Hole Depth - 3.3 ft.			
Test performed and recorded by: BTM							
t ₁	d ₁	t ₂	d ₂	Δt	Δd	Rate (R, mpi)	Adjusted Rate (R, mpi)
0	2.80	10	3.02	10	0.22	3.8	8.3
11	2.80	21	3.01	10	0.21	4.0	8.7
21	2.80	31	3.00	10	0.20	4.2	9.2
32	2.80	42	3.01	10	0.21	4.0	8.7
44	2.80	54	3.01	10	0.21	4.0	8.7
55	2.80	65	3.01	10	0.21	4.0	8.7

Notes:

t_1 = initial time when filling or refilling is completed in minutes

d_1 = initial depth to water in hole at t_1 in feet

t_2 = final time when incremental water level reading is taken in minutes

d_2 = final depth to water in hole at t_2 in feet

Δt = change in time between initial and final water level readings in minutes ($t_2 - t_1$)

Δd = change in depth to water in feet ($d_2 - d_1$)

MPI = minutes per inch

Test Date - 4/06/09						PT - 3	
Approximate Test Hole Diameter - 6.0 in				Approximate Test Hole Depth - 2.7 ft.			
Test performed and recorded by: BTM							
t ₁	d ₁	t ₂	d ₂	Δt	Δd	Rate (R, mpi)	Adjusted Rate (R, mpi)
0	2.20	10	2.49	10	0.29	2.9	6.3
12	2.20	22	2.47	10	0.27	3.1	6.8
23	2.20	33	2.48	10	0.28	3.0	6.5
33	2.20	43	2.47	10	0.27	3.1	6.8
44	2.20	54	2.47	10	0.27	3.1	6.8
55	2.20	65	2.47	10	0.27	3.1	6.8

Test Date - 4/06/09					PT - 4		
Approximate Test Hole Diameter - 6.0 in					Approximate Test Hole Depth - 3.3 ft.		
Test performed and recorded by: BTM							
t ₁	d ₁	t ₂	d ₂	Δt	Δd	Rate (R, mpi)	Adjusted Rate (R, mpi)
0	2.80	9	3.30	9	0.50	1.5	3.3
11	2.80	20	3.30	9	0.50	1.5	3.3

Notes:

t_1 = initial time when filling or refilling is completed in minutes

d_1 = initial depth to water in hole at t_1 in feet

t_2 = final time when incremental water level reading is taken in minutes

d_2 = final depth to water in hole at t_2 in feet

Δt = change in time between initial and final water level readings in minutes ($t_2 - t_1$)

Δd = change in depth to water in feet ($d_2 - d_1$)

MPI = minutes per inch

Test Date - 4/06/09						PT - 5	
Approximate Test Hole Diameter - 6.0 in				Approximate Test Hole Depth - 2.8 ft.			
Test performed and recorded by: BTM							
t ₁	d ₁	t ₂	d ₂	Δt	Δd	Rate (R, mpi)	Adjusted Rate (R, mpi)
0	2.25	8	2.75	8	0.50	1.3	2.9
10	2.25	18	2.75	8	0.50	1.3	2.9

Test Date - 4/09/09						PT - 6	
Approximate Test Hole Diameter - 6.0 in				Approximate Test Hole Depth - 3.3 ft.			
Test performed and recorded by: BTM							
t ₁	d ₁	t ₂	d ₂	Δt	Δd	Rate (R, mpi)	Adjusted Rate (R, mpi)
0.0	2.72	30.0	2.72	30	0.00	NA	NA
30.0	2.72	60.0	2.73	30	0.01	250.0	549.6
60.0	2.73	90.0	2.73	30	0.00	NA	NA
90.0	2.73	120.0	2.74	30	0.01	250.0	549.6
120.0	2.74	150.0	2.74	30	0.00	NA	NA
150.0	2.74	180.0	2.75	30	0.01	250.0	549.6

Notes:

t_1 = initial time when filling or refilling is completed in minutes

d_1 = initial depth to water in hole at t_1 in feet

t_2 = final time when incremental water level reading is taken in minutes

d_2 = final depth to water in hole at t_2 in feet

Δt = change in time between initial and final water level readings in minutes ($t_2 - t_1$)

Δd = change in depth to water in feet ($d_2 - d_1$)

MPI = minutes per inch

NA = did not percolate

APPENDIX E
RESISTIVITY SURVEY

April 27, 2009
Project No. 109087

Mr. Frank Moreland
Ninyo & Moore
5710 Ruffin Road
San Diego, California 92123

Subject: Geophysical Evaluation
 Harper Lake Power Facility
 San Bernardino County, California

Dear Mr. Moreland:

In accordance with your authorization, we have performed geophysical survey services for the proposed Harper Lake Power Facility to be located in the Lockhart area of San Bernardino County, California (Figure 1). The purpose of our services was to collect in-situ electrical resistivity measurements for use in the design and construction of the subject project. Our services were conducted on April 10, 2009. This report presents the survey methodology, equipment used, analysis, and results.

Our scope of services for the project included collection of electrical resistivity data at five locations on the property, compilation of the data collected, and preparation of this data report. Specifically we conducted two orthogonal resistivity soundings in north-south and east-west directions. The soundings are labeled “a” and “b” for the north-south and east-west directions, respectively. Figures 2a and 2b illustrate the approximate location of the lines, and Figures 3a through 3c depict the general site conditions in the area of the lines. The data were collected in general accordance with ASTM G 57 using an Advanced Geosciences, Inc. (AGI) SuperSting R8 earth resistivity meter and four stainless steel electrodes in a Wenner configuration. The SuperSting can generate up to 800 volts and 2 amps and allows for the direct measurement of resistance.

Soil resistance measurements were collected at electrode spacings of approximately 2, 5, 10, 15, 20, 30, 40, 60, and 80 feet, except for R-1 which had a maximum spacing of 60 feet. The general

locations of the soundings were pre-selected by a representative of your office. The electrode locations were cleared of vegetation, and the soil around the electrode was moistened with salt water prior to conducting the measurements. Special care was exercised to ensure firm contact with the soil.

The results of the electrical resistivity surveys are presented in Figures 4a and 4b. In general, the measurements collected along orthogonal soundings are fairly consistent, indicating subsurface homogeneous conditions at the test locations. In addition, the standard deviation between multiple readings was generally less than 0.3 percent.


The field services and geophysical analyses presented in this report have been conducted in general accordance with current practice and the standard of care exercised by consultants performing similar tasks in the project area. No warranty, expressed or implied, is made regarding the conclusions presented in this report. Please also note that our evaluation was limited to measuring in-situ apparent soil resistivity at locations generally selected by your office. Southwest Geophysics, Inc. should be contacted if the reader has questions regarding the content, interpretations presented, or completeness of this document. This report is intended exclusively for use by the client. Any use or reuse of this report by parties other than the client is undertaken at said parties' sole risk.

We appreciate the opportunity to be of service on this project. Should you have any questions related to this report, please contact the undersigned at your convenience.

Sincerely,
SOUTHWEST GEOPHYSICS, INC.



Patrick Lehrmann, P.G., R.Gp.
Principal Geologist/Geophysicist



Hans van de Vrugt, C.E.G., R.Gp.
Principal Geologist/Geophysicist

HV/PFL/hv

Attachments: Figure 1 – Site Location Map
Figures 2a and 2b – Resistivity Sounding Location Maps
Figures 3a and 3b – Site Photographs
Figures 4a and 4b – Electrical Resistivity Results



Distribution: Addressee (electronic)



SITE LOCATION MAP



Harper Lake Power Facility
San Bernardino County, California

Project No.: 109087

Date: 04/09



Figure 1




Figure 2a

Harper Lake Power Facility
San Bernardino County, California

Project No.: 109087



Date: 04/09



RESISTIVITY SOUNDING LOCATION MAP



RESISTIVITY SOUNDING LOCATION MAP		Harper Lake Power Facility San Bernardino County, California Project No.: 109087	Figure 2b	approximate scale in feet
--	--	--	-----------	---------------------------



SITE PHOTOGRAPHS




Harper Lake Power Facility
San Bernardino County, California

Project No.: 109087

Date: 04/09



Figure 3a



SITE PHOTOGRAPHS



Harper Lake Power Facility
San Bernardino County, California

Project No.: 109087

Date: 04/09



Figure 3b



SITE PHOTOGRAPHS

Harper Lake Power Facility
San Bernardino County, California

Project No.: 109087

Date: 04/09



Figure 3c

Line No. (Orientation)	Spacing (ft)	Current (mA)	Resistance (Ohms)	Error (%)	Apparent Resistivity	
					(ohm-cm)	(ohm-ft)
R-1a	2	2.379	40.030	0.1	15332.40	503.03
(N-S)	5	2.914	10.160	0.1	9728.78	319.19
	10	3.346	2.530	0.1	4845.24	158.96
	15	2.478	1.284	0.0	3688.51	121.01
	20	4.469	0.835	0.2	3197.09	104.89
	30	6.615	0.443	0.0	2544.61	83.48
	40	3.18	0.507	1.2	3886.15	127.50
	60	7.238	0.487	0.0	5600.56	183.75
R-1b	2	4.296	39.740	0.0	15221.32	499.39
(E-W)	5	6.485	10.100	0.1	9671.32	317.30
	10	2.555	3.434	0.2	6576.50	215.76
	15	16.52	1.361	0.0	3909.70	128.27
	20	3.601	1.491	0.1	5710.87	187.36
	30	7.96	0.551	0.3	3162.81	103.77
	40	7.518	0.320	0.0	2449.81	80.37
	60	3.146	0.240	0.2	2754.32	90.36
R-2a	2	25.26	28.620	0.0	10962.11	359.65
(N-S)	5	36.68	10.830	0.1	10370.34	340.23
	10	17.01	2.930	0.0	5611.28	184.10
	15	13.81	1.451	0.0	4168.24	136.75
	20	16.1	0.952	0.0	3647.91	119.68
	30	22.82	0.460	0.0	2640.56	86.63
	40	17.23	0.280	0.1	2144.16	70.35
	60	14.54	0.096	0.0	1097.59	36.01
	80	8.113	0.057	0.2	878.04	28.81
R-2b	2	12.41	31.260	0.0	11973.29	392.82
(E-W)	5	34.18	9.812	0.0	9395.55	308.25
	10	12.58	3.574	0.0	6844.61	224.56
	15	9.211	1.814	0.1	5211.02	170.97
	20	11.58	1.048	0.1	4014.08	131.70
	30	57.12	0.475	0.1	2731.33	89.61
	40	79.82	0.246	0.0	1885.24	61.85
	60	18.9	0.102	0.2	1175.50	38.57
	80	26.12	0.050	0.2	763.61	25.05
R-3a	2	29.46	33.550	0.0	12850.41	421.60
(N-S)	5	38.14	5.773	0.0	5527.97	181.36
	10	20.78	1.441	0.0	2759.68	90.54
	15	24.98	0.766	0.0	2200.18	72.18
	20	12.05	0.561	0.0	2149.52	70.52
	30	7.634	0.309	0.1	1774.74	58.23
	40	20.4	0.189	0.1	1450.12	47.58
	60	30.51	0.087	0.2	1001.76	32.87
	80	11.36	0.040	0.1	618.20	20.28

Electrical Resistivity Results

Harper Lake Power Facility
San Bernardino County, California

Project No.: 109087

Date: 04/09



Figure 4a

Line No. (Orientation)	Spacing (ft)	Current (mA)	Resistance (Ohms)	Error (%)	Apparent Resistivity	
					(ohm-cm)	(ohm-ft)
R-3b	2	4.814	44.950	0.2	17216.87	564.86
(E-W)	5	15.99	5.607	0.0	5369.02	176.15
	10	20.5	1.274	0.0	2439.85	80.05
	15	5.651	0.763	0.1	2191.85	71.91
	20	12.11	0.506	0.1	1938.86	63.61
	30	16.86	0.305	0.1	1749.46	57.40
	40	15.09	0.207	0.1	1581.88	51.90
	60	10.75	0.084	0.2	970.16	31.83
	80	21.73	0.051	0.0	777.54	25.51
R-4a	2	23.87	41.380	0.0	15849.48	520.00
(N-S)	5	15.06	6.492	0.0	6216.46	203.95
	10	26.57	1.522	0.0	2914.80	95.63
	15	18.23	1.127	0.0	3237.50	106.22
	20	22.96	0.962	0.0	3685.83	120.93
	30	37.47	0.660	0.0	3791.35	124.39
	40	66.99	0.460	0.0	3523.04	115.59
	60	44.22	0.221	0.1	2535.99	83.20
	80	20.57	0.112	0.1	1714.41	56.25
R-4b	2	14.09	43.530	0.1	16672.98	547.01
(E-W)	5	23.78	6.061	0.1	5803.75	190.41
	10	20.62	1.471	0.0	2817.13	92.43
	15	18.24	1.149	0.0	3300.70	108.29
	20	28	1.021	0.1	3910.66	128.30
	30	13.5	0.658	0.2	3779.28	123.99
	40	11.73	0.432	0.3	3307.78	108.52
	60	4.493	0.254	0.3	2916.33	95.68
	80	5.908	0.140	0.0	2137.27	70.12
R-5a	2	14.8	32.500	0.0	12448.24	408.41
(N-S)	5	6.577	5.424	0.0	5193.79	170.40
	10	2.643	2.725	0.1	5218.68	171.22
	15	7.87	1.155	0.0	3317.93	108.86
	20	7.668	0.890	0.1	3409.67	111.87
	30	5.393	0.753	0.1	4328.54	142.01
	40	6.53	0.473	0.1	3626.46	118.98
	60	6.072	0.303	0.2	3479.38	114.15
	80	10	0.200	0.1	3056.52	100.28
R-5b	2	7.478	33.090	0.0	12674.22	415.82
(E-W)	5	7.415	5.413	0.0	5183.25	170.05
	10	6.479	2.489	0.2	4766.72	156.39
	15	5.087	1.492	0.0	4286.02	140.62
	20	7.748	0.868	0.0	3323.87	109.05
	30	6.464	0.638	0.0	3666.68	120.30
	40	5.679	0.461	0.2	3531.47	115.86
	60	8.539	0.317	0.1	3644.84	119.58
	80	7.098	0.212	0.1	3246.50	106.51

Electrical Resistivity Results

Harper Lake Power Facility
San Bernardino County, California

Project No.: 109087

Date: 04/09



Figure 4b

APPENDIX F
TYPICAL EARTHWORK GUIDELINES

TABLE OF CONTENTS

	<u>Page</u>
1. GENERAL.....	1
2. OBLIGATIONS OF PARTIES	2
3. SITE PREPARATION	3
4. REMOVALS AND EXCAVATIONS	4
5. COMPACTED FILL	4
6. OVERSIZED MATERIAL	7
7. SLOPES.....	8
8. TRENCH BACKFILL.....	10
9. DRAINAGE	12
10. SITE PROTECTION	12
11. DEFINITIONS OF TERMS	15

Figures

Figure A – Fill Slope over Natural Ground or Cut

Figure B – Transition and Undercut Lot Details

Figure C – Canyon Subdrain Detail

Figure D – Oversized Rock Placement Detail

TYPICAL EARTHWORK GUIDELINES

1. GENERAL

These guidelines and the standard details attached hereto are presented as general procedures for earthwork construction for sites having slopes less than 10 feet high. They are to be utilized in conjunction with the project grading plans. These guidelines are considered a part of the geotechnical report, but are superseded by recommendations in the geotechnical report in the case of conflict. Evaluations performed by the consultant during the course of grading may result in new recommendations which could supersede these specifications and/or the recommendations of the geotechnical report. It is the responsibility of the contractor to read and understand these guidelines as well as the geotechnical report and project grading plans.

- 1.1. The contractor shall not vary from these guidelines without prior recommendations by the geotechnical consultant and the approval of the client or the client's authorized representative. Recommendations by the geotechnical consultant and/or client shall not be considered to preclude requirements for approval by the jurisdictional agency prior to the execution of any changes.
- 1.2. The contractor shall perform the grading operations in accordance with these specifications, and shall be responsible for the quality of the finished product notwithstanding the fact that grading work will be observed and tested by the geotechnical consultant.
- 1.3. It is the responsibility of the grading contractor to notify the geotechnical consultant and the jurisdictional agencies, as needed, prior to the start of work at the site and at any time that grading resumes after interruption. Each step of the grading operations shall be observed and documented by the geotechnical consultant and, where needed, reviewed by the appropriate jurisdictional agency prior to proceeding with subsequent work.
- 1.4. If, during the grading operations, geotechnical conditions are encountered which were not anticipated or described in the geotechnical report, the geotechnical consultant shall be notified immediately and additional recommendations, if applicable, may be provided.
- 1.5. An as-graded report shall be prepared by the geotechnical consultant and signed by a registered engineer and registered engineering geologist. The report documents the geotechnical consultants' observations, and field and laboratory test results, and provides conclusions regarding whether or not earthwork construction was performed in accordance with the geotechnical recommendations and the grading

plans. Recommendations for foundation design, pavement design, subgrade treatment, etc., may also be included in the as-graded report.

- 1.6. For the purpose of evaluating quantities of materials excavated during grading and/or locating the limits of excavations, a licensed land surveyor or civil engineer shall be retained.
- 1.7. Definitions of terms utilized in the remainder of these specifications have been provided in Section 11.

2. OBLIGATIONS OF PARTIES

The parties involved in the projects earthwork activities shall be responsible as outlined in the following sections.

- 2.1. The client is ultimately responsible for each of the aspects of the project. The client or the client's authorized representative has a responsibility to review the findings and recommendations of the geotechnical consultant. The client shall authorize the contractor and/or other consultants to perform work and/or provide services. During grading the client or the client's authorized representative shall remain on site or remain reasonably accessible to the concerned parties to make the decisions that may be needed to maintain the flow of the project.
- 2.2. The contractor is responsible for the safety of the project and satisfactory completion of grading and other associated operations, including, but not limited to, earthwork in accordance with the project plans, specifications, and jurisdictional agency requirements. During grading, the contractor or the contractor's authorized representative shall remain on site. The contractor shall further remain accessible during non-working hours, including at night and during days off.
- 2.3. The geotechnical consultant shall provide observation and testing services and shall make evaluations to advise the client on geotechnical matters. The geotechnical consultant shall report findings and recommendations to the client or the client's authorized representative.
- 2.4. Prior to proceeding with any grading operations, the geotechnical consultant shall be notified two working days in advance to schedule the needed observation and testing services.
 - 2.4.1. Prior to any significant expansion or reduction in the grading operation, the geotechnical consultant shall be provided with two working days notice to make appropriate adjustments in scheduling of on-site personnel.

- 2.4.2. Between phases of grading operations, the geotechnical consultant shall be provided with two working days notice in advance of commencement of additional grading operations.

3. SITE PREPARATION

Site preparation shall be performed in accordance with the recommendations presented in the following sections.

- 3.1. The client, prior to any site preparation or grading, shall arrange and attend a pre-grading meeting between the grading contractor, the design engineer, the geotechnical consultant, and representatives of appropriate governing authorities, as well as any other involved parties. The parties shall be given two working days notice.
- 3.2. Clearing and grubbing shall consist of the substantial removal of vegetation, brush, grass, wood, stumps, trees, tree roots greater than 1/2-inch in diameter, and other deleterious materials from the areas to be graded. Clearing and grubbing shall extend to the outside of the proposed excavation and fill areas.
- 3.3. Demolition in the areas to be graded shall include removal of building structures, foundations, reservoirs, utilities (including underground pipelines, septic tanks, leach fields, seepage pits, cisterns, etc.), and other manmade surface and subsurface improvements, and the backfilling of mining shafts, tunnels and surface depressions. Demolition of utilities shall include capping or rerouting of pipelines at the project perimeter, and abandonment of wells in accordance with the requirements of the governing authorities and the recommendations of the geotechnical consultant at the time of demolition.
- 3.4. The debris generated during clearing, grubbing and/or demolition operations shall be removed from areas to be graded and disposed of off site at a legal dump site. Clearing, grubbing, and demolition operations shall be performed under the observation of the geotechnical consultant.
- 3.5. The ground surface beneath proposed fill areas shall be stripped of loose or unsuitable soil. These soils may be used as compacted fill provided they are generally free of organic or other deleterious materials and evaluated for use by the geotechnical consultant. The resulting surface shall be evaluated by the geotechnical consultant prior to proceeding. The cleared, natural ground surface shall be scarified to a depth of approximately 8 inches, moisture conditioned, and compacted in accordance with the specifications presented in Section 5 of these guidelines.

4. REMOVALS AND EXCAVATIONS

Removals and excavations shall be performed as recommended in the following sections.

4.1. Removals

- 4.1.1. Materials which are considered unsuitable shall be excavated under the observation of the geotechnical consultant in accordance with the recommendations contained herein. Unsuitable materials include, but may not be limited to, dry, loose, soft, wet, organic, compressible natural soils, fractured, weathered, soft bedrock, and undocumented or otherwise deleterious fill materials.
- 4.1.2. Materials deemed by the geotechnical consultant to be unsatisfactory due to moisture conditions shall be excavated in accordance with the recommendations of the geotechnical consultant, watered or dried as needed, and mixed to a generally uniform moisture content in accordance with the specifications presented in Section 5 of this document.

4.2. Excavations

- 4.2.1. Temporary excavations no deeper than 5 feet in firm fill or natural materials may be made with vertical side slopes. To satisfy California Occupational Safety and Health Administration (CAL OSHA) requirements, any excavation deeper than 5 feet shall be shored or laid back at a 1:1 inclination or flatter, depending on material type, if construction workers are to enter the excavation.

5. COMPACTED FILL

Fill shall be constructed as specified below or by other methods recommended by the geotechnical consultant. Unless otherwise specified, fill soils shall be compacted to 90 percent relative compaction, as evaluated in accordance with ASTM Test Method D 1557.

- 5.1. Prior to placement of compacted fill, the contractor shall request an evaluation of the exposed ground surface by the geotechnical consultant. Unless otherwise recommended, the exposed ground surface shall then be scarified to a depth of approximately 8 inches and watered or dried, as needed, to achieve a generally uniform moisture content at or near the optimum moisture content. The scarified materials shall then be compacted to 90 percent relative compaction. The evaluation of compaction by the geotechnical consultant shall not be considered to preclude any requirements for observation or approval by governing agencies. It is the contractor's responsibility to notify the geotechnical consultant and the appro-

appropriate governing agency when project areas are ready for observation, and to provide reasonable time for that review.

- 5.2. Excavated on-site materials which are in general compliance with the recommendations of the geotechnical consultant may be utilized as compacted fill provided they are generally free of organic or other deleterious materials and do not contain rock fragments greater than 6 inches in dimension. During grading, the contractor may encounter soil types other than those analyzed during the preliminary geotechnical study. The geotechnical consultant shall be consulted to evaluate the suitability of any such soils for use as compacted fill.
- 5.3. Where imported materials are to be used on site, the geotechnical consultant shall be notified three working days in advance of importation in order that it may sample and test the materials from the proposed borrow sites. No imported materials shall be delivered for use on site without prior sampling, testing, and evaluation by the geotechnical consultant.
- 5.4. Soils imported for on-site use shall preferably have very low to low expansion potential (based on UBC Standard 18-2 test procedures). Lots on which expansive soils may be exposed at grade shall be undercut 3 feet or more and capped with very low to low expansion potential fill. Details of the undercutting are provided in the Transition and Undercut Lot Details, Figure B of these guidelines. In the event expansive soils are present near the ground surface, special design and construction considerations shall be utilized in general accordance with the recommendations of the geotechnical consultant.
- 5.5. Fill materials shall be moisture conditioned to near optimum moisture content prior to placement. The optimum moisture content will vary with material type and other factors. Moisture conditioning of fill soils shall be generally uniform in the soil mass.
- 5.6. Prior to placement of additional compacted fill material following a delay in the grading operations, the exposed surface of previously compacted fill shall be prepared to receive fill. Preparation may include scarification, moisture conditioning, and recompaction.
- 5.7. Compacted fill shall be placed in horizontal lifts of approximately 8 inches in loose thickness. Prior to compaction, each lift shall be watered or dried as needed to achieve near optimum moisture condition, mixed, and then compacted by mechanical methods, using sheepsfoot rollers, multiple-wheel pneumatic-tired rollers, or other appropriate compacting rollers, to the specified relative compaction. Successive lifts shall be treated in a like manner until the desired finished grades are achieved.

- 5.8. Fill shall be tested in the field by the geotechnical consultant for evaluation of general compliance with the recommended relative compaction and moisture conditions. Field density testing shall conform to ASTM D 1556-00 (Sand Cone method), D 2937-00 (Drive-Cylinder method), and/or D 2922-96 and D 3017-96 (Nuclear Gauge method). Generally, one test shall be provided for approximately every 2 vertical feet of fill placed, or for approximately every 1000 cubic yards of fill placed. In addition, on slope faces one or more tests shall be taken for approximately every 10,000 square feet of slope face and/or approximately every 10 vertical feet of slope height. Actual test intervals may vary as field conditions dictate. Fill found to be out of conformance with the grading recommendations shall be removed, moisture conditioned, and compacted or otherwise handled to accomplish general compliance with the grading recommendations.
- 5.9. The contractor shall assist the geotechnical consultant by excavating suitable test pits for removal evaluation and/or for testing of compacted fill.
- 5.10. At the request of the geotechnical consultant, the contractor shall "shut down" or restrict grading equipment from operating in the area being tested to provide adequate testing time and safety for the field technician.
- 5.11. The geotechnical consultant shall maintain a map with the approximate locations of field density tests. Unless the client provides for surveying of the test locations, the locations shown by the geotechnical consultant will be estimated. The geotechnical consultant shall not be held responsible for the accuracy of the horizontal or vertical locations or elevations.
- 5.12. Grading operations shall be performed under the observation of the geotechnical consultant. Testing and evaluation by the geotechnical consultant does not preclude the need for approval by or other requirements of the jurisdictional agencies.
- 5.13. Fill materials shall not be placed, spread or compacted during unfavorable weather conditions. When work is interrupted by heavy rains, the filling operation shall not be resumed until tests indicate that moisture content and density of the fill meet the project specifications. Regrading of the near-surface soil may be needed to achieve the specified moisture content and density.
- 5.14. Upon completion of grading and termination of observation by the geotechnical consultant, no further filling or excavating, including that planned for footings, foundations, retaining walls or other features, shall be performed without the involvement of the geotechnical consultant.
- 5.15. Fill placed in areas not previously viewed and evaluated by the geotechnical consultant may have to be removed and recompacted at the contractor's expense. The depth and extent of removal of the unobserved and undocumented fill will be decided based upon review of the field conditions by the geotechnical consultant.

- 5.16. Off-site fill shall be treated in the same manner as recommended in these specifications for on-site fills. Off-site fill subdrains temporarily terminated (up gradient) shall be surveyed for future locating and connection.

6. OVERSIZED MATERIAL

Oversized material shall be placed in accordance with the following recommendations.

- 6.1. During the course of grading operations, rocks or similar irreducible materials greater than 6 inches in dimension (oversized material) may be generated. These materials shall not be placed within the compacted fill unless placed in general accordance with the recommendations of the geotechnical consultant.
- 6.2. Where oversized rock (greater than 6 inches in dimension) or similar irreducible material is generated during grading, it is recommended, where practical, to waste such material off site, or on site in areas designated as "nonstructural rock disposal areas." Rock designated for disposal areas shall be placed with sufficient sandy soil to generally fill voids. The disposal area shall be capped with a 5-foot thickness of fill which is generally free of oversized material.
- 6.3. Rocks 6 inches in dimension and smaller may be utilized within the compacted fill, provided they are placed in such a manner that nesting of rock is not permitted. Fill shall be placed and compacted over and around the rock. The amount of rock greater than 3/4-inch in dimension shall generally not exceed 40 percent of the total dry weight of the fill mass, unless the fill is specially designed and constructed as a "rock fill."
- 6.4. Rocks or similar irreducible materials greater than 6 inches but less than 4 feet in dimension generated during grading may be placed in windrows and capped with finer materials in accordance with the recommendations of the geotechnical consultant, the approval of the governing agencies, and the Oversized Rock Placement Detail, Figure D, of these guidelines. Selected native or imported granular soil (Sand Equivalent of 30 or higher) shall be placed and flooded over and around the windrowed rock such that voids are filled. Windrows of oversized materials shall be staggered so that successive windrows of oversized materials are not in the same vertical plane. Rocks greater than 4 feet in dimension shall be broken down to 4 feet or smaller before placement, or they shall be disposed of off site.

7. SLOPES

The following sections provide recommendations for cut and fill slopes.

7.1. Cut Slopes

- 7.1.1. The geotechnical consultant shall observe cut slopes during excavation. The geotechnical consultant shall be notified by the contractor prior to beginning slope excavations.
- 7.1.2. If, during the course of grading, adverse or potentially adverse geotechnical conditions are encountered in the slope which were not anticipated in the preliminary evaluation report, the geotechnical consultant shall evaluate the conditions and provide appropriate recommendations.

7.2. Fill Slopes

- 7.2.1. When placing fill on slopes steeper than 5:1 (horizontal:vertical), topsoil, slope wash, colluvium, and other materials deemed unsuitable shall be removed. Near-horizontal keys and near-vertical benches shall be excavated into sound bedrock or firm fill material, in accordance with the recommendation of the geotechnical consultant. Keying and benching shall be accomplished. Compacted fill shall not be placed in an area subsequent to keying and benching until the area has been observed by the geotechnical consultant. Where the natural gradient of a slope is less than 5:1, benching is generally not recommended. However, fill shall not be placed on compressible or otherwise unsuitable materials left on the slope face.
- 7.2.2. Within a single fill area where grading procedures dictate two or more separate fills, temporary slopes (false slopes) may be created. When placing fill adjacent to a temporary slope, benching shall be conducted in the manner described in Section 7.2.1. A 3-foot or higher near-vertical bench shall be excavated into the documented fill prior to placement of additional fill.
- 7.2.3. Unless otherwise recommended by the geotechnical consultant and accepted by the Building Official, permanent fill slopes shall not be steeper than 2:1 (horizontal:vertical). The height of a fill slope shall be evaluated by the geotechnical consultant.
- 7.2.4. Unless specifically recommended otherwise, compacted fill slopes shall be overbuilt and cut back to grade, exposing firm compacted fill. The actual amount of overbuilding may vary as field conditions dictate. If the desired results are not achieved, the existing slopes shall be overexcavated and reconstructed in accordance with the recommendations of the geotechnical consultant. The degree of overbuilding may be increased until the desired

compacted slope face condition is achieved. Care shall be taken by the contractor to provide mechanical compaction as close to the outer edge of the overbuilt slope surface as practical.

- 7.2.5. If access restrictions, property line location, or other constraints limit overbuilding and cutting back of the slope face, an alternative method for compaction of the slope face may be attempted by conventional construction procedures including backrolling at intervals of 4 feet or less in vertical slope height, or as dictated by the capability of the available equipment, whichever is less. Fill slopes shall be backrolled utilizing a conventional sheeps foot-type roller. Care shall be taken to maintain the specified moisture conditions and/or reestablish the same, as needed, prior to backrolling.
- 7.2.6. The placement, moisture conditioning and compaction of fill slope materials shall be done in accordance with the recommendations presented in Section 5 of these guidelines.
- 7.2.7. The contractor shall be ultimately responsible for placing and compacting the soil out to the slope face to obtain a relative compaction of 90 percent as evaluated by ASTM D 1557 and a moisture content in accordance with Section 5. The geotechnical consultant shall perform field moisture and density tests at intervals of one test for approximately every 10,000 square feet of slope.
- 7.2.8. Backdrains shall be provided in fill as recommended by the geotechnical consultant.

7.3. Top-of-Slope Drainage

- 7.3.1. For pad areas above slopes, positive drainage shall be established away from the top of slope. This may be accomplished utilizing a berm and pad gradient of 2 percent or steeper at the top-of-slope areas. Site runoff shall not be permitted to flow over the tops of slopes.
- 7.3.2. Gunite-lined brow ditches shall be placed at the top of cut slopes to redirect surface runoff away from the slope face where drainage devices are not otherwise provided.

7.4. Slope Maintenance

- 7.4.1. In order to enhance surficial slope stability, slope planting shall be accomplished at the completion of grading. Slope plants shall consist of deep-rooting, variable root depth, drought-tolerant vegetation. Native vegetation is generally desirable. Plants native to semiarid and arid areas may also be appropriate. Large-leafed ice plant should not be used on slopes. A landscape

architect shall be consulted regarding the actual types of plants and planting configuration to be used.

- 7.4.2. Irrigation pipes shall be anchored to slope faces and not placed in trenches excavated into slope faces. Slope irrigation shall be maintained at a level just sufficient to support plant growth. Property owners shall be made aware that over watering of slopes is detrimental to slope stability. Slopes shall be monitored regularly and broken sprinkler heads and/or pipes shall be repaired immediately.
- 7.4.3. Periodic observation of landscaped slope areas shall be planned and appropriate measures taken to enhance growth of landscape plants.
- 7.4.4. Graded swales at the top of slopes and terrace drains shall be installed and the property owners notified that the drains shall be periodically checked so that they may be kept clear. Damage to drainage improvements shall be repaired immediately. To reduce siltation, terrace drains shall be constructed at a gradient of 3 percent or steeper, in accordance with the recommendations of the project civil engineer.
- 7.4.5. If slope failures occur, the geotechnical consultant shall be contacted immediately for field review of site conditions and development of recommendations for evaluation and repair.

8. TRENCH BACKFILL

The following sections provide recommendations for backfilling of trenches.

- 8.1. Trench backfill shall consist of granular soils (bedding) extending from the trench bottom to 1 foot or more above the pipe. On-site or imported fill which has been evaluated by the geotechnical consultant may be used above the granular backfill. The cover soils directly in contact with the pipe shall be classified as having a very low expansion potential, in accordance with UBC Standard 18-2, and shall contain no rocks or chunks of hard soil larger than 3/4-inch in diameter.
- 8.2. Trench backfill shall, unless otherwise recommended, be compacted by mechanical means to 90 percent relative compaction as evaluated by ASTM D 1557. Backfill soils shall be placed in loose lifts 8-inches thick or thinner, moisture conditioned, and compacted in accordance with the recommendations of Section 5. of these guidelines. The backfill shall be tested by the geotechnical consultant at vertical intervals of approximately 2 feet of backfill placed and at spacings along the trench of approximately 100 feet in the same lift.

-
- 8.3. Jetting of trench backfill materials is generally not a recommended method of densification, unless the on-site soils are sufficiently free-draining and provisions have been made for adequate dissipation of the water utilized in the jetting process.
 - 8.4. If it is decided that jetting may be utilized, granular material with a sand equivalent greater than 30 shall be used for backfilling in the areas to be jetted. Jetting shall generally be considered for trenches 2 feet or narrower in width and 4 feet or shallower in depth. Following jetting operations, trench backfill shall be mechanically compacted to the specified compaction to finish grade.
 - 8.5. Trench backfill which underlies the zone of influence of foundations shall be mechanically compacted to 90 percent or greater relative compaction, as evaluated by ASTM D 1557-02. The zone of influence of the foundations is generally defined as the roughly triangular area within the limits of a 1:1 (horizontal:vertical) projection from the inner and outer edges of the foundation, projected down and out from both edges.
 - 8.6. Trench backfill within slab areas shall be compacted by mechanical means to a relative compaction of 90 percent, as evaluated by ASTM D 1557. For minor interior trenches, density testing may be omitted or spot testing may be performed, as deemed appropriate by the geotechnical consultant.
 - 8.7. When compacting soil in close proximity to utilities, care shall be taken by the grading contractor so that mechanical methods used to compact the soils do not damage the utilities. If the utility contractors indicate that it is undesirable to use compaction equipment in close proximity to a buried conduit, then the grading contractor may elect to use light mechanical compaction equipment or, with the approval of the geotechnical consultant, cover the conduit with clean granular material. These granular materials shall be jetted in place to the top of the conduit in accordance with the recommendations of Section 8.4 prior to initiating mechanical compaction procedures. Other methods of utility trench compaction may also be appropriate, upon review by the geotechnical consultant and the utility contractor, at the time of construction.
 - 8.8. Clean granular backfill and/or bedding materials are not recommended for use in slope areas unless provisions are made for a drainage system to mitigate the potential for buildup of seepage forces or piping of backfill materials.
 - 8.9. The contractor shall exercise the specified safety precautions, in accordance with OSHA Trench Safety Regulations, while conducting trenching operations. Such precautions include shoring or laying back trench excavations at 1:1 or flatter, depending on material type, for trenches in excess of 5 feet in depth. The geotechnical consultant is not responsible for the safety of trench operations or stability of the trenches.

9. DRAINAGE

The following sections provide recommendations pertaining to site drainage.

- 9.1. Roof, pad, and slope drainage shall be such that it is away from slopes and structures to suitable discharge areas by nonerrodible devices (e.g., gutters, downspouts, concrete swales, etc.).
- 9.2. Positive drainage adjacent to structures shall be established and maintained. Positive drainage may be accomplished by providing drainage away from the foundations of the structure at a gradient of 2 percent or steeper for a distance of 5 feet or more outside the building perimeter, further maintained by a graded swale leading to an appropriate outlet, in accordance with the recommendations of the project civil engineer and/or landscape architect.
- 9.3. Surface drainage on the site shall be provided so that water is not permitted to pond. A gradient of 2 percent or steeper shall be maintained over the pad area and drainage patterns shall be established to remove water from the site to an appropriate outlet.
- 9.4. Care shall be taken by the contractor during grading to preserve any berms, drainage terraces, interceptor swales or other drainage devices of a permanent nature on or adjacent to the property. Drainage patterns established at the time of finish grading shall be maintained for the life of the project. Property owners shall be made very clearly aware that altering drainage patterns may be detrimental to slope stability and foundation performance.

10. SITE PROTECTION

The site shall be protected as outlined in the following sections.

- 10.1. Protection of the site during the period of grading shall be the responsibility of the contractor unless other provisions are made in writing and agreed upon among the concerned parties. Completion of a portion of the project shall not be considered to preclude that portion or adjacent areas from the need for site protection, until such time as the project is finished as agreed upon by the geotechnical consultant, the client, and the regulatory agency.
- 10.2. The contractor is responsible for the stability of temporary excavations. Recommendations by the geotechnical consultant pertaining to temporary excavations are made in consideration of stability of the finished project and, therefore, shall not be considered to preclude the responsibilities of the contractor. Recommendations by the geotechnical consultant shall also not be considered to preclude more restrictive requirements by the applicable regulatory agencies.

- 10.3. Precautions shall be taken during the performance of site clearing, excavation, and grading to protect the site from flooding, ponding, or inundation by surface runoff. Temporary provisions shall be made during the rainy season so that surface runoff is away from and off the working site. Where low areas cannot be avoided, pumps shall be provided to remove water as needed during periods of rainfall.
- 10.4. During periods of rainfall, plastic sheeting shall be used as needed to reduce the potential for unprotected slopes to become saturated. Where needed, the contractor shall install check dams, desilting basins, riprap, sandbags or other appropriate devices or methods to reduce erosion and provide recommended conditions during inclement weather.
- 10.5. During periods of rainfall, the geotechnical consultant shall be kept informed by the contractor of the nature of remedial or precautionary work being performed on site (e.g., pumping, placement of sandbags or plastic sheeting, other labor, dozing, etc.).
- 10.6. Following periods of rainfall, the contractor shall contact the geotechnical consultant and arrange a walk-over of the site in order to visually assess rain-related damage. The geotechnical consultant may also recommend excavation and testing in order to aid in the evaluation. At the request of the geotechnical consultant, the contractor shall make excavations in order to aid in evaluation of the extent of rain-related damage.
- 10.7. Rain- or irrigation-related damage shall be considered to include, but may not be limited to, erosion, silting, saturation, swelling, structural distress, and other adverse conditions noted by the geotechnical consultant. Soil adversely affected shall be classified as "Unsuitable Material" and shall be subject to overexcavation and replacement with compacted fill or to other remedial grading as recommended by the geotechnical consultant.
- 10.8. Relatively level areas where saturated soils and/or erosion gullies exist to depths greater than 1 foot shall be overexcavated to competent materials as evaluated by the geotechnical consultant. Where adverse conditions extend to less than 1 foot in depth, saturated and/or eroded materials may be processed in-place. Overexcavated or in-place processed materials shall be moisture conditioned and compacted in accordance with the recommendations provided in Section 5. If the desired results are not achieved, the affected materials shall be overexcavated, moisture conditioned, and compacted until the specifications are met.
- 10.9. Slope areas where saturated soil and/or erosion gullies exist to depths greater than 1 foot shall be overexcavated and replaced as compacted fill in accordance with the applicable specifications. Where adversely affected materials exist to depths of 1 foot or less below proposed finished grade, remedial grading by moisture conditioning in-place and compaction in accordance with the appropriate specifications may be attempted. If the desired results are not achieved, the affected materials shall be overexcavated, moisture conditioned, and compacted until the specifications are met. As conditions dictate, other slope repair procedures may also be recommended by the geotechnical consultant.

- 10.10. During construction, the contractor shall grade the site to provide positive drainage away from structures and to keep water from ponding adjacent to structures. Water shall not be allowed to damage adjacent properties. Positive drainage shall be maintained by the contractor until permanent drainage and erosion reducing devices are installed in accordance with project plans.


11. DEFINITIONS OF TERMS


ALLUVIUM:	Unconsolidated detrital deposits deposited by flowing water; includes sediments deposited in river beds, canyons, flood plains, lakes, fans at the foot of slopes, and in estuaries.
AS-GRADED (AS-BUILT):	The site conditions upon completion of grading.
BACKCUT:	A temporary construction slope at the rear of earth-retaining structures such as buttresses, shear keys, stabilization fills, or retaining walls.
BACKDRAIN:	Generally a pipe-and-gravel or similar drainage system placed behind earth-retaining structures such as buttresses, stabilization fills, and retaining walls.
BEDROCK:	Relatively undisturbed in-place rock, either at the surface or beneath surficial deposits of soil.
BENCH:	A relatively level step and near-vertical riser excavated into sloping ground on which fill is to be placed.
BORROW (IMPORT):	Any fill material hauled to the project site from off-site areas.
BUTTRESS FILL:	A fill mass, the configuration of which is designed by engineering calculations, to retain slopes containing adverse geologic features. A buttress is generally specified by a key width and depth and by a backcut angle. A buttress normally contains a back drainage system.
CIVIL ENGINEER:	The Registered Civil Engineer or consulting firm responsible for preparation of the grading plans and surveying, and evaluating as-graded topographic conditions.
CLIENT:	The developer or a project-responsible authorized representative. The client has the responsibility of reviewing the findings and recommendations made by the geotechnical consultant and authorizing the contractor and/or other consultants to perform work and/or provide services.
COLLUVIUM:	Generally loose deposits, usually found on the face or near the base of slopes and brought there chiefly by gravity through slow continuous downhill creep (see also Slope Wash).
COMPACTION:	The densification of a fill by mechanical means.


CONTRACTOR:	A person or company under contract or otherwise retained by the client to perform demolition, grading, and other site improvements.
DEBRIS:	The products of clearing, grubbing, and/or demolition, or contaminated soil material unsuitable for reuse as compacted fill, and/or any other material so designated by the geotechnical consultant.
ENGINEERED FILL:	A fill which the geotechnical consultant or the consultant's representative has observed and/or tested during placement, enabling the consultant to conclude that the fill has been placed in substantial compliance with the recommendations of the geotechnical consultant and the governing agency requirements.
ENGINEERING GEOLOGIST:	A geologist registered by the state licensing agency who applies geologic knowledge and principles to the exploration and evaluation of naturally occurring rock and soil, as related to the design of civil works.
EROSION:	The wearing away of the ground surface as a result of the movement of wind, water, and/or ice.
EXCAVATION:	The mechanical removal of earth materials.
EXISTING GRADE:	The ground surface configuration prior to grading; original grade.
FILL:	Any deposit of soil, rock, soil-rock blends, or other similar materials placed by man.
FINISH GRADE:	The as-graded ground surface elevation that conforms to the grading plan.
GEOFABRIC:	An engineering textile utilized in geotechnical applications such as subgrade stabilization and filtering.
GEOTECHNICAL CONSULTANT:	The geotechnical engineering and engineering geology consulting firm retained to provide technical services for the project. For the purpose of these specifications, observations by the geotechnical consultant include observations by the geotechnical engineer, engineering geologist and other persons employed by and responsible to the geotechnical consultant.


GEOTECHNICAL ENGINEER:	A licensed civil engineer and geotechnical engineer, registered by the state licensing agency, who applies scientific methods, engineering principles, and professional experience to the acquisition, interpretation, and use of knowledge of materials of the earth's crust to the resolution of engineering problems. Geotechnical engineering encompasses many of the engineering aspects of soil mechanics, rock mechanics, geology, geophysics, hydrology, and related sciences.
GRADING:	Any operation consisting of excavation, filling, or combinations thereof and associated operations.
LANDSLIDE DEPOSITS:	Material, often porous and of low density, produced from instability of natural or manmade slopes.
OPTIMUM MOISTURE:	The moisture content that is considered optimum relative to correction operations obtained from ASTM test method D 1557.
RELATIVE COMPACTION:	The degree of compaction (expressed as a percentage) of a material as compared to the dry density obtained from ASTM test method D 1557.
ROUGH GRADE:	The ground surface configuration at which time the surface elevations approximately conform to the project plan.
SHEAR KEY:	Similar to a subsurface buttress; however, it is generally constructed by excavating a slot within a natural slope in order to stabilize the upper portion of the slope without encroaching into the lower portion of the slope.
SITE:	The particular parcel of land where grading is being performed.
SLOPE:	An inclined ground surface, the steepness of which is generally specified as a ratio of horizontal units to vertical units.
SLOPE WASH:	Soil and/or rock material that has been transported down a slope by gravity assisted by the action of water not confined to channels (see also Colluvium).
SLOUGH:	Loose, uncompacted fill material generated during grading operations.

SOIL:	Naturally occurring deposits of sand, silt, clay, etc., or combinations thereof.
STABILIZATION FILL:	A fill mass, the configuration of which is typically related to slope height and is specified by the standards of practice for enhancing the stability of locally adverse conditions. A stabilization fill is normally specified by a key width and depth and by a backcut angle. A stabilization fill may or may not have a back drainage system specified.
SUBDRAIN:	Generally a pipe-and-gravel or similar drainage system placed beneath a fill along the alignment of buried canyons or former drainage channels.
TAILINGS:	Non-engineered fill which accumulates on or adjacent to equipment haul roads.
TERRACE:	A relatively level bench constructed on the face of a graded slope surface for drainage and maintenance purposes.
TOPSOIL:	The upper zone of soil or bedrock materials, which is usually dark in color, loose, and contains organic materials.
WINDROW:	A row of large rocks buried within engineered fill in accordance with guidelines set forth by the geotechnical consultant.









APPENDIX L

PALEONTOLOGY STUDY

Errata Notice

Following publication of this report by SWCA, new project description information was developed by SCE. In particular, the 55 new poles between Lockhart Substation and Harper Lake Road are no longer needed; existing transmission line structures will be used for cable installation. The figures in this report have been annotated regarding this change.

**Paleontological Resources
Assessment in Support of the
Environmental Assessment of the
Abengoa Mojave Solar Project,
San Bernardino County, California**

Prepared for

AECOM

Prepared by

SWCA Environmental Consultants

Pasadena Office

June 2010

**PALEONTOLOGICAL RESOURCES ASSESSMENT IN SUPPORT OF THE ENVIRONMENTAL ASSESSMENT
OF THE ABENGOA MOJAVE SOLAR PROJECT; SAN BERNARDINO COUNTY, CALIFORNIA**

SWCA PROJECT NUMBER 16646

SUBMITTED TO:

AECOM

1420 Kettner Boulevard, Suite 500
San Diego, California 92101

SUBMITTED BY:

SWCA Environmental Consultants
625 Fair Oaks Avenue, Suite 190
South Pasadena, California 91030



Jessica L. DeBusk, SWCA Project Manager and Paleontology Lead



Cara Corsetti, SWCA Office Principal and Qualified Paleontologist

PROJECT SUMMARY

PURPOSE AND SCOPE

SWCA Environmental Consultants was retained by AECOM to conduct paleontological resources management services in support of the Environmental Assessment (EA) of the Abengoa Mojave Solar Project (AMSP) located near Barstow in San Bernardino County, California. A paleontological resources assessment of the AMSP site was conducted by SWCA in July 2009 (DeBusk and Corsetti, 2009). The current study addresses the paleontological resource potential of associated supporting infrastructure for the AMSP, hereinafter referred to as the “project area.” The scope of services for the current study included a comprehensive museum records search and literature review and preparation of this technical report of findings that includes recommended mitigation measures.

DATES OF INVESTIGATION

The museum records search was performed on May 7, 2010. This technical report was completed in June 2010.

RESULTS OF THE INVESTIGATION

Geologic mapping by Bortugno and Spittler (1986) and Dibblee (2008a; 2008b) indicate that the project area is underlain by the following geologic units, in approximate ascending stratigraphic order: (1) the Tropico Group of Miocene age (23 million years ago [Ma] to 5.3 Ma), (2) older Quaternary alluvial deposits of Pleistocene age (1.8 Ma to 10,000 years before present [BP]), and (3) younger alluvium of Holocene age (10,000 years BP to Recent). Museum collections records maintained by the San Bernardino County Museum (SBCM) indicate that 18 previously recorded potential fossil localities exist within the project area and immediate vicinity. In addition, numerous vertebrate fossil localities have been recorded throughout the region within the same or similar sedimentary deposits that occur within the project area.

The combined results of the museum records search and literature review indicate that geologic units underlying the project area have a paleontological sensitivity ranging from low to high. Therefore, development of the AMSP may potentially result in direct adverse impacts to nonrenewable fossil resources and will require implementation of paleontological resources mitigation measures to reduce such impacts to a less-than-significant level.

RECOMMENDATIONS

SWCA recommends that a qualified paleontologist be retained to design and implement a paleontological resources monitoring and mitigation plan (PRMMP) for areas where ground disturbance is proposed. All significant fossils recovered during construction monitoring should be prepared, stabilized, identified, and permanently curated in an approved repository or museum such as the SBCM.

DISPOSITION OF DATA

This report will be filed with AECOM. A copy will be retained at SWCA Environmental Consultants, along with all other records relating to the project.

TABLE OF CONTENTS

PROJECT SUMMARY	i
Purpose and Scope.....	i
Dates of Investigation.....	i
Results of the Investigation	i
Recommendations	i
Disposition of Data.....	i
INTRODUCTION	4
Definition and Significance of Paleontological Resources	4
LAWS, ORDINANCES, REGULATIONS, AND STANDARDS	4
National Environmental Policy Act.....	5
Federal Land Policy and Management Act	5
American Antiquities Act.....	5
National Historic Preservation Act.....	5
Code of Federal Regulations Title 43.....	6
Department of the Interior Report—Fossils on Federal and Indian Lands	6
Professional Standards	6
RESOURCE ASSESSMENT Summary	7
PROJECT LOCATION AND DESCRIPTION	8
PROJECT PERSONNEL	10
METHODS	11
Museum Records Search.....	11
GEOLOGY AND PALEONTOLOGY	11
Geologic Setting.....	11
Site-specific Geology and Paleontology	12
Tropico Group.....	12
Quaternary Older Alluvium.....	16
Quaternary Younger Alluvium	16
ANALYSIS AND RESULTS	16
Museum Records Search.....	16
CONCLUSIONS	18
RECOMMENDED MITIGATION MEASURES	18
Preconstruction Assessment, Survey, and Excavation	18
Survey	18
Sampling	19
Salvage.....	19
Avoidance	19
Construction Monitoring.....	19
Fossil Preparation and Curation.....	20
Reporting	20
REFERENCES	21

LIST OF FIGURES

Figure 1. Project Overview Map.....	9
Figure 2. Geologic and Paleontological Sensitivity Map 1 of 3	13
Figure 3. Geologic and Paleontological Sensitivity Map 2 of 3	14

Figure 4. Geologic and Paleontological Sensitivity Map 3 of 3	15
Figure 5. Index Map of Confidential Localities.....	1
Figure 6. Confidential Localities Map 1 of 2.....	2
Figure 7. Confidential Localities Map 2 of 2.....	3

LIST OF TABLES

Table 1. Geologic Units within the Project Area	16
Table 2. Previously Recorded Fossil Localities within Project Area and Vicinity.....	17

APPENDIX

Confidential Appendix A: Paleontological Localities

INTRODUCTION

This report presents the findings of a comprehensive literature review and museum records search conducted in support of the Environmental Assessment of the Abengoa Mojave Solar Project (AMSP) located near Barstow, San Bernardino County, California. This study was performed to evaluate the paleontological sensitivity of the project area and vicinity, assess potential project-related environmental impacts on paleontological resources, and provide recommendations for the management of paleontological resources. This study was conducted in accordance with the professional guidelines established by the Society of Vertebrate Paleontology (SVP) (1995).

DEFINITION AND SIGNIFICANCE OF PALEONTOLOGICAL RESOURCES

Paleontology is a multidisciplinary science that combines elements of geology, biology, chemistry, and physics in an effort to understand the history of life on earth. Paleontological resources, or fossils, are the remains, imprints, or traces of once-living organisms preserved in rocks and sediments. These include mineralized, partially mineralized, or unmineralized bones and teeth, soft tissues, shells, wood, leaf impressions, footprints, burrows, and microscopic remains. The fossil record is the only evidence that life on earth has existed for more than 3.6 billion years. Fossils are considered nonrenewable resources because the organisms they represent no longer exist. Thus, once destroyed, a fossil can never be replaced. Fossils are an important scientific and educational resource because they are used to:

- Study the phylogenetic relationships between extinct organisms, as well as their relationships to modern groups.
- Elucidate the taphonomic, behavioral, temporal, and diagenetic pathways responsible for fossil preservation, including biases in the fossil record.
- Reconstruct ancient environments, climate change, and paleoecological relationships.
- Provide a measure of relative geologic dating, which forms the basis for biochronology and biostratigraphy, and which is an independent and supporting line of evidence for isotopic dating.
- Study the geographic distribution of organisms and tectonic movements of land masses and ocean basins through time.
- Study patterns and processes of evolution, extinction, and speciation.
- Identify past and potential future human-caused effects to global environments and climates (Murphey and Daitch, 2007).

LAWS, ORDINANCES, REGULATIONS, AND STANDARDS

Fossils are classified as nonrenewable scientific resources and are protected by various laws, ordinances, regulations, and standards (LORS) across the country. Professional standards for the assessment and mitigation of adverse impacts on paleontological resources have been established by the SVP (1995, 1996). Federal protections for scientifically significant paleontological resources apply to projects if any construction or other related project impacts occur on federally owned or managed lands, involve the crossing of state lines, or are federally funded. Federal protections would apply to paleontological resources within the area of potential effect (APE) for this project because it is in part federally funded and because a portion of the project area crosses federal lands administered by the Bureau of Land Management (BLM). Pertinent federal LORS are summarized in the following sections.

NATIONAL ENVIRONMENTAL POLICY ACT

The National Environmental Policy Act (NEPA) of 1969, as amended (Pub. L. 91-190, 42 USC 4321-4347, January 1, 1970, as amended by Pub. L. 94-52, July 3, 1975, Pub. L. 94-83, August 9, 1975, and Pub. L. 97-258 § 4(b), Sept. 13, 1982) recognizes the continuing responsibility of the Federal Government to “preserve important historic, cultural, and natural aspects of our national heritage...” (Sec. 101 [42 USC § 4321]) (#382).

The goal of the NEPA process is to make informed, publicly supported decisions regarding environmental issues. Under NEPA, the Federal Government requires that:

- a) all federal agencies consider the environmental impacts of proposed actions;
- b) the public be informed of the potential environmental impacts of proposed actions; and
- c) that the public be involved in planning and analysis relevant to actions that impact the environment.

FEDERAL LAND POLICY AND MANAGEMENT ACT

The Federal Land Policy and Management Act (FLPMA) of 1976 (43 USC 1712[c], 1732[b]); sec. 2, Federal Land Policy and Management Act of 1962 [30 USC 611]; Subpart 3631.0 et seq.), Federal Register Vol. 47, No. 159, 1982 does not refer specifically to fossils. However, “significant fossils” are understood and recognized in policy as scientific resources. Permits that authorize the collection of significant fossils for scientific purposes are issued under the authority of FLPMA.

Under FLPMA, federal agencies are charged to:

- a) manage public lands in a manner that protects the quality of scientific, scenic, historical, ecological, environmental, air and atmospheric, archaeological, and water resources, and, where appropriate, preserve and protect certain public lands in their natural condition (Section 102[a][8] [11]);
- b) periodically inventory public lands so that the data can be used to make informed land-use decisions (Section 102[a][2]); and
- c) regulate the use and development of public lands and resources through easements, licenses, and permits (Section 302[b]).

AMERICAN ANTIQUITIES ACT

The American Antiquities Act of 1906 1 (6 USC 431 433) establishes a penalty for disturbing or excavating any historic or prehistoric ruin or monument or object of antiquity on federal lands as a maximum fine of \$500 or 90 days in jail.

NATIONAL HISTORIC PRESERVATION ACT

The National Historic Preservation Act of 1966 (Pub. L. 89 665; 80 Stat. 915, 16 U.S.C. 470 et seq.) provides for the survey, recovery, and preservation of significant paleontological data when such data may be destroyed or lost due to a federal, federally licensed, or federally funded project.

CODE OF FEDERAL REGULATIONS TITLE 43

Under the Code of Federal Regulations (CFR) Title 43, Section 8365.1-5, the collection of scientific resources, including vertebrate fossils, is prohibited without a permit. Except where prohibited, individuals are also authorized to collect some fossils for their personal use. The use of fossils found on federal lands for commercial purposes is also prohibited.

DEPARTMENT OF THE INTERIOR REPORT—FOSSILS ON FEDERAL AND INDIAN LANDS

In 2000, the Secretary of the Interior submitted a report to Congress titled “Assessment of Fossil Management on Federal and Indian Lands.” This report was prepared with the assistance of eight federal agencies including the Bureau of Indian Affairs, the Bureau of Land Management (BLM), the Bureau of Reclamation, the United States Fish and Wildlife Service, the United States Forest Service (USFS), the National Park Service, the U.S. Geological Survey (USGS), and the Smithsonian Institution. The consulting agencies concluded that administrative and Congressional actions with respect to fossils should be governed by these seven basic principles:

- a) Fossils on federal land are a part of America's heritage.
- b) Most vertebrate fossils are rare.
- c) Some invertebrate and plant fossils are rare.
- d) Penalties for fossil theft should be strengthened.
- e) Effective stewardship requires accurate information.
- f) Federal fossil collections should be preserved and available for research and public education.
- g) Federal fossil management should emphasize opportunities for public involvement.

PROFESSIONAL STANDARDS

The SVP has established standard guidelines (SVP, 1995) that outline professional protocols and practices for the conducting of paleontological resource assessments and surveys, monitoring and mitigation, data and fossil recovery, sampling procedures, and specimen preparation, identification, analysis, and curation. Most practicing professional vertebrate paleontologists adhere closely to the SVP's assessment, mitigation, and monitoring requirements as specifically provided in its standard guidelines. Typically, state regulatory agencies with paleontological LORS accept and use the professional standards set forth by the SVP.

As defined by the SVP (1995:26), significant nonrenewable paleontological resources are defined as:

...Fossils and fossiliferous deposits here restricted to vertebrate fossils and their taphonomic and associated environmental indicators. This definition excludes invertebrate or paleobotanical fossils except when present within a given vertebrate assemblage. Certain invertebrate and plant fossils may be defined as significant by a project paleontologist, local paleontologist, specialists, or special interest groups, or by lead agencies or local governments.

As defined by the SVP (1995:26), significant fossiliferous deposits are defined as:

A rock unit or formation which contains significant nonrenewable paleontologic resources, here defined as comprising one or more identifiable vertebrate fossils, large or small, and any associated invertebrate and plant fossils, traces and other data that provide taphonomic, taxonomic, phylogenetic, ecologic, and stratigraphic information (ichnites and trace fossils generated by vertebrate animals, e.g., trackways, or nests and middens which provide datable material and climatic information). Paleontologic resources are considered to be older than recorded history and/or older than 5,000 years, BP [before present].

Based on the significance definitions of the SVP (1995), all identifiable vertebrate fossils are considered to have significant scientific value. This position is adhered to because vertebrate fossils are relatively uncommon, and only rarely will a fossil locality yield a statistically significant number of specimens of the same genus. Therefore, every vertebrate fossil found has the potential to provide significant new information on the taxon it represents, its paleoenvironment, and/or its distribution. Furthermore, all geologic units in which vertebrate fossils have previously been found are considered to have high sensitivity. Identifiable plant and invertebrate fossils are considered significant if found in association with vertebrate fossils or if defined as significant by project paleontologists, specialists, or local government agencies.

A geologic unit known to contain significant fossils is considered to be “sensitive” to adverse impacts if there is a high probability that earth-moving or ground-disturbing activities in that rock unit will either disturb or destroy fossil remains directly or indirectly. This definition of sensitivity differs fundamentally from that for archaeological resources as follows:

It is extremely important to distinguish between archaeological and paleontological (fossil) resource sites when defining the sensitivity of rock units. The boundaries of archaeological sites define the areal extent of the resource. Paleontologic sites, however, indicate that the containing sedimentary rock unit or formation is fossiliferous. The limits of the entire rock formation, both areal and stratigraphic, therefore define the scope of the paleontologic potential in each case. [SVP, 1995]

Many archaeological sites contain features that are visually detectable on the surface. In contrast, fossils are contained within surficial sediments or bedrock and are therefore not observable or detectable unless exposed by erosion or human activity. Monitoring by experienced paleontologists greatly increases the probability that fossils will be discovered during ground-disturbing activities and that, if these remains are significant, successful mitigation and salvage efforts may be undertaken to prevent adverse impacts to these resources.

RESOURCE ASSESSMENT SUMMARY

Paleontological sensitivity is defined as the potential for a geologic unit to produce scientifically significant fossils. This is determined by rock type, past history of the geologic unit in producing significant fossils, and fossil localities recorded from that unit. Paleontological sensitivity is derived from the known fossil data collected from the entire geologic unit, not just from a specific survey. In its “Standard Guidelines for the Assessment and Mitigation of Adverse Impacts to Nonrenewable Paleontologic Resources,” the SVP (1995:23) defines three categories of paleontological sensitivity (potential) for sedimentary rock units: high, low, and undetermined:

- **High Potential.** Rock units from which vertebrate or significant invertebrate fossils or suites of plant fossils have been recovered and are considered to have a high potential for containing significant nonrenewable fossiliferous resources. These units include, but are not limited to, sedimentary formations and some volcanic formations that contain significant nonrenewable paleontologic resources anywhere within their geographical extent and sedimentary rock units temporally or lithologically suitable for the preservation of fossils. Sensitivity comprises both (a) the potential for yielding abundant or significant vertebrate fossils or for yielding a few significant fossils, large or small, vertebrate, invertebrate, or botanical, and (b) the importance of recovered evidence for new and significant taxonomic, phylogenetic, ecologic, or stratigraphic data. Areas that contain potentially datable organic remains older than Recent, including deposits associated with nests or middens, and areas that may contain new vertebrate deposits, traces, or trackways are also classified as significant.
- **Low Potential.** Reports in the paleontological literature or field surveys by a qualified vertebrate paleontologist may allow determination that some areas or units have low potentials for yielding significant fossils. Such units will be poorly represented by specimens in institutional collections.
- **Undetermined Potential.** Specific areas underlain by sedimentary rock units for which little information is available are considered to have undetermined fossiliferous potentials.

It should be noted that highly metamorphosed rocks and granitic rock units do not generally yield fossils and therefore have low potential to yield significant nonrenewable fossiliferous resources.

In general terms, for geologic units with high potential, full-time monitoring typically is recommended during any project-related ground disturbance. For geologic units with low potential, protection or salvage efforts typically are not required. For geologic units with undetermined potential, field surveys by a qualified paleontologist are usually recommended to specifically determine the paleontologic potential of the rock units present within the study area.

PROJECT LOCATION AND DESCRIPTION

The AMSP is located in unincorporated San Bernardino County approximately 9 miles northwest of Hinkley, California (Figure 1). It would have a combined nominal electrical output of 250 megawatts (MW) from twin 125-MW power blocks. The power blocks would be joined at the transmission line interconnection substation to form one full-output transmission interconnection. The project interconnection is proposed to connect to the Southern California Edison (SCE)-owned Kramer-Coolwater 230-kV transmission line located adjacent to the southern border of the project. SCE would lead the permitting effort for the transmission improvements past the project-specific interconnection to the statewide system as a separate process. All project-related transmission facilities are within the project boundaries. Natural gas for the project's ancillary purposes would be supplied by a Southern California Gas Company-owned pipeline that runs to the project boundary.




Figure 1. Project Overview Map

The AMSP project includes approximately 31 miles of new fiber-optic cable to be installed between the proposed Lockhart Substation and the existing Tortilla Substation, located to the southeast in Barstow (See Figure 1). The fiber-optic cable would require the construction of approximately 55 new poles between the Lockhart Substation and Harper Lake Road. The new underground trench would be located within the disturbed road ROW of Harper Lake Road, on the east side of the road, before transitioning to the west side of the road. From this point, the underground cable would transition back to the overhead line via a riser to existing overhead transmission line poles that parallel Harper Lake Road for approximately 5 miles south. This method, stringing the cable on existing transmission line structures, would continue between the intersection of Harper Lake Road/SR-58 heading east, then south on Summerset Road, east on Community Road, and south on Lenwood and Sun Valley roads until intersecting with an existing 33-kV transmission line located approximately one-third mile south of Main Street. The cable would be strung on the existing transmission line structures (called the Poco 33-kV line) for approximately 4.7 miles, then would continue to be strung on existing transmission line structures south on I Street. Where the overhead line intersects Bonanza Road, the cable would be strung on existing transmission line structures heading east along Bonanza Road until intersecting with the existing SCE Kramer-Tortilla 115-kV transmission line.

Fiber-optic cable between the Lockhart Substation and Kramer Substation commences with trenching within the substation site to install the cable in an underground conduit approximately 1,000 feet long until it reaches the overhead poles for the proposed substation light and power lines. These overhead poles, approximately 30 in number, would be new poles proposed within the AMSP property between the substation and Lockhart Road to the north. The cable would then be strung along existing power and transmission line structures until it intersects with the existing Kramer Substation, where it would transition to an underground conduit.

Fiber-optic cable connecting the Kramer Substation to Victor Substation would commence at Kramer Substation by installing cable in both a new underground conduit and existing underground conduit. It would then transition to, and be strung on, the existing Kramer-Victor 115-kV transmission line for a majority of this alignment. There are areas where the cable would need to be installed underground where the 115-kV line crosses other transmission lines. One trench would be located just north of the Victor Substation (See Figure 1), where the cable would be installed in an underground trench underneath SR-18 and stretch 225 feet. Two other areas, farther north near U.S. Highway 395, consist of 500 linear feet each (See Figure 1). Trenching would also be located within the Roadway and Kramer Substation boundaries, within the disturbed footprint of those existing facilities (See Figure 1). In addition, approximately 30 new poles would be required in two main areas along this alignment, as shown in Figure 1.

For the purposes of this study, the “project area” includes proposed areas of ground disturbance where underground trenching for new cable installation and grading or excavations are anticipated during the installation of new poles.

PROJECT PERSONNEL

SWCA Paleontology Lead Jessica DeBusk managed this project and authored this technical report. Geographic Information Systems (GIS) Specialist Chad Flynn produced graphics. Technical Editor Elizabeth Slocum edited and formatted this report. Cara Corsetti, Qualified Paleontologist and SWCA Office Principal, provided quality review/quality assurance (QA/QC) review of this technical report.

METHODS

Due to the nature of the fossil record, paleontologists cannot know either the quality or the quantity of fossils present in a given geologic unit prior to natural erosion or human-caused exposure. Therefore, in the absence of surface fossils, it is necessary to assess the sensitivity of rock units based on their known potential to produce scientifically significant fossils elsewhere within the same geologic unit (both within and outside of the study area) or a unit representative of the same depositional environment.

MUSEUM RECORDS SEARCH

For this project, a museum records search was performed by the Department of Earth Sciences at the San Bernardino County Museum (SBCM). Museum collections records were searched for the purposes of determining whether there are any known fossil localities in or near the project site, identifying the geologic units present in the project area, and determining the paleontological sensitivity ratings of those geologic units to assess potential impacts to nonrenewable paleontological resources. Published and unpublished literature and geologic maps were reviewed, and mitigation measures specific to this project were developed in accordance with the SVP's professional standards and guidelines (1995).

Geologic units were assigned a paleontological sensitivity rating based on the museum records search and literature review. For the purpose of this study, geologic units and paleontological sensitivity are mapped for those areas where ground disturbance is proposed (See Figures 2 through 4).

GEOLOGY AND PALEONTOLOGY

GEOLOGIC SETTING

California is naturally divided into the following 12 geomorphic provinces, each distinguished from one another by having unique topographic features and geologic formations: (1) the Sierra Nevada, (2) the Klamath Mountains, (3) the Cascade Range, (4) the Modoc Plateau, (5) the Basin and Range, (6) the Mojave Desert, (7) the Colorado Desert, (8) the Peninsular Ranges, (9) the Transverse Ranges, (10) the Coast Ranges, (11) the Great Valley, and (12) the Offshore area. The AMSP, substation, interconnect and fiber-optic routes are located in the western region of the Mojave Desert geomorphic province. The Mojave Desert is bounded to the northwest by the Transverse Ranges and to the southwest by the Colorado Desert. The Sierra Nevada and the Basin and Ranges provinces establish the northern boundary and the Nevada state line and Colorado River establish the eastern boundary (Norris and Webb, 1976).

The Mojave Desert is an elevated alluvial plain located on a wedge-shaped fault block bounded by the San Andreas and Garlock fault zones to the southwest and north, respectively. The western Mojave Desert is characterized by three major rock groups. The first is the basement complex consisting of a pre-Tertiary granitoid batholith believed to be an extension of the Sierra Nevada batholith (Dibblee, 1967). The second is Tertiary-age sedimentary and volcanic rocks mostly of terrestrial origin and consisting of conglomerates, sandstones, shales, carbonates, tuffs and breccias, lava flows, and basaltic and rhyolitic plugs. The third major rock assemblage in the western Mojave Desert is composed of Quaternary alluvial, fluvial, and playa, or lakebed, deposits. Quaternary-age alluvial sediments, largely derived from the San Gabriel and Sierra Nevada mountains, were deposited either conformably or, more commonly, unconformably on top of Tertiary- and pre-Tertiary-age rocks. The depth of alluvial deposition ranges from a few feet to possibly several thousand feet in thickness. Both Quaternary and Tertiary-age deposits underlie the project area; these units are discussed in more detail below.

SITE-SPECIFIC GEOLOGY AND PALEONTOLOGY

The geology in the project area has been mapped by Bortugno and Spittler (1986) at a scale of 1:250,000 and Dibblee (2008a; 2008b) at a scale of 1:62,500. No larger-scale maps (1:24,000) were available for this analysis. Geologic mapping by Bortugno and Spittler (1986) and Dibblee (2008a; 2008b) indicate that the project area is underlain by the following geologic units, in approximate ascending stratigraphic order: (1) the Tropico Group of Miocene age (23 million years old [Ma] to 5.3 Ma, (2) older Quaternary alluvial deposits of Pleistocene age (1.8 Ma to 10,000 years before present [BP]), and (3) younger alluvium of Holocene age (10,000 years BP to Recent).

Tropico Group

The Tropico Group is made up of Tertiary age non-marine and volcanic rocks scattered throughout the western Mojave Desert, exposed mostly in the vicinities of Rosamond, Mojave, and Boron. The group has a maximum exposed thickness of 2,800 feet and is divided into several lithological units of local extent. In general, its lower part is composed of tuffaceous material of rhyolitic composition, and its upper part is composed of coarse stream-laid or fine lacustrine sediments (or both). The Tropico Group overlies the deeply eroded surface of pre-Tertiary granitic basement rocks and is unconformably overlain by Quaternary age alluvial sediments (Dibblee, 1958).

According to geologic mapping by Dibblee (2008a), the Project area traverses a small portion of a basalt unit within the lower part of the Tropico Group in the vicinity of Kramer Hills (See Figure 3). This unit, mapped as “Tb,” is composed of black non-vesicular massive olivine basalt occurring locally as flows or sills up to 300 feet in thickness. Most volcanic rocks do not have the potential to contain paleontological resources and are not generally suitable for the preservation of fossils due to their molten origin. Therefore, “Tb” is assigned a “low” sensitivity.




Figure 2. Geologic and Paleontological Sensitivity Map 1 of 3




Figure 3. Geologic and Paleontological Sensitivity Map 2 of 3




Figure 4. Geologic and Paleontological Sensitivity Map 3 of 3

Quaternary Older Alluvium

Quaternary older alluvial sediments of Pleistocene age (1.8 Ma to 10,000 years BP) occur both at the surface within portions of the project area (See Figure 4) and at depth (Dibblee, 2008a; 2008b). Older alluvium within the study area consists of weakly consolidated, moderately to poorly bedded gravel, sand, and silt light gray to buff in color. These deposits are locally dissected and in part indurated by white caliche (Dibblee, 2008a). Pleistocene-aged alluvium has proven to yield scientifically significant vertebrate fossils both within the region and throughout southern California. Sediments of similar or the same lithologic composition throughout the areas of Barstow and Lenwood to the east as well as Victorville to the south have also been proven to yield significant fossil localities; thus, this unit is determined to have a high potential for paleontological resources (Whistler, 1990; Scott, 2010).

Quaternary Younger Alluvium

The youngest geologic unit found within the project area is Quaternary alluvium of Holocene age to latest Pleistocene in age (Bortugno and Spittler; 1986; Dibblee, 2008a; 2008b). These sediments, making up the majority of the surficial deposits within the project area (See Figures 2 through 4), are composed of unconsolidated and poorly sorted stream, fan, and basin deposits ranging from clay to boulder in size (Bortugno and Spittler, 1986). Although the uppermost sediments of Holocene age may contain the remains of modern organisms, they are too young to contain significant paleontological resources. However, underlying Pleistocene-age sediments are considered to have a high paleontological sensitivity. Therefore, Quaternary younger alluvium within the project area is assigned a paleontological sensitivity ranging from low to high, increasing with age (i.e., depth).

Table 1. Geologic Units within the Project Area

Age	Geologic Unit	Map Abbreviation	Typical Fossil Types	Paleontological Resource Potential (Sensitivity)
Holocene	Younger surficial alluvium	Qa	None	Low to high (increases with depth)
Pleistocene	Older alluvium	Qoa	Vertebrates	High
Miocene	Tropico Group (basalt)	Tb	None	Low

ANALYSIS AND RESULTS

MUSEUM RECORDS SEARCH

A review of the Regional Paleontologic Locality Inventory (RPLI) maintained by the SBCM revealed that 18 vertebrate localities have been previously recorded and collected during a prior mitigation project within the project area. These recorded localities are listed in Table 2 below and shown on Figures 6 and 7 in Confidential Appendix A. These localities yielded specimens of small terrestrial vertebrates such as pocket mouse, jackrabbit, deer mouse, pocket gopher, kangaroo rat, squirrel, cottontail rabbit, and packrat as well as bird, reptile, and a few mostly indeterminate large mammal specimens (Table 2). Eleven of the localities reported a depth of discovery ranging from three to 14 feet below the ground surface; four localities were reportedly surficial localities, and seven localities did not report depth of discovery. All specimens were of extant species, and no time-diagnostic taxa were identified from any of these localities;

therefore, the age of the material cannot be conclusively determined. The SVP (1995) defines paleontological resources as “older than recorded history and/or older than 5,000 years BP.” Since all identified taxa from these localities are also present in the region in modern times, their presumed age of greater than 5,000 years BP cannot be verified (Scott, 2010).

Table 2. Previously Recorded Fossil Localities within Project Area and Vicinity

Geological Formation	Museum Locality Number	Taxon	Common Name
Quaternary alluvium	SBCM 1.115.1	Mammalia (large)	Mammal
	SBCM 1.115.2	Mammalia (large)	Mammal
	SBCM 1.115.3	?Artiodactyla	Even-toed ungulate
	SBCM 1.115.4	Mammalia (large)	Mammal
	SBCM 1.115.5	Mammalia (small)	Mammal
	SBCM 1.115.6	<i>Lepus sp.</i>	Jackrabbit
	SBCM 1.115.7	<i>Lepus sp.</i>	Jackrabbit
		Camelidae	Camel
	SBCM 1.115.11	<i>Thomomys sp.</i>	Pocket gopher
	SBCM 1.155.422	Rodentia	Rodent
	SBCM 1.155.423	Mammalia (small)	Mammal
		Vertebrata (large)	Vertebrate
	SBCM 1.155.424	<i>Perognathus sp.</i>	Pocket mouse
		<i>Dipodomys sp.</i>	Kangaroo rat
		<i>Peromyscus sp.</i>	Deer mouse
		? <i>Neotoma sp.</i>	Packrat
		Mammalia (large)	Mammal
		Mammalia (small)	Mammal
	SBCM 1.155.425 SBCM 1.155.426 SBCM 1.155.427	Mammalia (small)	Mammal
		<i>Dipodomys sp.</i>	Kangaroo rat
		Vertebrata (small)	Vertebrate
		<i>Phrynosoma sp.</i>	Horned lizard
		?Iguanidae	Lizard
		Lacertilia	Lizard
		Lampropeltinae	Snake
		<i>Crotalus sp.</i>	Rattlesnake
		<i>Sylvilagus sp.</i>	Cottontail rabbit
		?Sciuridae	Squirrel
		<i>Thomomys sp.</i>	Pocket gopher
		<i>Perognathus sp.</i>	Pocket mouse
		<i>Dipodomys sp.</i>	Kangaroo rat
		Mammalia (small)	Mammal
	SBCM 1.155.428	Colubridae	Snake
		Lacertilia	Lizard
		<i>Crotalus sp.</i>	Rattlesnake
		Aves	Bird
		<i>Lepus sp.</i>	Jackrabbit

Table 2. Previously Recorded Fossil Localities within Project Area and Vicinity

Geological Formation	Museum Locality Number	Taxon	Common Name
		Sciuridae (small)	Squirrel
		<i>Thomomys sp.</i>	Pocket gopher
		<i>Perognathus sp.</i>	Pocket mouse
		<i>Dipodomys sp.</i>	Kangaroo rat
		? <i>Peromyscus sp.</i>	Deer mouse
		<i>Neotoma sp.</i>	Packrat
		Mammalia (small)	Mammal
	SBCM 1.155.474	Vertebrata (small)	Vertebrate
	SBCM 1.155.475	Vertebrata (small)	Vertebrate
	SBCM 1.155.476	Ophidia	Reptile
		<i>Phrynosoma sp.</i>	Horned lizard
		<i>Lepus sp.</i>	Jackrabbit
		<i>Thomomys sp.</i>	Pocket gopher
		<i>Dipodomys sp.</i>	Kangaroo rat
		Mammalia (small)	Mammal

CONCLUSIONS

The destruction of fossils as a result of human-caused ground disturbance has a significant cumulative impact, as it makes biological records of ancient life permanently unavailable for study by scientists. Implementation of proper mitigation measures can, however, reduce the impacts to the paleontological resources to below the level of significance. Various activities related to the installation of new fiber optic cable may require substantial trenching, grading, and excavating for pole foundations, as well as borehole drilling for pole installation. Surficial disturbance may also occur within equipment staging areas. Any ground disturbances in areas considered to be paleontologically sensitive may have an adverse impact on paleontological resources unless proper mitigation measures are implemented.

RECOMMENDED MITIGATION MEASURES

The following are mitigation measures that have been developed to reduce adverse impacts on paleontological resources to a less than significant level. They have been successfully implemented for surface-disturbing projects in California and throughout the western United States.

PRECONSTRUCTION ASSESSMENT, SURVEY, AND EXCAVATION

Survey

Prior to development of the project, a comprehensive pedestrian survey should be conducted by a qualified paleontologist in all areas underlain by geologic units determined to have a high paleontological sensitivity (See Figures 2 through 4). Based on the results of the survey, additional paleontological mitigation (construction monitoring) may be recommended. If the paleontological sensitivity of rock formations, members, individual strata and/or lithology types within the project area is determined to be

more than or less than anticipated as a result of the survey, the paleontological sensitivity of portions of the project area may be adjusted accordingly.

The field survey should consist of an inspection of all potentially fossiliferous rock outcrops and exposures of surficial sediments within the project area. All fossil occurrences, whether significant or not, should be recorded. Recordation should include the types of fossils discovered, geographic coordinates, stratigraphic provenance, photographs for locality relocation, and the lithologies of the fossil-bearing strata. If possible, all significant fossils should be collected during the survey, depending on the number present and their size. This is because it is often difficult to relocate small fossils, and erosion and weathering are adverse impacts on fossils which can be prevented if the fossils are collected and removed from the site. The results of the pre-construction survey will be taken into account during construction monitoring in order to more effectively salvage the resources. For example, a particularly fossiliferous stratum observed during the survey should be more carefully monitored and sampled during construction excavations.

The following are typical recommendations that may result from an initial paleontological field survey:

Sampling

Scientifically significant microfossils (vertebrate, invertebrate, plant or trace fossils) may be identified in rock matrix during a field survey, or, if they are known to occur elsewhere in the same geologic unit or type of deposit in the general area, a determination of their presence or absence may require the use of test sampling of rock matrix for screen-washing in a paleontological laboratory, even if microfossils are not visible in the field. The fossils found, if any, would then be inspected and evaluated in order to determine their significance and make additional mitigation recommendations, if any. Mitigation would include collection of additional matrix for screen-washing.

Salvage

If medium- or large-sized fossils are discovered within a given project site, and they are determined to be scientifically significant, they should be salvaged. Fossil salvages typically involve the systematic excavation of fossil remains as determined on a case-by-case basis, and they should be designed in such a way as to prevent delays to project schedules while properly collecting the fossil and associated data.

Avoidance

If the cost of salvage or other mitigation options are determined to be too high, or permanent damage to the resource caused by surface disturbance is considered to be unavoidable, it may be necessary to “avoid” or “reroute” the locality in order to prevent adverse impacts on the resource. Avoidance should also be considered if a known fossil locality contains critical scientific information and should be left undisturbed for subsequent scientific evaluation.

Construction Monitoring

Paleontological monitoring work should be performed by a qualified paleontological monitor under the supervision of a qualified paleontologist. Paleontological monitoring would include inspection of exposed rock units and microscopic examination of matrix to determine if fossils are present. This work would take place during surface-disturbing activities such as excavations for the construction of roads, buildings, and other associated facilities or infrastructure. Depending upon the paleontological sensitivity of the

area/geologic units, and the types and significance of potential fossils that could be present in sub-surface sedimentary deposits, monitoring would be scheduled to take place continuously or to consist of spot-checks of construction excavations. Paleontological monitors would follow earth-moving equipment and examine excavated sediments and excavation sidewalls for evidence of significant paleontological resources. The monitors would have authority to temporarily divert grading away from exposed fossils in order to professionally and efficiently recover the fossil specimens and collect associated data. All efforts to avoid delays to project schedules would be made.

If any subsurface bones or other potential fossils were found by construction personnel during construction when a paleontological monitor is not present, work in the immediate area would cease immediately, and the qualified paleontologist would be contacted to evaluate the significance of the find. Once salvage or other mitigation measures (including sampling) was complete, the qualified paleontologist would notify the construction supervisor that paleontological clearance had been granted.

Paleontological monitors should be equipped with the necessary tools for the rapid removal of fossils and retrieval of associated data in order to prevent construction delays. This equipment would include handheld global positioning system (GPS) receivers, digital cameras, cell phones, laptop computers, as well as toolkits containing specimen containers and matrix sampling bags, field labels, field tools (awls, hammers, chisels, shovels, etc.), and plaster kits. The collected fossils would be transported to a paleontological laboratory for processing.

Fossil Preparation and Curation

In the laboratory, all fossils would be prepared, identified, inventoried, and a determination of significance made. Specimen preparation and stabilization methods would be recorded for use by the paleontological repository. All fossil specimens would then be transferred to a public museum or other approved paleontological repository accompanied by a copy of the final paleontological monitoring report and all data in hard and electronic copy. The cost of curation, maintenance, and permanent storage of fossil specimens is generally assessed by the repository.

Reporting

The final paleontological monitoring report shall be prepared to include, but not be limited to, a discussion of the results of the mitigation-monitoring plan, an evaluation and analysis of the fossils collected (including an assessment of their significance, age, and geologic context), an itemized inventory of fossils collected, a confidential appendix of locality and specimen data with locality maps and photographs, an appendix of curation agreements and other appropriate communications, and a copy of the project-specific paleontological monitoring and mitigation plan.

REFERENCES

- Bortugno, E.J., and Spittler, T.E., 1986, Geologic Map of the San Bernardino Quadrangle, California: California Division of Mines and Geology Regional Map Series, scale: 1:250,000.
- County of San Bernardino, 2007, County of San Bernardino General Plan: Adopted March 13, 2007.
- DeBusk, J., and C. Corsetti, 2009. Paleontological Resources Assessment for the Mojave Solar Project, San Bernardino County, California. Prepared for Abengoa Solar, Incorporated. On file at SWCA Environmental Consultants Pasadena Office.
- Dibblee, T.W., Jr., 1958, Tertiary Stratigraphic Units of Western Mojave Desert, California. Bulletin of the American Association of Petroleum Geologists Vol. 42, No. 1. PP. 135-144.
- Dibblee, T.W., Jr., 1967, Areal geology of the western Mojave Desert, California: U.S. Geological Survey Professional Paper 522.
- Dibblee, T.W., Jr., 2008a, Geologic Map of the Kramer and Hawes 15 Minute Quadrangles, Kern, San Bernardino, and Los Angeles Counties, California: Dibblee Geological Foundation Map DF-385, scale 1:62,500
- Dibblee, T.W., Jr., 2008b, Geologic Map of the Shadow Mountains and Victorville 15 Minute Quadrangles, San Bernardino and Los Angeles Counties, California: Dibblee Geological Foundation Map DF-387, Scale: 1:62,500.
- Murphey, P.C., and Daitch, D., 2007, Paleontological overview of oil shale and tar sands areas in Colorado, Utah and Wyoming: U.S. Department of Energy, Argonne National Laboratory Report Prepared for the U.S. Department of Interior Bureau of Land Management, 468 p. and 6 maps, scale 1:500,000.
- Norris, R.M., and R.W. Webb, 1976, Geology of California, second edition: John Wiley & Sons, New York, p. 277–300.
- Society of Vertebrate Paleontology (SVP), 1995, Assessment and Mitigation of Adverse Impacts to Nonrenewable Paleontologic Resources: Standard Guidelines: Society of Vertebrate Paleontology News Bulletin. v. 163, p. 22–27.
- Norris, R.M., and R.W. Webb, 1976, *Geology of California*. 2d ed. New York: John Wiley & Sons, p. 277–300.
- Scott, E., 2010, Unpublished paleontological specimen and locality data: San Bernardino County Museum, Redlands, California, 6p.
- Whistler, D.P., 1990, A Late Pleistocene (Rancholabrean) fossil assemblage from the northwestern Mojave Desert, California: San Bernardino County Museum Association Quarterly, v. 37, p. 1–17.

**Confidential APPENDIX A:
Paleontological Localities**

On file with
Department of
Energy

APPENDIX M

BIOLOGICAL RESOURCES

APPENDIX M

DESCRIPTION OF VEGETATION COMMUNITIES

AMSP, Lockhart Substation and Interconnection Study Area

Desert Saltbush Scrub. Desert saltbush scrub is dominated by four-wing saltbush (*Atriplex canescens*), spinescale (*Atriplex spinifera*), and allscale (*Atriplex polycarpa*) shrubs up to 6 feet in height. Other shrubs found growing within desert saltbush scrub included winter fat (*Krashennikovia lanata*), horsebrush (*Tetradymia* sp.), and creosote bush (*Larrea tridentata*).

Disturbed – Desert Saltbush Scrub. Disturbed desert saltbush scrub occurs mainly at the edges or adjacent to abandoned agricultural fields. It was mapped in areas that have been altered by previous human activity including grading, repeated clearing, and vehicular damage, which over time has degraded “naturally” occurring desert saltbush scrub resulting in a lower shrub density and an increased abundance of nonnative plant species. Disturbed desert saltbush scrub is mainly dominated by allscale and spinescale with a dominant understory of nonnative herbaceous plants.

Mojave Creosote Bush Scrub. Mojave creosote bush scrub occurs near the southern portion of the AMSP/ Lockhart Substation site. Mojave creosote bush scrub consists of widely spaced shrubs from 2 to 6 feet in height and dominated by creosote bush and white bursage (*Ambrosia dumosa*). While dominated by shrubs, this vegetation community also was found to have a relatively diverse herbaceous layer that included such native annual species as dwarf cottonrose (*Filago depressa*), Fremont’s phacelia (*Phacelia fremontii*), and desert dandelion (*Malacothrix glabrata*).

Desert Sink Scrub. Desert sink scrub is characterized as dominated by chenopod-type plants that grow on poorly drained soils with high alkalinity and sometimes with a layer of salt crust at the soil surface. Dominant plants for this vegetation community within the Project study area include bush seepweed, alkali heath (*Frankenia salina*), red molly (*Kochia californica*), and five-hook bassia. This vegetation community occurred between, or intermixed with, alkali marsh and desert saltbush scrub.

Tamarisk Scrub. This community is dominated by tamarisk (*Tamarix ramosissima*), a nonnative shrub to small tree from Central Asia. The plant was originally introduced for erosion control and windbreak purposes. Tamarisk is deep rooted and can be found along streams and lake shores throughout California. Tamarisk is highly invasive and is associated with dramatic changes in groundwater availability. This species is also capable

of forming monotypic stands that outcompete native species for water. Tamarisk scrub is restricted to a few areas within the Project study area that are mainly situated near the western margin of Harper Dry Lake. Tamarisk was also detected along roadsides adjacent to abandoned agricultural fields, and as windbreaks surrounding some of the residential developments.

Mojave Desert Wash Scrub. Mojave Desert wash scrub consists mostly of sandy, braided, shallow washes dominated by allscale and creosote bush. In areas where a more defined channel was present, shrub species included Anderson's boxthorn (*Lycium andersonii*), peachthorn (*Lycium cooperi*), cheesebush (*Ambrosia [Hymenoclea] salsola*), and white bursage. Native annuals included whitestem blazingstar (*Mentzelia albicaulis*), Mojave pincushion (*Chaenactis xantiana*), easterbonnets (*Eriophyllum wallacei*), whitemargin sandmat (*Chamaesyce albomarginata*), and Mojave suncups (*Cammissonia campestris*).

Dry Lake. Dry lake was determined to be bare saline soils devoid of vegetation and occurs in the northeastern portion of the AMSP/ Lockhart Substation site; however, the Project has been designed to avoid impacts to the dry lakebed.

Fallow Agricultural - Disturbed Desert Saltbush Scrub. The fallow agricultural - disturbed desert saltbush scrub regrowth community occurs in areas previously used for agricultural purposes but that have now become occupied with several *Atriplex* species. The dominant species is allscale, a colonizer that readily occupies abandoned agricultural lands in the Mojave Desert. The degree of regrowth appears to correspond to variation in soil texture and moisture retention. Other plants that were detected in this vegetation community included shadscale (*Atriplex confertiflora*), Russian thistle (*Salsola tragus*), annual bursage (*Ambrosia acanthicarpa*), and salt heliotrope (*Heliotropium curassavicum*).

Fallow Agricultural-Ruderal. This land cover type represents the largest category that occurs within the AMSP/Lockhart Substation site. The fallow agricultural-ruderal vegetation community occurs on land formerly used for agricultural purposes and is dominated by ruderal nonnative plants. The dominant plant species are Russian thistle, Saharan mustard (*Brassica tournefortii*), and split grass (*Schismus arabicus*).

Active Agricultural. The active agricultural area is currently farmed with alfalfa (*Medicago sativa*) and is being irrigated with a center pivot system.

Disturbed. Disturbed habitat is land that has been altered by previous human activity including grading, repeated clearing, and vehicular damage. Disturbed land is typically characterized by more than 50 percent bare ground and an absence of remnant native vegetation. Disturbed habitat is mostly unvegetated; when vegetation is present, it mostly consists of Saharan mustard.

Developed. The areas mapped as developed include paved roads, dirt roads, and residential areas.

Evaporation Ponds. Two evaporation ponds are located in the northwestern portion of the Harper Dry Lake Solar Electric Generating Stations (SEGS), northwest and outside of the boundaries of the Project study area and within the one-mile buffer zone. The ponds are mentioned here for comparison to the proposed new ponds.

Telecommunication System Study Area

White Bursage Scrub. White bursage scrub consists of white bursage with creosote bush in a lower proportion. The shrub canopy is two tiered with a few creosote shrubs in the upper tier and white bursage in the lower tier. This white bursage scrub vegetation community was described as Mojave creosote bush scrub-*Ambrosia dumosa* dominant and Mojave Creosote Bush –*Ambrosia dumosa* – *Atriplex* Scrub in the preliminary analysis (AECOM 2010a).

Joshua Tree Woodlands. Joshua tree woodlands consist of Joshua trees (*Yucca brevifolia*) interspersed with *Atriplex* species, white bursage, and creosote bush.

Table M-1. Special Status Plant Species and Probability of Occurrence in the Project study area

Common Name <i>Scientific Name</i>	Sensitivity Status ¹	Habitat Requirements (CNPS 2008)	Blooming Period	Probability of Occurrence
Chaparral sand-verbena <i>Abronia villosa</i> var. <i>aurita</i>	CNPS List 1B.1	Known to occur in chaparral, coastal scrub, and desert dunes or sandy areas.	Annual herb Blooms January through September	Low potential of occurrence within Project study area. Chaparral sand-verbena is known to occur over 5 miles from the Project study area near the town of Hinkley, California (CDFG 2008). No populations were observed in the Project study area during 2008 botanical surveys.
Desert cymopterus <i>Cymopterus deserticola</i>	CNPS List 1B.2	Found in Joshua tree woodland and Mojave desert scrub.	Perennial herb Blooms March through May	Detected in the vicinity of the Project study area. One individual was detected in a small wash, south of Santa Fe Avenue, and approximately 4,350 feet southwest of the southernmost section of the AMSP site.
Recurved larkspur <i>Delphinium recurvatum</i>	CNPS List 1B.2	Known to occur in chenopod scrub, cismontane woodland, and valley/foothill grassland.	Perennial herb Blooms March through June	Low potential of occurrence within Project study area. Recurved larkspur is not listed as occurring near the Project study area using a nine-quad search centered on the Lockhart quad (CDFG 2008). The closest occurrence of recurved larkspur (recorded in 1952) is approximately 20 miles west of the Project study area, near the northeast corner of Edwards Air Force Base and near State Route 58. No populations were observed in the Project study area during 2008 botanical surveys.
Barstow woolly sunflower <i>Eriophyllum mohavense</i>	CNPS List 1B.2	Creosote bush scrub, desert playas, and desert saltbush scrub.	Annual herb Blooms March through April	Moderate to high potential of occurrence within Project study area. Barstow woolly sunflower is known from a population just north of Harper Dry Lake (CDFG 2008). No populations were observed in the Project study area during 2008 botanical surveys.

Common Name <i>Scientific Name</i>	Sensitivity Status ¹	Habitat Requirements (CNPS 2008)	Blooming Period	Probability of Occurrence
Sagebrush loeflingia <i>Loeflingia squarrosa</i> var. <i>artemisiarum</i>	CNPS List 2.2	Desert dunes, great basin scrub, and sonoran desert scrub.	Annual herb Blooms April through May	Low potential of occurrence within Project study area. Sagebrush loeflingia is not listed as occurring near the Project study area using a nine-quadrant search centered on the Lockhart quad (CDFG 2008). No populations were observed in the Project study area during 2008 botanical surveys.
Mojave monkeyflower <i>Mimulus mohavensis</i>	CNPS List 1B.2	Joshua tree woodland and Mojave desert scrub.	Annual herb Blooms April through June	Low potential of occurrence within Project study area. Mojave monkeyflower is not listed as occurring near the Project study area using a nine-quadrant search centered on the Lockhart quad (CDFG 2008). No populations were observed in the Project study area during 2008 botanical surveys.
Utah glasswort <i>Salicornia [Sarcocornia] utahensis</i>	CNPS List 2.2	Known to occur along alkali playas and marshes.	Perennial succulent Blooms August through September	Moderate potential of occurrence within the Project study area. According to information in the CNDDDB, this species was previously detected near the Rancho Percebu Duck Club Pond, west of Harper Dry Lake (CDFG 2008). A pickleweed species was found growing in the proximity of alkali marsh outside of the Project study area, but based on rigorous field inspection during the appropriate blooming period, it was determined that the species was annual pickleweed.

¹ Sensitivity Status Key.

California Native Plant Society (CNPS).

List 1B.1- Plants rare, threatened, or endangered in California and elsewhere; seriously endangered in California.

List 1B.2 - Plants rare, threatened, or endangered in California and elsewhere; fairly endangered in California.

List 2.2 - Plants rare, threatened, or endangered in California, but more common elsewhere; fairly endangered in California.

Table M-2. Special Status Wildlife Species and Probability of Occurrence in the Project study area

Common Name <i>Scientific Name</i>	Sensitivity Status ¹	Habitat Requirements	Probability of Occurrence
Reptiles			
<i>Testudines</i> (Turtles)			
Desert tortoise (DT) <i>Gopherus agassizii</i>	ESA: Threatened CESA: Threatened	Various desert scrubs and desert washes up to about 5,000 feet, but not including large, unvegetated playas.	DT individuals were not detected during 2009 surveys; however, in 2008, 35 DTs were encountered in the within or near the Project study area, with six observed on Zone of Influence (ZOI) transects for a total of 41 DT observations. No DTs were documented within the AMSP site during 2007 or 2008 surveys. One female DT was observed twice near and within one of the ranches located in the AMSP site during reconnaissance surveys in 2006 (EREMICO 2006); however, this DT may have been preyed upon by dogs residing at the home as it was not seen during 2007 or 2008 surveys.
Birds			
<i>Pelecaniformes</i> (Tropicbirds, Pelicans, and Relatives)			
American white pelican <i>Pelecanus erythrorhynchos</i>	CDFG: Species of Special Concern	Breeds in northeastern California, winters throughout central and southern California. Rivers, lakes, estuaries, bays, marshes, nests usually in brackish or freshwater lake islands.	Detected. Remains of this species were found in August 2007, north of the AMSP site within the one-mile buffer. The carcass was scavenged.
<i>Falconiformes</i> (Vultures, Hawks, and Falcons)			
Swainson's hawk <i>Buteo swainsoni</i>	CESA: Threatened	Migrant that breeds in North America and winters in South America. Forages in open grasslands, agricultural areas, sparse shrublands, and small open woodlands. Nests in scattered trees within grasslands, shrublands, or agricultural landscapes.	Detected. One individual of this species was observed perched within the AMSP site near the southern boundary in June 2007. Two other individuals were observed soaring above the 1-mile buffer in August 2007.
Northern harrier <i>Circus cyaneus</i>	CDFG: Species of Special Concern	Occurs in grasslands and agricultural fields during migration and in winter.	Detected. Two individuals of this species were observed within the 1-mile buffer, one in May 2007, and one in August 2007. This species was also detected during 2006 reconnaissance surveys (EREMICO 2006; EDAW 2006).

Common Name <i>Scientific Name</i>	Sensitivity Status ¹	Habitat Requirements	Probability of Occurrence
American peregrine falcon <i>Falco peregrinus anatum</i>	CESA: Endangered CDFG: Fully Protected	Open habitats from tundra, moorlands, steppe, and seacoasts to mountains, and open forested regions, especially where there are suitable nesting cliffs.	Detected. One individual of this species was observed within the AMSP site perched north of the active agricultural field in August 2007. This individual was likely a transient or at most may use the area in the vicinity of the Project study area as a peripheral and occasional part of its home range.
<i>Charadriiformes</i> (Shorebirds, Gulls, and Relatives)			
Western snowy plover <i>Charadrius alexandrinus nivosus</i> *Federal listing applies only to the Pacific coastal population.	CDFG: Species of Special Concern (nesting)	Sandy beaches, dunes, and salt flats. Outside the breeding season they are more widespread.	Low potential for this species to occur. This bird was reported as occurring on the southwestern edge of Harper Dry Lake in 1978, with an estimated count of 94 birds. Most individuals appeared to be displaying nesting behavior; one nest found with three eggs. Since that time, the marsh area has become degraded due to loss of artificial water inputs from agricultural operations; therefore, habitat for this species is not present, and it is not expected that this species would utilize the Project study area as habitat.
<i>Strigiformes</i> (Owls)			
Short-eared owl <i>Asio flammeus</i>	CDFG: Species of Special Concern	Nests in well-vegetated open areas including grasslands, grain fields, riparian edges, and marshes. Many populations of this species are migratory.	High potential for this species to occur. This species was detected within the Project study area during a reconnaissance survey conducted in 2006 (EREMICO 2006). Suitable nesting habitat for this species occurs in the active agricultural field.
Western burrowing owl (WBO) <i>Athene cunicularia</i>	CDFG: Species of Special Concern	Found mainly in grassland and open scrub from the seashore to foothills. Strongly associated with ground squirrel burrows.	Detected. In 2008, one WBO was observed within the AMSP site. Also, one owl pellet was observed in the northwestern corner of the AMSP site in 2008. In 2007, a pair of WBOs was observed; however, they were not observed during 2008 surveys. An unchained domestic dog was observed within this area, so the loss of the pair may have been due to dog predation, or the WBO may have moved. Four WBOs were detected during a reconnaissance survey conducted within the AMSP site in 2006 (EREMICO 2006).
<i>Passeriformes</i> (Perching Birds)			

Common Name Scientific Name	Sensitivity Status ¹	Habitat Requirements	Probability of Occurrence
Yellow warbler <i>Dendroica petechia</i>	CDFG: Species of Special Concern	Breeds in mature riparian woodlands that consist of cottonwood, willow, alder, and ash trees.	Detected. This species was observed within the AMSP site during May 2007 surveys. Suitable breeding habitat for this species does not occur within the AMSP site or the 1-mile buffer; therefore, this individual was likely a migrant and was not mapped.
Willow flycatcher <i>Empidonax traillii</i>	ESA: Endangered (only <i>E. t. extimus</i> is federally listed) CESA: Endangered	Riparian woodlands with current or evidence of recent water flow and scouring. Riparian corridors must be at least 33 feet wide, closed canopy, relatively dense understory, and open mid-story.	Detected. One individual of this species was observed using a small stand of ornamental trees within the AMSP site near the southern boundary in June 2007. Suitable breeding habitat for this species does not occur within the Project study area or the 1-mile buffer; therefore, this individual was likely a migrant.
Loggerhead shrike <i>Lanius ludovicianus</i>	CDFG: Species of Special Concern	Occurs in semiopen country with utility posts, wires, and trees to perch on.	Detected. Suitable habitat for loggerhead shrike occurs throughout the AMSP site. Loggerhead shrikes were observed in the AMSP site during 2007 and 2009. This species was also detected during 2006 reconnaissance surveys (EREMICO 2006; EDAW 2006).
Mammals			
Mohave ground squirrel (MGS) <i>Spermophilus mohavensis</i>	CESA: Threatened	Mojave desert scrub, alkali scrub, and Joshua tree woodland between 1,800 and 5,000 feet. Sandy to gravelly soils.	Detected. In 2007, one MGS was trapped (one adult female; age approx. 1 year) within the AMSP site at the edge of an active alfalfa field in the northeast quarter of Section 32 during a reconnaissance survey (EREMICO 2006).
American badger <i>Taxidea taxus</i>	CDFG: Species of Special Concern	Coastal sage scrub, mixed chaparral, grassland, oak woodland, chamise chaparral, mixed conifer, pinyon-juniper, desert scrub, desert wash, montane meadow, open areas, and sandy soils.	High potential for this species to occur. A badger den was detected within the AMSP site during a 2006 reconnaissance survey (EREMICO 2006).

¹ Sensitivity Status Key.

Federal Endangered Species Act (ESA).

State California Endangered Species Act (CESA).

California Department of Fish and Game (CDFG).

Special Status Species Survey Results, AMSP/Lockhart Substation Study Area

Desert Tortoise. Results of DT reconnaissance and focused protocol surveys for the AMSP indicated that very few DTs utilized the site over a 4-year period. In 2006, the only DT observed within the Project study area was detected near an existing ranch property and was thought to be a pet of the ranch owner (pers. comm., William Clark, 2009). No other DTs were documented within the site during subsequent focused protocol-level surveys.

Another DT observation occurred in 2006, approximately 700 feet south outside of the Project study area boundary (south of the Beta site and coincidentally, near an active alfalfa field) (EDAW 2006). In addition to the two DT observations in 2006, a DT was also observed approximately 500 feet southeast of the Project study area boundary in 2008. These three DTs were the only individuals observed in proximity to the Project study area.

The remainder of DTs observed during Project surveys were observed to the west and east and relatively distant from the Project study area. For example, in 2008, the nearest DT observation occurred over 2,250 feet from the Project study area boundary. West of the Project study area boundary, the nearest observation of DT in 2008 was over 2,300 feet away.

In 2008, DT surveys resulted in observation of 35 DTs, plus six within the Zone of Influence (ZOI) transects, totaling 41 DT observations in 2008. Of the observed DTs, 33 were adults, six were subadults, and 2 were juveniles. DT sign observed within the Project study area includes five DT bone groups. In 2007, only one DT was documented during surveys, within the 1-mile CEC buffer south of the Project study area.

Other DT sign detected within the Project study area (burrows, scat, etc.) consisted mainly of DT carcasses. Specific DT sign locations and descriptions are provided in appendices of the AMSP AFC.

Swainson's Hawk. Suitable nesting and foraging habitat for SWHA occurs within the site in the form of large ornamental trees at occupied and abandoned residences and open active and fallow agricultural fields. A single SWHA was observed perched on a small shrub within the site on June 20, 2007, during a raptor survey, and a pair of SWHAs was observed soaring over the site on August 13, 2007, during a WBO survey. At least two large, empty stick nests were also found within the 1-mile buffer; however, no birds were seen using these nests, and the bird species using these nests could not be determined.

American Peregrine Falcon. One American peregrine falcon, likely a transient, was detected within the Project study area perched north of the active agricultural field on August 14, 2007, during WBO surveys.

Willow Flycatcher. A willow flycatcher was observed within the Project study area on June 12, 2007, during the spring migratory period for a northern subspecies of willow flycatcher (*E. traillii brewsteri*) that is known to migrate through this area. No suitable willow flycatcher breeding habitat occurs within the Project study area; therefore, this individual was likely a transient. Based on this lack of suitable

habitat, the willow flycatcher is not expected to remain or breed within the site or the Project study area.

Mohave Ground Squirrel. In consultation with resource agencies, it was determined that surveys for MGS were not required in 2009. No MGS were detected during habitat assessment activities in 2008. During 2007 surveys, one MGS was captured within the Project study area at the edge of an active alfalfa field in the northeast quarter of Section 32 (EREMICO 2007). No MGS were captured during trapping efforts in 2006 (EREMICO 2006). The AMSP/Lockhart Substation area is surrounded by the MGS Conservation Area as designated in the West Mojave Plan (BLM 2005). However, all of the area lies outside of the MGS Conservation Area.

Species of Special Concern Detected within AMSP/Lockhart Substation site or within one-mile

American White Pelican. During 2007 surveys, remains of this species were found north of the Project study area and within the 1-mile buffer. No suitable American white pelican breeding habitat occurs within the Project study area; therefore, this individual was likely a transient. Based on this lack of suitable habitat, the American white pelican is not expected to remain or breed within the site or the Project study area.

Northern Harrier. Harriers were detected twice in the 1-mile buffer north of the AMSP site: May 30, 2007, during DT surveys and August 22, 2007, during WBO surveys. This species was also detected within the site during 2006 reconnaissance surveys (EREMICO 2006).

Western Snowy Plover. The western snowy plover was reported to occur on the southwestern edge of Harper Dry Lake in 1978, with an estimated count of 94 birds (CDFG 2008). Most individuals seemed to be displaying nesting behavior; one nest was found with three eggs. Since that time, the marsh area has degraded and lost all structure and function; therefore, habitat for this species is not present, and it is not expected that this species would utilize the site or the Project study area. The interior population of western snowy plover is not considered a federally listed (threatened) species, although both the interior and coastal populations are CDFG SSC (CDFG 2009; USFWS 2009).

Western Burrowing Owl. During WBO surveys in 2008, a single WBO was observed within the AMSP/Lockhart Substation site. A pair of WBO that had been observed in the site during 2007 surveys was not observed in the 2008 surveys. A domestic dog was observed within this area, so the loss of the pair may have been due to dog predation, or the owls may have simply moved. During 2006 reconnaissance surveys, four WBO individuals were detected in the eastern section of the site.

Short-eared Owl. One short-eared owl was observed within the site during reconnaissance surveys in 2006; however, because this species tends to be active both day and night and no subsequent observations were recorded, it is likely that this individual was a transient and did not breed within the site.

Loggerhead Shrike. Suitable breeding and nonbreeding habitat for loggerhead shrike occurs throughout the Project study area. Loggerhead shrikes were observed during biological surveys of the vicinity of the

AMSP/Lockhart Substation site. Loggerhead shrikes were observed in the site during 2007 and 2009. This species was also detected during 2006 reconnaissance surveys (EREMICO 2006; EDAW 2006).

Yellow Warbler. This species was observed within the Project study area during the May 2007 surveys. Suitable breeding habitat for this species does not occur within the site or the 1-mile buffer; therefore, this individual was likely a migrant and was not mapped.

American Badger. The American badger was not detected during 2007/2008 surveys; however, one badger den was detected within the AMSP/Lockhart Substation site during reconnaissance surveys in 2006 (EREMICO 2006). The den was partially filled in and no recent badger sign was evident, indicating that the den likely had not been used recently.

Raptor Survey Results, AMSP/Lockhart Substation Site and Study Area

Cooper's Hawk. A Cooper's hawk was observed flying over the Project study area during DT surveys in 2008. It would not be expected to nest within the Project study area due to lack of suitable habitat. The species typically nests in relatively large trees, and in areas of dense patches of trees. Within the Project study area, there is a relatively sparse occurrence of trees within and adjacent to the Project; therefore, there is a low probability that the Cooper's hawk would nest on site.

Merlin. The merlin was documented within the fallow agricultural fields in the Project study area during both DT and WBO surveys in 2008.

Prairie Falcon. Prairie falcons were observed twice within the Project study area; a pair was observed soaring just west of the Project study area during DT surveys, and a single individual was observed hunting in the active agricultural area on two consecutive days (August 22 and 23, 2007) during WBO surveys. This species was also detected during reconnaissance surveys of the Project study area in 2006. Suitable prairie falcon nesting habitat occurs on the desert bluffs approximately 8 miles northeast of the Project study area but not within the Project study area.

APPENDIX M-1

DESERT TORTOISE CLEARANCE AND RELOCATION/TRANSLOCATION PLAN

MOJAVE SOLAR PROJECT

DESERT TORTOISE CLEARANCE AND RELOCATION/TRANSLOCATION PLAN

Submitted to:

**MOJAVE SOLAR, LLC
13911 Park Avenue, Suite 206
Victorville, California 92392**

Prepared by:

**Alice E. Karl, Ph.D.
P.O. Box 74006
Davis, California 95617**

January 2011

TABLE OF CONTENTS

1.0 Background	1
1.1 Project Description and Setting	1
1.2 Desert Tortoise Occurrence in the Project Area and Vicinity	2
2.0 Purpose and Structure of the Plan	3
3.0 Procedures Applicable to All Relocations and Translocations.....	4
3.1 Data Gathered on Relocated and Translocated Tortoises	4
3.2 Transmitters	5
3.3 Tortoise Transportation and Holding.....	5
3.4 Handling Temperatures.....	6
3.5 Authorized Handlers	6
4.0 Clearance and Relocation/Translocation During	
Specific Project Phases	7
4.1 Project Area Perimeter Fencing and Temporary Fencing.....	7
4.1.1 Project Area Fencing Schedule.....	8
4.1.2 Surveys and Monitoring during Fence Construction	8
4.1.3 Tortoise Relocation Methods during Fence Construction	9
4.1.4 Health Considerations	14
4.1.5 Post-Release Tortoise Monitoring	14
4.1.6 Nest Relocation.....	18
4.1.7 Monitoring Fence Integrity	18
4.2 Plant Sites and Associated Facilities inside the Project Area	18
4.2.1 Clearance Surveys.....	18
4.2.2 Translocation Release Areas and Designated Translocation Sites	20
4.2.3 Translocation Methods.....	22
4.2.4 Health Considerations	24
4.2.5 Post-Release Tortoise Monitoring	26
4.2.6 Nest Relocation.....	26
4.3 SCE Fiberoptics Construction, Construction Outside the Project	
Area, and Harper Lake Road	26
4.4 Operations Phase.....	27

4.5 Decommissioning and Reclamation Phase	28
4.6 Injured or Dead Tortoises	28
5.0 Reporting	28
6.0 Funding	29
7.0 Literature Cited	29
 Appendix 1. Sample Desert Tortoise Data Form.....	 33

List of Figures

Figure 1.	Location of the Mojave Solar Project	36
Figure 2.	Mojave Solar Project Vegetation Cover and Special Management Areas	37
Figure 3.	Desert Tortoise Sign Observed during Surveys.....	38
Figure 4.	Relocation Sites and Proposed Surveys for Diseased Resident Tortoises.....	39
Figure 5.	Translocation Sites and Proposed Surveys for Diseased Resident Tortoises.....	40

List of Tables

Table 1.	Alternatives for Relocating Tortoises Found during Periods of Ambient Temperatures Outside the USFWS (2009, 2010b) Guidelines	11
-----------------	---	----

MOJAVE SOLAR PROJECT

DESERT TORTOISE CLEARANCE AND RELOCATION/TRANSLOCATION PLAN

1.0 BACKGROUND

1.1 Project Description and Setting

Mojave Solar, LLC, (Mojave Solar) proposes to develop the 1,765-acre Mojave Solar Project (MSP or Project), approximately nine miles northwest of the town of Hinkley, California, in an unincorporated area of San Bernardino County (Figure 1). The Project is a 250 MW, parabolic solar thermal trough facility, the details of which can be found in the Biological Assessment (BA; U.S. Department of Energy [DOE] 2010). In summary, the Project includes the following:

- Within the Project Area (i.e., Project footprint) there will be two, independent Plant Sites (Alpha and Beta), each of which includes a solar electric generating facility with a nominal net electrical output of 125 megawatts (MW). Each Plant Site contains a solar array, power block and power generating equipment, support facilities and two evaporation ponds with a nominal surface area of 5 acres each (10 acres total, or 20 acres for the entire Project).
- The Project will connect to the Southern California Edison (SCE)-owned Kramer-Coolwater 220 kilovolt (kV) transmission line located adjacent to the southern border of the Project. SCE's new Lockhart Substation and most interconnection facilities will be entirely located within the boundaries of the southern portion of the Project Area. Part of the proposed "transmission line loop", will be located outside the Project boundary in the existing SCE right-of-way (ROW). Also outside the Project Area is SCE's proposed telecommunication system between Lockhart Substation and other regional substations. This will require that new fiber-optic cables be strung on existing and/or new transmission poles in SCE ROWs along one or more of three potential routes.
- Natural gas for the Project's ancillary purposes will be supplied by a pipeline owned by Southern California Gas (SoCal Gas) that runs to the Project boundary. No off-site pipeline facilities are proposed as a part of this Project.
- Water for all industrial and construction uses will be supplied from on-site groundwater wells. Drinking water will be produced using an onsite water treatment system to meet potable standards.
- A sanitary septic system and on-site leach field will be used to dispose of sanitary wastewater.

The Project is sited on formerly and currently farmed lands. Abandoned agricultural operations include crops, especially alfalfa, irrigated by center-pivot irrigation, as well as some livestock operations. Half of one center-pivot field is still farmed for alfalfa and wheat. Existing adjacent anthropogenic development includes the Solar Electric Generating Systems (SEGS) VIII and IX facility to the north-northwest and a few remaining residences. Other aboveground development includes SCE's Kramer-Coolwater 230-kV transmission line, which travels east-west, south of the Project, and the paved Harper Lake Road, which runs through the Project Area.

Relict native plant communities on the site exist in the corners of the center-pivot fields and consist of disturbed saltbush scrub (*Atriplex polycarpa* and *A. confertifolia*). There is also some saltbush scrub regrowth in the former dairy operation and formerly farmed fields west of Harper Lake Road, and northeast of Harper Lake Road. Areas surrounding the Project Area include developed or disturbed lands, native Mojave creosote bush scrub and native saltbush scrub. Harper Dry Lake and associated shoreline vegetation intersects the northeastern corner of the Project Area.

The topography is generally flat with elevations ranging from approximately 2,025 to 2,105 ft. The Project Area is covered by older alluvium consisting of dry, loose-to-moderately dense, silty fine-to-coarse sand with occasional gravel; subsurface layers of silt and possibly clay are likely to be present (Ninyo & Moore, 2006). In general, the hydrology of the Project Area, which was originally characterized by washes flowing northeast into the dry lake, has been disrupted by long-term farming.

Conservation areas in the Project vicinity include the Harper Dry Lake Area of Critical Ecological Concern (ACEC), adjacent and northeast of the Project Area (Figure 2). U. S. Fish and Wildlife Service (USFWS)-designated desert tortoise critical habitat abuts or is near the Project in the north, west and south. The U. S. Bureau of Land Management (BLM) has also designated the Superior-Cronese Desert Wildlife Management Area (DWMA) abutting the southern boundary of the Project and a Mohave Ground Squirrel Conservation Area to the south and east that overlaps the DWMA.

1.2 Desert Tortoise Occurrence in the Project Area and Vicinity

Desert tortoise focused surveys were conducted in April and May of 2007, 2008, and 2009 according to USFWS desert tortoise survey protocol (USFWS 1992). The survey area changed each year with refinements in the Project footprint, but was always a subset of the broadest area surveyed in 2007 - the Biological Resources Survey Area (BRSA) - which also included a one-mile buffer around the BRSA (see Mojave Solar [2009], Figure 5.3b in Section 5.3). In 2008, the proposed Project Area was modified as a subset of the BRSA. Surveys in 2008 were conducted within an updated Project Area and out to one mile from the Project Area boundary. During 2009, supplemental protocol-level surveys for desert tortoise were conducted within select locations of the Project Area. (See Mojave Solar [2009] for a detailed description of surveys completed each year.)

The survey data (Figure 3) indicate that tortoises are unlikely to occupy the Project Area. Tortoise sign observed on the Project Area consisted of carcass parts and one full carcass of an immature tortoise; one old scat was observed in a center-pivot field, approximately 600 ft from the southern Project Area border. No recent scat and no burrows were observed. No live desert tortoise were documented on the Project Area during any focused surveys, although one tortoise was observed in the northeastern Project Area near a residence and along the southern Beta field border during surveys in 2006 for another project. Density on the Project Area is considered to equal zero. During the cumulative surveys, substantial quantities of tortoise sign were observed outside the Project Area to the east, west and south. (See Mojave Solar [2009], Section 5.3, for details of desert tortoise observations.)

2.0 Purpose, Background and Structure of the Plan

The purpose of this relocation/translocation plan (Plan) is to provide direction for the removal of tortoises from harm's way on the Project Area during all Project activities. A draft Plan was submitted to USFWS, the California Department of Fish and Game (CDFG), and the California Energy Commission (CEC) in March 2010 (Karl 2010a). USFWS provided comments on 26 April 2010 (USFWS 2010a); CDFG provided comments on 6 May 2010 (CDFG 2010). This was followed by discussions between CDFG (E. Weiss and T. Moore), USFWS (A. Blackford), and A. Karl (representing Mojave Solar) on 13 and 21 May 2010. Since those conversations, USFWS guidance has changed repeatedly, with new translocation guidance issued as recently as August 2010 (USFWS 2010b). This updated Plan incorporates the original agency comments, as well as changes reflected in the more recent USFWS (2010b) guidance¹. Except where superseded by this recent guidance document and informal communications from USFWS, this Plan relies on formal guidelines from USFWS in December 2009 (USFWS 2009a). Finally, this version of the Plan incorporates relevant agency comments on a revised version submitted in November 2010. Because USFWS is in the process of analyzing desert tortoise translocation in general, relevant newer guidance will be incorporated into the Project relocation/translocation procedures as they become available.

Biologically, translocation refers to moving an animal outside its home range. For desert tortoises, males generally have been shown to have larger home ranges than females in studies of sufficient duration and sample size (O'Connor et al. 1994; TRW 1999a), approximately 111.6 acres (range: 10.4–487.8 acres) (45.2 ha; range: 4.2–197.5 ha) for adult males and 43.5 acres (range: 4.7–143.3 acres) (17.6 ha; range: 1.9–58.0 ha) for adult females. These areas result in home range diameters of 2482 ft (752 m) for males

¹ Although there have been many changes in USFWS policy since May 2010, MSP has received no formal or informal communications from CDFG since 6 May 2010 regarding CDFG translocation policy. However, based on conversations between Dr. Larry Lapre (BLM) and Dr. Karl, it appears that CDFG policy is consistent with the most recent USFWS (2010b) guidance. Mojave Solar is proceeding with this Plan under this assumption.

and 1554 ft (470 m) for females. Studies of shorter duration or with a smaller sample size found smaller home ranges (e.g., Burge 1977, Barrett 1990, O'Connor et al. 1994, Duda et al., 1999). Home ranges for both genders (Duda et al, 1999) and for males, only, in one study (TRW 1999), decreased significantly in drought years.

USFWS terminology regarding translocation has changed repeatedly in the past year, as has the distance within which tortoises are considered translocated. Currently, the USFWS is attempting to use the phrases “tortoises translocated >500 m” and “tortoises translocated <500m” for any tortoises moved off of project sites, including during perimeter fencing. They are using the phrase “tortoises moved out of harm’s way” to describe tortoises that are moved off of linear facilities, such as access roads and pipelines outside a project site proper. This is not only awkward terminology for repeated use in a document, but it is likely to change again during USFWS’ continued analysis of desert tortoise translocation. For the purposes of this Plan and ease of use, the following simple terms, which are consistent with the 2009 *Desert Tortoise Field Manual*, will be used:

- Relocation – Moving a tortoise out of harm’s way to a point within that tortoise’s home range. This would include tortoises moved <500m.
- Translocation – Moving a tortoise out of harm’s way to a point distant from the tortoise’s home range. This would include tortoises moved >500m.

The structure of this Plan is first to describe general procedures applicable to all tortoise relocations/translocations: data collected on all tortoises; tortoise transportation; authorized handlers; and reporting. The Plan then addresses desert tortoise clearance and translocation during various Project phases, from site perimeter fencing through construction, restoration activities following construction, operations, and Project decommissioning. The reader is advised that this Plan is for desert tortoise clearance and translocation only. Other actions associated with tortoise protection measures (construction monitoring, fence construction and monitoring, etc.) are included in other, relevant documents, such as the BA (DOE 2010) and CEC license (CEC 2010). All avoidance, protection, and minimization measures that are identified in other Project documents for other biological and cultural resources will be implemented in concert with this Plan.

3.0 Procedures Applicable to All Relocations and Translocations

3.1 Data Gathered on Relocated and Translocated Tortoises

Each captured tortoise will be processed at capture, prior to translocation. The gender, carapace length, width along the widest area between and inclusive of Marginals 5 and 6, height at the third vertebral, distinguishing morphology, clinical signs of disease, capture site location and description, and the amount of void, if any, will be recorded. In addition,

the tortoise will be photographed and drawn. All release site locations will also be recorded at relocation/translocation, along with their descriptions. All tortoise handling will be accomplished by techniques outlined in the USFWS *Field Manual* (2009a: Sections 7.6-7.8) and including the most recent disease prevention techniques (e.g., Wendland et al. 2009). Each tortoise will be assigned an individual number, with a number series to be provided by USFWS. Marking techniques will be approved by USFWS, but temporary marks using very small epoxy numbers (e.g., clear epoxy over a small, indelible number on a correction fluid [Wite-Out®] background) on a costal or interior marginal area that receives little to no abrasion are suggested, with a Project-specific identifier. Such numbers will last for several years, which will facilitate identifying specific tortoises if they are subsequently observed during Project maintenance or other activities, including repeated observations during construction (e.g., on the perimeter fence).

3.2 Transmitters

If needed for monitoring relocated or translocated tortoises, transmitters will be affixed to the tortoises. Holohil R1-2B transmitters (24 mm wide by 11 mm thick; 14.9 g; www.holohil.com) will be epoxied onto a carapace scute using five-minute gel epoxy. For males, transmitters will be affixed to the fifth vertebral; for females, transmitters will be affixed to the anterior carapace in the most appropriate location for the animal's shell shape that will preclude interference with righting. The transmitter antenna will be fed through a plastic sheath with a diameter slightly greater than the antenna. This sheath will be epoxied low on the carapace, just above the marginal scutes, and split at the scute seams (growth areas) to preclude distortion of the tortoise's shell during growth. This technique permits the antenna to remain protected from abrasion, but move freely, thereby not affecting tortoise growth. Juvenile tortoises will be similarly equipped but with smaller transmitters, appropriate for their mass and size (<10% of the tortoise's mass). Because the antenna sheath is tightly curved on a very small tortoise, potentially constricting antenna movement with subsequent growth distortion, much more of the antenna will remain free on small tortoises. These are proven techniques to minimize disturbance to the tortoise, refined and/or developed and used by Dr. Karl for more than 20 yrs and on over 300 tortoises and subsequently used at Fort Irwin for several hundred tortoises.

3.3 Tortoise Transportation and Holding

Tortoises that only need to be moved a few hundred feet will be hand-carried to the release site. Each tortoise that is hand-carried will be kept upright and the handler, wearing disposable examination gloves (one pair per tortoise), will move the tortoise as quickly and smoothly as possible. Tortoises that must be moved farther from the capture site or temporarily held in a climate-controlled situation will be sequestered in individual, sterilized tubs with taped, sterilized lids or single-use cardboard boxes with lids. During transport by vehicle, the tortoise tub will be kept shaded and the tub will be placed on a well-padded surface that is not over a heated portion of the vehicle floor. These measures are consistent with USFWS guidance (2009a: Section 7.10).

Should a tortoise void or defecate between capture and release, it will be thoroughly rinsed to remove potential attracting odors to predators. Then, it will be placed in a shallow bath of room temperature water to re-hydrate it, per USFWS guidance (2009a: Section 7.9). The tortoise's mass following this procedure will be recorded.

3.4 Handling Temperatures

Handling will adhere to USFWS (2010b) handling guidelines, which state that tortoises can only be handled when air temperatures, measured at 2 in (5 cm) above the ground (shaded bulb), are not expected to exceed 95°F (35°C) during the handling session. If the air temperature exceeds 95°F during handling or processing, desert tortoises will be kept shaded in an environment where the ambient air temperatures do not exceed 91°F (32.7 °C) and air temperature does not exceed 95°F. The desert tortoise will not be released until air temperature at the release site declines to 95°F.

Tortoises must go underground to escape surface heat at ground surface temperatures of 109°F (43°C) (Karl 1992) to 113°F (45°C) (Zimmerman et al., 1994). Because surface temperatures can easily exceed 109°F when air temperatures at two inches are still below 95°F, the more conservative temperature will govern all tortoise handling described in this Plan, to minimize harm to tortoises. In other words, the USFWS guidelines will be followed except in the situation where they exceed 109°F ground temperature.

USFWS (2009a, 2010b) has not provided guidance relative to handling temperatures for tortoises found during cold temperatures (e.g., less than approximately 50°F (10°C) except as they relate to moving the tortoise. This is addressed in the relevant sections below on relocation and translocation.

3.5 Authorized Handlers

USFWS describes a single designation for biologists who can be approved to handle tortoises - "Authorized Biologist" (AB) (http://www.fws.gov/ventura/speciesinfo/protocols_guidelines/docs/dt; USFWS 2009a). Such biologists have demonstrated to USFWS that they possess sufficient desert tortoise knowledge and experience to handle and move tortoises appropriately. Specific ABs will be approved to conduct specific tasks, including such specialized tasks as health assessments, blood sampling and transmitter attachment. Notwithstanding that the CEC only has designations for "Designated Biologist" and "Biological Monitor," only those biologists authorized by USFWS, CDFG, and BLM, presumably including the Designated Biologist and certain Biological Monitors, can conduct specific handling tasks on desert tortoises.

For USFWS, ABs are permitted to approve specific biological monitors (BM)s to assist in certain tasks, at their discretion, without further approvals from USFWS. Direct supervision from the AB (i.e., voice and sight contact) is required for all clearance

surveys and other specialized tasks. However, CDFG, BLM and CEC must also approve ABs, and BLM and CDFG will independently approve BMs for specific activities. .

4.0 Clearance and Relocation/Translocation During Specific Project Phases

Tortoise relocation/translocation that is necessary during Project construction may occur during initial perimeter fence construction, tortoise clearance from the Plant Site and Lockhart Substation (i.e., all facilities inside the Project Area), and initial grading on the Project Area. Based on the survey results, it is anticipated that no or very few desert tortoises would require removal from the Project Area. Tortoises may also be moved from harm's way during the SCE installation of the fiber optics line and associated poles. While unlikely, a tortoise could be found on the Project Area during operations. Relocation/translocation may also occur during decommissioning.

4.1 Project Area Perimeter Fencing and Temporary Fencing

Prior to the onset of Project Area tortoise clearance, both Plant Sites (Alpha and Beta Sites) and Lockhart Substation will be fenced with permanent, tortoise exclusion fence per USFWS (2009a) guidelines, to keep tortoises in habitat adjacent to the Project Area from entering during construction and operations phases. The permanent fence around the Plant Sites will also include the drainage channel. Tortoise exclusion fence will be attached to the MSP permanent perimeter fence. Exclusion fence material will be one-inch by two-inch vertical wire mesh fence, extending at least two feet above the ground and buried at least one foot. Although unlikely, where burial is impossible, the mesh will be bent at a right angle toward the outside of the fence, with the bent portion anchored by stakes and further held down by rocks and soil to prevent tortoises from digging under the fence. Tortoise-proof gates will be established at all site entry points, to remain closed except during entry by personnel. If shown to be effective and not potentially dangerous to tortoises, tortoise "cattle guards" may be installed instead of or in addition to gates.

Temporary fencing may be used to exclude tortoises until the permanent fence is installed. Currently, no Project-related construction is planned outside the facility, although some work (e.g., drainage channel crossing at Harper Lake Road) may occur. Should any work outside the fenced Project occur where tortoises are possible, temporary fencing may be installed where the AB believes that it would provide better protection than monitoring by BMs. Temporary fencing will follow guidelines and materials for permanent fencing except in very temporary situations, when silt fencing may be used. In both cases, supporting stakes will be sufficiently spaced (e.g., ≤ 8 ft for wire mesh; ≤ 5 ft for silt fencing) to maintain fence integrity. Fencing may be buried if it would not create a biologically significant disturbance, or bent outward at the ground level, with the bent portion tacked and/or held down by rocks and soil.

4.1.1 Project Area Perimeter Fencing Schedule

Project Area perimeter fencing is planned for installation prior to April 2011, with tortoise clearance and relocation/translocation beginning in April 2011. Should this schedule change, or construction phasing occur, then the same criteria expressed in this Plan to ensure that tortoises are safe during construction, clearance and relocation/translocation procedures still will be implemented.

4.1.2 Surveys and Monitoring during Fence Construction

Within 24 hours prior to fence installation, biologists will survey the staked fenceline for all desert tortoise burrows and tortoises, covering a swath of at least 90 ft centered on the fenceline, using 15-ft-wide transects. Tortoise burrows will be mapped using Global Positioning System (GPS), and the size and occupancy recorded; if not occupied, indications of how recently the burrow was used will be recorded. Burrows also will be flagged if they would not be likely to attract poaching. Burrows will be avoided if at all possible (especially if this is temporary fencing). But, if a burrow must be destroyed for fencing to occur, then it will be visually and tactilely examined for occupancy by tortoises and other wildlife. If occupancy is negative or cannot be established, the burrow will be carefully excavated with hand tools, using standardized techniques approved by USFWS (2009a) and the Desert Tortoise Council (1994). No burrows that can be avoided will be collapsed during perimeter fence construction.

All fence construction will be monitored by approved biologists to ensure that no desert tortoises are harmed. The level of monitoring will depend on the specific fencing activity, but at least one BM will accompany each separate construction team, such that no driving, trenching, fence pulling, or any surface disturbing activities will occur without the immediate presence of a BM. Maps of burrows from the pre-construction survey will be provided to all BMs to assist in protecting tortoises. Such maps will also be potentially useful for relocating tortoises.

Following the onset of the tortoise activity season, or if exclusion fencing is installed when tortoises are known to be active (for example, if unusually warm weather occurs in winter before fencing is completed), then all installed exclusion fence (partial or complete) will be checked ensure that no tortoise is trapped inside the Project Area. If fencing is installed during a warm period in winter, then all fencing will be checked twice daily, during the warmer periods of the day. Any tortoise would be relocated as described in Section 4.1.3, Tortoise Relocation Methods during Fence Construction, below. If fencing occurs during spring or summer (approximately 1 April through September), then all fencing will be checked 2-3 times daily during tortoise activity temperatures (between approximately 15 and 42°C ground surface temperature), for two weeks, to ensure that a tortoise is not inadvertently trapped inside. Tortoises would be passively or actively relocated as identified below in Section 4.1.3 and Table 1. If, for any reason, tortoise clearance surveys were delayed for several months after fencing, at least one clearance pass would be completed as soon as tortoises became active following the completion of fencing (e.g., April if fencing were completed in winter, immediately

after fencing if fencing were completed from April through October); see Section 4.2.1, Clearance Surveys, below. These measures would ensure that no tortoise were trapped into the non-habitat inside the site following fencing.

4.1.3 Tortoise Relocation Methods during Fence Construction

Tortoises will be avoided if at all possible. Fence gaps and erection of temporary fencing will be used to “encourage” a tortoise to return to the outside of the fence. For instance, if an active tortoise is observed inside the Project boundary, construction and equipment can be temporarily moved to another section of the fence, a large gap can be left in the fence nearest the tortoise and a temporary (e.g., silt) fence can be quickly constructed from the gap edges well around the tortoise so that it moves through this channel to the outside of the Project. Following exit from Project Area, the tortoise would then be immediately monitored as identified below in Section 4.1.5, Post-Release Monitoring.

Any tortoise that must be moved during perimeter fencing will be relocated immediately outside the construction zone, but onto MSP land (Figure 4). Release points will be as close as possible to the capture point, to keep tortoises within their home range, but will always be on or immediately adjacent to suitable habitat. Specific release points cannot be identified at this time without knowing where tortoises are, but the highest likelihood of finding a tortoise along the perimeter fence is along the southern, eastern and northeastern border of the Beta Site and the western border of the Alpha Site (Figure 4).

Generally, tortoises will be placed in the shade of a shrub or, if known, in the entrance of that tortoise’s burrow (but see below in the event that ambient temperatures are high). The most recent USFWS guidance (USFWS 2010b) states that all “perimeter fence” tortoises be moved to the interior of the Project Area. Because the solar project site has limited desert tortoise habitat and is expected to support few if any desert tortoises, which is supported by the limited amount sign and burrows on the proposed solar fields, it is believed that any individual found during fence construction maintains a territory outside of the solar project site and is utilizing the project area for foraging or movement. Therefore, desert tortoises on the MSP project found during fence construction will be placed outside of the solar project site rather than inside.

All tortoises relocated from harm’s way during perimeter fencing will be translocated as described in Section 3.2, above. The exception will be tortoises brumating (≈hibernating) in burrows during winter (see below for a discussion of handling tortoises outside of USFWS temperature guidelines).

USFWS guidance (2009a, 2010b) regarding translocation temperatures states that translocation occur when air temperatures at 2 in (5 cm) above the ground, are not forecast to exceed 90°F (32°C) within three hours of release and 95°F (35°C) within one week of release; additionally, daily low temperatures should not be cooler than 50°F (10°C). The rationale for the higher temperature constraints is that tortoises must find or dig new refuges in the potentially unfamiliar translocation area prior to the onset of lethal daily temperatures. Along the perimeter fenceline, however, tortoises would be moved

only a short distance, within their home ranges, where they are knowledgeable about the locations of refuges. USFWS (2010b) has agreed that relocation on linear facilities, including perimeter fencing, may occur during any time of the year. The only high temperature constraint is that no tortoise will be moved when air temperatures are expected to exceed 90°F (32°C) within three hours of release.

Although fence construction is currently planned for February to March 2011, schedules may change. Fence construction is permitted by USFWS for any time of the year, so air and ground temperatures will exceed lethal levels in the warmer months or may be lower than 50°F during some winter days and evenings. Contingencies must be in place in the event that a tortoise must be relocated. The following options to protect tortoises address potential contingencies during periods of high temperatures. (Note, however, that no tortoise would be moved when air temperatures exceed 95°F, except in an emergency.) A summary of these activities is found in Table 1.

- *If a tortoise is found under a shrub*, a temporary fence can be erected to keep the tortoise from entering the construction zone. The fence will be flagged to ensure avoidance. Fencing will be 1 by 2-inch mesh or other, adequate temporary fencing (e.g., silt fencing can be used for very short-term needs). If practical, the fence would be removed later in the day (or several days later if needed to protect the tortoise) when the tortoise could be allowed to move away from the construction area of its own accord (preferred) or safely moved. If the tortoise must be handled, it would be processed and transmittered.

If the AB determines that leaving the tortoise under a shrub would potentially result in overexposure to high temperatures and no burrow is known for that tortoise, construction in that area will halt and all personnel will depart. Construction can be resumed later in the day when air temperature has dropped below 95°F. Less preferably, the tortoise can be collected in a sterile, covered tub, held in a climate-controlled location (e.g., Project office), transmittered, and released in early evening, when air temperature has dropped below 95°F or the following morning. All boxed tortoises would be checked several times until release, to ensure their safety. All released tortoises would be visually monitored until they found a suitable burrow. At the AB's discretion, if this tortoise's burrow is known, the tortoise can be placed at that burrow and watched until it enters the burrow.

- *If a tortoise is in a burrow that can be avoided*, a temporary fence will be erected to keep the tortoise from entering the construction zone. The fence will be flagged to ensure avoidance.
- *If a tortoise is in a burrow that cannot be avoided by construction activities*, then the tortoise will be collected in a sterile, covered tub, held in a climate-controlled location (e.g., Project office) until early evening, when air temperature has

Table 1. Alternatives for Relocating or Translocating Tortoises Found During Periods of Ambient Temperatures Outside the USFWS (2009a, 2010b) Translocation Guidelines. Note that in all cases, no tortoises will be handled during air temperatures at two inches above the ground that exceed 95°F.

Project Phase	Project Activities	Alternatives for Relocation or Translocation ¹		
		During Periods of High Temperatures		During Winter ²
		Tortoise Found Under Shrub	Tortoise Found In Burrow	
Construction	Construction of Project Area perimeter fence; tortoises on Harper Lake Road; SCE telecommunications upgrades and interconnection construction outside the Project boundary	<ul style="list-style-type: none"> Relocate to known burrow; monitor Erect temporary fence between tortoise and construction; monitor; remove fence when appropriate Temporarily move construction to another area Collect and hold in climate-controlled facility; release in evening or the following morning; monitor 	<ul style="list-style-type: none"> Erect temporary fence between tortoise and construction; monitor; remove fence when appropriate If cannot be avoided, collect and hold in climate-controlled facility; release late afternoon/early evening or following morning; monitor 	<ul style="list-style-type: none"> If cannot be avoided, place tortoise in artificial burrow, temporarily block in and monitor; remove block at two weeks (or earlier depending on the weather) and monitor If tortoise fails to find suitable winter burrow and will not use artificial burrow, hold in climate-controlled facility, in the dark at temperatures simulating burrow temperatures, until seasonal temperatures warm and tortoises are active; release within 100 ft of capture burrow; monitor
	Grading of Project Area; tortoises trapped inside Project Area after fencing	<ul style="list-style-type: none"> Capture and hold in climate-controlled facility, contact USFWS and CDFG for direction 	<ul style="list-style-type: none"> Capture and hold in climate-controlled facility, contact USFWS and CDFG for direction 	Not applicable
Operations	Plant Sites	<ul style="list-style-type: none"> Capture and hold in climate-controlled facility, contact USFWS and CDFG for direction 	<ul style="list-style-type: none"> Capture and hold in climate-controlled facility, contact USFWS and CDFG for direction 	Not applicable

	Access road, utilities maintenance	<ul style="list-style-type: none"> • Allow tortoise to proceed out of area unimpeded; monitor • Relocate to known burrow; monitor • Erect temporary fence between tortoise and construction; monitor; remove fence when appropriate • Temporarily move construction to another area • Collect and hold in climate-controlled facility; release in evening or the following morning; monitor 	<ul style="list-style-type: none"> • Erect temporary fence between tortoise and construction; monitor; remove fence when appropriate • Collect and hold in climate-controlled facility; release late afternoon/early evening or following morning; monitor 	<ul style="list-style-type: none"> • If cannot be avoided, place tortoise in artificial burrow, temporarily block in and monitor; remove block at two weeks (or earlier depending on the weather) and monitor • If tortoise fails to find suitable winter burrow and will not use artificial burrow, hold in climate-controlled facility, in the dark at temperatures simulating burrow temperatures, until seasonal temperatures warm and tortoises are active; release within 100 ft of capture burrow; monitor
Decommissioning	Project decommissioning and site restoration, outside fenced areas	<ul style="list-style-type: none"> • Relocate to known burrow; monitor • Erect temporary fence between tortoise and construction; monitor; remove fence when appropriate • Temporarily move construction to another area • Collect and hold in climate-controlled facility; release in evening or the following morning; monitor 	<ul style="list-style-type: none"> • Erect temporary fence between tortoise and construction; monitor; remove fence when appropriate • If cannot be avoided, collect and hold in climate-controlled facility; release late afternoon/early evening or following morning; monitor 	<ul style="list-style-type: none"> • If cannot be avoided, place tortoise in artificial burrow, temporarily block in and monitor; remove block at two weeks (or earlier depending on the weather) and monitor • If tortoise fails to find suitable winter burrow and will not use artificial burrow, hold in climate-controlled facility, in the dark at temperatures simulating burrow temperatures, until seasonal temperatures warm and tortoises are active; release within 100 ft of capture burrow; monitor

¹ See the text for the details of each alternative.

² Winter is defined as the period when tortoises are brumating, approximately 1 November to 1 April.

dropped below 95°F. At that time, the transmittered tortoise will be released outside the Project Area fence within a few feet of the point of collection. It will be followed until it either finds a suitable burrow or night falls. (If this exercise occurs in the morning, the threshold will be air temperatures exceeding 95°F.) If no suitable burrow has been found, the tortoise would be again tracked in the morning until it finds a suitable burrow or the threshold temperature has been reached. If the latter occurs, the tortoise will again be collected and the process repeated that evening. Because tortoises use many burrows, it is anticipated that the tortoise would locate a suitable burrow quickly.

If fencing occurs during winter when tortoises are inactive (approximately 1 November to 1 April), tortoises found in burrows will be avoided, and the burrow fenced with high visibility fencing (if this would not attract poaching) and mapped on construction drawings; a biological monitor will continually monitor the burrow and fence while construction is proceeding in the immediate area of the burrow, to ensure tortoise safety (Table 1). The high visibility fencing will be removed once all danger of construction is past. A brumating tortoise will not be removed from its burrow for the sole purpose of transmittering it. If a tortoise in a burrow that cannot be avoided² and tortoises are still in brumation, then an artificial burrow that replicates the capture burrow (i.e., location relative to a shrub, direction, length) will be constructed as nearby as possible outside the Project fence and in an area where construction has finished (i.e., the tortoise will not be disturbed). All burrows that cannot be avoided will be completely excavated using standardized techniques approved by USFWS (2009a) and the Desert Tortoise Council (1994). The tortoise will be captured at night, affixed with a transmitter and placed in the artificial burrow along with soil and scat from the capture burrow. The tortoise will be blocked into the burrow for two weeks (unless the weather warms, in which case the barriers will be removed), at which time the blocks will be removed and the tortoise continually monitored to ensure that it either remains in the burrow or finds another suitable burrow. If the tortoise fails to find a burrow in several days, and the nighttime air temperatures fall below approximately 50°F, then it will be captured and held in a climate-controlled, dark, quiet, and safe location (e.g., room in Project office) at an air temperature equivalent to the air temperature one meter inside a natural burrow, until seasonal temperatures warm and tortoises are observed to be active in the area. At that point, it will be released within 100 ft of its capture burrow and monitored as described in Section 4.1.5, Post-Release Tortoise Monitoring, below.

Any tortoise found aboveground during winter is highly likely to be near its burrow, except during extended periods of warm weather. A transmitter will be affixed to the tortoise and it will be tracked daily until it is established that the tortoise is sequestered in a suitable burrow.

² This could occur where the permanent fence was the first and only perimeter fence constructed.

4.1.4 Health Considerations

Visual health assessments will be conducted on all tortoises relocated during site fencing (i.e., moved <500 m), by an experienced biologist approved by the USFWS. USFWS (2010b) guidance and later e-mails from USFWS (T. Englehard, pers. comm. to A. Karl) have identified that no tortoise will be relocated within 1.5 km (0.9 mi) of a diseased resident tortoise because relocated tortoises may move 1.5 km after translocation. Mojave Solar will comply with the requirement to complete a 100%-coverage survey for resident diseased tortoises within 1.5 km of any relocated tortoise (Figure 4). However, surveying for such resident tortoises would be problematic during the anticipated time when fence construction is occurring (February-March 2011). Also, USFWS' rationale is highly unlikely to apply to the Project, since any tortoise that must be relocated from the Project Area likely will be moved only a few meters. The USFWS anticipates that such "relocated tortoises typically remain within their home range" (USFWS 2010b:27). Based on these factors, alternatives may be discussed with USFWS following relocation of all tortoises during perimeter fencing activities.

No tortoise with clinical signs of mycoplasmosis will be relocated. Schumacher *et al.* (1997) observed that clinical signs had a high statistical correlation with positive serology (i.e., exposure to *Mycoplasma agassizii*). A mucous nasal discharge was the clinical sign that was the most reliable predictor (93% of tortoises with a mucous nasal discharge were seropositive), although it could be caused by pathogens other than *M. agassizii*. Furthermore, a purulent nasal discharge was the only clinical sign that was relatively objective; other clinical signs were far more subjective, were potentially present for other reasons, and reduced the statistical predictability of positive serology. For the MSP, a purulent nasal discharge will be the threshold to identify a diseased tortoise, unless USFWS determines that other clinical signs should be used for diagnosing a diseased tortoise.

Desert tortoises determined to be infectious or unhealthy will be sent to the Desert Tortoise Conservation Center (DTCC) or other USFWS-approved facility where they will undergo further assessment, treatment, and/or necropsy. Mojave Solar will provide a flat fee of \$9,000 for each desert tortoise sent to the DTCC commensurate with the cost to provide housing, care, treatment, and other services for five years (\$3,000 for Year 1, \$1,500 for Years 2 to 5).

4.1.5 Post-Release Tortoise Monitoring

While tortoises moved a short distance from construction activities along the perimeter fence would be assumed to be within their home range and familiar with burrow locations, they would receive immediate post-release monitoring. This may be especially critical for juvenile tortoises, which are highly subject to depredation. Any tortoise moved will be watched for at least one hour to determine if it is behaving safely (e.g., seeking shade or a burrow) or if it is likely to try and re-enter the construction area. Because each relocated tortoise will have a transmitter, it will also be located via

telemetry for the next two days during tortoise activity temperatures to ensure that the tortoise is not fence-walking and is using burrows. .

As described above in Section 4.1.3, Tortoise Relocation Methods during Fence Construction, any tortoise moved in the evening during a period when daily air temperatures exceed 95°F (late April through early October) will be followed until it either finds a suitable burrow or night falls. (If this exercise occurs in the morning, the threshold will be air temperatures exceeding 95°F by which a tortoise must find a suitable burrow.) If it has not found a suitable burrow, the tortoise would be again tracked in the morning until it finds a suitable burrow or the threshold temperature has been reached. If the latter occurs, the tortoise will again be collected, held in a climate-controlled environment and the process repeated that evening. Because tortoises use many burrows, it is anticipated that the tortoise would locate a suitable burrow quickly.

USFWS (2010b) requires a five-year monitoring program for translocatees, including tortoises removed from the perimeter fence. Mojave Solar will monitor all translocated tortoises for five years from the time of relocation/translocation. Based on multiple Project surveys, it is assumed that fewer than five tortoises will be part of the study. USFWS (2010b) has determined that no resident and control study cohorts are required for fewer than five translocatees. The Ventura Field Office (VFO) requires that juveniles be counted in the total for monitoring but recognizes the difficulty in obtaining juvenile control and recipient cohorts. So, if mostly juveniles are translocated, then USFWS will consider a modification of the five-year monitoring program. If five or more desert tortoises are translocated from the project site, Mojave Solar will work with the BLM, CDFG, and Service to identify appropriate locations for control and resident desert tortoise monitoring.

Based on the requirements from the USFWS (2010b), the following elements will be part of the monitoring program:

- Tortoises will be located by telemetry according to the schedule identified in USFWS (2010b) guidelines. Each time the tortoise is located, the behavior, location (UTM), and burrow description (if any) will be recorded.
- Survival and general health will be monitored through body condition indices (mass to volume ratios), clinical signs of disease, serology, and inspection for injuries. Any time a tortoise is handled, it will be examined for clinical signs of disease. Formal health assessments will be conducted during April (following brumation), July (following oviposition), and October (prior to brumation). At these times, body condition (mass to volume ratio) also will be measured (mass, carapace length, width at Marginal 5 or 6, height).
- Blood samples will be taken and analyzed annually, in July or October. An approved biologist will conduct the assessments and tissue sampling. While

blood samples are not required of tortoises moved <500 m during relocation, blood will be sampled shortly after relocation³ in order to provide baseline data.

- Sampling frequency and techniques for disease analysis will be updated as necessary during the study, based on the newest disease information from this and other studies. This may include tests for other pathogens (e.g. *Mycoplasma* spp., herpesvirus, iridovirus) as their importance and evaluation techniques become validated for desert tortoises. Data will be recorded on a data sheet similar to that in Appendix 1, with an additional health assessment data sheet to be provided by USFWS.
- Any health problems observed (e.g., rapid declines in body condition, perceived outbreaks of disease, mortality events) will be reported to the USFWS, CDFG and BLM⁴ such that appropriate actions can be taken in a timely manner.
- Should a translocated tortoise die, the cause of death will be determined to the extent possible. This information, along with the location and any other analysis that could assist the USFWS, CDFG, BLM and DOE will be provided to these agencies within 48 hours, verbally, or five business days, if by e-mail. All fresh carcasses will be salvaged and frozen. They will be submitted for necropsy upon direction from USFWS, CDFG, and BLM; DOE will also be notified.
- Transmitters will be changed as necessary.

USFWS' stated purpose for this study is "to evaluate the effectiveness of translocation as a take minimization measure" (USFWS 2010b). Part of USFWS' rationale for monitoring perimeter fence tortoises is to assess the impact of the new barrier to movement in their home range (A. Blackford, USFWS, pers. comm. to A. Karl). Recognizing the site-specific conditions (i.e., the existing and historical agriculture is already a barrier to use), as well as the anecdotal results from such a small study cohort, USFWS has expressed interest in discussing other research questions. Mojave Solar offers the following research questions for discussion, if fewer than five tortoises are moved:

- 1. What is the survival of tortoises following relocation and short-distance translocation until tortoises settle into home ranges?**

³ USFWS (2010b) requires that blood sampling be conducted no sooner than 15 May, "based on activity of the immune system." This premise is currently under scrutiny (e.g., e-mail from M. Brown, University of Florida Mycoplasma Lab, to K. Fields, USFWS, 8 October 2010).

⁴ Although no relocation sites are located on BLM land, these sites are immediately adjacent to BLM land, so most relocated tortoises will use BLM land. One translocation site is on BLM land. Consequently, BLM will be included in all decisions relative to tortoises in relocation/translocation areas.

Background and Rationale - Tortoises that may be relocated or translocated from the Project Area currently reside outside the site, as evidenced by the complete lack of burrows and only one old scat within 200 m of the border in three years of surveys (not including the 2006 reconnaissance). Therefore, since tortoises in the area are already accustomed to the area outside the site, moving them outside again, should they happen to be on the site at the time of clearance, merely moves them into an area with which they are already familiar. It seems far-fetched to assume that they would experience the same stressors that a tortoise translocated into unfamiliar territory would experience. So, mortality or harm due to relocation or translocation seems highly unlikely.

Approach - Mojave Solar would monitor all translocated tortoises for 2.2 years, from the time of relocation/translocation (expected March 2011) through May 2013. All monitoring elements described above for the USFWS monitoring program would form the basis of the monitoring program. A period of 2.2 years is being proposed because two translocation studies have identified that translocated animals exhibit similar movement patterns as resident animals (i.e., settle into new home ranges) in approximately nine months to two years following translocation to an unfamiliar area (Nussear 2004, Karl and Resource Design Technology, 2007)

2. How do tortoises respond to a large barrier fence in their home range following relocation and short-distance translocation?

Rationale – In general, to answer this USFWS question, it would be useful to monitor tortoises that live in the immediate area of the fence more closely than the weekly and bi-weekly schedule proposed by the USFWS. This would provide information on a tortoise's use of the area relative to the tortoise's proximity to the fence. A temporal component would provide information on how that use changed following fence installation.

At MSP, tortoises already do not use the Project Area because long-term agriculture has virtually eliminated tortoise habitat there; even the center-pivot corners and former residential area in the north are very small and disturbed. So, the Project presents a special situation whereby the Project fence should have a negligible effect on normal tortoise behaviors.

Approach - Mojave Solar would track all translocated tortoises twice a day during the height of the activity season (March to May and October-November). (During the remainder of the year, the monitoring schedule for #1, above would be maintained.) Wildlife cameras might be used to augment fenceline sampling for tortoises that reside very close to the fence, or were frequently found there. The study would last the same length of time as #1, above. All locations and behavior would be recorded. Data analysis would examine the density of above-ground locations and burrows with respect to distance from the fence; covariates would include time since translocation, gender, and tortoise size.

Per USFWS (2010b) guidelines, triggers for implementation of adaptive management will be developed through coordination with USFWS, CDFG, BLM and DOE.

4.1.6 Nest Relocation

Any nests found between November 1 and April 15 are unlikely to be viable and will not be moved; hatching is typically completed by October. In the event that nests are found between April 15 and October 31, the nests will be moved. Eggs will be inspected to determine if they are viable and, if so, will be moved to an identical microsite (e.g., cover, plant species, soil type, substrate, aspect) on the approved Translocation Site (see Section 4.2.2, Translocation Release Areas and Designated Translocated Site, below) using standard techniques (e.g. Desert Tortoise Council 1994, USFWS 2009a). Translocated nests will be fenced with open-mesh fencing (e.g. 2-inch wide mesh) that will permit hatchlings to escape but prevent depredation by canids that might be attracted to the new nests by human scent predator entry. Open-mesh fencing or avian netting also will be installed on the roof of the nest enclosure to prevent predator entry. Nests will be monitored from a 30-foot distance once a month until late November, at which time they will be excavated for examination. If possible, hatchlings will be weighed, measured, photographed, described and marked.

4.1.7 Monitoring Fence Integrity

All permanent exclusion fencing will be inspected monthly and immediately after all rainfall events where soil and water flow through washes or overland and could damage the fence or erode the soil underneath. Temporary fencing will be inspected at least weekly if construction is occurring; if there is a delay in construction, temporary fence inspections will follow the same schedule as for permanent fencing. Any damage to the fencing will be repaired immediately. If it cannot be repaired immediately, any gaps that are open to tortoise habitat will be continuously monitored until the gap can be repaired, to ensure that a tortoise has not entered the site through the gap.

4.2 Plant Sites and Associated Facilities inside the Project Area

4.2.1 Clearance Surveys

A clearance survey for tortoises will be conducted inside the completed perimeter Project boundary tortoise fence or suitable temporary fence. Clearance surveys will coincide with heightened tortoise activity to maximize the probability of finding all tortoises. These periods occur from April through May and during late September through October (and often into early November).

Currently, Project Area perimeter fencing is planned for installation in Winter 2011, with tortoise clearance and relocation/translocation beginning 1 April, or as soon as tortoises in the area are found to be consistently active. (Clearance earlier than 1 April would have to be approved by USFWS and CDFG.) Construction is scheduled to begin after tortoise clearance, probably from July to September 2011. Surveys would begin approximately 1

April, with two passes completed by approximately 10 April. For tortoise translocation to be successful in spring, clearance must be completed in early April to meet appropriate translocation temperatures. Tortoises must be relocated or translocated from the Project Area at least one week before daily, midday temperatures are expected to exceed 95°F (35°C) air temperature (at 2 in) or 108°F (42°C) ground surface temperature (see discussion in Section 4.1.3, Tortoise Relocation Methods during Fence Construction, above) whichever is lower. The rationale is that tortoises must find or dig new refuges in the potentially unfamiliar translocation area, prior to the onset of lethal daily temperatures. Mojave Solar intends to begin grading the entire Project Area after tortoise clearance surveys, so all tortoises must be removed prior to grading.

Should this schedule change, or construction phasing occur, then the same criteria expressed throughout this Plan to ensure that tortoises are safe during construction, clearance and relocation/translocation procedures will be implemented for separate phases. It is always important to consider that Project scheduling may change, resulting in Project Area clearance surveys being conducted outside temperatures that are higher than the USFWS guidelines for translocation. For instance, tortoises are very active (i.e., available for surveying) well past the period when it is safe to translocate in spring. Likewise, during September, high activity will likely occur prior to safe, autumn translocation temperatures. Generally, in either event, any tortoise found typically would be monitored onsite, via telemetry, until the next period when ambient temperatures permitted translocation. . However, because there is so little habitat on the Project Area, and arguably not enough to support a tortoise, if fencing is completed from April through September, then clearance surveys will occur immediately after fencing is complete to ensure that no tortoise is trapped inside the Project boundary. (Note also that fence checks would be conducted twice daily for fence-walking tortoises – see Section 4.1.2, Surveys and Monitoring during Fence Construction, above.) It would be prudent to consider relocating or translocating this tortoise prior to the following “safe” translocation period. So, if a tortoise is observed during clearance surveys when ambient temperatures are likely to be too high for translocation (i.e., mid-April and early October), then: (1) the tortoise will be “encouraged to exit the Project Area by the use of openings in the fence and temporary corrals (see Section 4.1.3, above); or (2) the tortoise will be monitored onsite to see if it has a burrow and could be reasonably monitored onsite until the following safe translocation period; or (3) CDFG and USFWS will be contacted to determine methods of release for that tortoise. If, through monitoring onsite, the tortoise is found to have one or more burrows and ample forage, it would be tracked at least once per week during high activity seasons (April through June, September) and twice per month during diminished activity seasons (July and August), until translocation.

Per USFWS (2010b) guidelines, a minimum of three, 100% coverage clearance passes will be completed. For the Project Area to be deemed cleared of tortoises, no additional tortoises may be found on the two, final, consecutive clearance passes. If a tortoise is found on one of these passes, two clean passes (i.e., no new tortoises) must follow before the Project Area can be declared to be cleared of tortoises. In this event, and because of the broad fields of non-habitat, it would not be necessary to complete another clearance

of the entire Project Area, but instead only that portion of the site where the tortoise was found. For instance, if a tortoise were found in a center pivot corner, where degraded relict habitat remains, that corner, as well as all other connected habitat and a several hundred meter band into the farmed field, would be searched.

Clearance transects generally will be 15 ft wide. Transects narrower than 15 ft wide will be used if dictated by dense shrub vegetation or where visibility is otherwise compromised. Wider transects during the second and third passes may be requested of USFWS on the shrub-less crop fields, depending on the height and nature of the vegetation there and the results of the first clearance pass. On each subsequent pass, an attempt will be made to view all shrubs and the terrain from as many angles as possible. To achieve this, transects programmed into GPS units will be either perpendicular, parallel but offset, and/or approached from the opposite direction on each subsequent pass (Karl and Resource Design Technology, Inc., 2007).

All tortoise sign will be mapped and evaluated (e.g., type, age, size) during all passes, and all scat collected. During subsequent passes, areas where fresh scat is found will prompt concentrated searches. After the second pass, concentrated searches will be conducted in all areas where recent sign is concentrated, unless a tortoise has been found in that area.

No burrows will be collapsed until the third pass, assuming that all tortoises probably have been relocated from the Project Area. (Fresh burrows used by other wildlife, including badgers or foxes, will not be collapsed until occupants have been removed via active or passive techniques approved by CDFG.) While clearance is planned to occur when ambient temperatures are safe for translocating tortoises, ambient temperatures may rise unexpectedly during the second pass such that a tortoise or other wildlife might be trapped in the open if its burrow has been excavated and collapsed during the search effort. To assist the identification of currently used burrows, all burrows will be inspected and assessed for occupation or recent use by tortoises during the first two passes, gated with small sticks along the entrance to detect future use, mapped and flagged. On the third pass, burrows will be completely excavated using standardized techniques approved by USFWS (2009a) and the Desert Tortoise Council (1994). During excavation, attention will be given to potential tortoise nests (see Nest Relocation, below).

Once all tortoises have been translocated from the Project Area, heavy equipment will be allowed to enter the site to conduct construction activities. However, the Project AB(s) will be continuously available during the construction period to remove any tortoises overlooked during the clearance surveys.

4.2.2 Translocation Release Areas and Designated Translocation Sites

Based on the multi-year surveys (Figure 3), it is highly likely that any tortoises found on the Project Area would be close to the Project Area borders, so few tortoises are likely to be moved >500 m (1650 ft) (Figure 4). Those moved <500 m will be relocated

immediately outside the perimeter fence, onto suitable habitat on MSP land. Release points will be as close as possible to the tortoise's capture location, to keep tortoises within their home ranges. These locations cannot be specifically predicted, since surveys did not find any tortoises or burrows in the Project Area. However, based on habitat quality and observed tortoise sign (Figures 2 and 3), the release points most likely would occur along the southern, eastern and northeastern border of the Beta Site and the western border of the Alpha Site (Figure 4).

There is very little area inside the Project Area that is further than 500 m from the boundary (Figure 4). However, much of the Project boundary does not have suitable habitat into which to move a tortoise, even if it were <500 m from the border. Where tortoises must be moved >500 m, they will be translocated to individual pens in one of two designated Translocation Sites. USFWS (2010b) has mandated that any tortoise moved >500 m must be quarantined onsite or offsite until the serology lab report is obtained in mid to late May. Onsite quarantine is not possible on the Project Area because there is not sufficient habitat onsite to support a tortoise. Furthermore, all areas inside the perimeter fence will be graded following tortoise clearance. Two translocation sites were chosen, one on each side of Harper Lake Road, to minimize post-translocation movements of tortoises across that road. All tortoises west of Harper Lake Road will be moved to the Translocation Site in Section 25, on land owned by Mojave Solar. All tortoises east of Harper Lake Road will be moved to the Translocation Site in Section 4, in the BLM DWMA and ACEC. Translocation to a DWMA or ACEC is preferred by CDFG, and BLM has agreed to move the few potential tortoises from MSP to BLM land (L. Encinas, pers. comm.). While the Translocation Sites constitute the release areas for tortoises moved >500 m, each Translocation Site plus surrounding area to 6.5 km (per USFWS 2010b) collectively would be considered a Translocation Area. This area meets the following critical requirements for an appropriate translocation site:

- Acclimation by translocatees would be facilitated by site familiarity, since tortoises currently live outside the Project Area, very likely all in the Translocation Area.
- The Translocation Sites are within the same population as the Project Area, so genetic, morphological and behavioral integrity would be maintained.
- The Translocation Sites are immediately adjacent to, in, or very near areas receiving moderate protection from BLM.
- The Translocation Area is part of a broad expanse of occupied tortoise habitat, sufficient to accommodate a few translocated tortoises. Tortoise populations are currently well below carrying capacity throughout their documented range, including the western Mojave Desert, due to a long-term drought and other factors (Karl 2004 and 2010b, McLuckie et al. 2006, Boarman et al. 2008). Based on the pattern of rangewide and local declines, it is likely that tortoise densities in the Project vicinity have similarly declined, so long-term carrying capacity would not be exceeded by the addition of a few tortoises. USFWS (2010b) has estimated that

adult tortoise density in any Translocation Area should not exceed 130% of the current density, which was recently estimated as 2.7 tortoises/km² for the Fremont-Kramer DWMA and 6.3 tortoises/km² for the Superior-Cronese DWMA (USFWS 2009b). This would translate into a maximum allowable density (130%) of 3.5 and 8.5 tortoises/km², respectively, or the addition of one tortoise to the Fremont-Kramer DWMA and two tortoises to the Superior-Cronese DWMA.

However, this exercise is irrelevant for the MSP because, although one to few tortoises may be translocated from the Project Area, they would not be *added* to the population since they already live in the Translocation Area. In conclusion, then, since no tortoises are known to live on the Project Area, there is no chance that tortoise density in the Translocation Area would exceed the allowable 130% threshold or carrying capacity following translocation of tortoises from the Project Area.

The Translocation Site pens will be sufficiently large to support each tortoise pending disease testing results. Each will be a minimum of 165 x 165 ft (50 by 50 m), thereby providing adequate forage and sufficient habitat for a tortoise to find and/or construct adequate cover sites. Pens will be constructed using double-walled, 1 by 2 inch tortoise-proof fencing, installed as identified in Section 4.1, Project Area Fencing and Temporary Fencing, above. They will be separated by a minimum of 100 m so that tortoises will not be crowded once the fences are removed (if tortoises are seronegative) and tortoises fully released. Prior to Project Area clearance, pen design and an animal husbandry plan for penned tortoises will be approved by experienced personnel from an accredited American Zoological Association institution and approved by USFWS, BLM, and CDFG. While design will be pre-approved, pens will not be constructed until after that clearance pass on which tortoises are found, because it is highly unlikely that pens will be needed at all. All pens will be surveyed prior to and following their construction to ensure that no resident tortoises inhabit the pen.

4.2.3 Translocation Methods

All tortoises relocated or translocated from the Project Area will be measured, weighed, assessed for health, and affixed with a transmitter at the time of initial capture, and transported as described in detail in Section 3.0, Procedures Applicable to All Relocations and Translocations, above. Transmitted tortoises will be located daily the first week after transmitting and weekly thereafter until relocation or translocation.

All tortoises will be relocated or translocated at least one week before daily, midday temperatures are expected to exceed 95°F (35°C) air temperature (at 2 in) or 109°F (43°C) ground surface temperature, whichever is lower. This is expected to occur following the second clearance pass. No tortoise will be moved when air temperatures are expected to exceed 90°F (32°C) within three hours of release (USFWS 2010b).

All translocated tortoises will be rehydrated within 12 hours prior to release, via USFWS (2009a) methods.

All tortoises moved <500 m (1650 ft) will be placed in the shade of a shrub⁵ or at the entrance to a known burrow for that tortoise, and monitored as described in Section 4.2.5, Post-Release Tortoise Monitoring, below.

Any tortoise found further inside the Project Area than 500 m will be transmittered and monitored daily for one week to determine if it typically lives that far inside the Project Area or if the observed location was outside its core use area. If its burrows or core use areas are closer to the perimeter fence than 500 m, or outside the fence (i.e., the tortoise fencewalks), it will be relocated as identified above for tortoises moved < 500 m.

Any tortoise translocated >500 m will be placed in an individual quarantine pen in the relevant Translocation Site (see above), under a shrub or near an artificial burrow. Two artificial burrows, each at least 4 ft (1.2 m) long, will be constructed for each tortoise, using a gas-powered auger or shovel/plywood, per USFWS (2009a) guidance.

Moving tortoises from the Project Area to the Translocation Site following the second clearance pass in April will ensure that tortoises are moved well prior to lethal temperatures. Because blood samples must be collected on tortoises moved >500 m (see Section 4.2.4, Health Considerations, below) and blood sampling cannot occur prior to 15 May (USFWS 2010b)⁵, if tortoises were left on the Project Area until blood samples could be collected, then the spring translocation temperature window would be missed. If lab results are negative for exposure to *M. agassizii*, then the pen fence simply will be removed, thereby passively releasing the tortoise. This method ensures that tortoises are moved only once during the translocation process.

Juvenile tortoises, especially those under 4.4 inches (110 mm) in length, are highly subject to depredation by canids, badgers, and ravens, and require special consideration for successful translocation. Little is known about juvenile tortoise movements. Based on two studies of hatchling and/or juvenile tortoises, the mean distance translocatees moved in approximately one month was 521-723 ft (158-219 m; Hazard and Morafka 2002). For non-translocated hatchlings, the distance between nests and first-year hibernacula was 304-350 ft (92-106 m; TRW 1999b). Based on these values, as well as other data reported in these studies, a juvenile tortoise moved farther than 330 ft (100 m) may be outside its recent or familiar use area. For MSP clearance, if juvenile tortoises are moved within 330 ft of the capture location, where they may have site familiarity, they will be released under a shrub and monitored initially as described in Section 4.2.5, Post-Release Tortoise Monitoring, below. For distances >330 ft, they will be moved to the Translocation Site into a predator-proof enclosure, using 5-ft-tall “Non-Climb”, 2 by 4 inch vertical mesh fencing, buried at least 1 ft. and with avian netting over the top. The size of the enclosure would depend on the number of tortoises found, but would be a

⁵ In past relocation/translocation efforts, an artificial burrow has typically been constructed for tortoises. However, relocated and translocated tortoises do not use these burrows and it is anticipated that most tortoises removed from the Project Area will be relocated to areas where they have known burrows. Therefore, no artificial burrows will be constructed for relocated tortoises.

minimum of 20 ft in diameter, extending to 50 ft or more, as necessary, to accommodate more juvenile tortoises. (Morafka *et al.* 1997 successfully penned juvenile tortoises at the rate of 62-123 tortoises per acre (152-305 animals per hectare). After tortoises have become familiar with the site's odors and landmarks for at least two weeks, escape holes will be opened in the lower edge for tortoises to escape passively (e.g., Morafka *et al.* 1997). Modifications to the design and process may occur in response to predator interest in the enclosure or juvenile tortoise behavior in the enclosure, incorporating new and relevant head-starting techniques used at Twentynine Palms Marine Corps Air Ground Combat Center.

This Plan recognizes that a tortoise may be found in the Project Area during site grading or routine fence monitoring, at ambient temperatures that are higher than the USFWS translocation guidelines. In such cases, the disposition of the tortoise will be determined by the AB, in consultation with USFWS and CDFG. In any case, the tortoise will be captured, secured in an individual, sterilized box and temporarily placed in a quiet, climate-controlled environment (e.g., the onsite Project office). Depending on temperatures and other factors, it is possible that the tortoise could be affixed with a transmitter and relocated outside the Project Area or translocated into the Translocation Site the same day, when temperatures subside (or the following morning for juvenile tortoises), and monitored to ensure its safety. Options are provided in Table 1. If the tortoise would likely be harmed or die, it will be held in captivity at a location approved by USFWS and CDFG, away from other tortoises, to be released into the Translocation Site during the next available window. Other options will also be investigated. The goal of the translocation is to keep the tortoise in the population, in order to promote recovery.

4.2.4 Health Considerations

Health assessments will be conducted on all tortoises relocated or translocated during Project Area clearance, by an experienced biologist approved by the USFWS. No tortoise with clinical signs of mycoplasmosis will be relocated. Schumacher *et al.* (1997) observed that clinical signs had a high statistical correlation with positive serology (i.e., exposure to *Mycoplasma agassizii*). A mucous nasal discharge was the clinical sign that was the most reliable predictor (93% of tortoises with a mucous nasal discharge were seropositive), although it could be caused by pathogens other than *M. agassizii*. Furthermore, a purulent nasal discharge was the only clinical sign that was relatively objective; other clinical signs were far more subjective, were potentially present for other reasons, and reduced the statistical predictability of positive serology. For the Project, a purulent nasal discharge will be the threshold to identify a diseased tortoise, unless USFWS determines that other clinical signs should be used for diagnosing a diseased tortoise.

Tortoises moved <500 m (1650 ft) will only have visual health assessments. Tortoises moved >500 m will also have blood samples collected. Blood samples (no more than 2 cc) will be collected via standardized techniques of brachial or subcarapacial venipuncture (University of Florida, Department of Pathobiology, no date) to test for the presence of antibodies to *M. agassizii* and other pathogens. Whole blood will be

centrifuged and the plasma packaged on ice and sent overnight express freight to the University of Florida Mycoplasma Research Lab for analysis. USFWS (2010b) has determined that blood sampling on translocated tortoises cannot be collected until 15 May⁵. If this should change, then tortoises will be sampled as early as permitted. Only experienced, approved persons who have been previously permitted to conduct this work on desert tortoises will be permitted to collect the samples.

Desert tortoises relocated or translocated from the Project Area that have clinical signs of disease or are seropositive will be sent to the Desert Tortoise Conservation Center (DTCC) or other agency-approved facility where they will undergo further assessment, treatment, and/or necropsy. Mojave Solar will provide a flat fee of \$9,000 for each desert tortoise sent to the DTCC commensurate with the cost to provide housing, care, treatment, and other services for five years (\$3,000 for Year 1, \$1,500 for Years 2 to 5).

USFWS (2010b) and more recent communications (T. Engelhard, pers. comm. to A. Karl) have mandated that if a diseased or seropositive resident is within 1.5 km (0.9 mi) of a relocated tortoise or 6.5 km (4.1 mi) of a translocated tortoise, then the relocation site (or translocation site) must be moved. The rationale given is that relocated tortoises may move 1.5 km after relocation and translocated tortoises may move as much as 6.5 km. This rationale is highly unlikely to apply to MSP, since any tortoise that must be relocated or translocated from the Project Area is likely a transient; most would be moved only a few meters. Per USFWS (2010b) guidance, Mojave Solar will conduct a 100% coverage survey for all diseased or seropositive residents within 1.5 km of any release site for a relocated tortoise (Figure 4) and within 6.5 km of the translocation site to which a tortoise is translocated (Figure 5). However, recognizing the unusual, site-specific conditions for the Project, USFWS, CDFG, and BLM have agreed to consider alternatives for this measure based on the number and distance of tortoises actually moved.

Mojave Solar would conduct surveys for resident tortoises during the second clearance pass (assuming that tortoises have been observed inside the Project Area) based on locations of tortoises found inside the Project Area – these would determine release sites and if the Translocation Site is likely to be needed.

All resident tortoises within 1.5 km of a relocation site and 6.5 km of a translocation site will be processed (weighed, measured, described, photographed), marked with an epoxy number for future identification and their health assessed. If any tortoises from the Project Area are moved more than 500 m, then all resident tortoises within 6.5 km of the Translocation Site will be transmittered for follow-up blood sampling at the earliest date approved by USFWS, currently 15 May (USFWS 2010b). All transmittered residents will be located the first day following the transmitter attachment, every other day for two weeks to determine the tortoise's use area (for ease of future monitoring), and then according to the USFWS (2010b) schedule. If a resident tortoise has clinical disease signs or is seropositive following lab testing, the relocation site that is within 1.5 km or the Translocation Site that is within 6.5 km will be shifted to be outside of those respective

distances. If this cannot be accommodated, further coordination with the agencies will be needed.

4.2.5 Post-release Tortoise Monitoring

All relocated or translocated tortoises will receive immediate post-release visual monitoring as described for Project Area Perimeter Fencing in Section 4.1.5, Post-Release Tortoise Monitoring, above. Additionally, each will be located via telemetry for the next two days during tortoise activity temperatures to ensure that no tortoise is fence-walking or otherwise compromised. All tortoises in quarantine pens will be monitored according to the approved husbandry plan. A minimum monitoring effort will include checking twice daily for the first two weeks, or until fence-walking (should it occur) ceases, whichever is longest. Following this, all tortoises sequestered in pens will be checked daily via telemetry until serology results are returned and tortoises can either be released or transferred to an approved facility. All pen fences will be monitored daily to ensure that they are intact.

All relocated or translocated tortoises will become part of the five-year monitoring study, as described for Project Area Perimeter Fencing in Section 4.1.5, Post-Release Tortoise Monitoring, above.

4.2.6 Nest Relocation

Nest relocation and monitoring during Project Area clearance will follow the same procedures as outlined above for Project Area Perimeter Fencing in Section 4.1.6, Nest Relocation.

4.3 SCE Fiberoptics Construction, Construction Outside the Project Area, and Harper Lake Road

SCE's upgrades to their existing transmission line to accommodate telecommunications will be subject to all tortoise protection measures, including but not limited to pre-construction surveys, construction monitoring, and relocation, that are identical to those for construction of the perimeter fence in Section 4.1, Project Area Perimeter Fencing and Temporary Fencing, above, with the exception that no tortoises would be transmitted or included in a long-term monitoring program.

Although not anticipated, any other Project-related construction activities that occur in unfenced, native habitat will adhere to the same tortoise protection measures described for SCE telecommunications upgrades. Harper Lake Road will be the main access to the Project during both construction and operation. Tortoise exclusion fencing was previously installed on sections of this road, but it is incomplete. According to BIO-7 (CEC 2010), during construction a BM will drive this road at least every three hours during the desert tortoise activity period (approximately 1 April to 1 November). Outside of the active period, a BM will monitor the road in advance of peak morning and evening traffic. If possible, tortoises will be allowed to move off the road of their own accord;

follow-up monitoring will ensure that the tortoise will not re-enter the road. For tortoises that must be moved to protect them, they will be handled in accordance with the measures provided in Section 3.0 Procedures Applicable to All Relocations/Translocations, above. All tortoises will be placed in the deep shade of a large shrub with immediate follow-up monitoring as described for tortoises moved during Project Area fence construction (Section 4.1, Project Area Perimeter Fencing and Temporary Fencing, above).

4.4 Operations Phase

Tortoises observed during maintenance activities outside the Project Area fence or along the main access road by personnel leaving or entering the Project Site will not be disturbed or handled and will be allowed to move away of their own accord. Any maintenance or emergency/unexpected repairs outside the fence that require surface disturbance or heavy equipment will require the same protection measures described for Project Area fence construction in Section 4.1, Project Area Fencing and Temporary Fencing, above.

Because it is anticipated that the Project Area will be entirely devoid of vegetation following surface grading, (except for small, landscaped areas at the offices) there will be no areas where a tortoise could reside onsite. Therefore, any tortoise found during Project operations likely will have entered the Project Area through a gate or breach in the fence. It is likely, although not impossible, that any tortoise found during Project operations would not yet have constructed a burrow and would have entered the site only recently. Any such tortoise will be relocated, under supervision of the AB, to the nearest suitable, safe habitat outside the fence onto Project or BLM land adjacent to the Project. Because any tortoise found inside the Project Area is likely to be a transient, it is anticipated that the tortoise would seek a familiar burrow when released outside the Project Area. All tortoises will be placed in the deep shade of a large shrub and monitored as described for tortoises moved during Project Area fence construction (Section 4.1, Project Area Perimeter Fencing and Temporary Fencing, above). USFWS, CDFG, BLM, CEC, and DOE will be contacted and informed of the disposition when any desert tortoise is located within the solar field during operations.

In the event that surface temperatures are in excess of USFWS translocation temperatures, the tortoise will be secured in an individual, sterilized box and placed in a quiet, climate-controlled environment (e.g., the onsite Project office). Under supervision of the AB, the tortoise will be released in the late afternoon/early evening of the same day, when ambient temperatures subside. Juvenile tortoises will be released in the early morning to minimize depredation. All boxed tortoises or tortoises affixed with transmitters will be monitored periodically during the day and following release, to ensure their safety, according to methods described for perimeter fencing in Section 4.1.5 Post-Release Tortoise Monitoring, above.

It would be highly unlikely for a tortoise to be discovered wintered in a burrow on the site. However, if such an inactive tortoise were found, it would be handled and removed

from the site as specified for wintering tortoises in Section 4.1, Project Area Perimeter Fencing and Temporary Fencing, above.

4.5 Decommissioning and Reclamation Phase

During the Project decommissioning and reclamation phase, activities will take place both inside fenced areas and in unfenced native habitat. All techniques provided above for tortoise relocation and translocation during perimeter fence construction will apply to decommissioning activities outside fenced areas. Newer information will be incorporated, as appropriate, to optimize tortoise relocation.

4.6 Injured or Dead Tortoises

During construction or operations, any tortoise injured or killed will be reported by phone to USFWS, CDFG, BLM, DOE and CEC no later than noon on the first business day following the discovery of the injured/killed tortoise; a follow-up written report will be e-mailed or faxed within 48 hours. Prior to initiation of relocation/translocation, the DB will contact CDFG for the name of an approved veterinarian or wildlife rehabilitation clinic (per BIO-7 [CEC 2010]). If a tortoise is injured, the tortoise will be taken immediately to one of these facilities at the expense of the Project owner. If a tortoise is killed, it will be salvaged for necropsy.

5.0 Reporting

BIO-11 of the final CEC license (CEC 2010) requires that the Designated Biologist provide a report to the CEC within 30 days of completing Project Area clearance. This report will document how each of the desert tortoise mitigation measures in this Plan have been satisfied. At a minimum, the report will also document survey results, the capture and release locations of all desert tortoises found, immediate post-release monitoring, individual tortoise data, and other relevant data. These reports will be submitted to USFWS, CDFG, BLM⁶ and DOE; the AB in charge of relocation/translocation will approve these reports prior to submittal. Monthly and annual reports that document similar data, collected during all monitoring activities, will be prepared as part of the Designated Biologist's duties and submitted to the CEC, USFWS, CDFG, BLM and DOE.

For the post-relocation monitoring study, an annual report will be submitted to the USFWS, CDFG, BLM, CEC and DOE to document activities and analyze preliminary results. A comprehensive report will be conducted at the end of the monitoring program. Interim contact will be made (e.g., via e-mail or letter reports) if important findings could assist the resource agencies in desert tortoise recovery.

⁶ All reports relative to tortoises on BLM lands will be provided to BLM, as well as USFWS, CDFG, CEC, and DOE.

6.0 Funding

Mojave Solar will provide adequate funds to complete all work as described.

7.0 Literature Cited

- Barrett, S.L. 1990. Home range and habitat of the desert tortoise (*Xerobates agassizii*) in the Picacho Mountains of Arizona. *Herpetologica* 46:202-206.
- Blackford, A. USFWS, Ventura Field Office. 21 May 2010. Personal communication to A. Karl
- , W.B. Kristan, III, and A.P. Woodman. 2008. Neither here nor there: current status of Sonoran desert tortoise populations in Arizona. Paper presented at the 2008 Desert Tortoise Council Symposium, Las Vegas, NV.
- Brown, M.B. 2010. E-mail on blood sampling for ELISA testing and seasonal effects on immune systems to Kimberleigh Field, USFWS. 6 October 2010.
- Burge, B.L. 1977. Movements and behavior of the desert tortoise, *Gopherus agassizi*. M.S. Thesis, Univ. of Nevada, Las Vegas. 225 pp.
- California Department of Fish and Game. 2010. Comments from Eric Weiss and Tonya Moore on the Abengoa Draft Translocation Plan. E-mail to Heather Blair, Aspen Environmental.
- California Energy Commission. 2010. Commission decision on the Abengoa Mojave Solar Project. Docket No.09-AFC-5. 583 pp.
- Desert Tortoise Council, 1994 (rev. 1999). Guidelines for handling desert tortoises during construction projects. E.L. LaRue, Jr. (ed.) Wrightwood, CA.
- Duda, J.J., A.J. Krzysik, and J.E. Freilich. 1999. Effects of drought on desert tortoise movement and activity. *Jour. Wildlife Mgmt.* 63(4):1181-1192.
- Encinas, L. 17 November 2010. E-mail to C. Hammel-Smith, A. Karl, and A. Blackford.
- Englehard, T. USFWS, Carlsbad Fish and Wildlife Office. 24 September 2010. E-mail to A. Karl.
- Hazard, L.C. and D.J. Morafka. 2002. Comparative dispersion of neonate and headstarted juvenile desert tortoises (*Gopherus agassizii*): a preliminary assessment of age effects. *Chelonian Conserv. Biol.* 4(2):406-409.

- Holland, R. F. 1986. Preliminary descriptions of the terrestrial natural communities of California. California Department of Fish and Game, Nongame-Heritage Program. 155 pp.
- Karl, A.E. 1989. Investigations of the desert tortoise at the California Department of Health Services' proposed low-level radioactive waste facility site in Ward Valley, California. Unpub. rept. submitted to US Ecology and Ecological Research Services. 116 pp.
- . 1992. Annual report to the U.S. Fish and Wildlife Service for Permit No. PRT-746058. 12 pp.
- . 2004. Drought: acute effects and impacts to recovery of the desert tortoise. Paper presented at the 2004 Desert Tortoise Council Symposium, Las Vegas, NV.
- . 2010a. Mojave Solar Project desert tortoise clearances and relocation/translocation plan. Submitted to Mojave Solar, LLC. CEC Docket No. 09-AFC-5. 29 pp.
- . 2010b. Ridgecrest Solar Power Project. Analysis of population and species impacts to the desert tortoise, due to the siting of this project in its current location. Docketed 29 April 2010. 19 pp.
- and Resource Design Technology, Inc. 2007 Mesquite Regional Landfill. Initial desert tortoise clearance-October 2005. Submitted to the Los Angeles County Sanitation Districts, Whittier, CA. 28 pp plus attachments.
- Marlow, R. W., K. von Seckendorff Hoff, and P. Brussard. 1997. Management of wild tortoise populations is complicated by escape or release of captives. Pp. 479-480 *in* J. van Abbema (ed.), Proceedings: Conservation, Restoration, and Management of Tortoises and Turtles – an International Conference. Joint publ. of the New York Turtle and Tortoise Society and the WCS Turtle Recovery Program.
- McLuckie, A.M., M.R.M. Bennion, R.A. Fridell, and R. Radant. Status of the desert tortoise in the Red Cliffs Desert Reserve. Paper presented at the 2006 Desert Tortoise Council Symposium, Las Vegas, NV.
- Morafka, D.J., K.H. Berry, and E.K. Spangenberg. 1997. Predator-proof field enclosures for enhancing hatching success and survivorship of juvenile tortoises: a critical evaluation. Pp. 147-165 *in* the New York Turtle and Tortoise Society, Proceedings: Conservation, Restoration, and Management of Tortoises and Turtles – an International Conference.

- Mojave Solar, LLC. 2009. Mojave Solar Project Application for Certification. Submitted to the California Energy Commission, Sacramento, CA. August 31, 2009.
- Ninyo & Moore, 2006. Ninyo & Moore Geotechnical and Environmental Sciences Consultants (Ninyo & Moore), 2006. Geotechnical Reconnaissance Harper Lake Dairy Park, Lockhart, California. Prepared for Metcalf & Eddy. July 7.
- Nussear, K.E. 2004. Mechanistic investigation of the distributional limits of the desert tortoise, *Gopherus agassizii*. *Ph.D. Diss.* University of Nevada, Reno.
- O'Connor, M. P., L. C. Zimmerman, D. E. Ruby, S. J. Bulova, and J. R. Spotila. 1994. Home range size and movements by desert tortoises, *Gopherus agassizii*, in the eastern Mojave Desert. *Herp. Monogr.* 8:60-71.
- Schumacher, I.M., M.B. Brown, E.R. Jacobson, B.R. Collins, and P.A. Klein. Detection of antibodies to a pathogenic *Mycoplasma* in desert tortoises (*Gopherus agassizii*) with upper respiratory tract disease. *J. Clin. Microbiol.* 31(6):1454-1460.
- TRW Environmental Safety Systems, Inc. 1999a. Movement patterns of desert tortoises at Yucca Mountain. Unpubl. rept. to U.S. Department of Energy, Yucca Mountain Site Characterization Office, North Las Vegas, NV. Document No. B00000000-01717-5705-00049.
- . 1999b. Cover use and movement patterns of hatchling desert tortoises at Yucca Mountain, Nevada. Unpubl. rept. to U.S. Department of Energy, Yucca Mountain Site Characterization Office, North Las Vegas, NV. Document No. B00000000-01717-5705-00073. 11 pp.
- United States Department of Energy. 2010. Biological Assessment: Mojave Solar Project. Prepared by AECOM, San Diego, CA, for Mojave Solar, LLC. 110pp.
- United States Fish and Wildlife Service. 1992. Field survey protocol for any federal action that may occur within the range of the desert tortoise. Ventura, California Field Office.
- . 2009a. Desert tortoise field manual. Available online at (http://www.fws.gov/ventura/speciesinfo/protocols_guidelines/docs/dt/dt_fieldmanual)
- . 2009b. Range-wide monitoring of the Mojave Population of the desert tortoise: 2007 annual report. Desert Tortoise Recovery Office, Reno, NV.
- . 2010a. Comments on the draft Mojave Solar Project Desert Tortoise Clearance and Relocation/Translocation Plan from Ashleigh Blackford, USFWS, Ventura Field Office. 26 April 2010.

---. 2010b. Translocation of desert tortoises (Mojave Population) from project sites: plan development guidance. August 2010. Unpub. document. 11 pp.

University of Florida, Department of Pathobiology. No date. Serologic test for tortoise exposure to *Mycoplasma*. Unpub. doc. 5 pp.

Zimmerman, L.C., M.P. O'Connor, S.J. Bulova, J.R. Spotila, S. J. Kemp, and C.J. Salice. 1994. Thermal ecology of desert tortoises in the eastern Mojave Desert: seasonal patterns of operative and body temperatures, and microhabitat utilization. *Herp. Monogr.* 8:45-59.

APPENDIX 1. Sample Desert Tortoise Data Form

LIVE TORTOISE DATA FORM
HYUNDAI MOTOR AMERICA TEST TRACK PROJECT
CALIFORNIA CITY, KERN COUNTY, CALIFORNIA

OBSERVER Eli Berasker
PROCESSOR Karl
DATE 10-18-03
TIME (pst) FOUND 1600 on 10/17/03
START PROC. 0837 found / 1003 - retr. from burrow
FINISH PROC. 149 10/19
T_a 22.7°C T_b 23.9°C WIND 0-1 mph T_{scn} 22.9
PPT/CC 90% cirrostratus

TORTOISE # H-08
TRANSMITTER: TYPE NOL # 87159
DATA LOGGER # NONE

BEHAVIOR (check one, elaborate as necessary):

IN BURROW, FACE IN (end ~167cm)
IN BURROW, FACE OUT
ENTERING BURROW
RUNWAY, EXITING
BASKING
TRAVELLING when found on 10/17
UNDER SHRUB IN SHADE
UNDER SHRUB, FACE INTO STEM
OTHER T-P out

DISEASE INDICATIONS (elaborate as necessary; grade severity of abnormal conditions: (1) mild; (2) moderate; (3) severe)

BEAK/NARES (answer all):

GREEN NO DRY ✓ OCCLUDED NO
NASAL EXUDATE NO
SEROUS
NON-SEROUS (severity, color, quality)

CAKED DIRT ON BEAK/FORELIMBS NO

EXUDATE ON FORELIMBS NO

BREATHING (ck all that apply; describe/grade abn. cond):

CLEAR ✓ WHISTLING
OBSTRUCTED

EYES (ck all that apply; describe/grade abn. cond.):

CLEAR, BRIGHT ✓ MOIST LIDS NO
SWOLLEN OR SUNKEN NO

DISCHARGE NO
CONJUNCTIVITIS NO

CHIN GLANDS DRAINING? NO

ORAL CAVITY (ck all that apply; describe/grade abn. cond):

COLOR Pale pink
LESIONS NO
ODOR NO

ATTITUDE (check all that apply)

STRONG ✓ ACTIVE
QUIET, WITHDRAWN ✓
RELAXED LETHARGIC, WEAK

SHELL (ck all that apply; describe/grade abn. cond.):

NORMAL ABNORMALLY SCALEY Pl. scales along midline to ant. wh. 1, 2, nodal
LESIONS TO BONE/BLOODY LOSS OF KERATIN IN SMALL "divots" - may be lesions. Bone shows along humerus + pectoral

EXTERNAL PARASITES (answer all that apply) # seams +

NONE ✓ TYPE # LOCATION

these seams are deep; appear to have some keratin loss. Ant. margins 1+2 + nodal also seem abnormally scaley (1-2)

Both front + leg surfaces have experienced some loss of scales, esp. L. Prob. chewing.

CAPTURE LOCATION:

GENERAL LOCATION NE 1/4 of S16

UTM: E 0404614 N 3878932

RELEASE LOCATION:

GENERAL LOCATION

UTM: E N

GENDER ♀

If unknown, check the following indicators and elaborate:

TAIL LENGTH PYGAL

ABDOMINALS

ANALS WIDTH OF FOREFOOT

CHIN GLANDS

MASS (g): INITIAL 3790 FINAL (w/transmitter) 3815

VOID: URINE? SCAT VISCOSITY

COLOR PPT

TOTAL MASS OF EXCRETA (g)

MEASUREMENTS (mm):

MCL 280 PLN 247.5 HT 110
WIDTH M7/8 (seam) 214 GW 222 @ PM 6
WIDTH M6 (mid) if GW is not M5, M6, or M7 X

SHELL WEAR CLASS 6


SUPER- or SUB-NUMERY MARGINALS? NO, but extra vet

NUMBER OF GROWTH RINGS Ant + coact

GENERAL TORTOISE SHAPE (check one):

☐ ☒ ☐
PHOTO: ROLL 1 FRAMES 17-19
17 - Pleation L.H.
18 - Ant. pleation 19 - foot
20 - C w/ transmitter
21 - " " "
22 - " " "
23 - " " "


DIAGRAM TRAUMA AND ANOMALIES:




FIGURES



Final MSP Desert Tortoise Translocation Plan /January 2011
 P:\2008\08090191 Harper Lake Alvaros AF\04.0 Documents_Reference\4.7 Draft Documents\Figure\2009 Botanical Survey Ltr Rpt -corona-bennett\ 7/23/09



Source: NAIP 2005; USFWS 2006; BLM 2009; Mojave Solar, LLC 2009; San Bernardino County 2009



Final MSP Desert Tortoise Translocation Plan /January 2011

Path: P:\2009\09090191 Harper Lake Abongos APC\6.0 GIS\6.2 Project Directory\6.2.5 Layout\Compliance\DET0\veg_cvr.mxd, 01/17/11, BogonkaM

Figure 2
Mojave Solar Project Vegetation Cover and Special Management Areas




Figure 3
Desert Tortoise Sign




Figure 4
Relocation Sites and Surveys for Diseased Resident Tortoises




Figure 5
Translocation Sites and Surveys for Diseased Resident Tortoises

Final MSP Desert Tortoise Translocation Plan /January 2011

Path: P:\2008\0000191 Harper Lake Abengoa APC\6.0 GIS\6.2 Project Directory\6.2.3 Layout\Compliance\DETOTranslocation Sites_half.mxd, 01/18/11, BugonhoM

APPENDIX M-2

COMMON RAVEN MONITORING, MANAGEMENT, AND CONTROL PLAN

Common Raven Monitoring, Management and Control Plan

Mojave Solar Project

Raven Control Plan



Prepared on behalf of:

Mojave Solar, LLC

Prepared by:

AECOM
1420 Kettner Boulevard, Suite 500
San Diego, California 92101
(619) 233-1454

December 2010

Common Raven Monitoring, Management and Control Plan

Mojave Solar Project

Table of Contents

1.0	INTRODUCTION	1
1.1	Purpose and Objectives	1
1.2	Project Background	2
1.3	Conditions of Concern – Raven Subsidies or Attractants	3
1.4	Roles and Responsibilities	5
2.0	REGIONWIDE RAVEN MANAGEMENT AND MONITORING PROGRAM.....	5
3.0	PROJECT DESIGN FEATURES, PROJECT-SPECIFIC CONTROL MEASURES, AND IMPLEMENTATION OF PROJECT DESIGN FEATURES	6
3.1	Construction	6
3.1.1	Evaporation Ponds	6
3.1.2	Raven Perching, Roosting, and Nesting Sites.....	6
3.1.3	Ponding Water	7
3.1.4	Raven Food Sources from Soil Disturbance and Roadkill	7
3.1.5	Human Food and Waste Management.....	7
3.2	Operations	7
3.2.1	Evaporation Ponds	8
3.2.2	Raven Perching, Roosting, and Nesting Sites.....	8
3.2.3	Ponding Water	8
3.2.4	Raven Food Sources from Soil Disturbance and Roadkill	8
3.2.5	Human Food and Waste Management.....	9
4.0	RAVEN MONITORING STRATEGIES	9
4.1	Construction Phase	9
4.2	Operation Phase	9
4.2.1	Ongoing Monthly Raven Monitoring	10
4.2.2	Breeding Season Raven Surveys.....	11
4.3	Nest Removal	11
4.4	Decommissioning and Restoration Phase	12
5.0	ADAPTIVE MANAGEMENT	12
5.1	Definition	12
5.2	Adaptive Management Triggers	12
5.3	Adaptive Management Measures	13
5.3.1	Control Practices	13
6.0	REPORTING	14
7.0	REFERENCES	15

ATTACHMENT A. Figures 1–4

Common Raven Monitoring, Management and Control Plan

Mojave Solar Project

This page intentionally left blank.

Mojave Solar Project

1.0 INTRODUCTION

In response to the Final Decision issued by the California Energy Commission (CEC) on September 15, 2010, for the Mojave Solar Project (MSP or Project) this Common Raven Monitoring, Management, and Control Plan (Raven Control Plan or Plan) has been prepared for approval by CEC, the U.S. Fish and Wildlife Service (USFWS), and California Department of Fish and Game (CDFG) as specified in the Condition of Certification (COC) Bio 18. This Plan has been developed to expand on the components already addressed in the Application for Certification (AFC) in Avoidance and Minimization Measure DT-18 (Abengoa 2009: 5.3–45). The purpose of this Plan is to address concerns related to raven (*Corvus corax*) predation on hatchling and juvenile desert tortoise (*Gopherus agassizii*; DT) resulting from the proposed MSP. The Plan will also address similar concerns related to Mohave ground squirrel (*Spermophilus mohavensis*; MGS) depredation from ravens. The following section will provide a discussion of the Project background, the Plan's purpose and objectives, and the conditions of concern associated with the proposed MSP.

1.1 Purpose and Objectives

This section introduces the Project background, purpose, objectives, and conditions of concern related to raven monitoring and control in the vicinity of the MSP.

The establishment of an effective management plan and set of control measures is intended to ensure that the proposed MSP does not create new subsidies such as new sources of food and water, which would increase the presence, survival, or reproductive success of ravens that might be attracted to the Project area. Common ravens are known to prey on hatchling and juvenile DT, which is listed as threatened under the Federal Endangered Species Act (FESA) and California Endangered Species Act (CESA). The purpose of the Raven Control Plan is to establish management strategies and Project-specific control measures to avoid, minimize, and mitigate potential Project-related raven depredation of DT within the Project area. The specific objectives of the Raven Control Plan are as follows:

1. Identify Project activities or features that have the potential to attract ravens to the Project area (conditions of concern) and identify ways to eliminate or reduce raven attractants.
2. Discuss how the Project will implement Project design features (PDFs) and other control measures to manage the specific conditions of concern identified for the MSP.
3. Document the successes and failures of PDFs and other measures set forth in this Plan.
4. Establish criteria that will trigger modifications to PDFs and other control measures through adaptive management principles.
5. Define additional control measures and how they would be implemented if the monitoring results indicate that additional controls are necessary.

To ensure that the purpose and objectives of this Raven Control Plan are being achieved, management controls and monitoring practices will be implemented to regulate and track raven activity within the Project area. The qualitative data derived from this effort will be used to evaluate the successes and failures of the PDFs, as well as the other raven management control measures implemented for the MSP.

The Raven Control Plan designed for the MSP site will work in concert with the USFWS rangewide raven monitoring and control program to help monitor and control raven populations within the MSP site and adjoining regions.

Mojave Solar Project

1.2 Project Background

The Abengoa Mojave Solar Project (AMSP or Project) is a solar electric generating facility to be located on approximately 1,765 acres in unincorporated San Bernardino County, California, approximately 26 miles northwest of Barstow. Mojave Solar LLC, a subsidiary of Abengoa Solar Inc., (Abengoa or ASI) will own and operate the project. ASI filed an Application for Certification (AFC) with the California Energy Commission (CEC) for the Project on August 10, 2009. The CEC issued a Final Permit Decision adopting the Presiding Member's Proposed Decision (PMPD) to recommend licensing the project on September 8, 2010.

The Project site is accessed by Harper Lake Road, which is located approximately 20 miles west of Barstow along the Highway 58 corridor. The Project site is approximately six miles north of where Harper Lake Road intersects with Highway 58. See the regional map (Figure 1) and a vicinity map (Figure 2).

The project site is comprised of private property historically used as the Lockhart Ranch complex. The site once served as an agricultural and cattle center and included farming activities that used flood and pivot system irrigation.

The Project will implement well-established parabolic trough technology to heat a heat transfer fluid (HTF). The heated HTF will generate steam in solar steam generators (SSGs), and the steam will then be expanded through a steam turbine generator (STG) to produce electrical power.

The Project will have a combined nominal electrical output of 250 megawatts (MW) from twin, independently-operable solar fields (Alpha and Beta), each feeding a 125-MW power island. The Alpha site is approximately 950 acres in size, and the Beta site is approximately 815 acres. Approximately 70 percent (%) of the total project area will consist of solar fields. Approximately 3% of the site will be occupied by the power blocks, with the remaining 27% consisting of drainage improvements, evaporation ponds, a substation, and other common elements. The electrical output from the Alpha and Beta sites will join at an on-site transmission line interconnection substation to form one full-output transmission interconnection. The power generated by the project will be transmitted to Southern California Edison's (SCE's) transmission grid through SCE's existing 230-kilovolt (kV) Kramer-Cool Water #1 transmission line. The entire site perimeter will be fenced. The layout of the Alpha and Beta facilities, and the associated drainage channels, are shown in Figure 3.

The sun will provide 100% of the power supplied to the Project through solar-thermal collectors; no supplementary fossil-based energy source (e.g., natural gas) is proposed for electrical power production. However, each power island will have a natural-gas-fired auxiliary boiler to provide equipment freeze protection and HTF freeze protection. The auxiliary boiler will supply steam to HTF heat exchangers as needed during offline hours to keep the HTF in a liquid state when ambient temperatures fall below its freezing point of 54 degrees Fahrenheit (°F). Each power island will also have a diesel engine-driven firewater pump for fire protection and a diesel engine-driven backup generator for power plant essentials.

The Project will use wet cooling towers for power plant cooling, and the project owner owns adjudicated water rights for this purpose. Water for cooling tower makeup, process water makeup, and other industrial uses such as Solar Collector Array (SCA) washing will be supplied from onsite groundwater wells drawing from these water rights and will also be used to supply potable water. A packaged water treatment system will be used to treat the water to meet potable standards since the source is brackish.

Mojave Solar Project

A sanitary septic system and onsite leach field will be used to dispose of sanitary wastewater at each power island. Project cooling water blowdown will be piped to lined, onsite evaporation ponds for each plant area. The ponds will be sized to retain all solids generated during the life of the plant. However, if required for maintenance, dewatered residues from the ponds could be sent to an appropriate offsite landfill as non-hazardous waste.

Natural gas for the Project's ancillary purposes, such as the auxiliary boilers, space heating, and the like will be supplied by a Southwest Gas Corporation (SGC) owned pipeline that runs to the Project boundary near the Alpha power island. No offsite pipeline facilities are proposed as a part of this Project.

Construction of the AMS facility, from site preparation and grading to commercial operation, is expected to take place approximately 2-1/2 years. Commercial service is expected by winter of 2013. The AMS project has an expected operating life of between 30 years to 40 years. Whenever the facility is closed, whether temporarily or permanently, the closure procedures outlined in the CEC Decision will ensure compliance with applicable laws, ordinances, regulations, and standards (LORS).

Although certain features of the proposed Project (i.e., evaporation ponds, support structures, substations) have the potential to offer human-provided subsidies of food, water, and nest sites that may increase the attraction and presence of common ravens within the Project area, these features currently exist on the adjacent SEGS VIII and IX facilities. As described in the AFC (Abengoa 2009) prepared for the Project, DT have been observed within and near the Project area; therefore, the proposed Project has the potential to indirectly impact DT populations within the Project area. This Raven Control Plan describes effective management mechanisms to control the presence of ravens within the Project area.

1.3 Conditions of Concern – Raven Subsidies or Attractants

Project-specific activities and/or features that attract or subsidize ravens are called "conditions of concern." These conditions have the potential to increase raven presence and/or use of resources within the Project area. Construction and operation of the MSP would introduce raven subsidies or attractants similar to the existing SEGS facility immediately to the northwest of the MSP. Approximately 75% of the existing vegetation within the current Project area is either fallow or active agricultural habitat. These habitat types currently provide subsidies that exist due to agriculture (e.g., fresh water, rodents, and rabbits killed during harvesting). These habitats will be removed by the implementation of the Project. With appropriate measures to reduce the attractiveness of any of the conditions of concern below, the Project will be able to limit the attractiveness of the site to ravens after Project implementation. The following five conditions of concern are associated with the MSP:

1. Availability of water from evaporation ponds;
2. Potential creation of new perching/roosting/nesting sites for ravens;
3. Temporary water ponding potential from dust suppression associated with construction, operation, and maintenance;
4. Raven food sources from soil disturbance (rodents, insects, etc.) and roadkill associated with construction activity; and
5. Human food and waste management.

Common Raven Monitoring, Management and Control Plan

Mojave Solar Project

Each of these conditions of concern is defined in more detail below to ensure that appropriate PDFs and control measures are established and implemented for the MSP.

Evaporation Ponds

The proposed Project includes four evaporation ponds, two for each plant unit's power block, that will collect blowdown water from the cooling towers. In addition to these evaporation ponds, water is also periodically available within marsh habitat within Harper Dry Lake. While the groundwater that historically supported the marsh habitat within the lake has largely been depleted by agricultural activities, there is a small amount of marshland in the southwest corner of the lake that is largely supported by runoff from farms. A reduction in agricultural activities within the area has reduced the amount of water to the lake. The Bureau of Land Management (BLM) set up an agreement for the existing SEGS VIII and IX facilities that provides pumped water to the lake to maintain marshland habitat. Water is also currently available to ravens from existing irrigation in the active agricultural fields in the Project area. While water is currently available near the site, additional water sources are likely to benefit the regional raven population.

Raven Perching, Roosting, and Nesting Sites

Ravens often nest and perch on power towers, telephone poles, buildings, billboards, fences, abandoned vehicles, freeway or railroad overpasses, and light posts, and large communal roosts are known to form on transmission towers (Boarman 1993). Therefore, Project components such as tower structures, fencing, transmission poles and lines, and support structures will introduce new elevated perching sites.

Ponding Water

As discussed above, water is a critical resource for ravens in the desert. However, water is currently available in the immediate Project area (see above). Dust-suppression activities occurring during the construction phase of the MSP have the potential to create sources of free or standing water within the Project area. Ponding water may occur as a result of water being applied to newly graded areas, construction rights-of-way, dirt roads, trenches, spoil piles, and other areas of ground disturbances to reduce dust emissions and erosion of topsoil. During operation of the MSP, deionized water will be used to wash mirrors; however, the amount of water used will be minimal and is not anticipated to result in ponding water on site. During rain events, water will collect in the drainage channel on site, though is expected to flow into Harper Lake due to the slope of the channel. Landscaping, if any, will incorporate xeriscaping techniques to minimize the use of irrigation that might provide temporarily ponded water.

Raven Food Sources from Soil Disturbance

The operation of heavy equipment during the construction, decommissioning, and restoration phases of the MSP will cause soil disturbance within the Project area. This soil disturbance could potentially "unearth" and expose natural food sources such as rodents and insects. Since ravens scavenge roadkill, they may be drawn to the soil disturbance areas to prey on unearthed, injured, and dead animals.

Human Food and Waste Management

Ravens scavenge refuse at landfills for food and obtain food subsidies at sewage ponds, open dumpsters, agricultural fields, feedlots, parks, and picnic areas (Boarman 2003). In addition, dumpsters with food waste can attract ravens and small mammals (e.g., rodents) that may

Common Raven Monitoring, Management and Control Plan

Mojave Solar Project

become an additional food source for ravens. Implementation of the MSP will result in increased food and waste generation in the Project area, so proper waste management will be conducted to prevent the creation of subsidies that could attract ravens to the site.

Landscaping

Any landscaping could provide food (insects and rodents), water (irrigation for landscaping), and perching. Landscaping plans, therefore, would incorporate xeriscaping techniques to avoid the use of irrigation and would avoid using trees that would provide roosting and nesting opportunities.

1.4 Roles and Responsibilities

Prior to the initiation of construction activities, to ensure that all conditions of this Raven Control Plan are being met, Mojave Solar will assign a Designated Biologist (DB) to the MSP. This section describes the roles and responsibilities of the DB, as well as the required qualifications for the position.

Designated Biologist

Prior to the initiation of construction activities, Mojave Solar will be required to designate a DB to the Project. (The DB will be the same as the Project Authorized Biologist [AB] discussed in the AFC.) Mojave Solar will submit the resume of the proposed DB, with at least three references and contact information, to the CEC Compliance Project Manager (CPM) for approval in consultation with CDFG and USFWS.

The DB will have the following background and training:

- Bachelor's degree in biological sciences, zoology, botany, ecology, or a closely related field, and 3 years of experience in field biology or current certification of a nationally recognized biological society, such as The Ecological Society of America or The Wildlife Society.
- At least 1 year of field experience with biological resources found in or near the Project area.
- Be aware of the latest information on the USFWS protocols and guidelines for DT.
- Have a thorough and current knowledge of DT behavior, natural history, ecology, and physiology, and demonstrate substantial field experience.

Mojave Solar will ensure that the DB performs the activities specified in the Plan. In addition, Mojave Solar will also designate an alternate biologist with the same qualifications as the DB, outlined above. The CPM, in consultation with CDFG and USFWS, could also appoint a DB without the above-mentioned qualifications if the candidate is determined to be otherwise qualified with the appropriate training and background to effectively implement the Raven Control Plan.

2.0 REGIONWIDE RAVEN MANAGEMENT AND MONITORING PROGRAM

MSP will contribute to the USFWS regional raven management and monitoring program to offset the MSP's cumulative effects on DT due to raven predation. Mojave Solar will contribute approximately \$105 per acre of land to be permanently disturbed to the fund to avoid, minimize,

Mojave Solar Project

and mitigate potential impacts to DT resulting from increased raven predation associated with implementation of the MSP. It is anticipated that the funds contributed by Mojave Solar would be held by the National Fish and Wildlife Foundation established under the USFWS regional raven management program until needed to implement the regionwide program.

3.0 PROJECT DESIGN FEATURES, PROJECT-SPECIFIC CONTROL MEASURES, AND IMPLEMENTATION OF PROJECT DESIGN FEATURES

To reduce the potential Project impacts to DT from common ravens, it is imperative that the PDFs (i.e., those features that are built into the Project's physical design and functioning) eliminate or mitigate any subsidizing of ravens with water, nest sites, food, or other resources. This section describes the PDFs, management practices, and Project-specific control measures that have been established to ensure that activities associated with the MSP during both the construction and operation phases do not create new subsidies that will increase the presence or attraction of ravens to the Project area. These management practices specifically address the five basic conditions of concern identified in Section 1.4. These are divided into the construction phase of the MSP (Section 3.1) and the operation phase of the MSP (Section 3.2).

3.1 Construction

Impacts associated with the construction phase of the MSP are considered to be more temporary than operational impacts. As such, temporary management practices can be implemented to effectively preclude and/or minimize the potential to attract additional ravens to the Project area. Temporary measures include best management practices (BMPs) during construction such as trash containment and removal from the construction site, limited application of water to the site, and removal of road kill. Worker education will be implemented to ensure that all food and waste is properly stored. Mojave Solar will monitor the site during construction to determine raven use and if deterrent or hazing techniques (detailed in 6.3.1) are needed. Hazing techniques involve the diligent application of a number of visual and/or auditory devices designed to scare birds and create an integrated system of negative stimuli to reduce the attraction of birds to an area. Monthly reports will be submitted outlining the raven use of the site, whether control measures are working, and recommendations.

3.1.1 Evaporation Ponds

Rainwater may collect in the four onsite evaporation ponds during the construction phase of the MSP. Given the scarcity of water resources in the desert, ravens could be drawn to this new water source. However, it should be noted that Harper Dry Lake is located adjacent to the Project area, which includes a limited water supply and marsh habitat within the southwest corner of the lake, and currently supports raven (eBird 2010). During construction monitoring, Mojave Solar will monitor for the presence of ravens and, if ravens are identified to be present at evaporation ponds, hazing techniques will be used to discourage use (mentioned in 6.3.1). If unsuccessful, additional or alternative methods will be implemented, as discussed in Section 5.0, "Adaptive Management."

3.1.2 Raven Perching, Roosting, and Nesting Sites

Equipment and/or materials associated with construction of the MSP may provide temporary perch, roost, or nest sites for ravens within the Project area. During construction monitoring, Mojave Solar will monitor raven presence and, if ravens are found perching, roosting, or nesting

Mojave Solar Project

on building materials, equipment, waste piles, or other construction debris, hazing techniques will be used to discourage use. During construction, if ravens are found building a nest on any of the Project components, the nest should be removed. If the nest is not detected until young are present, the birds will be allowed to complete their nesting cycle and then the nest will be removed. If ravens are found to be attracted to certain debris piles or other construction elements, attempts to modify or move the attractant will be made, and the situation will be documented.

3.1.3 Ponding Water

The application rates of water for dust-suppression activities will be predetermined to minimize excessive application and curtail ponding water within the Project area. Soil infiltration and evaporation rates will be used to determine the appropriate application amount and frequency. In the vicinity of the water truck refill area, water will run off into a collection tank or other system that will preclude surface pooling. Mojave Solar will monitor areas to make certain water does not puddle for long periods (more than 1 hour) and make recommendations for reduced water application rates, as necessary.

3.1.4 Raven Food Sources from Soil Disturbance and Roadkill

Ravens are scavengers and are well known for eating animals that have been killed along roads and highways (Boarman and Heinrich 1999). In fact, roadkill is considered to make up a substantial portion of a raven's diet. This food source facilitates increased raven nesting near roads and highways in areas that might otherwise offer little food (Kristan et al. 2004).

The operation of heavy equipment during the construction, decommissioning, and restoration phases of the MSP will cause soil disturbance within the Project area. This soil disturbance will "unearth" and expose natural food sources such as rodents and insects. Construction monitoring conducted by Mojave Solar will include observations of the MSP site, as well as access roads, to ensure that food sources are properly disposed of within containers that are not accessible to ravens.

3.1.5 Human Food and Waste Management

During the construction phase of the MSP, a trash abatement program will be prepared to ensure that trash and food items are contained in closed, secured containers on the MSP site and removed weekly to reduce potential food sources to ravens and other scavengers. Biweekly observations of the construction site and access roads will ensure proper disposal of all trash and roadkill. These observations will be included in the monitoring report. If it is found that the waste containers are not working to deter ravens from scavenging, alternative containers will be used to ensure that scavenging ceases to occur. In addition, the Worker Environmental Awareness Program (WEAP) will assist in reinforcing with workers that no trash or roadkill that might attract DT predators will be left for ravens.

3.2 Operations

Impacts associated with the operations phase of the MSP are more long term and require the implementation of ongoing PDFs and management practices for the life of the Project. If, through monitoring, it is determined that these PDFs or management practices are not effective in accomplishing the goal of this Raven Control Plan, modifications to these practices and/or additional measures will be implemented through adaptive management and monitored to ensure

Common Raven Monitoring, Management and Control Plan

Mojave Solar Project

the Plan's purpose and objectives are being met. All information will be recorded and presented in the annual report.

3.2.1 Evaporation Ponds

Because the ponds need to remain uncovered to maximize evaporation rates, a series of avian deterrence measures such as the BirdAvert system are being considered for incorporation into the design and operation of the evaporation ponds. The operational design of the ponds is described in detail in the MSP Evaporation Pond Monitoring and Remediation Action Plan (AECOM 2009).

Other options include the use of antiperching devices placed strategically along the perimeter of the ponds to exclude ravens and other birds from accessing the edge of the ponds to drink water. These design features will make it difficult for perching birds (e.g., ravens) and/or shorebirds and wading birds to access the water. Netting of the pond may also be considered if other design measures do not prove to be effective.

The DB will be responsible for making qualitative observations on the relative success of the deterrent(s) at each pond and providing recommendations for future improvements in monthly reports, which will be submitted to CPM, including adapting the current configuration of the antiperching devices to maximize deterrence.

3.2.2 Raven Perching, Roosting, and Nesting Sites

PDFs that will be considered to reduce raven perching, roosting, and nesting are physical bird deterrents such as bird spikes, plus auditory and visual deterrents. In addition, nest removal will occur in conjunction with monitoring, as discussed below in Section 5.3. Under specific circumstances, the Animal and Plant Health Inspection Service – Wildlife Services (APHIS–WS) is authorized to remove “offending” ravens. “Offending” ravens are ravens that are known to be depredating DTs. The purpose of this activity is to reduce or eliminate predation of DT by common ravens within the Mojave Desert in San Bernardino, Riverside, and Kern counties in California. Mojave Solar or DB will notify USFWS of ravens that show evidence of depredating tortoises (USDA 2009).

3.2.3 Ponding Water

The application rates of water for dust-suppression activities will be predetermined to minimize excessive application and curtail areas of ponding water within the Project area. Soil infiltration and evaporation rates will be used to determine the appropriate application amount and frequency. Mojave Solar will monitor areas to make certain water does not puddle for long periods (more than 1 hour) and make recommendations for reduced water application rates, as necessary, to adjust for seasonal changes. During operations, deionized water will be used to wash mirrors; however, the amount of water used will be minimal and is not anticipated to result in ponded water on site.

3.2.4 Raven Food Sources from Soil Disturbance and Roadkill

Operational activities associated with the MSP will not result in new ground or soil disturbance. As such, potential food sources for ravens will not be unearthed and no additional PDFs related to this issue are necessary.

Mojave Solar Project

Mojave Solar will document and remove any roadkill observed during the regular monitoring during Project operations (see below). Areas observed will include the MSP site, the associated paved and dirt access roads, staging areas, and/or any other Project area facilities that may support vehicular traffic, potentially extending to Harper Lake Road, if necessary. In addition, MSP operations staff will notify the proper Mojave Solar representative daily if roadkill is observed within these areas.

3.2.5 Human Food and Waste Management

The trash abatement program developed for the construction phase will also include operational measures to be implemented for the life of the Project. Trash and food items will be contained in closed, secured containers and removed weekly to reduce the potential attraction of ravens to the site. Mojave Solar will continue to ensure that these practices are enforced and make recommendations for improvements, where applicable, as discussed in Section 6.0.

4.0 RAVEN MONITORING STRATEGIES

This section describes the monitoring practices that will be performed as part of this Raven Control Plan. Both qualitative and quantitative monitoring activities will be used to evaluate the effectiveness of the PDFs and the other raven management and control measures implemented for the MSP. This monitoring program will be based on observations and performed during both the construction and operation phases of the MSP in an effort to record and evaluate any changes in raven activity and populations.

4.1 Construction Phase

During the construction phase of the MSP, Mojave Solar will perform reconnaissance-level surveys in the Project area at biweekly (i.e., once every two weeks), or more frequently as needed. Initially and periodically, the DB will assist Mojave Solar to ensure that monitoring objectives are being achieved. Mojave Solar will specifically focus survey efforts on the following Project features:

- Evaporation ponds,
- Waste disposal areas,
- Built structures,
- Equipment staging and storage areas,
- Locations where water will be applied to control dust and erosion,
- Potential nest sites, and
- Areas where there have been surface and soil disturbances.

Monitoring of the Project area will record when and how ravens are hazed and where problem areas occur. Mojave Solar will take note of the general activity of the ravens (i.e., flying, perching, nesting, and scavenging) as well as the general location of the observed ravens. Perching sites will be identified and actions taken to discourage future use will be recorded and monitored to determine success. Any nesting locations will be documented and uninhabited nests will be removed pursuant to methods set forth in Section 4.2.2 of this Plan.

4.2 Operation Phase

During the operation and maintenance phase of the MSP, Mojave Solar, in coordination with the DB, as appropriate, will perform monthly reconnaissance-level surveys at the MSP site for the

Mojave Solar Project

first two years of the Project, unless it is determined that fewer surveys are necessary. In addition, annual breeding season monitoring will be conducted at the MSP in perpetuity. Details pertaining to these monitoring requirements are discussed in detail below.

4.2.1 Ongoing Monthly Raven Monitoring

Mojave Solar will conduct monthly surveys, monitoring raven activity for the first 2 years of Project operation, beginning when the Project becomes operational. Mojave Solar will be accompanied by the DB during the first four surveys, and periodically thereafter to facilitate appropriate data collection. The DB will also periodically look at data sheets and discuss the monitoring with Mojave Solar to ensure that monitoring objectives are being achieved. After the first 2 years of Project operation, surveys will be conducted twice during the breeding season for at least 1 year out of every 5 years into perpetuity, unless results indicate more frequent or less frequent monitoring is appropriate.

Survey locations will be identified by the DB based on Project features that may influence raven presence, activity, and behavior by potentially allowing perching, roosting, and nesting opportunities or by providing other subsidies such as food and water. These Project features include tower structures, transmission poles and lines, and support structures, as well as waste disposal facilities and evaporation ponds, and may occur both inside and outside of the Project footprint, depending on access. The DB will identify up to twelve permanent sampling points. This may include the evaporation ponds, parking areas, administration buildings, and along fence lines. If it is determined that, with a reduction of points, all important areas can still be viewed, the number of permanent sampling points can be reduced, with the concurrence of CEC, CDFG, and USFWS. Points would be located within areas that have the greatest likelihood of attracting ravens. Figure 4 shows an example of how these permanent sampling locations may be set up.

The evaporation ponds will be monitored as described in this Plan and as outlined in the Evaporation Pond Monitoring/Remediation Action Plan (AECOM 2009). Overlapping surveys for both plans will be performed concurrently.

At each determined survey point, Mojave Solar will conduct a 5-minute sampling session to observe and listen for ravens. Raven sightings will be recorded along with the type of behavior (e.g., perched, flying, nesting, scavenging) and distance and direction from the survey point. If the raven(s) is found perching or nesting, detail will be recorded pertaining to the type of perch (structures, fences, etc.). Other data to be collected will include the survey start/stop time and weather (including temperature, average wind speed, and percent cloud cover). In addition, the location of any nests discovered during a survey will be documented and their location recorded using Universal Transverse Mercator (UTM) coordinates. Just prior to the initiation of the breeding season for ravens, extra effort will be taken to remove any inactive nests to prevent these nests from becoming active. The area below any nest sites will be searched each spring for any evidence that ravens are depredating DT. If evidence of predation of DTs is found, Mojave Solar or DB will notify USFWS so that APHIS–WS can be notified and the offending ravens removed.

A data sheet will be prepared in advance of operational monitoring activities that will include the aforementioned data to be collected. Surveys will be performed as scheduled unless wind or rain interferes with audible or visual detection of ravens. Surveys will be rescheduled to occur as soon as the wind or rain has subsided.

Mojave Solar Project

4.2.2 Breeding Season Raven Surveys

The typical raven breeding season begins in mid-February and continues through the end of June (Boarman 2002, 2003). In surveys conducted during the breeding season, Mojave Solar will systematically search project lands and identify nests, as well as evidence of DT predation at nest locations.

Surveys will be conducted by vehicle, when possible, and on foot as necessary. All trees, landscaping, utility poles, transmission towers, and other structures within the Project area will be searched for nests. If nests are encountered, Mojave Solar will contact the DB to verify nest conditions. Mojave Solar will record a UTM coordinate for any nest locations and identify the nesting substrate and the current breeding status, if it can be determined. Raven activity will be documented for all observations so that the data can be reviewed to determine how ravens are using the site. Once data have been collected, the DB will determine if the nest is unoccupied (i.e., no eggs in the nest or nestlings have fledged), in which case the nest will be removed by the DB or Mojave Solar (see description of nest removal below). If occupied nests are detected during surveys, Mojave Solar will enter the information into the appropriate database by accessing the Desert Managers Group (DMG) website (www.dmg.gov). In addition, the DB will also investigate the 30-meter radius surrounding any detected nest site and/or perch site for evidence of DT predation. If any depredated DTs are discovered, they will be photographed, a UTM coordinate collected, and the length of the DT carapace measured (or estimated). The DB will then notify USFWS within 24 hours if the nest is still active. To avoid duplication of data recording on subsequent surveys, each DT shell will be marked.

Semi-quantitative and qualitative data will be collected to document raven nesting behavior and DT predation. This survey data will provide valuable information for assessing raven behavior and documenting potential problem individuals for management actions. If the survey results reveal that raven activities appear to have increased within the Project area, modifications to the PDFs and/or other control measures through adaptive management (as described in Section 5.0) may be necessary.

4.3 Nest Removal

The majority of raven predation on DT is most likely to occur in the spring, from April to May, when DT are most active and ravens are feeding their young (Boarman and Heinrich 1999). To help reduce raven depredation on DT during this time, the removal of unoccupied raven nests will be conducted as part of the MSP-specific raven management efforts. Nest removal will only occur within Mojave Solar-controlled lands and inactive nest removal can only be conducted by the DB. Removal of active nests cannot be conducted by either Mojave Solar or DB. In situations where raven predation of DT can be documented, USFWS will be contacted within 24 hours and APHIS–WS has the authority to remove offending ravens and their nests. If an identified nest is located outside of Project area boundaries, USFWS will be notified by the DB.

If an unoccupied raven nest is detected outside of the breeding window during surveys, it will be removed by the DB. Removing raven nests outside of the breeding season may have a smaller effect on the raven population, since they may readily rebuild the following season. However, evidence suggests that birds with no nests in their territory at the beginning of the breeding season are less likely to commence nesting than those that already have intact nests (Kristan and Boarman 2003). A recent study in the Mojave Desert showed a roughly 50% decrease in the number of nests rebuilt following wintertime removal (Boarman in prep.).

Mojave Solar Project

4.4 Decommissioning and Restoration Phase

If the MSP requires a decommissioning and restoration phase, Mojave Solar will perform reconnaissance-level surveys in the Project area at least biweekly (or more frequently as needed) during ground-disturbance activities. Monitoring will follow the procedures set forth in the construction phase (Section 4.1 above).

5.0 ADAPTIVE MANAGEMENT

This section discusses how adaptive management will be applied as a tool to help attain the overall purpose and objectives of this Raven Control Plan. This section provides a broad definition of adaptive management, identifies the conditions that will trigger the need for implementation of adaptive management measures, and summarizes how modifications to specific PDFs and/or other control measures can be made to likely improve the Plan's overall success.

5.1 Definition

Adaptive management is a problem-solving environmental management approach to facilitate more effective management of resources to achieve desired objectives. It involves synthesizing existing knowledge, exploring alternative actions, making explicit predictions of their outcomes, selecting one or more actions to implement, monitoring to determine whether outcomes match those predicted, and using these results to adjust future plans (Holling 1978). By nature of the definition, adaptive management can be defined as an iterative and structured optimal decision-making process based on feedback and adjustment that is intended to reduce uncertainty through system monitoring. The iterative process simultaneously maximizes one or more resource objectives and accrues information needed to improve future management, either actively or passively.

Adaptive management is usually categorized in one of two ways: active or passive. Passive adaptive management involves the use of conceptual modeling to guide management actions. The model is adjusted as new knowledge is obtained and management decisions are subsequently modified. Active adaptive management involves testing alternative hypotheses through system manipulation. Passive adaptive management is based on information gained from observational studies, whereas active adaptive management is based on information gained from experimental manipulation (Holling 1978). This Plan will focus on passive adaptive management but may ultimately apply both passive and active adaptive management.

5.2 Adaptive Management Triggers

Should the results from the monitoring practices reveal that ravens are continually and actively using the Project area, modifications to the PDFs and/or other control measures through adaptive management will be necessary. The implementation of adaptive management measures will be triggered if both of the following conditions are met:

1. The monthly and/or annual breeding season raven monitoring and survey results indicate that the existing PDFs are ineffective at controlling raven presence and activity in the Project area (the raven population size has increased, active nests are present, etc.), thereby increasing the potential for DT predation; and
2. Mojave Solar has made every attempt to adjust PDFs to control raven occurrences, and has contacted and worked with the DB and the resource agencies to identify other sources of ravens and/or management measures, but increased raven occurrences and use of the Project area appears to continue.

Mojave Solar Project

This Plan sets forth measures to preclude attracting ravens to the Project area and control measures to eliminate those that become problematic, regardless of their association with Project activities.

5.3 Adaptive Management Measures

During implementation of the monitoring program, identified adaptive management measures will be discussed by Mojave Solar, CEC, USFWS, and CDFG before any decisions are made to incorporate them into the MSP. Adaptive management measures may include modifications to PDFs or monitoring strategies, or implementation of additional control measures. Key examples are 1) modifications to the monitoring program survey frequency, including increase or reduction of the monitoring frequency and survey points should results of surveys deem it to be warranted; 2) removal or enhancement of a PDF or management measure if it is not working; or 3) incorporating a defined control measure if impacts are observed that would not otherwise be implemented (triggered).

5.3.1 Control Practices

If the results of the monitoring efforts suggest that there is a substantial and ongoing increase in raven activity that may result in DT predation, even with the implementation of PDFs, then Mojave Solar may need to implement agency-approved additional control practices to further manage ravens in the Project area. This section defines the types of control practices that may be implemented if additional measures are determined to be necessary based on the adaptive management triggers described above in Section 5.2. If none of the control measures included below work to achieve the objectives of this Raven Control Plan, additional control measures will need to be considered and implemented.

Roadkill Removal

If Mojave Solar and/or MSP operations staff regularly observes roadkill that may be attributable to the Project, it may be necessary for Mojave Solar to develop a roadkill removal program specific to the MSP.

Hazing

Hazing techniques involve the diligent application of a number of visual and/or auditory devices designed to scare birds and create an integrated system of negative stimuli to reduce the attraction of birds to an area. Hazing must be dynamic, creative, and mobile. Hazing techniques include implementation of floating or stationary figures, helium-filled balloons, air or propane cannons, human or aircraft herding, and/or bioacoustic deterrents.

The key elements of hazing are timing, organization, variation (random), and persistence. Because ravens are adept at learning the type, timing, and location of hazing techniques, these variables must be changed frequently. This effort will help to delay raven habituation to the hazing techniques.

Often, a combination of the above tactics must be employed to be effective, as many birds become accustomed to methods quickly. If hazing techniques are determined to be necessary for the MSP, the DB and Mojave Solar, in consultation with CEC, CDFG, and USFWS, will develop a hazing program specific to the Project area. Because some of these techniques will create additional sources of noise in the areas, permission may be required from the local authorities, as there may be local ordinances that prohibit the creation of loud noises.

Common Raven Monitoring, Management and Control Plan

Mojave Solar Project

Methyl Anthranilate

Methyl anthranilate (MA) is a naturally occurring non-toxic, non-lethal listed compound used as a food flavoring and fragrance additive that acts as a chemosensory repellent, irritating pain receptors associated with taste and smell. It has been documented to be an effective bird repellent; however, MA is thought to have limitations for topical application as it is considered highly volatile and breaks down readily under exposure to ultraviolet (UV) light (Umeda and Sullivan 2001). With USFWS and CDFG approval, the most appropriate application of MA would be to small areas of ponding water or areas where known nesting has occurred. In areas of ponding water, it would be necessary to repeat topical application due to the chemical breakdown that occurs with exposure to UV light. In areas where known nesting has occurred, Mojave Solar could apply MA to deter nest rebuilding in that location. However, before MA is applied to any area at the MSP, research will be conducted by the DB to obtain the most current application of MA; the most effective methods to deter raven activity will then be developed in coordination with Mojave Solar and CEC.

Lethal Removal (Depredation)

Lethal removal may be considered if ravens are still attracted to the MSP even after the implementation of PDFs, modification to PDFs, and implementation of control measures. Lethal removal is also appropriate if there is evidence that nesting ravens are depredating DT. Under this control method, targeted ravens will be shot by rifle or shotgun. If shooting is not possible (e.g., on power lines) or has been proven unsuccessful, ravens will be trapped and humanely euthanized. Juvenile ravens found in nests of removed adults will also need to be euthanized humanely. Lethal removal will only occur after consultation with CDFG and USFWS, and issuance of proper permits for “taking” of ravens.

It should be noted that there is no evidence suggesting that lethal removal will have a long-lasting effect on raven population levels, raven foraging behavior, or survival of juvenile DT (Boarman 2002). Targeting and removing individuals in this fashion is also considered time consuming. However, this method can be effective if there are specific raven pairs determined to be responsible for taking relatively large numbers of DT (Boarman 2002). These individuals can often be identified by the presence of juvenile DT shells beneath their nests, which are often used for consecutive years by the same pair of breeding ravens (Boarman and Heinrich 1999). While it would be very difficult to identify the target bird(s) with absolute certainty and lethally remove both members of a pair, removing those birds known to prey on DT would likely increase the survival of juvenile DT in that vicinity (Boarman 2003).

6.0 REPORTING

During construction of the MSP, monthly monitoring reports will be prepared. Mojave Solar will then forward the reports to the CEC. These reports will provide a summary of all monitoring activities occurring within the Project area and describe any noted raven activity and/or any observations reported by MSP operations staff. During project operation, monitoring data will continue to be provided annually. The annual report will be prepared and submitted to summarize the overall monitoring results, evaluate the effectiveness (success or failure) of PDFs, and make recommendations for modification of PDFs or implementation of control measures, if needed. Results of the monitoring efforts will be used to assess the overall impacts of the MSP and specific Project components, such as evaporation ponds, on raven activities (e.g., presence or type of activity). Annual reports will be submitted to the CEC.

Common Raven Monitoring, Management and Control Plan

Mojave Solar Project

7.0 REFERENCES

- Abengoa, Inc. (Abengoa). 2009. Application for Certification – Mojave Solar Project. July.
- AECOM. 2009. Evaporation Pond Monitoring/Remediation Action Plan. December.
- Boarman, William I. 1993. When a Native Predator Becomes a Pest: A Case Study. For: *Conservation and Resource Management* (S.K. Majumdar, et al., eds.), pp. 186–201. Pennsylvania Academy of Science, Easton, Pennsylvania.
- Boarman, William I. 2002. Reducing Predation by Common Ravens on Desert Tortoises in the Mojave and Colorado Deserts. Prepared for the Bureau of Land Management (BLM) by the U.S. Geological Survey (USGS), Western Ecological Center.
- Boarman, William I. 2003. Managing a Subsidized Predator Population: Reducing Common Raven Predation on Desert Tortoises. *Environmental Management*. V32:2 pp. 205–217.
- Boarman, W., and B. Heinrich. 1999. Common Raven. *The Birds of North America*. Eds. A. Poole, and F. Gill., No. 476. The Birds of North America, Inc., Philadelphia, Pennsylvania.
- eBird. 2010. WWW.ebird-.org
- Holling, C. S. 1978. *Adaptive Environmental Assessment and Management*. Chichester: Wiley.
- Kristan, W. B., III, and W. I. Boarman. 2003. Spatial Pattern of Risk of Common Raven Predation on Desert Tortoises. *Ecology* 84(9):2,432–2,443.
- Kristan, W. B., III, W. I. Boarman, and J. J. Crayon. 2004. Diet Composition of Common Ravens Across the Urban-Wildland Interface of the West Mojave Desert. *Wildlife Society Bulletin* 32(1):244–253.
- Umeda, K., and L. Sullivan. 2001. Evaluation of Methyl Anthranilate for Use as a Bird Repellent in Selected Crops. University of Arizona College of Agriculture 2001 Vegetable Report. Available at <http://ag.arizona.edu/pubs/crops/az1252/>.
- United States Department of Agriculture (USDA). 2009. Animal and Plant Health Inspection Service: Wildlife Services. Work Plan on Public Land Administered by the U.S. Department of Interior Bureau of Land Management, California Desert District. March to September.

Common Raven Monitoring, Management and Control Plan

Mojave Solar Project

This page intentionally left blank.

ATTACHMENT A

FIGURES 1–4



Source: Mojave Solar, LLC 2010; ESRI 2010





Figure 1
Regional Map: Mojave Solar Project



Source: NAIP 2005; USFWS 2006; BLM 2009; Mojave Solar, LLC 2009; BLM 2010





Figure 2
Vicinity Map: Mojave Solar Project Site



Legend


- Project Boundary
- Survey Area (CEC 1-mile Biology Buffer)
- Previous Biological Resources Survey Area
- Desert Tortoise Critical Habitat
- Mohave Ground Squirrel (MGS) Conservation Area
- Superior-Cronese Desert Wildlife Management Area
- Fremont-Kramer Desert Wildlife Management Area
- Area of Critical Ecological Concern

Source: NAIP 2005; USFWS 2006; BLM 2009; Mojave Solar, LLC 2009; BLM 2010

3,500 1,750 0 3,500 Feet

Scale: 1 = 42,000; 1 inch = 3,500 feet

Figure 3
Plant Site Layout



Source: NAIP 2005; USFWS 2006; BLM 2009; Mojave Solar, LLC 2009; BLM 2010




Figure 4
Raven Monitoring Areas

APPENDIX M-3

**BURROWING OWL MONITORING
AND MITIGATION PLAN**

DRAFT
MOJAVE SOLAR PROJECT
BURROWING OWL
MONITORING AND MITIGATION PLAN

Prepared for:

Mojave Solar, LLC
13911 Park Avenue, Suite 206
Victorville, California 92392
Contact: Scott Frier
Phone: (760) 617-2570

Prepared by:

AECOM
1420 Kettner Boulevard, Suite 500
San Diego, California 92101
Contact: Lyndon Quon
Phone: (619) 233-1454

January 2011

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
1.0 INTRODUCTION	1
1.1 Purpose of the Plan	1
1.2 Project Background.....	2
1.3 Definitions.....	5
1.4 Roles and Responsibilities	5
1.5 2006–2009 Survey Results	7
2.0 PASSIVE RELOCATION METHODS	13
2.1 Nonnesting Season Preactivity Survey	13
2.2 Passive Relocation	14
2.3 Artificial Burrow and Relocation Site	17
2.4 Preconstruction Surveys.....	20
3.0 MONITORING.....	23
3.1 Monitoring Passive Relocation Areas Left Idle for More Than 30 Days	23
3.2 Nesting Season Occupied Burrow Monitoring	23
3.3 Artificial Burrow and Relocation Area Monitoring.....	24
4.0 REPORTING	25
5.0 WESTERN BURROWING OWL COMPENSATION LANDS	27
6.0 REFERENCES	29

APPENDIX A. Burrowing Owl Survey Protocol and Mitigation Guidelines

LIST OF FIGURES

<u>Figure</u>	<u>Page</u>
1 Regional Map.....	3
2 Burrowing Owl Observations	9
3 Vegetation Communities	11
4 Artificial Burrowing Owl Burrow Design A	18
5 Artificial Burrowing Owl Burrow Design B	19

LIST OF TABLES

<u>Table</u>	<u>Page</u>
1 2006–2008 WBO Protocol Survey Results and Other WBO Occurrences	8

1.0 INTRODUCTION

1.1 PURPOSE OF THE PLAN

This Burrowing Owl Mitigation Plan (Plan) describes the actions to be taken to protect resident and/or nesting western burrowing owls (*Athene cunicularia hypugea*; WBO) known to occur within and in the vicinity of the proposed Abengoa Mojave Solar Project (AMS or Project). The Plan specifies a passive relocation approach that, when implemented, will facilitate avoidance, minimization, and the offset of impacts to WBO relocated from the Project Disturbance Area. The primary purpose of this Plan is to provide a strategy that will facilitate the protection of WBO, a California Species of Special Concern, during AMS construction. This Plan fulfills the Project mitigation measures identified in the Project Application for Certification (AFC) (MSLLC 2009) and Condition of Certification (COC) BIO-13 in the Final Commission Decision (CEC 2010), requiring passive relocation and/or non-disturbance buffers (area in which no activity will occur) of WBO.

Specific objectives for WBO protection addressed by this Plan are as follows:

- Provide avoidance measures to protect WBOs during Project implementation.
- Describe the strategy and methodology for passive relocation of all WBOs within the Project area to a nearby area that provides suitable nesting and foraging habitat.
- Minimize impacts to WBOs within the passive relocation site.
- Assess the success of the WBO passive relocation effort through monitoring.
- Implement mitigation/compensation measures for WBO.

These objectives will be met through the following actions:

- Detecting the locations of WBO-occupied and WBO-suitable burrows prior to the nesting season (February 1 through August 31) for Project Disturbance Areas in which construction will occur plus a 160-foot construction buffer of that area;
- Identifying suitable artificial burrow location sites, in coordination with the California Department of Fish and Game (CDFG), and California Energy Commission (CEC) Compliance Project Manager (CPM) beyond 160 feet of the overall Project Disturbance Area within the compensation lands;

-
- Passively relocating, banding, and monitoring WBO from identified WBO burrows within the Project Disturbance Areas during the nonnesting season (September 1 through January 31);
 - Monitoring all areas cleared of WBO during preconstruction surveys for the period prior to ground disturbance;
 - Monitoring all WBO-occupied burrows in the 160-foot construction buffer and any burrows occupied and surrounded with nondisturbance fencing during nesting season;
 - Maintenance, monitoring, reporting, and management of the WBO on the relocation property; and
 - Monitoring of mitigation lands for 2 years (two spring and two winter surveys per year).

1.2 PROJECT BACKGROUND

The Abengoa Mojave Solar Project (AMSP or Project) is a solar electric generating facility to be located on approximately 1,765 acres in unincorporated San Bernardino County, California, approximately 26 miles northwest of Barstow. Mojave Solar LLC, a subsidiary of Abengoa Solar Inc., (Abengoa or ASI) will own and operate the project. ASI filed an Application for Certification (AFC) with the California Energy Commission (CEC) for the Project on August 10, 2009. The CEC issued a Final Permit Decision adopting the Presiding Member's Proposed Decision (PMPD) to recommend licensing the project on September 8, 2010.

The Project site is accessed by Harper Lake Road, which is located approximately 20 miles west of Barstow along the Highway 58 corridor. The Project site is approximately six miles north of where Harper Lake Road intersects with Highway 58. See the regional map (Figure 1).

The project site is comprised of private property historically used as the Lockhart Ranch complex. The site once served as an agricultural and cattle center and included farming activities that used flood and pivot system irrigation.

The Project will implement well-established parabolic trough technology to heat a heat transfer fluid (HTF). The heated HTF will generate steam in solar steam generators (SSGs), and the steam will then be expanded through a steam turbine generator (STG) to produce electrical power.



Source: Mojave Solar, LLC 2010; ESRI 2010




Figure 1
Regional Map

The Project will have a combined nominal electrical output of 250 megawatts (MW) from twin, independently-operable solar fields (Alpha and Beta), each feeding a 125-MW power island. The Alpha site is approximately 950 acres in size, and the Beta site is approximately 815 acres. Approximately 70 percent (%) of the total project area will consist of solar fields. Approximately 3% of the site will be occupied by the power blocks, with the remaining 27% consisting of drainage improvements, evaporation ponds, a substation, and other common elements. The electrical output from the Alpha and Beta sites will join at an on-site transmission line interconnection substation to form one full-output transmission interconnection. The power generated by the project will be transmitted to Southern California Edison's (SCE's) transmission grid through SCE's existing 230-kilovolt (kV) Kramer-Cool Water #1 transmission line. The entire site perimeter will be fenced.

The sun will provide 100% of the power supplied to the Project through solar-thermal collectors; no supplementary fossil-based energy source (e.g., natural gas) is proposed for electrical power production. However, each power island will have a natural-gas-fired auxiliary boiler to provide equipment freeze protection and HTF freeze protection. The auxiliary boiler will supply steam to HTF heat exchangers as needed during offline hours to keep the HTF in a liquid state when ambient temperatures fall below its freezing point of 54 degrees Fahrenheit (°F). Each power island will also have a diesel engine-driven firewater pump for fire protection and a diesel engine-driven backup generator for power plant essentials.

The Project will use wet cooling towers for power plant cooling, and the project owner owns adjudicated water rights for this purpose. Water for cooling tower makeup, process water makeup, and other industrial uses such as Solar Collector Array (SCA) washing will be supplied from onsite groundwater wells drawing from these water rights and will also be used to supply potable water. A packaged water treatment system will be used to treat the water to meet potable standards since the source is brackish.

A sanitary septic system and onsite leach field will be used to dispose of sanitary wastewater at each power island. Project cooling water blowdown will be piped to lined, onsite evaporation ponds for each plant area. The ponds will be sized to retain all solids generated during the life of the plant. However, if required for maintenance, dewatered residues from the ponds could be sent to an appropriate offsite landfill as non-hazardous waste.

Natural gas for the Project's ancillary purposes, such as the auxiliary boilers, space heating, and the like will be supplied by a Southwest Gas Corporation (SGC) owned pipeline that runs to the

Project boundary near the Alpha power island. No offsite pipeline facilities are proposed as a part of this Project.

Construction of the AMS facility, from site preparation and grading to commercial operation, is expected to take approximately 2-1/2 years. Commercial service is expected by winter of 2013. The AMS project has an expected operating life of between 30 years to 40 years. Whenever the facility is closed, whether temporarily or permanently, the closure procedures outlined in the CEC Decision will ensure compliance with applicable laws, ordinances, regulations, and standards (LORS).

Once the Project is completed and the site is developed, the site would be devoid of vegetation and likely would no longer provide suitable habitat for WBO.

AECOM was contracted by ASI to perform environmental services to support the review process being undertaken by CEC. The WBO is protected under the Federal Migratory Bird Treaty Act (MBTA) and is designated as a Species of Special Concern by CDFG.

1.3 DEFINITIONS

The following terms will be used throughout this report:

- **Project Biological Resources Survey Area (BRSA):** The Project BRSA includes the Project Disturbance Area and all associated buffers.
- **Project Disturbance Area:** Includes the area of anticipated ground disturbance associated with implementation of the Project.

1.4 ROLES AND RESPONSIBILITIES

ASI is ultimately responsible for implementing this WBO Plan. It is anticipated that ASI contractors and other parties responsible for implementing components of this WBO Plan will include the following:

EPC Contractor(s): The engineering, procurement, and construction (EPC) contractor construction manager will have ultimate oversight of the construction contractor to ensure compliance with the provisions of this WBO Plan. Contractual language will be included in construction documents and ongoing maintenance contracts to verify that all contractors, subcontractors, vendors, maintenance personnel, and other parties performing either construction

or ongoing maintenance or repairs at the site abide by and implement the provisions of this WBO Plan as it relates to their work. Implementing the construction provisions of this WBO Plan will be a part of construction contracts. Landscape contractors and other specialists will implement specific provisions of this WBO Plan either as subcontractors to the general construction contractor or through independent contracts with ASI.

California Energy Commission: CEC provided guidelines and COCs for the Project. CEC, acting through the Compliance Project Manager (CPM), will determine whether the WBO Plan and activities performed under the WBO Plan have been satisfied.

Designated Biologist: ASI will assign a Designated Biologist (DB) to the Project. A resume of the proposed DB, along with the required three references and contact information, will be submitted to the CEC CPM for approval in consultation with CDFG and the U.S. Fish and Wildlife Service (USFWS). The DB will have the following background and training:

- Bachelor's degree in biological sciences, zoology, botany, ecology, or a closely related field and 3 years of experience in field biology or current certification of a nationally recognized biological society such as The Ecological Society of America or The Wildlife Society; and
- At least 1 year of field experience with biological resources found in or near the Project area.

In lieu of the above requirements, the resume will demonstrate, to the satisfaction of the CPM in consultation with CDFG and USFWS, that the proposed DB has the appropriate training and background to effectively implement the WBO Plan. ASI will ensure that the DB performs the activities specified in the WBO Plan.

ASI will also designate an alternate biologist with the same qualifications as the DB, outlined above.

Biological Monitor: ASI will designate a Biological Monitor(s) to provide oversight of WBO surveys, relocation, and protection measures, and to ensure compliance with the provisions of this WBO Plan. The Biological Monitor will be responsible for detecting WBO within and adjacent to construction areas and reinforcing worker education regarding protective measures. The Biological Monitor will be contracted by ASI and must be knowledgeable about the Project, WBO avoidance and protection obligations, and the habitat use of WBO in the vicinity of the Project area.

1.5 2006–2009 SURVEY RESULTS

A reconnaissance-level survey was conducted in 2006 and protocol surveys were conducted in spring 2007 and 2008 by AECOM biologists to determine WBO presence/absence, distribution, abundance, and breeding status within a broad expanse of land under the control of the Applicant. The ultimate proposed Project was sited within a portion of this land, in order to avoid and minimize Project effects to biological resources (EDAW 2007, 2009). Figure 2 displays the locations of WBOs observed during the 2006 reconnaissance survey and the 2007 and 2008 protocol surveys. Surveys for WBO were conducted per California Burrowing Owl Consortium (CBOC) protocol (CBOC 1993), and were focused to determine the presence or absence, distribution, abundance, and breeding status of the species. Surveys were conducted within the lands under control of the Applicant, plus a 500-foot buffer per the CBOC protocol, with the addition of a 1-mile buffer as directed by CEC where two CEC-recommended transects within a 1-mile buffer were also conducted. Transects located at $\frac{3}{4}$ -mile and 1-mile intervals from and parallel to the disturbance boundary were surveyed. The limits of the survey extend to this 1-mile CEC buffer.

Information collected on WBO was included in the biological resources analysis in the Project AFC, which quantifies potential impacts on WBO and identifies appropriate avoidance, minimization, and mitigation measures. A detailed description of the survey methodology and results can be found in the Project AFC, Volume 3 (MSLLC 2009).


Most of the lands under control of the Applicant, as well as the adjacent buffer, are considered suitable WBO habitat. The survey area consists of primarily previously disturbed vegetation. Within the proposed Project site, the dominant vegetation community is fallow agricultural fields, with lesser patches of disturbed areas, active agriculture, saltbush scrub regrowth, and minor pockets of vegetation associated with the Harper Dry Lake margin (Figure 3).

During 2006 reconnaissance surveys, four WBO individuals were detected along the borders of the Project area. Protocol surveys in 2007 found a pair of WBO plus five individual WBOs within the Project area. Additionally, four individual WBO were found outside the Project area in the 1-mile survey buffer. During WBO surveys in 2008, a single WBO was observed within the Project area, and one WBO was observed within the 1-mile survey buffer. A pair of WBO that had been observed in the Project area during 2007 surveys was not observed in the 2008 surveys. A domestic dog was observed within this area, so the loss of the pair may have been due to dog predation, or the owls may have simply moved. The number of WBO observations, year, and proximity to the Project area are detailed in Table 1, below.

Table 1
2006–2008 WBO Protocol Survey Results and Other WBO Occurrences

Distinct Observation(s)	Year	Area/Proximity of Project Area
4 individuals	2006	Within eastern section of Project area
4 individuals	2007	Within 1-mile survey buffer east and south of Project area
5 individuals plus 1 pair	2007	One WBO within western section, all other WBO within eastern section of Project area
1 individual	2008	Within 1-mile survey buffer east of Project area
1 individual	2008	Within eastern section of Project area

Burrows where WBOs were either observed or where their sign was documented were all located in flat, sparsely vegetated areas. The low density of WBO in the Project site is consistent with the documented low general numbers of the species in the surrounding region.



Source: NAIP 2009; Mojave Solar, LLC 2009; AECOM 2009





Figure 2
Burrowing Owl Observations

This page intentionally left blank.



Source: NAIP 2009; Mojave Solar, LLC 2009; AECOM 2009




Figure 3
Vegetation Communities

This page intentionally left blank.

2.0 PASSIVE RELOCATION METHODS

This section discusses the specific procedures and methods to be used to achieve the purposes and objectives of this Plan, including preactivity surveys, preconstruction surveys, artificial burrow installation and passive relocation protocols. Preactivity surveys are conducted outside the nesting season. This is generally the time when passive relocation can occur, but passive relocation can also occur after it has been determined by a qualified biologist that the young have fledged from the nest. Preconstruction surveys are conducted 30 days prior to the initiation of ground disturbing activities. Preactivity surveys can function as preconstruction surveys if they are conducted within 30 days prior to construction. Artificial burrows are to be constructed to provide burrow opportunities for WBOs that have been passively relocated and to provide burrow opportunities for WBOs within the area.

2.1 NONNESTING SEASON PRACTIVITY SURVEY

Nonnesting season preactivity surveys as described in this section are required to identify locations of WBO within the Project area and a 160-foot survey buffer. These surveys will be conducted during the nonnesting season (September 1 through January 31) prior to planned activity in all Project Disturbance Areas. They will involve a burrow survey (CBOC Phase II) to update the protocol surveys conducted in 2007 and 2008, and identify the locations of any newly established WBO-occupied or WBO-suitable burrows. Focused surveys will be conducted as necessary at dawn or dusk according to CBOC guidelines to determine presence or absence of WBO at suitable burrows and/or where sign is observed. This survey will be conducted in the areas where construction will occur during that year plus a 160-foot construction buffer of that area. The survey will be staffed by qualified wildlife biologists. Specific requirements of this protocol stipulate that walking survey transects will be spaced to allow 100% visual coverage of the ground surface; distance between transect center lines will be no more than 98 feet and will be reduced to account for differences in terrain, vegetation density, and ground surface visibility. This survey will be conducted by walking through suitable habitat over the Project Disturbance Area and within 160 feet of the Project Disturbance Area. This 160-foot buffer zone is included to account for adjacent burrows and foraging habitat outside the Project Disturbance Area and impacts from factors such as noise and vibration due to heavy equipment, which could impact resources outside the Project Disturbance Area (CBOC 1993). The results of the nonnesting season preactivity survey will be included as an addendum to the final version of the Burrowing Owl Monitoring and Mitigation Plan (detailing the number of WBO observed within the Project

area), which will be submitted within 10 days of completion of the WBO preconstruction surveys to the CPM, CDFG, and USFWS.

This survey serves three purposes:

1. Identify any WBO that will be color leg-banded with aircraft aluminum bands in accordance with the guidance provided by the U.S. Geological Survey (USGS) bird banding lab in order to monitor relocation success. This process is discussed in Section 2.1.
2. Identify all burrows from which WBO will need to be passively relocated or excluded from future use during the allowable relocation window prior to the start of the breeding season. Passive relocation of WBO is discussed in Section 2.1.
3. Determine the number of WBOs occupying the Project Disturbance Areas scheduled for activity to determine the number of artificial burrows needed per CBOC guidelines (five artificial burrows will be installed for each identified WBO burrow in the Project area that would be destroyed). Artificial burrow installation and site selection are discussed in Section 2.2.
4. If Project disturbance is scheduled to start within 30 days of this preactivity survey, this survey serves as the preconstruction survey. Preconstruction survey protocols and scheduling considerations are discussed in Section 2.3.

2.2 PASSIVE RELOCATION

Passive relocation is considered the preferred option to trapping (CBOC 1993). During the non-breeding season (September 1 to January 31), owls to be relocated will be color-banded with aircraft aluminum bands in accordance with USGS bird banding lab guidelines by approved and permitted biologists. According to BIO-13 of the CECs Conditions of Certification (COCs), WBOs will be given a minimum of 3 weeks to become familiar with the new artificial burrows to be constructed within compensatory habitat outside of the Project area, after which eviction of owls within the Project area will begin. If it can be determined that suitable habitat (including natural burrows) is present within 600 meters of occupied WBO burrows (but outside the Project disturbance area) then a three week waiting period should not be necessary. The WBOs would already be familiar with the available natural burrows within the area, and the constructed artificial burrows are not likely to be visited unless the WBOs to be relocated are in close proximity to the compensatory habitat. In such an instance, the DB will coordinate with DFG, USFWS and the CPM to review the availability of potential habitat nearby for passively

relocated owls, as well as the relocation strategy and timing as it relates to construction of artificial burrows. The success of the passive relocation effort will be determined through the monitoring effort as proposed in Section 3 below.

One-way doors as described by Trulio (1995) and Clark and Plumpton (2005) will be used to facilitate passive relocation of WBO. If relocation occurs near the breeding season, focused monitoring of the WBOs will be conducted to ensure nesting is not underway or to determine if nesting has been concluded prior to relocation efforts. Burrows will be excavated after determined vacant by use of a down-hole camera, monitoring, and the use of one-way doors.

Excluded burrows will be monitored daily for three days to confirm no additional WBO use them before excavating burrows. After burrows are confirmed to no longer be in use, the burrow will be excavated using hand tools and refilled to prevent reoccupation. Sections of flexible plastic pipe or burlap bag will be inserted into the tunnels during excavation to maintain an escape route for any WBOs inside the burrow.

WBO must be excluded from WBO-occupied and WBO-suitable burrows identified during the nonnesting preactivity survey prior to the following nesting season (February 1 through August 31) and any Project disturbance. WBO passive relocation efforts will be led by the DB and staffed by qualified wildlife biologists. WBO will be excluded from identified burrows by installing one-way doors (e.g., 4-inch-diameter corrugated irrigation pipe with gravity-closing see-through door) in each burrow entrance.

The sequence of events to exclude WBO from the Project Disturbance Area is described below:

1. Install one-way doors in all suitably sized burrows (greater than or equal to 4 inches in diameter) actively used by WBO and suitable burrows in the immediate vicinity of the occupied burrow(s). Suitable burrows without recent WBO sign will be addressed first. One-way doors will be installed in burrows actively used by WBO after installation occurs on all other suitable burrows in the immediate vicinity to avoid multiple evictions.
2. One-way doors will be installed during the afternoon with care taken not to flush any WBO from the Project Disturbance Area during one-way door installation. If any WBO are detected leaving the Project Disturbance Area in response to one-way door installation, installation activity will cease until the activity no longer poses a potential harassment threat (all detected WBO have voluntarily left the vicinity). In the event a burrow is larger than the diameter of the one-way door, that burrow will be remotely

investigated with a fiber-optic scope camera to ensure an animal larger than the one-way door is not occupying the burrow. If not inspected, berms used to hold the one-way door in place may trap larger wildlife.

3. For known occupied burrows, WBO will be observed at dusk (i.e., beginning 1 hour before evening civil twilight and ending at twilight) to document their departure from the Project Disturbance Area. This may require more than one observer to account for the location of all WBO. All observers will remain 250 feet from the one-way doors under surveillance so their presence does not alter the WBO behavior.
4. One-way doors will be installed in the burrows that the WBO have been recently using after the WBO have departed the area at dusk. One-way doors installed in known occupied burrows will be installed at not greater than a 45 degree angle from the ground to ensure WBO are able to depart.
5. On the 2 days following one-way door installation, the exclusion area will be observed beginning at dawn (i.e., no later than morning civil twilight) until at least 1 hour after sunrise the following morning and WBO presence or absence recorded in the exclusion area and their reaction to the presence of one-way doors documented.
6. On the third morning following one-way door installation, using a fiber-optic scope camera, the recently used burrows identified in steps 2 and 4 above will be scoped. Suitable burrows without recent WBO sign (step 2) will be scoped to ensure that no other sensitive species are currently occupying burrows. Burrows known to be recently occupied by WBO (step 4) will be scoped to ensure all WBO have vacated the burrow. Upon confirmation that the burrow is unoccupied, the burrows will be excavated with hand tools using flexible pipe to allow wildlife to escape, and refilled to prevent reoccupation by WBO or other sensitive species.
7. The Project Disturbance Area and 160-foot buffer area will be monitored for WBO presence, including sign, for seven mornings (beginning at morning civil twilight) after the passive relocation effort is complete to ensure that other resident wildlife do not reexcavate burrows and WBO do not reoccupy those burrows.

The results of the passive relocation effort will be included in a report to the CPM, CDFG, and USFWS. This information will also be included in the Project's Annual Compliance Report.


2.3 ARTIFICIAL BURROW AND RELOCATION SITE

In the event that WBO are observed within the Project area during nonnesting season surveys, artificial WBO burrows will be installed at a ratio of 5:1 to replace each identified WBO burrow in the Project area that is destroyed during passive relocation. These burrows will be installed in WBO suitable habitat within the compensation lands identified in Figures 2 and 3. The specific location of each burrow enhancement site or artificial burrow will be determined after WBO surveys of the compensation lands identify suitable locations for placement of artificial burrows and establish a baseline for WBO use in the compensation lands. WBO surveys of the compensation lands will be conducted concurrently with surveys of the Project area prior to the WBO nesting season and prior to ground disturbance or heavy equipment staging only if WBO are detected within the Project area.

Artificial burrows will be designed to maximize their suitability and effectiveness. If improperly designed, an artificial burrow may attract predators; fill with rainwater, dirt, or debris; or fail to provide adequate cover. Figures 4 and 5 depict examples of artificial burrows that will be installed within the compensation lands. Two different WBO artificial burrow designs are provided for flexibility based on habitat, vegetation, and topographical characteristics within the compensation lands. One design (Figure 4) depicts an artificial burrow that may be installed in a hillside or other location where topographical relief provides suitable habitat for WBO. The second design (Figure 5) depicts an artificial burrow with a mima-mound component that may be more suitable in flat terrain, but with vegetation. The elevated mound on top of the burrow allows WBO to have suitable visual coverage from predators. The CPM and DB will decide the final locations of the artificial burrows and approve the specific design of artificial burrow to be used.


Prior to ground disturbance at the artificial burrow installation site, surveys for other sensitive species (e.g., desert tortoise, sensitive plants) may be required to verify that the construction of artificial burrows at the relocation site will not adversely impact those species. Installation of artificial burrows will be conducted in a manner to minimize impacts to desert tortoise and Mohave ground squirrel habitat.

Artificial burrow installation will be led by the DB and staffed by qualified wildlife biologists. Summaries of the identified areas will be submitted to and approved by CDFG, USFWS, and the CEC CPM prior to the initiation of passive relocation efforts. A description of activities at the artificial burrow and relocation site will be included in the addendum to the final Burrowing Owl Monitoring and Mitigation Plan.



Not to Scale

Figure 4
Artificial Burrowing Owl Burrow Design A



LEGEND

- | | |
|---|---|
| ① NATIVE SOIL HORIZONS (TOPSOIL & CLAY PAN) | ⑤ MOUND OF SOIL (APPROXIMATELY 20 - 25 CUBIC YARDS) |
| ② 2" - 3" ADDITIONAL TOPSOIL UNDER IRRIGATION BOX | ⑥ GEO-MESH COVERING MOUND TO DETER PREDATION
APPROXIMATELY 4" - 6" BELOW TOPSOIL HORIZON OF MOUND
SMALL HOLES CUT IN MESH TO ACCOMMODATE PLANT MATERIAL |
| ③ PLASTIC IRRIGATION VALVE BOX
APPROXIMATELY 2'x1.5'x1' | ⑦ LANDSCAPING CONSISTING OF LOW GROWING PLANTS AND ROCKS |
| ④ CORRUGATED PLASTIC PIPE (6" DIAMETER)
ABOVE CLAY PAN TO PREVENT FLOODING | |

Not to Scale

Figure 5
Artificial Burrowing Owl Burrow Design B

In addition, arrangements will be made for repairs to be completed for any damage to artificial burrows observed during spring and winter visits. Surveys of the artificial burrows will be conducted two times in the spring and two times in the winter following eviction. The second survey within a season will be conducted within 30 days of the first survey. Surveys will continue for 2 years after installation of artificial burrows to encompass a total of four spring and four winter surveys. Monitoring information will also be included in the Project's Annual Compliance Report.

2.4 PRECONSTRUCTION SURVEYS

Preactivity surveys and associated passive relocation activities meet the requirements of a preconstruction survey for any ground-disturbing activities occurring within 30 days following completion of passive relocation activities. Otherwise, a preconstruction WBO survey is required, per BIO-13, in the Project Disturbance Area. This is necessary because it is possible for fossorial mammals to enter the Project Disturbance Area and establish burrows in the areas cleared during the preactivity survey if it is left idle. In this event, WBO may occupy those newly established burrows. Any necessary preconstruction surveys will follow CBOC Phase II burrow survey protocols (see Section 2.1 for specific protocol requirements). If passive relocation has already occurred, this survey will serve to document that burrows excavated during passive relocation continue to be unoccupied by WBO and no newly established WBO-occupied or WBO-suitable burrows are available for WBO occupation in the Project Disturbance Area. This survey will be staffed by qualified wildlife biologists. In the event any WBO-occupied burrows are observed during the preconstruction survey, they will be passively relocated. During the nonbreeding season, WBO can be passively relocated as described in Section 2.2, above.

If WBO are found occupying a burrow within 160 feet of the Project Disturbance Area during the breeding season (February 1 through August 31), a 250-foot buffer will be flagged surrounding the occupied burrow per CBOC guidelines. Exclusion fencing will be installed and work activity will remain outside of the fenced area until a DB determines the burrow is no longer occupied (e.g., juveniles are foraging independently and are capable of independent survival). Signs will be posted in English and Spanish at the fence line indicating no entry or disturbance is permitted within the fenced buffer. In addition, at least 10 days prior to the start of any activities in the Project Disturbance Area, the DB will provide to the CPM documentation indicating that nondisturbance buffer fencing has been installed. This documentation will include a description of the burrow, summary of the occupants of the burrow, account of the surrounding habitat conditions, a photograph of the burrow, and latitude/longitude coordinates for the burrow.

In the event any WBO-suitable burrows with no sign of occupation are found (e.g., no wash, pellets, feathers) during the preconstruction survey, such burrows will be remotely investigated to ensure WBO and other wildlife do not occupy the burrow (e.g., with a fiber-optic scope camera), excavated with hand tools using flexible pipe to allow wildlife to escape, and refilled to prevent occupation by WBO. The results of each preconstruction survey will be included in the next monthly report on the implementation of WBO avoidance and minimization measures to the CPM, CDFG, and USFWS. This information will also be included in the Project's Annual Compliance Report.

This page intentionally left blank.

3.0 MONITORING

3.1 MONITORING PASSIVE RELOCATION AREAS LEFT IDLE FOR MORE THAN 30 DAYS

If work in the Project Disturbance Area is scheduled to commence more than 30 days after passive relocation activities are complete, monitoring of that area will occur until disturbance commences. The frequency of the monitoring will depend on the abundance of fossorial mammal activity and the friability of soils in the passive relocation area. This monitoring will reduce the likelihood that other resident wildlife species are able to reexcavate burrows, allowing WBO to reoccupy those burrows. Results of this monitoring will be included in the Project's Annual Compliance Report.

3.2 NESTING SEASON OCCUPIED BURROW MONITORING

If construction activities in the Project Disturbance Area occur within 160 feet of an occupied burrow during the nesting season (February 1 through August 31), the DB or a Biological Monitor will monitor to determine whether these activities have potential to adversely affect nesting efforts, and, as necessary, will make recommendations for adaptive management measures to minimize or avoid such disturbance.

Additional monitoring and adaptive management measures to prevent disturbance to nesting birds from construction-related activities will be employed as determined necessary by the DB or a Biological Monitor and CPM. Any adaptive management measures will be determined in consultation with the CPM, CDFG, and USFWS. Triggers for adaptive management will be evidence of Project-related disturbance to nesting owls such as agitation behavior (displacement, avoidance, and defense), increased vigilance behavior at burrow sites, changes in foraging and feeding behavior, or nest site abandonment.

Monitoring will occur each month and findings will be included in the monthly report on the implementation of WBO avoidance and minimization measures to the CPM, CDFG, and USFWS for the duration of construction. This information will also be included in the Project's Annual Compliance Report.

3.3 ARTIFICIAL BURROW AND RELOCATION AREA MONITORING

Post-relocation monitoring will include two spring and two winter censuses of the relocation site to determine if burrowing owls are using natural or artificial burrows within the relocation area. The second survey within a season will be conducted within 30 days of the first survey for that season. Monitoring will occur for 2 years. Maintenance of artificial burrows will occur three to four times during the year immediately following relocation, as necessary, to ensure boxes are usable for the breeding and non-breeding seasons.

During spring and winter visits to the WBO artificial burrow and relocation site to occur for a duration of 2 years, the DB or a Biological Monitor will record observations of relocated WBO and/or occurrences of migrating or other local WBO using the artificial burrows and relocation site, evidence of known predators or humans visiting or disturbing the site, and any other pertinent data gathered through the monitoring. Findings will be included in the report on the implementation of WBO avoidance and minimization measures to the CPM, CDFG, and USFWS for the duration of construction. This information will also be included in the Project's Annual Compliance Report.

If the burrowing owls do not use the relocation area, remedial measures will be developed by the DB in consultation with the CPM and CDFG.

4.0 REPORTING

An annual report will be submitted to CEC, CDFG, and USFWS following each breeding season for 2 years post-relocation. The annual reports will include the date when passive relocation efforts began, the date of burrow excavations, findings, and dates of initiation of construction activities. Additionally, any injuries, mortality, or other unforeseen circumstances will be reported to all resource agencies within 24 hours.

Reports will include the following data:

- Project name, locations, and all pertinent information pertaining to the origin site;
- Known predators or humans visiting or disturbing the site;
- Dates of removal of one-way exclusion doors and the collapse of unoccupied burrows;
- Monitoring results;
- Any other pertinent data gathered through the exclusion, passive relocation efforts, and post-relocation monitoring; and
- Remedial measures taken.

This page intentionally left blank.

5.0 WESTERN BURROWING OWL COMPENSATION LANDS

As discussed above, the Applicant owns approximately 647 acres of habitat west of the Project area. Within this parcel, the Applicant proposes to compensate for impacts to sensitive resources, including desert tortoise, Mohave ground squirrel, and WBO, and provide the locations for artificial burrows for WBO, within an approximately 118.2-acre compensation site (Figures 2 and 3). The Applicant has assessed the proposed compensation site as supporting biological resources that include components of suitable WBO habitat (AECOM 2010). A winter season WBO survey of the compensation site will identify if the site is currently occupied by WBO and identify locations for placement of artificial burrows. It is anticipated that this 118.2 acres would fully mitigate potential Project impacts to WBO.

As specified in BIO-13 of the COCs, offsite mitigation for impacts to the occupied WBO habitat will follow CBOC guidelines. The guidelines specify that 9.75 acres of preserved offsite habitat is required to mitigate for one WBO or WBO pair if the habitat is occupied by WBO, or 19.5 acres of preserved offsite habitat if the habitat is unoccupied by WBO. Based on the results of previous WBO surveys of the Project area and surrounding buffers, it is anticipated that the 118.2 acres will be sufficient to provide compensation for the pairs (or individuals assumed to be pairs) of WBO that have been or may be identified within the Project area or buffers. Per the CBOC and CDFG mitigation guidelines, a preconstruction survey will be conducted to determine the number of WBO pairs and the amount of compensation land that will be required to be protected.

The compensatory habitat will be managed for the benefit of WBOs with the following specific goals:

- a. Maintenance of the functionality of artificial and natural burrows; and
- b. Weed management through the minimization of occurrence of weed species at less than 10% cover of the shrub and herb layers. The weed species managed are those considered “moderate” or “high” threat to California wildlands (as defined by the California Invasive Plant Council [CAL-IPC 2006] and noxious weeds rated “A” or “B” by the California Department of Food and Agriculture and any federally rated pest plants [CDFA 2010]).

This page intentionally left blank.

6.0 REFERENCES

AECOM

- 2010 Abengoa Mojave Solar Project Compensatory Mitigation Site Details Letter Report. April.

California Burrowing Owl Consortium (CBOC)

- 1993 Burrowing Owl Survey Protocols and Mitigation Guidelines. Sacramento, California.

California Department of Fish and Game (CDFG)

- 1995 Staff report on burrowing owl mitigation. Unpublished report.

California Department of Food and Agriculture (CDFA)

- 2010 Pest Ratings of Noxious Weed Species and Noxious Weed Seed. State of California Department of Food and Agriculture, Division of Plant Health & Pest Prevention Services. January.

California Invasive Plant Council (Cal-IPC)

- 2006 California Invasive Plant Inventory. Cal-IPC Publication 2006-02. California Invasive Plant Council: Berkeley, California. Available at www.cal-ipc.org.

California Energy Commission (CEC)

- 2010 Abengoa Mojave Solar Project: Commission Decision. CEC-800-2010-008 - CMF, Docket Number 09-AFC-5

Clark, H. O., Jr., and D. L. Plumpton

- 2005 A Simple One-Way Door Design for Passive Relocation of Western Burrowing Owls. California Fish and Game 91:286-289. Available at <http://www.docstoc.com/docs/1660512/Clark-HO-Jr-and-DL-Plumpton-2005-A-simple-one-way-door-design-for-passive-relocation-of-western-burrowing-owls--California-Fish-and-Game-91286-289>.

EDAW

- 2007 Harper Lake Solar Project Burrowing Owl Presence/Absence Survey, San Bernardino County, California. December.

2009 Report Summarizing Results of the Proposed Harper Lake Solar Project Burrowing Owl Presence/Absence Surveys. January.

Mojave Solar, LLC (MSLLC)

2009 Mojave Solar Project Application for Certification. Volumes 1 through 3. July.

Trulio, Lynne A.

1995 Passive Relocation: A Method to Preserve Burrowing Owls on Disturbed Sites. *Journal of Field Ornithology* 66(11): 99–106.

APPENDIX A
BURROWING OWL SURVEY PROTOCOL AND
MITIGATION GUIDELINES

BURROWING OWL SURVEY PROTOCOL
AND MITIGATION GUIDELINES

Prepared by:

The California Burrowing Owl Consortium

April 1993

INTRODUCTION

The California Burrowing Owl Consortium developed the following Survey Protocol and Mitigation Guidelines to meet the need for uniform standards when surveying burrowing owl (*Speotyto cunicularia*) populations and evaluating impacts from development projects. The California Burrowing Owl Consortium is a group of biologists in the San Francisco Bay area who are interested in burrowing owl conservation. The following survey protocol and mitigation guidelines were prepared by the Consortium's Mitigation Committee. These procedures offer a decision-making process aimed at preserving burrowing owls in place with adequate habitat.

California's burrowing owl population is clearly in peril and if declines continue unchecked the species may qualify for listing. Because of the intense pressure for development of open, flat grasslands in California, resource managers frequently face conflicts between owls and development projects. Owls can be affected by disturbance and habitat loss, even though there may be no direct impacts to the birds themselves or their burrows. There is often inadequate information about the presence of owls on a project site until ground disturbance is imminent. When this occurs there is usually insufficient time to evaluate impacts to owls and their habitat. The absence of standardized field survey methods impairs adequate and consistent impact assessment during regulatory review processes, which in turn reduces the possibility of effective mitigation.

These guidelines are intended to provide a decision-making process that should be implemented wherever there is potential for an action or project to adversely affect burrowing owls or the resources that support them. The process begins with a four-step survey protocol to document the presence of burrowing owl habitat, and evaluate burrowing owl use of the project site and a surrounding buffer zone. When surveys confirm occupied habitat, the mitigation measures are followed to minimize impacts to burrowing owls, their burrows and foraging habitat on the site. These guidelines emphasize maintaining burrowing owls and their resources in place rather than minimizing impacts through displacement of owls to an alternate site.

Each project and situation is different and these procedures may not be applicable in some circumstances. Finally, these are not strict rules or requirements that must be applied in all situations. They are guidelines to consider when evaluating burrowing owls and their habitat, and they suggest options for burrowing owl conservation when land use decisions are made.

Section 1 describes the four phase Burrowing Owl Survey Protocol. Section 2 contains the Mitigation Guidelines. Section 3 contains a discussion of various laws and regulations that protect burrowing owls and a list of references cited in the text.

We have submitted these documents to the California Department of Fish and Game (CDFG) for review and comment. These are untested procedures and we ask for your comments on improving their usefulness.

SECTION 1 BURROWING OWL SURVEY PROTOCOL

PHASE I: HABITAT ASSESSMENT

The first step in the survey process is to assess the presence of burrowing owl habitat on the project site including a 150-meter (approx. 500 ft.) buffer zone around the project boundary (Thomsen 1971, Martin 1973).

Burrowing Owl Habitat Description

Burrowing owl habitat can be found in annual and perennial grasslands, deserts, and scrublands characterized by low-growing vegetation (Zarn 1974). Suitable owl habitat may also include trees and shrubs if the canopy covers less than 30 percent of the ground surface. Burrows are the essential component of burrowing owl habitat: both natural and artificial burrows provide protection, shelter, and nests for burrowing owls (Henny and Blus 1981). Burrowing owls typically use burrows made by fossorial mammals, such as ground squirrels or badgers, but also may use man-made structures, such as cement culverts; cement, asphalt, or wood debris piles; or openings beneath cement or asphalt pavement.

Occupied Burrowing Owl Habitat

Burrowing owls may use a site for breeding, wintering, foraging, and/or migration stopovers. Occupancy of suitable burrowing owl habitat can be verified at a site by an observation of at least one burrowing owl, or, alternatively, its molted feathers, cast pellets, prey remains, eggshell fragments, or excrement at or near a burrow entrance. Burrowing owls exhibit high site fidelity, reusing burrows year after year (Rich 1984, Feeney 1992). A site should be assumed occupied if at least one burrowing owl has been observed occupying a burrow there within the last three years (Rich 1984).

The Phase II burrow survey is required if burrowing owl habitat occurs on the site. If burrowing owl habitat is not present on the project site and buffer zone, the Phase II burrow survey is not necessary. A written report of the habitat assessment should be prepared (Phase IV), stating the reason(s) why the area is not burrowing owl habitat.

PHASE II: BURROW SURVEY

1. A survey for-burrows and owls should be conducted by walking through suitable habitat over the entire project site and in areas within 150 meters (approx 500 ft.) of the project impact zone. This 150-meter buffer zone is included to account for adjacent burrows and foraging habitat outside the project area and impacts from factors such as noise and vibration due to heavy equipment which could impact resources outside the project area.

2. Pedestrian survey transects should be spaced to allow 100 percent visual coverage of the ground surface. The distance between transect center lines should be no more than 30 meters (approx. 100 ft.), and should be reduced to account for differences in terrain, vegetation density, and ground surface visibility. To efficiently survey projects larger than 100 acres, it is recommended that two or more surveyors conduct concurrent surveys. Surveyors should maintain a minimum distance of 50 meters (approx. 160 ft.) from any owls or occupied burrows. It is important to minimize disturbance near occupied burrows during all seasons.
3. If burrows or burrowing owls are recorded on the site, a map should be prepared of the burrow concentration areas. A breeding season survey and census (Phase III) of burrowing owls is the next step required.
4. Prepare a report (Phase IV) of the burrow survey stating whether or not burrows are present.
5. A preconstruction survey may be required by project-specific mitigations no more than 30 days prior to ground disturbing activity.

PHASE III: BURROWING OWL SURVEYS, CENSUS AND MAPPING

If the project site contains burrows that could be used by burrowing owls, then survey efforts should be directed towards determining owl presence on the site. Surveys in the breeding season are required to describe if, when, and how the site is used by burrowing owls. If no owls are observed using the site during the breeding season, a winter survey is required.

Survey Methodology

A complete burrowing owl survey consists of four site visits. During the initial site visit examine burrows for owl sign and map the locations of occupied burrows. Subsequent observations should be conducted from as many fixed points as necessary to provide visual coverage of the site using spotting scopes or binoculars. It is important to minimize disturbance near occupied burrows during all seasons. Site visits must be repeated on four separate days. Conduct these visits from two hours before sunset to one hour after or from one hour before to two hours after sunrise. Surveys should be conducted during weather that is conducive to observing owls outside their burrows. Avoid surveys during heavy rain, high winds (> 20 mph), or dense fog.

Nesting Season Survey. The burrowing owl nesting season begins as early as February 1 and continues through August 31 (Thomsen 1971, Zam 1974). The timing of nesting activities may vary with latitude and climatic conditions. If possible, the nesting season survey should be conducted during the peak of the breeding season, between April 15 and July 15. Count and map all burrowing owl sightings, occupied burrows, and burrows with owl sign. Record numbers of pairs and juveniles, and behavior such as courtship and copulation. Map the approximate territory boundaries and foraging areas if known.

Survey for Winter Residents (non-breeding owls). Winter surveys should be conducted between December 1 and January 31, during the period when wintering owls are most likely to be present. Count and map all owl sightings, occupied burrows, and burrows with owl sign.

Surveys Outside the Winter and Nesting Seasons. Positive results, (i.e., owl sightings)- outside of the above survey periods would be adequate to determine presence of owls on site. However, results of these surveys may be inadequate for mitigation planning because the numbers of owls and their pattern of distribution may change during winter and nesting seasons. Negative results during surveys outside the above periods are not conclusive proof that owls do not use the site.

Preconstruction Survey. A preconstruction survey may be required by project-specific mitigations and should be conducted no more than 30 days prior to ground disturbing activity.

PHASE IV: RESOURCE SUMMARY, WRITTEN REPORT

A report should be prepared for CDFG that gives the results of each Phase of the survey protocol, as outlined below.

Phase I: Habitat Assessment

1. Date and time of visit(s) including weather and visibility conditions; methods of survey.
2. Site description including the following information: location, size, topography, vegetation communities, and animals observed during visit(s).
3. An assessment of habitat suitability for burrowing owls and explanation.
4. A map of the site.

Phase II: Burrow Survey

1. Date and time of visits including weather and visibility conditions; survey methods including transect spacing.
2. A more detailed site description should be made during this phase of the survey protocol including a partial plant list of primary vegetation, location of nearest freshwater (on or within one mile of site), animals observed during transects.
3. Results of survey transects including a map showing the location of concentrations of burrow(s) (natural or artificial) and owl(s), if present.

Phase III: Burrowing Owl Surveys, Census and Mapping

1. Date and time of visits including weather and visibility conditions; survey methods including transect spacing.
2. Report and map the location of all burrowing owls and owl sign. Burrows occupied by owl(s) should be mapped indicating the number of owls at each burrow. Tracks, feathers, pellets, or other items (prey remains, animal scat) at burrows should also be reported.
3. Behavior of owls during the surveys should be carefully recorded (from a distance) and reported. Describe and map areas used by owls during the surveys. Although not required, all behavior is valuable to document including feeding, resting, courtship, alarm, territorial, parental, or juvenile behavior.
4. Both winter and nesting season surveys should be summarized. If possible include information regarding productivity of pairs, seasonal pattern of use, and include a map of the colony showing territorial boundaries and home ranges.
5. The historical presence of burrowing owls on site should be documented, as well as the source of such information (local bird club, Audubon society, other biologists, etc.).

Burrowing: Owl Survey Protocol

April 1993




Figure 1.

SECTION 2 BURROWING OWL MITIGATION GUIDELINES

The objective of these mitigation guidelines is to minimize impacts to burrowing owls and the resources that support viable owl populations. These guidelines are intended to provide a decision-making process that should be implemented wherever there is potential for an action or project to adversely affect burrowing owls or their resources. The process begins with a four-step survey protocol (see *Burrowing Owl Survey Protocol*) to document the presence of burrowing owl habitat, and evaluate burrowing owl use of the project site and a surrounding buffer zone. When surveys confirm occupied habitat, the mitigation measures described below are followed to minimize impacts to burrowing owls, their burrows and foraging habitat on the site. These guidelines emphasize maintaining burrowing owls and their resources in place rather than minimizing impacts through displacement of owls to an alternate site.

Mitigation actions should be carried out prior to the burrowing owl breeding season, generally from February 1 through August 31 (Thomsen 1971, Zarn 1974). The timing of nesting activity may vary with latitude and climatic conditions. Project sites and buffer zones with suitable habitat should be resurveyed to ensure no burrowing owls have occupied them in the interim period between the initial surveys and ground disturbing activity. Repeat surveys should be conducted not more than 30 days prior to initial ground disturbing activity.

DEFINITION OF IMPACTS

1. Disturbance or harassment within 50 meters (approx. 160 ft.) of occupied burrows.
2. Destruction of burrows and burrow entrances. Burrows include structures such as culverts, concrete slabs and debris piles that provide shelter to burrowing owls.
3. Degradation of foraging habitat adjacent to occupied burrows.

GENERAL CONSIDERATIONS

1. Occupied burrows should not be disturbed during the nesting season, from February 1 through August 31, unless the Department of Fish and Game verifies that the birds have not begun egg-laying and incubation or that the juveniles from those burrows are foraging independently and capable of independent survival at an earlier date.
2. A minimum of 6.5 acres of foraging habitat, calculated on a 100-m (approx. 300 ft.) foraging radius around the natal burrow, should be maintained per pair (or unpaired resident single bird) contiguous with burrows occupied within the last three years (Rich 1984, Feeney 1992). Ideally, foraging habitat should be retained in a long-term conservation easement.

3. When destruction of occupied burrows is unavoidable, burrows should be enhanced (enlarged or cleared of debris) or created (by installing artificial burrows) in a ratio of 1:1 in adjacent suitable habitat that is contiguous with the foraging habitat of the affected owls.
4. If owls must be moved away from the disturbance area, passive relocation (see below) is preferable to trapping. A time period of at least one week is recommended to allow the owls to move and acclimate to alternate burrows.
5. The mitigation committee recommends monitoring the success of mitigation programs as required in Assembly Bill 3180. A monitoring plan should include mitigation success criteria and an annual report should be submitted to the California Department of Fish and Game.

AVOIDANCE

Avoid Occupied Burrows

No disturbance should occur within 50 m (approx. 160 ft.) of occupied burrows during the non-breeding Season of September 1 through January 31 or within 75 m (approx. 250 ft.) during the breeding Season of February 1 through August 31. Avoidance also requires that a minimum of 6.5 acres of foraging habitat be preserved contiguous with occupied burrow sites for each pair of breeding burrowing owls (with or without dependent young) or single unpaired resident bird (Figure 2).


MITIGATION FOR UNAVOIDABLE IMPACTS

On-site Mitigation

On-site passive relocation should be implemented if the above avoidance requirements cannot be met. Passive relocation is defined as encouraging owls to move from occupied burrows to alternate natural or artificial burrows that are beyond 50 m from the impact zone and that are within or contiguous to a minimum of 6.5 acres of foraging habitat for each pair of relocated owls (Figure 3). Relocation of owls should only be implemented during the non-breeding season. On-site habitat should be preserved in a conservation easement and managed to promote burrowing owl use of the site.

Owls should be excluded from burrows in the immediate impact zone and within a 50 m (approx. 160 ft.) buffer zone by installing one-way doors in burrow entrances: One-way doors should be left in place 48 hours to insure owls have left the burrow before excavation. One alternate natural or artificial burrow should be provided for each burrow that will be excavated in the project impact zone. The project area should be monitored daily for one week to confirm owl use of alternate burrows before excavating burrows in the immediate impact zone. Whenever possible, burrows should be excavated using hand tools and refilled to prevent reoccupation. Sections of flexible plastic pipe or burlap bags should be inserted into the tunnels

AVOIDANCE




Non-breeding season

1 Sept. - 31 Jan.

No impacts within
50 m of occupied
burrow

Occupied
burrow

Maintain
at least 6.5 acres
foraging habitat



Breeding season

1 Feb. - 31 Aug.

No impacts within
75 m of occupied
burrow

Occupied
burrow

Maintain
at least 6.5 acres
foraging habitat




Figure 2. Burrowing owl mitigation guidelines.

ON-SITE MITIGATION IF AVOIDANCE NOT MET

(More than 6.5 acres suitable habitat available)




Figure 3. Burrowing owl mitigation guidelines.

during excavation to maintain an escape route for any animals inside the burrow.

Off-site Mitigation

If the project will reduce suitable habitat on-site below the threshold level of 6.5 acres per relocated pair or single bird, the habitat should be replaced off-site. Off-site habitat must be suitable burrowing owl habitat, as defined in the *Burrowing Owl Survey Protocol*, and the site approved by CDFG. Land should be purchased and/or placed in a conservation easement in perpetuity and managed to maintain suitable habitat. Off-site mitigation should use one of the following ratios:

1. Replacement of occupied habitat with occupied habitat: 1.5 times 6.5 (9.75) acres per pair or single bird.
2. Replacement of occupied habitat with habitat contiguous to currently occupied habitat: 2 times 6.5 (13.0) acres per pair or single bird.
3. Replacement of occupied habitat with suitable unoccupied habitat: 3 times 6.5 (19.5) acres per pair or single bird.

SECTION 3 LEGAL STATUS

The burrowing owl is a migratory bird species protected by international treaty under the Migratory Bird Treaty Act (MBTA) of 1918 (16 U.S.C. 703-711). The MBTA makes it unlawful to take, possess, buy, sell, purchase, or barter, any migratory bird listed in 50 C.F.R. Part 10, including feathers or other parts, nests, eggs, or products, except as allowed by implementing regulations (50 C.F.R. 21). Sections 3503, 3503.5, and 3800 of the California Department of Fish and Game Code prohibit the take, possession, or destruction of birds, their nests or eggs. Implementation of the take provisions requires that project-related disturbance at active nesting territories be reduced or eliminated during critical phases of the nesting cycle (March 1 - August 15, annually). Disturbance that causes nest abandonment and/or loss of reproductive effort (e.g., killing or abandonment of eggs or young) or the loss of habitat upon which the birds depend is considered “taking” and is potentially punishable by fines and/or imprisonment. Such taking would also violate federal law protecting migratory birds (e.g., MBTA).

The burrowing owl is a Species of Special Concern to California because of declines of suitable habitat and both localized and statewide population declines. Guidelines for the Implementation of the California Environmental Quality Act (CEQA) provide that a species be considered as endangered or “rare” regardless of appearance on a formal list for the purposes of the CEQA (Guidelines, Section 15380, subsections b and d). The CEQA requires a mandatory findings of significance if impacts to threatened or endangered species are likely to occur (Sections 21001(c), 21083. Guidelines 15380, 15064, 15065). Avoidance or mitigation must be presented to reduce impacts to less than significant levels.

CEQA AND SUBDIVISION MAP ACT

CEQA Guidelines Section 15065 directs that a mandatory finding of significance is required for projects that have the potential to substantially degrade or reduce the habitat of, or restrict the range of a threatened or endangered species. CEQA requires agencies to implement feasible mitigation measures or feasible alternatives identified in EIR’s for projects which will otherwise cause significant adverse impacts (Sections 21002, 21081, 21083; Guidelines, sections 15002, subd. (a)(3), 15021, subd. (a)(2), 15091, subd. (a).).

To be legally adequate, mitigation measures must be capable of “avoiding the impact altogether by not taking a certain action or parts of an action”; “minimizing impacts by limiting the degree or magnitude of the action and its implementation”; “rectifying the impact by repairing, rehabilitating or restoring the impacted environment”; “or reducing or eliminating the impact over time by preservation and maintenance operations during the life of the action.” (Guidelines, Section 15.370).

Section 66474 (e) of the Subdivision Map Act states “a legislative body of a city or county shall deny approval of a tentative map or parcel map for which a tentative map was not required, if

it makes any of the following findings:... (e) that the design of the subdivision or the proposed improvements are likely to cause substantial environmental damage or substantially and avoidably injure fish and wildlife or their habitat". In recent court cases, the court upheld that Section 66474(e) provides for environmental impact review separate from and independent of the requirements of CEQA (Topanga Assn. for a Scenic Community v. County of Los Angeles, 263 Cal. Rptr. 214 (1989).). The finding in Section 66174 is in addition to the requirements for the preparation of an EIR or Negative Declaration.

LITERATURE CITED

- Feeney, L. 1992. Site fidelity in burrowing owls. Unpublished paper presented to Raptor Research Annual Meeting, November 1992. Seattle, Washington.
- Haug, E. A. and L. W. Oliphant. 1990. Movements, activity patterns, and habitat use of burrowing owls in Saskatchewan. J. Wildlife Management 54:27-35.
- Henny, C. J. and L. J. Blus. 1981. Artificial burrows provide new insight into burrowing owl nesting biology. Raptor Research 15:82-85.
- Martin, D. J. 1973. Selected aspects of burrowing owl ecology and behavior. Condor 75:446-456.
- Rich, T. 1984. Monitoring burrowing owl populations: Implications of burrow re-use. Wildlife Society Bulletin 12: 178- 180.
- Thomsen, L. 1971. Behavior and ecology of burrowing owls on the Oakland Municipal Airport. Condor 73: 177-192.
- Zam, M. 1974. Burrowing owl. U. S. Department of Interior, Bureau of Land Management. Technical Note T-N 250. Denver, Colorado. 25pp.

APPENDIX N

CULTURAL RESOURCES STUDY

CONFIDENTIAL APPENDIX

ON FILE WITH DEPARTMENT OF ENERGY

CONTACT: CAROL HAMMEL-SMITH, 202.287.5655

APPENDIX O

SOCIOECONOMICS

Appendix O: Socioeconomics

Table O-1: Employment Growth by Occupation (Most Job Openings) - San Bernardino, Los Angeles, and Kern Counties, 2006-2016

San Bernardino		Los Angeles		Kern	
Occupation	Number of New Jobs Projected	Occupation	Number of New Jobs Projected	Occupation	Number of New Jobs Projected
Retail Salespersons	24,360	Retail Salespersons	63,140	Farmworkers and Laborers	14,270
Cashiers	20,170	Personal and Home Care Aides	51,810	Cashiers	3,820
Waiters and Waitresses	15,340	Cashiers	48,060	Retail Salespersons	3,760
Laborers and Freight, Stock, and Material Movers	13,460	Office Clerks	35,820	Elementary School Teachers (Except Special Education)	2,160
Combined Food Preparation and Serving Workers (Including Fast Food)	12,880	Waiters and Waitresses	34,590	Laborers and Freight, Stock, and Material Movers	2,140
Elementary School Teachers (Except Special Education)	11,450	Laborers and Freight, Stock, and Material Movers	32,440	Waiters and Waitresses	2,040
Office Clerks	11,190	Customer Service Representatives	29,880	Combined Food Preparation and Serving Workers (Including Fast Food)	1,950
Personal and Home Care Aides	9,710	Registered Nurses	24,810	Truck Drivers	1,940
Customer Service Representatives	8,890	Elementary School Teachers (Except Special Education)	22,810	Office Clerks	1,730
Registered Nurses	8,380	Combined Food Preparation and Serving Workers (Including Fast Food)	21,070	Correctional Officers and Jailers	1,690

Source: California EDD, 2009.

Tables O-2 through O-4 present San Bernardino County, Los Angeles County, and Kern County employment figures for those types of skilled workers (by craft) required for construction and operation of the Project. Existing employment figures for 2006 are provided, as well as employment projections for the selected occupations for 2016.

Table O-2: Skilled Workers by Craft Required by Project - San Bernardino County

Occupational Title	Annual Average Employment		Employment Change		Average Annual Job Openings		
	2006	2016	Number	Percent	New Jobs	Net Replacements	Total
Construction Managers	4,380	5,110	730	16.7	73	68	141
Construction Workers	116,810	132,160	15,350	13.1	1,535	1,815	3,350
Carpenters	28,850	32,390	3,540	12.3	354	390	744
Cement Masons and Concrete Finishers	4,110	4,690	580	14.1	58	119	177
Construction Laborers	27,930	32,080	4,150	14.9	415	210	625
Paving, Surfacing, and Tamping Equipment Operators	630	720	90	14.3	9	13	22
Operating Engineers and Other Construction Equipment Operators	4,790	5,460	670	14.0	67	93	160
Drywall and Ceiling Tile Installers	7,570	8,310	740	9.8	74	104	178
Electricians	6,740	7,600	860	12.8	86	174	260
Painters, Construction and Maintenance	7,950	9,210	1,260	15.8	126	141	267
Plumbers, Pipefitters, and Steamfitters	4,630	5,330	700	15.1	70	96	166
Metal Workers and Plastic Workers	19,460	20,800	1,340	6.9	134	378	512
Helpers - Construction Trades	120	130	10	8.3	1	3	4
Maintenance and Repair Workers, General	11,920	13,690	1,770	14.8	177	29	206
Welders, Cutters, Solderers, and Brazers	3,960	4,640	680	17.2	68	84	152
Plant and System Operators	2,030	2,380	350	17.2	35	46	81
Power Plant Operators	310	370	60	19.4	6	11	17
Architects, Surveyors, and Cartographers	1,420	1,670	250	17.6	25	35	60
Engineering Managers	1,370	1,600	230	16.8	23	28	51
Supervisors, Construction and Extraction Workers	10,990	12,380	1,390	12.6	139	153	292
Machinists	2,630	2,960	330	12.5	33	41	74

Source: California EDD, 2009

Table O-3: Skilled Workers by Craft Required by Project - Los Angeles County

Occupational Title	Annual Average Employment		Employment Change		Average Annual Job Openings		
	2006	2016	Number	Percent	New Jobs	Net Replacements	Total
Construction Managers	10,320	11,670	1,350	13.1	135	160	295
Construction Workers	143,280	153,890	10,610	7.4	1,061	2,347	3,408
Carpenters	28,070	30,050	1,980	7.1	198	380	578
Cement Masons and Concrete Finishers	4,150	4,530	380	9.2	38	120	158
Construction Laborers	31,330	34,810	3,480	11.1	348	236	584
Paving, Surfacing, and Tamping Equipment Operators	790	870	80	10.1	8	16	24
Operating Engineers and Other Construction Equipment Operators	4,410	4,780	370	8.4	37	85	122
Drywall and Ceiling Tile Installers	8,600	8,850	250	2.9	25	118	143
Electricians	13,040	13,700	660	5.1	66	336	402
Painters, Construction and Maintenance	13,240	14,250	1,010	7.6	101	235	336
Plumbers, Pipefitters, and Steamfitters	12,090	12,900	810	6.7	81	249	330
Metal Workers and Plastic Workers	54,990	52,230	-2,760	-5.0	0	1,024	1,024
Helpers - Construction Trades	6,670	7,020	350	5.2	35	169	204
Maintenance and Repair Workers, General	30,520	32,930	2,410	7.9	241	75	316
Welders, Cutters, Solderers, and Brazers	8,410	8,890	480	5.7	48	178	226
Plant and System Operators	4,620	4,980	360	7.8	36	104	140
Power Plant Operators	320	360	40	12.5	4	11	15
Architects, Surveyors, and Cartographers	6,470	7,030	560	8.7	56	135	191
Engineering Managers	8,410	8,840	430	5.1	43	170	213
Supervisors, Construction and Extraction Workers	15,490	16,440	950	6.1	95	216	311
Machinists	10,400	10,380	-20	-0.2	0	161	161

Source: California EDD, 2009

Table O-4: Skilled Workers by Craft Required by Project - Kern County

Occupational Title	Annual Average Employment		Employment Change		Average Annual Job Openings		
	2006	2016	Number	Percent	New Jobs	Net Replacements	Total
Construction Managers	1,050	1,250	200	19.0	20	16	36
Construction Workers	19,190	21,310	2,120	11.0	212	321	533
Carpenters	2,740	3,060	320	11.7	32	37	69
Cement Masons and Concrete Finishers	990	1,100	110	11.1	11	29	40
Construction Laborers	4,860	5,570	710	14.6	71	37	108
Paving, Surfacing, and Tamping Equipment Operators	100	110	10	10.0	1	2	3
Operating Engineers and Other Construction Equipment Operators	1,500	1,570	70	4.7	7	29	36
Drywall and Ceiling Tile Installers	920	980	60	6.5	6	13	19
Electricians	2,350	2,580	230	9.8	23	61	84
Painters, Construction and Maintenance	990	1,120	130	13.1	13	18	31
Plumbers, Pipefitters, and Steamfitters	1,340	1,530	190	14.2	19	28	47
Metal Workers and Plastic Workers	2,200	2,620	420	19.1	42	44	86
Helpers - Construction Trades	870	960	90	10.3	9	22	31
Maintenance and Repair Workers, General	2,630	3,100	470	17.9	47	7	54
Welders, Cutters, Solderers, and Brazers	1,110	1,430	320	28.8	32	24	56
Plant and System Operators	1,460	1,600	140	9.6	14	39	53
Power Plant Operators	190	220	30	15.8	3	7	10
Architects, Surveyors, and Cartographers	400	500	100	25.0	10	10	20
Engineering Managers	380	460	80	21.1	8	8	16
Supervisors, Construction and Extraction Workers	2,460	2,820	360	14.6	36	34	70
Machinists	410	480	70	17.1	7	6	13

Source: California EDD, 2009

APPENDIX P

PUBLIC HEALTH AND SAFETY

Health Risk Assessment Support Data

Health Risk Assessment Process, Goals, Assumptions, and Uses

“In recent years, the public has become increasingly aware of the presence of harmful chemicals in our environment. Many people express concerns about pesticides and other foreign substances in food, contaminants in drinking water, and toxic pollutants in the air. Others believe these concerns are exaggerated or unwarranted. How can we determine which of these potential hazards really deserve attention? How do we, as a society, decide where to focus our efforts and resources to control these hazards? When we hear about toxic threats that affect us personally, such as the discovery of industrial waste buried in our neighborhood or near our children’s school, how concerned should we be?

Health risk assessment is a scientific tool designed to help answer these questions. Government agencies rely on risk assessments to help them determine which potential hazards are the most significant. Risk assessments can also guide regulators in abating environmental hazards. Members of the public who learn the basics of risk assessment can improve their understanding of both real and perceived environmental hazards, and they can work more effectively with decision makers on solutions to environmental problems.

Chemicals can be either beneficial or harmful, depending on a number of factors, such as the amounts to which we are exposed. Low levels of some substances may be necessary for good health, but higher levels may be harmful. Health risk assessments are used to determine if a particular chemical poses a significant risk to human health and, if so, under what circumstances. Could exposure to a specific chemical cause significant health problems? How much of the chemical would someone have to be exposed to before it would be dangerous? How serious could the health risks be? What activities might put people at increased risk?

If it were possible to prevent all human exposure to all hazardous chemicals, there would be no need for risk assessment. However, the total removal of harmful pollutants from the environment is often infeasible or impossible, and many naturally occurring substances also pose health risks. Risk assessment helps scientists and regulators identify serious health hazards and determine realistic goals for reducing exposure to toxics so that there is no significant health threat to the public.

Estimating the hazards posed by toxic chemicals in the environment involves the compilation and evaluation of complex sets of data. Government regulators, therefore, turn to specialists to perform or assist with risk assessments. These specialists include scientists with degrees in toxicology (the study of the toxic effects of chemicals) and epidemiology (the study of disease or illness in populations) as well as physicians, biologists, chemists, and engineers.

The term “health risk assessment” is often misinterpreted. People sometimes think that a risk assessment will tell them whether a current health problem or symptom was caused by exposure

to a chemical. This is not the case. Scientists who are searching for links between chemical exposures and health problems in a community may conduct an epidemiologic study. These studies typically include a survey of health problems in a community and a comparison of health problems in that community with those in other cities, communities, or the population as a whole.

Although they are both important, health risk assessments and epidemiologic studies have different objectives. Most epidemiologic studies evaluate whether *past* chemical exposures may be responsible for documented health problems in a specific group of people. In contrast, health risk assessments are used to estimate whether current or future chemical exposures will pose health risks to a broad population, such as a city or a community. Scientific methods used in health risk assessment cannot be used to link individual illnesses to past chemical exposures, nor can health risk assessments and epidemiologic studies prove that a specific toxic substance caused an individual's illness.

The U.S. Environmental Protection Agency (U.S. EPA) is a leading risk assessment agency at the federal level. In California, the Office of Environmental Health Hazard Assessment (OEHHA) in the California Environmental Protection Agency (Cal/EPA) has the primary responsibility for developing procedures and practices for performing health risk assessments. Other agencies within Cal/EPA, such as the Department of Pesticide Regulation and the Department of Toxic Substances Control, have extensive risk assessment programs of their own but work closely with OEHHA.

The Department of Pesticide Regulation uses risk assessments to make regulatory decisions concerning safe pesticide uses. The Department of Toxic Substances Control uses risk assessments to determine requirements for the management and cleanup of hazardous wastes. OEHHA's health risk assessments are used by the Air Resources Board to develop regulations governing toxic air contaminants, and by the Department of Health Services to develop California's drinking water standards. These agencies' decisions take into account the seriousness of potential health effects along with the economic and technical feasibility of measures that can reduce the health risks.

Health risk assessment requires both sound science and professional judgment and is a constantly developing process. Cal/EPA is nationally recognized for developing new procedures that improve the accuracy of risk assessments. Cal/EPA also works closely with U.S. EPA in all phases of risk assessment.

The risk assessment process is typically described as consisting of four basic steps: hazard identification, exposure assessment, dose-response assessment, and risk characterization. Each of these steps will be explained in the following text.

Hazard Identification

In the first step, hazard identification, scientists determine the types of health problems a chemical could cause by reviewing studies of its effects in humans and laboratory animals. Depending on the chemical, these health effects may include short-term ailments, such as headaches; nausea; and eye, nose, and throat irritation; or chronic diseases, such as cancer. Effects on sensitive populations, such as pregnant women and their developing fetuses, the elderly, or those with health problems

(including those with weakened immune systems), must also be considered. Responses to toxic chemicals will vary depending on the amount and length of exposure. For example, short-term exposure to low concentrations of chemicals may produce no noticeable effect, but continued exposure to the same levels of chemicals over a long period of time may eventually cause harm. An important step in hazard identification is the selection of key research studies that can provide accurate, timely information on the hazards posed to humans by a particular chemical. The selection of a study is based upon factors such as whether the study has been peer reviewed by qualified scientists, whether the study's findings have been verified by other studies, and the species tested (human studies provide the best evidence). Some studies may involve humans that have been exposed to the chemical, while others may involve studies with laboratory animals.

Human data frequently are useful in evaluating human health risks associated with chemical exposures. Human epidemiologic studies typically examine the effects of chemical exposure on a large number of people, such as employees exposed to varying concentrations of chemicals in the workplace. In many cases, these exposures took place prior to the introduction of modern worker-safety measures.

One weakness of occupational studies is that they generally measure the effects of chemicals on healthy workers and do not consider children, the elderly, those with pre-existing medical conditions, or other sensitive groups. Since occupational studies are not controlled experiments, there may be uncertainties about the amount and duration of exposure or the influence of lifestyle choices, such as smoking or alcohol use, on the health of workers in the studies. Exposure of workers to other chemicals at the same time may also influence and complicate the results.

Laboratory studies using human volunteers are better able to gauge some health effects because chemical exposures can then be measured with precision. But these studies usually involve small numbers of people and, in conformance with ethical and legal requirements, use only adults who agree to participate in the studies. Moreover, laboratory studies often use simple measurements that identify immediate responses to the chemical but might miss significant, longer-term health effects. Scientists can also use physicians' case reports of an industrial or transportation accident in which individuals were unintentionally exposed to a chemical. However, these reports may involve very small numbers of people, and the level of exposure to the chemical could be greater than exposures to the same chemical in the environment. Nevertheless, human studies are preferred for risk assessment, so OEIHA makes every effort to use them when they are available.

Because the effects of the vast majority of chemicals have not been studied in humans, scientists must often rely on animal studies to evaluate a chemical's health effects. Animal studies have the advantage of being performed under controlled laboratory conditions that reduce much of the uncertainty related to human studies. If animal studies are used, scientists must determine whether a chemical's health effects in humans are likely to be similar to those in the animals tested. Although effects seen in animals can also occur in humans, there may be subtle or even significant differences in the ways humans and experimental animals react to a chemical. Comparison of human and animal metabolism may be useful in selecting the animal species that should be studied, but it is often not possible to determine which species is most like humans in its response to a chemical exposure. However, if similar effects were found in more than one species, the results would strengthen the evidence that humans may also be at risk.

Exposure Assessment

In exposure assessment, scientists attempt to determine how long people were exposed to a chemical; how much of the chemical they were exposed to; whether the exposure was continuous or intermittent; and how people were exposed – through eating, drinking water and other liquids, breathing, or skin contact. All of this information is combined with factors such as breathing rates, water consumption, and daily activity patterns to estimate how much of the chemical was taken into the bodies of those exposed.

People can be exposed to toxic chemicals in various ways. These substances can be present in the air we breathe, the food we eat, or the water we drink. Some chemicals, due to their particular characteristics, may be both inhaled and ingested. For example, airborne chemicals can settle on the surface of water, soil, leaves, fruits, vegetables, and forage crops used as animal feed. Cows, chickens, or other livestock can become contaminated when eating, drinking, or breathing the chemicals present in the air, water, feed, and soil. Fish can absorb the chemicals as they swim in contaminated water or ingest contaminated food. Chemicals can be absorbed through the skin, so infants and children can be exposed simply by crawling or playing in contaminated dirt. They can also ingest chemicals if they put their fingers or toys in their mouths after playing in contaminated dirt. Chemicals can also be passed on from nursing mothers to their children through breast milk.

To estimate exposure levels, scientists rely on air, water, and soil monitoring; human blood and urine samples; or computer modeling. Although monitoring of a pollutant provides excellent data, it is time consuming, costly, and typically limited to only a few locations. For those reasons, scientists often rely on computer modeling, which uses mathematical equations to describe how a chemical is released and to estimate the speed and direction of its movement through the surrounding environment. Modeling has the advantage of being relatively inexpensive and less time consuming, provided all necessary information is available and the accuracy of the model can be verified through testing.

Computer modeling is often used to assess chemical releases from industrial facilities. Such models require information on the type of chemicals released, facilities' hours of operation, industrial processes that release the chemicals, smokestack height and temperature, any pollution-control equipment that is used, surrounding land type (urban or rural), local topography and meteorology, and census data regarding the exposed population.

In all health risk assessments, scientists must make assumptions in order to estimate human exposure to a chemical. For example, scientists assessing the effects of air pollution may need to make assumptions about the time people spend outdoors, where they are more directly exposed to pollutants in the ambient air, or the time they spend in an area where the pollution is greatest. An assessment of soil contamination may require scientists to make assumptions about people's consumption of fruits and vegetables that may absorb soil contaminants.

To avoid underestimating actual human exposure to a chemical, scientists often look at the range of possible exposures. For example, people who jog in the afternoon, when urban air pollution levels are highest, would have much higher exposures to air pollutants than people who come home after work and relax indoors. Basing an exposure estimate on a value near the higher end of

a range of exposure levels (closer to the levels experienced by the jogger than by the person remaining indoors) provides a realistic worst-case estimate of exposure. These kinds of conservative assumptions, which presume that people are exposed to the highest amounts of a chemical that can be considered credible, are referred to as “health-protective” assumptions.

Dose-Response Assessment

In dose-response assessment, scientists evaluate the information obtained during the hazard identification step to estimate the amount of a chemical that is likely to result in a particular health effect in humans.

An established principle in toxicology is that “the dose makes the poison.” For example, a commonplace chemical like table salt is harmless in small quantities, but it can cause illness in large doses. Similarly, hydrochloric acid, a hazardous chemical, is produced naturally in our stomachs but can be quite harmful if taken in large doses.

Scientists perform a dose-response assessment to estimate how different levels of exposure to a chemical can impact the likelihood and severity of health effects. The dose-response relationship is often different for many chemicals that cause cancer than it is for those that cause other kinds of health problems.

Cancer Effects

For chemicals that cause cancer, the general assumption in risk assessment has been that there are no exposures that have “zero risk” unless there is clear evidence otherwise. In other words, even a very low exposure to a cancer-causing chemical may result in cancer if the chemical happens to alter cellular functions in a way that causes cancer to develop. Thus, even very low exposures to carcinogens might increase the risk of cancer, if only by a very small amount.

Several factors make it difficult to estimate the risk of cancer. Cancer appears to be a progressive disease because a series of cellular transformations is thought to occur before cancer develops. In addition, cancer in humans often develops many years after exposure to a chemical. Also, the best information available on the ability of chemicals to cause cancer often comes from studies in which a limited number of laboratory animals are exposed to levels of chemicals that are much higher than the levels humans would normally be exposed to in the environment. As a result, scientists use mathematical models based on studies of animals exposed to high levels of a chemical to estimate the probability of cancer developing in a diverse population of humans exposed to much lower levels. The uncertainty in these estimates may be rather large. To reduce these uncertainties, risk assessors must stay informed of new scientific research. Data from new studies can be used to improve estimates of cancer risks.

Non-cancer Effects

Non-cancer health effects (such as asthma, nervous system disorders, birth defects, and developmental problems in children) typically become more severe as exposure to a chemical increases. One goal of dose-response assessment is to estimate levels of exposure that pose only a low or negligible risk for non-cancer health effects. Scientists analyze studies of the health effects of a chemical to develop this estimate. They take into account such factors as the quality of the scientific studies, whether humans or laboratory animals were studied, and the degree to which some people may be more sensitive to the chemical than others. The estimated level of exposure

that poses no significant health risks can be reduced to reflect these factors.

Risk Characterization

The last step in risk assessment brings together the information developed in the previous three steps to estimate the risk of health effects in an exposed population. In the risk characterization step, scientists analyze the information developed during the exposure and dose-response assessments to describe the resulting health risks that are expected to occur in the exposed population. This information is presented in different ways for cancer and non-cancer health effects, as explained below.

Cancer Risk

Cancer risk is often expressed as the maximum number of new cases of cancer projected to occur in a population of one million people due to exposure to the cancer-causing substance over a 70-year lifetime. For example, a cancer risk of one in one million means that in a population of one million people, not more than one additional person would be expected to develop cancer as the result of the exposure to the substance causing that risk.

An individual's actual risk of contracting cancer from exposure to a chemical is often less than the theoretical risk to the entire population calculated in the risk assessment. For example, the risk estimate for a drinking-water contaminant may be based on the health-protective assumption that the individual drinks two liters of water from a contaminated source daily over a 70-year lifetime. However, an individual's actual exposure to that contaminant would likely be lower due to a shorter time of residence in the area. Moreover, an individual's risk not only depends on the individual's exposure to a specific chemical but also on his or her genetic background (i.e., a family history of certain types of cancer); health; diet; and lifestyle choices, such as smoking or alcohol consumption.

Cancer risks presented in risk assessments are often compared to the overall risk of cancer in the general U.S. population (about 250,000 cases for every one million people) or to the risk posed by all harmful chemicals in a particular medium, such as the air. The cancer risk from breathing current levels of pollutants in California's ambient air over a 70-year lifetime is estimated to be 760 in one million.

Non-cancer Risk

Non-cancer risk is usually determined by comparing the actual level of exposure to a chemical to the level of exposure that is not expected to cause any adverse effects, even in the most susceptible people. Levels of exposure at which no adverse health effects are expected are called "health reference levels," and they generally are based on the results of animal studies. However, scientists usually set health reference levels much lower than the levels of exposure that were found to have no adverse effects in the animals tested. This approach helps to ensure that real health risks are not underestimated by adjusting for possible differences in a chemical's effects on laboratory animals and humans; the possibility that some humans, such as children and the elderly, may be particularly sensitive to a chemical; and possible deficiencies in data from the animal studies.

Depending on the amount of uncertainty in the data, scientists may set a health reference level 100 to 10,000 times lower than the levels of exposure observed to have no adverse effects in

animal studies. Exposures above the health reference level are not necessarily hazardous, but the risk of toxic effects increases as the dose increases. If an assessment determines that human exposure to a chemical exceeds the health reference level, further investigation is warranted.

Risk managers rely on risk assessments when making regulatory decisions, such as setting drinking water standards, or developing plans to clean up hazardous waste sites. Risk managers are responsible for protecting human health, but they must also consider public acceptance, as well as technological, economic, social, and political factors, when arriving at their decisions. For example, they may need to consider how much it would cost to remove a contaminant from drinking water supplies or how seriously the loss of jobs would affect a community if a factory were to close due to the challenge of meeting regulatory requirements that are set at the most stringent level.

Health risk assessments can help risk managers weigh the benefits and costs of various alternatives for reducing exposure to chemicals. For example, a health risk assessment of a hazardous waste site could help determine whether placing a clay cap over the waste to prevent exposure would offer the same health protection as the more costly option of removing the waste from the site.

One of the most difficult questions of risk management is: How much risk is acceptable? While it would be ideal to completely eliminate all exposure to hazardous chemicals, it is usually not possible or feasible to remove all traces of a chemical once it has been released into the environment. The goal of most regulators is to reduce the health risks associated with exposure to hazardous pollutants to a negligibly low level.

Regulators generally presume that a one-in-one million risk of cancer from life-long exposure to a hazardous chemical is an "acceptable risk" level because the risk is extremely low compared to the overall cancer rate. If a drinking water standard for a cancer-causing chemical were set at the level posing a "one-in-one million" risk, it would mean that not more than one additional cancer case (beyond what would normally occur in the population) would potentially occur in a population of one million people drinking water meeting that standard over a 70-year lifetime.

Actual regulatory standards for chemicals or hazardous waste cleanups may be set at less stringent risk levels, such as one in 100,000 (not more than one additional cancer case per 100,000 people) or one in 10,000 (not more than one additional cancer case per 10,000 people). These less stringent risk levels are often due to economic or technological considerations. Regulatory agencies generally view these higher risk levels to be acceptable if there is no feasible way to reduce the risks further."¹

The exposure and dose-response estimates for the project analysis were conducted using HARP (Version 1.4a).

¹ A Guide to Health Risk Assessment, CalEPA-Office of Environmental Health Hazard Assessment, 1001 I Street, Sacramento, Ca. 95812, (est. 2001).

The following tables summarize the results of the HRA performed by the proposed MS1 facility.

TABLE C.4-1 CRITERIA AND AIR TOXIC POLLUTANTS EMITTED FROM MS1 FACILITY

NOx	Diesel Particulate Matter
CO	Metals (Cooling Tower)
VOC*	Acetaldehyde
SOx	Acrolein
PM10/PM2.5	Benzene
1-3 Butadiene	Ethylbenzene
Formaldehyde	Hexane
PAHs	Naphthalene
Propylene	Propylene Oxide
Toluene	Xylenes

TABLE C.4-2 HEALTH EFFECTS SIGNIFICANT THRESHOLD LEVELS

Agency	Significance Thresholds	
	MDAQMD	State of California
Cancer Risk per million	Moderate Risk $>1 \times 10^{-6}$	≤ 1.0 without T-BACT ≤ 10.0 with T-BACT
Acute HI	Significant Risk $\geq 100 \times 10^{-6}$	1.0
Chronic HI	HI ≥ 10	1.0
Cancer Burden	Significant Health Risk $\geq 10 \times 10^{-6}$ HI ≥ 1	1.0

No specific health related studies were identified which pertain to the local project area for any identified toxic air pollutant or identified specific population.

The other assumptions used in running the HARP program were as follows:

- Emission rates for non-criteria pollutants are taken from AFC Section 5.2, and from Appendix C.1.
- Number of residents affected is based upon the updated 2000 population data for those census tracts or portions of census tracts which lie within the maximum impact receptor radius of the proposed facility.
- All receptors were treated as residential receptors, which allows for the assumption that the MIR, if assumed residential, will represent the highest risk and no other receptor will show risks higher than the MIR. This deletes the need for running worker risks. The HARP risk run options as recommended by South Coast AQMD (Chico, 10-20-05) were utilized (i.e., for cancer – 70-year and derived adjusted method; for chronic – 70-year and derived OEHHHA method; for acute – no options).
- Deposition velocity is taken to be 0.02 m/s, as recommended by ARB for controlled emission sources.
- Fraction of residents with gardens is taken to be 0.15 which is likely conservatively high for the rural (desert) area near the project site.
- Fraction of produce grown at home is taken to be 0.15, which is also likely to be conservatively high for the rural (desert) area near the project site.

The HARP program is a tool that assists with the programmatic requirements of the Air Toxics Hot Spots Program, and it can be used for preparing health risk assessments for other related programs such as air toxic control measure development or facility permitting applications. HARP is a computer based risk assessment program which combines the tools of emission inventory database, facility prioritization, air dispersion modeling, and risk assessment analysis. Use of HARP promotes statewide consistency in the area of risk assessment, increases the efficiency of evaluating potential health impacts, and provides a cost effective tool for developing facility health risk assessments. HARP may be used on single sources, facilities with multiple sources, or multiple facilities in close proximity to each other. The receptor grid used in HARP was the same as the grid used in the air quality impact analysis (AERMOD). The AERMOD files used in the HARP analysis were processed via the HARP On-Ramp program.

The HARP program results for acute and chronic inhalation and chronic non-inhalation exposures, cancer burden and individual cancer risk (workplace and residential) for the proposed sources are included in this Appendix.

The modeling results show that the maximum modeled cancer risk (MIR) from MS1 is expected to be 2.59×10^{-7} . This risk is well below the ten in one million level (with T-BACT), and the MDAQMD significance value. The chronic and acute non-cancer hazard indices are 0.00208 and 0.0101, respectively (at the cancer MIR location). Both are well below the significant impact level of 1.0. The MIR was located offsite approximately 453 feet from the site grid center. At this radius there are no impacted populations, therefore the total cancer burden was calculated to be 0.0, which is also well below the state threshold value of 1.0, as well as being below the MDAQMD Rule 1320 significance level of 0.5. Detailed calculations and results for each significant receptor are included in the modeling results, which are being submitted electronically.

TABLE C.4-3 HEALTH RISK ASSESSMENT SUMMARY (MIR)		
Stationary Sources Only		
Risk Category	Facility Values	Applicable Significance Threshold
Cancer Risk	2.59×10^{-7}	$\leq 10.0 \times 10^{-6}$
Chronic Hazard Index	0.00208	1.0
Acute Hazard Index	0.0101	1.0
Cancer Burden	0	0.5
Facility MIR location coordinates are: Cancer risk and chronic MIR – 469945mE, 3874500mN Acute MIR location coordinates are: Acute MIR – 469945mE, 3874500mN		

The calculated health effects as summarized above do not exceed the district significance threshold values, therefore the health effects would be considered “not significant” and may even be “zero”. These HRA results are also provided on the air modeling CD. Due to length of the results output files, hard copies are not included in this appendix.

The following tables and figures are presented at the end of this appendix:

- Table C.4-4 Sensitive Receptor Listing for the Primary Impact Area
- Table C.4-5 OEHHA/CARB Risk Assessment Health Values
- Table C.4-6 Census Tract Numbers, and Population Data
- Table C.4-7 3 Highest MIR Locations and Risk Values
- Figure C.4-1 Census Tracts in the Site Area
- Figure C.4-2 6-Mile Radius Zone Map
- Figure C.4-3 3 Highest Cancer MIR Locations

Risk Assessment input and output files are included on the modeling CD.

Table C.4-4 Identified Sensitive Receptors and Distances from Site
Harper Lake Solar Generating Station

Receptor ID	Google Earth Data				Dist. From Site, m.	Dist. From Site, ft.	Receptor #	NAD27		
	UTM Em	UTM Nm	Elev., ft.	Site				UTM Em	UTM Nm	Elev. ft.
Kramer Junction	470569	3874265	2062	na	20120.7	na	1	470696	3874280	2013
worker	450560	3872148	2522	3241.5	3241.5	66016.0	2	450687	3872163	2473
worker	468349	3876627	2068	2082.1	2082.1	10635.4	3	468476	3876642	2019
res	450580	3872334	2491	19704.1	19704.1	65889.2	4	450707	3872349	2442
worker	450971	3872223	2478	20689.6	20689.6	64649.1	5	451098	3872238	2429
res	449883	3874649	2471	24559.0	24559.0	67882.5	6	450010	3874664	2422
res-Boron	447224	3881891	2848	28376.3	28376.3	80578.1	7	447351	3881906	2799
sch	442195	3873904	2469	33941.5	33941.5	93102.6	8	442322	3873919	2420
pre-sch	436634	3873603	2411	33955.5	33955.5	111361.9	9	436761	3873618	2362
worker	436622	3873505	2413	34508.3	34508.3	111408.0	10	436749	3873520	2364
res-Hinkley	436184	3877180	2414	14069.9	14069.9	113221.9	11	436311	3877195	2365
sch-Barstow	481797	3865786	2165	24202.3	24202.3	46163.3	12	481924	3865801	2116
hosp-Barstow	490882	3861107	2188	30594.0	30594.0	79407.7	13	491009	3861122	2139
unk (res-farm)	498280	3861300	2255	201.6	201.6	100378.8	14	498407	3861315	2206
unk (res-farm)	470768	3874297	2062	947.7	947.7	661.3	15	470895	3874312	2013
unk (res-farm)	469724	3874694	2067	2467.0	2467.0	3109.3	16	469851	3874709	2018
unk (res-farm)	468687	3875860	2070	339.5	339.5	8094.1	17	468814	3875875	2021
unk (res-farm)	470358	3873999	2072	957.6	957.6	1114.0	18	470485	3874014	2023
unk (res-farm)	469629	3874082	2079	854.1	854.1	3142.0	19	469756	3874097	2030
unk (res-farm)	469823	3873849	2077	2003.7	2003.7	2802.5	20	469950	3873864	2028
unk (res-farm)	469753	3872435	2129	2279.1	2279.1	6574.1	21	469880	3872450	2080
unk (res-farm)	469693	3872161	2140	1053.8	1053.8	7477.7	22	469820	3872176	2091
unk (res-farm)	471622	3874305	2047			3457.4		471749	3874320	1998

Table C.4-5

OEHHA/CARB Consolidated Risk Value Summary Table

(14 pages total)

Table 1
CONSOLIDATED TABLE OF OEHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES*

CONSOLIDATED TABLE OF OLIMPIA AND APPROVED RISK ASSESSMENT HEALTH VALUES															
Substance	Chemical Abstract Number	Noncancer Effects						Cancer Risk							
		Acute Inhalation (µg/m ³)	Date Value Reviewed [Added]	8-Hour Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Oral (mg/kg-d)	Date Value Reviewed [Added]	Inhalation Unit Risk (µg/m ³) ⁻¹	Inhalation Cancer Potency Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	Oral Slope Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	M* W A F
ACETALDEHYDE	75-07-0	4.7E+02	12/08	3.0E+02	12/08	1.4E+02	12/08			2.7E-06	1.0E-02	4/99 [5/93]			1
ACETAMIDE	60-35-5									2.0E-05	7.0E-02	4/99			1
ACROLEIN	107-02-8	2.5E+00	12/08	7.0E-01	12/08	3.5E-01	12/08								1
ACRYLAMIDE	79-06-1									1.3E-03	4.5E+00	4/99 [7/90]			1
ACRYLIC ACID	79-10-7	6.0E+03	4/99												1
ACRYLONITRILE	107-13-1					5.0E+00	12/01			2.9E-04	1.0E+00	4/99 [1/91]			1
ALLYL CHLORIDE	107-05-1									6.0E-06	2.1E-02	4/99			1
2-AMINOANTHRAQUINONE	117-79-3									9.4E-06	3.3E-02	4/99			1
AMMONIA	7664-41-7	3.2E+03	4/99			2.0E+02	2/00								1
ANILINE	62-53-3									1.6E-06	5.7E-03	4/99			1
ARSENIC AND COMPOUNDS (INORGANIC) ^{TAC}	7440-38-2 1016 [1015]	2.0E-01	12/08	1.5E-02	12/08	1.5E-02	12/08	3.5E-06	12/08	3.3E-03 ^{TAC}	1.2E+01	7/90	1.5E+00	10/00	1
ARSINE	7784-42-1	2.0E-01	12/08	1.5E-02	12/08	1.5E-02	12/08								1
ASBESTOS ^{TAC H}	1332-21-4									1.9E-04 ^{TAC H}	2.2E+02	3/86			333.33
BENZENE ^{TAC}	71-43-2	1.3E+03	4/99			6.0E+01	2/00			2.9E-05 ^{TAC}	1.0E-01	1/85			1
BENZIDINE (AND ITS SALTS) values also apply to:	92-87-5									1.4E-01	5.0E+02	4/99 [1/91]			1
Benzidine based dyes	1020									1.4E-01	5.0E+02	4/99 [1/91]			1
Direct Black 38	1937-37-7									1.4E-01	5.0E+02	4/99 [1/91]			1
Direct Blue 6	2602-46-2									1.4E-01	5.0E+02	4/99 [1/91]			1
Direct Brown 95 (technical grade)	16071-86-6									1.4E-01	5.0E+02	4/99 [1/91]			1
BENZYL CHLORIDE	100-44-7	2.4E+02	4/99							4.9E-05	1.7E-01	4/99			1
BERYLLIUM AND COMPOUNDS	7440-41-7 [1021]					7.0E-03	12/01	2.0E-03	12/01	2.4E-03	8.4E+00	4/99 [7/90]			1
BIS(2-CHLOROETHYL)ETHER (Dichloroethyl ether)	111-44-4									7.1E-04	2.5E+00	4/99			1
BIS(CHLOROMETHYL)ETHER	542-88-1									1.3E-02	4.6E+01	4/99 [1/91]			1
BROMINE AND COMPOUNDS	7726-95-6 [1040]														1
POTASSIUM BROMATE	7758-01-2									1.4E-04	4.9E-01	4/99 [10/93]			1

Table 1
CONSOLIDATED TABLE OF OEHAH/ARB APPROVED RISK ASSESSMENT HEALTH VALUES*

CONSOLIDATED TABLE OF OLIMPIATRAC APPROVED RISK ASSESSMENT HEALTH VALUES															
Substance	Chemical Abstract Number	Noncancer Effects						Cancer Risk							
		Acute Inhalation (µg/m ³)	Date Value Reviewed [Added]	8-Hour Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Oral (mg/kg-d)	Date Value Reviewed [Added]	Inhalation Unit Risk (µg/m ³) ⁻¹	Inhalation Cancer Potency Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	Oral Slope Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	M* W A F
1,3-BUTADIENE ^{TAC}	106-99-0					2.0E+01	1/01			1.7E-04 TAC	6.0E-01	7/92			1
CADMIUM AND COMPOUNDS ^{TAC}	7440-43-9 [1045]					2.0E-02	1/01	5.0E-04	10/00	4.2E-03 TAC	1.5E+01	1/87			1
CARBON DISULFIDE	75-15-0	6.2E+03	4/99			8.0E+02	5/02								1
CARBON MONOXIDE	630-08-0	2.3E+04	4/99												1
CARBON TETRACHLORIDE ^{TAC} (Tetrachloromethane)	56-23-5	1.9E+03	4/99			4.0E+01	1/01			4.2E-05 TAC	1.5E-01	9/87			1
CHLORINATED PARAFFINS	108171-26-2									2.5E-05	8.9E-02	4/99			1
CHLORINE	7782-50-5	2.1E+02	4/99			2.0E-01	2/00								1
CHLORINE DIOXIDE	10049-04-4					6.0E-01	1/01								1
4-CHLORO-O-PHENYLENEDIAMINE	95-83-0									4.6E-06	1.6E-02	4/99			1
CHLOROBENZENE	108-90-7					1.0E+03	1/01								1
CHLORODIFLUOROMETHANE ... (see Fluorocarbons)															
CHLOROFORM ^{TAC}	67-66-3	1.5E+02	4/99			3.0E+02	4/00			5.3E-06 TAC	1.9E-02	12/90			1
Chlorophenols	1060														
PENTACHLOROPHENOL	87-86-5									5.1E-06	1.8E-02	4/99			1
2,4,6-TRICHLOROPHENOL	88-06-2									2.0E-05	7.0E-02	4/99 [1/91]			1
CHLOROPICRIN	76-06-2	2.9E+01	4/99			4.0E-01	12/01								1
p-CHLORO-o-TOLUIDINE	95-69-2														
CHROMIUM 6+ ^{TAC} values also apply to:	18540-29-9					2.0E-01	1/01	2.0E-02	10/00	1.5E-01 TAC	5.1E+02	1/86	Ø		1
Barium chromate	10294-40-3					2.0E-01	1/01	2.0E-02	10/00	1.5E-01 TAC	5.1E+02	1/86	Ø		0.2053
Calcium chromate	13765-19-0					2.0E-01	1/01	2.0E-02	10/00	1.5E-01 TAC	5.1E+02	1/86	Ø		0.3332
Lead chromate	7758-97-6					2.0E-01	1/01	2.0E-02	10/00	1.5E-01 TAC	5.1E+02	1/86	Ø		0.1609
Sodium dichromate	10588-01-9					2.0E-01	1/01	2.0E-02	10/00	1.5E-01 TAC	5.1E+02	1/86	Ø		0.397
Strontium chromate	7789-06-2					2.0E-01	1/01	2.0E-02	10/00	1.5E-01 TAC	5.1E+02	1/86	Ø		0.2554
CHROMIUM TRIOXIDE (as chromic acid mist)	1333-82-0					2.0E-01	1/01	2.0E-02	10/00	1.5E-01 TAC	5.1E+02	1/86	Ø		0.52
COPPER AND COMPOUNDS	7440-50-8 [1067]	1.0E+02	4/99			2.0E-03	1/01	2.0E-02	10/00	1.5E-01 TAC	5.1E+02	1/86	Ø		
p-CRESIDINE	120-71-8														1
CRESOLS (mixtures of)	1319-77-3									4.3E-05	1.5E-01	4/99			1
m-CRESOL	108-39-4					6.0E+02	1/01								1

Table 1
CONSOLIDATED TABLE OF OEHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES*

Substance	Chemical Abstract Number	Noncancer Effects						Cancer Risk					
		Acute Inhalation ($\mu\text{g}/\text{m}^3$)	Date Value Reviewed [Added]	Chronic Inhalation ($\mu\text{g}/\text{m}^3$)	Date Value Reviewed [Added]	8-Hour Inhalation ($\mu\text{g}/\text{m}^3$)	Chronic Oral (mg/kg-d)	Date Value Reviewed [Added]	Inhalation Unit Risk ($\mu\text{g}/\text{m}^3$) ⁻¹	Inhalation Cancer Potency Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	Oral Slope Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]
o-CRESOL	95-48-7			6.0E+02	1/01								1
p-CRESOL	106-44-5			6.0E+02	1/01								1
CUPFERRON	135-20-6								6.3E-05	2.2E-01	4/99		1
Cyanide Compounds (inorganic)	57-12-5 1073	3.4E+02	4/99	9.0E+00	4/00								1
HYDROGEN CYANIDE (Hydrocyanic acid)	74-90-8	3.4E+02	4/99	9.0E+00	4/00								1
2,4-DIAMINODANISOLE	615-05-4								6.6E-06	2.3E-02	4/99		1
2,4-DIAMINOTOLUENE	95-80-7								1.1E-03	4.0E+00	4/99		1
1,2-DIBROMO-3-CHLOROPROPANE (DBCP)	96-12-8								2.0E-03	7.0E+00	4/99		1
p-DICHLOROBENZENE	106-46-7			8.0E+02	1/01				1.1E-05	4.0E-02	4/99		1
3,3-DICHLOROBENZIDINE	91-94-1								3.4E-04	1.2E+00	4/99		1
1,1-DICHLOROETHANE (Ethylene dichloride)	75-34-3								1.6E-06	5.7E-03	4/99		1
1,1-DICHLOROETHYLENE ... (see Vinylidene Chloride)													
DI(2-ETHYLHEXYL)PHTHALATE (DEHP)	117-81-7								2.4E-06	8.4E-03	4/99	8.4E-03	10/00
DIESEL EXHAUST ... (see Particulate Emissions from Diesel-Fueled Engines)													
DIETHANOLAMINE	111-42-2			3.0E+00	12/01								
p-DIMETHYLAMINOAZOBENZENE	60-11-7								1.3E-03	4.6E+00	4/99		1
N,N-DIMETHYL FORMAMIDE	68-12-2			8.0E+01	1/01								1
2,4-DINITROTOLUENE	121-14-2								8.9E-05	3.1E-01	4/99		1
1,4-DIOXANE	123-91-1	3.0E+03	4/99	3.0E+03	4/00				7.7E-06	2.7E-02	4/99		1
EPICHLOROHYDRIN (1-Chloro-2,3-epoxypropane)	106-89-8	1.3E+03	4/99	3.0E+00	1/01				2.3E-05	8.0E-02	4/99		1
1,2-EPOXYBUTANE	106-88-7			2.0E+01	1/01								1
ETHYL BENZENE	100-41-4			2.0E+03	2/00				2.5E-06	8.7E-3	11/07		1
ETHYL CHLORIDE (Chloroethane)	75-00-3			3.0E+04	4/00								1
ETHYLENE DIBROMIDE ^{TAC} (1,2-Dibromoethane)	106-93-4			8.0E-01	12/01				7.1E-05	2.5E-01	7/85		1
ETHYLENE DICHLORIDE ^{TAC} (1,2-Dichloroethane)	107-06-2			4.0E+02	1/01				2.1E-05	7.2E-02	9/85		1
ETHYLENE GLYCOL	107-21-1			4.0E+02	4/00								1
ETHYLENE GLYCOL BUTYL ETHER ... (see Glycol ethers)													

Table 1
CONSOLIDATED TABLE OF OEHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES°

CONSOLIDATED TABLE OF SELECTED APPROVED RISK ASSESSMENT HEALTH VALUES															
Substance	Chemical Abstract Number	Noncancer Effects							Cancer Risk						
		Acute Inhalation (µg/m ³)	Date Value Reviewed [Added]	8-Hour Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Oral (mg/kg-d)	Date Value Reviewed [Added]	Inhalation Unit Risk (µg/m ³) ⁻¹	Inhalation Cancer Potency Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	Oral Slope Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	M ⁺ W A F
ETHYLENE OXIDE ^{TAC} (1,2-Epoxyethane)	75-21-8					3.0E+01	1/01			8.8E-05 ^{TAC}	3.1E-01	11/87			1
ETHYLENE THIOUREA Fluorides	96-45-7					1.3E+01				1.3E-05	4.5E-02	4/99			1
HYDROGEN FLUORIDE (Hydrofluoric acid)	1101	2.4E+02	4/99			1.3E+01	8/03	4.0E-02	8/03						7
	7664-39-3	2.4E+02	4/99			1.4E+01	8/03	4.0E-02	8/03						1
FORMALDEHYDE ^{TAC}	50-00-0	5.5E+01	12/08	9.0E+00	12/08	9.0E+00	12/08			6.0E-06 ^{TAC}	2.1E-02	3/92			1
GLUTARALDEHYDE	111-30-8					8.0E-02	1/01								1
GLYCOL ETHERS	1115														1
ETHYLENE GLYCOL BUTYL ETHER – EGBE	111-76-2	1.4E+04	4/99												1
ETHYLENE GLYCOL ETHYL ETHER – EGEE	110-80-5	3.7E+02	4/99[1/92]			7.0E+01	2/00								1
ETHYLENE GLYCOL ETHYL ETHER ACETATE – EGEEA	111-15-9	1.4E+02	4/99			3.0E+02	2/00								1
ETHYLENE GLYCOL METHYL ETHER – EGME	109-86-4	9.3E+01	4/99			6.0E+01	2/00								1
ETHYLENE GLYCOL METHYL ETHER ACETATE – EGMEA	110-49-6					9.0E+01	2/00								1
HEXACHLOROBENZENE	118-74-1									5.1E-04	1.8E+00	4/99 [1/91]			1
HEXACHLOROCYCLOHEXANES (mixed or technical grade)	608-73-1									1.1E-03	4.0E+00	4/99 [1/91]	4.0E+00	10/00 [1/92]	1
alpha- HEXACHLOROCYCLOHEXANE	319-84-6									1.1E-03	4.0E+00	4/99 [1/91]	4.0E+00	10/00 [1/92]	1
beta- HEXACHLOROCYCLOHEXANE	319-85-7									1.1E-03	4.0E+00	4/99 [1/91]	4.0E+00	10/00 [1/92]	1
gamma- HEXACHLOROCYCLOHEXANE (Lindane)	58-89-9									1.1E-03	4.0E+00	4/99 [1/91]	4.0E+00	10/00 [1/92]	1
n-HEXANE	110-54-3									3.1E-04	1.1E+00	4/99	1.1E+00	10/00	1
HYDRAZINE	302-01-2					7.0E+03	4/00								1
HYDROCHLORIC ACID (Hydrogen chloride)						2.0E-01	1/01			4.9E-03	1.7E+01	4/99 [7/90]			1
HYDROGEN BROMIDE	7647-01-0	2.1E+03	4/99			9.0E+00	2/00								1
HYDROGEN CYANIDE ... (see Bromine & Compounds)															
... (see Cyanide & Compounds)															
HYDROGEN FLUORIDE ... (see Fluorides & Compounds)															

Table 1
CONSOLIDATED TABLE OF OEHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES*

CONDENSED TABLE OF ULTIMATE RISK ASSESSMENT REALITY VALUES															
Substance	Chemical Abstract Number	Noncancer Effects						Cancer Risk							
		Acute Inhalation (µg/m ³)	Date Value Reviewed [Added]	8-Hour Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Oral (mg/kg-d)	Date Value Reviewed [Added]	Inhalation Unit Risk (µg/m ³) ⁻¹	Inhalation Cancer Potency Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	Oral Slope Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	M* W A F
HYDROGEN SELENIDE ... (see Selenium & Compounds)															
HYDROGEN SULFIDE	7783-06-4	4.2E+01	4/99[7/90]			1.0E+01	4/00								1
ISOPHORONE	78-59-1					2.0E+03	12/01								
ISOPROPYL ALCOHOL (Isopropanol)	67-63-0	3.2E+03	4/99			7.0E+03	2/00								1
LEAD AND COMPOUNDS ^{TAC,†*} (inorganic) values also apply to:	7439-92-1 1128 [1130]									1.2E-05 _{TAC}	4.2E-02	4/97	8.5E-03	10/00	1
Lead acetate	301-04-2									1.2E-05 _{TAC}	4.2E-02	4/97	8.5E-03	10/00	0.637
Lead phosphate	7446-27-7									1.2E-05 _{TAC}	4.2E-02	4/97	8.5E-03	10/00	0.7659
Lead subacetate	1335-32-6									1.2E-05 _{TAC}	4.2E-02	4/97	8.5E-03	10/00	0.7696
LINDANE ... (see gamma-Hexachlorocyclohexane)															
MALEIC ANHYDRIDE	108-31-6					7.0E-01	12/01								1
MANGANESE AND COMPOUNDS	7439-96-5 [1132]			1.7E-01	12/08	9.0E-02	12/08								1
MERCURY AND COMPOUNDS (INORGANIC)	7439-97-6 [1133]	6.0E-01	12/08	6.0E-02	12/08	3.0E-02	12/08	1.6E-04	12/08						1
Mercuric chloride	7487-94-7	6.0E-01	12/08	6.0E-02	12/08	3.0E-02	12/08	1.6E-04	12/08						1
METHANOL	67-56-1	2.8E+04	4/99			4.0E+03	4/00								1
METHYL BROMIDE (Bromomethane)	74-83-9	3.9E+03	4/99			5.0E+00	2/00								1
METHYL tertiary-BUTYL ETHER	1634-04-4					8.0E+03	2/00			2.6E-07	1.8E-03	11/99			1
METHYL CHLOROFORM (1,1,1-Trichloroethane)	71-55-6	6.8E+04	4/99			1.0E+03	2/00								1
METHYL ETHYL KETONE (2-Butanone)	78-93-3	1.3E+04	4/99												1
METHYL ISOCYANATE	624-83-9					1.0E+00	12/01								1
METHYL MERCURY ... (see Mercury & Compounds)															
4,4'-METHYLENE BIS (2-CHLOROANILINE) (MOCA)	101-14-4									4.3E-04	1.5E+00	4/99			1
METHYLENE CHLORIDE ^{TAC} (Dichloromethane)	75-09-2	1.4E+04	4/99			4.0E+02	2/00			1.0E-06 _{TAC}	3.5E-03	7/89			1
4,4'-METHYLENE DIANILINE (AND ITS DICHLORIDE)	101-77-9					2.0E+01	12/01			4.6E-04	1.6E+00	4/99	1.6E+00	10/00	1
METHYLENE DIPHENYL ISOCYANATE	101-68-8					7.0E-01	1/01								1
MICHLER'S KETONE (4,4-Bis(dimethylamino)benzophenone)	90-94-8									2.5E-04	8.6E-01	4/99			1
N-NITROSODI-n-BUTYLAMINE	924-16-3									3.1E-03	1.1E+01	4/99 [1/92]			1

Table 1
CONSOLIDATED TABLE OF OEHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES*

CANCER RISK FACTORS FROM ADDITIONAL REVIEWED NONCANCER EFFECTS DATA															
Substance	Chemical Abstract Number	Noncancer Effects						Cancer Risk							
		Acute Inhalation (µg/m ³)	Date Value Reviewed [Added]	8-Hour Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Oral (mg/kg-d)	Date Value Reviewed [Added]	Inhalation Unit Risk (µg/m ³) ⁻¹	Inhalation Cancer Potency Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	Oral Slope Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	M* W A F
N-NITROSODI-n-PROPYLAMINE	621-64-7									2.0E-03	7.0E+00	4/99 [1/91]			1
N-NITROSODIETHYLAMINE	55-18-5									1.0E-02	3.6E+01	4/99 [1/91]			1
N-NITROSODIMETHYLAMINE	62-75-9									4.6E-03	1.6E+01	4/99 [1/91]			1
N-NITROSODIPHENYLAMINE	86-30-6									2.6E-06	9.0E-03	4/99 [1/91]			1
N-NITROSO-N-METHYLETHYLAMINE	10595-95-6									6.3E-03	2.2E+01	4/99 [7/90]			1
N-NITROSOMORPHOLINE	59-89-2									1.9E-03	6.7E+00	4/99 [7/92]			1
N-NITROSOPIPERIDINE	100-75-4									2.7E-03	9.4E+00	4/99 [7/92]			1
N-NITROSOPIRROLIDINE	930-55-2									6.0E-04	2.1E+00	4/99 [7/90]			1
NAPHTHALENE (see Polycyclic aromatic hydrocarbons) NICKEL AND COMPOUNDS ^{TAC} values also apply to:	7440-02-0 [1145]	6.0E+00	4/99			5.0E-02	2/00	5.0E-02	10/00	2.6E-04 ^{TAC}	9.1E-01	8/91			1
Nickel acetate	373-02-4	6.0E+00	4/99			5.0E-02	2/00	5.0E-02	10/00	2.6E-04 ^{TAC}	9.1E-01	8/91			0.3321
Nickel carbonate	3333-67-3	6.0E+00	4/99			5.0E-02	2/00	5.0E-02	10/00	2.6E-04 ^{TAC}	9.1E-01	8/91			0.4945
Nickel carbonyl	13463-39-3	6.0E+00	4/99			5.0E-02	2/00	5.0E-02	10/00	2.6E-04 ^{TAC}	9.1E-01	8/91			0.3438
Nickel hydroxide	12054-48-7	6.0E+00	4/99			5.0E-02	2/00	5.0E-02	10/00	2.6E-04 ^{TAC}	9.1E-01	8/91			0.6332
Nickelocene	1271-28-9	6.0E+00	4/99			5.0E-02	2/00	5.0E-02	10/00	2.6E-04 ^{TAC}	9.1E-01	8/91			0.4937
NICKEL OXIDE	1313-99-1	6.0E+00	4/99			1.0E-01	2/00	5.0E-02	10/00	2.6E-04 ^{TAC}	9.1E-01	8/91			0.7859
Nickel refinery dust from the pyrometallurgical process	1146	6.0E+00	4/99			5.0E-02	2/00	5.0E-02	10/00	2.6E-04 ^{TAC}	9.1E-01	8/91			1
Nickel subsulfide	12035-72-2	6.0E+00	4/99			5.0E-02	2/00	5.0E-02	10/00	2.6E-04 ^{TAC}	9.1E-01	8/91			0.2443
NITRIC ACID	7697-37-2	8.6E+01	4/99												1
NITROGEN DIOXIDE	10102-44-0	4.7E+02	4/99[1/92]												1
p-NITROSODIPHENYLAMINE	156-10-5									6.3E-06	2.2E-02	4/99			1
OZONE	10028-15-6	1.8E+02	4/99[1/92]												1
PARTICULATE EMISSIONS FROM DIESEL-FUELED ENGINES ^{TAC} [1]	9901					5.0E+00 ^{TAC}	8/98			3.0E-04 ^{TAC}	1.1E+00	8/98			1
PENTACHLOROPHENOL ... (see Chlorophenols)															

Table 1
CONSOLIDATED TABLE OF OEHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES*

CONSOLIDATED TABLE OF OLIMPIRADAR APPROVED RISK ASSESSMENT HEALTH VALUES															
Substance	Chemical Abstract Number	Noncancer Effects						Cancer Risk							
		Acute Inhalation (µg/m ³)	Date Value Reviewed [Added]	8-Hour Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Oral (mg/kg-d)	Date Value Reviewed [Added]	Inhalation Unit Risk (µg/m ³) ⁻¹	Inhalation Cancer Potency Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	Oral Slope Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	M* W A F
PERCHLOROETHYLENE ^{TAC} (Tetrachloroethylene)	127-18-4	2.0E+04	4/99			3.5E+01 TAC	10/91			5.9E-06 TAC	2.1E-02	10/91			1
PHENOL	108-95-2	5.8E+03	4/99			2.0E+02	4/00								1
PHOSGENE	75-44-5	4.0E+00	4/99												1
PHOSPHINE	7803-51-2					8.0E-01	9/02								1
PHOSPHORIC ACID	7664-38-2					7.0E+00	2/00								1
PTHALIC ANHYDRIDE	85-44-9					2.0E+01	1/01								1
PCB (POLYCHLORINATED BIPHENYLS) (unspeciated mixture) [lowest risk] ☼*	1336-36-3									2.0E-05	7.0E-02	4/99	7.0E-02	10/00	1
PCB (POLYCHLORINATED BIPHENYLS) (unspeciated mixture) [low risk] ☼*	1336-36-3									1.1E-04	4.0E-01*		4.0E-01*		1
PCB (POLYCHLORINATED BIPHENYLS) (unspeciated mixture) [high risk] ☼*	1336-36-3									5.7E-04	2.0E+00	4/99	2.0E+00	10/00	1
PCB (POLYCHLORINATED BIPHENYLS) (speciated) ☼															
3,3',4,4'- TETRACHLOROBIPHENYL (PCB 77)	32598-13-3					4.0E-01	8/03	1.0E-04	8/03	3.8E-03	1.3E+01	8/03	1.3E+01	8/03	1
3,4,4',5'- TETRACHLOROBIPHENYL (PCB 81)	70362-50-4					4.0E-01	8/03	1.0E-04	8/03	3.8E-03	1.3E+01	8/03	1.3E+01	8/03	1
2,3,3',4,4'- PENTACHLOROBIPHENYL (PCB 105)	32598-14-4					4.0E-01	8/03	1.0E-04	8/03	3.8E-03	1.3E+01	8/03	1.3E+01	8/03	1
2,3,4,4',5'- PENTACHLOROBIPHENYL (PCB 114)	74472-37-0					8.0E-02	8/03	2.0E-05	8/03	1.9E-02	6.5E+01	8/03	6.5E+01	8/03	1
2,3',4,4',5'- PENTACHLOROBIPHENYL (PCB 118)	31508-00-6					4.0E-01	8/03	1.0E-04	8/03	3.8E-03	1.3E+01	8/03	1.3E+01	8/03	1
2,3',4,4',5'- PENTACHLOROBIPHENYL (PCB 123)	65510-44-3					4.0E-01	8/03	1.0E-04	8/03	3.8E-03	1.3E+01	8/03	1.3E+01	8/03	1
3,3',4,4',5'- PENTACHLOROBIPHENYL (PCB 126)	57465-28-8					4.0E-04	8/03	1.0E-07	8/03	3.8E+00	1.3E+04	8/03	1.3E+04	8/03	1
2,3,3',4,4',5'- HEXACHLOROBIPHENYL (PCB 156)	38380-08-4					8.0E-02	8/03	2.0E-05	8/03	1.9E-02	6.5E+01	8/03	6.5E+01	8/03	1
2,3,3',4,4',5'- HEXACHLOROBIPHENYL (PCB 157)	69782-90-7					8.0E-02	8/03	2.0E-05	8/03	1.9E-02	6.5E+01	8/03	6.5E+01	8/03	1

Table 1
CONSOLIDATED TABLE OF OEHHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES^a

CONSOLIDATED TABLE OF ULTIMATE APPROVED RISK ASSESSMENT HEALTH VALUES															
Substance	Chemical Abstract Number	Noncancer Effects						Cancer Risk							
		Acute Inhalation (ug/m ³)	Date Value Reviewed [Added]	8-Hour Inhalation (ug/m ³)	Date Value Reviewed [Added]	Chronic Inhalation (ug/m ³)	Date Value Reviewed [Added]	Chronic Oral (mg/kg-d)	Date Value Reviewed [Added]	Inhalation Unit Risk (ug/m ³) ⁻¹	Inhalation Cancer Potency Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	Oral Slope Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	M W A F
2,3',4,4',5,5'-HEXACHLOROBIPHENYL (PCB 167)	52663-72-6					4.0E+00	8/03	1.0E-03	8/03	3.8E-04	1.3E+00	8/03	1.3E+00	8/03	1
3,3',4,4',5,5'-HEXACHLOROBIPHENYL (PCB 169)	32774-16-6					4.0E-03	8/03	1.0E-06	8/03	3.8E-01	1.3E+03	8/03	1.3E+03	8/03	1
2,3',4,4',5,5'-HEPTACHLOROBIPHENYL (PCB 189)	39635-31-9					4.0E-01	8/03	1.0E-04	8/03	3.8E-03	1.3E+01	8/03	1.3E+01	8/03	1
POLYCHLORINATED DIBENZO-P-DIOXINS (PCDD) (Treated as 2,3,7,8-TCDD for HRA) ^{TAC}	1085 1086					4.0E-05	2/00	1.0E-08	10/00	3.8E+01 TAC	1.3E+05	8/86	1.3E+05 TAC	8/86	1
2,3,7,8- ^{TAC} P-DIOXIN	1746-01-6					4.0E-05	2/00	1.0E-08	10/00	3.8E+01 TAC	1.3E+05	8/86	1.3E+05 TAC	8/86	1
1,2,3,7,8-PENTACHLORODIBENZO-P-DIOXIN	40321-76-4					4.0E-05	8/03	1.0E-08	8/03	3.8E+01	1.3E+05	8/03	1.3E+05	8/03	1
1,2,3,4,7,8-HEXACHLORODIBENZO-P-DIOXIN	39227-28-6					4.0E-04	2/00	1.0E-07	10/00	3.8E+00	1.3E+04	4/99	1.3E+04	10/00	1
1,2,3,6,7,8-HEXACHLORODIBENZO-P-DIOXIN	57653-85-7					4.0E-04	2/00	1.0E-07	10/00	3.8E+00	1.3E+04	4/99	1.3E+04	10/00	1
1,2,3,7,8,9-HEXACHLORODIBENZO-P-DIOXIN	19408-74-3					4.0E-04	2/00	1.0E-07	10/00	3.8E+00	1.3E+04	4/99	1.3E+04	10/00	1
1,2,3,4,6,7,8-HEPTACHLORODIBENZO-P-DIOXIN	35822-46-9					4.0E-03	2/00	1.0E-06	10/00	3.8E-01	1.3E+03	4/99	1.3E+03	10/00	1
1,2,3,4,6,7,8,9-OCTACHLORODIBENZO-P-DIOXIN	3268-87-9					4.0E-01	8/03	1.0E-04	8/03	3.8E-03	1.3E+01	8/03	1.3E+01	8/03	1
POLYCHLORINATED DIBENZOFURANS (PCDF) ^{TAC} (Treated as 2,3,7,8-TCDD for HRA)	1080					4.0E-05	2/00	1.0E-08	10/00	3.8E+01 TAC	1.3E+05	8/86	1.3E+05 TAC	8/86	1
2,3,7,8-TETRACHLORODIBENZOFURAN	5120-73-19					4.0E-04	2/00	1.0E-07	10/00	3.8E+00	1.3E+04	4/99	1.3E+04	10/00	1
1,2,3,7,8-PENTACHLORODIBENZOFURAN	57117-41-6					8.0E-04	2/00	2.0E-07	10/00	1.9E+00	6.5E+03	4/99	6.5E+03	10/00	1
2,3,4,7,8-PENTACHLORODIBENZOFURAN	57117-31-4					8.0E-05	2/00	2.0E-08	10/00	1.9E+01	6.5E+04	4/99	6.5E+04	10/00	1
1,2,3,4,7,8-HEXACHLORODIBENZOFURAN	70648-26-9					4.0E-04	2/00	1.0E-07	10/00	3.8E+00	1.3E+04	4/99	1.3E+04	10/00	1

Table 1
CONSOLIDATED TABLE OF OEHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES^o

CONSOLIDATED TABLE OF CERITAPARK EFFECTS RISK ASSESSMENT HEALTH VALUES															
Substance	Chemical Abstract Number	Noncancer Effects						Cancer Risk							
		Acute Inhalation (µg/m ³)	Date Value Reviewed [Added]	8-Hour Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Oral (mg/kg-d)	Date Value Reviewed [Added]	Inhalation Unit Risk (µg/m ³) ⁻¹	Inhalation Cancer Potency Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	Oral Slope Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	M W A F
1,2,3,6,7,8- HEXACHLORODIBENZOFURAN	57117-44-9					4.0E-04	2/00	1.0E-07	10/00	3.8E+00	1.3E+04	4/99	1.3E+04	10/00	1
1,2,3,7,8,9- HEXACHLORODIBENZOFURAN	72918-21-9					4.0E-04	2/00	1.0E-07	10/00	3.8E+00	1.3E+04	4/99	1.3E+04	10/00	1
2,3,4,6,7,8- HEXACHLORODIBENZOFURAN	60851-34-5					4.0E-04	2/00	1.0E-07	10/00	3.8E+00	1.3E+04	4/99	1.3E+04	10/00	1
1,2,3,4,6,7,8- HEPTACHLORODIBENZOFURAN	67562-39-4					4.0E-03	2/00	1.0E-06	10/00	3.8E-01	1.3E+03	4/99	1.3E+03	10/00	1
1,2,3,4,7,8,9- HEPTACHLORODIBENZOFURAN	55673-89-7					4.0E-03	2/00	1.0E-06	10/00	3.8E-01	1.3E+03	4/99	1.3E+03	10/00	1
1,2,3,4,6,7,8,9- OCTACHLORODIBENZOFURAN	39001-02-0					4.0E-01	8/03	1.0E-04	8/03	3.8E-03	1.3E+01	8/03	1.3E+01	8/03	1
POLYCYCLIC AROMATIC HYDROCARBON (PAH) ^Φ [Treated as B(a)P for HRA]	1150 1151									1.1E-03	3.9E+00	4/99 [4/94]	1.2E+01	10/00 [4/94]	1
BENZO(A)ANTHRACENE [*]	56-55-3									1.1E-04	3.9E-01	4/99 [4/94]	1.2E+00	10/00 [4/94]	1
BENZO(A)PYRENE [*]	50-32-8									1.1E-03	3.9E+00	4/99 [4/94]	1.2E+01	10/00 [4/94]	1
BENZO(B)FLUORANTHENE [*]	205-99-2									1.1E-04	3.9E-01	4/99 [4/94]	1.2E+00	10/00 [4/94]	1
BENZO(J)FLUORANTHENE [*]	205-82-3									1.1E-04	3.9E-01	4/99 [4/94]	1.2E+00	10/00 [4/94]	1
BENZO(K)FLUORANTHENE [*]	207-08-9									1.1E-04	3.9E-01	4/99 [4/94]	1.2E+00	10/00 [4/94]	1
CHRYSENE [*]	218-01-9									1.1E-05	3.9E-02	4/99 [4/94]	1.2E-01	10/00 [4/94]	1
DIBENZO(A,H)ACRIDINE [*]	226-36-8									1.1E-04	3.9E-01	4/99 [4/94]	1.2E+00	10/00 [4/94]	1
DIBENZO(A,H)ANTHRACENE [*]	53-70-3									1.2E-03	4.1E+00	4/99 [4/94]	4.1E+00	10/00 [4/94]	1
DIBENZO(A,J)ACRIDINE [*]	224-42-0									1.1E-04	3.9E-01	4/99 [4/94]	1.2E+00	10/00 [4/94]	1
DIBENZO(A,E)PYRENE [*]	192-65-4									1.1E-03	3.9E+00	4/99 [4/94]	1.2E+01	10/00 [4/94]	1
DIBENZO(A,H)PYRENE [*]	189-64-0									1.1E-02	3.9E+01	4/99 [4/94]	1.2E+02	10/00 [4/94]	1

Table 1
CONSOLIDATED TABLE OF OEHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES^o

CONSOLIDATED TABLE OF ULTIMATE APPROVED RISK ASSESSMENT HEALTH VALUES															
Substance	Chemical Abstract Number	Noncancer Effects						Cancer Risk							
		Acute Inhalation (ug/m ³)	Date Value Reviewed [Added]	8-Hour Inhalation (ug/m ³)	Date Value Reviewed [Added]	Chronic Inhalation (ug/m ³)	Date Value Reviewed [Added]	Chronic Oral (mg/kg-d)	Date Value Reviewed [Added]	Inhalation Unit Risk (ug/m ³) ⁻¹	Inhalation Cancer Potency Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	Oral Slope Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	M W A F
DIBENZO(A,I)PYRENE ^o	189-55-9									1.1E-02	3.9E+01	4/99 [4/94]	1.2E+02	10/00 [4/94]	1
DIBENZO(A,L)PYRENE ^o	191-30-0									1.1E-02	3.9E+01	4/99 [4/94]	1.2E+02	10/00 [4/94]	1
7H-DIBENZO(C,G)CARBAZOLE ^o	194-59-2									1.1E-03	3.9E+00	4/99 [4/94]	1.2E+01	10/00 [4/94]	1
7,12-DIMETHYLBENZ(A)ANTHRACENE ^o	57-97-6									7.1E-02	2.5E+02	4/99 [4/94]	2.5E+02	10/00 [4/94]	1
1,6-DINITROPYRENE ^o	42397-64-8									1.1E-02	3.9E+01	4/99 [4/94]	1.2E+02	10/00 [4/94]	1
1,8-DINITROPYRENE ^o	42397-65-9									1.1E-03	3.9E+00	4/99 [4/94]	1.2E+01	10/00 [4/94]	1
INDENO(1,2,3-C,D)PYRENE ^o	193-39-5									1.1E-04	3.9E-01	4/99 [4/94]	1.2E+00	10/00 [4/94]	1
3-METHYLCHOLANTHRENE ^o	56-49-5									6.3E-03	2.2E+01	4/99 [4/94]	2.2E+01	10/00 [4/94]	1
5-METHYLCHRYSENE ^o	3697-24-3									1.1E-03	3.9E+00	4/99 [4/94]	1.2E+01	10/00 [4/94]	1
NAPHTHALENE	91-20-3					9.0E+00	4/00			3.4E-05	1.2E-01	8/04			1
5-NITROACENAPHTHENE ^o	602-87-9									3.7E-05	1.3E-01	4/99 [4/94]	1.3E-01	10/00 [4/94]	1
6-NITROCHRYSENE ^o	7496-02-8									1.1E-02	3.9E+01	4/99 [4/94]	1.2E+02	10/00 [4/94]	1
2-NITROFLUORENE ^o	607-57-8									1.1E-05	3.9E-02	4/99 [4/94]	1.2E-01	10/00 [4/94]	1
1-NITROPYRENE ^o	5522-43-0									1.1E-04	3.9E-01	4/99 [4/94]	1.2E+00	10/00 [4/94]	1
4-NITROPYRENE ^o	57835-92-4									1.1E-04	3.9E-01	4/99 [4/94]	1.2E+00	10/00 [4/94]	1
POTASSIUM BROMATE..... ... (see Bromine & Compounds)															
1,3-PROPANE SULFONE	1120-71-4									6.9E-04	2.4E+00	4/99			1
PROPYLENE (PROPENE)	115-07-1					3.0E+03	4/00								1
PROPYLENE GLYCOL MONOMETHYL ETHER	107-98-2					7.0E+03	2/00								1
PROPYLENE OXIDE	75-56-9	3.1E+03	4/99			3.0E+01	2/00			3.7E-06	1.3E-02	4/99 [7/90]			1
SELENIUM AND COMPOUNDS	7782-49-2 [1170]					2.0E+01	12/01								1
HYDROGEN SELENIDE	7783-07-5	5.0E+00	4/99												1
Selenium sulfide	7446-34-6					2.0E+01	12/01								1

Table 1
CONSOLIDATED TABLE OF OEHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES^o

Substance	Chemical Abstract Number	Noncancer Effects						Cancer Risk					
		Acute Inhalation (µg/m ³)	Date Value Reviewed [Added]	8-Hour Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Inhalation (µg/m ³)	Date Value Reviewed [Added]	Inhalation Unit Risk (µg/m ³) ⁻¹	Inhalation Cancer Potency Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	Oral Slope Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	M* W A F
SILICA [CRYSTALLINE, RESPIRABLE]	1175												1
SODIUM HYDROXIDE	1310-73-2	8.0E+00	4/99			3.0E+00	2/05						1
STYRENE	100-42-5	2.1E+04	4/99			9.0E+02	4/00						1
SULFATES	9960	1.2E+02	4/99										1
SULFUR DIOXIDE	7446-09-5	6.6E+02	4/99 [192]										1
SULFURIC ACID AND OLEUM	9961	1.2E+02	4/99			1.0E+00	12/01						1
SULFURIC ACID	7664-93-9	1.2E+02	4/99			1.0E+00	12/01						1
SULFUR TRIOXIDE	7446-71-9	1.2E+02	4/99			1.0E+00	12/01						1
OLEUM	8014-95-7	1.2E+02	4/99			1.0E+00	12/01						1
1,1,2,2-TETRACHLOROETHANE	79-34-5							5.8E-05	2.0E-01	4/99			1
TETRACHLOROPHENOLS													
... (see Chlorophenols)													
2,4,5-TRICHLOROPHENOL													
... (see Chlorophenols)													
2,4,6-TRICHLOROPHENOL													
... (see Chlorophenols)													
THIOACETAMIDE	62-55-5												
TOLUENE	108-88-3	3.7E+04	4/99					1.7E-03	6.1E+00	4/99			1
<i>Toluene diisocyanates</i>	26471-62-5					3.0E+02	4/00						1
TOLUENE-2,4-DIISOCYANATE	584-84-9					7.0E-02	1/01	1.1E-05	3.9E-02	4/99			1
TOLUENE-2,6-DIISOCYANATE	91-08-7					7.0E-02	1/01	1.1E-05	3.9E-02	4/99			1
1,1,2-TRICHLOROETHANE (Vinyl trichloride)	79-00-5					7.0E-02	1/01	1.1E-05	3.9E-02	4/99			1
TRICHLOROETHYLENE ^{TAC}	79-01-6							1.6E-05	5.7E-02	4/99			1
TRIETHYLAMINE	121-44-8	2.8E+03	4/99			6.0E+02	4/00	2.0E-06 TAC	7.0E-03	10/90			1
URETHANE (Ethyl carbamate)	51-79-6					2.0E+02	9/02						1
<i>Vanadium Compounds</i>	N/A							2.9E-04	1.0E+00	4/99 [7/90]			1
<i>Vanadium (fume or dust)</i>	7440-62-2	3.0E+01	4/99										1
VANADIUM PENTOXIDE	1314-62-1	3.0E+01	4/99										1
VINYL ACETATE	108-05-4					2.0E+02	12/01						1
VINYL CHLORIDE ^{TAC} (Chloroethylene)	75-01-4	1.8E+05	4/99					7.8E-05 TAC	2.7E-01	12/90			1
VINYLDENE CHLORIDE (1,1-Dichloroethylene)	75-35-4					7.0E+01	1/01						1



Table 1
CONSOLIDATED TABLE OF OEHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES°

Substance	Chemical Abstract Number	Noncancer Effects							Cancer Risk						
		Acute Inhalation (µg/m ³)	Date Value Reviewed [Added]	8-Hour Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Inhalation (µg/m ³)	Date Value Reviewed [Added]	Chronic Oral (mg/kg-d)	Date Value Reviewed [Added]	Inhalation Unit Risk (µg/m ³) ⁻¹	Inhalation Cancer Potency Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	Oral Slope Factor (mg/kg-d) ⁻¹	Date Value Reviewed [Added]	M W A F
XYLENES (mixed isomers)	1330-20-7	2.2E+04	4/99				7.0E+02	4/00							1
m-XYLENE	108-38-3	2.2E+04	4/99				7.0E+02	4/00							1
o-XYLENE	95-47-6	2.2E+04	4/99				7.0E+02	4/00							1
p-XYLENE	106-42-3	2.2E+04	4/99				7.0E+02	4/00							1

Table 1
CONSOLIDATED TABLE OF OEHHHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES*

<p>Purpose: The purpose of this reference table is to provide a quick list of all health values that have been approved by the Office of Environmental Health Hazard Assessment (OEHHHA) and the Air Resources Board (ARB) for use in facility health risk assessments conducted for the AB 2588 Air Toxics Hot Spots Program. The OEHHHA has developed and adopted new risk assessment guidelines that update and replace the California Air Pollution Control Officers Association's (CAPCOA) Air Toxics "Hot Spots" Program Revised 1992 Risk Assessment Guidelines, October 1993. The OEHHHA has adopted four technical support documents for these guidelines, which can be found on their website (http://www.oehha.ca.gov/air/hot_spots/index.html). This table lists the OEHHHA adopted inhalation and oral cancer slope factors, noncancer acute Reference Exposure Levels (RELs), and inhalation and oral noncancer chronic RELs. OEHHHA is still in the process of adopting new health values. Therefore, new health values will periodically be added to, or deleted from, this table. Users of this table are advised to monitor the OEHHHA website (www.oehha.ca.gov) for any updates to the health values.</p> <p>May 2008 update: The Air Resources Board adopted amendments to the AB 2588 Air Toxics "Hot Spots" Emission Inventory Criteria and Guidelines Regulation (Title 17, California Code of Regulations, Section 93300.5) on November 16, 2006. The amendments became effective on September 26, 2007, after approval from the Office of Administrative Law. Under the new amendments, the substances previously listed in Appendix A-1 (Substances For Which Emissions Must Be Quantified) and Appendix F (Criteria For Inputs For Risk Assessment Using Screening Air Dispersion Modeling) of the ARB's Air Toxics "Hot Spots" Emission Inventory Criteria and Guidelines (EICG) (July 1997) have been removed from this table. Substances written in <i>italics</i> do not have explicit OEHHHA approved health values, but are included in this table to clarify applicability of OEHHHA adopted health effects values to individual or grouped substances listed in the Air Toxics "Hot Spots" Emission Inventory Criteria and Guidelines. Appendix A-1 list of "Substances For Which Emissions Must Be Quantified".</p>	<p>▼ Chemical Abstract Service Number (CAS): For chemical groupings and mixtures where a CAS number is not applicable, the 4-digit code used in the Air Toxics "Hot Spots" Emission Inventory Criteria and Guidelines (EICG) Report is listed. The 4-digit codes enclosed in brackets [] are codes that have been phased out, but may still appear on previously reported Hot Spots emissions. For information on the origin and use of the 4-digit code, see the EICG report.</p> <p>◆ Date Value Reviewed [Added]: These columns list the date that the health value was last reviewed by OEHHHA and the Scientific Review Panel, and/or approved for use by CAPCOA is listed within the brackets [].</p> <ul style="list-style-type: none"> • April 1999 is listed for the cancer potency values and noncancer acute RELs, which have been adopted by the OEHHHA as part of the AB 2588 Hot Spot Risk Assessment Guidelines. • February 2000, April 2000, January 2001, and December 2001 are listed for the first set of 22, the second set of 22, the third set of 16, the third set of 22, and the fourth set of 12 noncancer chronic RELs, respectively. The chronic REL for carbon disulfide was adopted in May 2002. Chronic RELs for phosphine and triethylamine were adopted in September 2002. Chronic RELs for fluorides including hydrogen fluoride were adopted August 2003. Chronic REL for silica [crystalline respirable] was adopted February 2005. • October 2000 is listed for the oral chronic RELs and oral cancer slope factors. • Cancer potency value adopted for naphthalene in August 2004. The inhalation and oral cancer potency values for ethyl benzene were adopted in November 2007. • For the substances identified as Toxic Air Contaminants, the Air Resources Board hearing date is listed. The dates for acetaldehyde, benz[a]pyrene, and methyl tertiary-butyl ether represent the dates the values were approved by the Scientific Review Panel. • On December 19, 2008, OEHHHA adopted new acute, 8-hour, and chronic RELs for acetaldehyde, acrolein, arsenic, formaldehyde, and mercury. The most current health values can be found at: http://www.oehha.ca.gov/air/airtox.html. Note that the 8-hour RELs are not included in the HARP program. These health factors will be added after OEHHHA approves the Guidelines Manual (Part V). <p>Note: 1. OEHHHA presents the new oral RELs in micrograms (µg/kg-d) and we converted them to milligrams (mg/kg-d) for consistency.</p> <p>2. Acute RELs with longer averaging periods (i.e., 4-hour, 6-hour, and 7-hour) will now use the 1-hour averaging period. The affected chemicals are: arsenic & inorganic arsenic compounds, benzene, carbon disulfide, carbon tetrachloride, chloroform, ethylene glycol monoethyl ether, ethylene glycol dimethyl ether, and ethylene glycol monomethyl ether.</p> <p>3. At OEHHHA's direction, the chronic oral REL for arsenic does not apply to arsine because arsine is a gas and not particle associated.</p>	<p>* Inhalation cancer potency factor: The "unit risk factor" has been replaced in the new risk assessment algorithms by a factor called the "inhalation cancer potency factor". Inhalation cancer potency factors are expressed as units of inverse dose [i.e., (mg/kg-day)⁻¹]. They were derived from unit risk factors [units = (µg/m³)⁻¹] by assuming that a receptor weighs 70 kilograms and breathes 20 cubic meters of air per day. The inhalation potency factor is used to calculate a potential inhalation cancer risk using the new risk assessment algorithms defined in the OEHHHA, Air Toxics Hot Spots Program, Part IV, Technical Support Document for Exposure Assessment and Stochastic Analysis (September 2000).</p> <p>◆ Molecular Weight Adjustment Factor: Molecular weight adjustment factors (MWAFF) are only to be used when a toxic metal has a cancer potency factor. For most of the Hot Spots toxic metals, the OEHHHA cancer potency factor applies to the weight of the toxic metal atom contained in the overall compound. Some of the Hot Spots compounds contain various elements along with the toxic metal atom (e.g., "Nickel hydroxide" CAS number 12054-48-7, has a formula of H₂NiO₂). Therefore, an adjustment to the reported pounds of the overall compound is needed before applying the OEHHHA cancer potency factor for "Nickel and compounds" to such a compound. This ensures that the cancer potency factor is applied only to the fraction of the overall weight of the emissions that are associated with health effects of the metal. In other cases, the Hot Spots metals are already reported as the metal atom equivalent (e.g., CAS 7440-02-0, "Nickel"), and these cases do not use any further molecular weight adjustment. (Refer to Note [7] in Appendix A. List of Substances in the EICG Report for further information on how the emissions of various Hot Spots metal compounds are reported.) The appropriate molecular weight adjustment factors (MWAFF) to be used along with the OEHHHA cancer potency factors for Hot Spots metals can be found in the MWAFF column of this table.</p>	<p>So, for example, assume 100 pounds of "Nickel hydroxide" emissions are reported under CAS number 12054-48-7. To get the Nickel atom equivalent of these emissions, multiply by the listed MWAFF (0.6332) for Nickel hydroxide:</p> <ul style="list-style-type: none"> • 100 pounds x 0.6332 = 63.32 pounds of Nickel atom equivalent <p>This step should be completed prior to applying the OEHHHA cancer potency factor for "Nickel and compounds" in a calculation for a prioritization score or risk assessment calculation. (For more information see Chapter 8 of OEHHHA's document, The Air Toxics Hot Spots Program Guidance Manual for Preparation of Health Risk Assessments.)</p> <p>Note: The value listed in the MWAFF column for Asbestos is not a molecular weight adjustment. This is a conversion factor for adjusting mass to fibers or structures. See Appendix C of OEHHHA's document The Air Toxics Hot Spots Program Guidance Manual for Preparation of Health Risk Assessments for more information on Asbestos, or see the EICG report for reporting guidance. Also see the Asbestos footnote (designated by the symbol H)</p>
--	--	---	---

Table 1
CONSOLIDATED TABLE OF OEHA/ARB APPROVED RISK ASSESSMENT HEALTH VALUES°

N/A	Not Applicable
TAC	Toxic Air Contaminant: The Air Resources Board has identified this substance as a Toxic Air Contaminant.
H	Asbestos: The units for the Inhalation Cancer Potency factor for asbestos are (100 PCM fibers/m ³) ⁻¹ . A conversion factor of 100 fibers/0.003 µg can be multiplied by a receptor concentration of asbestos expressed in µg/m ³ . Unless other information necessary to estimate the concentration (fibers/m ³) of asbestos at receptors of interest is available. A unit risk factor of 1.9 E 10 ⁻⁴ (µg/m ³) ⁻¹ and an inhalation cancer potency factor of 2.2 E 10 ⁻² (mg/kg BW • day) ⁻¹ are available. For more information on asbestos quantity conversion factors, see Appendix C of OEHA's <i>The Air Toxics Hot Spots Program Risk Assessment Guidelines</i> ; Part II, <i>Technical Support Document for Describing Available Cancer Potency Factors</i> , and Appendix C of OEHA's document <i>The Air Toxics Hot Spots Program Guidance Manual for Preparation of Health Risk Assessments</i> .
Q	Hexavalent Chromium: The oral cancer slope factor for chromium 6+ and compounds has been withdrawn by the Office of Environmental Health Hazard Assessment.
	Inorganic Lead: Inorganic Lead was identified by the Air Resources Board as a Toxic Air Contaminant in April 1997. Since information on noncancer health effects show no identified threshold, no Reference Exposure Level has been developed. The document, <i>Risk Management Guidelines for New, Modified, and Existing Sources of Lead</i> , March 2001, has been developed by ARB and OEHA staff for assessing noncancer health impacts from sources of lead. See Appendix F of OEHA's document <i>The Air Toxics Hot Spots Program Guidance Manual for Preparation of Health Risk Assessments</i> for an overview of how to evaluate noncancer impacts from exposure to lead using these risk management guidelines.
Φ	Polycyclic Aromatic Hydrocarbons (PAHs): These substances are PAH or PAH-derivatives that have OEHA-developed Potency Equivalency Factors (PEFs) which were approved by the Scientific Review Panel in April 1994 (see ARB document entitled <i>Benzofluorene as a Toxic Air Contaminant</i>). PAH inhalation slope factors listed here have been adjusted by the PEFs. See Appendix G of OEHA's document <i>The Air Toxics Hot Spots Program Guidance Manual for Preparation of Health Risk Assessments</i> for more information. See section 8.2.3 of OEHA's <i>The Air Toxics Hot Spots Program Guidance Manual for Preparation of Health Risk Assessments</i> for conducting health risks when total (unspecified) PAHs are reported.
	Polychlorinated Biphenyls: (unspecified mixtures) Lowest Risk: For use in cases where congeners with more than four chlorines comprise less than one-half percent of total polychlorinated biphenyls. High Risk: For use in cases where congeners with more than four chlorines do not comprise less than one-half percent of total polychlorinated biphenyls. Low Risk: This number would not ordinarily be used in the Hot Spots program. Chronic Oral: The chronic oral value is U.S. EPA's 1996 oral Reference Dose for Aroclor-1254.
Q	Polychlorinated Biphenyls (specified): Values calculated using WHO ₉₇ TEF procedure. See OEHA memo dated August 29, 2003.
•	Polychlorinated Dibenzop-dioxins and Polychlorinated Dibenzofurans (also referred to as chlorinated dioxins and dibenzofurans): The OEHA has adopted the World Health Organization 1997 (WHO ₉₇) Toxicity Equivalency Factor scheme for evaluating the cancer risk due to exposure to samples containing mixtures of polychlorinated dibenzo-p-dioxins (PCDD) and polychlorinated dibenzofurans (PCDF) and determining cancer risks for a number of specific PCB congeners. See Appendix A of OEHA's <i>Technical Support Document For Describing Available Cancer Potency Factors</i> for more information about the scheme. See Appendix E of OEHA's <i>The Air Toxics Hot Spots Program Guidance Manual for Preparation of Health Risk Assessments</i> for the methodology for calculating 2,3,7,8-equivalents for PCDD, PCDFs and a number of specific PCB congeners. See section 8.2.3 of OEHA's <i>The Air Toxics Hot Spots Program Guidance Manual for Preparation of Health Risk Assessments</i> for conducting health risks when total (unspecified) chlorinated dioxins and furans are reported.
¶	Particulate Emissions from Diesel-Fueled Engines: The inhalation cancer potency factor and chronic REL were derived from whole diesel exhaust and should be used only for impacts from the inhalation pathway. The inhalation impacts from speciated emissions from diesel-fueled engines are already accounted for in the inhalation cancer potency factor and REL. However, at the discretion of the risk assessor, speciated emissions from diesel-fueled engines may be used to estimate acute noncancer health impacts or the contribution to cancer risk for the non-inhalation exposure pathway. See Appendix D of OEHA's document <i>The Air Toxics Hot Spots Program Guidance Manual for Preparation of Health Risk Assessments</i> for more information.

MSDS Number: B2347 ***** Effective Date: 11/17/99 ***** Supercedes: 12/08/96

MSDS Material Safety Data Sheet	From: Mallinckrodt Baker, Inc. 222 Red School Lane Phillipsburg, NJ 08865	24 Hour Emergency Telephone: 908-859-2151 CHEMTREC: 1-800-424-9300 National Response in Canada CANUTEC: 613-996-8666 Outside U.S. And Canada Chemtrec: 703-527-3887
	MBI	NOTE: CHEMTREC, CANUTEC and National Response Center emergency numbers to be used only in the event of chemical emergencies involving a spill, leak, fire, exposure or accident involving chemicals.

All non-emergency questions should be directed to Customer Service (1-800-582-2537) for assistance.

BIPHENYL

1. Product Identification

Synonyms: Diphenol; 1,1'biphenyl; phenylbenzene
CAS No.: 92-52-4
Molecular Weight: 154.21
Chemical Formula: C12H10

2. Composition/Information on Ingredients

Ingredient	CAS No	Percent	Hazardous
Biphenyl	92-52-4	90 - 100%	Yes

3. Hazards Identification

Emergency Overview

WARNING! HARMFUL IF SWALLOWED, INHALED OR ABSORBED THROUGH SKIN. CAUSES IRRITATION TO SKIN, EYES AND RESPIRATORY TRACT. MAY AFFECT LIVER, CENTRAL AND PERIPHERAL NERVOUS SYSTEMS. MAY CAUSE ALLERGIC SKIN REACTION.

Potential Health Effects

Inhalation:

Inhalation of dust or vapors can irritate the mucous membranes and respiratory tract. Other symptoms may parallel those from ingestion exposure.

Ingestion:

Exerts toxic effects on the central nervous system and liver. Symptoms may include headache, diffuse gastro-intestinal pain, nausea, numbness, body aches, and general fatigue.

Skin Contact:

May cause irritation. May be absorbed through the skin with symptoms paralleling those from ingestion exposure. May cause allergic reaction in sensitive individuals.

Eye Contact:

Vapors and dust cause eye irritation.

Chronic Exposure:

Chronic exposure may cause peripheral nerve damage and liver injury.

Aggravation of Pre-existing Conditions:

No information found.

4. First Aid Measures

Inhalation:

Remove to fresh air. If not breathing, give artificial respiration. If breathing is difficult, give oxygen. Get medical attention.

Ingestion:

Induce vomiting immediately as directed by medical personnel. Never give anything by mouth to an unconscious person. Get medical attention.

Skin Contact:

Immediately flush skin with plenty of soap and water for at least 15 minutes while removing contaminated clothing and shoes. Get medical attention. Wash clothing before reuse. Thoroughly clean shoes before reuse.

Eye Contact:

Immediately flush eyes with plenty of water for at least 15 minutes, lifting lower and upper eyelids occasionally. Get medical attention immediately.

5. Fire Fighting Measures

Fire:

Flash point: 113C (235F) CC

Autoignition temperature: 540C (1004F)

Flammable limits in air % by volume:

lcl: 0.6; ucl: 5.8

Explosion:

Above the flash point, explosive vapor-air mixtures may be formed. Fine dust dispersed in air in sufficient concentrations, and in the presence of an ignition source is a potential dust explosion hazard.

Fire Extinguishing Media:

Water spray, dry chemical, alcohol foam, or carbon dioxide. Water or foam may cause frothing.

Special Information:

In the event of a fire, wear full protective clothing and NIOSH-approved self-contained breathing apparatus with full facepiece operated in the pressure demand or other positive pressure mode.

6. Accidental Release Measures

Remove all sources of ignition. Ventilate area of leak or spill. Wear appropriate personal protective equipment as specified in Section 8. Spills: Clean up spills in a manner that does not disperse dust into the air. Use non-sparking tools and equipment. Reduce airborne dust and prevent scattering by moistening with water. Pick up spill for recovery or disposal and place in a closed container. US Regulations (CERCLA) require reporting spills and releases to soil, water and air in excess of reportable quantities. The toll free number for the US Coast Guard National Response Center is (800) 424-8802.

7. Handling and Storage

Keep in a tightly closed container, stored in a cool, dry, ventilated area. Protect against physical damage. Isolate from incompatible substances. Containers of this material may be hazardous when empty since they retain product residues (dust, solids); observe all warnings and precautions listed for the product.

8. Exposure Controls/Personal Protection

Airborne Exposure Limits:

-OSHA Permissible Exposure Limit (PEL):

0.2 ppm (TWA).

-ACGIH Threshold Limit Value (TLV):

0.2 ppm (TWA)

Ventilation System:

A system of local and/or general exhaust is recommended to keep employee exposures below the Airborne Exposure Limits. Local exhaust ventilation is generally preferred because it can control the emissions of the contaminant at its source, preventing dispersion of it into the general work area. Please refer to the ACGIH document, *Industrial Ventilation, A Manual of Recommended Practices*, most recent edition, for details.

Personal Respirators (NIOSH Approved):

If the exposure limit is exceeded and engineering controls are not feasible, a half-face respirator with an organic vapor cartridge and particulate filter (NIOSH type N95 or better filter) may be worn for up to ten times the exposure limit or the maximum use concentration specified by the appropriate regulatory agency or respirator supplier, whichever is lowest. A full-face piece respirator with an organic vapor cartridge and particulate filter (NIOSH N 100 filter) may be worn up to 50 times the exposure limit, or the maximum use concentration specified by the appropriate regulatory agency or respirator supplier, whichever is lowest. If oil particles (e.g. lubricants, cutting fluids, glycerine, etc.) are present, use a NIOSH type R or P particulate filter. For emergencies or instances where the exposure levels are not known, use a full-face piece positive-pressure, air-supplied respirator. WARNING: Air-purifying respirators do not protect workers in oxygen-deficient atmospheres.

Skin Protection:

Wear impervious protective clothing, including boots, gloves, lab coat, apron or coveralls, as appropriate, to prevent skin contact.

Eye Protection:

Use chemical safety goggles and/or full face shield where dusting or splashing of solutions is possible. Maintain eye wash fountain and quick-drench facilities in work area.

9. Physical and Chemical Properties

Appearance:

White crystals.

Odor:

Pleasant, peculiar odor.

Solubility:

Insoluble in water.

Specific Gravity:

1.041

pH:

No information found.

% Volatiles by volume @ 21C (70F):

0

Boiling Point:

254 - 255C (489 - 491F)

Melting Point:

69 - 70C (156 - 158F)

Vapor Density (Air=1):

5.31

Vapor Pressure (mm Hg):

0.005 @ 20.4C (68F)

Evaporation Rate (BuAc=1):

No information found.

10. Stability and Reactivity

Stability:

Stable under ordinary conditions of use and storage.

Hazardous Decomposition Products:

Carbon dioxide and carbon monoxide may form when heated to decomposition.

Hazardous Polymerization:

Will not occur.

Incompatibilities:

Strong oxidizers.

Conditions to Avoid:

Heat, flame, ignition sources, dusting and incompatibles.

11. Toxicological Information**Toxicological Data:**

Oral rat LD50 2400 mg/kg; Skin rabbit LD50: > 5010 mg/kg; Irritation (std Draize) rabbit: eye = 100 mg, mild. Investigated as a tumorigen and mutagen.

Carcinogenicity:

EPA / IRIS classification: Group D1 - Not classifiable as a human carcinogen.

-----\Cancer Lists\-----			
Ingredient	---NTP Carcinogen---		
	Known	Anticipated	IARC Category
Biphenyl (92-52-4)	No	No	None

12. Ecological Information**Environmental Fate:**

No information found.

Environmental Toxicity:

No information found.

13. Disposal Considerations

Whatever cannot be saved for recovery or recycling should be managed in an appropriate and approved waste disposal facility. Processing, use or contamination of this product may change the waste management options. State and local disposal regulations may differ from federal disposal regulations. Dispose of container and unused contents in accordance with federal, state and local requirements.

14. Transport Information**International (Water, I.M.O.)****Proper Shipping Name:** ENVIRONMENTALLY HAZARDOUS SUBSTANCES, SOLID, N.O.S. (DIPHENYL)**Hazard Class:** 9**UN/NA:** UN3077**Packing Group:** III**Information reported for product/size:** 1KG**International (Air, I.C.A.O.)****Proper Shipping Name:** ENVIRONMENTALLY HAZARDOUS SUBSTANCES, SOLID, N.O.S. (DIPHENYL)**Hazard Class:** 9**UN/NA:** UN3077**Packing Group:** III**Information reported for product/size:** 1KG**15. Regulatory Information**

-----\Chemical Inventory Status - Part 1\-----				
Ingredient	TSCA	EC	Japan	Australia
Biphenyl (92-52-4)	Yes	Yes	Yes	Yes

-----\Chemical Inventory Status - Part 2\-----				
Ingredient	Korea	--Canada--		
		DSL	NDSL	Phil.
Biphenyl (92-52-4)	Yes	Yes	No	Yes

-----\Federal, State & International Regulations - Part 1\-----				
Ingredient	-SARA 302-		-SARA 313-	
	RQ	TPQ	List	Chemical Catg.
Biphenyl (92-52-4)	No	No	Yes	No

-----\Federal, State & International Regulations - Part 2\-----			
Ingredient	CERCLA	-RCRA-	
		261.33	-TSCA- 8 (d)
Biphenyl (92-52-4)	100	No	No

Chemical Weapons Convention: No TSCA 12(b): No CDTA: Yes
 SARA 311/312: Acute: Yes Chronic: Yes Fire: No Pressure: No
 Reactivity: No (Pure / Solid)

Australian Hazchem Code: None allocated.

Poison Schedule: None allocated.

WHMIS:

This MSDS has been prepared according to the hazard criteria of the Controlled Products Regulations (CPR) and the MSDS contains all of the information required by the CPR.

16. Other Information

NFPA Ratings: Health: 2 Flammability: 1 Reactivity: 0

Label Hazard Warning:

WARNING! HARMFUL IF SWALLOWED, INHALED OR ABSORBED THROUGH SKIN. CAUSES IRRITATION TO SKIN, EYES AND RESPIRATORY TRACT. MAY AFFECT LIVER, CENTRAL AND PERIPHERAL NERVOUS SYSTEMS. MAY CAUSE ALLERGIC SKIN REACTION.

Label Precautions:

Avoid contact with eyes, skin and clothing.

Avoid breathing dust.

Keep container closed.

Use only with adequate ventilation.

Wash thoroughly after handling.

Label First Aid:

In case of contact, immediately flush eyes or skin with plenty of water for at least 15 minutes while removing contaminated clothing and shoes. Wash clothing before reuse. If inhaled, remove to fresh air. If not breathing, give artificial respiration. If breathing is difficult, give oxygen. If swallowed, induce vomiting immediately as directed by medical personnel. Never give anything by mouth to an unconscious person. In all cases, get medical attention.

Product Use:

Laboratory Reagent.

Revision Information:

MSDS Section(s) changed since last revision of document include: 8.

Disclaimer:

Mallinckrodt Baker, Inc. provides the information contained herein in good faith but makes no representation as to its comprehensiveness or accuracy. This document is intended only as a guide to the appropriate precautionary handling of the material by a properly trained person using this product. Individuals receiving the information must exercise their independent judgment in determining its appropriateness for a particular purpose. MALLINCKRODT BAKER, INC. MAKES NO REPRESENTATIONS OR WARRANTIES, EITHER EXPRESS OR IMPLIED, INCLUDING WITHOUT LIMITATION ANY WARRANTIES OF MERCHANTABILITY, FITNESS FOR A PARTICULAR PURPOSE WITH RESPECT TO THE INFORMATION SET FORTH HEREIN OR THE PRODUCT TO WHICH THE INFORMATION REFERS. ACCORDINGLY, MALLINCKRODT BAKER, INC. WILL NOT BE RESPONSIBLE FOR DAMAGES RESULTING FROM USE OF OR RELIANCE UPON THIS INFORMATION.

Prepared by: Environmental Health & Safety

Phone Number: (314) 654-1600 (U.S.A.)

Table C.4-6

CENSUS FINDINGS

<u>Map ID</u>	<u>Tract Number</u>	<u>Total Population</u>	<u>Population in Radius</u>	<u>Total Area(sq.mi.)</u>	<u>Area in Radius(sq.mi.)</u>
T1	0116.00	6151	505.2	1369.86	112.52

Table C.4-7 Three Highest MIR Locations and Risk Values

RECEPTORS WITH HIGHEST CANCER RISK

REC	TYPE	CANCER	CHRONIC	ACUTE	UTME	UTMN	ZONE
130	GRID	2.59E-07	2.08E-03	1.01E-02	469945	3874500	11
131	GRID	2.53E-07	1.68E-03	9.45E-03	469945	3874550	11
302	GRID	2.28E-07	1.53E-03	4.79E-03	473151	3873400	11

RECEPTORS WITH HIGHEST CHRONIC HI

REC	TYPE	CANCER	CHRONIC	ACUTE	UTME	UTMN	ZONE
130	GRID	2.59E-07	2.08E-03	1.01E-02	469945	3874500	11
131	GRID	2.53E-07	1.68E-03	9.45E-03	469945	3874550	11
302	GRID	2.28E-07	1.53E-03	4.79E-03	473151	3873400	11

RECEPTORS WITH HIGHEST ACUTE HI

REC	TYPE	CANCER	CHRONIC	ACUTE	UTME	UTMN	ZONE
130	GRID	2.59E-07	2.08E-03	1.01E-02	469945	3874500	11
113	GRID	1.23E-07	1.08E-03	1.01E-02	469919	3874450	11
112	GRID	1.68E-07	1.31E-03	9.86E-03	469919	3874500	11

Figure C.4-1
Census Tracts in Site Area




Figure C.4-2
6-Mile Radius Zone Map





Figure C.4-3
3 Highest Cancer MIR Locations



**PHASE I
ENVIRONMENTAL INVESTIGATION**

FOR

**APN Number
Unincorporated area – San Bernardino County – Near Hinkley CA**

Assessor Parcel No.'s

0490-131-06
0490-131-07
0490-131-08
0490-131-11
0490-131-12
0490-131-13
0490-131-15
0490-131-16

0490-161-08
0490-161-09
0490-161-10
0490-161-11
0490-161-12
0490-161-13

0490-121-42

0490-171-09

Prepared for: Mojave Solar Project

May 28, 2009

Prepared by:
SHIRLEY R. HIBBETTS
R.E.A. – 06404
ENVIRO ✓ CHEK
P. O. Box 355
Helendale CA 92342
(760) 952-3572

TABLE OF CONTENTS

- I. Introduction / Purpose
- II. Historical Review
- III. Site Description
- IV. Site Reconnaissance
- V. Summary / Interviews & Records Review
 - A San Bernardino County Fire Department
Hazardous Materials Division
 - B Rodney Most
 - C Nick Grill – Terawatt Construction
 - D Gary Clark
 - E Henry Orlosky
 - F Mojave Water Agency
 - G Southwest Gas Corporation
 - H Lahontan Regional Water Quality Control Board VI
- VI. Findings & Conclusions
- VII. Vicinity Maps & Metroscan Property Profile – San Bernardino County
- VIII. Photographs
- IX. Attachments - Contacts

I. INTRODUCTION / PURPOSE

The purpose of this Phase I Environmental Site Assessment (ESA) was to determine if the parcels of real property listed in this report are subject to environmental conditions. Investigation was done to identify any conditions indicative of releases and /or threatened releases of hazardous substances, and to identify any areas known to be contaminated, (or a source of contamination), at or near the site. The site was photographed. Investigations were conducted to verify that there is not now, nor has there ever been release of any hazardous substances, hazardous waste, or petroleum products upon the property.

Enviro Chek environmental site assessments are conducted in accordance with general industry practices and most guidelines established within the American Society for Testing and Materials (ASTM) Standard E 1527-05. The focus of this assessment will relate exclusively to hazardous materials issues in direct relation only to soil and groundwater contamination at the site. The investigation targets issues that constitute recognized environmental conditions at the site. These are primarily issues that may or would require soil or groundwater investigation or clean-up activities.

II. HISTORICAL REVIEW:

The site is approximately 1,765 acres in size located in section numbers 28, 29, 30, 32, and 33, within Township 11 North, Range 4 West, San Bernardino Base and Meridian, County of San Bernardino, State of California. The sites have been used for agricultural purposes in the past, and have historically been used for agricultural production and cattle ranching since at least the 1930's.

Historical review consists of: 1) interviews with municipal employees to obtain information on former and present land use of the site, 2) Physical inspection of the property and surrounding area for the purpose of detecting potential environmentally hazardous conditions, 3) interviews with governmental and regulatory agencies and review of available public records to determine the locations of properties with known or suspected hazardous waste contamination in the general area of the subject site.

On 04-24-09 the databases of Metroscan Property Profiles, San Bernardino California, and the San Bernardino County Assessor's Office were queried. Those records indicate that ownership history as of that date for the properties in question is as follows:

III. SITE DESCRIPTION:

APN Site Address: Legal Description:	0490-121-42-0000 - 588.42 Acres 41800 Harper Lake Road, Hinkley CA 92347 PARCEL MAP 12194 PARCEL 4 EX PTN LYING WITHIN THE NE ¼ NW ¼ SEC 30 TP 11N R 4 W Land Use: 0712 Agr. Field Crops Property Type: Agricultural
Transfer History:	Solucar Inc. 05-10-2007 Harper Lake LLC 06-09-2004 Orlosky Family Trust 04-02-1999 Milton W & Jennie Most 04-27-1992 Orlosky Family Trust No date Harper Lake Energy Corp. No date Bank of America Nt. & SA No date
APN Site Address: Legal Description:	0490 131 06 000 – 160 Acres Lockhart Road, Hinkley CA 92347 SE ¼ SEC 29 TP 11N R 4W 160 AC Land Use: 0712 Agr. field Crops Property Type: Agricultural
Structure #1:	4 rooms, 2 bedrooms, 1 bath, 742 sq ft. Built 1950
Structure #2	4 rooms, 2 bedrooms, 1 bath, 948 sq ft. Built 1952
Transfer History:	Solucar Inc. 05-10-2007 Harper Lake LLC 06-09-2004 Orlosky, Henry/Kathy Family Trust 08-31-2000 Milton W & Jennie Most 04-28-1992 Orlosky Family Trust No date Harper Lake Energy Cor No date Bank of America Nt & Sa No date
APN Site Address: Legal Description:	0490 131 07 0000 – 160 Acres 48084 Hoffman Road Hinkley 92347 SW ¼ SEC 29 TP 11N R 4W 160 AC Land Use: 0712 Agr. Field Crops Property Type: Agricultural
Transfer History:	Solucar Inc 05-10-2007
APN Site Address: Legal Description:	0490 131 11 0000 – 40 Acres No Site Address NW ¼ SW ¼ SEC 28 TP 11N R 4W 40 AC Land Use: Vacant Property Type: Single Family Residential
Transfer History:	Abengoa Solar Inc. 11-26-08
APN Site Address: Legal Description:	0490 131 12 0000 – 40 Acres 16198 Lockhart Road Hinkley 92347 SW ¼ SW ¼ SEC 28 TP 11N R 4W 40 AC Lane Use: 0510 Single Family Residence Property Type: Single Family Residential
Structure:	6 rooms, 3 bedrooms 2 bath, fireplace, central heat

	evaporative cooler, Comp Shingle Roof, Built 1956 1472 sq ft / detached garage
Transfer History:	Abengoa Solar Inc. 11-26-2008
APN Site Address: Legal Description	0490 131 13 0000 – 20 Acres No Site Address E ½ SE ¼ SW ¼ SEC 28 TP 11N R 4W EX MNL RTS RESERVATION OF RECORD
Transfer History:	Larry T. Lampkin/ Virginia Hernandez No Date
APN Site Address: Legal Description:	0490 131 15 000 – 20 Acres No Site Address W ½ SE ¼ SW ¼ SEC 28 TP 11N R 42 EX MNL RTS RESERVATION OF RECORD Land Use: Vacant Property Type: Single Family Residential
Transfer History:	Abengoa Solar Inc 07-10-2008
APN Site Address: Legal Description	0490 131 16 0000 – 40 Acres No Site Address NE ¼ SW ¼ SEC 28 TP 11N R 4W EX MNL RTS RESERVATION OF RECORD Land Use: Vacant Property Type: Single Family Residential
Transfer History:	Abengoa Solar Inc. 07-10-2008
APN Site Address: Legal Description:	0490 161 08 0000 – 80 Acres No Site Address W ½ NE ¼ SEC 32 TP 11N R 4W 80 AC Land Use: 0712 Agr. Field Crops Property Type: Agricultural
Transfer History:	Desert View Dairy 02-18-2004 Van Vliet, Hugo N. / Geri 03-22-2000 Thelma & Pamela G. Harold 05-16-1979 Desert View Dairy No date VanVliet, Hugo N. / Geri No date
APN Site Address: Legal Description:	0490 161 09 0000 – 80 Acres None Listed E ½ NE ¼ SEC 32 TP 11n r 4W 9- AC Land Use: 712 Agr. Field Crops Property Type: Agricultural
Transfer History:	Desert View Dairy 02-18-2004 Van Vliet, Hugs N. 03-22-2000 Desert View Dairy No date Van Vliet, Nugo N/ Geri No date Harold & Pamela G. Harold No date
APN Site Address: Legal Description:	0490 161 10 0000 – 160 Acres 48084 Hoffman Road, Hinkley CA NW ¼ SEC 33 TP 11N R 4W 160 AC Land Use: 0712 Agr. Field Crops Property Type: Agricultural

Transfer History:	<table> <tr><td>Solucar, Inc.</td><td>05-10-2007</td></tr> <tr><td>Harper Lake Llc</td><td>06-09-2004</td></tr> <tr><td>Henry/Kathy Orlosky Fmly Trust</td><td>08-31-2000</td></tr> <tr><td>Milton & Jennie Most</td><td>04-27-1992</td></tr> <tr><td>Orlosky Family Trust</td><td>No date</td></tr> <tr><td>Harper Lake Energy Corp</td><td>No date</td></tr> <tr><td>Bank of America Nt & Sa</td><td>No date</td></tr> </table>	Solucar, Inc.	05-10-2007	Harper Lake Llc	06-09-2004	Henry/Kathy Orlosky Fmly Trust	08-31-2000	Milton & Jennie Most	04-27-1992	Orlosky Family Trust	No date	Harper Lake Energy Corp	No date	Bank of America Nt & Sa	No date
Solucar, Inc.	05-10-2007														
Harper Lake Llc	06-09-2004														
Henry/Kathy Orlosky Fmly Trust	08-31-2000														
Milton & Jennie Most	04-27-1992														
Orlosky Family Trust	No date														
Harper Lake Energy Corp	No date														
Bank of America Nt & Sa	No date														
APN Site Address: Legal Description:	0490 161 11 0000 – 160 Acres County Road, Hinkley CA 92347 NE ¼ SEC 33 TP 11N R 4W EX MNL RTS RESERVATION OF RECORD 160 AC Land Use: 0712 Agr. Field Crops Property Type: Agricultural														
Transfer History:	<table> <tr><td>Solucar Inc.</td><td>05-10-2007</td></tr> <tr><td>Harper Lake Llc</td><td>06-09-2004</td></tr> <tr><td>Henry/Kathy Olosky Family Trust</td><td>08-31-2000</td></tr> <tr><td>Milton W. & Jennie Most</td><td>04-27-1992</td></tr> <tr><td>Orlosky Family Trust</td><td>No date</td></tr> <tr><td>Harper Lake Energy Corp</td><td>No date</td></tr> <tr><td>Bank of America Nt & Sa</td><td>No date</td></tr> </table>	Solucar Inc.	05-10-2007	Harper Lake Llc	06-09-2004	Henry/Kathy Olosky Family Trust	08-31-2000	Milton W. & Jennie Most	04-27-1992	Orlosky Family Trust	No date	Harper Lake Energy Corp	No date	Bank of America Nt & Sa	No date
Solucar Inc.	05-10-2007														
Harper Lake Llc	06-09-2004														
Henry/Kathy Olosky Family Trust	08-31-2000														
Milton W. & Jennie Most	04-27-1992														
Orlosky Family Trust	No date														
Harper Lake Energy Corp	No date														
Bank of America Nt & Sa	No date														
APN Site Address: Legal Description:	0490 161 12 0000 – 160 Acres 48084 Hoffman Road, Hinkley 92347 SE ¼ SEC 33 TP 11N R 4W 160 AC EX WATER RIGHTS														
Transfer History:	<table> <tr><td>Solucar Inc.</td><td>05-10-2007</td></tr> <tr><td>Harper Lake Llc</td><td>06-09-2004</td></tr> <tr><td>Henry/Kathy Orlosky Family Trust</td><td>08-31-2000</td></tr> <tr><td>Milton M & Jennie Most</td><td>04-27-1992</td></tr> <tr><td>Orlosky Family Trust</td><td>No Date</td></tr> <tr><td>Harper Lake Energy Corp</td><td>No Date</td></tr> <tr><td>Bank of America Nt & Sa</td><td>No Date</td></tr> </table>	Solucar Inc.	05-10-2007	Harper Lake Llc	06-09-2004	Henry/Kathy Orlosky Family Trust	08-31-2000	Milton M & Jennie Most	04-27-1992	Orlosky Family Trust	No Date	Harper Lake Energy Corp	No Date	Bank of America Nt & Sa	No Date
Solucar Inc.	05-10-2007														
Harper Lake Llc	06-09-2004														
Henry/Kathy Orlosky Family Trust	08-31-2000														
Milton M & Jennie Most	04-27-1992														
Orlosky Family Trust	No Date														
Harper Lake Energy Corp	No Date														
Bank of America Nt & Sa	No Date														
APN Site Address: Legal Description:	0490 161 13 0000 – 160 Acres 48084 Hoffman Road Hinkley 92347 SW ¼ SEC 33 TP 11N R 42 160 AC Land Use: 071- Agr. Field Crops Property Type: Agricultural														
Transfer History:	<table> <tr><td>Solucar Inc.</td><td>05-10-2007</td></tr> <tr><td>Harper Lake Llc</td><td>06-09-2004</td></tr> <tr><td>Henry/Kathy Orlosky Family Trust</td><td>08-31-2000</td></tr> <tr><td>Milton M & Jennie Most</td><td>04-27-1992</td></tr> <tr><td>Orlosky Family Trust</td><td>No Date</td></tr> <tr><td>Harper Lake Energy Corp</td><td>No Date</td></tr> <tr><td>Bank of America Nt & Sa</td><td>No Date</td></tr> </table>	Solucar Inc.	05-10-2007	Harper Lake Llc	06-09-2004	Henry/Kathy Orlosky Family Trust	08-31-2000	Milton M & Jennie Most	04-27-1992	Orlosky Family Trust	No Date	Harper Lake Energy Corp	No Date	Bank of America Nt & Sa	No Date
Solucar Inc.	05-10-2007														
Harper Lake Llc	06-09-2004														
Henry/Kathy Orlosky Family Trust	08-31-2000														
Milton M & Jennie Most	04-27-1992														
Orlosky Family Trust	No Date														
Harper Lake Energy Corp	No Date														
Bank of America Nt & Sa	No Date														

IV. SITE RECONNAISSANCE:

05-06-09 & 05-08-09 - Representatives of Enviro Chek toured the proposed site to identify areas of potential environmental concern on and in close proximity to the project area. On this date, the parcels were visually and physically, checked, utilizing a grid pattern, and from the periphery of the property. Photographs were also taken; 12 of which are included with this report as exhibits. All photographs taken will be provided on digital media CD.

	NORTH	SOUTH	WEST	EAST
Section 28	Undeveloped land	Section 33	Undeveloped and residentially developed land	Undeveloped land
Section 29	Undeveloped and residentially developed land	Undeveloped and residentially developed land	Section 30	Undeveloped and residentially developed land
Section 30	SEGS Solar Energy Plant	Undeveloped and residentially developed land	Undeveloped land	Section 29
Section 32	Section 29	Undeveloped and residentially developed land	Section 31	Section 33
Section 33	Section 28	Undeveloped land	Section 32	Undeveloped land

There was a previous cattle farming operation located on Section 30 (APN 0490 121 42). Remnants of the pens and associated watering/feeding troughs are still in place at the site. Cow manure generated during previous operations was likely "land-applied" to the surrounding crop fields as fertilizers. In sections 28, 29, 32, and 33, there is evidence of past agricultural activity on the property. This agricultural use may have included pesticide applications.

Properties are accessible by public paved and unpaved highway. Electric service is overhead. Water is provided by private wells, and there is no sewer.

Aboveground/Underground Storage Tanks (ASTs/USTs) APN 0490 121 42

A previous Phase I ESA completed in 2004 by Altec Testing & Engineering, Inc. reported that there had been underground storage tanks (UST's) at the Lockhart General Store site, located at 41800 Harper Lake Road (APN 0490 121 42). The report indicates the tanks were in front of the general store and were associated with gas dispensing. Mr. Milton Most, previous owner of APN 0490-121-42, reported to staff of Altec that the underground tanks associated with gasoline dispensing at the General Store located at 41800 Harper Lake Road, Hinkley, CA. were removed by an unnamed firm from Los Angeles CA approximately between 1987 and 1990. Enviro Chek has learned that Mr. Milton Most is deceased, therefore could not verify this information through him. According to the Altec Report, they were unable substantiate this UST removal because no County of San Bernardino Permits were obtained for said removal.

Three vent pipes indicative of those associated with the use of underground storage tanks were located on the south wall of the General Store Building. These vent pipes were photographed. (Exhibit 1, Photo #1).

There is some soil discoloration around the area in front of the islands where the gas pumps were formerly located and adjacent to the general store building on all sides. This discoloration was photographed. (Exhibit 1, Photo #2). No chemical spills or large scale soil staining was noted on site on the day of the visit.

Additionally, the Altec report mentions a previously existing 200 – 300 gallon underground storage tank approximately 30' north of the General Store building. Reportedly, this tank was used for aviation fuel. Mr. Most told Altec the tank was removed in 2000 or 2001 by Terawatt Construction. Following those coordinates, located approximately 30' north of the store, there was light discoloration of the soil around that area, which was photographed. It is likely this is the spot from where the aviation fuel tank was removed. (Exhibit 2, Photo #3).

A large barn/hanger with asphalt and dirt floor is located northwest of the General Store. There are some stains on the asphalt and soil

Altec's interview with Mr. Milton Most revealed that at the time of their report (2004) there were three above ground storage tanks, two for gasoline and one for diesel fuel, located to the west and rear of the general store building. There is a concrete slab to the rear of the general store, and there was evidence that the tanks could have previously been located there. The soil around that area was slightly discolored. The area was photographed. (Exhibit 2, Photo #4).

Tanker Trailer – APN 0490 121 42

05-06-09 – It was noted there is a tanker trailer parked at the southeast corner of APN 0490 121 42. There are no identification markings or license plates on the tanker trailer which is moveable, however, is parked with the stabilizers deployed. Some discoloration of the soil was noted under the trailer. The only identifying markings on the trailer was a serial number 190120, with the wording Silica Flour on the southeast side of the tank. There was a mailbox bolted to the front of the trailer. Inside that mailbox was paperwork listing the name of Southwestern Seal & Coating, Adelanto CA. The recipient of a bulk delivery of some type of bulk product was listed as Apex Bulk Commodities, 12531 Violet Road, Adelanto CA 92301 – telephone 760-246-6077. There was another address on the paperwork of SWSC, PO Box 1040, Murrieta CA 92564. There was a tag on the tanker tongue with: USDOE/NV – R190136.

On 05-08-09, upon arrival at the site, it appeared that the tanker trailer had been moved. A hose had been positioned on the back of the tanker and was lying on the ground with a white foam substance leaking from the end of the hose. Near the tanker to the east was several spots of unknown white foam substance. Under the tanker, there was evidence of some type of product that was leaking from within the tank. While photographing the changes in the appearance of the tanker and area around it, a County of San Bernardino truck came by. The unnamed driver indicated that the tanker was used to store magnesium chloride, a substance used for dust control and dirt road maintenance. It was the understanding of the employee that SEGS Solar Plant (located to the north of the project area) is the one responsible for spraying this substance and maintaining the dirt roads in the surrounding area. The tanker and ground were photographed. (Exhibit 3, Photo #5 & #6).

Water Wells

There are numerous water wells/pumps, and irrigation stand pipes located throughout the project area. A complete detail of the location of the wells, both working and historic was provided by Mojave Water agency and is attached to this report. (Attachment #1)

APN 0490 161 11

There is a working well on the north side that is fenced with 6' chain link fence.

APN 0490 161 09

In the northeast corner a working well was located. The soil around the bottom of the well casing was slightly discolored, possibly from diesel fuel, or petroleum products. North of the well was a large above ground tank, bearing a sign which read: "WARNING Chemicals known to the State of California to cause cancer, birth defects, or other reproductive harm may be found in certain petroleum, chemical and fertilizer products." Under the nozzle on the bottom of the tank a small amount of discolored soil was observed. This well and tank were photographed. (Exhibit 4, Photo #7 & #8)

Solid Waste Debris:

On this date, a small amount of solid waste refuse debris was noted throughout the property and all parcels. That solid waste debris was not of a type that would be subject to an enforcement action, or present a material risk of harm to public health or the environment. (Exhibit 5 – Photo #9).

APN 0490 161 12

On the northwest portion of this parcel a small structure was located, which could have been a wash/bath house, with what appears to be a septic tank on the northeast side of the structure

APN 0490 171 09

There is an abandoned well and tank on Harper Lake Road. The soil near the well is stained with what could be petroleum products, possibly diesel fuel. This area was photographed. (Exhibit 5, Photo #10).

Transformers and Other Suspect PCB-containing Equipment

There are several electrical transformers present in the project area along the perimeters of the property. There are also remnants of electrical components at the structures, commercial buildings ruins and well houses. These components could contain PCB's (polychlorinated biphenyls). One such transformer located on the southwest corner of APN 0490 131 06. The transformer was photographed. (Exhibit 6, Photo #11).

Asbestos-Containing Materials

The existing buildings and structural ruins were constructed prior to 1957. Based upon their age, asbestos is suspected as a potential component of the building materials. No samples were collected.

Lead-Based Paint

Based upon the construction date of the onsite buildings and structural ruins, there is a potential that lead-based paints are present. No samples were collected.

V. SUMMARY / INTERVIEWS REGULATORY AGENCY INQUIRIES & RECORDS REVIEW

Between April 8, 2009 and May 28, 2009, interviews were conducted with representatives of the following organizations to verify past and present history of the parcels relevant to the proposed development sites. Follow-up letters confirming all interviews were sent on the day of each interview. Any pertinent responses will be noted and become a part of this report.

A.	San Bernardino County Fire Department Elizabeth King, Environmental Technician III Office of the Fire Marshal Hazardous Materials Division
-----------	---

05-13-09 – Elizabeth King of the Office of the Fire Marshal, Hazardous Materials Division, San Bernardino County, indicated, "This is to confirm that the San Bernardino County Hazardous Materials Division has searched its records for any file (s) pertaining to the subject property, as described in your request, and had identified records that may pertain to the subject site as described in your request for records search." (Attachment #2).

A search of Assessor records indicate:

- APN 0490 121 42 has an address of 41800 Harper Lake Road
- APN 0490 131 06 - 08 has situs Lockhart Road
- APN 0490 131 11 and 13 have no situs
- APN 0490 131 12 has an address of 16198 Lockhart Road
- APN 0490 131 15 – 16 have no situs
- APN 0490 161 08 – 09 (Desert View Dairy) have no situs
- APN 0490 151 10 – 13 have no situs
- APN 0490 171 09 has no situs

Ms. King notes that Assessor maps and ownership history were consulted for searching all parcels, regardless of situs.

Active Permit Facilities:

Regulatory files for facilities with annual operating permits to maintain underground storage tanks, storage of hazardous materials, and/or generate hazardous waste. Files include permits, inspections, reports, test results, correspondence, and related materials. Files also include any underground tank removal/construction activity records and site remediation/contamination records for facilities still in operation.

Desert View Dairy
37601 Mountain View Road
Hinkley CA

FA010927
Hazardous Material Handler Permit
Special type (consolidated manifest)

NOTE: 05-19-09 – Representatives of Enviro Chek visited the San Bernardino Fire Department offices in San Bernardino CA and reviewed the files pertaining to the listed APN's. In the file for Desert View Dairy, a Hazardous Waste Generator and Hazardous Materials Handler Inspection Report, dated May 11, 2007 was noted. The report cited violations (that were to be corrected within 30 days) at that location as follows: No Hazardous Waste Generator Permit; No hazardous materials contingency plan; unlawful storage of used oil filters; failure to meet storage and labeling requirements. Mr. Paul Ryken was listed as the owner.

Hazardous materials inventory for Desert View Dairy outlined: One (1) - 1,000 gal. AST with diesel fuel (red dye); one (1) – 550 gal. AST clear diesel fuel; one (1) 550 gal. AST gasoline; two (2) 55 gal. drums teat dip; one (1) 66 gal. drum propylene glycol; two (2) – 30 gal. drums serilnet; one (1) 55 gal. drum turbine oil; two (2) – 215 cubic feet cylinders Acetylene; two (2) 337 cubic feet cylinders oxygen; and one (1) 227 cubic feet cylinders Argon.

Inactive Permit and/or Non-Permit Facilities:

Inactive regulatory files for formerly permitted facilities that maintained underground storage tanks, stored hazardous materials, and/or generate hazardous waste and/or facilities with underground storage tanks removed and/or materials and waste removed. File also includes any underground tank removal/construction activity records and site remediation/contamination records for facilities no longer operating underground tanks.

Most Ranch
41800 Harper Lake Rd.
Hinkley

FA0004863 (EST 87014349)
Hazardous Material Handler Permit
Underground Storage Tank Permit

San Bernardino County Fire files revealed copies of two environmental reports, one of which was referenced in the Altec Phase I Investigation in 2004 called "The Bradley Report", dated February 13, 1996. In this report there is indication that UST's at 41800 Harper Lake Road (The General Store), had been removed, "and that results of a soil and gas survey completed in the UST vicinity revealed that it is unlikely that a large volume of hydrocarbon impacted soil exists onsite." Report further states, "The eight remaining 400 gallon diesel AST's onsite used to pump the irrigation wells have limited soil staining and is limited to less than 2 feet below the ground surface, and is not considered to be a problematic environmental issue.

NOTE: Handwritten file notes indicate that the UST's were removed between March 30, 1994 and March 19, 1996.

The report further indicates that pesticides were used on the crops; however, they were never stored onsite, according to Mr. Milton Most. The pesticides were brought in for short durations and applied with "crop duster" planes, which landed on a dirt landing strip on the subject site. (The Bradley Report is attached to this report. (Attachment #3).

The second report located in this file check was a "Soil Gas Vapor Survey Result at Most Ranch," completed by ENSR Consulting and Engineering (Camarillo CA), dated September 1990. This report listed only one area of concern; that being the area where the aviation fuel tank was located. ENSR's

conclusion about contamination in this area was that "it is unlikely VOCs exist in the soils surrounding the avgas tank." (Attachment #4).

Permits to Remove/Install/Modify Tanks:

No record of permits to remove/install/modify UGSTs for subject APN's.*

*NOTE: Although there is no record of a permit to remove underground storage tanks in San Bernardino County Fire files, a copy of an environmental assessment report on file for Most Ranch 41800 Harper Lake Road, Hinkley, indicates that 4 UGSTs were removed in the early 1990's. It appears the tanks were removed without permits.

Haz Mat Incident and/or Spill Response Activity:

Other records of spill notifications and/or complaints not listed below may exist in facility permit files

RP: SCE (Vandals)	CO0024125
41800 Harper Lake Road	02-24-07
Hinkley	Release of mineral oil, 30 gallons

On 02-24-07, San Bernardino County Fire was notified by Southern California Edison of "vandals cutting down power lines to access copper at this address. Four transformers released a total of 30 gallons of mineral oil. (Non PCB) ACTI onsite 2/25 to perform cleanup. San Bernardino County Fire staff verified on 02-25-07 that the cleanup was acceptable. No waters affected."

Site Remediation:

Underground storage tank cleanup-under Local Oversight Program or Voluntary Hazardous Waste Clean-Up activity under local jurisdictions. No record of site remediation and/or cleanup action under local jurisdiction on the above APNs.

Records searched include permit database systems for facilities with permits as hazardous waste generators, hazardous materials handlers, and/or underground storage tanks, including inactive and/or out of business records; logs of permits issued for the removal and/or installation of underground storage tanks, records and databases pertaining to illicit dumping and releases; records of non-permitted facilities; sites undergoing remediation for contaminated soil and/or groundwater; and incidents responded to by the hazardous materials emergency response team.

B.	Rodney Most 125 May Street Barstow CA 92311
-----------	--

05-08-09 – Mr. Rodney Most, brother of Milton Most, (former owner of Lockhart Ranch), was contacted for an interview. Mr. Most stated that during the time his brother ran the Lockhart Ranch, he worked and lived there as a ranch hand in the alfalfa fields, and with the livestock. He and his wife lived in the small bungalows located northwest of the General Store.

Mr. Most stated, though he recalled the presence of the gas dispensing operation, he was unaware of when any tanks were removed. He said there was a tank where his nephew and brother filled the fuel tank on their airplane. When not in use, the airplane was parked in the large barn/hanger type structure to the northwest of the General Store. Rodney verified that the tank for the airplane fuel was approximately 30' north of the General Store building. He stated the plane was used by his brother and the nephew for pleasure and for crop dusting of the alfalfa fields. He was not aware if or when the tank for aviation fuel was removed.

Mr. Most was asked about any other above ground tanks that might have been present at that site. He indicated that there were two or three tanks used for gasoline and diesel fuel for farm equipment that had been present on a concrete slab to the rear of the General Store. He was unable to provide

information about the removal of those tanks. He was unaware of any spills or contamination on the property in question.

C.	Nick Grill Terawatt Construction Company Hinkley CA
-----------	--

05-18-09 – Contact was made with Mr. Nick Grill of Terawatt Construction Company. The Altec Report indicated Mr. Grill had knowledge of the underground storage tank used for aviation fuel near the general store on parcel 0490-121-42. Mr. Grill advised that in approximately 2001, he did in fact remove a 500 gallon underground storage tank from the north side of the General Store. He said to his knowledge, the tank had been used to store aviation fuel for Mr. Most's airplane. He stated there was no contamination and the area was backfilled with soil from right there at the site. He advised that the tank was in his storage yard on this date. The tank was photographed. (Exhibit 6, Photo #12).

D.	Gary Clark Wilde Road Helendale CA
-----------	---

05-20-09 – Through the Mojave River Museum in Barstow, Mr. Gary Clark was located and interviewed. Mr. Clark advised that he and his father lived at the Lockhart Ranch when he was in his late teens, from approximately 1957 until 1963. He stated the Lockhart Ranch was a very large cattle farming operation, with large fields where grain was grown, then processed. His father, Tom Clark, was the ranch manager for Mr. Arnold Ditmar, who purchased or leased the ranch from Lockhart in approximately 1957 with the intent of making it into a boy's farm. Apparently, Mr. Ditmar only had the property for about a year, and could not make a go of the boy's farm, so left the area.

Gary said he and his father stayed on at the ranch and the mortgage was purchased from Mr. Lockhart in 1958 by Mr. L. M. Helper, who was a land developer.

According to Gary, the ranch was subsequently purchased by the Oreda Land & Cattle Company of Brawley CA. (Gary was not sure of the proper spelling of the name of the company). He stated they hired Mr. Milton Most as Ranch Manager, and he eventually bought them out and ran the whole operation for a time. Gary stated he was under the impression Mr. Most lost the ranch, and it was taken over by the bank, who then sold the property to Henry Orlosky. He stated Mr. Orlosky lives in Oak Hills CA.

Gary stated he has researched the area for the Mojave River Valley Museum, and that at one time, there was a post office at the Lockhart Ranch. The post office was established January 1, 1953 until February 28, 1957. It was closed for a time, then re-established March 1, 1957. The post office was closed permanently January 31, 1958.

He further advised that Mr. Lockhart had built many little residences around the area of the ranch where his workers lived. Lockhart carried provisions at the general store, so that workers and their families would not have to travel to purchase supplies.

Gary was not aware of any information about underground or above ground tanks, nor was he aware of any information about spills or contamination from petroleum products or hazardous materials. He provided several 8" x 10", black and white photographs he indicated were taken at the time he and his father were at the ranch in 1957. Copies of the photos were sent to the staff of Merrell Johnson Engineering for reference.

E.	Henry Orlosky Oak Hills CA
-----------	---------------------------------------

05-23-09 – Contact was made with Mr. Henry Orlosky, previous owner of the Lockhart Ranch including (APN's 0490-161-10, 11, 12, & 13). He said that ranching started in the Project area approximately 100 years ago in the early 1900's. He said Mr. Lockhart bought the portion he owned in the early 1950's. He said that Milton Most had an alfalfa pellet factory on the property. He purportedly sold the pellets in the LA basin, and the left over product was sold to local dairy farmers. He said he had many conversations with Mr. Milton Most, previous owner, who stated that there had been farm materials, herbicides, insecticides, and fuel tanks on the property; however, there were no reported spills or contamination according to Mr. Most. Mr. Most purportedly told Mr. Orlosky that he had the fuel tanks for fuel dispensing had been removed 25 to 30 years ago. Mr. Orlosky stated there had been a 500 gallon aviation fuel underground tank on the north side of the general store building. He had that tank removed by Nick Grill of Terawatt Construction in 2000 or 2001. He (Orlosky) said there were no leaks or contamination associated with that tank or its removal.

He said Mr. Most used crude oil for his alfalfa factory, and that there had been a crude oil tank located north/northwest of the bungalows northwest of the general store. He stated the 400 to 500 gallon tank had been removed by a salvage company that had scraped up the discolored soil around it.

Mr. Orlosky advised that at one time, wells in the area used diesel engines that had fuel tanks. To his knowledge, all engines had been removed, and he was unaware of any spills or contamination from the diesel fuel. He said there was some staining on the soil after the removal of the engines, however nothing that required any cleanup actions. He said that by-in-large, there have been no agricultural or ranching operations on the property in many years. Those operations ceased in approximately 1999. He stated there was no ranching on the property after 2000. He was unaware of any adverse impacts from the alfalfa ranching.

Mr. Orlosky stated there could possibly be some "drainage tiles" intended to divert rain or flooding near the wells. He said the tiles are supposedly buried under five feet of soil. He was not sure but he thinks the tiles are made of a substance called "Crystal Lite." It is his understanding that the tiles may contain asbestos. He thinks they're on all the agriculture fields. He has only been told about the supposed presence of the tiles, and is not sure they actually exist.

He stated that while he, (Orlosky), owned the property there were no spills or storage of any petroleum products or hazardous materials. Mr. Orlosky believes the ranch is in "reasonably good condition for its age and use."

05-27-09 – Mr. Orlosky sent an e-mail to Enviro Chek to clarify his previous interview. He stated: " It is my belief and understanding that the ranch contained no hazardous materials at the time of sale to Abengoa, other than disclosures previously provided and contained in a Phase I study that was conducted and provided Abengoa in the disclosure documents provided during the transaction."

"Other than very minor oil stains surrounding long ago removed water pumps, fuel containers, and a crude oil container, I am not aware of any other items. Alfalfa growers typically use tiles to drain fields, fertilizers and other substances to enhance plant growth and removal of pest. Such tiles may or may not be on a hazardous list; however, the ranch has not had any farming operations since late 1999 and there was no storage of any chemicals, to my knowledge on the property at the time of transfer."

**F. Mojave Water Agency
Christy Huiner, Data Analyst
Apple Valley CA**

04-29-09 – Christy Huiner, Data Analyst, Water Resources Department, of the Mojave Water Agency provided information from the agency's databases and other sources which included a locator map of wells (production, active and historic) within a quarter mile radius of the APNs address in this report. She also provided a list of state well numbers, assessor parcel number of the well, and the datum source used to plot each well. A copy of that locator map and list of State well numbers is included with this report. (Attachment #1)

**G. Southwest Gas Corporation
Kurt Edwards, Supervisor/Engineering
Victorville CA**

04-29-09 – Kurt Edwards, Supervising Engineer for Southwest Gas Corporation provided a Southwest Gas facility map which details the structures in the project area. The map shows 16" Southwest Gas steel lines running north along the west side of Harper Lake Road to Hoffman Road, then west on Hoffman Road. (map attached to this report). Approximately 500' from the intersection of Harper Lake Road and Lockhart road, on the west side of Harper Lake Road is a Southwest Gas regulating station. A copy of the Southwest Gas Map is included with this report. No information was provided by Southwest Gas relating to storage or spill of hazardous substances. (Attachment #5).

**H. Lahontan Regional Water Quality Control Board
Region 6 – San Bernardino County
Geo Tracker Information Data Base**

05-11-09 – A check of the data base of the Lahontan Regional Water Quality Board indicated Case reports in the Hinkley CA area as follows:

Location	Status Date	Status	Substance
Desert View Dairy 37601 Mountain View Road Hinkley CA 92347	Cleanup Program Site 08-15-01 01-02-65	Open as of 06-30-02	Potential contaminant of concern - Nitrates
Pacific Gas & Electric 37501 Mountain View Road Hinkley CA 92347	Cleanup Program Site Reported 01-01-71 06-01-01 – cleanup & abatement order; 03-24-03 – Pump & treat groundwater	Open remediation as of 07-27-04.	Interim Plume Containment & Heavalent Chromium Treatment
Lenwood Hinkley Landfill 4 mi new of Barstow Land Disposal Site	Remediation/groundwater monitoring well Quarterly monitoring report	Open as of 01-01-65	No contaminant specified

Location	Status Date	Status	Substance
**SEGS 8, SEGS 9 43880 Harper Lake Rd Hinkley CA 92347	LUST Cleanup Site Leak reported 04-30-07 contamination of soil – 08-07-08 soil & water investigation - 2 1000 gal UST's abandoned in place	Open site assessment as of 05-22-07	Potential contaminants of concern – Waste Oil / Motor Hydraulic/ Lubricating
Land Disposal Site Three Surface Impoundments 36863 Fairview Rd. Hinkley CA 92347 (Hinkley Compressor Stn / Pacific Gas & Electric / Three surface impoundments)	Cleanup Open as of 01-01-65 – Remediation / groundwater monitoring well	Open as of 01-01-65	No Potential contaminants of concerned specified
Whiting Brothers Service Station 26487 Hwy 58 Hinkley CA 92347	Open 01-15-02 – Potential media affected: Aquifer used for drinking water supply	Open – Verification monitoring as of 02-05-09	Potential contaminants of concern: Benzene, diesel, fuel oxygenates, gasoline, other chlorinated hydrocarbons, Toulene, Xylene

**** NOTE:** Regarding the leaking UST at SEGS VIII and IX: An engineering report prepared in August of 2008, by Ocean Blue Engineers, of Los Angeles CA recommends that the County of San Bernardino Fire Department issue a closure certificate for the two in-place abandoned 1,000 gallon underground storage tanks at SEGS VIII and SEGS IX, located at 43880 Harper Lake Road, Hinkley CA 92347.

The SEGS VIII and IX listing is located just north of Section 30. SEGS VIII & IX is located in the down gradient direction from the site. Enviro Chek found no reason to suspect that the Project site has been adversely impacted from off-site migration of contaminants from the surrounding area.

VI. FINDINGS & CONCLUSIONS:


A Phase I Environmental Site Assessment was performed in accordance with generally and currently accepted environmental engineering principles and practices. On the date of the physical / visual inspection of the property, several areas of soil discoloration were located, which could possibly indicate some level of ground contamination, possibly from petroleum products. Those areas were photographed.

Two previously conducted environmental reports, were located in San Bernardino County Fire Department files. One of the reports, "The Bradley Report," dated February 13, 1996, was also referenced in the Altec Phase I Investigation conducted in 2004. In the Bradley Report there is indication that UST's at 41800 Harper Lake Road (The General Store), were removed, "and results of a soil and gas survey completed in the UST vicinity revealed it is unlikely that a large volume of hydrocarbon impacted soil exists onsite." The report further indicates: "The eight remaining 400 gallon diesel AST's onsite used to pump the irrigation wells have limited soil staining and is limited to less than 2 feet below the ground surface, and is not considered to be a problematic environmental issue. Those tanks have subsequently been removed. There are no UST's remaining on that property (41800 Harper Lake Road). There is no evidence in the area where those tanks were located of significant spill or contamination.

It is concluded from the investigation, coupled with interviews with regulatory agencies concerning the property, and checks of standard state and federal databases, that there is possibly some minor surface ground staining at the above sites. There is no indication that a significant release or spill has occurred on any of the properties listed. No areas of serious environmental concern were noted at the adjacent properties or on the subject property.

The findings in this report are a professional opinion, formulated from the information obtained during the investigation and interview, and should not be considered a definite statement that hazardous contamination is or is not present at the site. Enviro Chek conclusions and recommendations are based on information obtained at this time from visual inspections of the site, interviews with former tenants of the site, and relevant federal, state and local agencies. This report was compiled in conformance with the scope and limitations of the American Society for Testing and Materials (ASTM) Standard E 1527-05. The services performed by Enviro Chek have been conducted in a manner consistent with the level of care and skill ordinarily exercised by members of our profession currently practicing under similar conditions in the Southern California area. No other warranty, expressed or implied, is made.

This report was prepared for Mojave Solar Project. Enviro Chek consents to the release of this report to third parties at the direction of Mojave Solar (Abengoa); however, Enviro Chek makes no warranty of any kind to third parties and cannot be held liable for any reliance by third parties upon the information contained herein.

Report Submitted by: 
Shirley R. Hibbetts
R.E.A. #06404 / Expires 06-30-10




VII


METRO SCAN VICINITY MAPS

Page No. 1715c. P.M. 42/44-53

Assessor's Map
Book 0490 Page 12
San Bernardino County



E.1/2 Sec.32 & Sec.33, T.11N., R.4W., S.B.B.&M.



SEP 07 2005

01568


Assessor's Map
Book 0490 Page 16
San Bernardino County

June 2005

11/2 200.07, 1.11.11.4 II., J.D.D.G.M.



1. JAMES MONROE MINOTTA CHASE




SEP 07 2005

Assessor's Map
Book 0490 Page 17
San Bernardino County

5002 2005

Tax Rate Area
56103

U.S. MAIL PERMIT NO. 1000 NEW YORK, N.Y.



ROAD

~~HAARP LATE~~

25947

SEP 07 2005

Page 3

Assessor's Map
Book 0490 Page 13
San Bernardino County

June 2005

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

OWNERSHIP INFORMATION

Parcel Number : 0490 121 42 0000 Sequence :
Parcel Type : Real Property
Owner : Solucar Inc
CoOwner :
Site Address : 41800 Harper Lake Rd Hinkley 92347
Mail Address : 1806 Orange Tree Ln #C Redlands Ca 92374
Owner Phone :

SALES AND LOAN INFORMATION

Transferred : 05/10/2007 Loan Amount : \$13,500,000
Document # : 284167 Multi-parcel Lender : Private Individua
Sale Price : \$30,000,000 Full Loan Type : Seller
Deed Type : Grant Deed Interest Rate : Fixed
% Owned : 100 Vesting Type : Corporation

ASSESSMENT AND TAX INFORMATION

Land : \$386,706 Exempt Type :
Structure : \$202,900 Exempt Amount :
Other : Tax Rate Area : 056053
Total : \$589,606 08-09 Taxes : \$6,865.22
% Improved : 34

PROPERTY DESCRIPTION

Easement :
Map Grid :
Census : Tract:116.00 Block:2
Land Use : 0712 Agr, Field Crops
Prop Type : AGRICULTURAL
Legal : PARCEL MAP 12194 PARCEL 4 EX PTN
: LYING WITHIN NE 1/4 NW 1/4 SEC 30
: TP 11N R 4W
Tract Number :

Profile-Page 1 of 2

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

Parcel Number :0490 121 42 0000

PROPERTY CHARACTERISTICS

Total Rooms :	1st Floor SqFt :
Bedrooms :	2nd Floor SqFt :
Bathrooms :	3rd Floor SqFt :
Family Rooms :	Total Living SqFt :
Fireplace :	Room Additional SqFt :
Heating :	Building Total SqFt :
Cooling :	Patio/Porch SqFt :
Pool :	Basement SqFt :
Spa :	Garage SqFt :
Year Built :	Carport SqFt :
EffYearBuilt :	Parking Deck SqFt :
Stories :	Garage Spaces :
Units :	Lot Acres :588.42
Roof Type :	Lot SqFt :25,631,575
Construction :	Lot Size :
Waterfront :	
Ground Cover :	
Topography :Level	UTILITIES
View Quality :None	Electric Service :Overhead
View Type :	Gas Service :
Street Access :Pub-pvd	Water Service :
Nuisance :	Sewer Service :None
Quality Class :	
Building Class :	
Building Shape :	
Building Type :	
Bldg Quality :	
Building Use :	
Garage :	

Special Improvements

- 1.
- 2.
- 3.

Profile-Page 2 of 2

Information compiled from various sources. Real Estate Solutions makes no representations or warranties as to the accuracy or completeness of information contained in this report.

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

OWNERSHIP INFORMATION

Parcel Number :0490 131 06 0000 Sequence :1 SFR
Parcel Type :Real Property
Owner :Solucar Inc
CoOwner :
Site Address :Lockhart Rd Hinkley 92347
Mail Address :1806 Orange Tree Ln #C Redlands Ca 92374
Owner Phone :

SALES AND LOAN INFORMATION

Transferred :05/10/2007 Loan Amount :\$13,500,000
Document # :284167 Multi-parcel Lender :Private Individua
Sale Price :\$30,000,000 Full Loan Type :Seller
Deed Type :Grant Deed Interest Rate :Fixed
% Owned :100 Vesting Type :Corporation

ASSESSMENT AND TAX INFORMATION

Land :\$113,386 Exempt Type :
Structure :\$71,612 Exempt Amount :
Other : Tax Rate Area :056103
Total :\$184,998 08-09 Taxes :\$2,146.68
% Improved :39

PROPERTY DESCRIPTION

Easement :
Map Grid :
Census :Tract: Block:
Land Use :0712 Agr, Field Crops
Prop Type :AGRICULTURAL
Legal :SE 1/4 SEC 29 TP 11N R 4W 160 AC
:
:
Tract Number :

Profile-Page 1 of 2

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

Parcel Number :0490 131 06 0000

PROPERTY CHARACTERISTICS

Total Rooms	:4	1st Floor SqFt	:752
Bedrooms	:2	2nd Floor SqFt	:
Bathrooms	:1.00	3rd Floor SqFt	:
Family Rooms	:	Total Living SqFt	:
Fireplace	:	Room Additional SqFt	:
Heating	:Flr\wall	Building Total SqFt	:752
Cooling	:None	Patio/Porch SqFt	:
Pool	:	Basement SqFt	:
Spa	:	Garage SqFt	:
Year Built	:1950	Carport SqFt	:
EffYearBuilt	:1950	Parking Deck SqFt	:
Stories	:1	Garage Spaces	:
Units	:	Lot Acres	:160.00
Roof Type	:Other	Lot SqFt	:6,969,600
Construction	:	Lot Size	:
Waterfront	:		
Ground Cover	:		
Topography	:Level		
View Quality	:Average		
View Type	:		
Street Access	:Pub-unpvd		
Nuisance	:		
Quality Class	:D045B		
Building Class	:4.5		
Building Shape	:L-shape		
Building Type	:Frame		
Bldg Quality	:		
Building Use	:		
Garage	:		

UTILITIES

Electric Service	:None
Gas Service	:None
Water Service	:
Sewer Service	:None

Special Improvements

- 1.
- 2.
- 3.

Profile-Page 2 of 2

Information compiled from various sources. Real Estate Solutions makes no representations or warranties as to the accuracy or completeness of information contained in this report.

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

OWNERSHIP INFORMATION

Parcel Number :0490 131 06 0000 Sequence :2 SFR
Parcel Type :Real Property
Owner :Solucar Inc
CoOwner :
Site Address :Lockhart Rd Hinkley 92347
Mail Address :1806 Orange Tree Ln #C Redlands Ca 92374
Owner Phone :

SALES AND LOAN INFORMATION

Transferred :05/10/2007 Loan Amount :\$13,500,000
Document # :284167 Multi-parcel Lender :Private Individua
Sale Price :\$30,000,000 Full Loan Type :Seller
Deed Type :Grant Deed Interest Rate :Fixed
% Owned :100 Vesting Type :Corporation

ASSESSMENT AND TAX INFORMATION

Land :\$113,386 Exempt Type :
Structure :\$71,612 Exempt Amount :
Other : Tax Rate Area :056103
Total :\$184,998 08-09 Taxes :\$2,146.68
% Improved :39

PROPERTY DESCRIPTION

Easement :
Map Grid :
Census :Tract: Block:
Land Use :0712 Agr,Field Crops
Prop Type :AGRICULTURAL
Legal :SE 1/4 SEC 29 TP 11N R 4W 160 AC
:
:
Tract Number :

Profile-Page 1 of 2

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

Parcel Number :0490 131 06 0000

PROPERTY CHARACTERISTICS

Total Rooms	:4	1st Floor SqFt	:948
Bedrooms	:2	2nd Floor SqFt	:
Bathrooms	:1.00	3rd Floor SqFt	:
Family Rooms	:	Total Living SqFt	:
Fireplace	:	Room Additional SqFt	:
Heating	:Flr\wall	Building Total SqFt	:948
Cooling	:None	Patio/Porch SqFt	:
Pool	:	Basement SqFt	:
Spa	:	Garage SqFt	:
Year Built	:1952	Carport SqFt	:
EffYearBuilt	:1952	Parking Deck SqFt	:
Stories	:1	Garage Spaces	:
Units	:	Lot Acres	:160.00
Roof Type	:	Lot SqFt	:6,969,600
Construction	:	Lot Size	:
Waterfront	:		
Ground Cover	:		
Topography	:Level	UTILITIES	
View Quality	:Average	Electric Service	:None
View Type	:	Gas Service	:None
Street Access	:Pub-unpvd	Water Service	:
Nuisance	:	Sewer Service	:None
Quality Class	:D045B		
Building Class	:4.5		
Building Shape	:L-shape		
Building Type	:Frame		
Bldg Quality	:		
Building Use	:		
Garage	:		

Special Improvements

- 1.
- 2.
- 3.

Profile-Page 2 of 2

Information compiled from various sources. Real Estate Solutions makes no representations or warranties as to the accuracy or completeness of information contained in this report.

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

OWNERSHIP INFORMATION

Parcel Number : 0490 131 07 0000 Sequence :
Parcel Type : Real Property
Owner : Solucar Inc
CoOwner :
Site Address : 48084 Hoffman Rd Hinkley 92347
Mail Address : 1806 Orange Tree Ln #C Redlands Ca 92374
Owner Phone :

SALES AND LOAN INFORMATION

Transferred : 05/10/2007 Loan Amount : \$13,500,000
Document # : 284167 Multi-parcel Lender : Private Individua
Sale Price : \$30,000,000 Full Loan Type : Seller
Deed Type : Grant Deed Interest Rate : Fixed
% Owned : 100 Vesting Type : Corporation

ASSESSMENT AND TAX INFORMATION

Land : \$113,386 Exempt Type :
Structure : \$11,340 Exempt Amount :
Other : Tax Rate Area : 056103
Total : \$124,726 08-09 Taxes : \$1,489.60
% Improved : 9

PROPERTY DESCRIPTION

Easement :
Map Grid :
Census : Tract: 119.00 Block:
Land Use : 0712 Agr, Field Crops
Prop Type : AGRICULTURAL
Legal : SW 1/4 SEC 29 TP 11N R 4W 160 AC
:
:
Tract Number :

Profile-Page 1 of 2

= M E T R O S C A N P R O P E R T Y P R O F I L E =
San Bernardino (CA)

Parcel Number :0490 131 07 0000

PROPERTY CHARACTERISTICS

Total Rooms :	1st Floor SqFt :
Bedrooms :	2nd Floor SqFt :
Bathrooms :	3rd Floor SqFt :
Family Rooms :	Total Living SqFt :
Fireplace :	Room Additional SqFt :
Heating :	Building Total SqFt :
Cooling :	Patio/Porch SqFt :
Pool :	Basement SqFt :
Spa :	Garage SqFt :
Year Built :	Carport SqFt :
EffYearBuilt :	Parking Deck SqFt :
Stories :	Garage Spaces :
Units :	Lot Acres :160.00
Roof Type :	Lot SqFt :6,969,600
Construction :	Lot Size :
Waterfront :	
Ground Cover :	
Topography :Level	UTILITIES
View Quality :Average	Electric Service :Overhead
View Type :	Gas Service :None
Street Access :Pub-unpvd	Water Service :Public
Nuisance :	Sewer Service :None
Quality Class :	
Building Class :	
Building Shape :	
Building Type :	
Bldg Quality :	
Building Use :	
Garage :	

Special Improvements

- 1.
- 2.
- 3.

Profile-Page 2 of 2

Information compiled from various sources. Real Estate Solutions makes no representations or warranties as to the accuracy or completeness of information contained in this report.

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

OWNERSHIP INFORMATION

Parcel Number : 0490 131 08 0000 Sequence :
Parcel Type : Real Property
Owner : Solucar Inc
CoOwner :
Site Address : 48084 Hoffman Rd Hinkley 92347
Mail Address : 1806 Orange Tree Ln #C Redlands Ca 92374
Owner Phone :

SALES AND LOAN INFORMATION

Transferred : 05/10/2007 Loan Amount : \$13,500,000
Document # : 284167 Multi-parcel Lender : Private Individua
Sale Price : \$30,000,000 Full Loan Type : Seller
Deed Type : Grant Deed Interest Rate : Fixed
% Owned : 100 Vesting Type : Corporation

ASSESSMENT AND TAX INFORMATION

Land : \$56,693 Exempt Type :
Structure : Exempt Amount :
Other : Tax Rate Area : 056103
Total : \$56,693 08-09 Taxes : \$684.13
% Improved :

PROPERTY DESCRIPTION

Easement :
Map Grid :
Census : Tract:119.00 Block:
Land Use : 0000 Vac,Vacant
Prop Type : AGRICULTURAL
Legal : W 1/2 NW 1/4 SEC 29 TP 11N R 4W 80
 : AC
 :
Tract Number :

Profile-Page 1 of 2

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

Parcel Number :0490 131 08 0000

PROPERTY CHARACTERISTICS

Total Rooms :	1st Floor SqFt :
Bedrooms :	2nd Floor SqFt :
Bathrooms :	3rd Floor SqFt :
Family Rooms :	Total Living SqFt :
Fireplace :	Room Additional SqFt :
Heating :	Building Total SqFt :
Cooling :	Patio/Porch SqFt :
Pool :	Basement SqFt :
Spa :	Garage SqFt :
Year Built :	Carport SqFt :
EffYearBuilt :	Parking Deck SqFt :
Stories :	Garage Spaces :
Units :	Lot Acres :80.00
Roof Type :	Lot SqFt :3,484,800
Construction :	Lot Size :
Waterfront :	
Ground Cover :	
Topography :Level	UTILITIES
View Quality :Average	Electric Service :Overhead
View Type :	Gas Service :None
Street Access :Pub-pvd	Water Service :Public
Nuisance :	Sewer Service :None
Quality Class :	
Building Class:	
Building Shape:	
Building Type :	
Bldg Quality :	
Building Use :	
Garage :	

Special Improvements

- 1.
- 2.
- 3.

Profile-Page 2 of 2

Information compiled from various sources. Real Estate Solutions makes no representations or warranties as to the accuracy or completeness of information contained in this report.

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

OWNERSHIP INFORMATION

Parcel Number : 0490 131 11 0000 Sequence :
Parcel Type : Real Property
Owner : Abengoa Solar Inc
CoOwner :
Site Address : *no Site Address*
Mail Address : 2030 Addison St #420 Berkeley Ca 94704
Owner Phone :

SALES AND LOAN INFORMATION

Transferred : 11/26/2008 Loan Amount :
Document # : 529392 Lender :
Sale Price : \$80,000 Full Loan Type :
Deed Type : Grant Deed Interest Rate :
% Owned : 100 Vesting Type : Corporation

ASSESSMENT AND TAX INFORMATION

Land : \$11,582 Exempt Type :
Structure : Exempt Amount :
Other : Tax Rate Area : 056103
Total : \$11,582 08-09 Taxes : \$141.58
% Improved :

PROPERTY DESCRIPTION

Easement :
Map Grid :
Census : Tract: Block:
Land Use : 0000 Vac, Vacant
Prop Type : SINGLE FAMILY RESIDENTIAL
Legal : NW 1/4 SW 1/4 SEC 28 TP 11N R 4W 40
 : AC
 :
Tract Number :

Profile-Page 1 of 2

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

Parcel Number :0490 131 11 0000

PROPERTY CHARACTERISTICS

Total Rooms :	1st Floor SqFt :
Bedrooms :	2nd Floor SqFt :
Bathrooms :	3rd Floor SqFt :
Family Rooms :	Total Living SqFt :
Fireplace :	Room Additional SqFt :
Heating :	Building Total SqFt :
Cooling :	Patio/Porch SqFt :
Pool :	Basement SqFt :
Spa :	Garage SqFt :
Year Built :	Carport SqFt :
EffYearBuilt :	Parking Deck SqFt :
Stories :	Garage Spaces :
Units :	Lot Acres :40.00
Roof Type :	Lot SqFt :1,742,400
Construction :	Lot Size :
Waterfront :	
Ground Cover :	
Topography :Level	UTILITIES
View Quality :Fair	Electric Service :None
View Type :	Gas Service :None
Street Access :Priv-unpvd	Water Service :
Nuisance :	Sewer Service :None
Quality Class :	
Building Class :	
Building Shape :	
Building Type :	
Bldg Quality :	
Building Use :	
Garage :	

Special Improvements

- 1.
- 2.
- 3.

Profile-Page 2 of 2

Information compiled from various sources. Real Estate Solutions makes no representations or warranties as to the accuracy or completeness of information contained in this report.

- METROSCAN PROPERTY PROFILE -
San Bernardino (CA)

OWNERSHIP INFORMATION

Parcel Number :0490 131 12 0000 Sequence :1 SFR
Parcel Type :Real Property
Owner :Abengoa Solar Inc
CoOwner :
Site Address :16198 Lockhart Rd Hinkley 92347
Mail Address :13911 Park Ave #206 Victorville Ca 92392
Owner Phone :760-962-9200

SALES AND LOAN INFORMATION

Transferred :07/10/2008 Loan Amount :
Document # :313484 Multi-parcel Lender :
Sale Price :\$300,000 Full Loan Type :
Deed Type :Grant Deed Interest Rate :
% Owned :100 Vesting Type :Corporation

ASSESSMENT AND TAX INFORMATION

Land :\$13,789 Exempt Type :
Structure :\$37,923 Exempt Amount :
Other : Tax Rate Area :056103
Total :\$51,712 08-09 Taxes :\$672.01
% Improved :73

PROPERTY DESCRIPTION

Easement :
Map Grid :
Census :Tract:119.00 Block:
Land Use :0510 Res,Single Family Residence
Prop Type :SINGLE FAMILY RESIDENTIAL
Legal :SW 1/4 SW 1/4 SEC 28 TP 11N R 4W 40
:AC
:
Tract Number :

Profile-Page 1 of 2

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

Parcel Number :0490 131 12 0000

PROPERTY CHARACTERISTICS

Total Rooms	:6	1st Floor SqFt	:1,472
Bedrooms	:3	2nd Floor SqFt	:
Bathrooms	:2.00	3rd Floor SqFt	:
Family Rooms	:	Total Living SqFt	:
Fireplace	:1	Room Additional SqFt	:
Heating	:Central	Building Total SqFt	:1,472
Cooling	:Evap-noncent	Patio/Porch SqFt	:
Pool	:	Basement SqFt	:
Spa	:	Garage SqFt	:488
Year Built	:1956	Carport SqFt	:
EffYearBuilt	:1956	Parking Deck SqFt	:
Stories	:1	Garage Spaces	:2
Units	:	Lot Acres	:40.00
Roof Type	:Comp Shingle	Lot SqFt	:1,742,400
Construction	:	Lot Size	:
Waterfront	:		
Ground Cover	:Poor		
Topography	:Level		
View Quality	:None		
View Type	:		
Street Access	:		
Nuisance	:		
Quality Class	:D040A		
Building Class	:4.0		
Building Shape	:Rectangle		
Building Type	:Frame		
Bldg Quality	:		
Building Use	:		
Garage	:DD4 Detached		

UTILITIES

Electric Service	:None
Gas Service	:None
Water Service	:
Sewer Service	:None

Special Improvements

- 1.
- 2.
- 3.

Profile-Page 2 of 2

Information compiled from various sources. Real Estate Solutions makes no representations or warranties as to the accuracy or completeness of information contained in this report.

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

OWNERSHIP INFORMATION

Parcel Number :0490 131 13 0000 Sequence :
Parcel Type :Real Property
Owner :Lampkin Larry T
CoOwner :Hernandez H V
Site Address :*no Site Address*
Mail Address :13823 Almetz St Sylmar Ca 91342
Owner Phone :

SALES AND LOAN INFORMATION

Transferred : Loan Amount :
Document # : Lender :
Sale Price : Loan Type :
Deed Type : Interest Rate :
% Owned : Vesting Type :

ASSESSMENT AND TAX INFORMATION

Land :\$2,790 Exempt Type :
Structure : Exempt Amount :
Other : Tax Rate Area :056103
Total :\$2,790 08-09 Taxes :\$35.84
% Improved :

PROPERTY DESCRIPTION

Easement :
Map Grid :
Census :Tract: Block:
Land Use :0000 Vac,Vacant
Prop Type :SINGLE FAMILY RESIDENTIAL
Legal :E 1/2 SE 1/4 SW 1/4 SEC 28 TP 11N R
 :4W EX MNL RTS RESERVATION OF RECORD
 :
Tract Number :

Profile-Page 1 of 2

= M E T R O S C A N P R O P E R T Y P R O F I L E =
San Bernardino (CA)

Parcel Number :0490 131 13 0000

PROPERTY CHARACTERISTICS

Total Rooms :	1st Floor SqFt :
Bedrooms :	2nd Floor SqFt :
Bathrooms :	3rd Floor SqFt :
Family Rooms :	Total Living SqFt :
Fireplace :	Room Additional SqFt :
Heating :	Building Total SqFt :
Cooling :	Patio/Porch SqFt :
Pool :	Basement SqFt :
Spa :	Garage SqFt :
Year Built :	Carport SqFt :
EffYearBuilt :	Parking Deck SqFt :
Stories :	Garage Spaces :
Units :	Lot Acres :20.00
Roof Type :	Lot SqFt :871,200
Construction :	Lot Size :
Waterfront :	
Ground Cover :	
Topography :Level	UTILITIES
View Quality :Average	Electric Service :Overhead
View Type :	Gas Service :None
Street Access :Pub-unpvd	Water Service :
Nuisance :	Sewer Service :None
Quality Class :	
Building Class :	
Building Shape :	
Building Type :	
Bldg Quality :	
Building Use :	
Garage :	

Special Improvements

- 1.
- 2.
- 3.

Profile-Page 2 of 2

Information compiled from various sources. Real Estate Solutions makes no representations or warranties as to the accuracy or completeness of information contained in this report.

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

OWNERSHIP INFORMATION

Parcel Number : 0490 131 15 0000 Sequence :
Parcel Type : Real Property
Owner : Abengoa Solar Inc
CoOwner :
Site Address : *no Site Address*
Mail Address : 13911 Park Ave #206 Victorville Ca 92392
Owner Phone : 760-962-9200

SALES AND LOAN INFORMATION

Transferred : 07/10/2008 Loan Amount :
Document # : 313484 Multi-parcel Lender :
Sale Price : \$300,000 Full Loan Type :
Deed Type : Grant Deed Interest Rate :
% Owned : 100 Vesting Type : Corporation

ASSESSMENT AND TAX INFORMATION

Land : \$8,617 Exempt Type :
Structure : Exempt Amount :
Other : Tax Rate Area : 056103
Total : \$8,617 08-09 Taxes : \$105.92
% Improved :

PROPERTY DESCRIPTION

Easement :
Map Grid :
Census : Tract: Block:
Land Use : 0000 Vac, Vacant
Prop Type : SINGLE FAMILY RESIDENTIAL
Legal : W 1/2 SE 1/4 SW 1/4 SEC 28 TP 11N R
 : 4W EX MNL RTS RESERVATION OF RECORD
 :
Tract Number :

Profile-Page 1 of 2

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

Parcel Number :0490 131 15 0000

PROPERTY CHARACTERISTICS

Total Rooms :	1st Floor SqFt :
Bedrooms :	2nd Floor SqFt :
Bathrooms :	3rd Floor SqFt :
Family Rooms :	Total Living SqFt :
Fireplace :	Room Additional SqFt :
Heating :	Building Total SqFt :
Cooling :	Patio/Porch SqFt :
Pool :	Basement SqFt :
Spa :	Garage SqFt :
Year Built :	Carport SqFt :
EffYearBuilt :	Parking Deck SqFt :
Stories :	Garage Spaces :
Units :	Lot Acres :20.00
Roof Type :	Lot SqFt :871,200
Construction :	Lot Size :
Waterfront :	
Ground Cover :	
Topography :	UTILITIES
View Quality :	Electric Service :
View Type :	Gas Service :
Street Access :	Water Service :
Nuisance :	Sewer Service :
Quality Class :	
Building Class :	
Building Shape :	
Building Type :	
Bldg Quality :	
Building Use :	
Garage :	

Special Improvements

- 1.
- 2.
- 3.

Profile-Page 2 of 2

Information compiled from various sources. Real Estate Solutions makes no representations or warranties as to the accuracy or completeness of information contained in this report.

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

OWNERSHIP INFORMATION

Parcel Number : 0490 131 16 0000 Sequence :
Parcel Type : Real Property
Owner : Abengoa Solar Inc
CoOwner :
Site Address : *no Site Address*
Mail Address : 13911 Park Ave #206 Victorville Ca 92392
Owner Phone : 760-962-9200

SALES AND LOAN INFORMATION

Transferred : 07/10/2008 Loan Amount :
Document # : 313484 Multi-parcel Lender :
Sale Price : \$300,000 Full Loan Type :
Deed Type : Grant Deed Interest Rate :
% Owned : 100 Vesting Type : Corporation

ASSESSMENT AND TAX INFORMATION

Land : \$13,789 Exempt Type :
Structure : Exempt Amount :
Other : Tax Rate Area : 056103
Total : \$13,789 08-09 Taxes : \$168.13
% Improved :

PROPERTY DESCRIPTION

Easement :
Map Grid :
Census : Tract: Block:
Land Use : 0000 Vac, Vacant
Prop Type : SINGLE FAMILY RESIDENTIAL
Legal : NE 1/4 SW 1/4 SEC 28 TP 11N R 4W EX
 : MNL RTS RESERVATION OF RECORD
 :
Tract Number :

Profile-Page 1 of 2

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

Parcel Number : 0490 131 16 0000

PROPERTY CHARACTERISTICS

Total Rooms :	1st Floor SqFt :
Bedrooms :	2nd Floor SqFt :
Bathrooms :	3rd Floor SqFt :
Family Rooms :	Total Living SqFt :
Fireplace :	Room Additional SqFt :
Heating :	Building Total SqFt :
Cooling :	Patio/Porch SqFt :
Pool :	Basement SqFt :
Spa :	Garage SqFt :
Year Built :	Carport SqFt :
EffYearBuilt :	Parking Deck SqFt :
Stories :	Garage Spaces :
Units :	Lot Acres : 40.00
Roof Type :	Lot SqFt : 1,742,400
Construction :	Lot Size :
Waterfront :	
Ground Cover :	
Topography :	UTILITIES
View Quality :	Electric Service :
View Type :	Gas Service :
Street Access :	Water Service :
Nuisance :	Sewer Service :
Quality Class :	
Building Class :	
Building Shape :	
Building Type :	
Bldg Quality :	
Building Use :	
Garage :	

Special Improvements

- 1.
- 2.
- 3.

Profile-Page 2 of 2

Information compiled from various sources. Real Estate Solutions makes no representations or warranties as to the accuracy or completeness of information contained in this report.

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

OWNERSHIP INFORMATION

Parcel Number : 0490 161 08 0000 Sequence :
Parcel Type : Real Property
Owner : Desert View Dairy
CoOwner :
Site Address : *no Site Address*
Mail Address : 37501 Mountain View Rd Hinkley Ca 92347
Owner Phone :

SALES AND LOAN INFORMATION

Transferred : 02/18/2004 Loan Amount :
Document # : 115569 Lender :
Sale Price : Loan Type :
Deed Type : Interest Rate :
% Owned : 100 Vesting Type :

ASSESSMENT AND TAX INFORMATION

Land : \$187,220 Exempt Type :
Structure : Exempt Amount :
Other : Tax Rate Area : 056103
Total : \$187,220 08-09 Taxes : \$2,253.99
% Improved :

PROPERTY DESCRIPTION

Easement :
Map Grid :
Census : Tract: Block:
Land Use : 0712 Agr, Field Crops
Prop Type : AGRICULTURAL
Legal : W 1/2 NE 1/4 SEC 32 TP 11N R 4W 80
 : AC
 :
Tract Number :

Profile-Page 1 of 2

Information compiled from various sources. Real Estate Solutions makes no representations or warranties as to the accuracy or completeness of information contained in this report.

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

Parcel Number :0490 161 08 0000

PROPERTY CHARACTERISTICS

Total Rooms :	1st Floor SqFt :
Bedrooms :	2nd Floor SqFt :
Bathrooms :	3rd Floor SqFt :
Family Rooms :	Total Living SqFt :
Fireplace :	Room Additional SqFt :
Heating :	Building Total SqFt :
Cooling :	Patio/Porch SqFt :
Pool :	Basement SqFt :
Spa :	Garage SqFt :
Year Built :	Carport SqFt :
EffYearBuilt :	Parking Deck SqFt :
Stories :	Garage Spaces :
Units :	Lot Acres :80.00
Roof Type :	Lot SqFt :3,484,800
Construction :	Lot Size :
Waterfront :	
Ground Cover :	
Topography :	UTILITIES
View Quality :	Electric Service :
View Type :	Gas Service :
Street Access :	Water Service :
Nuisance :	Sewer Service :
Quality Class :	
Building Class :	
Building Shape :	
Building Type :	
Bldg Quality :	
Building Use :	
Garage :	

Special Improvements

- 1.
- 2.
- 3.

Profile-Page 2 of 2

Information compiled from various sources. Real Estate Solutions makes no representations or warranties as to the accuracy or completeness of information contained in this report.

" METROSCAN PROPERTY PROFILE "
San Bernardino (CA)

OWNERSHIP INFORMATION

Parcel Number : 0490 161 09 0000 Sequence :
Parcel Type : Real Property
Owner : Desert View Dairy
CoOwner :
Site Address : *no Site Address*
Mail Address : 37501 Mountain View Rd Hinkley Ca 92347
Owner Phone :

SALES AND LOAN INFORMATION

Transferred : 02/18/2004 Loan Amount :
Document # : 115569 Lender :
Sale Price : Loan Type :
Deed Type : Interest Rate :
% Owned : 100 Vesting Type :

ASSESSMENT AND TAX INFORMATION

Land : \$187,220 Exempt Type :
Structure : \$35,104 Exempt Amount :
Other : Tax Rate Area : 056103
Total : \$222,324 08-09 Taxes : \$2,636.68
% Improved : 16

PROPERTY DESCRIPTION

Easement :
Map Grid :
Census : Tract: Block:
Land Use : 0712 Agr, Field Crops
Prop Type : AGRICULTURAL
Legal : E 1/2 NE 1/4 SEC 32 TP 11N R 4W 80
 : AC
 :
Tract Number :

Profile-Page 1 of 2

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

Parcel Number : 0490 161 09 0000

PROPERTY CHARACTERISTICS

Total Rooms :	1st Floor SqFt :
Bedrooms :	2nd Floor SqFt :
Bathrooms :	3rd Floor SqFt :
Family Rooms :	Total Living SqFt :
Fireplace :	Room Additional SqFt :
Heating :	Building Total SqFt :
Cooling :	Patio/Porch SqFt :
Pool :	Basement SqFt :
Spa :	Garage SqFt :
Year Built :	Carport SqFt :
EffYearBuilt :	Parking Deck SqFt :
Stories :	Garage Spaces :
Units :	Lot Acres : 80.00
Roof Type :	Lot SqFt : 3,484,800
Construction :	Lot Size :
Waterfront :	
Ground Cover :	
Topography :	UTILITIES
View Quality :	Electric Service :
View Type :	Gas Service :
Street Access :	Water Service :
Nuisance :	Sewer Service :
Quality Class :	
Building Class :	
Building Shape :	
Building Type :	
Bldg Quality :	
Building Use :	
Garage :	

Special Improvements

- 1.
- 2.
- 3.

Profile-Page 2 of 2

Information compiled from various sources. Real Estate Solutions makes no representations or warranties as to the accuracy or completeness of information contained in this report.

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

OWNERSHIP INFORMATION

Parcel Number : 0490 161 10 0000 Sequence :
Parcel Type : Real Property
Owner : Solucar Inc
CoOwner :
Site Address : 48084 Hoffman Rd Hinkley 92347
Mail Address : 1806 Orange Tree Ln #C Redlands Ca 92374
Owner Phone :

SALES AND LOAN INFORMATION

Transferred : 05/10/2007 Loan Amount : \$13,500,000
Document # : 284167 Multi-parcel Lender : Private Individua
Sale Price : \$30,000,000 Full Loan Type : Seller
Deed Type : Grant Deed Interest Rate : Fixed
% Owned : 100 Vesting Type : Corporation

ASSESSMENT AND TAX INFORMATION

Land : \$113,386 Exempt Type :
Structure : \$26,259 Exempt Amount :
Other : Tax Rate Area : 056103
Total : \$139,645 08-09 Taxes : \$1,652.25
% Improved : 19

PROPERTY DESCRIPTION

Easement :
Map Grid :
Census : Tract:119.00 Block:
Land Use : 0712 Agr, Field Crops
Prop Type : AGRICULTURAL
Legal : NW 1/4 SEC 33 TP 11N R 4W 160 AC
:
:
Tract Number :

Profile-Page 1 of 2

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

Parcel Number :0490 161 10 0000

PROPERTY CHARACTERISTICS

Total Rooms :	1st Floor SqFt :
Bedrooms :	2nd Floor SqFt :
Bathrooms :	3rd Floor SqFt :
Family Rooms :	Total Living SqFt :
Fireplace :	Room Additional SqFt :
Heating :	Building Total SqFt :
Cooling :	Patio/Porch SqFt :
Pool :	Basement SqFt :
Spa :	Garage SqFt :
Year Built :	Carport SqFt :
EffYearBuilt :	Parking Deck SqFt :
Stories :	Garage Spaces :
Units :	Lot Acres :160.00
Roof Type :	Lot SqFt :6,969,600
Construction :	Lot Size :
Waterfront :	
Ground Cover :	
Topography :Level	UTILITIES
View Quality :Average	Electric Service :Overhead
View Type :	Gas Service :None
Street Access :Pub-unpvd	Water Service :Public
Nuisance :	Sewer Service :None
Quality Class :	
Building Class :	
Building Shape :	
Building Type :	
Bldg Quality :	
Building Use :	
Garage :	

Special Improvements

- 1.
- 2.
- 3.

Profile-Page 2 of 2

Information compiled from various sources. Real Estate Solutions makes no representations or warranties as to the accuracy or completeness of information contained in this report.

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

OWNERSHIP INFORMATION

Parcel Number : 0490 161 11 0000 Sequence :
Parcel Type : Real Property
Owner : Solucar Inc
CoOwner :
Site Address : County Rd Hinkley 92347
Mail Address : 1806 Orange Tree Ln #C Redlands Ca 92374
Owner Phone :

SALES AND LOAN INFORMATION

Transferred : 05/10/2007 Loan Amount : \$13,500,000
Document # : 284167 Multi-parcel Lender : Private Individua
Sale Price : \$30,000,000 Full Loan Type : Seller
Deed Type : Grant Deed Interest Rate : Fixed
% Owned : 100 Vesting Type : Corporation

ASSESSMENT AND TAX INFORMATION

Land : \$113,386 Exempt Type :
Structure : \$36,998 Exempt Amount :
Other : Tax Rate Area : 056103
Total : \$150,384 08-09 Taxes : \$1,769.33
% Improved : 25

PROPERTY DESCRIPTION

Easement :
Map Grid :
Census : Tract: Block:
Land Use : 0712 Agr, Field Crops
Prop Type : AGRICULTURAL
Legal : NE 1/4 SEC 33 TP 11N R 4W EX MNL
: RTS RESERVATION OF RECORD 160 AC
:
Tract Number :

Profile-Page 1 of 2

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

Parcel Number : 0490 161 11 0000

PROPERTY CHARACTERISTICS

Total Rooms :	1st Floor SqFt :
Bedrooms :	2nd Floor SqFt :
Bathrooms :	3rd Floor SqFt :
Family Rooms :	Total Living SqFt :
Fireplace :	Room Additional SqFt :
Heating :	Building Total SqFt :
Cooling :	Patio/Porch SqFt :
Pool :	Basement SqFt :
Spa :	Garage SqFt :
Year Built :	Carport SqFt :
EffYearBuilt :	Parking Deck SqFt :
Stories :	Garage Spaces :
Units :	Lot Acres : 160.00
Roof Type :	Lot SqFt : 6,969,600
Construction :	Lot Size :
Waterfront :	
Ground Cover :	
Topography : Level	UTILITIES
View Quality : Average	Electric Service : Overhead
View Type :	Gas Service : None
Street Access : Pub-unpvd	Water Service : Public
Nuisance :	Sewer Service : None
Quality Class :	
Building Class :	
Building Shape :	
Building Type :	
Bldg Quality :	
Building Use :	
Garage :	

Special Improvements

- 1.
- 2.
- 3.

Profile-Page 2 of 2

Information compiled from various sources. Real Estate Solutions makes no representations or warranties as to the accuracy or completeness of information contained in this report.

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

OWNERSHIP INFORMATION

Parcel Number : 0490 161 12 0000 Sequence :
Parcel Type : Real Property
Owner : Solucar Inc
CoOwner :
Site Address : 48084 Hoffman Rd Hinkley 92347
Mail Address : 1806 Orange Tree Ln #C Redlands Ca 92374
Owner Phone :

SALES AND LOAN INFORMATION

Transferred : 05/10/2007 Loan Amount : \$13,500,000
Document # : 284167 Multi-parcel Lender : Private Individua
Sale Price : \$30,000,000 Full Loan Type : Seller
Deed Type : Grant Deed Interest Rate : Fixed
% Owned : 100 Vesting Type : Corporation

ASSESSMENT AND TAX INFORMATION

Land : \$113,386 Exempt Type :
Structure : \$19,096 Exempt Amount :
Other : Tax Rate Area : 056103
Total : \$132,482 08-09 Taxes : \$1,574.16
% Improved : 14

PROPERTY DESCRIPTION

Easement :
Map Grid :
Census : Tract:119.00 Block:
Land Use : 0712 Agr, Field Crops
Prop Type : AGRICULTURAL
Legal : SE 1/4 SEC 33 TP 11N R 4W 160 AC EX
 : WATER RIGHTS
 :
Tract Number :

Profile-Page 1 of 2

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

Parcel Number :0490 161 12 0000

PROPERTY CHARACTERISTICS

Total Rooms :	1st Floor SqFt :
Bedrooms :	2nd Floor SqFt :
Bathrooms :	3rd Floor SqFt :
Family Rooms :	Total Living SqFt :
Fireplace :	Room Additional SqFt :
Heating :	Building Total SqFt :
Cooling :	Patio/Porch SqFt :
Pool :	Basement SqFt :
Spa :	Garage SqFt :
Year Built :	Carport SqFt :
EffYearBuilt :	Parking Deck SqFt :
Stories :	Garage Spaces :
Units :	Lot Acres :160.00
Roof Type :	Lot SqFt :6,969,600
Construction :	Lot Size :
Waterfront :	
Ground Cover :	
Topography :Level	UTILITIES
View Quality :Average	Electric Service :Overhead
View Type :	Gas Service :None
Street Access :Pub-unpvd	Water Service :Public
Nuisance :	Sewer Service :None
Quality Class :	
Building Class :	
Building Shape :	
Building Type :	
Bldg Quality :	
Building Use :	
Garage :	

Special Improvements

- 1.
- 2.
- 3.

Profile-Page 2 of 2

Information compiled from various sources. Real Estate Solutions makes no representations or warranties as to the accuracy or completeness of information contained in this report.

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

OWNERSHIP INFORMATION

Parcel Number : 0490 161 13 0000 Sequence :
Parcel Type : Real Property
Owner : Solucar Inc
CoOwner :
Site Address : 48084 Hoffman Rd Hinkley 92347
Mail Address : 1806 Orange Tree Ln #C Redlands Ca 92374
Owner Phone :

SALES AND LOAN INFORMATION

Transferred : 05/10/2007 Loan Amount : \$13,500,000
Document # : 284167 Multi-parcel Lender : Private Individua
Sale Price : \$30,000,000 Full Loan Type : Seller
Deed Type : Grant Deed Interest Rate : Fixed
% Owned : 100 Vesting Type : Corporation

ASSESSMENT AND TAX INFORMATION

Land : \$113,386 Exempt Type :
Structure : Exempt Amount :
Other : Tax Rate Area : 056103
Total : \$113,386 08-09 Taxes : \$1,365.98
% Improved :

PROPERTY DESCRIPTION

Easement :
Map Grid :
Census : Tract: 119.00 Block:
Land Use : 0712 Agr, Field Crops
Prop Type : AGRICULTURAL
Legal : SW 1/4 SEC 33 TP 11N R 4W 160 AC
:
:
Tract Number :

Profile-Page 1 of 2

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

Parcel Number :0490 161 13 0000

PROPERTY CHARACTERISTICS

Total Rooms :	1st Floor SqFt :
Bedrooms :	2nd Floor SqFt :
Bathrooms :	3rd Floor SqFt :
Family Rooms :	Total Living SqFt :
Fireplace :	Room Additional SqFt :
Heating :	Building Total SqFt :
Cooling :	Patio/Porch SqFt :
Pool :	Basement SqFt :
Spa :	Garage SqFt :
Year Built :	Carport SqFt :
EffYearBuilt :	Parking Deck SqFt :
Stories :	Garage Spaces :
Units :	Lot Acres :160.00
Roof Type :	Lot SqFt :6,969,600
Construction :	Lot Size :
Waterfront :	
Ground Cover :	
Topography :Level	UTILITIES
View Quality :Average	Electric Service :Overhead
View Type :	Gas Service :None
Street Access :Pub-unpvd	Water Service :Public
Nuisance :	Sewer Service :None
Quality Class :	
Building Class :	
Building Shape :	
Building Type :	
Bldg Quality :	
Building Use :	
Garage :	

Special Improvements

- 1.
- 2.
- 3.

Profile-Page 2 of 2

Information compiled from various sources. Real Estate Solutions makes no representations or warranties as to the accuracy or completeness of information contained in this report.

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

OWNERSHIP INFORMATION

Parcel Number :0490 171 09 0000 Sequence :
Parcel Type :Real Property
Owner :Abengoa Solar Inc
CoOwner :
Site Address :*no Site Address*
Mail Address :2030 Addison St #420 Berkeley Ca 94704
Owner Phone :

SALES AND LOAN INFORMATION

Transferred :12/11/2008 Loan Amount :
Document # :547638 Lender :
Sale Price :\$77,000 Full Loan Type :
Deed Type :Grant Deed Interest Rate :
% Owned :100 Vesting Type :Corporation

ASSESSMENT AND TAX INFORMATION

Land :\$47,340 Exempt Type :
Structure :\$1,624 Exempt Amount :
Other : Tax Rate Area :056103
Total :\$48,964 08-09 Taxes :\$589.35
% Improved :3

PROPERTY DESCRIPTION

Easement :
Map Grid :
Census :Tract: Block:
Land Use :0002 Vac,Water Well Site
Prop Type :AGRICULTURAL
Legal :NW 1/4 NW 1/4 SEC 32 TP 11N R 4W 40
:AC
:
Tract Number :

Profile-Page 1 of 2

= METROSCAN PROPERTY PROFILE =
San Bernardino (CA)

Parcel Number :0490 171 09 0000

PROPERTY CHARACTERISTICS

Total Rooms :	1st Floor SqFt :
Bedrooms :	2nd Floor SqFt :
Bathrooms :	3rd Floor SqFt :
Family Rooms :	Total Living SqFt :
Fireplace :	Room Additional SqFt :
Heating :	Building Total SqFt :
Cooling :	Patio/Porch SqFt :
Pool :	Basement SqFt :
Spa :	Garage SqFt :
Year Built :	Carport SqFt :
EffYearBuilt :	Parking Deck SqFt :
Stories :	Garage Spaces :
Units :	Lot Acres :40.00
Roof Type :	Lot SqFt :1,742,400
Construction :	Lot Size :
Waterfront :	
Ground Cover :	
Topography :	UTILITIES
View Quality :	Electric Service :
View Type :	Gas Service :
Street Access :	Water Service :
Nuisance :	Sewer Service :
Quality Class :	
Building Class :	
Building Shape :	
Building Type :	
Bldg Quality :	
Building Use :	
Garage :	

Special Improvements

- 1.
- 2.
- 3.

Profile-Page 2 of 2

Information compiled from various sources. Real Estate Solutions makes no representations or warranties as to the accuracy or completeness of information contained in this report.

VIII

PHOTOGRAPHS

EXHIBIT 1

Photo #1 – APN 0490 121 42 – Vent Pipes South Side of General Store Building



Photo #2 – APN 0490 121 42 – Discoloration of soil in front of General Store near canopy.



EXHIBIT 2

Photo #3 - APN # 0490-121-42 – Possible site of 500 gal aviation fuel tank removed 2000 or 2001.



Photo #4 – APN 0490 121 42 – Concrete slab, possible location of AST's that were removed.



EXHIBIT 3

Photo #5 – APN 0490 121 42 – Tanker Trailer parked at southeast corner Harper Lake Rd & Lockhart Rd.



Photo #6 – Staining on ground underneath tanker on May 8, 2008.



Photo #7 – APN 0490 161 09 – Working Well



Photo #8 – Soil stain underneath valve on tank.



Photo #9 – Example of Solid Waste Debris located in various places throughout project area.



Photo #10 – APN 0490 171 09 – Abandoned well & tank east side of Harper Lake Road



Photo #11 – APN 0490 131 06 – Example of electrical transformers located throughout project area.



Photo #12 – UST previously removed from next to General Store, now stored @ Terawatt Construction.



IX

ATTACHMENTS

CONTACTS

Mojave Water Agency Christy Huiner, Data Analyst 22460 Headquarters Drive Apple Valley CA 92307	Nick Grill Terawatt Construction Company PO Box 67 Hinkley CA 92347
Rodney Most 125 May Street Barstow CA 92311	Lahontan Regional Water Quality Control Board Geo Tracker Information Data Base 15428 Civic Drive Ste 100 Victorville CA 92392
San Bernardino County Fire Dept Hazardous Materials Division Elizabeth King, Haz. Mat. Tech. III 620 S. E. Street San Bernardino CA 02415-0413	Southwest Gas Corporation Kurt Edwards Supervisor/Engineering Southern California Division 13471 Mariposa Road Victorville CA 92392-0919
Gary Clark Wilde Road Helendale CA 92342	Henry Orlosky Oak Hills CA




PIR REQUEST Mojave Solar Project Well Proximity

- Production Wells
(.25 Mile Radius)
- Actual and Historic Wells
(.25 Mile Radius)
- Parcel Boundary



**All well locations approximate*



<u>ASSESSOR PARCEL NUMBER</u>	<u>STATE WELL NUMBER</u>	<u>DATUM SOURCE</u>
049017132	11N04W32F02	APN
049011103	11N04W19Q02	MWA
049011104	11N04W19Q03	APN
049011112	11N04W19R04	APN
049012104	11N04W30N04	APN
049012113	11N04W30R02	APN
049012129	11N04W30C02	USGS
049012133	11N04W30H01	APN
049012139	11N04W31A02	APN
049012142	11N04W30D01	MWA
049012142	11N04W30E01	MWA
049012142	11N04W30F01	APN
049012142	11N04W30M01	MWA
049012142	11N04W30N06	MWA
049012142	11N04W30N07	MWA
049012142	11N04W30P02	MWA
049012142	11N04W30B01	MWA
049012142	11N04W30Q03	MWA
049012143	11N04W30C04	APN
049012143	11N04W30G01	APN
049013106	11N04W29J01	MWA
049013106	11N04W29J02	APN
049013106	11N04W29Q02	APN
049013107	11N04W29P01	MWA
049013112	11N04W28N03	APN
049016109	11N04W32A02	MWA
049016110	11N04W33C02	MWA
049016110	11N04W33F01	APN
049016111	11N04W33B01	APN
049016111	11N04W33B02	MWA
049016111	11N04W33G02	APN
049016111	11N04W33G03	APN
049016111	11N04W33G04	MWA
049016112	11N04W33J01	MWA
049016112	11N04W33Q01	USGS
049017109	11N04W32D03	MWA
049017110	11N04W32C04	APN
049017111	11N04W32C02	APN
049017111	11N04W32C05	APN
049017118	11N04W32F06	APN
049017119	11N04W32F03	APN
049017120	11N04W32F07	APN
049017130	11N04W32E01	APN
049017133	11N04W29R02	APN
049022332	11N05W24L01	MWA

<u>ASSESSOR PARCEL NUMBER</u>	<u>STATE WELL NUMBER</u>	<u>DATUM SOURCE</u>
UNKNOWN	11N04W19N01	Quarter/Quarter
UNKNOWN	11N04W19P01	USGS
UNKNOWN	11N04W19P02	Quarter/Quarter
UNKNOWN	11N04W19Q01	Quarter/Quarter
UNKNOWN	11N04W19R01	USGS
UNKNOWN	11N04W19R02	Quarter/Quarter
UNKNOWN	11N04W28N01	USGS
UNKNOWN	11N04W28N02	USGS
UNKNOWN	11N04W28Q01	USGS
UNKNOWN	11N04W28R01	Quarter/Quarter
UNKNOWN	11N04W29D01	Quarter/Quarter
UNKNOWN	11N04W29N01	Quarter/Quarter
UNKNOWN	11N04W29Q01	USGS
UNKNOWN	11N04W29R01	USGS
UNKNOWN	11N04W30C01	USGS
UNKNOWN	11N04W30J01	Quarter/Quarter
UNKNOWN	11N04W30N01	USGS
UNKNOWN	11N04W30N02	USGS
UNKNOWN	11N04W30N03	USGS
UNKNOWN	11N04W30P01	USGS
UNKNOWN	11N04W30Q01	Quarter/Quarter
UNKNOWN	11N04W30Q02	Quarter/Quarter
UNKNOWN	11N04W30R01	USGS
UNKNOWN	11N04W30Z02	USGS
UNKNOWN	11N04W31A01	USGS
UNKNOWN	11N04W31H01	USGS
UNKNOWN	11N04W32A01	USGS
UNKNOWN	11N04W32C01	Quarter/Quarter
UNKNOWN	11N04W32D01	Quarter/Quarter
UNKNOWN	11N04W32D02	USGS
UNKNOWN	11N04W32F01	USGS
UNKNOWN	11N04W32L01	USGS
UNKNOWN	11N04W33C01	Quarter/Quarter
UNKNOWN	11N04W33D01	Quarter/Quarter
UNKNOWN	11N04W33G01	Quarter/Quarter
UNKNOWN	11N04W34D01	Quarter/Quarter
UNKNOWN	11N04W34D02	Quarter/Quarter
UNKNOWN	11N05W24R02	USGS
UNKNOWN	11N05W24RXX	Quarter/Quarter

The information displayed in this response to your public information request has been taken from MWA's databases and other sources. It is made available in good faith but its accuracy or completeness is not guaranteed and no representations or warranties are implied. The user will not seek to hold the MWA liable under any circumstances for damages with respect to any claim by the user or any third party on account or arising from the use of this data.

The information displayed in this response to your public information request has been taken from MWA's databases and other sources. It is made available

SAN BERNARDINO COUNTY FIRE DEPARTMENT



COUNTY OF SAN BERNARDINO
PUBLIC AND SUPPORT
SERVICES GROUP

OFFICE OF THE FIRE MARSHAL
HAZARDOUS MATERIALS DIVISION
620 South "E" Street • San Bernardino, CA 92415-0153
(909) 386-8401 • Fax (909) 386-8460

PAT A. DENNEN
Fire Chief
County Fire Warden
May 19, 2009

Enviro Chek
P. O. Box 355
Helendale, CA 92342

ATTENTION: Shirley R. Hibbetts

SUBJECT: CERTIFIED RECORD SEARCH FINDINGS - REVISED

**RE: Assessor Parcel Nos. 0490-121-42, 0490-131-06—08;
0490-131-11—13; 0490-131-15—16; 0490-161-08—09;
0490-151-10—13; 0490-171-09
Hinkley, California**

This is to confirm that the San Bernardino County Hazardous Materials Division has identified records that may pertain to the subject site, as described in your request for records search.

A search of Assessor records indicates APN 0490-121-42 has address 41800 Harper Lake Rd. APN 0490-131-06—08 has situs Lockhart Rd. APN 0490-131-11 and -13 have no situs, but APN 0490-131-12 has address 16198 Lockhart Rd.

APN 0490-131-15—16 have no situs. 0490-161-08—09 (Desert View Dairy) have no situs; however, a search of permit records indicates a record exists for Desert View Dairy with the address 37501 Mountain View Rd.

APN 0490-151-10—13 have no situs; nor does 0490-171-09.

(Assessor maps and ownership history were consulted for searching all parcels regardless of situs).

The file(s) listed below are available for your review. Please e-mail this office at eking@sbcfire.org or call the number at the end of this letter if you wish to arrange an appointment to view original documents.

ACTIVE PERMIT FACILITIES:

(Regulatory files for facilities with annual operating permits to maintain underground storage tanks, storage hazardous materials, and/or generate hazardous waste. Files include permits, inspections, reports, test results, correspondence, and related materials. Files will also include any underground tank removal/construction activity records and site remediation/contamination records for facilities still in operation).

Desert View Dairy
37501 Mountain View Rd.
Hinkley

FA0010927
Hazardous Material Handler Permit
Hazardous Waste Generator Permit
-- special type (consolidated manifest)

INACTIVE PERMIT AND/OR NON-PERMIT FACILITIES:

(Inactive regulatory files for formerly permitted facilities that maintained underground storage tanks, stored hazardous materials, and/or generated hazardous waste and/or facilities with underground storage tanks removed and/or materials and waste removed. Files will also

MARK H. UFFER
County Administrative Officer

NORMAN A. KANOLD
Assistant County Administrator
Public and Support
Services Group

Board of Supervisors
BRAD MITZELFELT First District NEIL DERRY Third District
PAUL BIANE Second District GARY C. OVITT Fourth District
JOSIE GONZALES Fifth District

include any underground tank removal/construction activity records and site remediation/contamination records for facilities no longer operating underground tanks).

Most Ranch
41800 Harper Lake Rd.
Hinkley

FA0004863 (EST 87014349)
Hazardous Material Handler Permit
Underground Storage Tank Permit

PERMITS TO REMOVE/INSTALL/MODIFY TANKS:

No record of permits to remove/install/modify ugsts*

*NOTE: Although there is no record of a permit to remove underground storage tanks, a copy of an environmental assessment report on file for Most Ranch 41800 Harper Lake Rd., Hinkley, indicates that 4 ugsts were removed in the early 1990's. It appears the tanks were removed without permits.

HAZ MAT INCIDENT AND/OR SPILL RESPONSE ACTIVITY:

(other records of spill notifications and/or complaints not listed below may exist in facility permit files).

RP: SCE (Vandals)
41800 Harper Lake Rd.
Hesperia

CO0024125
2/24/07
Release of mineral oil, 30 gallons


SITE REMEDIATION:

(Underground Storage Tank Clean-Up under Local Oversight Program or Voluntary Hazardous Waste Clean-Up activity under Local Jurisdiction) (documents may be included in regular active or inactive permit files listed above).

No record of site remediation and/or cleanup action under local jurisdiction

Records searched include permit database systems for facilities with permits as hazardous waste generators, hazardous materials handlers, and/or underground storage tanks, including inactive and/or out of business records; logs of permits issued for the removal and/or installation of underground storage tanks; records and databases pertaining to illicit dumping and releases; records of non-permitted facilities; sites undergoing remediation for contaminated soil and/or groundwater; and incidents responded to by the hazardous materials emergency response team.

Please e-mail me at eking@sbcfire.org or contact me at the number below for a review appointment or for further clarification.*



ELIZABETH A. KING
Environmental Specialist III
OFM Hazardous Materials Division
(909) 386-8468 (909) 386-8460 FAX
eking@sbcfire.org

*We will copy up to forty (40) pre-selected pages from a file at a charge \$0.27 per page copied. (Be prepared to make this payment at the time of service). If the copies selected exceed forty (40) pages or if you want a copy of the entire file and it exceeds forty (40) pages, we will refer you to a private copy service. If you prefer to bring a portable copier on site, you may do so. Please let us know your plans in advance so that accommodations can be made.

Records consist of 3 files, about 1-1/2" to 2" thick combined. Files were provided at File Review Appt. 5/19/09 2:00 p.m.

BRADLEY

ENVIRONMENTAL SERVICES

CONSULTING • REMEDIATION • MANAGEMENT



February 13, 1996

Ms. Donna DiRocco, Environmental Analyst
 Bank of America, Environmental Services #24122
 4000 Mac Arthur Boulevard, Suite 100
 Newport Beach, California 92660

RE: Environmental Site Investigation Questionnaire (ESIQ) for 41800 Harper Lake Road, Hinkley, California, Bank of America Work Order Number 03432-01, Bradley Environmental Services (Bradley) Project Number 6403.

Dear Ms. DiRocco,

Enclosed are two copies of the ESIQ report documenting the findings and conclusions for the assessment of the subject agricultural property. This work was performed in accordance with the terms and conditions of the professional services agreement between Bank of America and Bradley (No. 94-112) dated October 17, 1994.

Bradley did not identify serious environmental concerns at the adjacent properties or on the subject property. However about 6000 square feet of 9" x 9" vinyl floor tiles in poor condition containing 15% - 20% chrysotile asbestos exists in the 7,800 square foot maintenance building on the subject property. In addition about 200 linear feet of transite pipe exists north of the maintenance building onsite in good condition. The estimated cost for abatement of the flooring is between \$10,000 and \$13,500.

The USTs that were onsite have been removed. Based on conversations with Mr. Most that indicate the USTs had been empty, and the results of a soil gas survey completed in the UST vicinity, it is unlikely that a large volume of hydrocarbon impacted soil exists onsite. The eight remaining 4000 gallon diesel ASTs onsite used to pump the irrigation wells have limited soil staining that is limited to less than 2 feet below the ground surface, and is not considered to be a problematic environmental issue. Disposal of this diesel impacted soil would be between \$5,000 and \$8,000.

If you have any questions regarding the findings and conclusions presented in this report, please contact me at (909) 596-7780.

Sincerely,

Steven Kerchner, REA
 Senior Environmental Specialist

enclosures (2)

BANK OF AMERICA

**ENVIRONMENTAL SITE INSPECTION QUESTIONNAIRE (ESIQ)
AGRICULTURAL REAL ESTATE LOANS (AG-ESIQ)
(To Be Completed by Consultant on Behalf of Bank of America)**

I. GENERAL INFORMATION

ES PROJECT#: 404630

Site Name: Milton Most Ranch
Address: 41,800 Harper Lake Road, Hinkley, California.
(1628 acre alfalfa farm).

Firm Completing ESIQ: Bradley Environmental Services
Inspector's Name/Title: Steven Kerchner, Senior Environmental Specialist
Telephone Number: (909) 596-7780

Date of Inspection: 2-8-96

Site Contacts:

<u>Name</u>	<u>Title</u>	<u>Affiliation</u>
<u>Milton Most</u>	<u>Owner</u>	<u>N/A</u>
<u>Donna DiRocco</u>	<u>Env. Analyst</u>	<u>Bank of America</u>
<u>Jim Clark</u>	<u>Acct. Officer</u>	<u>Bank of America</u>

II. SITE DESCRIPTION/USE/HISTORY

A. DESCRIPTION

1. Provide a description of the site (ie. existing structures, geographic conditions etc.).
The site consists of a 1628 acre alfalfa farm located at 41,800 Harper Lake Road, Hinkley, California. The site is currently inactive and no new spring crop is planned. The buildings on site include twenty different structures ranging from a 7,800 sq. ft. cement vehicle maintenance building, with 2nd floor living quarters, to grain storage silos & grain processing buildings with associated equipment. Other buildings include living quarters for workers (used for storage). The site has been used as a stockyard and grain growing/loading enterprise prior to Mr. Most having taken it over in the 1950's. Haz-mat storage includes eight diesel ASTs (4,000 gallon approx. each), and two 55-gallon drums of waste-oil. No pesticide containers or PCB containing equipment were noted on the day of the inspection. Pesticides were never stored onsite according to Mr. Most. The pesticides were brought in for short durations and applied with "crop duster" planes which landed on a dirt landing strip on the subject site. Fifteen water wells are onsite, but only eight are active (each with one of the 8 diesel ASTs to run the 8 well pumps). The site had four fuel USTs onsite, which included diesel, aviation gas, and gasoline, but they and the fuel dispenser island were removed in the early 1990's. Undeveloped desert land is adjacent to the subject property with the "Luz" electrical generating station .5 mile to the northwest. The site is on fairly level ground with adequate drainage and is poorly maintained.

B. CURRENT USE

1. Provide a description of the current sites uses (ie. products made, processes, raw material used and waste streams generated, etc.). If multiple tenants, then describe individually.
The 1628 acre alfalfa farm has not been active, but tractor/vehicle maintenance activities are still onsite which generates waste oil. Tractors, forklifts, trucks/automobiles, and assorted farm vehicles were on site the day of the visit, including a trailer mounted tank for Ag chemical application (volume, 250 gal). The site is no longer in current agricultural production, however.
2. Attach a Plot Plan describing key features. Provide color photographs that characterize the pertinent features of the site for correlation with the features noted on the Plot Plan.

NOTE: MORE PAGES SHOULD BE ATTACHED IF MORE SPACE IS REQUIRED FOR EXPLANATIONS.

C. FORMER SITE USES

1. Based on site observations and discussions with site contacts, describe the former site uses including dates where known.

This parcel was used for agricultural purposes in the past, prior to Mr. Most's acquisition of the site, and has historically been used for agricultural production since at least the 1930's.

2. Were any buildings demolished or removed from the site?

Yes X No _____. If so, describe how determined (i.e., infrastructure foundation, sidewalks, communications with site personnel, etc.).

A single family residence or migrant worker quarters was burned out on the day of the inspection.

III. ADJACENT SITE USES AND HISTORY

A. CURRENT USES

1. Describe adjacent site uses and make note of any particular areas of concern. Provide color photographs of all noted areas of environmental concern.
There are no adjacent site uses of concern. The adjacent site uses include the "Luz" electrical generation station N.W. of the subject site and undeveloped desert land which pose no environmental concerns. There are no industrial or manufacturing concerns in the adjacent areas.

2. Describe adjacent site and area history and provide dates where known. In addition, please state how this information was determined. Provide color photographs of noted concerns.

The surrounding area is undeveloped desert with the "Luz" operation .5 mile to the northwest. There is no indication of industrial or manufacturing activity for the adjacent sites.

IV. SITE INSPECTION INFORMATION

A. **ASBESTOS CONTAINING MATERIALS (ACM)**

1. What is the reported construction date of buildings/structures at the site?

The SFR and metal storage shed on site were constructed in the mid 1950's.

2. Based on your site visit, were any suspect ACM identified?

Yes X No _____. If yes, list below.

Type/Description	Condition	Location	Quantity (sq. ft.)
<u>9"x 9" Vinyl Floor</u>	<u>Poor</u>	<u>Maint. Bldg.</u>	<u>6000</u>
<u>Transite Pipe</u>	<u>Good</u>	<u>Storage Area</u>	<u>200 Linear feet</u>

Three (3) samples were taken of the floor tiles and the transite pipe, all of which were positive for asbestos. No complete survey has been performed at the site, as it was not in the original scope of work. A copy of the lab analysis has been attached.

3. Has an ACM survey ever been performed at the site?

Yes _____ No X. If yes, attach a copy.

B. **POLYCHLORINATED BIPHENYLS (PCB)**

1. Are any electrical transformers, capacitors, or other equipment located onsite which may contain PCB's?

Yes _____ No X. If yes, please describe (ie. condition, leakage, labels etc.).

2. Based on site observations, can it be determined if the equipment is owned by a public utility or the property owner?

Yes___ No X If yes, please indicate.

C. UNDERGROUND STORAGE TANKS (USTs)

1. Are there any USTs currently on the site?

Yes___ No X

2. Were there any USTs abandoned in place or removed from the site?

Yes X No ___

3. If yes to Items 1 or 2 above, please describe type of system, construction (ie.single-walled steel tank etc.), location, product stored, and age of tank or when removed.

According to Mr. Most, four (4) steel single wall USTs were removed from the site including ; 1) Two (2) 4,000 gallon (assumed) diesel USTs; 2) 4,000 gallon (assumed) aviation gas UST; 3) 4,000 gallon (assumed) leaded gasoline UST; all 4 removed in the early 1990's (see Figure 3).

4. Have the existing UST systems ever been repaired?

Yes___ No X If yes, please describe.

N/A

5. How are the existing UST systems being monitored for leaks? Please describe the system.

Not Applicable.

6. Have the UST systems ever been integrity tested for leaks?

Yes___ No X If yes, when and what were the results?

N/A

7a. Have there been any site investigations completed due to UST leakage?

Yes___ No X

7b. If so, were these site investigations initiated due to regulatory directives?

Yes ___ No X

7c. If yes to either question 7a or 7b, please describe.

N/A

D. ABOVE GROUND STORAGE TANKS (AST)

1. Are there any ASTs located on the property?

Yes X No ____ . If yes, please describe the types, size and products stored. Also, describe any type of monitoring system or secondary containment in place.

Eight (8) diesel ASTs are currently onsite to run the water well pumps for irrigation of the crops and are assumed to be about 4,000 gallons each. An aboveground cement electrical box or bunker was found north of the maintenance building which has rainwater and asphaltic roofing compound mixed together inside, which is not considered to be an environmental issue.

2. Is there any evidence of spillage or release from the tanks?

Yes X No ____ . If so, please describe.

Spillage was discerned at the base of each of the eight ASTs in the bare mineral soil. However the extent of the diesel spillage was limited to less than 2 feet below the ground surface, and in most cases, less than 18 inches, as determined by digging with a steel probe on the day of the site visit.

E. HAZARDOUS MATERIAL STORAGE AREA

1. Are any chemicals stored on the property in drums or other containers?

Yes X No ____ If yes, please provide a listing of the types and approximate quantities of chemicals stored and the condition of their containers.

Type	Quantity	Condition
<u>Waste oil</u>	<u>Two 55-gallon drums</u>	<u>Good</u>
<u>New grease & oil</u>	<u>Ten 5-gallon drums</u>	<u>Good</u>

2. Please describe the hazardous materials storage area.

The above mentioned drums are stored in, and adjacent to, the main maintenance building on the subject site. All drums and storage containers are on cement foundations within each building with no signs of staining or spillage.

Is there any evidence of leaks or spills?

Yes ____ No X If yes, please describe.

Minimal staining was noted beneath the drums on the cement building foundations.

No chemical spills, or large scale soil staining was noted on site on the day of the visit.
The 8 diesel ASTs at the active water wells throughout the site have a small amount of
diesel in the soil at the base of each AST.

4. Have site contacts indicated that leaks have occurred in the past?
Yes___ N X_. If yes, please describe.

F. PIPELINES

1. Are any above or below-ground pipelines (including water and sanitary sewers) located on the property?
Yes X___ No ____. If so, please describe.
_Water lines exist on site. _____

2. Are any pipelines being monitored for leaks?
Yes___ NX_. If yes, please describe.

3. Have any pipelines leaked in the past?
Yes___ No X___

G. OIL AND GAS WELLS

1. Are there any oil or gas wells or related activity located on or near the site?
Yes___ No X_. If yes, please describe.

H. AIR EMISSIONS

1. Are air emissions from facilities at the site subject to air pollution control regulations?
Yes___ No X_. If yes, please describe, including type of emission, type of burners, fuel, air pollution control devices, etc.

I. WATER AND WASTEWATER

1. What is the source of water supply for the site?

Public 15 Onsite wells Other (Describe) - Only 8 of the 15 water wells onsite are active, and depth to groundwater is about 200 feet.

2. What is the water used for at the site?

 X Irrigation Domestic
 Sanitary Facilities Other (Describe)

3. What are the sources of wastewater? Please describe each source including waste constituents and volume of water generated.

There are no sources of wastewater.

4. What site facilities are present for handling of wastewater?

<u> X </u> Not applicable	
<u> </u> Above-ground tanks	<u> </u> Trenches
<u> </u> Underground tanks	<u> </u> Vats
<u> </u> Clarifiers	<u> </u> Sumps
<u> </u> Treatment Systems	<u> </u> Ponds

5. How is wastewater disposed of and what is the average daily flow? Please describe.

N/A

6. How is stormwater managed onsite? Please describe.

The stormwater on the site appears to follow topography toward the dry lake bed 2 miles to the northeast (Harper Lake) which allows drainage for the site.

7. Are there any dry wells, leachfields, septic systems or other wastewater disposal systems located onsite?

Yes No X If yes, please describe.

8. Have any citations been received for any discharge violations?

Yes No X If yes, please describe.

9. Please attach copies of wastewater treatment and/or wastewater discharge permits pertaining to the property. If not applicable, please indicate why.

The site is an agricultural parcel of land with no prior history of industrial development.

J. WASTE GENERATION, STORAGE AND DISPOSAL

1. Please list all hazardous and non-hazardous waste streams generated onsite.

<u>Waste Description</u>	<u>Quantity</u>	<u>How Disposed</u>	<u>How often</u>
<u>Waste oil</u>	<u>100 gallons</u>	<u>Hauled</u>	<u>6 months</u>
<u> </u>	<u> </u>	<u> </u>	<u> </u>
<u> </u>	<u> </u>	<u> </u>	<u> </u>
<u> </u>	<u> </u>	<u> </u>	<u> </u>

2. Is there onsite storage of wastes?

Yes___ No X . If yes, please describe.

Waste oil as described above, which is stored in 55 gallon drums.

3. Does the storage area have secondary containment?

Yes___ No X . If yes, describe.

N/A

4. Is there any evidence of spills or releases?

Yes___ No X . If yes, describe.

5. Have site contacts indicated that spills or releases occurred in the past?

Yes___ No X . If yes, describe.

K. PESTICIDES/HERBICIDES AND AGRICULTURAL CHEMICALS

1. Have pesticides, herbicides, or other agricultural chemicals ever been applied to the property?

Yes X No ____ . If so, please describe.

It appears that Agricultural chemicals have been applied to the site, but Mr. Most was not very lucid concerning amount of application and type of chemicals used. Based on Bradley's previous experience with similar agricultural properties, it is unlikely that large amounts of residual pesticides exist in the soil onsite.

2. Have pesticides, herbicides, or other agricultural chemicals ever been mixed, formulated, rinsed or disposed of on the property?
Yes ____ No X. If so, please describe the agricultural chemicals that were processed, the volumes involved and the location of the processing.

Pesticides were never stored onsite according to Mr. Most. The pesticides were brought in for short durations and applied with "crop duster" planes which landed on a dirt landing strip on the subject site. The pesticides were delivered by truck and dispensed to the crop dusters at the landing strip.

L. RADON

1. Have radon levels been monitored at the property or any information gathered concerning the potential for radon accumulation?
Yes ____ No X. If so, please describe.
-
-

V. ENVIRONMENTAL STUDIES, REPORTS, CITATIONS, ENFORCEMENT AND CLEANUP ACTIONS

1. Have any environmental assessment studies been performed for the site with respect to soil, groundwater, air or site facilities and processes?

Yes X No ____ . If so, please describe briefly and attach complete dated copies of such reports.

It was reported that "Luz" Corporation took soil samples from the vicinity of the USTs onsite, and the analysis indicated no tank leakage from the onsite USTs, however a copy of the report was not available for review. In addition a soil gas survey was conducted by ENSR in August, 1990, which was reviewed by Bradley. The report indicates that no significant fuel release has occurred onsite, but goes on to say that a soil sample should be collected from beneath the removed aviation gas tank location for analysis. Based on conversations with Mr. Most, these tanks haven't been used for years (empty) and residual hydrocarbon impacted soil, if any, would be negligible. Depth to groundwater is 200 feet for the subject site area. The Lahontan Region of the Regional Water Quality Control Board indicated that a chromium plume in the groundwater exists from a PG&E

compressor station about 8-10 miles southeast of the subject site which is unlikely to impact the subject site.

2. Has any public agency ever investigated or cited the property for violation or possible violation of any environmental law or commenced enforcement or cleanup action under environmental law with respect to the property?

Yes__ No X. If yes, describe.

3. Has any public agency ever listed the property as a site requiring or qualifying for cleanup under environmental law?

Yes__ No X. If yes, please describe.

LIMITATIONS

It is understood by Bank of America that the inspection by the above individual/company has been performed within the limits of the contract between the consultant and Bank of America in accordance with current generally accepted principles and practices of environmental consulting. No other warranty or representation, either expressed or implied, is included in the completion of the questionnaire.

Any conclusions presented in the questionnaire are professional opinions based on the data obtained. The conclusions presented are based on the assumption that conditions do not deviate from those observed during the inspection, as described in the questionnaire. It is recognized that this inspection is not intended to be a definitive study of environmental conditions at the site. It is understood that other conditions may exist at the site which could not be identified from the limited inspection based solely on site observation.

Any opinions presented apply to site conditions existing at the time of the inspection and those reasonably foreseeable; they cannot necessarily apply to site changes made of which the inspector could not observe and has not had the opportunity to evaluate. Changes in the conditions of the subject property can occur with time, because of the natural processes or the works of man, on the subject site or on adjacent properties. Changes in applicable engineering and construction standards can also occur as the result of legislation or from the broadening of knowledge. Accordingly the data presented in the questionnaire may be invalidated, wholly or in part, by changes beyond the control of the inspector.

Signature of Consultant/Inspector

Steven C. Kerchner
Typed Name

2-14-96
Date

Affix Registration Stamp:

Signature of Consultant/Reviewer

Wade R. Cooksey
Typed Name

2-14-96
Date

Affix Registration Stamp:




PLATE 1: View of subject site showing wellhead, which has 4 1/2 inch dry scale, and 1 1/2 inch wet scale.





PLATE 2: View of subject site showing diesel AST at Well #8.

BULK SAMPLE ANALYSIS REPORT
(NIOSH METHOD 7403)

PROJECT: BANK OF AMERICA-#6403 TEST DATE: 02-12-96
SITE ADDRESS: 41800 HARPER LAKE RD. SAMPLE DATE: 02-09-96
HINKLEY, CA
CLIENT: BRADLEY ENV. SERVICES SAMPLE TAKEN BY: S. KERCHNER
1815 WRIGHT AVE.
LA VERNE, CA 91750 PAGE:

ABBREVIATIONS:	<u>SAMPLE TYPE</u>	<u>ASBESTOS TYPE</u>	<u>MATERIAL TYPE</u>
	VT-Vinyl Floor Tile	CHRY-CHrysotile	CELL-Cellulose
	LIN-Linoleum	AMOS-Amosite	FG-Fibrous Glass
	AC-Acoustical Spray-On	CROC-Crocidolite	AGG-Aggregate
	CT-Ceiling Tile	ANTH-Anthropyllite	NF-Non Fibrous
	INSUL-Insulation	ACTIN-Actinolite	SYN-Synthetic
	DJM-Drywall Joint Mud	ND-None Detected	GYP-Gypsum
	WP-Wall Plaster	TRACE-<1% Asbestos	CAL-Calcite

SAMPLE #	SAMPLE TYPE LOCATION	ASBESTOS CONTENT	LIABILITY	OTHER MATERIAL
#1	VT-9X9/BROWN	20% CHRY	NF	+ BINDER
#2	TRANSITE	40% CHRY 5% CROC	NF	+ BINDER
#3	VT-9X9/TAN	15% CHRY	NF	+ BINDER




ANALYST

*This report pertains only to the items tested. This report may not be reproduced except in full with permission of MACS Lab.
*Floor Tile samples may yield "False Negative" (<1%) asbestos due to the size of asbestos fibers. Definitive results can be obtained by TEM or SEM analysis.

DRADLE

ENVIRONMENTAL SERVICES

REPORT TO: BRADLEY ENVIRONMENTAL SERVICES, INC. • 5171 PARKFIELD LANE • LA VERNE • CALIFORNIA • 91750
PHONE (909) 596-7780 • FAX (909) 593-8441




Not to Scale. Copyright 1978

Neighborhood Map

Fractional Sec's 30 & 31, T1N R4W, S.B.B. & M.

Burrow United
Tax Rate Area
56103

499-



SUBJECT


Assessor's Map No. 12194, P.M. 142/14-53

Note - Assessor's Bk & Lot
Numbers Shown in Circles

Assessor's Map
Book 490, Page 12
San Bernardino County

Plat Map

Sec 28 a 29, TIN R 4W., S88 a M



Assessor's Map
Book 490, Page 13
San Bernardino County

**Note - Assessor's Six & Last
Numbers Shown in Circles**

SUBJECT


Plat Map

E 1/2 Sec 32 & Sec 33, T11N R4W, S8B & M.

Borstar Unified
Tax Rate Area
56103

SUBJECT →

(13)



(17)

33

32

(14)


496
02

496
05

Assessor's Map
Book 490, Page 16
Note-Assessor's Blk & Lot
Numbers Shown in Circles
San Bernardino County

Plat Map

STRIP MAP OF COMMERCIAL PROPERTIES



HARPER DRY LAKE
JANUARY 27, 1994

Site Plan

Site Plan

STRIP MAP OF COMMERCIAL PROPERTIES

HENDO FACILITY

HENDER FACILITY

RESERVOIR

ALPHA

FARMSTEAD PLAT


NOT TO SCALE

2


TARPER

LAKE

ROAD



Asbestos
Floor
tile



SOURCE:
USGS MAP, BARSTOW QUADRANGLE,
15 MINUTE SERIES, 1956.





FIGURE 1 VICINITY MAP

PACIFIC GAS AND ELECTRIC COMPANY
NATURAL GAS COMPRESSOR STATION
HINKLEY, CALIFORNIA

PROJECT NO. 10-187



ALISTO ENGINEERING GROUP
WALNUT CREEK, CALIFORNIA



NOTE:
Well locations are based on state
survey coordinates.

FIGURE 6

DISTRIBUTION OF TOTAL CHROMIUM IN GROUNDWATER

OCTOBER 3-6, 1995

REMEDATION PROJECT
PACIFIC GAS AND ELECTRIC COMPANY
NATURAL GAS COMPRESSOR STATION
HINKLEY, CALIFORNIA

PROJECT NO. 10-187-12



ISTO ENGINEERING (LONDON)
WATKINS ENGINEERING (LONDON)




TABLE 3
RESULTS OF GROUNDWATER MONITORING AND SAMPLING
REMEDIATION PROJECT
PG&E HINKLEY COMPRESSOR STATION

RWQCB Order No. 6-91-917A1
RWQCB WQID No. 6B069107001
Aikio Project No. 10-187-12

Well ID	Sampling/ Monitoring (Date)	(a)	Casing Elevation (Feet)	(b)	Depth To Water (Feet)	Groundwater Elevation (Feet)	(c)	--Field Measurements--		Temp. (F)	Total Chromium (mg/l)	Lab
								E.C. (uS/cm)	pH (pH Unit)			
PGE-01	02/22/94	(e)	2203.60		N/A (d)	---	---	---	---	---	---	---
PGE-01	06/01/94	(e)	2203.60		86.85	2116.75	---	---	---	---	---	---
PGE-01	08/11/94	(e)	2203.60		86.27	2117.33	---	---	---	---	---	---
PGE-01	10/24/94	(e)	2203.60		85.72	2117.88	---	---	---	---	---	---
PGE-01	02/06/95	(e)	2203.60		85.07	2118.53	---	---	---	---	---	---
PGE-01	04/05/95	(e)	2203.60		84.65	2118.95	---	---	---	---	---	---
PGE-01	08/17/95	(e)	2203.60		83.56	2120.04	---	---	---	---	---	---
PGE-01	10/04/95	(e)	2203.60		83.01	2120.59	---	---	---	---	---	---
PGE-02	02/22/94	(e)	2207.37		83.70	2123.67	---	---	---	---	---	---
PGE-02	06/01/94	(e)	2207.37		82.20	2125.17	---	---	---	---	---	---
PGE-02	08/11/94		2207.37		85.00	2122.37	437	7.75	71.5	ND<0.01	APCL	
PGE-02	10/24/94		2207.37		85.70	2121.67	403	6.83	70.5	ND<0.01	APCL	
PGE-02	02/06/95		2207.37		83.31	2124.06	417	8.11	65.0	ND<0.01	APCL	
PGE-02	04/05/95		2207.37		83.06	2124.31	366	7.91	70.0	ND<0.01	APCL	
PGE-02	08/17/95		2207.37		84.98	2122.39	473	7.26	63.1	ND<0.01	APCL	
PGE-02	10/04/95		2207.37		83.65	2123.72	356	7.92	65.8	ND<0.01	APCL	
PGE-04	02/24/94	(e)	2202.87		86.78	2116.09	---	---	---	---	---	---
PGE-04	05/31/94	(e)	2202.87		85.06	2117.81	---	---	---	---	---	---
PGE-04	08/11/94	(e)	2202.87		85.15	2117.72	---	---	---	---	---	---
PGE-04	10/24/94	(e)	2202.87		85.08	2117.79	---	---	---	---	---	---
PGE-04	02/06/95	(e)	2202.87		82.81	2120.06	---	---	---	---	---	---
PGE-04	04/05/95	(e)	2202.87		82.35	2120.52	---	---	---	---	---	---
PGE-04	08/17/95	(e)	2202.87		79.34	2123.53	---	---	---	---	---	---
PGE-04	10/04/95	(e)	2202.87		78.86	2124.01	---	---	---	---	---	---
PGE-06	02/24/94	(e)	2196.55		N/A (d)	---	---	---	---	---	---	---
PGE-06	05/31/94	(e)	2196.55		76.50	2120.05	---	---	---	---	---	---
PGE-06	08/11/94	(e)	2196.55		N/A (d)	---	---	---	---	---	---	---
PGE-06	10/24/94	(e)	2196.55		N/A (d)	---	---	---	---	---	---	---
PGE-06	02/06/95	(e)	2195.81	(f)	74.42	2121.39	---	---	---	---	---	---
PGE-06	04/05/95	(e)	2195.81		N/A (d)	---	---	---	---	---	---	---
PGE-06	08/17/95	(e)	2195.81		N/A (d)	---	---	---	---	---	---	---
PGE-06	10/04/95	(e)	2195.81		N/A (d)	---	---	---	---	---	---	---
PGE-07	02/24/94		2196.55		103.61	2092.94	755	7.12	69.4	2.80	APCL	
PGE-07	06/01/94		2196.55		97.09	2099.46	890	7.53	75.2	3.50	APCL	
PGE-07	08/11/94		2196.55		97.30	2099.25	775	7.14	70.2	2.40	APCL	
PGE-07D (g)	08/11/94		---		---	---	---	---	---	2.30	APCL	
PGE-07	10/26/94		2196.55		97.41	2099.14	1184	6.94	71.1	2.60	APCL	
PGE-07	02/06/95		2196.55		96.95	2099.60	910	7.58	67.5	2.60	APCL	
PGE-07	04/05/95		2196.55		92.24	2104.31	687	7.29	68.6	2.20	APCL	
PGE-07	08/17/95		2196.55		95.44	2101.11	797	7.40	62.7	1.70	APCL	
PGE-07 (g)	08/17/95		---		---	---	---	---	---	1.70	APCL	
PGE-07	10/04/95		2196.55		95.01	2101.54	590	7.99	67.0	2.10	APCL	
PGE-09	02/24/94		2209.09		84.44	2124.65	296	7.94	47.6	ND<0.01	APCL	
PGE-09D (g)	02/24/94		---		---	---	---	---	---	ND<0.01	APCL	
PGE-09	06/01/94	(e)	2209.09		84.61	2124.48	555	7.62	71.4	ND<0.01	APCL	
PGE-09	08/11/94	(e)	2209.09		85.55	2123.54	---	---	---	---	---	---
PGE-09	10/24/94	(e)	2209.09		86.07	2123.02	---	---	---	---	---	---
PGE-09	02/06/95	(e)	2208.48	(f)	85.22	2123.26	---	---	---	---	---	---
PGE-09	04/05/95	(e)	2208.48		85.37	2123.11	---	---	---	---	---	---
PGE-09	08/17/95	(e)	2208.48		85.66	2122.82	---	---	---	---	---	---
PGE-09	10/04/95	(e)	2208.48		84.82	2123.66	---	---	---	---	---	---
PGE-11	02/23/94	(e)	2195.10		103.40	2091.70	---	---	---	---	---	---
PGE-11	05/31/94	(e)	2195.10		70.06	2125.04	347	8.10	72.7	ND<0.01	APCL	
PGE-11	08/11/94	(e)	2195.10		70.34	2124.76	---	---	---	---	---	---
PGE-11	10/27/94	(e)	2195.10		71.05	2124.05	---	---	---	---	---	---
PGE-11	02/06/95	(e)	2193.92	(f)	68.78	2125.14	---	---	---	---	---	---
PGE-11	04/05/95	(e)	2193.92		65.92	2128.00	---	---	---	---	---	---
PGE-11	08/17/95	(e)	2193.92		64.04	2129.88	---	---	---	---	---	---
PGE-11	10/04/95	(e)	2193.92		64.11	2129.81	---	---	---	---	---	---
PGE-12	02/23/94	(e)	2196.26		84.14	2112.12	---	---	---	---	---	---
PGE-12	05/31/94	(e)	2196.26		78.13	2118.13	---	---	---	---	---	---
PGE-12	08/11/94		2196.26		78.16	2118.10	410	7.91	91.2	ND<0.01	APCL	
PGE-12	10/27/94		2196.26		77.36	2118.90	360	8.06	73.3	0.23 (k)	APCL	
PGE-12	02/06/95		2196.26		75.54	2120.72	340	8.21	69.4	ND<0.01	APCL	
PGE-12	04/05/95	(e)	2196.26		74.34	2121.92	---	---	---	---	---	---
PGE-12	08/17/95	(e)	2196.26		71.02	2125.24	---	---	---	---	---	---
PGE-12	10/04/95		2196.26		70.32	2125.94	317	8.07	65.5	0.03 (k)	APCL	

**Luz Development and
Finance Corporation**

Los Angeles, California



**Soil Gas Vapor Survey Results
at Most Ranch**

ENSR Consulting and Engineering

September 1990

Document Number 4360-025-500

MILTON MOST

41800 Harper Lake Rd.

Hinkley, Ca. 92347



Formerly ERT

September 14, 1990

ENSR Consulting
and Engineering

1220 Avenida Acaso
Camarillo, CA 93012
(805) 388-3775
(805) 388-3577 (FAX)

Ms. Carrie Weisse, P.E.
Manager, Environmental Engineering
Luz Development and Finance Corporation
924 Westwood Boulevard, Suite 1000
Los Angeles, California 90024

Dear Ms. Weisse:

The following is ENSR's report of the soil gas vapor survey results at Most Ranch. The survey took place August 16, 1990. No volatile organics were detected surrounding the underground diesel and gasoline tanks. Minor hydrocarbon concentrations were detected in the vapor at two points in the area surrounding the aviation gas storage tank. We recommend collecting a soil sample for laboratory analysis to quantitatively confirm the presence of hydrocarbons in the soil.

PURPOSE

The scope of work performed for the soil vapor survey of the Most Ranch property located on Harper Lake Road, San Bernardino County, California, consisted of multiple soil vapor survey points to determine the possible existence of petroleum hydrocarbon-affected soils in the subsurface. A Photovac 10S50 portable gas chromatograph (GC) was used to analyze soil vapor samples extracted from slotted intake probes driven into the soil. Soil vapor sample points were located in the vicinity of the underground tank containing avgas, and in the area surrounding the group of underground tanks and dispensers containing gasoline and diesel. Soil vapor data were then used to evaluate areas relative to each other. Recommended action items for areas where soil vapor screening indicate the possible presence of subsurface petroleum hydrocarbons are included in this report.

SOIL VAPOR SURVEY METHODOLOGY

Collection and analysis of soil vapor is a screening method used to evaluate areas where volatile organic compounds (VOCs) may be present in the subsurface. As stated, soil vapor is analyzed using a Photovac 10S50 portable GC equipped with a sampling pump, analytical column, and photoionization detector (PID). The GC is calibrated at least twice daily (depending upon field conditions) by using a previously prepared standard containing a 10-ppm average concentration of benzene, toluene, ethylbenzene, and xylenes (BTEX). BTEX constituents are used because they are the most volatile components of gasoline and are readily detected by the PID.

September 14, 1990
Ms. Carrie Weisse, P.E.
Page 2

Samples are collected using a stainless steel probe machined with slotted intakes at the tip. The probe is connected to the GC with Teflon tubing and airtight fittings. Before using a probe for sampling, the probe is verified as being free from VOC contamination by drawing a sample of ambient air through the probe and analyzing the sample with the GC. At a particular sampling point, the probe is driven into the ground to a depth of approximately 3 feet. The GC is equipped with a pump which draws a soil vapor sample out of the soil and introduces the sample into the analytical column of the GC. VOCs are chromatographically separated in the column before detection by the PID. A chromatogram is generated that summarizes the PID response in volt-seconds and indicates the relative presence or absence of VOCs.

FIELD ACTIVITIES

Soil vapor survey field activities were conducted on August 16, 1990 at the Most Ranch property located on Harper Lake Road in San Bernardino County (Figure A-1). ENSR personnel conducting the survey were Todd Walker, Chemist, and Humberto Hernandez, Technician. A total of 18 soil vapor samples were collected across the site (Figure A-2).

Besides calibrating the Photovac GC with a BTEX standard, an avgas standard was also analyzed in order to provide data showing the chromatographic "fingerprint" of avgas. Soil probe blanks were analyzed before using the probe at each sampling location. After collecting a sample, the probe was cleaned to remove soil from the slotted intakes.

Eleven soil vapor samples were collected around the perimeter of the avgas storage tank. Seven soil vapor samples were collected around the perimeter of the concrete pad covering the underground gasoline and diesel tanks (Figure A-2).

RESULTS

Soil vapor survey results and relative levels are summarized in Table 1. Table 1 indicates the soil vapor sample identification number with respect to the locations indicated on Figure A-2 and on the chromatograms (Appendix A).

Chromatographic peaks were registered at soil vapor sample location SV-1, located approximately 25 feet northeast of the underground avgas tank. Soil vapor sample SV-18 was located adjacent to the location of sample SV-1 in an attempt to duplicate and confirm the positive result found at SV-1. VOCs were not encountered in sample SV-18.



September 14, 1990
Ms. Carrie Weisse, P.E.
Page 3

Soil vapor sample SV-3 did not produce a response on the chromatogram while the probe was in the ground; however, after removing the probe from the ground and cleaning soil clogging the slotted intakes, a blank of this probe (which had not been used previous to sampling SV-3) was run and chromatographics were registered. VOCs were not detected at SV-2 or at SV-4 through SV-18.

CONCLUSIONS AND RECOMMENDATIONS

Based on the analysis described above, there is no indication that a significant release has occurred from the underground storage tanks located at the Most Ranch property. The following paragraphs provide a summary of key findings and recommendations.

VOC peaks were registered at sample point SV-1. However, sample point SV-18, located next to SV-1, did not detect any VOCs. It is possible the VOCs detected at SV-1 were a carryover from the standards run prior to this sample point.

In addition, there were no VOCs detected at sample point SV-3. However, minor peaks were registered in the probe blank after sample SV-3. This may be due to equipment cross-contamination.

Based upon review of the chromatograms from sample points surrounding the avgas tank, it is unlikely VOCs exist in the soils surrounding the avgas tank. However, ENSR does recommend collecting a soil sample below the avgas tank invert to verify quantitatively the presence of possible avgas-related VOCs in the subsurface. The sample should be analyzed by EPA Method 8015 modified for total extractable hydrocarbons (solvent extraction).

No VOCs were detected from sample points surrounding the gasoline and diesel tanks. Based upon review of the chromatograms, it is unlikely VOCs are present in the subsurface soils surrounding the tanks.



September 14, 1990
Ms. Carrie Weisse, P.E.
Page 4

If you have any questions or comments, please call me at (805) 388-3775.

Sincerely,


Timothy M. Strawn
Project Manager

TMS/bhm

ENSR Document No. 4360-025-500
ENSR Reference No. ARS/1448/90




Figure A-1. Site Location Map
Most Ranch Building and Stockyard Area




TABLE 1**Summary of Soil Vapor Survey
Analytical Results**

Sample ID	Volatile Organic Compounds (VOCs)
SV-1	ML
SV-2	ND
SV-3	ND*
SV-4	ND
SV-5	ND
SV-6	ND
SV-7	ND
SV-8	ND
SV-9	ND
SV-10	ND
SV-11	ND
SV-12	ND
SV-13	ND
SV-14	ND
SV-15	ND
SV-16	ND
SV-17	ND
SV-18	ND
Notes:	
<ul style="list-style-type: none">VOCs not detected in sample; however, post-analytical blank indicated VOCs were present (see text).	
ND = VOCs not detected.	
ML = moderate level of VOCs detected.	

APPENDIX A

REPORT

START

1
2
3
4
5
6
7
8
9
10


Adjust Gain to 10

11
12
13
14
15
16

STOP 0 200.2
SAMPLE LIBRARY 1 AUG 10 1990 3:11
ANALYSIS # 2 SYSTEM BLANK
INTERNAL TEMP 50
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	4	21.8	57.0 μS
UNKNOWN	11	125.3	411.1 μS

PHOTOPAC



AUG 16 1959 9:24

FIELD: 29
POWER: 39

SAMPLE	0.0	60.0
CAL	0.0	0.0
EVENT 3	60.0	160.0
EVENT 4	0.0	60.0
EVENT 5	60.0	160.0
EVENT 6	0.0	0.0
EVENT 7	0.0	0.0
EVENT 8	0.0	0.0


STOP 8 269.4

SAMPLE LIBRARY 1 AUG 16 1959 9:24
ANALYSIS # 4 STEX STD
INTERNAL TEMP 35
GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
---------------	------	------	----------

UNKNOWN	1	9.3	213.7 AUS
UNKNOWN	2	13.2	541.7 AUS
UNKNOWN	3	18.5	216.1 AUS
UNKNOWN	4	33.9	16.0 US
UNKNOWN	5	70.2	11.1 US
UNKNOWN	6	124.7	21.7 AUS
UNKNOWN	7	167.7	5.5 US
UNKNOWN	8	196.7	254.3 AUS

PHOTOVAC




STOP 236.8
 SAMPLE LIBRARY 1 AUG 16 1990 9:48
 ANALYSIS # 7 LUZ SOLAR
 INTERNAL TEMP 35 AUGAS STANDARD
 GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	4.4	10.0 AUS
UNKNOWN	2	13.1	2.7 US
BENZENE	3	19.3	2.000 PPM
BENZENE	4	27.5	2.936 PPM
BENZENE	5	35.3	14.74 PPM
TOLUENE	6	71.6	47.39 PPM
TOLUENE	7	122.3	1.033 PPM
TOLUENE	8	163.5	3.055 PPM

Multiple System Blanks
 Run After Augas Std
 to achieve relatively
 clean blank - 10 blanks
 run before SV-1 probe
 blank. TW


PHOTOVAC



STOP 0 247.1
 SAMPLE LIBRARY 1 AUG 10 1990 10:32
 ANALYSIS 8 18 LUZ SOLAR
 INTERNAL TEMP 33 PROBE BLANK
 GAIN 10 SV-1

COMPOUND NAME	PEAK	R.T.	AREA/PPM
BENZENE	3	20.8	114.8 PPM
BENZENE	4	33.7	10.83 PPM
TOLUENE	6	71.7	1.775 PPM
TOLUENE	7	124.9	22.71 PPM
TOLUENE	8	160.5	134.3 PPM

PHOTOVAC



STOP 8 348.4

SAMPLE LIBRARY 1 AUG 18 1998 18:42


ANALYSIS 8 13 LUZ SOLAR

INTERNAL TEMP 39 ~~PROBE BLANK~~ SV-1

GAIN 18

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	2	10.2	1.7 US
BENZENE	3	18.7	572.4 PPM
BENZENE	4	28.3	888.9 PPM
BENZENE	5	27.1	1.844 PPM
BENZENE	6	33.5	12.71 PPM
TOLUENE	7	58.4	28.83 PPM
TOLUENE	9	159.7	978.9 PPM
TOLUENE	10	180.7	5.883 PPM


PHOTOLAC



STOP @ 324.1
 SAMPLE LIBRARY 1 AUG 16 1958 10:52
 ANALYSIS # 21 LUZ SOLAR
 INTERNAL TEMP 48 SYST BLANK
 GAIN 10

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	2	14.6	27.8 AUS
BENZENE	4	27.7	182.4 PPB
BENZENE	5	32.9	11.42 PPB
TOLUENE	7	78.5	1.888 PPM
TOLUENE	8	124.9	18.28 PPB
TOLUENE	9	155.1	319.6 PPB


PHOTOVAC



STOP 8 105.0
 SAMPLE LIBRARY 1 AUG 10 1330 11: 3
 ANALYSIS 8 23 LUZ SOLAR
 INTERNAL TEMP 42 SU-2
 GAIN 10 SAMPLE

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	5.0	9.3 MUS
UNKNOWN	2	14.3	18.0 MUS
BENZENE	4	30.0	150.0 PPD
TOLUENE	6	60.1	302.7 PPD
TOLUENE	9	124.9	22.38 PPD
TOLUENE	10	151.9	34.00 PPD

PHOTOCUAC




STOP 0 156.0
 SAMPLE LIBRARY 1 AUG 16 1990 11:13
 ANALYSIS # 24 LUZ SOLAR
 INTERNAL TEMP 43 30-3
 GAIN 10 BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	5.7	7.1 MUS
UNKNOWN	3	14.3	61.7 MUS
BENZENE	5	26.5	224.9 PPM
BENZENE	6	36.3	776.7 PPM
TOLUENE	7	66.4	2,224 PPM
TOLUENE	8	125.1	17.96 PPM
TOLUENE	9	146.7	18.43 PPM

CHANGE (previous
Probes changed
probe)

PHOTOVAC

Possible
System
Contam.



STOP 8 187.9
SAMPLE LIBRARY 1 AUG 10 1958 11:28
ANALYSIS # 25 LUT SOLAR
INTERNAL TEMP 44 SU-3
GAIN 10 BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	2	14.2	178.1 MUS
BENZENE	3	28.4	181.9 PPS
BENZENE	4	28.8	7.338 PPS
BENZENE	5	35.8	485.3 PPS
TOLUENE	6	64.8	2.968 PPM
TOLUENE	8	124.9	18.38 PPS
TOLUENE	9	143.9	283.6 PPS

PHOTOVAC




STOP 8 202.9
 SAMPLE LIBRARY 1 AUG 16 1998 11:28
 ANALYSIS # 28 LUZ SOLAR
 INTERNAL TEMP 44 SU-3
 GAIN 10 SAMPLE

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	0.0	0.5 AUS
UNKNOWN	2	14.1	10.3 AUS
BENZENE	4	29.1	305.2 PPM
BENZENE	5	30.7	33.42 PPM
TOLUENE	9	63.4	280.3 PPM
TOLUENE	11	124.5	16.33 PPM

Blank on probe used
for SU-3 (1st use of this probe)



PHOTOLAC




STOP 8 196.1
SAMPLE LIBRARY 1 AUG 16 1990 11:34
ANALYSIS # 27 LUZ SOLAR
INTERNAL TEMP 45 SU-4
GAIN 10 BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPH
UNKNOWN	2	13.9	447.8 nUS
BENZENE	3	18.2	358.8 PPH
BENZENE	4	24.5	517.8 PPH
BENZENE	5	34.3	3.008 PPH
TOLUENE	6	68.2	5.614 PPH
TOLUENE	7	135.9	386.2 PPH

Change
Probe

Syst Blanky

START



```

-----
STOP @ 152.3
SAMPLE LIBRARY 1 AUG 16 1992 11:39
ANALYSIS # 28 LUZ SOLAR
INTERNAL TEMP 47 SU-4
GAIN 10 BLANK (system)

```

COMPOUND NAME	PEAK	R.T.	AREA/PTH
UNKNOWN	4	11.3	36.8 MUS
UNKNOWN	5	13.9	125.2 MUS
BENZENE	6	33.5	559.3 PPD
TOLUENE	7	59.7	1.134 PPD
TOLUENE	9	125.1	2.521 PPD
TOLUENE	10	132.9	55.23 PPD


PHOTOVAC



STOP @ 281.8
 SAMPLE LIBRARY 1 AUG 10 1998 11:44
 ANALYSIS # 29 LUZ SOLAR
 INTERNAL TEMP 47 SU-4
 GAIN 18 BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	5.9	6.2 MUS
UNKNOWN	3	13.8	23.5 MUS
BENZENE	4	28.6	154.4 PPM
TOLUENE	7	58.8	458.5 PPM
TOLUENE	11	124.9	21.18 PPM
TOLUENE	12	130.3	2.291 PPM


PHOTO COPY



STOP @ 201.8
 SAMPLE LIBRARY 1 AUG 16 1998 11:44
 ANALYSIS # 29 LUZ SOLAR
 INTERNAL TEMP 47 SU-4
 GAIN 10 BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPH
UNKNOWN	1	5.9	5.2 MUS
UNKNOWN	3	13.8	23.5 MUS
BENZENE	4	28.8	134.4 PPH
TOLUENE	7	58.8	438.5 PPH
TOLUENE	11	124.9	21.18 PPH
TOLUENE	12	138.3	7.731 PPH

PHOTOLOG



STOP # 243.7
 SAMPLE LIBRARY 1 AUG 16 1998 11:58
 ANALYSIS # 00 LUZ SOLAR
 INTERNAL TEMP 47 SU-4
 GAIN 10 ~~BLANK~~ Sample


COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	2	11.8	2.1 μ S
UNKNOWN	3	13.8	34.1 μ S
BENZENE	4	32.1	669.5 PPM
TOLUENE	5	52.4	588.4 PPM
TOLUENE	10	124.9	87.86 PPM

START

1 2 3 4 5 6 7 8 9 10 11 12

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	5.7	8.7 MUS
UNKNOWN	2	12.9	57.8 MUS
UNKNOWN	3	13.7	138.7 MUS
BENZENE	4	19.8	111.9 PPM
BENZENE	5	22.2	688.9 PPM
TOLUENE	6	56.1	1.248 PPM
TOLUENE	10	124.9	168.9 PPM


PHOTONAC



STOP 8 235.8
 SAMPLE LIBRARY 1 AUG 16 1998 12:1
 ANALYSIS 8 32 LUZ SOLAR
 INTERNAL TEMP 42 SU-5
 GAIN 10 SAMPLE

COMPOUND NAME	PEAK	R.T.	AREA/PPH
UNKNOWN	3	13.6	38.6 MUS
BENZENE	4	31.8	154.3 PPH
BENZENE	5	54.9	425.9 PPH
TOLUENE	9	124.9	21.75 PPH


PHOTOGRAPH



STOP 8 268.1
 SAMPLE LIBRARY 1 AUG 18 1998 12:10
 ANALYSIS 8. 33 LUZ SOLAR
 INTERNAL TEMP 57 SU-8
 GAIN 18 BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	4	10.9	88.9 AUS
UNKNOWN	5	13.8	95.5 AUS
BENZENE	6	31.1	582.1 PPM
BENZENE	7	54.2	476.7 PPM
TOLUENE	9	122.9	4.532 PPM

PPCTOL 13



STOP @ 296.5
 SAMPLE LIBRARY 1 AUG 18 1998 12:18
 ANALYSIS # 34 LUZ SOLAR
 INTERNAL TEMP 49 SU-8
 GAIN 18 SAMPLE


COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	6.9	16.5 AUS
UNKNOWN	2	13.7	42.3 AUS
BENZENE	3	23.6	127.6 PPM
BENZENE	4	32.6	287.6 PPM
TOLUENE	7	124.7	16.23 PPM



STOP 189.3
 SAMPLE LIBRARY 1 AUG 16 1990 12:23
 ANALYSIS 35 LUZ SOLAR
 INTERNAL TEMP 52 SU-7
 GAIN 10 BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	6.8	14.8 MUS
UNKNOWN	2	10.4	10.7 MUS
UNKNOWN	3	13.6	63.2 MUS
BENZENE	4	29.5	468.0 PPM
BENZENE	5	31.1	588.4 PPM
TOLUENE	10	124.9	14.51 PPM

PHOTOGRAPH



STOP 0 278.2

SAMPLE LIBRARY 1 AUG 16 1958 12:02


ANALYSIS 4 36 LUZ SOLAR

INTERNAL TEMP 52 SU-7

GAIN 10 SAMPLE

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	6.9	15.8 MUS
UNKNOWN	2	13.6	99.7 MUS
BENZENE	3	29.1	538.8 PPM
BENZENE	4	58.3	471.5 PPM
TOLUENE	6	103.5	5.238 PPM
TOLUENE	7	124.9	28.18 PPM


PHOTOGRAPH



STOP 0 194.2
 SAMPLE LIBRARY 1 AUG 18 1990 12:38
 ANALYSIS 8 37 LUZ SOLAR
 INTERNAL TEMP 53 SU-8
 GAIN 10 BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	6.3	13.0 MUS
UNKNOWN	2	10.4	344.2 MUS
UNKNOWN	3	13.2	215.7 MUS
BENZENE	4	19.1	99.99 PPB
BENZENE	5	20.2	12.62 PPB
BENZENE	6	23.2	489.5 PPB
TOLUENE	10	24.9	40.76 PPB


PHOTOGRAPH



STOP 8 338.7
 SAMPLE LIBRARY 1 AUG 10 1990 12:45
 ANALYSIS 8 38 LUZ SOLAR
 INTERNAL TEMP 51 SU-8
 GAIN 10 SAMPLE

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	8.1	15.7 AUS
UNKNOWN	2	10.4	138.7 AUS
BENZENE	3	25.6	237.9 PPB
BENZENE	4	42.9	237.4 PPB
TOLUENE	5	102.2	5.150 PPB
TOLUENE	7	124.7	35.52 PPB


PHOTOGRAPH



STOP @ 204.3
 SAMPLE LIBRARY 1 AUG 16 1999 13:25
 ANALYSIS @ 09 LUZ SOLAR
 INTERNAL TEMP 45 SU-9
 GAIN 10 BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	2	10.3	438.8 AUS
UNKNOWN	3	10.3	105.9 AUS
BENZENE	5	21.0	4.373 PPM
BENZENE	6	25.4	15.87 PPM
BENZENE	7	47.3	188.5 PPM
TOLUENE	12	124.5	4.818 PPM

PHOTOGRAPH



STOP @ 383.3
 SAMPLE LIBRARY 1 AUG 18 1998 13:35
 ANALYSIS # 48 LUZ SOLAR
 INTERNAL TEMP 43 SU-9
 GAIN 10 SAMPLE

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	3	10.4	7.2 MUS
UNKNOWN	4	13.8	13.6 MUS
BENZENE	5	20.9	27.23 PPM
BENZENE	6	40.8	143.2 PPM
TOLUENE	11	124.7	4.721 PPM

PHOTOVAC

START 8 132



STOP 8 139.2

SAMPLE LIBRARY 1 AUG 10 1990 13:39


ANALYSIS 8 41 LUZ SOLAR

INTERNAL TEMP 47 SU-10

GAIN 10 BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	2	18.4	291.6 AUS
UNKNOWN	3	13.3	92.5 AUS
BENZENE	5	27.2	93.71 PPM
BENZENE	6	29.6	29.35 PPM
BENZENE	7	49.4	145.0 PPM


PHOTOGRAPH



STOP 2 213.4
 SAMPLE LIBRARY 1 AUG 16 1990 13:44
 ANALYSIS 2 42 LUZ SOLAR
 INTERNAL TEMP 40 SU-10
 GAIN 10 SAMPLE

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	3	13.7	11.0 AUS
BENZENE	4	29.3	120.0 PPM
BENZENE	5	31.3	17.44 PPM
BENZENE	8	43.8	8.870 PPM
TOLUENE	15	124.9	5.392 PPM

PHOTONAC



STOP 8 287.4
 SAMPLE LIBRARY 1 AUG 16 1998 13:58
 ANALYSIS 4 43 LUZ SOLAR
 INTERNAL TEMP 47 SU-11
 GAIN 18 BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNIDENTIFIED	4	10.7	34.7 MUS
BENZENE	5	38.2	117.3 PPS
BENZENE	6	58.5	314.8 PPS

PHOTOCOPY

START 1..1

15

16

2

● ●

15

18



STOP 250.6

SAMPLE LIBRARY 1 AUG 16 1998 10:55

ANALYSIS 8 44 LUZ SOLAR

INTERNAL TEMP 47 SU-11

GAIN	10	SAMPLE
------	----	--------

COMPOUND NAME	PEAK	R. T.	AREA/PPM
---------------	------	-------	----------


UNION LIN 4 13.6 42.5 MUS

BENZENE	5	29.1	43.40	PPB
---------	---	------	-------	-----

BENZENE	5	29.1	43.48	PPD
BENZENE	6	50.7	129.7	PPD

PHOTOKAC

START 8.2



STOP 8 164.8

SAMPLE LIBRARY 1 AUG 16 1998 14:1

ANALYSIS # 49 LUZ SOLAR

INTERNAL TEMP 49 SU-12

GAIN 10 BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
---------------	------	------	----------

UNKNOWN	3	10.5	100.9 AUS
---------	---	------	-----------

UNKNOWN	4	13.7	81.6 AUS
---------	---	------	----------

BENZENE	5	28.7	19.35 PPB
---------	---	------	-----------

BENZENE	8	51.9	77.65 PPB
---------	---	------	-----------

START

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

STOP 0 387.9

SAMPLE LIBRARY 1 AUG 18 1998 14:11

ANALYSIS # 46 LUZ SOLAR

INTERNAL TEMP 47 SU-12

GAIN 10 SAMPLE


COMPOUND NAME	PEAK	R.T.	AREA/PPM
---------------	------	------	----------

UNKNOWN	3	13.8	20.9 AUS
---------	---	------	----------

BENZENE	5	30.8	20.12 PPB
---------	---	------	-----------

BENZENE	6	51.8	162.9 PPB
---------	---	------	-----------

PHOTOMAC



STOP 6 161.0
 SAMPLE LIBRARY 1 AUG 16 1999 14:10
 ANALYSIS # 47 LUZ SOLAR
 INTERNAL TEMP 49 SU-10
 GAIN 10 BLANK

COMPOUND NAME	PEAK	R. T.	AREA/PPM
UNKNOWN	2	10.5	621.2 AUS
UNKNOWN	3	13.9	257.6 AUS
BENZENE	4	20.5	82.33 PPM
BENZENE	5	26.2	39.65 PPM
BENZENE	6	51.3	97.35 PPM


PHOTOVAC

START 1 1

1 4
2 5
3 6
4 7
5 8
6 9
7 10
8 11
9 12
10 13
11 14
12 15
13 16
14 17
15 18
16 19
17 20
18 21
19 22
20 23
21 24
22 25
23 26
24 27
25 28
26 29
27 30
28 31
29 32
30 33
31 34
32 35
33 36
34 37
35 38
36 39
37 40
38 41
39 42
40 43
41 44
42 45
43 46
44 47
45 48
46 49
47 50
48 51
49 52
50 53
51 54
52 55
53 56
54 57
55 58
56 59
57 60
58 61
59 62
60 63
61 64
62 65
63 66
64 67
65 68
66 69
67 70
68 71
69 72
70 73
71 74
72 75
73 76
74 77
75 78
76 79
77 80
78 81
79 82
80 83
81 84
82 85
83 86
84 87
85 88
86 89
87 90
88 91
89 92
90 93
91 94
92 95
93 96
94 97
95 98
96 99
97 100
98 101
99 102
100 103
101 104
102 105
103 106
104 107
105 108
106 109
107 110
108 111
109 112
110 113
111 114
112 115
113 116
114 117
115 118
116 119
117 120
118 121
119 122
120 123
121 124
122 125
123 126
124 127
125 128
126 129
127 130
128 131
129 132
130 133
131 134
132 135
133 136
134 137
135 138
136 139
137 140
138 141
139 142
140 143
141 144
142 145
143 146
144 147
145 148
146 149
147 150
148 151
149 152
150 153
151 154
152 155
153 156
154 157
155 158
156 159
157 160
158 161
159 162
160 163
161 164
162 165
163 166
164 167
165 168
166 169
167 170
168 171
169 172
170 173
171 174
172 175
173 176
174 177
175 178
176 179
177 180
178 181
179 182
180 183
181 184
182 185
183 186
184 187
185 188
186 189
187 190
188 191
189 192
190 193
191 194
192 195
193 196
194 197
195 198
196 199
197 200
198 201
199 202
200 203
201 204
202 205
203 206
204 207
205 208
206 209
207 210
208 211
209 212
210 213
211 214
212 215
213 216
214 217
215 218
216 219
217 220
218 221
219 222
220 223
221 224
222 225
223 226
224 227
225 228
226 229
227 230
228 231
229 232
230 233
231 234
232 235
233 236
234 237
235 238
236 239
237 240
238 241
239 242
240 243
241 244
242 245
243 246
244 247
245 248
246 249
247 250
248 251
249 252
250 253
251 254
252 255
253 256
254 257
255 258
256 259
257 260
258 261
259 262
260 263
261 264
262 265
263 266
264 267
265 268
266 269
267 270
268 271
269 272
270 273
271 274
272 275
273 276
274 277
275 278
276 279
277 280
278 281
279 282
280 283
281 284
282 285
283 286
284 287
285 288
286 289
287 290
288 291
289 292
290 293
291 294
292 295
293 296
294 297
295 298
296 299
297 300
298 301
299 302
300 303
301 304
302 305
303 306
304 307
305 308
306 309
307 310
308 311
309 312
310 313
311 314
312 315
313 316
314 317
315 318
316 319
317 320
318 321
319 322
320 323
321 324
322 325
323 326
324 327
325 328
326 329
327 330
328 331
329 332
330 333
331 334
332 335
333 336
334 337
335 338
336 339
337 340
338 341
339 342
340 343
341 344
342 345
343 346
344 347
345 348
346 349
347 350
348 351
349 352
350 353
351 354
352 355
353 356
354 357
355 358
356 359
357 360
358 361
359 362
360 363
361 364
362 365
363 366
364 367
365 368
366 369
367 370
368 371
369 372
370 373
371 374
372 375
373 376
374 377
375 378
376 379
377 380
378 381
379 382
380 383
381 384
382 385
383 386
384 387
385 388
386 389
387 390
388 391
389 392
390 393
391 394
392 395
393 396
394 397
395 398
396 399
397 400
398 401
399 402
400 403
401 404
402 405
403 406
404 407
405 408
406 409
407 410
408 411
409 412
410 413
411 414
412 415
413 416
414 417
415 418
416 419
417 420
418 421
419 422
420 423
421 424
422 425
423 426
424 427
425 428
426 429
427 430
428 431
429 432
430 433
431 434
432 435
433 436
434 437
435 438
436 439
437 440
438 441
439 442
440 443
441 444
442 445
443 446
444 447
445 448
446 449
447 450
448 451
449 452
450 453
451 454
452 455
453 456
454 457
455 458
456 459
457 460
458 461
459 462
460 463
461 464
462 465
463 466
464 467
465 468
466 469
467 470
468 471
469 472
470 473
471 474
472 475
473 476
474 477
475 478
476 479
477 480
478 481
479 482
480 483
481 484
482 485
483 486
484 487
485 488
486 489
487 490
488 491
489 492
490 493
491 494
492 495
493 496
494 497
495 498
496 499
497 500
498 501
499 502
500 503
501 504
502 505
503 506
504 507
505 508
506 509
507 510
508 511
509 512
510 513
511 514
512 515
513 516
514 517
515 518
516 519
517 520
518 521
519 522
520 523
521 524
522 525
523 526
524 527
525 528
526 529
527 530
528 531
529 532
530 533
531 534
532 535
533 536
534 537
535 538
536 539
537 540
538 541
539 542
540 543
541 544
542 545
543 546
544 547
545 548
546 549
547 550
548 551
549 552
550 553
551 554
552 555
553 556
554 557
555 558
556 559
557 560
558 561
559 562
560 563
561 564
562 565
563 566
564 567
565 568
566 569
567 570
568 571
569 572
570 573
571 574
572 575
573 576
574 577
575 578
576 579
577 580
578 581
579 582
580 583
581 584
582 585
583 586
584 587
585 588
586 589
587 590
588 591
589 592
590 593
591 594
592 595
593 596
594 597
595 598
596 599
597 600
598 601
599 602
600 603
601 604
602 605
603 606
604 607
605 608
606 609
607 610
608 611
609 612
610 613
611 614
612 615
613 616
614 617
615 618
616 619
617 620
618 621
619 622
620 623
621 624
622 625
623 626
624 627
625 628
626 629
627 630
628 631
629 632
630 633
631 634
632 635
633 636
634 637
635 638
636 639
637 640
638 641
639 642
640 643
641 644
642 645
643 646
644 647
645 648
646 649
647 650
648 651
649 652
650 653
651 654
652 655
653 656
654 657
655 658
656 659
657 660
658 661
659 662
660 663
661 664
662 665
663 666
664 667
665 668
666 669
667 670
668 671
669 672
670 673
671 674
672 675
673 676
674 677
675 678
676 679
677 680
678 681
679 682
680 683
681 684
682 685
683 686
684 687
685 688
686 689
687 690
688 691
689 692
690 693
691 694
692 695
693 696
694 697
695 698
696 699
697 700
698 701
699 702
700 703
701 704
702 705
703 706
704 707
705 708
706 709
707 710
708 711
709 712
710 713
711 714
712 715
713 716
714 717
715 718
716 719
717 720
718 721
719 722
720 723
721 724
722 725
723 726
724 727
725 728
726 729
727 730
728 731
729 732
730 733
731 734
732 735
733 736
734 737
735 738
736 739
737 740
738 741
739 742
740 743
741 744
742 745
743 746
744 747
745 748
746 749
747 750
748 751
749 752
750 753
751 754
752 755
753 756
754 757
755 758
756 759
757 760
758 761
759 762
760 763
761 764
762 765
763 766
764 767
765 768
766 769
767 770
768 771
769 772
770 773
771 774
772 775
773 776
774 777
775 778
776 779
777 780
778 781
779 782
780 783
781 784
782 785
783 786
784 787
785 788
786 789
787 790
788 791
789 792
790 793
791 794
792 795
793 796
794 797
795 798
796 799
797 800
798 801
799 802
800 803
801 804
802 805
803 806
804 807
805 808
806 809
807 810
808 811
809 812
810 813
811 814
812 815
813 816
814 817
815 818
816 819
817 820
818 821
819 822
820 823
821 824
822 825
823 826
824 827
825 828
826 829
827 830
828 831
829 832
830 833
831 834
832 835
833 836
834 837
835 838
836 839
837 840
838 841
839 842
840 843
841 844
842 845
843 846
844 847
845 848
846 849
847 850
848 851
849 852
850 853
851 854
852 855
853 856
854 857
855 858
856 859
857 860
858 861
859 862
860 863
861 864
862 865
863 866
864 867
865 868
866 869
867 870
868 871
869 872
870 873
871 874
872 875
873 876
874 877
875 878
876 879
877 880
878 881
879 882
880 883
881 884
882 885
883 886
884 887
885 888
886 889
887 890
888 891
889 892
890 893
891 894
892 895
893 896
894 897
895 898
896 899
897 900
898 901
899 902
900 903
901 904
902 905
903 906
904 907
905 908
906 909
907 910
908 911
909 912
910 913
911 914
912 915
913 916
914 917
915 918
916 919
917 920
918 921
919 922
920 923
921 924
922 925
923 926
924 927
925 928
926 929
927 930
928 931
929 932
930 933
931 934
932 935
933 936
934 937
935 938
936 939
937 940
938 941
939 942
940 943
941 944
942 945
943 946
944 947
945 948
946 949
947 950
948 951
949 952
950 953
951 954
952 955
953 956
954 957
955 958
956 959
957 960
958 961
959 962
960 963
961 964
962 965
963 966
964 967
965 968
966 969
967 970
968 971
969 972
970 973
971 974
972 975
973 976
974 977
975 978
976 979
977 980
978 981
979 982
980 983
981 984
982 985
983 986
984 987
985 988
986 989
987 990
988 991
989 992
990 993
991 994
992 995
993 996
994 997
995 998
996 999
997 1000
998 1001
999 1002
1000 1003
1001 1004
1002 1005
1003 1006
1004 1007
1005 1008
1006 1009
1007 1010
1008 1011
1009 1012
1010 1013
1011 1014
1012 1015
1013 1016
1014 1017
1015 1018
1016 1019
1017 1020
1018 1021
1019 1022
1020 1023
1021 1024
1022 1025
1023 1026
1024 1027
1025 1028
1026 1029
1027 1030
1028 1031
1029 1032
1030 1033
1031 1034
1032 1035
1033 1036
1034 1037
1035 1038
1036 1039
1037 1040
1038 1041
1039 1042
1040 1043
1041 1044
1042 1045
1043 1046
1044 1047
1045 1048
1046 1049
1047 1050
1048 1051
1049 1052
1050 1053
1051 1054
1052 1055
1053 1056
1054 1057
1055 1058
1056 1059
1057 1060
1058 1061
1059 1062
1060 1063
1061 1064
1062 1065
1063 1066
1064 1067
1065 1068
1066 1069
1067 1070
1068 1071
1069 1072
1070 1073
1071 1074
1072 1075
1073 1076
1074 1077
1075 1078
1076 1079
1077 1080
1078 1081
1079 1082
1080 1083
1081 1084
1082 1085
1083 1086
1084 1087
1085 1088
1086 1089
1087 1090
1088 1091
1089 1092
1090 1093
1091 1094
1092 1095
1093 1096
1094 1097
1095 1098
1096 1099
1097 1100
1098 1101
1099 1102
1100 1103
1101 1104
1102 1105
1103 1106
1104 1107
1105 1108
1106 1109
1107 1110
1108 1111
1109 1112
1110 1113
1111 1114
1112 1115
1113 1116
1114 1117
1115 1118
1116 1119
1117 1120
1118 1121
1119 1122
1120 1123
1121 1124
1122 1125
1123 1126
1124 1127
1125 1128
1126 1129
1127 1130
1128 1131
1129 1132
1130 1133
1131 1134
1132 1135
1133 1136
1134 1137
1135 1138
1136 1139
1137 1140
1138 1141
1139 1142
1140 1143
1141 1144
1142 1145
1143 1146
1144 1147
1145 1148
1146 1149
1147 1150
1148 1151
1149 1152
1150 1153
1151 1154
1152 1155
1153 1156
1154 1157
1155 1158
1156 1159
1157 1160
1158 1161
1159 1162
1160 1163
1161 1164
1162 1165
1163 1166
1164 1167
1165 1168
1166 1169
1167 1170
1168 1171
1169 1172
1170 1173
1171 1174
1172 1175
1173 1176
1174 1177
1175 1178
1176 1179
1177 1180
1178 1181
1179 1182
1180 1183
1181 1184
1182 1185
1183 1186
1184 1187
1185 1188
1186 1189
1187 1190
1188 1191
1189 1192
1190 1193
1191 1194
1192 1195
1193 1196
1194 1197
1195 1198
1196 1199
1197 1200
1198 1201
1199 1202
1200 1203
1201 1204
1202 1205
1203 1206
1204 1207
1205 1208
1206 1209
1207 1210
1208 1211
1209 1212
1210 1213
1211 1214
1212 1215
1213 1216
1214 1217
1215 1218
1216 1219
1217 1220
1218 1221
1219 1222
1220 1223
1221 1224
1222 1225
1223 1226
1224 1227
1225 1228
1226 1229
1227 1230
1228 1231
1229 1232
1230 1233
1231 1234
1232 1235
1233 1236
1234 1237
1235 1238
1236 1239
1237 1240
1238 1241
1239 1242
1240 1243
1241 1244
1242 1245
1243 1246
1244 1247
1245 1248
1246 1249
1247 1250
1248 1251
1249 1252
1250 1253
1251 1254
1252 1255
1253 1256
1254 1257
1255 1258
1256 1259
1257 1260
1258 1261
1259 1262
1260 1263
1261 1264
1262 1265
1263 1266
1264 1267
1265 1268
1266 1269
1267 1270
1268 1271
1269 1272
1270 1273
1271 1274
1272 1275
1273 1276
1274 1277
1275 1278
1276 1279
1277 1280
1278 1281
1279 1282
1280 1283
1281 1284
1282 1285
1283 1286
1284 1287
1285 1288
1286 1289
1287 1290
1288 1291
1289 1292
1290 1293
1291 1294
1292 1295
1293 1296
1294 1297
1295 1298
1296 1299
1297 1300
1298 1301
1299 1302
1300 1303
1301 1304
1302 1305
1303 1306
1304 1307
1305 1308
1306 1309
1307 1310
1308 1311
1309 1312
1310 1313
1311 1314
1312 1315
1313 1316
1314 1317
1315 1318
1316 131

PERFORMANCE

START




STOP 231.5
 SAMPLE LIBRARY 1 AUG 16 1990 14:27
 ANALYSIS # 49 LUT SOLAR
 INTERNAL TEMP 40 SU-14
 GAIN 10 BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	8.8	6.5 μS
UNKNOWN	2	10.8	7.3 μS
UNKNOWN	3	13.8	26.2 μS
BENZENE	4	15.8	7.834 PPM
BENZENE	8	50.2	58.85 PPM
TOLUENE	11	124.5	8.476 PPM

#

PHOTOCAL

START



STOP 0 222.2

SAMPLE LIBRARY 1 AUG 18 1950 14:37
 ANALYSIS # 51 LUZ SOLAR
 INTERNAL TEMP 51 SU-15
 GAIN 10 BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	7.0	6.1 AUS
UNKNOWN	2	10.4	152.1 AUS
UNKNOWN	3	13.4	92.1 AUS
BENZENE	4	20.4	10.30 PPB
BENZENE	5	26.1	11.94 PPB
BENZENE	6	50.5	30.17 PPB
TOLUENE	10	124.9	10.37 PPB

ELECTROVAC

START 1 1

AUG 16 1958 14:39
INTERNAL BATTERIES LOW, POWER OFF
AC OPERATION REQUIRED

START

1
2
3
4
5
6
7
8

STOP 146.0

SAMPLE LIBRARY 1 AUG 16 1998 14:43

ANALYSIS # 1 007 SOLAR

INTERNAL TEMP 50 SU-15

GAIN 10 BLANK

COMPOUND NAME	PEAK	R.T.	AREA/PPM
---------------	------	------	----------

UNKNOWN	2	13.4	29.5 AUS
---------	---	------	----------

BENZENE	4	25.8	23.00 PPM
---------	---	------	-----------

BENZENE	6	48.2	3.138 PPM
---------	---	------	-----------

TOLUENE	8	124.9	7.668 PPM
---------	---	-------	-----------

START 8 1

8 3
8 4
8 5
8 6
8 7
8 8
8 9

STOP 8 208.5

SAMPLE LIBRARY 1 AUG 16 1990 14:49

ANALYSIS 8 2 LUZ SOLAR

INTERNAL TEMP 54 SU-15

GAIN 10 SAMPLE

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	3.8	7.4 AUS
UNKNOWN	2	10.5	30.8 AUS
BENZENE	3	13.8	5.894 PPM
BENZENE	4	30.8	14.18 PPM
BENZENE	5	48.3	21.31 PPM
TOLUENE	8	124.5	9.528 PPM

1407075

START

1 4
2 5
3 6
4 7
5 8
6 10

STOP 145.4

SAMPLE LIBRARY 1 AUG 16 1990 15: 1

ANALYSIS 3 LU2 SOLAR

INTERNAL TEMP 54 SU-16

GAIN 10 BLANK

COMPOUND NAME PEAK R.T. AREA/PPM

UNKNOWN	1	7.8	8.6 PPM
UNKNOWN	2	10.6	5.8 PPM
UNKNOWN	3	13.3	27.8 PPM
BENZENE	4	25.8	22.03 PPM
BENZENE	5	47.8	24.84 PPM

START

1	1
2	2
3	3
4	4
5	5
6	6
7	7
8	8
9	9
10	10
11	11
12	12
13	13
14	14
15	15
16	16
17	17
18	18
19	19
20	20
21	21
22	22
23	23

```

STOP #      295.6
SAMPLE LIBRARY 1  AUG 16 1990  15. 9
ANALYSIS #      4  LUZ SOLAR
INTERNAL TEMP 50  SU-18
GAIN          10  SAMPLE

```


COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	1	8.1	9.8 MUS
UNKNOWN	2	13.2	25.5 MUS
BENZENE	4	24.5	82.84 PPM
BENZENE	5	27.4	21.97 PPM
BENZENE	7	45.8	8.341 PPM
TOLUENE	11	124.7	5.838 PPM

REPORT

START # 1
 # 2
 # 3
 # 4
 # 5
 # 6
 # 7
 # 8
 # 9
 # 10
 # 11
 # 12

STOP # 118.6
 SAMPLE LIBRARY 1 AUG 16 1990 15:29
 ANALYSIS # 8 LUT SOLAR
 INTERNAL TEMP 56 SU-10
 GAIN 10 SAMPLE

COMPOUND NAME	PEAK	R.T.	AREA/PPM
UNKNOWN	2	13.0	6.1 MUS
BENZENE	4	22.9	15.06 PPM



STOP 0 201.9
 SAMPLE LIBRARY 1 AUG 16 1990 15:34
 ANALYSIS # 3 LUT SOLAR
 INTERNAL TEMP 50 BTEX STD
 GAIN 10 10 PPM

COMPOUND NAME	PEAK	R. T.	AREA/PPM
UNKNOWN	2	10.0	37.3 AUS
UNKNOWN	3	13.0	70.2 AUS
BENZENE	4	16.2	31.50 PPM
BENZENE	5	23.3	2.683 PPM
BENZENE	6	44.3	2.327 PPM
TOLUENE	7	51.9	4.314 PPM



SOUTHWEST GAS CORPORATION

April 29, 2009

Enviro Chek
Attn: Shirley Hibbetts
P. O. Box 355
Helendale, CA 92342

**Re: Unincorporated area-San Bernardino County-Near Hinkley CA-Parcel
numbers 0490-131-06 thru 16, 0490-161-08 thru 13, 0490-121-42 and 0490-171-09**

Dear Ms Hibbetts,

Please find enclosed Southwest Gas Corporation (SWG) facility maps which detail gas structures in your project area.

This information is provided only for design purposes. Please forward a copy of the final design drawings for this project when they are available. Possible conflicts must be field checked prior to a final solution. If a conflict in a specific site is anticipated, please contact SWG as soon as possible to allow us a minimum of 90 days to recommend a solution.

If you have any questions, please contact me at (760)951-4033.

Best Regards,

Kurt Edwards, PE
Supervisor/Engineering
Southern California Division
Kurt.Edwards@swgas.com

KBE/lgw

Table P-1. Small Quantity Hazardous Substances Onsite during Construction

Materials	CAS No.	Relative Toxicity and Hazard Class	Permissible Exposure Limit	Storage Description; Capacity	Storage Practices and Special Handling Precautions
Concrete Curing Compound	64742-95-6 95-63-6 8052-41-3 64742-82-1 1330-20-7 98-82-8 103-65-1	Moderate Toxicity; Hazard Class - NFPA 2 flammability	PEL of 8052-41-3 = 2900 mg/m ³ , 500 ppm REL of 95-63-6 = 125 mg/m ³ 150 ppm PEL for 1330-20-7 = 435 mg/m ³ , 100 ppm	Steel drum (qty-1) - 55 gallons	Construction inventory management
Krylon or similar - Fluorescent Paint 13% Propane 12% Butane 1% Hexane 9% V. M. & P. Naphtha 1% Toluene 2% Ethylbenzene 12% Xylene 15% Acetone 17% Calcium Carbonate	74-98-6 106-97-8 110-54-3 64742-89-8 108-88-3 100-41-4 1330-20-7 67-64-1 471-34-1			2 cases of 12 steel containers = 288 ounces	Inventory management per manufacturer recommendations
Hand Soap	64-17-5	Non-toxic; Hazard class - NA	None established	Plastic containers: quantity up to 45 gallons	Storage within portable wash facility locations
Herbicide Roundup® or equivalent	38641-94-0	Low toxicity; Hazard class- Irritant	Isopropylamine salt of glyphosphate = no specific occupational exposure has been established	No onsite storage, brought on site by licensed contractor, used immediately	No excess inventory stored onsite
Paint & Enamel (Rust Preventive Enamel)	74-98-6, 106-97-8, 64742-89-8, 108-88-3, 100-41-4, 1330-20-7, 67-64-1, 108-10-1			2 cases of 6 containers = 12lbs	Inventory management
Pipe Thread Compound	109-99-9 78-93-3 67-64-1 9002-86-2 108-94-1 112945-52-5			1 case = 384 ounces on site at any given time contained inside of original steel container	Contractor inventory management practices

Materials	CAS No.	Relative Toxicity and Hazard Class	Permissible Exposure Limit	Storage Description; Capacity	Storage Practices and Special Handling Precautions
Primer for PVC Pipe	78-93-3 67-64-1 109-99-9 108-94-1			1 case = 384 ounces on site at any given time contained inside of original steel container	Contractor inventory management practices
Super Butyl Concentrate	111-76-2 6834-92-0	Low toxicity Hazard class - NA	None established	< 1 gallon plastic container	Stored inside plastic container per manufacture recommendations
Tap matic - Gold / Metal cutting fluid	64742-52-5 124-38-9			Case of 6 contained in plastic containers = 192 ounces	Contractor inventory management
WD-40	64742-47-8 64742-48-9 64742-88-7 64742-65-0 64742-47-8 124-38-9	Moderate toxicity- Hazard class - Flammable aerosol	64742-47-8 PEL = 100 ppm 64742-88-7 PEL = 100 ppm 64742-65-0 PEL = 5 mg/m ³ 64742-47-8 PEL = 1200mg/m ³ 124-38-9 = 5,000 ppm	1 case of 6 in steel containers or 72 ounces	Inventory management methods per manufacture recommendations
Welding Rods / Filler Wire	7439-89-6	Low toxicity Hazard class - NA	None established	4- 50 lb boxes to equal 200 pounds; filler wire 316L 30 lbs	Construction inventory management methods

Table P-2. Large Quantity Hazardous Substances Onsite during Construction

Materials	CAS No.	Relative Toxicity and Hazard Class	Permissible Exposure Limit	Storage Description; Capacity	Storage Practices and Special Handling Precautions
Diesel Fuel	#1- 8008-20-6 #2- 68476-34-6	Low toxicity; Hazard class- Combustible liquid	PEL: none established LV: 100 mg/m ³	Carbon steel tank transported to site (2,000 gallons)	Stored only in transport vehicle
Blue Chemical Destroyer	50-00-0 87-56-1	Low toxicity Hazard class - NA	None established	Plastic containment within portable toilets: 1 part blue chemical to 20 parts water	Construction inventory management methods

Materials	CAS No.	Relative Toxicity and Hazard Class	Permissible Exposure Limit	Storage Description; Capacity	Storage Practices and Special Handling Precautions
Carbon Dioxide BOC Gases	124-38-9	Low toxicity; Hazard class - Non flammable gas	TLV: 5,000 ppm (9,000 mg/m ³) TWA	Steel Cylinder (qty-1) on-site	Used for small welding operations: Mig guns
Form Oil	530-000	Low toxicity Hazard class - NA	None established	55-gallon steel drums 1-2 drums	Contractor Inventory management for concrete formwork
Hydraulic Fluid	64742- 58-1	Low to moderate toxicity; Hazard class - Class IIIB combustible liquid	TWA (oil mist): 5 mg/m ³ STEL: 10 mg/m ³	Carbon steel tanks and sumps; 500 gallons in equipment, maintenance inventory of 110 gallons in 55- gallon steel drums	Found only in equipment with a small maintenance inventory. Maintenance inventory stored within secondary containment.
Lube Oil	64742- 55-8	Low toxicity Hazard class - NA	None established	2 cases of 10W 40 in plastic containers	Construction inventory containment in plastic containers and/or contained within transport maintenance vehicle to support equipment i.e. such as earth moving equipment.
Mineral Insulating Oil	64742- 11-6	Low toxicity Hazard class - NA	None established	Carbon steel transformers, 64,000 gal (within transformers)	Used only in transformers, secondary containment for each transformer
Natural Gas (methane)	74-82-8	Low toxicity; Hazard class - Non flammable gas	None established	No on site storage, up to 140 pounds of natural gas in equipment and piping; pressurized carbon steel pipeline for delivery to site	No storage on site. Piping will be designed to U.S. Department of Transportation (DOT) specifications; onsite facilities (gas metering) will be designed and operated to industry standards.
Nitrogen	7727-37- 9	Low toxicity; Hazard class - Non flammable gas	None established	Carbon steel tank; 7,500 pounds total inventory	Carbon steel tank with crash posts

Materials	CAS No.	Relative Toxicity and Hazard Class	Permissible Exposure Limit	Storage Description; Capacity	Storage Practices and Special Handling Precautions
Soil stabilizer (Coherex)	64742-11-6	Non-toxic; Hazard class - NA	None established	No onsite storage, supplied in 55-gallon drums or 400-gallon totes, used immediately	No excess inventory stored onsite
Praxair Stargon Gas or similar (blend of Argon, Carbon Dioxide, and Nitrogen)	74440-37-1 7782-44-7 124-38-9	Low toxicity; Hazard class- Nonflammable gas	PEL: none established besides Carbon Dioxide - 5,000 ppm	Steel cylinders; 230 cubic foot each, 3,000 cubic foot total on site	Inventory management
Therminol VP1 Diphenyl ether (73.5%) Biphenyl (26.5%)	101-84-8 92-52-4	Moderate toxicity; Hazard class - Irritant; Combustible Liquid (Class III-B)	Biphenyl= PEL: 0.2ml/m ³ (8-hr TWA) TLV: 0.2 ml/m ³ (1mg/m ³) (8-hr TWA) Diphenyl ether= TLV: 1 ml/m ³ (8-hr TWA) TLV: 2 ml/m ³ (15-min TWA) PEL: 1 ml/m ³ (7 mg/m ³) (15-min TWA)	Qty: 2,292,000 gallons	Continuous monitoring of pressure in piping network; routine inspections (sight, sound, smell) by operations staff; isolation valves throughout piping network to minimize fluid loss in the event of a leak; prompt clean up and repair. Area containment shall be in place for bulk storage.
Welding gas Acetylene	74-86-2	Moderate toxicity; Hazard class - Toxic	PEL: none established	Steel cylinders; 145 cubic foot each, 4,000 cubic foot total on site	Inventory management, isolated from incompatible chemicals
Welding gas Oxygen	7782-44-7	Low toxicity; Hazard class- Oxidizer	PEL: none established	Steel cylinders; 251 cubic foot each, 4,000 cubic foot total on site	Inventory management, isolated from incompatible cylinders and chemicals
Welding gas Argon	7440-37-1	Low toxicity; Hazard class- Nonflammable gas	PEL: none established	Steel cylinders; 248 cubic foot each, 11,904 cubic foot total on site	Inventory management

Table P-3. Small Quantity Hazardous Substances Onsite during Operations

Hazardous Material Name	Concentration	CAS No.	Quantity to be used Onsite	Reportable Quantity
Paint and paint thinners	–	–	50 gal	–
Lab reagents	–	–	10 gal	–
Lab gases	–	–	150 CF	–
Cleaning chemicals (Janitorial supplies)	–	–	20 gal	–
Welding rods	–	7439-89-6	100 lbs	–
Air Conditioning fluids	–	–	40 lbs	–
Herbicides and pesticides	–	–	5 gal	–
Office Supplies (batteries, etc)	–	–	1 cubic foot	–
Bathroom supplies – liquid soap	–	–	25 gal	–

Table P-4. Large Quantity Hazardous Substances Onsite during Operations

Hazardous Material Name	Concentration	CAS No.	Quantity to be used Onsite	Reportable Quantity
Heat Transfer Fluid: Diphenyl ether (73.5%) Biphenyl (26.5%)	73.5% 26.5%	101-84-8 92-52-4	2,292,000 gal	Diphenyl ether (N/A) Biphenyl (CERCLA) RQ = 100 lbs (=377 lbs, or 42 gal of Therminol)
Sodium Hydroxide	50% solution	1310-73-2	2,000 gal (2 tanks x 1,000 gal)	1,000 lbs
Sodium Hypochlorite	12.5% solution	7681-52-9 10022-70-5	12,000 gal (2 tanks x 6,000 gal)	100 lbs
Sulfuric Acid	29.5% solution	7664-93-9 8014-95-7	2,000 gal (in batteries)	1,000 lbs
Sulfuric Acid	93% solution	7664-93-9 8014-95-7	1,600 gal (4 x 400 gal)	1,000 lbs
ChemTreat, Inc. BL-1558 or similar 3-Methoxypropylamine Cyclohexylamine Diethoxyamine	10 – 30% 10 – 30% 1 – 5%	5332-73-0 108-91-8 3710-84-7	totes, 4 x 300 gal	N/A 10,000 lbs N/A
ChemTreat, Inc. BL-1260 or similar Carbohydrazide	5 -10%	497-18-7	totes, 4 x 300 gal	N/A
ChemTreat, Inc. CL-1432 or similar Potassium phosphate, tribasic 1-Hydroxyethylidene-1,1-diphosphonic acid, tetrapotassium salt Tetrapotassium pyrophosphate Potassium hydroxide Tolyltriazole, sodium salt	5 – 10% 0.5 – 1.5% 1 – 5% 5 – 10% 1 – 5%	7778-53-2 14860-53-8 7320-34-5 1310-58-3 64665-57-2	totes, 2 x 1,000 gal	N/A N/A N/A 1000 lbs N/A

Hazardous Material Name	Concentration	CAS No.	Quantity to be used Onsite	Reportable Quantity
ChemTreat, Inc. BL-124 or similar Sodium bisulfite	15 – 40%	7631-90-5	totes, 2 x 300 gal	5000 lbs
ChemTreat, Inc. BL-1794 or similar Trisodium phosphate		7601-54-9	Plastic totes, 2 x 300 gal	N/A
ChemTreat, Inc. BL-180 or similar Nitrous acid, sodium salt Sodium tetraborate pentahydrate	10 – 30% 1 – 5%	7632-00-0 12179-04-3	totes, 2 x 300 gal	100 lbs N/A
Natural Gas (methane)		74-82-8	No on-site storage, natural gas in equipment and piping; pressurized carbon steel pipeline for delivery to site	N/A
Gasoline	100%	86290-81-5	1,000 – 2,000 gal (See also response to Item 36)	N/A
Water treatment chemical ChemTreat, Inc. CT-9004 or similar 1-Hydroxyethylidene-1,1-diphosphonic acid	3-7%	2809-21-4	totes, 2 x 300 gallons	N/A
Water treatment chemical ChemTreat, Inc. P-813 E or similar Petroleum distillate hydrotreated light	10-30%	64742-47-8	totes 2 x 275 gallons	N/A
Water treatment chemical ChemTreat, Inc. CL-2156 or similar 5-chloro-2-methyl-4-isothiazolin-3-one 2-methyl-4-isothiazolin-3-one Magnesium nitrate Magnesium chloride	1.11% 0.39% 1.61% 0.96%	26172-55-4 2682-20-4 10377-60-3 7786-30-3	totes 2 x 300 gallons	N/A N/A N/A N/A

Hazardous Material Name	Concentration	CAS No.	Quantity to be used Onsite	Reportable Quantity
Lube Oil		64742-55-8	5,000 gal in equipment and piping, additional maintenance inventory of up to 550 gallons in 55- gallon steel drums.	N/A
Mineral Insulating Oil		64742-53-6 68037-01-4	total onsite inventory of 64,000 gal (in transformers)	N/A
Diesel Fuel, No. 2		68476-34-6	6,500 gal tank/power island and two small Day tanks per power island 600 gal (2 x 300). Total 14,200 gal inventory.	N/A
Nitrogen		7727-37-9	37,200 gal total inventory (2 tanks x 18,600 gal)	N/A
Hydraulic fluid		64742-58-1	6,400 gallons in equipment, maintenance inventory of 220 gallons in 4 x 55-gallon steel drums	N/A
Welding gas Acetylene		74-86-2	Steel cylinders; 8 x 200 cubic foot each, 1,600 cubic foot total on site	N/A
Welding gas Oxygen		7782-44-7	Steel cylinders; 16 x 200 cubic foot each, 3,200 cubic foot total on site	N/A
Welding gas Argon		7440-37-1	Steel cylinders; 8 x 200 cubic foot each, 1,600 cubic foot total on site	N/A
Fertilizer (Bioremediation) Urea		57-13-6 1317-25-5	Stored in bags (dry pellets), 6 x 50-pound, 300 pound total inventory	N/A

Hazardous Material Name	Concentration	CAS No.	Quantity to be used Onsite	Reportable Quantity
Fertilizer (Bioremediation) Monopotassium phosphate		7778-77-0	Used in two x 1,000-lb canisters, 2,000 pounds total inventory, no additional storage	N/A
Herbicide Roundup® or equivalent (Glyphosate, isopropylamine salt)	0.96 – 50.2 wt%	38641-94-0	No onsite storage, brought on site by licensed contractor, used immediately	N/A
Soil stabilizer Coherex or similar	50-70%	64742-11-6	No onsite storage, supplied in 400-gallon totes, used immediately	N/A

APPENDIX Q

TRAFFIC

Appendix Q: Transportation

Table Q-1: Signalized Intersection Level of Service: Highway Capacity Manual Operational Analysis Method

Average Control Delay (seconds/vehicle)	Level of Service (LOS) Characteristics
<10	<i>LOS A</i> describes operations with very low delay. This occurs when progression is extremely favorable, and most vehicles do not stop at all. Short cycle lengths may also contribute to low delay.
>10– 20	<i>LOS B</i> describes operations with generally good progression and/or short cycle lengths. More vehicles stop than for LOS A, causing higher levels of average delay.
>20 – 35	<i>LOS C</i> describes operations with higher delays, which may result from fair progression and/or longer cycle lengths. Individual cycle failures may begin to appear at this level. The number of vehicles stopping is significant at this level, although many still pass through the intersection without stopping.
>35– 55	<i>LOS D</i> describes operations with high delay, resulting from some combination of unfavorable progression, long cycle lengths, or high volumes. The influence of congestion becomes more noticeable, and individual cycle failures are noticeable.
>55 – 80	<i>LOS E</i> is considered the limit of acceptable delay. Individual cycle failures are frequent occurrences.
>80	<i>LOS F</i> describes a condition of excessively high delay, considered unacceptable to most drivers. This condition often occurs when arrival flow rates exceed the LOS D capacity of the intersection. Poor progression and long cycle lengths may also be major contributing causes to such delay.

Source: 2000 Highway Capacity Manual, TRB Special Report 209

Table Q-2: Level of Service Criteria for Stop Controlled Unsignalized Intersections

Average Control Delay (sec/veh)	Level of Service (LOS)
≤10	A
>10 and ≤15	B

>15 and ≤25	C
>25 and ≤35	D
>35 and ≤50	E
>50	F

Source: 2000 Highway Capacity Manual, TRB Special Report 209

Description of the ILV capacity characteristics

Table Q-3: Ramp Junction Capacity Analysis: Near-Term Base Conditions

Ramp Junction	Peak Hour	ILV / Hour	Description
Main Street/SR-58 NB Ramps	AM	474	<1200: (Under Capacity)
	PM	558	<1200: (Under Capacity)
Main Street/SR-58 SB Ramps	AM	371	<1200: (Under Capacity)
	PM	547	<1200: (Under Capacity)


Source: Wilson & Company, Inc., Engineers & Architects; June 2009


Table Q-4: Project Trips Generation: Construction Phase – Peak Hours

Peak Period	Project Site		Park-and-Ride	
	Trips (In/Out)	PCE	Trips (In/Out)	PCE
AM (car)	300/0	300/0	169/0	169/0
AM (bus)	3/3	9/9	3/3	9/9
AM (Total)	N/A	309/9	N/A	178/9
PM (car)	0/300	0/300	0/169	0/169
PM (bus)	3/3	9/9	3/3	9/9
PM (total)	N/A	9/309	N/A	9/178

Source: Wilson & Company, Inc., Engineers & Architects; June 2009

Figure Q-1: Heavy Haul Routes





SOURCE: Wilson & Company, Inc., Engineers & Architects; June 2009

Figure 5.13-8
Near Term Base
Traffic Volumes

APPENDIX R

CORRESPONDENCE

PUBLIC UTILITIES COMMISSION

320 WEST 4TH STREET, SUITE 500
LOS ANGELES, CA 90013



July 30, 2010

Carol Hammel-Smith
U.S. Department of Energy
1000 Independence Avenue, SW
LP-10
Washington, DC 20585

Dear Ms. Hammel-Smith:

Re: SCH# 2010074001; Abengoa Solar Project

The California Public Utilities Commission (Commission) has jurisdiction over the safety of highway-rail crossings (crossings) in California. The California Public Utilities Code requires Commission approval for the construction or alteration of crossings and grants the Commission exclusive power on the design, alteration, and closure of crossings.

The Commission's Rail Crossings Engineering Section (RCES) is in receipt of the *Notice of Completion & Environmental Document Transmittal – Intent to Prepare an Environmental Assessment (EA)* from the State Clearinghouse for the proposed Abengoa Solar Project near the City of Hinkley. RCES has the following concerns:

- The proposed project site is located approximately 9 miles northwest of the City of Hinkley. There are two nearby at-grade crossings, one on SR 395 (DOT #: 028208V) and the other on SR 58 (DOT #: 028209C) that might be traversed to access to the project site. RCES staff has received numerous near miss reports from BNSF Railway Company at both locations. Also, at both highway rail crossing locations, there has also been several incidents that involve trucks.
- RCES is also concerned with the cumulative impacts of the traffic, especially with the truck traffic for both crossings. RCES in the last year has submitted comments to two solar projects near the City of Hinkley and Kramer Junction. The two RCES comment letters are attached for your reference.

RCES staff recommends that the Department of Energy include the two nearby crossings in their traffic impact and safety assessment as part of the EA and if possible propose safety measures at both crossings due to the increased truck volume. Safety measures to consider include, but are not limited to, the planning for grade separation and improvements to the existing at-grade crossings.

The Department of Energy should arrange a meeting with the Commission's RCES, and the BNSF Railway Company to discuss relevant safety issues and if necessary, file a GO 88-B application request for authority to modify an at-grade crossings. Before the schedule meeting, RCES would like to review the traffic study for the project when available.


Ms. Carol Hammel-Smith

July 30, 2010

Page 2 of 2

If you have any questions, please contact me at 213-576-1399 or email at bll@cpuc.ca.gov.

Sincerely,

A handwritten signature in black ink, appearing to read "Bill Lay", written over a horizontal dotted line.

Bill Lay, P.E.

Utilities Engineer

Rail Crossings Engineering Section

Consumer Protection & Safety Division

cc: Melvin Thomas, BNSF



DEPARTMENT OF THE ARMY

915 Wilshire Boulevard
Los Angeles, California 90017

February 26, 2010

REPLY TO
ATTENTION OF

Office of the Chief
Regulatory Division

Joshua Zinn
AECOM
1420 Kettner Boulevard, Suite 500
San Diego, California 92101

SUBJECT: Approved Jurisdictional Determination Regarding Absence of Geographic Jurisdiction

Dear Mr. Zinn:

Reference is made to your request (File No. SPL-2009-00928-SME) dated August 26, 2009, for an approved Department of the Army jurisdictional determination (JD) for the Abengoa Mojave Solar Energy project site (35.0173, -117.3058) located near the community of Lockhart, San Bernardino County, California.

As you may know, the Corps' evaluation process for determining whether or not a Department of the Army permit is needed involves two tests. If both tests are met, then a permit is required. The first test determines whether or not the proposed project is located in a water of the United States (i.e., it is within the Corps' geographic jurisdiction). The second test determines whether or not the proposed project is a regulated activity under Section 10 of the River and Harbor Act or Section 404 of the Clean Water Act. As part of the evaluation process, pertaining to the first test only, we have made the jurisdictional determination below.

Based on available information, we have determined there are no waters of the United States on the project site, in the locations depicted on the enclosed drawing. The basis for our determination can be found in the enclosed JD forms.

The aquatic resources identified as tamarisk wetlands and a playa lakebed on the above drawing are intrastate isolated waters with no apparent interstate or foreign commerce connection. As such, these waters are not currently regulated by the Corps of Engineers. This disclaimer of jurisdiction is only for Section 404 of the Clean Water Act. Other Federal, State, and local laws may apply to your activities. In particular, you may need authorization from the California State Water Resources Control Board and/or the U.S. Fish and Wildlife Service.

This letter contains an approved jurisdictional determination for the Abengoa Mojave Solar Energy project site. If you object to this decision, you may request an administrative appeal under Corps regulations at 33 CFR Part 331. Enclosed you will find a Notification of Appeal Process (NAP) fact sheet (Appendix A) and Request for Appeal (RFA) form. If you request to appeal this decision you must submit a completed RFA form to the Corps South Pacific Division Office at the following address:

Tom Cavanaugh
Administrative Appeal Review Officer,
U.S. Army Corps of Engineers
South Pacific Division, CESPD-PDS-O, 2042B
1455 Market Street, San Francisco, California 94103-1399

In order for an RFA to be accepted by the Corps, the Corps must determine that it is complete, that it meets the criteria for appeal under 33 C.F.R. Part 331.5, and that it has been received by the Division Office within 60 days of the date on the NAP. Should you decide to submit an RFA form, it must be received at the above address by April 27, 2010. It is not necessary to submit an RFA form to the Division office if you do not object to the decision in this letter.


This verification is valid for five years from the date of this letter, unless new information warrants revision of the determination before the expiration date. If you wish to submit new information regarding the approved jurisdictional determination for this site, please submit this information to Stephen Estes at the letterhead address by April 27, 2010. The Corps will consider any new information so submitted and respond within 60 days by either revising the prior determination, if appropriate, or reissuing the prior determination. A revised or reissued jurisdictional determination can be appealed as described above.

This determination has been conducted to identify the extent of the Corps' Clean Water Act jurisdiction on the particular project site identified in your request. This determination may not be valid for the wetland conservation provisions of the Food Security Act of 1985. If you or your tenant are USDA program participants, or anticipate participation in USDA programs, you should request a certified wetland determination from the local office of the Natural Resources Conservation Service, prior to starting work.

If you have any questions, please contact Stephen Estes at 213-452-3660 or via e-mail at Stephen.M.Estes@usace.army.mil.

Please be advised that you can now comment on your experience with Regulatory Division by accessing the Corps web-based customer survey form at:
<http://per2.nwp.usace.army.mil/survey.html>.

Sincerely,

A handwritten signature in black ink, appearing to read "Mark Durham". The signature is fluid and cursive, with a large, stylized "M" and "D".

Mark Durham
Chief, South Coast Branch
Regulatory Division

Enclosures

NOTIFICATION OF ADMINISTRATIVE APPEAL OPTIONS AND PROCESS AND REQUEST FOR APPEAL

Applicant: None Consultant: Joshua Zinn, AECOM	File Number: SPL-2009-00928-SME	Date: 02/26/2010
Attached is:		See Section below
<input type="checkbox"/>	INITIAL PROFFERED PERMIT (Standard Permit or Letter of permission)	A
<input type="checkbox"/>	PROFFERED PERMIT (Standard Permit or Letter of permission)	B
<input type="checkbox"/>	PERMIT DENIAL	C
<input checked="" type="checkbox"/>	APPROVED JURISDICTIONAL DETERMINATION	D
<input type="checkbox"/>	PRELIMINARY JURISDICTIONAL DETERMINATION	E

SECTION I - The following identifies your rights and options regarding an administrative appeal of the above decision. Additional information may be found at <http://usace.army.mil/inet/functions/cw/cecwo/reg> or Corps regulations at 33 CFR Part 331.

A: INITIAL PROFFERED PERMIT: You may accept or object to the permit.

- **ACCEPT:** If you received a Standard Permit, you may sign the permit document and return it to the district engineer for final authorization. If you received a Letter of Permission (LOP), you may accept the LOP and your work is authorized. Your signature on the Standard Permit or acceptance of the LOP means that you accept the permit in its entirety, and waive all rights to appeal the permit, including its terms and conditions, and approved jurisdictional determinations associated with the permit.
- **OBJECT:** If you object to the permit (Standard or LOP) because of certain terms and conditions therein, you may request that the permit be modified accordingly. You must complete Section II of this form and return the form to the district engineer. Your objections must be received by the district engineer within 60 days of the date of this notice, or you will forfeit your right to appeal the permit in the future. Upon receipt of your letter, the district engineer will evaluate your objections and may: (a) modify the permit to address all of your concerns, (b) modify the permit to address some of your objections, or (c) not modify the permit having determined that the permit should be issued as previously written. After evaluating your objections, the district engineer will send you a proffered permit for your reconsideration, as indicated in Section B below.

B: PROFFERED PERMIT: You may accept or appeal the permit.

- **ACCEPT:** If you received a Standard Permit, you may sign the permit document and return it to the district engineer for final authorization. If you received a Letter of Permission (LOP), you may accept the LOP and your work is authorized. Your signature on the Standard Permit or acceptance of the LOP means that you accept the permit in its entirety, and waive all rights to appeal the permit, including its terms and conditions, and approved jurisdictional determinations associated with the permit.
- **APPEAL:** If you choose to decline the proffered permit (Standard or LOP) because of certain terms and conditions therein, you may appeal the declined permit under the Corps of Engineers Administrative Appeal Process by completing Section II of this form and sending the form to the division engineer. This form must be received by the division engineer within 60 days of the date of this notice.

C: PERMIT DENIAL: You may appeal the denial of a permit under the Corps of Engineers Administrative Appeal Process by completing Section II of this form and sending the form to the division engineer. This form must be received by the division engineer within 60 days of the date of this notice.

D: APPROVED JURISDICTIONAL DETERMINATION: You may accept or appeal the approved JD or provide new information.

- **ACCEPT:** You do not need to notify the Corps to accept an approved JD. Failure to notify the Corps within 60 days of the date of this notice means that you accept the approved JD in its entirety, and waive all rights to appeal the approved JD.
- **APPEAL:** If you disagree with the approved JD, you may appeal the approved JD under the Corps of Engineers Administrative Appeal Process by completing Section II of this form and sending the form to the division engineer. This form must be received by the division engineer within 60 days of the date of this notice.

E: PRELIMINARY JURISDICTIONAL DETERMINATION: You do not need to respond to the Corps regarding the preliminary JD. The Preliminary JD is not appealable. If you wish, you may request an approved JD (which may be appealed), by contacting the Corps district for further instruction. Also you may provide new information for further consideration by the Corps to reevaluate the JD.

SECTION II - REQUEST FOR APPEAL or OBJECTIONS TO AN INITIAL PROFFERED PERMIT

REASONS FOR APPEAL OR OBJECTIONS: (Describe your reasons for appealing the decision or your objections to an initial proffered permit in clear concise statements. You may attach additional information to this form to clarify where your reasons or objections are addressed in the administrative record.)

ADDITIONAL INFORMATION: The appeal is limited to a review of the administrative record, the Corps memorandum for the record of the appeal conference or meeting, and any supplemental information that the review officer has determined is needed to clarify the administrative record. Neither the appellant nor the Corps may add new information or analyses to the record. However, you may provide additional information to clarify the location of information that is already in the administrative record.

POINT OF CONTACT FOR QUESTIONS OR INFORMATION:

If you have questions regarding this decision and/or the appeal process you may contact:

DISTRICT ENGINEER
Los Angeles District, Corps of Engineers
ATTN: Chief, Regulatory Division
P.O. Box 532711
Los Angeles, CA 90053-2325
Tel. (213) 452-3425


If you only have questions regarding the appeal process you may also contact:


DIVISION ENGINEER
South Pacific Division, Corps of Engineers
ATTN: Tom Cavanaugh
Administrative Appeal Review Officer,
South Pacific Division, CESPD-PDS-O, 2042B
1455 Market Street, San Francisco, California 94103-1399
Tel. (415) 503-6574

RIGHT OF ENTRY: Your signature below grants the right of entry to Corps of Engineers personnel, and any government consultants, to conduct investigations of the project site during the course of the appeal process. You will be provided a 15 day notice of any site investigation, and will have the opportunity to participate in all site investigations.

<hr/> Signature of appellant or agent.	Date:	Telephone number:
---	-------	-------------------

Administrative Appeal Process for Approved Jurisdictional Determinations





2010



1,375 607.5 0 1,375 Feet

Scale: 1 in = 16,500; 1 inch = 1,375 feet

Mojave Solar Project - Jurisdictional Delineation Report

Ref. #12080502019 Harper Lab Aberrant APC-6.0 GSK-3 β Inactivation Signaling 3 Project (optimization, 06/19/09, Angila)

APPROVED JURISDICTIONAL DETERMINATION FORM
U.S. Army Corps of Engineers

This form should be completed by following the instructions provided in Section IV of the JD Form Instructional Guidebook.

SECTION I: BACKGROUND INFORMATION

A. REPORT COMPLETION DATE FOR APPROVED JURISDICTIONAL DETERMINATION (JD): February 3, 2010

B. DISTRICT OFFICE, FILE NAME, AND NUMBER: SPL-2009-00928-SME-JD1

C. PROJECT LOCATION AND BACKGROUND INFORMATION:

State: California County/parish/borough: San Bernardino City: Lockhart
Center coordinates of site (lat/long in degree decimal format): Lat. 35.01449° N Long. -117.32124° W
Universal Transverse Mercator:

Name of nearest waterbody: Harper Dry Lake

Name of nearest Traditional Navigable Water (TNW) into which the aquatic resource flows: None (isolated)

Name of watershed or Hydrologic Unit Code (HUC): Coyote-Cuddleback Lakes Watershed (HUC 18090207)

☒ Check if map/diagram of review area and/or potential jurisdictional areas is/are available upon request.

☒ Check if other sites (e.g., offsite mitigation sites, disposal sites, etc...) are associated with this action and are recorded on a different JD form.

D. REVIEW PERFORMED FOR SITE EVALUATION (CHECK ALL THAT APPLY):

☒ Office (Desk) Determination. Date: February 1, 2010

☒ Field Determination. Date(s): January 14, 2010

SECTION II: SUMMARY OF FINDINGS

A. RHA SECTION 10 DETERMINATION OF JURISDICTION.

There Are no "navigable waters of the U.S." within Rivers and Harbors Act (RHA) jurisdiction (as defined by 33 CFR part 329) in the review area. [Required]

☐ Waters subject to the ebb and flow of the tide.

☐ Waters are presently used, or have been used in the past, or may be susceptible for use to transport interstate or foreign commerce.
Explain:

B. CWA SECTION 404 DETERMINATION OF JURISDICTION.

There Are no "waters of the U.S." within Clean Water Act (CWA) jurisdiction (as defined by 33 CFR part 328) in the review area. [Required]

1. Waters of the U.S.

a. Indicate presence of waters of U.S. in review area (check all that apply):¹

- ☐ TNWs, including territorial seas
- ☐ Wetlands adjacent to TNWs
- ☐ Relatively permanent waters² (RPWs) that flow directly or indirectly into TNWs
- ☐ Non-RPWs that flow directly or indirectly into TNWs
- ☐ Wetlands directly abutting RPWs that flow directly or indirectly into TNWs
- ☐ Wetlands adjacent to but not directly abutting RPWs that flow directly or indirectly into TNWs
- ☐ Wetlands adjacent to non-RPWs that flow directly or indirectly into TNWs
- ☐ Impoundments of jurisdictional waters
- ☐ Isolated (interstate or intrastate) waters, including isolated wetlands

b. Identify (estimate) size of waters of the U.S. in the review area:

Non-wetland waters: linear feet: width (ft) and/or acres.

Wetlands: acres.

c. Limits (boundaries) of jurisdiction based on: Pick List

Elevation of established OHWM (if known):

2. Non-regulated waters/wetlands (check if applicable):³

- ☒ Potentially jurisdictional waters and/or wetlands were assessed within the review area and determined to be not jurisdictional.
Explain: Tamarisk Scrub Wetlands #16, #18-19, and #21-30 are groundwater-fed wetlands. These waters are situated within the southwest portion of the Coyote-Cuddleback Lakes Watershed. Surface flows within the project site travel

¹ Boxes checked below shall be supported by completing the appropriate sections in Section III below.

² For purposes of this form, an RPW is defined as a tributary that is not a TNW and that typically flows year-round or has continuous flow at least "seasonally" (e.g., typically 3 months).

³ Supporting documentation is presented in Section III.F.

in a general northeast direction to Harper Dry Lake, which is an intrastate dry lake (the project area extends into Harper Dry Lake; however, the lake itself is in a construction exclusion area). Precipitation ranges from 2.23 to 2.5 inches per year. Wetland waters exist on the project site despite the dry climate, as they are hydrologically supported by groundwater. Historically, these wetlands were much more extensive. Agricultural uses on the project site created a lower groundwater table over time, reducing the quantity and quality of the wetlands. Since Harper Dry Lake is the elevational low point for the basin, it serves as the terminus for Tamarisk Scrub Wetlands #16, #18-19, and #21-30. All surface flows entering Harper Dry Lake percolate into the groundwater table. Surface waters for the Harper Dry Lake system are isolated from the Mojave River (which is located approximately 10 miles to the southeast) by higher ground surrounding the dry lake on its eastern and southern boundaries. A dry wash flows northwest from the Mojave River toward Harper Dry Lake, but only flows during extreme events, is not a relatively permanent connection between Harper Dry Lake and the Mojave River, and only flows from the Mojave River to Harper Dry Lake, NOT from Harper Dry Lake to the Mojave River. The predominant soil types in the project area are Norob-Halloran Complex and Cajon Loamy Sand (Cajon Sand), which are characterized by moderate and somewhat excessive rates of permeability, respectively. Both surface and groundwater flows from the surrounding mountain ranges are directed to Harper Dry Lake. The project site wetland waters have physical surface sheet flow connectivity and hydrologic connectivity with Harper Dry Lake. Harper Dry Lake, as the terminus for these 13 wetland waters, is NOT a TNW. Moreover, Harper Dry Lake is NOT an (a)(3) water as defined by 33 CFR 328.3. Harper Dry Lake does NOT meet criteria (a)(3)(i-iii), as it: i) DOES NOT have use for surface water recreation or other purposes by foreign or interstate travelers, ii) DOES NOT have harvesting activities of fish or shellfish that may be sold in interstate or foreign commerce, and iii) DOES NOT have surface water industrial usage by industries in interstate commerce. Lastly, Tamarisk Scrub Wetlands #16, #18-19, and #21-30 themselves are NOT (a)(3) waters as defined by 33 CFR 328.3. Therefore, since Harper Dry Lake is an isolated water without a surface water connection to commerce, these 13 wetland waters are also isolated, and additionally, have no nexus to commerce. Based on the above information, the Corps concludes that Tamarisk Scrub Wetlands #16, #18-19, and #21-30 (isolated wetlands) are NONJURISDICTIONAL waters, since the waters are NOT tributary to either a TNW or an (a)(3) water and are NOT (a)(3) waters themselves. The Corps makes such a conclusion since the waters are tributary to an isolated lake that does not qualify as a TNW or as an (a)(3) water, and since the waters also do not qualify as (a)(3) waters..

SECTION III: CWA ANALYSIS

A. TNWs AND WETLANDS ADJACENT TO TNWs

The agencies will assert jurisdiction over TNWs and wetlands adjacent to TNWs. If the aquatic resource is a TNW, complete Section III.A.1 and Section III.D.1. only; if the aquatic resource is a wetland adjacent to a TNW, complete Sections III.A.1 and 2 and Section III.D.1.; otherwise, see Section III.B below.

1. TNW

Identify TNW:

Summarize rationale supporting determination:

2. Wetland adjacent to TNW

Summarize rationale supporting conclusion that wetland is "adjacent":

B. CHARACTERISTICS OF TRIBUTARY (THAT IS NOT A TNW) AND ITS ADJACENT WETLANDS (IF ANY):

This section summarizes information regarding characteristics of the tributary and its adjacent wetlands, if any, and it helps determine whether or not the standards for jurisdiction established under *Rapanos* have been met.

The agencies will assert jurisdiction over non-navigable tributaries of TNWs where the tributaries are "relatively permanent waters" (RPWs), i.e. tributaries that typically flow year-round or have continuous flow at least seasonally (e.g., typically 3 months). A wetland that directly abuts an RPW is also jurisdictional. If the aquatic resource is not a TNW, but has year-round (perennial) flow, skip to Section III.D.2. If the aquatic resource is a wetland directly abutting a tributary with perennial flow, skip to Section III.D.4.

A wetland that is adjacent to but that does not directly abut an RPW requires a significant nexus evaluation. Corps districts and EPA regions will include in the record any available information that documents the existence of a significant nexus between a relatively permanent tributary that is not perennial (and its adjacent wetlands if any) and a traditional navigable water, even though a significant nexus finding is not required as a matter of law.

If the waterbody⁴ is not an RPW, or a wetland directly abutting an RPW, a JD will require additional data to determine if the waterbody has a significant nexus with a TNW. If the tributary has adjacent wetlands, the significant nexus evaluation must consider the tributary in combination with all of its adjacent wetlands. This significant nexus evaluation that combines, for analytical purposes, the tributary and all of its adjacent wetlands is used whether the review area identified in the JD request is the tributary, or its adjacent wetlands, or both. If the JD covers a tributary with adjacent wetlands, complete Section III.B.1 for the tributary, Section III.B.2 for any onsite wetlands, and Section III.B.3 for all wetlands adjacent to that tributary, both onsite and offsite. The determination whether a significant nexus exists is determined in Section III.C below.

1. Characteristics of non-TNWs that flow directly or indirectly into TNW

(i) General Area Conditions:

Watershed size: Pick List

Drainage area: Pick List

Average annual rainfall: _____ inches

Average annual snowfall: _____ inches

(ii) Physical Characteristics:

(a) Relationship with TNW:

☐ Tributary flows directly into TNW.

☐ Tributary flows through Pick List tributaries before entering TNW.

Project waters are Pick List river miles from TNW.

Project waters are Pick List river miles from RPW.

Project waters are Pick List aerial (straight) miles from TNW.

Project waters are Pick List aerial (straight) miles from RPW.

Project waters cross or serve as state boundaries. Explain:

Identify flow route to TNW⁵:

Tributary stream order, if known:

⁴ Note that the Instructional Guidebook contains additional information regarding swales, ditches, washes, and erosional features generally and in the arid West.

⁵ Flow route can be described by identifying, e.g., tributary a, which flows through the review area, to flow into tributary b, which then flows into TNW.

(b) General Tributary Characteristics (check all that apply):

Tributary is: ☐ Natural
☐ Artificial (man-made). Explain:
☐ Manipulated (man-altered). Explain:

Tributary properties with respect to top of bank (estimate):

Average width: feet
Average depth: feet
Average side slopes: Pick List.

Primary tributary substrate composition (check all that apply):

☐ Silts ☐ Sands ☐ Concrete
☐ Cobbles ☐ Gravel ☐ Muck
☐ Bedrock ☐ Vegetation. Type/% cover:
☐ Other. Explain:

Tributary condition/stability [e.g., highly eroding, sloughing banks]. Explain:

Presence of run/riffle/pool complexes. Explain:

Tributary geometry: Pick List

Tributary gradient (approximate average slope): %

(c) Flow:

Tributary provides for: Pick List

Estimate average number of flow events in review area/year: Pick List

Describe flow regime:

Other information on duration and volume:

Surface flow is: Pick List. Characteristics:

Subsurface flow: Pick List. Explain findings:

☐ Dye (or other) test performed:

Tributary has (check all that apply):

☐ Bed and banks
☐ OHWM⁶ (check all indicators that apply):
☐ clear, natural line impressed on the bank ☐ the presence of litter and debris
☐ changes in the character of soil ☐ destruction of terrestrial vegetation
☐ shelving ☐ the presence of wrack line
☐ vegetation matted down, bent, or absent ☐ sediment sorting
☐ leaf litter disturbed or washed away ☐ scour
☐ sediment deposition ☐ multiple observed or predicted flow events
☐ water staining ☐ abrupt change in plant community
☐ other (list):
☐ Discontinuous OHWM.⁷ Explain:

If factors other than the OHWM were used to determine lateral extent of CWA jurisdiction (check all that apply):

☐ High Tide Line indicated by: ☐ Mean High Water Mark indicated by:
☐ oil or scum line along shore objects ☐ survey to available datum;
☐ fine shell or debris deposits (foreshore) ☐ physical markings;
☐ physical markings/characteristics ☐ vegetation lines/changes in vegetation types.
☐ tidal gauges
☐ other (list):

(iii) Chemical Characteristics:

Characterize tributary (e.g., water color is clear, discolored, oily film; water quality; general watershed characteristics, etc.).

Explain:

Identify specific pollutants, if known:

⁶A natural or man-made discontinuity in the OHWM does not necessarily sever jurisdiction (e.g., where the stream temporarily flows underground, or where the OHWM has been removed by development or agricultural practices). Where there is a break in the OHWM that is unrelated to the waterbody's flow regime (e.g., flow over a rock outcrop or through a culvert), the agencies will look for indicators of flow above and below the break.

⁷Ibid.

(iv) **Biological Characteristics. Channel supports (check all that apply):**

- ☐ Riparian corridor. Characteristics (type, average width):
- ☐ Wetland fringe. Characteristics:
- ☐ Habitat for:
 - ☐ Federally Listed species. Explain findings:
 - ☐ Fish/spawn areas. Explain findings:
 - ☐ Other environmentally-sensitive species. Explain findings:
 - ☐ Aquatic/wildlife diversity. Explain findings:

2. **Characteristics of wetlands adjacent to non-TNW that flow directly or indirectly into TNW**

(i) **Physical Characteristics:**

(a) General Wetland Characteristics:

Properties:

Wetland size: acres

Wetland type. Explain:

Wetland quality. Explain:

Project wetlands cross or serve as state boundaries. Explain:

(b) General Flow Relationship with Non-TNW:

Flow is: Pick List. Explain:

Surface flow is: Pick List

Characteristics:

Subsurface flow: Pick List. Explain findings:

☐ Dye (or other) test performed:

(c) Wetland Adjacency Determination with Non-TNW:

- ☐ Directly abutting
- ☐ Not directly abutting
 - ☐ Discrete wetland hydrologic connection. Explain:
 - ☐ Ecological connection. Explain:
 - ☐ Separated by berm/barrier. Explain:

(d) Proximity (Relationship) to TNW

Project wetlands are Pick List river miles from TNW.

Project waters are Pick List aerial (straight) miles from TNW.

Flow is from: Pick List.

Estimate approximate location of wetland as within the Pick List floodplain.

(ii) **Chemical Characteristics:**

Characterize wetland system (e.g., water color is clear, brown, oil film on surface; water quality; general watershed characteristics; etc.). Explain:

Identify specific pollutants, if known:

(iii) **Biological Characteristics. Wetland supports (check all that apply):**

- ☐ Riparian buffer. Characteristics (type, average width):
- ☐ Vegetation type/percent cover. Explain:
- ☐ Habitat for:
 - ☐ Federally Listed species. Explain findings:
 - ☐ Fish/spawn areas. Explain findings:
 - ☐ Other environmentally-sensitive species. Explain findings:
 - ☐ Aquatic/wildlife diversity. Explain findings:

3. **Characteristics of all wetlands adjacent to the tributary (if any)**

All wetland(s) being considered in the cumulative analysis: Pick List

Approximately () acres in total are being considered in the cumulative analysis.

For each wetland, specify the following:

Directly abuts? (Y/N)

Size (in acres)

Directly abuts? (Y/N)

Size (in acres)

Summarize overall biological, chemical and physical functions being performed:

C. SIGNIFICANT NEXUS DETERMINATION

A significant nexus analysis will assess the flow characteristics and functions of the tributary itself and the functions performed by any wetlands adjacent to the tributary to determine if they significantly affect the chemical, physical, and biological integrity of a TNW. For each of the following situations, a significant nexus exists if the tributary, in combination with all of its adjacent wetlands, has more than a speculative or insubstantial effect on the chemical, physical and/or biological integrity of a TNW. Considerations when evaluating significant nexus include, but are not limited to the volume, duration, and frequency of the flow of water in the tributary and its proximity to a TNW, and the functions performed by the tributary and all its adjacent wetlands. It is not appropriate to determine significant nexus based solely on any specific threshold of distance (e.g. between a tributary and its adjacent wetland or between a tributary and the TNW). Similarly, the fact an adjacent wetland lies within or outside of a floodplain is not solely determinative of significant nexus.

Draw connections between the features documented and the effects on the TNW, as identified in the *Rapanos* Guidance and discussed in the Instructional Guidebook. Factors to consider include, for example:

- Does the tributary, in combination with its adjacent wetlands (if any), have the capacity to carry pollutants or flood waters to TNWs, or to reduce the amount of pollutants or flood waters reaching a TNW?
- Does the tributary, in combination with its adjacent wetlands (if any), provide habitat and lifecycle support functions for fish and other species, such as feeding, nesting, spawning, or rearing young for species that are present in the TNW?
- Does the tributary, in combination with its adjacent wetlands (if any), have the capacity to transfer nutrients and organic carbon that support downstream foodwebs?
- Does the tributary, in combination with its adjacent wetlands (if any), have other relationships to the physical, chemical, or biological integrity of the TNW?

Note: the above list of considerations is not inclusive and other functions observed or known to occur should be documented below:

1. **Significant nexus findings for non-RPW that has no adjacent wetlands and flows directly or indirectly into TNWs.** Explain findings of presence or absence of significant nexus below, based on the tributary itself, then go to Section III.D:
2. **Significant nexus findings for non-RPW and its adjacent wetlands, where the non-RPW flows directly or indirectly into TNWs.** Explain findings of presence or absence of significant nexus below, based on the tributary in combination with all of its adjacent wetlands, then go to Section III.D:
3. **Significant nexus findings for wetlands adjacent to an RPW but that do not directly abut the RPW.** Explain findings of presence or absence of significant nexus below, based on the tributary in combination with all of its adjacent wetlands, then go to Section III.D:

D. DETERMINATIONS OF JURISDICTIONAL FINDINGS. THE SUBJECT WATERS/WETLANDS ARE (CHECK ALL THAT APPLY):

1. **TNWs and Adjacent Wetlands.** Check all that apply and provide size estimates in review area:
☐ TNWs: linear feet width (ft), Or, acres.
☐ Wetlands adjacent to TNWs: acres.
2. **RPWs that flow directly or indirectly into TNWs.**
☐ Tributaries of TNWs where tributaries typically flow year-round are jurisdictional. Provide data and rationale indicating that tributary is perennial:
☐ Tributaries of TNW where tributaries have continuous flow "seasonally" (e.g., typically three months each year) are jurisdictional. Data supporting this conclusion is provided at Section III.B. Provide rationale indicating that tributary flows seasonally:

Provide estimates for jurisdictional waters in the review area (check all that apply):

☐ Tributary waters: linear feet width (ft).

☐ Other non-wetland waters: acres.

Identify type(s) of waters: .

3. Non-RPWs⁸ that flow directly or indirectly into TNWs.

- ☐ Waterbody that is not a TNW or an RPW, but flows directly or indirectly into a TNW, and it has a significant nexus with a TNW is jurisdictional. Data supporting this conclusion is provided at Section III.C.

Provide estimates for jurisdictional waters within the review area (check all that apply):

☐ Tributary waters: linear feet width (ft).

☐ Other non-wetland waters: acres.

Identify type(s) of waters: .

4. Wetlands directly abutting an RPW that flow directly or indirectly into TNWs.

- ☐ Wetlands directly abut RPW and thus are jurisdictional as adjacent wetlands.

☐ Wetlands directly abutting an RPW where tributaries typically flow year-round. Provide data and rationale indicating that tributary is perennial in Section III.D.2, above. Provide rationale indicating that wetland is directly abutting an RPW: .

☐ Wetlands directly abutting an RPW where tributaries typically flow "seasonally." Provide data indicating that tributary is seasonal in Section III.B and rationale in Section III.D.2, above. Provide rationale indicating that wetland is directly abutting an RPW: .

Provide acreage estimates for jurisdictional wetlands in the review area: acres.

5. Wetlands adjacent to but not directly abutting an RPW that flow directly or indirectly into TNWs.

- ☐ Wetlands that do not directly abut an RPW, but when considered in combination with the tributary to which they are adjacent and with similarly situated adjacent wetlands, have a significant nexus with a TNW are jurisdictional. Data supporting this conclusion is provided at Section III.C.

Provide acreage estimates for jurisdictional wetlands in the review area: acres.

6. Wetlands adjacent to non-RPWs that flow directly or indirectly into TNWs.

- ☐ Wetlands adjacent to such waters, and have when considered in combination with the tributary to which they are adjacent and with similarly situated adjacent wetlands, have a significant nexus with a TNW are jurisdictional. Data supporting this conclusion is provided at Section III.C.

Provide estimates for jurisdictional wetlands in the review area: acres.

7. Impoundments of jurisdictional waters.⁹

As a general rule, the impoundment of a jurisdictional tributary remains jurisdictional.

☐ Demonstrate that impoundment was created from "waters of the U.S.," or

☐ Demonstrate that water meets the criteria for one of the categories presented above (1-6), or

☐ Demonstrate that water is isolated with a nexus to commerce (see E below).

E. ISOLATED [INTERSTATE OR INTRA-STATE] WATERS, INCLUDING ISOLATED WETLANDS, THE USE, DEGRADATION OR DESTRUCTION OF WHICH COULD AFFECT INTERSTATE COMMERCE, INCLUDING ANY SUCH WATERS (CHECK ALL THAT APPLY):¹⁰

☐ which are or could be used by interstate or foreign travelers for recreational or other purposes.

☐ from which fish or shellfish are or could be taken and sold in interstate or foreign commerce.

☐ which are or could be used for industrial purposes by industries in interstate commerce.

☐ Interstate isolated waters. Explain: .

☐ Other factors. Explain: .

Identify water body and summarize rationale supporting determination:

⁸See Footnote # 3.

⁹To complete the analysis refer to the key in Section III.D.6 of the Instructional Guidebook.

¹⁰Prior to asserting or declining CWA jurisdiction based solely on this category, Corps Districts will elevate the action to Corps and EPA HQ for review consistent with the process described in the Corps/EPA Memorandum Regarding CWA Act Jurisdiction Following Rapanos.

Provide estimates for jurisdictional waters in the review area (check all that apply):

☐ Tributary waters: linear feet width (ft).

☐ Other non-wetland waters: acres.

Identify type(s) of waters:

☐ Wetlands: acres.

F. NON-JURISDICTIONAL WATERS, INCLUDING WETLANDS (CHECK ALL THAT APPLY):

☐ If potential wetlands were assessed within the review area, these areas did not meet the criteria in the 1987 Corps of Engineers Wetland Delineation Manual and/or appropriate Regional Supplements.

☒ Review area included isolated waters with no substantial nexus to interstate (or foreign) commerce.

☒ Prior to the Jan 2001 Supreme Court decision in "SWANCC," the review area would have been regulated based solely on the "Migratory Bird Rule" (MBR).

☐ Waters do not meet the "Significant Nexus" standard, where such a finding is required for jurisdiction. Explain:

☐ Other: (explain, if not covered above):

Provide acreage estimates for non-jurisdictional waters in the review area, where the sole potential basis of jurisdiction is the MBR factors (i.e., presence of migratory birds, presence of endangered species, use of water for irrigated agriculture), using best professional judgment (check all that apply):

☐ Non-wetland waters (i.e., rivers, streams): linear feet width (ft).

☐ Lakes/ponds: acres.

☐ Other non-wetland waters: acres. List type of aquatic resource:

☒ Wetlands: 1.633 acres.

Provide acreage estimates for non-jurisdictional waters in the review area that do not meet the "Significant Nexus" standard, where such a finding is required for jurisdiction (check all that apply):

☐ Non-wetland waters (i.e., rivers, streams): linear feet, width (ft).

☐ Lakes/ponds: acres.

☐ Other non-wetland waters: acres. List type of aquatic resource:

☐ Wetlands: acres.

SECTION IV: DATA SOURCES.

A. SUPPORTING DATA. Data reviewed for JD (check all that apply - checked items shall be included in case file and, where checked and requested, appropriately reference sources below):

☒ Maps, plans, plots or plat submitted by or on behalf of the applicant/consultant: Jurisdictional Delineation Report: Potential Jurisdictional Waters of the U.S. and State.

☒ Data sheets prepared/submitted by or on behalf of the applicant/consultant.

☐ Office concurs with data sheets/delineation report.

☒ Office does not concur with data sheets/delineation report.

☐ Data sheets prepared by the Corps:

☐ Corps navigable waters' study:

☐ U.S. Geological Survey Hydrologic Atlas:

☐ USGS NHD data.

☐ USGS 8 and 12 digit HUC maps.

☐ U.S. Geological Survey map(s). Cite scale & quad name:

☒ USDA Natural Resources Conservation Service Soil Survey. Citation: USDA. 1986. Soil Conservation Service Soil Survey of San Bernardino County California-Mojave River Area.

☐ National wetlands inventory map(s). Cite name:

☐ State/Local wetland inventory map(s):

☐ FEMA/FIRM maps:

☐ 100-year Floodplain Elevation is: (National Geodetic Vertical Datum of 1929)

☒ Photographs: ☒ Aerial (Name & Date): Juris. Delineation Report: Potential Jurisdictional Waters of the U.S. and State (2005).
or ☐ Other (Name & Date):

☐ Previous determination(s). File no. and date of response letter:

☐ Applicable/supporting case law:

☐ Applicable/supporting scientific literature:

☒ Other information (please specify): Field visit on January 14, 2010 supported this JD.

B. ADDITIONAL COMMENTS TO SUPPORT JD:

APPROVED JURISDICTIONAL DETERMINATION FORM
U.S. Army Corps of Engineers

This form should be completed by following the instructions provided in Section IV of the JD Form Instructional Guidebook.

SECTION I: BACKGROUND INFORMATION

A. REPORT COMPLETION DATE FOR APPROVED JURISDICTIONAL DETERMINATION (JD): February 3, 2010

B. DISTRICT OFFICE, FILE NAME, AND NUMBER: SPL-2009-00928-SME-JD2

C. PROJECT LOCATION AND BACKGROUND INFORMATION:

State: California County/parish/borough: San Bernardino City: Lockhart
Center coordinates of site (lat/long in degree decimal format): Lat. 35.01449° N, Long. -117.32124° W
Universal Transverse Mercator:

Name of nearest waterbody: Harper Dry Lake

Name of nearest Traditional Navigable Water (TNW) into which the aquatic resource flows: None (isolated)

Name of watershed or Hydrologic Unit Code (HUC): Coyote-Cuddleback Lakes Watershed (HUC 18090207)

☒ Check if map/diagram of review area and/or potential jurisdictional areas is/are available upon request.

☒ Check if other sites (e.g., offsite mitigation sites, disposal sites, etc...) are associated with this action and are recorded on a different JD form.

D. REVIEW PERFORMED FOR SITE EVALUATION (CHECK ALL THAT APPLY):

☒ Office (Desk) Determination. Date: February 1, 2010

☒ Field Determination. Date(s): January 14, 2010

SECTION II: SUMMARY OF FINDINGS

A. RHA SECTION 10 DETERMINATION OF JURISDICTION.

There Are no "navigable waters of the U.S." within Rivers and Harbors Act (RHA) jurisdiction (as defined by 33 CFR part 329) in the review area. [Required]

☐ Waters subject to the ebb and flow of the tide.

☐ Waters are presently used, or have been used in the past, or may be susceptible for use to transport interstate or foreign commerce.
Explain:

B. CWA SECTION 404 DETERMINATION OF JURISDICTION.

There Are no "waters of the U.S." within Clean Water Act (CWA) jurisdiction (as defined by 33 CFR part 328) in the review area. [Required]

1. Waters of the U.S.

a. Indicate presence of waters of U.S. in review area (check all that apply):¹

- ☐ TNWs, including territorial seas
- ☐ Wetlands adjacent to TNWs
- ☐ Relatively permanent waters² (RPWs) that flow directly or indirectly into TNWs
- ☐ Non-RPWs that flow directly or indirectly into TNWs
- ☐ Wetlands directly abutting RPWs that flow directly or indirectly into TNWs
- ☐ Wetlands adjacent to but not directly abutting RPWs that flow directly or indirectly into TNWs
- ☐ Wetlands adjacent to non-RPWs that flow directly or indirectly into TNWs
- ☐ Impoundments of jurisdictional waters
- ☐ Isolated (interstate or intrastate) waters, including isolated wetlands

b. Identify (estimate) size of waters of the U.S. in the review area:

Non-wetland waters: linear feet: width (ft) and/or acres.

Wetlands: acres.

c. Limits (boundaries) of jurisdiction based on: Pick List

Elevation of established OHWM (if known):

2. Non-regulated waters/wetlands (check if applicable):³

- ☒ Potentially jurisdictional waters and/or wetlands were assessed within the review area and determined to be not jurisdictional.
Explain: **Playa Lakebed #17 is a portion of Harper Dry Lake and is within the proposed project boundaries. This water is situated within the southwest portion of the Coyote-Cuddleback Lakes Watershed. Surface flows within the**

¹ Boxes checked below shall be supported by completing the appropriate sections in Section III below.

² For purposes of this form, an RPW is defined as a tributary that is not a TNW and that typically flows year-round or has continuous flow at least "seasonally" (e.g., typically 3 months).

³ Supporting documentation is presented in Section III.F.

project site travel in a general northeast direction to Harper Dry Lake, which is an intrastate dry lake (the project area extends into Harper Dry Lake; however, Playa Lakebed #17 is in a construction exclusion area). Precipitation ranges from 2.23 to 2.5 inches per year. Harper Dry Lake is the elevational low point for the basin. All surface flows entering Harper Dry Lake percolate into the groundwater table. Surface waters for the Harper Dry Lake system are isolated from the Mojave River (which is located approximately 10 miles to the southeast) by higher ground surrounding the dry lake on its eastern and southern boundaries. A dry wash flows northwest from the Mojave River toward Harper Dry Lake, but only flows during extreme events, is not a relatively permanent connection between Harper Dry Lake and the Mojave River, and only flows from the Mojave River to Harper Dry Lake, NOT from Harper Dry Lake to the Mojave River. The predominant soil types in the project area are Norob-Halloran Complex and Cajon Loamy Sand (Cajon Sand), which are characterized by moderate and somewhat excessive rates of permeability, respectively. Both surface and groundwater flows from the surrounding mountain ranges are directed to Harper Dry Lake. Harper Dry Lake is NOT a TNW. Moreover, Harper Dry Lake is NOT an (a)(3) water as defined by 33 CFR 328.3. Harper Dry Lake does NOT meet criteria (a)(3)(i-iii), as it: i) DOES NOT have use for surface water recreation or other purposes by foreign or interstate travelers, ii) DOES NOT have harvesting activities of fish or shellfish that may be sold in interstate or foreign commerce, and iii) DOES NOT have surface water industrial usage by industries in interstate commerce. Therefore, Harper Dry Lake is an isolated water without a surface water connection to commerce. Based on the above information, the Corps concludes that Playa Lakebed #17 is a NONJURISDICTIONAL water, since the water is NOT tributary to either a TNW or an (a)(3) water. The Corps makes such a conclusion since the water is an isolated lake that does not qualify as a TNW or as an (a)(3) water.

SECTION III: CWA ANALYSIS

A. TNWs AND WETLANDS ADJACENT TO TNWs

The agencies will assert jurisdiction over TNWs and wetlands adjacent to TNWs. If the aquatic resource is a TNW, complete Section III.A.1 and Section III.D.1. only; if the aquatic resource is a wetland adjacent to a TNW, complete Sections III.A.1 and 2 and Section III.D.1.; otherwise, see Section III.B below.

1. TNW

Identify TNW:

Summarize rationale supporting determination:

2. Wetland adjacent to TNW

Summarize rationale supporting conclusion that wetland is "adjacent":

B. CHARACTERISTICS OF TRIBUTARY (THAT IS NOT A TNW) AND ITS ADJACENT WETLANDS (IF ANY):

This section summarizes information regarding characteristics of the tributary and its adjacent wetlands, if any, and it helps determine whether or not the standards for jurisdiction established under *Rapanos* have been met.

The agencies will assert jurisdiction over non-navigable tributaries of TNWs where the tributaries are "relatively permanent waters" (RPWs), i.e. tributaries that typically flow year-round or have continuous flow at least seasonally (e.g., typically 3 months). A wetland that directly abuts an RPW is also jurisdictional. If the aquatic resource is not a TNW, but has year-round (perennial) flow, skip to Section III.D.2. If the aquatic resource is a wetland directly abutting a tributary with perennial flow, skip to Section III.D.4.

A wetland that is adjacent to but that does not directly abut an RPW requires a significant nexus evaluation. Corps districts and EPA regions will include in the record any available information that documents the existence of a significant nexus between a relatively permanent tributary that is not perennial (and its adjacent wetlands if any) and a traditional navigable water, even though a significant nexus finding is not required as a matter of law.

If the waterbody⁴ is not an RPW, or a wetland directly abutting an RPW, a JD will require additional data to determine if the waterbody has a significant nexus with a TNW. If the tributary has adjacent wetlands, the significant nexus evaluation must consider the tributary in combination with all of its adjacent wetlands. This significant nexus evaluation that combines, for analytical purposes, the tributary and all of its adjacent wetlands is used whether the review area identified in the JD request is the tributary, or its adjacent wetlands, or both. If the JD covers a tributary with adjacent wetlands, complete Section III.B.1 for the tributary, Section III.B.2 for any onsite wetlands, and Section III.B.3 for all wetlands adjacent to that tributary, both onsite and offsite. The determination whether a significant nexus exists is determined in Section III.C below.

1. Characteristics of non-TNWs that flow directly or indirectly into TNW

(i) General Area Conditions:

Watershed size: Pick List

Drainage area: Pick List

Average annual rainfall: _____ inches

Average annual snowfall: _____ inches

(ii) Physical Characteristics:

(a) Relationship with TNW:

☐ Tributary flows directly into TNW.

☐ Tributary flows through Pick List tributaries before entering TNW.

Project waters are Pick List river miles from TNW.

Project waters are Pick List river miles from RPW.

Project waters are Pick List aerial (straight) miles from TNW.

Project waters are Pick List aerial (straight) miles from RPW.

Project waters cross or serve as state boundaries. Explain:

Identify flow route to TNW⁵:

Tributary stream order, if known:

⁴ Note that the Instructional Guidebook contains additional information regarding swales, ditches, washes, and erosional features generally and in the arid West.

⁵ Flow route can be described by identifying, e.g., tributary a, which flows through the review area, to flow into tributary b, which then flows into TNW.

(b) General Tributary Characteristics (check all that apply):

Tributary is: ☐ Natural
☐ Artificial (man-made). Explain:
☐ Manipulated (man-altered). Explain:

Tributary properties with respect to top of bank (estimate):

Average width: feet
Average depth: feet
Average side slopes: Pick List.

Primary tributary substrate composition (check all that apply):

☐ Silts ☐ Sands ☐ Concrete
☐ Cobbles ☐ Gravel ☐ Muck
☐ Bedrock ☐ Vegetation. Type/% cover:
☐ Other. Explain:

Tributary condition/stability [e.g., highly eroding, sloughing banks]. Explain:

Presence of run/riffle/pool complexes. Explain:

Tributary geometry: Pick List

Tributary gradient (approximate average slope): %

(c) Flow:

Tributary provides for: Pick List

Estimate average number of flow events in review area/year: Pick List

Describe flow regime:

Other information on duration and volume:

Surface flow is: Pick List. Characteristics:

Subsurface flow: Pick List. Explain findings:

☐ Dye (or other) test performed:

Tributary has (check all that apply):

☐ Bed and banks
☐ OHWM⁶ (check all indicators that apply):
☐ clear, natural line impressed on the bank ☐ the presence of litter and debris
☐ changes in the character of soil ☐ destruction of terrestrial vegetation
☐ shelving ☐ the presence of wrack line
☐ vegetation matted down, bent, or absent ☐ sediment sorting
☐ leaf litter disturbed or washed away ☐ scour
☐ sediment deposition ☐ multiple observed or predicted flow events
☐ water staining ☐ abrupt change in plant community
☐ other (list):
☐ Discontinuous OHWM.⁷ Explain:

If factors other than the OHWM were used to determine lateral extent of CWA jurisdiction (check all that apply):

☐ High Tide Line indicated by: ☐ Mean High Water Mark indicated by:
☐ oil or scum line along shore objects ☐ survey to available datum;
☐ fine shell or debris deposits (foreshore) ☐ physical markings;
☐ physical markings/characteristics ☐ vegetation lines/changes in vegetation types.
☐ tidal gauges
☐ other (list):

(iii) Chemical Characteristics:

Characterize tributary (e.g., water color is clear, discolored, oily film; water quality; general watershed characteristics, etc.).

Explain:

Identify specific pollutants, if known:

⁶A natural or man-made discontinuity in the OHWM does not necessarily sever jurisdiction (e.g., where the stream temporarily flows underground, or where the OHWM has been removed by development or agricultural practices). Where there is a break in the OHWM that is unrelated to the waterbody's flow regime (e.g., flow over a rock outcrop or through a culvert), the agencies will look for indicators of flow above and below the break.

⁷Ibid.

(iv) **Biological Characteristics. Channel supports (check all that apply):**

- ☐ Riparian corridor. Characteristics (type, average width):
- ☐ Wetland fringe. Characteristics:
- ☐ Habitat for:
 - ☐ Federally Listed species. Explain findings:
 - ☐ Fish/spawn areas. Explain findings:
 - ☐ Other environmentally-sensitive species. Explain findings:
 - ☐ Aquatic/wildlife diversity. Explain findings:

2. **Characteristics of wetlands adjacent to non-TNW that flow directly or indirectly into TNW**

(i) **Physical Characteristics:**

(a) General Wetland Characteristics:

Properties:

Wetland size: acres

Wetland type. Explain:

Wetland quality. Explain:

Project wetlands cross or serve as state boundaries. Explain:

(b) General Flow Relationship with Non-TNW:

Flow is: Pick List. Explain:

Surface flow is: Pick List

Characteristics:

Subsurface flow: Pick List. Explain findings:

☐ Dye (or other) test performed:

(c) Wetland Adjacency Determination with Non-TNW:

☐ Directly abutting

☐ Not directly abutting

☐ Discrete wetland hydrologic connection. Explain:

☐ Ecological connection. Explain:

☐ Separated by berm/barrier. Explain:

(d) Proximity (Relationship) to TNW

Project wetlands are Pick List river miles from TNW.

Project waters are Pick List aerial (straight) miles from TNW.

Flow is from: Pick List.

Estimate approximate location of wetland as within the Pick List floodplain.

(ii) **Chemical Characteristics:**

Characterize wetland system (e.g., water color is clear, brown, oil film on surface; water quality; general watershed characteristics; etc.). Explain:

Identify specific pollutants, if known:

(iii) **Biological Characteristics. Wetland supports (check all that apply):**

- ☐ Riparian buffer. Characteristics (type, average width):
- ☐ Vegetation type/percent cover. Explain:
- ☐ Habitat for:
 - ☐ Federally Listed species. Explain findings:
 - ☐ Fish/spawn areas. Explain findings:
 - ☐ Other environmentally-sensitive species. Explain findings:
 - ☐ Aquatic/wildlife diversity. Explain findings:

3. **Characteristics of all wetlands adjacent to the tributary (if any)**

All wetland(s) being considered in the cumulative analysis: Pick List

Approximately () acres in total are being considered in the cumulative analysis.

For each wetland, specify the following:

Directly abuts? (Y/N)

Size (in acres)

Directly abuts? (Y/N)

Size (in acres)

Summarize overall biological, chemical and physical functions being performed:

C. SIGNIFICANT NEXUS DETERMINATION

A significant nexus analysis will assess the flow characteristics and functions of the tributary itself and the functions performed by any wetlands adjacent to the tributary to determine if they significantly affect the chemical, physical, and biological integrity of a TNW. For each of the following situations, a significant nexus exists if the tributary, in combination with all of its adjacent wetlands, has more than a speculative or insubstantial effect on the chemical, physical and/or biological integrity of a TNW. Considerations when evaluating significant nexus include, but are not limited to the volume, duration, and frequency of the flow of water in the tributary and its proximity to a TNW, and the functions performed by the tributary and all its adjacent wetlands. It is not appropriate to determine significant nexus based solely on any specific threshold of distance (e.g. between a tributary and its adjacent wetland or between a tributary and the TNW). Similarly, the fact an adjacent wetland lies within or outside of a floodplain is not solely determinative of significant nexus.

Draw connections between the features documented and the effects on the TNW, as identified in the *Rapanos* Guidance and discussed in the Instructional Guidebook. Factors to consider include, for example:

- Does the tributary, in combination with its adjacent wetlands (if any), have the capacity to carry pollutants or flood waters to TNWs, or to reduce the amount of pollutants or flood waters reaching a TNW?
- Does the tributary, in combination with its adjacent wetlands (if any), provide habitat and lifecycle support functions for fish and other species, such as feeding, nesting, spawning, or rearing young for species that are present in the TNW?
- Does the tributary, in combination with its adjacent wetlands (if any), have the capacity to transfer nutrients and organic carbon that support downstream foodwebs?
- Does the tributary, in combination with its adjacent wetlands (if any), have other relationships to the physical, chemical, or biological integrity of the TNW?

Note: the above list of considerations is not inclusive and other functions observed or known to occur should be documented below:

1. **Significant nexus findings for non-RPW that has no adjacent wetlands and flows directly or indirectly into TNWs.** Explain findings of presence or absence of significant nexus below, based on the tributary itself, then go to Section III.D:
2. **Significant nexus findings for non-RPW and its adjacent wetlands, where the non-RPW flows directly or indirectly into TNWs.** Explain findings of presence or absence of significant nexus below, based on the tributary in combination with all of its adjacent wetlands, then go to Section III.D:
3. **Significant nexus findings for wetlands adjacent to an RPW but that do not directly abut the RPW.** Explain findings of presence or absence of significant nexus below, based on the tributary in combination with all of its adjacent wetlands, then go to Section III.D:

D. DETERMINATIONS OF JURISDICTIONAL FINDINGS. THE SUBJECT WATERS/WETLANDS ARE (CHECK ALL THAT APPLY):

1. **TNWs and Adjacent Wetlands.** Check all that apply and provide size estimates in review area:

- ☐ TNWs: linear feet width (ft), Or, acres.
- ☐ Wetlands adjacent to TNWs: acres.

2. **RPWs that flow directly or indirectly into TNWs.**

- ☐ Tributaries of TNWs where tributaries typically flow year-round are jurisdictional. Provide data and rationale indicating that tributary is perennial:
- ☐ Tributaries of TNW where tributaries have continuous flow "seasonally" (e.g., typically three months each year) are jurisdictional. Data supporting this conclusion is provided at Section III.B. Provide rationale indicating that tributary flows seasonally:

Provide estimates for jurisdictional waters in the review area (check all that apply):

☐ Tributary waters: linear feet width (ft).

☐ Other non-wetland waters: acres.

Identify type(s) of waters:

3. Non-RPWs⁸ that flow directly or indirectly into TNWs.

- ☐ Waterbody that is not a TNW or an RPW, but flows directly or indirectly into a TNW, and it has a significant nexus with a TNW is jurisdictional. Data supporting this conclusion is provided at Section III.C.

Provide estimates for jurisdictional waters within the review area (check all that apply):

☐ Tributary waters: linear feet width (ft).

☐ Other non-wetland waters: acres.

Identify type(s) of waters:

4. Wetlands directly abutting an RPW that flow directly or indirectly into TNWs.

- ☐ Wetlands directly abut RPW and thus are jurisdictional as adjacent wetlands.

☐ Wetlands directly abutting an RPW where tributaries typically flow year-round. Provide data and rationale indicating that tributary is perennial in Section III.D.2, above. Provide rationale indicating that wetland is directly abutting an RPW:

☐ Wetlands directly abutting an RPW where tributaries typically flow "seasonally." Provide data indicating that tributary is seasonal in Section III.B and rationale in Section III.D.2, above. Provide rationale indicating that wetland is directly abutting an RPW:

Provide acreage estimates for jurisdictional wetlands in the review area: acres.

5. Wetlands adjacent to but not directly abutting an RPW that flow directly or indirectly into TNWs.

- ☐ Wetlands that do not directly abut an RPW, but when considered in combination with the tributary to which they are adjacent and with similarly situated adjacent wetlands, have a significant nexus with a TNW are jurisdictional. Data supporting this conclusion is provided at Section III.C.

Provide acreage estimates for jurisdictional wetlands in the review area: acres.

6. Wetlands adjacent to non-RPWs that flow directly or indirectly into TNWs.

- ☐ Wetlands adjacent to such waters, and have when considered in combination with the tributary to which they are adjacent and with similarly situated adjacent wetlands, have a significant nexus with a TNW are jurisdictional. Data supporting this conclusion is provided at Section III.C.

Provide estimates for jurisdictional wetlands in the review area: acres.

7. Impoundments of jurisdictional waters.⁹

As a general rule, the impoundment of a jurisdictional tributary remains jurisdictional.

☐ Demonstrate that impoundment was created from "waters of the U.S.," or

☐ Demonstrate that water meets the criteria for one of the categories presented above (1-6), or

☐ Demonstrate that water is isolated with a nexus to commerce (see E below).

E. ISOLATED [INTERSTATE OR INTRA-STATE] WATERS, INCLUDING ISOLATED WETLANDS, THE USE, DEGRADATION OR DESTRUCTION OF WHICH COULD AFFECT INTERSTATE COMMERCE, INCLUDING ANY SUCH WATERS (CHECK ALL THAT APPLY):¹⁰

☐ which are or could be used by interstate or foreign travelers for recreational or other purposes.

☐ from which fish or shellfish are or could be taken and sold in interstate or foreign commerce.

☐ which are or could be used for industrial purposes by industries in interstate commerce.

☐ Interstate isolated waters. Explain:

☐ Other factors. Explain:

Identify water body and summarize rationale supporting determination:

⁸See Footnote # 3.

⁹To complete the analysis refer to the key in Section III.D.6 of the Instructional Guidebook.

¹⁰Prior to asserting or declining CWA jurisdiction based solely on this category, Corps Districts will elevate the action to Corps and EPA HQ for review consistent with the process described in the Corps/EPA Memorandum Regarding CWA Act Jurisdiction Following Rapanos.

Provide estimates for jurisdictional waters in the review area (check all that apply):

- ☐ Tributary waters: linear feet width (ft).
- ☐ Other non-wetland waters: acres.
- Identify type(s) of waters:
- ☐ Wetlands: acres.

F. NON-JURISDICTIONAL WATERS, INCLUDING WETLANDS (CHECK ALL THAT APPLY):

- ☐ If potential wetlands were assessed within the review area, these areas did not meet the criteria in the 1987 Corps of Engineers Wetland Delineation Manual and/or appropriate Regional Supplements.
- ☒ Review area included isolated waters with no substantial nexus to interstate (or foreign) commerce.
 - ☒ Prior to the Jan 2001 Supreme Court decision in "SWANCC," the review area would have been regulated based solely on the "Migratory Bird Rule" (MBR).
- ☐ Waters do not meet the "Significant Nexus" standard, where such a finding is required for jurisdiction. Explain: .
- ☐ Other: (explain, if not covered above): .

Provide acreage estimates for non-jurisdictional waters in the review area, where the sole potential basis of jurisdiction is the MBR factors (i.e., presence of migratory birds, presence of endangered species, use of water for irrigated agriculture), using best professional judgment (check all that apply):

- ☐ Non-wetland waters (i.e., rivers, streams): linear feet width (ft).
- ☒ Lakes/ponds: 9.44 acres.
- ☐ Other non-wetland waters: acres. List type of aquatic resource: .
- ☐ Wetlands: acres.

Provide acreage estimates for non-jurisdictional waters in the review area that do not meet the "Significant Nexus" standard, where such a finding is required for jurisdiction (check all that apply):

- ☐ Non-wetland waters (i.e., rivers, streams): linear feet, width (ft).
- ☐ Lakes/ponds: acres.
- ☐ Other non-wetland waters: acres. List type of aquatic resource: .
- ☐ Wetlands: acres.

SECTION IV: DATA SOURCES.

A. SUPPORTING DATA. Data reviewed for JD (check all that apply - checked items shall be included in case file and, where checked and requested, appropriately reference sources below):

- ☒ Maps, plans, plots or plat submitted by or on behalf of the applicant/consultant: Jurisdictional Delineation Report: Potential Jurisdictional Waters of the U.S. and State.
- ☒ Data sheets prepared/submitted by or on behalf of the applicant/consultant.
 - ☒ Office concurs with data sheets/delineation report.
 - ☐ Office does not concur with data sheets/delineation report.
- ☐ Data sheets prepared by the Corps:
- ☐ Corps navigable waters' study:
- ☐ U.S. Geological Survey Hydrologic Atlas:
 - ☐ USGS NHD data.
 - ☐ USGS 8 and 12 digit HUC maps.
- ☐ U.S. Geological Survey map(s). Cite scale & quad name: .
- ☒ USDA Natural Resources Conservation Service Soil Survey. Citation: USDA. 1986. Soil Conservation Service Soil Survey of San Bernardino County California-Mojave River Area.
- ☐ National wetlands inventory map(s). Cite name: .
- ☐ State/Local wetland inventory map(s): .
- ☐ FEMA/FIRM maps:
- ☐ 100-year Floodplain Elevation is: (National Geodetic Vertical Datum of 1929)
- ☒ Photographs: ☒ Aerial (Name & Date): Juris. Delineation Report: Potential Jurisdictional Waters of the U.S. and State (2005).
 - or ☐ Other (Name & Date): .
- ☐ Previous determination(s). File no. and date of response letter: .
- ☐ Applicable/supporting case law: .
- ☐ Applicable/supporting scientific literature: .
- ☒ Other information (please specify): Field visit on January 14, 2010 supported this JD.

B. ADDITIONAL COMMENTS TO SUPPORT JD:

APPROVED JURISDICTIONAL DETERMINATION FORM
U.S. Army Corps of Engineers

This form should be completed by following the instructions provided in Section IV of the JD Form Instructional Guidebook.

SECTION I: BACKGROUND INFORMATION

A. REPORT COMPLETION DATE FOR APPROVED JURISDICTIONAL DETERMINATION (JD): February 3, 2010

B. DISTRICT OFFICE, FILE NAME, AND NUMBER: SPL-2009-00928-SME-JD3

C. PROJECT LOCATION AND BACKGROUND INFORMATION:

State: California County/parish/borough: San Bernardino City: Lockhart
Center coordinates of site (lat/long in degree decimal format): Lat. 35.01449° N Long. -117.32124° W
Universal Transverse Mercator:

Name of nearest waterbody: Harper Dry Lake

Name of nearest Traditional Navigable Water (TNW) into which the aquatic resource flows: None (isolated)

Name of watershed or Hydrologic Unit Code (HUC): Coyote-Cuddleback Lakes Watershed (HUC 18090207)

☒ Check if map/diagram of review area and/or potential jurisdictional areas is/are available upon request.

☒ Check if other sites (e.g., offsite mitigation sites, disposal sites, etc...) are associated with this action and are recorded on a different JD form.

D. REVIEW PERFORMED FOR SITE EVALUATION (CHECK ALL THAT APPLY):

☒ Office (Desk) Determination. Date: February 1, 2010

☒ Field Determination. Date(s): January 14, 2010

SECTION II: SUMMARY OF FINDINGS

A. RHA SECTION 10 DETERMINATION OF JURISDICTION.

There **Are no** "navigable waters of the U.S." within Rivers and Harbors Act (RHA) jurisdiction (as defined by 33 CFR part 329) in the review area. [Required]

☐ Waters subject to the ebb and flow of the tide.

☐ Waters are presently used, or have been used in the past, or may be susceptible for use to transport interstate or foreign commerce.
Explain:

B. CWA SECTION 404 DETERMINATION OF JURISDICTION.

There **Are no** "waters of the U.S." within Clean Water Act (CWA) jurisdiction (as defined by 33 CFR part 328) in the review area. [Required]

1. Waters of the U.S.

a. Indicate presence of waters of U.S. in review area (check all that apply):¹

- ☐ TNWs, including territorial seas
- ☐ Wetlands adjacent to TNWs
- ☐ Relatively permanent waters² (RPWs) that flow directly or indirectly into TNWs
- ☐ Non-RPWs that flow directly or indirectly into TNWs
- ☐ Wetlands directly abutting RPWs that flow directly or indirectly into TNWs
- ☐ Wetlands adjacent to but not directly abutting RPWs that flow directly or indirectly into TNWs
- ☐ Wetlands adjacent to non-RPWs that flow directly or indirectly into TNWs
- ☐ Impoundments of jurisdictional waters
- ☐ Isolated (interstate or intrastate) waters, including isolated wetlands

b. Identify (estimate) size of waters of the U.S. in the review area:

Non-wetland waters: linear feet: width (ft) and/or acres.
Wetlands: acres.

c. Limits (boundaries) of jurisdiction based on: Pick List

Elevation of established OHWM (if known):

2. Non-regulated waters/wetlands (check if applicable):³

☐ Potentially jurisdictional waters and/or wetlands were assessed within the review area and determined to be not jurisdictional.
Explain:

¹ Boxes checked below shall be supported by completing the appropriate sections in Section III below.

² For purposes of this form, an RPW is defined as a tributary that is not a TNW and that typically flows year-round or has continuous flow at least "seasonally" (e.g., typically 3 months).

³ Supporting documentation is presented in Section III.F.

SECTION III: CWA ANALYSIS

A. TNWs AND WETLANDS ADJACENT TO TNWs

The agencies will assert jurisdiction over TNWs and wetlands adjacent to TNWs. If the aquatic resource is a TNW, complete Section III.A.1 and Section III.D.1. only; if the aquatic resource is a wetland adjacent to a TNW, complete Sections III.A.1 and 2 and Section III.D.1.; otherwise, see Section III.B below.

1. **TNW**

Identify TNW:

Summarize rationale supporting determination:

2. **Wetland adjacent to TNW**

Summarize rationale supporting conclusion that wetland is "adjacent":

B. CHARACTERISTICS OF TRIBUTARY (THAT IS NOT A TNW) AND ITS ADJACENT WETLANDS (IF ANY):

This section summarizes information regarding characteristics of the tributary and its adjacent wetlands, if any, and it helps determine whether or not the standards for jurisdiction established under *Rapanos* have been met.

The agencies will assert jurisdiction over non-navigable tributaries of TNWs where the tributaries are "relatively permanent waters" (RPWs), i.e. tributaries that typically flow year-round or have continuous flow at least seasonally (e.g., typically 3 months). A wetland that directly abuts an RPW is also jurisdictional. If the aquatic resource is not a TNW, but has year-round (perennial) flow, skip to Section III.D.2. If the aquatic resource is a wetland directly abutting a tributary with perennial flow, skip to Section III.D.4.

A wetland that is adjacent to but that does not directly abut an RPW requires a significant nexus evaluation. Corps districts and EPA regions will include in the record any available information that documents the existence of a significant nexus between a relatively permanent tributary that is not perennial (and its adjacent wetlands if any) and a traditional navigable water, even though a significant nexus finding is not required as a matter of law.

If the waterbody⁴ is not an RPW, or a wetland directly abutting an RPW, a JD will require additional data to determine if the waterbody has a significant nexus with a TNW. If the tributary has adjacent wetlands, the significant nexus evaluation must consider the tributary in combination with all of its adjacent wetlands. This significant nexus evaluation that combines, for analytical purposes, the tributary and all of its adjacent wetlands is used whether the review area identified in the JD request is the tributary, or its adjacent wetlands, or both. If the JD covers a tributary with adjacent wetlands, complete Section III.B.1 for the tributary, Section III.B.2 for any onsite wetlands, and Section III.B.3 for all wetlands adjacent to that tributary, both onsite and offsite. The determination whether a significant nexus exists is determined in Section III.C below.

1. **Characteristics of non-TNWs that flow directly or indirectly into TNW**

(i) **General Area Conditions:**

Watershed size: Pick List

Drainage area: Pick List

Average annual rainfall: inches

Average annual snowfall: inches

(ii) **Physical Characteristics:**

(a) Relationship with TNW:

☐ Tributary flows directly into TNW.

☐ Tributary flows through Pick List tributaries before entering TNW.

Project waters are Pick List river miles from TNW.

Project waters are Pick List river miles from RPW.

Project waters are Pick List aerial (straight) miles from TNW.

Project waters are Pick List aerial (straight) miles from RPW.

Project waters cross or serve as state boundaries. Explain:

Identify flow route to TNW⁵:

Tributary stream order, if known:

⁴ Note that the Instructional Guidebook contains additional information regarding swales, ditches, washes, and erosional features generally and in the arid West.

⁵ Flow route can be described by identifying, e.g., tributary a, which flows through the review area, to flow into tributary b, which then flows into TNW.

(b) General Tributary Characteristics (check all that apply):

Tributary is: ☐ Natural
☐ Artificial (man-made). Explain:
☐ Manipulated (man-altered). Explain:

Tributary properties with respect to top of bank (estimate):

Average width: feet
Average depth: feet
Average side slopes: Pick List.

Primary tributary substrate composition (check all that apply):

☐ Silts ☐ Sands ☐ Concrete
☐ Cobbles ☐ Gravel ☐ Muck
☐ Bedrock ☐ Vegetation. Type/% cover:
☐ Other. Explain:

Tributary condition/stability [e.g., highly eroding, sloughing banks]. Explain:

Presence of run/riffle/pool complexes. Explain:

Tributary geometry: Pick List

Tributary gradient (approximate average slope): %

(c) Flow:

Tributary provides for: Pick List

Estimate average number of flow events in review area/year: Pick List

Describe flow regime:

Other information on duration and volume:

Surface flow is: Pick List. Characteristics:

Subsurface flow: Pick List. Explain findings:

☐ Dye (or other) test performed:

Tributary has (check all that apply):

☐ Bed and banks
☐ OHWM⁶ (check all indicators that apply):
☐ clear, natural line impressed on the bank ☐ the presence of litter and debris
☐ changes in the character of soil ☐ destruction of terrestrial vegetation
☐ shelving ☐ the presence of wrack line
☐ vegetation matted down, bent, or absent ☐ sediment sorting
☐ leaf litter disturbed or washed away ☐ scour
☐ sediment deposition ☐ multiple observed or predicted flow events
☐ water staining ☐ abrupt change in plant community
☐ other (list):
☐ Discontinuous OHWM.⁷ Explain:

If factors other than the OHWM were used to determine lateral extent of CWA jurisdiction (check all that apply):

☐ High Tide Line indicated by: ☐ Mean High Water Mark indicated by:
☐ oil or scum line along shore objects ☐ survey to available datum;
☐ fine shell or debris deposits (foreshore) ☐ physical markings;
☐ physical markings/characteristics ☐ vegetation lines/changes in vegetation types.
☐ tidal gauges
☐ other (list):

(iii) Chemical Characteristics:

Characterize tributary (e.g., water color is clear, discolored, oily film; water quality; general watershed characteristics, etc.).

Explain:

Identify specific pollutants, if known:

⁶A natural or man-made discontinuity in the OHWM does not necessarily sever jurisdiction (e.g., where the stream temporarily flows underground, or where the OHWM has been removed by development or agricultural practices). Where there is a break in the OHWM that is unrelated to the waterbody's flow regime (e.g., flow over a rock outcrop or through a culvert), the agencies will look for indicators of flow above and below the break.

⁷Ibid.

(iv) **Biological Characteristics. Channel supports (check all that apply):**

- ☐ Riparian corridor. Characteristics (type, average width):
- ☐ Wetland fringe. Characteristics:
- ☐ Habitat for:
 - ☐ Federally Listed species. Explain findings:
 - ☐ Fish/spawn areas. Explain findings:
 - ☐ Other environmentally-sensitive species. Explain findings:
 - ☐ Aquatic/wildlife diversity. Explain findings:

2. **Characteristics of wetlands adjacent to non-TNW that flow directly or indirectly into TNW**

(i) **Physical Characteristics:**

(a) General Wetland Characteristics:

Properties:

Wetland size: acres

Wetland type. Explain:

Wetland quality. Explain:

Project wetlands cross or serve as state boundaries. Explain:

(b) General Flow Relationship with Non-TNW:

Flow is: Pick List. Explain:

Surface flow is: Pick List

Characteristics:

Subsurface flow: Pick List. Explain findings:

☐ Dye (or other) test performed:

(c) Wetland Adjacency Determination with Non-TNW:

- ☐ Directly abutting
- ☐ Not directly abutting
 - ☐ Discrete wetland hydrologic connection. Explain:
 - ☐ Ecological connection. Explain:
 - ☐ Separated by berm/barrier. Explain:

(d) Proximity (Relationship) to TNW

Project wetlands are Pick List river miles from TNW.

Project waters are Pick List aerial (straight) miles from TNW.

Flow is from: Pick List.

Estimate approximate location of wetland as within the Pick List floodplain.

(ii) **Chemical Characteristics:**

Characterize wetland system (e.g., water color is clear, brown, oil film on surface; water quality; general watershed characteristics; etc.). Explain:

Identify specific pollutants, if known:

(iii) **Biological Characteristics. Wetland supports (check all that apply):**

- ☐ Riparian buffer. Characteristics (type, average width):
- ☐ Vegetation type/percent cover. Explain:
- ☐ Habitat for:
 - ☐ Federally Listed species. Explain findings:
 - ☐ Fish/spawn areas. Explain findings:
 - ☐ Other environmentally-sensitive species. Explain findings:
 - ☐ Aquatic/wildlife diversity. Explain findings:

3. **Characteristics of all wetlands adjacent to the tributary (if any)**

All wetland(s) being considered in the cumulative analysis: Pick List

Approximately () acres in total are being considered in the cumulative analysis.

For each wetland, specify the following:

Directly abuts? (Y/N)

Size (in acres)

Directly abuts? (Y/N)

Size (in acres)

Summarize overall biological, chemical and physical functions being performed:

C. SIGNIFICANT NEXUS DETERMINATION

A significant nexus analysis will assess the flow characteristics and functions of the tributary itself and the functions performed by any wetlands adjacent to the tributary to determine if they significantly affect the chemical, physical, and biological integrity of a TNW. For each of the following situations, a significant nexus exists if the tributary, in combination with all of its adjacent wetlands, has more than a speculative or insubstantial effect on the chemical, physical and/or biological integrity of a TNW. Considerations when evaluating significant nexus include, but are not limited to the volume, duration, and frequency of the flow of water in the tributary and its proximity to a TNW, and the functions performed by the tributary and all its adjacent wetlands. It is not appropriate to determine significant nexus based solely on any specific threshold of distance (e.g. between a tributary and its adjacent wetland or between a tributary and the TNW). Similarly, the fact an adjacent wetland lies within or outside of a floodplain is not solely determinative of significant nexus.

Draw connections between the features documented and the effects on the TNW, as identified in the *Rapanos* Guidance and discussed in the Instructional Guidebook. Factors to consider include, for example:

- Does the tributary, in combination with its adjacent wetlands (if any), have the capacity to carry pollutants or flood waters to TNWs, or to reduce the amount of pollutants or flood waters reaching a TNW?
- Does the tributary, in combination with its adjacent wetlands (if any), provide habitat and lifecycle support functions for fish and other species, such as feeding, nesting, spawning, or rearing young for species that are present in the TNW?
- Does the tributary, in combination with its adjacent wetlands (if any), have the capacity to transfer nutrients and organic carbon that support downstream foodwebs?
- Does the tributary, in combination with its adjacent wetlands (if any), have other relationships to the physical, chemical, or biological integrity of the TNW?

Note: the above list of considerations is not inclusive and other functions observed or known to occur should be documented below:

1. **Significant nexus findings for non-RPW that has no adjacent wetlands and flows directly or indirectly into TNWs.** Explain findings of presence or absence of significant nexus below, based on the tributary itself, then go to Section III.D:
2. **Significant nexus findings for non-RPW and its adjacent wetlands, where the non-RPW flows directly or indirectly into TNWs.** Explain findings of presence or absence of significant nexus below, based on the tributary in combination with all of its adjacent wetlands, then go to Section III.D:
3. **Significant nexus findings for wetlands adjacent to an RPW but that do not directly abut the RPW.** Explain findings of presence or absence of significant nexus below, based on the tributary in combination with all of its adjacent wetlands, then go to Section III.D:

D. DETERMINATIONS OF JURISDICTIONAL FINDINGS. THE SUBJECT WATERS/WETLANDS ARE (CHECK ALL THAT APPLY):

1. **TNWs and Adjacent Wetlands.** Check all that apply and provide size estimates in review area:

☐ TNWs: linear feet width (ft), Or, acres.
☐ Wetlands adjacent to TNWs: acres.

2. **RPWs that flow directly or indirectly into TNWs.**

☐ Tributaries of TNWs where tributaries typically flow year-round are jurisdictional. Provide data and rationale indicating that tributary is perennial:
☐ Tributaries of TNW where tributaries have continuous flow "seasonally" (e.g., typically three months each year) are jurisdictional. Data supporting this conclusion is provided at Section III.B. Provide rationale indicating that tributary flows seasonally:

Provide estimates for jurisdictional waters in the review area (check all that apply):

- ☐ Tributary waters: linear feet width (ft).
☐ Other non-wetland waters: acres.
Identify type(s) of waters:

3. **Non-RPWs⁸ that flow directly or indirectly into TNWs.**

- ☐ Waterbody that is not a TNW or an RPW, but flows directly or indirectly into a TNW, and it has a significant nexus with a TNW is jurisdictional. Data supporting this conclusion is provided at Section III.C.

Provide estimates for jurisdictional waters within the review area (check all that apply):

- ☐ Tributary waters: linear feet width (ft).
☐ Other non-wetland waters: acres.
Identify type(s) of waters:

4. **Wetlands directly abutting an RPW that flow directly or indirectly into TNWs.**

- ☐ Wetlands directly abut RPW and thus are jurisdictional as adjacent wetlands.
☐ Wetlands directly abutting an RPW where tributaries typically flow year-round. Provide data and rationale indicating that tributary is perennial in Section III.D.2, above. Provide rationale indicating that wetland is directly abutting an RPW:
☐ Wetlands directly abutting an RPW where tributaries typically flow "seasonally." Provide data indicating that tributary is seasonal in Section III.B and rationale in Section III.D.2, above. Provide rationale indicating that wetland is directly abutting an RPW:

Provide acreage estimates for jurisdictional wetlands in the review area: acres.

5. **Wetlands adjacent to but not directly abutting an RPW that flow directly or indirectly into TNWs.**

- ☐ Wetlands that do not directly abut an RPW, but when considered in combination with the tributary to which they are adjacent and with similarly situated adjacent wetlands, have a significant nexus with a TNW are jurisdictional. Data supporting this conclusion is provided at Section III.C.

Provide acreage estimates for jurisdictional wetlands in the review area: acres.

6. **Wetlands adjacent to non-RPWs that flow directly or indirectly into TNWs.**

- ☐ Wetlands adjacent to such waters, and have when considered in combination with the tributary to which they are adjacent and with similarly situated adjacent wetlands, have a significant nexus with a TNW are jurisdictional. Data supporting this conclusion is provided at Section III.C.

Provide estimates for jurisdictional wetlands in the review area: acres.

7. **Impoundments of jurisdictional waters.⁹**

As a general rule, the impoundment of a jurisdictional tributary remains jurisdictional.

- ☐ Demonstrate that impoundment was created from "waters of the U.S.," or
☐ Demonstrate that water meets the criteria for one of the categories presented above (1-6), or
☐ Demonstrate that water is isolated with a nexus to commerce (see E below).

E. **ISOLATED [INTERSTATE OR INTRA-STATE] WATERS, INCLUDING ISOLATED WETLANDS, THE USE, DEGRADATION OR DESTRUCTION OF WHICH COULD AFFECT INTERSTATE COMMERCE, INCLUDING ANY SUCH WATERS (CHECK ALL THAT APPLY):¹⁰**

- ☐ which are or could be used by interstate or foreign travelers for recreational or other purposes.
☐ from which fish or shellfish are or could be taken and sold in interstate or foreign commerce.
☐ which are or could be used for industrial purposes by industries in interstate commerce.
☐ Interstate isolated waters. Explain:
☐ Other factors. Explain:

Identify water body and summarize rationale supporting determination:

⁸See Footnote # 3.

⁹To complete the analysis refer to the key in Section III.D.6 of the Instructional Guidebook.

¹⁰ Prior to asserting or declining CWA jurisdiction based solely on this category, Corps Districts will elevate the action to Corps and EPA HQ for review consistent with the process described in the Corps/EPA Memorandum Regarding CWA Act Jurisdiction Following Rapanos.



DEPARTMENT OF THE ARMY

915 Wilshire Boulevard
Los Angeles, California 90017

February 26, 2010

REPLY TO
ATTENTION OF

Office of the Chief
Regulatory Division

Joshua Zinn
AECOM
1420 Kettner Boulevard, Suite 500
San Diego, California 92101

SUBJECT: Determination Regarding Requirement for Department of the Army Permit

Dear Mr. Zinn:

Reference is made to your request (File No. SPL-2009-00928-SME) dated August 26, 2009, for clarification on whether a Department of the Army Permit is required for the Abengoa Mojave Solar Energy Project (35.0173, -117.3058) located near the community of Lockhart, San Bernardino County, California.

As you may know, the Corps' evaluation process for determining whether or not a Department of the Army permit is needed involves two tests. If both tests are met, then a permit is required. The first test determines whether or not the proposed project is located in a water of the United States (i.e., it is within the Corps' geographic jurisdiction). The second test determines whether or not the proposed project is a regulated activity under Section 10 of the River and Harbor Act or Section 404 of the Clean Water Act. As part of our evaluation process, we have made the determination below.

Geographic Jurisdiction:

Based on the approved jurisdictional determination dated February 26, 2010, we have determined the Abengoa Mojave Solar Energy project site does not contain waters of the United States pursuant to 33 C.F.R. §325.9.

Activity:

Based on the information you have provided, we have determined the proposed work, were it to occur in waters of the U.S. (see above, "Geographic Jurisdiction"), would involve a discharge of dredged or fill material and therefore, would be regulated under Section 404 of the Clean Water Act if the activity is performed in the manner described in your request.

Requirement for a Department of the Army Permit:


Based on the discussion above, we have determined your proposed project is not subject to our jurisdiction under Section 404 of the Clean Water Act and a Section 404 permit would not be required from our office if the activity is performed in the manner described.

Notwithstanding our determination above, your proposed project may be regulated under other Federal, State, and local laws.

If you have any questions, please contact Stephen Estes at 213-452-3660 or via e-mail at Stephen.M.Estes@usace.army.mil.


Please be advised that you can now comment on your experience with Regulatory Division by accessing the Corps web-based customer survey form at:
<http://per2.nwp.usace.army.mil/survey.html>.

Sincerely,

A handwritten signature in black ink, appearing to read "Mark Durham". The signature is written in a cursive, flowing style.

Mark Durham
Chief, South Coast Branch
Regulatory Division

Enclosures



Source: Thomas Guide, 2007




Figure 1
Regional Map

1000




Figure 3
Project Footprint

Mojave Solar Project - Jurisdictional Delineation Report

Path: I:\Documents\071 Harper Lake\Mojave\PC\06\CHAS\3 Project\Drawings\033 Topo\OUTOUTPRT1.AXD\$VDW, Figure 3, Project Information, 06/18/09, dgk/rlr




Figure #
Potential Jurisdictional Waters of the U.S. and State

Mojave Solar Project - Jurisdictional Delimitation Report

Final Report
Prepared for: [Redacted]
Prepared by: [Redacted]
Date: [Redacted]



Department of Energy
Washington, DC 20585

February 14, 2011

Ms. Ann Brierty
San Manuel Band of Mission Indians
Environmental Division
26569 Community Center Drive
Highland, CA 92346

Subject: Consultation for the Abengoa Mojave Solar Project

Dear Ms. Brierty:

In my September 27, 2010, letter to you I indicated that the US Department of Energy (DOE) is considering issuing a loan guarantee to support construction of the proposed Abengoa Mojave Solar Project (the Project), a solar thermal electric power plant nine miles northwest of Hinkley, California. The proposed power plant site would be located on previously farmed land. Telecommunication upgrades would also be required along existing transmission alignments. Minimal ground disturbance would occur along the alignments because existing access roads and poles would be used, with very few new or replacement poles needed.

My September 27 letter also noted that, with regard to the Project, DOE was serving as the lead federal agency for compliance with the National Environmental Policy Act (NEPA), and the US Bureau of Land Management (BLM) is cooperating with DOE in the NEPA review and is serving as the lead federal agency for compliance with the National Historic Preservation Act (NHPA) cultural resource review and Section 106 consultation process.

DOE has been working closely with BLM in the NHPA cultural review process and, as such, is familiar with the discussions you have had with Jim Shearer at BLM. I thank you for your comments thus far, and we look forward to participating with you in completing the environmental and cultural resource review process. DOE believes that consideration of any comments or concerns you provide, particularly with regard to sites of religious and cultural significance, will help ensure that DOE and BLM comply with our NEPA and NHPA Section 106 responsibilities for the Project. DOE and BLM remain available for continued government-to-government consultation on the Project at your request.

As part of our outreach, BLM requested that DOE inform you on the status of the cultural review. Class III cultural resource surveys have been completed at the proposed power plant site and along the transmission alignments. The surveys have identified archaeological sites in the project area. A table summarizing potential effects of the Project on these sites is attached.

Questions concerning the cultural review or Section 106 consultation process for the Project should be directed to Mr. Jim Shearer in the BLM Barstow Field Office (see contact information below). I would also appreciate being copied on correspondence to Mr. Shearer so I am apprised of any concerns that you might have. I can be reached by e-mail at matthew.mcmillen@hq.doe.gov, by phone at 202-586-



7248, or by mail at US Department of Energy, Loan Programs Office, LP-10, 1000 Independence Ave. SW., Washington, DC 20585.

Respectfully,



Matthew C. McMillen
Director, Environmental Compliance
Loan Programs Office

Attachment

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Office

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Road
Barstow, CA 92311
JShearer@BLM.gov
760.252.6034



Department of Energy
Washington, DC 20585

February 8, 2011

Honorable Charles Wood
Chairperson
Chemehuevi Reservation
P.O. Box 1976
Havasupai Lake, CA 92363

Subject: Consultation for the Abengoa Mojave Solar Project

Dear Chairperson Wood:

In my September 27, 2010 letter to you, I indicated that the US Department of Energy (DOE) is considering issuing a loan guarantee to support construction of the proposed Abengoa Mojave Solar Project (the Project), a solar thermal electric power plant nine miles northwest of Hinkley, California. The proposed power plant site would be located on previously farmed land. Telecommunication upgrades would also be required along existing transmission alignments. Minimal ground disturbance would occur along the alignments because existing access roads and poles would be used, with very few new or replacement poles needed.

My September 27 letter also noted that, with regard to the Project, DOE was serving as the lead federal agency for compliance with the National Environmental Policy Act (NEPA), and the US Bureau of Land Management (BLM) is cooperating with DOE in the NEPA review and is serving as the lead federal agency for compliance with the National Historic Preservation Act (NHPA) cultural resource review and Section 106 consultation process.

DOE has been working closely with BLM in the NHPA cultural review process and, at BLM's request, would like to inform you of the status of the review. Class III cultural resource surveys have been completed at the proposed power plant site and along the transmission alignments. The surveys have identified archaeological sites in the project area. A table summarizing potential effects of the Project on these sites is attached.

As indicated in my September 27 letter, DOE is available for government-to-government consultation on the Project at your request, and looks forward to participating with you in completing the environmental and cultural resource review process. DOE believes that consideration of any comments or concerns you provide, particularly with regard to sites of religious and cultural significance, will help ensure that DOE and BLM comply with our NEPA and NHPA Section 106 responsibilities for the Project.

Questions concerning the cultural review or Section 106 consultation process for the Project should be directed to Mr. Jim Shearer in the BLM Barstow Field Office (see contact information below). I would also appreciate being copied on correspondence to Mr. Shearer so I am apprised



of any concerns that you might have. I can be reached by e-mail at matthew.mcmillen@hq.doe.gov , by phone at 202-586-7248, or by mail at US Department of Energy, Loan Programs Office, LP-10, 1000 Independence Ave. SW, Washington, DC 20585.

Respectfully,



Matthew C. McMillen
Director, Environmental Compliance
Loan Programs Office

Enclosure

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Office

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Road
Barstow, CA 92311
JShearer@BLM.gov
760.252.6034



Department of Energy
Washington, DC 20585

February 8, 2011

Honorable Lora Tom
Chairperson
Paiute Indian Tribe of Utah
440 N. Paiute Drive
Cedar City, UT 84720-2613

Subject: Consultation for the Abengoa Mojave Solar Project

Dear Chairperson Tom:

In my September 27, 2010 letter to you, I indicated that the US Department of Energy (DOE) is considering issuing a loan guarantee to support construction of the proposed Abengoa Mojave Solar Project (the Project), a solar thermal electric power plant nine miles northwest of Hinkley, California. The proposed power plant site would be located on previously farmed land. Telecommunication upgrades would also be required along existing transmission alignments. Minimal ground disturbance would occur along the alignments because existing access roads and poles would be used, with very few new or replacement poles needed.

My September 27 letter also noted that, with regard to the Project, DOE was serving as the lead federal agency for compliance with the National Environmental Policy Act (NEPA), and the US Bureau of Land Management (BLM) is cooperating with DOE in the NEPA review and is serving as the lead federal agency for compliance with the National Historic Preservation Act (NHPA) cultural resource review and Section 106 consultation process.

DOE has been working closely with BLM in the NHPA cultural review process and, at BLM's request, would like to inform you of the status of the review. Class III cultural resource surveys have been completed at the proposed power plant site and along the transmission alignments. The surveys have identified archaeological sites in the project area. A table summarizing potential effects of the Project on these sites is attached.

As indicated in my September 27 letter, DOE is available for government-to-government consultation on the Project at your request, and looks forward to participating with you in completing the environmental and cultural resource review process. DOE believes that consideration of any comments or concerns you provide, particularly with regard to sites of religious and cultural significance, will help ensure that DOE and BLM comply with our NEPA and NHPA Section 106 responsibilities for the Project.

Questions concerning the cultural review or Section 106 consultation process for the Project should be directed to Mr. Jim Shearer in the BLM Barstow Field Office (see contact information below). I would also appreciate being copied on correspondence to Mr. Shearer so I am apprised



of any concerns that you might have. I can be reached by e-mail at matthew.mcmillen@hq.doe.gov , by phone at 202-586-7248, or by mail at US Department of Energy, Loan Programs Office, LP-10, 1000 Independence Ave. SW, Washington, DC 20585.

Respectfully,



Matthew C. McMillen
Director, Environmental Compliance
Loan Programs Office

Enclosure

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Office

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Road
Barstow, CA 92311
JShearer@BLM.gov
760.252.6034



Department of Energy

Washington, DC 20585

February 8, 2011

Honorable Darren Daboda
Chairman
Moapa Band of Paiute Indians
P.O. Box 340
Moapa, NV 89025-0340

Subject: Consultation for the Abengoa Mojave Solar Project

Dear Chairman Daboda:

In my September 27, 2010 letter to you, I indicated that the US Department of Energy (DOE) is considering issuing a loan guarantee to support construction of the proposed Abengoa Mojave Solar Project (the Project), a solar thermal electric power plant nine miles northwest of Hinkley, California. The proposed power plant site would be located on previously farmed land. Telecommunication upgrades would also be required along existing transmission alignments. Minimal ground disturbance would occur along the alignments because existing access roads and poles would be used, with very few new or replacement poles needed.

My September 27 letter also noted that, with regard to the Project, DOE was serving as the lead federal agency for compliance with the National Environmental Policy Act (NEPA), and the US Bureau of Land Management (BLM) is cooperating with DOE in the NEPA review and is serving as the lead federal agency for compliance with the National Historic Preservation Act (NHPA) cultural resource review and Section 106 consultation process.

DOE has been working closely with BLM in the NHPA cultural review process and, at BLM's request, would like to inform you of the status of the review. Class III cultural resource surveys have been completed at the proposed power plant site and along the transmission alignments. The surveys have identified archaeological sites in the project area. A table summarizing potential effects of the Project on these sites is attached.

As indicated in my September 27 letter, DOE is available for government-to-government consultation on the Project at your request, and looks forward to participating with you in completing the environmental and cultural resource review process. DOE believes that consideration of any comments or concerns you provide, particularly with regard to sites of religious and cultural significance, will help ensure that DOE and BLM comply with our NEPA and NHPA Section 106 responsibilities for the Project.

Questions concerning the cultural review or Section 106 consultation process for the Project should be directed to Mr. Jim Shearer in the BLM Barstow Field Office (see contact information below). I would also appreciate being copied on correspondence to Mr. Shearer so I am apprised



of any concerns that you might have. I can be reached by e-mail at matthew.mcmillen@hq.doe.gov , by phone at 202-586-7248, or by mail at US Department of Energy, Loan Programs Office, LP-10, 1000 Independence Ave. SW, Washington, DC 20585.

Respectfully,



Matthew C. McMillen
Director, Environmental Compliance
Loan Programs Office

Enclosure

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Office

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Road
Barstow, CA 92311
JShearer@BLM.gov
760.252.6034



Department of Energy

Washington, DC 20585

February 8, 2011

Honorable Alfreda Mitre
Chairperson
Las Vegas Tribe of Paiute Indians
Number One Paiute Drive
Las Vegas, NV 89106

Subject: Consultation for the Abengoa Mojave Solar Project

Dear Chairperson Mitre:

In my September 27, 2010 letter to you, I indicated that the US Department of Energy (DOE) is considering issuing a loan guarantee to support construction of the proposed Abengoa Mojave Solar Project (the Project), a solar thermal electric power plant nine miles northwest of Hinkley, California. The proposed power plant site would be located on previously farmed land. Telecommunication upgrades would also be required along existing transmission alignments. Minimal ground disturbance would occur along the alignments because existing access roads and poles would be used, with very few new or replacement poles needed.

My September 27 letter also noted that, with regard to the Project, DOE was serving as the lead federal agency for compliance with the National Environmental Policy Act (NEPA), and the US Bureau of Land Management (BLM) is cooperating with DOE in the NEPA review and is serving as the lead federal agency for compliance with the National Historic Preservation Act (NHPA) cultural resource review and Section 106 consultation process.

DOE has been working closely with BLM in the NHPA cultural review process and, at BLM's request, would like to inform you of the status of the review. Class III cultural resource surveys have been completed at the proposed power plant site and along the transmission alignments. The surveys have identified archaeological sites in the project area. A table summarizing potential effects of the Project on these sites is attached.

As indicated in my September 27 letter, DOE is available for government-to-government consultation on the Project at your request, and looks forward to participating with you in completing the environmental and cultural resource review process. DOE believes that consideration of any comments or concerns you provide, particularly with regard to sites of religious and cultural significance, will help ensure that DOE and BLM comply with our NEPA and NHPA Section 106 responsibilities for the Project.

Questions concerning the cultural review or Section 106 consultation process for the Project should be directed to Mr. Jim Shearer in the BLM Barstow Field Office (see contact information below). I would also appreciate being copied on correspondence to Mr. Shearer so I am apprised



of any concerns that you might have. I can be reached by e-mail at matthew.mcmillen@hq.doe.gov, by phone at 202-586-7248, or by mail at US Department of Energy, Loan Programs Office, LP-10, 1000 Independence Ave. SW, Washington, DC 20585.

Respectfully,



Matthew C. McMillen
Director, Environmental Compliance
Loan Programs Office

Enclosure

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Office

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Road
Barstow, CA 92311
JShearer@BLM.gov
760.252.6034



Department of Energy

Washington, DC 20585

February 8, 2011

Honorable Ona Segundo
Chairperson
Kaiband Band of Paiute Indians
HC65, Box 2
Freedonia, AZ 86022

Subject: Consultation for the Abengoa Mojave Solar Project

Dear Chairperson Segundo:

In my September 27, 2010 letter to you, I indicated that the US Department of Energy (DOE) is considering issuing a loan guarantee to support construction of the proposed Abengoa Mojave Solar Project (the Project), a solar thermal electric power plant nine miles northwest of Hinkley, California. The proposed power plant site would be located on previously farmed land. Telecommunication upgrades would also be required along existing transmission alignments. Minimal ground disturbance would occur along the alignments because existing access roads and poles would be used, with very few new or replacement poles needed.

My September 27 letter also noted that, with regard to the Project, DOE was serving as the lead federal agency for compliance with the National Environmental Policy Act (NEPA), and the US Bureau of Land Management (BLM) is cooperating with DOE in the NEPA review and is serving as the lead federal agency for compliance with the National Historic Preservation Act (NHPA) cultural resource review and Section 106 consultation process.

DOE has been working closely with BLM in the NHPA cultural review process and, at BLM's request, would like to inform you of the status of the review. Class III cultural resource surveys have been completed at the proposed power plant site and along the transmission alignments. The surveys have identified archaeological sites in the project area. A table summarizing potential effects of the Project on these sites is attached.

As indicated in my September 27 letter, DOE is available for government-to-government consultation on the Project at your request, and looks forward to participating with you in completing the environmental and cultural resource review process. DOE believes that consideration of any comments or concerns you provide, particularly with regard to sites of religious and cultural significance, will help ensure that DOE and BLM comply with our NEPA and NHPA Section 106 responsibilities for the Project.

Questions concerning the cultural review or Section 106 consultation process for the Project should be directed to Mr. Jim Shearer in the BLM Barstow Field Office (see contact information below). I would also appreciate being copied on correspondence to Mr. Shearer so I am apprised



of any concerns that you might have. I can be reached by e-mail at matthew.mcmillen@hq.doe.gov , by phone at 202-586-7248, or by mail at US Department of Energy, Loan Programs Office, LP-10, 1000 Independence Ave. SW, Washington, DC 20585.

Respectfully,



Matthew C. McMillen
Director, Environmental Compliance
Loan Programs Office

Enclosure

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Office

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Road
Barstow, CA 92311
JShearer@BLM.gov
760.252.6034



Department of Energy

Washington, DC 20585

February 8, 2011

Honorable Timothy Williams
Chairman
Fort Mojave Indian Tribe
500 Merriman Avenue
Needles, CA 92363

Subject: Consultation for the Abengoa Mojave Solar Project

Dear Chairman Williams:

In my September 27, 2010 letter to you, I indicated that the US Department of Energy (DOE) is considering issuing a loan guarantee to support construction of the proposed Abengoa Mojave Solar Project (the Project), a solar thermal electric power plant nine miles northwest of Hinkley, California. The proposed power plant site would be located on previously farmed land. Telecommunication upgrades would also be required along existing transmission alignments. Minimal ground disturbance would occur along the alignments because existing access roads and poles would be used, with very few new or replacement poles needed.

My September 27 letter also noted that, with regard to the Project, DOE was serving as the lead federal agency for compliance with the National Environmental Policy Act (NEPA), and the US Bureau of Land Management (BLM) is cooperating with DOE in the NEPA review and is serving as the lead federal agency for compliance with the National Historic Preservation Act (NHPA) cultural resource review and Section 106 consultation process.

DOE has been working closely with BLM in the NHPA cultural review process and, at BLM's request, would like to inform you of the status of the review. Class III cultural resource surveys have been completed at the proposed power plant site and along the transmission alignments. The surveys have identified archaeological sites in the project area. A table summarizing potential effects of the Project on these sites is attached.

As indicated in my September 27 letter, DOE is available for government-to-government consultation on the Project at your request, and looks forward to participating with you in completing the environmental and cultural resource review process. DOE believes that consideration of any comments or concerns you provide, particularly with regard to sites of religious and cultural significance, will help ensure that DOE and BLM comply with our NEPA and NHPA Section 106 responsibilities for the Project.

Questions concerning the cultural review or Section 106 consultation process for the Project should be directed to Mr. Jim Shearer in the BLM Barstow Field Office (see contact information below). I would also appreciate being copied on correspondence to Mr. Shearer so I am apprised



of any concerns that you might have. I can be reached by e-mail at matthew.mcmillen@hq.doe.gov, by phone at 202-586-7248, or by mail at US Department of Energy, Loan Programs Office, LP-10, 1000 Independence Ave. SW, Washington, DC 20585.

Respectfully,



Matthew C. McMillen
Director, Environmental Compliance
Loan Programs Office

Enclosure

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Office

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Road
Barstow, CA 92311
JShearer@BLM.gov
760.252.6034



Department of Energy
Washington, DC 20585

February 8, 2011

Mr. Raphael Bear
President
Fort McDowell Yavapai Nation
P.O. Box 17779
Fountain Hills, AZ 85268

Subject: Consultation for the Abengoa Mojave Solar Project

Dear Mr. Bear:

In my September 27, 2010 letter to you, I indicated that the US Department of Energy (DOE) is considering issuing a loan guarantee to support construction of the proposed Abengoa Mojave Solar Project (the Project), a solar thermal electric power plant nine miles northwest of Hinkley, California. The proposed power plant site would be located on previously farmed land. Telecommunication upgrades would also be required along existing transmission alignments. Minimal ground disturbance would occur along the alignments because existing access roads and poles would be used, with very few new or replacement poles needed.

My September 27 letter also noted that, with regard to the Project, DOE was serving as the lead federal agency for compliance with the National Environmental Policy Act (NEPA), and the US Bureau of Land Management (BLM) is cooperating with DOE in the NEPA review and is serving as the lead federal agency for compliance with the National Historic Preservation Act (NHPA) cultural resource review and Section 106 consultation process.

DOE has been working closely with BLM in the NHPA cultural review process and, at BLM's request, would like to inform you of the status of the review. Class III cultural resource surveys have been completed at the proposed power plant site and along the transmission alignments. The surveys have identified archaeological sites in the project area. A table summarizing potential effects of the Project on these sites is attached.


As indicated in my September 27 letter, DOE is available for government-to-government consultation on the Project at your request, and looks forward to participating with you in completing the environmental and cultural resource review process. DOE believes that consideration of any comments or concerns you provide, particularly with regard to sites of religious and cultural significance, will help ensure that DOE and BLM comply with our NEPA and NHPA Section 106 responsibilities for the Project.

Questions concerning the cultural review or Section 106 consultation process for the Project should be directed to Mr. Jim Shearer in the BLM Barstow Field Office (see contact information below). I would also appreciate being copied on correspondence to Mr. Shearer so I am apprised



of any concerns that you might have. I can be reached by e-mail at matthew.mcmillen@hq.doe.gov , by phone at 202-586-7248, or by mail at US Department of Energy, Loan Programs Office, LP-10, 1000 Independence Ave. SW, Washington, DC 20585.

Respectfully,



Matthew C. McMillen
Director, Environmental Compliance
Loan Programs Office

Enclosure

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Office

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Road
Barstow, CA 92311
JShearer@BLM.gov
760.252.6034



Department of Energy
Washington, DC 20585

February 8, 2011

Honorable Daniel Eddy
Chairman
Tribes of the Colorado River
26600 Mohave Road
Parker, AZ 85344

Subject: Consultation for the Abengoa Mojave Solar Project

Dear Chairman Eddy:

In my September 27, 2010 letter to you, I indicated that the US Department of Energy (DOE) is considering issuing a loan guarantee to support construction of the proposed Abengoa Mojave Solar Project (the Project), a solar thermal electric power plant nine miles northwest of Hinkley, California. The proposed power plant site would be located on previously farmed land. Telecommunication upgrades would also be required along existing transmission alignments. Minimal ground disturbance would occur along the alignments because existing access roads and poles would be used, with very few new or replacement poles needed.

My September 27 letter also noted that, with regard to the Project, DOE was serving as the lead federal agency for compliance with the National Environmental Policy Act (NEPA), and the US Bureau of Land Management (BLM) is cooperating with DOE in the NEPA review and is serving as the lead federal agency for compliance with the National Historic Preservation Act (NHPA) cultural resource review and Section 106 consultation process.

DOE has been working closely with BLM in the NHPA cultural review process and, at BLM's request, would like to inform you of the status of the review. Class III cultural resource surveys have been completed at the proposed power plant site and along the transmission alignments. The surveys have identified archaeological sites in the project area. A table summarizing potential effects of the Project on these sites is attached.

As indicated in my September 27 letter, DOE is available for government-to-government consultation on the Project at your request, and looks forward to participating with you in completing the environmental and cultural resource review process. DOE believes that consideration of any comments or concerns you provide, particularly with regard to sites of religious and cultural significance, will help ensure that DOE and BLM comply with our NEPA and NHPA Section 106 responsibilities for the Project.

Questions concerning the cultural review or Section 106 consultation process for the Project should be directed to Mr. Jim Shearer in the BLM Barstow Field Office (see contact information below). I would also appreciate being copied on correspondence to Mr. Shearer so I am apprised



of any concerns that you might have. I can be reached by e-mail at matthew.mcmillen@hq.doe.gov, by phone at 202-586-7248, or by mail at US Department of Energy, Loan Programs Office, LP-10, 1000 Independence Ave. SW, Washington, DC 20585.

Respectfully,



Matthew C. McMillen
Director, Environmental Compliance
Loan Programs Office

Enclosure

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Office

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Road
Barstow, CA 92311
JShearer@BLM.gov
760.252.6034



Department of Energy
Washington, DC 20585

February 8, 2011

Mr. Anthony Madrigal
Cultural Lead
Twenty-Nine Palms Band of Mission Indians
46-200 Harrison Street
Coachella, CA 92236

Subject: Consultation for the Abengoa Mojave Solar Project

Dear Mr. Madrigal:

In my September 27, 2010 letter to you, I indicated that the US Department of Energy (DOE) is considering issuing a loan guarantee to support construction of the proposed Abengoa Mojave Solar Project (the Project), a solar thermal electric power plant nine miles northwest of Hinkley, California. The proposed power plant site would be located on previously farmed land. Telecommunication upgrades would also be required along existing transmission alignments. Minimal ground disturbance would occur along the alignments because existing access roads and poles would be used, with very few new or replacement poles needed.

My September 27 letter also noted that, with regard to the Project, DOE was serving as the lead federal agency for compliance with the National Environmental Policy Act (NEPA), and the US Bureau of Land Management (BLM) is cooperating with DOE in the NEPA review and is serving as the lead federal agency for compliance with the National Historic Preservation Act (NHPA) cultural resource review and Section 106 consultation process.

DOE has been working closely with BLM in the NHPA cultural review process and, at BLM's request, would like to inform you of the status of the review. Class III cultural resource surveys have been completed at the proposed power plant site and along the transmission alignments. The surveys have identified archaeological sites in the project area. A table summarizing potential effects of the Project on these sites is attached.

As indicated in my September 27 letter, DOE is available for government-to-government consultation on the Project at your request, and looks forward to participating with you in completing the environmental and cultural resource review process. DOE believes that consideration of any comments or concerns you provide, particularly with regard to sites of religious and cultural significance, will help ensure that DOE and BLM comply with our NEPA and NHPA Section 106 responsibilities for the Project.

Questions concerning the cultural review or Section 106 consultation process for the Project should be directed to Mr. Jim Shearer in the BLM Barstow Field Office (see contact information below). I would also appreciate being copied on correspondence to Mr. Shearer so I am apprised



of any concerns that you might have. I can be reached by e-mail at matthew.mcmillen@hq.doe.gov, by phone at 202-586-7248, or by mail at US Department of Energy, Loan Programs Office, LP-10, 1000 Independence Ave. SW, Washington, DC 20585.

Respectfully,



Matthew C. McMillen
Director, Environmental Compliance
Loan Programs Office

Enclosure

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Office

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Road
Barstow, CA 92311
JShearer@BLM.gov
760.252.6034



Department of Energy
Washington, DC 20585

February 8, 2011

Honorable Darrell Mike
Chairperson
Twenty-Nine Palms Band of Mission Indians
46-200 Harrison Street
Coachella, CA 92236

Subject: Consultation for the Abengoa Mojave Solar Project

Dear Chairperson Mike:

In my September 27, 2010 letter to you, I indicated that the US Department of Energy (DOE) is considering issuing a loan guarantee to support construction of the proposed Abengoa Mojave Solar Project (the Project), a solar thermal electric power plant nine miles northwest of Hinkley, California. The proposed power plant site would be located on previously farmed land. Telecommunication upgrades would also be required along existing transmission alignments. Minimal ground disturbance would occur along the alignments because existing access roads and poles would be used, with very few new or replacement poles needed.

My September 27 letter also noted that, with regard to the Project, DOE was serving as the lead federal agency for compliance with the National Environmental Policy Act (NEPA), and the US Bureau of Land Management (BLM) is cooperating with DOE in the NEPA review and is serving as the lead federal agency for compliance with the National Historic Preservation Act (NHPA) cultural resource review and Section 106 consultation process.

DOE has been working closely with BLM in the NHPA cultural review process and, at BLM's request, would like to inform you of the status of the review. Class III cultural resource surveys have been completed at the proposed power plant site and along the transmission alignments. The surveys have identified archaeological sites in the project area. A table summarizing potential effects of the Project on these sites is attached.

As indicated in my September 27 letter, DOE is available for government-to-government consultation on the Project at your request, and looks forward to participating with you in completing the environmental and cultural resource review process. DOE believes that consideration of any comments or concerns you provide, particularly with regard to sites of religious and cultural significance, will help ensure that DOE and BLM comply with our NEPA and NHPA Section 106 responsibilities for the Project.

Questions concerning the cultural review or Section 106 consultation process for the Project should be directed to Mr. Jim Shearer in the BLM Barstow Field Office (see contact information below). I would also appreciate being copied on correspondence to Mr. Shearer so I am apprised



of any concerns that you might have. I can be reached by e-mail at matthew.mcmillen@hq.doe.gov, by phone at 202-586-7248, or by mail at US Department of Energy, Loan Programs Office, LP-10, 1000 Independence Ave. SW, Washington, DC 20585.

Respectfully,

A handwritten signature in blue ink, reading "Matthew C. McMillen". The signature is fluid and cursive, with the first name "Matthew" being more prominent than the last name "McMillen".

Matthew C. McMillen
Director, Environmental Compliance
Loan Programs Office

Enclosure

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Office

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Road
Barstow, CA 92311
JShearer@BLM.gov
760.252.6034



Department of Energy
Washington, DC 20585

February 8, 2011

Honorable James Ramos
Chairman
San Manuel Band of Mission Indians
26569 Community Center Drive
Highland, CA 92346

Subject: Consultation for the Abengoa Mojave Solar Project

Dear Chairman Ramos:

In my September 27, 2010 letter to you, I indicated that the US Department of Energy (DOE) is considering issuing a loan guarantee to support construction of the proposed Abengoa Mojave Solar Project (the Project), a solar thermal electric power plant nine miles northwest of Hinkley, California. The proposed power plant site would be located on previously farmed land. Telecommunication upgrades would also be required along existing transmission alignments. Minimal ground disturbance would occur along the alignments because existing access roads and poles would be used, with very few new or replacement poles needed.

My September 27 letter also noted that, with regard to the Project, DOE was serving as the lead federal agency for compliance with the National Environmental Policy Act (NEPA), and the US Bureau of Land Management (BLM) is cooperating with DOE in the NEPA review and is serving as the lead federal agency for compliance with the National Historic Preservation Act (NHPA) cultural resource review and Section 106 consultation process.

DOE has been working closely with BLM in the NHPA cultural review process and, at BLM's request, would like to inform you of the status of the review. Class III cultural resource surveys have been completed at the proposed power plant site and along the transmission alignments. The surveys have identified archaeological sites in the project area. A table summarizing potential effects of the Project on these sites is attached.

As indicated in my September 27 letter, DOE is available for government-to-government consultation on the Project at your request, and looks forward to participating with you in completing the environmental and cultural resource review process. DOE believes that consideration of any comments or concerns you provide, particularly with regard to sites of religious and cultural significance, will help ensure that DOE and BLM comply with our NEPA and NHPA Section 106 responsibilities for the Project.

Questions concerning the cultural review or Section 106 consultation process for the Project should be directed to Mr. Jim Shearer in the BLM Barstow Field Office (see contact information below). I would also appreciate being copied on correspondence to Mr. Shearer so I am apprised



of any concerns that you might have. I can be reached by e-mail at matthew.mcmillen@hq.doe.gov , by phone at 202-586-7248, or by mail at US Department of Energy, Loan Programs Office, LP-10, 1000 Independence Ave. SW, Washington, DC 20585.

Respectfully,



Matthew C. McMillen
Director, Environmental Compliance
Loan Programs Office

Enclosure

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Office

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Road
Barstow, CA 92311
JShearer@BLM.gov
760.252.6034



Department of Energy
Washington, DC 20585

February 8, 2011

Ms. June Leivas, Cultural Lead
Chemehuevi Reservation
P.O. Box 1976
Havas Lake, CA 92363

Subject: Consultation for the Abengoa Mojave Solar Project

Dear Ms. Leivas:

In my September 27, 2010 letter to you, I indicated that the US Department of Energy (DOE) is considering issuing a loan guarantee to support construction of the proposed Abengoa Mojave Solar Project (the Project), a solar thermal electric power plant nine miles northwest of Hinkley, California. The proposed power plant site would be located on previously farmed land. Telecommunication upgrades would also be required along existing transmission alignments. Minimal ground disturbance would occur along the alignments because existing access roads and poles would be used, with very few new or replacement poles needed.

My September 27 letter also noted that, with regard to the Project, DOE was serving as the lead federal agency for compliance with the National Environmental Policy Act (NEPA), and the US Bureau of Land Management (BLM) is cooperating with DOE in the NEPA review and is serving as the lead federal agency for compliance with the National Historic Preservation Act (NHPA) cultural resource review and Section 106 consultation process.

DOE has been working closely with BLM in the NHPA cultural review process and, at BLM's request, would like to inform you of the status of the review. Class III cultural resource surveys have been completed at the proposed power plant site and along the transmission alignments. The surveys have identified archaeological sites in the project area. A table summarizing potential effects of the Project on these sites is attached.

As indicated in my September 27 letter, DOE is available for government-to-government consultation on the Project at your request, and looks forward to participating with you in completing the environmental and cultural resource review process. DOE believes that consideration of any comments or concerns you provide, particularly with regard to sites of religious and cultural significance, will help ensure that DOE and BLM comply with our NEPA and NHPA Section 106 responsibilities for the Project.

Questions concerning the cultural review or Section 106 consultation process for the Project should be directed to Mr. Jim Shearer in the BLM Barstow Field Office (see contact information below). I would also appreciate being copied on correspondence to Mr. Shearer so I am apprised



of any concerns that you might have. I can be reached by e-mail at matthew.mcmillen@hq.doe.gov , by phone at 202-586-7248, or by mail at US Department of Energy, Loan Programs Office, LP-10, 1000 Independence Ave. SW, Washington, DC 20585.

Respectfully,



Matthew C. McMillen
Director, Environmental Compliance
Loan Programs Office

Enclosure

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Office

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Road
Barstow, CA 92311
JShearer@BLM.gov
760.252.6034



Department of Energy
Washington, DC 20585

February 8, 2011

Honorable Jamie Fullmer
Chairman
Yavapai-Apache Nation of the Camp
2400 W. Datsi
Camp Verde, AZ 86322

Subject: Consultation for the Abengoa Mojave Solar Project

Dear Chairman Fullmer:

In my September 27, 2010 letter to you, I indicated that the US Department of Energy (DOE) is considering issuing a loan guarantee to support construction of the proposed Abengoa Mojave Solar Project (the Project), a solar thermal electric power plant nine miles northwest of Hinkley, California. The proposed power plant site would be located on previously farmed land. Telecommunication upgrades would also be required along existing transmission alignments. Minimal ground disturbance would occur along the alignments because existing access roads and poles would be used, with very few new or replacement poles needed.

My September 27 letter also noted that, with regard to the Project, DOE was serving as the lead federal agency for compliance with the National Environmental Policy Act (NEPA), and the US Bureau of Land Management (BLM) is cooperating with DOE in the NEPA review and is serving as the lead federal agency for compliance with the National Historic Preservation Act (NHPA) cultural resource review and Section 106 consultation process.

DOE has been working closely with BLM in the NHPA cultural review process and, at BLM's request, would like to inform you of the status of the review. Class III cultural resource surveys have been completed at the proposed power plant site and along the transmission alignments. The surveys have identified archaeological sites in the project area. A table summarizing potential effects of the Project on these sites is attached.

As indicated in my September 27 letter, DOE is available for government-to-government consultation on the Project at your request, and looks forward to participating with you in completing the environmental and cultural resource review process. DOE believes that consideration of any comments or concerns you provide, particularly with regard to sites of religious and cultural significance, will help ensure that DOE and BLM comply with our NEPA and NHPA Section 106 responsibilities for the Project.

Questions concerning the cultural review or Section 106 consultation process for the Project should be directed to Mr. Jim Shearer in the BLM Barstow Field Office (see contact information below). I would also appreciate being copied on correspondence to Mr. Shearer so I am apprised



of any concerns that you might have. I can be reached by e-mail at matthew.mcmillen@hq.doe.gov , by phone at 202-586-7248, or by mail at US Department of Energy, Loan Programs Office, LP-10, 1000 Independence Ave. SW, Washington, DC 20585.

Respectfully,



Matthew C. McMillen
Director, Environmental Compliance
Loan Programs Office

Enclosure

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Office

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Road
Barstow, CA 92311
JShearer@BLM.gov
760.252.6034



Department of Energy

Washington, DC 20585

February 8, 2011

Mr. Mike Contreras
Morongo Band of Mission Indians
Cultural Heritage Program
12700 Pumarra Road
Banning, CA 92220

Subject: Consultation for the Abengoa Mojave Solar Project

Dear Mr. Contreras:

In my September 27, 2010 letter to you, I indicated that the US Department of Energy (DOE) is considering issuing a loan guarantee to support construction of the proposed Abengoa Mojave Solar Project (the Project), a solar thermal electric power plant nine miles northwest of Hinkley, California. The proposed power plant site would be located on previously farmed land. Telecommunication upgrades would also be required along existing transmission alignments. Minimal ground disturbance would occur along the alignments because existing access roads and poles would be used, with very few new or replacement poles needed.

My September 27 letter also noted that, with regard to the Project, DOE was serving as the lead federal agency for compliance with the National Environmental Policy Act (NEPA), and the US Bureau of Land Management (BLM) is cooperating with DOE in the NEPA review and is serving as the lead federal agency for compliance with the National Historic Preservation Act (NHPA) cultural resource review and Section 106 consultation process.

DOE has been working closely with BLM in the NHPA cultural review process and, at BLM's request, would like to inform you of the status of the review. Class III cultural resource surveys have been completed at the proposed power plant site and along the transmission alignments. The surveys have identified archaeological sites in the project area. A table summarizing potential effects of the Project on these sites is attached.

As indicated in my September 27 letter, DOE is available for government-to-government consultation on the Project at your request, and looks forward to participating with you in completing the environmental and cultural resource review process. DOE believes that consideration of any comments or concerns you provide, particularly with regard to sites of religious and cultural significance, will help ensure that DOE and BLM comply with our NEPA and NHPA Section 106 responsibilities for the Project.

Questions concerning the cultural review or Section 106 consultation process for the Project should be directed to Mr. Jim Shearer in the BLM Barstow Field Office (see contact information below). I would also appreciate being copied on correspondence to Mr. Shearer so I am apprised



of any concerns that you might have. I can be reached by e-mail at matthew.mcmillen@hq.doe.gov, by phone at 202-586-7248, or by mail at US Department of Energy, Loan Programs Office, LP-10, 1000 Independence Ave. SW, Washington, DC 20585.

Respectfully,


Matthew C. McMillen
Director, Environmental Compliance
Loan Programs Office

Enclosure

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Office

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Road
Barstow, CA 92311
JShearer@BLM.gov
760.252.6034



Department of Energy
Washington, DC 20585

February 8, 2011

Honorable Robert Martin
Chairperson
Morongo Band of Mission Indians
12700 Pumarra Road
Banning, CA 92220

Subject: Consultation for the Abengoa Mojave Solar Project

Dear Chairperson Martin:

In my September 27, 2010 letter to you, I indicated that the US Department of Energy (DOE) is considering issuing a loan guarantee to support construction of the proposed Abengoa Mojave Solar Project (the Project), a solar thermal electric power plant nine miles northwest of Hinkley, California. The proposed power plant site would be located on previously farmed land. Telecommunication upgrades would also be required along existing transmission alignments. Minimal ground disturbance would occur along the alignments because existing access roads and poles would be used, with very few new or replacement poles needed.

My September 27 letter also noted that, with regard to the Project, DOE was serving as the lead federal agency for compliance with the National Environmental Policy Act (NEPA), and the US Bureau of Land Management (BLM) is cooperating with DOE in the NEPA review and is serving as the lead federal agency for compliance with the National Historic Preservation Act (NHPA) cultural resource review and Section 106 consultation process.

DOE has been working closely with BLM in the NHPA cultural review process and, at BLM's request, would like to inform you of the status of the review. Class III cultural resource surveys have been completed at the proposed power plant site and along the transmission alignments. The surveys have identified archaeological sites in the project area. A table summarizing potential effects of the Project on these sites is attached.

As indicated in my September 27 letter, DOE is available for government-to-government consultation on the Project at your request, and looks forward to participating with you in completing the environmental and cultural resource review process. DOE believes that consideration of any comments or concerns you provide, particularly with regard to sites of religious and cultural significance, will help ensure that DOE and BLM comply with our NEPA and NHPA Section 106 responsibilities for the Project.

Questions concerning the cultural review or Section 106 consultation process for the Project should be directed to Mr. Jim Shearer in the BLM Barstow Field Office (see contact information below). I would also appreciate being copied on correspondence to Mr. Shearer so I am apprised



of any concerns that you might have. I can be reached by e-mail at matthew.mcmillen@hq.doe.gov , by phone at 202-586-7248, or by mail at US Department of Energy, Loan Programs Office, LP-10, 1000 Independence Ave. SW, Washington, DC 20585.

Respectfully,



Matthew C. McMillen
Director, Environmental Compliance
Loan Programs Office

Enclosure

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Office

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Road
Barstow, CA 92311
JShearer@BLM.gov
760.252.6034



Department of Energy

Washington, DC 20585

September 27, 2010

Honorable Charles Wood
Chairman
Chemehuevi Reservation
PO Box 1976
Havasu Lake, CA 92363

Subject: Federal Loan Guarantee to Abengoa Solar

Dear Chairman Wood:

The U.S. Department of Energy (DOE) is evaluating the application of a company called Abengoa Solar (Abengoa) for a Federal loan guarantee to construct a solar thermal electric power plant nine miles northwest of the town of Hinkley, California, in unincorporated San Bernardino County. DOE will be performing an environmental review of the Abengoa Project in compliance with the National Environmental Policy Act (NEPA).

In addition to the solar power plant, the proposed project would include transmission alignment telecom upgrades that cross Bureau of Land Management (BLM) land. BLM has agreed to be a cooperating agency in accordance with a Memorandum of Understanding between the DOE and BLM, signed in January 2010. Because of BLM's special expertise, DOE is deferring lead authority to BLM solely for activities pertaining to historic resources review to comply with Section 106 of the National Historic Preservation Act. Under DOE's deferment, and as provided for in 36 C.F.R. § 800.2 (a) (2), BLM will act on DOE's behalf to fulfill the collective responsibilities of DOE and BLM under Section 106. Otherwise, DOE will continue to play an active role as the project lead for the NEPA review process, and is available for government-to-government consultation on those matters. BLM's point of contact is Mr. Jim Shearer, who is copied on this letter.

Our records show that your Tribe has expressed an historical interest in San Bernardino County, California. I am writing this letter to extend an opportunity to you to provide comments on the proposed loan guarantee to Abengoa. Consideration of any comments or concerns you provide will help ensure that DOE complies with its NEPA responsibilities.


The project would be located on 1,765 acres, approximately halfway between the city of Barstow and Kramer Junction (Highway 395/58 Junction). The site is in a rural area used previously for farming. To assist you, a more detailed description of the proposed project, and a map showing the proposed plant site (shown as AMSP), and transmission alignments (shown in red), are enclosed.



Currently, a third-party consultant, AECOM, of San Diego, California is undertaking cultural resource Class III surveys for the entire project area. They may be contacting you to gather additional information.

We would greatly appreciate receiving any comments or concerns you may have regarding the NEPA review process by October 25, 2010. Please direct comments related to the Section 106 consultation process to Jim Shearer from the BLM's Barstow office. His contact information is provided below. Please also copy me via email to matthew.mcmillen@hq.doe.gov on comments sent to Mr. Shearer so that I am apprised of any concerns you might have. Written comments regarding the NEPA review can be sent via email to matthew.mcmillen@hq.doe.gov, or sent to the following address: U.S. Department of Energy, 1000 Independence Ave., SW, LP-10, Washington, DC 20585. I can also be reached by telephone at 202-586-7248.

Respectfully,



Matthew McMillen
Director, Environmental Compliance
DOE Loan Programs Office

Enclosures

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Officer

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Rd.
Barstow, CA 92311
(760) 252.6034
jshearer@blm.gov



Department of Energy
Washington, DC 20585

September 27, 2010

Ms. June Leivas
Cultural Lead
Chemehuevi Reservation
PO Box 1976
Havasup Lake, CA 92363

Subject: Federal Loan Guarantee to Abengoa Solar

Dear Ms. Leivas:

The U.S. Department of Energy (DOE) is evaluating the application of a company called Abengoa Solar (Abengoa) for a Federal loan guarantee to construct a solar thermal electric power plant nine miles northwest of the town of Hinkley, California, in unincorporated San Bernardino County. DOE will be performing an environmental review of the Abengoa Project in compliance with the National Environmental Policy Act (NEPA).

In addition to the solar power plant, the proposed project would include transmission alignment telecom upgrades that cross Bureau of Land Management (BLM) land. BLM has agreed to be a cooperating agency in accordance with a Memorandum of Understanding between the DOE and BLM, signed in January 2010. Because of BLM's special expertise, DOE is deferring lead authority to BLM solely for activities pertaining to historic resources review to comply with Section 106 of the National Historic Preservation Act. Under DOE's deferment, and as provided for in 36 C.F.R. § 800.2 (a) (2), BLM will act on DOE's behalf to fulfill the collective responsibilities of DOE and BLM under Section 106. Otherwise, DOE will continue to play an active role as the project lead for the NEPA review process, and is available for government-to-government consultation on those matters. BLM's point of contact is Mr. Jim Shearer, who is copied on this letter.

Our records show that your Tribe has expressed an historical interest in San Bernardino County, California. I am writing this letter to extend an opportunity to you to provide comments on the proposed loan guarantee to Abengoa. Consideration of any comments or concerns you provide will help ensure that DOE complies with its NEPA responsibilities.

The project would be located on 1,765 acres, approximately halfway between the city of Barstow and Kramer Junction (Highway 395/58 Junction). The site is in a rural area used previously for farming. To assist you, a more detailed description of the proposed project, and a map showing the proposed plant site (shown as AMSP), and transmission alignments (shown in red), are enclosed.



Currently, a third-party consultant, AECOM, of San Diego, California is undertaking cultural resource Class III surveys for the entire project area. They may be contacting you to gather additional information.

We would greatly appreciate receiving any comments or concerns you may have regarding the NEPA review process by October 25, 2010. Please direct comments related to the Section 106 consultation process to Jim Shearer from the BLM's Barstow office. His contact information is provided below. Please also copy me via email to matthew.mcmillen@hq.doe.gov on comments sent to Mr. Shearer so that I am apprised of any concerns you might have. Written comments regarding the NEPA review can be sent via email to matthew.mcmillen@hq.doe.gov, or sent to the following address: U.S. Department of Energy, 1000 Independence Ave., SW, LP-10, Washington, DC 20585. I can also be reached by telephone at 202-586-7248.

Respectfully,



Matthew McMillen
Director, Environmental Compliance
DOE Loan Programs Office

Enclosures

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Officer

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Rd.
Barstow, CA 92311
(760) 252.6034
jshearer@blm.gov



Department of Energy
Washington, DC 20585

September 27, 2010

Mr. Mike Contreras
Cultural Heritage Program
Morongo Band of Mission Indians
12700 Pumarra Road
Banning, CA 92220

Subject: Federal Loan Guarantee to Abengoa Solar

Dear Mr. Contreras:

The U.S. Department of Energy (DOE) is evaluating the application of a company called Abengoa Solar (Abengoa) for a Federal loan guarantee to construct a solar thermal electric power plant nine miles northwest of the town of Hinkley, California, in unincorporated San Bernardino County. DOE will be performing an environmental review of the Abengoa Project in compliance with the National Environmental Policy Act (NEPA).

In addition to the solar power plant, the proposed project would include transmission alignment telecom upgrades that cross Bureau of Land Management (BLM) land. BLM has agreed to be a cooperating agency in accordance with a Memorandum of Understanding between the DOE and BLM, signed in January 2010. Because of BLM's special expertise, DOE is deferring lead authority to BLM solely for activities pertaining to historic resources review to comply with Section 106 of the National Historic Preservation Act. Under DOE's deferment, and as provided for in 36 C.F.R. § 800.2 (a) (2), BLM will act on DOE's behalf to fulfill the collective responsibilities of DOE and BLM under Section 106. Otherwise, DOE will continue to play an active role as the project lead for the NEPA review process, and is available for government-to-government consultation on those matters. BLM's point of contact is Mr. Jim Shearer, who is copied on this letter.

Our records show that your Tribe has expressed an historical interest in San Bernardino County, California. I am writing this letter to extend an opportunity to you to provide comments on the proposed loan guarantee to Abengoa. Consideration of any comments or concerns you provide will help ensure that DOE complies with its NEPA responsibilities.

The project would be located on 1,765 acres, approximately halfway between the city of Barstow and Kramer Junction (Highway 395/58 Junction). The site is in a rural area used previously for farming. To assist you, a more detailed description of the proposed project, and a map showing the proposed plant site (shown as AMSP), and transmission alignments (shown in red), are enclosed.



Currently, a third-party consultant, AECOM, of San Diego, California is undertaking cultural resource Class III surveys for the entire project area. They may be contacting you to gather additional information.

We would greatly appreciate receiving any comments or concerns you may have regarding the NEPA review process by October 25, 2010. Please direct comments related to the Section 106 consultation process to Jim Shearer from the BLM's Barstow office. His contact information is provided below. Please also copy me via email to matthew.mcmillen@hq.doe.gov on comments sent to Mr. Shearer so that I am apprised of any concerns you might have. Written comments regarding the NEPA review can be sent via email to matthew.mcmillen@hq.doe.gov, or sent to the following address: U.S. Department of Energy, 1000 Independence Ave., SW, LP-10, Washington, DC 20585. I can also be reached by telephone at 202-586-7248.

Respectfully,



Matthew McMillen
Director, Environmental Compliance
DOE Loan Programs Office

Enclosures

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Officer

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Rd.
Barstow, CA 92311
(760) 252.6034
jshearer@blm.gov



Department of Energy

Washington, DC 20585

September 27, 2010

Honorable Robert Martin
Chairperson
Morongo Band of Mission Indians
12700 Pumarra Road
Banning, CA 92220

Subject: Federal Loan Guarantee to Abengoa Solar

Dear Chairman Martin:

The U.S. Department of Energy (DOE) is evaluating the application of a company called Abengoa Solar (Abengoa) for a Federal loan guarantee to construct a solar thermal electric power plant nine miles northwest of the town of Hinkley, California, in unincorporated San Bernardino County. DOE will be performing an environmental review of the Abengoa Project in compliance with the National Environmental Policy Act (NEPA).

In addition to the solar power plant, the proposed project would include transmission alignment telecom upgrades that cross Bureau of Land Management (BLM) land. BLM has agreed to be a cooperating agency in accordance with a Memorandum of Understanding between the DOE and BLM, signed in January 2010. Because of BLM's special expertise, DOE is deferring lead authority to BLM solely for activities pertaining to historic resources review to comply with Section 106 of the National Historic Preservation Act. Under DOE's deferment, and as provided for in 36 C.F.R. § 800.2 (a) (2), BLM will act on DOE's behalf to fulfill the collective responsibilities of DOE and BLM under Section 106. Otherwise, DOE will continue to play an active role as the project lead for the NEPA review process, and is available for government-to-government consultation on those matters. BLM's point of contact is Mr. Jim Shearer, who is copied on this letter.

Our records show that your Tribe has expressed an historical interest in San Bernardino County, California. I am writing this letter to extend an opportunity to you to provide comments on the proposed loan guarantee to Abengoa. Consideration of any comments or concerns you provide will help ensure that DOE complies with its NEPA responsibilities.


The project would be located on 1,765 acres, approximately halfway between the city of Barstow and Kramer Junction (Highway 395/58 Junction). The site is in a rural area used previously for farming. To assist you, a more detailed description of the proposed project, and a map showing the proposed plant site (shown as AMSP), and transmission alignments (shown in red), are enclosed.



Currently, a third-party consultant, AECOM, of San Diego, California is undertaking cultural resource Class III surveys for the entire project area. They may be contacting you to gather additional information.

We would greatly appreciate receiving any comments or concerns you may have regarding the NEPA review process by October 25, 2010. Please direct comments related to the Section 106 consultation process to Jim Shearer from the BLM's Barstow office. His contact information is provided below. Please also copy me via email to matthew.mcmillen@hq.doe.gov on comments sent to Mr. Shearer so that I am apprised of any concerns you might have. Written comments regarding the NEPA review can be sent via email to matthew.mcmillen@hq.doe.gov, or sent to the following address: U.S. Department of Energy, 1000 Independence Ave., SW, LP-10, Washington, DC 20585. I can also be reached by telephone at 202-586-7248.

Respectfully,



Matthew McMillen
Director, Environmental Compliance
DOE Loan Programs Office

Enclosures

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Officer

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Rd.
Barstow, CA 92311
(760) 252.6034
jshearer@blm.gov



Department of Energy
Washington, DC 20585

September 27, 2010

Ms. Ann Brierty
Environmental Division
San Manuel Band of Mission Indians
26569 Community Center Drive
Highland, CA 92346

Subject: Federal Loan Guarantee to Abengoa Solar

Dear Ms. Brierty:

The U.S. Department of Energy (DOE) is evaluating the application of a company called Abengoa Solar (Abengoa) for a Federal loan guarantee to construct a solar thermal electric power plant nine miles northwest of the town of Hinkley, California, in unincorporated San Bernardino County. DOE will be performing an environmental review of the Abengoa Project in compliance with the National Environmental Policy Act (NEPA).

In addition to the solar power plant, the proposed project would include transmission alignment telecom upgrades that cross Bureau of Land Management (BLM) land. BLM has agreed to be a cooperating agency in accordance with a Memorandum of Understanding between the DOE and BLM, signed in January 2010. Because of BLM's special expertise, DOE is deferring lead authority to BLM solely for activities pertaining to historic resources review to comply with Section 106 of the National Historic Preservation Act. Under DOE's deferment, and as provided for in 36 C.F.R. § 800.2 (a) (2), BLM will act on DOE's behalf to fulfill the collective responsibilities of DOE and BLM under Section 106. Otherwise, DOE will continue to play an active role as the project lead for the NEPA review process, and is available for government-to-government consultation on those matters. BLM's point of contact is Mr. Jim Shearer, who is copied on this letter.

Our records show that your Tribe has expressed an historical interest in San Bernardino County, California. I am writing this letter to extend an opportunity to you to provide comments on the proposed loan guarantee to Abengoa. Consideration of any comments or concerns you provide will help ensure that DOE complies with its NEPA responsibilities.


The project would be located on 1,765 acres, approximately halfway between the city of Barstow and Kramer Junction (Highway 395/58 Junction). The site is in a rural area used previously for farming. To assist you, a more detailed description of the proposed project, and a map showing the proposed plant site (shown as AMSP), and transmission alignments (shown in red), are enclosed.



Currently, a third-party consultant, AECOM, of San Diego, California is undertaking cultural resource Class III surveys for the entire project area. They may be contacting you to gather additional information.

We would greatly appreciate receiving any comments or concerns you may have regarding the NEPA review process by October 25, 2010. Please direct comments related to the Section 106 consultation process to Jim Shearer from the BLM's Barstow office. His contact information is provided below. Please also copy me via email to matthew.mcmillen@hq.doe.gov on comments sent to Mr. Shearer so that I am apprised of any concerns you might have. Written comments regarding the NEPA review can be sent via email to matthew.mcmillen@hq.doe.gov, or sent to the following address: U.S. Department of Energy, 1000 Independence Ave., SW, LP-10, Washington, DC 20585. I can also be reached by telephone at 202-586-7248.

Respectfully,



Matthew McMillen
Director, Environmental Compliance
DOE Loan Programs Office

Enclosures

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Officer

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Rd.
Barstow, CA 92311
(760) 252.6034
jshearer@blm.gov



Department of Energy
Washington, DC 20585

September 27, 2010

Honorable James Ramos
Chairman
San Manuel Band of Mission Indians
26569 Community Center Drive
Highland, CA 92346

Subject: Federal Loan Guarantee to Abengoa Solar

Dear Chairman Ramos:

The U.S. Department of Energy (DOE) is evaluating the application of a company called Abengoa Solar (Abengoa) for a Federal loan guarantee to construct a solar thermal electric power plant nine miles northwest of the town of Hinkley, California, in unincorporated San Bernardino County. DOE will be performing an environmental review of the Abengoa Project in compliance with the National Environmental Policy Act (NEPA).

In addition to the solar power plant, the proposed project would include transmission alignment telecom upgrades that cross Bureau of Land Management (BLM) land. BLM has agreed to be a cooperating agency in accordance with a Memorandum of Understanding between the DOE and BLM, signed in January 2010. Because of BLM's special expertise, DOE is deferring lead authority to BLM solely for activities pertaining to historic resources review to comply with Section 106 of the National Historic Preservation Act. Under DOE's deferment, and as provided for in 36 C.F.R. § 800.2 (a) (2), BLM will act on DOE's behalf to fulfill the collective responsibilities of DOE and BLM under Section 106. Otherwise, DOE will continue to play an active role as the project lead for the NEPA review process, and is available for government-to-government consultation on those matters. BLM's point of contact is Mr. Jim Shearer, who is copied on this letter.

Our records show that your Tribe has expressed an historical interest in San Bernardino County, California. I am writing this letter to extend an opportunity to you to provide comments on the proposed loan guarantee to Abengoa. Consideration of any comments or concerns you provide will help ensure that DOE complies with its NEPA responsibilities.

The project would be located on 1,765 acres, approximately halfway between the city of Barstow and Kramer Junction (Highway 395/58 Junction). The site is in a rural area used previously for farming. To assist you, a more detailed description of the proposed project, and a map showing the proposed plant site (shown as AMSP), and transmission alignments (shown in red), are enclosed.



Currently, a third-party consultant, AECOM, of San Diego, California is undertaking cultural resource Class III surveys for the entire project area. They may be contacting you to gather additional information.

We would greatly appreciate receiving any comments or concerns you may have regarding the NEPA review process by October 25, 2010. Please direct comments related to the Section 106 consultation process to Jim Shearer from the BLM's Barstow office. His contact information is provided below. Please also copy me via email to matthew.mcmillen@hq.doe.gov on comments sent to Mr. Shearer so that I am apprised of any concerns you might have. Written comments regarding the NEPA review can be sent via email to matthew.mcmillen@hq.doe.gov, or sent to the following address: U.S. Department of Energy, 1000 Independence Ave., SW, LP-10, Washington, DC 20585. I can also be reached by telephone at 202-586-7248.

Respectfully,



Matthew McMillen
Director, Environmental Compliance
DOE Loan Programs Office

Enclosures

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Officer

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Rd.
Barstow, CA 92311
(760) 252.6034
jshearer@blm.gov



Department of Energy

Washington, DC 20585

September 27, 2010

Honorable Darrell Mike
Chairperson
Twenty-Nine Palms Band of Mission Indians
46-200 Harrison Street
Coachella, CA 92236

Subject: Federal Loan Guarantee to Abengoa Solar

Dear Chairman Mike:

The U.S. Department of Energy (DOE) is evaluating the application of a company called Abengoa Solar (Abengoa) for a Federal loan guarantee to construct a solar thermal electric power plant nine miles northwest of the town of Hinkley, California, in unincorporated San Bernardino County. DOE will be performing an environmental review of the Abengoa Project in compliance with the National Environmental Policy Act (NEPA).

In addition to the solar power plant, the proposed project would include transmission alignment telecom upgrades that cross Bureau of Land Management (BLM) land. BLM has agreed to be a cooperating agency in accordance with a Memorandum of Understanding between the DOE and BLM, signed in January 2010. Because of BLM's special expertise, DOE is deferring lead authority to BLM solely for activities pertaining to historic resources review to comply with Section 106 of the National Historic Preservation Act. Under DOE's deferment, and as provided for in 36 C.F.R. § 800.2 (a) (2), BLM will act on DOE's behalf to fulfill the collective responsibilities of DOE and BLM under Section 106. Otherwise, DOE will continue to play an active role as the project lead for the NEPA review process, and is available for government-to-government consultation on those matters. BLM's point of contact is Mr. Jim Shearer, who is copied on this letter.

Our records show that your Tribe has expressed an historical interest in San Bernardino County, California. I am writing this letter to extend an opportunity to you to provide comments on the proposed loan guarantee to Abengoa. Consideration of any comments or concerns you provide will help ensure that DOE complies with its NEPA responsibilities.


The project would be located on 1,765 acres, approximately halfway between the city of Barstow and Kramer Junction (Highway 395/58 Junction). The site is in a rural area used previously for farming. To assist you, a more detailed description of the proposed project, and a map showing the proposed plant site (shown as AMSP), and transmission alignments (shown in red), are enclosed.



Currently, a third-party consultant, AECOM, of San Diego, California is undertaking cultural resource Class III surveys for the entire project area. They may be contacting you to gather additional information.

We would greatly appreciate receiving any comments or concerns you may have regarding the NEPA review process by October 25, 2010. Please direct comments related to the Section 106 consultation process to Jim Shearer from the BLM's Barstow office. His contact information is provided below. Please also copy me via email to matthew.mcmillen@hq.doe.gov on comments sent to Mr. Shearer so that I am apprised of any concerns you might have. Written comments regarding the NEPA review can be sent via email to matthew.mcmillen@hq.doe.gov, or sent to the following address: U.S. Department of Energy, 1000 Independence Ave., SW, LP-10, Washington, DC 20585. I can also be reached by telephone at 202-586-7248.

Respectfully,



Matthew McMillen
Director, Environmental Compliance
DOE Loan Programs Office

Enclosures

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Officer

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Rd.
Barstow, CA 92311
(760) 252.6034
jshearer@blm.gov



Department of Energy

Washington, DC 20585

September 27, 2010

Mr. Anthony Madrigal
Cultural Lead
Twenty-Nine Palms Band of Mission Indians
46-200 Harrison Street
Coachella, CA 92236

Subject: Federal Loan Guarantee to Abengoa Solar

Dear Mr. Madrigal:

The U.S. Department of Energy (DOE) is evaluating the application of a company called Abengoa Solar (Abengoa) for a Federal loan guarantee to construct a solar thermal electric power plant nine miles northwest of the town of Hinkley, California, in unincorporated San Bernardino County. DOE will be performing an environmental review of the Abengoa Project in compliance with the National Environmental Policy Act (NEPA).

In addition to the solar power plant, the proposed project would include transmission alignment telecom upgrades that cross Bureau of Land Management (BLM) land. BLM has agreed to be a cooperating agency in accordance with a Memorandum of Understanding between the DOE and BLM, signed in January 2010. Because of BLM's special expertise, DOE is deferring lead authority to BLM solely for activities pertaining to historic resources review to comply with Section 106 of the National Historic Preservation Act. Under DOE's deferment, and as provided for in 36 C.F.R. § 800.2 (a) (2), BLM will act on DOE's behalf to fulfill the collective responsibilities of DOE and BLM under Section 106. Otherwise, DOE will continue to play an active role as the project lead for the NEPA review process, and is available for government-to-government consultation on those matters. BLM's point of contact is Mr. Jim Shearer, who is copied on this letter.

Our records show that your Tribe has expressed an historical interest in San Bernardino County, California. I am writing this letter to extend an opportunity to you to provide comments on the proposed loan guarantee to Abengoa. Consideration of any comments or concerns you provide will help ensure that DOE complies with its NEPA responsibilities.

The project would be located on 1,765 acres, approximately halfway between the city of Barstow and Kramer Junction (Highway 395/58 Junction). The site is in a rural area used previously for farming. To assist you, a more detailed description of the proposed project, and a map showing the proposed plant site (shown as AMSP), and transmission alignments (shown in red), are enclosed.



Currently, a third-party consultant, AECOM, of San Diego, California is undertaking cultural resource Class III surveys for the entire project area. They may be contacting you to gather additional information.

We would greatly appreciate receiving any comments or concerns you may have regarding the NEPA review process by October 25, 2010. Please direct comments related to the Section 106 consultation process to Jim Shearer from the BLM's Barstow office. His contact information is provided below. Please also copy me via email to matthew.mcmillen@hq.doe.gov on comments sent to Mr. Shearer so that I am apprised of any concerns you might have. Written comments regarding the NEPA review can be sent via email to matthew.mcmillen@hq.doe.gov, or sent to the following address: U.S. Department of Energy, 1000 Independence Ave., SW, LP-10, Washington, DC 20585. I can also be reached by telephone at 202-586-7248.

Respectfully,



Matthew McMillen
Director, Environmental Compliance
DOE Loan Programs Office

Enclosures

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Officer

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Rd.
Barstow, CA 92311
(760) 252.6034
jshearer@blm.gov



Department of Energy
Washington, DC 20585

September 27, 2010

Honorable Daniel Eddy
Chairman
Colorado River Indian
Tribes of the Colorado Indian
26600 Mohave Road
Parker, AZ 85344

Subject: Federal Loan Guarantee to Abengoa Solar

Dear Chairman Eddy:

The U.S. Department of Energy (DOE) is evaluating the application of a company called Abengoa Solar (Abengoa) for a Federal loan guarantee to construct a solar thermal electric power plant nine miles northwest of the town of Hinkley, California, in unincorporated San Bernardino County. DOE will be performing an environmental review of the Abengoa Project in compliance with the National Environmental Policy Act (NEPA).

In addition to the solar power plant, the proposed project would include transmission alignment telecom upgrades that cross Bureau of Land Management (BLM) land. BLM has agreed to be a cooperating agency in accordance with a Memorandum of Understanding between the DOE and BLM, signed in January 2010. Because of BLM's special expertise, DOE is deferring lead authority to BLM solely for activities pertaining to historic resources review to comply with Section 106 of the National Historic Preservation Act. Under DOE's deferment, and as provided for in 36 C.F.R. § 800.2 (a) (2), BLM will act on DOE's behalf to fulfill the collective responsibilities of DOE and BLM under Section 106. Otherwise, DOE will continue to play an active role as the project lead for the NEPA review process, and is available for government-to-government consultation on those matters. BLM's point of contact is Mr. Jim Shearer, who is copied on this letter.

Our records show that your Tribe has expressed an historical interest in San Bernardino County, California. I am writing this letter to extend an opportunity to you to provide comments on the proposed loan guarantee to Abengoa. Consideration of any comments or concerns you provide will help ensure that DOE complies with its NEPA responsibilities.

The project would be located on 1,765 acres, approximately halfway between the city of Barstow and Kramer Junction (Highway 395/58 Junction). The site is in a rural area used previously for farming. To assist you, a more detailed description of the proposed project, and a map showing the proposed plant site (shown as AMSP), and transmission alignments (shown in red), are enclosed.



Currently, a third-party consultant, AECOM, of San Diego, California is undertaking cultural resource Class III surveys for the entire project area. They may be contacting you to gather additional information.

We would greatly appreciate receiving any comments or concerns you may have regarding the NEPA review process by October 25, 2010. Please direct comments related to the Section 106 consultation process to Jim Shearer from the BLM's Barstow office. His contact information is provided below. Please also copy me via email to matthew.mcmillen@hq.doe.gov on comments sent to Mr. Shearer so that I am apprised of any concerns you might have. Written comments regarding the NEPA review can be sent via email to matthew.mcmillen@hq.doe.gov, or sent to the following address: U.S. Department of Energy, 1000 Independence Ave., SW, LP-10, Washington, DC 20585. I can also be reached by telephone at 202-586-7248.

Respectfully,



Matthew McMillen
Director, Environmental Compliance
DOE Loan Programs Office

Enclosures

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Officer

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Rd.
Barstow, CA 92311
(760) 252.6034
jshearer@blm.gov



Department of Energy
Washington, DC 20585

September 27, 2010

Mr. Ralph Bear
President
Fort McDowell Yavapai Nation
PO Box 17779
Fountain Hills, AZ 85268

Subject: Federal Loan Guarantee to Abengoa Solar

Dear Mr. Bear:

The U.S. Department of Energy (DOE) is evaluating the application of a company called Abengoa Solar (Abengoa) for a Federal loan guarantee to construct a solar thermal electric power plant nine miles northwest of the town of Hinkley, California, in unincorporated San Bernardino County. DOE will be performing an environmental review of the Abengoa Project in compliance with the National Environmental Policy Act (NEPA).

In addition to the solar power plant, the proposed project would include transmission alignment telecom upgrades that cross Bureau of Land Management (BLM) land. BLM has agreed to be a cooperating agency in accordance with a Memorandum of Understanding between the DOE and BLM, signed in January 2010. Because of BLM's special expertise, DOE is deferring lead authority to BLM solely for activities pertaining to historic resources review to comply with Section 106 of the National Historic Preservation Act. Under DOE's deferment, and as provided for in 36 C.F.R. § 800.2 (a) (2), BLM will act on DOE's behalf to fulfill the collective responsibilities of DOE and BLM under Section 106. Otherwise, DOE will continue to play an active role as the project lead for the NEPA review process, and is available for government-to-government consultation on those matters. BLM's point of contact is Mr. Jim Shearer, who is copied on this letter.

Our records show that your Tribe has expressed an historical interest in San Bernardino County, California. I am writing this letter to extend an opportunity to you to provide comments on the proposed loan guarantee to Abengoa. Consideration of any comments or concerns you provide will help ensure that DOE complies with its NEPA responsibilities.


The project would be located on 1,765 acres, approximately halfway between the city of Barstow and Kramer Junction (Highway 395/58 Junction). The site is in a rural area used previously for farming. To assist you, a more detailed description of the proposed project, and a map showing the proposed plant site (shown as AMSP), and transmission alignments (shown in red), are enclosed.



Currently, a third-party consultant, AECOM, of San Diego, California is undertaking cultural resource Class III surveys for the entire project area. They may be contacting you to gather additional information.

We would greatly appreciate receiving any comments or concerns you may have regarding the NEPA review process by October 25, 2010. Please direct comments related to the Section 106 consultation process to Jim Shearer from the BLM's Barstow office. His contact information is provided below. Please also copy me via email to matthew.mcmillen@hq.doe.gov on comments sent to Mr. Shearer so that I am apprised of any concerns you might have. Written comments regarding the NEPA review can be sent via email to matthew.mcmillen@hq.doe.gov, or sent to the following address: U.S. Department of Energy, 1000 Independence Ave., SW, LP-10, Washington, DC 20585. I can also be reached by telephone at 202-586-7248.

Respectfully,



Matthew McMillen
Director, Environmental Compliance
DOE Loan Programs Office

Enclosures

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Officer

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Rd.
Barstow, CA 92311
(760) 252.6034
jshearer@blm.gov



Department of Energy

Washington, DC 20585

September 27, 2010

Honorable Timothy Williams
Chairman
Fort Mojave Indian Tribe
500 Merriman Avenue
Needles, CA 92363

Subject: Federal Loan Guarantee to Abengoa Solar

Dear Chairman Williams:

The U.S. Department of Energy (DOE) is evaluating the application of a company called Abengoa Solar (Abengoa) for a Federal loan guarantee to construct a solar thermal electric power plant nine miles northwest of the town of Hinkley, California, in unincorporated San Bernardino County. DOE will be performing an environmental review of the Abengoa Project in compliance with the National Environmental Policy Act (NEPA).

In addition to the solar power plant, the proposed project would include transmission alignment telecom upgrades that cross Bureau of Land Management (BLM) land. BLM has agreed to be a cooperating agency in accordance with a Memorandum of Understanding between the DOE and BLM, signed in January 2010. Because of BLM's special expertise, DOE is deferring lead authority to BLM solely for activities pertaining to historic resources review to comply with Section 106 of the National Historic Preservation Act. Under DOE's deferment, and as provided for in 36 C.F.R. § 800.2 (a) (2), BLM will act on DOE's behalf to fulfill the collective responsibilities of DOE and BLM under Section 106. Otherwise, DOE will continue to play an active role as the project lead for the NEPA review process, and is available for government-to-government consultation on those matters. BLM's point of contact is Mr. Jim Shearer, who is copied on this letter.

Our records show that your Tribe has expressed an historical interest in San Bernardino County, California. I am writing this letter to extend an opportunity to you to provide comments on the proposed loan guarantee to Abengoa. Consideration of any comments or concerns you provide will help ensure that DOE complies with its NEPA responsibilities.

The project would be located on 1,765 acres, approximately halfway between the city of Barstow and Kramer Junction (Highway 395/58 Junction). The site is in a rural area used previously for farming. To assist you, a more detailed description of the proposed project, and a map showing the proposed plant site (shown as AMSP), and transmission alignments (shown in red), are enclosed.



Currently, a third-party consultant, AECOM, of San Diego, California is undertaking cultural resource Class III surveys for the entire project area. They may be contacting you to gather additional information.

We would greatly appreciate receiving any comments or concerns you may have regarding the NEPA review process by October 25, 2010. Please direct comments related to the Section 106 consultation process to Jim Shearer from the BLM's Barstow office. His contact information is provided below. Please also copy me via email to matthew.mcmillen@hq.doe.gov on comments sent to Mr. Shearer so that I am apprised of any concerns you might have. Written comments regarding the NEPA review can be sent via email to matthew.mcmillen@hq.doe.gov, or sent to the following address: U.S. Department of Energy, 1000 Independence Ave., SW, LP-10, Washington, DC 20585. I can also be reached by telephone at 202-586-7248.

Respectfully,



Matthew McMillen
Director, Environmental Compliance
DOE Loan Programs Office

Enclosures

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Officer

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Rd.
Barstow, CA 92311
(760) 252.6034
jshearer@blm.gov



Department of Energy
Washington, DC 20585

September 27, 2010

Honorable Ona Segundo
Chairperson
Kaiband Band of Paiute Indians
HC65, Box 2
Freedonia, AZ 86022

Subject: Federal Loan Guarantee to Abengoa Solar

Dear Chairperson Segundo:

The U.S. Department of Energy (DOE) is evaluating the application of a company called Abengoa Solar (Abengoa) for a Federal loan guarantee to construct a solar thermal electric power plant nine miles northwest of the town of Hinkley, California, in unincorporated San Bernardino County. DOE will be performing an environmental review of the Abengoa Project in compliance with the National Environmental Policy Act (NEPA).

In addition to the solar power plant, the proposed project would include transmission alignment telecom upgrades that cross Bureau of Land Management (BLM) land. BLM has agreed to be a cooperating agency in accordance with a Memorandum of Understanding between the DOE and BLM, signed in January 2010. Because of BLM's special expertise, DOE is deferring lead authority to BLM solely for activities pertaining to historic resources review to comply with Section 106 of the National Historic Preservation Act. Under DOE's deferment, and as provided for in 36 C.F.R. § 800.2 (a) (2), BLM will act on DOE's behalf to fulfill the collective responsibilities of DOE and BLM under Section 106. Otherwise, DOE will continue to play an active role as the project lead for the NEPA review process, and is available for government-to-government consultation on those matters. BLM's point of contact is Mr. Jim Shearer, who is copied on this letter.

Our records show that your Tribe has expressed an historical interest in San Bernardino County, California. I am writing this letter to extend an opportunity to you to provide comments on the proposed loan guarantee to Abengoa. Consideration of any comments or concerns you provide will help ensure that DOE complies with its NEPA responsibilities.

The project would be located on 1,765 acres, approximately halfway between the city of Barstow and Kramer Junction (Highway 395/58 Junction). The site is in a rural area used previously for farming. To assist you, a more detailed description of the proposed project, and a map showing the proposed plant site (shown as AMSP), and transmission alignments (shown in red), are enclosed.



Currently, a third-party consultant, AECOM, of San Diego, California is undertaking cultural resource Class III surveys for the entire project area. They may be contacting you to gather additional information.

We would greatly appreciate receiving any comments or concerns you may have regarding the NEPA review process by October 25, 2010. Please direct comments related to the Section 106 consultation process to Jim Shearer from the BLM's Barstow office. His contact information is provided below. Please also copy me via email to matthew.mcmillen@hq.doe.gov on comments sent to Mr. Shearer so that I am apprised of any concerns you might have. Written comments regarding the NEPA review can be sent via email to matthew.mcmillen@hq.doe.gov, or sent to the following address: U.S. Department of Energy, 1000 Independence Ave., SW, LP-10, Washington, DC 20585. I can also be reached by telephone at 202-586-7248.

Respectfully,



Matthew McMillen
Director, Environmental Compliance
DOE Loan Programs Office

Enclosures

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Officer

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Rd.
Barstow, CA 92311
(760) 252.6034
jshearer@blm.gov



Department of Energy
Washington, DC 20585

September 27, 2010

Honorable Alfreda Mitre
Chairperson
Las Vegas Tribe of Paiute Indians
Number One Paiute Drive
Las Vegas, NV 89106

Subject: Federal Loan Guarantee to Abengoa Solar

Dear Chairperson Mitre:

The U.S. Department of Energy (DOE) is evaluating the application of a company called Abengoa Solar (Abengoa) for a Federal loan guarantee to construct a solar thermal electric power plant nine miles northwest of the town of Hinkley, California, in unincorporated San Bernardino County. DOE will be performing an environmental review of the Abengoa Project in compliance with the National Environmental Policy Act (NEPA).

In addition to the solar power plant, the proposed project would include transmission alignment telecom upgrades that cross Bureau of Land Management (BLM) land. BLM has agreed to be a cooperating agency in accordance with a Memorandum of Understanding between the DOE and BLM, signed in January 2010. Because of BLM's special expertise, DOE is deferring lead authority to BLM solely for activities pertaining to historic resources review to comply with Section 106 of the National Historic Preservation Act. Under DOE's deferment, and as provided for in 36 C.F.R. § 800.2 (a) (2), BLM will act on DOE's behalf to fulfill the collective responsibilities of DOE and BLM under Section 106. Otherwise, DOE will continue to play an active role as the project lead for the NEPA review process, and is available for government-to-government consultation on those matters. BLM's point of contact is Mr. Jim Shearer, who is copied on this letter.

Our records show that your Tribe has expressed an historical interest in San Bernardino County, California. I am writing this letter to extend an opportunity to you to provide comments on the proposed loan guarantee to Abengoa. Consideration of any comments or concerns you provide will help ensure that DOE complies with its NEPA responsibilities.

The project would be located on 1,765 acres, approximately halfway between the city of Barstow and Kramer Junction (Highway 395/58 Junction). The site is in a rural area used previously for farming. To assist you, a more detailed description of the proposed project, and a map showing the proposed plant site (shown as AMSP), and transmission alignments (shown in red), are enclosed.



Currently, a third-party consultant, AECOM, of San Diego, California is undertaking cultural resource Class III surveys for the entire project area. They may be contacting you to gather additional information.

We would greatly appreciate receiving any comments or concerns you may have regarding the NEPA review process by October 25, 2010. Please direct comments related to the Section 106 consultation process to Jim Shearer from the BLM's Barstow office. His contact information is provided below. Please also copy me via email to matthew.mcmillen@hq.doe.gov on comments sent to Mr. Shearer so that I am apprised of any concerns you might have. Written comments regarding the NEPA review can be sent via email to matthew.mcmillen@hq.doe.gov, or sent to the following address: U.S. Department of Energy, 1000 Independence Ave., SW, LP-10, Washington, DC 20585. I can also be reached by telephone at 202-586-7248.

Respectfully,



Matthew McMillen
Director, Environmental Compliance
DOE Loan Programs Office

Enclosures

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Officer

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Rd.
Barstow, CA 92311
(760) 252.6034
jshearer@blm.gov



Department of Energy
Washington, DC 20585

September 27, 2010

Honorable Darren Daboda
Chairman
Moapa Band of Paiute Indians
PO Box 340
Moapa, NV 89025-0340

Subject: Federal Loan Guarantee to Abengoa Solar

Dear Chairman Daboda:

The U.S. Department of Energy (DOE) is evaluating the application of a company called Abengoa Solar (Abengoa) for a Federal loan guarantee to construct a solar thermal electric power plant nine miles northwest of the town of Hinkley, California, in unincorporated San Bernardino County. DOE will be performing an environmental review of the Abengoa Project in compliance with the National Environmental Policy Act (NEPA).

In addition to the solar power plant, the proposed project would include transmission alignment telecom upgrades that cross Bureau of Land Management (BLM) land. BLM has agreed to be a cooperating agency in accordance with a Memorandum of Understanding between the DOE and BLM, signed in January 2010. Because of BLM's special expertise, DOE is deferring lead authority to BLM solely for activities pertaining to historic resources review to comply with Section 106 of the National Historic Preservation Act. Under DOE's deferment, and as provided for in 36 C.F.R. § 800.2 (a) (2), BLM will act on DOE's behalf to fulfill the collective responsibilities of DOE and BLM under Section 106. Otherwise, DOE will continue to play an active role as the project lead for the NEPA review process, and is available for government-to-government consultation on those matters. BLM's point of contact is Mr. Jim Shearer, who is copied on this letter.

Our records show that your Tribe has expressed an historical interest in San Bernardino County, California. I am writing this letter to extend an opportunity to you to provide comments on the proposed loan guarantee to Abengoa. Consideration of any comments or concerns you provide will help ensure that DOE complies with its NEPA responsibilities.

The project would be located on 1,765 acres, approximately halfway between the city of Barstow and Kramer Junction (Highway 395/58 Junction). The site is in a rural area used previously for farming. To assist you, a more detailed description of the proposed project, and a map showing the proposed plant site (shown as AMSP), and transmission alignments (shown in red), are enclosed.



Currently, a third-party consultant, AECOM, of San Diego, California is undertaking cultural resource Class III surveys for the entire project area. They may be contacting you to gather additional information.

We would greatly appreciate receiving any comments or concerns you may have regarding the NEPA review process by October 25, 2010. Please direct comments related to the Section 106 consultation process to Jim Shearer from the BLM's Barstow office. His contact information is provided below. Please also copy me via email to matthew.mcmillen@hq.doe.gov on comments sent to Mr. Shearer so that I am apprised of any concerns you might have. Written comments regarding the NEPA review can be sent via email to matthew.mcmillen@hq.doe.gov, or sent to the following address: U.S. Department of Energy, 1000 Independence Ave., SW, LP-10, Washington, DC 20585. I can also be reached by telephone at 202-586-7248.

Respectfully,



Matthew McMillen
Director, Environmental Compliance
DOE Loan Programs Office

Enclosures

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Officer

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Rd.
Barstow, CA 92311
(760) 252.6034
jshearer@blm.gov



Department of Energy
Washington, DC 20585

September 27, 2010

Honorable Lora Tom
Chairperson
Paiute Indian Tribe of Utah
440 N. Paiute Drive
Cedar City, UT 84720-2613

Subject: Federal Loan Guarantee to Abengoa Solar

Dear Chairperson Tom:

The U.S. Department of Energy (DOE) is evaluating the application of a company called Abengoa Solar (Abengoa) for a Federal loan guarantee to construct a solar thermal electric power plant nine miles northwest of the town of Hinkley, California, in unincorporated San Bernardino County. DOE will be performing an environmental review of the Abengoa Project in compliance with the National Environmental Policy Act (NEPA).

In addition to the solar power plant, the proposed project would include transmission alignment telecom upgrades that cross Bureau of Land Management (BLM) land. BLM has agreed to be a cooperating agency in accordance with a Memorandum of Understanding between the DOE and BLM, signed in January 2010. Because of BLM's special expertise, DOE is deferring lead authority to BLM solely for activities pertaining to historic resources review to comply with Section 106 of the National Historic Preservation Act. Under DOE's deferment, and as provided for in 36 C.F.R. § 800.2 (a) (2), BLM will act on DOE's behalf to fulfill the collective responsibilities of DOE and BLM under Section 106. Otherwise, DOE will continue to play an active role as the project lead for the NEPA review process, and is available for government-to-government consultation on those matters. BLM's point of contact is Mr. Jim Shearer, who is copied on this letter.

Our records show that your Tribe has expressed an historical interest in San Bernardino County, California. I am writing this letter to extend an opportunity to you to provide comments on the proposed loan guarantee to Abengoa. Consideration of any comments or concerns you provide will help ensure that DOE complies with its NEPA responsibilities.


The project would be located on 1,765 acres, approximately halfway between the city of Barstow and Kramer Junction (Highway 395/58 Junction). The site is in a rural area used previously for farming. To assist you, a more detailed description of the proposed project, and a map showing the proposed plant site (shown as AMSP), and transmission alignments (shown in red), are enclosed.



Currently, a third-party consultant, AECOM, of San Diego, California is undertaking cultural resource Class III surveys for the entire project area. They may be contacting you to gather additional information.

We would greatly appreciate receiving any comments or concerns you may have regarding the NEPA review process by October 25, 2010. Please direct comments related to the Section 106 consultation process to Jim Shearer from the BLM's Barstow office. His contact information is provided below. Please also copy me via email to matthew.mcmillen@hq.doe.gov on comments sent to Mr. Shearer so that I am apprised of any concerns you might have. Written comments regarding the NEPA review can be sent via email to matthew.mcmillen@hq.doe.gov, or sent to the following address: U.S. Department of Energy, 1000 Independence Ave., SW, LP-10, Washington, DC 20585. I can also be reached by telephone at 202-586-7248.

Respectfully,



Matthew McMillen
Director, Environmental Compliance
DOE Loan Programs Office

Enclosures

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Officer

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Rd.
Barstow, CA 92311
(760) 252.6034
jshearer@blm.gov



Department of Energy
Washington, DC 20585

September 27, 2010

Honorable Jamie Fullmer
Chairman
Yavapai-Apache Nation of the Camp
2400 W. Datsi
Camp Verde, AZ 86322

Subject: Federal Loan Guarantee to Abengoa Solar

Dear Chairman Fullmer:

The U.S. Department of Energy (DOE) is evaluating the application of a company called Abengoa Solar (Abengoa) for a Federal loan guarantee to construct a solar thermal electric power plant nine miles northwest of the town of Hinkley, California, in unincorporated San Bernardino County. DOE will be performing an environmental review of the Abengoa Project in compliance with the National Environmental Policy Act (NEPA).

In addition to the solar power plant, the proposed project would include transmission alignment telecom upgrades that cross Bureau of Land Management (BLM) land. BLM has agreed to be a cooperating agency in accordance with a Memorandum of Understanding between the DOE and BLM, signed in January 2010. Because of BLM's special expertise, DOE is deferring lead authority to BLM solely for activities pertaining to historic resources review to comply with Section 106 of the National Historic Preservation Act. Under DOE's deferment, and as provided for in 36 C.F.R. § 800.2 (a) (2), BLM will act on DOE's behalf to fulfill the collective responsibilities of DOE and BLM under Section 106. Otherwise, DOE will continue to play an active role as the project lead for the NEPA review process, and is available for government-to-government consultation on those matters. BLM's point of contact is Mr. Jim Shearer, who is copied on this letter.

Our records show that your Tribe has expressed an historical interest in San Bernardino County, California. I am writing this letter to extend an opportunity to you to provide comments on the proposed loan guarantee to Abengoa. Consideration of any comments or concerns you provide will help ensure that DOE complies with its NEPA responsibilities.

The project would be located on 1,765 acres, approximately halfway between the city of Barstow and Kramer Junction (Highway 395/58 Junction). The site is in a rural area used previously for farming. To assist you, a more detailed description of the proposed project, and a map showing the proposed plant site (shown as AMSP), and transmission alignments (shown in red), are enclosed.



Currently, a third-party consultant, AECOM, of San Diego, California is undertaking cultural resource Class III surveys for the entire project area. They may be contacting you to gather additional information.

We would greatly appreciate receiving any comments or concerns you may have regarding the NEPA review process by October 25, 2010. Please direct comments related to the Section 106 consultation process to Jim Shearer from the BLM's Barstow office. His contact information is provided below. Please also copy me via email to matthew.mcmillen@hq.doe.gov on comments sent to Mr. Shearer so that I am apprised of any concerns you might have. Written comments regarding the NEPA review can be sent via email to matthew.mcmillen@hq.doe.gov, or sent to the following address: U.S. Department of Energy, 1000 Independence Ave., SW, LP-10, Washington, DC 20585. I can also be reached by telephone at 202-586-7248.

Respectfully,



Matthew McMillen
Director, Environmental Compliance
DOE Loan Programs Office

Enclosures

cc: Milford Wayne Donaldson, FAIA
State Historic Preservation Officer

Mr. Jim Shearer
Barstow Field Office Archaeologist
Bureau of Land Management
2601 Barstow Rd.
Barstow, CA 92311
(760) 252.6034
jshearer@blm.gov

APPENDIX S

ENVIRONMENTAL PROTECTION MEASURES, DESIGN MEASURES, AND BMPS

TABLE S-1
ENVIRONMENTAL PROTECTION MEASURES, DESIGN MEASURES AND BMPs

The following measures are incorporated into the Project and were assumed in making the determinations of environmental effect in the respective EA Sections 3.1 through 3.13. CEC Conditions of Certification are included for ease of reference for air quality and biology; other CEC conditions are referenced in their respective EA section as being in the applicable resource area appendix (e.g., water resources).

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
Visual Resources		
1. Design Feature 1: The surfaces of all aboveground structures except the solar collectors (i.e., control building, administration building, warehouse, water treatment building, solar collector array assembly buildings, enclosures for mechanical and electrical equipment, substation MERS building, water storage tanks, etc.) will be given low reflectivity finishes with neutral desert tan colors sympathetic to the desert environment to minimize the contrast of the structures with their backdrops.	X	
2. Design Feature 2: All substation equipment will be specified with low reflectivity, neutral finishes. All insulators at the substations and on the takeoff equipment will be nonreflective and nonrefractive. The chain-link fences surrounding the substations and the Project site will have a dulled finish to reduce contrast with the desert surroundings.		X
3. Design Feature 3: For overhead transmission lines, tubular steel poles (TSPs) will be painted light-gray colors or will be dulled galvanized steel. If concrete monopoles are used, they will be natural concrete with light-gray colors. All insulators specified for this Project will be made of materials that do not reflect or refract light. All conductors specified for the AMSP/Lockhart Substation site will be nonspecular; that is, they will be treated at the factory to dull their surfaces to reduce their potential to reflect light.	X	X
4. Design Feature 4: All construction-related operations at the construction laydown area will be kept clean and tidy. Mojave Solar will remove construction debris promptly at regular intervals, not to exceed 2 weeks at any one location.		
5. Design Feature 5: All outdoor lighting will be the minimum required to meet safety and security standards and all light fixtures will be hooded to eliminate any potential for glare effects and to prevent light from spilling off the site or up into the sky. In addition, the light fixtures will have sensors and switches to permit the lighting to be turned off at times when it is not required.	X	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
6. Design Feature 6: The Applicant will voluntarily consult with residential property owners within 0.5 mile of the proposed AMSP/Lockhart site boundary to suggest offsite-planting on adjacent residential properties (if landowner is interested) to assist with visual screening of the AMSP/Lockhart site as seen from these single-family residential locations.	X	
Air Quality		
Design Measures		
1. The Applicant will have an onsite construction mitigation manager who will be responsible for the implementation and compliance of the construction mitigation program. The documentation of the ongoing implementation and compliance with the proposed construction mitigations will be provided on a periodic basis.	X	
2. All unpaved roads and disturbed areas in the Project and laydown construction sites will be watered as frequently as necessary to control fugitive dust. The frequency of watering will be on a minimum schedule of every 2 hours during the daily construction activity period. Watering may be reduced or eliminated during periods of precipitation.	X	
3. Vehicle speeds within the AMSP site will be limited to 5 mph on unpaved areas within the construction zones.	X	
4. The AMSP construction site entrance(s) will be posted with visible speed limit signs.	X	
5. All construction equipment vehicle tires will be inspected and cleaned as necessary to be free of dirt prior to leaving the construction site via paved roadways.	X	
6. Gravel ramps will be provided at the tire cleaning area within the AMSP site.	X	
7. All unpaved exits from the AMSP construction site will be graveled or treated to reduce track-out to public roadways.	X	
8. All construction vehicles will enter the AMSP construction site through the treated entrance roadways, unless an alternative route has been provided.	X	
9. Construction areas adjacent to any paved roadway will be provided with sandbags or other similar measures as specified in the construction Storm Water Pollution Prevention Plan (SWPPP) to prevent runoff to roadways.	X	X
10. All paved roads within the AMSP construction site will be cleaned on a periodic basis (or less during periods of precipitation), to prevent the accumulation of dirt and debris.	X	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
11. The first 500 feet of any public roadway exiting the AMSP construction site will be cleaned on a periodic basis (or less during periods of precipitation), using wet sweepers or air-filtered dry vacuum sweepers, when construction activity occurs or on any day when dirt or runoff from the construction site is visible on the public roadways.	X	
12. Any soil storage piles and/or disturbed areas that remain inactive for longer than 10 days will be covered, or shall be treated with appropriate dust suppressant compounds.	X	X
13. All vehicles used to transport solid bulk material on public roadways and that have the potential to cause visible emissions will be covered, or the materials shall be sufficiently wetted and loaded onto the trucks in a manner to minimize fugitive dust emissions. A minimum freeboard height of 2 feet will be required on all bulk materials transport.	X	X
14. Wind erosion control techniques (such as windbreaks, water, chemical dust suppressants, and/or vegetation) will be used on all construction areas that may be disturbed. Any windbreaks installed to comply with this condition will remain in place until the soil is stabilized or permanently covered with vegetation.	X	
15. Disturbed areas will be revegetated or covered with gravel or other dust suppressant material as soon as practical.	X	X
16. The Applicant will work with the construction contractor to utilize to the extent feasible, EPA/CARB Tier II/Tier III engine compliant equipment for equipment over 100 horsepower (hp).	X	X
17. Ensure periodic maintenance and inspections per manufacturer specifications.	X	X
18. Reduce idling time through equipment and construction scheduling.	X	X
19. Use California low sulfur diesel fuels (≤ 15 parts per million by weight [ppmw] sulfur).	X	X
Mitigation Measures from the CEC Conditions of Certification – Applicable to AMSP/Lockhart Substation. Refer to Appendix I for MDAQMD conditions.		
AQ-SC1 Air Quality Construction Mitigation Manager (AQCMM): The Project owner shall designate and retain an onsite AQCMM who shall be responsible for directing and documenting compliance with Conditions of Certification AQ-SC3, AQ-SC4, and AQ-SC5 for the entire Project site and linear facility construction. The onsite AQCMM may delegate responsibilities to one or more AQCMM Delegates. The AQCMM and AQCMM Delegates shall have full access to all areas of construction on the Project site and linear facilities, and shall have the authority to stop any or all construction activities as warranted by applicable construction mitigation conditions. The AQCMM and AQCMM Delegates may have other responsibilities in addition to those described in this condition. The AQCMM shall not be terminated without written consent of the compliance project manager (CPM).	X-COC	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
Verification: At least 30 days prior to the start of ground disturbance, the Project owner shall submit to the CPM for approval, the name, resume, qualifications, and contact information for the onsite AQCM and all AQCM Delegates.		
AQ-SC2 Air Quality Construction Mitigation Plan (AQCMP): The Project owner shall provide an AQCMP, for approval, which details the steps that will be taken and the reporting requirements necessary to ensure compliance with Conditions of Certification AQ-SC3, AQ-SC4, and AQ-SC5.	X-COC	
Verification: At least 30 days prior to the start of any ground disturbance, the Project owner shall submit the AQCMP to the CPM for approval. The AQCMP shall include effectiveness and environmental data for the proposed soil stabilizer. The CPM will notify the Project owner of any necessary modifications to the plan within 15 days from the date of receipt.		
AQ-SC3 Construction Fugitive Dust Control: The AQCM shall submit documentation to the CPM in each Monthly Compliance Report that demonstrates compliance with the AQCMP mitigation measures for the purposes of minimizing fugitive dust emission creation from construction activities and preventing all fugitive dust plumes that will not comply with the performance standards identified in AQ-SC4 from leaving the Project site. The following fugitive dust mitigation measures shall be included in the AQCMP required by AQ-SC2, and any deviation from the AQCMP mitigation measures shall require prior CPM notification and approval. a. The main access roads through the facility to the power block areas will be either paved or stabilized using soil binders, or equivalent methods, to provide a stabilized surface that is similar for the purposes of dust control to paving, that may or may not include a crushed rock (gravel or similar material with fines removed) top layer, prior to initiating construction in the main power block area, and delivery areas for operations materials (chemicals, replacement parts, etc.) will be paved or treated prior to taking initial deliveries. b. All unpaved construction roads and unpaved operation and maintenance site roads, as they are being constructed, shall be stabilized with a nontoxic soil stabilizer or soil weighting agent that can be determined to be both as efficient or more efficient for fugitive dust control as CARB-approved soil stabilizers, and shall not increase any other environmental impacts, including loss of vegetation to areas beyond where the soil stabilizers are being applied for dust control. All other disturbed areas in the Project and linear construction sites shall be watered as frequently as necessary during grading (consistent with BIO-7) and after active construction activities shall be stabilized with a nontoxic soil stabilizer or soil weighting agent, or alternative approved soil stabilizing methods, in order to comply with the dust mitigation objectives of Condition of Certification AQ-SC4. The frequency of watering	X-COC	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>can be reduced or eliminated during periods of precipitation.</p> <p>c. No vehicle shall exceed 10 mph on unpaved areas within the construction site, with the exception that vehicles may travel up to 25 mph on stabilized unpaved roads as long as such speeds do not create visible dust emissions.</p> <p>d. Visible speed limit signs shall be posted at the construction site entrances.</p> <p>e. All construction equipment vehicle tires shall be inspected and washed as necessary to be cleaned free of dirt prior to entering paved roadways.</p> <p>f. Gravel ramps of at least 20 feet in length must be provided at the tire washing/cleaning station.</p> <p>g. All unpaved exits from the construction site shall be graveled or treated to prevent track-out to public roadways.</p> <p>h. All construction vehicles shall enter the construction site through the treated entrance roadways, unless an alternative route has been submitted to and approved by the CPM.</p> <p>i. Construction areas adjacent to any paved roadway below the grade of the surrounding construction area or otherwise directly impacted by sediment from site drainage shall be provided with sandbags or other equivalently effective measures to prevent runoff to roadways, or other similar runoff control measures as specified in the SWPPP, only when such SWPPP measures are necessary so that this condition does not conflict with the requirements of the SWPPP.</p> <p>j. All paved roads within the construction site shall be swept daily or as needed (less during periods of precipitation) on days when construction activity occurs to prevent the accumulation of dirt and debris.</p> <p>k. At least the first 500 feet of any paved public roadway exiting the construction site or exiting other unpaved roads en route from the construction site or construction staging areas shall be swept as needed (less during periods of precipitation) on days when construction activity occurs or on any other day when dirt or runoff resulting from the construction site activities is visible on the public paved roadways.</p> <p>l. All soil storage piles and disturbed areas that remain inactive for longer than 10 days shall be covered, or shall be treated with appropriate dust suppressant compounds.</p> <p>m. All vehicles that are used to transport solid bulk material on public roadways and that have potential to cause visible emissions shall be provided with a cover, or the materials shall be sufficiently wetted and loaded onto the trucks in a manner to provide at least 1 foot of freeboard.</p> <p>n. Wind erosion control techniques (such as windbreaks, water, chemical dust suppressants, and/or vegetation) shall be used on all construction areas that may be disturbed. Any windbreaks installed to comply with this condition shall remain in place until the soil is stabilized or permanently covered with vegetation.</p>		

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>Verification: The AQCMM shall provide the CPM a Monthly Compliance Report to include the following to demonstrate control of fugitive dust emissions:</p> <ul style="list-style-type: none"> A. A summary of all actions taken to maintain compliance with this condition; B. Copies of any complaints filed with the District in relation to Project construction; and C. Any other documentation deemed necessary by the CPM or AQCMM to verify compliance with this condition. Such information may be provided via electronic format or disk at the Project owner's discretion. 		
<p>AQ-SC4 Dust Plume Response Requirement: The AQCMM or an AQCMM Delegate shall monitor all construction activities for visible dust plumes. Observations of visible dust plumes that have the potential to be transported (A) off the Project site and within 400 feet upwind of any regularly occupied structures not owned by the Project owner or (B) 200 feet beyond the centerline of the construction of linear facilities indicate that existing mitigation measures are not resulting in effective mitigation. The AQCMP shall include a section detailing how the additional mitigation measures will be accomplished within the time limits specified. The AQCMM or Delegate shall implement the following procedures for additional mitigation measures in the event that such visible dust plumes are observed: Step 1: The AQCMM or Delegate shall direct more intensive application of the existing mitigation methods within 15 minutes of making such a determination. Step 2: The AQCMM or Delegate shall direct implementation of additional methods of dust suppression if Step 1, specified above, fails to result in adequate mitigation within 30 minutes of the original determination. Step 3: The AQCMM or Delegate shall direct a temporary shutdown of the activity causing the emissions if Step 2, specified above, fails to result in effective mitigation within 1 hour of the original determination. The activity shall not restart until the AQCMM or Delegate is satisfied that appropriate additional mitigation or other site conditions have changed so that visual dust plumes will not result upon restarting the shutdown source. The Project owner may appeal to the CPM any directive from the AQCMM or Delegate to shut down an activity, if the shutdown shall go into effect within 1 hour of the original determination, unless overruled by the CPM before that time. Verification: The AQCMM shall provide the CPM a Monthly Compliance Report to include:</p> <ul style="list-style-type: none"> A. A summary of all actions taken to maintain compliance with this condition; B. Copies of any complaints filed with the District in relation to Project construction; and C. Any other documentation deemed necessary by the CPM or AQCMM to verify compliance with this condition. Such information may be provided via electronic format or disk at the Project owner's discretion. 	X-COC	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>AQ-SC5</p> <p>Diesel-Fueled Engine Control: The AQCMM shall submit to the CPM, in the Monthly Compliance Report, a construction mitigation report that demonstrates compliance with the AQCMP mitigation measures for purposes of controlling diesel construction-related emissions. The following off-road diesel construction equipment mitigation measures shall be included in the AQCMP required by AQ-SC2, and any deviation from the AQCMP mitigation measures shall require prior and CPM notification and approval.</p> <ol style="list-style-type: none"> All diesel-fueled engines used in the construction of the facility shall have clearly visible tags issued by the onsite AQCMM showing that the engine meets the conditions set forth herein. All construction diesel engines with a rating of 50 hp or higher and lower than 750 hp shall meet, at a minimum, the Tier 3 California Emission Standards for Off-Road Compression-Ignition Engines, as specified in California Code of Regulations, Title 13, section 2423(b)(1), unless a good faith effort to the satisfaction of the CPM that is certified by the onsite AQCMM demonstrates that such engine is not available for a particular item of equipment. Engines larger than 750 hp shall meet Tier 2 engine standards. In the event that a Tier 3 engine is not available for any off-road equipment larger than 50100 hp and smaller than 750 hp, that equipment shall be equipped with a Tier 2 engine, or an engine that is equipped with retrofit controls to reduce exhaust emissions of nitrogen oxides (NO_x) and diesel particulate matter (DPM) to no more than Tier 2 levels unless certified by engine manufacturers or the onsite AQCMM that the use of such devices is not practical for specific engine types. For purposes of this condition, the use of such devices is “not practical” for the following, as well as other, reasons. <ol style="list-style-type: none"> There is no available retrofit control device that has been verified by either the California Air Resources Board or U.S. Environmental Protection Agency to control the engine in question to Tier 2 equivalent emission levels and the highest level of available control using retrofit or Tier 1 engines is being used for the engine in question; or The construction equipment is intended to be on-site for 10 days or less. The CPM may grant relief from this requirement if the AQCMM can demonstrate a good faith effort to comply with this requirement and that compliance is not practical. The use of a retrofit control device may be terminated immediately, provided that the CPM is informed within 10 working days of the termination and that a replacement for the equipment item in <ol style="list-style-type: none"> The use of the retrofit control device is excessively reducing the normal availability of the construction equipment due to increased down time for maintenance, and/or reduced power output due to an excessive increase in back pressure. The retrofit control device is causing or is reasonably expected to cause engine damage. 	X-COC	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>3. The retrofit control device is causing or is reasonably expected to cause a substantial risk to workers or the public.</p> <p>4. Any other seriously detrimental cause that has the approval of the CPM prior to implementation of the termination.</p> <p>d. All heavy earth-moving equipment and heavy duty construction-related trucks with engines meeting the requirements of (b) above shall be properly maintained and the engines tuned to the engine manufacturer's specifications.</p> <p>e. All diesel heavy construction equipment shall not idle for more than 5 minutes. Vehicles that need to idle as part of their normal operation (such as concrete trucks) are exempted from this requirement.</p> <p>f. Construction equipment will employ electric motors when feasible.</p>		
<p>Verification: The AQCMM shall include in the Monthly Compliance Report the following to demonstrate control of diesel construction-related emissions:</p> <p>A. A summary of all actions taken to control diesel construction related emissions;</p> <p>B. A list of all heavy equipment used onsite during that month, including the owner of that equipment and a letter from each owner indicating that equipment has been properly maintained; and</p> <p>C. Any other documentation deemed necessary by the CPM or AQCMM to verify compliance with this condition. Such information may be provided via electronic format or disk at the Project owner's discretion.</p>		
<p>AQ-SC6</p> <p>The Project owner, when obtaining dedicated on-road or off-road vehicles for mirror washing activities and other facility maintenance activities, shall only obtain vehicles that meet California on-road vehicle emission standards or appropriate EPA/California off-road engine emission standards for the latest model year available when obtained.</p>	X-COC	
<p>Verification: At least 30 days prior to the start commercial operation, the Project owner shall submit to the CPM a copy of the plan that identifies the size and type of the onsite vehicle and equipment fleet and the vehicle and equipment purchase orders and contracts and/or purchase schedule. The plan shall be updated every other year and submitted in the Annual Compliance Report.</p>		
<p>AQ-SC7</p> <p>The Project owner shall provide a site Operations Dust Control Plan, including all applicable fugitive dust control measures identified in the verification of AQ-SC3 that will be applicable to minimizing fugitive dust emission creation from operation and maintenance activities and preventing all fugitive dust plumes that will not comply with the performance standards identified in AQ-SC4 from leaving the Project site; that:</p>	X-COC	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>A. Describes the active operations and wind erosion control techniques such as windbreaks and chemical dust suppressants, including their ongoing maintenance procedures, that shall be used on areas that could be disturbed by vehicles or wind anywhere within the Project boundaries; and</p> <p>B. Identifies the location of signs throughout the facility that will limit traveling on unpaved portion of roadways to solar equipment maintenance vehicles only. In addition, vehicle speed shall be limited to no more than 10 mph on these unpaved roadways, with the exception that vehicles may travel up to 25 mph on stabilized unpaved roads as long as such speeds do not create visible dust emissions. The site operations fugitive dust control plan shall include the use of durable nontoxic soil stabilizers on all regularly used unpaved roads and disturbed off-road areas, or alternative methods for stabilizing disturbed off-road areas, within the Project boundaries, and shall include the inspection and maintenance procedures that will be undertaken to ensure that the unpaved roads remain stabilized. The soil stabilizer used shall be a nontoxic soil stabilizer or soil weighting agent that can be determined to be as efficient as or more efficient for fugitive dust control than CARB-approved soil stabilizers, and that shall not increase any other environmental impacts, including loss of vegetation to areas beyond where the soil stabilizers are being applied for dust control. The performance and application of the fugitive dust controls shall also be measured against and meet the performance requirements of condition AQ-SC4. The measures and performance requirements of AQ-SC4 shall also be included in the Operations Dust Control Plan.</p>		
<p>Verification: At least 30 days prior to start of commercial operation, the Project owner shall submit to the CPM for review and approval a copy of the site Operations Dust Control Plan that identifies the dust and erosion control procedures, including effectiveness and environmental data for the proposed soil stabilizer that will be used during operation of the Project and that identifies all locations of the speed limit signs. Within 60 days after commercial operation, the Project owner shall provide to the CPM a report identifying the locations of all speed limit signs, and a copy of the Project employee and contractor training manual that clearly identifies that Project employees and contractors are required to comply with the dust and erosion control procedures and onsite speed limits.</p> <p>AQ-SC8</p> <p>The Project owner shall provide the CPM copies of all District-issued Authority to Construct (ATC) and Permit to Operate (PTO) documents for the facility. The Project owner shall submit to the CPM for review and approval any modification proposed by the Project owner to any Project Federal air permit. The Project owner shall submit to the CPM any modification to any Federal air permit proposed by the District or EPA, and any revised Federal air permit issued by the District or EPA, for the Project.</p>	X-COC	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
Verification: The Project owner shall submit any ATC, PTO, and proposed Federal air permit modifications to the CPM within 5 working days of its submittal either by (1) the Project owner to an agency, or (2) receipt of proposed modifications from an agency. The Project owner shall submit all modified ATC/PTO documents and all Federal air permits to the CPM within 15 days of receipt.		
AQ-SC9 The Project owner shall offer to pay for temporary equivalent lodging to all residents that are located within 0.25 mile of the Project site fence line during the initial grading/site preparation phase of construction, for those periods of time when the initial grading/site preparation earth-moving activities may occur within 0.25 mile of these residential properties. The Project owner shall contact and provide this offer of temporary lodging to all residents affected by this condition at least 1 month prior to the start of initial grading.	X-COC	
Verification: The Project owner shall provide to the CPM, prior to the start of initial grading, a statement signed by the Project owner's project manager stating that the owner or residents of the properties affected by this condition have been notified and that the residents have been offered by the Project owner paid relocation during the affected period of the initial grading/site preparation phase of construction. The statement shall list affected property owners/residents notified and the means of notification. Additionally, in the Monthly Compliance Report the Project owner shall provide documentation regarding any requests from the residents to be relocated for longer periods during construction and the Project owner's actions to evaluate those requests.		
Noise		
Construction Phase Noise Control Measures		
1. At least 15 days prior to the start of ground disturbance, the Project proponent, or its designee shall notify all residents within 2 miles of the site, by mail or other effective means, of the commencement of construction. At the same time, a telephone number shall be established for use by the public and included in the notice to report any undesirable noise conditions associated with the construction and operation of the Project and include that telephone number in the above notice.	X	
2. Throughout the construction and operation of the AMSP, Mojave Solar, or its designee, shall document, investigate, evaluate, and attempt to resolve all legitimate, Project-related noise complaints.	X	
3. Mojave Solar, or its designee, shall prepare a noise control program and a statement verifying that the noise control program will be implemented throughout construction of the Project. The noise control program shall be used to reduce employee exposure to high noise levels during construction and also to comply with applicable OSHA and Cal/OSHA standards.	X	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
4. Noisy construction work (such as grading, drilling, and heavy lifts) shall be restricted to the period from 7 a.m. to 7 p.m. on weekdays and Saturdays, unless otherwise permitted in accordance with the San Bernardino County Code. If construction work outside of these hours is needed to maintain the overall development schedule, such after-hours construction shall be limited to relatively quiet activities (such as welding, circuit testing, and inspections) so as to not disturb the closest residential receptors.	X	
5. Construction equipment shall have appropriate silencing features or equipment installed and maintained during the course of the construction phase. For example, haul trucks and other engine-powered equipment shall be equipped with adequate mufflers. Stationary compressors and generators shall utilize noise-reduction enclosures or similar noise control features. Haul trucks shall be operated in accordance with posted speed limits. Truck engine exhaust braking shall be limited to emergencies.	X	
6. To minimize construction-related truck traffic noise, stockpiling and vehicle staging areas shall be located at least 200 feet away from occupied residential dwellings or other sensitive receptor locations to reduce annoyances from vehicular traffic. Construction routes will be established to minimize truck movements near residential streets.	X	
7. Mojave Solar, or its designee, will install temporary silencers on air and steam discharge vents during the Commissioning and Initial Start-up Phase of the AMSP. This will reduce noise from the few weeks of air and steam blow cleaning that only occurs during this part of the plant's life cycle.		
8. If a traditional, high-pressure steam blow process is employed, Mojave Solar, or its designee, shall equip steam blow piping with a temporary silencer that quiets the noise of steam blows to no greater than 110 dBA measured at a distance of 100 feet. The Project owner shall conduct steam blows only during the hours of 8 a.m. to 5 p.m., unless it can be demonstrated that offsite noise impacts will not cause annoyance.	X	
9. At least 15 days prior to the first steam blow(s), Mojave Solar, or its designee, shall notify all residents within 2 miles of the site of the planned steam blow activity, and shall make the notification available to other area residents in an appropriate manner. The notification may be in the form of letters to the area residences, telephone calls, fliers, or other effective means. The notification shall include a description of the purpose and nature of the steam blow(s), the proposed schedule, the expected sound levels, and the explanation that it is a one-time operation and not a part of normal plant operations.	X	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
Operational Phase Noise Control Measures		
<p>1. Within 90 days of the AMSP achieving a sustained output of 80% or greater of rated capacity, Mojave Solar, or its designee, shall conduct a 25-hour community noise survey, utilizing the same monitoring sites employed in the pre-Project ambient noise survey as a minimum. The survey shall also include the octave band pressure levels to ensure that no new pure-tone noise components have been introduced. A verification survey report will be prepared within 30 days following the completion of the field effort.</p> <p>No single piece of equipment will be allowed to stand out as a source of noise that draws legitimate complaints. Steam relief valves will be adequately muffled to preclude noise that draws legitimate complaints. If the results from the survey indicate that the Project noise levels are in excess of County limits, additional measures may be implemented to reduce noise to a level of compliance. A copy of the verification survey report will be provided to the County of San Bernardino; the County will be kept apprised of progress made toward correcting any noise-related issues.</p>	X	
<p>2. Within 120 days of the AMSP achieving a sustained output of 80% or greater of rated capacity, Mojave Solar, or its designee, shall conduct an occupational noise survey to identify the noise hazardous areas in the facility. The survey will be conducted by a qualified person in accordance with the provisions of Title 8, CCR Sections 5095–5099 and Title 29, CFR Section 1910.95. The survey results will be used to prepare a report and determine the magnitude of employee noise exposure. If necessary, measures will be identified to comply with the applicable California and Federal regulations. The report will be kept on file with the onsite plant manager.</p>	X	
<p>3. Given the very low, late-night noise levels in the vicinity of the AMSP/Lockhart Substation site, the occasional mirror-washing activities will be conducted, if practical, using lower-noise water trucks (i.e., gasoline-powered, natural gas-powered, or electric-powered), rather than diesel-powered trucks. Mirror-washing equipment will have appropriate silencing features or equipment (such as mufflers) installed and maintained. Further, mirror washing in solar field areas closest to residential receptors will be conducted before midnight, if practical.</p>	X	
Geology		
Seismic Safety Design Measures		
<p>1. Power plant structures and equipment will be designed in accordance with seismic requirements of the Alquist-Priolo Earthquake Fault Zoning Act. For new substation construction, specific requirements for seismic design will be followed based on the Institute of Electrical and Electronic Engineers' 693 "Recommended Practices for Seismic Design of Substations."</p>	X	X

¹ Applies only where ground disturbance is expected (trenching, replacement poles and inter-set poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
2. Project foundations will be designed in accordance with recommendations provided in the final geotechnical design report for the AMSP and Lockhart Substation.	X	X
Erosion Control During Construction Phase		
1. Local soil berms and a detention area will be constructed to contain stormwater runoff.	X	
2. Site grading, clearing, and grubbing will be confined to only those areas needed for facility construction as indicated in the conceptual grading plan.	X	
3. Temporary erosion controls including crushed rock, silt fences and fiber rolls will be used as needed to minimize erosion in active grading areas. Soil stockpiles will be covered prior to forecasted storm events and during windy conditions. Fiber rolls or gravel bags will be placed around the perimeter of the stockpiles to further minimize the potential for runoff.	X	
4. Additionally, water will be used to control dust and will be applied at a rate to minimize runoff.	X	
5. An erosion control plan will be developed and implemented to ensure minimum soil loss and to maintain water quality. Temporary and long-term erosion control measures will be constructed and maintained as necessary during and following construction until long-term stabilization has been established.		X
Paleontology		
1. Prior to the start of any Project-related construction (defined as construction-related vegetation clearing, ground disturbance and preparation, and site excavation activities), the Project owner will ensure that the paleontological resource specialist is available for field activities and prepared to implement these measures. The paleontological resource specialist will be responsible for implementing all the paleontological measures and for using qualified personnel to assist in this work.	X	X ¹
2. Prior to the start of construction, a Paleontological Resource Monitoring and Mitigation Plan will be prepared by a paleontological resource specialist. The plan will identify general and specific measures to minimize potential impacts to sensitive paleontological resources. The Project paleontological resource specialist will implement the Paleontological Resource Monitoring and Mitigation Plan as needed. The Paleontological Resource Monitoring and Mitigation Plan will include, but not be limited to, the following elements and measures. <ul style="list-style-type: none"> A discussion of the sequence of Project-related tasks, such as any preconstruction surveys, fieldwork, flagging or staking; construction monitoring; mapping and data recovery; fossil preparation and recovery; identification and inventory; preparation of final reports; and transmittal of materials for curation; 	X	X ¹

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<ul style="list-style-type: none"> • Identification of the person(s) expected to assist with each of the tasks identified within this condition, and a discussion of the mitigation team leadership and organizational structure, and the interrelationship of tasks and responsibilities; • Where monitoring of Project construction activities is deemed necessary, the extent of the areas where monitoring is to occur and a schedule for the monitoring; • An explanation that the designated paleontological resource specialist shall have the authority to halt or redirect construction in the immediate vicinity of a vertebrate fossil find until the significance of the find can be determined; • A discussion of the equipment and supplies necessary for the recovery of fossil materials and any specialized equipment needed to prepare, remove, load, transport, and analyze large-sized fossils or extensive fossil deposits; • Inventory, preparation, and delivery for curation into a retrievable storage collection in a public repository or museum that meets the SVP standards and requirements for the curation of paleontological resources; and <p>Identification of the institution (expected to be the SBCM) that has agreed to receive any data and fossil materials recovered during Project-related monitoring and mitigation work, discussion of any requirements of specifications for materials delivered for curation and how they will be met, and the name and phone number of the contact person at the institution.</p> <p>3. Prior to the start of construction, the paleontological resource specialist will prepare a staff training program. The paleontological training program will address the potential to encounter paleontological resources in the field, the sensitivity and importance of these resources, and the legal obligations to preserve and protect such resources. The training program will also include the set of reporting procedures that workers are to follow if paleontological resources are encountered during Project activities.</p>	X	X ¹

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
4. During construction, the designated paleontological resource specialist or paleontological monitor will monitor construction-related grading, excavation, trenching, and/or augering in areas with a significant potential for fossil-bearing sediments to occur. All ground disturbances in Quaternary older alluvium (greater than 5 feet in depth) and Quaternary lake deposits will be monitored on a full-time basis because of their high paleontological sensitivity. All ground disturbances in Quaternary younger alluvium (at or less than 5 feet in depth) will be spot-checked by paleontological monitors. Paleontological monitoring will include inspection of exposed rock units and microscopic examination of matrix to determine if fossils are present. Paleontological monitors will have authority to temporarily divert excavations or drilling away from exposed fossils in order to efficiently and professionally recover the fossil specimens and collect associated data.	X	X ¹
5. The Project owner, through the designated paleontological resource specialist, will ensure recovery, preparation for analysis, analysis, identification and inventory, the preparation for curation, and the delivery for curation of all significant paleontological resource materials encountered and collected during the monitoring, data recovery, mapping, and mitigation activities related to the Project.	X	X ¹
6. The Project owner will ensure preparation of a Paleontological Resources Report by the designated paleontological resource specialist following the analysis of the recovered fossil materials and related information. The report will include a description and inventory list of recovered fossil materials, a map showing the location of paleontological resources found in the field, determinations of sensitivity and significance, and a statement by the paleontological resource specialist that Project impacts to paleontological resources have been mitigated.	X	X ¹
Water Resources		
BMPs for Operational Impacts. Refer to Appendix E for CEC Conditions of Certification for AMSP.		
1. Initially, grading will proceed in a systematic manner in those areas needed for site construction and operation. Undisturbed areas will remain so until being actively graded.	X	
2. Berms are proposed to be used along slopes or check structures to control sediment loss and erosion. As indicated for the storm channel sections, riprap gabions or other erosion control measures will be used to minimize scour and erosion.	X	
3. Roads and paved areas are proposed to be kept free of dust, dirt, and visible soil materials. A stabilized construction entrance/exit shall be constructed and maintained. Stabilized construction roadways will be used throughout the Project site and maintained throughout the construction period. Water is proposed to be used to control fugitive dust emissions and applied as to minimize and control water runoff.	X	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
4. BMPs are proposed to be applied and, if necessary, repaired as soon as erosion is evident or a particular measure fails. Temporary erosion control measures are proposed as well and temporary sediment control materials are proposed to be maintained onsite throughout the construction period to respond as needed to unforeseen rain or emergencies.	X	
5. The AMSP will develop and implement a Channel Maintenance Program for routine maintenance of the storm water channels to protect the integrity of the channels from erosion and sedimentation.	X	
Biological Resources		
1. Designated Biologist Selection BIO-1: The project owner shall assign a Designated Biologist to the project. The project owner shall submit the resume of the proposed Designated Biologist, with at least three references and contact information, to the Energy Commission Compliance Project Manager (CPM), CDFG, and USFWS for approval. The Designated Biologist must meet the following minimum qualifications:	X-COC	X
1. Bachelor's Degree in biological sciences, zoology, botany, ecology, or a closely related field; and	X-COC	X
2. Three years of experience in field biology or current certification of a nationally recognized biological society, such as The Ecological Society of America or The Wildlife Society;	X-COC	X
3. At least one year of field experience with biological resources found in or near the project area;	X-COC	X
4. Meet current USFWS Authorized Biologist criteria and demonstrate familiarity with protocols and guidelines for the desert tortoise; and	X-COC	X
5. Possess a recovery permit for desert tortoise and a California ESA Memorandum of Understanding pursuant to Section 2081(a) for desert tortoise and Mohave ground squirrel or have adequate experience and qualifications to obtain these authorizations. It is possible that two biologists may be utilized – each with an MOU for desert tortoise or MGS. In lieu of the above requirements, the resume shall demonstrate to the satisfaction of the CPM, that the proposed Designated Biologist or alternate has the appropriate training and background to effectively implement the conditions of certification.	X-COC	X
2. Designated Biologist Duties BIO-2 The project owner shall ensure that the Designated Biologist performs the following during any site (or related facilities) mobilization, ground disturbance, grading, construction, operation, and closure activities. The Designated Biologist may be assisted by the approved Biological Monitor(s), but remains the contact for the project owner and CPM.	X-COC	X
1. Advise the project owner's Construction and Operation Managers on the implementation of the biological resources conditions of certification;	X-COC	X

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
2. Consult on the preparation of the Biological Resources Mitigation Implementation and Monitoring Plan (BRMIMP), to be submitted by the project owner;	X-COC	X
3. Be available to supervise, conduct and coordinate mitigation, monitoring, and other biological resources compliance efforts, particularly in areas requiring avoidance or containing sensitive biological resources, such as special status species or their habitat;	X-COC	X
4. Halt any and all activities in any area when determined that there would be an unauthorized adverse impact to biological resources if the activities continued or a violation of federal or state environmental laws or a violation of any environmental agreements/conditions made between the applicant and the CPM and/or the regulatory agencies;	X-COC	X
5. Clearly mark sensitive biological resource areas, if present and inspect these areas at appropriate intervals for compliance with regulatory terms and conditions;	X-COC	X
6. Inspect active construction areas where animals may have become trapped prior to construction commencing each day. At the end of the day, inspect for the installation of structures that prevent entrapment or allow escape during periods of construction inactivity. Periodically inspect areas with high vehicle activity (i.e. parking lots) for animals in harm's way;	X-COC	X
7. Notify the project owner and the CPM of any non-compliance with any biological resources condition of certification;	X-COC	X
8. Respond directly to inquiries of the CPM regarding biological resource issues;	X-COC	X
9. Maintain written records of the tasks specified above and those included in the BRMIMP. Summaries of these records shall be submitted in the Monthly Compliance Report and the Annual Report; and	X-COC	X
10. Train the Biological Monitors as appropriate, and ensure their familiarity with the BRMIMP, Worker Environmental Awareness Program (WEAP) training and all permits.	X-COC	X
3. Biological Monitor Selection, Qualifications, and Duties BIO-3 The project owner's CPM-approved Designated Biologist shall submit the resume, at least three references and contact information, of the proposed Biological Monitors to the CPM, CDFG, and USFWS for approval. The resume shall demonstrate to the satisfaction of the CPM, the appropriate education and experience to accomplish the assigned biological resource tasks, including:	X-COC	X
<ul style="list-style-type: none"> Biological Monitor(s) involved in any aspect of desert tortoise surveys or handling must meet the criteria to be considered a USFWS Authorized Biologist (USFWS 2008) and demonstrate familiarity with the most recent protocols and guidelines for the desert tortoise. 	X-COC	X

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<ul style="list-style-type: none"> Biological Monitor(s) involved in any aspect of Mohave ground squirrel surveys or handling must possess a California ESA Memorandum of Understanding pursuant to Section 2081(a) for Mohave ground squirrel or have adequate experience and qualifications to obtain this authorizations. Biological Monitor(s) training by the Designated Biologist shall include familiarity with the conditions of certification and the Biological Resources Mitigation Implementation and Monitoring Plan (BRMIMP), Worker Environmental Awareness Program (WEAP), and all permits. The Biological Monitors shall assist the Designated Biologist in conducting surveys and in monitoring of site mobilization activities, construction-related ground disturbance, grading, boring or trenching. The Designated Biologist shall remain the contact for the Project owner, BLM's Authorized Officer and the CPM. 	X-COC	X
	X-COC	X
	X-COC	X
<p>4. Designated Biologist and Biological Monitor Authority BIO-4 The project owner's Construction/Operation Manager shall act on the advice of the Designated Biologist and Biological Monitor(s) to ensure conformance with the biological resources conditions of certification.</p> <p>If required by the Designated Biologist and Biological Monitor(s) the project owner's Construction/Operation Manager shall halt all site mobilization, ground disturbance, grading, construction, and operation activities in areas specified by the Designated Biologist. The Designated Biologist shall:</p> <ol style="list-style-type: none"> Halt any and all activities in any area when determined that there would be an unauthorized adverse impact to biological resources if the activities continued or a violation of federal or state environmental laws or a violation of any environmental agreements/conditions made between the applicant and the CPM and/or the regulatory agencies; Inform the project owner and the Construction/Operation Manager when to resume activities; and Notify the CPM if there is a halt of any activities, and advise the CPM of any corrective actions that have been taken, or will be instituted, as a result of the work stoppage. If the Designated Biologist is unavailable for direct consultation, the Biological Monitor shall act on behalf of the Designated Biologist. It is expected that the Designated Biologist will be onsite during construction or otherwise available by phone. 	X-COC	X
	X-COC	X
	X-COC	X
	X-COC	X
	X-COC	X

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>5. Worker Environmental Awareness Program BIO-5 The project owner shall develop and implement a CPM-approved Worker Environmental Awareness Program (WEAP) in which each of its employees, as well as employees of contractors and subcontractors who work on the project site or any related facilities during site mobilization, ground disturbance, grading, construction, operation, and closure are informed about sensitive biological resources associated with the project.</p> <p>The WEAP must:</p> <ol style="list-style-type: none"> 1. Be developed by or in consultation with the Designated Biologist and consist of an on-site or training center presentation in which supporting written material and electronic media is made available to all participants; 2. Discuss the locations and types of sensitive biological resources on the project site and adjacent areas, if present; 3. Present the reasons for protecting these resources; 4. Present the meaning of various temporary and permanent habitat protection measures as necessary; 5. Discuss penalties for violation of applicable LORS (e.g., federal and state endangered species acts); 6. Identify whom to contact if there are further comments and questions about the material discussed in the program; and 7. Include a training acknowledgment form to be signed by each worker indicating that they received training and shall abide by the guidelines. <p>The specific program can be administered by a competent individual(s) acceptable to the Designated Biologist.</p>	X-COC	X
	X-COC	X
	X-COC	X
	X-COC	X
	X-COC	X
	X-COC	X
	X-COC	X
6. Biological Resources Mitigation Implementation and Monitoring Plan (BRMIMP) Development and Compliance BIO-6 The project owner shall develop a BRMIMP and submit two copies of the proposed BRMIMP to the CPM (for review and approval) and to CDFG and USFWS (for review and comment) if applicable and shall implement the measures identified in the approved BRMIMP. A copy of the BRMIMP shall be kept onsite and made readily available to biologists, regulatory agencies, the project owner, contractors, and subcontractors as needed.	X-COC	X
The BRMIMP shall be prepared in consultation with the Designated Biologist and shall identify:	X-COC	X
1. All biological resource mitigation, monitoring, and compliance measures proposed and agreed to by the project owner;	X-COC	X
2. All applicant-proposed mitigation measures presented in the Application for Certification, data request responses, and workshop responses;	X-COC	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
3. All biological resource conditions of certification identified as necessary to avoid or mitigate impacts;	X-COC	
4. All biological resource mitigation, monitoring, and compliance measures required in federal agency terms and conditions, such as those provided in the Biological Opinion;	X-COC	X
5. All biological resource mitigation, monitoring, and compliance measures required in local agency permits, such as site grading and landscaping requirements;	X-COC	X
6. All sensitive biological resources to be impacted, avoided, or mitigated by project construction, operation, and closure;	X-COC	X
7. All required mitigation measures for each sensitive biological resource;	X-COC	X
8. A detailed description of measures that shall be taken to avoid or mitigate temporary disturbances from construction activities;	X-COC	X
9. All locations on a map, at an approved scale, of sensitive biological resource areas subject to disturbance and areas requiring temporary protection and avoidance during construction;	X-COC	X
10. Aerial photographs, at an approved scale, of all areas to be disturbed during project construction activities — one set prior to any site (and related facilities) mobilization disturbance and one set subsequent to completion of project construction. Include planned timing of aerial photography and a description of why times were chosen;	X-COC	X
11. Duration for each type of monitoring and a description of monitoring methodologies and frequency;	X-COC	X
12. Performance standards to be used to help decide if/when proposed mitigation is or is not successful;	X-COC	X
13. All performance standards and remedial measures to be implemented if performance standards are not met;	X-COC	X
14. A preliminary discussion of biological resources-related facility closure measures; and	X-COC	X
15. A process for proposing plan modifications to the CPM and appropriate agencies for review and approval.	X-COC	X
7. Impact Avoidance and Minimization Measures BIO-7 The project owner shall implement the following measures during construction and operation to manage their project site and related facilities in a manner to avoid or minimize impacts to the local biological resources:	X-COC	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
1. <u>Limit Disturbance Area.</u> The boundaries of all areas to be temporarily or permanently disturbed (including staging areas, access roads, and sites for temporary placement of spoils) shall be delineated with stakes and flagging prior to construction activities in consultation with the Designated Biologist. Spoils shall be stockpiled in disturbed areas, which do not provide habitat for special-status species. Parking areas, staging and disposal site locations shall similarly be located in areas without native vegetation or special-status species habitat. All disturbances, vehicles, and equipment shall be confined to the flagged areas.	X-COC	
2. <u>Minimize Road Impacts.</u> New and existing roads that are planned for construction, widening, or other improvements shall not extend beyond the flagged impact area as described above. All vehicles passing or turning around will do so within the planned impact area or in previously disturbed areas. Where new access is required outside of existing roads (e.g., new spur roads) or the construction zone, the route will be clearly marked (i.e., flagged and/or staked) prior to the onset of construction.	X-COC	X
3. <u>Minimize Traffic Impacts.</u> Vehicular traffic during project construction and operation shall be confined to existing routes of travel to and from the project site, and cross country vehicle and equipment use outside designated work areas shall be prohibited. The speed limit shall not exceed 25 miles per hour on Harper Lake Road and within fenced areas that have been cleared of tortoises and other wildlife. The speed limit shall not exceed 15 miles per hour within unfenced areas and secondary unpaved access roads.	X-COC	
4. <u>Monitor During Construction.</u> The Designated Biologist or Biological Monitor shall be present at the construction site during all project activities that have potential to disturb soil, vegetation, and wildlife. The USFWS-approved Designated Biologist or Biological Monitor shall closely monitor vegetation removal and grading activities to prevent wildlife injury or mortality.	X-COC	X
5. <u>Minimize Impacts of Transmission/Pipeline Alignments, Roads, Staging Areas.</u> Staging areas for construction on the plant site shall be within the area that has been fenced with desert tortoise exclusion fencing and cleared. Temporary disturbance areas, if necessary, shall occur within the project site and shall be designed, installed, and maintained with the goal of minimizing disturbance. Transmission lines and all electrical components shall be designed, installed, and maintained in accordance with the Avian Power Line Interaction Committee's (APLIC's) <i>Suggested Practices for Avian Protection on Power Lines</i> (APLIC 2006) and <i>Mitigating Bird Collisions with Power Lines</i> (APLIC 2004) to reduce the likelihood of bird electrocutions and collisions.	X-COC	X

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
6. <u>Avoid Use of Toxic Substances.</u> Road surfacing and sealants as well as soil bonding and weighting agents used on unpaved surfaces shall be non-toxic to wildlife and plants.	X-COC	
7. <u>Minimize Lighting Impacts.</u> Facility lighting shall be designed, installed, and maintained to prevent side casting of light towards the project boundaries and the Harper Dry Lake marsh. Lighting shall be shielded, directional, and at the lowest intensity required for activity.	X-COC	X
8. <u>Avoid Vehicle Impacts to Desert Tortoise.</u> Parking and storage shall occur within desert tortoise exclusion fencing to the extent feasible. No vehicles or construction equipment parked outside the fenced area shall be moved prior to an inspection of the ground beneath the vehicle for the presence of desert tortoise. During construction, a Biological Monitor shall drive along project access roads, particularly Harper Lake Road at least every three hours during the desert tortoise active period (April through May and September through October) looking for desert tortoise or other vulnerable wildlife within the roadway. Outside of the active period, roads shall be monitored at least twice a day in advance of peak AM and PM traffic periods. During operation, employees shall report any desert tortoise sightings along roadways to the Biological Monitor. If a desert tortoise is observed in the roadway or beneath a parked vehicle, it will be left to move on its own or a Biological Monitor may remove and transfer the animal to a safe location if temperatures are within the appropriate range as identified in the Final Desert Tortoise Clearing and Translocation Plan.	X-COC	X
9. <u>Avoid Wildlife Pitfalls.</u> At the end of each work day, the Designated Biologist shall ensure that all potential wildlife pitfalls (trenches, bores, and other excavations) outside the permanently fenced area have been backfilled. If backfilling is not feasible, all trenches, bores, and other excavations shall be sloped at a 3:1 ratio at the ends to provide wildlife escape ramps, or covered completely to prevent wildlife access, or fully enclosed with tortoise-exclusion fencing. All trenches, bores, and other excavations outside the areas permanently fenced with desert tortoise exclusion fencing shall be inspected at the beginning of each workday, periodically throughout, and at the end of each workday by the Designated Biologist or a Biological Monitor. Should a tortoise or other wildlife become trapped, the Designated Biologist or Biological Monitor shall remove and relocate the individual to a safe location. Any wildlife encountered during the course of construction shall be allowed to leave the construction area unharmed.	X-COC	X

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
10. <u>Avoid Entrapment of Wildlife.</u> Any construction pipe, culvert, or similar structure with a diameter greater than three inches, stored less than eight inches above ground for one or more days/nights, shall be inspected for wildlife before the material is moved, buried, or capped. As an alternative, all such structures may be capped before being stored, or placed on pipe racks.	X-COC	
11. <u>Report Wildlife Injury and Mortality.</u> All inadvertent deaths of sensitive species, including road kill, shall be reported to the appropriate project representative. Species name, physical characteristics of the animal (sex, age class, length, weight), and other pertinent information shall be noted and reported in the Monthly Compliance Reports. Injured animals shall be reported to CDFG or USFWS and the CPM and the project owner shall follow instructions that are provided by CDFG or USFWS. If CDFG or USFWS cannot be immediately reached, consideration should be given to taking the animal to a veterinary hospital. If any golden eagles are recovered dead, they shall be sent to the National Eagle Repository after cause of death has been investigated.	X-COC	X
12. <u>Minimize Standing Water.</u> Water applied to dirt roads and construction areas (trenches or spoil piles) for dust abatement shall use the minimal amount needed to meet safety and air quality standards in an effort to prevent the formation of puddles, which could attract desert tortoises, common ravens, and other wildlife to construction sites. A Biological Monitor shall patrol these areas to ensure water does not puddle and attract desert tortoise, common ravens, and other wildlife to the site and shall take appropriate action to reduce water application where necessary.	X-COC	
13. <u>Minimize Spills of Hazardous Materials.</u> All vehicles and equipment shall be maintained in proper working condition to minimize the potential for fugitive emissions of motor oil, antifreeze, hydraulic fluid, grease, or other hazardous materials. The Designated Biologist shall be informed of any hazardous spills immediately as directed in the project Hazardous Materials Plan. Hazardous spills shall be cleaned up immediately and the contaminated soil properly disposed of at a licensed facility. Servicing of construction equipment shall take place only at a designated area. Service/maintenance vehicles shall carry a bucket and pads to absorb leaks or spills.	X-COC	X
14. <u>Worker Guidelines.</u> During construction all trash and food-related waste shall be placed in self-closing containers and removed daily from the site. Workers shall not feed wildlife or bring pets to the project site. Except for law enforcement personnel, no workers or visitors to the site shall bring firearms or weapons.	X-COC	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>15. <u>Avoid Spread of Noxious Weeds.</u> The project owner shall implement the following Best Management Practices during construction and operation to prevent the spread and propagation of noxious weeds:</p> <ul style="list-style-type: none"> a. Limit the size of any vegetation and/or ground disturbance to the absolute minimum and limit ingress and egress to defined routes; b. Reestablish vegetation quickly on disturbed sites temporarily disturbed areas, including pipelines, transmission lines, and staging areas (see BIO-9); c. Prevent spread of non-native plants via vehicular sources by implementing Trackclean™ or other methods of vehicle cleaning for vehicles coming and going from construction sites. Earth-moving equipment and construction vehicles shall be cleaned within an approved area or commercial facility prior to transport to the construction site. The number of cleaning stations shall be limited and weed control/herbicide application shall be used at the cleaning station(s); d. Use only weed-free straw, hay bales, and seed for erosion control and sediment barrier installations; e. Invasive non-native species shall not be used in landscaping plans and erosion control; and f. Monitor and rapidly implement control measures to ensure early detection and eradication of weed invasions. <p>16. <u>Implement Erosion Control Measures.</u> Standard erosion control measures shall be implemented for all phases of construction and operation. All disturbed soils and roads within the project site shall be stabilized to reduce erosion potential, both during and following construction. Areas of disturbed soils (access and staging areas) with slopes toward an ephemeral drainage or Harper Dry Lake shall be stabilized to reduce erosion potential.</p> <p>17. <u>Monitor Ground Disturbing Activities Prior to Site Mobilization.</u> If ground disturbing activities are required prior to site mobilization, such as for geotechnical borings or hazardous waste evaluations, a Designated Biologist or Biological Monitor shall be present to monitor any actions that could disturb soil, vegetation, or wildlife. Actions not included in the project description are prohibited.</p>	<p>X-COC</p> <p>X-COC</p> <p>X-COC</p> <p>X-COC</p> <p>X-COC</p> <p>X-COC</p> <p>X-COC</p> <p>X-COC</p>	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>8. Pre-Construction Nest Surveys and Impact Avoidance and Minimization Measures for Migratory Birds BIO-8 Pre-construction nest surveys shall be conducted if construction activities will occur from February 1 through August 1. At all times of the year, noise generating activities shall be limited during early morning and evening to avoid impacts to birds protected under the Migratory Bird Treaty Act. The Designated Biologist or Biological Monitor shall perform surveys in accordance with the following guidelines:</p> <ol style="list-style-type: none"> 1. Surveys shall cover all potential nesting habitat in the project site and within 500 feet of the boundaries of the plant site as well as any areas potentially exposed to noise levels above 60 dBA; 2. At least two pre-construction surveys shall be conducted, separated by a minimum 10-day interval. One of the surveys needs to be conducted within the 10-day period preceding initiation of construction activity. Additional follow-up surveys may be required if periods of construction inactivity exceed three weeks in any given area, an interval during which birds may establish a nesting territory and initiate egg laying and incubation; 3. If active nests are detected during the survey, a no-disturbance buffer zone (protected area surrounding the nest, the size of which is to be determined by the Designated Biologist in consultation with CDFG and USFWS) and monitoring plan shall be developed. Nest locations shall be mapped using GPS technology and submitted, along with a weekly report stating the survey results, to the CPM; and 4. The Designated Biologist or Biological Monitor shall monitor the nest until he or she determines that nestlings have fledged and dispersed; activities that might, in the opinion of the Designated Biologist in consultation with the CPM, disturb nesting activities (e.g., excessive noise above 60 dBA), shall be prohibited within the buffer zone until such a determination is made. 	<p>X-COC</p> <p>X-COC</p> <p>X-COC</p> <p>X-COC</p>	<p>X</p> <p></p> <p>X</p> <p>X</p> <p>X</p>
<p>9. Golden Eagle Territory-Specific Management Plan BIO-9 In addition to the breeding season golden eagle inventory conducted in spring 2010 (per USFWS protocol [Pagel et al. 2010]), a non-breeding season golden eagle inventory survey shall be conducted in late-summer/early-winter 2010 (USFWS, in prep).</p> <p>If an occupied golden eagle territory is identified within 10 miles of the project site (except for the territory identified at Black Mountain in April 2010) during breeding or non-breeding inventory surveys for the AMS project, the project owner shall prepare and implement a Golden Eagle Territory-Specific Management Plan. This plan shall:</p>	<p>X-COC</p> <p>X-COC</p>	<p></p> <p></p>

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
A. <u>Timing and Supervision of Fence Installation.</u> The exclusion fencing shall be installed prior to site clearing and grubbing. The fence installation shall be supervised by the Designated Biologist and monitored by the Biological Monitors to ensure the safety of any tortoise present.	X-COC	
B. <u>Fence Material and Installation.</u> The permanent tortoise exclusionary fencing shall consist of galvanized hard wire cloth 1 by 2 inch mesh sunk 12 inches into the ground, and 24 inches above ground (refer to parameters for USFWS-approved tortoise exclusion fencing at www.fws.gov/ventura/speciesinfo/protocols_guidelines). For temporary exclusion fencing, a “folded bottom” technique shall be implemented. This method follows the same guidelines as installation of permanent fencing except instead of burying the bottom 12 inches of the fencing, it is bent at a approximately 90 degree angle (to follow the contour of the ground) and spikes or other retaining methods are driven into the ground every two linear feet in such a manner as to “anchor” the bottom of the fence. This method eliminates the need for trenching, which for short-term temporary impacts may be more beneficial to the recovery of the landscape, and thus the species.	X-COC	
C. <u>Security Gates.</u> Security gates shall be designed with minimal ground clearance to deter ingress by tortoises. The gates shall remain closed except during vehicle passage and may be electronically activated to open and close immediately after vehicle(s) have entered or exited to prevent extended periods with open gates, which might lead to a tortoise entering.	X-COC	X
D. <u>Stormwater Drainage Fencing.</u> The onsite stormwater drainage channels, including the headwalls, outlet, and road crossings, shall be permanently fenced to ensure exclusion of desert tortoise during AMS operation.	X-COC	
E. <u>Fence Inspections.</u> Following installation of the desert tortoise exclusion fencing for the permanent site and stormwater drainage fencing and temporary fencing (if required), the fencing shall be regularly inspected. Permanent fencing shall be inspected monthly and during/immediately following all major rainfall events. Any damage to the fencing shall be temporarily repaired immediately to keep tortoises out of the site, and permanently repaired within two days of observing damage. Inspections of permanent site fencing shall occur for the life of the project. Temporary fencing must be inspected immediately following major rainfall events. All temporary fencing shall be repaired immediately upon discovery and, if the fence may have permitted tortoise entry while damaged, the Designated Biologist shall inspect the area enclosed by the fence for tortoise.	X-COC	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>2. <u>Desert Tortoise Clearance Surveys.</u> Following construction of the tortoise exclusionary fencing around the Plant Site, all fenced areas shall be cleared of tortoises by the Designated Biologist, who may be assisted by Biological Monitors. A minimum of two, 100 percent coverage protocol clearance surveys with negative results must be completed and these must coincide with heightened desert tortoise activity from April through May and September through October. Non-protocol clearance surveys may be conducted in areas of certainly unsuitable habitat (e.g., developed) with prior approval of specific areas by USFWS and CDFG (these proposed areas shall be identified in the draft Desert Tortoise Plan). Clearance survey transects shall be followed as described in the Final Desert Tortoise plan. Additional clearance survey guidelines area provided in the USFWS <i>Desert Tortoise Field Manual</i> (www.fws.gov/ventura/speciesinfo/protocols_guidelines).</p> <p><u>Translocation of Desert Tortoise.</u> If desert tortoises are detected during clearance surveys within the project impact area, the Designated Biologist shall safely translocate the tortoise the shortest possible distance to the nearest suitable habitat. Any handling efforts shall be in accordance with techniques described in the final Desert Tortoise Plan, which shall be consistent with the USFWS <i>Desert Tortoise Field Manual</i> (www.fws.gov/ventura/speciesinfo/protocols_guidelines). If a visibly diseased tortoise is encountered onsite, procedures shall be implemented in accordance with the approved final Desert Tortoise Plan.</p>	X-COC	
	X-COC	X
<p>3. <u>Burrow Inspection.</u> All potential desert tortoise burrows within the fenced area shall be searched for presence. To prevent reentry by a tortoise or other wildlife, all burrows shall be collapsed once absence has been determined, in accordance with the final Desert Tortoise Plan. Immediately following excavation and if environmental conditions warrant immediate translocation, tortoises excavated from burrows shall be translocated to unoccupied natural or artificial burrows within the location approved by USFWS and CDFG per the final Desert Tortoise Plan.</p>	X-COC	
<p>4. <u>Burrow Excavation.</u> Burrows inhabited by tortoises shall be excavated by the Designated Biologist using hand tools, and then collapsed or blocked to prevent re-occupation, in accordance with the final Desert Tortoise Plan. If excavated during May through July, the Designated Biologist shall search for desert tortoise nests/eggs. All desert tortoise handling and removal, and burrow excavations, including nests, shall be conducted by the Designated Biologist in accordance with the USFWS <i>Desert Tortoise Field Manual</i> (www.fws.gov/ventura/speciesinfo/protocols_guidelines).</p>	X-COC	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>shall be conducted using non-invasive methods (i.e., high-powered binoculars, spotting scope, or camera). Owls shall not be trapped or otherwise handled to read the color band. If survey results indicate burrowing owls are not nesting within the surveyed area, remedial actions may be developed and implemented in consultation with the CPM, CDFG and USFWS to correct conditions at the site that might be preventing owls from nesting there. A report describing survey results and any remedial actions taken shall be submitted to the CPM, CDFG and USFWS no later than January 31 of each year for two years.</p> <p>4. <u>Preserve and Manage Compensatory Habitat.</u> For each individual owl or pair identified on the project site during pre-construction surveys, off-site mitigation shall be required as described in the California Burrowing Owl Consortium guidelines (CBOC 1993). Determining which ratio to apply depends on whether the proposed compensatory habitat is occupied or unoccupied.</p> <p>A. Replacement of occupied habitat with occupied habitat: 1.5 times 6.5 (9.75) acres per pair of single bird</p> <p>B. Replacement of occupied habitat with suitable unoccupied habitat: 3 times 6.5 (19.5) acres per pair of single bird.</p> <p>Compensatory habitat shall be suitable for occupation by burrowing owls and preserved and managed in perpetuity for this purpose. Compensatory mitigation may be within the 118.2 acres proposed for desert tortoise and MGS (refer to BIO-15), provided that it also meets the criteria for suitable burrowing owl habitat. The compensatory habitat shall be managed for the benefit of burrowing owls, with the specific goals of:</p> <p>A. Maintaining the functionality of artificial and natural burrows; and</p> <p>B. Minimizing the occurrence of weeds (species considered “moderate” or “high” threat to California wildlands as defined by CAL-IPC [2006] and noxious weeds rated “A” or “B” by the California Department of Food and Agriculture and any federal-rated pest plants [CDFA 2009]) at less than 10% cover of the shrub and herb layers.</p>	<p>X-COC</p> <p>X-COC</p> <p>X-COC</p> <p>X-COC</p> <p>X-COC X-COC</p>	<p>X</p> <p>X</p> <p>X</p> <p>X</p> <p>X</p>

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>The Burrowing Owl Plan shall also include monitoring and maintenance requirements for the compensatory habitat, details on methods for measuring compliance goals, and remedial actions to be taken if management goals are not met. The final Burrowing Owl Plan is due before preconstruction surveys begin to ensure that an approved relocation methodology will be followed for any owls occurring within the project area. Therefore, it is understood that the compensatory mitigation acreage (if required) may not be identified in the Burrowing Owl Plan. However, the Plan shall propose a location for compensatory mitigation land and the acreage required, quantified according to the CBOC methods outlined above. If owls are identified during the pre-construction survey, the project owner shall submit an addendum to the Burrowing Owl Plan, which identifies the number of owls identified and the exact acreage to be preserved and managed in perpetuity for burrowing owl based on the results of the preconstruction survey and as agreed to in consultation with CDFG.</p>	X-COC	X
<p>14. American Badger and Desert Kit Fox Impact Avoidance and Minimization Measures BIO-14 To avoid direct impacts to American badgers and desert kit fox, preconstruction surveys shall be conducted for these species concurrent with the desert tortoise surveys. Surveys shall be conducted as described below:</p>	X-COC	
<p>Biological Monitors shall perform pre-construction surveys for badger setts and kit fox burrows in the project area, including areas within 250 feet of the project site. If burrows are detected, each burrow shall be classified as inactive, potentially active, or definitely active.</p>	X-COC	X
<p>Inactive burrows and setts that would be directly impacted by construction activities shall be excavated by hand and backfilled to prevent reuse by badgers or kit fox.</p>	X-COC	X
<p>Potentially and definitely active burrows and setts shall not be disturbed during the whelping/pupping season (February 1 – September 30). Potentially and definitely active dens that would be directly impacted by construction activities shall be monitored by the Biological Monitor for three consecutive nights using a tracking medium (such as diatomaceous earth or fire clay) and/or infrared camera stations at the entrance. If no tracks are observed in the tracking medium or no photos of the target species are captured after three nights, the den shall be excavated and backfilled by hand. If tracks are observed, the Biological Monitor shall directly observe the burrow or sett and block the entrance after the animal exits and the Biological Monitor has verified that there are no animals in the burrow or sett. The burrow or den shall be blocked with natural materials (e.g., rocks, dirt, sticks, and vegetation piled in front of the entrance) or passive hazing methods shall be employed for the next three to five nights to discourage the badger or kit fox from continued use. Passive hazing methods shall be approved by CDFG. Live or other traps shall not be used (CCR Title 14 Section 460). A kit fox or badger shall never be trapped in its</p>	X-COC	X

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
burrow/sett. After verification that the den is unoccupied it shall then be excavated and backfilled by hand to ensure that no badgers or kit fox are trapped in the den.		
<p>15. Compensatory Mitigation BIO-15 To fully mitigate for habitat loss and incidental take of desert tortoise and Mohave ground squirrel as well as burrowing owl, the project owner shall acquire, prior to ground-disturbing activities, in fee or in easement, no less than 118.2 acres of land suitable for these species and shall provide funding for the enhancement and long-term management of these compensation lands. The responsibilities for management of the compensation lands may be delegated by written agreement to CDFG or to a third party, such as a non-governmental organization dedicated to habitat conservation, subject to approval by the CPM, in consultation with CDFG and USFWS prior to land acquisition or management activities. If habitat disturbance exceeds that described in this analysis, the project owner shall be responsible for acquisition and management of additional compensation lands and/or additional funds required to compensate for any additional habitat disturbances. Additional funds shall be based on the adjusted market value of compensation lands at the time of construction to acquire and manage habitat. Agreements to delegate land acquisition or management shall be implemented within 12 months of the Energy Commission's decision. The acquisition and management of compensation lands shall include, but is not limited to, the following elements:</p> <p>1. <u>Selection Criteria for Compensation Lands.</u> The compensation lands selected for acquisition or title/easement transfer shall:</p> <p>A. have substantial capacity to support resident and dispersing desert tortoise, MGS, and burrowing owl;</p> <p>B. be a contiguous block of land (preferably) or located so that parcel(s) result in a contiguous block of protected habitat;</p> <p>C. not be encumbered by easements or uses that will preclude fencing of the site or preclude management of the site for the primary benefit of the species for which mitigation lands were secured; and</p> <p>D. include mineral/water rights or ensure that those rights may not be evoked in a manner to negate the value of the compensation lands.</p>	X-COC	
	X-COC	
	X-COC	X
	X-COC	
	X-COC	X
	X-COC	X

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
2. <u>Review and Approval of Compensation Lands Prior to Acquisition or Title/Easement Transfer.</u> A minimum of three months prior to acquisition or transfer of the property title and/or easement, the project owner, or a third-party approved by the CPM, in consultation with CDFG and USFWS, shall submit a proposal to the CPM, CDFG, and USFWS describing the parcel(s) intended for purchase or title/easement transfer. This proposal shall discuss the suitability of the proposed parcel(s) as compensation lands for desert tortoise, MGS, and burrowing owl in relation to the criteria listed above. Approval from the CPM, in consultation with USFWS and CDFG, shall be required for acquisition of all parcels comprising no less than 118.2 acres in advance of purchase or title/easement transfer.	X-COC	
3. <u>Review and Approval of Compensation Lands Management Plan.</u> Within six months of the land or easement purchase or transfer, as determined by the date on the title, the project owner, or a third-party approved by the CPM, in consultation with CDFG and USFWS, shall submit a compensation lands management plan to the CPM, CDFG, and USFWS. The plan shall include, but not be limited to proposed measures to enhance habitat (e.g., removal of structures and other human attractants); maintenance procedures; general maintenance provisions (e.g., trash dumping, trespass, pesticide use avoidance, etc.).	X-COC	X
4. <u>Mitigation.</u> Security for Compensation Lands and <u>Avoidance/Minimization Measures.</u> The project owner shall provide financial assurances to the CPM, with copies of the document(s) to CDFG and USFWS, to guarantee that an adequate level of funding is available to implement all biological avoidance, minimization, and compensation measures described in the conditions of certification. These funds shall be used solely for implementation of the measures associated with the project. The project owner or an approved third party shall complete acquisition of the proposed compensation lands prior to initiating ground-disturbing project activities.	X-COC	X
5. <u>Conditions for Acquisition of Compensation Lands.</u> The project owner shall comply with the following conditions relating to acquisition of compensation lands or transfer of the property's title and/or easement after the CPM, in consultation with CDFG and USFWS, has approved the proposed compensation lands as described above.	X-COC	X
A. <u>Preliminary Report:</u> The project owner, or approved third party, shall provide a recent preliminary title report (no more than six months old), hazardous materials survey report (i.e., Phase I ESA), biological analysis, and other necessary documents for the proposed 118.2 acres. All documents conveying or conserving compensation lands and all conditions of title/easement are subject to a field review and approval by the CPM, in consultation with CDFG and USFWS, California Department of General Services and, if applicable, the Fish and Game Commission and/or Wildlife Conservation Board.	X-COC	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>B. <u>Title/Conveyance</u>: The project owner shall transfer fee title/deed or a conservation easement for the 118.2 acres of compensation lands to CDFG under terms approved by CDFG. Alternatively, a CPM-approved, in consultation with CDFG and USFWS, non-profit organization qualified pursuant to California Government Code section 65965 may hold fee title or a conservation easement over the compensation lands. In the event an approved non-profit holds title, a conservation easement shall be recorded in favor of CDFG in a form approved by CDFG and USFWS; in the event an approved nonprofit holds a conservation easement over the compensation lands, CDFG shall be named a third party beneficiary. USFWS shall be named a third party beneficiary regardless of who holds the easement. The project owner shall also provide a property assessment and warranty.</p>	X-COC	
<p>C. <u>Enhancement Fund</u>. The project owner shall fund the initial protection and enhancement of the 118.2 acres by providing the enhancement fund to the CDFG. Alternatively, a CPM-approved, in consultation with CDFG and USFWS, non-profit organization qualified pursuant to California Government Code section 65965 to manage the compensation lands may hold the enhancement funds. If CDFG takes fee title to the compensation lands, the enhancement fund must go to CDFG.</p>	X-COC	
<p>D. <u>Endowment Fund</u>: Prior to ground-disturbing project activities, the project owner shall provide to CDFG a capital endowment in the amount determined through the Property Analysis Record (PAR) or PAR-like analysis that will be conducted for the 118.2 acres of compensation lands. Alternatively, a CPM-approved, in consultation with CDFG and USFWS, non-profit organization qualified pursuant to California Government Code section 65965 may hold the endowment fees. If CDFG takes fee title to the compensation lands, the endowment must go to CDFG, where it will likely be held in the special deposit fund established pursuant to Government Code section 16370. If the special deposit fund is not used to manage the endowment, the California Wildlife Foundation will manage the endowment for CDFG and with CDFG guidance.</p> <p>The project owner and the CPM shall ensure that an agreement is in place with the endowment holder/manager to ensure the following:</p> <ul style="list-style-type: none"> • <u>Interest</u>. Interest generated from the initial capital endowment shall be available for reinvestment into the principal and for the long-term operation, management, and protection of the approved compensation lands, including reasonable administrative overhead, biological monitoring, improvements to carrying capacity, law enforcement measures, and any other action designed to protect or improve the habitat values of the compensation lands. 	<p>X-COC</p> <p>X-COC</p>	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<ul style="list-style-type: none"> • <u>Withdrawal of Principal</u>. The endowment principal shall not be drawn upon unless such withdrawal is deemed necessary by the CDFG or the approved third-party endowment manager to ensure the continued viability of the species on the 118.2 acres. If CDFG takes fee title to the compensation lands, monies received by CDFG pursuant to this provision will likely be deposited in a special deposit fund established pursuant to Government Code section 16370. If the special deposit fund is not used to manage the endowment, the California Wildlife Foundation will manage the endowment for CDFG and with CDFG guidance. 	X-COC	
E. <u>Pooling Endowment Funds</u> . CDFG, or a CPM-approved, in consultation with CDFG and USFWS, non-profit organization qualified pursuant to California Government Code section 65965 to hold endowments may pool the endowment with other endowments for the operation, management, and protection of the 118.2 acres for local populations of desert tortoise and MGS. However, for reporting purposes, the endowment fund must be tracked and reported individually.	X-COC	
F. <u>Security Deposit</u> . The project owner may proceed with ground disturbing activities before fully performing its compensatory mitigation duties and obligations as set forth above only if the project owner secures its performance by providing funding to CDFG (Security Deposit), or if CDFG approves, administrative proof of funding, necessary to cover easement costs, fencing/cleanup costs, and as necessary, initial protection and enhancement of the compensation lands. If the Security is provided to allow the commencement of project disturbance prior to completion of compensation actions, the project owner, CDFG, or a third-party entity approved by the CPM, in consultation with CDFG and USFWS, may draw on the principle sum if it is determined that the project owner has failed to comply with the conditions of certification. The security will be returned to the project owner upon completion of the legal transfer of the compensation lands to CDFG or approved third-party entity, or upon completion of an implementation agreement with a third party mitigation banking entity acceptable to the CPM and CDFG, to acquire and/or manage the compensation lands. The Security is calculated as follows: <ul style="list-style-type: none"> • Costs of enhancing compensation lands are estimated at \$250 per acre. • Costs of establishing an endowment for long-term management of compensation lands are estimated at \$1,300 per acre. 	X-COC	X
	X-COC	X

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
Monitoring and maintenance of the site shall be conducted for five years unless less monitoring can be justified. Following the first year of monitoring, if the project owner petitions to terminate the monitoring program, staff and CDFG will determine whether more years are of monitoring are needed.	X-COC	
17. Monitoring Impacts of Solar Collection Technology on Birds BIO-17 The project owner shall prepare and implement a Bird Monitoring Study to monitor the death and injury of birds from collisions with facility features such as reflective mirror-like surfaces and from heat, and bright light from concentrating sunlight. The study design shall be approved by the CPM in consultation with CDFG and USFWS, and shall be incorporated into the project's BRMIMP and implemented. The Bird Monitoring Study shall include detailed specifications on data and carcass collection protocol and a rationale justifying the proposed schedule of carcass searches. The study shall also include seasonal trials to assess bias from carcass removal by scavengers as well as searcher bias.	X-COC	
18. Common Raven Monitoring, Management, and Control BIO-18 The project owner shall implement the following measures to manage their construction site and related facilities in a manner to control raven populations and to mitigate cumulative and indirect impacts to desert tortoise associated with regional increases in raven numbers:	X-COC	
1. Common Raven Monitoring, Management, and Control Plan. The project owner shall design and implement a Common Raven Monitoring, Management, and Control Plan that is consistent with the most current USFWS-approved raven management guidelines and that meets the approval of USFWS, CDFG, and Energy Commission staff. The Raven Plan shall:	X-COC	
A. Identify conditions associated with the project that might provide raven subsidies or attractants;	X-COC	X
B. Describe management practices to avoid or minimize conditions that might increase raven numbers and predatory activities;	X-COC	X
C. Describe control practices for ravens;	X-COC	X
D. Address monitoring and nest removal during construction and for the life of the project;	X-COC	X
E. And discuss reporting requirements.	X-COC	X
2. USFWS Regional Raven Management. The project owner shall submit payment to the project sub-account of the REAT Account held by the National Fish and Wildlife Foundation (NFWF) to support the regional raven management plan. The amount shall be a one-time payment of \$105 per acre of land permanently disturbed by the project.	X-COC	X

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>19. Evaporation Pond Monitoring and Adaptive Management Plan BIO-19 The project owner shall design and implement an Evaporation Pond Monitoring and Adaptive Management Plan that meets the requirements of the USFWS, CDFG, RWQCB and the CPM. The objective of the Plan is to define the monitoring and reporting procedures as well as triggers for adaptive management strategies that shall be implemented to prevent wildlife mortality at the evaporation ponds. The plan shall include:</p> <ul style="list-style-type: none"> • A description of evaporation pond design features such as side slope specifications, freeboard and depth requirements, which will prevent use by wildlife. • A detailed description of the wildlife monitoring procedures and schedule. For the initial implementation of a new technology, daily monitoring shall be conducted both at the project evaporation ponds and the wetlands within the Harper Lake ACEC. Monitoring may be reduced to weekly and potentially bi-weekly or monthly depending on the results of initial monitoring period. • A detailed description of the water quality and water level monitoring procedures and schedule. Water quality and water level monitoring shall coincide with wildlife monitoring to provide a basis for comparative analysis. • A description of wildlife exclusion/deterrent technologies and adaptive management strategies. Technologies shall include but are not limited to netting, and shall not disturb or harass non-target wildlife adjacent to the project area. • Triggers for adaptive management (i.e., modifications to existing technology or replacement with new technology). Adaptive management shall be necessary if: 1) more than one dead bird per quarter is discovered at the evaporation ponds; or 2) one special-status animal is discovered at the evaporation ponds; or 3) noise levels attributable to the technology exceed 60 dBA at the Harper Lake ACEC wetlands. After three failed attempts at new technology, the ponds shall be netted. • Reporting requirements, to include monthly reporting for the first year if a technology other than netting is used. Reporting may be reduced to monthly or quarterly thereafter if no bird or wildlife deaths are reported during the first year. If wildlife mortality occurs at the ponds or if birds are disturbed at the marsh as described above, the CPM shall be notified within 10 days of the incident and the accompanying adaptive management action to implemented. • Evaporation pond monitoring and reporting shall continue for the life of the project. The draft Plan submitted by the Applicant (AS 2009d) shall provide the basis for the final plan, subject to review and revisions from the CPM in coordination with USFWS, CDFG, and RWQCB. 	<p>X-COC</p> <p>X-COC</p> <p>X-COC</p> <p>X-COC</p> <p>X-COC</p> <p>X-COC</p> <p>X-COC</p>	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>20. Harper Dry Lake Marsh Water Delivery BIO-20 To ensure continuity of water delivery to the Harper Dry Lake ACEC the project owner shall not decommission the existing well on Mojave Solar, LLC-owned property that currently serves the Harper Dry Lake marsh (wetland well) until an alternate well is able to effectively convey a minimum of 75 acre feet per year to the Harper Dry Lake marsh.</p> <p>This condition of certification does not transfer to Mojave Solar, LLC the obligation of Luz Solar Partners Ltd. to allow BLM to pump 75 acre feet of water per year to the marsh, under SEGS IX Condition of Certification BIO-11.k.</p>	<p>X-COC</p> <p>X-COC</p>	
<p>21. USFWS Biological Opinion BIO-21 The project owner shall provide a copy of the Biological Opinion per Section 7 of the federal Endangered Species Act written by the U. S. Fish and Wildlife Service in consultation with U.S. Department of Energy. The terms and conditions contained in the Biological Opinion shall be incorporated into the project's BRMIMP and implemented by the project owner.</p>	X-COC	X
<p>22. Prior to the commencement of ground disturbance activities, clearance surveys will be conducted for MGS burrows along the alignment concurrently with the DT surveys. All burrows within work areas will be excavated. If MGS are detected, they will be allowed to escape the exclusion area prior to completion of fencing of the area. The Designated Biologist will maintain records of squirrels that have been excluded from the work areas, and will prepare a report for submittal to the CDFG 30 day after clearance surveys.</p>		X
<p>23. Prior to construction, a California Burrowing Owl Consortium (CBOC), with CDFG approval, protocol-level burrowing owl survey will be conducted along the fiber-optic alignments to detect the presence of burrowing owls. Active owl burrows will be mapped and avoided to the maximum extent possible with a minimum 1,250-foot buffer around the active burrow. If the burrow cannot be avoided, the owl will be passively relocated outside of nesting season February 1 through August 31. Relocation of owls will follow the guidelines in the avoidance and minimization measures listed in section 3.8.4.1.2 of this document.</p>		X
<p>24. Surveys for sensitive plant species will be conducted during the Spring season and within appropriate habitats prior to commencement of ground disturbance activities. Surveys will be conducted in the Spring prior to construction/ground disturbance. Surveys will follow the rare plant and vegetation survey guidelines provided by CNPS (CNPS 2001a), CDFG (CDFG 2000), and the CEC Recommended Biological Resources Field Survey Guidelines for Large Solar Projects, Draft April 2, 2009 (CEC 2009).</p>		X
<p>25. Desert Tortoise avoidance and minimization measures per the Desert Tortoise Clearance and Relocation/Translocation Plan (Desert Tortoise Plan), to be approved by CEC, CDFG, USFWS, and BLM:</p>		

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
Plant Site Clearance Surveys		
<ul style="list-style-type: none"> All tortoise sign will be mapped and evaluated (e.g., type, age, size) during all passes, and all scat collected. During subsequent passes, areas where fresh scat is found will prompt concentrated searches. After the second pass, concentrated searches will be conducted in all areas where recent sign is concentrated, unless a tortoise has been found in that area. No burrows will be collapsed until the third pass, assuming that all tortoises probably have been relocated from the Project Area. (Fresh burrows used by other wildlife, including badgers or foxes, will not be collapsed until occupants have been removed via active or passive techniques approved by CDFG.) While clearance is planned to occur when ambient temperatures are safe for translocating tortoises, ambient temperatures may rise unexpectedly during the second pass such that a tortoise or other wildlife might be trapped in the open if its burrow has been excavated and collapsed during the search effort. To assist the identification of currently used burrows, all burrows will be inspected and assessed for occupation or recent use by tortoises during the first two passes, gated with small sticks along the entrance to detect future use, mapped and flagged. On the third pass, burrows will be completely excavated using standardized techniques approved by USFWS (2009a) and the Desert Tortoise Council (1994). During excavation, attention will be given to potential tortoise nests (see Nest Relocation, below). Following the installation of exclusionary fencing and after ensuring DT are absent from the Project site, heavy equipment shall be allowed to enter the Project site to perform earthwork such as clearing, grubbing, leveling, and trenching. A biological monitor shall be onsite at all times during initial clearing and grading activities. Should a tortoise be discovered, it shall be relocated as described above in accordance with the final Desert Tortoise Plan. 	<p>X</p> <p>X</p>	
<p>Data Collected:</p> <ul style="list-style-type: none"> Each captured tortoise will be processed at capture, prior to translocation. The gender, carapace length, width along the widest area between and inclusive of Marginals 5 and 6, height at the third vertebral, distinguishing morphology, clinical signs of disease, capture site location and description, and the amount of void, if any, will be recorded. In addition, the tortoise will be photographed and drawn. All release site locations will also be recorded at relocation/translocation, along with their descriptions. All tortoise handling will be accomplished by techniques outlined in the USFWS <i>Field Manual</i> (2009a: Sections 7.6-7.8) and including the most recent disease prevention techniques (e.g., Wendland et al. 2009). Each tortoise will be assigned an individual number, with a number series to be provided by USFWS. Marking techniques will be approved by USFWS, but temporary marks using very small epoxy numbers (e.g., clear epoxy 	X	X

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
over a small, indelible number on a correction fluid [Wite-Out®] background) on an ostal or interior marginal area that receives little to no abrasion are suggested, with a Project specific identifier. Such numbers will last for several years, which will facilitate identifying specific tortoises if they are subsequently observed during Project maintenance or other activities, including repeated observations during construction (e.g., on the perimeter fence).		
<p>Health Considerations:</p> <ul style="list-style-type: none"> Visual health assessments will be conducted on all tortoises relocated (i.e., moved <500 m) or translocated (moved > 500 m), by an experienced biologist approved by the USFWS. USFWS (2010b) guidance and later e-mails from USFWS (T. Englehard, pers. comm. to A. Karl) have identified that no tortoise will be relocated within 1.5 km (0.9 mi) of a diseased resident tortoise because relocated tortoises may move 1.5 km after translocation. No tortoise may be translocated within 6 km of a diseased resident tortoise. Mojave Solar will comply with the requirement to complete a 100%-coverage survey for resident diseased tortoises within 1.5 km of any tortoise relocated from the MSP site, including during perimeter fence construction, or within 6 km of any tortoise translocated. All resident tortoises within 1.5 km of a relocation site and 6.5 km of a translocation site will be processed (weighed, measured, described, photographed), marked with an epoxy number for future identification and their health assessed. If any tortoises from the Project Area are moved more than 500 m, then all resident tortoises within 6.5 km of the Translocation Site will be fitted with a transmitter for follow-up blood sampling at the earliest date approved by USFWS, currently 15 May. No tortoise with clinical signs of mycoplasmosis will be relocated or translocated. Schumacher <i>et al.</i> (1997) observed that clinical signs had a high statistical correlation with positive serology (i.e., exposure to <i>Mycoplasma agassizii</i>). A mucous nasal discharge is the clinical sign that was the most reliable predictor (93% of tortoises with a mucous nasal discharge were seropositive), although it could be caused by pathogens other than <i>M. agassizii</i>. Furthermore, a purulent nasal discharge was the only clinical sign that was relatively objective; other clinical signs were far more subjective, were potentially present for other reasons, and reduced the statistical predictability of positive serology. For the MSP, a purulent nasal discharge will be the threshold to identify a diseased tortoise, unless USFWS determines that other clinical signs should be used for diagnosing a diseased tortoise. 	<p>X</p> <p>X</p> <p>X</p>	<p>X</p>

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<ul style="list-style-type: none"> Relocated or translocated desert tortoises determined to be infectious or unhealthy will be sent to the Desert Tortoise Conservation Center (DTCC) or other USFWS-approved facility where they will undergo further assessment, treatment, and/or necropsy. Mojave Solar will provide a flat fee of \$9,000 for each desert tortoise sent to the DTCC commensurate with the cost to provide housing, care, treatment, and other services for five years (\$3,000 for Year 1, \$1,500 for Years 2 to 5). 	X	
<p>Transmitters:</p> <ul style="list-style-type: none"> If needed for monitoring relocated or translocated tortoises, transmitters will be affixed to the tortoises. Holohil R1-2B transmitters (24 mm wide by 11 mm thick; 14.9 g; www.holohil.com) will be epoxied onto a carapace scute using five-minute gel epoxy. For males, transmitters will be affixed to the fifth vertebral; for females, transmitters will be affixed to the anterior carapace in the most appropriate location for the animal's shell shape that will preclude interference with righting. The transmitter antenna will be fed through a plastic sheath with a diameter slightly greater than the antenna. This sheath will be epoxied low on the carapace, just above the marginal scutes, and split at the scute seams (growth areas) to preclude distortion of the tortoise's shell during growth. This technique permits the antenna to remain protected from abrasion, but move freely, thereby not affecting tortoise growth. Juvenile tortoises will be similarly equipped but with smaller transmitters, appropriate for their mass and size (<10% of the tortoise's mass). Because the antenna sheath is tightly curved on a very small tortoise, potentially constricting antenna movement with subsequent growth distortion, much more of the antenna will remain free on small tortoises. These are proven techniques to minimize disturbance to the tortoise, refined and/or developed and used by Dr. Karl for more than 20 years and on over 300 tortoises and subsequently used at Fort Irwin for several hundred tortoises. 	X	
<p>Transportation and Handling:</p> <ul style="list-style-type: none"> Tortoises that only need to be moved a few hundred feet will be hand-carried to the release site. Each tortoise that is hand-carried will be kept upright and the handler, wearing disposable examination gloves (one pair per tortoise), will move the tortoise as quickly and smoothly as possible. Tortoises that must be moved farther from the capture site or temporarily held in a climate-controlled situation will be sequestered in individual, sterilized tubs with taped, sterilized lids or single-use cardboard boxes with lids. During transport by vehicle, the tortoise tub will be kept shaded and the tub will be placed on a well-padded surface that is not over a heated portion of the vehicle floor. These measures are consistent with USFWS guidance (2009a: Section 7.10). 	X	X

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<ul style="list-style-type: none"> Should a tortoise void or defecate between capture and release, it will be thoroughly rinsed to remove potential attracting odors to predators. Then, it will be placed in a shallow bath of room temperature water to re-hydrate it, per USFWS guidance (2009a: Section 7.9). The tortoise's mass following this procedure will be recorded. 	X	X
<p>Handling Temperatures:</p> <ul style="list-style-type: none"> Handling will adhere to USFWS (2010b) handling guidelines, which state that tortoises can only be handled when air temperatures, measured at 2 in (5 cm) above the ground (shaded bulb), are not expected to exceed 95°F (35°C) during the handling session. If the air temperature exceeds 95°F during handling or processing, desert tortoises will be kept shaded in an environment where the ambient air temperatures do not exceed 91°F (32.7°C) and air temperature does not exceed 95°F. The desert tortoise will not be released until air temperature at the release site declines to 95°F. Tortoises must go underground to escape surface heat at ground surface temperatures of 109°F (43°C) (Karl 1992) to 113°F (45°C) (Zimmerman et al., 1994). Because surface temperatures can easily exceed 109°F when air temperatures at two inches are still below 95°F, the more conservative temperature will govern all tortoise handling described in the Desert Tortoise Plan, to minimize harm to tortoises. In other words, the USFWS guidelines will be followed except in the situation where they exceed 109°F ground temperature. <p>Relocation/Translocation Procedures</p> <p>Perimeter Fencing:</p> <ul style="list-style-type: none"> Any tortoise that must be moved during perimeter fencing will be relocated immediately outside the construction zone, but onto MSP land. Release points will be as close as possible to the capture point, to keep tortoises within their home range, but will always be on or immediately adjacent to suitable habitat. Specific release points cannot be identified at this time without knowing where tortoises are, but the highest likelihood of finding a tortoise along the perimeter fence is along the southern, eastern and northeastern border of the Beta Site and the western border of the Alpha Site. 	<p>X</p> <p>X</p> <p>X</p>	<p>X</p> <p>X</p> <p>X</p>

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<ul style="list-style-type: none"> Generally, tortoises will be placed in the shade of a shrub or, if known, in the entrance of that tortoise's burrow (but see below in the event that ambient temperatures are high). The most recent USFWS guidance (USFWS 2010b) states that all "perimeter fence" tortoises be moved to the interior of the Project Area. Because the solar project site has limited desert tortoise habitat and is expect to support few if any desert tortoises, which is supported by the limited amount sign and burrows on the proposed solar fields, it is believed that any individual found during fence construction maintains a territory outside of the solar project site and is utilizing the project area for foraging or movement. Therefore, desert tortoises on the MSP project found during fence construction will be placed outside of the solar project site rather than inside. All tortoises relocated from harm's way during perimeter fencing will be transmittered as described above. The exception will be tortoises brumating (≈hibernating) in burrows during winter (see below for a discussion of handling tortoises outside of USFWS temperature guidelines). Translocation will occur when air temperatures at 2 in (5 cm) above the ground, are not forecast to exceed 90°F (32°C) within three hours of release and 95°F (35°C) within one week of release; additionally, daily low temperatures should not be cooler than 50°F (10°C). The rationale for the higher temperature constraints is that tortoises must find or dig new refuges in the potentially unfamiliar translocation area prior to the onset of lethal daily temperatures. Along the perimeter fenceline, however, tortoises will be moved only a short distance, within their home ranges, where they are knowledgeable about the locations of refuges. USFWS (2010b) has agreed that relocation on linear facilities, including perimeter fencing, may occur during any time of the year. The only high temperature constraint is that no tortoise will be moved when air temperatures are expected to exceed 90°F (32°C) within three hours of release. Alternatives below summarize conditions and methods detailed in the Desert Tortoise Plan whereby tortoises could be relocated during <i>periods</i> of higher temperatures, although no tortoise will be moved when air temperatures exceed 95°F, except in an emergency Relocate to known burrow; monitor Erect temporary fence between tortoise and construction; monitor; remove fence when appropriate Temporarily move construction to another area Collect and hold in climate controlled facility; release in evening or the following morning; monitor 	<p>X</p> <p>X</p> <p>X</p>	<p>X</p> <p></p> <p>X</p>

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>During winter or low temperatures, the following methods summarize the approach to relocating tortoises that must be moved along the perimeter fence:</p> <ul style="list-style-type: none"> • If cannot be avoided, place tortoise in artificial burrow, temporarily block in and monitor; remove block at two weeks (or earlier depending on the weather) and monitor • If tortoise fails to find suitable winter burrow and will not use artificial burrow, hold in climate-controlled facility, in the dark at temperatures simulating burrow temperatures, until seasonal temperatures warm and tortoises are active; release within 100 feet of capture burrow; monitor. <p>Plant Site:</p> <ul style="list-style-type: none"> • Any tortoise that must be moved <500 meters will be relocated immediately outside the construction zone, but onto MSP land, and placed in the shade of a shrub or at the entrance to a known burrow for that tortoise. Release points will be as close as possible to the capture point, to keep tortoises within their home range, but will always be on or immediately adjacent to suitable habitat. Specific release points cannot be identified at this time without knowing where tortoises are, but the highest likelihood of finding a tortoise along the perimeter fence is along the southern, eastern and northeastern border of the Beta Site and the western border of the Alpha Site. • Any tortoise translocated >500 meters will be placed in an individual quarantine pen in the relevant Translocation Site (see below), under a shrub or near an artificial burrow. Two artificial burrows, each at least 4 feet (1.2 m) long, will be constructed for each tortoise, using a gas-powered auger or shovel/plywood, per USFWS (2009a) guidance. Translocated tortoises will only be translocated once. • Based on published and unpublished research, a juvenile tortoise moved farther than 330 feet (100 m) may be outside its recent or familiar use area. For AMSP clearance, if juvenile tortoises are moved within 330 feet of the capture location, where they may have site familiarity, they will be released under a shrub and monitored initially as described in Post-Release Tortoise Monitoring, below. For distances >330 ft, they will be moved to the Translocation Site into a predator-proof enclosure, using 5-ft-tall "Non-Climb", 2 by 4 inch vertical mesh fencing, buried at least 1 ft. and with avian netting over the top. The size of the enclosure will depend on the number of tortoises found, but will be a minimum of 20 feet in diameter, extending to 50 feet or more, as necessary, to accommodate more juvenile tortoises. (Morafka <i>et al.</i> 1997 successfully penned juvenile tortoises at the rate of 62-123 tortoises per acre (152-305 animals per hectare). After tortoises have become familiar with the site's odors and landmarks for at least two weeks, escape holes will be opened in the lower edge for tortoises to escape passively (e.g., Morafka <i>et al.</i> 1997). Modifications to the design and process may occur in response to predator interest in 	<p>X</p> <p>X</p> <p>X</p>	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>the enclosure or juvenile tortoise behavior in the enclosure, incorporating new and relevant head-starting techniques used at Twentynine Palms Marine Corps Air Ground Combat Center.</p> <ul style="list-style-type: none"> • All translocated tortoises will be rehydrated within 12 hours prior to release, via USFWS (2009a) methods • Two translocation sites were chosen, one on each side of Harper Lake Road, to minimize post-translocation movements of tortoises across that road. All tortoises west of Harper Lake Road will be moved to the Translocation Site in Section 25, on land owned by Mojave Solar. All tortoises east of Harper Lake Road will be moved to the Translocation Site in Section 4, in the BLM DWMA and ACEC. Translocation to a DWMA or ACEC is preferred by CDFG, and BLM has agreed to move the few potential tortoises from MSP to BLM land (L. Encinas, pers. comm.). • The Translocation Site pens will be sufficiently large to support each tortoise pending disease testing results. Each will be a minimum of 165 x 165 feet (50 by 50 m), thereby providing adequate forage and sufficient habitat for a tortoise to find and/or construct adequate cover sites. Pens will be constructed using double-walled, 1 by 2 inch tortoise-proof fencing, installed as identified for perimeter fencing, above. They will be separated by a minimum of 100 meters so that tortoises will not be crowded once the fences are removed (if tortoises are seronegative) and tortoises fully released. Prior to Project Area clearance, pen design and an animal husbandry plan for penned tortoises will be approved by experienced personnel from an accredited American Zoological Association institution and approved by USFWS, BLM, and CDFG. • If a tortoise is found inside the Plant Site during initial grading or operations, and temperatures are too high for safe relocation/translocation, the tortoise will be captured, secured in an individual, sterilized box and temporarily placed in a quiet, climate-controlled environment (e.g., the onsite Project office). Depending on temperatures and other factors, it is possible that the tortoise could be affixed with a transmitter and relocated outside the Project Area or translocated into the Translocation Site the same day, when temperatures subside (or the following morning for juvenile tortoises), and monitored to ensure its safety. If the tortoise will likely be harmed or die, it will be held in captivity at a location approved by USFWS and CDFG, away from other tortoises, to be released into the Translocation Site during the next available window. Other options will also be investigated. The goal of the translocation is to keep the tortoise in the population, in order to promote recovery. 	<p>X</p> <p>X</p> <p>X</p> <p>X</p>	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>Post- Release Monitoring</p> <ul style="list-style-type: none"> During perimeter fence construction, tortoises will be moved a short distance from construction activities along the perimeter fence and therefore will be assumed to be within their home range and familiar with burrow locations. However, they will receive immediate post-release monitoring nonetheless. This may be especially critical for juvenile tortoises, which are highly subject to depredation. The Desert Tortoise Plan discusses the details of immediate post-release monitoring for all tortoises relocated during fence USFWS (2010b) requires a five-year monitoring program for translocatees, including tortoises relocated during perimeter fence construction. Based on multiple Project surveys, it is assumed that fewer than five tortoises will be part of the study. USFWS (2010b) has determined that no resident and control study cohorts are required for fewer than five translocatees (including juveniles). If five or more desert tortoises are translocated from the project site, Mojave Solar will work with the BLM, CDFG, and Service to identify appropriate locations for control and resident desert tortoise monitoring. Mojave Solar will monitor all translocated tortoises for five years from the time of relocation/translocation. Tortoises will be located by telemetry according to the schedule identified in USFWS (2010b) guidelines. Each time the tortoise is located, the behavior, location (UTM), and burrow description (if any) will be recorded. Survival and general health will be monitored through body condition indices (mass to volume ratios), clinical signs of disease, serology, and inspection for injuries. Any time a tortoise is handled, it will be examined for clinical signs of disease. Formal health assessments will be conducted during April (following brumation), July (following oviposition), and October (prior to brumation). At these times, body condition (mass to volume ratio) also will be measured (mass, carapace length, width at Marginal 5 or 6, height) Blood samples will be taken and analyzed annually, in July or October. An approved biologist will conduct the assessments and tissue sampling. While blood samples are not required of tortoises moved <500 meters during relocation, blood will be sampled shortly after relocation³ in order to provide baseline data. 	<p>X</p> <p>X</p> <p>X</p> <p>X</p> <p>X</p>	<p>X</p>

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<ul style="list-style-type: none"> Sampling frequency and techniques for disease analysis will be updated as necessary during the study, based on the newest disease information from this and other studies. This may include tests for other pathogens (e.g. <i>Mycoplasma</i> spp., herpesvirus, iridovirus) as their importance and evaluation techniques become validated for desert tortoises. Data will be recorded on a data sheet similar to that in Appendix 1, with an additional health assessment data sheet to be provided by USFWS. Any health problems observed (e.g., rapid declines in body condition, perceived outbreaks of disease, mortality events) will be reported to the USFWS, CDFG and BLM such that appropriate actions can be taken in a timely manner. Should a transmittered tortoise die, the cause of death will be determined to the extent possible. This information, along with the location and any other analysis that could assist the USFWS, CDFG, BLM and DOE will be provided to these agencies within 48 hours, verbally, or five business days, if by e-mail. All fresh carcasses will be salvaged and frozen. They will be submitted for necropsy upon direction from USFWS, CDFG, and BLM; DOE will also be notified. Transmitters will be changed as necessary. <p>Mojave Solar has also proposed some alternatives for consideration if fewer than five tortoises are relocated/translocated.</p> <p>Nest Relocation</p> <ul style="list-style-type: none"> Any nests found between November 1 and April 15 are unlikely to be viable and will not be moved; hatching is typically completed by October. In the event that nests are found between April 15 and October 31, the nests will be moved. Eggs will be inspected to determine if they are viable and, if so, will be moved to an identical microsite (e.g., cover, plant species, soil type, substrate, aspect) on the approved Translocation Site using standard techniques (e.g. Desert Tortoise Council 1994, USFWS 2009a). Translocated nests will be fenced with open-mesh fencing (e.g. 2-inch wide mesh) that will permit hatchlings to escape but prevent depredation by canids that might be attracted to the new nests by human scent predator entry. Open-mesh fencing or avian netting also will be installed on the roof of the nest enclosure to prevent predator entry. Nests will be monitored from a 30-foot distance once a month until late November, at which time they will be excavated for examination. If possible, hatchlings will be weighed, measured, photographed, described and marked. 	<p>X</p> <p>X</p> <p>X</p> <p>X</p> <p>X</p> <p>X</p>	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<ul style="list-style-type: none"> In construction areas in potentially occupied desert tortoise areas, work and staging areas, including the locations of the fiber-optic upgrades under construction, may be fenced with USFWS-approved temporary desert tortoise fencing in a manner that prevents equipment and vehicles from straying from the designated work area into adjacent habitat. The Designated Biologist or Biological Monitor will assist in determining the boundaries of the area to be fenced in consultation with USFWS and CDFG, and with BLM when construction areas are within lands administered by the BLM. All workers will be advised that equipment and vehicles must remain within the fenced work areas. Installation of the fencing and any necessary surveys will be directed and/or conducted by the Designated Biologist or Biological Monitor in concurrence with these agencies. The fencing will remain in place for the duration of construction activities at a particular location and will be removed when construction activities are complete. The Designated Biologist or Biological Monitor will inspect the fencing on a biweekly basis to ensure that no holes develop that could allow desert tortoises to enter the work areas. If holes are found, they will be repaired immediately. If desert tortoises are found within an area that has been fenced to exclude them, activities will cease until the Designated Biologist or Biological Monitor moves the desert tortoises out of harm's way outside of the fence, no greater than 1,640 feet (500 meters) away from their original location. At this time, the fencing will be inspected for holes. If desert tortoises are found in a construction area where fencing was deemed unnecessary, the tortoise will be moved per the Desert Tortoise Plan. Any desert tortoises found during clearance surveys will be translocated per the Desert Tortoise Plan. Monitoring of active construction outside fenced areas will be continuous. A monitor must be onsite to address any tortoises found inside fenced areas that are not fully graded. The Designated Biologist or Biological Monitor will follow the handling guidelines at all times if handling desert tortoises is required. The Designated Biologist or Biological Monitor will have the authority to stop all activities until appropriate corrective measures have been completed. <p>SCE will restrict work to daylight hours, except during an emergency, to avoid nighttime activities when desert tortoises may be present on the access road. Traffic speed will be maintained at 15 miles per hour (24 kilometers per hour) or less in the work area.</p>		<p>X</p> <p>X</p> <p>X</p> <p>X</p> <p>X</p> <p>X</p> <p>X</p>

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>The temporary ground disturbance associated with the trenching will occur within previously disturbed areas, and will not require rehabilitation or restoration. However, for any construction laydown areas required for the SCE downstream upgrade that will result in soil excavation or surface scouring in non-disturbed areas supporting native vegetation, the following shall be implemented to restore native vegetation:</p> <ol style="list-style-type: none"> 1. <u>Stockpile Topsoil.</u> To increase chances for revegetation success in temporarily disturbed areas of native vegetation, topsoil shall be stockpiled from the Project work area where temporary disturbances include vegetation removal and soil excavation (e.g., trenching for the installation of fiber-optic cable conduit) for use in revegetation. Native topsoil from the least disturbed locations of temporary excavations, and only areas that are free of noxious weeds, shall be used as a source of topsoil. Topsoil shall be stockpiled from the areas of native vegetation identified for disturbance at a particular site for use in revegetation of temporarily disturbed soils. Two (2) to three (3) inches of soil shall be scraped and stockpiled for use in revegetation of temporarily disturbed areas. Elements related to the collection and stockpiling of topsoil shall be conducted as described on pages 39-40 of <i>Rehabilitation of Disturbed Lands in California</i> (Newton and Claassen 2003). 2. <u>Restore Temporarily Disturbed Areas.</u> Only seed from locally occurring species shall be used for revegetation. Seeds shall contain a mix of short-lived early pioneer species such as native annuals and perennials and subshrubs (for example, cheesebush, matchweed, peppergrass, rabbitbrush, creosote bush, burro-weed, needlegrass, rice grass, and goldenhead). Seeding shall be conducted as described in Chapter 5 of <i>Rehabilitation of Disturbed Lands in California</i> (Newton and Claassen 2003). A list of plant species suitable for Mojave Desert region revegetation projects, including recommended seed treatments, are included in Appendix A-8 of the same report. The list of native plants observed during surveys of the Project area can also be used as a guide to site-specific plant selection for revegetation. 3. <u>Control Noxious Weeds.</u> Maintain percent cover of noxious weeds (species considered “moderate” or “high” threat to California wildlands as defined by the California Invasive Plant Council [CAL-IPC 2006] and noxious weeds rated “A” or “B” by the California Department of Food and Agriculture [CDFA] and any Federal-rated pest plants [CDFA 2009]) below current levels in rehabilitated areas. 		<p>X</p> <p>X</p> <p>X</p>

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>4. <u>Performance Standard.</u> Since all temporary impacts are to be mitigated as permanent, in the form of habitat replacement at set ratios, no performance standard shall be put in place on the success of the restoration of these areas. Implementation of the measures outlined in BIO-12, and the documentation of the restoration activities by the Designated Biologist shall be sufficient for adherence to this measure.</p> <p>5. <u>Reporting.</u> The Designated Biologist shall record the following information for any restoration activity: a) the locations (narrative and maps) and dates of habitat restoration; b) extent of surface area disturbed and restored; c) type and source of native seed mix used; d) general description of the pre-disturbance site (plant species diversity, presence of invasive plant species, etc.); and e) a general description of the areas immediately surrounding the restoration site (plant species diversity, presence of invasive plant species, habitat quality, level of disturbance, etc.).</p>		<p>X</p> <p>X</p>
26. Prior to the commencement of ground disturbance activities, clearance surveys will be conducted for MGS burrows along the alignment concurrently with the DT surveys. All burrows within work areas will be excavated. If MGS are detected, they will be allowed to escape the exclusion area prior to completion of fencing of the area. The Designated Biologist will maintain records of squirrels that have been excluded from the work areas, and will prepare a report for submittal to the CDFG 30 day after clearance surveys.		X
27. Prior to construction, a California Burrowing Owl Consortium (CBOC), with CDFG approval, protocol-level burrowing owl survey will be conducted along the fiber-optic alignments to detect the presence of burrowing owls. Active owl burrows will be mapped and avoided to the maximum extent possible with a minimum 1,250-foot buffer around the active burrow. If the burrow cannot be avoided, the owl will be passively relocated outside of nesting season February 1 through August 31. Relocation of owls will follow the guidelines in the avoidance and minimization measures listed in section 3.8.4.1.2 of this document.		X
28. If construction activities occur during avian nesting season (February 1 through August 1), two surveys separated by a 10-day interval will be conducted to detect potential active avian nests by a qualified biologist familiar with locating nests. If active nests are found, CDFG will be consulted to establish a no disturbance buffer, until the nest is no longer active as determined by a qualified biologist. This will be accomplished by monitoring the nest with a non-invasive method such as observing the nest with a spotting scope.	X ²	X

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<ul style="list-style-type: none"> • <u>Avoid Wildlife Pitfalls.</u> At the end of each work day, the Designated Biologist shall ensure that all potential wildlife pitfalls (trenches, bores, and other excavations) outside the permanently fenced area have been backfilled. If backfilling is not feasible, all trenches, bores, and other excavations shall be sloped at a 3:1 ratio at the ends to provide wildlife escape ramps, or covered completely to prevent wildlife access, or fully enclosed with tortoise-exclusion fencing. All trenches, bores, and other excavations outside the areas permanently fenced with desert tortoise exclusion fencing shall be inspected at the beginning of each workday, periodically throughout, and at the end of each workday by the Designated Biologist or a Biological Monitor. Should a tortoise or other wildlife become trapped, the Designated Biologist or Biological Monitor shall remove and relocate the individual to a safe location. Any wildlife encountered during the course of construction shall be allowed to leave the construction area unharmed. • <u>Avoid Entrapment of Wildlife.</u> Any construction pipe, culvert, or similar structure with a diameter greater than three inches, stored less than eight inches above ground for one or more days/nights, shall be inspected for wildlife before the material is moved, buried, or capped. As an alternative, all such structures may be capped before being stored, or placed on pipe racks. • <u>Report Wildlife Injury and Mortality.</u> All inadvertent deaths of sensitive species, including road kill, shall be reported to the appropriate project representative. Species name, physical characteristics of the animal (sex, age class, length, weight), and other pertinent information shall be noted and reported in the Monthly Compliance Reports. Injured animals shall be reported to CDFG or USFWS and the CPM and the project owner shall follow instructions that are provided by CDFG or USFWS. If CDFG or USFWS cannot be immediately reached, consideration should be given to taking the animal to a veterinary hospital. If any golden eagles are recovered dead, they shall be sent to the National Eagle Repository after cause of death has been investigated. • <u>Minimize Standing Water.</u> Water applied to dirt roads and construction areas (trenches or spoil piles) for dust abatement shall use the minimal amount needed to meet safety and air quality standards in an effort to prevent the formation of puddles, which could attract desert tortoises, common ravens, and other wildlife to construction sites. A Biological Monitor shall patrol these areas to ensure water does not puddle and attract desert tortoise, common ravens, and other wildlife to the site and shall take appropriate action to reduce water application where necessary. 	<p>X²</p> <p>X²</p> <p>X²</p> <p>X²</p>	<p>X</p> <p></p> <p>X</p> <p></p>

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<ul style="list-style-type: none"> • <u>Implement Erosion Control Measures.</u> Standard erosion control measures shall be implemented for all phases of construction and operation. All disturbed soils and roads within the project site shall be stabilized to reduce erosion potential, both during and following construction. Areas of disturbed soils (access and staging areas) with slopes toward an ephemeral drainage or Harper Dry Lake shall be stabilized to reduce erosion potential. • <u>Monitor Ground Disturbing Activities Prior to Site Mobilization.</u> If ground disturbing activities are required prior to site mobilization, such as for geotechnical borings or hazardous waste evaluations, a Designated Biologist or Biological Monitor shall be present to monitor any actions that could disturb soil, vegetation, or wildlife. Actions not included in the project description are prohibited. 	<p>X²</p> <p>X²</p>	
<p>31. Desert Tortoise avoidance and minimization measures: A Desert Tortoise Clearance and Relocation/Translocation Plan (Desert Tortoise Plan) will be approved by CEC, CDFG, USFWS, and BLM. Perimeter Fencing</p> <ul style="list-style-type: none"> • Prior to ground disturbance and tortoise clearance of the plant site, the entire site shall be fenced with DT exclusion fence. To avoid impacts to DT during fence construction, the proposed fence alignment shall be flagged and the alignment surveyed within 24 hours prior to fence construction. Surveys shall be conducted by the Designated Biologist using techniques approved by USFWS and CDFG. Biological monitors may assist the Designated Biologist under his or her supervision. These surveys shall provide 100% coverage of all areas to be disturbed during fence construction and an additional transect along both sides of the proposed fence line. This fence line transect shall cover an area approximately 90 feet wide centered on the fence alignment. Transects shall be no greater than 15 feet apart. • Burrows and tortoises will be avoided if at all possible (especially for temporary fencing). But, if a burrow must be destroyed for fencing to occur, then it will be visually and tactilely examined for occupancy by tortoises and other wildlife. If occupancy is negative or cannot be established, the burrow will be carefully excavated with hand tools, using standardized techniques approved by USFWS (2009a) and the Desert Tortoise Council (1994). No burrows that can be avoided will be collapsed during perimeter fence construction. 	<p>X²</p> <p>X²</p>	<p>X</p>

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<ul style="list-style-type: none"> The fence installation shall be supervised by the Designated Biologist and monitored by the biological monitors to ensure the safety of any tortoise present. The level of monitoring will depend on the specific fencing activity, but at least one biological monitor will accompany each separate construction team, such that no driving, trenching, fence pulling, or any surface disturbing activities will occur without the immediate presence of a biological monitor. Maps of burrows from the pre-construction survey will be provided to all biological monitors to assist in protecting tortoises. Such maps will also be potentially useful for relocating tortoises. Tortoises will be avoided if at all possible. Any tortoise that must be moved will be relocated as detailed in the Desert Tortoise Relocation/Translocation section, below. The permanent tortoise exclusionary fencing shall consist of galvanized hard wire cloth, 1-by-2-inch mesh sunk 12 inches into the ground, and at least 24 inches above ground, with t-stakes or other solid, permanent poles placed at 8 to 10-foot intervals (refer to parameters for USFWS-approved tortoise exclusion fencing at www.fws.gov/ventura/species_info/protocols_guidelines). Temporary fencing may be used to exclude tortoises until the permanent fence is installed. Temporary fencing will follow guidelines and materials for permanent fencing except in very temporary situations, when silt fencing may be used. In both cases, supporting stakes will be sufficiently spaced (e.g., ≤8 feet for wire mesh; ≤5 feet for silt fencing) to maintain fence integrity. Fencing may be buried if it will not create a biologically significant disturbance, or bent outward at or below the ground level, with the bent portion tacked and/or held down by rocks and soil. This method eliminates the need for trenching, which, for short-term temporary impacts, may be more beneficial to the recovery of the landscape, and thus the species. Security gates shall be designed with minimal ground clearance to deter ingress by tortoises. The gates shall remain closed except during vehicle passage and may be electronically activated to open and close immediately after vehicle(s) have entered or exited to prevent extended periods with open gates, which might lead to a tortoise entering. The onsite storm water drainage channels, including the headwalls, outlet, and road crossings, shall be permanently fenced to ensure exclusion of DT during plant operation. 	<p>X²</p> <p>X²</p> <p>X²</p> <p>X²</p> <p>X²</p> <p>X²</p>	<p></p> <p>X</p> <p></p> <p>X</p> <p></p> <p></p>

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<ul style="list-style-type: none"> Following installation of the DT exclusion fencing for the permanent site, storm water drainage fencing, and temporary fencing (if required), the fencing shall be regularly inspected. Permanent fencing shall be inspected monthly <u>and</u> during/immediately following all rainfall events where soil and water flow through washes or overland and could damage the fence or erode the soil underneath. Any damage to the fencing will be repaired immediately. If it cannot be repaired immediately, any gaps that are open to tortoise habitat will be continuously monitored until the gap can be repaired to ensure that a tortoise has not entered the site through the gap. Temporary fencing will be inspected at least weekly if construction is occurring; if there is a delay in construction, temporary fence inspections will follow the same schedule as for permanent fencing. All gaps in temporary fencing shall be repaired immediately upon discovery and, if the fence may have permitted tortoise entry while damaged, the Designated Biologist shall inspect the area enclosed by the fence for tortoises. Following the onset of the tortoise activity season, or if exclusion fencing is installed when tortoises are known to be active (for example, if unusually warm weather occurs in winter before fencing is completed), then all installed exclusion fence (partial or complete) will be checked ensure that no tortoise is trapped inside the fenced area. If fencing is installed during a warm period in winter, then all fencing will be checked twice daily, during the warmer periods of the day. Any tortoise will be relocated as described for fence construction. If fencing occurs during spring or summer (approximately 1 April through September), then all fencing will be checked 2-3 times daily during tortoise activity temperatures (between approximately 15 and 42°C ground surface temperature), for two weeks, to ensure that a tortoise is not inadvertently trapped inside. Tortoises will be passively or actively relocated as identified for fence construction. If, for any reason, tortoise clearance surveys were delayed for several months after fencing, at least one clearance pass will be completed as soon as tortoises became active following the completion of fencing (e.g., April if fencing were completed in winter, immediately after fencing if fencing were completed from April through October). These measures will ensure that no tortoise are trapped into the non-habitat inside the site following fencing. 	<p>X²</p> <p>X²</p>	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>Data Collected:</p> <ul style="list-style-type: none"> Each captured tortoise will be processed at capture, prior to translocation. The gender, carapace length, width along the widest area between and inclusive of Marginals 5 and 6, height at the third vertebral, distinguishing morphology, clinical signs of disease, capture site location and description, and the amount of void, if any, will be recorded. In addition, the tortoise will be photographed and drawn. All release site locations will also be recorded at relocation/translocation, along with their descriptions. All tortoise handling will be accomplished by techniques outlined in the USFWS <i>Field Manual</i> (2009a: Sections 7.6-7.8) and including the most recent disease prevention techniques (e.g., Wendland et al. 2009). Each tortoise will be assigned an individual number, with a number series to be provided by USFWS. Marking techniques will be approved by USFWS, but temporary marks using very small epoxy numbers (e.g., clear epoxy over a small, indelible number on a correction fluid [Wite-Out®] background) on an ostal or interior marginal area that receives little to no abrasion are suggested, with a Project specific identifier. Such numbers will last for several years, which will facilitate identifying specific tortoises if they are subsequently observed during Project maintenance or other activities, including repeated observations during construction (e.g., on the perimeter fence). 	X	X
<p>Health Considerations:</p> <ul style="list-style-type: none"> Visual health assessments will be conducted on all tortoises relocated (i.e., moved <500 m) or translocated (moved > 500 m), by an experienced biologist approved by the USFWS. USFWS (2010b) guidance and later e-mails from USFWS (T. Englehard, pers. comm. to A. Karl) have identified that no tortoise will be relocated within 1.5 km (0.9 mi) of a diseased resident tortoise because relocated tortoises may move 1.5 km after translocation. No tortoise may be translocated within 6 km of a diseased resident tortoise. Mojave Solar will comply with the requirement to complete a 100%-coverage survey for resident diseased tortoises within 1.5 km of any tortoise relocated from the MSP site, including during perimeter fence construction, or within 6 km of any tortoise translocated. All resident tortoises within 1.5 km of a relocation site and 6.5 km of a translocation site will be processed (weighed, measured, described, photographed), marked with an epoxy number for future identification and their health assessed. If any tortoises from the Project Area are moved more than 500 m, then all resident tortoises within 6.5 km of the Translocation Site will be fitted with a transmitter for follow-up blood sampling at the earliest date approved by USFWS, currently 15 May. 	<p>X</p> <p>X</p>	X

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<ul style="list-style-type: none"> No tortoise with clinical signs of mycoplasmosis will be relocated or translocated. Schumacher <i>et al.</i> (1997) observed that clinical signs had a high statistical correlation with positive serology (i.e., exposure to <i>Mycoplasma agassizii</i>). A mucous nasal discharge is the clinical sign that was the most reliable predictor (93% of tortoises with a mucous nasal discharge were seropositive), although it could be caused by pathogens other than <i>M. agassizii</i>. Furthermore, a purulent nasal discharge was the only clinical sign that was relatively objective; other clinical signs were far more subjective, were potentially present for other reasons, and reduced the statistical predictability of positive serology. For the MSP, a purulent nasal discharge will be the threshold to identify a diseased tortoise, unless USFWS determines that other clinical signs should be used for diagnosing a diseased tortoise. Relocated or translocated desert tortoises determined to be infectious or unhealthy will be sent to the Desert Tortoise Conservation Center (DTCC) or other USFWS-approved facility where they will undergo further assessment, treatment, and/or necropsy. Mojave Solar will provide a flat fee of \$9,000 for each desert tortoise sent to the DTCC commensurate with the cost to provide housing, care, treatment, and other services for five years (\$3,000 for Year 1, \$1,500 for Years 2 to 5). 	<p>X</p> <p>X</p>	
<p>Transmitters:</p> <ul style="list-style-type: none"> If needed for monitoring relocated or translocated tortoises, transmitters will be affixed to the tortoises. Holohil R1-2B transmitters (24 mm wide by 11 mm thick; 14.9 g; www.holohil.com) will be epoxied onto a carapace scute using five-minute gel epoxy. For males, transmitters will be affixed to the fifth vertebral; for females, transmitters will be affixed to the anterior carapace in the most appropriate location for the animal's shell shape that will preclude interference with righting. The transmitter antenna will be fed through a plastic sheath with a diameter slightly greater than the antenna. This sheath will be epoxied low on the carapace, just above the marginal scutes, and split at the scute seams (growth areas) to preclude distortion of the tortoise's shell during growth. This technique permits the antenna to remain protected from abrasion, but move freely, thereby not affecting tortoise growth. Juvenile tortoises will be similarly equipped but with smaller transmitters, appropriate for their mass and size (<10% of the tortoise's mass). Because the antenna sheath is tightly curved on a very small tortoise, potentially constricting antenna movement with subsequent growth distortion, much more of the antenna will remain free on small tortoises. These are proven techniques to minimize disturbance to the tortoise, refined and/or developed and used by Dr. Karl for more than 20 years [G2] and on over 300 tortoises and subsequently used at Fort Irwin for several hundred tortoises. 	X	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>Transportation and Handling:</p> <ul style="list-style-type: none"> Tortoises that only need to be moved a few hundred feet will be hand-carried to the release site. Each tortoise that is hand-carried will be kept upright and the handler, wearing disposable examination gloves (one pair per tortoise), will move the tortoise as quickly and smoothly as possible. Tortoises that must be moved farther from the capture site or temporarily held in a climate-controlled situation will be sequestered in individual, sterilized tubs with taped, sterilized lids or single-use cardboard boxes with lids. During transport by vehicle, the tortoise tub will be kept shaded and the tub will be placed on a well-padded surface that is not over a heated portion of the vehicle floor. These measures are consistent with USFWS guidance (2009a: Section 7.10). Should a tortoise void or defecate between capture and release, it will be thoroughly rinsed to remove potential attracting odors to predators. Then, it will be placed in a shallow bath of room temperature water to re-hydrate it, per USFWS guidance (2009a: Section 7.9). The tortoise's mass following this procedure will be recorded. 	X	X
<p>Handling Temperatures:</p> <ul style="list-style-type: none"> Handling will adhere to USFWS (2010b) handling guidelines, which state that tortoises can only be handled when air temperatures, measured at 2 in (5 cm) above the ground (shaded bulb), are not expected to exceed 95°F (35°C) during the handling session. If the air temperature exceeds 95°F during handling or processing, desert tortoises will be kept shaded in an environment where the ambient air temperatures do not exceed 91°F (32.7 °C) and air temperature does not exceed 95°F. The desert tortoise will not be released until air temperature at the release site declines to 95°F. Tortoises must go underground to escape surface heat at ground surface temperatures of 109°F (43°C) (Karl 1992) to 113°F (45°C) (Zimmerman et al., 1994). Because surface temperatures can easily exceed 109°F when air temperatures at two inches are still below 95°F, the more conservative temperature will govern all tortoise handling described in the Desert Tortoise Plan, to minimize harm to tortoises. In other words, the USFWS guidelines will be followed except in the situation where they exceed 109°F ground temperature. 	X	X

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>least 1 ft. and with avian netting over the top. The size of the enclosure will depend on the number of tortoises found, but will be a minimum of 20 feet in diameter, extending to 50 feet or more, as necessary, to accommodate more juvenile tortoises. (Morafka <i>et al.</i> 1997 successfully penned juvenile tortoises at the rate of 62-123 tortoises per acre (152-305 animals per hectare). After tortoises have become familiar with the site's odors and landmarks for at least two weeks, escape holes will be opened in the lower edge for tortoises to escape passively (e.g., Morafka <i>et al.</i> 1997). Modifications to the design and process may occur in response to predator interest in the enclosure or juvenile tortoise behavior in the enclosure, incorporating new and relevant head-starting techniques used at Twentynine Palms Marine Corps Air Ground Combat Center.</p> <ul style="list-style-type: none"> • All translocated tortoises will be rehydrated within 12 hours prior to release, via USFWS (2009a) methods • Two translocation sites were chosen, one on each side of Harper Lake Road, to minimize post-translocation movements of tortoises across that road. All tortoises west of Harper Lake Road will be moved to the Translocation Site in Section 25, on land owned by Mojave Solar. All tortoises east of Harper Lake Road will be moved to the Translocation Site in Section 4, in the BLM DWMA and ACEC. Translocation to a DWMA or ACEC is preferred by CDFG, and BLM has agreed to move the few potential tortoises from MSP to BLM land (L. Encinas, pers. comm.). • The Translocation Site pens will be sufficiently large to support each tortoise pending disease testing results. Each will be a minimum of 165 x 165 feet (50 by 50 m), thereby providing adequate forage and sufficient habitat for a tortoise to find and/or construct adequate cover sites. Pens will be constructed using double-walled, 1 by 2 inch tortoise-proof fencing, installed as identified for perimeter fencing, above. They will be separated by a minimum of 100 meters so that tortoises will not be crowded once the fences are removed (if tortoises are seronegative) and tortoises fully released. Prior to Project Area clearance, pen design and an animal husbandry plan for penned tortoises will be approved by experienced personnel from an accredited American Zoological Association institution and approved by USFWS, BLM, and CDFG. • If a tortoise is found inside the Plant Site during initial grading or operations, and temperatures are too high for safe relocation/translocation, the tortoise will be captured, secured in an individual, sterilized box and temporarily placed in a quiet, climate-controlled environment (e.g., the onsite Project office). Depending on temperatures and other factors, it is possible that the tortoise could be affixed with a transmitter and relocated outside the Project Area or translocated into the Translocation Site the same day, when temperatures subside (or the following morning for juvenile tortoises), and monitored to ensure its safety. If the tortoise will likely be harmed or 	<p>X</p> <p>X</p> <p>X</p> <p>X</p>	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
die, it will be held in captivity at a location approved by USFWS and CDFG, away from other tortoises, to be released into the Translocation Site during the next available window. Other options will also be investigated. The goal of the translocation is to keep the tortoise in the population, in order to promote recovery.		
<p>Post- Release Monitoring</p> <ul style="list-style-type: none"> During perimeter fence construction, tortoises will be moved a short distance from construction activities along the perimeter fence and therefore will be assumed to be within their home range and familiar with burrow locations. However, they will receive immediate post-release monitoring nonetheless. This may be especially critical for juvenile tortoises, which are highly subject to depredation. The Desert Tortoise Plan discusses the details of immediate post-release monitoring for all tortoises relocated during fence USFWS (2010b) requires a five-year monitoring program for translocatees, including tortoises relocated during perimeter fence construction. Based on multiple Project surveys, it is assumed that fewer than five tortoises will be part of the study. USFWS (2010b) has determined that no resident and control study cohorts are required for fewer than five translocatees (including juveniles). If five or more desert tortoises are translocated from the project site, Mojave Solar will work with the BLM, CDFG, and Service to identify appropriate locations for control and resident desert tortoise monitoring. Mojave Solar will monitor all translocated tortoises for five years from the time of relocation/translocation. Tortoises will be located by telemetry according to the schedule identified in USFWS (2010b) guidelines. Each time the tortoise is located, the behavior, location (UTM), and burrow description (if any) will be recorded. Survival and general health will be monitored through body condition indices (mass to volume ratios), clinical signs of disease, serology, and inspection for injuries. Any time a tortoise is handled, it will be examined for clinical signs of disease. Formal health assessments will be conducted during April (following brumation), July (following oviposition), and October (prior to brumation). At these times, body condition (mass to volume ratio) also will be measured (mass, carapace length, width at Marginal 5 or 6, height) Blood samples will be taken and analyzed annually, in July or October. An approved biologist will conduct the assessments and tissue sampling. While blood samples are not required of tortoises moved <500 meters during relocation, blood will be sampled shortly after relocation³ in order to provide baseline data. 	<p>X</p> <p>X</p>	X

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<ul style="list-style-type: none"> Sampling frequency and techniques for disease analysis will be updated as necessary during the study, based on the newest disease information from this and other studies. This may include tests for other pathogens (e.g. <i>Mycoplasma</i> spp., herpesvirus, iridovirus) as their importance and evaluation techniques become validated for desert tortoises. Data will be recorded on a data sheet similar to that in Appendix 1, with an additional health assessment data sheet to be provided by USFWS. Any health problems observed (e.g., rapid declines in body condition, perceived outbreaks of disease, mortality events) will be reported to the USFWS, CDFG and BLM such that appropriate actions can be taken in a timely manner. Should a translocated tortoise die, the cause of death will be determined to the extent possible. This information, along with the location and any other analysis that could assist the USFWS, CDFG, BLM and DOE will be provided to these agencies within 48 hours, verbally, or five business days, if by e-mail. All fresh carcasses will be salvaged and frozen. They will be submitted for necropsy upon direction from USFWS, CDFG, and BLM; DOE will also be notified. Transmitters will be changed as necessary. <p>Mojave Solar has also proposed some alternatives for consideration if fewer than five tortoises are relocated/translocated.</p>		
<p>Nest Relocation</p> <ul style="list-style-type: none"> Any nests found between November 1 and April 15 are unlikely to be viable and will not be moved; hatching is typically completed by October. In the event that nests are found between April 15 and October 31, the nests will be moved. Eggs will be inspected to determine if they are viable and, if so, will be moved to an identical microsite (e.g., cover, plant species, soil type, substrate, aspect) on the approved Translocation Site using standard techniques (e.g. Desert Tortoise Council 1994, USFWS 2009a). Translocated nests will be fenced with open-mesh fencing (e.g. 2-inch wide mesh) that will permit hatchlings to escape but prevent depredation by canids that might be attracted to the new nests by human scent predator entry. Open-mesh fencing or avian netting also will be installed on the roof of the nest enclosure to prevent predator entry. Nests will be monitored from a 30-foot distance once a month until late November, at which time they will be excavated for examination. If possible, hatchlings will be weighed, measured, photographed, described and marked. <p>Measures specific to the SPS Upgrades: A qualified biologist will conduct preconstruction clearance surveys for desert tortoises within the limits of the proposed work activity associated with the fiber-optic upgrades. The résumés of the biologists</p>	X	X

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>MSLLC and SCE wish to perform these surveys will be provided to USFWS for concurrence prior to conducting the surveys, as part of the process identified in BIO-1 through BIO-4, for the selection of the Designated Biologist and Biological Monitor, if feasible. The limits of proposed work activity will be fenced with temporary desert tortoise fencing, immediately prior to the clearance survey. Clearance surveys will follow the current USFWS desert tortoise survey protocol.</p> <p>In addition to the WEAP training required under BIO-5, all personnel involved in the construction, operation, and maintenance of the fiber-optic upgrades will adhere to the following measures:</p> <ul style="list-style-type: none"> • During construction, all vehicles will remain on existing access and spur roads in potentially occupied desert tortoise habitat. Vehicle speeds in these areas will not exceed 15 miles per hour. Personnel will check under parked vehicles prior to moving the vehicle. If a desert tortoise is found under a vehicle and does not leave on its own, a Designated Biologist or Biological Monitor may be called to relocate the animal out of harm's way, no more than 1,640 feet (500 meters) from its original location. • During operations and maintenance activities, all vehicles will remain on existing access and spur roads in potentially occupied desert tortoise habitat. Vehicle speeds in these areas will not exceed 15 miles per hour. Personnel will check under parked vehicles prior to moving the vehicle. If a desert tortoise is found under a vehicle, a Designated Biologist or Biological Monitor will move the desert tortoise as described in the attached Desert Tortoise Plan. 		
<ul style="list-style-type: none"> • In construction areas in potentially occupied desert tortoise areas, work and staging areas, including the locations of the fiber-optic upgrades under construction, may be fenced with USFWS-approved temporary desert tortoise fencing in a manner that prevents equipment and vehicles from straying from the designated work area into adjacent habitat. The Designated Biologist or Biological Monitor will assist in determining the boundaries of the area to be fenced in consultation with USFWS and CDFG, and with BLM when construction areas are within lands administered by the BLM. All workers will be advised that equipment and vehicles must remain within the fenced work areas. Installation of the fencing and any necessary surveys will be directed and/or conducted by the Designated Biologist or Biological Monitor in concurrence with these agencies. The fencing will remain in place for the duration of construction activities at a particular location and will be removed when construction activities are complete. The Designated Biologist or Biological Monitor will inspect the fencing on a biweekly basis to ensure that no holes develop that could allow desert tortoises to enter the work areas. If holes are found, they will be repaired immediately. 		

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<ul style="list-style-type: none"> • If desert tortoises are found within an area that has been fenced to exclude them, activities will cease until the Designated Biologist or Biological Monitor moves the desert tortoises out of harm's way outside of the fence, no greater than 1,640 feet (500 meters) away from their original location. At this time, the fencing will be inspected for holes. • If desert tortoises are found in a construction area where fencing was deemed unnecessary, the tortoise will be moved per the Desert Tortoise Plan. • Any desert tortoises found during clearance surveys will be translocated per the Desert Tortoise Plan. Monitoring of active construction outside fenced areas will be continuous. A monitor must be onsite to address any tortoises found inside fenced areas that are not fully graded. • The Designated Biologist or Biological Monitor will follow the handling guidelines at all times if handling desert tortoises is required. • The Designated Biologist or Biological Monitor will have the authority to stop all activities until appropriate corrective measures have been completed. <p>SCE will restrict work to daylight hours, except during an emergency, to avoid nighttime activities when desert tortoises may be present on the access road. Traffic speed will be maintained at 15 miles per hour (24 kilometers per hour) or less in the work area.</p> <p>The temporary ground disturbance associated with the trenching will occur within previously disturbed areas, and will not require rehabilitation or restoration. However, for any construction laydown areas required for the SCE downstream upgrade that will result in soil excavation or surface scouring in non-disturbed areas supporting native vegetation, the following shall be implemented to restore native vegetation:</p> <ol style="list-style-type: none"> 1. <u>Stockpile Topsoil.</u> To increase chances for revegetation success in temporarily disturbed areas of native vegetation, topsoil shall be stockpiled from the Project work area where temporary disturbances include vegetation removal and soil excavation (e.g., trenching for the installation of fiber-optic cable conduit) for use in revegetation. Native topsoil from the least disturbed locations of temporary excavations, and only areas that are free of noxious weeds, shall be used as a source of topsoil. Topsoil shall be stockpiled from the areas of native vegetation identified for disturbance at a particular site for use in revegetation of temporarily disturbed soils. Two (2) to three (3) 		

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>inches of soil shall be scraped and stockpiled for use in revegetation of temporarily disturbed areas. Elements related to the collection and stockpiling of topsoil shall be conducted as described on pages 39-40 of <i>Rehabilitation of Disturbed Lands in California</i> (Newton and Claassen 2003).</p> <p>2. <u>Restore Temporarily Disturbed Areas.</u> Only seed from locally occurring species shall be used for revegetation. Seeds shall contain a mix of short-lived early pioneer species such as native annuals and perennials and subshrubs (for example, cheesebush, matchweed, peppergrass, rabbitbrush, creosote bush, burro-weed, needlegrass, rice grass, and goldenhead). Seeding shall be conducted as described in Chapter 5 of <i>Rehabilitation of Disturbed Lands in California</i> (Newton and Claassen 2003). A list of plant species suitable for Mojave Desert region revegetation projects, including recommended seed treatments, are included in Appendix A-8 of the same report. The list of native plants observed during surveys of the Project area can also be used as a guide to site-specific plant selection for revegetation.</p>		
<p>3. <u>Control Noxious Weeds.</u> Maintain percent cover of noxious weeds (species considered “moderate” or “high” threat to California wildlands as defined by the California Invasive Plant Council [CAL-IPC 2006] and noxious weeds rated “A” or “B” by the California Department of Food and Agriculture [CDFA] and any Federal-rated pest plants [CDFA 2009]) below current levels in rehabilitated areas.</p> <p>4. <u>Performance Standard.</u> Since all temporary impacts are to be mitigated as permanent, in the form of habitat replacement at set ratios, no performance standard shall be put in place on the success of the restoration of these areas. Implementation of the measures outlined in BIO-12, and the documentation of the restoration activities by the Designated Biologist shall be sufficient for adherence to this measure.</p> <p>5. <u>Reporting.</u> The Designated Biologist shall record the following information for any restoration activity: a) the locations (narrative and maps) and dates of habitat restoration; b) extent of surface area disturbed and restored; c) type and source of native seed mix used; d) general description of the pre-disturbance site (plant species diversity, presence of invasive plant species, etc.); and e) a general description of the areas immediately surrounding the restoration site (plant species diversity, presence</p>		

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
of invasive plant species, habitat quality, level of disturbance, etc.).		
32. The project owner shall provide a copy of the Biological Opinion per Section 7 of the federal Endangered Species Act written by the U. S. Fish and Wildlife Service in consultation with U.S. Department of Energy. The terms and conditions contained in the Biological Opinion shall be incorporated into the project's BRMIMP and implemented by the project owner.		
33. To fully mitigate for habitat loss and incidental take of desert tortoise and Mohave ground squirrel as well as burrowing owl, the project owner shall acquire, prior to ground-disturbing activities, in fee or in easement, no less than 118.2 acres of land suitable for these species and shall provide funding for the enhancement and long-term management of these compensation lands. The responsibilities for management of the compensation lands may be delegated by written agreement to CDFG or to a third party, such as a non-governmental organization dedicated to habitat conservation, subject to approval by the CPM, in consultation with CDFG and USFWS prior to land acquisition or management activities. If habitat disturbance exceeds that described in this analysis, the project owner shall be responsible for acquisition and management of additional compensation lands and/or additional funds required to compensate for any additional habitat disturbances. Additional funds shall be based on the adjusted market value of compensation lands at the time of construction to acquire and manage habitat. Agreements to delegate land acquisition or management shall be implemented within 12 months of the Energy Commission's decision. The acquisition and management of compensation lands shall include, but is not limited to, the following elements: 1. <u>Selection Criteria for Compensation Lands.</u> The compensation lands selected for acquisition or title/easement transfer shall: A. have substantial capacity to support resident and dispersing desert tortoise, MGS, and burrowing owl; B. be a contiguous block of land (preferably) or located so that parcel(s) result in a contiguous block of protected habitat; C. not be encumbered by easements or uses that will preclude fencing of the site or preclude management of the site for the primary benefit of the species for which mitigation lands were secured; and D. include mineral/water rights or ensure that those rights may not be evoked in a manner to negate the value of the compensation lands. 2. <u>Review and Approval of Compensation Lands Prior to Acquisition or Title/Easement Transfer.</u> A minimum of three months prior to acquisition or transfer of the property title and/or easement, the project owner, or a third-party approved by the CPM, in consultation with CDFG and USFWS, shall submit a proposal to the CPM, CDFG, and USFWS describing the parcel(s) intended for	X	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>purchase or title/easement transfer. This proposal shall discuss the suitability of the proposed parcel(s) as compensation lands for desert tortoise, MGS, and burrowing owl in relation to the criteria listed above. Approval from the CPM, in consultation with USFWS and CDFG, shall be required for acquisition of all parcels comprising no less than 118.2 acres in advance of purchase or title/easement transfer.</p> <p>3. <u>Review and Approval of Compensation Lands Management Plan.</u> Within six months of the land or easement purchase or transfer, as determined by the date on the title, the project owner, or a third-party approved by the CPM, in consultation with CDFG and USFWS, shall submit a compensation lands management plan to the CPM, CDFG, and USFWS. The plan shall include, but not be limited to proposed measures to enhance habitat (e.g., removal of structures and other human attractants); maintenance procedures; general maintenance provisions (e.g., trash dumping, trespass, pesticide use avoidance, etc.).</p> <p>4. <u>Mitigation. Security for Compensation Lands and Avoidance/Minimization Measures.</u> The project owner shall provide financial assurances to the CPM, with copies of the document(s) to CDFG and USFWS, to guarantee that an adequate level of funding is available to implement all biological avoidance, minimization, and compensation measures described in the conditions of certification. These funds shall be used solely for implementation of the measures associated with the project. The project owner or an approved third party shall complete acquisition of the proposed compensation lands prior to initiating ground-disturbing project activities.</p> <p>5. <u>Conditions for Acquisition of Compensation Lands.</u> The project owner shall comply with the following conditions relating to acquisition of compensation lands or transfer of the property's title and/or easement after the CPM, in consultation with CDFG and USFWS, has approved the proposed compensation lands as described above.</p> <p>A. <u>Preliminary Report:</u> The project owner, or approved third party, shall provide a recent preliminary title report (no more than six months old), hazardous materials survey report (i.e., Phase I ESA), biological analysis, and other necessary documents for the proposed 118.2 acres. All documents conveying or conserving compensation lands and all conditions of title/easement are subject to a field review and approval by the CPM, in consultation with CDFG and USFWS, California Department of General Services and, if applicable, the Fish and Game Commission and/or Wildlife Conservation Board.</p> <p>B. <u>Title/Conveyance:</u> The project owner shall transfer fee title/deed or a conservation easement for the 118.2 acres of compensation lands to CDFG under terms approved by CDFG. Alternatively, a CPM-approved, in consultation with CDFG and USFWS, non-profit organization qualified pursuant to California Government Code section 65965 may hold fee</p>		

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>title or a conservation easement over the compensation lands. In the event an approved non-profit holds title, a conservation easement shall be recorded in favor of CDFG in a form approved by CDFG and USFWS; in the event an approved nonprofit holds a conservation easement over the compensation lands, CDFG shall be named a third party beneficiary. USFWS shall be named a third party beneficiary regardless of who holds the easement. The project owner shall also provide a property assessment and warranty.</p> <p>C. <u>Enhancement Fund</u>. The project owner shall fund the initial protection and enhancement of the 118.2 acres by providing the enhancement fund to the CDFG. Alternatively, a CPM-approved, in consultation with CDFG and USFWS, non-profit organization qualified pursuant to California Government Code section 65965 to manage the compensation lands may hold the enhancement funds. If CDFG takes fee title to the compensation lands, the enhancement fund must go to CDFG.</p> <p>D. <u>Endowment Fund</u>: Prior to ground-disturbing project activities, the project owner shall provide to CDFG a capital endowment in the amount determined through the Property Analysis Record (PAR) or PAR-like analysis that will be conducted for the 118.2 acres of compensation lands. Alternatively, a CPM-approved, in consultation with CDFG and USFWS, non-profit organization qualified pursuant to California Government Code section 65965 may hold the endowment fees. If CDFG takes fee title to the compensation lands, the endowment must go to CDFG, where it will likely be held in the special deposit fund established pursuant to Government Code section 16370. If the special deposit fund is not used to manage the endowment, the California Wildlife Foundation will manage the endowment for CDFG and with CDFG guidance.</p> <p>The project owner and the CPM shall ensure that an agreement is in place with the endowment holder/manager to ensure the following:</p> <ul style="list-style-type: none"> • <u>Interest</u>. Interest generated from the initial capital endowment shall be available for reinvestment into the principal and for the long-term operation, management, and protection of the approved compensation lands, including reasonable administrative overhead, biological monitoring, improvements to carrying capacity, law enforcement measures, and any other action designed to protect or improve the habitat values of the compensation lands. • <u>Withdrawal of Principal</u>. The endowment principal shall not be drawn upon unless such withdrawal is deemed necessary by the CDFG or the approved third-party 		

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>endowment manager to ensure the continued viability of the species on the 118.2 acres. If CDFG takes fee title to the compensation lands, monies received by CDFG pursuant to this provision will likely be deposited in a special deposit fund established pursuant to Government Code section 16370. If the special deposit fund is not used to manage the endowment, the California Wildlife Foundation will manage the endowment for CDFG and with CDFG guidance.</p> <p>E. <u>Pooling Endowment Funds</u>. CDFG, or a CPM-approved, in consultation with CDFG and USFWS, non-profit organization qualified pursuant to California Government Code section 65965 to hold endowments may pool the endowment with other endowments for the operation, management, and protection of the 118.2 acres for local populations of desert tortoise and MGS. However, for reporting purposes, the endowment fund must be tracked and reported individually.</p> <p>F. <u>Security Deposit</u>. The project owner may proceed with ground disturbing activities before fully performing its compensatory mitigation duties and obligations as set forth above only if the project owner secures its performance by providing funding to CDFG (Security Deposit), or if CDFG approves, administrative proof of funding, necessary to cover easement costs, fencing/cleanup costs, and as necessary, initial protection and enhancement of the compensation lands. If the Security is provided to allow the commencement of project disturbance prior to completion of compensation actions, the project owner, CDFG, or a third-party entity approved by the CPM, in consultation with CDFG and USFWS, may draw on the principle sum if it is determined that the project owner has failed to comply with the conditions of certification. The security will be returned to the project owner upon completion of the legal transfer of the compensation lands to CDFG or approved third-party entity, or upon completion of an implementation agreement with a third party mitigation banking entity acceptable to the CPM and CDFG, to acquire and/or manage the compensation lands.</p> <p>The Security is calculated as follows:</p> <ul style="list-style-type: none"> Costs of enhancing compensation lands are estimated at \$250 per acre. Costs of establishing an endowment for long-term management of compensation lands are estimated at \$1,300 per acre. <p>G. <u>Reimbursement Fund</u>. The project owner shall provide reimbursement to the CDFG or approved third party for reasonable expenses incurred during title, easement, and documentation review; expenses incurred from other state agency reviews; and overhead related to providing compensation lands.</p> <p>The project owner is responsible for all compensation lands acquisition/easement costs, including but</p>		

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>not limited to, title and document review costs, as well as expenses incurred from other state agency reviews and overhead related to providing compensation lands to the department or approved third party; escrow fees or costs; environmental contaminants clearance; and other site cleanup measures.</p> <p>The project owner may choose to satisfy its mitigation obligations by paying an in-lieu fee instead of acquiring compensation lands to mitigate for 118.2 acres of habitat, pursuant to California Senate Bill 34 (enacting CESA § 2069 and 2099) or other applicable in-lieu fee provision, to the extent the in-lieu fee provision is found by the Energy Commission to be in compliance with CEQA and CESA requirements.</p>		
<p>34. To protect golden eagles within a 10 mile radius of the AMSP site the project will provide funding in the amount of \$60,000 to the U.S. Fish and Wildlife Service (Service), to be spent by the Service on monitoring and other actions that the Service determines will be beneficial to golden eagles located in a 10-mile radius of the AMSP. ASI may provide funds to implement this measure into the Renewable Energy Action Team (REAT) Account established with the National Fish and Wildlife Foundation (NFWF). It is anticipated that the \$60,000 payment may be used to fund actions such as (1) a 10-year monitoring program for the Black Mountain golden eagle nesting pair, which is located within a 10-mile radius of the AMSP; (2) implementing road restrictions along Black Mountain Road by placing large boulders along the road in those sections directly alongside the golden eagle nests; and (3) implementing seasonal road closures of Black Mountain Road by erecting steel gates at the northern and southern ends of Black Mountain Wash. The funds also may be spent on other actions deemed by the Service to be beneficial to golden eagles within a 10-mile radius of the AMSP.</p> <p>Pursuant to CEC License Decision Condition of Certification LAND-1, ASI will mitigate for the loss of 128 acres of agricultural land recently under production on the plant site by providing for the purchase of 128 acres of comparable agricultural land or an easement guaranteeing 128 acres of comparable land will be available in perpetuity for productive agricultural use. This will also provide foraging habitat for golden eagles within the project area.</p> <p>Pursuant to CEC License Decision Condition of Certification BIO-20, ASI will ensure continuity of water delivery to the Harper Dry Lake ACEC by providing an alternate well able to effectively convey a minimum of 75-acre feet per year to the Harper Dry Lake marsh. To ensure continuity of water delivery to the Harper Dry Lake ACEC the project owner shall not decommission the existing well on Mojave Solar, LLC-owned property that currently serves the Harper Dry Lake marsh (wetland well) until an alternate well is able to effectively convey a minimum of 75 acre feet per year to the Harper</p>	X	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<p>Dry Lake marsh. This condition of certification does not transfer to Mojave Solar, LLC the obligation of Luz Solar Partners Ltd. to allow BLM to pump 75 acre feet of water per year to the marsh, under SEGS IX Condition of Certification BIO-11.k.</p> <p>Pursuant to CEC License Decision Condition of Certification BIO-15, ASI will provide 118.2 acres of land suitable for desert tortoise, Mojave ground squirrel and burrowing owl to compensate for the loss of habitat for these species on the plant site. The compensation land is located directly west of the MSP plant site and will provide suitable foraging habitat for golden eagles. ASI also will provide funding for the enhancement and long-term management of the compensation lands.</p>		
35. The project owner shall provide documentation to the CPM that the project is in compliance with the Bald and Golden Eagle Protection Act (Title 16, United States Code, sections 668-668d).	X	
36. The project owner shall prepare and implement a Bird Monitoring Study to monitor the death and injury of birds from collisions with facility features such as reflective mirror-like surfaces and from heat, and bright light from concentrating sunlight. The study design shall be approved by the CPM in consultation with CDFG and USFWS, and shall be incorporated into the project's BRMIMP and implemented. The Bird Monitoring Study shall include detailed specifications on data and carcass collection protocol and a rationale justifying the proposed schedule of carcass searches. The study shall also include seasonal trials to assess bias from carcass removal by scavengers as well as searcher bias.	X	
<p>37. Avoidance and minimization measures for the SWHA, a State-listed threatened species, will include:</p> <ul style="list-style-type: none"> • Pre-construction surveys of the AMSP site and a surrounding 0.5-mile buffer, per the recommended CDFG survey methodology for the species (CDFG 2000b). • If active nesting is documented within a 0.5-mile radius of the site during the surveys, Mojave Solar will coordinate with CDFG to develop additional conservation measures, such as nest monitoring during construction or delaying construction activities near the nest until all chicks have fledged. Mitigation for the loss of SWHA foraging habitat will be offset by the preservation of the compensation lands. <p>38. The project owner shall design and implement an Evaporation Pond Monitoring and Adaptive Management Plan that meets the requirements of the USFWS, CDFG, RWQCB, and the CPM. The objective of the Plan is to define the monitoring and reporting procedures as well as triggers for adaptive management strategies that shall be implemented to prevent wildlife mortality at the evaporation ponds. The plan shall include the following:</p>	<p>X</p> <p>X, from COC</p>	

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<ul style="list-style-type: none"> • A description of evaporation pond design features such as side slope specifications, freeboard and depth requirements, which will prevent use by wildlife. • A detailed description of the wildlife monitoring procedures and schedule. For the initial implementation of a new technology, daily monitoring shall be conducted both at the project evaporation ponds and the wetlands within the Harper Lake ACEC. Monitoring may be reduced to weekly and potentially bi-weekly or monthly depending on the results of initial monitoring period. • A detailed description of the water quality and water level monitoring procedures and schedule. Water quality and water level monitoring shall coincide with wildlife monitoring to provide a basis for comparative analysis. • A description of wildlife exclusion/deterrent technologies and adaptive management strategies. Technologies shall include but are not limited to netting, and shall not disturb or harass non-target wildlife adjacent to the project area. • Triggers for adaptive management (i.e., modifications to existing technology or replacement with new technology). Adaptive management shall be necessary if: 1) more than one dead bird per quarter is discovered at the evaporation ponds; or 2) one special-status animal is discovered at the evaporation ponds; or 3) noise levels attributable to the technology exceed 60 dBA at the Harper Lake ACEC wetlands. After three failed attempts at new technology, the ponds shall be netted. • Reporting requirements, to include monthly reporting for the first year if a technology other than netting is used. Reporting may be reduced to monthly or quarterly thereafter if no bird or wildlife deaths are reported during the first year. If wildlife mortality occurs at the ponds or if birds are disturbed at the marsh as described above, the CPM shall be notified within 10 days of the incident and the accompanying adaptive management action to implemented. • Evaporation pond monitoring and reporting shall continue for the life of the project. The draft Plan submitted by the Applicant (AS 2009d) shall provide the basis for the final plan, subject to review and revisions from the CPM in coordination with USFWS, CDFG, and RWQCB. <p>For the CPM and CDFG to deem the eradication successful:</p> <ul style="list-style-type: none"> • The site shall not contain more than 5% exotic plant species for the CPM and CDFG to deem the tamarisk removal successful. 		

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

Environmental Protection Measures, Design Measures and BMPs	Responsible Party	
	Mojave Solar	SCE
<ul style="list-style-type: none"> All plant species with rates of dispersal and establishment listed as “High” or “Moderate” on the California Invasive Plant Inventory shall have documented absence, or have been removed for the site for at least three years for the CPM and CDFG to deem the site successful. The site shall not contain invasive wildlife species for the CPM and CDFG to deem the site successful. <p>Monitoring and maintenance of the site shall be conducted for five years unless less monitoring can be justified. Following the first year of monitoring, if the project owner petitions to terminate the monitoring program, staff and CDFG will determine whether more years of monitoring are needed.</p>		
Cultural Resources		
1. A Monitoring Plan will be developed prior to start of construction. The document will provide protocols for construction monitoring and procedures in the event unanticipated cultural material is encountered during construction.	X	X
2. All sub-surface ground-disturbing activities shall be monitored by a qualified archaeologist.	X	X
3. A Monitoring report documenting the results of the monitoring will be prepared and submitted to BLM.	X	X
4. In the event of the discovery of unanticipated cultural material, the qualified archaeologist will coordinate with the Project construction manager and environmental compliance manager to stop all work in the vicinity of the find until the BLM archaeologist can be notified and the find can be assessed. If the discovery is determined to be not eligible, work will be allowed to continue.	X	
5. Based on the Native American contact program, Native American representatives have expressed interest in involvement in construction monitoring. The project owner will coordinate with local Native American tribes regarding their participation in construction monitoring.	X	X
6. Avoidance of cultural resources determined eligible for listing in the NRHP is preferred. If cultural resources are discovered during construction that are determined to be eligible to the NRHP, the BLM archaeologist shall be notified and BLM, the SHPO, and other interested parties will consult regarding effects. Whenever practicable, cultural resource discovered during construction that are determined eligible for listing in the NRHP will be left in place and preserved from damage. If avoidance is not feasible, adverse effects will be addressed in a Memorandum of Agreement.	X	X

¹ Applies only where ground disturbance is expected (trenching, replacement poles and interset poles).

² COC = Conditions of Certification from the CEC Final License Decision for the Abengoa Mojave Solar Plant Project.

This page intentionally left blank.