

*Southern California Edison*  
**Presidential Substation Project A.08-12-023**

**DATA REQUEST SET Presidential ED-03 (Part 2)**

**To:** CPUC

**Prepared by:** Kendra Heinicke

**Title:** Estimator

**Dated:** 05/19/2009

---

**Question 26:**

**Project Description**

In addition to the subtransmission lines, how many distribution lines and telecommunication lines are expected to be located on the poles?

**Response to Question 26:**

Upon completion of the project, SCE expects to have one, four-wire 16 kv circuit and 1 SCE telecom line on the poles. In addition, while SCE has not counted the individual lines, SCE anticipates having secondary distribution conductors and cable/telecom lines on the poles. These secondary lines currently exist within the corridor and are attached to the existing wood poles. In essence, all secondary lines and service conductors currently attached on the wood poles would be transferred to the new steel poles.